

code of federal regulations

Telecommunication

47

PARTS 0 TO 19

Revised as of October 1, 1997

CONTAINING
A CODIFICATION OF DOCUMENTS
OF GENERAL APPLICABILITY
AND FUTURE EFFECT

AS OF OCTOBER 1, 1997

With Ancillaries

Published by
the Office of the Federal Register
National Archives and Records
Administration

as a Special Edition of
the Federal Register



U.S. GOVERNMENT PRINTING OFFICE
WASHINGTON : 1997

For sale by U.S. Government Printing Office
Superintendent of Documents, Mail Stop: SSOP, Washington, DC 20402-9328

Table of Contents

Explanation	<i>Page</i> v
Title 47:	
Chapter I—Federal Communications Commission	3
Finding Aids:	
Material Approved for Incorporation by Reference	699
Table of CFR Titles and Chapters	701
Alphabetical List of Agencies Appearing in the CFR	717
List of CFR Sections Affected	727

Cite this Code: CFR

*To cite the regulations in
this volume use title,
part and section num-
ber. Thus, 47 CFR 0.1
refers to title 47, part 0,
section 1.*

Explanation

The Code of Federal Regulations is a codification of the general and permanent rules published in the Federal Register by the Executive departments and agencies of the Federal Government. The Code is divided into 50 titles which represent broad areas subject to Federal regulation. Each title is divided into chapters which usually bear the name of the issuing agency. Each chapter is further subdivided into parts covering specific regulatory areas.

Each volume of the Code is revised at least once each calendar year and issued on a quarterly basis approximately as follows:

Title 1 through Title 16.....	as of January 1
Title 17 through Title 27.....	as of April 1
Title 28 through Title 41.....	as of July 1
Title 42 through Title 50.....	as of October 1

The appropriate revision date is printed on the cover of each volume.

LEGAL STATUS

The contents of the Federal Register are required to be judicially noticed (44 U.S.C. 1507). The Code of Federal Regulations is prima facie evidence of the text of the original documents (44 U.S.C. 1510).

HOW TO USE THE CODE OF FEDERAL REGULATIONS

The Code of Federal Regulations is kept up to date by the individual issues of the Federal Register. These two publications must be used together to determine the latest version of any given rule.

To determine whether a Code volume has been amended since its revision date (in this case, October 1, 1997), consult the “List of CFR Sections Affected (LSA),” which is issued monthly, and the “Cumulative List of Parts Affected,” which appears in the Reader Aids section of the daily Federal Register. These two lists will identify the Federal Register page number of the latest amendment of any given rule.

EFFECTIVE AND EXPIRATION DATES

Each volume of the Code contains amendments published in the Federal Register since the last revision of that volume of the Code. Source citations for the regulations are referred to by volume number and page number of the Federal Register and date of publication. Publication dates and effective dates are usually not the same and care must be exercised by the user in determining the actual effective date. In instances where the effective date is beyond the cut-off date for the Code a note has been inserted to reflect the future effective date. In those instances where a regulation published in the Federal Register states a date certain for expiration, an appropriate note will be inserted following the text.

OMB CONTROL NUMBERS

The Paperwork Reduction Act of 1980 (Pub. L. 96-511) requires Federal agencies to display an OMB control number with their information collection request.

Many agencies have begun publishing numerous OMB control numbers as amendments to existing regulations in the CFR. These OMB numbers are placed as close as possible to the applicable recordkeeping or reporting requirements.

OBSOLETE PROVISIONS

Provisions that become obsolete before the revision date stated on the cover of each volume are not carried. Code users may find the text of provisions in effect on a given date in the past by using the appropriate numerical list of sections affected. For the period before January 1, 1986, consult either the List of CFR Sections Affected, 1949–1963, 1964–1972, or 1973–1985, published in seven separate volumes. For the period beginning January 1, 1986, a “List of CFR Sections Affected” is published at the end of each CFR volume.

INCORPORATION BY REFERENCE

What is incorporation by reference? Incorporation by reference was established by statute and allows Federal agencies to meet the requirement to publish regulations in the Federal Register by referring to materials already published elsewhere. For an incorporation to be valid, the Director of the Federal Register must approve it. The legal effect of incorporation by reference is that the material is treated as if it were published in full in the Federal Register (5 U.S.C. 552(a)). This material, like any other properly issued regulation, has the force of law.

What is a proper incorporation by reference? The Director of the Federal Register will approve an incorporation by reference only when the requirements of 1 CFR part 51 are met. Some of the elements on which approval is based are:

- (a) The incorporation will substantially reduce the volume of material published in the Federal Register.
- (b) The matter incorporated is in fact available to the extent necessary to afford fairness and uniformity in the administrative process.
- (c) The incorporating document is drafted and submitted for publication in accordance with 1 CFR part 51.

Properly approved incorporations by reference in this volume are listed in the Finding Aids at the end of this volume.

What if the material incorporated by reference cannot be found? If you have any problem locating or obtaining a copy of material listed in the Finding Aids of this volume as an approved incorporation by reference, please contact the agency that issued the regulation containing that incorporation. If, after contacting the agency, you find the material is not available, please notify the Director of the Federal Register, National Archives and Records Administration, Washington DC 20408, or call (202) 523–4534.

CFR INDEXES AND TABULAR GUIDES

A subject index to the Code of Federal Regulations is contained in a separate volume, revised annually as of January 1, entitled CFR INDEX AND FINDING AIDS. This volume contains the Parallel Table of Statutory Authorities and Agency Rules (Table I), and Acts Requiring Publication in the Federal Register (Table II). A list of CFR titles, chapters, and parts and an alphabetical list of agencies publishing in the CFR are also included in this volume.

An index to the text of “Title 3—The President” is carried within that volume.

The Federal Register Index is issued monthly in cumulative form. This index is based on a consolidation of the “Contents” entries in the daily Federal Register.

A List of CFR Sections Affected (LSA) is published monthly, keyed to the revision dates of the 50 CFR titles.

REPUBLICATION OF MATERIAL

There are no restrictions on the republication of material appearing in the Code of Federal Regulations.

INQUIRIES

For a legal interpretation or explanation of any regulation in this volume, contact the issuing agency. The issuing agency's name appears at the top of odd-numbered pages.

For inquiries concerning CFR reference assistance, call 202-523-5227 or write to the Director, Office of the Federal Register, National Archives and Records Administration, Washington, DC 20408.

SALES

The Government Printing Office (GPO) processes all sales and distribution of the CFR. For payment by credit card, call 202-512-1800, M-F, 8 a.m. to 4 p.m. e.s.t. or fax your order to 202-512-2233, 24 hours a day. For payment by check, write to the Superintendent of Documents, Attn: New Orders, P.O. Box 371954, Pittsburgh, PA 15250-7954. For GPO Customer Service call 202-512-1803.

RAYMOND A. MOSLEY,

Director,

Office of the Federal Register.

October 1, 1997.

THIS TITLE

Title 47—TELECOMMUNICATION is composed of five volumes. The parts in these volumes are arranged in the following order: Parts 0–19, parts 20–39, parts 40–69, parts 70–79, and part 80 to end, chapter I—Federal Communications Commission. The last volume, part 80 to end, also includes chapter II—Office of Science and Technology Policy and National Security Council, and chapter III—National Telecommunications and Information Administration, Department of Commerce. The contents of these volumes represent all current regulations codified under this title of the CFR as of October 1, 1997.

Part 73 contains a numerical designation of FM broadcast channels (§73.201) and a table of FM allotments designated for use in communities in the United States, its territories, and possessions (§73.202). Part 73 also contains a numerical designation of television channels (§73.603) and a table of allotments which contain channels designated for the listed communities in the United States, its territories, and possessions (§73.606).

The OMB control numbers for the Federal Communications Commission, appear in §0.408 of chapter I. For the convenience of the user §0.408 is reprinted in the Finding Aids section of the second through fifth volumes.

A redesignation table appears in the Finding Aids section of the volume containing part 80 to end.

For this volume, Kenneth R. Payne Chief Editor. The Code of Federal Regulations publication program is under the direction of Frances D. McDonald, assisted by Alomha S. Morris.

Would you like to know...

if any changes have been made to the *Code of Federal Regulations* or what documents have been published in the *Federal Register* every day? If so, you may wish to subscribe to the *LSA* (List of CFR Sections Affected), the *Federal Register Index*, or both.


LSA

The *LSA* (List of CFR Sections Affected) is designed to lead users of the *Code of Federal Regulations* to amendatory actions published in the *Federal Register*. The *LSA* is issued monthly in cumulative form. Entries indicate the nature of the changes—such as revised, removed, or corrected. \$27 per year.

Federal Register Index

The index, covering the contents of the daily *Federal Register*, is issued monthly in cumulative form. Entries are carried primarily under the names of the issuing agencies. Significant subjects are carried as cross-references. \$25 per year.

A finding aid is included in each publication which lists *Federal Register* page numbers with the date of publication in the *Federal Register*.



Superintendent of Documents Subscription Order Form

Order Processing Code

***5421**

☐ **YES**, send me the following indicated subscriptions for one year:

☐ **LSA (List of CFR Sections Affected)**, (LCS) for \$27 per year.

☐ **Federal Register Index** (FRSU) \$25 per year.

The total cost of my order is \$ _____

Price is subject to change. International customers please add 25%.

Company or personal name

Street address

City, State, ZIP code

Daytime phone with area code

Purchase order No. (optional)

(Includes regular shipping and handling.)

For privacy check box below:

☐ Do not make my name available to other mailers

Check method of payment:

☐ Check payable to Superintendent of Documents

☐ GPO Deposit Account ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

☐ VISA ☐ MasterCard ☐ ☐ ☐ ☐ ☐ (expiration date)

Credit card No. (must be 20 digits)

Thank you for your order!



Fax your orders (202) 512-2250
Phone your orders (202) 512-1800

Authorizing signature

1/97

Mail To: Superintendent of Documents
P.O. Box 371954
Pittsburgh PA 15250-7954

Title 47— Telecommunication

(This book contains parts 0 to 19)

	<i>Part</i>
CHAPTER I—FEDERAL COMMUNICATIONS COMMISSION	0

CHAPTER I—FEDERAL COMMUNICATIONS COMMISSION

SUBCHAPTER A—GENERAL

<i>Part</i>		<i>Page</i>
0	Commission organization	5
1	Practice and procedure	88
2	Frequency allocations and radio treaty matters; general rules and regulations	317
3	Authorization and administration of accounting authorities in maritime and maritime mobile- satellite radio services	559
5	Experimental radio services (other than broadcast)	568
11	Emergency Alert System (EAS)	584
13	Commercial radio operators	601
15	Radio frequency devices	610
17	Construction, marking, and lighting of antenna structures	676
18	Industrial, scientific, and medical equipment	684
19	Employee responsibilities and conduct	690

SUPPLEMENTAL PUBLICATIONS:

Annual Reports of the FCC to Congress.

FCC Record of Orders and Decisions.

Communications Act of 1934 (with amendments and index thereto), Recap, Version to May 1989.

Study Guide and Reference Material for Commercial Radio Operator Examinations, May 1987 edition.

SUBCHAPTER A—GENERAL

PART 0—COMMISSION ORGANIZATION

Subpart A—Organization

GENERAL

- Sec.
0.1 The Commission.
0.3 The Chairman.
0.5 General description of Commission organization and operations.

OFFICE OF MANAGING DIRECTOR

- 0.11 Functions of the Office.

OFFICE OF INSPECTOR GENERAL

- 0.13 Functions of the Office.

OFFICE OF PUBLIC AFFAIRS

- 0.15 Functions of the Office.

OFFICE OF LEGISLATIVE AFFAIRS

- 0.17 Functions of the Office.

OFFICE OF PLANS AND POLICY

- 0.21 Functions of the Office.

OFFICE OF ENGINEERING AND TECHNOLOGY

- 0.31 Functions of the Office.

OFFICE OF GENERAL COUNSEL

- 0.41 Functions of the Office.

INTERNATIONAL BUREAU

- 0.51 Functions of the Bureau

MASS MEDIA BUREAU

- 0.61 Functions of the Bureau.

OFFICE OF WORKPLACE DIVERSITY

- 0.81 Functions of the Office.

COMMON CARRIER BUREAU

- 0.91 Functions of the Bureau.

CABLE SERVICES BUREAU

- 0.101 Functions of the Bureau.

COMPLIANCE AND INFORMATION BUREAU

- 0.111 Functions of the Bureau.
0.121 Location of field installations.

WIRELESS TELECOMMUNICATIONS BUREAU

- 0.131 Functions of the Bureau.

OFFICE OF ADMINISTRATIVE LAW JUDGES

- 0.151 Functions of the Office.

DEFENSE AND EMERGENCY PREPAREDNESS FUNCTIONS

- 0.181 The Defense Commissioner.
0.182 Chief, Compliance and Information Bureau.
0.183 Emergency Communications Administration.
0.185 Responsibilities of the bureaus and staff offices.
0.186 Emergency Relocation Board.

Subpart B—Delegations of Authority

GENERAL

- 0.201 General provisions.
0.203 Authority of person, panel, or board to which functions are delegated.
0.204 The exercise of delegated authority.

COMMISSIONERS

- 0.211 Chairman.
0.212 Board of Commissioners.
0.218 Authority of, and delegated to, an individual Commissioner or Commissioners.

MANAGING DIRECTOR

- 0.231 Authority delegated.

CHIEF ENGINEER

- 0.241 Authority delegated.
0.247 Record of actions taken.

GENERAL COUNSEL

- 0.251 Authority delegated.

INTERNATIONAL BUREAU

- 0.261 Authority delegated.
0.262 Record of actions taken.

OFFICE OF PLANS AND POLICY

- 0.271 Authority delegated.

CHIEF, MASS MEDIA BUREAU

- 0.283 Authority delegated.
0.284 Actions taken under delegated authority.
0.285 Record of actions taken.

CHIEF, COMMON CARRIER BUREAU

- 0.291 Authority delegated.
0.301 [Reserved]
0.302 Record of actions taken.
0.303 Authority concerning registration of telephone terminal equipment.

COMPLIANCE AND INFORMATION BUREAU

- 0.311 Authority delegated.
0.314 Additional authority delegated.
0.317 Record of action taken.

Pt. 0

CABLE SERVICES BUREAU

- 0.321 Authority delegated.
- 0.325 Record of actions taken.

WIRELESS TELECOMMUNICATIONS BUREAU

- 0.331 Authority delegated.
- 0.332 Actions taken under delegated authority.
- 0.333–0.337 [Reserved]

ADMINISTRATIVE LAW JUDGES

- 0.341 Authority of administrative law judge.
- 0.347 Record of actions taken.

CHIEF ADMINISTRATIVE LAW JUDGE

- 0.351 Authority delegated.
- 0.357 Record of actions taken.

**NATIONAL SECURITY AND EMERGENCY
PREPAREDNESS DELEGATIONS**

- 0.381 Defense Commissioner.
- 0.383 Emergency Relocation Board, authority delegated.
- 0.387 Other national security and emergency preparedness delegations; cross reference.

OFFICE OF WORKPLACE DIVERSITY

- 0.391 Authority delegated.

Subpart C—General Information

GENERAL

- 0.401 Location of Commission offices.
- 0.403 Office hours.
- 0.405 Statutory provisions.
- 0.406 The rules and regulations.
- 0.408 OMB control numbers assigned pursuant to the Paperwork Reduction Act.
- 0.409 Communication policy on private printing of FCC forms.

PRINTED PUBLICATIONS

- 0.411 General reference materials.
- 0.413 The Commission's printed publications.
- 0.414 The Communications Act and other statutory materials.
- 0.415 The rules and regulations (looseleaf service).
- 0.416 The Federal Communications Commission Record.
- 0.417 The Annual Reports.
- 0.420 Other Commission publications.

**FORMS AND DOCUMENTS AVAILABLE UPON
REQUEST**

- 0.421 Application forms.
- 0.422 Current action documents and public notices.
- 0.423 Information bulletins.

47 CFR Ch. I (10–1–97 Edition)

**LISTS CONTAINING INFORMATION COMPILED BY
THE COMMISSION**

- 0.431 The FCC service frequency lists.
- 0.433 The radio equipment lists.
- 0.434 Data bases and lists of authorized broadcast stations and pending broadcast applications.

**PUBLIC INFORMATION AND INSPECTION OF
RECORDS**

- 0.441 General.
- 0.442 Disclosure to other Federal government agencies of information submitted to the Commission in confidence.
- 0.443 General information office.
- 0.445 Publication, availability and use of opinions, orders, policy statements, interpretations, administrative manuals, and staff instructions.
- 0.451 Inspection of records: Generally.
- 0.453 Public reference rooms.
- 0.455 Other locations at which records may be inspected.
- 0.457 Records not routinely available for public inspection.
- 0.459 Requests that materials or information submitted to the Commission be withheld from public inspection.
- 0.460 Requests for inspection of records which are routinely available for public inspection.
- 0.461 Requests for inspection of materials not routinely available for public inspection.
- 0.463 Demand by competent authority for the production of documents or testimony concerning information contained therein.
- 0.465 Request for copies of materials which are available, or made available, for public inspection.
- 0.466 Definitions.
- 0.467 Search and review fees.
- 0.468 Interest.
- 0.469 Advance payments.
- 0.470 Assessment of fees.

**PLACES FOR MAKING SUBMITTALS OR RE-
QUESTS, FOR FILING APPLICATIONS, AND FOR
TAKING EXAMINATIONS**

- 0.471 Miscellaneous submittals or requests.
- 0.473 Reports of violations.
- 0.475 Applications for employment.
- 0.481 Place of filing applications for radio authorizations.
- 0.482 Application for waiver of private radio rules.
- 0.483 Applications for amateur or commercial radio operator licenses.
- 0.484 Amateur radio operator examinations.
- 0.485 Commercial radio operator examinations.
- 0.489 Applications for ship radio inspection and periodical survey.
- 0.491 Applications for exemption from compulsory ship radio requirements.

Federal Communications Commission

§0.5

0.493 Non-radio common carrier applications.

Subpart D—Mandatory Declassification of National Security Information

- 0.501 General.
- 0.502 Purpose.
- 0.503 Submission of requests for mandatory declassification review.
- 0.504 Processing requests for declassification.
- 0.505 Fees and charges.
- 0.506 FOIA and Privacy Act requests.

Subpart E—Privacy Act Regulations

- 0.551 Purpose and scope; definitions.
- 0.552 Notice identifying Commission systems of records.
- 0.553 New uses of information.
- 0.554 Procedures for requests pertaining to individual records in a system of records.
- 0.555 Disclosure of record information to individuals.
- 0.556 Request to correct or amend records.
- 0.557 Administrative review of an initial decision not to amend a record.
- 0.558 Advice and assistance.
- 0.559 Disclosure of disputed information to persons other than the individual to whom it pertains.
- 0.560 Penalty for false representation of identity.
- 0.561 Exemptions.

Subpart F—Meeting Procedures

- 0.601 Definitions.
- 0.602 Open meetings.
- 0.603 Bases for closing a meeting to the public.
- 0.605 Procedures for announcing meetings.
- 0.606 Procedures for closing a meeting to the public.
- 0.607 Transcript, recording or minutes; availability to the public.

AUTHORITY: Sec. 5, 48 Stat. 1068, as amended; 47 U.S.C. 155, 225, unless otherwise noted.

Subpart A—Organization

AUTHORITY: Secs. 5, 48 Stat. 1068, as amended; 47 U.S.C. 155.

GENERAL

§0.1 The Commission.

The Federal Communications Commission is composed of five (5) members who are appointed by the president subject to confirmation by the Senate. Normally, one Commissioner is

appointed or reappointed each year, for a term of five (5) years.

[53 FR 29054, Aug. 2, 1988]

§0.3 The Chairman.

(a) One of the members of the Commission is designated by the President to serve as Chairman, or chief executive officer, of the Commission. As Chairman, he has the following duties and responsibilities:

(1) To preside at all meetings and sessions of the Commission.

(2) To represent the Commission in all matters relating to legislation and legislative reports; however, any other Commissioner may present his own or minority views or supplemental reports.

(3) To represent the Commission in all matters requiring conferences or communications with other governmental officers, departments or agencies.

(4) To coordinate and organize the work of the Commission in such a manner as to promote prompt and efficient disposition of all matters within the jurisdiction of the Commission.

(b) The Commission will, in the case of a vacancy in the Office of the Chairman of the Commission, or in the absence or inability of the Chairman to serve, temporarily designate one of its members to act as Chairman until the cause or circumstance requiring such designation has been eliminated or corrected.

[32 FR 10569, July 19, 1967]

§0.5 General description of Commission organization and operations.

(a) *Principal staff units.* The Commission is assisted in the performance of its responsibilities by its staff, which is divided into the following principal units:

- (1) Office of Managing Director.
- (2) Office of Engineering and Technology.
- (3) Office of General Counsel.
- (4) Office of Plans and Policy.
- (5) Office of Public Affairs.
- (6) Office of Legislative Affairs.
- (7) Office of Administrative Law Judges.
- (8) Office of Inspector General.
- (9) Mass Media Bureau.

§0.11

- (10) Common Carrier Bureau.
- (11) Wireless Telecommunications Bureau.
- (12) International Bureau.
- (13) Cable Services Bureau.
- (14) Compliance and Information Bureau.

(b) Staff responsibilities and functions. The organization and functions of these major staff units are described in detail in §§0.11 through 0.151. The defense and emergency preparedness functions of the Commission are set forth separately, beginning at §0.181. For a complete description of staff functions, reference should be made to those provisions. (See also the U.S. Government Organization Manual, which contains a chart showing the Commission's organization, the names of the members and principal staff officers of the Commission, and other information concerning the Commission.)

(c) *Delegations of authority to the staff.* Pursuant to section 5(c) of the Communications Act, the Commission has delegated authority to its staff to act on matters which are minor or routine or settled in nature and those in which immediate action may be necessary. See subpart B of this part. Actions taken under delegated authority are subject to review by the Commission, on its own motion or on an application for review filed by a person aggrieved by the action. Except for the possibility of review, actions taken under delegated authority have the same force and effect as actions taken by the Commission. The delegation of authority to a staff officer, however, does not mean that he will exercise that authority in all matters subject to the delegation. In non-hearing matters, the staff is at liberty to refer any matter at any stage to the Commission for action, upon concluding that it involves matters warranting the Commission's consideration, and the Commission may instruct the staff to do so.

(d) *Commission action.* Matters requiring Commission action, or warranting its consideration, are dealt with by the Commission at regular monthly meetings, or at special meetings called to consider a particular matter. Meetings are normally held at the principal offices of the Commission in the District

47 CFR Ch. I (10–1–97 Edition)

of Columbia, but may be held elsewhere in the United States. In appropriate circumstances, Commission action may be taken between meetings "by circulation", which involves the submission of a document to each of the Commissioners for his approval.

(Secs. 4(i), 303(r) and 5(c)(i), Communications Act of 1934, as amended; 47 CFR 0.61 and 0.283)

[32 FR 10569, July 19, 1967, as amended at 62 FR 4170, Jan. 29, 1997]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §0.5, see the List of CFR Sections Affected in the Finding Aids section of this volume.

OFFICE OF MANAGING DIRECTOR

§0.11 Functions of the Office.

(a) The Managing Director is appointed by the Chairman with the approval of the Commission. Under the supervision and direction of the Chairman, the Managing Director shall serve as the Commission's chief operating and executive official with the following duties and responsibilities:

(1) Provide managerial leadership to and exercise supervision and direction over the Commission's Bureaus and Offices with respect to management and administrative matters but not substantive regulatory matters such as regulatory policy and rule making, authorization of service, administration of sanctions, and adjudication.

(2) Formulate and administer all management and administrative policies, programs, and directives for the Commission consistent with authority delegated by the Commission and the Chairman and recommend to the Chairman and the Commission major changes in such policies and programs.

(3) Assist the Chairman in carrying out the administrative and executive responsibilities delegated to the Chairman as the administrative head of the agency.

(4) Advise the Chairman and Commission on management, administrative, and related matters; review and evaluate the programs and procedures of the Commission; initiate action or make recommendations as may be necessary to administer the Communications Act most effectively in the public interest.

Federal Communications Commission

§0.13

Assess the management, administrative, and resource implications of any proposed action or decision to be taken by the Commission or by a Bureau or Office under delegated authority; recommend to the Chairman and Commission program priorities, resource and position allocations, management, and administrative policies.

(5) Plan and administer the Commission's Management by Objectives system. Assure that objectives, priorities, and action plans established by Bureaus and Offices are consistent with overall Commission objectives and priorities.

(6) Plan and administer the Commission's Program Evaluation System. Ensure that evaluation results are utilized in Commission decision-making and priority-setting activities.

(7) Direct agency efforts to improve management effectiveness, operational efficiency, employee productivity, and service to the public. Administer Commission-wide management programs.

(8) Plan and manage the administrative affairs of the Commission with respect to the functions of personnel and position management; labor-management relations; budget and financial management; information management and processing; organization planning; management analysis; procurement; office space management and utilization; administrative and office services; supply and property management; records management; personnel and physical security; and international telecommunications settlements.

(9) [Reserved]

(10) With the concurrence of the General Counsel, interpret rules and regulations pertaining to fees.

(b) The Secretary is the official custodian of the Commission's documents.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[46 FR 59975, Dec. 8, 1981, as amended at 47 FR 41380, Sept. 20, 1982; 49 FR 45583, Nov. 19, 1984; 50 FR 27953, July 9, 1985; 53 FR 29054, Aug. 2, 1988; 53 FR 47536, Nov. 23, 1988; 54 FR 152, Jan. 4, 1989; 59 FR 26971, May 25, 1994; 60 FR 5323, Jan. 27, 1995; 62 FR 15853, Apr. 3, 1997; 62 FR 51052, Sept. 30, 1997]

OFFICE OF INSPECTOR GENERAL

§0.13 Functions of the Office.

The Office of Inspector General is directly responsible to the Chairman as head of the agency. However, the Chairman may not prevent or prohibit the Office of Inspector General from carrying out its duties and responsibilities as mandated by the Inspector General Act Amendments of 1988 (Pub. L. 100-504) and the Inspector General Act of 1978 (5 U.S.C. Appendix 3), as amended. The Office has the following duties and responsibilities.

(a) Provide policy direction for and to conduct, supervise and coordinate audits and investigations relating to the programs and operations of the Federal Communications Commission.

(b) Review existing and proposed legislation and regulations relating to programs and operations of the Commission and to make recommendations in its required semiannual reports to Congress concerning the impact of such legislation or regulations on the economy and efficiency in the administration of these programs and operations, or the prevention and detection of fraud and abuse in such programs and operations.

(c) Recommend policies and conduct or coordinate other activities to promote economy and efficiency in the administration of Commission programs, or detect and prevent fraud and abuse in Commission activities. Coordinate with other governmental agencies and non-governmental entities on these matters.

(d) Keep the Chairman of the Commission—and through him the other Commissioners—and the Congress fully and currently informed concerning fraud and other serious problems, abuses, and deficiencies relating to the administration of Commission programs and operations; recommend corrective action and report on the progress made in implementing such corrective action. In addition to providing the Chairman with the results of completed audits and inspections, the Inspector General shall prepare statutorily required reports, identified as such, to include:

§0.15

47 CFR Ch. I (10–1–97 Edition)

(1) Semiannual reports summarizing activities of the office during the preceding six month period (due to the Chairman by April 30 and October 31);

(2) Special reports specifically identifying any serious or flagrant problems, abuses or deficiencies (due to the Chairman immediately upon discovery of these matters by the Inspector General).

[54 FR 15194, Apr. 17, 1989]

OFFICE OF PUBLIC AFFAIRS

§0.15 Functions of the Office.

The Office of Public Affairs is directly responsible to the Commission. The Office has the following duties and responsibilities:

(a) Develop, recommend, coordinate and administer Commission objectives, plans and programs to enhance public understanding of and compliance with the Commission's regulatory requirements. Evaluate public information dissemination practices and develop methods of improving these practices.

(b) Act as the principal channel for communicating information to the news media, regulated industries, and the general public on Commission policies, programs, and activities. Make official announcements of Commission decisions and actions. Maintain liaison with the information media to facilitate the dissemination of news and information on FCC activities. Advise the Commission on public reaction to and comment on FCC policies and programs.

(c) Develop, recommend, coordinate and administer objectives, plans and programs to encourage participation by the public in the Commission's decision-making processes. Promote increased awareness within the Commission of the impact of Commission policies on the ability of consumers of communications services to participate in decisions that affect them. Evaluate the effectiveness of mechanisms developed and used to facilitate public input and develop new initiatives as appropriate.

(d) Serve as the Commission's primary point of contact with individual consumers of communications services and with organizations of such consumers. Maintain liaison with consumers

to facilitate an interchange of information and cooperative efforts to improve the Commission's information-gathering, policy-making, and information dissemination functions.

(e) Act as the principal point of public contact in disseminating information about Commission programs to promote equal employment opportunity and minority enterprise in Commission-regulated industries. Maintain liaison with industry representatives, women's and minority groups and other interested parties regarding public information about and public evaluation of these programs. Organize FCC seminars and serve as FCC spokesperson to outside organizations on these subjects.

(f) Develop and implement programs to assist in providing information to minority entrepreneurs engaged in or seeking to participate in telecommunications industries regulated by the Commission.

(g) Review Commission contract procurement policy to devise ways of increasing information about proposed Commission contracts received by minority contractors.

(h) Advise the Commission on its information dissemination and public participation policies, as they affect liaison with the information media, the public and the Commission's regulatees. Provide policy and program guidance to the bureaus and offices on these subjects based on feedback received through the information dissemination functions of the Office.

(i) Maintain liaison with the Compliance and Information Bureau regarding the press and news media, and consumer assistance and information activities of the Commission's field offices.

(Secs. 4, 5, 303, 48 Stat. 1066, 1082, as amended; 47 U.S.C. 154, 155, 303)

[44 FR 12425, Mar. 7, 1979, as amended at 44 FR 70471, Dec. 7, 1979; 50 FR 2985, Jan. 23, 1985; 52 FR 42438, Nov. 5, 1987; 61 FR 8477, Mar. 5, 1996]

OFFICE OF LEGISLATIVE AFFAIRS

§0.17 Functions of the Office.

The Office of Legislative Affairs is directly responsible to the Commission.

Federal Communications Commission

§0.31

The Office has the following duties and responsibilities:

(a) Advise and make recommendations to the Commission with respect to legislation proposed by members of Congress or the Executive Branch and coordinate the preparation of Commission views thereon for submission to Congress or the Executive Branch.

(b) Coordinate with the Office of General Counsel responses to Congressional or Executive Branch inquiries as to the local ramifications of Commission policies, regulations, rules, and statutory interpretations.

(c) Assist the Office of the Managing Director in preparation of the annual report to Congress, the Commission budget and appropriations legislation to Congress; assist the Office of Public Affairs in preparation of the Commission's Annual Report.

(d) Assist the Chairman and Commissioners in preparation for, and the coordination of their appearances before the Committees of Congress.

(e) Coordinate the annual Commission legislative program.

(f) Coordinate Commission and staff responses to inquiries by individual members of Congress, congressional committees and staffs.

[52 FR 42438, Nov. 5, 1987]

OFFICE OF PLANS AND POLICY

§0.21 Functions of the Office.

The Office of Plans and Policy, as a staff office to the Commission, assists, advises and makes recommendations to the Commission with respect to the development and implementation of communications policies in all areas of Commission authority and responsibility. A principal function of the Office is to conduct independent policy analyses to assess the long-term effects of alternative Commission policies on domestic and international communication industries and services, with due consideration of the responsibilities and programs of other staff units, and to recommend appropriate Commission action. The Office is also responsible for coordinating the policy research and development activities of other staff units, with special concern for matters which transcend their individual areas of responsibility. The Office

is composed of legal, engineering, economic, and sociological policy analysts and other personnel, and is headed by a chief having the following duties and responsibilities:

(a) To identify and define significant communications policy issues in all areas of Commission interest and responsibility;

(b) To conduct technical, economic, and sociological impact studies of existing and proposed communications policies and operations, including cooperative studies with other staff units and consultant and contract efforts as appropriate;

(c) To develop and evaluate alternative policy options and approaches for consideration by the Commission;

(d) To review and comment on all significant actions proposed to be taken by the Commission in terms of their overall policy implications;

(e) To recommend and evaluate governmental (state and federal), academic, and industry sponsored research affecting Commission policy issues;

(f) To prepare briefings, position papers, proposed Commission actions, or other agenda items as appropriate;

(g) To manage the Commission's policy research program, recommend budget levels and priorities for this program, and serve as central account manager for all contractual policy research studies funded by the Commission;

(h) To coordinate the formation and presentation of Commission positions in communications policy; represent the Commission at appropriate discussions and conferences.

(i) Develop and recommend procedures and plans for the effective handling of policy issues within the Commission.

[38 FR 17005, June 28, 1973, as amended at 45 FR 25400, Apr. 15, 1980; 51 FR 12615, Apr. 14, 1986; 60 FR 5323, Jan. 27, 1995]

OFFICE OF ENGINEERING AND TECHNOLOGY

§0.31 Functions of the Office.

The Office of Engineering and Technology has the following duties and responsibilities:

§0.41

(a) To evaluate evolving technology for interference potential and to suggest ways to facilitate its introduction in response to Bureau initiatives, and advise the Commission and staff offices in such matters.

(b) Represent the Commission at various national conferences and meetings (and, in consultation with the International Bureau, at various international conferences and meetings) devoted to the progress of communications and the development of technical and other information and standards, and serve as Commission coordinator for the various national conferences when appropriate.

(c) To conduct scientific and technical studies in advanced phases of terrestrial and space communications, and special projects to obtain theoretical and experimental data on new or improved techniques.

(d) To advise the Commission concerning engineering matters, including the privacy and security of communications, involved in making or implementing policy or in resolving specific cases.

(e) To develop and implement procedures to acquire, store, and retrieve scientific and technical information useful in the engineering work of the Commission.

(f) To advise and represent the Commission on frequency allocation and spectrum usage matters.

(g) To render, in cooperation with the General Counsel and the Office of Plans and Policy, advice to the Commission, participate in and coordinate staff work with respect to general frequency allocation proceedings and other proceedings not within the jurisdiction of any single bureau, and render service and advice with respect to rule making matters and proceedings affecting more than one Bureau.

(h) To collaborate with and advise other Bureaus and Offices in the formulation of technical requirements of the Rules.

(i) To administer parts 2, 5, 15, and 18 of this chapter, including licensing, recordkeeping, and rule making.

(j) To perform all engineering and management functions of the Commission with respect to formulating rules and regulations, technical standards,

47 CFR Ch. I (10–1–97 Edition)

and general policies for parts 15 and 18 of this chapter, and for type approval and acceptance, and certification of radio equipment for compliance with the Rules.

(k) To maintain liaison with other agencies of government, technical experts representing foreign governments, and members of the public and industry concerned with communications and frequency allocation and usage.

(l) To calibrate and standardize technical equipment and installations used by the Commission.

(m) To exercise authority as may be assigned or referred by the Commission pursuant to section 5(c) of the Communications Act of 1934, as amended.

(Secs. 2, 3, 4, 5, 301, 303, 307, 308, 309, 315, 317, 48 Stat., as amended, 1064, 1065, 1066, 1068, 1081, 1082, 1083, 1084, 1085, 1088, 1089; 47 U.S.C. 152, 153, 154, 155, 301, 303, 307, 308, 309, 315, 317)

[45 FR 28718, Apr. 30, 1980, as amended at 46 FR 45342, Sept. 11, 1981; 51 FR 12615, Apr. 14, 1986; 60 FR 5323, Jan. 27, 1995; 62 FR 4170, Jan. 29, 1997]

OFFICE OF GENERAL COUNSEL

§0.41 Functions of the Office.

The Office of the General Counsel has the following duties and responsibilities:

(a) To advise and represent the Commission in matters of litigation.

(b) To advise and make recommendations to the Commission with respect to proposed legislation and submit agency views on legislation when appropriate.

(c) To interpret the statutes, international agreements, and international regulations affecting the Commission.

(d) To prepare and make recommendations and interpretations concerning procedural rules of general applicability and to review all rules for consistency with other rules, uniformity, and legal sufficiency.

(e) To conduct research in legal matters as directed by the Commission.

(f) In cooperation with the Office of Engineering and Technology, to participate in, render advice to the Commission, and coordinate the staff work with respect to general frequency allocation proceedings and other proceedings not within the jurisdiction of any

Federal Communications Commission

§0.51

single bureau, and to render advice with respect to rule making matters and proceedings affecting more than one bureau.

(g) To serve as the Commission's advocate for competition throughout the telecommunications industry and, specifically, to help to ensure that Commission policy development employs uniform or consistent analysis and that FCC policy encourages and promotes competitive market structures in affected industry segments by providing bureaus/offices with the necessary support to identify, evaluate, and effectively resolve competitiveness issues.

(h) To exercise such authority as may be assigned or referred to it by the Commission pursuant to section 5(c) of the Communications Act of 1934, as amended.

(i) To cooperate with the International Bureau on all matters pertaining to space satellite communications.

(j) To interpret statutes and executive orders affecting the Commission's national defense responsibilities, and to perform such functions involving implementation of such statutes and executive orders as may be assigned to it by the Commission or the Defense Commissioner.

(k) To perform all legal functions with respect to leases, contracts, tort claims and such other internal legal problems as may arise.

(l) To issue written determinations on behalf of the Chairman, and otherwise act as the Chairman's designee on matters regarding the interception of telephone conversations, as required by the General Services Administration's regulations. 41 CFR 201-6.202 *et seq.*

(m) To advise the Commission in the preparation and revision of rules and the implementation and administration of ethics regulations and the Freedom of Information, Privacy, Government in the Sunshine and Alternative Dispute Resolution Acts.

(n) To assist and make recommendations to the Commission, and to individual Commissioners assigned to review initial decisions, as to the disposition of cases of adjudication and such other cases as, by Commission policy, are handled in the same manner and

which have been designated for hearing.

(o) To serve as the principal operating office on *ex parte* matters involving restricted proceedings. To review and dispose of all *ex parte* communications received from the public and others.

(Secs. 2, 3, 4, 5, 301, 303, 307, 308, 309, 315, 317, 48 Stat., as amended, 1064, 1065, 1066, 1068, 1081, 1082, 1083, 1084, 1085, 1088, 1089; 47 U.S.C. 152, 153, 154, 155, 301, 303, 307, 308, 309, 315, 317)

[28 FR 12392, Nov. 22, 1963; 37 FR 19372, Sept. 20, 1972, as amended at 40 FR 17253, Apr. 18, 1975; 43 FR 29006, July 5, 1978; 44 FR 39179, July 5, 1979; 46 FR 57050, Nov. 20, 1981; 49 FR 47604, Dec. 6, 1984; 50 FR 2985, Jan. 23, 1985; 50 FR 49048, Nov. 29, 1985; 51 FR 12615, Apr. 14, 1986; 60 FR 5323, Jan. 27, 1995; 60 FR 34901, July 5, 1995; 62 FR 4170, Jan. 29, 1997; 62 FR 15853, Apr. 3, 1997]

INTERNATIONAL BUREAU

§0.51 Functions of the Bureau.

The International Bureau has the following duties and responsibilities:

(a) To initiate and direct the development and articulation of international telecommunications policies, consistent with the priorities of the Commission;

(b) To advise the Chairman and Commissioners on matters of international telecommunications policy, and on the adequacy of the Commission's actions to promote the vital interests of the American public in international commerce, national defense, and foreign policy;

(c) To develop, recommend, and administer policies, rules, standards, and procedures for the authorization and regulation of international telecommunications facilities and services, domestic and international satellite systems, and international broadcast services;

(d) To monitor compliance with the terms and conditions of authorizations and licenses granted by the Bureau, and to pursue enforcement actions in conjunction with appropriate bureaus and offices;

(e) To represent the Commission on international telecommunications matters at both domestic and international conferences and meetings, and to direct and coordinate the Commission's preparation for such conferences and meetings;

§0.61

47 CFR Ch. I (10–1–97 Edition)

(f) To serve as the single focal point within the Commission for cooperation and consultation on international telecommunications matters with other federal agencies, international or foreign organizations, and appropriate regulatory bodies and officials of foreign governments;

(g) To develop, coordinate with other federal agencies, and administer the regulatory assistance and training programs for foreign administrations to promote telecommunications development;

(h) To provide advice and technical assistance to U.S. trade officials in the negotiation and implementation of telecommunications trade agreements, and consult with other bureaus and offices as appropriate;

(i) To conduct economic, legal, technical, statistical, and other appropriate studies, surveys, and analyses in support of international telecommunications policies and programs.

(j) To collect and disseminate within the Commission information and data on international telecommunications policies, regulatory and market developments in other countries, and international organizations;

(k) To work with the Office of Legislative Affairs to coordinate the Commission's activities on significant matters of international policy with appropriate Congressional offices;

(l) To promote the international coordination of spectrum allocations and frequency and orbital assignments so as to minimize cases of international radio interference involving U.S. licensees;

(m) To direct and coordinate, in consultation with other bureaus and offices as appropriate, negotiation of international agreements to provide for arrangements and procedures for coordination of radio frequency assignments to prevent or resolve international radio interference involving U.S. licensees;

(n) To ensure fulfillment of the Commission's responsibilities under international agreements and treaty obligations, and, consistent with Commission policy, to ensure that the Commission's regulations, procedures, and frequency allocations comply with the mandatory requirements of all applica-

ble international and bilateral agreements;

(o) To oversee and, as appropriate, administer activities pertaining to the international consultation, coordination, and notification of U.S. frequency and orbital assignments, including activities required by bilateral agreements, the international Radio Regulations, and other international agreements;

(p) To advise the Chairman on priorities for international travel and develop, coordinate, and administer the international travel plan;

(q) To develop, recommend, and administer policies, rules, and regulations implementing the Commission's oversight responsibilities regarding COMSAT's participation in INTELSAT and INMARSAT;

(r) To exercise authority to issue non-hearing related subpoenas for the attendance and testimony of witnesses and the production of books, papers, correspondence, memoranda, schedules of charges, contracts, agreements, and any other records deemed relevant to the investigation of matters within the jurisdiction of the International Bureau. Before issuing a subpoena, the International Bureau shall obtain the approval of the Office of General Counsel.

[60 FR 5323, Jan. 27, 1995, as amended at 60 FR 35504, July 10, 1995]

MASS MEDIA BUREAU

§0.61 Functions of the Bureau.

The Mass Media Bureau develops, recommends and administers policies and programs for the regulation of all radio and television broadcast industry services. Advises and recommends to the Commission, or acts for the Commission under delegated authority, in matters pertaining to the regulation and development of radio and television services. The Mass Media Bureau has the following duties and responsibilities:

(a) Process applications for authorizations in radio and television services, including conventional and auxiliary broadcast services (other than international broadcast services) and multi-point and multi-channel multi-point distribution services.

Federal Communications Commission

§0.81

(b) Process applications for renewal of licenses and for assignment or transfer of ownership interests in such licenses.

(c) Participate in hearings before the Administrative Law Judges and the Commission.

(d) Plan and develop proposed rulemakings and conduct comprehensive studies and analyses (legal, engineering, social and economic) of various petitions for policy or rule changes submitted by industry or the public.

(e) Conduct studies and compile data relating to radio and television network operations necessary for the Commission to develop and maintain an adequate regulatory program.

(f) Investigate complaints and answer general inquiries from the public and handle political broadcasting and fairness doctrine complaints.

(g) [Reserved]

(h) To exercise authority to issue non-hearing related subpoenas for the attendance and testimony of witnesses and the production of books, papers, correspondence, memoranda, schedules of charges, contracts, agreements, and any other records deemed relevant to the investigation of matters within the jurisdiction of the Mass Media Bureau. Before issuing a subpoena, the Mass Media Bureau shall obtain the approval of the Office of General Counsel.

[47 FR 47829, Oct. 28, 1982, as amended at 49 FR 12271, Mar. 29, 1984; 58 FR 29752, May 21, 1993; 59 FR 32132, June 22, 1994; 59 FR 38374, July 28, 1994; 60 FR 5323, Jan. 27, 1995; 60 FR 35504, July 10, 1995; 62 FR 4170, Jan. 29, 1997; 62 FR 45172, Aug. 26, 1997]

OFFICE OF WORKPLACE DIVERSITY

§0.81 Functions of the Office.

(a) The Office of Workplace Diversity (OWD), as a staff office to the Commission, shall develop, coordinate, evaluate, and recommend to the Commission policies, programs, and practices that foster a diverse workforce and promote and ensure equal opportunity for all employees and applicants for employment. A principal function of the Office is to lead, advise, and assist the Commission, including all of its component Bureau/Office managers, supervisors, and staff, at all levels, on ways to pro-

mote inclusion and full participation of all employees in pursuit of the Commission's mission. In accordance with this function, the Office shall:

(1) Conduct independent analyses of the Commission's policies and practices to ensure that those policies and practices foster diversity in the workplace and ensure equal opportunity and equal treatment for employees and applicants; and

(2) Advise the Commission, Bureaus, and Offices of their responsibilities under Title VII of the Civil Rights Act of 1964, as amended; Section 501 of the Rehabilitation Act of 1973, as amended; Age Discrimination in Employment Act of 1967, as amended; Executive Order 11478; and all other statutes, Executive Orders, and regulatory provisions relating to workplace diversity, equal employment opportunity, non-discrimination, and civil rights.

(b) The Office has the following duties and responsibilities:

(1) Through its Director, serves as the principal advisor to the Chairman and Commission officials on all aspects of workplace diversity, affirmative recruitment, equal employment opportunity, non-discrimination, and civil rights;

(2) Provides leadership and guidance to create a work environment that values and encourages diversity in the workplace;

(3) Is responsible for developing, implementing, and evaluating programs and policies to foster a workplace whose diversity reflects the diverse makeup of the Nation, enhances the mission of the Commission, and demonstrates the value and effectiveness of a diverse workforce;

(4) Is responsible for developing, implementing, and evaluating programs and policies that promote understanding among members of the Commission's workforce of their differences and the value of those differences and provide a channel for communication among diverse members of the workforce at all levels;

(5) Develops, implements, and evaluates programs and policies to ensure that all members of the Commission's workforce and candidates for employment have equal access to opportunities for employment, career growth,

§ 0.91

47 CFR Ch. I (10–1–97 Edition)

training, and development and are protected from discrimination and harassment;

(6) Develops and recommends Commission-wide workforce diversity goals and reports on achievements;

(7) Is responsible for developing, implementing, and evaluating programs and policies to enable all Bureaus and Offices to manage a diverse workforce effectively and in compliance with all equal employment opportunity and civil rights requirements;

(8) Works closely with the Associate Managing Director—Human Resources Management to ensure compliance with Federal and Commission recruitment and staffing requirements;

(9) Manages the Commission's equal employment opportunity compliance program. Responsibilities in this area include processing complaints alleging discrimination, recommending to the Chairman final decisions on EEO complaints within the Commission, and providing counseling services to employees and applicants on EEO matters;

(10) Develops and administers the Commission's program of accessibility and accommodation for disabled persons in accordance with applicable regulations;

(11) Represents the Commission at meeting with other public and private groups and organizations on matters counseling workplace diversity and equal employment opportunity and workplace diversity issues;

(12) Maintains liaison with and solicits views of organizations within and outside the Commission on matters relating to equal opportunity and workplace diversity.

[61 FR 2727, Jan. 29, 1996]

COMMON CARRIER BUREAU

§ 0.91 Functions of the Bureau.

The Common Carrier Bureau develops, recommends, and administers policies and programs for the regulation of services, facilities and practices of entities which furnish interstate communications service or interstate access service for hire—whether by wire, radio or cable—and of ancillary operations related to the provision of such services (excluding public coast stations in

the maritime mobile services and multi-point and multi-channel multi-point distribution services and excluding matters pertaining exclusively to the regulation and licensing of wireless telecommunications services and facilities). The Bureau also develops, recommends, and administers policies and programs for the regulation of rates, terms and conditions under which communications entities furnish interstate communications service, interstate access service, and (in cooperation with the International Bureau) foreign communications service for hire—whether by wire, cable or satellite. The Bureau also performs the following functions:

(a) Advises and makes recommendations to the Commission, or acts for the Commission under delegated authority, in matters pertaining to the regulation and licensing of communication common carriers and ancillary operations (other than matters pertaining exclusively to the regulation and licensing of wireless telecommunications services and facilities). This includes: Policy development and coordination; adjudicatory and rule making proceedings, including rate and service investigations; determinations regarding lawfulness of carrier tariffs; action on applications for service and facility authorizations; review of carrier performance; economic research and analysis; administration of Commission accounting and reporting requirements; compliance and enforcement activities; and any matters concerning wireline carriers that also affect wireless carriers in cooperation with the Wireless Telecommunications Bureau.

(b) Collaborates with representatives of state regulatory commissions and with the National Association of Regulatory Utility Commissioners in cooperative studies of common carrier and related matters.

(c) Advises and assists the public, other government agencies and industry groups on wireline common carrier regulation and related matters.

(d) Exercises such authority as may be assigned or referred to it by the Commission pursuant to Section 5(c) of the Communications Act of 1934, as amended.

Federal Communications Commission

§0.101

(e) Obtains from carriers and from persons directly or indirectly controlling or controlled by, or under direct or indirect common control with, such carriers full and complete information necessary to enable the Commission to perform the duties and carry out the objectives for which it was created.

(f) Carries out the functions of the Commission under the Communications Act of 1934, as amended, except as reserved to Commission under §0.291.

(g) Acts jointly with the Office of Engineering and Technology on applications for registration of equipment to be directly connected to the telephone network, and acts on complaints brought by any party concerning the registration or operation of such equipment.

(h) Administers the Telecommunications Service Priority System with the concurrence of the Compliance and Information Bureau, and resolves matters involving assignment of priorities and other issues pursuant to part 64 of this chapter.

(i) Acts upon matters involving telecommunications relay services complaints and certification.

(j) Develops, in coordination with the Office of Plans and Policy, policies for the selection of licenses from mutually exclusive applicants in the Common Carrier Service subject to competitive bidding; issues Public Notices announcing auctions for Common Carrier Service Licenses; specifies the licenses to be auctioned; the deadlines for filing short-form applications, filing fees, and submission of upfront payments; the time and place of the auction; the method of competitive bidding to be used; competitive bidding procedures including, but not limited to, designated entity preferences, applicable bid submission procedures, upfront payment requirements, activity rules, stopping rules, and bid withdrawal procedures.

(Secs. 4, 303, 48 Stat., as amended, 1066, 1082; 47 U.S.C. 154, 303)

[39 FR 28435, Aug. 7, 1974, as amended at 40 FR 7451, Feb. 20, 1975; 41 FR 7751, Feb. 20, 1976; 42 FR 42341, Aug. 23, 1977; 43 FR 36094, Aug. 15, 1978; 44 FR 39179, July 5, 1979; 45 FR 71569, Oct. 29, 1980; 48 FR 23431, May 25, 1983; 50 FR 26567, June 27, 1985; 51 FR 12615, Apr. 14, 1986; 53 FR 47536, Nov. 23, 1988; 54 FR 152, Jan. 4, 1989; 56 FR 36731, Aug. 1, 1991; 59 FR 26747, May 24, 1994; 59 FR 26971, May 25, 1994; 59 FR 38374, July 28, 1994; 60 FR 5323, 5324, Jan. 27, 1995; 60 FR 35504, July 10, 1995; 61 FR 8477, Mar. 5, 1996; 62 FR 4170, Jan. 29, 1997; 62 FR 8401, Feb. 25, 1997]

CABLE SERVICES BUREAU

§0.101 Functions of the Bureau.

The Cable Services Bureau develops, recommends and administers policies and programs with respect to the regulation of services, facilities, rates and practices of cable television systems and with respect to the creation of competition to cable systems, and with respect to video programming services provided by other multichannel video programming distributors and multichannel video programmers. The Cable Services Bureau advises and recommends to the Commission, or acts for the Commission under delegated authority, in matters pertaining to the regulation and development of cable television and other multichannel video programming services. The Bureau also performs the following functions:

(a) Administers and enforces rules and policies regarding:

(1) Cable television systems, operators, and services, including those relating to rates, technical standards, customer service, ownership, competition to cable systems, broadcast station signal retransmission and carriage, program access, wiring equipment, channel leasing, and federal-state/local regulatory relationships. This includes: acting, after Commission assumption of jurisdiction to regulate cable television rates for basic service and associated equipment, on cable operator requests for approval of

§0.111

existing or increased rates; reviewing appeals of local franchising authorities' rate making decisions involving rates for the basic service tier and associated equipment, except when such appeals raise novel or unusual issues; acting upon complaints involving cable programming service rates except for final action on complaints raising novel or unusual issues; evaluating basic rate regulation certification requests filed by cable system franchising authorities; periodically reviewing and, when appropriate, revising standard forms used in administering: the Commission's complaint process regarding cable programming service rates; the certification process for local franchising authorities wishing to regulate rates, and the substantive rate regulation standards prescribed by the Commission;

(2) Access to poles, ducts, conduits and rights-of-way and the rates, terms and conditions for pole attachments, when such attachments are not regulated by a state and not provided by railroads or governmentally or cooperatively owned utilities, and complaints involving access to or rates, terms and conditions arising from pole attachments, except for final action on complaints raising novel or unusual issues;

(3) Open video systems;

(4) Preemption of restrictions on devices designed for over-the-air reception of television broadcast signals, multichannel multipoint distribution service, and direct broadcast satellite services;

(5) The commercial availability of navigational devices;

(6) The accessibility of video programming to persons with disabilities; and

(7) Scrambling of sexually explicit adult video programming by multichannel video programming distributors.

(b) Plans and develops proposed rulemakings and conducts studies and analyses (legal, engineering, social and economic) of various petitions for policy or rule changes submitted by industry or the public.

(c) Conducts studies and compiles data relating to multichannel video programming services necessary for

47 CFR Ch. I (10–1–97 Edition)

the Commission to develop and maintain an adequate regulatory program.

(d) Advises and assists the public, other government agencies and industry groups.

(e) Administers financial and other reporting systems.

(f) Investigates complaints and answers general inquiries from the public.

(g) Participates in hearings before the Administrative Law Judges and the Commission.

(h) Processes applications for authorizations in the Cable Television Relay Service.

(i) Processes and acts on all applications for authorization, petitions for special relief, petitions to deny, waiver requests, requests for certification, objections, complaints, and requests for declaratory rulings and stays regarding the areas listed above, that do not involve novel questions of fact, law or policy that cannot be resolved under existing precedents and guidelines.

(j) Periodically reviews and, when appropriate, revises standard forms related to the areas listed above.

(k) Exercises authority to issue non-hearing related subpoenas for the attendance of witnesses and the production of books, papers, correspondence, memoranda, schedule of charges, contracts, agreements, and any other records deemed relevant to the investigation of the Cable Services Bureau. Before issuing a subpoena, the Cable Services Bureau shall obtain the approval of the Office of General Counsel.

(l) Carries out the functions of the Commission under the Communications Act of 1934, as amended, except as reserved to the Commission under §0.321.

[62 FR 8401, Feb. 25, 1997]

COMPLIANCE AND INFORMATION BUREAU

§0.111 Functions of the Bureau.

(a) Enforce the Commission's Rules and Regulations; provide support to other governmental units, investigate all non-government communications matters; issue sanctions.

(b) Disseminate to the public on a local basis information regarding communications issues and Commission rules, policies, and programs.

Federal Communications Commission

§ 0.121

(c) Collect information through a customer intelligence network to inform the Commission on the needs of its customer and on the impact of regulations and necessary refinements to them as suggested by the users and the public.

(d) Participate in international conferences dealing with monitoring and measurement; serve as the point of contact for the U.S. Government in matters of international monitoring, fixed and mobile direction-finding, and interference resolution. Provide technical and administrative support on the administration of the ITU Fellowship program and oversee coordination of non-routine communications and materials between the Commission and international or regional public organizations or foreign administrations.

(e) Reduce or eliminate interference to authorized communications. Promote private sector solutions to interference problems; investigate and resolve those unsuitable for private sector resolution or where the private sector is unable to provide solutions. Work, in conjunction with the Office of Engineering and Technology, with technical standards bodies.

(f) Perform investigations in support of Commission policies.

(g) Maintain, operate, and manage the toll-free telephone receiving center for complaint and inquiries. Coordinate with the Office of Public Affairs and maintain liaison with the rest of the agency to ensure that the needs of the public for information are handled promptly, accurately, and comprehensively and that complaints are directed to those charged with acting upon them.

(h) Under the general direction of the Defense Commissioner, coordinate the defense activities of the Commission, and provide support to the Defense Commissioner in his participation in the Joint Telecommunication Resources Board and the National Security Telecommunications Advisory Committee, including recommendation of national emergency plans and preparedness programs covering Commission functions during national emergencies. Support the Chief, Common Carrier Bureau on assignment of Telecommunications Service Priority Sys-

tem priorities and the administration of this system. The Chief, Compliance and Information Bureau, or the designee of that person, acts as the FCC Defense Coordinator and the principal of the Commission to the National Communications System.

[61 FR 8476, Mar. 5, 1996]

§ 0.121 Location of field installations.

(a) Field offices are located throughout the United States. For the address and phone number of the closest office contact the Compliance and Information Bureau or see the U.S. Government Manual.

(b) Protected field offices are located at the following geographical coordinates:

Allegan, Michigan
42</d>36'20" N. Latitude
85</d>57'20" W. Longitude
Anchorage, Alaska
61</d>09'43" N. Latitude
149</d>59'55" W. Longitude
Belfast, Maine
44</d>26'42" N. Latitude
69</d>04'58" W. Longitude
Canandaigua, New York
42</d>54'48" N. Latitude
77</d>15'59" W. Longitude
Douglas, Arizona
31</d>30'02" N. Latitude
109</d>39'12" W. Longitude
Ferndale, Washington
48</d>57'21" N. Latitude
122</d>33'13" W. Longitude
Grand Island, Nebraska
40</d>55'21" N. Latitude
98</d>25'42" W. Longitude
Kingsville, Texas
27</d>26'29" N. Latitude
97</d>53'00" W. Longitude
Laurel, Maryland
39</d>09'54" N. Latitude
76</d>49'17" W. Longitude
Livermore, California
37</d>43'30" N. Latitude
121</d>45'12" W. Longitude
Powder Springs, Georgia
33</d>51'44" N. Latitude
84</d>43'26" W. Longitude
Sabana Seca, Puerto Rico
18</d>27'23" N. Latitude
66</d>13'37" W. Longitude
Santa Isabel, Puerto Rico
18</d>00'26" N. Latitude
66</d>22'32" W. Longitude
Vero Beach, Florida
27</d>36'21" N. Latitude
80</d>38'06" W. Longitude
Waipahu, Hawaii
21</d>22'45" N. Latitude

§0.131

157°59'54" W. Longitude

[53 FR 29054, Aug. 2, 1988, as amended at 61 FR 8477, Mar. 5, 1996]

WIRELESS TELECOMMUNICATIONS BUREAU

§0.131 Functions of the Bureau.

The Wireless Telecommunications Bureau develops, recommends and administers the programs and policies for the regulation of the terms and conditions under which communications entities offer domestic wireless telecommunications services and of ancillary operations related to the provision of such services (satellite communications excluded). These functions include all wireless telecommunications service providers' and licensees' activities. The Bureau also performs the following specific functions:

(a) Advises and makes recommendations to the Commission, or acts for the Commission under delegated authority, in all matters pertaining to the licensing and regulation of wireless telecommunications, including ancillary operations related to the provision or use of such services; and any matters concerning wireless carriers that also affect wireline carriers in cooperation with the Common Carrier Bureau. These activities include: policy development and coordination; conducting rulemaking and adjudicatory proceedings, including licensing and complaint proceedings; acting on waivers of rules; acting on applications for service and facility authorizations; compliance and enforcement activities; determining resource impacts of existing, planned or recommended Commission activities concerning wireless telecommunications, and developing and recommending resource deployment priorities.

(b) Develops and recommends policy goals, objectives, programs and plans for the Commission on matters concerning wireless telecommunications, drawing upon relevant economic, technological, legislative, regulatory and judicial information and developments. Such matters include meeting the present and future wireless telecommunications needs of the Nation; fostering economic growth by promoting efficiency and innovation in the al-

47 CFR Ch. I (10–1–97 Edition)

location, licensing and use of the electromagnetic spectrum; ensuring choice, opportunity and fairness in the development of wireless telecommunications services and markets; promoting economically efficient investment in wireless telecommunications infrastructure and the integration of wireless communications networks into the public telecommunications network; enabling access to national communications services; promoting the development and widespread availability of wireless telecommunications services. Reviews and coordinates orders, programs and actions initiated by other Bureaus and Offices in matters affecting wireless telecommunications to ensure consistency of overall Commission policy.

(c) Serves as the Commission's principal policy and administrative staff resource with regard to spectrum auctions. Administers all Commission spectrum auctions. Develops, recommends and administers policies, programs and rules concerning auctions of spectrum for wireless telecommunications. Advises the Commission on policy, engineering and technical matters relating to auctions of spectrum used for other purposes. Administers procurement of auction-related services from outside contractors. Provides policy, administrative and technical assistance to other Bureaus and Offices on auction issues.

(d) Regulates the charges, practices, classifications, terms and conditions for, and facilities used to provide, wireless telecommunications services. Develops and recommends consistent, integrated policies, programs and rules for the regulation of commercial mobile radio services and private mobile radio services.

(e) Develops and recommends policy, rules, standards, procedures and forms for the authorization and regulation of wireless telecommunications facilities and services, including all facility authorization applications involving domestic terrestrial transmission facilities. Coordinates with and assists the International Bureau regarding frequency assignment, coordination and interference matters.

Federal Communications Commission

§0.151

(f) Develops and recommends responses to legislative, regulatory or judicial inquiries and proposals concerning or affecting wireless telecommunications.

(g) Develops and recommends policies regarding matters affecting the collaboration and coordination of relations among Federal agencies, and between the Federal government and the states, concerning wireless telecommunications issues. Maintains liaison with Federal and state government bodies concerning such issues.

(h) Develops and recommends policies, programs and rules to ensure interference-free operation of wireless telecommunications equipment and networks. Coordinates with and assists other Bureaus and Offices, as appropriate, concerning spectrum management, planning, and interference matters and issues, and in all compliance and enforcement activities. Studies technical requirements for equipment for wireless telecommunications services in accordance with standards established by the Chief, Office of Engineering and Technology.

(i) Advises and assists consumers, businesses and other government agencies on wireless telecommunications issues and matters relating thereto.

(j) Administers the Commission's commercial radio operator program (part 13 of this chapter) and the Commission's program for registration, construction, marking and lighting of antenna structures (part 17 of this chapter).

(k) Coordinates with and assists the International Bureau with respect to treaty activities and international conferences concerning wireless telecommunications.

(l) Exercises such authority as may be assigned, delegated or referred to it by the Commission.

(m) Certifies frequency coordinators; considers petitions seeking review of coordinator actions; and engages in oversight of coordinator actions and practices.

(n) Administers the Commission's commercial radio operator (part 13 of this chapter) and amateur radio programs (part 97 of this chapter) and the program for construction, marking and

lighting of antenna structures (part 17 of this chapter).

(o) Exercises authority to issue non-hearing related subpoenas for the attendance and testimony of witnesses and the production of books, papers, correspondence, memoranda, schedules of charges, contracts, agreements, and any other records deemed relevant to the investigation of wireless telecommunications operators for any alleged violation or violations of the Communications Act of 1934, as amended, or the Commission's rules and orders. Before issuing a subpoena, the Wireless Telecommunications Bureau shall obtain the approval of the Office of General Counsel.

(p) Certifies, in the name of the Commission, volunteer entities to coordinate maintain and disseminate a common data base of amateur station special event call signs, and issues Public Notices detailing the procedures of amateur service call sign systems.

[60 FR 35505, July 10, 1995, as amended at 61 FR 4361, Feb. 6, 1996; 62 FR 17567, Apr. 10, 1997]

OFFICE OF ADMINISTRATIVE LAW JUDGES

§0.151 Functions of the Office.

The Office of Administrative Law Judges consists of a Chief Administrative Law Judge, an Assistant Chief Administrative Law Judge, and as many other Administrative Law Judges qualified and appointed pursuant to the requirements of section 11 of the Administrative Procedure Act as the Commission may find necessary. It is responsible for hearing and conducting all adjudicatory cases designated for any evidentiary adjudicatory hearing other than those designated to be heard by the Commission en banc, those designated to be heard by one or more members of the Commission, and those involving the authorization of service in the Instructional Television Fixed Service. The Office of Administrative Law Judges is also responsible for conducting such other hearings as the Commission may assign.

[61 FR 10689, Mar. 15, 1996]

§0.181

DEFENSE AND EMERGENCY PREPAREDNESS FUNCTIONS

§0.181 The Defense Commissioner.

A Defense Commissioner and two Alternate Defense Commissioners are designated by the Commission. The Defense Commissioner directs the defense activities of the Commission and has the following duties and responsibilities:

(a) To keep the Commission informed as to significant developments in the field of emergency preparedness, defense mobilization, and any defense activities that involve formulation or revision of Commission policy in any area of responsibility of the Commission.

(b) To represent the Commission in national defense matters requiring conferences or communications with other governmental officers, departments, or agencies.

(c) To act as the Defense Coordinator in representations with other agencies with respect to planning for the continuity of the essential functions of the Commission under national emergency conditions, and to serve as the principal representative of the Commission to the Interagency Emergency Planning Committee of the Federal Preparedness Agency/General Services Administration.

(d) To serve as the principal representative of the Commission to the Interagency Civil Defense Committee of the Defense Civil Preparedness Agency of the Department of Defense.

(e) To serve as the principal point of contact for the Commission on all matters pertaining to the National Communications System.

(f) To take such measures as will assure continuity of the Commission's functions under any foreseeable circumstances with a minimum of interruption.

(g) In the event of enemy attack, or the imminent threat thereof, or other disaster resulting in the inability of the Commission to function at its offices in Washington, D.C., to assume all of the duties and responsibilities of the Commission and the Chairman, until relieved or augmented by other Commissioners or members of the staff, as set forth in §§0.186 and 0.383.

47 CFR Ch. I (10–1–97 Edition)

(h) To approve national emergency plans and develop preparedness programs covering: provision of service by common carriers; broadcasting facilities, and the safety and special radio services; radio frequency assignment; electromagnetic radiation; investigation and enforcement.

(i) To perform such other duties and assume such other responsibilities related to the Commission's defense activities as may be necessary for the continuity of functions and the protection of Commission personnel and property.

[29 FR 14664, Oct. 28, 1964, as amended at 41 FR 31209, July 27, 1976]

§0.182 Chief, Compliance and Information Bureau.

(a) Recommends national emergency plans and preparedness programs covering: Provision of service by common carriers, broadcasting facilities, and the safety and special radio services; radio frequency assignment; electromagnetic radiation; investigation and enforcement.

(b) Acts as Alternate Defense Coordinator in representations with other agencies with respect to planning for the continuity of the essential functions of the Commission under national emergency conditions.

(c) Serves as the alternate representative of the Commission to the Interagency Emergency Planning Committee of the Federal Preparedness Agency/General Services Administration; serves as the alternate representative of the Commission to the Interagency Civil Defense Committee of the Defense Civil Preparedness Agency of the Department of Defense.

(d) Provides administrative support for the National Advisory Committee (NAC).

(e) Keeps the Defense Commissioner informed as to significant developments in the field of emergency preparedness and related defense activities.

[41 FR 31209, July 27, 1976, as amended at 50 FR 27953, July 9, 1985; 59 FR 26971, May 25, 1994; 59 FR 67092, Dec. 28, 1994]

Federal Communications Commission

§ 0.201

§ 0.183 Emergency Communications Administration.

The Compliance and Information Bureau coordinates the National Security and Emergency Preparedness (NSEP) activities of the Federal Communications Commission including Continuity of Government Planning, the Emergency Alert System (EAS) and other functions as may be delegated during a national emergency or activation of the President's war emergency powers as specified in section 706 of the Communications Act; maintains liaison with FCC Bureaus/Offices, and other government agencies, the telecommunications industry and FCC licensees on NSEP matters; and, as requested, represents the Commission at NSEP meetings and conferences.

[59 FR 67092, Dec. 28, 1994]

§ 0.185 Responsibilities of the bureaus and staff offices.

The head of each of the bureaus and staff offices, in rendering assistance to the Chief, Compliance and Information Bureau in the performance of that person's duties with respect to defense activities will have the following duties and responsibilities:

(a) To keep the Chief, Compliance and Information Bureau informed of the investigation, progress, and completion of programs, plans, or activities with respect to defense in which they are engaged or have been requested to engage.

(b) To render assistance and advice to the Chief, Compliance and Information Bureau on matters which relate to the functions of their respective bureaus or staff offices.

(c) To render such assistance and advice to other agencies as may be consistent with the functions of their respective bureaus or staff offices and the Commission's policy with respect thereto.

(d) To perform such other duties related to the Commission's defense activities as may be assigned to them by the Commission.

[29 FR 14665, Oct. 28, 1964, as amended at 50 FR 27953, July 9, 1985; 59 FR 26971, May 25, 1994; 61 FR 8477, Mar. 5, 1996]

§ 0.186 Emergency Relocation Board.

(a) As specified in the Commission's Continuity of Government Plan and consistent with the exercise of the War Emergency Powers of the President as set forth in section 706 of the Communications Act of 1934, as amended, an Emergency Relocation Board will be convened at the Commission's Headquarters or other relocation site designated to serve as Primary FCC Staff to perform the functions of the Commission following the announcement of national level mobilization of the Federal government by the President or other designated authority; in the absence of such announcement, immediately following receipt of an attack warning signal; or in the absence of either announcement or attack warning, immediately following an actual attack.

(b) The Board shall comprise such Commissioners as may be present and able to act. In the absence of the Chairman, the Commissioner present with the longest seniority in office will serve as acting Chairman. If no Commissioner is present and able to act, the person designated as next most senior official in the Commission's Continuity of Government Plan will head the Board.

[53 FR 29055, Aug. 2, 1988]

Subpart B—Delegations of Authority

AUTHORITY: Sec. 5, 48 Stat. 1068, as amended; 47 U.S.C. 155.

EDITORIAL NOTE: Nomenclature changes to subpart B appear at 37 FR 19372, Sept. 20, 1972.

GENERAL

§ 0.201 General provisions.

(a) There are three basic categories of delegations made by the Commission pursuant to section 5(c) of the Communications Act of 1934, as amended:

(1) *Delegations to act in non-hearing matters and proceedings.* The great bulk of delegations in this category are made to bureau chiefs and other members of the Commission's staff. This category also includes delegations to individual commissioners and to

§0.203

boards or committees of commissioners.

(2) *Delegations to rule on interlocutory matters in hearing proceedings.* Delegations in this category are made to the Chief Administrative Law Judge.

NOTE TO PARAGRAPH (A)(2): Interlocutory matters which are not delegated to the Chief Administrative Law Judge are ruled on by the presiding officer by virtue of the authority vested in him to control the course and conduct of the hearing. This authority stems from section 7 of the Administrative Procedure Act and section 409 of the Communications Act rather than from delegations of authority made pursuant to section 5(c) of the Communications Act. (See §§0.218 and 0.341.).

(3) *Delegations to review an initial decision.* Delegations in this category are made to individual commissioners, to panels of commissioners.

(b) Delegations are arranged in this subpart under headings denoting the person, panel, or board to whom authority has been delegated, rather than by the categories listed in paragraph (a) of this section.

(c) Procedures pertaining to the filing and disposition of interlocutory pleadings in hearing proceedings are set forth in §§1.291 through 1.298 of this chapter. Procedures pertaining to appeals from rulings of the presiding officer are set forth in §1.301. Procedures pertaining to reconsideration of the presiding officer's rulings are set forth in §1.303. Procedures pertaining to reconsideration and review of actions taken pursuant to delegated authority are set forth in §§1.101, 1.102, 1.104, 1.106, 1.113, 1.115, and 1.117. Procedures pertaining to exceptions to initial decisions are set forth in §§1.276–1.279.

(d) The Commission, by vote of a majority of the members then holding office, may delegate its functions either by rule or by order, and may at any time amend, modify, or rescind any such rule or order.

(1) Functions of a continuing or recurring nature are delegated by rule. The rule is published in the FEDERAL REGISTER and is included in this subpart.

(2) Functions pertaining to a particular matter or proceeding are delegated by order. The order is published in the FEDERAL REGISTER and associated with the record of that matter or proceed-

47 CFR Ch. I (10–1–97 Edition)

ing, but neither the order nor any reference to the delegation made thereby is included in this subpart.

[28 FR 12402, Nov. 22, 1963, as amended at 50 FR 26567, June 27, 1985; 62 FR 4170, Jan. 29, 1997]

§0.203 Authority of person, panel, or board to which functions are delegated.

(a) The person, panel, or board to which functions are delegated shall, with respect to such functions, have all the jurisdiction, powers, and authority conferred by law upon the Commission, and shall be subject to the same duties and obligations.

(b) Except as provided in §1.102 of this chapter, any action taken pursuant to delegated authority shall have the same force and effect and shall be made, evidenced, and enforced in the same manner as actions of the Commission.

[28 FR 12402, Nov. 22, 1963]

§0.204 The exercise of delegated authority.

(a) *Authority to issue orders and to enter into correspondence.* Any official (or group of officials) to whom authority is delegated in this subpart is authorized to issue orders (including rulings, decisions, or other action documents) pursuant to such authority and to enter into general correspondence concerning any matter for which he is responsible under this subpart or subpart A of this part.

(b) *Authority of subordinate officials.* Authority delegated to any official to issue orders or to enter into correspondence under paragraph (a) of this section may be exercised by that official or by appropriate subordinate officials acting for him.

(c) *Signature.* (1) Other orders made by a committee, board or panel identify the body and are signed by the Secretary.

(2) Upon signing an order, the Secretary affixes the Commission's seal.

(3) General correspondence by a committee or board is signed by the committee or board chairman.

(4) All other orders and letters are signed by the official who has given final approval of their contents.

Federal Communications Commission

§0.218

(5) With the exception of license forms requiring the signature of an appropriate official of the issuing bureau or office, license forms bear only the seal of the Commission.

(d) *Form of orders.* Orders may be issued in any appropriate form (e.g., as captioned orders, letters, telegrams) and may, if appropriate, be issued orally. Orders issued orally shall, if practicable, be confirmed promptly in writing.

(e) *Minutes entries.* Except as otherwise provided in this subpart, actions taken as provided in paragraph (d) of this section shall be recorded in writing and filed in the official minutes of the Commission.

[33 FR 8227, June 1, 1968, as amended at 38 FR 18550, July 12, 1973; 62 FR 4170, Jan. 29, 1997]

COMMISSIONERS

§0.211 Chairman.

The responsibility for the general administration of internal affairs of the Commission is delegated to the Chairman of the Commission. The Chairman will keep the Commission advised concerning his actions taken under this delegation of authority. This authority includes:

(a) Actions of routine character as to which the Chairman may take final action.

(b) Actions of non-routine character which do not involve policy determinations. The Chairman may take final action on these matters but shall specifically advise the Commission on these actions.

(c) Actions of an important character or those which involve policy determinations. In these matters the Chairman will develop proposals for presentation to the Commission.

(d) To act within the purview of the Federal Tort Claims Act, as amended, 28 U.S.C. 2672, upon tort claims directed against the Commission where the amount of damages does not exceed \$5,000.

(e) Authority to act as "Head of the Agency" or "Agency Head" for administrative determinations required by

Federal Procurement Regulations and Federal Management Circulars.

[28 FR 12402, Nov. 22, 1963, as amended at 41 FR 49095, Nov. 8, 1976; 51 FR 23550, June 30, 1986]

§0.212 Board of Commissioners.

(a) Whenever the Chairman or Acting Chairman of the Commission determines that a quorum of the Commission is not present or able to act, he may convene a Board of Commissioners. The Board shall be composed of all Commissioners present and able to act.

(b) The Board of Commissioners is authorized to act upon all matters normally acted upon by the Commission en banc, except the following:

(1) The final determination on the merits of any adjudicatory or investigatory hearing proceeding or of any rule making proceeding, except upon a finding by the Board that the public interest would be disserved by waiting the convening of a quorum of the Commission.

(2) Petitions for reconsideration of Commission actions.

(3) Applications for review of actions taken pursuant to delegated authority.

(c) The Board of Commissioners is authorized to act upon all matters normally acted upon by an individual Commissioner (when he or his alternates are not present or able to act) or by a committee of Commissioners (in the absence of a quorum of the committee).

(d) Actions taken by the Board of Commissioners shall be recorded in the same manner as actions taken by the Commission en banc.

(e) This section has no application in circumstances in which the Commission is unable to function at its offices in Washington, D.C. See §§0.181–0.186 and §§0.381–0.387.

[30 FR 9314, July 27, 1965]

§0.218 Authority of, and delegated to, an individual Commissioner or Commissioners.

(a) One or more members of the Commission may be designated to preside in a hearing proceeding. The Commissioner or Commissioners designated to preside at such a hearing shall fix the time and place of the hearing and shall

§0.231

act upon all motions, petitions or other matters which may arise while the proceeding is in hearing status.

(b) One or more members of the Commission may be designated to review an initial decision issued in any hearing case.

(c) Except for actions taken during the course of a hearing and upon the record thereof, actions taken by a Commissioner or Commissioners pursuant to the provisions of this section shall be recorded in writing and filed in the official minutes of the Commission.

[27 FR 7931, Aug. 10, 1962]

MANAGING DIRECTOR

§0.231 Authority delegated.

(a) The Managing Director, or his designee, upon securing concurrence of the General Counsel, is delegated authority to act upon requests for waiver, reduction or deferment of fees, establish payment dates, and issue notices proposing amendments or adjustments to the fee schedules established under part 1, subpart G, of this chapter.

(b) The Managing Director, or his designee, is delegated authority to make nonsubstantive, editorial revisions of the Commission's rules and regulations upon approval of the bureau or staff office primarily responsible for the particular part or section involved.

(c) [Reserved]

(d) The Managing Director, or his designee, upon securing the concurrence of the General Counsel, is delegated authority, within the purview of the Federal Tort Claims Act, as amended, 28 U.S.C. 2672, to grant tort claims directed against the Commission where the amount of the claim does not exceed \$5,000. In addition thereto, the Managing Director, or his designee, upon securing the concurrence of the General Counsel, is delegated authority to act in the disposition of claims arising under the Military Personnel and Civilian Employees' Claims Act, as amended, 31 U.S.C. 3701 and 3721, where the amount of the claim does not exceed \$6,500.

(e) The Managing Director is delegated authority to act as Head of the Procurement Activity and Contracting Officer for the Commission and to des-

47 CFR Ch. I (10-1-97 Edition)

ignate appropriate subordinate officials to act as Contracting Officers for the Commission. As Head of the Procurement Activity, the Managing Director will refer all appeals filed against final decisions regarding award of contracts to the Board of Contract Appeals of the General Services Administration for resolution. Appeals will be handled in accordance with the Rules of the Board of Contract Appeals.

(f) [Reserved]

(g) The Managing Director, after consultation with the Chairman shall establish, renew, and terminate all Federal advisory committees. He shall also exercise all management responsibilities under the Federal Advisory Committee Act as amended (Pub. L. No. 92-463, 5 U.S.C. App.).

(h) [Reserved]

(i) The Secretary, acting under the supervision of the Managing Director, serves as the official custodian of the Commission's documents and shall have authority to appoint a deputy or deputies for purposes of custody and certification of documents located in Gettysburg, Pennsylvania or other established locations.

CROSS REFERENCE: 47 CFR part 19, subpart E.

(Secs. 4, 303, 48 Stat., as amended, 1066, 1082; 47 U.S.C. 154, 303; 18 U.S.C. 207(j); 39 U.S.C. 3220; Notice of Preliminary Guidelines issued by the Department of Justice, 50 FR 46622, November 8, 1985)

[29 FR 14666, Oct. 28, 1964]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting §0.231, see the List of CFR Sections Affected in the Finding Aids section of this volume.

CHIEF ENGINEER

§0.241 Authority delegated.

(a) The performance of functions and activities described in §0.31 of this part is delegated to the Chief Engineer: *Provided*, That the following matters shall be referred to the Commission en banc for disposition:

(1) Notices of proposed rulemaking and of inquiry and final orders in rulemaking proceedings, inquiry proceedings and non-editorial orders making changes. See §0.231(d).

Federal Communications Commission

§0.251

(2) Petitions for review of actions taken to delegated authority. See §1.115 of this chapter.

(3) Petitions and other requests for waivers of the Commission's rules, whether or not accompanied by an application, when such petitions or requests contain new or novel arguments not previously considered by the Commission or present facts or arguments which appear to justify a change in Commission policy.

(4) Petitions and other requests for declaratory rulings, when such petitions or requests contain new or novel arguments not previously considered by the Commission or present facts or arguments which appear to justify a change in Commission policy.

(5) Any other petition, pleading or request presenting new or novel questions of fact, law, or policy which cannot be resolved under outstanding precedents and guidelines.

(6) Any other complaint or enforcement matter presenting new or novel questions of fact, law, or policy which cannot be resolved under outstanding precedents and guidelines.

(7) Authority to issued a notice of opportunity for hearing pursuant to §1.80(g) of this chapter; and authority to issue notices of apparent liability, final forfeiture orders, and orders cancelling or reducing forfeitures imposed under §1.80(f) of this chapter, if the amount set out in the notice of apparent liability is more than \$20,000.

(8) Proposed actions following any case remanded by the courts.

(b) The Chief Engineer is delegated authority to administer the Equipment Authorization program as described in part 2 of the Commission's Rules.

(c) The Chief Engineer is delegated authority to administer the Experimental Radio Service program pursuant to part 5 of the Commission's Rules.

(d) The Chief engineer is delegated authority to examine all applications for certification (approval) of subscription television technical systems as acceptable for use under a subscription television authorization as provided for in this chapter, to notify the applicant that an examination of the certified technical information and data submitted in accordance with the provisions

of this chapter indicates that the system does or does not appear to be acceptable for authorization as a subscription television system. This delegation shall be exercised in consultation with the Chief, Mass Media Bureau.

(e) The Chief Engineer is authorized to dismiss or deny petitions for rule-making which are repetitive or moot or which, for other reasons plainly do not warrant consideration by the Commission.

(f) The Chief of the Office of Engineering and Technology is authorized to enter into agreements with the National Institute of Standards and Technology and other accreditation bodies to perform accreditation of test laboratories pursuant to §2.948(d) of this chapter. In addition, the Chief is authorized to make determinations regarding the continued acceptability of individual accrediting organizations and accredited laboratories.

[51 FR 41106, Nov. 13, 1986, as amended at 57 FR 18088, Apr. 29, 1992; 60 FR 5324, Jan. 27, 1995; 60 FR 32119, June 20, 1995; 61 FR 4918, Feb. 9, 1996; 61 FR 31045, June 19, 1996; 62 FR 48952, Sept. 18, 1997]

§0.247 Record of actions taken.

The application and authorization files and other appropriate files of the Office of Engineering and Technology are designated as the official minute entries of actions taken pursuant to §§0.241 and 0.243.

[33 FR 8228, June 1, 1968, as amended at 44 FR 39179, July 5, 1979; 51 FR 12615, Apr. 14, 1986]

GENERAL COUNSEL

§0.251 Authority delegated.

(a) The General Counsel is delegated authority to act as the "designated agency ethics official."

(b) Insofar as authority is not delegated to any other Bureau or Office, and with respect only to matters which are not in hearing status, the General Counsel is delegated authority:

(1) To act upon requests for extension of time within which briefs, comments or pleadings may be filed.

(2) To dismiss, as repetitious, any petition for reconsideration of a Commission order which disposed of a petition for reconsideration and which did not

§0.261

reverse, change, or modify the original order.

(3) To dismiss or deny petitions for rulemaking which are repetitive or moot or which, for other reasons, plainly do not warrant consideration by the Commission.

(4) To dismiss as repetitious any petition for reconsideration of a Commission order denying an application for review which fails to rely on new facts or changed circumstances.

(c) The General Counsel is delegated authority in adjudicatory hearing proceedings which are pending before the Commission en banc to act on all requests for relief, and to issue all appropriate orders, except those which involve final disposition on the merits of a previously specified issue concerning an applicant's basic qualifications or two or more applicants' comparative qualifications.

(d) When an adjudicatory proceeding is before the Commission for the issuance of a final order or decision, the General Counsel will make every effort to submit a draft order or decision for Commission consideration within four months of the filing of the last responsive pleading. If the Commission is unable to adopt an order or decision in such cases within five months of the last responsive pleading, it shall issue an order indicating that additional time will be required to resolve the case.

(e) The official record of all actions taken by the General Counsel pursuant to §0.251 (c) and (d) is contained in the original docket folder, which is maintained by the Secretary in the Dockets Branch.

(f) The General Counsel is delegated authority to issue written determinations on behalf of the Chairman, and otherwise act as the Chairman's designee on matters regarding the interception of telephone conversations, as required by the General Services Administration's regulations. 41 CFR 201-6.202 *et seq.*

(g) The General Counsel is delegated authority to act upon any application for a determination of exempt telecommunications company status filed pursuant to section 34(a)(1) of the Public Utility Holding Company Act of

47 CFR Ch. I (10-1-97 Edition)

1935, as amended by section 103 of the Telecommunications Act of 1996.

(h) The General Counsel is delegated authority to issue rulings on whether violations of the *ex parte* rules have occurred.

(i) The General Counsel is delegated authority to make determinations regarding and waive the applicability of section 4(b) of the Communications Act (47 U.S.C. §154(b)) and the Federal conflict of interest statutes (18 U.S.C. §§203, 205 and 208).

(Secs. 2, 3, 4, 5, 301, 303, 307, 308, 309, 315, 317, 48 Stat., as amended, 1064, 1065, 1066, 1068, 1081, 1082, 1083, 1084, 1085, 1088, 1089; 47 U.S.C. 152, 153, 154, 155, 301, 303, 307, 308, 309, 315, 317)

[28 FR 12402, Nov. 22, 1963, as amended at 31 FR 3074, Feb. 24, 1966; 31 FR 4456, Mar. 16, 1966; 31 FR 11756, Sept. 8, 1966; 31 FR 13474, Oct. 19, 1966; 44 FR 60294, Oct. 19, 1979; 46 FR 57050, Nov. 20, 1981; 47 FR 16032, Apr. 14, 1982; 48 FR 57133, Dec. 28, 1983; 49 FR 47604, Dec. 6, 1984; 50 FR 85, Jan. 2, 1985; 50 FR 49048, Nov. 29, 1985; 56 FR 792, Jan. 9, 1991; 57 FR 19387, May 6, 1992; 59 FR 39703, Aug. 4, 1994; 60 FR 34902, July 5, 1995; 61 FR 26464, May 28, 1996; 61 FR 29311, June 10, 1996; 62 FR 15853, Apr. 3, 1997; 62 FR 24055, May 2, 1997; 62 FR 51052, Sept. 30, 1997]

INTERNATIONAL BUREAU

SOURCE: Sections 0.261 and 0.262 appear at 60 FR 5324, Jan. 27, 1995, unless otherwise noted.

§0.261 Authority delegated.

(a) Subject to the limitations set forth in paragraph (b) of this section, the Chief, International Bureau, is hereby delegated the authority to perform the functions and activities described in §0.51, including without limitation the following:

(1) To recommend rulemakings, studies, and analyses (legal, engineering, social, and economic) of various petitions for policy or rule changes submitted by industry or the public, and to assist the Commission in conducting the same;

(2) To assume the principal representational role on behalf of the Commission in international conferences, meetings, and negotiations, and direct Commission preparation for such conferences, meetings, and negotiations with other bureaus and offices, as appropriate;

Federal Communications Commission

§ 0.261

(3) To act upon applications for international telecommunications facilities and services pursuant to part 23 of this chapter and relevant portions of part 63 of this chapter, and coordinate with the Common Carrier Bureau as appropriate;

(4) To act upon applications for international and domestic satellite systems and earth stations pursuant to part 25 and part 100 of this chapter;

(5) To act upon applications for cable landing licenses pursuant to § 1.767 of this chapter;

(6) To act upon requests for designation of Recognized Private Operating Agency (RPOA) status under part 63 of this chapter;

(7) To act upon applications relating to international broadcast station operations, or for permission to deliver programming to foreign stations, under part 73 of this chapter;

(8) To administer and enforce the policies and rules on international settlements under part 64 of this chapter;

(9) To administer portions of part 2 of this chapter dealing with international treaties and call sign provisions, and to make call sign assignments, individually and in blocks, to U.S. Government agencies and FCC operating bureaus;

(10) To act upon applications for closure of public coast stations in the maritime service under part 63 of this chapter and to coordinate its efforts with the Wireless Telecommunications Bureau.

(11) To administer Commission participation in the International Telecommunication Union (ITU) Fellowship telecommunication training program for foreign officials offered through the U.S. Telecommunications Training Institute;

(12) In consultation with the affected Bureaus and Offices, to recommend revision of Commission rules and procedures as appropriate to conform to the outcomes of international conferences, agreements, or treaties;

(13) To notify the ITU of the United States' terrestrial and satellite assignments for inclusion in the Master International Frequency Register;

(14) To conduct studies and compile such data relating to international telecommunications as may be nec-

essary for the Commission to develop and maintain an adequate regulatory program; and

(15) To interpret and enforce rules and regulations pertaining to matters under its jurisdiction.

(b) Notwithstanding the authority delegated in paragraph (a) of this section, the Chief, International Bureau, shall not have authority:

(1) To act on any application, petition, pleading, complaint, enforcement matter, or other request that:

(i) Presents new or novel arguments not previously considered by the Commission;

(ii) Presents facts or arguments which appear to justify a change in Commission policy; or

(iii) Cannot be resolved under outstanding precedents and guidelines after consultation with appropriate Bureaus or Offices.

(2) To issue notices of proposed rulemaking, notices of inquiry, or reports or orders arising from rulemaking or inquiry proceedings;

(3) To act upon any application for review of actions taken by the Chief, International Bureau, pursuant to delegated authority, which application complies with § 1.115 of this chapter;

(4) To act upon any formal or informal radio application or section 214 application for common carrier services which is in hearing status;

(5) To designate for hearing any applications except:

(i) Mutually exclusive applications for radio facilities filed pursuant to parts 23, 25, 73, or 100 of this chapter; and

(ii) Applications for facilities where the issues presented relate solely to whether the applicant has complied with outstanding precedents and guidelines; or

(6) To impose, reduce, or cancel forfeitures pursuant to section 203 or section 503(b) of the Communications Act of 1934, as amended, in amounts of more than \$80,000 for common carrier providers and \$20,000 for non-common carrier providers.

[60 FR 5324, Jan. 27, 1995, as amended at 60 FR 35506, July 10, 1995]

§0.262

47 CFR Ch. I (10–1–97 Edition)

§0.262 Record of actions taken.

The application and authorization files in the appropriate central files of the International Bureau are designated as the Commission's official records of actions by the Chief, International Bureau, pursuant to authority delegated to him.

OFFICE OF PLANS AND POLICY

§0.271 Authority delegated.

(a) Insofar as authority is not delegated to any other Bureau or Office, and with respect only to matters which are not in hearing status, the Chief, Office of Plans and Policy is delegated authority to deny requests or to extend the time within which comments may be filed in dockets over which the Office of Plans and Policy has primary authority.

(b) [Reserved]

[45 FR 10347, Feb. 15, 1980]

CHIEF, MASS MEDIA BUREAU

§0.283 Authority delegated.

The performance of functions and activities described in §0.61 of this part is delegated to the Chief, Mass Media Bureau: Provided, That the following matters shall be referred by the Chief, Mass Media Bureau to the Commission en banc for disposition:

(a) *Applications.* Formal and informal applications for new or modified facilities, and for the renewal, assignment, and transfer of construction permits and licenses involving such facilities, when such applications fail to satisfy the requirements of Commission rules or established Commission policy in the following areas of special concern:

(1) *Multiple ownership, concentration of control, and cross-interests.* (i) Acquisition of a third broadcast station or modification of facilities if such would result in the common ownership of three broadcast stations where any two are within 100 miles of a third and primary service contour overlap would occur; "one-to-a-market" situations involving UHF stations or TV satellite stations; and duopoly situations involving TV satellite stations. (Commonly owned AM and FM stations in the same market are treated as one

station for the purpose of the "third station" limitations.)

(ii) Acquisition of a broadcast station by a newspaper in the same area, or other organization having substantial interests in the print media in the same area.

(iii) Creation of common ownership interests, management ties, or employment relationships between licensees serving substantial common areas and populations. Commonality of areas and populations served shall be determined in duopoly situations by overlap of the following service contours: AM—1 mVm; FM—1 mVm; and TV—Grade B. In "one-to-a-market" situations, commonality of areas and populations served shall be determined by community encompassment with the following service contours: AM—2 mVm; FM—1 mVm; and TV—Grade A.

(iv) Acquisition of broadcast properties by corporations or individuals appearing to dominate the economic life of the community.

(2) *Anti-trust activity, unfair trade practices, and violations of law not previously considered by the Commission.* (i) Proposals by applicants against whom communications-related anti-trust suits are pending or against whom there is pending any anti-trust suit in which an adverse verdict has been reached.

(ii) Proposals by applicants who have entered into a consent decree, have pleaded guilty or nolo contendere, or have been adjudged guilty in an anti-trust case during the three-year period preceding the filing of the application.

(iii) Proposals by applicants who have been the subject of a final cease and desist or consent order issued by the Federal Trade Commission during the three-year period preceding the filing of the application.

(iv) Proposals by applicants or including parties with felony or capital offense conviction records, or against whom a criminal proceeding is pending.

(3) *Violations and complaint matters.* Proposals filed by applicants against whom violation notices of a serious nature are outstanding or against whom

Federal Communications Commission

§0.283

questions suggesting serious misconduct remain unresolved, or by applicants with records of serious past misconduct.

(4) *Equal employment opportunities.* Proposals filed by applicants whose equal employment opportunities programs do not comply with Commission rules or policies and cannot be cleared by further staff inquiry or action, or whose past performance suggests the existence of discriminatory practices.

(5) *Short term licenses and renewals.* Proposals which in the opinion of the Chief, Mass Media Bureau, warrant the issuance of a short-term license or renewal authorization.

(6) [Reserved]

(7) *Programming: Program content and ascertainment of community needs.* (i) Applications for new stations or assignments and transfers.

(A) Commercial AM and FM proposals and commercial TV proposals of applicants for new stations and of assignees and transfers that have not submitted a narrative statement of their proposed programming.

(8) [Reserved]

(9) *Hearing orders.* (i) Mutually exclusive applications not in the Instructional Television Fixed Service, including renewal and construction permit applications, involving non-routine hearing issues.

(ii) Other renewal and assignment and transfer applications which appear to call for an evidentiary hearing.

(iii) Such other applications, as in the opinion of the Chief, Mass Media Bureau, warrant referral to the Commission prior to designation for hearing.

(10) *Interference and mileage separations.* Proposals for new or modified AM, FM, and TV facilities which would create substantial new prohibited overlap or station separation shortages. In the case of AM proposals (other than Class IV), a net increase in objectionable interference to another AM station involving more than 1 percent of the population served by such other station, whether or not consented to by the station affected, shall be referred to the Commission.

(11) *VHF television expansion.* Commercial VHF television proposals seeking to bring or extend their Grade B

contours into a significant area or population included within the predicted Grade B contour of a UHF television station where the area or population involved is covered by fewer than 4 VHF television signals.

(12) *Agreements to amend or dismiss applications.* Any situation in which a community will be deprived of a proposed broadcast station by reason of amendment or dismissal of an application mutually exclusive with another application for a different community.

(13) *Experimental and developmental operation.* Proposals for experimental and developmental authority containing policy implications which, in the opinion of the Chief, Mass Media Bureau, warrant referral to the Commission.

(14) *Miscellaneous applications and requests.* (i) Proposals for special temporary, emergency, conditional, or interim operating authority of more than routine significance.

(ii) Any other application, proposals, or request presenting novel questions of fact, law, or policy which cannot be resolved under outstanding precedents and guidelines.

(b) *Petitions and other requests for Commission action.* (1) Petitions to deny, informal objections, and other petitions, directed against AM, FM, and TV applications for new or modified facilities, or for renewal, assignment or transfer of control, will be referred to the Commission if they: (i) Contain new or novel issues not previously considered by the Commission, (ii) appear to justify a change in Commission policy; or (iii) present documented allegations of failure to comply with the Commission's Equal Employment Opportunity rules and policies, or the applicant in question falls outside the applicable processing criteria in its employment of women and minorities.

(2) Petitions and other requests for reconsideration of actions taken by the Chief, Mass Media Bureau, when such petitions or requests contain new or novel arguments not previously considered by the Commission, present facts or arguments which appear to justify a change in Commission policy, or request reconsideration of orders designating cases for hearing.

§0.284

47 CFR Ch. I (10–1–97 Edition)

(3) Applications for review of actions taken by the Chief, Mass Media Bureau, which comply with §1.115 of this chapter.

(4) Petitions and other requests for waiver of Commission rules, whether or not accompanied by an application, when such petitions or requests contain new or novel arguments not previously considered by the Commission, or present facts or arguments which appear to justify a change in Commission policy.

(5) Petitions and other requests for declaratory rulings, when such petitions or requests contain new or novel arguments not previously considered by the Commission, or present facts or arguments which appear to justify a change in Commission policy.

(6) Petitions for rulemaking which have been accepted under §1.403, and final dispositions of rulemaking proceedings not involving routine changes in the FM and TV Tables of Assignments.

(7) Petitions and other requests for waiver of the prime-time access rule, in areas where Commission policy is not clearly established.

(8) Petitions and other requests for long-term waiver of the policy limiting affiliations by commonly owned networks in the same market.

(9) Petitions and other requests for waiver of the sponsorship identification provisions of the Communications Act, in accordance with section 317(d) thereof.

(10) Any other petition, pleading, or request presenting novel questions of fact, law, or policy which cannot be resolved under outstanding precedents and guidelines.

(c) *Administration and enforcement.* (1) Proposed orders to show cause why station licenses or construction permits should not be revoked.

(2) Proposed actions following any case remanded by the courts.

(3) Notices of opportunity for hearing pursuant to §1.80(g) of this chapter, and notices of apparent liability, final forfeiture orders, and orders cancelling or reducing forfeitures imposed under §1.80(f) of this chapter if the amount set out in the notice of apparent liability is more than \$20,000, except that all forfeiture matters relating to the Com-

mission's equal employment opportunity rules shall be referred to the Commission.

(4) Proposed public notices expressing Commission policy, interpreting the provisions of law, regulations, or treaties, or warning the broadcast industry as to certain types of violations.

(5) Problems involving apparent violation of the Commission's rules governing equal employment opportunities or otherwise indicating the existence of discriminatory practices which, in the opinion of the Chief, Mass Media Bureau, or the Equal Employment Opportunity Commission should be brought to the attention of FCC Commissioners.

(6) Any other complaint or enforcement matter presenting novel questions of fact, law, or policy which cannot be resolved under outstanding precedents and guidelines.

[47 FR 47829, Oct. 28, 1982, as amended at 47 FR 55929, Dec. 14, 1982; 47 FR 58269, Dec. 30, 1982; 48 FR 24386, June 1, 1983; 49 FR 33603, Aug. 23, 1984; 57 FR 18088, Apr. 29, 1992; 61 FR 10689, Mar. 15, 1996]

§0.284 Actions taken under delegated authority.

(a) In discharging the authority conferred by §0.283 of this part, the Chief, Mass Media Bureau, shall establish working relationships with other bureaus and staff offices to assure the effective coordination of actions taken in the following areas of joint responsibility;

(1) Complaints arising under sections 315 and 605 of the Communications Act—Office of General Counsel.

(2) Objections to proposed call signs and requests for waiver of procedural rules governing call sign assignments—Office of Managing Director.

(3) Requests for waiver of tower painting and lighting specifications—Wireless Telecommunications Bureau.

(4) Matters involving emergency communications, including the issuance of Emergency Alert System Authorizations (FCC Form 392) Compliance and Information Bureau.

(5) Requests for use of frequencies or bands of frequencies shared with private sector nonbroadcast or government services—Office of Engineering

Federal Communications Commission

§0.291

and Technology and appropriate operating bureau.

(6) Requests involving coordination with other agencies of government—Office of General Counsel, Office of Engineering and Technology and appropriate operating bureau.

(7) Proposals involving transmitter sites on public lands owned or controlled by the Departments of Agriculture or Interior—Office of Engineering and Technology.

(8) Proposals involving possible harmful impact on radio astronomy or radio research installations—Office of Engineering and Technology.

(9) [Reserved]

(b) With respect to non-routine applications granted under authority delegated in §0.283 of this part, the Chief, Mass Media Bureau or his designees, shall enter on the working papers associated with each application a narrative justification of the action taken. While not available for public inspection, these working papers shall, upon request, be made available to the Commissioners and members of their staffs.

(c) The Chief, Mass Media Bureau, shall prepare and submit to the Commission a quarterly statistical summary of actions taken during the preceding quarter under authority delegated to him in §0.283 of this part. The statistical summary shall be accompanied by a statement of industry trends apparent in the staff handling of non-routine matters during the same quarter.

[47 FR 47829, Oct. 28, 1982; 47 FR 56852, Dec. 21, 1982, as amended at 51 FR 12615, Apr. 14, 1986; 52 FR 5288, Feb. 20, 1987; 53 FR 29055, Aug. 2, 1988; 59 FR 26971, May 25, 1994; 59 FR 32132, June 22, 1994; 59 FR 67092, Dec. 28, 1994; 61 FR 8477, Mar. 5, 1996]

§0.285 Record of actions taken.

The history card, the station file, and other appropriate files are designated to be the official record of the action taken by the Chief of the Mass Media Bureau.

[47 FR 47829, Oct. 28, 1982]

CHIEF, COMMON CARRIER BUREAU

§0.291 Authority delegated.

The Chief, Common Carrier Bureau, is hereby delegated authority to per-

form all functions of the Bureau, described in §0.91, subject to the following exceptions and limitations.

(a) *Authority concerning applications.*

(1) The Chief, Common Carrier Bureau shall not have authority to act on any formal or informal common carrier applications or section 214 applications for common carrier services which are in hearing status.

(2) The Chief, Common Carrier Bureau shall not have authority to act on any applications or requests which present novel questions of fact, law or policy which cannot be resolved under outstanding precedents and guidelines.

(b) *Authority concerning section 220 of the Act.* The Chief, Common Carrier Bureau shall not have authority to promulgate regulations or orders prescribing permanent depreciation rates for common carriers, or to prescribe interim depreciation rates to be effective more than one year, pursuant to section 220 of the Communications Act of 1934, as amended.

(c) *Authority concerning section 221(a) of the Act.* (1) The Chief, Common Carrier Bureau shall not have authority to determine whether hearings shall be held on applications filed under section 221(a) of the Communications Act of 1934, as amended, where a request has been made by a telephone company, an association of telephone companies, a State Commission or local government authority.

(2) The Chief, Common Carrier Bureau shall not have authority to act upon applications filed under section 221(a) of the Communications Act of 1934, as amended, where the proposed expenditure for consolidation, acquisition or control is in excess of \$10 million.

(3) The Chief, Common Carrier Bureau shall not have authority to act upon any application, petition or request under section 221(a) of the Communications Act of 1934, as amended, which presents novel questions of fact, law or policy which cannot be resolved under outstanding precedents and guidelines.

(d) *Authority to designate for hearing.* The Chief, Common Carrier Bureau, shall not have authority to designate for hearing any formal complaints which present novel questions of fact,

§0.301

law, or policy which cannot be resolved under outstanding precedents or guidelines. The Chief, Common Carrier Bureau, shall not have authority to designate for hearing any applications except applications for facilities where the issues presented relate solely to whether the applicant has complied with outstanding precedents and guidelines.

(e) *Authority concerning forfeitures.* The Chief, Common Carrier Bureau shall not have authority to impose, reduce or cancel forfeitures pursuant to Section 203 or Section 503(b) of the Communications Act of 1934, as amended, in amounts of more than \$80,000.

(f) *Authority concerning applications for review.* The Chief, Common Carrier Bureau shall not have authority to act upon any applications for review of actions taken by the Chief, Common Carrier Bureau, pursuant to any delegated authority.

(g) *Authority concerning rulemaking and investigatory proceedings.* The Chief, Common Carrier Bureau, shall not have authority to issue notices of proposed rulemaking, notices of inquiry, or reports or orders arising from either of the foregoing, except that the Chief, Common Carrier Bureau, shall have authority, in consultation and coordination with the Chief, International Bureau, to issue and revise a manual on the details of the reporting requirements for international carriers set forth in §43.61(d) of this chapter.

(h) *Authority concerning the issuance of subpoenas.* The Chief of the Common Carrier Bureau or her/his designee is authorized to issue non-hearing related subpoenas for the attendance and testimony of witnesses and the production of books, papers, correspondence, memoranda, schedules of charges, contracts, agreements, and any other records deemed relevant to the investigation of matters within the jurisdiction of the Common Carrier Bureau. Before issuing a subpoena, the Bureau shall obtain the approval of the Office of General Counsel.

(Secs. 4, 5, 303, 48 Stat. 1066, 1068, 1082, as amended; 47 U.S.C. 154, 155, 303; secs. 2, 3, 4, 5, 301, 303, 307, 308, 309, 315, 317, 48 Stat., as amended, 1064, 1065, 1066, 1068, 1081, 1082, 1083,

47 CFR Ch. I (10–1–97 Edition)

1084, 1085, 1089; 47 U.S.C. 152, 153, 154, 155, 303, 307, 308, 309, 315, 317)

[44 FR 18501, Mar. 28, 1979; 44 FR 22078, Apr. 13, 1979, as amended at 45 FR 22945, Apr. 4, 1980; 45 FR 25399, Apr. 15, 1980; 45 FR 31723, May 14, 1980; 48 FR 23431, May 25, 1983; 49 FR 6908, Feb. 24, 1984; 50 FR 18489, May 1, 1985; 51 FR 13230, Apr. 18, 1986; 52 FR 35918, Sept. 24, 1987; 55 FR 30461, July 26, 1990; 57 FR 8579, Mar. 11, 1992; 57 FR 22181, May 27, 1992; 59 FR 66487, Dec. 27, 1994; 60 FR 5324, Jan. 27, 1995; 60 FR 35506, July 10, 1995; 61 FR 16230, Apr. 12, 1996]

§0.301 [Reserved]

§0.302 Record of actions taken.

The application and authorization files in the appropriate central files of the Common Carrier Bureau are designated as the Commission's official records of actions by the Chief, Common Carrier Bureau pursuant to authority delegated to the Chief.

[60 FR 35506, July 10, 1995]

§0.303 Authority concerning registration of telephone terminal equipment.

Authority is delegated to the Chief of the Common Carrier Bureau jointly in cooperation with the Chief Engineer to act upon applications for registration of equipment to be directly connected to the telephone network; *Provided, however,* That the Chief, Common Carrier Bureau shall exercise overall policy direction of the program, with appropriate consultation with the Chief Engineer (For record of actions taken under this section, see §0.247).

(Secs. 4, 5, 303, 48 Stat. 1066, 1068, 1082, as amended; 47 U.S.C. 154, 155, 303)

[41 FR 7750, Feb. 20, 1976. Redesignated at 44 FR 18501, Mar. 28, 1979, and amended at 44 FR 39180, July 5, 1979; 51 FR 12615, Apr. 14, 1986]

COMPLIANCE AND INFORMATION BUREAU

§0.311 Authority delegated.

The performance of functions and activities described in §0.111 is delegated to the Chief, Compliance and Information Bureau, provided that:

(a) The following matters shall be referred by the Chief, Compliance and Information Bureau to the Commission en banc for disposition:

Federal Communications Commission

§0.311

(1) Notices of proposed rulemaking and of inquiry and final orders in rulemaking and inquiry proceedings.

(2) Applications for review of actions taken pursuant to delegated authority. (See §1.115 of this chapter).

(3) Petitions and other requests for waiver of Commission rules, whether or not accompanied by an application, when such petitions or requests contain new or novel arguments not previously considered by the Commission, or present facts or arguments which appear to justify a change in Commission policy.

(4) Petitions and other requests for declaratory rulings, when such petitions or requests contain new or novel arguments not previously considered by the Commission, or present facts or arguments which appear to justify a change in Commission policy.

(5) Any other petition, pleading, or request presenting new or novel questions of fact, law, or policy, which cannot be resolved under outstanding precedents and guidelines after consultation with appropriate Bureaus or offices.

(6) Any other complaint or enforcement matter presenting new or novel questions of fact, law, or policy which cannot be resolved under outstanding precedents and guidelines after consultation with appropriate Bureaus or offices.

(b) The Chief and the Deputy Chief of the Compliance and Information Bureau are authorized to declare that a state of general communications emergency exists and to act on behalf of the Commission pursuant to the provision of §97.107 of this chapter with respect to the operation of amateur stations during a state of general communications emergency.

(c) Rulings and orders concerning radio operator matters in a hearing status shall not be made by the Chief, Compliance and Information Bureau.

(d)(1) The Chief of the Compliance and Information Bureau is authorized to issue notices of apparent liability, final forfeiture orders, and orders cancelling or reducing forfeitures, pursuant to §1.80 of this chapter, if the amount set out in the notice of apparent liability is \$20,000 or less. The Chief of the Compliance and Information Bu-

reau is authorized to further delegate this authority.

(2) The Chief of the Compliance and Information Bureau is authorized to issue citations pursuant to §1.80(d) of this chapter and to further delegate this authority.

(e) The Chief of the Compliance and Information Bureau is authorized to make determinations and notifications of the presence of harmful interference to radio communications involving safety of life or protection of property which requires temporary suspension of operation under §74.23 of this chapter. Upon invoking the authority granted pursuant to this section, the Chief of the Compliance and Information Bureau shall immediately inform the Chairman of the Commission.

(f) The Chief, Compliance and Information Bureau, is authorized to issue non-hearing related subpoenas for the production of books, papers, correspondence, memoranda, and other records relating to investigations under the authority of the Communications Act of 1934, as amended. Before issuing a subpoena, the bureau shall obtain the approval of the Office of General Counsel.

(g) The Chief, Compliance and Information Bureau is delegated authority to grant waivers of the requirements of part 11 of this chapter to participants required to install, operate or test Emergency Alert System (EAS) equipment. The Chief, Compliance and Information Bureau is further authorized to delegate this authority. Waiver requests must be made in writing and forwarded to the FCC's EAS office 1919 M Street NW., Washington, DC 20554. Such requests must state the reason why the waiver is necessary and provide sufficient information such as, statements of fact regarding the financial status of the broadcast station, the number of other broadcast stations providing coverage in its service area or the likelihood of hazardous risks to justify a grant of the waiver.

(h) The Chief, Compliance and Information Bureau is delegated authority to execute in the name of the Commission all agreements pertaining to the loan of United States Government property to broadcast stations or other

entities participating in the Emergency Alert System (EAS) for national defense purposes. The Chief, Compliance and Information Bureau is authorized to delegate this authority.

(i) The Chief of the Compliance and Information Bureau is authorized to rely on reports, documents or log entries made by the holder of an FCC General Radiotelephone Operator License, GMDSS Radio Maintainer's License, Second Class Radiotelegraph Operator's Certificate, or First Class Radiotelegraph Operator's Certificate as certification that the vessel complies with requirements of Articles XI, XII, and XIII of the Great Lakes Agreement. The Chief, Compliance and Information Bureau is authorized to delegate this authority.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[40 FR 17254, Apr. 18, 1975, as amended at 47 FR 1395, Jan. 13, 1982; 48 FR 37414, Aug. 18, 1983; 50 FR 37189, Sept. 12, 1985; 57 FR 18088, Apr. 29, 1992; 58 FR 13020, Mar. 9, 1993; 58 FR 68053, Dec. 23, 1993; 59 FR 26971, May 25, 1994; 59 FR 67092, Dec. 28, 1994; 60 FR 31256, June 14, 1995; 60 FR 35506, July 10, 1995; 60 FR 55998, Nov. 6, 1995; 60 FR 61662, Dec. 1, 1995; 61 FR 8477, Mar. 5, 1996; 61 FR 25805, May 23, 1996]

§0.314 Additional authority delegated.

The Engineer in Charge at each installation is delegated authority to act upon applications, requests, or other matters, which are not in hearing status, and direct the following activities necessary to conduct investigations or inspections:

(a)–(b) [Reserved]

(c) On informal requests from broadcast stations to extend temporary authority for operation without monitors, plate ammeter, plate voltmeter, base current meter, common point meter, and transmission line meter from FM and television stations.

(d) [Reserved]

(e)(1) For periodic survey as required by section 385 of the Communications Act of 1934, as amended, and issuance of Communications Act radiotelephony certificates in accordance with §80.903 of this chapter.

(2) Extend the Communications Act Safety Radiotelephony Certificate for a period of up to 90 days beyond the specified expiration date.

(3) Grant emergency exemption requests, extensions or waivers of inspection to ships in accordance with applicable provisions of the Communications Act, the Safety Convention, the Great Lakes Agreement or the Commission's rules.

(f) [Reserved]

(g) To act on and make determinations on behalf of the Commission regarding requests for assignments and reassignments of priorities under the Telecommunications Service Priority System, Part 64 of the rules, when circumstances require immediate action and the common carrier seeking to provide service states that it cannot contact the National Communications System or the Commission office normally responsible for such assignments.

(h) Require special equipment and program tests during inspections or investigations to determine compliance with technical requirements specified by the Commission.

(i) Require stations to operate with pre-sunrise and nighttime facilities during daytime hours in order that an inspection or investigation may be made by an authorized Commission representative to determine operating parameters.

(j) For ship radio inspection and certification of the ship radio license, pursuant to the requirements of section 362(b) of the Communications Act of 1934, as amended.

(k) Issue a Safety Radiotelegraphy Certificate or a Safety Radiotelephony Certificate in accordance with the terms of Regulations 12 and 13, Chapter I, of the Safety Convention.

(l) For inspection or periodical survey as required by Article XII of the Great Lakes Agreement and certification prescribed by Article XIII thereof. The District Director may require that the inspection be conducted by an FCC-licensed technician holding an FCC General Radiotelephone Operator License, GMDSS Radio Maintainer's License, Second Class Radiotelegraph Operator's Certificate, or First Class Radiotelegraph Operator's Certificate.

(m) Issuances of notices and orders to operators of industrial, scientific, and medical (ISM) equipment, as provided in §18.115 of this chapter.

Federal Communications Commission

§0.331

(n) Requests for permission to resume operation of ISM equipment on a temporary basis, as provided by §18.115 of this chapter, and requests for extensions of time within which to file final reports, as provided by §18.117 of this chapter.

(o)–(w) [Reserved]

(x) When deemed necessary by the Engineer-in-Charge of a Commission field facility to assure compliance with the Rules, a station licensee shall maintain a record of such operating and maintenance records as may be necessary to resolve conditions of interference or deficient technical operation.

(Secs. 4, 5, 303, 307, 308, 309, 48 Stat., as amended, 1066, 1068, 1082, 1083, 1084, 1085; 47 U.S.C. 154, 303, 307, 308, 309)

[28 FR 12402, Nov. 22, 1963, as amended at 36 FR 8871, May 14, 1971; 40 FR 17254, Apr. 18, 1975; 42 FR 3167, Jan. 17, 1977; 43 FR 25122, June 9, 1978; 46 FR 35460, July 8, 1981; 48 FR 23432, May 25, 1983; 48 FR 26607, June 9, 1983; 48 FR 37414, Aug. 18, 1983; 50 FR 36067, Sept. 5, 1985; 51 FR 20290, June 4, 1986; 51 FR 31304, Sept. 2, 1986; 53 FR 29055, Aug. 2, 1988; 53 FR 47536, Nov. 23, 1988; 58 FR 13020, Mar. 9, 1993; 61 FR 25805, May 23, 1996]

§0.317 Record of action taken.

The application, authorization, and other appropriate central files of the Compliance and Information Bureau are designated as the Commission's official records of action taken pursuant to authority delegated under §§0.311 and 0.314, and shall constitute the official Commission minutes entry of such actions.

[40 FR 17254, Apr. 18, 1975, as amended at 61 FR 8477, Mar. 5, 1996]

CABLE SERVICES BUREAU

§0.321 Authority delegated.

The Chief, Cable Services Bureau is delegated authority to perform all functions of the Bureau, described in §0.101, subject to the following exceptions and limitations:

(a) Designate for hearing any formal complaints that present novel questions of fact, law or policy that cannot be resolved under existing precedents for guidelines;

(b) Impose, reduce, or cancel forfeitures pursuant to section 503(b) of the

Communications Act of 1934, as amended, in amounts of more than \$20,000;

(c) Act upon any applications for review of actions taken by the Chief, Cable Services Bureau pursuant to any delegated authority which comply with §1.115 of this chapter;

(d) Issue notices of proposed rulemaking, notices of inquiry or to issue report and orders arising from either of the foregoing, except that the Chief, Cable Services Bureau shall have authority to issue notices of rulemaking and report and orders redesignating market areas in accordance with section 614(f) of the Communications Act of 1934, as amended; and

(e) Act on any applications in the Cable Television Relay Service that present novel questions of fact, law, or policy that cannot be resolved under existing precedents and guidelines.

[62 FR 8401, Feb. 25, 1997]

§0.325 Record of actions taken.

The original file, the station file, and other appropriate files are designated to be the official record of the action taken by the Chief of the Cable Services Bureau.

[59 FR 32132, June 22, 1994]

WIRELESS TELECOMMUNICATIONS BUREAU

§0.331 Authority delegated.

The Chief, Wireless Telecommunications Bureau, is hereby delegated authority to perform all functions of the Bureau, described in §0.131, subject to the following exceptions and limitations.

(a) *Authority concerning applications.*

(1) The Chief, Wireless Telecommunications Bureau shall not have authority to act on any radio applications that are in hearing status.

(2) The Chief, Wireless Telecommunications Bureau shall not have authority to act on any complaints, petitions or requests, whether or not accompanied by an application, when such complaints, petitions or requests present new or novel questions of law or policy which cannot be resolved under outstanding Commission precedents and guidelines.

§0.332

(b) *Authority concerning forfeitures and penalties.* The Chief, Wireless Telecommunications Bureau, shall not have authority to impose, reduce, or cancel forfeitures pursuant to the Communications Act of 1934, as amended, and imposed under regulations in this chapter in amounts of more than \$80,000 for commercial radio providers and \$20,000 for private radio providers. Payments for bid withdrawal, default or to prevent unjust enrichment that are imposed pursuant to Section 309(j) of the Communications Act of 1934, as amended, and regulations in this chapter implementing Section 309(j) governing auction authority, are excluded from this restriction.

(c) *Authority concerning applications for review.* The Chief, Wireless Telecommunications Bureau shall not have authority to act upon any applications for review of actions taken by the Chief, Wireless Telecommunications Bureau pursuant to any delegated authority, except that the Chief may dismiss any such application that does not comply with the filing requirements of §1.115 (d) and (f) of this chapter.

(d) *Authority concerning rulemaking proceedings.* The Chief, Wireless Telecommunications Bureau shall not have the authority to act upon notices of proposed rulemaking and inquiry, final orders in rulemaking proceedings and inquiry proceedings, and reports arising from any of the foregoing except such orders involving ministerial conforming amendments to rule parts, or orders conforming any of the applicable rules to formally adopted international conventions or agreements where novel questions of fact, law, or policy are not involved. Also, the addition of new Marine VHF frequency coordination committee(s) to §80.514 of this chapter need not be referred to the Commission if they do not involve novel questions of fact, policy or law, as well as requests by the United States Coast Guard to:

(1) Designate radio protection areas for mandatory Vessel Traffic Services (VTS) and establish marine channels as VTS frequencies for these areas; or

47 CFR Ch. I (10–1–97 Edition)

(2) Designate regions for shared commercial and non-commercial vessel use of VHF marine frequencies.

[60 FR 35506, July 10, 1995, as amended at 61 FR 26465, May 28, 1996; 62 FR 40285, July 28, 1997]

§0.332 Actions taken under delegated authority.

In discharging the authority conferred by §0.331, the Chief, Wireless Telecommunications Bureau, shall establish working relationships with other bureaus and staff offices to assure the effective coordination of actions taken in the following areas of joint responsibility:

(a) Complaints arising under section 605 of the Communications Act—Office of General Counsel.

(b) Requests for waiver of tower painting and lighting specifications—Compliance and Information Bureau.

(c) Matters involving emergency communications—Compliance and Information Bureau.

(d) Complaints involving equal employment opportunities—Office of General Counsel.

(e) Requests for use of frequencies or bands of frequencies shared with broadcast, common carrier, or government services—Office of Engineering and Technology and appropriate operating bureau.

(f) Requests involving coordination with other Federal or state agencies when appropriate—Office of General Counsel, Office of Engineering and Technology or operating bureau.

(g) Proposals involving possible harmful impact on radio astronomy or radio research installations—Office of Engineering and Technology.

[40 FR 4423, Jan. 30, 1975, as amended at 44 FR 11070, Feb. 27, 1979; 44 FR 39180, July 5, 1979; 50 FR 27953, July 9, 1985; 51 FR 12615, Apr. 14, 1986; 51 FR 20290, June 4, 1986; 52 FR 5288, Feb. 20, 1987; 59 FR 26971, May 25, 1994; 60 FR 5325, Jan. 27, 1995; 60 FR 35507, July 10, 1995; 61 FR 8477, Mar. 5, 1996]

§§0.333–0.337 [Reserved]

ADMINISTRATIVE LAW JUDGES

§0.341 Authority of administrative law judge.

(a) After an administrative law judge has been designated to preside at a

Federal Communications Commission

§0.351

hearing and until he has issued an initial decision or certified the record to the Commission for decision, or the proceeding has been transferred to another administrative law judge, all motions, petitions and other pleadings shall be acted upon by such administrative law judge, except the following:

(1) Those which are to be acted upon by the Commission. See §1.291(a)(1) of this chapter.

(2) Those which are to be acted upon by the Chief Administrative Law Judge under §0.351.

(b) Any question which would be acted upon by the administrative law judge if it were raised by the parties to the proceeding may be raised and acted upon by the administrative law judge on his own motion.

(c) Any question which would be acted upon by the Chief Administrative Law Judge or the Commission, if it were raised by the parties, may be certified by the administrative law judge, on his own motion, to the Chief Administrative Law Judge, or the Commission, as the case may be.

(d) In the conduct of routine broadcast comparative hearings involving applicants for only new facilities, i.e., cases that do not involve numerous applicants and/or motions to enlarge issues, the presiding administrative law judge shall make every effort to conclude the case within nine months of the release of the hearing designation order. In so doing, the presiding judge will make every effort to release an initial decision in such cases within 90 days of the filing of the last responsive pleading.

(e) Upon assignment by the Chief Administrative Law Judge, Administrative Law Judges, including the Chief Judge, will act as settlement judges in appropriate cases. See 47 CFR 1.244 of this chapter.

[29 FR 6442, May 16, 1964, as amended at 37 FR 19372, Sept. 20, 1972; 41 FR 14870, Apr. 8, 1976; 56 FR 792, Jan. 9, 1991; 62 FR 4170, Jan. 29, 1997]

§0.347 Record of actions taken.

The official record of all actions taken by an Administrative Law Judge, including initial and recommended decisions and actions taken pursuant to §0.341, is contained in the

original docket folder, which is maintained by the Secretary in the Dockets Branch.

[39 FR 37061, Oct. 17, 1974]

CHIEF ADMINISTRATIVE LAW JUDGE

§0.351 Authority delegated.

The Chief Administrative Law Judge shall act on the following matters in proceedings conducted by hearing examiners:

(a) Initial specifications of the time and place of hearings where not otherwise specified by the Commission and excepting actions under authority delegated by §0.296.

(b) Designation of the hearing examiner to preside at hearings.

(c) Orders directing the parties or their attorneys to appear at a specified time and place before the hearing examiner for an initial prehearing conference in accordance with §1.251(a) of this chapter. (The administrative law judge named to preside at the hearing may order an initial prehearing conference although the Chief Administrative Law Judge may not have seen fit to do so and may order supplementary prehearing conferences in accordance with §1.251(b) of this chapter.)

(d) Petitions requesting a change in the place of hearing where the hearing is scheduled to begin in the District of Columbia or where the hearing is scheduled to begin at a field location and all appropriate proceedings at that location have not been completed. (See §1.253 of this chapter.) However, if all parties to a proceeding concur in holding all hearing sessions in the District of Columbia rather than at any field location, the presiding administrative law judge may act on the request.

(e) In the absence of the administrative law judge who has been designated to preside in a proceeding, to discharge the administrative law judge's functions.

(f) All pleadings filed, or matters which arise, after a proceeding has been designated for hearing, but before a law judge has been designated, which would otherwise be acted upon by the law judge, including all pleadings filed, or matters which arise, in cease and desist and/or revocation proceedings prior

§0.357

to the designation of a presiding officer.

(g) All pleadings (such as motions for extension of time) which are related to matters to be acted upon by the Chief Administrative Law Judge.

(h) If the administrative law judge designated to preside at a hearing becomes unavailable, to order a rehearing or to order that the hearing continue before another administrative law judge and, in either case, to designate the judge who is to preside.

(i) The consolidation of related proceedings pursuant to §1.227(a) of this chapter, after designation of those proceedings for hearing.

[29 FR 6443, May 16, 1964, as amended at 37 FR 19372, Sept. 20, 1972; 38 FR 30559, Nov. 6, 1973; 43 FR 49307, Oct. 23, 1978; 44 FR 76295, Dec. 26, 1979]

§0.357 Record of actions taken.

The official record of all actions taken by the Chief Administrative Law Judge in docketed proceedings pursuant to §0.351 is contained in the original docket folder, which is maintained by the Secretary in the Dockets Branch.

[39 FR 37061, Oct. 17, 1974]

NATIONAL SECURITY AND EMERGENCY PREPAREDNESS DELEGATIONS

§0.381 Defense Commissioner.

The authority delegated to the Commission under Executive Order 11490 is redelegated to the Defense Commissioner.

[41 FR 31210, July 27, 1976]

§0.383 Emergency Relocation Board, authority delegated.

(a) During any period in which the Commission is unable to function because of the circumstances set forth in §0.186(b), all work, business or functions of the Federal Communications Commission arising under the Communications Act of 1934, as amended, is assigned and referred to the Emergency Relocation Board.

(b) The Board, acting by a majority thereof, shall have the power and authority to hear and determine, order, certify, report or otherwise act as to any of the said work, business or func-

47 CFR Ch. I (10–1–97 Edition)

tions so assigned or referred to it, and in respect thereof shall have all the jurisdiction and powers conferred by law upon the Commission, and be subject to the same duties and obligations.

(c) Any order, decision or report made or other action taken by the said Board in respect of any matters so assigned or referred shall have the same effect and force, and may be made, evidenced, and enforced in the same manner, as if made or taken by the Commission.

[28 FR 12402, Nov. 22, 1963, as amended at 33 FR 8228, June 1, 1968; 53 FR 29055, Aug. 2, 1988]

§0.387 Other national security and emergency preparedness delega- tions; cross reference.

(a) For authority of the Chief of the Mass Media Bureau to issue Emergency Broadcast System Authorizations (FCC Form 392), see §§0.284(a)(4) and 73.913.

(b) For authority of the Chief and Deputy Chief of the Compliance and Information Bureau to declare a general communications emergency, see §0.311.

[28 FR 12411, Nov. 22, 1963, as amended at 40 FR 17254, Apr. 18, 1975; 53 FR 29055, Aug. 2, 1988; 54 FR 15195, Apr. 17, 1989; 61 FR 8477, Mar. 5, 1996]

OFFICE OF WORKPLACE DIVERSITY

§0.391 Authority delegated.

The Director, Office of Workplace Diversity, or his/her designee, is hereby delegated authority to:

(a) Manage the Commission's internal EEO compliance program pursuant to Title VII of the Civil Rights Act of 1964, as amended, the Rehabilitation Act of 1973, as amended, the Age Discrimination in Employment Act of 1967, as amended, the Equal Pay Act, and other applicable laws, rules, regulations, and Executive Orders, with authority that includes appointing EEO counselors, investigators, and mediators; investigating complaints of employment discrimination, and recommending to the Chairman final agency decisions on EEO complaints;

(b) Mediate EEO complaints;

(c) Develop the Commission's affirmative action goals and objectives;

Federal Communications Commission

§0.401

(d) Collect and analyze data on the Commission's affirmative action and EEO activities and accomplishments;

(e) Prepare and release reports on EEO, affirmative action, workplace diversity, and related subjects;

(f) Review personnel activities, including hiring, promotions, discipline, training, awards, and performance recognition for conformance with EEO and workplace diversity goals, objectives and requirements;

(g) Conduct studies and collect data on workplace diversity issues and problems;

(h) Assume representational role on behalf of the Commission at conferences, meetings, and negotiations on EEO and workplace diversity issues;

(i) Develop programs and strategies designed to foster and encourage fairness, equality, and inclusion of all employees in the workforce.

[61 FR 2728, Jan. 29, 1996]

Subpart C—General Information

GENERAL

§0.401 Location of Commission offices.

The Commission maintains several offices and receipt locations. Applications and other filings not submitted in accordance with the addresses or locations set forth below will be returned to the applicant without processing. When an application or other filing does not involve the payment of a fee, the appropriate filing address or location is established elsewhere in the rules for the various types of submissions made to the Commission. The public should identify the correct filing location by reference to these rules. Applications or submissions requiring fees must be submitted in accordance with §0.401(b) of the rules irrespective of the addresses that may be set out elsewhere in the rules for other submissions.

(a) General correspondence, as well as applications and filings not requiring the fees set forth at part 1, subpart G of the rules (or not claiming an exemption, waiver or deferral from the fee requirement), should be delivered to one of the following locations.

(1) The main office of the Commission is located at 1919 M Street, NW., Washington, DC.

(i) Documents submitted by mail to this office should be addressed to: Federal Communications Commission, Washington, DC 20554.

(ii) Hand-carried documents should be delivered to the Secretary's Office, 1919 M Street, NW., Room 222, Washington, DC.

(2) The Commission's laboratory is located near Columbia, Maryland. The mailing address is: Authorizations and Evaluation Division, Federal Communications Commission Laboratory, 7435 Oakland Mills Road, Columbia, MD 21045.

(3) The Commission also maintains offices at Gettysburg, PA.

(i) The address of the Wireless Telecommunications Bureau's licensing facilities are:

(A) Federal Communications Commission, 1270 Fairfield Road, Gettysburg, PA 17325-7245; and

(B) Federal Communications Commission, Wireless Telecommunications Bureau, Washington, DC 20554.

(ii) The mailing address of the International Telecommunications Section of the Finance Branch is: Federal Communications Commission, P.O. Box IT-70, Gettysburg, PA 17326.

(4) The locations of the field offices of the Compliance and Information Bureau are listed in §0.121.

(5) The location of the Office of General Counsel is Room 614, 1919 M Street NW., Washington, DC 20554.

(b) Applications or filings requiring the fees set forth at part 1, subpart G of the rules must be delivered to the Commission's lockbox bank in Pittsburgh, Pennsylvania with the correct fee and completed Fee Form attached to the application or filing, unless otherwise directed by the Commission. In the case of any conflict between this rule subpart and other rules establishing filing locations for submissions subject to a fee, this subpart shall govern.

NOTE: Applicants seeking a waiver or deferral of fees must submit their application or filing in accordance with the addresses set forth below. Applicants claiming a statutory exemption from the fees should file their applications in accordance with paragraph (a) of this section.

§0.403

(1) Applications and filings submitted by mail shall be addressed to the Mellon Bank in Pittsburgh, Pennsylvania. The bank maintains separate post office boxes for the receipt of different types of applications. It will also establish special post office boxes to receive responses to special filings such as applications filed in response to “filing windows” established by the Commission. The address for the submission of filings will be established in the Public Notice announcing the filing dates. In all other cases, applications and filings submitted by mail should be sent to the addresses listed in the appropriate fee rules.

NOTE: Wireless Telecommunications Bureau applications that require frequency coordination by certified coordinators must be submitted to the appropriate certified frequency coordinator before filing with the Commission. After coordination, the applications are filed with the Commission as set forth herein. (See §§90.127 and 90.175 of this chapter.)

(2) Applications and other filings may also be hand carried, in person or by courier, to the Mellon Bank, Three Mellon Bank Center, 525 William Penn Way, 27th Floor, room 153-2713, Pittsburgh, Pennsylvania. All applications and filings delivered in this manner must be in an envelope clearly marked for the “Federal Communications Commission,” addressed to the attention of “Wholesale Lockbox Shift Supervisor,” and identified with the appropriate Post Office Box address as set out in the fee schedule (§§1.1102-1.1107). Applications should be enclosed in a separate envelope for each Post Office Box. Hand-carried or couriered applications and filings may be delivered at any time on any day. Applications or filings received by the bank before midnight on any Commission business day will be treated as having been filed on that day. Materials received by the bank after midnight, Monday through Friday, or on weekends or holidays, will be treated as having been filed on the next Commission business day.

[52 FR 10227, Mar 31, 1987, as amended at 53 FR 18564, May 24, 1988; 53 FR 40886, Oct. 19, 1988; 54 FR 12453, Mar. 27, 1989; 55 FR 19154, May 8, 1990; 56 FR 64714, Dec. 12, 1991; 58 FR 13020, Mar. 9, 1993; 60 FR 5325, Jan. 27, 1995; 60 FR 35507, July 10, 1995; 61 FR 8477, Mar. 5, 1996]

47 CFR Ch. I (10-1-97 Edition)

§ 0.403 Office hours.

The main offices of the Commission are open from 8 a.m. to 5:30 p.m., Monday through Friday, excluding legal holidays, unless otherwise stated.

[52 FR 10228, Mar. 31, 1987]

§ 0.405 Statutory provisions.

The following statutory provisions, among others, will be of interest to persons having business with the Commission:

(a) The Federal Communications Commission was created by the Communications Act of 1934, 48 Stat. 1064, June 19, 1934, as amended, 47 U.S.C. 151-609.

(b) The Commission exercises authority under the Submarine Cable Landing Act, 42 Stat. 8, May 27, 1921, 47 U.S.C. 34-39. See section 5 of Executive Order 10530, 19 FR 2709, May 10, 1954, as amended, 3 CFR, 1965 ed., p. 463.

(c) The Commission exercises authority under the Communications Satellite Act of 1962, 76 Stat. 419, August 31, 1962, 47 U.S.C. 701-744.

(d) The Commission operates under the Administrative Procedure Act, 60 Stat. 237, June 11, 1946, as amended, originally codified as 5 U.S.C. 1001-1011. Pursuant to Pub. L. 89-554, September 6, 1966, 80 Stat. 378, the provisions of the Administrative Procedure Act now appear as follows in the Code:

Administrative Procedure Act	5 U.S.C.
Sec. 2-9	551-558
Sec. 10	701-706
Sec. 11	3105, 7521, 5362, 1305
Sec. 12	559

[32 FR 10570, July 19, 1967]

§ 0.406 The rules and regulations.

Persons having business with the Commission should familiarize themselves with those portions of its rules and regulations pertinent to such business. All of the rules have been published and are readily available. See §§0.411(b), 0.412, and 0.415. For the benefit of those who are not familiar with the rules, there is set forth in this section a brief description of their format and contents.

(a) *Format.* The rules are set forth in the Code of Federal Regulations as

chapter I of title 47. Chapter I is divided into parts numbered from 0–99. Each part, in turn, is divided into numbered sections. To allow for the addition of new parts and sections in logical sequence, without extensive renumbering, parts and sections are not always numbered consecutively. Thus, for example, part 2 is followed by part 5, and §1.8 is followed by §1.10; in this case, parts 3 and 4 and §1.9 have been reserved for future use. In numbering sections, the number before the period is the part number; and the number after the period locates the section within that part. Thus, for example, §1.1 is the first section of part 1 and §5.1 is the first section in part 5. Except in the case of accounting regulations (parts 31–35), the period should not be read as a decimal point; thus, §1.511 is not located between §§1.51 and 1.52 but at a much later point in the rules. In citing the Code of Federal Regulations, the citation, 47 CFR 5.1, for example, is to §5.1 (in part 5) of chapter I of title 47 of the Code, and permits the exact location of that rule. No citation to other rule units (e.g., subpart or chapter) is needed.

(b) *Contents.* Parts 0–19 of the rules have been reserved for provisions of a general nature. Parts 20–69 of this chapter have been reserved for provisions pertaining to common carriers. Parts 20–29 and 80–109 of this chapter have been reserved for provisions pertaining to the wireless telecommunications services. In the rules pertaining to common carriers, parts 20–25 and 80–99 of this chapter pertain to the use of radio; in the rules pertaining to common carriers, parts 21, 23, and 25 of this chapter pertain to the use of radio; parts 31–66 of this chapter pertain primarily to telephone and telegraph companies. Persons having business with the Commission will find it useful to consult one or more of the following parts containing provisions of a general nature in addition to the rules of the radio or wire communication service in which they are interested:

(1) *Part 0, Commission organization.* Part 0 describes the structure and functions of the Commission, lists delegations of authority to the staff, and sets forth information designed to assist those desiring to obtain information

from, or to do business with, the Commission. This part is designed, among other things, to meet certain of the requirements of the Administrative Procedure Act, as amended.

(2) *Part 1 of this chapter, practice and procedure.* Part 1, subpart A, of this chapter contains the general rules of practice and procedure. Except as expressly provided to the contrary, these rules are applicable in all Commission proceedings and should be of interest to all persons having business with the Commission. Part 1, subpart A of this chapter also contains certain other miscellaneous provisions. Part 1, subpart B, of this chapter contains the procedures applicable in formal hearing proceedings (see §1.201 of this chapter). Part 1, subpart C, of this chapter contains the procedures followed in making or revising the rule or regulations. Part 1, subpart D, of this chapter contains rules applicable to applications for licenses in the Broadcast Radio Services, including the forms to be used, the filing requirements, the procedures for processing and acting upon such applications, and certain other matters. Part 1, subpart F, of this chapter contain rules applicable to applications for licenses in the Wireless Telecommunications Bureau services, including the forms to be used, the filing requirements, the procedures for processing and acting on such applications, and certain other matters. Additional procedures applicable to certain common carriers by radio are set forth in part 21 of this chapter. Part 1, subpart F, of this chapter contains rules applicable to applications for licenses in the Private Radio Services, including the forms to be used, the filing requirements, the procedures for processing and acting on such applications, and certain other matters. Part 1, subpart G, of this chapter contains rules pertaining to the application processing fees established by the Consolidated Omnibus Budget Reconciliation Act of 1985 (Pub. L. 99–272, 100 Stat. 82 (1986)) and also contains rules pertaining to the regulatory fees established by the Omnibus Budget Reconciliation Act of 1993 (Pub. L. 103–66, 107 Stat. 397 (1993)). Part 1, subpart H, of this chapter, concerning *ex parte*

§0.408

47 CFR Ch. I (10–1–97 Edition)

presentations, sets forth standards governing communications with commission personnel in hearing proceedings and contested application proceedings. Part 1, subparts G and H, of this chapter will be of interest to all regulatees, and part 1, subpart H, of this chapter will, in addition, be of interest to all persons involved in hearing proceedings.

(3) *Part 2, frequency allocations and radio treaty matters; general rules and regulations.* Part 2 will be of interest to all persons interested in the use of radio. It contains definitions of technical terms used in the rules and regulations; provisions governing the allocation of radio frequencies among the numerous uses made of radio (e.g., broadcasting, land mobile) and radio services (e.g., television, public safety), including the Table of Frequency Allocations (§2.106); technical provisions dealing with emissions; provisions dealing with call signs and emergency communications; provisions governing type acceptance and type approval of radio equipment; and a list of treaties and other international agreements pertaining to the use of radio.

(4) *Part 5, experimental radio services (other than broadcast).* Part 5 deals with the temporary use of radio frequencies for research in the radio art, for communication involving other research projects, and for the development of equipment, data, or techniques.

(5) *Part 13, commercial radio operators.* Part 13 describes the procedures to be followed in applying for a commercial operator license, including the forms to be used and the examinations given, and sets forth rules governing licensed operators. It will be of interest to applicants for such licenses, licensed operators, and the licensees of radio stations which may be operated only by persons holding a commercial radio operator license.

(6) *Part 15, radio frequency devices.* Part 15 contains regulations designed to prevent harmful interference to radio communication from radio receivers and other devices which radiate radio frequency energy, and provides for the certification of radio receivers. It also provides for the certification of low power transmitters and for the op-

eration of certificated transmitters without a license.

(7) *Part 17, construction, marking, and lighting of antenna structures.* Part 17 contains criteria for determining whether applications for radio towers require notification of proposed construction to the Federal Aviation Administration, and specifications for obstruction marking and lighting of antenna structures.

(8) *Part 18, industrial, scientific and medical equipment.* Part 18 contains regulations designed to prevent harmful interference to radio communication from ultrasonic equipment, industrial heating equipment, medical diathermy equipment, radio frequency stabilized arc welders, and other equipment which uses radio energy for purposes other than communication.

(9) *Part 19, employee responsibilities and conduct.* Part 19 prescribes standards of conduct for the members and staff of the Commission.

[32 FR 10571, July 19, 1967, as amended at 32 FR 12180, Aug. 24, 1967; 37 FR 20553, Sept. 30, 1972; 52 FR 5288, Feb. 20, 1987; 58 FR 13021, Mar. 9, 1993; 59 FR 30998, June 16, 1994; 60 FR 35507, July 10, 1995]

§0.408 OMB control numbers and expiration dates assigned pursuant to the Paperwork Reduction Act.

(a) *Purpose.* This section collects and displays the control numbers and expiration dates for the Commission information collection requirements assigned by the Office of Management and Budget (“OMB”) pursuant to the Paperwork Reduction Act of 1995, Public Law 104–13. The Commission intends that this section comply with the requirement that agencies display current control numbers and expiration dates assigned by the Director of OMB for each approved information collection requirement. Notwithstanding any other provisions of law, no person shall be subject to any penalty for failing to comply with a collection of information subject to the Paperwork Reduction Act (PRA) that does not display a valid control number. Questions concerning the OMB control numbers and expiration dates should be directed to the Records Management Branch, Federal Communications Commission, Washington, DC 20554.

Federal Communications Commission

§ 0.408

(b) *Display.*

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060-0003	FCC 610	9/30/96
3060-0004	Sec. 1.1307, 1.1308, 1.311	11/30/96
3060-0009	FCC 316	5/31/99
3060-0010	FCC 323	7/31/98
3060-0012	Parts 21, 23, 25 and FCC 701	3/31/97
3060-0016	FCC 346	4/30/97
3060-0017	FCC 347	4/30/97
3060-0019	FCC 403	10/31/97
3060-0020	FCC 406	5/31/99
3060-0021	FCC 480	12/31/97
3060-0022	FCC 610A	8/31/98
3060-0024	Sec. 76.29	8/31/98
3060-0025	FCC 755	7/31/97
3060-0027	FCC 301	8/31/98
3060-0028	FCC 313	2/28/99
3060-0029	FCC 302-TV	1/31/97
3060-0031	FCC 314	8/31/98
3060-0032	FCC 315	8/31/98
3060-0034	FCC 340	11/30/97
3060-0035	FCC 313-R	3/31/97
3060-0040	FCC 404/404-R	7/31/97
3060-0041	FCC 301-A	3/31/97
3060-0048	FCC 704	3/31/97
3060-0049	FCC 753	5/31/97
3060-0050	FCC 801	1/31/98
3060-0051	FCC 405-B	8/31/97
3060-0053	FCC 703	10/31/96
3060-0054	FCC 820	2/28/99
3060-0055	FCC 327	2/31/96
3060-0056	FCC 730	3/31/97
3060-0057	FCC 731	9/30/96
3060-0059	FCC 740	7/31/97
3060-0061	FCC 325	10/31/96
3060-0062	FCC 330	8/31/98
3060-0064	FCC 402	6/30/98
3060-0065	FCC 422	9/30/98
3060-0066	FCC 330-R	4/30/97
3060-0068	FCC 702	8/31/97
3060-0069	FCC 756	9/30/96
3060-0072	FCC 409	8/31/98
3060-0073	FCC 808	7/31/97
3060-0075	FCC 345	12/31/96
3060-0076	FCC 395	12/31/96
3060-0079	FCC 610-B	8/31/99
3060-0084	FCC 323-E	4/30/99
3060-0085	FCC 65	6/30/97
3060-0089	FCC 503	6/30/98
3060-0090	FCC 410	11/30/96
3060-0093	FCC 405	3/31/97
3060-0095	FCC 395-A, 395-AS	6/30/99
3060-0096	FCC 506, 506-A	8/31/99
3060-0099	FCC M	8/31/99
3060-0104	FCC 572	6/30/97
3060-0105	FCC 430	2/28/99
3060-0106	Sec. 43.61, FCC 43.61	8/31/98
3060-0107	FCC 405-A	12/31/96
3060-0108	FCC 201	1/31/97
3060-0110	FCC 303-S	8/31/99
3060-0113	FCC 396	12/31/96
3060-0119	Sec. 90.145	2/28/97
3060-0120	FCC 396-A	11/30/96
3060-0126	Sec. 73.1820	8/31/99
3060-0127	FCC 1046	4/30/97
3060-0128	FCC 574	6/30/98
3060-0132	FCC 1068A	12/31/97
3060-0134	FCC 574-R	5/31/99
3060-0136	FCC 574-T	3/31/98
3060-0139	FCC 854	6/30/98
3060-0141	FCC 402-R	5/31/97
3060-0147	Sec. 64.804	11/30/96

§ 0.408

47 CFR Ch. I (10–1–97 Edition)

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060–0149	Part 63, Sec. 214, 63.01–63.601	6/30/98
3060–0157	Sec. 73.99	3/31/97
3060–0160	Sec. 73.158	2/28/99
3060–0161	Sec. 73.61	11/30/96
3060–0164	Sec. 25.300	5/31/97
3060–0165	Part 41 Sec. 41.31	11/30/96
3060–0166	Part 42	8/31/98
3060–0168	Sec. 43.43	10/31/96
3060–0169	Sec. 43.51, 43.53	8/31/98
3060–0170	Sec. 73.1207	1/31/96
3060–0171	Sec. 73.1125	2/28/99
3060–0173	Sec. 73.1207	12/31/97
3060–0174	Sec. 73.1212	3/31/99
3060–0175	Sec. 73.1250	11/30/96
3060–0176	Sec. 73.1510	1/31/97
3060–0178	Sec. 73.1560	1/31/97
3060–0179	Sec. 73.1590	3/31/98
3060–0180	Sec. 73.1610	1/31/99
3060–0181	Sec. 73.1615	1/31/97
3060–0182	Sec. 73.1620	12/31/97
3060–0184	Sec. 73.1740	1/31/99
3060–0185	Sec. 73.3613	5/31/98
3060–0187	Sec. 73.3594	12/31/97
3060–0188	Sec. 73.3550	7/31/97
3060–0190	Sec. 73.3544C	12/31/97
3060–0192	Sec. 87.103	11/30/97
3060–0194	Sec. 74.21	1/31/99
3060–0202	Sec. 87.37	12/31/97
3060–0204	Sec. 90.38(B)	4/30/99
3060–0206	Part 21	7/31/97
3060–0207	Sec. 73.961 & 73.932	2/28/97
3060–0208	Sec. 73.1870	12/31/96
3060–0209	Sec. 73.1920	11/30/96
3060–0210	Sec. 73.1930	3/31/98
3060–0211	Sec. 73.1943	5/31/98
3060–0212	Sec. 73.2080	11/30/96
3060–0213	Sec. 73.3525B	7/31/97
3060–0214	Sec. 73.3526	7/31/99
3060–0215	Sec. 73.3527	11/30/96
3060–0216	Sec. 73.3538	11/30/98
3060–0218	Sec. 90.41(b)	12/31/97
3060–0219	Sec. 90.49(b)	11/30/96
3060–0221	Time in which stations must be placed in operation (exceptions)	12/31/97
3060–0222	Sec. 97.213	12/31/97
3060–0223	Sec. 90.129(B)	5/31/99
3060–0224	Sec. 90.151	2/28/98
3060–0225	Sec. 90.131(B)	11/30/96
3060–0226	Sec. 90.135 (d) & (e)	2/28/98
3060–0228	Sec. 80.59	8/31/98
3060–0233	Part 36	7/31/99
3060–0236	Sec. 74.703	7/31/99
3060–0240	Sec. 74.651	3/31/97
3060–0241	Sec. 74.633	3/31/97
3060–0242	Sec. 74.604	3/31/97
3060–0243	Sec. 74.551	5/31/99
3060–0245	Sec. 74.537	5/31/99
3060–0246	Sec. 74.452	7/31/97
3060–0248	Sec. 74.751	7/31/99
3060–0249	Sec. 74.781	11/30/96
3060–0250	Sec. 74.784	11/30/96
3060–0251	Sec. 74.833	11/30/96
3060–0253	Part 68 Sec. 68.106, 68.108, 68.110	2/28/98
3060–0254	Sec. 74.433	7/31/97
3060–0258	Sec. 90.176	11/30/96
3060–0259	Sec. 90.263	12/31/97
3060–0260	Sec. 90.239(D)	12/31/95
3060–0261	Sec. 90.215	12/31/97
3060–0262	Sec. 90.179	11/30/98
3060–0263	Sec. 90.177	11/30/96
3060–0264	Sec. 80.413	12/31/97
3060–0265	Sec. 80.868	8/31/98
3060–0270	Sec. 90.443	2/28/97

Federal Communications Commission

§ 0.408

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060-0272	Sec. 94.31	3/31/98
3060-0274	Sec. 94.45	2/28/97
3060-0280	Sec. 90.633 (F) & (G)	5/31/99
3060-0281	Sec. 90.651	2/28/98
3060-0282	Sec. 94.17	5/31/97
3060-0284	Sec. 94.25 (F) (G) & (I)	2/28/98
3060-0286	Sec. 80.302	12/31/96
3060-0287	Sec. 78.69	8/31/98
3060-0288	Sec. 78.33	12/31/96
3060-0289	Sec. 76.60	2/28/99
3060-0290	Sec. 90.5171	5/31/99
3060-0291	Sec. 90.477	2/28/98
3060-0292	Part 69	5/31/97
3060-0295	Sec. 90.607 (b)(1) & (c)(1)	12/31/97
3060-0297	Sec. 80.503	12/31/97
3060-0298	Part 61	7/31/97
3060-0300	Sec. 94.107	2/28/98
3060-0302	Sec. 97.9	12/31/95
3060-0303	Sec. 97.5	12/31/95
3060-0307	Sec. 90.629(A)	4/30/99
3060-0308	Sec. 90.505	2/28/98
3060-0309	Sec. 74.1281	2/28/99
3060-0310	Sec. 76.12	12/31/96
3060-0311	Sec. 76.54	11/30/96
3060-0313	Sec. 76.207	5/31/98
3060-0314	Sec. 76.209	12/31/97
3060-0315	Sec. 76.221	11/30/96
3060-0316	Sec. 76.305	5/31/98
3060-0318	FCC 489	10/31/97
3060-0319	FCC 490	10/31/97
3060-0320	Sec. 73.1350	2/28/98
3060-0321	Sec. 73.68	2/28/99
3060-0325	Sec. 80.605	6/30/99
3060-0326	Sec. 73.69	11/30/96
3060-0329	Sec. 2.955	4/30/99
3060-0331	Sec. 76.615	5/31/98
3060-0332	Sec. 76.614	6/30/98
3060-0339	Sec. 78.11	1/31/97
3060-0340	Sec. 73.51	8/31/97
3060-0341	Sec. 73.1680	8/31/97
3060-0342	Sec. 74.1284	7/31/97
3060-0343	Sec. 25.140	10/31/96
3060-0346	Sec. 78.27	12/31/97
3060-0347	Sec. 97.311	9/30/97
3060-0348	Sec. 76.79	12/31/97
3060-0349	Sec. 76.73 and 76.75	11/30/97
3060-0355	FCC 492 and FCC 492A	5/31/98
3060-0357	Sec. 63.701	5/31/98
3060-0360	Sec. 80.409(c)	7/31/98
3060-0361	Sec. 80.29	5/31/98
3060-0362	Sec. 80.401	8/31/99
3060-0364	Sec. 80.409 (d) and (e)	7/31/98
3060-0370	Part 32	9/30/98
3060-0374	Sec. 73.1690	11/30/98
3060-0383	Part 25	11/30/96
3060-0384	Sec. 64.904	2/28/99
3060-0386	Sec. 73.1635	5/31/99
3060-0387	Sec. 15.201(d)	5/31/99
3060-0388	Sec. 80.227	6/30/99
3060-0390	FCC 395B	11/30/96
3060-0391	Monitoring Program for Impact of Federal State Joint Board	8/31/98
3060-0392	Sec. 1.1401-1.1416	2/28/97
3060-0393	Sec. 73.45	11/30/96
3060-0394	Sec. 1.420	11/30/96
3060-0395	Sec. 43.21 and 43.22 FCC 43-02, FCC 43-05 and FCC 43-07	11/30/96
3060-0397	Sec. 15.7(A)	11/30/96
3060-0398	Sec. 2.943, 15.117(G)(2), 80.1053	4/30/99
3060-0400	Tariff Review Plan	9/30/96
3060-0402	FCC 494	5/31/97
3060-0403	FCC 494-A	3/31/97
3060-0404	FCC 350	1/31/97
3060-0405	FCC 349	9/30/98

§ 0.408

47 CFR Ch. I (10–1–97 Edition)

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060–0407	FCC 307	3/31/97
3060–0410	FCC 495A and FCC 495B	3/31/97
3060–0411	Sec. 1.720–1.735	3/31/98
3060–0414	Terrain Shielding Policy	6/30/97
3060–0419	Sec. 76.94, 76.95, 76.155, 76.156, 76.157, 76.159	9/30/98
3060–0421	New Service Reporting Requirements under Price Cap Regulation	2/28/99
3060–0422	Sec. 68.5	5/31/98
3060–0423	Sec. 73.3588	11/30/96
3060–0425	Sec. 74.913	8/31/98
3060–0427	Sec. 73.3523	7/31/97
3060–0430	Sec. 1.1206	5/31/98
3060–0433	FCC 320	1/30/99
3060–0434	Sec. 90.19(F)(7)	5/31/99
3060–0435	Sec. 80.361	10/31/96
3060–0436	Sec. 15.214 and 68.200	5/31/99
3060–0438	FCC 464	11/30/97
3060–0439	Regulations Concerning Indecent Communications by Telephone	2/28/98
3060–0441	Sec. 90.621(B)(4)	8/31/99
3060–0443	FCC 572C	5/31/99
3060–0444	FCC 800A	5/31/99
3060–0446	Sec. 1.402	9/30/98
3060–0447	Sec. 25.134	12/31/97
3060–0448	Sec. 63.07	11/30/96
3060–0449	Sec. 1.65(c)	1/31/99
3050–0450	Detariffing and Installation of Inside Wiring Services Reports on State Regulatory Activities	2/28/98
3060–0452	Sec. 73.3589	11/30/96
3060–0454	Regulation of International Accounting Rates	2/28/98
3060–0461	Sec. 90.173	12/31/96
3060–0463	Telecommunications Services for Individuals with Hearing and Speech Disabilities	6/30/97
3060–0465	Sec. 74.985	1/31/97
3060–0466	Sec. 74.1283	2/28/97
3060–0470	Computer III Remand Proceeding: BOC Safeguards and Tier 1 LEC Safeguards and Implementation of Further Costs, CC Docket 90–623	8/31/98
3060–0472	FCC 60271	2/28/97
3060–0473	Sec. 74.1251	2/28/97
3060–0474	Sec. 74.1263	3/31/97
3060–0475	Sec. 90.713	12/31/98
3060–0478	Informational Tariffs	3/31/97
3060–0479	Sec. 73.661 and 73.3526(A)(11)	11/30/96
3060–0480	FCC 493	5/31/97
3060–0481	FCC 452R	8/31/97
3060–0483	Sec. 73.687	7/31/97
3060–0484	Sec. 63.100	2/28/98
3060–0486	Document Index Terms	12/31/97
3060–0488	Sec. 73.30	12/31/97
3060–0489	Sec. 73.37	12/31/97
3060–0490	Sec. 74.902	12/31/97
3060–0491	Sec. 74.991	12/31/97
3060–0492	Sec. 74.992	12/31/97
3060–0493	Sec. 74.986	12/31/97
3060–0494	Sec. 74.990	12/31/97
3060–0496	FCC Report 43–08	11/30/97
3060–0497	FCC 91 FCC 92	8/31/98
3060–0498	FCC 90	8/31/98
3060–0500	Sec. 76.607	5/31/98
3060–0501	Sec. 76.206	5/31/98
3060–0502	Sec. 73.1942	5/31/98
3060–0504	Sec. 90.658	8/31/98
3060–0506	FCC 302–FM	1/31/97
3060–0508	Rewrite and Update of Part 22, of the Public Mobile Service Rules, CC Docket 92–115	10/31/97
3060–0509	FCC Reports FCC 21–01, FCC 22–01, FCC 25–01 and FCC 25–02	8/31/98
3060–0511	FCC Report 43–04	11/30/96
3060–0512	FCC Report 43–01	8/31/98
3060–0513	FCC Report 43–03	11/30/96
3060–0514	Sec. 43.21(c)	3/31/97
3060–0515	Sec. 43.21(d)	8/31/98
3060–0516	Revision of Radio Rules and Policies, Time Brokerage Ruling	11/30/98
3060–0519	Rules and Regulations Implementing the Telephone Consumer Protection Act of 1991	9/30/98
3060–0520	Sec. 90.127(E)	2/28/99
3060–0526	Density Pricing Zone Plans, Expanded Interconnection with Local Telephone Facilities (CC Docket 91–141)	1/31/99
3060–0532	Sec. 2.975(A)(8) and 2.1033(B)(12)	5/31/99

Federal Communications Commission

§ 0.408

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060-0536	FCC 431	6/30/99
3060-0537	Sec. 13.217	5/31/99
3060-0539	FCC 493, 430, and 405	2/28/97
3060-0540	Tariff Filing Requirement for Nondominant Common Carriers	2/28/99
3060-0541	FCC 464-A	2/28/99
3060-0542	Frequency Coordinator Evaluation	5/31/98
3060-0543	Part 1, 2, and 21	7/31/99
3060-0544	Sec. 76.701	6/30/99
3060-0546	Sec. 76.59	6/30/99
3060-0547	Sec. 76.61 and 76.7	9/30/98
3060-0548	Sec. 76.302 and 76.56	9/30/98
3060-0549	FCC 329	12/31/96
3060-0550	FCC 328	8/31/99
3060-0551	Sec. 76.1002	9/30/96
3060-0552	Sec. 76.1003	9/30/96
3050-0554	Section 87.199	6/30/99
3060-0556	Sec. 80.1061	6/30/99
3060-0560	Sec. 76.911	12/31/97
3060-0561	Sec. 76.913	12/31/97
3060-0562	Sec. 76.916	12/31/97
3060-0563	Sec. 76.915	6/30/97
3060-0564	Sec. 76.924	8/31/99
3060-0565	Sec. 76.944	6/30/97
3060-0567	Sec. 76.962	5/31/98
3060-0568	Sec. 76.970	7/31/99
3060-0569	Sec. 76.975	6/30/97
3060-0570	Sec. 76.982	12/31/97
3060-0571	FCC 393	7/31/99
3060-0572	Sec. 43.82	5/31/99
3060-0573	FCC 394	9/30/96
3060-0574	FCC 395-M	6/30/99
3060-0576	FCC 610R	8/31/99
3060-0577	Expanded Interconnection with Local Telephone Company Facilities	9/30/96
3060-0579	Expanded Interconnection with Local Telephone Company Facilities for Interstate Switched Transport Service	9/30/96
3060-0580	Sec. 76.504	1/31/97
3060-0581	Sec. 76.503	1/31/97
3060-0582	Sec. 76.1302	1/31/97
3060-0583	Amendment to Part 32 and 64 of the Commission's Rules to Account for Transactions Between Carriers and their Nonregulated Affiliates, CC Docket 93-251	10/31/96
3060-0584	FCC 45 FCC 44	7/31/99
3060-0589	FCC 159, and 159C	9/30/98
3060-0591	Amendment to the Commission's Rules to Establish Rules and Policies Pertaining to a Mobile Satellite Service in the 1610-1626.5/2483.5-2500 MHz Frequency Bands	2/28/97
3060-0593	FCC 1215	4/30/97
3060-0594	FCC 1220	4/30/97
3060-0595	FCC 1210	2/28/98
3060-0596	FCC 1225	4/30/97
3060-0597	FCC 1201	4/30/97
3060-0599	Implementation of Sections 3(n) and 322 of the Communications Act, GN 93-253	4/30/97
3060-0600	FCC 175 and 175-S	9/30/98
3060-0601	FCC 1200	4/30/97
3060-0602	Sec. 76.917	4/30/97
3060-0604	FCC 401, 489, 490, 405, 430, and 854	5/31/97
3060-0607	Sec. 76.922	2/28/98
3060-0608	Sec. 76.964(B)	8/31/97
3060-0609	Sec. 76.934(D)	8/31/97
3060-0610	Sec. 76.958	8/31/97
3060-0611	Sec. 74.783	7/31/97
3060-0613	Expanded Interconnection with Local Telephone Company Facilities, CC Docket 91-141	9/30/98
3060-0615	FCC 405S	8/31/97
3060-0621	FCC 401, 405, 430, 489, 490 and 854	10/31/97
3060-0623	FCC 600	2/28/99
3060-0624	Amendment of the Commission's Rules to Establish New Narrowband Personal Communications Services, ET Docket 92-100 and GN Docket 90-314	12/31/97
3060-0625	Amendment of the Commission's Rules to Establish New Personal Communications Services, GN Docket 90-314	11/30/97
3060-0626	Implementation of Sections 3(N) and 332 of the Communications Act, GN Docket 93-252	11/30/97
3060-0627	FCC 302-AM	1/31/98
3060-0629	Sec. 76.987(G)	2/28/98
3060-0630	Sec. 73.62	2/28/98
3060-0631	Sec. 73.1300	2/28/98

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060–0632	Sec. 73.1570	2/28/98
3060–0633	Sec. 73.1230, 74.165, 74.432, 74.564, 74.664, 74.765, 74.832, 74.965 and 74.1265	2/28/98
3060–0634	Sec. 73.691	2/28/98
3060–0635	FCC 610–V	4/30/98
3060–0636	Part 2 and 18	6/30/98
3060–0638	Sec. 76.934(F)(1)	5/31/98
3060–0639	Implementation of Section 309(J) of the Communications Act Competitive Bidding, PP 93–253	4/30/98
3060–0640	FCC 800I	7/31/98
3060–0641	FCC 2181	7/31/98
3060–0642	FCC Survey of Cable Industry Costs	12/31/96
3060–0643	Part 65 and 69	8/31/98
3060–0644	FCC 1230	8/31/98
3060–0648	Sec. 21.902	9/30/98
3060–0649	Sec. 76.58	9/30/98
3060–0650	Sec. 76.502	9/30/98
3060–0651	Sec. 76.9	9/30/98
3060–0652	Sec. 76.309 and 76.964	9/30/98
3060–0653	Sec. 64.703(b)	9/30/98
3060–0654	FCC 304	9/30/98
3060–0655	Request for Waivers of Regulatory Fees Predicated on Allegations of Financial Hardship, MM Docket 94–19	9/30/98
3060–0656	FCC 175–M	9/30/98
3060–0657	Sec. 21.956	9/30/98
3060–0658	Sec. 21.960	9/30/98
3060–0660	Sec. 21.937	9/30/98
3060–0661	Sec. 21.931	9/30/98
3060–0662	Sec. 21.930	9/30/98
3060–0663	Sec. 21.934	9/30/98
3060–0664	FCC 304A	9/30/98
3060–0665	Sec. 65.707	9/30/98
3060–0666	Sec. 64.703(a)	9/30/98
3060–0667	Sec. 76.630	9/30/98
3060–0668	Sec. 76.936	9/30/98
3060–0669	Sec. 76.946	9/30/98
3060–0670	Sec. 76.986	9/30/98
3060–0672	Sec. 76.951	9/30/98
3060–0673	Sec. 76.956	9/30/98
3060–0674	Sec. 76.931 and 76.932	9/30/98
3060–0675	RAO Letter 25	9/30/98
3060–0676	Sec. 64.1100	9/30/98
3060–0678	FCC 312	8/31/99
3060–0679	Streamlining the Commission's Rules and Regulations for Satellite Application and Licensing Procedures	9/30/98
3060–0680	FCC 43–09A, FCC 43–09B	12/31/96
3060–0681	Toll-Free Access Codes	2/28/99
3060–0682	Sec. 63.16	1/31/99
3060–0683	Direct Broadcast Satellite Service	1/31/99
3060–0684	Cost Sharing Plan for Microwave Relocation	8/31/99
3060–0685	FCC 1240	7/31/99
3060–0686	Streamlining the International Section 214 Authorization Process and Tariff Requirements	6/30/99
3060–0687	Access to Telecommunications Equipment and Services by Persons with Disabilities	2/28/99
3060–0688	FCC 1235	2/28/99
3060–0690	ET Docket 95–183	4/30/99
3060–0691	Amendment to Part 2 and 90 of the Commission's Rules to Provide for the Use of 200 Channels Outside the Designated Filing Areas in the 896–901 MHz Bands Allotted to Specialized Mobile	6/30/99
3060–0692	Sec. 76.802	4/30/99
3060–0695	WT Docket No. 96–1	4/30/99
3060–0696	Amendment of the Commission's Rules to Permit Flexible Service Offerings in the Commercial Mobile Radio Service	4/30/97
3060–0697	Revision of Part 22 and Part 90 of the Commission's Rules to Facilitate Future Development of Paging Systems	4/30/99
3060–0698	Amendment of the Commission's Rules to Establish a Radio Astronomy Coordination Zone in Puerto Rico	5/31/99
3060–0699	MM Docket 96–16	5/31/99
3060–0700	FCC 1275	8/31/99
3060–0701	CC Docket 96–23	5/31/99
3060–0702	Amendment to Part 20 and 24 of the Commission's Rules Broadband PCS Competitive Bidding and the Commercial Mobile Radio Service Spectrum Cap	5/31/99
3060–0703	CS Docket 96–57, FCC 1205	6/30/99
3060–0704	CC Docket 96–61	6/30/99
3060–0706	Order and NPRM on Cable Reform: Implementation of the Telecommunications Act of 1996	10/31/96
3060–0707	Restriction on Over-the Air Reception Devices (NPRM)	6/30/96

Federal Communications Commission

§0.411

OMB control no.	FCC form number or 47 CFR section or part, docket number or title identifying the collection	OMB expiration date
3060-0708	NPRM in MM Docket 96-58	7/31/99
3060-0709	Revision to Part 22 and Part 90 to Facilitate Future Development of the Paging System and Implementation of Section 309(j) of the Communications Act	10/31/96
3060-0710	CC Docket 96-98	2/28/97
3060-0711	GC Docket 96-101	7/31/99
3060-0712	Petition for Declaratory Ruling by Inmate Calling Services Providers Task Force	7/31/99
3060-0713	Alternative Broadcast Inspection Program	7/31/99
3060-0714	Antenna Registration Number Required as Supplement to Application Forms	9/30/96
3060-0715	CC 96-115	8/31/99
3060-0716	Section 73.1630	8/31/99
3060-0719	Proposed Quarterly Report of IntraLATA Carriers Listing Pay Phone Automatic Numbering Identification	8/31/99
3060-0722	Proposed Initial Report of Bell Operating Companies of Comparably Efficient Interconnect Plans	8/31/99
3060-0723	Proposed Public Disclosure of Network Information by Bell Operating Companies	8/31/99
3060-0724	Proposed Annual Report of Interexchange Carriers Listing the Compensation Amount Paid to Pay Phone Providers and the Number of Payees	8/31/99
3060-0725	Proposed Annual Filing of Nondiscrimination Reports (On Quality of Service, Installation, and Maintenance) by BOC's	8/31/99
3060-0726	Proposed Quarterly Report of Interexchange Carriers Listing the Number of Dial-Around Calls for which Compensation is Being Paid to Pay Phone Owners	8/31/99
3060-0728	Supplemental Information Requesting Taxpayer Identifying Numbers for Debt Collection	9/30/96
3060-0729	Bell Operating Provision of Out-of-Region Interexchange Services (Affiliated Company Record-keeping Requirements)	10/31/96
3060-0730	Toll-Free Service Access Codes, 800/888 Number Release Procedures	10/31/96
3060-0733	Implementations of Section 302 of the Telecommunications Act of 1996	10/31/96

[61 FR 51023, Sept. 30, 1996, as amended at 62 FR 45172, Aug. 26, 1997]

§0.409 Commission policy on private printing of FCC forms.

The Commission has established a policy regarding the printing of blank FCC forms by private companies if they elect to do so as a matter of expediency and convenience to their clients or consumers. The policy is as follows:

(a) Blank FCC forms may be reproduced by private companies at their own expense provided the following conditions are met:

(1) Use a printing process resulting in a product that is at least comparable in quality to the original document, without change to the page size, image size, configuration of pages, folds or perforations, and matching as closely as possible the paper weight, paper color and ink color.

(2) Delete in its entirety any and all U.S. Government Printing Office (GPO) indicia that may appear in the margin(s).

(3) If the printer wishes to identify a foreign country in which the forms are printed, a marginal notation must be added stating "No U.S. Government funds were used to print this document."

(4) Do not add to the form any other symbol, word or phrase that might be

construed as personalizing the form or advertising on it.

(5) Except as specified above, do not delete from or add to any part of the form, or attach anything thereto.

(6) Assure that the form being reproduced is an edition currently acceptable by the Commission, which will endeavor to keep the public advised of revisions to its forms, but cannot assume responsibility to the extent of eliminating any element of risk against the use of obsolete forms.

(b) These guidelines do not apply to forms which respondents may wish to reproduce as completed facsimiles on automated equipment to satisfy application or report requirements. Requests for permission to submit such forms to the Commission should be addressed to the Office of Managing Director.

[53 FR 27861, July 25, 1988]

PRINTED PUBLICATIONS

§0.411 General reference materials.

The following reference materials are available in many libraries and may be purchased from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402:

§0.413

(a) *Statutory materials.* Laws pertaining to communications are contained in Title 47 of the United States Code. Laws enacted since the printing of the last supplement to the Code are printed individually as slip laws, and these are compiled chronologically in the United States Statutes at Large. The Acts of Congress from 1910-62 pertaining to radio have been compiled in a single volume, *Radio Laws of the United States* (1962 ed.). See §§0.405 and 0.414.

(b) *Regulatory materials*—(1) *The Code of Federal Regulations.* The rules and regulations of the Commission are contained in chapter I of title 47 of the Code of Federal Regulations. Chapter I is divided into the following four subchapters, which may be purchased separately: Subchapter A—General; Subchapter B—Common Carrier Services; Subchapter C—Broadcast Radio Services; and Subchapter D—Private Radio Services. Most persons will find that they need subchapter A, containing the general rules, and one of the other volumes, depending upon their area of interest. These four volumes are revised annually to reflect changes in the rules. See §§0.406, 0.412, and 0.415. The Code of Federal Regulations is fully indexed and contains numerous finding aids. See 1 CFR appendix C.

(2) *The Federal Register.* As rules are adopted, amended, or repealed, the changes are published in the FEDERAL REGISTER, which is published daily except on legal holidays. Notices of proposed rule making, other rule making documents, statements of general policy, interpretations of general applicability, and other Commission documents having general applicability and legal effect are also published in the FEDERAL REGISTER. Summaries of the full Notices of proposed rule making and other rule making decisions adopted by the Commission constitute rule-making documents for purposes of FEDERAL REGISTER publication. The FEDERAL REGISTER is fully indexed and contains numerous findings aids.

[32 FR 10571, July 19, 1967, as amended at 44 FR 39180, July 5, 1979; 51 FR 7444, Mar. 4, 1986]

§0.413 The Commission's printed publications.

The Commission's printed publications are described in §§0.414-0.420.

47 CFR Ch. I (10-1-97 Edition)

These publications may be purchased from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. The Commission does not furnish copies of these publications but will furnish a price list (Administration Bulletin No. 1) upon request. Requests for copies of that list should be directed to the Office of Public Affairs, Federal Communications Commission, Washington, D.C. 20554.

[32 FR 10571, July 19, 1967, as amended at 44 FR 39180, July 5, 1979]

§0.414 The Communications Act and other statutory materials.

This publication, with packets of revised pages, contains the Communications Act of 1934, with amendments through 1964; the Administrative Procedure Act, with amendments through 1964; the Judicial Review Act; the Communications Satellite Act of 1962; and selected sections of the Criminal Code pertaining to communications. It also contains indexes to the Communications Act and the Administrative Procedure Act. Persons who do not have ready access to the United States Code, or who refer frequently to these materials, may find this volume to be useful.

[32 FR 10571, July 19, 1967]

§0.415 The rules and regulations (looseleaf service).

(a) In this service, the rules are divided into 10 volumes, each containing several related parts. Each volume may be purchased separately from the Superintendent of Documents. The purchase price for a volume includes a subscription to replacement pages reflecting changes in the rules contained therein until such time as the volume is revised. Each volume is revised periodically, depending primarily on the frequency with which the rules it contains have been amended. When a volume is revised, the revised volume and replacement pages therefor will be furnished to those who renew their subscriptions.

(b) [Reserved]

[41 FR 21449, May 26, 1976, as amended at 45 FR 49935, July 28, 1980; 51 FR 31304, Sept. 2, 1986]

Federal Communications Commission

§0.431

§0.416 The Federal Communications Commission Record.

Texts adopted by the Commission or a member of its staff on delegated authority and made available to the public through the Office of Congressional and Public Affairs are published in the FCC Record. The FCC Record is published biweekly in pamphlet form. The pamphlets are available on a subscription basis from the Superintendent of Documents. Each biweekly pamphlet contains a table of contents and current index. A consolidated index is published on a periodic basis.

[51 FR 45889, Dec. 23, 1986]

§0.417 The Annual Reports.

At the end of each fiscal year, the Commission publishes an Annual Report containing general information concerning the Commission and the history of regulation, a summary of developments during the year, and selected industry statistics.

[32 FR 10571, July 19, 1967]

§0.420 Other Commission publications.

The following additional Commission publications may be purchased from the Superintendent of Documents:

(a) Statistics of Communications Common Carriers.

(b) Figure M-3, Estimated AM Ground Conductivity of the United States (set of two maps).

(c) Television Network Program Procurement Report, 2d Interim Report, Part 2, by the Office of Network Study.

[32 FR 10571, July 19, 1967, as amended at 44 FR 39180, July 5, 1979]

FORMS AND DOCUMENTS AVAILABLE
UPON REQUEST

§0.421 Application forms.

All forms for use in submitting applications for radio authorization, together with instructions and information as to filing such forms, may be obtained at the Washington offices of the Commission or at any of the field offices listed in §0.121. For information concerning the forms to be used and filing requirements, see subparts D, E, F,

and G, of part 1 of this chapter and the appropriate substantive rules.

[40 FR 17254, Apr. 18, 1975]

§0.422 Current action documents and public notices.

A limited number of copies of the text of documents adopted by the Commission, public notices of Commission actions, and other public releases is made available at the Press and News Media Division when they are issued. Back issues of public releases are available for inspection in this office.

(47 U.S.C. 154, 155, 303)

[36 FR 15121, Aug. 13, 1971, as amended at 44 FR 12425, Mar. 7, 1979; 44 FR 70471, Dec. 7, 1979]

§0.423 Information bulletins.

A number of bulletins containing information about communications and the Federal Communications Commission have been prepared by the Commission for distribution to the public. A listing of these bulletins is included in ED Bulletin No. 1, "FCC Publications". Requests for bulletins should be directed to the Press and News Media Division.

(47 U.S.C. 154, 155, 303)

[36 FR 15121, Aug. 13, 1971, as amended at 44 FR 12425, Mar. 7, 1979; 44 FR 70471, Dec. 7, 1979]

LISTS CONTAINING INFORMATION
COMPILED BY THE COMMISSION

§0.431 The FCC service frequency lists.

Lists of frequency assignments to radio stations authorized by the Commission are recapitulated periodically by means of an automated record system. All stations licensed by the Commission are included, except the following: Aircraft, amateur, personal (except General Mobile Radio Service), Civil Air Patrol, and disaster. The resulting documents, the FCC service frequency lists, consist of several volumes arranged by nature of service, in frequency order, including station locations, call signs and other technical particulars of each assignment. These documents are available for public inspection at each of the Commission's Compliance and Information Bureau

§0.433

field offices (see §0.121) and, in Washington, DC, in the Office of Engineering and Technology. Copies may be purchased from the Commission's duplicating contractor. See §0.465(a).

[42 FR 8326, Feb. 9, 1977, as amended at 44 FR 39180, July 5, 1979; 51 FR 12615, Apr. 14, 1986; 61 FR 8477, Mar. 5, 1996]

§0.433 The radio equipment lists.

Lists of type approved and type accepted equipment (the radio equipment lists) are prepared periodically by the Commission. These documents are available for public inspection at each of the Commission's Field Operations Bureau field offices (see §0.121) and in the Office of Engineering and Technology. Copies may be purchased from the Commission's duplicating contractor. See §0.465(a).

[40 FR 17255, Apr. 18, 1975, as amended at 44 FR 39180, July 5, 1979; 51 FR 12615, Apr. 14, 1986]

§0.434 Data bases and lists of authorized broadcast stations and pending broadcast applications.

Periodically the FCC makes available copies of its data bases and lists containing information about authorized broadcast stations, pending applications for such stations, and rule-making proceedings involving amendments to the TV and FM Table of Allotments. The data bases, and the lists prepared from the data bases, contain frequencies, station locations, and other particulars. The lists are available for public inspection at the FCC's Public Reference Room, Washington, DC. Paper copies of the lists may be purchased from the FCC's duplicating contractor; see §0.465(a). Microfiche copies of the lists and the data bases themselves may be obtained from:

National Technical Information Service (NTIS), 5285 Port Royal Road, Springfield, Virginia 22161.

(703) 487-4763 for data bases on magnetic tape.

(703) 487-4808 for data bases on diskette.

(703) 487-4630 for monthly subscription to microfiche lists.

(703) 487-4650 for one-time purchases of microfiche lists.

(a) For AM broadcast:

47 CFR Ch. I (10-1-97 Edition)

(1) Lists available only on paper from the Commission's duplicating contractor:

(i) Pending construction permit applications for new stations and changes in existing facilities in order by frequency.

(ii) Pending construction permit applications for new stations and changes in existing facilities in order by state and city.

(iii) Pending construction permit applications for new stations and changes in existing facilities in order by file number.

Complete lists are prepared approximately once each month, with updates at least once each week.

(2) Lists available only on microfiche from NTIS:

(i) AM stations in order by state (U.S. only); summary listing.

(ii) AM stations in order by frequency (U.S. only); summary listing.

(iii) AM stations in order by country and state; complete listing including all countries in Region 2, tower information, etc.

Complete lists are prepared approximately once each month; there are no updates.

(3) Copies of the AM Engineering Data Base are supplied to NTIS approximately once each month. NTIS refers to this as the "Broadcast AM Data Base."

(b) For FM Broadcast:

(1) Lists available only on paper from the Commission's duplicating contractor:

(i) FM stations (including translators) in order by state; complete lists available monthly, with updates at least once each week.

(ii) FM stations (including translators) in order by frequency; complete lists available monthly, with updates at least once each week.

(iii) Vacant FM channels and applications therefor in order by state; complete lists are available monthly; there are no updates.

(2) Lists available only on microfiche from NTIS:

(i) FM stations (including translators) in order by state.

(ii) FM stations (including translators) in order by frequency.

Federal Communications Commission

§0.442

Complete lists are prepared approximately once each month; there are no updates.

(3) Copies of the FM Engineering Data Base are supplied to NTIS approximately once each month. NTIS refers to this as the "Broadcast FM Data Base."

(c) For TV stations, the lists are arranged as follows:

(1) Authorized stations, pending construction permit applications, proposed rulemakings, and vacant channels in order of state and city. A complete list is prepared approximately once a month, with updates approximately each week.

(2) Vacant assignments and applications therefor. The list is in order by state and city. Complete lists are prepared approximately once a month; there are no updates.

(d) For TV broadcast translator stations, the lists contain authorized stations and pending construction permit applications for new stations and changes in existing facilities. There is one list arranged in order by state, city, and channel; and another list arranged in order by state, channel, and call. Complete lists are prepared approximately once a month, with updates each week.

(e) Users of the data bases and the lists prepared from the data bases are cautioned that the data bases and the lists are unofficial. They have been prepared for the convenience of the FCC's staff, and should not be relied on by the public because in some instances the data bases and the lists may not agree with the primary sources of information (e.g., official license documents, international notifications, actual applications, and the like). Action by the public, such as the filing of applications, should be based on the primary sources of information and not on the data bases or lists. If there are discrepancies between the primary sources of information and the data bases or lists, the former control.

(f) The United States and its officers, agents, and employees shall not be responsible or liable for any loss, expense, or damage arising from or inci-

dent to the use of either the data bases or the lists by the public.

[45 FR 41151, June 18, 1980, as amended at 53 FR 4412, Feb. 16, 1988]

PUBLIC INFORMATION AND INSPECTION OF RECORDS

§0.441 General.

Any person desiring to obtain information may do so by writing or coming in person to any of the Commission's offices. A broader range of information and more comprehensive information facilities are available at the Commission's main office in Washington, D.C., however, and inquiries of a general nature should ordinarily be submitted to that office.

[32 FR 10573, July 19, 1967]

§0.442 Disclosure to other Federal government agencies of information submitted to the Commission in confidence.

(a) The disclosure of records to other federal government agencies is generally governed by 44 U.S.C. 3512 and 3508(a) rather than the Freedom of Information Act. The acceptance of materials in confidence under §0.457 or §0.459 does not provide assurance against their disclosure to other agencies.

(b) Information submitted to the Commission in confidence pursuant to §0.457(c) (2) and (3), (d) and (g) or §0.459 will be disclosed to other agencies of the federal government upon request: *Provided* (1) Specific Commission assurances against such disclosure have not been given, (2) the other agency has established a legitimate need for the information, (3) disclosure is made subject to the provisions of 44 U.S.C. 3508(a), and (4) disclosure is not prohibited by the Privacy Act or other provisions of law.

(c) The Commission's staff may give assurances against disclosure of information to other federal agencies only with the prior written approval of the General Counsel. In no event will assurance against disclosure to other

§0.443

agencies be given in advance of submission of the information to the Commission if submission is required by statute or by the provisions of this chapter; but the notice provisions of paragraph (d) of this section will apply to such information.

(d)(1) Except as provided in paragraph (d)(2) of this section a party who furnished records to the Commission in confidence will be notified at the time that the request for disclosure is submitted and will be afforded 10 days in which to oppose disclosure.

(2) If the agency requesting the records states to the satisfaction of the Commission that notice to the party who furnished the records to the Commission will interfere unduly with its law enforcement activities and further states that it will notify that party of the Commission's disclosure once the potential for such interference is eliminated, the Commission will not give notice of disclosure.

(3) If notice is given to the party who furnished the records to the Commission in confidence and disclosure is not opposed, the staff is authorized to make the records available to the agency which requested them.

(4) If disclosure is opposed and the Commission decides to make the records available to the other agency, the party who furnished the records to the Commission will be afforded ten (10) working days from the date of the ruling in which to move for a judicial stay of the Commission's action. If he does not move for stay within this period, the records will be disclosed.

(e) Nothing in this section is intended to govern disclosure of information to Congress.

[44 FR 55573, Sept. 27, 1979; 44 FR 57096, Oct. 4, 1979]

§0.443 General information office.

The Press and News Media Division is located at 1919 M Street NW., Washington, D.C. Here the public may obtain copies of public notices of Commission actions, formal documents adopted by the Commission and other public releases as they are issued. Back issues of public releases are available for inspection in this office. Copies of fact sheets which answer general questions

47 CFR Ch. I (10–1–97 Edition)

about the Commission may be obtained from this office.

[36 FR 15121, Aug. 13, 1971, as amended at 44 FR 12425, Mar. 7, 1979; 44 FR 70471, Dec. 7, 1979]

§0.445 Publication, availability and use of opinions, orders, policy statements, interpretations, administrative manuals, and staff instructions.

(a) Adjudicatory opinions and orders of the Commission, or its staff acting on delegated authority, are mailed to the parties, and as part of the record, are available for inspection in accordance with §§0.453 and 0.455.

(b) Texts adopted by the Commission or a member of its staff on delegated authority and made available to the public through the Office of Congressional and Public Affairs are published in the FCC Record. Older materials of this nature are available in the FCC Reports. In the event that such older materials are not published in the FCC Reports, reference should be made to the FEDERAL REGISTER or Pike and Fischer Radio Regulation.

(c) All rulemaking documents are published in the FEDERAL REGISTER. Summaries of the full Notices of proposed rule making and other rule making decisions adopted by the Commission constitute rulemaking documents for purposes of FEDERAL REGISTER publication. See §1.412(a)(1). The complete text of the Commission decision also is released by the Commission and is available for inspection and copying during normal business hours in the FCC Dockets Branch (Room 230), 1919 M Street, NW., Washington, DC, or as otherwise specified in the rulemaking document published in the FEDERAL REGISTER. The complete texts of rulemaking decisions may also be purchased from the Commission's duplicating contractor.

(d) Formal policy statements and interpretations designed to have general applicability and legal effect are published in the FEDERAL REGISTER, the FCC Record, FCC Reports, or Pike and Fischer. Commission decisions and other Commission documents not entitled formal policy statements or interpretations may contain substantive interpretations and statements regarding policy, and these are published as part

Federal Communications Commission

§0.451

of the document in the FCC Record, FCC Reports or Pike and Fischer. General statements regarding policy and interpretations furnished to individuals, in correspondence or otherwise, are not ordinarily published.

(e) If the documents described in paragraphs (a) through (d) of this section are published in the FEDERAL REGISTER, the FCC Record, FCC Reports, or Pike and Fischer Radio Regulation, they may be relied upon, used or cited as precedent by the Commission or private parties in any manner. If they are not so published, they may not be relied upon, used or cited as precedent, except against persons who have actual notice of the document in question or by such persons against the Commission. No person is expected to comply with any requirement or policy of the Commission unless he has actual notice of that requirement or policy or a document stating it has been published as provided in this paragraph. Nothing in this paragraph, however, shall be construed as precluding a reference to the rationale set forth in a recent document that is pending publication if the requirement or policy to which the rationale relates is contained in a published document or if actual notice of that requirement or policy has been given.

(f) The FEDERAL REGISTER, the FCC Record, FCC Reports and Pike and Fischer Radio Regulation are indexed. If the documents described in paragraphs (a)–(d) of this section are not published, they are neither indexed nor relied upon, except as provided in paragraph (e) of this section.

(g) There are two Commission staff manuals, the FCC Administrative Manual and the CIB Manual. The FCC Administrative Manual (excepting Part IX, concerning Civil Defense, which contains materials classified under E.O. 10501) is available for inspection in the Office of the Managing Director. Portions of the CIB Manual which pertain to administrative matters are available for inspection in the Compliance and Information Bureau. Portions of the CIB Manual which pertain to enforcement matters are not available for inspection. The Manuals are not indexed but are organized by subject, with tables of contents, and the mate-

rials contained therein can be located without difficulty.

(h) Subparts A and B of this part describe the functions of the staff and list the matters on which authority has been delegated to the staff. Except as provided in paragraph (g) of this section, all general instructions to the staff and limitations upon its authority are set forth in those subparts. As part of the Commission's rules and regulations, the provisions of these subparts are indexed in the FEDERAL REGISTER and the Code of Federal Regulations. Instructions to the staff in particular matters or cases are privileged and are not published or made available for public inspection.

(i) To the extent required to prevent a clearly unwarranted invasion of personal privacy, the Commission may delete identifying details when it makes available or publishes any document described in this section. The justification for any such deletion will be fully explained in a preamble to the document.

[32 FR 10573, July 19, 1967, as amended at 40 FR 17255, Apr. 18, 1975; 50 FR 27953, July 9, 1985; 51 FR 7444, Mar. 4, 1986; 51 FR 45889, Dec. 23, 1986; 61 FR 8477, Mar. 5, 1996]

§0.451 Inspection of records: Generally.

(a) *Records which are routinely available for public inspection.* Sections 0.453 and 0.455 list those Commission records which are routinely available for public inspection and the places at which those records may be inspected. Procedures governing requests for inspection of such records are set out in §0.460.

(b) *Records which are not routinely available for public inspection.* Records which are not listed in §0.453 or §0.455 are not routinely available for public inspection. Such records fall into two categories.

(1) The first category consists of those records or kinds of records listed in §0.457 and of particular records withheld from public inspection under §0.459. The Commission has determined that there is a statutory basis for withholding these records from public inspection. In some cases, the Commission is prohibited from permitting the inspection of records. In other cases, the records are the property of another

§0.453

47 CFR Ch. I (10–1–97 Edition)

agency, and the Commission has no authority to permit their inspection. In still other cases, the Commission is authorized, for reason of policy, to withhold records from inspection, but is not required to do so.

(2) The second category consists of records which are not listed in §0.453, §0.455, or §0.457 and have not been withheld from inspection under §0.459. In some cases, these records have not been identified for listing. In other cases (e.g., the general correspondence files), the Commission is unable to determine either that all records in a class should be routinely available for inspection or that all records in that class should not be routinely available for inspection, and individual determination is required.

(3) Procedures governing requests for inspection of these records are set out in §0.461.

(4) Procedures governing demands by competent authority for inspection of these records are set out in §0.463.

(5) Except as provided in §§0.461 and 0.463, no officer or employee of the Commission shall permit the inspection of records which are not routinely available for public inspection under §0.453 or §0.455, or disclose information contained therein.

(c) *Copies.* Section 0.465 applies to requests for copies of Commission records which are routinely available for public inspection under §§0.453 and 0.455 and those which are made available for inspection under §0.461. Section 0.467 applies to requests for certified copies of Commission records.

(d) *Search fees.* Section 0.466 prescribes fees to cover the expense of searching for records made available for inspection under §0.460 or §0.461.

[40 FR 7313, Feb. 19, 1975]

§0.453 Public reference rooms.

The Commission maintains the following public reference rooms at its offices in Washington, DC and Gettysburg, Pennsylvania. With the exception of the Private Radio Bureau Reference Room, which is located in Gettysburg, Pennsylvania, all reference rooms are located in Washington, DC:

(a) *The FCC Reference Center.* The following documents, files and records are

available for inspection at this location.

(1) Files containing the record of all docketed cases. A file is maintained for each docketed hearing case and for each docketed rule making proceeding. Cards summarizing the history of such cases are available for inspection.

(2) Broadcast applications and related files.

(3) Files containing petitions for rule making and related papers.

(b) [Reserved]

(c) *The Library.* Various legal and technical publications, and legislative history compilations, related to communications are available for inspection in the Library.

(d) *The Mass Media Bureau, Auxiliary Services Reference Room.* The following documents, files and records are available for inspection at this location.

(1) FM Translator applications and related files.

(2) FM Booster station applications and related files.

(e) *The Mass Media Bureau, Enforcement Division Reference Room.* The following documents, files and records are available for inspection at this location.

(1) Station files containing Notice of Apparent Liability and Memorandum of Opinion and Order and related files.

(2) Congressional correspondence files and related materials.

(3) Network correspondence files and related materials.

(f) *The Common Carrier Bureau, Accounting and Audits Reference Room.* The following documents, files and records are available for inspection at this location.

(1) Files containing contracts between carriers and affiliates, accounts and subaccounts, pension filings, property records, disposition units, and depreciation rate filings.

(2) Computer II files and related materials.

(3) Official correspondence files which include waiver requests and interpretations and related files.

(4) Docket 86–111 Implementation filings containing Cost Allocation Manuals and related materials.

(g) *The Common Carrier Bureau, Domestic Facilities Reference Room.* The following documents, files and records are

Federal Communications Commission

§0.453

available for inspection at this location.

(1) Microwave Point-to-Point and Digital Electronic Message Service (DEMS) application files and related materials.

(2) Section 214 applications and related files, to the extent that they concern domestic communications facilities and services.

(h) *The Common Carrier Bureau, Mobile Services Reference Room.* The following documents, files and records are available for inspection at two different locations. The Legal Branch is the responsible custodian for both locations.

(1) Station files containing a complete history of data submitted by the applicant that has been approved by the Commission which includes maps, diagrams, petitions, co-channel searches, and other background material.

(2) Pending files containing applications for additional facilities or modifications of existing facilities.

(3) Cellular Granted Station files and related materials.

(4) Pending cellular applications and related files.

(5) Petitions and related materials.

(i) *The Common Carrier Bureau, Industry Analysis Reference Room.* The following documents, files and records are available for inspection at this location.

(1) Files containing reports required by FCC Rules and Regulations, annual reports to stockholders, administrative reports, monthly bypass reports and related materials.

(2) Files containing reference material from major telephone companies.

(3) Files containing Local Exchange Rates and related files.

(j) *The Common Carrier Bureau Reference Room, Tariff Review Reference Room.* Contains currently effective tariffs filed by Communications Common Carriers pursuant to various FCC Rules and Regulations. Also available for review and copying are recent revisions to tariff filings and the Public Reference Room Log which is prepared daily and lists the tariff filings received the previous day.

(k) *The Office of Engineering and Technology, FCC Laboratory Reference Room.*

The following documents, files and records are available for inspection at this location. Files containing approved applications for Equipment Authorization (Type accepted, type approved, certified and notified) and related materials are available for review. These files are available in the Commission's Laboratory in Columbia, Maryland.

(l) *The Private Radio Bureau Reference Room.* Commercial radio operator application files and all authorizations in the Private Radio Services and files relating thereto, which includes Land Mobile, Microwave, Aviation Ground and Marine Coast applications. All of these materials are available in the Commission's offices in Gettysburg, Pennsylvania. See §0.457(f)(3). This reference room also contains station files containing applications and related materials for Remote Pickup, Aural STL/ICR, TV Auxiliary, and Low Power Auxiliary Stations in the Mass Media services. This reference room also contains station files containing applications and related materials for the Point-to-Point Microwave (including the Local Television Transmission Service) and Digital Electronic Message (DEMS) services in the Common Carrier services. Cards summarizing the historical record of applications and dispositions of the Broadcast Auxiliary service through May 1982 are available for inspection as well.

(m) *The International Bureau Reference Room.* Except to the extent they are excluded from routine public inspection under another section of this chapter, the following documents, files, and records are available for inspection at this location:

(1) Satellite and earth station applications files and related materials under parts 25 and 100 of this chapter;

(2) Section 214 applications and related files under part 63 of this chapter, to the extent that they concern international communications facilities and services;

(3) International Fixed Public Radio applications and related files under part 23 of this chapter;

(4) Files relating to submarine cable landing licenses and applications for such licenses since June 30, 1934, except for maps showing the exact location of

§0.455

47 CFR Ch. I (10–1–97 Edition)

submarine cables, which are withheld from inspection under section 4(j) of the Communications Act (see §0.457(c)(1)(i));

(5) Files relating to international settlements under part 64 of this chapter;

(6) Documents relating to INTELSAT or INMARSAT;

(7) International broadcast applications, applications for permission to deliver programming to foreign stations, and related files under part 73 of this chapter; and

(8) International settlement agreements and contracts and international cable agreements.

(n) *The Cable Services Bureau Reference Center*. The following documents, files and records are available for inspection at this location.

(1) All complaints regarding cable programming rates, all documents filed in connection therewith, and all communications related thereto, unless the cable operator has submitted a request pursuant to §0.459 that such information not be made routinely available for public inspection.

(2) All cable operator requests for approval of existing or increased cable television rates for basic service and associated equipment over which the Commission has assumed jurisdiction, all documents filed in connection therewith, and all communications related thereto, unless the cable operator has submitted a request pursuant to §0.459 that such information not be made routinely available for public inspection.

(3) Special relief petitions and files pertaining to cable television operations.

(4) Cable television system reports filed by operators pursuant to §76.403 of this chapter.

[32 FR 10573, July 19, 1967, as amended at 36 FR 15121, Aug. 13, 1971; 46 FR 27655, May 21, 1981; 50 FR 40014, Oct. 1, 1985; 52 FR 38764, Oct. 19, 1987; 58 FR 19772, Apr. 16, 1993; 59 FR 32132, June 22, 1994; 59 FR 38374, July 28, 1994; 60 FR 5325, Jan. 27, 1995; 60 FR 35507, July 10, 1995]

§0.455 Other locations at which records may be inspected.

Except as provided in §§0.453, 0.457, and 0.459, records are routinely available for inspection in the offices of the Bureau or Office which exercises re-

sponsibility over the matters to which those records pertain (see §0.5), or will be made available for inspection at those offices upon request. Upon inquiry to the appropriate Bureau or Office, persons desiring to inspect such records will be directed to the specific location at which the particular records may be inspected. A list of Bureaus and Offices and examples of the records available at each is set out below.

(a) *Mass Media Bureau*. (1) Applications for broadcast authorizations and related files are available for public inspection in the FCC Reference Center. See §0.453(a)(2). Certain broadcast applications, reports and records are also available for inspection in the community in which the station is located or is proposed to be located. See §§73.3526 and 73.3527 of this chapter.

(2) Ownership reports filed by licensees of broadcast stations pursuant to §73.3615.

(3) Network affiliation contracts between stations and networks (for television stations only).

(4) Contracts relating to network service to broadcast licensees filed on or after the 1st day of May 1969 under §73.3613.

(5) Annual employment reports filed by licensees and permittees of broadcast stations pursuant to §73.3612 of this chapter and cable television systems pursuant to §76.77 of this chapter.

(6) Contract files which contain pledges, trust agreements, options to purchase stock agreements, partnership agreements, management consultant agreements, and mortgage or loan agreements.

(7) Rulings under the Fairness Doctrine and section 315 of the Communications Act, and related materials.

(8) Ruling lists which contain brief summaries of rulings.

(9) Files containing Station History cards for stations in existence prior to 1982.

(b) *Common Carrier Bureau* which includes the *Formal Complaints and Investigations Branch* and the *Informal Complaints and Public Inquiries Branch*. (1) Annual reports filed by carriers under §43.21 of this chapter.

(2) Monthly reports filed by carriers under §43.31 of this chapter.

Federal Communications Commission

§0.457

(3) Reports on pensions and benefits filed by carriers under §43.42 of this chapter.

(4) Reports of proposed changes in depreciation rates filed by carriers under §43.43 of this chapter.

(5) Reports regarding division of international telegraph communications charges filed under §43.53 of this chapter.

(6) Reports regarding services performed by telegraph carriers filed under §43.54 of this chapter.

(7) Reports of public coast station operators filed under §43.71 of this chapter.

(8) Valuation reports filed under section 213 of the Communications Act, including exhibits filed in connection therewith, unless otherwise ordered by the Commission, with reasons therefor, pursuant to section 213(f) of the Communications Act. See §0.457(c)(2).

(9) A list of other reports filed by common carriers.

(10) Contracts and other arrangements filed under §43.51 and reports of negotiations regarding foreign communication matters filed under §43.52 of this chapter, except for those kept confidential by the Commission pursuant to section 412 of the Communications Act. See §0.457(c)(3).

(11) Tariff schedules for all charges for interstate and foreign wire or radio communications filed pursuant to section 203 of the Communications Act, all documents filed in connection therewith, and all communications related thereto.

(12) All applications for common carrier authorizations acted upon by the Common Carrier Bureau, and files relating thereto.

(13) All formal and informal complaints against common carriers filed under §§1.711 through 1.735 of this chapter, all documents filed in connection therewith, and all communications related thereto.

(14) Annual employment reports filed by common carrier licensees or permittees pursuant to §1.815 of this chapter.

(15) Enforcement proceedings and public inquiries and related materials.

(c) *Office of Managing Director.* (1) All minutes of Commission actions, containing a record of all final votes, minutes of actions and internal manage-

ment matters as provided in §0.457(b)(1) and (c)(1)(i). These records and files are available for inspection in the Agenda Branch.

(2) Files containing information concerning the history of the Commission's rules. These files are available for inspection in the Publications Branch.

(3) See §0.443.

(4) Reports filed pursuant to subpart E of part 19 of this chapter and applications for inspection of such reports. See §0.460(k).

(d) *Cable Services Bureau.* Correspondence and other actions and decisions relating to cable television services that are not filed in the FCC Reference Center.

(e) *Office of Engineering and Technology* which includes the Bureau's *Technical Library* containing technical reports, technical journals, and bulletins of spectrum management and related technical materials. (1) Experimental application and license files.

(2) The Master Frequency Records.

(3) Applications for Equipment Authorization (type accepted, type approval, certification, or advance approval of subscription television systems), following the effective date of the authorization. See §0.457(d)(1)(ii). (Application files, technical journals and other technical materials are maintained at the Commission's Laboratory at Columbia, Maryland.)

(f) *The Commission's offices in Gettysburg, Pennsylvania.* See §0.453(1) of the this chapter.

(g) *International Bureau.* The treaties and other international and bilateral agreements listed in §73.1650 of this chapter are available for inspection in the office of the Chief, Planning and Negotiations Division, International Bureau.

[52 FR 38765, Oct. 19, 1987; 52 FR 40020, Oct. 26, 1987, as amended at 58 FR 13021, Mar. 9, 1993; 58 FR 29752, May 21, 1993; 59 FR 32133, June 22, 1994; 60 FR 5325, Jan. 27, 1995]

§0.457 Records not routinely available for public inspection.

The records listed in this section are not routinely available for public inspection. The records are listed in this section by category, according to the statutory basis for withholding those

records from inspection; and under each category, if appropriate, the underlying policy considerations affecting the withholding and disclosure of records in that category are briefly outlined. Except where the records are not the property of the Commission or where the disclosure of those records is prohibited by law, the Commission will entertain requests from members of the public under §0.461 for permission to inspect particular records withheld from inspection under the provisions of this section, and will weigh the policy considerations favoring non-disclosure against the reasons cited for permitting inspection in the light of the facts of the particular case. In making such requests, it is important to appreciate that there may be more than one basis for withholding particular records from inspection. The listing of records by category is not intended to imply the contrary but is solely for the information and assistance of persons making such requests. Requests to inspect or copy the transcripts, recordings or minutes of agency or advisory committee meetings will be considered under §0.603 rather than under the provisions of this section.

(a) *Materials that are specifically authorized under criteria established by Executive Order to be kept secret in the interest of national defense or foreign policy and are in fact properly classified pursuant to such Executive Order, 5 U.S.C. 552(b)(1).* (1) E.O. 10450, “Security Requirements for Government Employees,” 18 FR 2489, April 27, 1953, 3 CFR, 1949–1953 Comp., p. 936. Pursuant to the provisions of E.O. 10450, reports and other material and information developed in security investigations are the property of the investigative agency. If they are retained by the Commission, it is required that they be maintained in confidence and that no access be given to them without the consent of the investigative agency. Such materials and information will not be made available for public inspection. See also paragraphs (f) and (g) of this section.

(2) E.O. 10501, “Safeguarding Official Information in the Interests of the Defense of the United States,” 18 FR 7049, November 10, 1953, as amended, 3 CFR, 1965 ed., p. 450. E.O. 10501, as amended,

provides for the classification of official information which requires protection in the interests of national defense, and prohibits the disclosure of classified information except as provided therein. Classified materials and information will not be made available for public inspection. See also, E.O. 10033, February 8, 1949, 14 FR 561, 3 CFR, 1949–1953 Comp., p. 226, and 47 U.S.C. 154(j).

(b) *Materials that are related solely to the internal personnel rules and practices of the Commission, 5 U.S.C. 552(b)(2).* (1) Materials related solely to internal management matters, including minutes of Commission actions on such matters. Such materials may be made available for inspection under §0.461, however, unless their disclosure would interfere with or prejudice the performance of the internal management functions to which they relate, or unless their disclosure would constitute a clearly unwarranted invasion of personal privacy (see paragraph (f) of this section).

(2) Materials relating to the negotiation of contracts.

(3) All materials used in conducting radio operator examinations, including test booklets, Morse Code tapes, and scoring masks.

(c) Materials that are specifically exempted from disclosure by statute (other than the Government in the Sunshine Act, 5 U.S.C. 552b): *Provided*, That such statute (1) requires that the materials be withheld from the public in such a manner as to leave no discretion on the issue, or (2) establishes particular criteria for withholding or refers to particular types of materials to be withheld. The Commission is authorized under the following statutory provisions to withhold materials from public inspection.

(1) Section 4(j) of the Communications Act, 47 U.S.C. 154(j), provides, in part, that, “The Commission is authorized to withhold publication of records or proceedings containing secret information affecting the national defense.” Pursuant to that provision, it has been determined that the following materials should be withheld from public inspection (see also paragraph (a) of this section):

Federal Communications Commission

§0.457

(i) Maps showing the exact location of submarine cables.

(ii) Minutes of Commission actions on classified matters.

(iii) Maps of nation-wide point-to-point microwave networks.

(2) Under section 213(f) of the Communications Act, 47 U.S.C. 213(f), the Commission is authorized to order, with the reasons therefor, that records and data pertaining to the valuation of the property of common carriers and furnished to the Commission by the carriers pursuant to the provisions of that section, shall not be available for public inspection. If such an order has been issued, the data and records will be withheld from public inspection, except under the provisions of §0.461. Normally, however, such data and information is available for inspection. See §0.455(c) (8).

(3) Under section 412 of the Communications Act, 47 U.S.C. 412, the Commission may withhold from public inspection certain contracts, agreements and arrangements between common carriers relating to foreign wire or radio communication. Reports of negotiations regarding such foreign communication matters, filed by carriers under §43.52 of this chapter, may also be withheld from public inspection under section 412. Any person may file a petition requesting that such materials be withheld from public inspection. To support such action, the petition must show that the contract, agreement or arrangement relates to foreign wire or radio communications; that its publication would place American communication companies at a disadvantage in meeting the competition of foreign communication companies; and that the public interest would be served by keeping its terms confidential. If the Commission orders that such materials be kept confidential, they will be made available for inspection only under the provisions of §0.461.

(4) Section 605 of the Communications Act, 47 U.S.C. 605, provides, in part, that, “no person not being authorized by the sender shall intercept any communication [by wire or radio] and divulge or publish the existence, contents, substance, purport, effect, or meaning of such intercepted commu-

nications to any person.” In executing its responsibilities, the Commission regularly monitors radio transmissions (see §0.116). Except as required for the enforcement of the communications laws, treaties and the provisions of this chapter, or as authorized in section 605, the Commission is prohibited from divulging information obtained in the course of these monitoring activities; and such information, and materials relating thereto, will not be made available for public inspection.

(5) Section 1905 of the Criminal Code, 18 U.S.C. 1905, prohibits the unauthorized disclosure of certain confidential information. See paragraph (d) of this section.

(d) *Trade secrets and commercial or financial information obtained from any person and privileged or confidential*, 5 U.S.C. 552(b)(4) and 18 U.S.C. 1905. Section 552(b)(4) is specifically applicable to trade secrets and commercial or financial information but is not limited to such matters. Under this provision, the Commission is authorized to withhold from public inspection materials which would be privileged as a matter of law if retained by the person who submitted them, and materials which would not customarily be released to the public by that person, whether or not such materials are protected from disclosure by a privilege. See, Attorney General’s Memorandum on the Public Information Section of the Administrative Procedure Act, June 1967, at pages 32–34.

(1) The materials listed in this subparagraph have been accepted, or are being accepted, by the Commission on a confidential basis pursuant to 5 U.S.C. 552(b)(4). To the extent indicated in each case, the materials are not routinely available for public inspection. If the protection afforded is sufficient, it is unnecessary for persons submitting such materials to submit therewith a request for non-disclosure pursuant to §0.459. A persuasive showing as to the reasons for inspection will be required in requests for inspection of such materials submitted under §0.461.

(i) Financial reports submitted by licensees of broadcast stations pursuant to §1.611 of this chapter or by radio and television networks are not routinely available for public inspection. (Fees

§0.457**47 CFR Ch. I (10–1–97 Edition)**

paid upon consummation of the assignment or transfer of a broadcast station license, pursuant to §1.1111 of this chapter, are computed from information contained in financial reports submitted pursuant to §1.611. Information and correspondence concerning such computations are not routinely available for public inspection.)

(ii) Applications for equipment authorizations (type acceptance, type approval, certification, or advance approval of subscription television systems), and materials relating to such applications, are not routinely available for public inspection prior to the effective date of the authorization. The effective date of the authorization will, upon request, be deferred to a date no earlier than that specified by the applicant. Following the effective date of the authorization, the application and related materials (including technical specifications and test measurements) will be made available for inspection upon request (see §0.460).

(iii) Schedules 2, 3, and 4 of financial reports submitted for cable television systems pursuant to §76.403 of this chapter.

(iv) Annual fee computation forms submitted for cable television systems pursuant to §76.406 of this chapter.

(2) Prior to July 4, 1967, the rules and regulations provided that certain materials submitted to the Commission would not be made available for public inspection or provided assurance, in varying degrees, that requests for non-disclosure of certain materials would be honored. See, e.g., 47 CFR (1966 ed.) 0.417, 2.557, 5.204, 5.255, 15.70, 21.406, 80.33, 87.153, 89.215, 91.208, 91.605 and 93.208. Materials submitted under these provisions are not routinely available for public inspection. To the extent that such materials were accepted on a confidential basis under the then existing rules, they are not routinely available for public inspection. The rules cited in this subdivision were superseded by the provisions of this paragraph, effective July 4, 1967. Equipment authorization information accepted on a confidential basis between July 4, 1967 and March 25, 1974, will not be routinely available for inspection and a persuasive showing as to the reasons for inspection of such information will

be required in requests for inspection of such materials submitted under §0.461.

(i) Unless the materials to be submitted are listed in paragraph (d)(1) of this section and the protection thereby afforded is adequate, it is important for any person who submits materials which he wishes withheld from public inspection under 5 U.S.C. 552(b)(4) to submit therewith a request for non-disclosure pursuant to §0.459. If it is shown in the request that the materials contain trade secrets or commercial, financial or technical data which would customarily be guarded from competitors, the materials will not be made routinely available for inspection; and a persuasive showing as to the reasons for inspection will be required in requests for inspection submitted under §0.461. In the absence of a request for non-disclosure, the Commission may, in the unusual instance, determine on its own motion that the materials should not be routinely available for public inspection. Ordinarily, however, in the absence of such a request, materials which are submitted will be made available for inspection upon request pursuant to §0.461, even though some question may be present as to whether they contain trade secrets or like matter.

(e) *Interagency and intra-agency memorandums or letters*, 5 U.S.C. 552(b)(5). Interagency and intra-agency memorandums or letters and the work papers of members of the Commission or its staff will not be made available for public inspection, except in accordance with the procedures set forth in §0.461. Only if it is shown in a request under §0.461 that such a communication would be routinely available to a private party through the discovery process in litigation with the Commission will the communication be made available for public inspection. Normally such papers are privileged and not available to private parties through the discovery process, since their disclosure would tend to restrain the commitment of ideas to writing, would tend to inhibit communication among Government personnel, and would, in some cases, involve premature disclosure of their contents.

Federal Communications Commission

§0.459

(f) *Personnel, medical and other files whose disclosure would constitute a clearly unwarranted invasion of personal privacy, 5 U.S.C. 552(b)(6).* (1) Under Executive Order 10561, 19 FR 5963, September 13, 1954, 3 CFR, 1954–1958 Comp., page 205, the Commission maintains an Official Personnel Folder for each of its employees. Such folders are under the jurisdiction and control, and are a part of the records, of the U.S. Office of Personnel Management. Except as provided in the rules of the Office of Personnel Management (5 CFR 294.701–294.703), such folders will not be made available for public inspection by the Commission. In addition, other records of the Commission containing private, personal or financial information concerning particular employees will be withheld from public inspection.

(2) [Reserved]

(3) Information submitted to the Commission by applicants for commercial radio operator licenses concerning the character and mental or physical health of the applicant is available for inspection only under procedures set forth in §0.461. Except in this respect, or where other aspects of a similar private nature warrant nondisclosure, commercial radio operator application files are available for inspection.

(g) *Investigatory records compiled for law enforcement purposes, to the extent that production of such records would:*

(1) Interfere with enforcement proceedings;

(2) Deprive a person of a right to fair trial or an impartial adjudication;

(3) Constitute an unwarranted invasion of personal privacy;

(4) Disclose the identity of a confidential source;

(5) Disclose investigative techniques or procedures; or

(6) Endanger the life or physical safety of law enforcement personnel, 5 U.S.C. 552(b)(7).

[32 FR 10573, July 19, 1967, as amended at 32 FR 12180, Aug. 24, 1967; 39 FR 5918, Feb. 14, 1974; 39 FR 27802, Aug. 1, 1974; 40 FR 7313, Feb. 19, 1975; 40 FR 17255, Apr. 18, 1975; 40 FR 34116, Aug. 14, 1975; 40 FR 39507, Aug. 28, 1975; 42 FR 12867, Mar. 7, 1977; 43 FR 51794, Nov. 7, 1978; 45 FR 39850, June 12, 1980; 51 FR 31304, Sept. 2, 1986]

§0.459 Requests that materials or information submitted to the Commission be withheld from public inspection.

(a) Any person submitting information or materials to the Commission may submit therewith a request that such information not be made routinely available for public inspection. (If the materials are specifically listed in §0.457, such a request is unnecessary.) A copy of the request shall be attached to and shall cover all of the materials to which it applies and all copies of those materials. If feasible, the materials to which the request applies shall be physically separated from any materials to which the request does not apply; if this is not feasible, the portion of the materials to which the request applies shall be identified.

(b) Each such request shall contain a statement of the reasons for withholding the materials from inspection (see §0.457) and of the facts upon which those reasons are based. If the request is that the materials be withheld from inspection for a limited period of time, that period shall be specified.

(c) Casual requests which do not comply with the requirements of paragraphs (a) and (b) of this section will not be considered.

(d) Requests which comply with the requirements of paragraphs (a) and (b) of this section will be acted on by the appropriate Bureau or Office Chief, who is directed to grant the request if it presents by a preponderance of the evidence a case for non-disclosure consistent with the provisions of the Freedom of Information Act, 5 U.S.C. 552. If the request is granted, the ruling will be placed in a public file in lieu of the materials withheld from public inspection. A copy of the ruling shall be forwarded to the General Counsel.

(e) If the materials are submitted voluntarily (i.e., absent any direction by the Commission), the person submitting them may request the Commission to return the materials without consideration if the request for confidentiality should be denied. In that event, the materials will ordinarily be returned (e.g., an application will be returned if it cannot be considered on a confidential basis); only in the unusual instance where the public

§0.460

47 CFR Ch. I (10–1–97 Edition)

interest so requires will the materials be made available for public inspection. If submission of the materials is required by the Commission and the request for confidentiality is denied, the materials will be made available for public inspection.

(f) If no request for confidentiality is submitted, the Commission assumes no obligation to consider the need for non-disclosure but, in the unusual instance, may determine on its own motion that the materials should be withheld from public inspection. See §0.457(g).

(g) If a request for confidentiality is denied, the person who submitted the request may, within 5 working days, file an application for review by the Commission. If the application for review is denied, the person who submitted the request will be afforded 5 working days in which to seek a judicial stay of the ruling. If these periods expire without action by the person who submitted the request, the materials will be returned to the person who submitted them or will be placed in a public file. Notice of denial and of the time for seeking review or a judicial stay will be given by telephone, with follow-up notice in writing. The first day to be counted in computing the time periods established in this subsection is the day after the date of oral notice.

(h) If the request is granted, the status of the materials is the same as that of materials listed in §0.457. Any person wishing to inspect them may submit a request for inspection under §0.461.

[40 FR 7313, Feb. 19, 1975, as amended at 49 FR 21719, May 23, 1984; 55 FR 8951, Mar. 9, 1990]

§0.460 Requests for inspection of records which are routinely available for public inspection.

(a) Sections 0.453 and 0.455 list those Commission records which are routinely available for public inspection and the places at which those records may be inspected. Subject to the limitations set out in this section and to the provisions of §0.466 and paragraph (k) of this section, a person who wants to inspect such records need only appear at the specified location and ask to see the records.

(b) A person who does not want a copy of the records must appear at the specified location during the office hours of the Commission and must inspect the records at that location. (Procedures governing requests for copies are set out in §0.465.) However, arrangements may be made in advance, by telephone or by correspondence, to make the records available for inspection on a particular date, and there are many circumstances in which such advance arrangements will save inconvenience. If the request is for a large number of documents, for example, a delay in collecting them is predictable. Current records may be in use by the staff when the request is made. Older records may have been forwarded to another location for storage.

(c) The records in question must be reasonably described by the person requesting them so as to permit their location by staff personnel. The information needed to locate the records will vary, depending on the records requested. Advice concerning the kind of information needed to locate particular records will be furnished in advance upon request. Members of the public will not be given access to the area in which records are kept and will not be permitted to search the files.

(d) If it appears that there will be an appreciable delay in locating or producing the records (as where a large number of documents is the subject of a single request or where an extended search for a document appears to be necessary), the request shall be submitted in writing, either in person or by mail.

(e) Written requests shall be captioned "REQUEST FOR INSPECTION OF RECORDS", shall be dated, shall list the telephone number (if any) of the person making the request and for each document requested, shall set out all information known to the person making the request which would be helpful in identifying and locating the document. Written requests shall, in addition, specify the maximum search fee the person making the request is prepared to pay. (see §0.467)

(f) Written requests shall be delivered or mailed directly to the chief of the organizational unit having custody of the records, as listed in §§0.453 and

Federal Communications Commission

§0.461

0.455. If the request is enclosed in an envelope, the envelope shall be marked, "REQUEST FOR INSPECTION OF RECORDS."

(g) When a written request is received by the custodian of the records, it will be date-stamped.

(h) All requests limited to records listed in §§0.453 and 0.455 will be granted, subject to paragraph (k) of this section. Requests for records listed in those sections shall not be combined with requests for other records.

(i) The records will be produced for inspection at the earliest possible time.

(j) Records shall be inspected within 7 days after notice is given that they have been located and are available for inspection. After that period, they will be returned to storage and additional charges may be imposed for again producing them.

(k) In addition to the other requirements of this section, the following provisions apply to the reports filed with the Commission pursuant to subpart E of part 19 of this chapter. (1) Such reports shall not be obtained or used:

(i) For any unlawful purpose; (ii) for any commercial purpose, other than by news and communications media for dissemination to the general public; (iii) for determining or establishing the credit rating of any individual; or (iv) for use, directly or indirectly, in the solicitation of money for any political, charitable, or other purpose.

(2) Such reports may not be made available to any person nor may any copy thereof be provided to any person except upon a written application by such person stating: (i) That person's name, occupation and address; (ii) the name and address of any other person or organization on whose behalf the inspection or copying is requested; and (iii) that such person is aware of the prohibitions on the obtaining or use of the report. Further, any such application for inspection shall be made available to the public throughout the period during which the report itself is made available to the public.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 397; 18 U.S.C. 207(j))

[40 FR 7314, Feb. 19, 1975, as amended at 45 FR 85027, Dec. 24, 1980; 48 FR 44800, Sept. 30, 1983; 53 FR 39093, Oct. 5, 1988]

§0.461 Requests for inspection of materials not routinely available for public inspection.

Any person desiring to inspect Commission records which are not listed in §0.453 or §0.455 shall file a request for inspection meeting the requirements of this section.

(a) The records in question must be reasonably described by the person requesting them, so as to permit their location by staff personnel. See §0.460(c).

(b)(1) Requests shall be captioned "Freedom of Information Act Request," shall be dated, shall list the telephone number (if any) of the person making the request and, for each document requested, shall set out all information known to the person making the request which would be helpful in identifying and locating the document.

(2) The request shall, in addition, specify the maximum search fee the person making the request is prepared to pay (see §0.467).

(c) If the records are of the kinds listed in §0.457 or if they have been withheld from inspection under §0.459, the request shall, in addition, contain a statement of the reasons for inspection and the facts in support thereof. In the case of other materials, no such statement need accompany the request; but the custodian of the records may require the submission of such a statement if he determines that the materials in question may lawfully be withheld from inspection.

(d)(1) Requests shall be delivered or mailed to the Managing Director. (For purposes of this section, the custodian of the records is the Chief of the appropriate Bureau or Office.)

(2) If the request is enclosed in an envelope, the envelope shall be marked, "Freedom of Information Act Request."

(3) An original and two copies of the request shall be submitted. If the request is for materials not open to routine public inspection under §0.457(d) or

§0.461

47 CFR Ch. I (10–1–97 Edition)

§0.459, one copy of the request will be mailed by the custodian of the records to the person who originally submitted the materials to the Commission.

(e) When the request is received by the Managing Director, it will be assigned to the Freedom of Information Act (FOIA) Control Office, where it will be date-stamped and assigned to the custodian of the records.

(f) Requests for inspection of records will be acted on as follows by the custodian of the records.

(1) If the Commission is prohibited from disclosing the records in question, the request for inspection will be denied with a statement setting forth the specific grounds for denial.

(2) If the records are the property of another agency, the request will be referred to that agency and the person who submitted the request will be so advised, with the reasons therefor.

(3) If it is determined that the Commission does not have authority to withhold the records from public inspection, the request will be granted.

(4) If it is determined that the Commission does have authority to withhold the records from public inspection, the considerations favoring disclosure and non-disclosure will be weighed in light of the facts presented, and the request will be granted, either conditionally or unconditionally, or denied.

(5) If there is a statutory basis for withholding part of a document only from inspection, that part will be deleted and the remainder will be made available for inspection.

(6) In locating and recovering records responsive to a FOIA request, only those records within the Commission's possession and control as of the date of its receipt of the request shall be considered.

(g) The custodian of the records will make every effort to act on the request within 10 working days after it is received by the FOIA Control Office. If it is not possible to locate the records and to determine whether they should be made available for inspection within 10 working days, the custodian may, in any of the following circumstances, extend the time for action by up to 10 working days:

(1) It is necessary to search for and collect the requested records from field facilities or other establishments that are separate from the office processing the request.

(2) It is necessary to search for, collect and appropriately examine a voluminous amount of separate and distinct records which are demanded in a single request; or

(3) It is necessary to consult with another agency having a substantial interest in the determination of the request or among two or more components of the Commission.

If these circumstances are not present or if it is not possible to locate the records and make the determination within the extended period, the person or persons who made the request will be advised of their rights and asked to consent to an extension or further extension. If the requestor agrees to an extension, the custodian of the records will confirm the agreement in a letter specifying the length of the agreed-upon extension. If he does not agree to an extension, the request will be denied, on the grounds that the custodian has not been able to locate the records and/or to make the determination within the period for a ruling mandated by the Freedom of Information Act, 4 U.S.C. 552. In that event, the custodian will continue to search for and/or assess the records and will advise the person who made the request of further developments; but that person may file an application for review by the Commission. When action is taken by the custodian of the records, written notice of the action will be given.

(h)(1) If a request for inspection of records submitted to the Commission in confidence under §0.457(d) or §0.459 is granted, an application for review of the action may be filed only by the person who submitted the records to the Commission. The application for review and the envelope containing it (if any) shall be captioned "Review of Freedom of Information Action." The application for review shall be filed within 10 working days after the date of the written ruling, shall be delivered or mailed to the General Counsel, and shall be served on the person who filed the request for inspection of records.

Federal Communications Commission

§0.461

The first day to be counted in computing the time period for filing the application for review is the day after the date of the written ruling. If an application for review is not filed within this period, the records will be produced for inspection. The person who filed the request for inspection of records may respond to the application for review within 10 working days after it is filed.

(2) If the request for inspection of records submitted to the Commission in confidence under §0.457(d) or §0.459 is partially granted and partially denied, the person who submitted the records to the Commission and the person who filed the request for inspection of those records may file an application for review within the 10 working days after the date of the written ruling. The application for review and the envelope containing it (if any) shall be captioned "REVIEW OF FREEDOM OF INFORMATION ACTION." The application for review shall be delivered or mailed to the General Counsel. If either person files an application for review, it shall be served upon the other person.

(3) If the application for review filed by either person is denied, that person will be notified in writing and advised of their rights.

(4) If an application for review filed by the person who submitted the records to the Commission is denied, or if the records are made available on review which were not initially made available, the person who submitted the records to the Commission will be afforded 10 working days from the date of the written ruling in which to move for a judicial stay of the Commission's action. The first day to be counted in computing the time period for seeking a judicial stay is the day after the date of the written ruling. If a motion for stay is not made within this period, the record will be produced for inspection.

(5) Because of the statutory constraints imposed upon the Commission, no extensions of time will be granted to seek either Commission review or a judicial stay.

(i) Except as provided in paragraph (h) of this section, an application for review of an initial action on a request for inspection may be filed only by the

person who made the request. The application shall be filed within 30 days after the date of the written ruling by the custodian of records, and shall be captioned, "Review of Freedom of Information Action." The envelope (if any) shall also be so captioned. The application shall be delivered or mailed to the General Counsel and shall be served on the person (if any) who originally submitted the materials to the Commission. That person may file a response within 10 working days after the application for review is filed. If the records are made available on review, the person who submitted them to the Commission (if any) will be afforded 10 working days after the date of the written ruling to seek a judicial stay. See paragraph (h) of this section. The first day to be counted in computing the time period for filing the application for review or seeking a judicial stay is the day after the date of the written ruling. (For general procedures relating to applications for review, see §1.115 of this chapter.)

(j) [Reserved]

(k) The Commission will make every effort to act on an application for review of an action on a request for inspection of records within 20 working days after it is filed. See, however, paragraph (h)(2) of this section. If it is not possible to locate the records and to determine whether they should be made available for inspection within 20 working days, the General Counsel may, in the following circumstances and to the extent time has not been extended under paragraphs (g) (1), (2), and (3) of this section, extend the time for action up to 10 working days. (The total period of extensions taken under this paragraph and under paragraph (g) of this section without the consent of the person who submitted the request shall not exceed 10 working days.):

(1) It is necessary to search for and collect the requested records from field facilities or other establishments that are separate from the office processing the request;

(2) It is necessary to search for, collect and appropriately examine a voluminous amount of separate and distinct records which are demanded in a single request; or

§0.463

(3) It is necessary to consult with another agency having a substantial interest in the determination of the request or among two or more components of the Commission.

If these circumstances are not present or if it is not possible to locate the records and make the determination within the extended period, the person who made the request will be advised of his/her rights and asked to consent to an extension or further extension. If the requester or person who made the request agrees to an extension, the General Counsel will confirm the agreement in a letter specifying the length of the agreed-upon extension. If the requestor or person who made the request does not agree to an extension, the Commission will continue to search for and/or assess the record and will advise the person who made the request of further developments; but that person may file a complaint in an appropriate United States district court.

(l) Subject to the application for review and judicial stay provisions of paragraphs (h) and (i) of this section, if the request is granted, the records will be produced for inspection at the earliest possible time.

(m) Staff orders and letters denying requests for inspection are signed by the official (or officials) who give final approval of their contents. If a request is denied by the Commission, notice of denial will set forth the names of the Commissioners participating in the decision.

(n) Records shall be inspected within 7 days after notice is given that they have been located and are available for inspection. After that period, they will be returned to storage, and additional charges may be imposed for again producing them.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 397; 47 FR 0.231(d))

[40 FR 39507, Aug. 28, 1975, as amended at 40 FR 59439, Dec. 24, 1975; 45 FR 85028, Dec. 24, 1980; 49 FR 13367, Apr. 4, 1984; 49 FR 38122, Sept. 27, 1984; 53 FR 39093, Oct. 5, 1988; 55 FR 8951, Mar. 9, 1990; 55 FR 9445, Mar. 14, 1990]

47 CFR Ch. I (10–1–97 Edition)

§0.463 Demand by competent authority for the production of documents or testimony concerning information contained therein.

(a) In the event that a demand (subpoena, order or other demand) is made by a court or other competent authority outside the Commission for the production of records or files or for testimony concerning information contained therein, the Managing Director shall promptly be advised of such demand, the nature of the papers or information sought, and all other relevant facts and circumstances. The Commission will thereupon issue such instructions as it may deem advisable.

(b) Unless specifically authorized to produce such records or files or to testify with respect thereto, any officer or employee of the Commission who is served with a demand for the production of records or files or testimony concerning the same, shall appear in response to the demand and respectfully decline to produce such records or files or to testify concerning them, basing the refusal upon this rule.

(Secs. 4(i), 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[49 FR 13367, Apr. 4, 1984]

§0.465 Request for copies of materials which are available, or made available, for public inspection.

(a) The Commission awards a contract to a commercial duplication firm to make copies of Commission records and offer them for sale to the public. In addition to the charge for copying, the contractor may charge a search fee for extracting the requested documents from the Commission's files.

NOTE: The name, address, telephone number, and schedule of fees for the current duplication contractor are published annually at the time of contract award or renewal in a Public Notice. This information may be obtained from the Office of Congressional and Public Affairs, Consumer Assistance and Small Business Division, Telephone (202) 632-7000.

(b) The Commission awards a contract to a commercial firm to transcribe Commission proceedings in which a verbatim record is kept and to

Federal Communications Commission

§0.465

offer copies of the transcript for sale to the public. Except as authorized by the Commission, the firm is required to retain the capacity to furnish copies of the transcript for a period of 5 years, and may retain that capacity for a longer period, even though another firm is currently transcribing Commission proceedings. Requests for copies of the transcript of the current proceedings should be directed to the current contractor. Requests for transcripts of older proceedings will be forwarded by the Commission to the firm which made the transcript in question; and the names of contracting firms for past years will be furnished upon request.

NOTE: The name, address, telephone number, and schedule of fees for the current transcription contractor are published annually at the time of contract award or renewal in a Public Notice. This information may be obtained from the Office of Congressional and Public Affairs, Consumer Assistance and Small Business Division, Telephone (202) 632-7000.

(c)(1) Contractual arrangements which have been entered into with commercial firms, as described in this section, do not in any way limit the right of the public to inspect Commission records or to extract therefrom whatever information may be desired. Coin-operated copy machines are available for use by the public in various reference rooms for the purpose of duplicating records available at those locations. In addition, any person may make photocopies of Commission records with his or her own equipment at locations where those records may be inspected. Prior approval for such arrangements, which must be obtained from the Operations Support Division, Office of Managing Director, is subject to the availability of adequate space and facilities to accommodate the user's equipment.

(2) The Commission has reserved the right to make copies of its records for its own use or for the use of other agencies of the U.S. Government. When it serves the regulatory or financial interests of the U.S. Government, the Commission will make and furnish copies of its records free of charge. In other circumstances, however, if it should be necessary for the Commission to make and furnish copies of its

records for the use of others, the fee for this service shall be 17 cents per page. For copies prepared with other media, such as computer tapes, microfiche or videotape, the charge will be the actual direct cost including operator time. Requests for copying should be accompanied by a statement specifying the maximum copying fee the person making the request is prepared to pay. If the Commission estimates that copying charges are likely to exceed \$25 or the amount which the requester has indicated that he/she is prepared to pay, then it shall notify the requester of the estimated amount of fees. Such a notice shall offer the requester the opportunity to confer with Commission personnel with the object of revising or clarifying the request.

NOTE: The criterion considered in acting on a waiver request is whether "waiver or reduction of the fee is in the public interest because furnishing the information can be considered as primarily benefiting the general public." 5 U.S.C. 552(a)(4)(A). The following factors are relevant in applying that criterion: the number of persons to be benefited, the significance of the benefit, the private interest of the requester which the release may further, the usefulness of the materials to be released to the general public and the likelihood that a tangible public benefit will be realized. (See Attorney General's 1974 FOI Amdts. Memorandum, at 15.)

(3) Requests for copies by representatives of foreign governments or persons residing in foreign countries shall be submitted to the General Counsel and will be reviewed by the General Counsel under criteria established by the Department of Commerce for controlling the export of technical data.

(4) Certified Documents. Copies of documents which are available or made available, for inspection under §§0.451 through 0.465, will be prepared and certified, under seal, by the Secretary, or for documents located in the Commission's Gettysburg, Pennsylvania Office by his deputy. Requests shall be in writing, specifying the exact documents, the number of copies desired, and the date on which they will be required. The request shall allow a reasonable time for the preparation and certification of copies. The fee for preparing copies shall be the same as that

§0.465

47 CFR Ch. I (10–1–97 Edition)

charged by the Commission as described in §0.465(c)(2). The fee for certification shall be \$10 for each document.

(d)(1) Copies of computer maintained data bases produced by the Commission may be obtained from the National Technical Information Service (NTIS), Department of Commerce, in the form of machine-readable media, e.g., magnetic tapes, microfiche, or diskettes. These materials are not available to the general public directly from the Commission. Data bases produced on magnetic tape and microfiche by the Commission are listed in two catalogs which may be obtained from NTIS. Extracts from these catalogs pertaining to the Commission are available without charge from the Office of Congressional and Public Affairs, Consumer Assistance and Small Business Division. The catalogs describe the data base, state the estimated fee for providing it, and specify ordering information. Periodic updates to computer maintained data bases, as they occur, will not be furnished in machine-readable form.

NOTE: The Commission awards a contract to provide the public with direct electronic access to a portion of the non-Government Master Frequency File data base released for access and residing on the contractor's computer system. The name, address, telephone number, and schedule of fees for the current contractor are published annually at the time of contract award or renewal in a Public notice. This information may be obtained from the Office of Congressional and Public Affairs, Consumer Assistance and Small Business Division, Telephone (202) 632–7000.

(2) Copies of computer generated data stored as paper printouts or on microfiche may also be obtained from the Commission's duplicating contractor (see paragraph (a) of this section).

(3) Copies of computer source programs and associated documentation produced by the Commission shall be obtained through the National Technical Information Service (NTIS), Department of Commerce. NTIS will forward each request to the Commission. If it can be determined that the requested program is available, the Commission will distribute the current edition to the requester. NTIS will act as billing agent for the Commission. NTIS

will bill the requester for the direct costs of production plus their overhead based on billing information provided by the Commission. Estimates of the total cost may be obtained from NTIS in advance. NTIS will not stock Commission source programs and documentation, nor will they maintain a catalog of Commission computer programs that may be available due to the large volume of programs and the frequency with which they are revised. Requests shall be limited to computer source programs and associated documentation in existence when the request is submitted; requests which require the Commission to produce unique computer programs, data bases and documentation, which are not part of its inventory at the time of the request, will not be honored. Likewise, periodic updates of these materials, as they occur, will not be furnished.

(4) The Commission reserves the right to distribute copies of its computer source programs and data bases to other entities as it sees fit, and when it serves the regulatory interests of the U.S. Government or the Commission, as determined by the Managing Director.

(e) This section has no application to printed publications, which may be purchased from the Superintendent of Documents or private firms (see §§0.411 through 0.420). Nor does it apply to application forms or information bulletins, which are prepared for the use and information of the public and are available upon request (see §§0.421 and 0.423).

(f) Anyone requesting copies of documents pursuant to this section may select either the Commission or the contractor to fulfill the request. If a request goes directly to the contractor, the requester will be charged by the contractor pursuant to the price list set forth in the latest contract. If a request goes directly to the Commission, it shall be sent to the Office of the Managing Director for appropriate processing according to the fee standards established under the FOIA.

Federal Communications Commission

§0.466

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 397; 47 CFR 0.231(d))

[32 FR 10573, July 19, 1967, as amended at 41 FR 51610, Nov. 23, 1976; 45 FR 85028, Dec. 24, 1980; 49 FR 13368, Apr. 4, 1984; 51 FR 34982, Oct. 1, 1986; 52 FR 36774, Oct. 1, 1987; 53 FR 39093, Oct. 5, 1988]

§0.466 Definitions.

(a) For the purpose of §§0.467 and 0.468, the following definitions shall apply:

(1) The term *direct costs* means those expenditures which the Commission actually incurs in searching for and duplicating (and in case of commercial requesters, reviewing) documents to respond to a FOIA request. Direct costs include the salary of the employee performing the work (the basic rate of pay for the employee plus 16 percent of that rate to cover benefits), and the cost of operating duplicating machinery. Not included in direct costs are overhead expenses, such as costs of space, and heating or lighting the facility in which the records are stored.

(2) The term *search* includes all time spent looking for material that is responsive to a request, including page-by-page or line-by-line identification of material contained within documents. Such activity should be distinguished, however, from “review” of material in order to determine whether the material is exempt from disclosure (see paragraph (a)(3) of this section).

(3) The term *review* refers to the process of examining documents located in response to a commercial use request (see paragraph (a)(4) of this section) to determine whether any portion of a document located is exempt from disclosure. It also includes processing any documents for disclosure, e.g., performing such functions that are necessary to excise them or otherwise prepare them for release. Review does not include time spent resolving general legal or policy issues regarding the application of FOIA exemptions.

(4) The term *commercial use* request refers to a request from or on behalf of one who seeks information for a use or purpose that furthers the commercial interests of the requester. In determining whether a requester properly falls within this category, the Commission shall determine the use to which a re-

quester will put the documents requested. Where the Commission has reasonable cause to question the use to which a requester will put the documents sought, or where that use is not clear from the request itself, the Commission shall seek additional clarification before assigning the request to a specific category.

(5) The term *educational institution* refers to a preschool, a public or private elementary or secondary school, an institution or graduate higher education, an institution of professional education and an institution of vocational education, which operates a program or programs of scholarly research.

(6) The term *non-commercial scientific institution* refers to an institution that is not operated on a commercial basis as that term is referenced in paragraph (a)(4) of this section, and which is operated solely for the purpose of conducting scientific research the results of which are not intended to promote any particular product or industry.

(7) The term *representative of the news media* refers to any person actively gathering news for an entity that is organized and operated to publish or broadcast news to the public. The term *news* means information that is about current events or that would be of current interest to the public. Examples of news media entities include television or radio stations broadcasting to the public at large, and publishers of periodicals (but only in those instances where they can qualify as disseminators of “news”) who make their products available for purchase or subscription by the general public. These examples are not intended to be all inclusive. Moreover, as traditional methods of news delivery evolve (e.g., electronic dissemination of newspapers through telecommunications services), such alternative media would be included in this category. In the case of “freelance” journalists, they may be regarded as working for a news organization if they can demonstrate a solid basis for expecting publication through that organization, even though not actually employed by it.

[53 FR 39093, Oct. 5, 1988]

§0.467

47 CFR Ch. I (10–1–97 Edition)

§0.467 Search and review fees.

(a)(1) Subject to the provisions of this section, an hourly fee shall be charged for recovery of the full, allowable direct costs of searching for and reviewing records requested under §0.460(e) or §0.461, unless such fees are precluded or waived pursuant to §0.470. The fee is based on the grade level of the employee(s) who conducts the search, as specified in the following schedule:

Grade	Hourly fee
GS-1	8.84
GS-2	9.62
GS-3	10.85
GS-4	12.18
GS-5	13.62
GS-6	15.09
GS-7	16.87
GS-8	18.70
GS-9	20.64
GS-10	22.74
GS-11	24.98
GS-12	29.94
GS-13	35.60
GS-14	42.07
GS-15	49.49

NOTE: These fees will be modified periodically to correspond with modifications in the rate of pay approved by Congress.

(2) The fees in paragraph (a)(1) of this section were computed at step 5 of each grade level based on the General Schedule effective January 1997 and include 20 percent for personnel benefits.

(b) Search fees may be assessed for time spent searching, even if the Commission fails to locate the records or if the records are determined to be exempt from disclosure.

(c) The Commission shall charge only for the initial review, i.e., the review undertaken initially when the Commission analyzes the applicability of a specific exemption to a particular record. The Commission shall not charge for review at the appeal level of an exemption already applied. However, records or portions of records withheld in full under an exemption that is subsequently determined not to apply may be reviewed again to determine the applicability of other exemptions not previously considered. The costs of such a subsequent review, under these circumstances, are properly assessable.

(d) The fee charged will not exceed an amount based on the time typically re-

quired to locate records of the kind requested.

(e) If the Commission estimates that search charges are likely to exceed \$25 or the amount which the requester indicated he/she is prepared to pay, then it shall notify the requester of the estimated amount of fees. Such a notice shall offer the requester the opportunity to confer with Commission personnel with the object of revising or clarifying the request.

(f) When the search has been completed, the custodian of the records will give notice of the charges incurred to the person who made the request.

(g) The fee shall be paid to the Financial Management Division, Office of Managing Director, or as otherwise directed by the Commission.

(h) Records shall be inspected within 7 days after notice is given that they have been located and are available for inspection. After that period, they will be returned to storage, and additional charges may be imposed for again producing them.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 397; 47 CFR 0.231(d))

[40 FR 7316, Feb. 19, 1975, as amended at 45 FR 85028, Dec. 24, 1980; 49 FR 13368, Apr. 4, 1984. Redesignated and amended at 53 FR 39093, Oct. 5, 1988; 59 FR 21946, Apr. 27, 1994; 60 FR 30002, June 7, 1995; 61 FR 14500, Apr. 2, 1996; 62 FR 42929, Aug. 11, 1997]

§0.468 Interest.

Interest shall be charged those requesters who fail to pay the fees charged. The agency will begin assessing interest charges on the amount billed starting on the 31st day following the day on which the billing was sent. The date on which the payment is received by the agency will determine whether and how much interest is due. The interest shall be set at the rate prescribed in 31 U.S.C. 3717.

[53 FR 39094, Oct. 5, 1988]

§0.469 Advance payments.

(a)(1) The Commission may not require advance payment of estimated FOIA fees except as provided in subsection (a)(2) or where the Commission estimates or determines that allowable charges that a requester may be required to pay are likely to exceed

Federal Communications Commission

§0.470

\$250.00 and the requester has no history of payment. Where allowable charges are likely to exceed \$250.00 and the requester has a history of prompt payment of FOIA fees the Commission may notify the requester of the estimated cost and obtain satisfactory assurance of full payment.

(2) Where a requester has previously failed to pay a fee charged in a timely fashion (i.e., within 30 days of the date of the billing), the Commission may require the requester to pay the full amount owed plus any applicable interest as provided in §0.468, and to make an advance payment of the full amount of the estimated fee before the Commission begins to process a new request or a pending request from that requester.

(3) When the Commission acts under paragraph (a) (1) or (2) of this section, the administrative time limits prescribed in subsection (a)(6) of the FOIA (i.e., 10 working days from receipt of initial requests and 20 working days from receipt of appeals from initial denials, plus permissible extensions of these time limits) will begin only after the agency has received the fee payments described above.

(b) [Reserved]

[53 FR 39094, Oct. 5, 1988]

§0.470 Assessment of fees.

(a)(1) Commercial use requesters. When the Commission receives a request for documents for commercial use, it will assess charges that recover the full direct cost of searching for, reviewing and duplicating the records sought pursuant to §§0.466 and 0.467, above.

(2) Educational and non-commercial scientific institution requesters and requesters who are representatives of the news media. The Commission shall provide documents to requesters in these categories for the cost of reproduction only, pursuant to §0.465 above, excluding reproduction charges for the first 100 pages, provided however, that requesters who are representatives of the news media shall be entitled to a reduced assessment of charges only when the request is for the purpose of disseminating information.

(3) All other requesters. The Commission shall charge requesters who do not

fit into any of the categories above fees which cover the full, reasonable direct cost of searching for and reproducing records that are responsive to the request, pursuant to §§0.467 and 0.465 above, except that the first 100 pages of reproduction and the first two hours of search time shall be furnished without charge.

(b)(1) The 100 page restriction on assessment of reproduction fees in paragraphs (a)(2) and (a)(3) of this section refers to 100 paper copies of a standard size, which will normally be "8½ × 11" or "11 × 14," or microfiche containing the equivalent of 100 pages or 100 pages of computer printout. Requesters will not be entitled to 100 microfiche.

(2) When the agency reasonably believes that a requester or group of requesters is attempting to segregate a request into a series of separate individual requests for the purpose of evading the assessment of fees, the agency will aggregate any such requests and assess charges accordingly.

(c) When a requester believes he is entitled to a restricted fee assessment pursuant to paragraphs (a)(2) and (a)(3), of this section, or a waiver pursuant to paragraph (e) of this section, the requester must include, in his original FOIA request, a statement explaining with specificity, the reasons demonstrating that he/she qualifies for a restricted fee or a fee waiver. Included in this statement should be a certification that the information will not be used to further the commercial interests of the requester.

NOTE: Anyone requesting a restricted fee must submit the request directly to the Commission and not to the contractor who will provide documents only at the contract price.

(d) If the Commission reasonably believes that a commercial interest exists, based on the information provided pursuant to paragraph (c) of this section, the requester shall be so notified and given an additional 5 working days to provide further information to justify receiving a restricted fee. During this time period, the materials will be available for inspection to the extent that the time period exceeds the 10 or 20 day time period for responding to FOIA requests, as appropriate.

§0.471

(e) Copying, search and review charges shall be waived or reduced by the General Counsel, when “disclosure of the information is in the public interest because it is likely to contribute significantly to public understanding of the operations or activities of the government and is not primarily in the commercial interest of the requester.” 5 U.S.C. 552(a)(4)(A)(iii).

(f) The Commission shall not assess any fees if the routine cost of collecting the fee would be equal to or greater than the fee itself.

[53 FR 39094, Oct. 5, 1988]

PLACES FOR MAKING SUBMITTALS OR REQUESTS, FOR FILING APPLICATIONS, AND FOR TAKING EXAMINATIONS

§0.471 Miscellaneous submittals or requests.

Persons desiring to make submittals or requests of a general nature should communicate with the Secretary of the Commission.

[36 FR 15121, Aug. 13, 1971]

§0.473 Reports of violations.

Reports of violations of the Communications Act or of the Commission’s rules and regulations may be submitted to the Commission in Washington or to any field office.

[32 FR 10578, July 19, 1967]

§0.475 Applications for employment.

Persons who wish to apply for employment should communicate with the Associate Managing Director-Personnel Management.

(Secs. 4(i), 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[49 FR 13368, Apr. 4, 1984]

§0.481 Place of filing applications for radio authorizations.

For locations for filing applications, and appropriate fees, see §§1.1102–1.1105 of this chapter.

[56 FR 64714, Dec. 12, 1991]

§0.482 Application for waiver of private radio rules.

All requests for waiver of the rules governing the Private Radio Services

47 CFR Ch. I (10–1–97 Edition)

that require a fee (see §1.1102) shall be submitted to the Mellon Bank, Pittsburgh, Pennsylvania at the address set forth in §1.1102. Waiver requests that do not require a fee should be addressed to: Federal Communications Commission, 1270 Fairfield Road, Gettysburg, Pennsylvania 17325–7245. Waiver requests attached to applications must be submitted in accordance with §0.401(b) of the rules.

[55 FR 19154, May 8, 1990, as amended at 56 FR 64714, Dec. 12, 1991]

§0.483 Applications for amateur or commercial radio operator licenses.

(a) Application filing procedures for amateur radio operator licenses are set forth in part 97 of this chapter.

(b) Application filing procedures for commercial radio operator licenses are set forth in part 13 of this chapter. Detailed information about application forms, filing procedures, and places to file applications for commercial radio operator licenses is contained in the bulletin “Commercial Radio Operator Licenses and Permits.” This bulletin is available from any Commission field office or the FCC, Washington, DC 20554.

[47 FR 53378, Nov. 26, 1982]

§0.484 Amateur radio operator examinations.

Generally, examinations for amateur radio operation licenses shall be administered at locations and times specified by volunteer examiners. (See §97.509). When the FCC conducts examinations for amateur radio operator licenses, they shall take place at locations and times designated by the FCC.

[58 FR 13021, Mar. 9, 1993]

§0.485 Commercial radio operator examinations.

Generally, written and telegraphy examinations for commercial radio operator licenses shall be conducted at locations and times specified by commercial operator license examination managers. (See §13.209 of this chapter). When the FCC conducts these examinations, they shall take place at locations and times specified by the FCC.

[58 FR 9124, Feb. 19, 1993]

Federal Communications Commission

§0.504

§0.489 Applications for ship radio inspection and periodical survey.

Applications for ship radio inspection or for periodical survey shall be forwarded to the radio district office nearest the desired port of inspection or place of survey.

[28 FR 12413, Nov. 22, 1963. Redesignated at 32 FR 10578, July 19, 1967]

§0.491 Applications for exemption from compulsory ship radio requirements.

Applications for exemption filed under the provisions of section 352(b) or 383 of the Communications Act; Regulation 4, chapter I of the Safety Convention; Regulation 5, chapter IV of the Safety Convention; Regulation 5, chapter IV of the Safety Convention; or article IX of the Great Lakes Agreement, must be filed at Exemption Requests, P.O. Box 358300, Pittsburgh, Pennsylvania 15251-5300. Emergency requests must be filed at the Federal Communications Commission, Office of the Secretary, 1919 M Street, NW., room 222, Washington, DC 20554.

[56 FR 64714, Dec. 12, 1991]

§0.493 Non-radio common carrier applications.

All such applications shall be filed at the Commission's offices in Washington, DC.

[28 FR 12413, Nov. 22, 1963. Redesignated at 32 FR 10578, July 19, 1967]

Subpart D—Mandatory Declassification of National Security Information

AUTHORITY: Secs. 4(i), 303(r), Communications Act of 1934, as amended (47 U.S.C. 154(i) and 303(r)).

SOURCE: 47 FR 53377, Nov. 26, 1982, unless otherwise noted.

§0.501 General.

Executive Order 12356 requires that information relating to national security be protected against unauthorized disclosure as long as required by national security considerations. The Order also provides that all information classified under Executive Order 12356 or predecessor orders be subject

to a review for declassification upon receipt of a request made by a United States citizen or permanent resident alien, a federal agency, or a state or local government.

§0.502 Purpose.

This subpart prescribes the procedures to be followed in submitting requests, processing such requests, appeals taken from denials of declassification requests and fees and charges.

§0.503 Submission of requests for mandatory declassification review.

(a) Requests for mandatory review of national security information shall be in writing, addressed to the Managing Director, and reasonably describe the information sought with sufficient particularity to enable Commission personnel to identify the documents containing that information and be reasonable in scope.

(b) When the request is for information originally classified by the Commission, the Managing Director shall assign the request to the appropriate bureau or office for action.

(c) Requests related to information, either derivatively classified by the Commission or originally classified by another agency, shall be forwarded, together with a copy of the record, to the originating agency. The transmittal may contain a recommendation for action.

§0.504 Processing requests for declassification.

(a) Responses to mandatory declassification review requests shall be governed by the amount of search and review time required to process the request. A final determination shall be made within one year from the date of receipt of the request, except in unusual circumstances.

(b) Upon a determination by the bureau or office that the requested material originally classified by the Commission no longer warrants protection, it shall be declassified and made available to the requester, unless withholding is otherwise authorized under law.

(c) If the information may not be declassified or released in whole or in part, the requester shall be notified as

§0.505

47 CFR Ch. I (10–1–97 Edition)

to the reasons for the denial, given notice of the right to appeal the denial to the Classification Review Committee, and given notice that such an appeal must be filed within 60 days of the date of denial in order to be considered.

(d) The Commission's Classification Review Committee, consisting of the Managing Director (Chairman), the General Counsel or his designee, and the Chief, Internal Review and Security Division, shall have authority to act, within 30 days, upon all appeals regarding denials of requests for mandatory declassification of Commission-originated classifications. The Committee shall be authorized to overrule previous determinations in whole or in part when, in its judgment, continued classification is no longer required. If the Committee determines that continued classification is required under the criteria of the Order, the requester shall be promptly notified and advised that an application for review may be filed with the Commission pursuant to 47 CFR 1.115.

§0.505 Fees and charges.

(a) The Commission has designated a contractor to make copies of Commission records and offer them for sale (See §0.465).

(b) An hourly fee is charged for recovery of the direct costs of searching for requested documents (See §0.466).

§0.506 FOIA and Privacy Act requests.

Requests for declassification that are submitted under the provisions of the Freedom of Information Act, as amended, (See §0.461), of the Privacy Act of 1974, (See §0.554) shall be processed in accordance with the provisions of those Acts.

Subpart E—Privacy Act Regulations

AUTHORITY: Secs. 4, 303, 49 Stat. as amended, 1066, 1082 (47 U.S.C. 154, 303).

SOURCE: 40 FR 44512, Sept. 26, 1975, unless otherwise noted.

§0.551 Purpose and scope; definitions.

(a) The purpose of this subpart is to implement the Privacy Act of 1974, 5 U.S.C. 552(a), and to protect the rights of the individual in the accuracy and

privacy of information concerning him which is contained in Commission records. The regulations contained herein cover any group of records under the Commission's control from which information about individuals is retrievable by the name of an individual or by some other personal identifier.

(b) In this subpart:

(1) *Individual* means a citizen of the United States or an alien lawfully admitted for permanent residence;

(2) *Record* means any item, collection or grouping of information about an individual that is maintained by the Commission, including but not limited to, such individual's education, financial transactions, medical history, and criminal or employment history, and that contains such individual's name, or the identifying number, symbol, or other identifying particular assigned to the individual, such as a finger or voice print or a photograph.

(3) *System of Records* means a group of records under the control of the Commission from which information is retrievable by the name of the individual or by some identifying number, symbol, or other identifying particular assigned to the individual;

(4) *Routine Use* means, with respect to the disclosure of a record, the use of such record for a purpose which is compatible with the purpose for which it was collected;

(5) *System Manager* means the Commission official responsible for the storage, maintenance, safekeeping, and disposal of a system of records.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 49 FR 13368, Apr. 4, 1984]

§0.552 Notice identifying Commission systems of records.

The Commission publishes in the FEDERAL REGISTER upon establishment or revision a notice of the existence and character of the system of records, including for each system of records:

(a) The name and location of the system;

(b) The categories of individuals on whom records are maintained in the system;

Federal Communications Commission

§0.554

(c) The categories of records maintained in the system;

(d) Each routine use of the records contained in the system, including the categories of users and the purposes of such use;

(e) The policies and practices of the agency regarding storage, retrievability, access controls, retention, and disposal of the records;

(f) The title and business address of the system manager;

(g) The address of the agency office to which inquiries should be addressed and the addresses of locations at which the individual may inquire whether a system contains records pertaining to himself;

(h) The agency procedures whereby an individual can be notified how access can be gained to any record pertaining to that individual contained in a system of records, and the procedure for correcting or contesting its contents; and

(i) The categories of sources of records in the system.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 49 FR 13368, Apr. 4, 1984]

§0.553 New uses of information.

Before establishing a new routine use of a system of records, the Commission will publish a notice in the FEDERAL REGISTER of its intention to do so, and will provide at least 30 days for public comment on such use. The notice will contain:

(a) The name of the system of records for which the new routine use is to be established;

(b) The authority for the system;

(c) The categories of records maintained;

(d) The proposed routine use(s); and

(e) The categories of recipients for each proposed routine use.

§0.554 Procedures for requests pertaining to individual records in a system of records.

(a) Upon request, the Commission will notify individuals as to whether it maintains information about them in a system of records and, subject to the provisions of §0.555(b), will disclose the

substance of such information to that individual. In order to properly request notification or access to record information, reference must be made to the Notice described in §0.552. A table of contents, which is alphabetized by bureau or office, precedes the system descriptions and allows members of the public to easily identify record systems of interest to them. An individual may inquire into information contained in any or all systems of records described in the Notice. However, each inquiry shall be limited to information from systems located within a single bureau or office and shall be addressed to that bureau or office.

(b) Reasonable identification is required of all individuals making requests pursuant to paragraph (a) of this section in order to assure that disclosure of any information is made to the proper person.

(1) Individuals who choose to register a request for information in person may verify their identity by showing any two of the following: social security card; drivers license; employee identification card; medicare card; birth certificate; bank credit card; or other positive means of identification. Documents incorporating a picture and/or signature of the individual shall be produced if possible. If an individual cannot provide suitable documentation for identification, that individual will be required to sign an identity statement stipulating that knowingly or willfully seeking or obtaining access to records about another person under false pretenses is punishable by a fine of up to \$5,000.

NOTE: An individual's refusal to disclose his social security number shall not constitute cause in and of itself, for denial of a request.

(2) All requests for record information sent by mail shall be signed by the requestor and shall include his printed name, current address and telephone number (if any). Commission officials receiving such requests will attempt to verify the identity of the requestor by comparing his or her signature to those in the record. If the record contains no signatures and if positive identification cannot be made on the basis of other information submitted, the requestor will be required to sign an

§0.555

identity statement and stipulate that knowingly or willfully seeking or obtaining access to records about another person under false pretense is punishable by a fine of up to \$5,000.

(3) If positive identification cannot be made on the basis of the information submitted, and if data in the record is so sensitive that unauthorized access could cause harm or embarrassment to the individual to whom the record pertains, the Commission reserves the right to deny access to the record pending the production of additional more satisfactory evidence of identity.

NOTE: The Commission will require verification of identity only where it has determined that knowledge of the existence of record information or its substance is not subject to the public disclosure requirements of the Freedom of Information Act, 5 U.S.C. 552, as amended.

(c) All requests for notification of the existence of record information or for access to such information shall be delivered to the business address of the system manager responsible for the system of records in question, except that requests relating to official personnel records shall be addressed to the Associate Managing Director—Personnel Management. Such addresses can be found in the FEDERAL REGISTER Notice described in §0.552.

(d) A written acknowledgement of receipt of a request for notification and/or access will be provided within 10 days (excluding Saturdays, Sundays, and legal public holidays) to the individual making the request. Such an acknowledgement may, if necessary, request any additional information needed to locate a record. A search of all systems of records identified in the individual's request will be made to determine if any records pertaining to the individual are contained therein, and the individual will be notified of the search results as soon as the search has been completed. Normally, a request will be processed and the individual notified of the search results within 30 days (excluding Saturdays, Sundays, and legal holidays) from the date the inquiry is received. However, in some cases, as where records have to be recalled from Federal Record Centers, notification may be delayed. If it is de-

47 CFR Ch. I (10–1–97 Edition)

termined that a record pertaining to the individual making the request does exist, the notification will state approximately when the record will be available for personal review. No separate acknowledgement is required if the request can be processed and the individual notified of the search results within the ten-day period.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 49 FR 13368, Apr. 4, 1984]

§0.555 Disclosure of record information to individuals.

(a) Individuals having been notified that the Commission maintains a record pertaining to them in a system of records may request access to such record in one of three ways: by in person inspection at the system location; by transfer of the record to a nearer location; or by mail.

(1) Individuals who wish to review their records at the system location must do so during regular Commission business hours (8:00 a.m.–4:30 p.m., Monday through Friday). For personal and administrative convenience, individuals are urged to arrange to review a record by appointment. Preferences as to specific dates and times can be made by writing or calling the system manager responsible for the system of records in question at least two days in advance of the desired appointment date, and by providing a telephone number where the individual can be reached during the day in case the appointment must be changed. Verification of identity is required as in §0.554(b)(1) before access will be granted an individual appearing in person. Individuals may be accompanied by a person of his or her own choosing when reviewing a record. However, in such cases, a written statement authorizing discussion of their record in the presence of a Commission representative having physical custody of the records.

(2) Individuals may request that a record be transferred to a Commission field office or installation in the vicinity of his or her home and that access be granted at that location. The addresses of Commission field offices are listed in §0.121. A request to transfer

Federal Communications Commission

§0.556

records must specify the exact location where the records should be sent and a telephone number to call when the information is available for review at the field location. Paragraph (a)(1) of this section regarding personal appointments, verification of identity accompanying persons, and disclosure of original records applies equally to this paragraph.

(3) Individuals may request that copies of records be sent directly to them. In such cases, individuals must verify their identity as §0.554(b)(2) and provide an accurate return address. Records shall be sent only to that address.

(b) The disclosure of record information under this section is subject to the following limitations:

(1) Records containing medical information pertaining to an individual are subject to individual access under this section unless, in the judgment of the system manager having custody of the records after consultation with a medical doctor, access to such record information could have an adverse impact on the individual. In such cases, a copy of the record will be delivered to a medical doctor named by the individual.

(2) Classified material, investigative material compiled for law enforcement purposes, investigatory material compiled solely for determining suitability for federal employment or access to classified information, and certain testing or examination material shall be removed from the records to the extent permitted in the Privacy Act of 1974, 5 U.S.C. 552(a). Section 0.561 of this subpart sets forth the systems of records maintained by the Commission which are either totally or partially exempt from disclosure under this subparagraph.

(c) No fee will be imposed if the number of pages of records requested is 25 or less. Requests involving more than 25 pages shall be submitted to the duplicating contractor (see §0.456(a)).

(d) The provisions of this section in no way give an individual the right to access any information compiled in reasonable anticipation of a civil action or proceeding.

(e) In the event that a determination is made denying an individual access to

records pertaining to that individual for any reason, such individual may either:

(1) Seek administrative review of the adverse determination. Such a request shall be in writing and should be addressed to the system manager who made the initial decision. In addition, the request for review shall state specifically why the initial decision should be reversed.

(2) Seek judicial relief in the district courts of the United States pursuant to paragraph (g)(1)(B) of the Act.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 40 FR 58858, Dec. 19, 1975; 49 FR 13369, Apr. 4, 1984]

§0.556 Request to correct or amend records.

(a) An individual may request the amendment of information contained in their record. Except as otherwise provided in this paragraph, the request to amend should be submitted in writing to the system manager responsible for the records. Requests to amend the official personnel records of active FCC employees should be submitted to the Associate Managing Director—Personnel Management, Office of Managing Director, 1919 M Street, NW., Washington, D.C. 20554. Requests to amend official personnel records of former FCC employees should be sent to the Assistant Director for Work Force Information, Compliance and Investigations Group, Office of Personnel Management, 1900 E Street, NW., Washington, D.C. 20415. Any request to amend should contain as a minimum:

(1) The identity verification information required by §0.554(b)(2) and the information needed to locate the record as required by §0.554(a).

(2) A brief description of the item or items of information to be amended; and

(3) The reason for the requested change.

(b) A written acknowledgement of the receipt of a request to amend a record will be provided within 10 days (excluding Saturdays, Sundays, and legal public holidays) to the individual

§0.557

47 CFR Ch. I (10–1–97 Edition)

requesting the amendment. Such an acknowledgement may, if necessary, request any additional information needed to make a determination. There will be no acknowledgement if the request can be reviewed, processed, and the individual notified of compliance or denial within the 10 day period.

(c) The responsible system manager, or in the case of official personnel records of active FCC employees, the Associate Managing Director—Personnel Management, shall (normally within 30 days) take one of the following actions regarding a request to amend:

(1) If the system manager agrees that an amendment to the record is warranted, the system manager shall:

(i) So advise the individual in writing;

(ii) Correct the record in compliance with the individual's request; and

(iii) If an accounting of disclosures has been made, advise all previous recipients of the fact that the record has been corrected and of the substance of the correction.

(2) If the system manager, after an initial review, does not agree that all or any portion of the record merits amendment, the system manager shall:

(i) Notify the individual in writing of such refusal to amend and the reasons therefore;

(ii) Advise the individual that further administrative review of the initial decision by the full Commission may be sought pursuant to the procedures set forth in §0.557. (In cases where the request to amend involves official personnel records, review is available exclusively from the Assistant Director for Work Force Information, Compliance and Investigations Group, Office of Personnel Management, Washington, DC 20415; and

(iii) Inform the individual of the procedures for requesting Commission review pursuant to §0.557.

(d) In reviewing a record in response to a request to amend, the system manager shall assess the accuracy, relevance, timeliness, or completeness of the record in light of each data element placed into controversy and the use of the record in making decisions that could possibly affect the individual. Moreover, the system manager shall adjudge the merits of any request

to delete information based on whether or not the information in controversy is both relevant and necessary to accomplish a statutory purpose required of the Commission by law or executive order of the President.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 45 FR 39850, June 12, 1980; 49 FR 13369, Apr. 4, 1984]

§0.557 Administrative review of an initial decision not to amend a record.

(a) Individuals have 30 days from the date of the determination not to amend a record consistent with their request to seek further administrative review by the full Commission. Such a request shall be in writing and should be addressed to either the system manager who made the initial adverse decision, or, in the case of official personnel records of active FCC employees, to the Assistant Director for Work Force Information, Compliance and Investigations Group, Office of Personnel Management, Washington, DC 20415. Any request for administrative review must:

(1) Clearly identify the questions presented for review (e.g., whether the record information in question is, in fact, accurate; whether information subject to a request to delete is relevant and necessary to the purpose for which it is maintained);

(2) Specify with particularity why the decision reached by the system manager is erroneous or inequitable; and

(3) Clearly state how the record should be amended or corrected.

(b) The Commission shall conduct an independent review of the record in controversy using the standards of review set out in §0.556(d). It may seek such additional information as is necessary to make its determination. Final administrative review shall be completed not later than 30 days (excluding Saturdays, Sundays and legal public holidays) from the date on which the individual requests such review unless the Chairman determines that a fair and equitable review cannot be made within the 30 day period. In

Federal Communications Commission

§ 0.561

such event, the individual will be informed in writing of the reasons for the delay and the approximate date on which the review is expected to be completed.

(c) If upon review of the record in controversy the Commission agrees with the individual that the requested amendment is warranted, the Commission will proceed in accordance with § 0.556(c)(1) (i) through (iii).

(d) If after the review, the Commission also refuses to amend the record as requested, it shall:

(1) Notify the individual in writing of its refusal and the reasons therefore;

(2) Advise the individual that a concise statement of the reasons for disagreeing with the decision of the Commission may be filed;

(3) Inform the individual:

(i) That such a statement should be signed and addressed to the system manager having custody of the record in question;

(ii) That the statement will be made available to any one to whom the record is subsequently disclosed together with, at the Commission's discretion, a summary of its reasons for refusing to amend the record; and

(iii) That prior recipients of the record will be provided a copy of the statement of dispute to the extent that an accounting of such disclosures is maintained; and

(4) Advise the individual that judicial review of the Commission's decision not to amend the record in any district court of the United States is available.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 45 FR 39850, June 12, 1980; 49 FR 13369, Apr. 4, 1984]

§ 0.558 Advice and assistance.

Individuals who have questions regarding the procedures contained in this subpart for gaining access to a particular system of records or for contesting the contents of a record, either administratively or judicially, should write or call the Privacy Liaison Officer at the following address:

Federal Communications Commission, Office of General Counsel, 1919 M Street NW., Washington, DC 20554.

Individuals who request clarification of the Notice described in § 0.552 or who have questions concerning the characterization of specific systems of records as set forth therein, should write or call the Privacy Liaison Officer at the following address:

Federal Communications Commission, Records Management Branch, Office of Managing Director, 1200 19th Street, NW. Room BB-325, Washington, DC 20554

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 49 FR 13369, Apr. 4, 1984]

§ 0.559 Disclosure of disputed information to persons other than the individual to whom it pertains.

If the Commission determines not to amend a record consistent with an individual's request, and if the individual files a statement of disagreement pursuant to § 0.557(d)(2), the Commission shall clearly annotate the record so that the disputed portion becomes apparent to anyone who may subsequently have access to, use or disclose the record. A copy of the individual's statement of disagreement shall accompany any subsequent disclosure of the record. In addition, the Commission may include a brief summary of its reasons for not amending the record when disclosing the record. Such statements become part of the individual's record for granting access, but are not subject to the amendment procedures of § 0.556.

§ 0.560 Penalty for false representation of identity.

Any individual who knowingly and willfully requests or obtains under false pretenses any record concerning an individual from any system of records maintained by the Commission shall be guilty of a misdemeanor and subject to a fine of not more than \$5,000.

§ 0.561 Exemptions.

The following systems of records are totally or partially exempt from subsections (c)(3), (d), (e)(1), (e)(4) (G), (H), and (I), and (f) of the Privacy Act of 1974, 5 U.S.C. 552(a), and from § 0.554 through 0.557 of this subpart:

§0.601

(a) *System name.* Radio Operator Records—FCC/FOB-1. Parts of this system of records are exempt pursuant to Section (k)(2) of the Act because they contain investigatory material compiled solely for law enforcement purposes.

(b) *System name.* Violators File (records kept on individuals who have been subjects of FCC field enforcement actions)—FCC/FOB-2. Parts of this system of records are EXEMPT because they are maintained as a protective service for individuals described in section 3056 of title 18, and because they are necessary for Commission employees to perform their duties, pursuant to sections (k) (1), (2), and (3) of the Act.

(c) *System name.* Attorney Misconduct Files—FCC/OGC-2. This system of records is exempt pursuant to section 3(k)(2) of the Act because it is maintained for law enforcement purposes.

(d) *System name.* Licensees or Unlicensed Persons Operating Radio Equipment Improperly—FCC. Parts of this system of records are exempt pursuant to section 3(k)(2) of the Act because they embody investigatory material compiled solely for law enforcement purposes.

(e) *System name.* Personnel Investigation Records—FCC/Central-6. Parts of these systems of records are exempt because they embody investigatory material pursuant to sections 3(k)(2) and 3(k)(5) of the Act as applicable.

(f) *System name.* Criminal Investigative Files—FCC/OIG-1. Compiled for the purpose of criminal investigations. This system of records is exempt pursuant to section (j)(2) of the Act because the records contain investigatory material compiled for criminal law enforcement purposes.

(g) *System name.* General Investigative Files—FCC/OIG-2. Compiled for law enforcement purposes. This system of records is exempt pursuant to section (k)(2) of the Act because the records contain investigatory material compiled for law enforcement purposes.

(Secs. 4(i) and 303(n), Communications Act of 1934, as amended, 47 U.S.C. 154(i) and 303(n); 47 CFR 0.231(d))

[40 FR 44512, Sept. 26, 1975, as amended at 49 FR 13369, Apr. 4, 1984; 58 FR 11549, Feb. 26, 1993]

47 CFR Ch. I (10–1–97 Edition)

Subpart F—Meeting Procedures

AUTHORITY: Secs. 4, 303, 48 Stat., as amended, 1066, 1082; (47 U.S.C. 154, 303).

SOURCE: 42 FR 12867, Mar. 7, 1977, unless otherwise noted.

§0.601 Definitions.

For purposes of this section:

(a) The term *agency* means:

(1) The Commission,

(2) A board of Commissioners (see §0.212),

(3) The Telecommunications Committee (see §0.215), and

(4) Any other group of Commissioners hereafter established by the Commission on a continuing or *ad hoc* basis and authorized to act on behalf of the Commission.

(b) The term *meeting* means the deliberations among a quorum of the Commission, a Board of Commissioners, or a quorum of a committee of Commissioners, where such deliberations determine or result in the joint conduct of disposition of official agency business, except that the term does not include deliberations to decide whether a meeting should be open or closed. (The term includes conference telephone calls, but does not include the separate consideration of Commission business by Commissioners.) For purposes of this subpart each item on the agenda of a meeting is considered a meeting or a portion of a meeting.

[42 FR 12867, Mar. 7, 1977, as amended at 48 FR 56391, Dec. 21, 1983]

§0.602 Open meetings.

(a) All meetings shall be conducted in accordance with the provisions of this subpart.

(b) Except as provided in §0.603, every portion of every meeting shall be open to public observation. Observation does not include participation or disruptive conduct by observers, and persons engaging in such conduct will be removed from the meeting.

(c) The right of the public to observe open meetings does not alter those rules in this chapter which relate to the filing of motions, pleadings, or other documents. Unless such pleadings conform to the other procedural requirements of this chapter, pleadings

Federal Communications Commission

§0.605

based upon comments or discussions at open meetings, as a general rule, will not become part of the official record, will receive no consideration, and no further action by the Commission will be taken thereon.

(d) Deliberations, discussions, comments or observations made during the course of open meetings do not themselves constitute action of the Commission. Comments made by Commissioners may be advanced for purposes of discussion and may not reflect the ultimate position of a Commissioner.

[42 FR 12867, Mar. 7, 1977, as amended at 45 FR 63491, Sept. 25, 1980]

§0.603 Bases for closing a meeting to the public.

Except where the agency finds that the public interest requires otherwise, an agency or advisory committee meeting may be closed to the public, and information pertaining to such meetings which would otherwise be disclosed to the public under §0.605 may be withheld, if the agency determines that an open meeting or the disclosure of such information is likely to:

(a) Disclose matters that: (1) Are specifically authorized under criteria established by executive order to be kept secret in the interest of national defense or foreign policy, and (2) are in fact properly classified pursuant to such executive order (see §0.457(a));

(b) Relate solely to the internal personnel rules and practices of an agency (see §0.457(b));

(c) Disclose matters specifically exempted from disclosure, by statute (other than the Freedom of Information Act, 5 U.S.C. 552). *Provided*, That such statute (1) requires that the matters be withheld from the public in such a manner as to leave no discretion on the issue, or (2) establishes particular criteria for withholding or refers to particular types of matters to be withheld (see §0.457(c));

(d) Disclose trade secrets and commercial or financial information obtained from a person and privileged or confidential (see §0.457(d));

(e) Involve accusing any person of a crime or formally censuring any person;

(f) Disclose information of a personal nature where disclosure would con-

stitute a clearly unwarranted invasion of personal privacy (see §0.457(f));

(g) Disclose investigatory records compiled for law enforcement purposes, or information which if written would be contained in such records, but only to the extent that the production of such records or information would (1) interfere with enforcement proceedings, (2) deprive a person of a right to a fair trial or an impartial adjudication, (3) constitute an unwarranted invasion of personal privacy, (4) disclose the identity of a confidential source, and, in the case of a record compiled by a criminal law enforcement authority in the course of a criminal investigation, or by an agency conducting a lawful national security intelligence investigation, confidential information furnished only by the confidential source, (5) disclose investigative techniques and procedures, or (6) endanger the life or physical safety of law enforcement personnel;

(h) Disclose information contained in or related to examination, operating, or condition reports prepared by, on behalf of, or for the use of an agency responsible for the regulation or supervision of financial institutions;

(i) Disclose information the premature disclosure of which would be likely to significantly frustrate implementation of a proposed agency action, except where the agency has already disclosed to the public the content or nature of the disclosed action, or where the agency is required by law to make such disclosure on its own initiative prior to taking final agency action on such proposal; or

(j) Specifically concern the agency's issuance of a subpoena, or the agency's participation in a civil action or proceeding, an action in a foreign court or international tribunal, or an arbitration, or the initiation, conduct, or disposition by the agency of a particular case of formal agency adjudication pursuant to the procedures specified in 5 U.S.C. 554 or otherwise involving a determination on the record after opportunity for hearing.

§0.605 Procedures for announcing meetings.

(a) Notice of all open and closed meetings will be given.

§0.606

47 CFR Ch. I (10–1–97 Edition)

(b) The meeting notice will be submitted for publication in the FEDERAL REGISTER on or before the date on which the announcement is made. Copies will be available in the Press and News Media Division on the day the announcement is made. Copies will also be attached to “FCC Actions Alert”, which is mailed to certain individuals and groups who have demonstrated an interest in representing the public in Commission proceedings.

(c)(1) If the agency staff determines that a meeting should be open to the public, it will, at least one week prior to the meeting, announce in writing the time, place and subject matter of the meeting, that it is to be open to the public, and the name and phone number of the Chief, Press and News Media Division, who has been designated to respond to requests for information about the meeting.

(2) If the staff determines that a meeting should be closed to the public, it will refer the matter to the General Counsel, who will certify that there is (or is not) a legal basis for closing the meeting to the public. Following action by the General Counsel, the matter may be referred to the agency for a vote on the question of closing the meeting (See §0.606).

(d)(1) If the question of closing a meeting is considered by the agency but no vote is taken, the agency will, at least one week prior to the meeting, announce in writing the time, place and subject matter of the meeting, that it is to be open to the public, and the name and phone number of the Chief, Press and News Media Division.

(2) If a vote is taken, the agency will, in the same announcement and within one day after the vote, make public the vote of each participating Commissioner.

(3) If the vote is to close the meeting, the agency will also, in that announcement, set out a full written explanation of its action, including the applicable provision(s) of §0.603, and a list of persons expected to attend the meeting, including Commission personnel, together with their affiliations. The Commissioners, their assistants, the General Counsel, the Executive Director, the Chief, Press and News Media Division, and the Secretary are ex-

pected to attend all Commission meetings. The appropriate Bureau or Office Chief and Division Chief are expected to attend meetings which relate to their responsibilities (see subpart A of this part).

(4) If a meeting is closed, the agency may omit from the announcement information usually included, if and to the extent that it finds that disclosure would be likely to have any of the consequences listed in §0.603.

(e) If the prompt and orderly conduct of agency business requires that a meeting be held less than one week after the announcement of the meeting, or before that announcement, the agency will issue the announcement at the earliest practicable time. In addition to other information, the announcement will contain the vote of each member of the agency who participated in the decision to give less than seven days notice and will specify the nature of the emergency situation if it is not clear from the subject matter.

(f) If, after announcement of a meeting, the time or place of the meeting is changed or the meeting is cancelled, the agency will announce the change at the earliest practicable time.

(g) If the subject matter or the determination to open or close a meeting is changed, the agency will publicly announce the change and the vote of each member at the earliest practicable time. The announcement will contain a finding that agency business requires the change and that no earlier announcement of the change was possible.

(47 U.S.C. 154, 155, 303)

[42 FR 12867, Mar. 7, 1977, as amended at 44 FR 12425, Mar. 7, 1979; 44 FR 70472, Dec. 7, 1979]

§0.606 Procedures for closing a meeting to the public.

(a) For every meeting closed under §0.603, the General Counsel will certify that there is a legal basis for closing the meeting to the public and will state each relevant provision of §0.603. The staff of the agency will refer the matter to the General Counsel for certification before it is referred to the agency for a vote on closing the meeting. Certifications will be retained in a

Federal Communications Commission

§0.607

public file in the Minute and Rules Branch, Office of the Secretary.

(b) The agency will vote on the question of closing a meeting.

(1) If a member of the agency requests that a vote be taken;

(2) If the staff recommends that a meeting be closed and one member of the agency requests that a vote be taken; or

(3) If a person whose interests may be directly affected by a meeting requests the agency to close the meeting for any of the reasons listed in §0.603 (e), (f) or (g), or if any person requests that a closed meeting be opened, and a member of the agency requests that a vote be taken. (Such requests may be filed with the Secretary at any time prior to the meeting and should briefly state the reason(s) for opening or closing the meeting. To assure that they reach the Commission for consideration prior to the meeting, they should be submitted at the earliest practicable time and should be called specifically to the attention of the Secretary—in person or by telephone. It will be helpful if copies of the request are furnished to the members of the agency and the General Counsel. The filing of a request shall not stay the holding of a meeting.)

(c) A meeting will be closed to the public pursuant to §0.603 only by vote of a majority of the entire membership of the agency. The vote of each participating Commissioner will be recorded. No Commissioner may vote by proxy.

(d) A separate vote will be taken before any meeting is closed to the public and before any information is withheld from the meeting notice. However, a single vote may be taken with respect to a series of meetings proposed to be closed to the public, and with respect to information concerning such series of meetings (a vote on each question, if both are presented), if each meeting involves the same particular matters and is scheduled to be held no later than 30 days after the first meeting in the series.

(e) Less than seven days notice may be given only by majority vote of the entire membership of the agency.

(f) The subject matter or the determination to open or close a meeting will be changed only if a majority of the entire membership of the agency

determines by recorded vote that agency business so requires and that no earlier announcement of the change was possible.

§0.607 Transcript, recording or minutes; availability to the public.

(a) The agency will maintain a complete transcript or electronic recording adequate to record fully the proceedings of each meeting closed to the public, except that in a meeting closed pursuant to paragraph (h) or (j) of §0.603, the agency may maintain minutes in lieu of a transcript or recording. Such minutes shall fully and clearly describe all matters discussed and shall provide a full and accurate summary of any actions taken, and the reasons therefor, including a description of each of the views expressed on any item and the record of any roll call vote. All documents considered in connection with any item will be identified in the minutes.

(b) A public file of transcripts (or minutes) of closed meetings will be maintained in the Minute and Rules Branch, Office of the Secretary. The transcript of a meeting will be placed in that file if, after the meeting, the responsible Bureau or Office Chief determines, in light of the discussion, that the meeting could have been open to the public or that the reason for withholding information concerning the matters discussed no longer pertains. Transcripts placed in the public file are available for inspection under §0.460. Other transcripts, and separable portions thereof which do not contain information properly withheld under §0.603, may be made available for inspection under §0.461. When a transcript, or portion thereof, is made available for inspection under §0.461, it will be placed in the public file. Copies of transcripts may be obtained from the duplicating contractor pursuant to §0.465(a). There will be no search or transcription fee. Requests for inspection or copies of transcripts shall specify the date of the meeting, the name of the agenda and the agenda item number; this information will appear in the notice of the meeting. Pursuant to §0.465(c)(3), the Commission will make

Pt. 1

47 CFR Ch. I (10–1–97 Edition)

copies of the transcript available directly, free of charge, if it serves the financial or regulatory interests of the United States.

(c) The Commission will maintain a copy of the transcript or minutes for a period of at least two years after the meeting, or until at least one year after conclusion of the proceeding to which the meeting relates, whichever occurs later.

(d) The Commissioner presiding at the meeting will prepare a statement setting out the time and place of the meeting, the names of persons other than Commission personnel who were present at the meeting, and the names of Commission personnel who participated in the discussion. These statements will be retained in a public file in the Minute and Rules Branch, Office of the Secretary.

**PART 1—PRACTICE AND
PROCEDURE**

**Subpart A—General Rules of Practice and
Procedure**

GENERAL

Sec.

- 1.1 Proceedings before the Commission.
- 1.2 Declaratory rulings.
- 1.3 Suspension, amendment, or waiver of rules.
- 1.4 Computation of time.
- 1.5 Mailing address furnished by licensee.
- 1.6 Availability of station logs and records for Commission inspection.
- 1.7 Documents are filed upon receipt.
- 1.8 Withdrawal of papers.
- 1.10 Transcript of testimony; copies of documents submitted.
- 1.12 Notice to attorneys of Commission documents.
- 1.13 Filing of petitions for review and notices of appeals of Commission orders.
- 1.14 Citation of Commission documents.
- 1.16 Unsworn declarations under penalty of perjury in lieu of affidavits.
- 1.17 Truthful written statements and responses to Commission inquiries and correspondence.
- 1.18 Administrative Dispute Resolution.
- 1.19 Use of metric units required.

PARTIES, PRACTITIONERS, AND WITNESSES

- 1.21 Parties.
- 1.22 Authority for representation.
- 1.23 Persons who may be admitted to practice.
- 1.24 Censure, suspension, or disbarment of attorneys.

- 1.25 [Reserved]
- 1.26 Appearances.
- 1.27 Witnesses; right to counsel.
- 1.28 [Reserved]
- 1.29 [Reserved]

PLEADINGS, BRIEFS, AND OTHER PAPERS

- 1.41 Informal requests for Commission action.
- 1.42 Applications, reports, complaints; cross-reference.
- 1.43 Requests for stay; cross-reference.
- 1.44 Separate pleadings for different requests.
- 1.45 Pleadings; filing periods.
- 1.46 Motions for extension of time.
- 1.47 Service of documents and proof of service.
- 1.48 Length of pleadings.
- 1.49 Specifications as to pleadings and documents.
- 1.50 Specifications as to briefs.
- 1.51 Number of copies of pleadings, briefs and other papers.
- 1.52 Subscription and verification.

GENERAL APPLICATION PROCEDURES

- 1.61 Procedures for handling applications requiring special aeronautical study.
- 1.62 Operation pending action on renewal application.
- 1.65 Substantial and significant changes in information furnished by applicants to the Commission.
- 1.68 Action on application for license to cover construction permit.
- 1.77 Detailed application procedures; cross references.

MISCELLANEOUS PROCEEDINGS

- 1.80 Forfeiture proceedings.
- 1.83 Applications for radio operator licenses.
- 1.84 Procedure with respect to commercial radio operator license applications.
- 1.85 Suspension of operator licenses.
- 1.87 Modification of license or construction permit on motion of the Commission.
- 1.88 Predesignation pleading procedure.
- 1.89 Notice of violations.
- 1.91 Revocation and/or cease and desist proceedings; hearings.
- 1.92 Revocation and/or cease and desist proceedings; after waiver of hearing.
- 1.93 Consent orders.
- 1.94 Consent order procedures.
- 1.95 Violation of consent orders.

**RECONSIDERATION AND REVIEW OF ACTIONS
TAKEN BY THE COMMISSION AND PURSUANT
TO DELEGATED AUTHORITY; EFFECTIVE
DATES AND FINALITY DATES OF ACTIONS**

- 1.101 General provisions.

Federal Communications Commission

Pt. 1

- 1.102 Effective dates of actions taken pursuant to delegated authority.
- 1.103 Effective dates of Commission actions; finality of Commission actions.
- 1.104 Preserving the right of review; deferred consideration of application for review.
- 1.106 Petitions for reconsideration.
- 1.108 Reconsideration on Commission's own motion.
- 1.110 Partial grants; rejection and designation for hearing.
- 1.113 Action modified or set aside by person, panel, or board.
- 1.115 Application for review of action taken pursuant to delegated authority.
- 1.117 Review on motion of the Commission.
- 1.120 Protests of grants without hearing.

Subpart B—Hearing Proceedings

GENERAL

- 1.201 Scope.
- 1.202 Official reporter; transcript.
- 1.203 The record.
- 1.204 Pleadings; definition.
- 1.205 Continuances and extensions.
- 1.207 Interlocutory matters, reconsideration and review; cross references.
- 1.209 Identification of responsible officer in caption to pleading.
- 1.211 Service.

PARTICIPANTS AND ISSUES

- 1.221 Notice of hearing; appearances.
- 1.223 Petitions to intervene.
- 1.224 Motion to proceed in forma pauperis.
- 1.225 Participation by non-parties; consideration of communications.
- 1.227 Consolidations.
- 1.229 Motions to enlarge, change, or delete issues.

PRESIDING OFFICER

- 1.241 Designation of presiding officer.
- 1.243 Authority of presiding officer.
- 1.244 Designation of a settlement judge.
- 1.245 Disqualification of presiding officer.

PREHEARING PROCEDURES

- 1.246 Admission of facts and genuineness of documents.
- 1.248 Prehearing conferences; hearing conferences.
- 1.249 Prehearing statement.

HEARING AND INTERMEDIATE DECISION

- 1.250 Discovery and preservation of evidence; cross-reference.
- 1.251 Summary decision.
- 1.253 Time and place of hearing.
- 1.254 Nature of the hearing; burden of proof.
- 1.255 Order of procedure.
- 1.258 Closing of the hearing.
- 1.260 Certification of transcript.
- 1.261 Corrections to transcript.

- 1.263 Proposed findings and conclusions.
- 1.264 Contents of findings of fact and conclusions.
- 1.267 Initial and recommended decisions.

REVIEW PROCEEDINGS

- 1.271 Delegation of review function.
- 1.273 Waiver of initial or recommended decision.
- 1.274 Certification of the record to the Commission for initial or final decision.
- 1.276 Appeal and review of initial decision.
- 1.277 Exceptions; oral arguments.
- 1.279 Limitation of matters to be reviewed.
- 1.282 Final decision of the Commission.

INTERLOCUTORY ACTIONS IN HEARING PROCEEDINGS

- 1.291 General provisions.
- 1.294 Oppositions and replies.
- 1.296 Service.
- 1.297 Oral argument.
- 1.298 Rulings; time for action.

APPEAL AND RECONSIDERATION OF PRESIDING OFFICER'S RULING

- 1.301 Appeal from presiding officer's interlocutory ruling; effective date of ruling.
- 1.302 Appeal from presiding officer's final ruling; effective date of ruling.

THE DISCOVERY AND PRESERVATION OF EVIDENCE

- 1.311 General.
- 1.313 Protective orders.
- 1.315 Depositions upon oral examination—notice and preliminary procedure.
- 1.316 Depositions upon written interrogatories—notice and preliminary procedure.
- 1.318 The taking of depositions.
- 1.319 Objections to the taking of depositions.
- 1.321 Use of depositions at the hearing.
- 1.323 Interrogatories to parties.
- 1.325 Discovery and production of documents and things for inspection, copying, or photographing.

SUBPENAS

- 1.331 Who may sign and issue.
- 1.333 Requests for issuance of subpoena.
- 1.334 Motions to quash.
- 1.335 Rulings.
- 1.336 Service of subpoenas.
- 1.337 Return of service.
- 1.338 Subpoena forms.
- 1.339 Witness fees.
- 1.340 Attendance of witness; disobedience.

EVIDENCE

- 1.351 Rules of evidence.
- 1.352 Cumulative evidence.
- 1.353 Further evidence during hearing.
- 1.354 Documents containing matter not material.

Pt. 1

47 CFR Ch. I (10–1–97 Edition)

- 1.355 Documents in foreign language.
- 1.356 Copies of exhibits.
- 1.357 Mechanical reproductions as evidence.
- 1.358 Tariffs as evidence.
- 1.359 Proof of official record; authentication of copy.
- 1.360 Proof of lack of record.
- 1.361 Other proof of official record.
- 1.362 Production of statements.
- 1.363 Introduction of statistical data.
- 1.364 Testimony by speakerphone.

Subpart C—Rulemaking Proceedings

GENERAL

- 1.399 Scope.
- 1.400 Definitions.

PETITIONS AND RELATED PLEADINGS

- 1.401 Petitions for rulemaking.
- 1.403 Notice and availability.
- 1.405 Responses to petitions; replies.
- 1.407 Action on petitions.

RULEMAKING PROCEEDINGS

- 1.411 Commencement of rulemaking proceedings.
- 1.412 Notice of proposed rulemaking.
- 1.413 Content of notice.
- 1.415 Comments and replies.
- 1.419 Form of comments and replies; number of copies.
- 1.420 Additional procedures in proceedings for amendment of the FM or TV Tables of Allotments.
- 1.421 Further notice of rulemaking.
- 1.423 Oral argument and other proceedings.
- 1.425 Commission action.
- 1.427 Effective date of rules.
- 1.429 Petition for reconsideration.

INQUIRIES

- 1.430 Proceedings on a notice of inquiry.

Subpart D—Broadcast Applications and Proceedings

- 1.502 Emergency Broadcast Authorizations.

GENERAL FILING REQUIREMENTS

- 1.511 Applications required.
- 1.512 Where to file; number of copies.
- 1.513 Who may sign applications.
- 1.514 Content of applications.
- 1.516 Specification of facilities.
- 1.517 Contingent applications.
- 1.518 Inconsistent or conflicting applications.
- 1.519 Repetitious applications.
- 1.520 Multiple applications.
- 1.522 Amendment of applications.
- 1.525 Agreements between parties for amendment or dismissal of, or failure to prosecute, broadcast applications.

- 1.526 Records to be maintained locally for public inspection by commercial applicants, permittees and licensees.
- 1.527 Records to be maintained locally for public inspection by noncommercial educational applicants, permittees and licensees.
- 1.531 Formal and informal applications.
- 1.533 Application forms for authority to construct a new station or make changes in an existing station.
- 1.534 Application for extension of construction permit or for construction permit to replace expired construction permit.
- 1.536 Application for license to cover construction permit.
- 1.538 Application for modification of license.
- 1.539 Application for renewal of license.
- 1.540 Application for voluntary assignment or transfer of control.
- 1.541 Application for involuntary assignment of license or transfer of control.
- 1.542 Application for temporary authorization.
- 1.543 Application for renewal or modification of special service authorization.
- 1.544 Application for broadcast station to conduct field strength measurements and for experimental operation.
- 1.545 Application for permit to deliver programs to foreign countries.
- 1.546 Application to determine operating power by direct measurement of antenna power.
- 1.549 Requests for extension of authority to operate without required monitors, indicating instruments, and EBS Attention Signal devices.
- 1.550 Requests for new or modified call sign assignments.
- 1.561 Staff consideration of applications which receive action by the Commission.
- 1.562 Staff consideration of applications which do not require action by the Commission.
- 1.564 Acceptance of applications.
- 1.566 Defective applications.
- 1.568 Dismissal of applications.
- 1.570 AM broadcast station applications involving other North American countries.
- 1.571 Processing AM broadcast station applications.
- 1.572 Processing TV broadcast and translator station applications.
- 1.573 Processing FM broadcast and translator station applications.
- 1.574 Processing of international broadcast station applications.
- 1.578 Amendments to applications for renewal, assignment or transfer of control.
- 1.580 Local public notice of filing of broadcast applications.
- 1.584 Petitions to deny.
- 1.587 Procedure for filing informal applications.
- 1.591 Grants without hearing.

Federal Communications Commission

Pt. 1

- 1.592 Conditional grant.
- 1.593 Designation for hearing.
- 1.594 Local public notice of designation for hearing.
- 1.597 Procedures on transfer and assignment applications.
- 1.598 Period of construction.
- 1.599 Forfeiture of construction permit.
- 1.601 Simultaneous modification and renewal of license.
- 1.603 Special waiver procedure relative to applications.
- 1.605 Retention of applications in hearing status after designation for hearing.
- 1.612 Annual employment report.
- 1.613 Filing of contracts.
- 1.615 Ownership reports.

Subpart E—Complaints, Applications, Tariffs, and Reports Involving Common Carriers

GENERAL

- 1.701 Show cause orders.
- 1.703 Appearances.

COMPLAINTS

- 1.711 Formal or informal complaints.

INFORMAL COMPLAINTS

- 1.716 Form.
- 1.717 Procedure.
- 1.718 Unsatisfied informal complaints; formal complaints relating back to the filing dates of informal complaints.

FORMAL COMPLAINTS

- 1.720 General pleading requirements.
- 1.721 Format and content.
- 1.722 Damages.
- 1.723 Joinder of complainants and causes of action.
- 1.724 Answers.
- 1.725 Cross complaints.
- 1.726 Replies.
- 1.727 Motions.
- 1.728 Formal complaints not stating a cause of action; defective pleadings.
- 1.729 Interrogatories to parties.
- 1.730 Other forms of discovery.
- 1.731 Confidentiality of information produced through discovery.
- 1.732 Other required written submissions.
- 1.733 Status conference.
- 1.734 Specifications as to pleadings, briefs, and other documents; subscription.
- 1.735 Copies; service; separate filings against multiple defendants.

APPLICATIONS

- 1.741 Scope.
- 1.742 Place of filing, fees, and number of copies.
- 1.743 Who may sign applications.
- 1.744 Amendments.

- 1.745 Additional statements.
- 1.746 Defective applications.
- 1.747 Inconsistent or conflicting applications.
- 1.748 Dismissal of applications.
- 1.749 Action on application under delegated authority.

SPECIFIC TYPES OF APPLICATIONS UNDER TITLE II OF COMMUNICATIONS ACT

- 1.761 Cross reference.
- 1.762 Interlocking directorates.
- 1.763 Construction, extension, acquisition or operation of lines.
- 1.764 Discontinuance, reduction, or impairment of service.
- 1.765 Consolidation or acquisition of telephone companies.
- 1.766 Consolidation of domestic telegraph carriers.
- 1.767 Cable landing licenses.

TARIFFS

- 1.771 Filing.
- 1.772 Application for special tariff permission.
- 1.773 Petitions for suspension or rejection of new tariff filings.

CONTRACTS, REPORTS, AND REQUESTS REQUIRED TO BE FILED BY CARRIERS

- 1.781 Requests for extension of filing time.

CONTRACTS

- 1.783 Filing.

FINANCIAL AND ACCOUNTING REPORTS AND REQUESTS

- 1.785 Annual financial reports.
- 1.786 [Reserved]
- 1.787 Reports of proposed changes in depreciation rates.
- 1.788 Reports regarding pensions and benefits.
- 1.789 Reports regarding division of international telegraph communication charges.
- 1.790 Reports relating to traffic by international carriers.
- 1.791 Reports and requests to be filed under part 32 of this chapter.
- 1.795 Reports regarding interstate rates of return.

SERVICES AND FACILITIES REPORTS

- 1.802 Reports relating to continuing authority to supplement facilities or to provide temporary or emergency service.
- 1.803 Reports relating to reduction in temporary experimental service.
- 1.805 Reports relating to service by carriers engaged in public radio service operations.

Pt. 1

47 CFR Ch. I (10–1–97 Edition)

MISCELLANEOUS REPORTS

- 1.811 Reports regarding amendments to charters, by-laws and partnership agreements of carriers engaged in domestic public radio services.
- 1.813 Reports of negotiations regarding foreign communication matters.
- 1.814 Reports regarding free service rendered the Government for national defense.
- 1.815 Reports of annual employment.

GRANTS BY RANDOM SELECTION

- 1.821 Scope.
- 1.822 General selection procedures.
- 1.823 Random selection procedures for the Public Mobile Services.
- 1.824 Random selection procedures for Multichannel Multipoint Distribution Service and Multipoint Distribution Service H-Channel stations.
- 1.825 Random selection procedures for Digital Electronic Message Service.

Subpart F—Private Radio Services Applications and Proceedings

GENERAL

- 1.901 Scope.

GENERAL FILING REQUIREMENTS

- 1.911 Applications required.
- 1.912 Where applications are to be filed.
- 1.913 Who may sign applications.
- 1.914 Full disclosures.
- 1.916 Repetitious applications.
- 1.918 Amendment of applications.

APPLICATION FORMS AND PARTICULAR FILING REQUIREMENTS

- 1.921 Procedure for obtaining a radio station authorization and for commencement of operation.
- 1.922 Forms to be used.
- 1.923 Waiver of construction permit requirement.
- 1.924 Assignment or transfer of control, voluntary and involuntary.
- 1.925 Application for special temporary authorization, temporary permit or temporary operating authority.
- 1.926 Application for renewal of license.
- 1.931 Requests for waiver of private radio rules.
- 1.933 Installation or removal of apparatus.
- 1.934 Procedure with respect to amateur radio operator license.

APPLICATION PROCESSING PROCEDURES

- 1.951 How applications are distributed.
- 1.952 How file numbers are assigned.
- 1.953 How applications are processed.
- 1.955 Frequency coordination, Canada.
- 1.958 Defective applications.
- 1.959 Resubmitted applications.

- 1.961 Dismissal of applications.
- 1.962 Public notice of acceptance for filing; petitions to deny applications of specified categories.

ACTION ON APPLICATIONS

- 1.971 Grants without a hearing.
- 1.972 Grants by random selection.
- 1.973 Designation for hearing.

REPORTS TO BE FILED WITH THE COMMISSION

- 1.981 Reports, annual and semiannual.

Subpart G—Schedule of Statutory Charges and Procedures for Payment

- 1.1101 Authority.
- 1.1102 Schedule of charges for applications and other filings in the wireless telecommunications services.
- 1.1103 Schedule of charges for equipment authorization, experimental radio services, ship inspections and international telecommunications settlements.
- 1.1104 Schedule of charges for applications and other filings in the mass media services.
- 1.1105 Schedule of charges for applications and other filings in the common carrier services.
- 1.1106 Schedule of charges for applications and other filings in the cable television services.
- 1.1107 Schedule of charges for applications and other filings in the international services.
- 1.1108 Attachment of charges.
- 1.1109 Payment of charges.
- 1.1110 Form of payment.
- 1.1111 Filing locations.
- 1.1112 Conditionality of Commission or staff authorizations.
- 1.1113 Return or refund of charges.
- 1.1114 General exemptions to charges.
- 1.1115 Adjustments to charges.
- 1.1116 Penalty for late or insufficient payments.
- 1.1117 Petitions and applications for review.
- 1.1118 Error claims.
- 1.1119 Billing procedures.
- 1.1151 Authority to prescribe and collect regulatory fees.
- 1.1152 Schedule of annual regulatory fees and filing locations for wireless radio services.
- 1.1153 Schedule of annual regulatory fees and filing locations for mass media services.
- 1.1154 Schedule of annual regulatory charges and filing locations for common carrier services.
- 1.1155 Schedule of regulatory fees and filing locations for cable television services.
- 1.1156 Schedule of regulatory fees and filing locations for international services.

Federal Communications Commission

Pt. 1

- 1.1157 Payment of charges for regulatory fees.
- 1.1158 Form of payment for regulatory.
- 1.1159 Filing locations and receipts for regulatory fees.
- 1.1160 Refunds of regulatory fees.
- 1.1161 Conditional license grants and delegated authorizations.
- 1.1162 General exemptions from regulatory fees.
- 1.1163 Adjustments to regulatory fees.
- 1.1164 Penalties for late or insufficient regulatory fee payments.
- 1.1165 Payment by cashier's check for regulatory fees.
- 1.1166 Waivers, reductions, and deferrals of regulatory fees.
- 1.1167 Error claims related to regulatory fees.
- 1.1181 Authority to prescribe and collect fees for competitive bidding-related services and products.
- 1.1182 Schedule of fees for products and services provided by the Commission in connection with competitive bidding procedures.

Subpart H—Ex Parte Communications

GENERAL

- 1.1200 Introduction.
- 1.1202 Definitions.

SUNSHINE PERIOD PROHIBITION

- 1.1203 Sunshine period prohibition.

GENERAL EXEMPTIONS

- 1.1204 Exempt ex parte presentations and proceedings.

NON-RESTRICTED PROCEEDINGS

- 1.1206 Permit-but-disclose proceedings.

RESTRICTED PROCEEDINGS

- 1.1208 Restricted proceedings.

PROHIBITION ON SOLICITATION OF PRESENTATIONS

- 1.1210 Prohibition on solicitation of presentations.

PROCEDURES FOR HANDLING OF PROHIBITED EX PARTE PRESENTATIONS

- 1.1212 Procedures for handling of prohibited ex parte presentations.
- 1.1214 Disclosure of information concerning violations of this subpart.

SANCTIONS

- 1.1216 Sanctions.

Subpart I—Procedures Implementing the National Environmental Policy Act of 1969

- 1.1301 Basis and purpose.

- 1.1302 Cross-reference; Regulations of the Council on Environmental Quality.

- 1.1303 Scope.

- 1.1304 Information and assistance.

- 1.1305 Actions which normally will have a significant impact upon the environment, for which Environmental Impact Statements must be prepared.

- 1.1306 Actions which are categorically excluded from environmental processing.

- 1.1307 Actions that may have a significant environmental effect, for which Environmental Assessments (EAs) must be prepared.

- 1.1308 Consideration of environmental assessments (EAs); findings of no significant impact.

- 1.1309 Application amendments.

- 1.1310 Radiofrequency radiation exposure limits.

- 1.1311 Environmental information to be included in the environmental assessment (EA).

- 1.1312 Facilities for which no preconstruction authorization is required.

- 1.1313 Objections.

- 1.1314 Environmental impact statements (EISs).

- 1.1315 The Draft Environmental Impact Statement (DEIS); Comments.

- 1.1317 The Final Environmental Impact Statement (FEIS).

- 1.1319 Consideration of the environmental impact statements.

Subpart J—Pole Attachment Complaint Procedures

- 1.1401 Purpose.

- 1.1402 Definitions.

- 1.1403 Duty to provide access; modifications; notice of removal, increase or modification; petition for temporary stay.

- 1.1404 Complaint.

- 1.1405 File numbers.

- 1.1406 Dismissal of complaints.

- 1.1407 Response and reply.

- 1.1408 Number of copies and form of pleadings.

- 1.1409 Commission consideration of the complaint.

- 1.1410 Remedies.

- 1.1411 Meetings and hearings.

- 1.1412 Enforcement.

- 1.1413 Forfeiture.

- 1.1414 State certification.

- 1.1415 Other orders.

- 1.1416 Imputation of rates; modification costs.

Pt. 1

47 CFR Ch. I (10–1–97 Edition)

Subpart K—Implementation of the Equal Access to Justice Act (EAJA) in Agency Proceedings

GENERAL PROVISIONS

- 1.1501 Purpose of these rules.
- 1.1502 When the EAJA applies.
- 1.1503 Proceedings covered.
- 1.1504 Eligibility of applicants.
- 1.1505 Standards for awards.
- 1.1506 Allowable fees and expenses.
- 1.1507 Rulemaking on maximum rates for attorney fees.
- 1.1508 Awards against other agencies.

INFORMATION REQUIRED FROM APPLICANTS

- 1.1511 Contents of application.
- 1.1512 Net worth exhibit.
- 1.1513 Documentation of fees and expenses.
- 1.1514 When an application may be filed.

PROCEDURES FOR CONSIDERING APPLICATIONS

- 1.1521 Filing and service of documents.
- 1.1522 Answer to application.
- 1.1523 Reply.
- 1.1524 Comments by other parties.
- 1.1525 Settlement.
- 1.1526 Further proceedings.
- 1.1527 Decision.
- 1.1528 Commission review.
- 1.1529 Judicial review.
- 1.1530 Payment of award.

Subpart L—Random Selection Procedures for Mass Media Services

GENERAL PROCEDURES

- 1.1601 Scope.
- 1.1602 Designation for random selection.
- 1.1603 Conduct of random selection.
- 1.1604 Post-selection hearings.
- 1.1621 Definitions.
- 1.1622 Preferences.
- 1.1623 Probability calculation.

Subpart M [Reserved]

Subpart N—Enforcement of Nondiscrimination on the Basis of Handicap in Programs or Activities Conducted by the Federal Communications Commission

- 1.1801 Purpose.
- 1.1802 Applications.
- 1.1803 Definitions.
- 1.1804–1.1809 [Reserved]
- 1.1810 Self-evaluation.
- 1.1811 Notice.
- 1.1812–1.1829 [Reserved]
- 1.1830 General prohibitions against discrimination.
- 1.1831–1.1839 [Reserved]
- 1.1840 Employment.
- 1.1841–1.1848 [Reserved]

- 1.1849 Program accessibility: Discrimination prohibited.
- 1.1850 Program accessibility: Existing facilities.
- 1.1851 Program accessibility: New construction and alterations.
- 1.1852–1.1859 [Reserved]
- 1.1860 Communications.
- 1.1861–1.1869 [Reserved]
- 1.1870 Compliance procedures.
- 1.1871–1.1899 [Reserved]

Subpart O—Collection of Claims Owed the United States

GENERAL PROVISIONS

- 1.1901 Definitions.
- 1.1902 Exceptions.
- 1.1903 Use of procedures.
- 1.1904 Conformance to law and regulations.
- 1.1905 Other procedures; collection of forfeiture penalties.
- 1.1906 Informal action.
- 1.1907 Return of property.
- 1.1908 Omissions not a defense.

ADMINISTRATIVE OFFSET—CONSUMER REPORTING AGENCIES—CONTRACTING FOR COLLECTION

- 1.1911 Demand for payment.
- 1.1912 Collection by administrative offset.
- 1.1913 Administrative offset against amounts payable from Civil Retirement and Disability Fund.
- 1.1914 Collection in installments.
- 1.1915 Exploration of compromise.
- 1.1916 Suspending or terminating collection action.
- 1.1917 Referrals to the Department of Justice or the General Accounting Office.
- 1.1918 Use of consumer reporting agencies.
- 1.1919 Contracting for collection services.

SALARY OFFSET

- 1.1925 Purpose.
- 1.1926 Scope.
- 1.1927 Notification.
- 1.1928 Hearing.
- 1.1929 Deduction from pay.
- 1.1930 Liquidation from final check or recovery from other payment.
- 1.1931 Non-waiver of rights by payments.
- 1.1932 Refunds.
- 1.1933 Interest, penalties and administrative costs.
- 1.1934 Recovery when paying agency is not creditor agency.
- 1.1935 Obtaining the services of a hearing official.

INTEREST, PENALTIES, ADMINISTRATIVE COSTS AND OTHER SANCTIONS

- 1.1940 Assessment.
- 1.1941 Exemptions.
- 1.1942 Other sanctions.

Federal Communications Commission

§1.2

COOPERATION WITH THE INTERNAL REVENUE SERVICE

- 1.1950 Reporting discharged debts to the Internal Revenue Service.
- 1.1951 Offset against tax refunds.

GENERAL PROVISIONS CONCERNING INTERAGENCY REQUESTS

- 1.1952 Interagency requests.

Subpart P—Implementation of the Anti-Drug Abuse Act of 1988

- 1.2001 Purpose.
- 1.2002 Applicants required to submit information.
- 1.2003 Applications affected.

Subpart Q—Competitive Bidding Proceedings

GENERAL PROCEDURES

- 1.2101 Purpose.
- 1.2102 Eligibility of applications for competitive bidding.
- 1.2103 Competitive bidding design options.
- 1.2104 Competitive bidding mechanisms.
- 1.2105 Bidding application and certification procedures; prohibition of collusion.
- 1.2106 Submission of upfront payments.
- 1.2107 Submission of down payment and filing of long-form applications.
- 1.2108 Procedures for filing petitions to deny against long-form applications.
- 1.2109 License grant, denial, default, and disqualification.
- 1.2110 Designated entities.
- 1.2111 Assignment or transfer of control: unjust enrichment.

Subpart R—Implementation of Section 4(g)(3) of the Communications Act: Procedures Governing Acceptance of Unconditional Gifts, Donations and Bequests

- 1.3000 Purpose and scope.
- 1.3001 Definitions.
- 1.3002 Structural rules and prohibitions.
- 1.3003 Mandatory factors for evaluating conflicts of interest.
- 1.3004 Public disclosure and reporting requirements.

Subpart S—Preemption of Restrictions That “Impair” a Viewer’s Ability To Receive Television Broadcast Signals, Direct Broadcast Satellite Services or Multichannel Multipoint Distribution Services

- 1.4000 Restrictions impairing reception of television broadcast signals, direct broadcast satellite services or multichannel multipoint distribution services.

Subpart T—Exempt Telecommunications Companies

- 1.5000 Purpose.
- 1.5001 Definitions.
- 1.5002 Contents of application and procedure for filing.
- 1.5003 Effect of filing.
- 1.5004 Commission action.
- 1.5005 Notification of Commission action to the Securities and Exchange Commission.
- 1.5006 Procedure for notifying Commission of material change in facts.
- 1.5007 Comments.

APPENDIX A TO PART 1—A PLAN OF COOPERATIVE PROCEDURE IN MATTERS AND CASES UNDER THE PROVISIONS OF SECTION 410 OF THE COMMUNICATIONS ACT OF 1934

AUTHORITY: 15 U.S.C. 79 *et seq.*; 47 U.S.C. 151, 154(i), 154(j), 155, 225, and 303(r).

Subpart A—General Rules of Practice and Procedure

SOURCE: 28 FR 12415, Nov. 22, 1963, unless otherwise noted.

GENERAL

§1.1 Proceedings before the Commission.

The Commission may on its own motion or petition of any interested party hold such proceedings as it may deem necessary from time to time in connection with the investigation of any matter which it has power to investigate under the law, or for the purpose of obtaining information necessary or helpful in the determination of its policies, the carrying out of its duties or the formulation or amendment of its rules and regulations. For such purposes it may subpoena witnesses and require the production of evidence. Procedures to be followed by the Commission shall, unless specifically prescribed in this part, be such as in the opinion of the Commission will best serve the purposes of such proceedings.

(Sec. 403, 48 Stat. 1094; 47 U.S.C. 403)

§1.2 Declaratory rulings.

The Commission may, in accordance with section 5(d) of the Administrative Procedure Act, on motion or on its own motion issue a declaratory ruling terminating a controversy or removing uncertainty.

§ 1.3

47 CFR Ch. I (10–1–97 Edition)

(5 U.S.C. 554)

§ 1.3 Suspension, amendment, or waiver of rules.

The provisions of this chapter may be suspended, revoked, amended, or waived for good cause shown, in whole or in part, at any time by the Commission, subject to the provisions of the Administrative Procedure Act and the provisions of this chapter. Any provision of the rules may be waived by the Commission on its own motion or on petition if good cause therefor is shown.

CROSS REFERENCE: See subpart C of this part for practice and procedure involving rulemaking.

§ 1.4 Computation of time.

(a) *Purpose.* The purpose of this rule section is to detail the method for computing the amount of time within which persons or entities must act in response to deadlines established by the Commission. It also applies to computation of time for seeking both reconsideration and judicial review of Commission decisions.

(b) *General Rule—Computation of Beginning Date When Action is Initiated by Commission or Staff.* Unless otherwise provided, the first day to be counted when a period of time begins with an action taken by the Commission, an Administrative Law Judge or by members of the Commission or its staff pursuant to delegated authority is the day *after the day* on which public notice of that action is given. See § 1.4(b) (1)–(5) of this section. Unless otherwise provided, all Rules measuring time from the date of the issuance of a Commission document entitled “Public Notice” shall be calculated in accordance with this section. See § 1.4(b)(4) of this section for a description of the “Public Notice” document. Unless otherwise provided in § 1.4 (g) and (h) of this section, it is immaterial whether the first day is a “holiday.” For purposes of this section, the term *public notice* means the date of any of the following events: See § 1.4(e)(1) of this section for definition of “holiday.”

(1) For documents in notice and comment rule making proceedings, including summaries thereof, the date of publication in the FEDERAL REGISTER.

Example 1: A document in a Commission rule making proceeding is published in the FEDERAL REGISTER on Wednesday, May 6, 1987. Public notice commences on Wednesday, May 6, 1987. The first day to be counted in computing the beginning date of a period of time for action in response to the document is Thursday, May 7, 1987, the “day after the day” of public notice.

Example 2: Section 1.429(e) provides that when a petition for reconsideration is timely filed in proper form, public notice of its filing is published in the FEDERAL REGISTER. Section 1.429(f) provides that oppositions to a petition for reconsideration shall be filed within 15 days after public notice of the petition’s filing in the FEDERAL REGISTER. Public notice of the filing of a petition for reconsideration is published in the FEDERAL REGISTER on Wednesday, June 10, 1987. For purposes of computing the filing period for an opposition, the first day to be counted is Thursday, June 11, 1987, which is the day after the date of public notice. Therefore, oppositions to the reconsideration petition must be filed by Thursday, June 25, 1987, 15 days later.

(2) For non-rulemaking documents released by the Commission or staff, whether or not published in the FEDERAL REGISTER, the release date. A document is “released” by making the full text available to the press and public in the Commission’s Office of Public Affairs. The release date appears on the face of the document.

Example 3: The Chief, Mass Media Bureau, adopts an order on Thursday, April 2, 1987. The text of that order is not released to the public until Friday, April 3, 1987. Public notice of this decision is given on Friday, April 3, 1987. Saturday, April 4, 1987, is the first day to be counted in computing filing periods.

(3) For rule makings of particular applicability, if the rule making document is to be published in the FEDERAL REGISTER and the Commission so states in its decision, the date of public notice will commence on the day of the FEDERAL REGISTER publication date. If the decision fails to specify FEDERAL REGISTER publication, the date of public notice will commence on the release date, even if the document is subsequently published in the FEDERAL REGISTER. See *Declaratory Ruling*, 51 FR 23059 (June 25, 1986).

Example 4: An order establishing an investigation of a tariff, and designating issues to be resolved in the investigation, is released on Wednesday, April 1, 1987, and is published in the FEDERAL REGISTER on Friday, April 10, 1987. If the decision itself specifies FEDERAL

Federal Communications Commission

§1.4

REGISTER publication, the date of public notice is Friday, April 10, 1987. If this decision does not specify FEDERAL REGISTER publication, public notice occurs on Wednesday, April 1, 1987, and the first day to be counted in computing filing periods is Thursday, April 2, 1987.

(4) If the full text of an action document is not to be released by the Commission, but a descriptive document entitled "Public Notice" describing the action is released, the date on which the descriptive "Public Notice" is released.

Example 5: At a public meeting the Commission considers an uncontested application to transfer control of a broadcast station. The Commission grants the application and does not plan to issue a full text of its decision on the uncontested matter. Five days after the meeting, a descriptive "Public Notice" announcing the action is publicly released. The date of public notice commences on the day of the release date.

Example 6: A Public Notice of petitions for rule making filed with the Commission is released on Wednesday, September 2, 1987; public notice of these petitions is given on September 2, 1987. The first day to be counted in computing filing times is Thursday, September 3, 1987.

(5) If a document is neither published in the FEDERAL REGISTER nor released, and if a descriptive document entitled "Public Notice" is not released, the date appearing on the document sent (e.g., mailed, telegraphed, etc.) to persons affected by the action.

Example 7: A Bureau grants a license to an applicant, or issues a waiver for non-conforming operation to an existing licensee, and no "Public Notice" announcing the action is released. The date of public notice commences on the day appearing on the license mailed to the applicant or appearing on the face of the letter granting the waiver mailed to the licensee.

(c) *General Rule—Computation of Beginning Date When Action is Initiated by Act, Event or Default.* Commission procedures frequently require the computation of a period of time where the period begins with the occurrence of an act, event or default and terminates a specific number of days thereafter. Unless otherwise provided, the first day to be counted when a period of time begins with the occurrence of an act, event or default is the day after the day on which the act, event or default occurs.

Example 8: Commission Rule §21.39(d) requires the filing of an application requesting

consent to involuntary assignment or control of the permit or license within thirty days after the occurrence of the death or legal disability of the licensee or permittee. If a licensee passes away on Sunday, March 1, 1987, the first day to be counted pursuant to §1.4(c) is the day after the act or event. Therefore, Monday, March 2, 1987, is the first day of the thirty day period specified in §21.39(d).

(d) *General Rule—Computation of Terminal Date.* Unless otherwise provided, when computing a period of time the last day of such period of time is included in the computation, and any action required must be taken on or before that day.

Example 9: Paragraph 1.4(b)(1) of this section provides that "public notice" in a notice and comment rule making proceeding begins on the day of FEDERAL REGISTER publication. Paragraph 1.4(b) of this section provides that the first day to be counted in computing a terminal date is the "day after the day" on which public notice occurs. Therefore, if the commission allows or requires an action to be taken 20 days after public notice in the FEDERAL REGISTER, the first day to be counted is the day after the date of the FEDERAL REGISTER publication. Accordingly, if the FEDERAL REGISTER document is published on Thursday, July 23, 1987, public notice is given on Thursday, July 23, and the first day to be counted in computing a 20 day period is Friday, July 24, 1987. The 20th day or terminal date upon which action must be taken is Wednesday, August 12, 1987.

(e) Definitions for purposes of this section:

(1) The term *holiday* means Saturday, Sunday, officially recognized federal legal holidays and any other day on which the Commission's offices are closed and not reopened prior to 5:30 p.m. For example, a regularly scheduled Commission business day may become a *holiday* if its offices are closed prior to 5:30 p.m. due to adverse weather, emergency or other closing.

NOTE: As of August 1987, officially recognized federal legal holidays are New Year's Day, January 1; Martin Luther King's Birthday, third Monday in January; Washington's Birthday, third Monday in February; Memorial Day, last Monday in May; Independence Day, July 4; Labor Day, first Monday in September; Columbus Day, second Monday in October; Veterans Day, November 11; Thanksgiving Day, fourth Thursday in November; Christmas Day, December 25. If a legal holiday falls on Saturday or Sunday, the holiday is taken, respectively, on the preceding Friday or the following Monday. In addition, January 20, (Inauguration Day)

§1.4

47 CFR Ch. I (10–1–97 Edition)

following a Presidential election year is a legal holiday in the metropolitan Washington, DC area. If Inauguration Day falls on Sunday, the next succeeding day is a legal holiday. See 5 U.S.C. 6103; Executive Order No. 11582, 36 FR 2957 (Feb. 11, 1971). The determination of a “holiday” will apply only to the specific Commission location(s) designated as on “holiday” on that particular day.

(2) The term *business day* means all days, including days when the Commission opens later than the time specified in Rule §0.403, which are not “holidays” as defined above.

(3) The term *filing period* means the number of days allowed or prescribed by statute, rule, order, notice or other Commission action for filing any document with the Commission. It does not include any additional days allowed for filing any document pursuant to paragraphs (g), (h) and (j) of this section.

(4) The term *filing date* means the date upon which a document must be filed after all computations of time authorized by this section have been made.

(f) Except as provided in §0.401(b) of the Rules, all petitions, pleadings, tariffs or other documents not required to be accompanied by a fee and which are hand-delivered must be tendered for filing in complete form before 5:30 p.m. in the Office of the Secretary, either in Washington or Gettysburg, as directed by the Rules. The Secretary will determine whether a tendered document meets the pre-5:30 deadline.

(g) Unless otherwise provided (e.g., §§1.773 and 76.1502(e)(1) of this chapter), if the filing period is less than 7 days, intermediate holidays shall not be counted in determining the filing date.

Example 10: A reply is required to be filed within 5 days after the filing of an opposition in a license application proceeding. The opposition is filed on Wednesday, June 10, 1987. The first day to be counted in computing the 5 day time period is Thursday, June 11, 1987. Saturday and Sunday are not counted because they are *holidays*. The document must be filed with the Commission on or before the following Wednesday, June 17, 1987.

(h) If a document is required to be served upon other parties by statute or Commission regulation and the document is in fact served by mail (see §1.47(f)), and the filing period for a response is 10 days or less, an additional 3 days (excluding holidays) will be al-

lowed to all parties in the proceeding for filing a response. This paragraph (§1.4(h)) shall not apply to documents filed pursuant to §1.89, §1.120(d), §1.315(b) or §1.316. For purposes of this paragraph service by facsimile shall be deemed equivalent to hand delivery.

Example 11: A reply to an opposition for a petition for reconsideration must be filed within 7 days after the opposition is filed. 47 CFR 1.106(h). The rules require that the opposition be served on the person seeking reconsideration. 47 CFR 1.106(g). If the opposition is served on the party seeking reconsideration by mail and the opposition is filed with the Commission on Monday, November 9, 1987, the first day to be counted is Tuesday, November 10, 1987 (the day after the day on which the event occurred, §1.4(c)), and the seventh day is Monday, November 16. An additional 3 days (excluding holidays) is then added at the end of the 7 day period, and the reply must be filed no later than Thursday, November 19, 1987.

Example 12: Assume that oppositions to a petition in a particular proceeding are due 10 days after the petition is filed and must be served on the parties to the proceeding. If the petition is filed on October 28, 1993, the last day of the filing period for oppositions is Sunday, November 7. If service is made by mail, the opposition is due three days after November 7, or Wednesday, November 10.

(i) If both paragraphs (g) and (h) of this section are applicable, make the paragraph (g) computation before the paragraph (h) computation.

Example 13: Section 1.45(b) requires the filing of replies to oppositions within five days after the time for filing oppositions has expired. If an opposition has been filed on the last day of the filing period (Friday, July 10, 1987), and was served on the replying party by mail, §1.4(i) of this section specifies that the paragraph (g) computation should be made before the paragraph (h) computation. Therefore, since the specified filing period is less than seven days, paragraph (g) is applied first. The first day of the filing period is Monday, July 13, 1987, and Friday, July 17, 1987 is the fifth day (the intervening weekend was not counted). Paragraph (h) is then applied to add three days for mailing (excluding holidays). That period begins on Monday, July 20, 1987. Therefore, Wednesday, July 22, 1987, is the date by which replies must be filed, since the intervening weekend is again not counted.

(j) Unless otherwise provided (e.g., §76.1502(e) of this chapter) if, after making all the computations provided for in this section, the filing date falls on a holiday, the document shall be

Federal Communications Commission

§ 1.10

filed on the next business day. See paragraph (e)(1) of this section.

Example 14: The filing date falls on Friday, December 25, 1987. The document is required to be filed on the next business day, which is Monday, December 28, 1987.

(k) Where specific provisions of part 1 conflict with this section, those specific provisions of part 1 are controlling. See, e.g., §§ 1.45(d), 1.773(a)(3) and 1.773(b)(2). Additionally, where § 76.1502(e) of this chapter conflicts with this section, those specific provisions of § 76.1502 are controlling. See e.g. 47 CFR 76.1502(e).

[52 FR 49159, Dec. 30, 1987; 53 FR 44196, Nov. 2, 1988, as amended at 56 FR 40567, 40568, Aug. 15, 1991; 58 FR 17529, Apr. 5, 1993; 61 FR 11749, Mar. 22, 1996; 62 FR 4170, Jan. 29, 1997; 62 FR 26238, May 13, 1997]

§ 1.5 Mailing address furnished by licensee.

(a) Each licensee shall furnish the Commission with an address to be used by the Commission in serving documents or directing correspondence to that licensee. Unless any licensee advises the Commission to the contrary, the address contained in the licensee's most recent application will be used by the Commission for this purpose.

(b) The licensee is responsible for making any arrangements which may be necessary in his particular circumstances to assure that Commission documents or correspondence delivered to this address will promptly reach him or some person authorized by him to act in his behalf.

§ 1.6 Availability of station logs and records for Commission inspection.

(a) Station records and logs shall be made available for inspection or duplication at the request of the Commission or its representative. Such logs or records may be removed from the licensee's possession by a Commission representative or, upon request, shall be mailed by the licensee to the Commission by either registered mail, return receipt requested, or certified mail, return receipt requested. The return receipt shall be retained by the licensee as part of the station records until such records or logs are returned to the licensee. A receipt shall be furnished when the logs or records are removed from the licensee's possession

by a Commission representative and this receipt shall be retained by the licensee as part of the station records until such records or logs are returned to the licensee. When the Commission has no further need for such records or logs, they shall be returned to the licensee. The provisions of this rule shall apply solely to those station logs and records which are required to be maintained by the provisions of this chapter.

(b) Where records or logs are maintained as the official records of a recognized law enforcement agency and the removal of the records from the possession of the law enforcement agency will hinder its law enforcement activities, such records will not be removed pursuant to this section if the chief of the law enforcement agency promptly certifies in writing to the Federal Communications Commission that removal of the logs or records will hinder law enforcement activities of the agency, stating insofar as feasible the basis for his decision and the date when it can reasonably be expected that such records will be released to the Federal Communications Commission.

§ 1.7 Documents are filed upon receipt.

Unless otherwise provided in this Title, by Public Notice, or by decision of the Commission or of the Commission's staff acting on delegated authority, pleadings and other documents are considered to be filed with the Commission upon their receipt at the location designated by the Commission.

[60 FR 16055, Mar. 29, 1995]

§ 1.8 Withdrawal of papers.

The granting of a request to dismiss or withdraw an application or a pleading does not authorize the removal of such application or pleading from the Commission's records.

§ 1.10 Transcript of testimony; copies of documents submitted.

In any matter pending before the Commission, any person submitting data or evidence, whether acting under compulsion or voluntarily, shall have the right to retain a copy thereof, or to procure a copy of any document submitted by him, or of any transcript

§ 1.12

made of his testimony, upon payment of the charges therefor to the person furnishing the same, which person may be designated by the Commission. The Commission itself shall not be responsible for furnishing the copies.

[29 FR 14406, Oct. 20, 1964]

§ 1.12 Notice to attorneys of Commission documents.

In any matter pending before the Commission in which an attorney has appeared for, submitted a document on behalf of or been otherwise designated by a person, any notice or other written communication pertaining to that matter issued by the Commission and which is required or permitted to be furnished to the person will be communicated to the attorney, or to one of such attorneys if more than one is designated. If direct communication with the party is appropriate, a copy of such communication will be mailed to the attorney.

[29 FR 14406, Oct. 20, 1964]

§ 1.13 Filing of petitions for review and notices of appeals of Commission orders.

(a)(1) This section pertains to each party filing a petition for review in any United States court of appeals of a Commission Order, pursuant to section 402(a) of the Communications Act, 47 U.S.C. 402(a), and 28 U.S.C. 2342(l), that wishes to avail itself of procedures established for selection of a court in the case of multiple appeals, pursuant to 28 U.S.C. 2112(a). Each such party shall, within ten days after the issuance of that order, file with the General Counsel in the Office of General Counsel, Room 614, 1919 M Street NW., Washington, DC 20554, a copy of its petition for review as filed and date-stamped by the court of appeals within which it was filed. Such copies of petitions for review must be filed by 5:30 p.m. Eastern Time on the tenth day of the filing period. A stamp indicating the time and date received by the Office of General Counsel will constitute proof of filing. Upon receipt of any copies of petitions for review, the Commission shall follow the procedures established in section 28 U.S.C. 2112(a) to determine the court in which to file the record in that case.

47 CFR Ch. I (10–1–97 Edition)

(2) Computation of time of the ten-day period for filing copies of petitions for review of a Commission order shall be governed by § 1.4 of the Commission's Rules, 47 CFR 1.4. The date of issuance of a Commission order for purposes of filing copies of petitions for review shall be the date of public notice as defined in § 1.4(b), 47 CFR 1.4(b).

(b) Copies of notices of appeals filed pursuant to 47 U.S.C. 402(b) shall be served upon the General Counsel.

NOTE: For administrative efficiency, the Commission requests that any petitioner seeking judicial review of Commission actions pursuant to 47 U.S.C. 402(a) serve a copy of its petition on the General Counsel regardless of whether it wishes to avail itself of the procedures for multiple appeals set forth in 47 U.S.C. 2112(a).

[54 FR 12453, Mar. 27, 1989]

§ 1.14 Citation of Commission documents.

The appropriate reference to the FCC Record shall be included as part of the citation to any document that has been printed in the Record. The citation should provide the volume, page number and year, in that order (e.g., 1 FCC Rcd. 1 (1986). Older documents may continue to be cited to the FCC Reports, first or second series, if they were printed in the Reports (e.g., 1 FCC 2d 1 (1965)).

[51 FR 45890, Dec. 23, 1986]

§ 1.16 Unsworn declarations under penalty of perjury in lieu of affidavits.

Any document to be filed with the Federal Communications Commission and which is required by any law, rule or other regulation of the United States to be supported, evidenced, established or proved by a written sworn declaration, verification, certificate, statement, oath or affidavit by the person making the same, may be supported, evidenced, established or proved by the unsworn declaration, certification, verification, or statement in writing of such person, except that, such declaration shall not be used in connection with: (a) A deposition, (b) an oath of office, or (c) an oath required to be taken before a specified official other than a notary public. Such

Federal Communications Commission

§ 1.21

declaration shall be subscribed by the declarant as true under penalty of perjury, and dated, in substantially the following form:

(1) If executed without the United States:

“I declare (or certify, verify, or state) under penalty of perjury under the laws of the United States of America that the foregoing is true and correct. Executed on (date).
(Signature)”.

(2) If executed within the United States, its territories, possessions, or commonwealths:

“I declare (or certify, verify, or state) under penalty of perjury that the foregoing is true and correct. Executed on (date).
(Signature)”.

[48 FR 8074, Feb. 25, 1983]

§ 1.17 Truthful written statements and responses to Commission inquiries and correspondence.

The Commission or its representatives may, in writing, require from any applicant, permittee or licensee written statements of fact relevant to a determination whether an application should be granted or denied, or to a determination whether a license should be revoked, or to some other matter within the jurisdiction of the Commission. No applicant, permittee or licensee shall in any response to Commission correspondence or inquiry or in any application, pleading, report or any other written statement submitted to the Commission, make any misrepresentation or willful material omission bearing on any matter within the jurisdiction of the Commission.

NOTE: Section 1.17 is limited in application to written matter. It implies no change in the Commission's existing policies respecting the obligation of applicants, permittees and licensees in all instances to respond truthfully to requests for information deemed necessary to the proper execution of the Commission's functions.

[55 FR 23084, June 6, 1990]

§ 1.18 Administrative Dispute Resolution.

(a) The Commission has adopted an initial policy statement that supports and encourages the use of alternative dispute resolution procedures in its administrative proceedings and proceed-

ings in which the Commission is a party, including the use of regulatory negotiation in Commission rulemaking matters, as authorized under the Administrative Dispute Resolution Act and Negotiated Rulemaking Act.

(b) In accordance with the Commission's policy to encourage the fullest possible use of alternative dispute resolution procedures in its administrative proceedings, procedures contained in the Administrative Dispute Resolution Act, including the provisions dealing with confidentiality, shall also be applied in Commission alternative dispute resolution proceedings in which the Commission itself is not a party to the dispute.

[56 FR 51178, Oct. 10, 1991, as amended at 57 FR 32181, July 21, 1992]

§ 1.19 Use of metric units required.

Where parenthesized English units accompany metric units throughout this chapter, and the two figures are not precisely equivalent, the metric unit shall be considered the sole requirement; except, however, that the use of metric paper sizes is not currently required, and compliance with the English unit shall be considered sufficient when the Commission form requests that data showing compliance with that particular standard be submitted in English units.

[58 FR 44893, Aug. 25, 1993]

PARTIES, PRACTITIONERS, AND
WITNESSES

§ 1.21 Parties.

(a) Any party may appear before the Commission and be heard in person or by attorney.

(b) The appropriate Bureau Chief(s) of the Commission shall be deemed to be a party to every adjudicatory proceeding (as defined in the Administrative Procedure Act) without the necessity of being so named in the order designating the proceeding for hearing.

(c) When, in any proceeding, a pleading is filed on behalf of either the General Counsel or the Chief Engineer, he shall thereafter be deemed a party to the proceeding.

(d) Except as otherwise expressly provided in this chapter, a duly authorized

§ 1.22

corporate officer or employee may act for the corporation in any matter which has not been designated for an evidentiary hearing and, in the discretion of the presiding officer, may appear and be heard on behalf of the corporation in an evidentiary hearing proceeding.

[28 FR 12415, Nov. 22, 1963, as amended at 37 FR 8527, Apr. 28, 1972; 44 FR 39180, July 5, 1979; 51 FR 12616, Apr. 14, 1986]

§ 1.22 Authority for representation.

Any person, in a representative capacity, transacting business with the Commission, may be required to show his authority to act in such capacity.

§ 1.23 Persons who may be admitted to practice.

(a) Any person who is a member in good standing of the bar of the Supreme Court of the United States or of the highest court of any state, territory or the District of Columbia, and who is not under any final order of any authority having power to suspend or disbar an attorney in the practice of law within any state, territory or the District of Columbia that suspends, enjoins, restrains, disbars, or otherwise restricts him or her in the practice of law, may represent others before the Commission.

(b) When such member of the bar acting in a representative capacity appears in person or signs a paper in practice before the Commission, his personal appearance or signature shall constitute a representation to the Commission that, under the provisions of this chapter and the law, he is authorized and qualified to represent the particular party in whose behalf he acts. Further proof of authority to act in a representative capacity may be required.

[28 FR 12415, Nov. 22, 1963, as amended at 57 FR 38285, Aug. 24, 1992]

§ 1.24 Censure, suspension, or disbarment of attorneys.

(a) The Commission may censure, suspend, or disbar any person who has practiced, is practicing or holding himself out as entitled to practice before it if it finds that such person:

(1) Does not possess the qualifications required by § 1.23;

47 CFR Ch. I (10–1–97 Edition)

(2) Has failed to conform to standards of ethical conduct required of practitioners at the bar of any court of which he is a member;

(3) Is lacking in character or professional integrity; and/or

(4) Displays toward the Commission or any of its hearing officers conduct which, if displayed toward any court of the United States or any of its Territories or the District of Columbia, would be cause for censure, suspension, or disbarment.

(b) Except as provided in paragraph (c) of this section, before any member of the bar of the Commission shall be censured, suspended, or disbarred, charges shall be preferred by the Commission against such practitioner, and he or she shall be afforded an opportunity to be heard thereon.

(c) Upon receipt of official notice from any authority having power to suspend or disbar an attorney in the practice of law within any state, territory, or the District of Columbia which demonstrates that an attorney practicing before the Commission is subject to an order of final suspension (not merely temporary suspension pending further action) or disbarment by such authority, the Commission may, without any preliminary hearing, enter an order temporarily suspending the attorney from practice before it pending final disposition of a disciplinary proceeding brought pursuant to § 1.24(a)(2), which shall afford such attorney an opportunity to be heard and directing the attorney to show cause within thirty days from the date of said order why identical discipline should not be imposed against such attorney by the Commission.

(d) Allegations of attorney misconduct in Commission proceedings shall be referred under seal to the Office of General Counsel. Pending action by the General Counsel, the decision maker may proceed with the merits of the matter but in its decision may make findings concerning the attorney's conduct only if necessary to resolve questions concerning an applicant and may not reach any conclusions regarding the ethical ramifications of the attorney's conduct. The General Counsel will determine if the allegations are substantial, and, if so,

Federal Communications Commission

§ 1.44

shall immediately notify the attorney and direct him or her to respond to the allegations. No notice will be provided to other parties to the proceeding. The General Counsel will then determine what further measures are necessary to protect the integrity of the Commission's administrative process, including but not limited to one or more of the following:

(1) Recommending to the Commission the institution of a proceeding under paragraph (a) of this section;

(2) Referring the matter to the appropriate State, territorial, or District of Columbia bar; or

(3) Consulting with the Department of Justice.

[28 FR 12415, Nov. 22, 1963, as amended at 57 FR 38285, Aug. 24, 1992; 60 FR 53277, Oct. 13, 1995]

§ 1.25 [Reserved]

§ 1.26 Appearances.

Rules relating to appearances are set forth in §§ 1.87, 1.91, 1.221, and 1.703.

§ 1.27 Witnesses; right to counsel.

Any individual compelled to appear in person in any Commission proceeding may be accompanied, represented, and advised by counsel as provided in this section. (Regulations as to persons seeking voluntarily to appear and give evidence are set forth in § 1.225.)

(a) Counsel may advise his client in confidence, either upon his own initiative or that of the witness, before, during, and after the conclusion of the proceeding.

(b) Counsel for the witness will be permitted to make objections on the record, and to state briefly the basis for such objections, in connection with any examination of his client.

(c) At the conclusion of the examination of his client, counsel may ask clarifying questions if in the judgment of the presiding officer such questioning is necessary or desirable in order to avoid ambiguity or incompleteness in the responses previously given.

(d) Except as provided by paragraph (c) of this section, counsel for the witness may not examine or cross-examine any witness, or offer documentary evidence, unless authorized by the Commission to do so.

(5 U.S.C. 555)

[29 FR 12775, Sept. 10, 1964]

§§ 1.28–1.29 [Reserved]

PLEADINGS, BRIEFS, AND OTHER PAPERS

§ 1.41 Informal requests for Commission action.

Except where formal procedures are required under the provisions of this chapter, requests for action may be submitted informally. Requests should set forth clearly and concisely the facts relied upon, the relief sought, the statutory and/or regulatory provisions (if any) pursuant to which the request is filed and under which relief is sought, and the interest of the person submitting the request.

§ 1.42 Applications, reports, complaints; cross-reference.

(a) Rules governing applications and reports are contained in subparts D, E, and F of this part.

(b) Special rules governing complaints against common carriers arising under the Communications Act are set forth in subpart E of this part.

§ 1.43 Requests for stay; cross-reference.

General rules relating to requests for stay of any order or decision are set forth in §§ 1.41, 1.44(e), 1.45 (d) and (e), and 1.298(a). See also §§ 1.102, 1.106(n), and 1.115(h).

§ 1.44 Separate pleadings for different requests.

(a) Requests requiring action by the Commission shall not be combined in a pleading with requests for action by an administrative law judge or by any person or persons acting pursuant to delegated authority.

(b) Requests requiring action by an administrative law judge shall not be combined in a pleading with requests for action by the Commission or by any person or persons acting pursuant to delegated authority.

(c) Requests requiring action by any person or persons pursuant to delegated authority shall not be combined in a pleading with requests for action by any other person or persons acting pursuant to delegated authority.

§ 1.45

(d) Pleadings which combine requests in a manner prohibited by paragraph (a), (b), or (c) of this section may be returned without consideration to the person who filed the pleading.

(e) Any request to stay the effectiveness of any decision or order of the Commission shall be filed as a separate pleading. Any such request which is not filed as a separate pleading will not be considered by the Commission.

NOTE: Matters which are acted on pursuant to delegated authority are set forth in subpart B of part 0 of this chapter. Matters acted on by the hearing examiner are set forth in § 0.341.

§ 1.45 Pleadings; filing periods.

Except as otherwise provided in this chapter, pleadings in Commission proceedings shall be filed in accordance with the provisions of this section.

(a) *Oppositions.* Oppositions to any motion, petition, or request may be filed within 10 days after the original pleading is filed. For matters related to part 22 of the rules, these microfiche copies must be filed within 15 calendar days of the paper filing (see § 22.6).

(b) *Replies.* The person who filed the original pleading may reply to oppositions within 5 days after the time for filing oppositions has expired. The reply shall be limited to matters raised in the oppositions, and the response to all such matters shall be set forth in a single pleading; separate replies to individual oppositions shall not be filed. For matters related to part 22 of the rules, three microfiche copies must be filed within 15 calendar days of the paper filing (see § 22.6).

(c) *Additional pleadings.* Additional pleadings may be filed only if specifically requested or authorized by the Commission.

(d) *Requests for temporary relief; shorter filing periods.* Oppositions to a request for stay of any order or to a request for other temporary relief shall be filed within 7 days after the request is filed. Replies to oppositions should not be filed and will not be considered. The provisions of § 1.4(h) shall not apply in computing the filing date for oppositions to a request for stay or for other temporary relief.

(e) *Ex parte disposition of certain pleadings.* As a matter of discretion, the

47 CFR Ch. I (10–1–97 Edition)

Commission may rule *ex parte* upon requests for continuances and extensions of time, requests for permission to file pleadings in excess of the length prescribed in this chapter, and requests for temporary relief, without waiting for the filing of oppositions or replies.

NOTE: Where specific provisions contained in part 1 conflict with this section, those specific provisions are controlling. See, in particular, §§ 1.294(c), 1.298(a), and 1.773.

[28 FR 12415, Nov. 22, 1963, as amended at 33 FR 7153, May 15, 1968; 45 FR 64190, Sept. 29, 1980; 54 FR 31032, July 26, 1989; 54 FR 37682, Sept. 12, 1989]

§ 1.46 Motions for extension of time.

(a) It is the policy of the Commission that extensions of time shall not be routinely granted.

(b) Motions for extension of time in which to file responses to petitions for rulemaking, replies to such responses, comments filed in response to notice of proposed rulemaking, replies to such comments and other papers in rulemaking proceedings conducted under subpart C of this part shall be filed at least 7 days before the filing date. If a timely motion is denied, the responses and comments, replies thereto, or other papers need not be filed until 2 business days after the Commission acts on the motion. In emergency situations, the Commission will consider a late-filed motion for a brief extension of time related to the duration of the emergency and will consider motions for acceptance of comments, reply comments or other papers filed after the filing date.

(c) If a motion for extension of time in which to file papers in proceedings other than notice and comment rule making proceedings is filed less than 7 days prior to the day for filing the papers, the party filing the motion shall (in addition to serving the motion on other parties) orally notify other parties and Commission staff personnel responsible for acting on the motion that the motion has been (or is being) filed.

[39 FR 43301, Dec. 12, 1974, as amended at 41 FR 9550, Mar. 5, 1976; 41 FR 14871, Apr. 8, 1976; 42 FR 28887, June 6, 1977]

Federal Communications Commission

§ 1.49

§ 1.47 Service of documents and proof of service.

(a) Where the Commission or any person is required by statute or by the provisions of this chapter to serve any document upon any person, service shall (in the absence of specific provisions in this chapter to the contrary) be made in accordance with the provisions of this section.

(b) Where any person is required to serve any document filed with the Commission, service shall be made by that person or by his representative on or before the day on which the document is filed: *Provided, however*, That formal complaints filed under section 208 of the Communications Act will be served by the Commission.

(c) Commission counsel who formally participate in any proceeding shall be served in the same manner as other persons who participate in that proceeding. The filing of a document with the Commission does not constitute service upon Commission counsel.

(d) Documents may be served upon a party, his attorney, or other duly constituted agent by delivering a copy or by mailing a copy to the last known address. When a party is represented by an attorney of record in a formal proceeding, service shall be made upon such attorney.

(e) Delivery of a copy pursuant to this section means handing it to the party, his attorney, or other duly constituted agent; or leaving it with the clerk or other person in charge of the office of the person being served; or, if there is no one in charge of such office, leaving it in a conspicuous place therein; or, if such office is closed or the person to be served has no office, leaving it at his dwelling house or usual place of abode with some person of suitable age and discretion then residing therein.

(f) Service by mail is complete upon mailing.

(g) Proof of service, as provided in this section, shall be filed before action is taken. The proof of service shall show the time and manner of service, and may be by written acknowledgment of service, by certificate of the person effecting the service, or by other proof satisfactory to the Commission. Failure to make proof of serv-

ice will not affect the validity of the service. The Commission may allow the proof to be amended or supplied at any time, unless to do so would result in material prejudice to a party.

[28 FR 12415, Nov. 22, 1963, as amended at 40 FR 55644, Dec. 1, 1975; 53 FR 11852, Apr. 11, 1988]

§ 1.48 Length of pleadings.

(a) Affidavits, statements, tables of contents and summaries of filings, and other materials which are submitted with and factually support a pleading are not counted in determining the length of the pleading. If other materials are submitted with a pleading, they will be counted in determining its length; and if the length of the pleadings, as so computed, is greater than permitted by the provisions of this chapter, the pleading will be returned without consideration.

(b) It is the policy of the Commission that requests for permission to file pleadings in excess of the length prescribed by the provisions of this chapter shall not be routinely granted. Where the filing period is 10 days or less, the request shall be made within 2 business days after the period begins to run. Where the period is more than 10 days, the request shall be filed at least 10 days before the filing date. (See § 1.4.) If a timely request is made, the pleading need not be filed earlier than 2 business days after the Commission acts upon the request.

[41 FR 14871, Apr. 8, 1976, and 49 FR 40169, Oct. 15, 1984]

§ 1.49 Specifications as to pleadings and documents.

(a) All pleadings and documents filed in any Commission proceeding shall be typewritten or prepared by mechanical processing methods, and shall be filed on A4 (21 cm. × 29.7 cm.) or on 8½ × 11 inch (21.6 cm. × 27.9 cm.) paper with the margins set so that the printed material does not exceed 6½ × 9½ inches (16.5 cm. × 24.1 cm.). The printed material may be in any typeface of at least 12-point (0.42333 cm. or 12/2" in height. The body of the text must be double spaced with a minimum distance of 7/32 of an inch (0.5556 cm.) between each line of text. Footnotes and long, indented quotations may be single

§1.50

spaced, but must be in type that is 12-point or larger in height, with at least $\frac{1}{16}$ of an inch (0.158 cm.) between each line of text. Counsel are cautioned against employing extended single spaced passages or excessive footnotes to evade prescribed pleading lengths. If single-spaced passages or footnotes are used in this manner the pleading will, at the discretion of the Commission, either be rejected as unacceptable for filing or dismissed with leave to be refiled in proper form. Pleadings may be printed on both sides of the paper. Pleadings that use only one side of the paper shall be stapled, or otherwise bound, in the upper left-hand corner; those using both sides of the paper shall be stapled twice, or otherwise bound, along the left-hand margin so that it opens like a book. The foregoing shall not apply to printed briefs specifically requested by the Commission, official publications, charted or maps, original documents (or admissible copies thereof) offered as exhibits, specially prepared exhibits, or if otherwise specifically provided. All copies shall be clearly legible.

(b) Except as provided in paragraph (d) of this section, all pleadings and documents filed with the Commission, the length of which as computed under this chapter exceeds ten pages, shall include, as part of the pleading or document, a table of contents with page references.

(c) Except as provided in paragraph (d) of this section, all pleadings and documents filed with the Commission, the length of which filings as computed under this chapter exceeds ten pages, shall include, as part of the pleading or document, a summary of the filing, suitably paragraphed, which should be a succinct, but accurate and clear condensation of the substance of the filing. It should not be a mere repetition of the headings under which the filing is arranged. For pleadings and documents exceeding ten but not twenty-five pages in length, the summary should seldom exceed one and never two pages; for pleadings and documents exceeding twenty-five pages in length, the summary should seldom exceed two and never five pages.

47 CFR Ch. I (10–1–97 Edition)

(d) The requirements of paragraphs (b) and (c) of this section shall not apply to:

- (1) Interrogatories or answers to interrogatories, and depositions;
- (2) FCC forms or applications;
- (3) Transcripts;
- (4) Contracts and reports;
- (5) Letters; or
- (6) Hearing exhibits, and exhibits or appendices accompanying any document or pleading submitted to the Commission.

(e) In addition to the provisions above, pleadings related to Part 22 of the rules, must also be submitted on microfiche. See §22.6 for specifications.

NOTE: The table of contents and the summary pages shall not be included in complying with any page limitation requirements as set forth by Commission rule.

[40 FR 19198, May 2, 1975, as amended at 47 FR 26393, June 18, 1982; 51 FR 16322, May 2, 1986; 54 FR 31032, July 26, 1989; 58 FR 44893, Aug. 25, 1993; 59 FR 37721, July 25, 1994]

§1.50 Specifications as to briefs.

The Commission's preference is for briefs that are typewritten or prepared by mechanical processing methods. Printed briefs will be accepted only if specifically requested by the Commission. Typewritten or mechanically produced briefs must conform to all of the specifications for pleadings and documents set forth in §1.49.

[59 FR 37721, July 25, 1994]

§1.51 Number of copies of pleadings, briefs and other papers.

Except as otherwise specifically provided in the Commission's rules and regulations, the number of copies of pleadings, briefs, and other papers to be filed is as follows:

(a) In hearing proceedings, the following number of copies shall be filed:

(1) If the paper filed relates to a matter to be acted upon by the presiding officer or the Chief Administrative Law Judge, an original and 6 copies shall be filed.

(2) If the paper filed relates to matters to be acted on by the Commission, an original and 14 copies shall be filed.

Federal Communications Commission

§ 1.61

(3) If more than one person presided (is presiding) at the hearing an additional copy shall be filed for each such additional person.

(b) In rulemaking proceedings which have not been designated for hearing, see section 1.419 of this chapter.

(c) In matters other than rule making and hearing cases, the following number of copies shall be filed:

(1) If the paper filed relates to matters to be acted on by the Commission, an original and 4 copies shall be filed. If the matter relates to Part 22 of the rules, see § 22.6.

(2) If the paper filed related to matters to be acted on by staff officials under delegated authority, an original and 4 copies shall be filed. If the matter relates to Part 22 of the rules, see § 22.6.

(d) Where statute or regulation provides for service by the Commission of papers filed with the Commission, an additional copy of such papers shall be filed for each person to be served.

(e) The parties to any proceeding may, on notice, be required to file additional copies of any or all papers filed in that proceeding.

(Secs. 4, 303, 48 Stat., as amended, 1066, 1082; (47 U.S.C. 154, 303))

[40 FR 48136, Oct. 14, 1975, as amended at 41 FR 50399, Nov. 16, 1976; 45 FR 64190, Sept. 29, 1980; 45 FR 79486, Dec. 1, 1980; 50 FR 26567, June 27, 1985; 54 FR 29037, July 11, 1989; 54 FR 31032, July 26, 1989; 62 FR 4170, Jan. 29, 1997]

§ 1.52 Subscription and verification.

The original of all petitions, motions, pleadings, briefs, and other documents filed by any party represented by counsel shall be signed by at least one attorney of record in his individual name, whose address shall be stated. A party who is not represented by an attorney shall sign and verify the document and state his address. Either the original document, or an electronic reproduction of such original document containing the facsimile signature of the attorney or unrepresented party is acceptable for filing. If a facsimile copy of a document is filed, the signatory shall retain the original until the Commission's decision is final and no longer subject to judicial review. Except when otherwise specifically provided by rule or statute, documents signed by the attorney for a party need

not be verified or accompanied by affidavit. The signature or electronic reproduction thereof by an attorney constitutes a certificate by him that he has read the document; that to the best of his knowledge, information, and belief there is good ground to support it; and that it is not interposed for delay. If the original of a document is not signed or is signed with intent to defeat the purpose of this section, or an electronic reproduction does not contain a facsimile signature, it may be stricken as sham and false, and the matter may proceed as though the document had not been filed. An attorney may be subjected to appropriate disciplinary action, pursuant to § 1.24, for a willful violation of this rule or if scandalous or indecent matter is inserted.

[50 FR 19360, May 8, 1985]

GENERAL APPLICATION PROCEDURES

§ 1.61 Procedures for handling applications requiring special aeronautical study.

(a) Antenna Structure Registration is conducted by the Wireless Telecommunications Bureau as follows:

(1) Each antenna structure owner that must notify the FAA of proposed construction using FAA Form 7460-1 shall, upon proposing new or modified construction, register that antenna structure with the Wireless Telecommunications Bureau using FCC Form 854.

(2) If an Environmental Assessment is required under § 1.1307, the Bureau will address the environmental concerns prior to processing the registration.

(3) If a final FAA determination of "no hazard" is not submitted along with FCC Form 854, processing of the registration may be delayed or disapproved.

(4) If the owner of the antenna structure cannot file FCC Form 854 because it is subject to a denial of federal benefits under the Anti-Drug Abuse Act of 1988, 21 U.S.C. 862, the first licensee authorized to locate on the structure must register the structure using FCC Form 854, and provide a copy of the Antenna Structure Registration (FCC

§ 1.62

47 CFR Ch. I (10–1–97 Edition)

Form 854R) to the owner. The owner remains responsible for providing a copy of FCC Form 854R to all tenant licensees on the structure and for posting the registration number as required by § 17.4(g) of this chapter.

(5) Upon receipt of FCC Form 854, and attached final FAA determination of “no hazard,” the Bureau prescribes antenna structure painting and/or lighting specifications or other conditions in accordance with the FAA airspace recommendation and returns a completed Antenna Structure Registration (FCC Form 854R) to the registrant. If the proposed structure is disapproved the registrant is so advised.

(b) Each operating Bureau or Office examines the applications for Commission authorization for which it is responsible to ensure compliance with FAA notification procedures as well as Commission Antenna Structure Registration as follows:

(1) If Antenna Structure Registration is required, the operating Bureau reviews the application for the Antenna Structure Registration Number and proceeds as follows:

(i) If the application contains the Antenna Structure Registration Number or if the applicant seeks a Cellular or PCS system authorization, the operating Bureau processes the application.

(ii) If the application does not contain the Antenna Structure Registration Number, but the structure owner has already filed FCC Form 854, the operating Bureau places the application on hold until Registration can be confirmed, so long as the owner exhibits due diligence in filing.

(iii) If the application does not contain the Antenna Structure Registration Number, and the structure owner has not filed FCC Form 854, the operating Bureau notifies the applicant that FCC Form 854 must be filed and places the application on hold until Registration can be confirmed, so long as the owner exhibits due diligence in filing.

(2) If Antenna Structure Registration is not required, the operating Bureau processes the application.

(c) Where one or more antenna farm areas have been designated for a community or communities (see § 17.9 of this chapter), an application proposing the erection of an antenna structure

over 1,000 feet in height above ground to serve such community or communities will not be accepted for filing unless:

(1) It is proposed to locate the antenna structure in a designated antenna farm area, or

(2) It is accompanied by a statement from the Federal Aviation Administration that the proposed structure will not constitute a menace to air navigation, or

(3) It is accompanied by a request for waiver setting forth reasons sufficient, if true, to justify such a waiver.

NOTE: By Commission Order (FCC 65–455), 30 FR 7419, June 5, 1965, the Commission issued the following policy statement concerning the height of radio and television antenna towers:

“We have concluded that this objective can best be achieved by adopting the following policy: Applications for antenna towers higher than 2,000 feet above ground will be presumed to be inconsistent with the public interest, and the applicant will have a burden of overcoming that strong presumption. The applicant must accompany its application with a detailed showing directed to meeting this burden. Only in the exceptional case, where the Commission concludes that a clear and compelling showing has been made that there are public interest reasons requiring a tower higher than 2,000 feet above ground, and after the parties have complied with applicable FAA procedures, and full Commission coordination with FAA on the question of menace to air navigation, will a grant be made. Applicants and parties in interest will, of course, be afforded their statutory hearing rights.”

[28 FR 12415, Nov. 22, 1963, as amended at 32 FR 8813, June 21, 1967; 32 FR 20860, Dec. 28, 1967; 34 FR 6481, Apr. 15, 1969; 45 FR 55201, Aug. 19, 1980; 58 FR 13021, Mar. 9, 1993, 61 FR 4361, Feb. 6, 1996]

§ 1.62 Operation pending action on renewal application.

(a)(1) Where there is pending before the Commission at the time of expiration of license any proper and timely application for renewal of license with respect to any activity of a continuing nature, in accordance with the provisions of section 9(b) of the Administrative Procedure Act, such license shall continue in effect without further action by the Commission until such time as the Commission shall make a final determination with respect to the

Federal Communications Commission

§ 1.65

renewal application. No operation by any licensee under this section shall be construed as a finding by the Commission that the operation will serve the public interest, convenience, or necessity, nor shall such operation in any way affect or limit the action of the Commission with respect to any pending application or proceeding.

(2) A licensee operating by virtue of this paragraph shall, after the date of expiration specified in the license, post, in addition to the original license, any acknowledgment received from the Commission that the renewal application has been accepted for filing or a signed copy of the application for renewal of license which has been submitted by the licensee, or in services other than broadcast and common carrier, a statement certifying that the licensee has mailed or filed a renewal application, specifying the date of mailing or filing.

(b) Where there is pending before the Commission at the time of expiration of license any proper and timely application for renewal or extension of the term of a license with respect to any activity not of a continuing nature, the Commission may in its discretion grant a temporary extension of such license pending determination of such application. No such temporary extension shall be construed as a finding by the Commission that the operation of any radio station thereunder will serve the public interest, convenience, or necessity beyond the express terms of such temporary extension of license, nor shall such temporary extension in any way affect or limit the action of the Commission with respect to any pending application or proceeding.

(c) Except where an instrument of authorization clearly states on its face that it relates to an activity not of a continuing nature, or where the non-continuing nature is otherwise clearly apparent upon the face of the authorization, all licenses issued by the Commission shall be deemed to be related to an activity of a continuing nature.

(5 U.S.C. 558)

§ 1.65 Substantial and significant changes in information furnished by applicants to the Commission.

(a) Each applicant is responsible for the continuing accuracy and completeness of information furnished in a pending application or in Commission proceedings involving a pending application. Except where paragraph (b) of this section applies, whenever the information furnished in the pending application is no longer substantially accurate and complete in all significant respects, the applicant shall as promptly as possible and in any event within 30 days, unless good cause is shown, amend or request the amendment of his application so as to furnish such additional or corrected information as may be appropriate. Except where paragraph (b) of this section applies, whenever there has been a substantial change as to any other matter which may be of decisional significance in a Commission proceeding involving the pending application, the applicant shall as promptly as possible and in any event within 30 days, unless good cause is shown, submit a statement furnishing such additional or corrected information as may be appropriate, which shall be served upon parties of record in accordance with § 1.47. Where the matter is before any court for review, statements and requests to amend shall in addition be served upon the Commission's General Counsel. For the purposes of this section, an application is "pending" before the Commission from the time it is accepted for filing by the Commission until a Commission grant or denial of the application is no longer subject to reconsideration by the Commission or to review by any court.

(b) Changes in information relating to § 1.1622, lottery preferences, must be furnished to the Commission no more than 7 days after the changes occur until: (1) In the case of a non-mutually exclusive application, the Commission releases the Public Notice proposing the application for grant; or (2) in the case of a mutually exclusive application, the Commission releases the final

§ 1.68

Public Notice announcing the acceptance of the last-filed mutually exclusive application.

(c) All broadcast permittees and licensees must report annually to the Commission any adverse finding or adverse final action taken by any court or administrative body that involves conduct bearing on the permittee's or licensee's character qualifications and that would be reportable in connection with an application for renewal as reflected in the renewal form. If a report is required by this paragraph(s), it shall be filed on the anniversary of the date that the licensee's renewal application is required to be filed, except that licensees owning multiple stations with different anniversary dates need file only one report per year on the anniversary of their choice, provided that their reports are not more than one year apart. Permittees and licensees bear the obligation to make diligent, good faith efforts to become knowledgeable of any such reportable adjudicated misconduct.

NOTE: The terms *adverse finding* and *adverse final action* as used in paragraph (c) of this section include adjudications made by an ultimate trier of fact, whether a government agency or court, but do not include factual determinations which are subject to review *de novo* unless the time for taking such review has expired under the relevant procedural rules. The pendency of an appeal of an adverse finding or adverse final action does not relieve a permittee or licensee from its obligation to report the finding or action.

[48 FR 27200, June 13, 1983, as amended at 55 FR 23084, June 6, 1990; 56 FR 25635, June 5, 1991; 56 FR 44009, Sept. 6, 1991; 57 FR 47412, Oct. 16, 1992]

§ 1.68 Action on application for license to cover construction permit.

(a) An application for license by the lawful holder of a construction permit will be granted without hearing where the Commission, upon examination of such application, finds that all the terms, conditions, and obligations set forth in the application and permit have been fully met, and that no cause or circumstance arising or first coming to the knowledge of the Commission since the granting of the permit would, in the judgment of the Commission, make the operation of such station against the public interest.

47 CFR Ch. I (10–1–97 Edition)

(b) In the event the Commission is unable to make the findings in paragraph (a) of this section, the Commission will designate the application for hearing upon specified issues.

(Sec. 319, 48 Stat. 1089, as amended; 47 U.S.C. 319)

§ 1.77 Detailed application procedures; cross references.

The application procedures set forth in §§ 1.61 through 1.68 are general in nature. More detailed procedures are set forth in this chapter as follows:

(a) Rules governing applications for authorizations in the Broadcast Radio Services are set forth in subpart D of this part.

(b) Rules governing applications for authorizations in the Common Carrier Radio Services are set forth in subpart E of this part.

(c) Rules governing applications for authorizations in the Private Radio Services are set forth in subpart F of this part.

(d) Rules governing applications for authorizations in the Experimental Radio Services (other than broadcast) are set forth in part 5 of this chapter.

(e) Rules governing applications for authorizations in the Domestic Public Radio Services are set forth in part 21 of this chapter.

(f) Rules governing applications for authorizations in the Industrial, Scientific, and Medical Service are set forth in part 18 of this chapter.

(g) Rules governing applications for type approval and type acceptance of equipment are set forth in part 2, subpart F, of this chapter.

(h) Rules governing applications for commercial radio operator licenses are set forth in part 13 of this chapter.

(i) Rules governing applications for authorizations in the Common Carrier and Private Radio terrestrial microwave services and Local Multipoint Distribution Services are set out in part 101 of this chapter.

[28 FR 12415, Nov. 22, 1963, as amended at 44 FR 39180, July 5, 1979; 47 FR 53378, Nov. 26, 1982; 61 FR 26670, May 28, 1996; 62 FR 23162, Apr. 29, 1997]

Federal Communications Commission

§ 1.80

MISCELLANEOUS PROCEEDINGS

§ 1.80 Forfeiture proceedings.

(a) *Persons against whom and violations for which a forfeiture may be assessed.* A forfeiture penalty may be assessed against any person found to have:

(1) Willfully or repeatedly failed to comply substantially with the terms and conditions of any license, permit, certificate, or other instrument of authorization issued by the Commission;

(2) Willfully or repeatedly failed to comply with any of the provisions of the Communications Act of 1934, as amended; or of any rule, regulation or order issued by the Commission under that Act or under any treaty, convention, or other agreement to which the United States is a party and which is binding on the United States;

(3) Violated any provision of section 317(c) or 508(a) of the Communications Act; or

(4) Violated any provision of section 1304, 1343, or 1464 of Title 18, United States Code.

A forfeiture penalty assessed under this section is in addition to any other penalty provided for by the Communications Act, except that the penalties provided for in paragraphs (b)(1), (b)(2) and (b)(3) of this section shall not apply to conduct which is subject to a forfeiture penalty under sections 202(c), 203(e), 205(b), 214(d), 219(b), 220(d), 223(b), 362(a), 362(b), 386(a), 386(b), 503(b), 506, and 634 of the Communications Act. The remaining provisions of this section are applicable to such conduct.

(b) *Limits on the amount of forfeiture assessed.* (1) If the violator is a broadcast station licensee or permittee, a cable television operator, or an applicant for any broadcast or cable television operator license, permit, certificate, or other instrument of authorization issued by the Commission, except as otherwise noted in this paragraph, the forfeiture penalty under this section shall not exceed \$27,500 for each violation or each day of a continuing violation, except that the amount assessed for any continuing violation shall not exceed a total of \$275,000 for any single act or failure to act de-

scribed in paragraph (a) of this section. There is no limit on forfeiture assessments for EEO violations by cable operators that occur after notification by the Commission of a potential violation. See section 634(f)(2) of the Communications Act.

(2) If the violator is a common carrier subject to the provisions of the Communications Act or an applicant for any common carrier license, permit, certificate, or other instrument of authorization issued by the Commission, the amount of any forfeiture penalty determined under this section shall not exceed \$110,000 for each violation or each day of a continuing violation, except that the amount assessed for any continuing violation shall not exceed a total of \$1,100,000 for any single act or failure to act described in paragraph (a) of this section.

(3) In any case not covered in paragraphs (b)(1) or (b)(2) of this section, the amount of any forfeiture penalty determined under this section shall not exceed \$11,000 for each violation or each day of a continuing violation, except that the amount assessed for any continuing violation shall not exceed a total of \$82,500 for any single act or failure to act described in paragraph (a) of this section.

NOTE: For information concerning notices of apparent liability and notices of opportunity for hearing, see paragraphs (e), (f), and (g) of this section.

(4) *Factors considered in determining the amount of the forfeiture penalty.* In determining the amount of the forfeiture penalty, the Commission or its designee will take into account the nature, circumstances, extent and gravity of the violations and, with respect to the violator, the degree of culpability, any history of prior offenses, ability to pay, and such other matters as justice may require.

Note to paragraph (b)(4):

GUIDELINES FOR ASSESSING FORFEITURES

The Commission and its staff may use these guidelines in particular cases. The Commission and its staff retain the discretion to issue a higher or lower forfeiture than provided in the guidelines, to issue no forfeiture at all, or to apply alternative or additional sanctions as permitted by the statute. The forfeiture ceiling per violation or per day for a continuing violation stated

§ 1.80

in Section 503 of the Communications Act and the Commission's Rules are \$25,000 for broadcasters and cable operators or applicants, \$100,000 for common carriers or applicants, and \$10,000 for all others. These base amounts listed are for a single violation or single day of a continuing violation. 47 U.S.C. 503(b)(2); 47 CFR 1.80. For continuing violations involving a single act or failure to act, the statute limits the forfeiture to \$250,000 for broadcasters and cable operators or applicants, \$1,000,000 for common carriers or applicants, and \$75,000 for all others. *Id.* Pursuant to the Debt Collection Improvement Act of 1996 (DCIA), Public Law 104-134, section 31001, 110 Stat. 1321 (1996), civil monetary penalties assessed by the federal government, whether set by statutory maxima or specific dollar amounts as provided by federal law, must be adjusted for inflation at least every four years based on the formula outlined in the DCIA. Thus, the statutory maxima increased to \$27,500 for broadcasters and cable operators or applicants; \$110,000 for common carriers or applicants, and \$11,000 for others. For continuing violations, the statutory maxima increased to \$27,500 for broadcasters, cable operators, or applicants; \$1,100,000 for common carriers or applicants; and \$82,500 for others. The increased statutory maxima became effective March 5, 1997. There is an upward adjustment factor for repeated or continuous violations, see Section II, *infra*. That upward adjustment is not necessarily applied on a per violation or per day basis. *Id.* Unless Commission authorization is required for the behavior involved, a Section 503 forfeiture proceeding against a non-licensee or non-applicant who is not a cable operator or common carrier can only be initiated for a second violation, after issuance of a citation in connection with a first violation. 47 U.S.C. 503(b)(5). A prior citation is not required, however, for non-licensee tower owners who have previously received notice of the obligations imposed by Section 303(q) and part 17 of the Commission's rules from the Commission. Forfeitures issued under other sections of the Act are dealt with separately in Section III of this note.

Section I.—Base Amounts for Section 503 Forfeitures

Forfeitures	Violation Amount
Misrepresentation/lack of candor	(¹)
Construction and/or operation without an instrument of authorization for the service	\$10,000
Failure to comply with prescribed lighting and/or marking	10,000
Violation of public file rules	10,000
Violation of political rules: reasonable access, lowest unit charge, equal opportunity, and discrimination	9,000
Unauthorized substantial transfer of control	8,000
Violation of children's television commercialization or programming requirements	8,000

47 CFR Ch. I (10-1-97 Edition)

Forfeitures	Violation Amount
Violations of rules relating to distress and safety frequencies	8,000
False distress communications	8,000
EAS equipment not installed or operational	8,000
Alien ownership violation	8,000
Failure to permit inspection	7,000
Transmission of indecent/obscene materials	7,000
Interference	7,000
Importation or marketing of unauthorized equipment	7,000
Exceeding of authorized antenna height	5,000
Fraud by wire, radio or television	5,000
Unauthorized discontinuance of service	5,000
Use of unauthorized equipment	5,000
Exceeding power limits	4,000
Failure to respond to Commission communications	4,000
Violation of sponsorship ID requirements	4,000
Unauthorized emissions	4,000
Using unauthorized frequency	4,000
Failure to engage in required frequency coordination	4,000
Construction or operation at unauthorized location	4,000
Violation of requirements pertaining to broadcasting of lotteries or contests	4,000
Violation of transmitter control and metering requirements	3,000
Failure to file required forms or information	3,000
Failure to make required measurements or conduct required monitoring	2,000
Failure to provide station ID	1,000
Unauthorized pro forma transfer of control	1,000
Failure to maintain required records	1,000

¹ Statutory Maximum for each Service.

Violations Unique to the Service

Violation	Services affected	Amount
Unauthorized conversion of long distance telephone service.	Common Carrier	\$40,000
Violation of operator services requirements.	Common Carrier	7,000
Violation of pay-per-call requirements.	Common Carrier	7,000
Failure to implement rate reduction or refund order.	Cable	7,500
Violation of cable program access rules.	Cable	7,500
Violation of cable leased access rules.	Cable	7,500
Violation of cable cross-ownership rules.	Cable	7,500
Violation of cable broadcast carriage rules.	Cable	7,500
Violation of pole attachment rules.	Cable	7,500
Failure to maintain directional pattern within prescribed parameters.	Broadcast	7,000
Violation of main studio rule.	Broadcast	7,000
Violation of broadcast hoax rule.	Broadcast	7,000
AM tower fencing	Broadcast	7,000
Broadcasting telephone conversations without authorization.	Broadcast	4,000

Federal Communications Commission

§ 1.80

Violation	Services affected	Amount
Violation of enhanced underwriting requirements.	Broadcast	2,000

Section II. Adjustment Criteria for Section 503 Forfeitures

Upward Adjustment Criteria

- (1) Egregious misconduct.
- (2) Ability to pay/relative disincentive.
- (3) Intentional violation.
- (4) Substantial harm.
- (5) Prior violations of any FCC requirements.
- (6) Substantial economic gain.
- (7) Repeated or continuous violation.

Downward Adjustment Criteria

- (1) Minor violation.
- (2) Good faith or voluntary disclosure.
- (3) History of overall compliance.
- (4) Inability to pay.

Section III. Non-Section 503 Forfeitures That Are Affected by the Downward Adjustment Factors

Unlike Section 503 of the Act, which establishes maximum forfeiture amounts, other sections of the Act, with one exception, state prescribed amounts of forfeitures for violations of the relevant section. These amounts are then subject to mitigation or remission under Section 504 of the Act. The one exception is Section 223 of the Act, which provides a maximum of \$50,000 per day. For convenience, the Commission will treat the \$50,000 set forth in Section 223 as if it were a prescribed base amount, subject to downward adjustments. The following amounts were adjusted for inflation pursuant to the Debt Collection Improvement Act of 1996 (DCIA) Public Law 104-134, section 31001, 110 Stat 1321 (1996). The new amounts became effective on March 5, 1997. These non-Section 503 forfeitures may be adjusted downward using the "Downward Adjustment Criteria" shown for Section 503 forfeitures in Section II of this note.

Violation	Statutory amount (\$)
Sec. 202(c) Common Carrier Discrimination	6,600 330/day
Sec. 203(e) Common Carrier Tariffs	6,600 330/day
Sec. 205(b) Common Carrier Prescriptions	13,200
Sec. 214(d) Common Carrier Line Extensions	1,200/day
Sec. 219(b) Common Carrier Reports	1,200
Sec. 220(d) Common Carrier Records & Accounts	6,600/day
Sec. 223(b) Dial-a-Porn	55,000 maximum/day
Sec. 364(a) Ship Station Inspection	5,500 (owner)

Violation	Statutory amount (\$)
Sec. 364(b) Ship Station Inspection	1,100 (vessel master)
Sec. 386(a) Forfeitures	5,500/day (owner)
Sec. 386(b) Forfeitures	1,100 (vessel master)
Sec. 634 Cable EEO	500/day

(5) *Inflation adjustments to the maximum forfeiture amount.* (i) Pursuant to the Debt Collection Improvement Act of 1996, Public Law 104-134 (110 Stat. 1321-358), which amends the Federal Civil Monetary Penalty Inflation Adjustment Act of 1990, Public Law 101-410 (104 Stat. 890; 28 U.S.C. 2461 note), the statutory maximum amount of a forfeiture penalty assessed under this section shall be adjusted for inflation at least once every four years using the following formula. First, obtain the inflation factor by dividing the CPI for June of the preceding year by the CPI for June of the year the forfeiture was last set or adjusted. Then, multiply the inflation factor by the statutory maximum amount. Round off this result using the rules in paragraph (b)(5)(ii) of this section. Add the rounded result to the statutory maximum forfeiture penalty amount. The sum is the statutory maximum amount, adjusted for inflation.

(ii) The rounding rules are as follows:

(A) Round increase to the nearest multiple of \$10 if the penalty is from \$0 to \$100;

(B) Round increase to the nearest multiple of \$100 if the penalty is from \$101 to \$1,000;

(C) Round increase to the nearest multiple of \$1,000 if the penalty is from \$1,001 to \$10,000;

(D) Round increase to the nearest multiple of \$5,000 if the penalty is from \$10,001 to \$100,000;

(E) Round increase to the nearest multiple of \$10,000 if the penalty is from \$100,001 to \$200,000; or

(F) Round increase to the nearest multiple of \$25,000 if the penalty is over \$200,001.

(iii) The first application of the inflation adjustments required by Public Law 104-134 results in the following adjustments to the statutory forfeitures

§ 1.80

47 CFR Ch. I (10–1–97 Edition)

currently authorized by the Communications Act:

U.S. Code citation	Current statutory maximum penalty	Maximum penalty after Public Law 104–134 adjustment
47 USC 202(c)	\$6,000	\$6,600
47 USC 203(e)	300	330
47 USC 205(b)	6,000	6,600
47 USC 214(d)	300	330
47 USC 219(b)	12,000	13,200
47 USC 220(d)	1,200	1,200
47 USC 223(b)	1,200	1,200
47 USC 362(a)	6,000	6,600
47 USC 362(b)	50,000	55,000
47 USC 386(a)	5,000	5,500
47 USC 386(b)	1,000	1,100
47 USC 503(b)(2)(A)	5,000	5,500
47 USC 503(b)(2)(B)	1,000	1,100
47 USC 503(b)(2)(C)	25,000	27,500
47 USC 506(a)	250,000	275,000
47 USC 506(b)	100,000	110,000
47 USC 554	1,000,000	1,100,000
	10,000	11,000
	75,000	82,500
	500	550
	100	110
	500	500

NOTE: Pursuant to Public Law 104–134, the first inflation adjustment cannot exceed 10 percent of the statutory maximum amount.

(c) *Limits on the time when a proceeding may be initiated.* (1) In the case of a broadcast station, no forfeiture penalty shall be imposed if the violation occurred more than 1 year prior to the issuance of the appropriate notice or prior to the date of commencement of the current license term, whichever is earlier. For purposes of this paragraph, “date of commencement of the current license term” means the date of commencement of the last term of license for which the licensee has been granted a license by the Commission. A separate license term shall not be deemed to have commenced as a result of continuing a license in effect under section 307(c) pending decision on an application for renewal of the license.

(2) In the case of a forfeiture imposed against a carrier under sections 202(c), 203(e), and 220(d), no forfeiture will be imposed if the violation occurred more than 5 years prior to the issuance of a notice of apparent liability.

(3) In all other cases, no penalty shall be imposed if the violation occurred more than 1 year prior to the date on which the appropriate notice is issued.

(d) *Preliminary procedure in some cases; citations.* No forfeiture penalty shall be imposed upon any person under this

section, if such person does not hold a license, permit, certificate, or other authorization issued by the Commission, and if such person is not an applicant for a license, permit, certificate, or other authorization issued by the Commission, unless, prior to the issuance of the appropriate notice, such person: (1) Is sent a citation reciting the violation charged; (2) is given a reasonable opportunity (usually 30 days) to request a personal interview with a Commission official, at the field office which is nearest to such person’s place of residence; and (3) subsequently engages in conduct of the type described in the citation. However, a forfeiture penalty may be imposed, if such person is engaged in (and the violation relates to) activities for which a license, permit, certificate, or other authorization is required or if such person is a cable television operator, or in the case of violations of section 303(q), if the person involved is a nonlicensee tower owner who has previously received notice of the obligations imposed by section 303(q) from the Commission or the permittee or licensee who uses that tower. Paragraph (c) of this section does not limit the issuance of citations. When the requirements of this paragraph have been satisfied with respect to a particular violation by a particular person, a forfeiture penalty may be imposed upon such person for conduct of the type described in the citation without issuance of an additional citation.

(e) *Alternative procedures.* In the discretion of the Commission, a forfeiture proceeding may be initiated either: (1) By issuing a notice of apparent liability, in accordance with paragraph (f) of this section, or (2) a notice of opportunity for hearing, in accordance with paragraph (g).

(f) *Notice of apparent liability.* Before imposing a forfeiture penalty under the provisions of this paragraph, the Commission or its designee will issue a written notice of apparent liability.

(1) *Content of notice.* The notice of apparent liability will:

(i) Identify each specific provision, term, or condition of any act, rule, regulation, order, treaty, convention, or other agreement, license, permit, certificate, or instrument of authorization

Federal Communications Commission

§ 1.80

which the respondent has apparently violated or with which he has failed to comply,

(ii) Set forth the nature of the act or omission charged against the respondent and the facts upon which such charge is based,

(iii) State the date(s) on which such conduct occurred, and

(iv) Specify the amount of the apparent forfeiture penalty.

(2) *Delivery.* The notice of apparent liability will be sent to the respondent, by certified mail, at his last known address (see § 1.5).

(3) *Response.* The respondent will be afforded a reasonable period of time (usually 30 days from the date of the notice) to show, in writing, why a forfeiture penalty should not be imposed or should be reduced, or to pay the forfeiture. Any showing as to why the forfeiture should not be imposed or should be reduced shall include a detailed factual statement and such documentation and affidavits as may be pertinent.

(4) *Forfeiture order.* If the proposed forfeiture penalty is not paid in full in response to the notice of apparent liability, the Commission, upon considering all relevant information available to it, will issue an order canceling or reducing the proposed forfeiture or requiring that it be paid in full and stating the date by which the forfeiture must be paid.

(5) *Judicial enforcement of forfeiture order.* If the forfeiture is not paid, the case will be referred to the Department of Justice for collection under section 504(a) of the Communications Act.

(g) *Notice of opportunity for hearing.* The procedures set out in this paragraph will ordinarily be followed only when a hearing is being held for some reason other than the assessment of a forfeiture (such as, to determine whether a renewal application should be granted) and a forfeiture is to be considered as an alternative or in addition to any other Commission action. However, these procedures may be followed whenever the Commission, in its discretion, determines that they will better serve the ends of justice.

(1) Before imposing a forfeiture penalty under the provisions of this paragraph, the Commission will issue a notice of opportunity for hearing. The

hearing will be a full evidentiary hearing before an administrative law judge, conducted under procedures set out in subpart B of this part, including procedures for appeal and review of initial decisions. A final Commission order assessing a forfeiture under the provisions of this paragraph is subject to judicial review under section 402(a) of the Communications Act.

(2) If, after a forfeiture penalty is imposed and not appealed or after a court enters final judgment in favor of the Commission, the forfeiture is not paid, the Commission will refer the matter to the Department of Justice for collection. In an action to recover the forfeiture, the validity and appropriateness of the order imposing the forfeiture are not subject to review.

(3) Where the possible assessment of a forfeiture is an issue in a hearing case to determine which pending application should be granted, and the applicant facing a potential forfeiture is dismissed pursuant to a settlement agreement or otherwise, and the presiding judge has not made a determination on the forfeiture issue, the order of dismissal shall be forwarded to the attention of the full Commission. Within the time provided by § 1.117, the Commission may, on its own motion, proceed with a determination of whether a forfeiture against the dismissing applicant is warranted. If the Commission so proceeds, it will provide the applicant with a reasonable opportunity to respond to the forfeiture issue (see paragraph (f)(3) of this section) and make a determination under the procedures outlined in paragraph (f) of this section.

(h) *Payment.* The forfeiture should be paid by check or money order drawn to the order of the Federal Communications Commission. The Commission does not accept responsibility for cash payments sent through the mails. The check or money order should be mailed to: Federal Communications Commission, P.O. Box 73482, Chicago, Illinois 60673-7482.

(i) *Remission and mitigation.* In its discretion, the Commission, or its designee, may remit or reduce any forfeiture imposed under this section. After issuance of a forfeiture order, any request that it do so shall be submitted

§1.83

47 CFR Ch. I (10–1–97 Edition)

as a petition for reconsideration pursuant to §1.106.

(j) *Effective date.* Amendments to paragraph (b) of this section implementing Pub. L. No. 101–239 are effective December 19, 1989.

[43 FR 49308, Oct. 23, 1978, as amended at 48 FR 15631, Apr. 12, 1983; 50 FR 40855, Oct. 7, 1985; 55 FR 25605, June 22, 1990; 56 FR 25638, June 5, 1991; 57 FR 23161, June 2, 1992; 57 FR 47006, Oct. 14, 1992; 57 FR 48333, Oct. 23, 1992; 58 FR 6896, Feb. 3, 1993; 58 FR 27473, May 10, 1993; 62 FR 4918, Feb. 3, 1997; 62 FR 43475, Aug. 14, 1997]

EFFECTIVE DATE NOTE: At 62 FR 43475, Aug. 14, 1997, the note to paragraph (b)(4) was added, effective Oct. 14, 1997.

§1.83 Applications for radio operator licenses.

(a) Application filing procedures for amateur radio operator licenses are set forth in part 97 of this chapter.

(b) Application filing procedures for commercial radio operator licenses are set forth in part 13 of this chapter. Detailed information about application forms, filing procedures, and where to file applications for commercial radio operator licenses is contained in the bulletin “Commercial Radio Operator Licenses and Permits.” This bulletin is available from the Private Radio Bureau, Licensing Division, Consumer Assistance Branch, 1270 Fairfield Road, Gettysburg, PA 17325–7245.

[47 FR 53378, Nov. 26, 1982, as amended at 58 FR 13021, Mar. 9, 1993]

§1.84 Procedure with respect to commercial radio operator license applications.

(a) Upon acceptance of an application for a commercial radio operator license, filed in accordance with part 13 of this chapter, an examination, if required, is conducted. If the applicant is found qualified and eligible in all respects, the license will be issued. If additional information is necessary to determine an applicant’s qualifications or eligibility, or if it appears that a grant of an application would not serve the public interest, the applicant will be notified in writing and given an opportunity to provide additional pertinent information in writing. If, from the information available, it appears that the applicant is not qualified or is

ineligible, or that a grant of the application would not serve the public interest, the applicant will be advised thereof in writing and given an opportunity to request, within a specified period of time, that the application be set for hearing. If the applicant does not request, within the specified period, that the application be set for hearing, the application will be denied.

(b)–(c) [Reserved]

(d) Failure to prosecute an application, or failure to respond to official correspondence or request for additional information, will be cause for dismissal. Such dismissal will be without prejudice where an application has not yet been designated for hearing; such dismissal may be made with prejudice after an application has been designated for hearing.

(Sec. 303(l), 48 Stat. 1082, as amended; 47 U.S.C. 303(l))

[29 FR 15965, Nov. 24, 1964, as amended at 47 FR 53378, Nov. 26, 1982]

§1.85 Suspension of operator licenses.

Whenever grounds exist for suspension of an operator license, as provided in section 303(m) of the Communications Act, the Chief of the Private Radio Bureau, with respect to amateur and commercial radio operator licenses, may issue an order suspending the operator license. No order of suspension of any operator’s license shall take effect until 15 days’ notice in writing of the cause for the proposed suspension has been given to the operator licensee, who may make written application to the Commission at any time within the said 15 days for a hearing upon such order. The notice to the operator licensee shall not be effective until actually received by him, and from that time he shall have 15 days in which to mail the said application. In the event that physical conditions prevent mailing of the application before the expiration of the 15-day period, the application shall then be mailed as soon as possible thereafter, accompanied by a satisfactory explanation of the delay. Upon receipt by the Commission of such application for hearing, said order of suspension shall be designated for hearing by the Chief, Private Radio Bureau and said suspension

Federal Communications Commission

§ 1.87

shall be held in abeyance until the conclusion of the hearing. Upon the conclusion of said hearing, the Commission may affirm, modify, or revoke said order of suspension. If the license is ordered suspended, the operator shall send his operator license to the office of the Commission in Washington, DC, on or before the effective date of the order, or, if the effective date has passed at the time notice is received, the license shall be sent to the Commission forthwith.

(Sec. 303(m), 48 Stat. 1082, as amended; 47 U.S.C. 303(m))

[28 FR 10415, Nov. 22, 1963, as amended at 44 FR 39180, July 5, 1979; 58 FR 13021, Mar. 9, 1993]

§ 1.87 Modification of license or construction permit on motion of the Commission.

(a) Whenever it appears that a station license or construction permit should be modified, the Commission shall notify the licensee or permittee in writing of the proposed action and reasons therefor, and afford the licensee or permittee at least thirty days to protest such proposed order of modification, except that, where safety of life or property is involved, the Commission may by order provide a shorter period of time.

(b) The notification required in paragraph (a) of this section may be effectuated by a notice of proposed rule making in regard to a modification or addition of an FM or television channel to the Table of Allotments (§§ 73.202 and 73.504) or Table of Assignments (§ 73.606). The Commission shall send a copy of any such notice of proposed rule making to the affected licensee or permittee by certified mail, return receipt requested.

(c) Any other licensee or permittee who believes that its license or permit would be modified by the proposed action may also protest the proposed action before its effective date.

(d) Any protest filed pursuant to this section shall be subject to the requirements of section 309 of the Communications Act of 1934, as amended, for petitions to deny.

(e) In any case where a hearing is conducted pursuant to the provisions of this section, both the burden of pro-

ceeding with the introduction of evidence and the burden of proof shall be upon the Commission except that, with respect to any issue that pertains to the question of whether the proposed action would modify the license or permit of a person filing a protest pursuant to paragraph (c) of this section, such burdens shall be as described by the Commission.

(f) In order to utilize the right to a hearing and the opportunity to appear and give evidence upon the issues specified in any hearing order, the licensee or permittee, in person or by attorney, shall, within the period of time as may be specified in the hearing order, file with the Commission a written statement stating that he or she will appear at the hearing and present evidence on the matters specified in the hearing order.

(g) The right to file a protest or have a hearing shall, unless good cause is shown in a petition to be filed not later than 5 days before the lapse of time specified in paragraph (a) or (f) of this section, be deemed waived:

(1) In case of failure to timely file the protest as required by paragraph (a) of this section or a written statement as required by paragraph (f) of this section.

(2) In case of filing a written statement provided for in paragraph (f) of this section but failing to appear at the hearing, either in person or by counsel.

(h) Where the right to file a protest or have a hearing is waived, the licensee or permittee will be deemed to have consented to the modification as proposed and a final decision may be issued by the Commission accordingly. Irrespective of any waiver as provided for in paragraph (g) of this section or failure by the licensee or permittee to raise a substantial and material question of fact concerning the proposed modification in his protest, the Commission may, on its own motion, designate the proposed modification for hearing in accordance with this section.

(i) Any order of modification issued pursuant to this section shall include a statement of the findings and the grounds and reasons therefor, shall

§ 1.88

specify the effective date of the modification, and shall be served on the licensee or permittee.

[52 FR 22654, June 15, 1987]

§ 1.88 Predesignation pleading procedure.

In cases where an investigation is being conducted by the Commission in connection with the operation of a broadcast station or a pending application for renewal of a broadcast license, the licensee may file a written statement to the Commission setting forth its views regarding the matters under investigation; the staff, in its discretion, may in writing, advise such licensee of the general nature of the investigation, and advise the licensee of its opportunity to submit such a statement to the staff. Any filing by the licensee will be forwarded to the Commission in conjunction with any staff memorandum recommending that the Commission take action as a result of the investigation. Nothing in this rule shall supersede the application of our *ex parte* rules to situations described in § 1.1203 of these rules.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; (47 U.S.C. 154, 303, 307))

[45 FR 65597, Oct. 3, 1980]

§ 1.89 Notice of violations.

(a) Except in cases of willfulness or those in which public health, interest, or safety requires otherwise, any person who holds a license, permit or other authorization appearing to have violated any provision of the Communications Act or any provision of this chapter will, before revocation, suspension, or cease and desist proceedings are instituted, be served with a written notice calling these facts to his or her attention and requesting a statement concerning the matter. FCC Form 793 may be used for this purpose. The Notice of Violation may be combined with a Notice of Apparent Liability to Monetary Forfeiture. In such event, notwithstanding the Notice of Violation, the provisions of § 1.80 apply and not those of § 1.89.

(b) Within 10 days from receipt of notice or such other period as may be specified, the recipient shall send a written answer, in duplicate, directly

47 CFR Ch. I (10–1–97 Edition)

to the Commission office originating the official notice. If an answer cannot be sent or an acknowledgment cannot be made within such 10-day period by reason of illness or other unavoidable circumstance, acknowledgment and answer shall be made at the earliest practicable date with a satisfactory explanation of the delay.

(c) The answer to each notice shall be complete in itself and shall not be abbreviated by reference to other communications or answers to other notices. In every instance the answer shall contain a statement of action taken to correct the condition or omission complained of and to preclude its recurrence. In addition:

(1) If the notice relates to violations that may be due to the physical or electrical characteristics of transmitting apparatus and any new apparatus is to be installed, the answer shall state the date such apparatus was ordered, the name of the manufacturer, and the promised date of delivery. If the installation of such apparatus requires a construction permit, the file number of the application shall be given, or if a file number has not been assigned by the Commission, such identification shall be given as will permit ready identification of the application.

(2) If the notice of violation relates to lack of attention to or improper operation of the transmitter, the name and license number of the operator in charge (where applicable) shall be given.

[48 FR 24890, June 3, 1983]

§ 1.91 Revocation and/or cease and desist proceedings; hearings.

(a) If it appears that a station license or construction permit should be revoked and/or that a cease and desist order should be issued, the Commission will issue an order directing the person to show cause why an order of revocation and/or a cease and desist order, as the facts may warrant, should not be issued.

(b) An order to show cause why an order of revocation and/or a cease and desist order should not be issued will contain a statement of the matters with respect to which the Commission

Federal Communications Commission

§ 1.92

is inquiring and will call upon the person to whom it is directed (the respondent) to appear before the Commission at a hearing, at a time and place stated in the order, but not less than thirty days after the receipt of such order, and given evidence upon the matters specified in the order to show cause. However, if safety of life or property is involved, the order to show cause may specify a hearing date less than thirty days from the receipt of such order.

(c) To avail himself of such opportunity for hearing, the respondent, personally or by his attorney, shall file with the Commission, within thirty days of the service of the order or such shorter period as may be specified therein, a written appearance stating that he will appear at the hearing and present evidence on the matters specified in the order. The Commission in its discretion may accept a late appearance. However, an appearance tendered after the specified time has expired will not be accepted unless accompanied by a petition stating with particularity the facts and reasons relied on to justify such late filing. Such petition for acceptance of late appearance will be granted only if the Commission determines that the facts and reasons stated therein constitute good cause for failure to file on time.

(d) Hearings on the matters specified in such orders to show cause shall accord with the practice and procedure prescribed in this subpart and subpart B of this part, with the following exceptions: (1) In all such revocation and/or cease and desist hearings, the burden of proceeding with the introduction of evidence and the burden of proof shall be upon the Commission; and (2) the Commission may specify in a show cause order, when the circumstances of the proceeding require expedition, a time less than that prescribed in §§ 1.276 and 1.277 within which the initial decision in the proceeding shall become effective, exceptions to such initial decision must be filed, parties must file requests for oral argument, and parties must file notice of intention to participate in oral argument.

(e) Correction of or promise to correct the conditions or matters com-

plained of in a show cause order shall not preclude the issuance of a cease and desist order. Corrections or promises to correct the conditions or matters complained of, and the past record of the licensee, may, however, be considered in determining whether a revocation and/or a cease and desist order should be issued.

(f) Any order of revocation and/or cease and desist order issued after hearing pursuant to this section shall include a statement of findings and the grounds therefor, shall specify the effective date of the order, and shall be served on the person to whom such order is directed.

(Sec. 312, 48 Stat. 1086, as amended; 47 U.S.C. 312)

§ 1.92 Revocation and/or cease and desist proceedings; after waiver of hearing.

(a) After the issuance of an order to show cause, pursuant to § 1.91, calling upon a person to appear at a hearing before the Commission, the occurrence of any one of the following events or circumstances will constitute a waiver of such hearing and the proceeding thereafter will be conducted in accordance with the provisions of this section.

(1) The respondent fails to file a timely written appearance as prescribed in § 1.91(c) indicating that he will appear at a hearing and present evidence on the matters specified in the order.

(2) The respondent, having filed a timely written appearance as prescribed in § 1.91(c), fails in fact to appear in person or by his attorney at the time and place of the duly scheduled hearing.

(3) The respondent files with the Commission, within the time specified for a written appearance in § 1.91(c), a written statement expressly waiving his rights to a hearing.

(b) When a hearing is waived under the provisions of paragraph (a) (1) or (3) of this section, a written statement signed by the respondent denying or seeking to mitigate or justify the circumstances or conduct complained of in the order to show cause may be submitted within the time specified in

§ 1.93

§ 1.91(c). The Commission in its discretion may accept a late statement. However, a statement tendered after the specified time has expired will not be accepted unless accompanied by a petition stating with particularity the facts and reasons relied on to justify such late filing. Such petitions for acceptance of a late statement will be granted only if the Commission determines that the facts and reasons stated therein constitute good cause for failure to file on time.

(c) Whenever a hearing is waived by the occurrence of any of the events or circumstances listed in paragraph (a) of this section, the Chief Administrative Law Judge (or the presiding officer if one has been designated) shall, at the earliest practicable date, issue an order reciting the events or circumstances constituting a waiver of hearing, terminating the hearing proceeding, and certifying the case to the Commission. Such order shall be served upon the respondent.

(d) After a hearing proceeding has been terminated pursuant to paragraph (c) of this section, the Commission will act upon the matters specified in the order to show cause in the regular course of business. The Commission will determine on the basis of all the information available to it from any source, including such further proceedings as may be warranted, if a revocation order and/or a cease and desist order should issue, and if so, will issue such order. Otherwise, the Commission will issue an order dismissing the proceeding. All orders specified in this paragraph will include a statement of the findings of the Commission and the grounds and reasons therefor, will specify the effective date thereof, and will be served upon the respondent.

(e) Corrections or promise to correct the conditions or matters complained of in a show cause order shall not preclude the issuance of a cease and desist order. Corrections or promises to correct the conditions or matters complained of, and the past record of the licensee, may, however, be considered in determining whether a revocation and/or a cease and desist order should be issued.

47 CFR Ch. I (10–1–97 Edition)

(Sec. 312, 48 Stat. 1086, as amended; 47 U.S.C. 312)

[28 FR 12415, Nov. 22, 1963, as amended at 29 FR 6443, May 16, 1964; 37 FR 19372, Sept. 20, 1972]

§ 1.93 Consent orders.

(a) As used in this subpart, a “consent order” is a formal decree accepting an agreement between a party to an adjudicatory hearing proceeding held to determine whether that party has violated statutes or Commission rules or policies and the appropriate operating Bureau, with regard to such party’s future compliance with such statutes, rules or policies, and disposing of all issues on which the proceeding was designated for hearing. The order is issued by the officer designated to preside at the hearing or (if no officer has been designated) by the Chief Administrative Law Judge.

(b) Where the interests of timely enforcement or compliance, the nature of the proceeding, and the public interest permit, the Commission, by its operating Bureaus, may negotiate a consent order with a party to secure future compliance with the law in exchange for prompt disposition of a matter subject to administrative adjudicative proceedings. Consent orders may not be negotiated with respect to matters which involve a party’s basic statutory qualifications to hold a license (see 47 U.S.C. 308 and 309).

[41 FR 14871, Apr. 8, 1976]

§ 1.94 Consent order procedures.

(a) Negotiations leading to a consent order may be initiated by the operating Bureau or by a party whose possible violations are issues in the proceeding. Negotiations may be initiated at any time after designation of a proceeding for hearing. If negotiations are initiated the presiding officer shall be notified. Parties shall be prepared at the initial prehearing conference to state whether they are at that time willing to enter negotiations. See § 1.248(c)(7). If either party is unwilling to enter negotiations, the hearing proceeding shall proceed. If the parties agree to enter negotiations, they will be afforded an appropriate opportunity to negotiate before the hearing is commenced.

Federal Communications Commission

§ 1.95

(b) Other parties to the proceeding are entitled, but are not required, to participate in the negotiations, and may join in any agreement which is reached.

(c) Every agreement shall contain the following:

(1) An admission of all jurisdictional facts;

(2) A waiver of the usual procedures for preparation and review of an initial decision;

(3) A waiver of the right of judicial review or otherwise to challenge or contest the validity of the consent order;

(4) A statement that the designation order may be used in construing the consent order;

(5) A statement that the agreement shall become a part of the record of the proceeding only if the consent order is signed by the presiding officer and the time for review has passed without rejection of the order by the Commission;

(6) A statement that the agreement is for purposes of settlement only and that its signing does not constitute an admission by any party of any violation of law, rules or policy (see 18 U.S.C. 6002); and

(7) A draft order for signature of the presiding officer resolving by consent, and for the future, all issues specified in the designation order.

(d) If agreement is reached, it shall be submitted to the presiding officer or Chief Administrative Law Judge, as the case may be, who shall either sign the order, reject the agreement, or suggest to the parties that negotiations continue on such portion of the agreement as he considers unsatisfactory or on matters not reached in the agreement. If he rejects the agreement, the hearing shall proceed. If he suggests further negotiations, the hearing will proceed or negotiations will continue, depending on the wishes of parties to the agreement. If he signs the consent order, he shall close the record.

(e) Any party to the proceeding who has not joined in any agreement which is reached may appeal the consent order under § 1.302, and the Commission may review the agreement on its own motion under the provisions of that section. If the Commission rejects the consent order, the proceeding will be

remanded for further proceedings. If the Commission does not reject the consent order, it shall be entered in the record as a final order and is subject to judicial review on the initiative only of parties to the proceeding who did not join in the agreement. The Commission may revise the agreement and consent order. In that event, private parties to the agreement may either accept the revision or withdraw from the agreement. If the party whose possible violations are issues in the proceeding withdraws from the agreement, the consent order will not be issued or made a part of the record, and the proceeding will be remanded for further proceedings.

(f) The provisions of this section shall not alter any existing procedure for informal settlement of any matter prior to designation for hearing (see, e.g., 47 U.S.C. 208) or for summary decision after designation for hearing.

(g) Consent orders, pleadings relating thereto, and Commission orders with respect thereto shall be served on parties to the proceeding. Public notice will be given of orders issued by an administrative law judge, the Chief Administrative Law Judge, or the Commission. Negotiating papers constitute work product, are available to parties participating in negotiations, but are not routinely available for public inspection.

[41 FR 14871, Apr. 8, 1976]

§ 1.95 Violation of consent orders.

Violation of a consent order shall subject the consenting party to any and all sanctions which could have been imposed in the proceeding resulting in the consent order if all of the issues in that proceeding had been decided against the consenting party and to any further sanctions for violation noted as agreed upon in the consent order. The Commission shall have the burden of showing that the consent order has been violated in some (but not in every) respect. Violation of the consent order and the sanctions to be imposed shall be the only issues considered in a proceeding concerning such an alleged violation.

[41 FR 14871, Apr. 8, 1976]

§ 1.101

47 CFR Ch. I (10–1–97 Edition)

RECONSIDERATION AND REVIEW OF ACTIONS TAKEN BY THE COMMISSION AND PURSUANT TO DELEGATED AUTHORITY; EFFECTIVE DATES AND FINALITY DATES OF ACTIONS

§ 1.101 General provisions.

Under section 5(c) of the Communications Act of 1934, as amended, the Commission is authorized, by rule or order, to delegate certain of its functions to a panel of commissioners, an individual commissioner, an employee board, or an individual employee. Section 0.201(a) of this chapter describes in general terms the basic categories of delegations which are made by the Commission. Subpart B of part 0 of this chapter sets forth all delegations which have been made by rule. Sections 1.102 through 1.120 set forth procedural rules governing reconsideration and review of actions taken pursuant to authority delegated under section 5(c) of the Communications Act, and reconsideration of actions taken by the Commission. As used in §§ 1.102 through 1.117, the term *designated authority* means any person, panel, or board which has been authorized by rule or order to exercise authority under section 5(c) of the Communications Act.

[28 FR 12415, Nov. 22, 1963, as amended at 62 FR 4170, Jan. 29, 1997]

§ 1.102 Effective dates of actions taken pursuant to delegated authority.

(a) *Final actions following review of an initial decision.* (1) Final decisions of a commissioner, or panel of commissioners following review of an initial decision shall be effective 40 days after public release of the full text of such final decision.

(2) If a petition for reconsideration of such final decision is filed, the effect of the decision is stayed until 40 days after release of the final order disposing of the petition.

(3) If an application for review of such final decision is filed, or if the Commission on its own motion orders the record of the proceeding before it for review, the effect of the decision is stayed until the Commission's review of the proceeding has been completed.

(b) *Non-hearing and interlocutory actions.* (1) Non-hearing or interlocutory actions taken pursuant to delegated

authority shall, unless otherwise ordered by the designated authority, be effective upon release of the document containing the full text of such action, or in the event such a document is not released, upon release of a public notice announcing the action in question.

(2) If a petition for reconsideration of a non-hearing action is filed, the designated authority may in its discretion stay the effect of its action pending disposition of the petition for reconsideration. Petitions for reconsideration of interlocutory actions will not be entertained.

(3) If an application for review of a non-hearing or interlocutory action is filed, or if the Commission reviews the action on its own motion, the Commission may in its discretion stay the effect of any such action until its review of the matters at issue has been completed.

[28 FR 12415, Nov. 22, 1963, as amended at 62 FR 4170, Jan. 29, 1997]

§ 1.103 Effective dates of Commission actions; finality of Commission actions.

(a) Unless otherwise specified by law or Commission rule (e.g. §§ 1.102 and 1.427), the effective date of any Commission action shall be the date of public notice of such action as that latter date is defined in § 1.4(b) of these rules: *Provided*, That the Commission may, on its own motion or on motion by any party, designate an effective date that is either earlier or later in time than the date of public notice of such action. The designation of an earlier or later effective date shall have no effect on any pleading periods.

(b) Notwithstanding any determinations made under paragraph (a) of this section, Commission action shall be deemed final, for purposes of seeking reconsideration at the Commission or judicial review, on the date of public notice as defined in § 1.4(b) of these rules.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[46 FR 18556, Mar. 25, 1981]

Federal Communications Commission

§1.106

§1.104 Preserving the right of review; deferred consideration of application for review.

(a) The provisions of this section apply to all final actions taken pursuant to delegated authority, including final actions taken by members of the Commission's staff on nonhearing matters. They do not apply to interlocutory actions of the Chief Administrative Law Judge in hearing proceedings, or to hearing designation orders issued under delegated authority. See §§0.351, 1.106(a) and 1.115(e).

(b) Any person desiring Commission consideration of a final action taken pursuant to delegated authority shall file either a petition for reconsideration or an application for review (but not both) within 30 days from the date of public notice of such action, as that date is defined in §1.4(b) of these rules. The petition for reconsideration will be acted on by the designated authority or referred by such authority to the Commission: *Provided*, That a petition for reconsideration of an order designating a matter for hearing will in all cases be referred to the Commission. The application for review will in all cases be acted upon by the Commission.

NOTE: In those cases where the Commission does not intend to release a document containing the full text of its action, it will state that fact in the public notice announcing its action.

(c) If in any matter one party files a petition for reconsideration and a second party files an application for review, the Commission will withhold action on the application for review until final action has been taken on the petition for reconsideration.

(d) Any person who has filed a petition for reconsideration may file an application for review within 30 days from the date of public notice of such action, as that date is defined in §1.4(b) of these rules. If a petition for reconsideration has been filed, any person who has filed an application for review may: (1) Withdraw his application for review, or (2) substitute an amended application therefor.

NOTE: In those cases where the Commission does not intend to release a document containing the full text of its action, it will

state that fact in the public notice announcing its action.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[28 FR 12415, Nov. 22, 1963, as amended at 41 FR 14871, Apr. 8, 1976; 44 FR 60294, Oct. 19, 1979; 46 FR 18556, Mar. 25, 1981; 62 FR 4170, Jan. 29, 1997]

§1.106 Petitions for reconsideration.

(a)(1) Petitions requesting reconsideration of a final Commission action will be acted on by the Commission. Petitions requesting reconsideration of other final actions taken pursuant to delegated authority will be acted on by the designated authority or referred by such authority to the Commission. A petition for reconsideration of an order designating a case for hearing will be entertained if, and insofar as, the petition relates to an adverse ruling with respect to petitioner's participation in the proceeding. Petitions for reconsideration of other interlocutory actions will not be entertained. (For provisions governing reconsideration of Commission action in notice and comment rule making proceedings, see §1.429. This §1.106 does not govern reconsideration of such actions.)

(2) Within the period allowed for filing a petition for reconsideration, any party to the proceeding may request the presiding officer to certify to the Commission the question as to whether, on policy in effect at the time of designation or adopted since designation, and undisputed facts, a hearing should be held. If the presiding officer finds that there is substantial doubt, on established policy and undisputed facts, that a hearing should be held, he will certify the policy question to the Commission with a statement to that effect. No appeal may be filed from an order denying such a request. See also, §§1.229 and 1.251.

(b)(1) Subject to the limitations set forth in paragraph (b)(2) of this section, any party to the proceeding, or any other person whose interests are adversely affected by any action taken by the Commission or by the designated authority, may file a petition requesting reconsideration of the action taken. If the petition is filed by a person who is not a party to the proceeding, it shall state with particularity

the manner in which the person's interests are adversely affected by the action taken, and shall show good reason why it was not possible for him to participate in the earlier stages of the proceeding.

(2) Where the Commission has denied an application for review, a petition for reconsideration will be entertained only if one or more of the following circumstances is present:

(i) The petition relies on facts which relate to events which have occurred or circumstances which have changed since the last opportunity to present such matters; or

(ii) The petition relies on facts unknown to petitioner until after his last opportunity to present such matters which could not, through the exercise of ordinary diligence, have been learned prior to such opportunity.

(3) A petition for reconsideration of an order denying an application for review which fails to rely on new facts or changed circumstances may be dismissed by the staff as repetitious.

(c) A petition for reconsideration which relies on facts not previously presented to the Commission or to the designated authority may be granted only under the following circumstances:

(1) The facts fall within one or more of the categories set forth in § 1.106(b)(2); or

(2) The Commission or the designated authority determines that consideration of the facts relied on is required in the public interest.

(d)(1) The petition shall state with particularity the respects in which petitioner believes the action taken by the Commission or the designated authority should be changed. The petition shall state specifically the form or relief sought and, subject to this requirement, may contain alternative requests.

(2) The petition for reconsideration shall also, where appropriate, cite the findings of fact and/or conclusions of law which petitioner believes to be erroneous, and shall state with particularity the respects in which he believes such findings and conclusions should be changed. The petition may request that additional findings of fact and conclusions of law be made.

(e) Where a petition for reconsideration is based upon a claim of electrical interference, under appropriate rules in this chapter, to an existing station or a station for which a construction permit is outstanding, such petition, in addition to meeting the other requirements of this section, must be accompanied by an affidavit of a qualified radio engineer. Such affidavit shall show, either by following the procedures set forth in this chapter for determining interference in the absence of measurements, or by actual measurements made in accordance with the methods prescribed in this chapter, that electrical interference will be caused to the station within its normally protected contour.

(f) The petition for reconsideration and any supplement thereto shall be filed within 30 days from the date of public notice of the final Commission action, as that date is defined in § 1.4(b) of these rules, and shall be served upon parties to the proceeding. The petition for reconsideration shall not exceed 25 double spaced typewritten pages. No supplement or addition to a petition for reconsideration which has not been acted upon by the Commission or by the designated authority, filed after expiration of the 30 day period, will be considered except upon leave granted upon a separate pleading for leave to file, which shall state the grounds therefor.

(g) Oppositions to a petition for reconsideration shall be filed within 10 days after the petition is filed, and shall be served upon petitioner and parties to the proceeding. Oppositions shall not exceed 25 double spaced typewritten pages.

(h) Petitioner may reply to oppositions within seven days after the last day for filing oppositions, and any such reply shall be served upon parties to the proceeding. Replies shall not exceed 10 double spaced typewritten pages, and shall be limited to matters raised in the opposition.

(i) Petitions for reconsideration, oppositions, and replies shall conform to the requirements of §§ 1.49, 1.51, and 1.52 and shall be submitted to the Secretary, Federal Communications Commission, Washington, D.C., 20554.

Federal Communications Commission

§ 1.108

(j) The Commission or designated authority may grant the petition for reconsideration in whole or in part or may deny the petition. Its order will contain a concise statement of the reasons for the action taken. Where the petition for reconsideration relates to an instrument of authorization granted without hearing, the Commission or designated authority will take such action within 90 days after the petition is filed.

(k)(1) If the Commission or the designated authority grants the petition for reconsideration in whole or in part, it may, in its decision:

(i) Simultaneously reverse or modify the order from which reconsideration is sought;

(ii) Remand the matter to a bureau or other Commission personnel for such further proceedings, including rehearing, as may be appropriate; or

(iii) Order such other proceedings as may be necessary or appropriate.

(2) If the Commission or designated authority initiates further proceedings, a ruling on the merits of the matter will be deferred pending completion of such proceedings. Following completion of such further proceedings, the Commission or designated authority may affirm, reverse, or modify its original order, or it may set aside the order and remand the matter for such further proceedings, including rehearing, as may be appropriate.

(3) Any order disposing of a petition for reconsideration which reverses or modifies the original order is subject to the same provisions with respect to reconsideration as the original order. In no event, however, shall a ruling which denies a petition for reconsideration be considered a modification of the original order. A petition for reconsideration of an order which has been previously denied on reconsideration may be dismissed by the staff as repetitious.

NOTE: For purposes of this section, the word "order" refers to that portion of its action wherein the Commission announces its judgment. This should be distinguished from the "memorandum opinion" or other material which often accompany and explain the order.

(l) No evidence other than newly discovered evidence, evidence which has

become available only since the original taking of evidence, or evidence which the Commission or the designated authority believes should have been taken in the original proceeding shall be taken on any rehearing ordered pursuant to the provisions of this section.

(m) The filing of a petition for reconsideration is not a condition precedent to judicial review of any action taken by the Commission or by the designated authority, except where the person seeking such review was not a party to the proceeding resulting in the action, or relies on questions of fact or law upon which the Commission or designated authority has been afforded no opportunity to pass. (See § 1.115(c).) Persons in those categories who meet the requirements of this section may qualify to seek judicial review by filing a petition for reconsideration.

(n) Without special order of the Commission, the filing of a petition for reconsideration shall not excuse any person from complying with or obeying any decision, order, or requirement of the Commission, or operate in any manner to stay or postpone the enforcement thereof. However, upon good cause shown, the Commission will stay the effectiveness of its order or requirement pending a decision on the petition for reconsideration. (This paragraph applies only to actions of the Commission en banc. For provisions applicable to actions under delegated authority, see § 1.102.)

(Secs. 4, 303, 307, 405, 48 Stat., as amended, 1066, 1082, 1083, 1095; 47 U.S.C. 154, 303, 307, 405)

[28 FR 12415, Nov. 22, 1963, as amended at 37 FR 7507, Apr. 15, 1972; 41 FR 1287, Jan. 7, 1976; 44 FR 60294, Oct. 19, 1979; 46 FR 18556, Mar. 25, 1981; 62 FR 4170, Jan. 29, 1997]

§ 1.108 Reconsideration on Commission's own motion.

The Commission may, on its own motion, set aside any action made or taken by it within 30 days from the date of public notice of such action, as that date is defined in § 1.4(b) of these rules.

§ 1.110

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[28 FR 12415, Nov. 22, 1963, as amended at 46 FR 18556, Mar. 25, 1981]

§ 1.110 Partial grants; rejection and designation for hearing.

Where the Commission without a hearing grants any application in part, or with any privileges, terms, or conditions other than those requested, or subject to any interference that may result to a station if designated application or applications are subsequently granted, the action of the Commission shall be considered as a grant of such application unless the applicant shall, within 30 days from the date on which such grant is made or from its effective date if a later date is specified, file with the Commission a written request rejecting the grant as made. Upon receipt of such request, the Commission will vacate its original action upon the application and set the application for hearing in the same manner as other applications are set for hearing.

§ 1.113 Action modified or set aside by person, panel, or board.

(a) Within 30 days after public notice has been given of any action taken pursuant to delegated authority, the person, panel, or board taking the action may modify or set it aside on its own motion.

(b) Within 60 days after notice of any sanction imposed under delegated authority has been served on the person affected, the person, panel, or board which imposed the sanction may modify or set it aside on its own motion.

(c) Petitions for reconsideration and applications for review shall be directed to the actions as thus modified, and the time for filing such pleadings shall be computed from the date upon which public notice of the modified action is given or notice of the modified sanction is served on the person affected.

§ 1.115 Application for review of action taken pursuant to delegated authority.

(a) Any person aggrieved by any action taken pursuant to delegated authority may file an application requesting review of that action by the

47 CFR Ch. I (10–1–97 Edition)

Commission. Any person filing an application for review who has not previously participated in the proceeding shall include with his application a statement describing with particularity the manner in which he is aggrieved by the action taken and showing good reason why it was not possible for him to participate in the earlier stages of the proceeding. Any application for review which fails to make an adequate showing in this respect will be dismissed.

(b)(1) The application for review shall concisely and plainly state the questions presented for review with reference, where appropriate, to the findings of fact or conclusions of law.

(2) Except as provided in paragraph (b)(5) of this section, the application for review shall specify with particularity, from among the following, the factor(s) which warrant Commission consideration of the questions presented:

(i) The action taken pursuant to delegated authority is in conflict with statute, regulation, case precedent, or established Commission policy.

(ii) The action involves a question of law or policy which has not previously been resolved by the Commission.

(iii) The action involves application of a precedent or policy which should be overturned or revised.

(iv) An erroneous finding as to an important or material question of fact.

(v) Prejudicial procedural error.

(3) The application for review shall state with particularity the respects in which the action taken by the designated authority should be changed.

(4) The application for review shall state the form of relief sought and, subject to this requirement, may contain alternative requests.

(c) No application for review will be granted if it relies on questions of fact or law upon which the designated authority has been afforded no opportunity to pass.

NOTE: Subject to the requirements of § 1.106, new questions of fact or law may be presented to the designated authority in a petition for reconsideration.

(d) Except as provided in paragraph (e) of this section, the application for review and any supplemental thereto shall be filed within 30 days of public

Federal Communications Commission

§1.115

notice of such action, as that date is defined in section 1.4(b). Opposition to the application shall be filed within 15 days after the application for review is filed. Except as provided in paragraph (e)(3) of this section, replies to oppositions shall be filed within 10 days after the opposition is filed and shall be limited to matters raised in the opposition.

(e)(1) Applications for review of interlocutory rulings made by the Chief Administrative Law Judge (see §0.351) shall be deferred until the time when exceptions are filed unless the Chief Judge certifies the matter to the Commission for review. A matter shall be certified to the Commission only if the Chief Judge determines that it presents a new or novel question of law or policy and that the ruling is such that error would be likely to require remand should the appeal be deferred and raised as an exception. The request to certify the matter to the Commission shall be filed within 5 days after the ruling is made. The application for review shall be filed within 5 days after the order certifying the matter to the Commission is released or such ruling is made. Oppositions shall be filed within 5 days after the application is filed. Replies to oppositions shall be filed only if they are requested by the Commission. Replies (if allowed) shall be filed within 5 days after they are requested. A ruling certifying or not certifying a matter to the Commission is final: *Provided, however,* That the Commission may, on its own motion, dismiss the application for review on the ground that objections to the ruling should be deferred and raised as an exception.

(2) The failure to file an application for review of an interlocutory ruling made by the Chief Administrative Law Judge or the denial of such application by the Commission, shall not preclude any party entitled to file exceptions to the initial decision from requesting review of the ruling at the time when exceptions are filed. Such requests will be considered in the same manner as exceptions are considered.

(3) Applications for review of a hearing designation order issued under delegated authority shall be deferred until exceptions to the initial decision in the

case are filed, unless the presiding Administrative Law Judge certifies such an application for review to the Commission. A matter shall be certified to the Commission only if the presiding Administrative Law Judge determines that the matter involves a controlling question of law as to which there is substantial ground for difference of opinion and that immediate consideration of the question would materially expedite the ultimate resolution of the litigation. A ruling refusing to certify a matter to the Commission is not appealable. In addition, the Commission may dismiss, without stating reasons, an application for review that has been certified, and direct that the objections to the hearing designation order be deferred and raised when exceptions in the initial decision in the case are filed. A request to certify a matter to the Commission shall be filed with the presiding Administrative Law Judge within 5 days after the designation order is released. Any application for review authorized by the Administrative Law Judge shall be filed within 5 days after the order certifying the matter to the Commission is released or such a ruling is made. Oppositions shall be filed within 5 days after the application for review is filed. Replies to oppositions shall be filed only if they are requested by the Commission. Replies (if allowed) shall be filed within 5 days after they are requested.

(f) Applications for review, oppositions, and replies shall conform to the requirements of §§1.49, 1.51, and 1.52, and shall be submitted to the Secretary, Federal Communications Commission, Washington, DC 20554. Except as provided below, applications for review and oppositions thereto shall not exceed 25 double-space typewritten pages. Applications for review of interlocutory actions in hearing proceedings (including designation orders) and oppositions thereto shall not exceed 5 double-spaced typewritten pages. When permitted (see paragraph (e)(3) of this section), reply pleadings shall not exceed 5 double-spaced typewritten pages. The application for review shall be served upon the parties to the proceeding. Oppositions to the application for review shall be served on the person seeking review and on parties to the

§1.117

47 CFR Ch. I (10–1–97 Edition)

proceeding. When permitted (see paragraph (e)(3) of this section), replies to the opposition(s) to the application for review shall be served on the person(s) opposing the application for review and on parties to the proceeding.

(g) The Commission may grant the application for review in whole or in part, or it may deny the application with or without specifying reasons therefor. A petition requesting reconsideration of a ruling which denies an application for review will be entertained only if one or more of the following circumstances is present:

(1) The petition relies on facts which related to events which have occurred or circumstances which have changed since the last opportunity to present such matters; or

(2) The petition relies on facts unknown to petitioner until after his last opportunity to present such matters which could not, through the exercise of ordinary diligence, have been learned prior to such opportunity.

(h)(1) If the Commission grants the application for review in whole or in part, it may, in its decision:

(i) Simultaneously reverse or modify the order from which review is sought;

(ii) Remand the matter to the designated authority for reconsideration in accordance with its instructions, and, if an evidentiary hearing has been held, the remand may be to the person(s) who conducted the hearing; or

(iii) Order such other proceedings, including briefs and oral argument, as may be necessary or appropriate.

(2) In the event the Commission orders further proceedings, it may stay the effect of the order from which review is sought. (See §1.102.) Following the completion of such further proceedings the Commission may affirm, reverse or modify the order from which review is sought, or it may set aside the order and remand the matter to the designated authority for reconsideration in accordance with its instructions. If an evidentiary hearing has been held, the Commission may remand the matter to the person(s) who conducted the hearing for rehearing on such issues and in accordance with such instructions as may be appropriate.

NOTE: For purposes of this section, the word “order” refers to that portion of its action wherein the Commission announces its judgment. This should be distinguished from the “memorandum opinion” or other material which often accompany and explain the order.

(i) An order of the Commission which reverses or modifies the action taken pursuant to delegated authority is subject to the same provisions with respect to reconsideration as an original order of the Commission. In no event, however, shall a ruling which denies an application for review be considered a modification of the action taken pursuant to delegated authority.

(j) No evidence other than newly discovered evidence, evidence which has become available only since the original taking of evidence, or evidence which the Commission believes should have been taken in the original proceeding shall be taken on any rehearing ordered pursuant to the provisions of this section.

(k) The filing of an application for review shall be a condition precedent to judicial review of any action taken pursuant to delegated authority.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[28 FR 12415, Nov. 22, 1963, as amended at 41 FR 14871, Apr. 8, 1976; 44 FR 60295, Oct. 19, 1979; 46 FR 18556, Mar. 25, 1981; 48 FR 12719, Mar. 28, 1983; 50 FR 39000, Sept. 26, 1985; 54 FR 40392, Oct. 2, 1989; 55 FR 36641, Sept. 6, 1990; 57 FR 19387, May 6, 1992; 62 FR 4170, Jan. 29, 1997]

§1.117 Review on motion of the Commission.

(a) Within 40 days after public notice is given of any action taken pursuant to delegated authority, the Commission may on its own motion order the record of the proceeding before it for review.

(b) If the Commission reviews the proceeding on its own motion, it may order such further procedure as may be useful to it in its review of the action taken pursuant to delegated authority.

(c) With or without such further procedure, the Commission may either affirm, reverse, modify, or set aside the action taken, or remand the proceeding to the designated authority for reconsideration in accordance with its instructions. If an evidentiary hearing

Federal Communications Commission

§1.120

has been held, the Commission may remand the proceeding to the person(s) who conducted the hearing for rehearing on such issues and in accordance with such instructions as may be appropriate. An order of the Commission which reverses or modifies the action taken pursuant to delegated authority, or remands the matter for further proceedings, is subject to the same provisions with respect to reconsideration as an original action of the Commission.

§1.120 Protests of grants without hearing.

(a) The provisions of this section shall not be applicable to any application: (1) Filed on or after December 12, 1960; (2) filed before December 12, 1960, but substantially amended (as defined in the applicable provisions of this chapter) on or after that date; or (3) filed before December 12, 1960, and not thereafter substantially amended, but with respect to which the rules in this chapter provide an opportunity for petitions to deny to be filed under section 309 of the Communications Act, as amended. See §§1.580 and 1.962.

(b) Where any instrument of authorization for a radio station, other than a license pursuant to a construction permit, has been granted without a hearing, any party in interest may file a protest directed to such grant and request a hearing on the application granted. Such protest shall be signed by the protestant and subscribed to under oath. Such protest must be filed with the Commission within 30 days after release of the document containing the full text of such action, or in case such a document is not released, after release of a "Public Notice" announcing the action in question and must separately set forth:

(1) Such allegations of fact as will show the protestant to be a party in interest, i.e., a person aggrieved or whose interests are adversely affected by the Commission's authorization, protest of which is sought. Each such allegation of fact shall be separately stated.

(2) Facts indicating the reasons why the grant was improperly made or would otherwise not be in the public interest. Each such reason shall be separately stated, and facts in support

thereof shall be specified in detail and shall not include general non-specific conclusory arguments and allegations.

(3) The specific issues upon which protestant wishes a hearing to be held, which issues must relate directly to a matter specified with particularity as part of paragraph (b)(2) of this section.

(c) Arguments and citations of authority may be set forth in a brief accompanying the protest but must be excluded from the protest itself.

(d) Oppositions to protests and briefs in support thereof shall contain all material, including that pertinent to the determination referred to in paragraph (i) of this section, deemed appropriate to the Commission's resolution of the protest. Such oppositions and supporting briefs must be filed within 10 days after the filing of such protest, and any replies to such oppositions must be filed within 5 days after the filing of the oppositions.

(e) Protests, oppositions, and replies shall be filed with the Commission in original and 14 copies and shall be accompanied by proof of service upon the grantee or the protestant, as the case may be, and/or their respective attorneys.

(f) The Commission may upon consideration of a protest direct either the protestant or grantee or both to submit further statements of fact under oath relating to the matters raised in the protest.

(g) Within 30 days from the date of the filing of the protest, the Commission will enter findings as to whether such protest meets the requirements set forth in paragraphs (b) (1) and (2) of this section. If the Commission finds that one of these requirements is not met, it will dismiss the protest. If the Commission finds that these requirements are met, it will designate the application in question for hearing. As to issues which the Commission believes present no grounds for setting aside the grant, even if the facts alleged were to be proven, the Commission may designate such issues for oral argument only. The other issues will be designated for evidentiary hearing except that the Commission may redraft the issues in accordance with the facts or

§ 1.201

substantive matters alleged in the protest and may also specify such additional issues as it deems desirable. In any evidentiary hearing subsequently held upon issues specified by the Commission, upon its own initiative or adopted by it, both the burden of proceeding with the introduction of evidence and the burden of proof shall be upon the grantee. With respect to issues resulting from facts set forth in the protest and not adopted or specified by the Commission on its own motion, both the burden of proceeding with the introduction of evidence and the burden of proof shall be upon the protestant.

(h) The procedure in such protest hearing shall be governed by the provisions of subpart B of this part, except as otherwise provided in this section.

(i) Pending hearing and decision, the effective date of the Commission's action to which protest is made shall be postponed to the effective date of the Commission's decision after hearing, unless the authorization involved is necessary to the maintenance or conduct of an existing service or unless the Commission affirmatively finds that the public interest requires that the grant remain in effect, in which event the Commission shall authorize the applicant to utilize the facilities or authorization in question pending the Commission's decision after hearing.

(Sec. 7, 66 Stat. 715, as amended. See, in particular, sec. 4 (a) and (d), 74 Stat. 889, 892; 47 U.S.C. 309)

[28 FR 12415, Nov. 22, 1963, as amended at 28 FR 14503, Dec. 31, 1963]

Subpart B—Hearing Proceedings

SOURCE: 28 FR 12425, Nov. 22, 1963, unless otherwise noted.

EDITORIAL NOTE: Nomenclature changes to subpart B appear at 37 FR 19372, Sept. 20, 1972.

GENERAL

§ 1.201 Scope.

This subpart shall be applicable to the following cases which have been designated for hearing:

(a) Adjudication (as defined by the Administrative Procedure Act); and

47 CFR Ch. I (10–1–97 Edition)

(b) Rule making proceedings which are required by law to be made on the record after opportunity for a Commission hearing.

NOTE: For special provisions relating to AM broadcast station applications involving other North American countries see § 73.3570.

[28 FR 12425, Nov. 22, 1963, as amended at 51 FR 32088, Sept. 9, 1986]

§ 1.202 Official reporter; transcript.

The Commission will designate from time to time an official reporter for the recording and transcribing of hearing proceedings. The transcript of the testimony taken, or argument had, at any hearing will not be furnished by the Commission, but will be open to inspection under § 0.453(a)(1) of this chapter. Copies of such transcript, if desired, may be obtained from the official reporter upon payment of the charges therefor.

(5 U.S.C. 556)

[32 FR 20861, Dec. 28, 1967]

§ 1.203 The record.

The transcript of testimony and exhibits, together with all papers and requests filed in the proceeding, shall constitute the exclusive record for decision. Where any decision rests on official notice of a material fact not appearing in the record, any party shall on timely request be afforded an opportunity to show the contrary.

(5 U.S.C. 556)

§ 1.204 Pleadings; definition.

As used in this subpart, the term *pleading* means any written notice, motion, petition, request, opposition, reply, brief, proposed findings, exceptions, memorandum of law, or other paper filed with the Commission in a hearing proceeding. It does not include exhibits or documents offered in evidence. See § 1.356.

[29 FR 8219, June 30, 1964]

§ 1.205 Continuances and extensions.

Continuances of any proceeding or hearing and extensions of time for making any filing or performing any act required or allowed to be done within a specified time may be granted

Federal Communications Commission

§ 1.221

by the Commission or the presiding officer upon motion for good cause shown, unless the time for performance or filing is limited by statute.

§ 1.207 Interlocutory matters, reconsideration and review; cross references.

(a) Rules governing interlocutory pleadings in hearing proceedings are set forth in §§ 1.291 through 1.298.

(b) Rules governing appeal from rulings made by the presiding officer are set forth as §§ 1.301 and 1.302.

(c) Rules governing the reconsideration and review of actions taken pursuant to delegated authority, and the reconsideration of actions taken by the Commission, are set forth in §§ 1.101 through 1.120.

[28 FR 12425, Nov. 22, 1963, as amended at 29 FR 6443, May 16, 1964; 36 FR 19439, Oct. 6, 1971]

§ 1.209 Identification of responsible officer in caption to pleading.

Each pleading filed in a hearing proceeding shall indicate in its caption whether it is to be acted upon by the Commission, the Chief Administrative Law Judge, or the presiding officer. If it is to be acted upon by the presiding officer, he shall be identified by name.

[29 FR 8219, June 30, 1964, as amended at 37 FR 19372, Sept. 20, 1972; 62 FR 4171, Jan. 29, 1997]

§ 1.211 Service.

Except as otherwise expressly provided in this chapter, all pleadings filed in a hearing proceeding shall be served upon all other counsel in the proceeding or, if a party is not represented by counsel, then upon such party. All such papers shall be accompanied by proof of service. For provisions governing the manner of service, see § 1.47.

[29 FR 8219, June 30, 1964]

PARTICIPANTS AND ISSUES

§ 1.221 Notice of hearing; appearances.

(a) Upon designation of an application for hearing, the Commission issues an order containing the following:

(1) A statement as to the reasons for the Commission's action.

(2) A statement as to the matters of fact and law involved, and the issues upon which the application will be heard.

(3) A statement as to the time, place, and nature of the hearing. (If the time and place are not specified, the order will indicate that the time and place will be specified at a later date.)

(4) A statement as to the legal authority and jurisdiction under which the hearing is to be held.

(b) The order designating an application for hearing is mailed to the applicant by the Secretary of the Commission and this order or a summary thereof is published in the FEDERAL REGISTER. Reasonable notice of hearing will be given to the parties in all proceedings; and, whenever possible, the Commission will give at least 60 days notice of comparative hearings.

(c) In order to avail himself of the opportunity to be heard, the applicant, in person or by his attorney, shall, within 20 days of the mailing of the notice of designation for hearing by the Secretary, file with the Commission, in triplicate, a written appearance stating that he will appear on the date fixed for hearing and present evidence on the issues specified in the order. Where an applicant fails to file such a written appearance within the time specified, or has not filed prior to the expiration of that time a petition to dismiss without prejudice, or a petition to accept, for good cause shown, such written appearance beyond expiration of said 20 days, the application will be dismissed with prejudice for failure to prosecute.

(d) The Commission will on its own motion name as parties to the hearing any person found to be a party in interest.

(e) In order to avail himself of the opportunity to be heard, any person named as a party pursuant to paragraph (d) of this section shall, within 20 days of the mailing of the notice of his designation as a party, file with the Commission, in person or by attorney, a written appearance in triplicate, stating that he will appear at the hearing. Any person so named who fails to file this written statement within the time specified, shall, unless good cause for such failure is shown, forfeit his hearing rights.

§ 1.223

47 CFR Ch. I (10–1–97 Edition)

(f) A fee must accompany each written appearance filed with the Commission in certain cases designated for hearing. See subpart G, part 1 for the amount due. Except as provided in paragraph (g) of this section, the fee must accompany each written appearance at the time of its filing and must be in conformance with the requirements of subpart G of the rules. A written appearance that does not contain the proper fee, or is not accompanied by a deferral request as per § 1.1115 of the rules, shall be dismissed and returned to the applicant by the fee processing staff. The presiding judge will be notified of this action and may dismiss the applicant with prejudice for failure to prosecute if the written appearance is not resubmitted with the correct fee within the original 20 day filing period.

NOTE: If the parties file a settlement agreement prior to filing the Notice of Appearance or simultaneously with it, the hearing fee need not accompany the Notice of Appearance. In filing the Notice of Appearance, the applicant should clearly indicate that a settlement agreement has been filed. (The fact that there are ongoing negotiations that may lead to a settlement does not affect the requirement to pay the fee.) If a settlement agreement is not effectuated, the Presiding Judge will require immediate payment of the fee.

(g) In comparative broadcast proceedings involving applicants for new facilities, where the hearing fee was paid before designation of the applications for hearing as required by the Public Notice described at § 73.3571(c), § 73.3572(d), or § 73.3573(g) of this chapter, a hearing fee payment should not be made with the filing of the Notice of Appearance.

(5 U.S.C. 554, Sec. 309, 48 Stat. 1085, as amended; 47 U.S.C. 309)

[28 12424, Nov. 22, 1963, as amended at 51 FR 19347, May 29, 1986; 52 FR 5288, Feb. 20, 1987; 55 FR 19154, May 8, 1990; 56 FR 25638, June 5, 1991]

§ 1.223 Petitions to intervene.

(a) Where, in cases involving applications for construction permits and station licenses, or modifications or renewals thereof, the Commission has failed to notify and name as a party to the hearing any person who qualifies as a party in interest, such person may

acquire the status of a party by filing, under oath and not more than 30 days after the publication in the FEDERAL REGISTER of the hearing issues or any substantial amendment thereto, a petition for intervention showing the basis of its interest. Where such person's interest is based upon a claim that a grant of the application would cause objectionable interference under applicable provisions of this chapter to such person as a licensee or permittee of an existing or authorized station, the petition to intervene must be accompanied by an affidavit of a qualified radio engineer which shall show, either by following the procedures prescribed in this chapter for determining interference in the absence of measurements or by actual measurements made in accordance with the methods prescribed in this chapter, the extent of such interference. Where the person's status as a party in interest is established, the petition to intervene will be granted.

(b) Any other person desiring to participate as a party in any hearing may file a petition for leave to intervene not later than 30 days after the publication in the FEDERAL REGISTER of the full text or a summary of the order designating an application for hearing or any substantial amendment thereto. The petition must set forth the interest of petitioner in the proceedings, must show how such petitioner's participation will assist the Commission in the determination of the issues in question, must set forth any proposed issues in addition to those already designated for hearing, and must be accompanied by the affidavit of a person with knowledge as to the facts set forth in the petition. The presiding officer, in his discretion, may grant or deny such petition or may permit intervention by such persons limited to a particular stage of the proceeding.

(c) Any person desiring to file a petition for leave to intervene later than 30 days after the publication in the FEDERAL REGISTER of the full text or a summary of the order designating an application for hearing or any substantial amendment thereto shall set forth the interest of petitioner in the proceeding, show how such petitioner's

participation will assist the Commission in the determination of the issues in question, must set forth any proposed issues in addition to those already designated for hearing, and must set forth reasons why it was not possible to file a petition within the time prescribed by paragraphs (a) and (b) of this section. Such petition shall be accompanied by the affidavit of a person with knowledge of the facts set forth in the petition, and where petitioner claims that a grant of the application would cause objectionable interference under applicable provisions of this chapter, the petition to intervene must be accompanied by the affidavit of a qualified radio engineer showing the extent of such alleged interference according to the methods prescribed in paragraph (a) of this section. If, in the opinion of the presiding officer, good cause is shown for the delay in filing, he may in his discretion grant such petition or may permit intervention limited to particular issues or to a particular stage of the proceeding.

(Sec. 309, 48 Stat. 1085, as amended; 47 U.S.C. 309)

[28 FR 12425, Nov. 22, 1963, as amended at 29 FR 7821, June 19, 1964; 41 FR 14872, Apr. 8, 1976; 51 FR 19347, May 29, 1986]

§1.224 Motion to proceed in forma pauperis.

(a) A motion to proceed in forma pauperis may be filed by an individual, a corporation, and unincorporated entity, an association or other similar group, if the moving party is either of the following:

(1) A respondent in a revocation proceeding, or a renewal applicant, who cannot carry on his livelihood without the radio license at stake in the proceeding; or

(2) An intervenor in a hearing proceeding who is in a position to introduce testimony which is of probable decisional significance, on a matter of substantial public interest importance, which cannot, or apparently will not, be introduced by other parties to the proceeding, and who is not seeking personal financial gain.

(b) In the case of a licensee, the motion to proceed in forma pauperis shall contain specific allegations of fact sufficient to show that the moving party

is eligible under paragraph (a) of this section and that he cannot, because of his poverty, pay the expenses of litigation and still be able to provide himself and his dependents with the necessities of life. Such allegations of fact shall be supported by affidavit of a person or persons with personal knowledge thereof. The information submitted shall detail the income and assets of the individual and his financial obligations and responsibilities, and shall contain an estimate of the cost of participation in the proceeding. Personal financial information may be submitted to the presiding officer in confidence.

(c)(1) In the case of an individual intervenor, the motion to proceed in forma pauperis shall contain specific allegations of fact sufficient to show that he is eligible under paragraph (a) of this section and that he has dedicated financial resources to sustain his participation which are reasonable in light of his personal resources and other demands upon them but are inadequate for effective participation in the proceeding. Such allegations of fact shall be supported by affidavit of a person or persons with personal knowledge thereof. The information submitted shall detail the income and assets of the individual and his immediate family and his financial obligations and responsibilities, and shall contain an estimate of the cost of participation. Personal financial information may be submitted to the presiding officer in confidence.

(2) In the case of an intervening group, the motion to proceed in forma pauperis shall contain specific allegations of fact sufficient to show that the moving party is eligible under paragraph (a) of this section and that it cannot pay the expenses of litigation and still be able to carry out the activities and purposes for which it was organized. Such allegations of fact shall be supported by affidavit of the President and Treasurer of the group, and/or by other persons having personal knowledge thereof. The information submitted shall include a copy of the corporate charter or other documents that describe the activities and purposes of the organization; a current

balance sheet and profit and loss statement; facts showing, under all the circumstances, that it would not be reasonable to expect added resources of individuals composing the group to be pooled to meet the expenses of participating in the proceeding; and an estimate of the cost of participation. Personal financial information pertaining to members of the group may be submitted to the presiding officer in confidence.

(d) If the motion is granted, the presiding officer may direct that a free copy of the transcript of testimony be made available to the moving party and may relax the rules of procedure in any manner which will ease his financial burden, is fair to other parties to the proceeding, and does not involve the payment of appropriated funds to a party.

[41 FR 53021, Dec. 3, 1976]

§ 1.225 Participation by non-parties; consideration of communications.

(a) Any person who wishes to appear and give evidence on any matter and who so advises the Secretary, will be notified by the Secretary if that matter is designated for hearing. In the case of requests bearing more than one signature, notice of hearing will be given to the person first signing unless the request indicates that such notice should be sent to someone other than such person.

(b) No person shall be precluded from giving any relevant, material, and competent testimony at a hearing because he lacks a sufficient interest to justify his intervention as a party in the matter.

(c) When a hearing is held, no communication will be considered in determining the merits of any matter unless it has been received into evidence. The admissibility of any communication shall be governed by the applicable rules of evidence, and no communication shall be admissible on the basis of a stipulation unless Commission counsel as well as counsel for all of the parties shall join in such stipulation.

§ 1.227 Consolidations.

(a) The Commission, upon motion or upon its own motion, will, where such action will best conduce to the proper

dispatch of business and to the ends of justice, consolidate for hearing:

(1) Any cases which involve the same applicant or involve substantially the same issues, or

(2) Any applications which present conflicting claims, except where a random selection process is used.

(b)(1) In broadcast cases, except as provided in paragraph (b)(5) of this section, and except as otherwise provided in § 1.1601, *et seq.*, no application will be consolidated for hearing with a previously filed application or applications unless such application, or such application as amended, if amended so as to require a new file number, is substantially complete and tendered for filing by the close of business on the day preceding the day designated by Public Notice as the day any one of the previously filed applications is available and ready for processing.

(2) In other than broadcast, common carrier, and safety and special radio services cases, any application that is mutually exclusive with another application or applications already designated for hearing will be consolidated for hearing with such other application or applications only if the later application in question has been filed within 5 days after public notice has been given in the FEDERAL REGISTER of the Commission's order which first designated for hearing the prior application or applications with which such application is in conflict.

(3) Common carrier cases: (i) *General rule.* Where an application is mutually exclusive with a previously filed application, the second application will be entitled to comparative consideration with the first or entitled to be included in a random selection process, only if the second has been properly filed at least one day before the Commission takes action on the first application. Specifically, the later filed application must have been received by the Commission, in a condition acceptable for filing, before the close of business on the day prior to the grant date or designation date of the earlier filed application.

(ii) *Domestic public fixed and public mobile.* See Rule §§ 21.31 and 22.31 for the requirements as to mutually exclusive applications. See also Rule §§ 21.23 and

Federal Communications Commission

§ 1.229

22.23 for the requirements as to amendments of applications.

(iii) *Public coast stations (Maritime mobile service)*. See paragraph (b)(4) of this section.

(4) This paragraph applies when mutually-exclusive applications subject to section 309(b) of the Communications Act are filed in the Private Radio Services or when there are more such applications for initial licenses than can be accommodated on available frequencies. In such cases, the applications either will be consolidated for hearing or designated for random selection (see § 1.972 of this part). An application which is substantially amended (as defined by § 1.962(c) of this part) will, for the purpose of this section, be considered to be a newly-filed application as of the receipt date of the amendment. Except for applications filed under part 94, Private Operational Fixed Microwave Service, mutual exclusivity will occur if the later application or applications are received by the Commission's offices in Gettysburg, PA (or Pittsburgh, PA for applications requiring the fees set forth at part 1, subpart G of the rules) in a condition acceptable for filing within 30 days after the release date of public notice listing the first prior filed application (with which subsequent applications are in conflict) as having been accepted for filing or within such other period as specified by the Commission. For applications in the Private Operational Fixed Microwave Service, mutual exclusivity will occur if two or more acceptable applications that are in conflict are filed on the same day.

(5) Any mutually exclusive application filed after the date prescribed in paragraph (b)(1), (b)(2), (b)(3), or (b)(4) of this section will be dismissed without prejudice and will be eligible for re-filing only after a final decision is rendered by the Commission with respect to the prior application or applications or after such application or applications are dismissed or removed from the hearing docket.

(6) An application which is mutually exclusive with an application for renewal of license of a broadcast station filed on or before May 1, 1995 will be designated for comparative hearing with such license renewal application

if it is substantially complete and tendered for filing no later than the date prescribed in § 73.3516(e).

[28 FR 12425, Nov. 22, 1963, as amended at 34 FR 7966, May 21, 1969; 37 FR 13983, July 15, 1972; 38 FR 26202, Sept. 19, 1973; 48 FR 27200, June 13, 1983; 48 FR 34039, July 27, 1983; 52 FR 10229, Mar. 31, 1987; 55 FR 46008, Oct. 31, 1990; 55 FR 46513, Nov. 5, 1990; 61 FR 18291, Apr. 25, 1996]

§ 1.229 Motions to enlarge, change, or delete issues.

(a) A motion to enlarge, change or delete the issues may be filed by any party to a hearing. Except as provided for in paragraph (b) of this section, such motions must be filed within 15 days after the full text or a summary of the order designating the case for hearing has been published in the FEDERAL REGISTER.

(b)(1) In comparative broadcast proceedings involving applicants for only new facilities, such motions shall be filed within 30 days of the release of the designation order, except that persons not named as parties to the proceeding in the designation order may file such motions with their petitions to intervene up to 30 days after publication of the full text or a summary of the designation order in the FEDERAL REGISTER. (See § 1.223 of this part).

(2) In comparative broadcast proceedings involving renewal applicants, such motions shall be filed within 30 days after publication of the full text or a summary of the designation order in the FEDERAL REGISTER.

(3) Any person desiring to file a motion to modify the issues after the expiration of periods specified in paragraphs (a), (b)(1), and (b)(2), of this section, shall set forth the reason why it was not possible to file the motion within the prescribed period. Except as provided in paragraph (c) of this section, the motion will be granted only if good cause is shown for the delay in filing. Motions for modifications of issues which are based on new facts or newly discovered facts shall be filed within 15 days after such facts are discovered by the moving party.

(c) In the absence of good cause for late filing of a motion to modify the issues, the motion to enlarge will be considered fully on its merits if (and only

§ 1.241

if) initial examination of the motion demonstrates that it raises a question of probable decisional significance and such substantial public interest importance as to warrant consideration in spite of its untimely filing.

(d) Such motions, opposition thereto, and replies to oppositions shall contain specific allegations of fact sufficient to support the action requested. Such allegations of fact, except for those of which official notice may be taken, shall be supported by affidavits of a person or persons having personal knowledge thereof. The failure to file an opposition or a reply will not necessarily be construed as an admission of any fact or argument contained in a pleading.

(e) In comparative broadcast proceedings involving applicants for only new facilities, in addition to the showing with respect to the requested issue modification described in paragraph (d) of this section, the party requesting the enlargement of issues against an applicant in the proceeding shall identify those documents the moving party wishes to have produced and any other discovery procedures the moving party wishes to employ in the event the requested issue is added to the proceeding.

(1) In the event the motion to enlarge issues is granted, the Commission or delegated authority acting on the motion will also rule on the additional discovery requests, and, if granted, such additional discovery will be scheduled to be completed within 30 days of the action on the motion.

(2) The moving party may file supplemental discovery requests on the basis of information provided in responsive pleadings or discovered as a result of initial discovery on the enlarged issue. The grant or denial of any such supplemental requests and the timing of the completion of such supplemental discovery are subject to the discretion of the presiding judge.

(3) The 30-day time limit for completion of discovery on enlarged issues shall not apply where the persons subject to such additional discovery are not parties to the proceeding. In such case, additional time will be required to afford such persons adequate notice

47 CFR Ch. I (10–1–97 Edition)

of the discovery procedures being employed.

(f) In any case in which the presiding judge or the Commission grants a motion to enlarge the issues to inquire into allegations that an applicant made misrepresentations to the Commission or engaged in other misconduct during the application process, the enlarged issues include notice that, after hearings on the enlarged issue and upon a finding that the alleged misconduct occurred and warrants such penalty, in addition to or in lieu of denying the application, the applicant may be liable for a forfeiture of up to the maximum statutory amount. See 47 U.S.C. 503(b)(2)(A).

[41 FR 14872, Apr. 8, 1976, as amended at 44 FR 34947, June 18, 1979; 51 FR 19347, May 29, 1986; 56 FR 792, Jan. 9, 1991; 56 FR 25639, June 5, 1991; 62 FR 4171, Jan. 29, 1997]

PRESIDING OFFICER

§ 1.241 Designation of presiding officer.

(a) Hearings will be conducted by the Commission, by one or more commissioners, or by a law judge designated pursuant to section 11 of the Administrative Procedure Act. If a presiding officer becomes unavailable to the Commission prior to the taking of testimony another presiding officer will be designated.

(b) Unless the Commission determines that due and timely execution of its functions requires otherwise, presiding officers shall be designated, and notice thereof released to the public, at least 10 days prior to the date set for hearing.

(5 U.S.C. 556)

§ 1.243 Authority of presiding officer.

From the time he is designated to preside until issuance of his decision or the transfer of the proceeding to the Commission or to another presiding officer the presiding officer shall have such authority as is vested in him by law and by the provisions of this chapter, including authority to:

- (a) Administer oaths and affirmations;
- (b) Issue subpoenas;
- (c) Examine witnesses;
- (d) Rule upon questions of evidence;

Federal Communications Commission

§1.245

(e) Take or cause depositions to be taken;

(f) Regulate the course of the hearing, maintain decorum, and exclude from the hearing any person engaging in contemptuous conduct or otherwise disrupting the proceedings;

(g) Require the filing of memoranda of law and the presentation of oral argument with respect to any question of law upon which he is required to rule during the course of the hearing;

(h) Hold conferences for the settlement or simplification of the issues by consent of the parties;

(i) Dispose of procedural requests or similar matters, as provided for in §0.341 of this chapter;

(j) Take actions and make decisions in conformity with the Administrative Procedure Act;

(k) Act on motions to enlarge, modify or delete the hearing issues; and

(l) Act on motions to proceed in forma pauperis pursuant to §1.224.

(5 U.S.C. 556)

[28 FR 12425, Nov. 22, 1963, as amended at 41 FR 53022, Dec. 3, 1976]

§1.244 Designation of a settlement judge.

(a) In broadcast comparative cases involving applicants for only new facilities, the applicants may request the appointment of a settlement judge to facilitate the resolution of the case by settlement.

(b) Where all applicants in the case agree that such procedures may be beneficial, such requests may be filed with the presiding judge no later than 15 days prior to the date scheduled by the presiding judge for the commencement of hearings. The presiding judge shall suspend the procedural dates in the case and forward the request to the Chief Administrative Law Judge for action.

(c) If, in the discretion of the Chief Administrative Law Judge, it appears that the appointment of a settlement judge will facilitate the settlement of the case, the Chief Judge will appoint a “neutral” as defined in 5 U.S.C. 581 and 583(a) to act as the settlement judge.

(1) The parties may request the appointment of a settlement judge of their own choosing so long as that per-

son is a “neutral” as defined in 5 U.S.C. 581.

(2) The appointment of a settlement judge in a particular case is subject to the approval of all the applicants in the proceeding. See 5 U.S.C. 583(b).

(3) The Commission’s Administrative Law Judges are eligible to act as settlement judges, except that an Administrative Law Judge will not be appointed as a settlement judge in any case in which the Administrative Law Judge also acts as the presiding officer.

(4) Other members of the Commission’s staff who qualify as neutrals may be appointed as settlement judges, except that staff members whose duties include drafting, review, and/or recommendations in adjudicatory matters pending before the Commission shall not be appointed as settlement judges.

(d) The settlement judge shall have the authority to require applicants to submit their Standardized Integration Statements and/or their written direct cases for review. The settlement judge may also meet with the applicants and/or their counsel, individually and/or at joint conferences, to discuss their cases and the cases of their competitors. All such meetings will be off-the-record, and the settlement judge may express an opinion as to the relative comparative standing of the applicants and recommend possible means to resolve the proceeding by settlement. The proceedings before the settlement judge shall be subject to the confidentiality provisions of 5 U.S.C. 574. Moreover, no statements, offers of settlement, representations or concessions of the parties or opinions expressed by the settlement judge will be admissible as evidence in any Commission licensing proceeding.

[56 FR 793, Jan. 9, 1991, as amended at 62 FR 4171, Jan. 29, 1997]

§1.245 Disqualification of presiding officer.

(a) In the event that a presiding officer deems himself disqualified and desires to withdraw from the case, he shall notify the Commission of his withdrawal at least 7 days prior to the date set for hearing.

(b) Any party may request the presiding officer to withdraw on the grounds

§ 1.246

47 CFR Ch. I (10–1–97 Edition)

of personal bias or other disqualification.

(1) The person seeking disqualification shall file with the presiding officer an affidavit setting forth in detail the facts alleged to constitute grounds for disqualification. Such affidavit shall be filed not later than 5 days before the commencement of the hearing unless, for good cause shown, additional time is necessary.

(2) The presiding officer may file a response to the affidavit; and if he believes himself not disqualified, shall so rule and proceed with the hearing.

(3) The person seeking disqualification may appeal a ruling of disqualification, and, in that event, shall do so at the time the ruling is made. Unless an appeal of the ruling is filed at this time, the right to request withdrawal of the presiding officer shall be deemed waived.

(4) If an appeal of the ruling is filed, the presiding officer shall certify the question, together with the affidavit and any response filed in connection therewith, to the Commission. The hearing shall be suspended pending a ruling on the question by the Commission.

(5) The Commission may rule on the question without hearing, or it may require testimony or argument on the issues raised.

(6) The affidavit, response, testimony or argument thereon, and the Commission's decision shall be part of the record in the case.

(5 U.S.C. 556)

[28 FR 12425, Nov. 22, 1963, as amended at 55 FR 36641, Sept. 6, 1990; 62 FR 4171, Jan. 29, 1997]

PREHEARING PROCEDURES

§ 1.246 Admission of facts and genuineness of documents.

(a) Within 20 days after the time for filing a notice of appearance has expired; or within 20 days after the release of an order adding parties to the proceeding (see §§ 1.223 and 1.227) or changing the issues (see § 1.229); or within such shorter or longer time as the presiding officer may allow on motion or notice, a party may serve upon any other party a written request for the admission by the latter of the

genuineness of any relevant documents identified in and exhibited by a clear copy with the request or of the truth of any relevant matters of fact set forth in the request.

(b) Each of the matters of which an admission is requested shall be deemed admitted unless, within a period designated in the request, not less than 10 days after service thereof, or within such shorter or longer time as the presiding officer may allow on motion or notice, the party to whom the request is directed serves upon the party requesting the admission either: (1) A sworn statement denying specifically the matters of which an admission is requested or setting forth in detail the reasons why he cannot truthfully admit or deny those matters, or (2) written objections on the ground that some or all of the requested admissions are privileged or irrelevant or that the request is otherwise improper in whole or in part. If written objections to a part of the request are made, the remainder of the request shall be answered within the period designated in the request. A denial shall fairly meet the substance of the requested admission, and when good faith requires that a party deny only a part or a qualification of a matter of which an admission is requested, he shall specify so much of it as is true and deny only the remainder.

(c) A copy of the request and of any answer shall be served by the party filing on all other parties to the proceeding and upon the presiding officer.

(d) Written objections to the requested admissions may be ruled upon by the presiding officer without additional pleadings.

[33 FR 463, Jan. 12, 1968, as amended at 35 FR 17333, Nov. 11, 1970]

§ 1.248 Prehearing conferences; hearing conferences.

(a) The Commission, on its own initiative or at the request of any party, may direct the parties or their attorneys to appear at a specified time and place for a conference prior to a hearing, or to submit suggestions in writing, for the purpose of considering, among other things, the matters set forth in paragraph (c) of this section. The initial prehearing conference shall

Federal Communications Commission

§1.248

be scheduled 30 days after the effective date of the order designating a case for hearing, unless good cause is shown for scheduling such conference at a later date.

(b)(1) The presiding officer (or the Commission or a panel of commissioners in a case over which it presides), on his own initiative or at the request of any party, may direct the parties or their attorneys to appear at a specified time and place for a conference prior to or during the course of a hearing, or to submit suggestions in writing, for the purpose of considering any of the matters set forth in paragraph (c) of this section. The initial prehearing conference shall be scheduled 30 days after the effective date of the order designating a case for hearing, unless good cause is shown for scheduling such conference at a later date.

(2) Except as circumstances otherwise require, the presiding officer shall allow a reasonable period prior to commencement of the hearing for the orderly completion of all prehearing procedures, including discovery, and for the submission and disposition of all prehearing motions. Where the circumstances so warrant, the presiding officer shall, promptly after the hearing is ordered, call a preliminary prehearing conference, to inquire into the use of available procedures contemplated by the parties and the time required for their completion, to formulate a schedule for their completion, and to set a date for commencement of the hearing.

(c) In conferences held, or in suggestions submitted, pursuant to paragraphs (a) and (b) of this section, the following matters, among others, may be considered:

(1) The necessity or desirability of simplification, clarification, amplification, or limitation of the issues;

(2) The admission of facts and of the genuineness of documents (see §1.246), and the possibility of stipulating with respect to facts;

(3) The procedure at the hearing;

(4) The limitation of the number of witnesses;

(5) In cases arising under Title II of the Communications Act, the necessity or desirability of amending the plead-

ings and offers of settlement or proposals of adjustment; and

(6) In cases involving comparative broadcast applications:

(i) Narrowing the issues or the areas of inquiry and proof at the hearing;

(ii) [Reserved]

(iii) Reports and letters relating to surveys or contacts;

(iv) Assumptions regarding the availability of equipment;

(v) Network programming;

(vi) Assumptions regarding the availability of networks proposed;

(vii) Offers of letters in general;

(viii) The method of handling evidence relating to the past cooperation of existing stations owned and/or operated by the applicants with organizations in the area;

(ix) Proof of contracts, agreements, or understandings reduced to writing;

(x) Stipulations;

(xi) Need for depositions;

(xii) The numbering of exhibits;

(xiii) The order or offer of proof with relationship to docket number;

(xiv) The date for the formal hearing; and

(xv) Such other matters as may expedite the conduct of the hearing.

(7) In proceedings in which consent agreements may be negotiated (see §1.93), the parties shall be prepared to state at the initial prehearing conference whether they are at that time willing to enter negotiations leading to a consent agreement.

(d) This paragraph applies to broadcast proceedings only.

(1) At the prehearing conference prescribed by this section, the parties to the proceeding shall be prepared to discuss the advisability of reducing any or all phases of their affirmative direct cases to written form.

(2) In hearings involving applications for new, improved and changed facilities and in comparative hearings involving only applications for new facilities, where it appears that it will contribute significantly to the disposition of the proceeding for the parties to submit all or any portion of their affirmative direct cases in writing, the presiding officer may, in his discretion, require them to do so.

(3) In other broadcast proceedings, where it appears that it will contribute

§ 1.249

significantly to the disposition of the proceeding for the parties to submit all or any portion of their affirmative direct cases in writing, it is the policy of the Commission to encourage them to do so. However, the phase or phases of the proceeding to be submitted in writing, the dates for the exchange of the written material, and other limitations upon the effect of adopting the written case procedure (such as whether material ruled out as incompetent may be restored by other competent testimony) is to be left to agreement of the parties as approved by the presiding officer.

(4) In broadcast comparative cases involving applicants for only new facilities, oral testimony and cross examination will be permitted only where, in the discretion of the presiding judge, material issues of decisional fact cannot be resolved without oral evidentiary hearing procedures or the public interest otherwise requires oral evidentiary proceedings.

(e) An official transcript of all conferences shall be made.

(f) The presiding officer may, upon the written request of a party or parties, approve the use of a speakerphone as a means of attendance at a prehearing conference if such use is found to conduce to the proper dispatch of business and the ends of justice.

[28 FR 12425, Nov. 22, 1963, as amended at 33 FR 463, Jan. 12, 1968; 36 FR 14133, July 30, 1971; 37 FR 7507, Apr. 15, 1972; 41 FR 14873, Apr. 8, 1976; 43 FR 33251, July 31, 1978; 56 FR 793, Jan. 9, 1991]

§ 1.249 Prehearing statement.

Immediately upon convening the formal hearing in any proceeding, the presiding officer shall enter upon the record a statement reciting all actions taken at the prehearing conferences, and incorporating into the record all of the stipulations and agreements of the parties which are approved by him, and any special rules which he may deem necessary to govern the course of the proceeding.

[28 FR 12425, Nov. 22, 1963. Redesignated at 33 FR 463, Jan. 12, 1968]

47 CFR Ch. I (10–1–97 Edition)

HEARING AND INTERMEDIATE DECISION

§ 1.250 Discovery and preservation of evidence; cross-reference.

For provisions relating to prehearing discovery and preservation of admissible evidence, see §§ 1.311 through 1.325.

[33 FR 463, Jan. 12, 1968]

§ 1.251 Summary decision.

(a)(1) Any party to an adjudicatory proceeding may move for summary decision of all or any of the issues set for hearing. The motion shall be filed at least 20 days prior to the date set for commencement of the hearing. The party filing the motion may not rest upon mere allegations or denials but must show, by affidavit or by other materials subject to consideration by the presiding officer, that there is no genuine issue of material fact for determination at the hearing.

(2) With the permission of the presiding officer, or upon his invitation, a motion for summary decision may be filed at any time before or after the commencement of the hearing. No appeal from an order granting or denying a request for permission to file a motion for summary decision shall be allowed. If the presiding officer authorizes a motion for summary decision after the commencement of the hearing, proposed findings of fact and conclusions of law on those issues which the moving party believes can be resolved shall be attached to the motion, and any other party may file findings of fact and conclusions of law as an attachment to pleadings filed by him pursuant to paragraph (b) of this section.

(b) Within 14 days after a motion for summary decision is filed, any other party to the proceeding may file an opposition or a countermotion for summary decision. A party opposing the motion may not rest upon mere allegations or denials but must show, by affidavit or by other materials subject to consideration by the presiding officer, that there is a genuine issue of material fact for determination at the hearing, that he cannot, for good cause, present by affidavit or otherwise facts essential to justify his opposition, or that summary decision is otherwise inappropriate.

Federal Communications Commission

§1.254

(c) Affidavits shall be made on personal knowledge, shall set forth such facts as would be admissible in evidence, and shall show affirmatively that the affiant is competent to testify to the matters stated therein.

(d) The presiding officer may, in his discretion, set the matter for argument and call for the submission of proposed findings, conclusions, briefs or memoranda of law. The presiding officer, giving appropriate weight to the nature of the proceeding, the issue or issues, the proof, and to the need for cross-examination, may grant a motion for summary decision to the extent that the pleadings, affidavits, materials obtained by discovery or otherwise, admissions, or matters officially noticed, show that there is no genuine issue as to any material fact and that a party is otherwise entitled to summary decision. If it appears from the affidavits of a party opposing the motion that he cannot, for good cause shown, present by affidavit or otherwise facts essential to justify his opposition, the presiding officer may deny the motion, may order a continuance to permit affidavits to be obtained or discovery to be had, or make such other order as is just.

(e) If all of the issues (or a dispositive issue) are determined on a motion for summary decision no hearing (or further hearing) will be held. The presiding officer will issue a Summary Decision, which is subject to appeal or review in the same manner as an Initial Decision. See §§1.271 through 1.282. If some of the issues only (including no dispositive issue) are decided on a motion for summary decision, or if the motion is denied, the presiding officer will issue a memorandum opinion and order, interlocutory in character, and the hearing will proceed on the remaining issues. Appeal from interlocutory rulings is governed by §1.301.

(f) The presiding officer may take any action deemed necessary to assure that summary decision procedures are not abused. He may rule in advance of a motion that the proceeding is not appropriate for summary decision, and may take such other measures as are necessary to prevent any unwarranted delay.

(1) Should it appear to the satisfaction of the presiding officer that a motion for summary decision has been presented in bad faith or solely for the purpose of delay, or that such a motion is patently frivolous, he will enter a determination to that effect upon the record.

(2) If, on making such determination, the presiding officer concludes that the facts warrant disciplinary action against an attorney, he will certify the matter to the Commission with his findings and recommendations, for consideration under §1.24.

(3) If, on making such determination, the presiding officer concludes that the facts warrant a finding of bad faith on the part of a party to the proceeding, he will certify the matter to the Commission, with his findings and recommendations, for a determination as to whether the facts warrant addition of an issue as to the character qualifications of that party.

[37 FR 7507, Apr. 15, 1972, as amended at 42 FR 56508, Oct. 26, 1977]

§1.253 Time and place of hearing.

(a) The Commission will specify the day on which and the place at which any hearing is to commence.

(b) The presiding officer will specify the days on which subsequent hearing sessions are to be held.

(c) If the Commission specifies that a hearing is to commence in the District of Columbia, it shall be moved therefrom only by order of the Commission.

(d) If the Commission specifies that a hearing is to commence at a field location, all appropriate proceedings will be completed at such location before the hearing is moved therefrom. When such proceedings are completed, the presiding officer may move the hearing from the field location specified to another appropriate field location or to the District of Columbia.

§1.254 Nature of the hearing; burden of proof.

Any hearing upon an application shall be a full hearing in which the applicant and all other parties in interest shall be permitted to participate but in which both the burden of proceeding with the introduction of evidence upon any issue specified by the Commission,

§ 1.255

as well as the burden of proof upon all such issues, shall be upon the applicant except as otherwise provided in the order of designation.

(Sec. 309, 48 Stat. 1085, as amended; 47 U.S.C. 309)

§ 1.255 Order of procedure.

(a) At hearings on a formal complaint or petition or in a proceeding for any instrument of authorization which the Commission is empowered to issue, the complainant, petitioner, or applicant, as the case may be, shall, unless the Commission otherwise orders, open and close. At hearings on protests, the protestant opens and closes the proceedings in case the issues are not specifically adopted by the Commission; otherwise the grantee does so. At hearings on orders to show cause, to cease and desist, to revoke or modify a station license under sections 312 and 316 of the Communications Act, or other like proceedings instituted by the Commission, the Commission shall open and close.

(b) At all hearings under Title II of the Communications Act, other than hearings on formal complaints, petitions, or applications, the respondent shall open and close unless otherwise specified by the Commission.

(c) In all other cases, the Commission or presiding officer shall designate the order of presentation. Intervenors shall follow the party in whose behalf intervention is made, and in all cases where the intervention is not in support of an original party, the Commission or presiding officer shall designate at what stage such intervenors shall be heard.

[28 FR 12425, Nov. 22, 1963, as amended at 33 FR 463, Jan. 12, 1968]

§ 1.258 Closing of the hearing.

The record of hearing shall be closed by an announcement to that effect at the hearing by the presiding officer when the taking of testimony has been concluded. In the discretion of the presiding officer, the record may be closed as of a future specified date in order to permit the admission into the record of exhibits to be prepared: *Provided*, The parties to the proceeding stipulate on the record that they waive the opportunity to cross-examine or present evi-

47 CFR Ch. I (10–1–97 Edition)

dence with respect to such exhibits. The record in any hearing which has been adjourned may not be closed by such officer prior to the day on which the hearing is to resume, except upon 10 days' notice to all parties to the proceeding.

§ 1.260 Certification of transcript.

After the close of the hearing, the complete transcript of testimony, together with all exhibits, shall be certified as to identity by the presiding officer and filed in the office of the Secretary of the Commission. Notice of such certification shall be served on all parties to the proceedings.

§ 1.261 Corrections to transcript.

At any time during the course of the proceeding, or as directed by the presiding officer, but not later than 10 days after the date of notice of certification of the transcript, any party to the proceeding may file with the presiding officer a motion requesting the correction of the transcript, which motion shall be accompanied by proof of service thereof upon all other parties to the proceeding. Within 5 days after the filing of such a motion, other parties may file a pleading in support of or in opposition to such motion. Thereafter, the presiding officer shall, by order, specify the corrections to be made in the transcript, and a copy of the order shall be served upon all parties and made a part of the record. The presiding officer, on his own initiative, may specify corrections to be made in the transcript on 5 days' notice.

[40 FR 51441, Nov. 5, 1975]

§ 1.263 Proposed findings and conclusions.

(a) Each party to the proceeding may file proposed findings of fact and conclusions, briefs, or memoranda of law: *Provided, however*, That the presiding officer may direct any party other than Commission counsel to file proposed findings of fact and conclusions, briefs, or memoranda of law. Such proposed findings of fact, conclusions, briefs, and memoranda of law shall be filed within 20 days after the record is closed, unless additional time is allowed.

(b) All pleadings and other papers filed pursuant to this section shall be

Federal Communications Commission

§1.273

accompanied by proof of service thereof upon all other counsel in the proceeding; if a party is not represented by counsel, proof of service upon such party shall be made.

(c) In the absence of a showing of good cause therefor, the failure to file proposed findings of fact, conclusions, briefs, or memoranda of law, when directed to do so, may be deemed a waiver of the right to participate further in the proceeding.

(5 U.S.C. 557)

§1.264 Contents of findings of fact and conclusions.

Proposed findings of fact shall be set forth in serially numbered paragraphs and shall set out in detail and with particularity all basic evidentiary facts developed on the record (with appropriate citations to the transcript of record or exhibit relied on for each evidentiary fact) supporting the conclusions proposed by the party filing same. Proposed conclusions shall be separately stated. Proposed findings of fact and conclusions submitted by a person other than an applicant may be limited to those issues in connection with the hearing which affect the interests of such person.

(5 U.S.C. 557)

§1.267 Initial and recommended decisions.

(a) Except as provided in this paragraph, in §§1.94, 1.251 and 1.274, or where the proceeding is terminated on motion (see §1.302), the presiding officer shall prepare an initial (or recommended) decision, which shall be transmitted to the Secretary of the Commission. In the case of rate making proceedings conducted under sections 201-205 of the Communications Act, the presumption shall be that the presiding officer shall prepare an initial or recommended decision. The Secretary will make the decision public immediately and file it in the docket of the case.

(b) Each initial and recommended decision shall contain findings of fact and conclusions, as well as the reasons or basis therefor, upon all the material issues of fact, law, or discretion presented on the record; each initial deci-

sion shall also contain the appropriate rule or order, and the sanction, relief or denial thereof; and each recommended decision shall contain recommendations as to what disposition of the case should be made by the Commission. Each initial decision will show the date upon which it will become effective in accordance with the rules in this part in the absence of exceptions, appeal, or review.

(c) The authority of the Presiding Officer over the proceedings shall cease when he has filed his Initial or Recommended Decision, or if it is a case in which he is to file no decision, when he has certified the case for decision: *Provided*, however, That he shall retain limited jurisdiction over the proceeding for the purpose of effecting certification of the transcript and corrections to the transcript, as provided in §§1.260 and 1.261, respectively, and for the purpose of ruling initially on applications for awards of fees and expenses under the Equal Access to Justice Act.

(Sec. 409, 48 Stat. 1096, as amended; 47 U.S.C. 409, 5 U.S.C. 557; secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083: 47 U.S.C. 154, 303, 307)

[28 FR 12425, Nov. 22, 1963, as amended at 41 FR 14873, Apr. 8, 1976; 47 FR 3786, Jan. 27, 1982]

REVIEW PROCEEDINGS

§1.271 Delegation of review function.

The Commission may direct, by order or rule, that its review function in a case or category of cases be performed by a commissioner, or a panel of commissioners, in which event the commissioner or panel shall exercise the authority and perform the functions which would otherwise have been performed by the Commission under §§1.273 through 1.282.

NOTE: To provide for an orderly completion of cases, exceptions and related pleadings filed after March 1, 1996, shall be directed to the Commission and will not be acted upon by the Review Board.

[62 FR 4171, Jan. 29, 1997]

§1.273 Waiver of initial or recommended decision.

At the conclusion of the hearing or within 20 days thereafter, all parties to

§ 1.274

47 CFR Ch. I (10–1–97 Edition)

the proceeding may agree to waive an initial or recommended decision, and may request that the Commission issue a final decision or order in the case. If the Commission has directed that its review function in the case be performed by a commissioner, a panel of commissioners, the request shall be directed to the appropriate review authority. The Commission or such review authority may in its discretion grant the request, in whole or in part, if such action will best conduce to the proper dispatch of business and to the ends of justice.

[28 FR 12425, Nov. 22, 1963, as amended at 62 FR 4171, Jan. 29, 1997]

§ 1.274 Certification of the record to the Commission for initial or final decision.

(a) Where the presiding officer is available to the Commission, and where the Commission finds upon the record that due and timely execution of its functions imperatively and unavoidably so requires, the Commission may direct that the record in a pending proceeding be certified to it for initial or final decision. Unless the Commission finds that due and timely execution of its functions imperatively and unavoidably requires that no recommended decision be issued, the presiding officer will prepare and file a recommended decision, which will be released with the Commission's initial or final decision.

(b) Where the presiding officer becomes unavailable to the Commission after the taking of testimony has been concluded, the Commission may direct that the record in a pending proceeding be certified to it for initial or final decision. In that event, the record shall be certified to the Commission by the Chief Administrative Law Judge.

(c)(1) Where the presiding officer becomes unavailable to the Commission after the taking of evidence has commenced but before it has been concluded, the Commission may order a rehearing before another presiding officer designated in accordance with § 1.241.

(2) Upon a finding that due and timely execution of its functions imperatively and unavoidably so requires, the Commission may (as an alternative)

order that the hearing be continued by another presiding officer designated in accordance with § 1.241 or by the Commission itself. In that event, the officer continuing the hearing shall, upon completion of the hearing, certify the proceeding to the Commission for an initial or final decision. Unless the Commission finds upon the record that due and timely execution of its functions imperatively and unavoidably requires that no recommended decision be issued, the officer continuing the hearing shall prepare and file a recommended decision to be released with the Commission's initial or final decision. If all the parties expressly consent, and if the Commission does not order otherwise, the officer continuing the hearing may prepare an initial decision.

(Sec. 409, 48 Stat. 1096, as amended; 47 U.S.C. 409)

§ 1.276 Appeal and review of initial decision.

(a)(1) Within 30 days after the date on which public release of the full text of an initial decision is made, or such other time as the Commission may specify, any of the parties may appeal to the Commission by filing exceptions to the initial decision, and such decision shall not become effective and shall then be reviewed by the Commission, whether or not such exceptions may thereafter be withdrawn. It is the Commission's policy that extensions of time for filing exceptions shall not be routinely granted.

(2) Exceptions shall be consolidated with the argument in a supporting brief and shall not be submitted separately. As used in this subpart, the term *exceptions* means the document consolidating the exceptions and supporting brief. The brief shall contain (i) a table of contents, (ii) a table of citations, (iii) a concise statement of the case, (iv) a statement of the questions of law presented, and (v) the argument, presenting clearly the points of fact and law relied upon in support of the position taken on each question, with specific reference to the record and all legal or other materials relied on.

(b) The Commission may on its own initiative provide, by order adopted not

Federal Communications Commission

§1.277

later than 20 days after the time for filing exceptions expires, that an initial decision shall not become final, and that it shall be further reviewed or considered by the Commission.

(c) In any case in which an initial decision is subject to review in accordance with paragraph (a) or (b) of this section, the Commission may, on its own initiative or upon appropriate requests by a party, take any one or more of the following actions:

(1) Hear oral argument on the exceptions;

(2) Require the filing of briefs;

(3) Prior to or after oral argument or the filing of exceptions or briefs, reopen the record and/or remand the proceedings to the presiding officer to take further testimony or evidence;

(4) Prior to or after oral argument or the filing of exceptions or briefs, remand the proceedings to the presiding officer to make further findings or conclusions; and

(5) Prior to or after oral argument or the filing of exceptions or briefs, issue, or cause to be issued by the presiding officer, a supplemental initial decision.

(d) No initial decision shall become effective before 50 days after public release of the full text thereof is made unless otherwise ordered by the Commission. The timely filing of exceptions, the further review or consideration of an initial decision on the Commission's initiative, or the taking of action by the Commission under paragraph (c) of this section shall stay the effectiveness of the initial decision until the Commission's review thereof has been completed. If the effective date of an initial decision falls within any further time allowed for the filing of exceptions, it shall be postponed automatically until 30 days after time for filing exceptions has expired.

(e) If no exceptions are filed, and the Commission has not ordered the review of an initial decision on its initiative, or has not taken action under paragraph (c) of this section, the initial decision shall become effective, an appropriate notation to that effect shall be entered in the docket of the case, and a "Public Notice" thereof shall be given by the Commission. The provisions of §1.108 shall not apply to such public notices.

(f) When any party fails to file exceptions within the specified time to an initial decision which proposes to deny its application, such party shall be deemed to have no interest in further prosecution of its application, and its application may be dismissed with prejudice for failure to prosecute.

(Sec. 40, 48 Stat. 1096, as amended; 47 U.S.C. 409)

[28 FR 12425, Nov. 22, 1963, as amended at 41 FR 14873, Apr. 8, 1976]

§1.277 Exceptions; oral arguments.

(a) The consolidated supporting brief and exceptions to the initial decision (see §1.276(a)(2)), including rulings upon motions or objections, shall point out with particularity alleged material errors in the decision or ruling and shall contain specific references to the page or pages of the transcript of hearing, exhibit or order if any on which the exception is based. Any objection not saved by exception filed pursuant to this section is waived.

(b) Within the period of time allowed in §1.276(a) for the filing of exceptions, any party may file a brief in support of an initial decision, in whole or in part, which may contain exceptions and which shall be similar in form to the brief in support of exceptions (see §1.276(a)(2)).

(c) Except by special permission, the consolidated brief and exceptions will not be accepted if the exceptions and argument exceed 25 double-spaced typewritten pages in length. (The table of contents and table of citations are not counted in the 25 page limit; however, all other contents of and attachments to the brief are counted.) Within 10 days, or such other time as the Commission or delegated authority may specify, after the time for filing exceptions has expired, any other party may file a reply brief, which shall not exceed 25 double spaced typewritten pages and shall contain a table of contents and a table of citations. If exceptions have been filed, any party may request oral argument not later than five days after the time for filing replies to the exceptions has expired. The Commission or delegated authority, in its discretion, will grant oral argument by order only in cases where such oral

§ 1.279

presentations will assist in the resolution of the issues presented. Within five days after release of an order designating an initial decision for oral argument, as provided in paragraph (d) of this section, any party who wishes to participate in oral argument shall file a written notice of intention to appear and participate in oral argument. Failure to file a written notice shall constitute a waiver of the opportunity to participate.

(d) Each order scheduling a case for oral argument will contain the allotment of time for each party for oral argument before the Commission. The Commission will grant, in its discretion, upon good cause shown, an extension of such time upon petition by a party, which petition must be filed within 5 days after issuance of said order for oral argument.

(e) Within 10 days after a transcript of oral argument has been filed in the office of the Secretary of the Commission, any party who participated in the oral argument may file with the Commission a motion requesting correction of the transcript, which motion shall be accompanied by proof of service thereof upon all other parties who participated in the oral argument. Within 5 days after the filing of such a motion, other parties may file a pleading in support of or in opposition to such motion. Thereafter, the officer who presided at the oral argument shall, by order, specify the corrections to be made in the transcript, and a copy of the order shall be served upon all parties to the proceeding. The officer who presided at the oral argument may, on his own initiative, by order, specify corrections to be made in the transcript on 5 days notice of the proposed corrections to all parties who participated in the oral argument.

(f) Any commissioner who is not present at oral argument and who is otherwise authorized to participate in a final decision may participate in making that decision after reading the transcript of oral argument.

(Sec. 409, 48 Stat. 1096, as amended; 47 U.S.C. 409)

[28 FR 12425, Nov. 22, 1963, as amended at 41 FR 14873, Apr. 8, 1976; 41 FR 34259, Aug. 13, 1976; 44 FR 12426, Mar. 7, 1979; 56 FR 793, Jan. 9, 1991; 62 FR 4171, Jan. 29, 1997]

47 CFR Ch. I (10–1–97 Edition)

§ 1.279 Limitation of matters to be reviewed.

Upon review of any initial decision, the Commission may, in its discretion, limit the issues to be reviewed to those findings and conclusions to which exceptions have been filed, or to those findings and conclusions specified in the Commission's order of review issued pursuant to § 1.276(b).

§ 1.282 Final decision of the Commission.

(a) After opportunity has been afforded for the filing of proposed findings of fact and conclusions, exceptions, supporting statements, briefs, and for the holding of oral argument as provided in this subpart, the Commission will issue a final decision in each case in which an initial decision has not become final.

(b) The final decision shall contain:

(1) Findings of fact and conclusions, as well as the reasons or basis therefor, upon all the material issues of fact, law or discretion presented on the record;

(2) Rulings on each relevant and material exception filed; the Commission will deny irrelevant exceptions, or those which are not of decisional significance, without a specific statement of reasons prescribed by paragraph (b)(1) of this section; and

(3) The appropriate rule or order and the sanction, relief or denial thereof.

(Sec. 8(b), 60 Stat. 2422; 5 U.S.C. 1007(b))

[28 FR 12425, Nov. 22, 1963, as amended at 41 FR 14873, Apr. 8, 1976]

INTERLOCUTORY ACTIONS IN HEARING PROCEEDINGS

§ 1.291 General provisions.

(a)(1) The Commission acts on petitions to amend, modify, enlarge or delete the issues in hearing proceedings which involve rule making matters exclusively. It also acts on interlocutory pleadings filed in matters or proceedings which are before the Commission.

(2) The Chief Administrative Law Judge acts on those interlocutory matters listed in § 0.351 of this chapter.

(3) All other interlocutory matters in hearing proceedings are acted on by the presiding officer. See §§ 0.218 and 0.341 of this chapter.

Federal Communications Commission

§1.298

(4) Each interlocutory pleading shall indicate in its caption whether the pleading is to be acted upon by the Commission, the Chief Administrative Law Judge, or the presiding officer. If the pleading is to be acted upon by the presiding officer, he shall be identified by name.

(b) All interlocutory pleadings shall be submitted in accordance with the provisions of §§1.4, 1.44, 1.47, 1.48, 1.49, and 1.52.

(c)(1) Procedural rules governing interlocutory pleadings are set forth in §§1.294–1.298.

(2) Rules governing appeal from, and reconsideration of, interlocutory rulings made by the presiding officer are set forth in §§1.301 and 1.303.

(3) Rules governing the review of interlocutory rulings made by the Chief Administrative Law Judge are set forth in §§1.101, 1.102(b), 1.115, and 1.117. Petitions requesting reconsideration of an interlocutory ruling made by the Commission, or the Chief Administrative Law Judge will not be entertained. See, however, §1.113.

(d) No initial decision shall become effective under §1.276(e) until all interlocutory matters pending before the Commission in the proceeding at the time the initial decision is issued have been disposed of and the time allowed for appeal from interlocutory rulings of the presiding officer has expired.

(Secs. 4(i), 303(r) and 5(c)(1) of the Communications Act of 1934, as amended; 47 CFR 0.61 and 0.283)

[29 FR 6443, May 16, 1964, as amended at 29 FR 12773, Sept. 10, 1964; 37 FR 19372, Sept. 20, 1972; 41 FR 14873, Apr. 8, 1976; 49 FR 4381, Feb. 6, 1984; 62 FR 4171, Jan. 29, 1997]

§1.294 Oppositions and replies.

(a) Any party to a hearing may file an opposition to an interlocutory request filed in that proceeding.

(b) Except as provided in paragraph (c) of this section, oppositions shall be filed within 4 days after the original pleading is filed, and replies to oppositions will not be entertained. See, however, §1.732.

(c) Oppositions to pleadings in the following categories shall be filed within 10 days after the pleading is filed. Replies to such oppositions shall be filed within 5 days after the opposition

is filed, and shall be limited to matters raised in the opposition.

(1) Petitions to amend, modify, enlarge, or delete the issues upon which the hearing was ordered.

(2) [Reserved]

(3) Petitions by adverse parties requesting dismissal of an application.

(4) Joint requests for approval of agreements filed pursuant to §1.525.

(d) Additional pleadings may be filed only if specifically requested or authorized by the person(s) who is to make the ruling.

[29 FR 6444, May 16, 1964, as amended at 39 FR 10909, Mar. 22, 1974]

§1.296 Service.

No pleading filed pursuant to §1.51 or §1.294 will be considered unless it is accompanied by proof of service upon the parties to the proceeding.

(Secs. 4(i), 303(r) and 5(c)(1) of the Communications Act of 1934, as amended; 47 CFR 0.61 and 0.283)

[49 FR 4381, Feb. 6, 1984, as amended at 62 FR 4171, Jan. 29, 1997]

§1.297 Oral argument.

Oral argument with respect to any contested interlocutory matter will be held when, in the opinion of the person(s) who is to make the ruling, the ends of justice will be best served thereby. Timely notice will be given of the date, time, and place of any such oral argument.

[29 FR 6444, May 16, 1964]

§1.298 Rulings; time for action.

(a) Unless it is found that irreparable injury would thereby be caused one of the parties, or that the public interest requires otherwise, or unless all parties have consented to the contrary, consideration of interlocutory requests will be withheld until the time for filing oppositions (and replies, if replies are allowed) has expired. As a matter of discretion, however, requests for continuances and extensions of time, requests for permission to file pleadings in excess of the length prescribed in this chapter, and requests for temporary relief may be ruled upon *ex parte* without waiting for the filing of responsive pleadings.

§ 1.301

47 CFR Ch. I (10–1–97 Edition)

(b) In the discretion of the presiding officer, rulings on interlocutory matters may be made orally at the hearing. The presiding officer may, in his discretion, state his reasons on the record or subsequently issue a written statement of the reasons for his ruling, either separately or as part of the initial decision.

[28 FR 12425, Nov. 22, 1963, as amended at 29 FR 6444, May 16, 1964; 41 FR 14874, Apr. 8, 1976]

APPEAL AND RECONSIDERATION OF PRESIDING OFFICER'S RULING

§ 1.301 Appeal from presiding officer's interlocutory ruling; effective date of ruling.

(a) *Interlocutory rulings which are appealable as a matter of right.* Rulings listed in this paragraph are appealable as a matter of right. An appeal from such a ruling may not be deferred and raised as an exception to the initial decision.

(1) If the presiding officer's ruling denies or terminates the right of any person to participate as a party to a hearing proceeding, such person, as a matter of right, may file an appeal from that ruling.

(2) If the presiding officer's ruling requires testimony or the production of documents, over objection based on a claim of privilege, the ruling on the claim of privilege is appealable as a matter of right.

(3) If the presiding officer's ruling denies a motion to disqualify the presiding judge, the ruling is appealable as a matter of right.

(4) Rulings granting a joint request filed under § 1.525 without terminating the proceeding are appealable by any party as a matter of right.

(5) A ruling removing counsel from the hearing is appealable as a matter of right, by counsel on his own behalf or by his client. (In the event of such ruling, the presiding officer will adjourn the hearing for such period as is reasonably necessary for the client to secure new counsel and for counsel to familiarize himself with the case).

(b) *Other interlocutory rulings.* Except as provided in paragraph (a) of this section, appeals from interlocutory rulings of the presiding officer shall be

filed only if allowed by the presiding officer. Any party desiring to file an appeal shall first file a request for permission to file appeal. The request shall be filed within 5 days after the order is released or (if no written order) after the ruling is made. Pleadings responsive to the request shall be filed only if they are requested by the presiding officer. The request shall contain a showing that the appeal presents a new or novel question of law or policy and that the ruling is such that error would be likely to require remand should the appeal be deferred and raised as an exception. The presiding officer shall determine whether the showing is such as to justify an interlocutory appeal and, in accordance with his determination, will either allow or disallow the appeal or modify the ruling. If the presiding officer allows or disallows the appeal, his ruling is final: *Provided, however,* That the Commission may, on its own motion, dismiss an appeal allowed by the presiding officer on the ground that objection to the ruling should be deferred and raised as an exception. In the discretion of the presiding officer, the request for permission to file appeal may be made orally, on the record of the proceeding. The request may be disposed of orally.

(1) If an appeal is not allowed, or is dismissed by the Commission, or if permission to file an appeal is not requested, objection to the ruling may be raised on review of the initial decision.

(2) If an appeal is allowed and is considered on its merits, the disposition on appeal is final. Objection to the ruling or to the action on appeal may not be raised on review of the initial decision.

(3) If the presiding officer modifies the ruling, any party adversely affected by the modified ruling may file a request for permission to file appeal, pursuant to the provisions of this paragraph.

(c) *Procedures, effective date.* (1) Unless the presiding officer orders otherwise, rulings made by him shall be effective when the order is released or (if no written order) when the ruling is made. The Commission may stay the effect of any ruling which comes before it for consideration on appeal.

Federal Communications Commission

§1.311

(2) Appeals filed under paragraph (a) of this section shall be filed within 5 days after the order is released or (if no written order) after the ruling is made. Appeals filed under paragraph (b) of this section shall be filed within 5 days after the appeal is allowed.

(3) The appeal shall conform with the specifications set out in §1.49 and shall be subscribed and verified as provided in §1.52.

(4) The appeal shall be served on parties to the proceeding (see §§1.47 and 1.211), and shall be filed with the Secretary, Federal Communications Commission, Washington, D.C. 20554.

(5) The appeal shall not exceed 5 double-spaced typewritten pages.

(6) Appeals are acted on by the Commission.

(7) Oppositions and replies shall be served and filed in the same manner as appeals and shall be served on appellant if he is not a party to the proceeding. Oppositions shall be filed within 5 days after the appeal is filed. Replies shall not be permitted, unless the Commission specifically requests them. Oppositions shall not exceed 5 double-spaced typewritten pages. Replies shall not exceed 5 double-spaced typewritten pages.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[35 FR 17333, Nov. 11, 1970, as amended at 40 FR 39509, Aug. 28, 1975; 41 FR 14874, Apr. 8, 1976; 41 FR 28789, July 13, 1976; 46 FR 58682, Dec. 3, 1981; 55 FR 36641, Sept. 6, 1990; 62 FR 4171, Jan. 29, 1997]

§1.302 Appeal from presiding officer's final ruling; effective date of ruling.

(a) If the presiding officer's ruling terminates a hearing proceeding, any party to the proceeding, as a matter of right, may file an appeal from that ruling within 30 days after the ruling is released.

(b) Any party who desires to preserve the right to appeal shall file a notice of appeal within 10 days after the ruling is released. If a notice of appeal is not filed within 10 days, the ruling shall be effective 30 days after the ruling is released and within this period, may be reviewed by the Commission on its own motion. If an appeal is not filed following notice of appeal, the ruling shall be effective 50 days after the day of its re-

lease and, within this period, may be reviewed by the Commission on its own motion. If an appeal is filed, or if the Commission reviews the ruling on its own motion, the effect of the ruling is further stayed pending the completion of proceedings on appeal or review.

(c) The appeal shall conform with the specifications set out in §1.49 and shall be subscribed and verified as provided in §1.52.

(d) The appeal shall be served on parties to the proceeding (see §§1.47 and 1.211), and shall be filed with the Secretary, Federal Communications Commission, Washington, D.C. 20554.

(e) The appeal shall not exceed 25 double-spaced typewritten pages.

(f) The Commission will act on the appeal.

(g) Oppositions and replies shall be filed and served in the same manner as the appeal. Oppositions to an appeal shall be filed within 15 days after the appeal is filed. Replies to oppositions shall be filed within 10 days after the opposition is filed and shall be limited to matters raised in the oppositions. Oppositions shall not exceed 25 double-spaced typewritten pages. Replies shall not exceed 10 double-spaced typewritten pages.

[35 FR 17333, Nov. 11, 1970, as amended at 36 FR 7423, Apr. 20, 1971; 62 FR 4171, Jan. 29, 1997]

THE DISCOVERY AND PRESERVATION OF EVIDENCE

AUTHORITY: Sections 1.311 through 1.325 are issued under secs. 4, 303, 409, 48 Stat., as amended, 1066, 1082, 1096; 47 U.S.C. 154, 303, 409, 5 U.S.C. 552.

§1.311 General.

Sections 1.311 through 1.325 provide for taking the deposition of any person (including a party), for interrogatories to parties, and for orders to parties relating to the production of documents and things and for entry upon real property. These procedures may be used for the discovery of relevant facts, for the production and preservation of evidence for use at the hearing, or for both purposes.

(a) *Applicability.* For purposes of discovery, these procedures may be used in any case of adjudication (as defined in the Administrative Procedure Act)

§ 1.311

47 CFR Ch. I (10–1–97 Edition)

which has been designated for hearing. For the preservation of evidence, they may be used in any case which has been designated for hearing and is conducted under the provisions of this subpart (see § 1.201).

(b) *Scope of examination.* Persons and parties may be examined regarding any matter, not privileged, which is relevant to the hearing issues, including the existence, description, nature, custody, condition and location of any books, documents, or other tangible things and the identity and location of persons having knowledge of relevant facts. It is not ground for objection to use of these procedures that the testimony will be inadmissible at the hearing if the testimony sought appears reasonably calculated to lead to the discovery of admissible evidence. The use of these procedures against the Commission is subject to the following additional limitations:

(1) The informer's privilege shall encompass information which may lead to the disclosure of an informer's identity.

(2) Commission personnel may not be questioned by deposition for the purposes of discovery except on special order of the Commission, but may be questioned by written interrogatories under § 1.323. Interrogatories shall be served on the appropriate Bureau Chief (see § 1.21(b)). They will be answered and signed by those personnel with knowledge of the facts. The answers will be served by the Secretary of the Commission upon parties to the proceeding.

(3) Commission records are not subject to discovery under § 1.325. The inspection of Commission records is governed by the Freedom of Information Act, as amended, and by §§ 0.451 through 0.467 of this chapter. Commission employees may be questioned by written interrogatories regarding the existence, nature, description, custody, condition and location of Commission records, but may not be questioned concerning their contents unless the records are available (or are made available) for inspection under §§ 0.451 through 0.467. See § 0.451(b)(5) of this chapter.

(4) Subject to paragraphs (b) (1) through (3) of this section, Commission

personnel may be questioned generally by written interrogatories regarding the existence, description, nature, custody, condition and location of relevant documents and things and regarding the identity and location of persons having knowledge of relevant facts, and may otherwise only be examined regarding facts of the case as to which they have direct personal knowledge.

(c) *Schedule for use of the procedures.*

(1) In comparative broadcast proceedings involving applicants for only new facilities, discovery commences with the release of the hearing designation order, and, in routine cases, the discovery phase of the proceeding will be conducted in a manner intended to conclude that portion of the case within 90 days of the release of the designation order.

(2) In all other proceedings, except as provided by special order of the presiding officer, discovery may be initiated before or after the prehearing conference provided for in § 1.248 of this part.

(3) In all proceedings, the presiding officer may at any time order the parties or their attorneys to appear at a conference to consider the proper use of these procedures, the time to be allowed for such use, and/or to hear argument and render a ruling on disputes that arise under these rules.

(d) *Who shall act.* Actions provided for in §§ 1.311 through 1.325 will, in most cases, be taken by the officer designated to preside at the hearing (see § 1.241). If the proceeding, or a particular matter to which the action relates, is before the Commission, a commissioner or panel of commissioners, or the Chief Administrative Law Judge, the action will be taken by such officer or body. The term *presiding officer*, as used in §§ 1.311 through 1.325 shall be understood to refer to the appropriate officer or body. See §§ 0.341, 0.351, 0.365, and 1.271 of this chapter.

(e) *Stipulations regarding the taking of depositions.* If all of the parties so stipulate in writing and if there is no interference to the conduct of the proceeding, depositions may be taken before any person, at any time (subject to the limitation below) or place, upon any notice and in any manner, and when so

Federal Communications Commission

§ 1.315

taken may be used like other depositions. An original and one copy of the stipulation shall be filed with the Secretary of the Commission, and a copy of the stipulation shall be served on the presiding officer, at least 3 days before the scheduled taking of the deposition.

[33 FR 463, Jan. 12, 1968, as amended at 40 FR 39509, Aug. 28, 1975; 47 FR 51873, Nov. 18, 1982; 56 FR 794, Jan. 9, 1991; 62 FR 4171, Jan. 29, 1997]

§ 1.313 Protective orders.

The use of the procedures set forth in §§ 1.311 through 1.325 of this part is subject to control by the presiding officer, who may issue any order consistent with the provisions of those sections which is appropriate and just for the purpose of protecting parties and deponents or of providing for the proper conduct of the proceeding. Whenever doing so would be conducive to the efficient and expeditious conduct of the proceeding, the presiding officer may convene a conference to hear argument and issue a ruling on any disputes that may arise under these rules. The ruling, whether written or delivered on the record at a conference, may specify any measures, including the following to assure proper conduct of the proceeding or to protect any party or deponent from annoyance, expense, embarrassment or oppression:

(a) That depositions shall not be taken or that interrogatories shall not be answered.

(b) That certain matters shall not be inquired into.

(c) That the scope of the examination or interrogatories shall be limited to certain matters.

(d) That depositions may be taken only at some designated time or place, or before an officer, other than that stated in the notice.

(e) That depositions may be taken only by written interrogatories or only upon oral examination.

(f) That, after being sealed, the deposition shall be opened only by order of the presiding officer.

[33 FR 463, Jan. 12, 1968, as amended at 56 FR 794, Jan. 9, 1991]

§ 1.315 Depositions upon oral examination—notice and preliminary procedure.

(a) *Notice.* A party to a hearing proceeding desiring to take the deposition of any person upon oral examination shall give a minimum of 21 days notice in writing to every other party, to the person to be examined, and to the presiding officer. An original and three copies of the notice shall be filed with the Secretary of the Commission. Related pleadings shall be served and filed in the same manner. The notice shall contain the following information:

(1) The name and address of each person to be examined, if known, and if the name is not known, a general description sufficient to identify him or the particular class or group to which he belongs.

(2) The time and place for taking the deposition of each person to be examined, and the name or descriptive title and address of the officer before whom the deposition is to be taken.

(3) The matters upon which each person will be examined. See § 1.319.

(b) *Responsive pleadings.* (1) Within 7 days after service of the notice to take depositions, a motion opposing the taking of depositions may be filed by any party to the proceeding or by the person to be examined. See § 1.319(a).

(2) Within 14 days after service of the notice to take depositions, a response to the opposition motion may be filed by any party to the proceeding.

(3) Additional pleadings should not be filed and will not be considered.

(4) The computation of time provisions set forth in § 1.4(g) shall not apply to pleadings filed under the provisions of this paragraph.

(c) *Protective order.* On an opposition motion filed under paragraph (b) of this section, or on his own motion, the presiding officer may issue a protective order. See § 1.313. A protective order issued by the presiding officer on his own motion may be issued at any time prior to the date specified in the notice for the taking of depositions.

(d) *Authority to take depositions.* (1) If an opposition motion is not filed within 7 days after service of the notice to take depositions, and if the presiding officer does not on his own motion

§ 1.316

47 CFR Ch. I (10–1–97 Edition)

issue a protective order prior to the time specified in the notice for the taking of depositions, the depositions described in the notice may be taken. An order for the taking of depositions is not required.

(2) If an opposition motion is filed, the depositions described in the notice shall not be taken until the presiding officer has acted on that motion. If the presiding officer authorizes the taking of depositions, he may specify a time, place or officer for taking them different from that specified in the notice to take depositions.

(3) If the presiding officer issues a protective order, the depositions described in the notice may be taken (if at all) only in accordance with the provisions of that order.

(e) *Broadcast comparative proceedings involving applicants for only new facilities.* In these cases, the 21-day advance notice provision of paragraph (a) of this section shall be inapplicable to depositions of active and passive owners of applicants in the proceeding. All applicants in such proceedings should be prepared to make their active and passive owners available for depositions during the period commencing with the deadline for filing notices of appearance and ending 90 days after the release of the designation order, if such depositions are requested by a party to the proceeding. All such depositions will be conducted in Washington, DC or in the community of license of the proposed station, at the deponent's option, unless all parties agree to some other location.

[33 FR 10571, July 25, 1968, as amended at 56 FR 794, Jan. 9, 1991]

§ 1.316 Depositions upon written interrogatories—notice and preliminary procedure.

(a) *Service of interrogatories; notice.* A party to the hearing proceeding desiring to take the deposition of any person upon written interrogatories shall serve the interrogatories upon every other party and shall give a minimum of 35 days notice in writing to every other party and to the person to be examined. An original and three copies of the interrogatories and the notice (and of all related pleadings) shall be filed with the Secretary of the Commission.

A copy of the interrogatories and the notice (and of all related pleadings) shall be served on the presiding officer. The notice shall contain the following information:

(1) The name and address of each person to be examined, if known, and if the name is not known, a general description sufficient to identify him or the particular class or group to which he belongs.

(2) The time and place for taking the deposition of each person to be examined, and the name or descriptive title and address of the officer before whom the deposition is to be taken.

(3) The matters upon which each person will be examined. See § 1.319.

(b) *Additional interrogatories.* Within 7 days after the filing and service of the original interrogatories, any other party to the proceeding may, in the same manner, file and serve additional interrogatories to be asked of the same witness at the same time and place, with notice to the witness of any additional matters upon which he will be examined.

(c) *Cross interrogatories.* Within 14 days after the filing and service of the original interrogatories, any party to the proceeding may, in the same manner, file and serve cross interrogatories, which shall be limited to matters raised in the original or in the additional interrogatories.

(d) *Responsive pleadings.* (1) Within 21 days after service of the original interrogatories, any party to the proceeding may move to limit or suppress any original, additional or cross interrogatory, and the person to be examined may file a motion opposing the taking of depositions. See § 1.319(a).

(2) Within 28 days after service of the original interrogatories, a response to a motion to limit or suppress any interrogatory or to a motion opposing the taking of depositions may be filed by any party to the proceeding.

(3) Additional pleadings should not be filed and will not be considered.

(e) *Protective order.* On a motion to limit or suppress or an opposition motion filed under paragraph (d) of this section, or on his own motion, the presiding officer may issue a protective order. See § 1.313. A protective order issued by the presiding officer on his own

motion may be issued at any time prior to the date specified in the notice for the taking of depositions.

(f) *Authority to take depositions.* (1) If an opposition motion is not filed within 21 days after service of the notice to take depositions, and if the presiding officer does not on his own motion issue a protective order prior to the time specified in the notice for the taking of depositions, the depositions described in the notice may be taken. An order for the taking of depositions is not required.

(2) If an opposition motion is filed, the depositions described in the notice shall not be taken until the presiding officer has acted on that motion. If the presiding officer authorizes the taking of depositions, he may specify a time, place or officer for taking them different from that specified in the notice to take depositions.

(3) If the presiding officer issues a protective order, the depositions described in the notice may be taken (if at all) only in accordance with the provisions of that order.

NOTE: The computation of time provisions of §1.4(g) shall not apply to interrogatories and pleadings filed under the provisions of this section.

[33 FR 10571, July 25, 1968]

§1.318 The taking of depositions.

(a) *Persons before whom depositions may be taken.* Depositions shall be taken before any judge of any court of the United States; any U.S. Commissioner; any clerk of a district court; any chancellor, justice or judge of a supreme or superior court; the mayor or chief magistrate of a city; any judge of a county court, or court of common pleas of any of the United States; any notary public, not being of counsel or attorney to any party, nor interested in the event of the proceeding; or presiding officers, as provided in §1.243.

(b) *Attendance of witnesses.* The attendance of witnesses at the taking of depositions may be compelled by the use of subpoena as provided in §§1.331 through 1.340.

(c) *Oath; transcript.* The officer before whom the deposition is to be taken shall administer an oath or affirmation to the witness and shall personally, or

by someone acting under his direction and in his presence record the testimony of the witness. The testimony may be taken stenographically or, upon approval by the presiding officer, testimony may be taken through the use of telephonically or electronically recorded methods, including videotape. In the event these latter methods are used for the deposition, the parties may agree to the waiver of the provisions of paragraphs (e) and (f) as appropriate and as approved by the presiding officer.

(d) *Examination.* (1) In the taking of depositions upon oral examination, the parties may proceed with examination and cross-examination of deponents as permitted at the hearing. In lieu of participating in the oral examination, parties served with the notice to take depositions may transmit written interrogatories to the officer designated in the notice, who shall propound them to the witness and record the answers verbatim.

(2) In the taking of depositions upon written interrogatories, the party who served the original interrogatories shall transmit copies of all interrogatories to the officer designated in the notice, who shall propound them to the witness and record the answers verbatim.

(e) *Submission of deposition to witness; changes; signing.* When the testimony is fully transcribed, the deposition of each witness shall be submitted to him for examination and shall be read to or by him, unless such examination and reading are waived by the witness and by the parties. Any changes in form or substance which the witness desires to make shall be entered upon the deposition by the officer with a statement of the reasons given by the witness for making them. The deposition shall then be signed by the witness, unless the parties by stipulation waive the signing, or the witness is ill, cannot be found, or refuses to sign. If the deposition is not signed by the witness, the officer shall sign it and state on the record the fact of the waiver, the illness or absence of the witness, or of his refusal to sign, together with the reason (if any) given therefor; and the deposition may then be used as fully as though signed, unless upon a motion to

§ 1.319

47 CFR Ch. I (10–1–97 Edition)

suppress, the presiding officer holds that the reason given for the refusal to sign requires rejection of the deposition in whole or in part.

(f) *Certification of deposition and filing by officer; copies.* The officer shall certify on the deposition that the witness was duly sworn by him, that the deposition is a true record of the testimony given by the witness, and that said officer is not of counsel or attorney to either of the parties, nor interested in the event of the proceeding or investigation. He shall then securely seal the deposition in an envelope endorsed with the title of the action and marked “Deposition of (here insert name of witness)” and shall promptly send the original and two copies of the deposition and of all exhibits, together with the notice and any interrogatories received by him, by certified mail to the Secretary of the Commission.

[33 FR 463, Jan. 12, 1968, as amended at 47 FR 51873, Nov. 18, 1982]

§ 1.319 Objections to the taking of depositions.

(a) *Objections to be made by motion prior to the taking of depositions.* If there is objection to the substance of any interrogatory or to examination on any matter clearly covered by the notice to take depositions, the objection shall be made in a motion opposing the taking of depositions or in a motion to limit or suppress the interrogatory as provided in §§ 1.315(b) and 1.316(d) and shall not be made at the taking of the deposition.

(b) *Objections to be made at the taking of depositions.* Errors and irregularities occurring at the oral examination in the manner of taking the deposition, in the form of the questions or answers, in the oath or affirmation, or in the conduct of parties, and errors of any kind which might be obviated, removed, or cured if promptly presented, are waived unless reasonable objection thereto is made at the taking of the deposition. If such objection is made, counsel shall, if possible, agree upon the measures required to obviate, remove, or cure such errors. The measures agreed upon shall be taken. If agreement cannot be reached, the objection shall be noted on the deposition by the officer taking it, and the testi-

mony objected to shall be taken subject to the objection.

(c) *Additional objections which may be made at the taking of depositions.* Objection may be made at the taking of depositions on the ground of relevancy or privilege, if the notice to take depositions does not clearly indicate that the witness is to be examined on the matters to which the objection relates. See paragraph (a) of this section. Objection may also be made on the ground that the examination is being conducted in such manner as to unreasonably annoy, embarrass, or oppress a deponent or party.

(1) When there is objection to a line of questioning, as permitted by this paragraph, counsel shall, if possible, reach agreement among themselves regarding the proper limits of the examination.

(2) If counsel cannot agree on the proper limits of the examination the taking of depositions shall continue on matters not objected to and counsel shall, within 24 hours, either jointly or individually, telegraph statements of their positions to the presiding officer, together with the telephone numbers at which they and the officer taking the depositions can be reached, or shall otherwise jointly confer with the presiding officer. If individual statements are submitted, copies shall be provided to all counsel participating in the taking of depositions.

(3) The presiding officer shall promptly rule upon the question presented or take such other action as may be appropriate under § 1.313, and shall give notice of his ruling, by telephone, to counsel who submitted statements and to the officer taking the depositions. The presiding officer shall thereafter reduce his ruling to writing.

(4) The taking of depositions shall continue in accordance with the presiding officer's ruling. Such rulings are not subject to appeal.

[33 FR 463, Jan. 12, 1968]

§ 1.321 Use of depositions at the hearing.

(a) No inference concerning the admissibility of a deposition in evidence shall be drawn because of favorable action on the notice to take depositions.

(b) Except as provided in this paragraph and in § 1.319, objection may be made at the hearing to receiving in evidence any deposition or part thereof for any reason which would require the exclusion of the evidence if the witness were then present and testifying.

(1) Objections to the competency of a witness, or the competency, relevancy or materiality of testimony are waived by failure to make them before or during the taking of depositions if (and only if) the ground of the objection is one which might have been obviated or removed if presented at that time.

(2) Objection on the ground of privilege is waived by failure to make it before or during the taking of depositions.

(c) A party shall not be deemed to make a person his own witness for any purpose by taking his deposition. The introduction in evidence of the deposition or any part thereof for any purpose other than that of contradicting or impeaching the deponent makes the deponent the witness of the party introducing the deposition, but this shall not apply to the use by an adverse party of a deposition as described in paragraph (d)(2) of this section. At the hearing any party may rebut any relevant evidence contained in a deposition whether introduced by him or by any other party.

(d) At the hearing (or in a pleading), any part or all of a deposition, so far as admissible, may be used against any party who was present or represented at the taking of the deposition or who had due notice thereof, in accordance with any one of the following provisions:

(1) Any deposition may be used by any party for the purpose of contradicting or impeaching the testimony of deponent as a witness.

(2) The deposition of a party or of any one who at the time of taking the deposition was an officer, director, or managing agent of a public or private corporation, partnership or association which is a party may be used by an adverse party for any purpose.

(3) To the extent that the affirmative direct case of a party is made in writing pursuant to § 1.248(d), the deposition of any witness, whether or not a party, may be used by any party for

any purpose, provided the witness is made available for cross-examination. In all cases, the deposition of a witness, whether or not a party, may be used by any party for any purpose if the presiding officer finds: (i) That the witness is dead; or (ii) that the witness is out of the United States, unless it appears that the absence of the witness was procured by the party offering the deposition; or (iii) that the witness is unable to attend or testify because of age, sickness, infirmity, or imprisonment; or (iv) upon application and notice, that such exceptional circumstances exist as to make it desirable in the interest of justice and with due regard to the importance of presenting the testimony of witnesses orally in open hearing, to allow the deposition to be used.

(4) If only part of a deposition is offered in evidence by a party, an adverse party may require him to introduce all of it which is relevant to the part introduced, and any party may introduce any other parts.

(5) Substitution of parties does not affect the right to use depositions previously taken; and, when an action in any hearing has been dismissed and another action involving the same subject matter is afterward brought between the same parties or their representatives or successors in interest, all depositions lawfully taken and duly filed in the former action may be used in the latter as if originally taken therefor.

[33 FR 463, Jan. 12, 1968, as amended at 41 FR 14874, Apr. 8, 1976]

§ 1.323 Interrogatories to parties.

(a) *Interrogatories.* Any party may serve upon any other party written interrogatories to be answered in writing by the party served or, if the party served is a public or private corporation or a partnership or association, by any officer or agent, who shall furnish such information as is available to the party. A copy of the interrogatories shall be served upon all parties to the proceeding. An original and three copies of the interrogatories, answers, and all related pleadings shall be filed with the Secretary of the Commission. A copy of the interrogatories, answers

§ 1.325

47 CFR Ch. I (10–1–97 Edition)

and all related pleadings shall be served on the presiding officer.

(1) Except as otherwise provided in a protective order, the number of interrogatories or sets of interrogatories is not limited.

(2) Except as provided in such an order, interrogatories may be served after a deposition has been taken, and a deposition may be sought after interrogatories have been answered.

(b) *Answers and objections.* Each interrogatory shall be answered separately and fully in writing under oath or affirmation, unless it is objected to, in which event the reasons for objection shall be stated in lieu of an answer. The answers shall be signed by the person making them, and the objections by the attorney making them. The party upon whom the interrogatories were served shall serve a copy of the answers and objections upon all parties to the proceeding within 14 days after service of the interrogatories, or within such shorter or longer period as the presiding officer may allow. Answers may be used in the same manner as depositions of a party (see § 1.321(d)).

(c) *Motion to compel an answer.* Any party to the proceeding may, within 7 days, move for an order with respect to any objection or other failure to answer an interrogatory. For purposes of this paragraph, an evasive or incomplete answer is a failure to answer; and if the motion is based on the assertion that the answer is evasive or incomplete, it shall contain a statement as to the scope and detail of an answer which would be considered responsive and complete. The party upon whom the interrogatories were served may file a response within 7 days after the motion is filed, to which he may append an answer or an amended answer. Additional pleadings should not be submitted and will not be considered.

(d) *Action by the presiding officer.* If the presiding officer determines that an objection is not justified, he shall order that the answer be served. If an interrogatory has not been answered, the presiding officer may rule that the right to object has been waived and may order that an answer be served. If an answer does not comply fully with the requirements of this section, the presiding officer may order that an

amended answer be served, may specify the scope and detail of the matters to be covered by the amended answer, and may specify any appropriate procedural consequences (including adverse findings of fact and dismissal with prejudice) which will follow from the failure to make a full and responsive answer. If a full and responsive answer is not made, the presiding officer may issue an order invoking any of the procedural consequences specified in the order to compel an answer.

(e) *Appeal.* As order to compel an answer is not subject to appeal.

[33 FR 10572, July 25, 1968, as amended at 35 FR 17334, Nov. 11, 1970]

§ 1.325 Discovery and production of documents and things for inspection, copying, or photographing.

(a) A party to a Commission proceeding may request any other party except the Commission to produce and permit inspection and copying or photographing, by or on behalf of the requesting party, of any designated documents, papers, books, accounts, letters, photographs, objects, or tangible things which constitute or contain evidence within the scope of the examination permitted by § 1.311(b) of this part and which are in his possession, custody, or control or to permit entry upon designated land or other property in his possession or control for purposes of inspecting, measuring, surveying, or photographing the property or any designated object or operation thereon within the scope of the examination permitted by § 1.311(b) of this part.

(1) Such requests need not be filed with the presiding officer, but copies of the request shall be served on all other parties to the proceeding.

(2) The party against whom the request was made must, within 10 days, comply with the request or object to the request, claiming a privilege or raising other proper objections. If the request is not complied with in whole or in part, the requesting party may file a motion to compel production of documents or access to property with the presiding officer. A motion to compel must be accompanied by a copy of the original request and the responding party's objection or claim of privilege.

Federal Communications Commission

§ 1.325

Motions to compel must be filed within five business days of the objection or claim of privilege.

(3) In resolving any disputes involving the production of documents or access to property, the presiding officer may direct that the materials objected to be presented to him for *in camera* inspection.

(b) Any party seeking the production of Commission records should proceed under § 0.460 or § 0.461 of this chapter. See §§ 0.451 through 0.467.

(c) In comparative broadcast proceedings involving applicants for only new facilities, all applicants will serve the materials listed in the Standard Document Production Order and the Standardized Integration Statement on all other parties in the case that have filed Notices of Appearance. The exchange of these materials must be accomplished within five days after the date established for filing notices of appearance (see § 1.221).

(1) *Standard Document Production Order.* The following documents must be produced or objected to on grounds of privilege (Unless otherwise directed by the presiding officer, copies of these documents should not be filed with the presiding officer):

(i) All formation and organizational documents, including articles of incorporation, by laws, partnership agreements, voting rights, proxies, and any amendments to the foregoing documents;

(ii) All minutes of meetings relating to the application;

(iii) All documents relating to the rights or plans of persons or entities to purchase an interest in the applicant or of current owners to alienate their interests;

(iv) All documents relating to pledges, mortgages, security interests, or other encumbrances of any kind with respect to the applicant;

(v) All bank letters and other financing documents with the dollar amounts unexpurgated;

(vi) All documents relating to the applicant's proposed transmitter site;

(vii) All documents relating to communications by proposed integrated principals with respect to their proposed participation in the management

of the station and the disposition of their current employment;

(viii) All documents relating to prior integration pledges made by principals who propose to be integrated into the management of the station at issue;

(ix) All documents relating to communications by and between principals of the applicant concerning the application, including communications between active and passive principals;

(x) Representative documents relating to enhancement credits and preferences sought by the applicant's principals for local residence, civic participation, past broadcast experience, minority/female status, and the like;

(xi) All documents relating to commitments to divest other media interests; and

(xii) All documents that identify or describe the principals who are responsible for completing the application, arranging financing, obtaining the applicant's transmitter site, publishing the required notices, establishing the local public inspection file, and retaining lawyers, engineers, and other professionals.

(2) *Standardized Integration Statement.* On the same day that documents are exchanged pursuant to the Standardized Document Production Order, the following information must also be provided by all applicants (Copies of this statement should be filed with the presiding officer and served on all parties to the proceeding that have filed Notices of Appearance):

(i) The ownership structure of the applicant, i.e., whether it is a partnership, limited partnership, or a corporation (if a corporation, indicate whether it has voting and non-voting stock);

(ii) The ownership percentage of each owner;

(iii) The identity of the owners who will work at the proposed station, what titles and duties they will have, how many hours they will work per week, and how they will reconcile any current business interests or employment with that commitment to the station;

(iv) All other media interests held by the persons identified under paragraph (c)(2)(ii), of this section;

§ 1.331

(v) Whether the integrated owners will claim credit for minority or female ownership and if so, specifically on what basis;

(vi) Whether the integrated owners will claim credit for local residence and civic involvement in the city of license or service area and if so, specifically on what basis (including a detailed chronology of past residence and a description of civic activities and their duration);

(vii) Whether the integrated owners will claim credit for previous broadcast experience and if so, provide a detailed list of the stations they worked at, the titles and duties they had, and the years in which they were so employed; and

(viii) Whether the applicant will claim a daytimer preference and if so, specifically on what basis.

(3) *Supplemental document production.* Parties may request additional relevant documents, not called for in the Standard Document Production Order, at any time after the release of the designation order. Supplemental requests for documents based on materials exchanged pursuant to the Standardized Document Production Order and Standardized Integration Statement must be filed no later than ten days after those standardized exchanges. Other supplemental document requests must be filed no later than ten days after receipt of the information on which those requests are based. Supplemental document requests will be handled under the procedures established in paragraph (a) of this section. To facilitate the resolution of disputes concerning the production of documents, the presiding officer may convene a pre-hearing conference to hear argument on and dispose of any such disputes.

[33 FR 463, Jan. 12, 1968, as amended at 40 FR 39509, Aug. 28, 1975; 56 FR 794, Jan. 9, 1991; 56 FR 25639, June 5, 1991]

SUBPENAS

AUTHORITY: Sections 1.331 and 1.333 through 1.340 are issued under sec. 409, 48 Stat. 1096; 47 U.S.C. 409.

47 CFR Ch. I (10–1–97 Edition)

§ 1.331 Who may sign and issue.

Subpenas requiring the attendance and testimony of witnesses, and subpenas requiring the production of any books, papers, schedules of charges, contracts, agreements, and documents relating to any matter under investigation or hearing, may be signed and issued as follows:

(a) Hearings before the Commission en banc, an individual commissioner, or a panel of commissioners: By any commissioner participating in the conduct of the hearing.

(b) Hearings before an administrative law judge: By the administrative law judge or, in his absence, by the Chief Administrative Law Judge.

§ 1.333 Requests for issuance of subpoena.

(a) Unless submitted on the record while a hearing is in progress, requests for a subpoena ad testificandum shall be submitted in writing.

(b) Requests for a subpoena *duces tecum* shall be submitted in writing, duly subscribed and verified, and shall specify with particularity the books, papers, and documents desired and the facts expected to be proved thereby. Where the subpoena *duces tecum* request is directed to a nonparty to the proceeding, the presiding officer may issue the same, upon request, without an accompanying subpoena to enforce a notice to take depositions, provided for in paragraph (e) of this section, where it appears that the testimony of said person is not required in connection with the subpoena *duces tecum*.

(c) All requests for subpoenas shall be supported by a showing of the general relevance and materiality of the evidence sought.

(d) Requests for subpoenas shall be submitted in triplicate, but need not be served on the parties to the proceeding.

(e) Requests for issuance of a subpoena ad testificandum to enforce a notice to take depositions shall be submitted in writing. Such requests may be submitted with the notice or at a later date. The request shall not be granted until the period for the filing of motions opposing the taking of depositions has expired or, if a motion has been filed, until that motion has been acted on.

Federal Communications Commission

§ 1.338

Regardless of the time when the subpoena request is submitted, it need not be accompanied by a showing that relevant and material evidence will be adduced, but merely that the person will be examined regarding a nonprivileged matter which is relevant to the hearing issues. The subpoena request may ask that a subpoena duces tecum be contemporaneously issued commanding the person to whom it is directed to produce designated books, papers, documents, or tangible things which constitute or contain evidence relating to any of the matters within the scope of the examination permitted by § 1.311(b) but in that event the subpoena request will be subject to the provisions of § 1.313 and paragraph (b) of this section.

(f) Requests for issuance of a subpoena duces tecum to enforce an order for the production of documents and things for inspection and copying under § 1.325 may be submitted with the motion requesting the issuance of such an order. Regardless of the time when the subpoena request is submitted, it need not be accompanied by a showing that relevant and material evidence will be adduced, but merely that the documents and things to be examined contain nonprivileged matter which is relevant to the subject matter of the proceeding.

[28 FR 12425, Nov. 22, 1963, as amended at 33 FR 466, Jan. 12, 1968; 47 FR 51873, Nov. 18, 1982]

§ 1.334 Motions to quash.

Any person against whom a subpoena is directed may file a motion to quash or limit the subpoena, setting forth the reasons why the subpoena should not be complied with or why it should be limited in scope.

§ 1.335 Rulings.

Prompt notice, including a brief statement of the reasons therefor, will be given of the denial, in whole or in part, of a request for subpoena or of a motion to quash.

§ 1.336 Service of subpoenas.

(a) A subpoena may be served by a United States marshal or his deputy, by Commission personnel, or by any person who is not a party to the proceeding and is not less than 18 years of age.

(b) Service of a subpoena upon the person named therein shall be made by exhibiting the original subpoena to him, by reading the original subpoena to him if he is unable to read, by delivering the duplicate subpoena to him, and by tendering to him the fees for one day's attendance at the proceeding to which he is summoned and the mileage allowed by law. If the subpoena is issued on behalf of the United States or an officer or agency thereof, attendance fees and mileage need not be tendered.

§ 1.337 Return of service.

(a) If service of the subpoena is made by a person other than a United States marshal or his deputy such person shall make affidavit thereof, stating the date, time, and manner of service.

(b) In case of failure to make service, the reasons for the failure shall be stated on the original subpoena by the person who attempted to make service.

(c) The original subpoena, bearing or accompanied by the required return affidavit or statement, shall be returned forthwith to the Secretary of the Commission or, if so directed on the subpoena, to the official before whom the person named in the subpoena is required to appear.

§ 1.338 Subpena forms.

(a) Subpena forms, marked "Original", "Duplicate", and "Triplicate", and bearing the Commission's seal, may be obtained from the Commission's Dockets Division. These forms are to be completed and submitted with any request for issuance of a subpoena.

(b) If the request for issuance of a subpoena is granted, the "Original" and "Duplicate" copies of the subpoena are returned to the person who submitted the request. The "Triplicate" copy is retained for the Commission's files.

(c) The "Original" copy of the subpoena includes a form for proof of service. This form is to be executed by the person who effects service and returned by him to the Secretary of the Commission or, if so directed on the subpoena, to the official before whom the person named in the subpoena is required to appear.

(d) The "Duplicate" copy of the subpoena shall be served upon the person

§ 1.339

named therein and retained by him. This copy should be presented in support of any claim for witness fees or mileage allowances for testimony on behalf of the Commission.

§ 1.339 Witness fees.

Witnesses who are subpoenaed and respond thereto are entitled to the same fees, including mileage, as are paid for like service in the courts of the United States. Fees shall be paid by the party at whose instance the testimony is taken.

§ 1.340 Attendance of witness; disobedience.

The attendance of witnesses and the production of documentary evidence may be required from any place in the United States at any designated place of hearing. In case of disobedience to a subpoena, the Commission or any party to a proceeding before the Commission may invoke the aid of any court of the United States in requiring the attendance and testimony of witnesses and the production of documentary evidence.

EVIDENCE**§ 1.351 Rules of evidence.**

Except as otherwise provided in this subpart, the rules of evidence governing civil proceedings in matters not involving trial by jury in the courts of the United States shall govern formal hearings. Such rules may be relaxed if the ends of justice will be better served by so doing.

§ 1.352 Cumulative evidence.

The introduction of cumulative evidence shall be avoided, and the number of witnesses that may be heard in behalf of a party on any issue may be limited.

§ 1.353 Further evidence during hearing.

At any stage of a hearing, the presiding officer may call for further evidence upon any issue and may require such evidence to be submitted by any party to the proceeding.

47 CFR Ch. I (10–1–97 Edition)**§ 1.354 Documents containing matter not material.**

If material and relevant matter offered in evidence is embraced in a document containing other matter not material or relevant, and not intended to be put in evidence, such document will not be received, but the party offering the same shall present to other counsel, and to the presiding officer, the original document, together with true copies of such material and relevant matter taken therefrom, as it is desired to introduce. Upon presentation of such matter, material and relevant, in proper form, it may be received in evidence, and become a part of the record. Other counsel will be afforded an opportunity to introduce in evidence, in like manner, other portions of such document if found to be material and relevant.

§ 1.355 Documents in foreign language.

Every document, exhibit, or other paper written in a language other than English, which shall be filed in any proceeding, or in response to any order, shall be filed in the language in which it is written together with an English translation thereof duly verified under oath to be a true translation. Each copy of every such document, exhibit, or other paper filed shall be accompanied by a separate copy of the translation.

§ 1.356 Copies of exhibits.

No document or exhibit, or part thereof, shall be received as, or admitted in, evidence unless offered in duplicate. In addition, when exhibits of a documentary character are to be offered in evidence, copies shall be furnished to other counsel unless the presiding officer otherwise directs.

§ 1.357 Mechanical reproductions as evidence.

Unless offered for the sole purpose of attempting to prove or demonstrate sound effect, mechanical or physical reproductions of sound waves shall not be admitted in evidence. Any party desiring to offer any matter alleged to be contained therein or thereupon shall have such matter typewritten on paper of the size prescribed by § 1.49, and the same shall be identified and offered in

Federal Communications Commission

§ 1.363

duplicate in the same manner as other exhibits.

§ 1.358 Tariffs as evidence.

In case any matter contained in a tariff schedule on file with the Commission is offered in evidence, such tariff schedule need not be produced or marked for identification, but the matter so offered shall be specified with particularity (tariff and page number) in such manner as to be readily identified, and may be received in evidence by reference subject to check with the original tariff schedules on file.

§ 1.359 Proof of official record; authentication of copy.

An official record or entry therein, when admissible for any purpose, may be evidenced by an official publication thereof or by a copy attested by the officer having legal custody of the record, or by his deputy, and accompanied with a certificate that such officer has the custody. If the office in which the record is kept is within the United States or within a territory or insular possession subject to the dominion of the United States, the certificate may be made by the judge of a court of record of the district or political subdivision in which the record is kept, authenticated by the seal of the court, or may be made by any public officer having a seal of office having official duties in the district or political subdivision in which the record is kept, authenticated by the seal of his office. If the office in which the record is kept is in a foreign state or country, the certificate may be made by a secretary of embassy or legation, consul general, consul, vice consul, or consular agent, or by any officer in the foreign service of the United States stationed in the foreign state or country in which the record is kept, and authenticated by the seal of his office.

§ 1.360 Proof of lack of record.

The absence of an official record or entry of a specified tenor in an official record may be evidenced by a written statement signed by an officer, or by his deputy, who would have custody of the official record, if it existed, that after diligent search no record or entry of a specified tenor is found to exist in

the records of his office, accompanied by a certificate as provided in § 1.359. Such statement and certificate are admissible as evidence that the records of his office contain no such record or entry.

§ 1.361 Other proof of official record.

Sections 1.359 and 1.360 do not prevent the proof of official records or of entry or lack of entry therein by any method authorized by any applicable statute or by the rules of evidence at common law.

§ 1.362 Production of statements.

After a witness is called and has given direct testimony in a hearing, and before he is excused, any party may move for the production of any statement of such witness, or part thereof, pertaining to his direct testimony, in possession of the party calling the witness, if such statement has been reduced to writing and signed or otherwise approved or adopted by the witness. Such motion shall be directed to the presiding officer. If the party declines to furnish the statement, the testimony of the witness pertaining to the requested statement shall be stricken.

[33 FR 466, Jan. 12, 1968]

§ 1.363 Introduction of statistical data.

(a) All statistical studies, offered in evidence in common carrier hearing proceedings, including but not limited to sample surveys, econometric analyses, and experiments, and those parts of other studies involving statistical methodology shall be described in a summary statement, with supplementary details added in appendices so as to give a comprehensive delineation of the assumptions made, the study plan utilized and the procedures undertaken. In the case of sample surveys, there shall be a clear description of the survey design, including the definition of the universe under study, the sampling frame, and the sampling units; an explanation of the method of selecting the sample and the characteristics measured or counted. In the case of econometric investigations, the econometric model shall be completely described and the reasons given for each

§ 1.364

assumption and statistical specification. The effects on the final results of changes in the assumptions should be made clear. When alternative models and variables have been employed, a record shall be kept of these alternative studies, so as to be available upon request. In the case of experimental analyses, a clear and complete description of the experimental design shall be set forth, including a specification of the controlled conditions and how the controls were realized. In addition, the methods of making observations and the adjustments, if any, to observed data shall be described. In the case of every kind of statistical study, the following items shall be set forth clearly: The formulas used for statistical estimates, standard errors and test statistics, the description of statistical tests, plus all related computations, computer programs and final results. Summary descriptions of input data shall be submitted. Upon request, the actual input data shall be made available.

(b) In the case of all studies and analyses offered in evidence in common carrier hearing proceedings, other than the kinds described in paragraph (a) of this section, there shall be a clear statement of the study plan, all relevant assumptions and a description of the techniques of data collection, estimation and/or testing. In addition, there shall be a clear statement of the facts and judgments upon which conclusions are based and a statement of the relative weights given to the various factors in arriving at each conclusion, together with an indication of the alternative courses of action considered. Lists of input data shall be made available upon request.

[35 FR 16254, Oct. 16, 1970]

§ 1.364 Testimony by speakerphone.

(a) If all parties to the proceeding consent and the presiding officer approves, the testimony of a witness may be taken by speakerphone.

(b) Documents used by the witness shall be made available to counsel by the party calling the witness in advance of the speakerphone testimony. The taking of testimony by speakerphone shall be subject to such

47 CFR Ch. I (10–1–97 Edition)

other ground rules as the parties may agree upon.

[43 FR 33251, July 31, 1978]

Subpart C—Rulemaking Proceedings

AUTHORITY: 5 U.S.C. 553.

SOURCE: 28 FR 12432, Nov. 22, 1963, unless otherwise noted.

GENERAL

§ 1.399 Scope.

This subpart shall be applicable to notice and comment rulemakings proceedings conducted under 5 U.S.C. 553, and shall have no application to formal rulemaking (or rate making) proceedings unless the Commission directs that it shall govern the conduct of a particular proceeding.

[42 FR 25735, May 19, 1977]

§ 1.400 Definitions.

As used in this subpart, the term *party* refers to any person who participates in a proceeding by the timely filing of a petition for rule making, comments on a notice of proposed rule making, a petition for reconsideration, or responsive pleadings in the manner prescribed by this subpart. The term does not include those who submit letters, telegrams or other informal materials.

[41 FR 1287, Jan. 7, 1976]

PETITIONS AND RELATED PLEADINGS

§ 1.401 Petitions for rulemaking.

(a) Any interested person may petition for the issuance, amendment or repeal of a rule or regulation.

(b) The petition for rule making shall conform to the requirements of §§ 1.49, 1.52 and 1.419(b) (or § 1.420(e), if applicable), and shall be submitted or addressed to the Secretary, Federal Communications Commission, Washington, DC 20554.

(c) The petition shall set forth the text or substance of the proposed rule, amendment, or rule to be repealed, together with all facts, views, arguments and data deemed to support the action requested, and shall indicate how the interests of petitioner will be affected.

Federal Communications Commission

§1.411

(d) Petitions for amendment of the FM Table of Assignments (§73.202 of this chapter) or the Television Table of Assignments (§73.606) shall be served by petitioner on any Commission licensee or permittee whose channel assignment would be changed by grant of the petition. The petition shall be accompanied by a certificate of service on such licensees or permittees. A draft Notice of Proposed Rule Making may be submitted with a petition for amendment of the FM or Television Table of Assignments.

(e) Petitions which are moot, premature, repetitive, frivolous, or which plainly do not warrant consideration by the Commission may be denied or dismissed without prejudice to the petitioner.

[28 FR 12432, Nov. 22, 1963, as amended at 28 FR 14503, Dec. 31, 1963; 40 FR 53391, Nov. 18, 1975; 45 FR 42621, June 25, 1980]

§1.403 Notice and availability.

All petitions for rule making (other than petitions to amend the FM, Television, and Air-Ground Tables of Assignments) meeting the requirements of §1.401 will be given a file number and, promptly thereafter, a “Public Notice” will be issued (by means of a Commission release entitled “Petitions for Rule Making Filed”) as to the petition, file number, nature of the proposal, and date of filing. Petitions for rule making are available at the Commission’s Dockets Reference Center (1919 M Street NW., Room 239, Washington, DC).

[60 FR 13637, Mar. 14, 1995]

§1.405 Responses to petitions; replies.

Except for petitions to amend the FM Television or Air-Ground Tables of Assignments:

(a) Any interested person may file a statement in support of or in opposition to a petition for rule making prior to Commission action on the petition but not later than 30 days after “Public Notice”, as provided for in §1.403, is given of the filing of such a petition. Such a statement shall be accompanied by proof of service upon the petitioner on or prior to the date of filing in conformity with §1.47 and shall conform in

other aspects with the requirements of §§1.49, 1.52, and 1.419(b).

(b) Any interested person may file a reply to statements in support of or in opposition to a petition for rule making prior to Commission action on the petition but not later than 15 days after the filing of such a statement. Such a reply shall be accompanied by proof of service upon the party or parties filing the statement or statements to which the reply is directed on or prior to the date of filing in conformity with §1.47 and shall conform in other aspects with the requirements of §§1.49, 1.52, and 1.419(b).

(c) No additional pleadings may be filed unless specifically requested by the Commission or authorized by it.

(d) The Commission may act on a petition for rule making at any time after the deadline for the filing of replies to statements in support of or in opposition to the petition. Statements in support of or in opposition to a petition for rule making, and replies thereto, shall not be filed after Commission action.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[28 FR 12413, Nov. 22, 1963, as amended at 28 FR 14503, Dec. 31, 1963; 45 FR 42621, June 25, 1980; 46 FR 60404, Dec. 9, 1981]

§1.407 Action on petitions.

If the Commission determines that the petition discloses sufficient reasons in support of the action requested to justify the institution of a rulemaking proceeding, and notice and public procedure thereon are required or deemed desirable by the Commission, an appropriate notice of proposed rule making will be issued. In those cases where notice and public procedure thereon are not required, the Commission may issue a final order amending the rules. In all other cases the petition for rule making will be denied and the petitioner will be notified of the Commission’s action with the grounds therefor.

RULEMAKING PROCEEDINGS

§1.411 Commencement of rulemaking proceedings.

Rulemaking proceedings are commenced by the Commission, either on

§ 1.412

it own motion or on the basis of a petition for rulemaking. See §§ 1.401–1.407.

§ 1.412 Notice of proposed rulemaking.

(a) Except as provided in paragraphs (b) and (c) of this section, prior notice of proposed rulemaking will be given.

(1) Notice is ordinarily given by publication of a “Notice of Proposed Rule Making” in the FEDERAL REGISTER. A summary of the full decision adopted by the Commission constitutes a “Notice of Proposed Rulemaking” for purposes of FEDERAL REGISTER publication.

(2) If all persons subject to the proposed rules are named, the proposal may (in lieu of publication) be personally served upon those persons.

(3) If all persons subject to the proposed rules are named and have actual notice of the proposal as a matter of law, further prior notice of proposed rulemaking is not required.

(b) Rule changes (including adoption, amendment, or repeal of a rule or rules) relating to the following matters will ordinarily be adopted without prior notice:

(1) Any military, naval, or foreign affairs function of the United States.

(2) Any matter relating to Commission management or personnel or to public property, loans, grants, benefits, or contracts.

(3) Interpretative rules.

(4) General statements of policy.

(5) Rules of Commission organization, procedure, or practice.

(c) Rule changes may in addition be adopted without prior notice in any situation in which the Commission for good cause finds that notice and public procedure are impracticable, unnecessary, or contrary to the public interest. The finding of good cause and a statement of the basis for that finding are in such situations published with the rule changes.

(d) In addition to the notice provisions of paragraph (a) of this section, the Commission, before prescribing any requirements as to accounts, records, or memoranda to be kept by carriers, will notify the appropriate State agencies having jurisdiction over any car-

47 CFR Ch. I (10–1–97 Edition)

rier involved of the proposed requirements.

[28 FR 12432, Nov. 22, 1963, as amended at 51 FR 7445, Mar. 4, 1986]

§ 1.413 Content of notice.

A notice of the proposed issuance, amendment, or repeal of a rule will include the following:

(a) A statement of the time, nature and place of any public rulemaking proceeding to be held.

(b) Reference to the authority under which the issuance, amendment or repeal of a rule is proposed.

(c) Either the terms or substance of the proposed rule or a description of the subjects and issues involved.

(d) The docket number assigned to the proceeding.

(e) A statement of the time for filing comments and replies thereto.

§ 1.415 Comments and replies.

(a) After notice of proposed rulemaking is issued, the Commission will afford interested persons an opportunity to participate in the rulemaking proceeding through submission of written data, views, or arguments, with or without opportunity to present the same orally in any manner.

(b) A reasonable time will be provided for submission of comments in support of or in opposition to proposed rules, and the time provided will be specified in the notice of proposed rulemaking.

(c) A reasonable time will be provided for filing comments in reply to the original comments, and the time provided will be specified in the notice of proposed rulemaking.

(d) No additional comments may be filed unless specifically requested or authorized by the Commission.

NOTE: In some (but not all) rulemaking proceedings, interested persons may also communicate with the Commission and its staff on an *ex parte* basis, provided certain procedures are followed. See §§ 1.420 and 1.1200 *et seq.* See also ____ FCC 2d ____ (1980) (i.e., this order).

(e) For time limits for filing motions for extension of time for filing responses to petitions for rulemaking, replies to such responses, comments filed

Federal Communications Commission

§1.420

in response to notices of proposed rulemaking, replies to such comments, see §1.46(b).

[28 FR 12432, Nov. 22, 1963, as amended at 42 FR 28888, June 6, 1977; 45 FR 45591, July 7, 1980; 52 FR 37460, Oct. 7, 1987]

§1.419 Form of comments and replies; number of copies.

(a) Comments, replies, and other documents filed in a rulemaking proceeding shall conform to the requirements of §1.49.

(b) An original and 4 copies of all comments, briefs and other documents filed in a rulemaking proceeding shall be furnished the Commission. The distribution of such copies shall be as follows:

Secretary (original and 1)	2
Bureau	2
Information office	1
Total	5

Participants filing the required 5 copies who also wish each Commissioner to have a personal copy of the comments may file an additional 5 copies. The distribution of such copies shall be as follows:

Commissioners	5
Secretary	2
Bureau	2
Information office	1
Total	10

However, members of the general public who wish to express their interest by participating informally in a rulemaking proceeding may do so by submitting an original and one copy of their comments, without regard to form, provided only that the Docket Number is specified in the heading. Informal comments filed after close of the reply comment period, or, if on reconsideration, the reconsideration reply comment period, should be labeled "ex parte" pursuant to section 1.1206(a) of this chapter. Letters submitted to Commissioners or Commission staff will be treated in the same way as informal comments, as set forth above. Also such informal participants who wish the responsible members of the staff and the Commissioners to have personal copies may file an addi-

tional 7 copies. The distribution of such copies shall be as follows:

Commissioners	5
Secretary	2
Bureau	2
Total	9

(c) Any person desiring to file identical documents in more than one docketed rulemaking proceeding shall furnish the Commission two additional copies of any such document for each additional docket. This requirement does not apply if the proceedings have been consolidated.

[28 FR 12432, Nov. 22, 1963, as amended at 41 FR 50399, Nov. 16, 1976; 50 FR 26567, June 27, 1985; 54 FR 29037, July 11, 1989]

§1.420 Additional procedures in proceedings for amendment of the FM or TV Tables of Allotments.

(a) Comments filed in proceedings for amendment of the FM Table of Allotments (§73.202 of this chapter) or the Television Table of Allotments (§73.606 of this chapter) which are initiated on a petition for rule making shall be served on petitioner by the person who files the comments.

(b) Reply comments filed in proceedings for amendment of the FM or Television Tables of Allotments shall be served on the person(s) who filed the comments to which the reply is directed.

(c) Such comments and reply comments shall be accompanied by a certificate of service.

(d) Counterproposals shall be advanced in initial comments only and will not be considered if they are advanced in reply comments.

(e) An original and 4 copies of all petitions for rulemaking, comments, reply comments, and other pleadings shall be filed with the Commission.

(f) Petitions for reconsideration and responsive pleadings shall be served on parties to the proceeding and on any licensee or permittee whose authorization may be modified to specify operation on a different channel, and shall be accompanied by a certificate of service.

(g) The Commission may modify the license or permit of an FM station to another class of channel or of a UHF

§ 1.421

47 CFR Ch. I (10–1–97 Edition)

TV station to a VHF channel in the same community in the course of the rule making proceeding to amend § 73.202(b), § 73.504(a) or § 73.606(b) if any of the following conditions are met:

(1) There is no other timely filed expression of interest, or

(2) If another interest in the proposed channel is timely filed an additional equivalent class of channel is also allotted, assigned or available for application, or

(3) With respect to FM, the modification of license or permit would occur on a mutually exclusive higher class adjacent or co-channel.

NOTE 1: In certain situations, a licensee or permittee may seek an adjacent, intermediate frequency or co-channel upgrade by application. See § 73.203(b) of this chapter.

(h) Where licensees (or permittees) of television broadcast stations jointly petition to amend § 73.606(b) and to exchange channels, and where one of the licensees (or permittees) operates on a commercial channel while the other operates on a reserved noncommercial educational channel within the same band, and the stations serve substantially the same market, then the Commission may amend § 73.606(b) and modify the licenses (or permits) of the petitioners to specify operation on the appropriate channels upon a finding that such action will promote the public interest, convenience, and necessity.

NOTE 2: Licensees and permittees operating Class A FM stations who seek to upgrade their facilities to Class B1, B, C3, C2, C1, or C on Channel 221, and whose proposed 1 mV/m signal contours would overlap the Grade B contour of a television station operating on Channel 6 must meet a particularly heavy burden by demonstrating that grants of their upgrade requests are in the public interest. In this regard, the Commission will examine the record in rule making proceedings to determine the availability of existing and potential non-commercial education service.

(i) In the course of the rule making proceeding to amend § 73.202(b) or § 73.606(b), the Commission may modify the license or permit of an FM or television broadcast station to specify a new community of license where the amended allotment would be mutually exclusive with the licensee's or permittee's present assignment.

(j) Whenever an expression of interest in applying for, constructing, and operating a station has been filed in a proceeding to amend the FM or TV Table of Allotments, and the filing party seeks to dismiss or withdraw the expression of interest, either unilaterally or in exchange for financial consideration, that party must file with the Commission a request for approval of the dismissal or withdrawal, a copy of any written agreement related to the dismissal or withdrawal, and an affidavit setting forth:

(1) A certification that neither the party withdrawing its interest nor its principals has received or will receive any money or other consideration in excess of legitimate and prudent expenses in exchange for the dismissal or withdrawal of the expression of interest;

(2) The exact nature and amount of any consideration received or promised;

(3) An itemized accounting of the expenses for which it seeks reimbursement; and

(4) The terms of any oral agreement related to the dismissal or withdrawal of the expression of interest.

(5) In addition, within 5 days of a party's request for approval, each remaining party to any written or oral agreement must submit an affidavit setting forth:

(i) A certification that neither it nor its principals has paid or will pay money or other consideration in excess of the legitimate and prudent expenses of the party withdrawing its expression of interest; and

(ii) The terms of any oral agreement relating to the dismissal or withdrawal of the expression of interest.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[39 FR 44022, Dec. 20, 1974, as amended at 40 FR 53391, Nov. 18, 1975; 41 FR 1287, Jan. 7, 1976; 51 FR 15629, Apr. 25, 1986; 51 FR 20291, June 4, 1986; 52 FR 8260, Mar. 17, 1987; 52 FR 25866, July 9, 1987; 54 FR 16366, Apr. 24, 1989; 54 FR 26201, June 22, 1989; 55 FR 28914, July 16, 1990; 58 FR 38535, July 19, 1993; 59 FR 59503, Nov. 17, 1994; 61 FR 43472, Aug. 23, 1996]

§ 1.421 Further notice of rulemaking.

In any rulemaking proceeding where the Commission deems it warranted, a

Federal Communications Commission

§ 1.429

further notice of proposed rulemaking will be issued with opportunity for parties of record and other interested persons to submit comments in conformity with §§ 1.415 and 1.419.

§ 1.423 Oral argument and other proceedings.

In any rulemaking where the Commission determines that an oral argument, hearing or any other type of proceeding is warranted, notice of the time, place and nature of such proceeding will be published in the FEDERAL REGISTER.

[58 FR 66300, Dec. 20, 1993]

§ 1.425 Commission action.

The Commission will consider all relevant comments and material of record before taking final action in a rulemaking proceeding and will issue a decision incorporating its finding and a brief statement of the reasons therefor.

§ 1.427 Effective date of rules.

(a) Any rule issued by the Commission will be made effective not less than 30 days from the time it is published in the FEDERAL REGISTER except as otherwise specified in paragraphs (b) and (c) of this section.

(b) For good cause found and published with the rule, any rule issued by the Commission may be made effective within less than 30 days from the time it is published in the FEDERAL REGISTER. Rules involving any military, naval or foreign affairs function of the United States; matters relating to agency management or personnel, public property, loans, grants, benefits or contracts; rules granting or recognizing exemption or relieving restriction; rules of organization, procedure or practice; or interpretative rules; and statements of policy may be made effective without regard to the 30-day requirement.

(c) In cases of alterations by the Commission in the required manner or form of keeping accounts by carriers, notice will be served upon affected carriers not less than 6 months prior to the effective date of such alterations.

§ 1.429 Petition for reconsideration.

(a) Any interested person may petition for reconsideration of a final action in a proceeding conducted under this subpart (see §§ 1.407 and 1.425). Where the action was taken by the Commission, the petition will be acted on by the Commission. Where action was taken by a staff official under delegated authority, the petition may be acted on by the staff official or referred to the Commission for action.

NOTE: The staff has been authorized to act on rulemaking proceedings described in § 1.420 and is authorized to make editorial changes in the rules (see § 0.231(d)).

(b) A petition for reconsideration which relies on facts which have not previously been presented to the Commission will be granted only under the following circumstances:

(1) The facts relied on relate to events which have occurred or circumstances which have changed since the last opportunity to present them to the Commission;

(2) The facts relied on were unknown to petitioner until after his last opportunity to present them to the Commission, and he could not through the exercise of ordinary diligence have learned of the facts in question prior to such opportunity; or

(3) The Commission determines that consideration of the facts relied on is required in the public interest.

(c) The petition for reconsideration shall state with particularity the respects in which petitioner believes the action taken should be changed.

(d) The petition for reconsideration and any supplement thereto shall be filed within 30 days from the date of public notice of such action, as that date is defined in § 1.4(b) of these rules. No supplement to a petition for reconsideration filed after expiration of the 30 day period will be considered, except upon leave granted pursuant to a separate pleading stating the grounds for acceptance of the supplement. The petition for reconsideration shall not exceed 25 double-spaced typewritten pages.

(e) Except as provided in § 1.420(f), petitions for reconsideration need not be served on parties to the proceeding. (However, where the number of parties

§ 1.430

is relatively small, the Commission encourages the service of petitions for reconsideration and other pleadings, and agreements among parties to exchange copies of pleadings.) When a petition for reconsideration is timely filed in proper form, public notice of its filing is published in the FEDERAL REGISTER. The time for filing oppositions to the petition runs from the date of public notice. See § 1.4(b).

(f) Oppositions to a petition for reconsideration shall be filed within 15 days after the date of public notice of the petition's filing and need be served only on the person who filed the petition. See § 1.4(b). Oppositions shall not exceed 25 double-spaced typewritten pages.

(g) Replies to an opposition shall be filed within 10 days after the time for filing oppositions has expired and need be served only on the person who filed the opposition. Replies shall not exceed 10 double-spaced typewritten pages.

(h) Petitions for reconsideration, oppositions and replies shall conform to the requirements of §§ 1.49 and 1.52, except that they need not be verified. Except as provided in § 1.420(e), an original and 11 copies shall be submitted to the Secretary, Federal Communications Commission, Washington, DC 20554.

(i) The Commission may grant the petition for reconsideration in whole or in part or may deny the petition. Its order will contain a concise statement of the reasons for the action taken. Any order disposing of a petition for reconsideration which modifies rules adopted by the original order is, to the extent of such modification, subject to reconsideration in the same manner as the original order. Except in such circumstance, a second petition for reconsideration may be dismissed by the staff as repetitious.

(j) The filing of a petition for reconsideration is not a condition precedent to judicial review of any action taken by the Commission, except where the person seeking such review was not a party to the proceeding resulting in the action or relies on questions of fact or law upon which the Commission has been afforded no opportunity to pass. Subject to the provisions of paragraph (b) of this section, such a person may

47 CFR Ch. I (10–1–97 Edition)

qualify to seek judicial review by filing a petition for reconsideration.

(k) Without special order of the Commission, the filing of a petition for reconsideration shall not excuse any person from complying with any rule or operate in any manner to stay or postpone its enforcement. However, upon good cause shown, the Commission will stay the effective date of a rule pending a decision on a petition for reconsideration. See, however, § 1.420(f).

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[41 FR 1287, Jan. 7, 1976, as amended at 44 FR 5436, Jan. 26, 1979; 46 FR 18556, Mar. 25, 1981; 52 FR 49161, Dec. 30, 1987]

INQUIRIES

§ 1.430 Proceedings on a notice of inquiry.

The provisions of this subpart also govern proceedings commenced by issuing a "Notice of Inquiry," except that such proceedings do not result in the adoption of rules, and Notices of Inquiry are not required to be published in the FEDERAL REGISTER.

[51 FR 7445, Mar. 4, 1986]

Subpart D—Broadcast Applications and Proceedings

SOURCE: 44 FR 38483, July 2, 1979, unless otherwise noted.

§ 1.502 Emergency Broadcast Authorizations.

See § 73.913.

GENERAL FILING REQUIREMENTS

§ 1.511 Applications required.

See § 73.3511.

§ 1.512 Where to file; number of copies.

See § 73.3512.

§ 1.513 Who may sign applications.

See § 73.3513.

§ 1.514 Content of applications.

See § 73.3514.

§ 1.516 Specification of facilities.

See § 73.3516.

Federal Communications Commission

§ 1.566

§ 1.517 Contingent applications.

See § 73.3517.

§ 1.518 Inconsistent or conflicting applications.

See § 73.3518.

§ 1.519 Repetitious applications.

See § 73.3519.

§ 1.520 Multiple applications.

See § 73.3520.

§ 1.522 Amendment of applications.

See § 73.3522.

§ 1.525 Agreements between parties for amendment or dismissal of, or failure to prosecute, broadcast applications.

See § 73.3525.

§ 1.526 Records to be maintained locally for public inspection by commercial applicants, permittees and licensees.

See § 73.3526.

§ 1.527 Records to be maintained locally for public inspection by non-commercial educational applicants, permittees and licensees.

See § 73.3527.

§ 1.531 Formal and informal applications.

See § 73.3511.

§ 1.533 Application forms for authority to construct a new station or make changes in an existing station.

See § 73.3533.

§ 1.534 Application for extension of construction permit or for construction permit to replace expired construction permit.

See § 73.3534.

§ 1.536 Application for license to cover construction permit.

See § 73.3536.

§ 1.538 Application for modification of license.

See § 73.3538.

§ 1.539 Application for renewal of license.

See § 73.3539.

§ 1.540 Application for voluntary assignment or transfer of control.

See § 73.3540.

§ 1.541 Application for involuntary assignment of license or transfer of control.

See § 73.3541.

§ 1.542 Application for temporary authorization.

See § 73.3542.

§ 1.543 Application for renewal or modification of special service authorization.

See § 73.3543.

§ 1.544 Application for broadcast station to conduct field strength measurements and for experimental operation.

See §§ 73.157 and 73.1510.

§ 1.545 Application for permit to deliver programs to foreign countries.

See § 73.3545.

§ 1.546 Application to determine operating power by direct measurement of antenna power.

See § 73.45.

§ 1.549 Requests for extension of authority to operate without required monitors, indicating instruments, and EBS Attention Signal devices.

See § 73.3549.

§ 1.550 Requests for new or modified call sign assignments.

See § 73.3550.

§ 1.561 Staff consideration of applications which receive action by the Commission.

See § 73.3561.

§ 1.562 Staff consideration of applications which do not require action by the Commission.

See § 73.3562.

§ 1.564 Acceptance of applications.

See § 73.3564.

§ 1.566 Defective applications.

See § 73.3566.

§ 1.568

§ 1.568 Dismissal of applications.

See § 73.3568.

§ 1.570 AM broadcast station applications involving other North American countries.

See § 73.3570.

§ 1.571 Processing AM broadcast station applications.

See § 73.3571.

§ 1.572 Processing TV broadcast and translator station applications.

See § 73.3572.

§ 1.573 Processing FM broadcast and translator station applications.

See § 73.3573.

§ 1.574 Processing of international broadcast station applications.

See § 73.3574.

§ 1.578 Amendments to applications for renewal, assignment or transfer of control.

See § 73.3578.

§ 1.580 Local public notice of filing of broadcast applications.

See § 73.3580.

§ 1.584 Petitions to deny.

See § 73.3584.

§ 1.587 Procedure for filing informal applications.

See § 73.3587.

§ 1.591 Grants without hearing.

See § 73.3591.

§ 1.592 Conditional grant.

See § 73.3592.

§ 1.593 Designation for hearing.

See § 73.3593.

§ 1.594 Local public notice of designation for hearing.

See § 73.3594.

§ 1.597 Procedures on transfer and assignment applications.

See § 73.3597.

§ 1.598 Period of construction.

See § 73.3598.

47 CFR Ch. I (10–1–97 Edition)

§ 1.599 Forfeiture of construction permit.

See § 73.3599.

§ 1.601 Simultaneous modification and renewal of license.

See § 73.3601.

§ 1.603 Special waiver procedure relative to applications.

See § 73.3603.

§ 1.605 Retention of applications in hearing status after designation for hearing.

See § 73.3605.

§ 1.612 Annual employment report.

See § 73.3612.

§ 1.613 Filing of contracts.

See § 73.3613.

§ 1.615 Ownership reports.

See § 73.3615.

Subpart E—Complaints, Applications, Tariffs, and Reports Involving Common Carriers

SOURCE: 28 FR 12450, Nov. 22, 1963, unless otherwise noted.

GENERAL

§ 1.701 Show cause orders.

(a) The Commission may commence any proceeding within its jurisdiction against any common carrier by serving upon the carrier an order to show cause. The order shall contain a statement of the particulars and matters concerning which the Commission is inquiring and the reasons for such action, and will call upon the carrier to appear before the Commission at a place and time therein stated and give evidence upon the matters specified in the order.

(b) Any carrier upon whom an order has been served under this section shall file its answer within the time specified in the order. Such answer shall specifically and completely respond to all allegations and matters contained in the show cause order.

(c) All papers filed by a carrier in a proceeding under this section shall

Federal Communications Commission

§1.718

conform with the specifications of §§1.49 and 1.50 and the subscription and verification requirements of §1.52.

[28 FR 12450, Nov. 22, 1963, as amended at 36 FR 7423, Apr. 20, 1971]

§1.703 Appearances.

(a) *Hearings.* Except as otherwise required by §1.221 regarding application proceedings, by §1.91 regarding proceedings instituted under section 312 of the Communications Act of 1934, as amended, or by Commission order in any proceeding, no written statement indicating intent to appear need be filed in advance of actual appearance at any hearing by any person or his attorney.

(b) *Oral arguments.* Within 5 days after release of an order designating an initial decision for oral argument or within such other time as may be specified in the order, any party who wishes to participate in the oral argument shall file a written statement indicating that he will appear and participate. Within such time as may be specified in an order designating any other matter for oral argument, any person wishing to participate in the The Commission will advise him whether he may participate. (See §1.277 for penalties for failure to file appearance statements in proceedings involving oral arguments on initial decisions.)

(c) *Commission counsel.* The requirement of paragraph (b) of this section shall not apply to counsel representing the Commission or the Chief of the Common Carrier Bureau.

COMPLAINTS

§1.711 Formal or informal complaints.

Complaints filed against carriers under section 208 of the Communications Act may be either formal or informal.

INFORMAL COMPLAINTS

§1.716 Form.

An informal complaint shall be in writing and should contain: (a) The name, address and telephone number of the complaint, (b) the name of the carrier against which the complaint is made, (c) a complete statement of the facts tending to show that such carrier

did or omitted to do anything in contravention of the Communications Act, and (d) the specific relief of satisfaction sought.

[51 FR 16039, Apr. 30, 1986]

§1.717 Procedure.

The Commission will forward informal complaints to the appropriate carrier for investigation. The carrier will, within such time as may be prescribed, advise the Commission in writing, with a copy to the complainant, of its satisfaction of the complaint or of its refusal or inability to do so. Where there are clear indications from the carrier's report or from other communications with the parties that the complaint has been satisfied, the Commission may, in its discretion, consider a complaint proceeding to be closed, without response to the complainant. In all other cases, the Commission will contact the complainant regarding its review and disposition of the matters raised. If the complainant is not satisfied by the carrier's response and the Commission's disposition, it may file a formal complaint in accordance with §1.721 of this part.

[51 FR 16039, Apr. 30, 1986]

§1.718 Unsatisfied informal complaints; formal complaints relating back to the filing dates of informal complaints.

When an informal complaint has not been satisfied pursuant to §1.717, the complainant may file a formal complaint with this Commission in the form specified in §1.721. Such filing will be deemed to relate back to the filing date of the informal complaint: *Provided*, That the formal complaint: (a) Is filed within 6 months from the date of the carrier's report, (b) makes reference to the date of the informal complaint, and (c) is based on the same cause of action as the informal complaint. If no formal complaint is filed within the 6-month period, the complainant will be deemed to have abandoned the unsatisfied informal complaint.

[51 FR 16040, Apr. 30, 1986]

§ 1.720

47 CFR Ch. I (10–1–97 Edition)

FORMAL COMPLAINTS

§ 1.720 General pleading requirements.

Formal complaint proceedings are generally resolved on a written record consisting of a complaint, answer and reply but may also include other written submissions such as briefs and written interrogatories. All written submissions, both substantive and procedural, must conform to the following standards:

(a) Pleadings must be clear, concise, and explicit. All matters concerning a claim, defense or requested remedy, including damages, should be pleaded fully and with specificity.

(b) Pleadings must contain facts which, if true, are sufficient to constitute a violation of the Act or Commission order or regulation, or a defense to such alleged violation.

(c) Facts must be supported by relevant documentation or affidavit.

(d) Legal arguments must be supported by appropriate judicial, Commission, or statutory authority.

(e) Opposing authorities must be distinguished.

(f) Copies must be provided of all non-Commission authorities relied upon which are not routinely available in national reporting systems, such as unpublished decisions or slip opinions of courts or administrative agencies.

(g) Parties are responsible for the continuing accuracy and completeness of all information and supporting authority furnished in a pending complaint proceeding. Information submitted, as well as relevant legal authorities, must be current and updated as necessary and in a timely manner at any time before a decision is rendered on the merits of the complaint.

(h) Specific reference must be made to any tariff provision relied on in support of a claim or defense. Parties are encouraged to provide copies of the tariff or relevant portions thereof.

(i) All statements purporting to summarize or explain Commission orders or policies must cite, in standard legal form, the Commission ruling upon which such statements are based.

[53 FR 11852, Apr. 11, 1988, as amended at 58 FR 25572, Apr. 27, 1993]

§ 1.721 Format and content.

(a) A formal complaint shall contain:

(1) The name of each complainant and defendant;

(2) The occupation, address and telephone number of each complainant and, to the extent known, each defendant;

(3) The name, address, and telephone number of complainant's attorney, if represented by counsel;

(4) Citation to the section of the Communications Act and/or order and/or regulation of the Commission alleged to have been violated.

(5) A complete statement of facts which, if proven true, would constitute such a violation;

(6) Complete identification or description, including relevant time period, of the communications, transmissions, services, or other carrier conduct complained of and nature of the injury sustained;

(7) The relief sought, including recovery of damages and the amount of damages claimed, if known; and

(8) Whether suit has been filed in any court or other government agency on the basis of the same cause of action.

(b) The following format may be used in cases to which it is applicable, with such modifications as the circumstances may render necessary:

BEFORE THE FEDERAL COMMUNICATIONS
COMMISSION, WASHINGTON, DC 20554

In the matter of

Complainant,
v.

Defendant.

File No. (To be inserted by the Common Carrier Bureau)

Complaint

To: The Commission.

The complainant (here insert full name of each complainant and, if a corporation, the corporate title of such complainant) shows that:

1. (Here state occupation, post office address, and telephone number of each complainant).

2. (Here insert the name, occupation and, to the extent known, address and telephone number of defendants).

3. (Here insert fully and clearly the specific act or thing complained of, together with

Federal Communications Commission

§ 1.724

such facts as are necessary to give a full understanding of the matter, including relevant legal and documentary support).

Wherefore, complainant asks (here state specifically the relief desired).

(Date)

(Name of each complainant)

(Name, address, and telephone number of attorney, if any)

[53 FR 11853, Apr. 11, 1988]

§ 1.722 Damages.

(a) In case recovery of damages is sought, the complaint shall contain appropriate allegations showing such evidence that will identify, with reasonable certainty, the amount of damages for which recovery is sought.

(b) Damages will not be awarded upon a complaint unless specifically requested. Damages may be awarded, however, upon a supplemental complaint based upon a finding of the Commission in the original proceeding. *Provided that:*

(1) If recovery of damages or overcharges is first sought by supplemental complaint, such supplemental complaint must be filed within, and recovery is limited to, the statutory periods of limitations contained in section 415 of the Communications Act;

(2) A claim for recovery of damages contained in a supplemental complaint based on a finding of the Commission in the original proceeding which meets the requirements of paragraph (a) of this section shall relate back to the filing date of the original formal complaint if:

(i) The original complaint clearly and unequivocally requests the recovery of damages (even if the precise amount and other specific details are unknown), and

(ii) Such supplemental complaint is filed no later than 60 days after public notice (as defined in § 1.4(b) of the rules) of a decision on the merits of the original complaint.

[53 FR 11853, Apr. 11, 1988]

§ 1.723 Joinder of complainants and causes of action.

(a) Two or more complainants may join in one complaint if their respective causes of action are against the same defendant and concern substantially the same facts and alleged violation of the Communications Act.

(b) Two or more grounds of complaint involving the same principle, subject, or statement of facts may be included in one complaint, but should be separately stated and numbered.

[53 FR 11853, Apr. 11, 1988]

§ 1.724 Answers.

(a) Any carrier upon which a copy of a formal complaint, supplemental complaint, amended complaint, or cross complaint is served under this subpart shall answer within 30 days of service of the pleading to which the answer is made, unless otherwise directed by the Commission.

(b) The answer shall advise the parties and the Commission fully and completely of the nature of any defense, and shall respond specifically to all material allegations of the complaint. Collateral or immaterial issues shall be avoided in answers and every effort should be made to narrow the issues. Any party failing to file and serve an answer within the time and in the manner prescribed by these rules may be deemed in default and an order may be entered against defendant in accordance with the allegations contained in the complaint.

(c) A party shall state concisely its defenses to each claim asserted and shall admit or deny the averments on which the adverse party relies. If the party is without knowledge or information sufficient to form a belief as to the truth of an averment, the party shall so state and this has the effect of a denial. When a pleader intends in good faith to deny only part of an averment, the pleader shall specify so much of it as is true and shall deny only the remainder. The pleader may make its denials as specific denials of designated averments or paragraphs, or may generally deny all the averments except such designated averments or paragraphs as the pleader expressly admits. When the pleader intends to controvert

§1.725

all averments, the pleader may do so by general denial.

(d) Averments in a pleading to which a responsive pleading is required, other than those as to the amount of damages, are deemed to be admitted when not denied in this responsive pleading.

(e) Affirmative defenses to allegations contained in the complaint shall be specifically captioned as such and presented separately from any denials made in accordance with paragraph (c) of this section.

[53 FR 11853, Apr. 11, 1988, as amended at 58 FR 25572, Apr. 27, 1993]

§1.725 Cross complaints.

A cross complaint, seeking any relief within the jurisdiction of the Commission against any carrier which is a party (complainant or defendant) to the proceeding, may be filed by a defendant with its answer. For the purpose of this subpart, the term *cross complaint* shall include counterclaim.

[53 FR 11854, Apr. 11, 1988]

§1.726 Replies.

Within 10 days after service of an answer containing affirmative defenses presented in accordance with §1.724(e), a complainant may file and serve a reply, which shall be responsive to only those allegations contained in affirmative defenses.

[58 FR 25572, Apr. 27, 1993]

§1.727 Motions.

(a) A request to the Commission for an order shall be by written motion, stating with particularity the grounds and authority therefor, and setting forth the relief or order sought.

(b) A motion that the allegations in the complaint be made more definite and certain shall be filed within 15 days after service of a complaint by the Commission.

(c) Where the matter involved in the motion is one of procedure or discovery, the moving party shall provide a proposed order for adoption, which appropriately incorporates the basis therefor.

(d) A party opposing any motion concerning procedure or discovery shall also provide a proposed order for adop-

47 CFR Ch. I (10–1–97 Edition)

tion, which appropriately incorporates the basis therefor.

(e) Oppositions to motions may be filed within ten days after the motion is filed. Oppositions shall be limited to the specific issues and allegations contained in the motion; when a motion is incorporated in an answer to a complaint, an opposition to the motion shall not address any issues presented in the answer that are not also specifically raised in the motion.

(f) No reply may be filed to an opposition to a motion.

[53 FR 11854, Apr. 11, 1988, as amended at 58 FR 25572, Apr. 27, 1993]

§1.728 Formal complaints not stating a cause of action; defective pleadings.

(a) Any document purporting to be a formal complaint which does not state a cause of action under the Communications Act will be dismissed. In such case, any amendment or supplement to such document will be considered a new filing which must be made within the statutory periods of limitations of actions contained in section 415 of the Communications Act.

(b) Any other pleading filed in a formal complaint proceeding not in conformity with the requirements of the applicable rules in this part may be deemed defective. In such case the Commission may strike the pleading or request that specified defects be corrected and that proper pleadings be filed with the Commission and served on all parties within a prescribed time as a condition to being made a part of the record in the proceeding.

[53 FR 11854, Apr. 11, 1988]

§1.729 Interrogatories to parties.

(a) During the time period beginning with service of the complaint and ending 30 days after the date an answer is due to be filed, any party may serve any other party written interrogatories, to be answered in writing by the party served or, if the party served is a public or private corporation or partnership or association, by any officer or agent who shall furnish such information as is available to the party.

Federal Communications Commission

§1.730

All interrogatories served on an opposing party shall be filed with the Commission at the time of service. Parties shall propound no more than 30 single interrogatories without prior Commission approval. Subparts of an interrogatory will be counted as separate interrogatories for purposes of compliance with this limit. This procedure may be used for the discovery of any nonprivileged matter which is relevant to the pleadings. Interrogatories may not be employed for the purpose of delay, harassment or to obtain information which is beyond the scope of permissible inquiry relating to the subject matter of the pleadings.

(b) Parties on whom interrogatories are served shall respond without waiting to be ordered to do so by the Commission. Each interrogatory shall be answered separately and fully in writing under oath or affirmation, unless it is objected to, in which event the reasons for objection shall be stated in lieu of an answer. The answers shall be signed by the person making them. The party on whom the interrogatories were served shall serve a copy of the answers and objections, if any, within 30 days after service of the interrogatories, except that a defendant may serve answers or objections within 15 days after filing its answer to the complaint, whichever period is longer. On proper motion being made, the Commission may allow a shorter or longer time for the filing of answers or objections.

(c) Where the responding party has failed to respond, or has objected, to any interrogatory, the party propounding the interrogatories may, within 15 days of the date the response was due if no response is filed or the date of service of the objection, move to compel a response thereto. The motion should state with specificity the relevance of and necessity for the requested information and must also comply with the requirements of §1.727 of this part pertaining to motions generally. Alternatively, the party may request that answers to interrogatories be discussed during a status conference, pursuant to §1.733.

(d) Answers to interrogatories shall not be filed with the Commission un-

less so ordered by the Commission or its staff.

(e) The Commission may in its discretion limit the scope of permissible inquiry so that matters pertaining solely to the amount or computation of damages are not addressed until after a finding of liability has been made against the complainant. Inquiries that relate dually to liability and damages will be permitted during initial discovery conducted during the liability phase. If a bifurcated framework is implemented and a finding of liability is made, the parties shall, within 5 working days, inform the Commission whether they wish to defer damages discovery in order to enter negotiations for the purpose of settling their dispute. If the parties commence settlement negotiations, damages discovery shall not be undertaken prior to 20 days after release of the liability order.

[53 FR 11854, Apr. 11, 1988, as amended at 58 FR 25572, Apr. 27, 1993]

§1.730 Other forms of discovery.

(a) If a party believes it needs to engage in some form of discovery other than by written interrogatories under §1.729, including but not limited to the production of documents, the taking of depositions, or the propounding of additional interrogatories, the party may file a motion with the Commission requesting that such discovery be permitted. The motion should state with specificity the type of discovery requested, the information which is expected to be elicited, the relevance of such information to the resolution of the proceeding, and must also comply with the requirements of §1.727 hereof, pertaining to motions generally. Such motions will not be routinely granted except for good cause shown.

(b) The party from whom the discovery is sought may file an opposition to a motion seeking discovery within 10 days after the motion is filed. No reply is permitted.

(c) Motions seeking discovery may be filed only during the period beginning with the service of a complaint and ending 30 days after the date an answer is filed or 15 days after responses to interrogatories under §1.729 are filed, whichever period is longer, except where the movant demonstrates that

§ 1.731

47 CFR Ch. I (10–1–97 Edition)

the need for such discovery could not, even with due diligence, have been ascertained within this period.

(d) Documents produced through discovery shall not be filed with the Commission unless so ordered by the Commission or its staff.

[53 FR 11854, Apr. 11, 1988, as amended at 58 FR 25572, Apr. 27, 1993]

§ 1.731 Confidentiality of information produced through discovery.

(a) Any materials generated or provided by a party in response to discovery may be designated as proprietary by that party if the party believes in good faith that the materials fall within an exemption to disclosure contained in the Freedom of Information Act (FOIA), 5 U.S.C. 552(b)(1)–(9). Any party asserting confidentiality for such materials shall so indicate by clearly marking each page, or portion thereof, for which a proprietary designation is claimed. If a proprietary designation is challenged, the party claiming confidentiality shall have the burden of demonstrating, by a preponderance of the evidence, that the material designated as proprietary falls under the standards for nondisclosure enunciated in the FOIA.

(b) Materials marked as proprietary may be disclosed solely to the following persons, only for use in prosecuting or defending a party to the complaint action, and only to the extent necessary to assist in the prosecution or defense of the case:

(1) Counsel of record representing the parties in the complaint action and any support personnel employed by such attorneys;

(2) Officers or employees of the opposing party who are named by the opposing party as being directly involved in the prosecution or defense of the case;

(3) Consultants or expert witnesses retained by the parties;

(4) The Commission and its staff; and

(5) Court reporters and stenographers in accordance with the terms and conditions of this section.

(c) These individuals shall not disclose information designated as proprietary to any person who is not authorized under this section to receive such information, and shall not use the in-

formation in any activity or function other than the prosecution or defense in the case before the Commission. Each individual who is provided access to the information shall sign a notarized statement affirmatively stating that the individual has personally reviewed the Commission's rules and understands the limitations they impose on the signing party.

(d) No copies of materials marked proprietary may be made except copies to be used by persons designated in paragraph (b) of this section. Each party shall maintain a log recording the number of copies made of all proprietary material and the persons to whom the copies have been provided.

(e) Upon termination of a formal complaint proceeding, including all appeals and petitions, all originals and reproductions of any proprietary materials, along with the log recording persons who received copies of such materials, shall be provided to the producing party. In addition, upon final termination of the complaint proceeding, any notes or other work product derived in whole or in part from the proprietary materials of an opposing or third party shall be destroyed.

[58 FR 25573, Apr. 27, 1993]

§ 1.732 Other required written submissions.

(a) The Commission may, in its discretion, require the parties to file briefs summarizing the facts and issues presented in the pleadings and other record evidence. These briefs shall contain the findings of fact and conclusions of law which that party is urging the Commission to adopt, with specific citation to the record, and supported by relevant authority and analysis. Absent an order by the Commission that briefs be filed, the parties may voluntarily submit briefs in accordance with the provisions of paragraphs (b) through (e) of this section.

(b) In cases when discovery is not conducted, briefs shall be filed concurrently by both complainant and defendant within 90 days from the date a complaint is served. Such briefs shall be no longer than 35 pages.

Federal Communications Commission

§1.734

(c) In cases when discovery is conducted, briefs shall be filed concurrently by both complainant and defendant at such time designated by the staff, typically within 30 days after discovery is completed. Such briefs shall be no longer than 50 pages.

(d) Reply briefs may be submitted by either party within 20 days from the date initial briefs are due. Reply briefs shall be no longer than 20 pages in cases when discovery is not conducted, and 30 pages in cases when discovery is conducted.

(e) Briefs containing information which is claimed by an opposing or third party to be proprietary under §1.731 shall be submitted to the Commission in confidence pursuant to the requirements of §0.459 of this chapter and clearly marked "Not for Public Inspection." An edited version removing all proprietary data shall also be filed with the Commission for inclusion in the public file. Edited versions shall be filed within five days from the date the unedited brief is submitted, and served on opposing parties.

(f) Either on its own motion or upon proper motion by a party, the Commission may establish other deadlines or page limits for briefs.

(g) The Commission may require the parties to submit any additional information it deems appropriate for a full, fair, and expeditious resolution of the proceeding, including affidavits and exhibits.

[53 FR 11855, Apr. 11, 1988. Redesignated and amended at 58 FR 25573, Apr. 27, 1993]

§1.733 Status conference.

(a) In any complaint proceeding, the Commission may in its discretion direct the attorneys and/or the parties to appear before it for a conference to consider:

(1) Simplification or narrowing of the issues;

(2) The necessity for or desirability of amendments to the pleadings, or of additional pleadings or evidentiary submissions;

(3) Obtaining admissions of fact or stipulations between the parties as to any or all of the matters in controversy;

(4) Settlement of the matters in controversy by agreement of the parties;

(5) The necessity and extent of discovery, including objections to interrogatories or requests for production of documents;

(6) The need and schedule for filing briefs, and the date for further conferences; and

(7) Such other matters that may aid in the disposition of the complaint.

(b) While a conference normally will be scheduled after the answer has been filed, any party may request that a conference be held at any time after the complaint has been filed.

(c) During a status conference, the Commission staff may issue oral rulings pertaining to a variety of interlocutory matters relevant to the conduct of a formal complaint proceeding including, *inter alia*, procedural matters, discovery, and the submission of briefs or other evidentiary materials. These rulings will be promptly memorialized in writing and served on the parties. When such rulings require a party to undertake affirmative action not subject to deadlines established by another provision of this subpart, such action will be required within 10 days from the date of the written memorialization unless the staff designates a later deadline.

(d) Conferences will be scheduled by the Commission at such time and place as it may designate, to be conducted in person or by telephone conference call.

(e) The failure of any attorney or party, following reasonable notice, to appear at a scheduled conference will be deemed a waiver and will not preclude the Commission from conferring with those parties or counsel present.

[53 FR 11855, Apr. 11, 1988. Redesignated and amended at 58 FR 25573, Apr. 27, 1993]

§1.734 Specifications as to pleadings, briefs, and other documents; subscription.

(a) All papers filed in any formal complaint proceeding must be drawn in conformity with the requirements of §§1.49 and 1.50.

(b) All averments of claims or defenses in complaints and answers shall be made in numbered paragraphs. The contents of each paragraph shall be limited as far as practicable to a statement of a single set of circumstances. Each claim founded on a separate

§1.735

transaction or occurrence and each affirmative defense shall be separately stated to facilitate the clear presentation of the matters set forth.

(c) The original of all pleadings and other submissions filed by any party shall be signed by that party, or by the party's attorney. The signing party shall state his or her address and telephone number and the date on which the document was signed. Copies should be conformed to the original. Except when otherwise specifically provided by rule or statute, pleadings need not be verified. The signature of an attorney or party shall be a certificate that the attorney or party has read the pleading, motion, or other paper; that to the best of his or her knowledge, information, and belief formed after reasonable inquiry, it is well grounded in fact and is warranted by existing law or a good faith argument for the extension, modification, or reversal of existing law; and that it is not interposed for any improper purpose.

[53 FR 11855, Apr. 11, 1988. Redesignated at 58 FR 25573, Apr. 27, 1993]

§1.735 Copies; service; separate filings against multiple defendants.

(a) Complaints may generally be brought against only one named carrier; such actions may not be brought against multiple defendants unless the defendant carriers are commonly owned or controlled, are alleged to have acted in concert, are alleged to be jointly liable to complainant, or the complaint concerns common questions of law or fact. Complaints may, however, be consolidated by the Commission for disposition.

(b) The complainant must file an original plus three copies of the complaint, accompanied by the correct fee, in accordance with subpart G of this part. See 47 CFR 1.1105(1)(c). However, if a complaint is addressed against multiple defendants, complainant shall pay separate fee and supply three additional copies of the complaint for each additional defendant.

(c) Generally, a separate file is set up for each defendant. An original plus two copies shall be filed of all pleadings and documents, other than the

47 CFR Ch. I (10–1–97 Edition)

complaint, for each file number assigned.

(d) The Commission will serve a copy of any formal complaint filed with it on the named defendant, together with a notice of the filing of the complaint. Such notice shall call upon the defendant to satisfy the complaint or to answer the complaint in writing within the time specified in the notice.

(e) All subsequent pleadings and briefs filed in any formal complaint proceeding, including any supplemental, amended, or cross complaint, as well as all letters, documents or other written submissions, shall be served by the filing party on all other parties to the proceeding, together with a proof of such service in accordance with the requirements of §1.47.

(f) The parties to any complaint proceeding may be required to file additional copies of any or all papers filed in the proceeding.

[53 FR 11855, Apr. 11, 1988. Redesignated and amended at 58 FR 25573, 25574, Apr. 27, 1993]

APPLICATIONS

§1.741 Scope.

The general rules relating to applications contained in §§1.742 through 1.748 apply to all applications filed by carriers except those filed by public correspondence radio stations pursuant to parts 80, 87, and 101 of this chapter, and those filed by common carriers pursuant to part 25 of this chapter. Parts 21 and 101 of this chapter contain general rules applicable to applications filed pursuant to these parts. For general rules applicable to applications filed pursuant to parts 80 and 87 of this chapter, see such parts and subpart F of this part. For rules applicable to applications filed pursuant to part 25, see said part.

[61 FR 26670, May 28, 1996]

§1.742 Place of filing, fees, and number of copies.

All applications which do not require a fee shall be filed at the Commission's main office in Washington, DC., Attention: Office of the Secretary. Hand-delivered applications will be dated by the Secretary upon receipt (mailed applications will be dated by the Mail Branch) and then forwarded to the

Federal Communications Commission

§1.744

Common Carrier Bureau. All applications accompanied by a fee payment should be filed with the Commission's lockbox bank in accordance with §1.1105, Schedule of Fees. The number of copies required for each application and the nonrefundable processing fees and any applicable regulatory fees (see subpart G of this part) which must accompany each application in order to qualify it for acceptance for filing and consideration are set forth in the rules in this chapter relating to various types of applications. However, if any application is not of the type covered by this chapter, an original and two copies of each such application shall be submitted.

[59 FR 30998, June 16, 1994]

§1.743 Who may sign applications.

(a) Except as provided in paragraph (b) of this section, applications, amendments thereto, and related statements of fact required by the Commission must be signed by the applicant, if the applicant is an individual; by one of the partners, if the applicant is a partnership; by an officer or duly authorized employee, if the applicant is a corporation; or by a member who is an officer, if the applicant is an unincorporated association. Applications, amendments, and related statements of fact filed on behalf of eligible government entities such as states and territories of the United States, their political subdivisions, the District of Columbia, and units of local government, including incorporated municipalities, must be signed by a duly elected or appointed official who is authorized to do so under the laws of the applicable jurisdiction.

(b) Applications, amendments thereto, and related statements of fact required by the Commission may be signed by the applicant's attorney in case of the applicant's physical disability or of his absence from the United States. The attorney shall in that event separately set forth the reason why the application is not signed by the applicant. In addition, if any matter is stated on the basis of the attorney's belief only (rather than his knowledge), he shall separately set forth his reasons for believing that such statements are true.

(c) Only the original of applications, amendments, or related statements of fact need be signed; copies may be conformed.

(d) Applications, amendments, and related statements of fact need not be signed under oath. Willful false statements made therein, however, are punishable by fine and imprisonment, U.S. Code, Title 18, section 1001, and by appropriate administrative sanctions, including revocation of station license pursuant to section 312(a)(1) of the Communications Act of 1934, as amended.

(e) "Signed," as used in this section, means an original hand-written signature, except that by public notice in the FEDERAL REGISTER the Common Carrier Bureau may allow signature by any symbol executed or adopted by the applicant with the intent that such symbol be a signature, including symbols formed by computer-generated electronic impulses.

[28 FR 12450, Nov. 22, 1963, as amended at 53 FR 17193, May 16, 1988; 59 FR 59503, Nov. 17, 1994]

§1.744 Amendments.

(a) Any application not designated for hearing may be amended at any time by the filing of signed amendments in the same manner, and with the same number of copies, as was the initial application. If a petition to deny (or to designate for hearing) has been filed, the amendment shall be served on the petitioner.

(b) After any application is designated for hearing, requests to amend such application may be granted by the presiding officer upon good cause shown by petition, which petition shall be properly served upon all other parties to the proceeding.

(c) The applicant may at any time be ordered to amend his application so as to make it more definite and certain. Such order may be issued upon motion of the Commission (or the presiding officer, if the application has been designated for hearing) or upon petition of any interested person, which petition shall be properly served upon the applicant and, if the application has been

§ 1.745

designated for hearing, upon all parties to the hearing.

[29 FR 6444, May 16, 1964, and 31 FR 14394, Nov. 9, 1966]

§ 1.745 Additional statements.

The applicant may be required to submit such additional documents and written statements of fact, signed and verified (or affirmed), as in the judgment of the Commission (or the presiding officer, if the application has been designated for hearing) may be necessary. Any additional documents and written statements of fact required in connection with applications under Title II of the Communications Act need not be verified (or affirmed).

[29 FR 6444, May 16, 1964]

§ 1.746 Defective applications.

(a) Applications not in accordance with the applicable rules in this chapter may be deemed defective and returned by the Commission without acceptance of such applications for filing and consideration. Such applications will be accepted for filing and consideration if accompanied by petition showing good cause for waiver of the rule with which the application does not conform.

(b) The assignment of a file number, if any, to an application is for the administrative convenience of the Commission and does not indicate the acceptance of the application for filing and consideration.

§ 1.747 Inconsistent or conflicting applications.

When an application is pending or undecided, no inconsistent or conflicting application filed by the same applicant, his successor or assignee, or on behalf or for the benefit of said applicant, his successor, or assignee, will be considered by the Commission.

§ 1.748 Dismissal of applications.

(a) *Before designation for hearing.* Any application not designated for hearing may be dismissed without prejudice at any time upon request of the applicant. An applicant's request for the return of an application that has been accepted for filing and consideration, but not designated for hearing, will be deemed

47 CFR Ch. I (10–1–97 Edition)

a request for dismissal without prejudice. The Commission may dismiss an application without prejudice before it has been designated for hearing when the applicant fails to comply or justify noncompliance with Commission requests for additional information in connection with such application.

(b) *After designation for hearing.* A request to dismiss an application without prejudice after it has been designated for hearing shall be made by petition properly served upon all parties to the hearing and will be granted only for good cause shown. An application may be dismissed with prejudice after it has been designated for hearing when the applicant:

(1) Fails to comply with the requirements of § 1.221(c);

(2) Otherwise fails to prosecute his application; or

(3) Fails to comply or justify noncompliance with Commission requests for additional information in connection with such application.

[28 FR 12450, Nov. 22, 1963, as amended at 29 FR 6445, May 16, 1964]

§ 1.749 Action on application under delegated authority.

Certain applications do not require action by the Commission but, pursuant to the delegated authority contained in subpart B of part 0 of this chapter, may be acted upon by the Telegraph Committee, the Telephone Committee, or the Chief of the Common Carrier Bureau, respectively, subject to reconsideration by the Commission.

SPECIFIC TYPES OF APPLICATIONS UNDER TITLE II OF COMMUNICATIONS ACT

§ 1.761 Cross reference.

Specific types of applications under Title III of the Communications Act involving public correspondence radio stations are specified in parts 23, 80, 87, and 101 of this chapter.

[61 FR 26671, May 28, 1996]

§ 1.762 Interlocking directorates.

Applications under section 212 of the Communications Act for authority to hold the position of officer or director of more than one carrier subject to the

Federal Communications Commission

§1.766

act or for a finding that two or more carriers are commonly owned shall be made in the form and manner, with the number of copies set forth in part 62 of this chapter. The Commission shall be informed of any change in status of any person authorized to hold the position of officer or director of more than one carrier, as required by part 62 of this chapter.

[52 FR 5289, Feb. 20, 1987]

§1.763 Construction, extension, acquisition or operation of lines.

(a) Applications under section 214 of the Communications Act for authority to construct a new line, extend any line, acquire or operate any line or extension thereof, or to engage in transmission over or by means of such additional or extended line, to furnish temporary or emergency service, or to supplement existing facilities shall be made in the form and manner, with the number of copies and accompanied by the fees specified in part 63 of this chapter.

(b) In cases under this section requiring a certificate, notice is given to and a copy of the application is filed with the Secretary of the Army, the Secretary of the Navy, and the Governor of each State involved. Hearing is held if any of these persons desires to be heard or if the Commission determines that a hearing should be held. Copies of applications for certificates are filed with the regulatory agencies of the States involved.

§1.764 Discontinuance, reduction, or impairment of service.

(a) Applications under section 214 of the Communications Act for the authority to discontinue, reduce, or impair service to a community or part of a community or for the temporary, emergency, or partial discontinuance, reduction, or impairment of service shall be made in the form and manner, with the number of copies specified in part 63 of this chapter (see also subpart G, part 1 of this chapter). Posted and public notice shall be given the public as required by part 63 of this chapter.

(b) In cases under this section requiring a certificate, notice is given to and a copy of the application is filed with the Secretary of Defense, the Secretary

of State (with respect to such applications involving service to foreign points), and the Governor of each State involved. Hearing is held if any of these persons desires to be heard or if the Commission determines that a hearing should be held. Copies of all formal applications under this section requesting authorizations (including certificates) are filed with the Secretary of Defense, the Secretary of State (with respect to such applications involving service to foreign points) and the Governor of each State involved. Copies of all applications under this section requesting authorizations (including certificates) are filed with the regulatory agencies of the States involved.

[28 FR 12450, Nov. 22, 1963, as amended at 52 FR 5289, Feb. 20, 1987]

§1.765 Consolidation or acquisition of telephone companies.

Applications under section 221(a) of the Communications Act for authority to consolidate or acquire telephone companies shall be made in the form and manner, with the number of copies and accompanied by the fees shown in part 66 of this chapter.

§1.766 Consolidation of domestic telegraph carriers.

(a) Applications under section 22 of the Communications Act by two or more domestic telegraph carriers for authorization to effect a consolidation or merger or by any domestic telegraph carrier to acquire all or any part of the domestic telegraph properties, domestic telegraph facilities, or domestic telegraph operations of any carrier shall contain such information as is necessary for the Commission to act upon such application under the provisions of section 222 of the Act.

(b) These applications are acted upon by the Commission after public hearing. Reasonable notice in writing of the public hearing and an opportunity to be heard is given by the Commission to the Governor of each of the States in which any of the physical property involved in such proposed consolidation or merger is situated, to the Secretary of State, the Secretary of the Army, the Attorney General of the United

§ 1.767

47 CFR Ch. I (10–1–97 Edition)

States, the Secretary of the Navy, representatives of employees where represented by bargaining representatives known to the Commission, and to such other persons as the Commission may deem advisable.

[28 FR 12450, Nov. 22, 1963, as amended at 52 FR 5289, Feb. 20, 1987]

§ 1.767 Cable landing licenses.

(a) Applications for cable landing licenses under 47 U.S.C. 34–39 and Executive Order No. 10530, dated May 10, 1954, should be filed in duplicate and in accordance with the provisions of that Executive Order. These applications should contain:

(1) The name, address and telephone number(s) of the applicant;

(2) The Government, State, or Territory under the laws of which each corporate or partnership applicant is organized;

(3) The name, title, post office address, and telephone number of the officer and any other contact point, such as legal counsel, to whom correspondence concerning the application is to be addressed;

(4) A description of the submarine cable, including the type and number of channels and the capacity thereof;

(5) A specific description of the cable landing location on the shore of the United States and in foreign countries where the cable will land (including a map). Applicants initially may file a general geographic description of the landing points; however, grant of the application will be conditioned on the Commission's final approval of a more specific description of the landing points to be filed by the applicant no later than 90 days prior to construction. The Commission will give public notice of the filing of this description, and grant of the license will be considered final if the Commission does not notify the applicant otherwise in writing no later than 60 days after receipt of the specific description of the landing points.

(6) A statement as to whether the cable will be operated on a common carrier or non-common carrier basis, and if operation will be on a non-common carrier basis, include the ownership information required in § 63.18

(e)(6) and (h) (1) through (2) of this chapter; and

(7) Any other information that may be necessary to enable the Commission to act on their application.

(b) These applications are acted upon by the Commission after obtaining the approval of the Secretary of State and such assistance from any executive department or establishment of the Government as it may require.

(c) Original files relating to submarine cable landing licenses and applications for licenses since June 30, 1934, are kept by the Commission. Such applications for licenses (including all documents and exhibits filed with and made a part thereof, with the exception of any maps showing the exact location of the submarine cable or cables to be licensed) and the licenses issued pursuant thereto, with the exception of such maps, shall, unless otherwise ordered by the Commission, be open to public inspection in the offices of the Commission in Washington, D.C.

(d) Original files relating to licenses and applications for licenses for the landing operation of cables prior to June 30, 1934, were kept by the Department of State, and such files prior to 1930 have been transferred to the Executive and Foreign Affairs Branch of the General Records Office of the National Archives. Requests for inspection of these files should, however, be addressed to the Federal Communications Commission, Washington, D.C., 20554; and the Commission will obtain such files for a temporary period in order to permit inspection at the offices of the Commission.

(e) A separate application shall be filed with respect to each individual cable system for which a license is requested, or for which modification or amendment of a previous license is requested.

(f) Applicants shall disclose to any interested member of the public, upon written request, accurate information concerning the location and timing for the construction of a submarine cable system authorized under this section. This disclosure shall be made within 30 days of receipt of the request.

[28 FR 12450, Nov. 22, 1963, as amended at 52 FR 5289, Feb. 20, 1987; 61 FR 15726, Apr. 9, 1996]

Federal Communications Commission

§1.773

TARIFFS

§1.771 Filing.

Schedules of charges, and classifications, practices, and regulations affecting such charges, required under section 203 of the Communications Act shall be constructed, filed, and posted in accordance with and subject to the requirements of part 61 of this chapter.

§1.772 Application for special tariff permission.

Applications under section 203 of the Communications Act for special tariff permission shall be made in the form and manner, with the number of copies set out in part 61 of this chapter.

[52 FR 5289, Feb. 20, 1987]

§1.773 Petitions for suspension or rejection of new tariff filings.

(a) *Petition*—(1) *Content*. Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing or any provision thereof shall specify the filing's Federal Communications Commission tariff number and carrier transmittal number, the items against which protest is made, and the specific reasons why the protested tariff filing warrants investigation, suspension, or rejection under the Communications Act. No petition shall include a prayer that it also be considered a formal complaint. Any formal complaint shall be filed as a separate pleading as provided in §1.721.

(i) Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing or any provision of such a publication, must specify the pertinent Federal Communications Commission tariff number and carrier transmittal number; the matters protested; and the specific reasons why the tariff warrants investigation, suspension, or rejection. When a single petition asks for more than one form of relief, it must separately and distinctly plead and support each form of relief. However, no petition may ask that it also be considered a formal complaint. Formal complaints must be separately lodged, as provided in §1.721.

(ii) For purposes of this section, tariff filings by nondominant carriers will be considered *prima facie* lawful, and will not be suspended by the Commis-

sion unless the petition requesting suspension shows:

(A) That there is a high probability the tariff would be found unlawful after investigation;

(B) That the harm alleged to competition would be more substantial than the injury to the public arising from the unavailability of the service pursuant to the rates and conditions proposed in the tariff filing;

(C) That irreparable injury will result if the tariff filing is not suspended; and

(D) That the suspension would not otherwise be contrary to the public interest.

(iii) For the purpose of this section, any tariff filing by a local exchange carrier filed pursuant to the requirements of §61.39 will be considered *prima facie* lawful and will not be suspended by the Commission unless the petition requesting suspension shows that the cost and demand studies or average schedule information was not provided upon reasonable request. If such a showing is not made, then the filing will be considered *prima facie* lawful and will not be suspended by the Commission unless the petition requesting suspension shows each of the following:

(A) That there is a high probability the tariff would be found unlawful after investigation;

(B) That any unreasonable rate would not be corrected in a subsequent filing;

(C) That irreparable injury will result if the tariff filing is not suspended; and

(D) That the suspension would not otherwise be contrary to the public interest.

(iv) For the purposes of this section, tariff filings made pursuant to §61.49(b) by carriers subject to price cap regulation will be considered *prima facie* lawful, and will not be suspended by the Commission unless the petition shows that the support information required in §61.49(b) was not provided, or unless the petition requesting suspension shows each of the following:

(A) That there is a high probability the tariff would be found unlawful after investigation;

(B) That the suspension would not substantially harm other interested parties;

(C) That irreparable injury will result if the tariff filing is not suspended; and

(D) That the suspension would not otherwise be contrary to the public interest.

(2) *When filed.* All petitions seeking investigation, suspension, or rejection of a new or revised tariff filing shall meet the filing requirements of this paragraph. In case of emergency and within the time limits provided, a telegraphic request for such relief may be sent to the Commission setting forth succinctly the substance of the matters required by paragraph (a)(1) of this section. A copy of any such telegraphic request shall be sent simultaneously to the Chief, Common Carrier Bureau, the Chief, Tariff Division, and the publishing carrier. Thereafter, the request shall be confirmed by petition filed and served in accordance with §1.773(a)(4).

(i) Petitions seeking investigation, suspension, or rejection of a new or revised tariff filed pursuant to section 204(a)(3) of the Communications Act made on 7 days notice shall be filed and served within 3 calendar days after the date of the tariff filing.

(ii) Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on less than 15 days notice shall be filed and served within 6 days after the date of the tariff filing.

(iii) Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on at least 15 but less than 30 days notice shall be filed and served within 7 days after the date of the tariff filing.

(iv) Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on at least 30 but less than 90 days notice shall be filed and served within 15 days after the date of the tariff filing.

(v) Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on 90 or more days notice shall be filed and served within 25 days after the date of the tariff filing.

(3) *Computation of time.* Intermediate holidays shall be counted in determin-

ing the above filing dates. If the date for filing the petition falls on a holiday, the petition shall be filed on the next succeeding business day.

(4) *Copies, service.* An original and four copies of each petition shall be filed with the Commission as follows: the original and three copies of each petition shall be filed with the Secretary, FCC room 222, 1991 M Street, NW., Washington, DC 20554; one copy must be delivered directly to the Commission's copy contractor, International Transcription Service, Inc., 2100 M St., NW., Suite 140, Washington, DC. Additional, separate copies shall be served simultaneously upon the Chief, Common Carrier Bureau; the Chief, Competitive Pricing Division; and the Chief, Tariff and Price Analysis Branch of the Competitive Pricing Division. Petitions seeking investigation, suspension, or rejection of a new or revised tariff made on 15 days or less notice shall be served either personally or via facsimile on the filing carrier. If a petition is served via facsimile, a copy of the petition must also be sent to the filing carrier via first class mail on the same day of the facsimile transmission. Petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on more than 15 days notice may be served on the filing carrier by mail.

(b) *Reply—(1) When filed.* A publishing carrier's reply to a petition for relief from a tariff filing shall be filed in accordance with the following periods:

(i) Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filed pursuant to section 204(a)(3) of the Act made on 7 days notice shall be filed and served within 2 days after the date the petition is filed with the Commission.

(ii) Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on less than 15 days notice shall be filed and served within 3 days after the date the petition is due to be filed with the Commission.

(iii) Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on at least 15 but less than 30 days notice shall be filed and served within 4 days after service of the petition.

Federal Communications Commission

§1.785

(iv) Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on at least 30 but less than 90 days notice shall be filed and served within 5 days after service of the petition.

(v) Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on 90 or more days notice shall be filed and served within 8 days after service of the petition.

(vi) Where all petitions against a tariff filing have not been filed on the same day, the publishing carrier may file a consolidated reply to all the petitions. The time for filing such a consolidated reply will begin to run on the last date for timely filed petitions, as fixed by paragraphs (a)(2) (i) through (iv) of this section, and the date on which the consolidated reply is due will be governed by paragraphs (b)(1) (i) through (iv) of this section.

(2) *Computation of time.* Intermediate holidays shall be counted in determining the 3-day filing date for replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on less than 15 days notice. Intermediate holidays shall not be counted in determining filing dates for replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff filing made on 15 or more days notice. When a petition is permitted to be served upon the filing carrier by mail, an additional 3 days (counting holidays) may be allowed for filing the reply. If the date for filing the reply falls on a holiday, the reply may be filed on the next succeeding business day.

(3) *Copies, service.* An original and four copies of each reply shall be filed with the Commission, as follows: the original and three copies must be filed with the Secretary, FCC room 222, 1919 M Street, NW., Washington, DC 20554; one copy must be delivered directly to the Commission's Copy contractor, International Transcription Service, Inc., 2100 M St., NW. Suite 140, Washington, DC. Additional separate copies shall be served simultaneously upon the Chief, Common Carrier Bureau; the Chief, Competitive Division; and the Chief, Tariff and Price Analysis Branch of the Competitive Pricing Division

and the petitioner. Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff made on 15 days or less notice shall be served on petitioners personally or via facsimile. Replies to petitions seeking investigation, suspension, or rejection of a new or revised tariff made on more than 15 days notice may be served upon petitioner personally, by mail or via facsimile.

[45 FR 64190, Sept. 29, 1980, as amended at 49 FR 40876, Oct. 18, 1984; 49 FR 49466, Dec. 20, 1984; 52 FR 26682, July 16, 1987; 54 FR 19840, May 8, 1989; 58 FR 17529, Apr. 5, 1993; 58 FR 51247, Oct. 1, 1993; 62 FR 5777, Feb. 7, 1997]

CONTRACTS, REPORTS, AND REQUESTS REQUIRED TO BE FILED BY CARRIERS

§1.781 Requests for extension of filing time.

Requests for extension of time within which to file contracts, reports, and requests referred to in §§1.783 through 1.814 shall be made in writing and may be granted for good cause shown.

CONTRACTS

§1.783 Filing.

Copies of carrier contracts, agreements, concessions, licenses, authorizations or other arrangements, shall be filed as required by part 43 of this chapter.

FINANCIAL AND ACCOUNTING REPORTS AND REQUESTS

§1.785 Annual financial reports.

(a) An annual financial report shall be filed by telephone carriers and affiliates as required by part 43 of this chapter on form M.

(b) Verified copies of annual reports filed with the Securities and Exchange Commission on its Form 10-K, Form 1-MD, or such other form as may be prescribed by that Commission for filing of equivalent information, shall be filed annually with this Commission by each person directly or indirectly controlling any communications common carrier in accordance with part 43 of this chapter.

(c) Carriers having separate departments or divisions for carrier and non-carrier operations shall file separate

§ 1.786

supplemental annual reports with respect to such carrier and non-carrier operations in accordance with part 43 of this chapter.

[28 FR 12450, Nov. 22, 1963, as amended at 31 FR 747, Jan. 20, 1966; 47 FR 50697, Nov. 9, 1982; 49 FR 36503, Sept. 18, 1984; 50 FR 41152, Oct. 9, 1985; 58 FR 36143, July 6, 1993]

§ 1.786 [Reserved]

§ 1.787 Reports of proposed changes in depreciation rates.

Carriers shall file reports regarding proposed changes in depreciation rates as required by part 43 of this chapter.

§ 1.788 Reports regarding pensions and benefits.

Carriers shall file reports regarding pensions and benefits as required by part 43 of this chapter.

§ 1.789 Reports regarding division of international telegraph communication charges.

Carriers engaging in international telegraph communication shall file reports in regard to the division of communication charges as required by part 43 of this chapter.

§ 1.790 Reports relating to traffic by international carriers.

Carriers shall file periodic reports regarding international point-to-point traffic as required by part 43 of this chapter.

[57 FR 8579, Mar. 11, 1992]

§ 1.791 Reports and requests to be filed under part 32 of this chapter.

Reports and requests shall be filed either periodically, upon the happening of specified events, or for specific approval by class A and class B telephone companies in accordance with and subject to the provisions of part 32 of this chapter.

[55 FR 30461, July 26, 1990]

§ 1.795 Reports regarding interstate rates of return.

Carriers shall file reports regarding interstate rates of return on FCC Form 492 as required by part 65 of this chapter.

[52 FR 274, Jan. 5, 1987]

47 CFR Ch. I (10–1–97 Edition)

SERVICES AND FACILITIES REPORTS

§ 1.802 Reports relating to continuing authority to supplement facilities or to provide temporary or emergency service.

Carriers receiving authority under part 63 of this chapter shall file quarterly or semiannual reports as required therein.

§ 1.803 Reports relating to reduction in temporary experimental service.

As required in part 63 of this chapter, carriers shall report reductions in service which had previously been expanded on an experimental basis for a temporary period.

§ 1.805 Reports relating to service by carriers engaged in public radio service operations.

Monthly and quarterly reports must be filed with the Commission in connection with certain fixed public radio service operations. No form is prescribed. A complete description of the contents of these reports is contained in part 23 of this chapter.

MISCELLANEOUS REPORTS

§ 1.811 Reports regarding amendments to charters, by-laws and partnership agreements of carriers engaged in domestic public radio services.

Amendments to such documents shall be reported and filed in accordance with part 21 of this chapter.

§ 1.813 Reports of negotiations regarding foreign communication matters.

Pursuant to the requirements of part 43 of this chapter, carriers engaging or participating in foreign communications shall file monthly reports covering negotiations conducted.

§ 1.814 Reports regarding free service rendered the Government for national defense.

Carriers rendering free service in connection with the national defense to any agency of the United States Government shall file reports in accordance with part 2 of this chapter.

Federal Communications Commission

§1.823

§1.815 Reports of annual employment.

(a) Each common carrier licensee or permittee with 16 or more full time employees shall file with the Commission, on or before May 31 of each year, on FCC Form 395, an annual employment report.

(b) A copy of every annual employment report filed by the licensee or permittee pursuant to the provisions herein; and copies of all exhibits, letters, and other documents filed as part thereof, all amendments thereto, all correspondence between the permittee or licensee and the Commission pertaining to the reports after they have been filed and all documents incorporated herein by reference are open for public inspection at the offices of the Commission.

(c) *Cross references*—(1) *Applicability of cable television EEO reporting requirements to MDS and MMDS facilities*, see §21.920 of this chapter.

(2) *Applicability of cable television EEO reporting requirements for FSS facilities*, see §25.601 of this chapter.

[35 FR 12894, Aug. 14, 1970, as amended at 36 FR 3119, Feb. 18, 1971; 58 FR 42249, Aug. 9, 1993]

GRANTS BY RANDOM SELECTION

§1.821 Scope.

The provisions of §§1.822, 1.823, 1.824 and 1.825 apply as indicated to those applications for permits, licenses or authorizations in the Public Mobile Services, Multichannel Multipoint Distribution Service and Digital Electronic Message Service for which action may be taken by the Chief, Common Carrier Bureau pursuant to delegated authority.

[59 FR 59503, Nov. 17, 1994]

§1.822 General selection procedures.

(a) Mutually exclusive applications for permits and licenses in the services specified in §1.821 may be designated for random selection according to the procedures established for each service. Following the random selection, the Commission shall determine whether the applicant is qualified to receive the permit or license. If, after reviewing the tentative selectee's application and pleadings properly filed against it, the

Commission determines that a substantial and material question of fact exists, it shall designate the qualifying issue(s) for an expedited hearing.

(b) Expedited hearing procedures. (1) Hearings may be conducted by the Commission or an Administrative Law Judge. In the case of a question which requires oral testimony for its resolution, the hearing will be conducted by an Administrative Law Judge.

(2) Parties have ten (10) days from publication in the FEDERAL REGISTER of the hearing designation order to file notices of appearance.

(3) When the Commission, under §1.221, issues an order stating the time, place, and nature of the hearing, this order shall instruct the applicant to submit its direct case in writing within thirty (30) days from the order's release date, or as otherwise specified in the order. The direct written case must set forth all those facts and circumstances related to the issues in the designation order. Documentary evidence upon which the applicant relies must be attached. Each exhibit must be numbered and must be accompanied by an affidavit from someone who has personal knowledge of the facts in the submission and who attests to the truth of the submission.

(4) The order will also specify those petitioners that directly raised an issue which was designated and will inform these parties of their opportunity to submit a written rebuttal case within twenty (20) days after the direct case is due. The procedures in paragraph (b)(3) of this section will apply as to documentary evidence, exhibits, and affidavits.

(5) Appeal of initial decisions rendered by an Administrative Law Judge shall lie with the Commission.

[48 FR 27201, June 13, 1983. Redesignated and amended at 50 FR 5991, Feb. 13, 1985]

§1.823 Random selection procedures for the Public Mobile Services.

(a) *General Procedures*. If there are mutually exclusive applications for an initial license, the Commission may use a random selection process. Each such random selection shall be conducted under the direction of the Chief of the Common Carrier Bureau. The designated Lottery Official shall select

the winning applicant from among mutually exclusive applicants. The Lottery Official may select in rank order a number of additional applicants. The number of additional applicants selected will be determined by the Chief of the Common Carrier Bureau and the Managing Director. No preferences shall be awarded to participants. Following the random selection, the Commission shall announce the tentative selectee and determine whether this applicant is qualified to receive the license. If the Commission determines that the tentative selectee is qualified, it shall grant the application.

(b) *Petitions to Deny*—(1) *Public Mobile Services other than the Cellular Radiotelephone Service.* Petitions to Deny and other pleadings may be filed against applications but are not reviewed prior to the random selection process. Petitions filed against tentative selectee applications are reviewed after the tentative selectee is announced.

(2) [Reserved]

(3) *Cellular Radiotelephone Service, unserved areas.* In the Phase I licensing phase, petitions to deny must be filed within 30 days after the date of public notice announcing the tentative selectee. If the tentative selectee is qualified, the Commission will grant its application and dismiss the losing applications. If the tentative selectee's application cannot be granted, it will be either designated for hearing or dismissed. If the winning application is dismissed or ultimately denied, another lottery will be held to select an application from the remaining applications. In the Phase II licensing phase, petitions to deny must be filed within 30 days from the date of public notice accepting the application for filing.

(c) *Petitions for Reconsideration.* Motions to Stay or Applications for Review may be filed only at such time as the Commission grants or denies the tentative selectee's application. The filing periods specified in the Rules shall apply for such pleadings.

[50 FR 5991, Feb. 13, 1985, as amended at 50 FR 51527, Dec. 18, 1985; 53 FR 52425, Dec. 28, 1988; 56 FR 58506, Nov. 20, 1991; 59 FR 59503, Nov. 17, 1994; 59 FR 59949, Nov. 21, 1994]

§ 1.824 Random selection procedures for Multichannel Multipoint Distribution Service and Multipoint Distribution Service H-Channel stations.

(a) If there are mutually exclusive applications for an initial conditional license or license, the Commission may use the random selection process to select the conditional licensee or licensee. Each such random selection shall be conducted under the direction of the Office of the Managing Director in conjunction with the Office of the Secretary. Following the random selection, the Commission shall announce the tentative selectee and determine whether the applicant is qualified to receive the conditional license or license. If the Commission determines that the tentative selectee is qualified, it shall grant the application. In the event that the tentative selectee's application is denied, a second random selection will be conducted. Petitions for Reconsideration, Motions to Stay or Applications for Review may be submitted at the time the Commission grants or denies the application of the tentative selectee. The filing periods specified in the rules shall apply for such pleadings.

(b) Competing applications for conditional licenses and licenses shall be designated for random selection in accordance with §§ 1.1621, 1.1622 (a), (b), (c), (d), and (e), and 1.1623. No preferences pursuant to § 1.1622 (b)(2) or (b)(3) shall be granted to any MMDS or MDS H-channel applicant whose owners, when aggregated, have an ownership interest of more than 50 percent in the media of mass communication whose service areas, as set forth at § 1.1622 (e)(1) through (e)(7), wholly encompass or are encompassed by the protected service area contour, computed in accordance with § 21.902(d) of this chapter, for which the license or conditional license is sought.

(c) Petitions to Deny may be filed only against the tentative selectee. These petitions must be filed within 30 days of the Public Notice announcing such tentative selection. A consolidated reply may be filed within 15 days of the due date for Petitions to Deny.

[50 FR 5992, Feb. 13, 1985, as amended at 56 FR 57815, Nov. 14, 1991]

Federal Communications Commission

§1.911

§1.825 Random selection procedures for Digital Electronic Message Service.

If there are mutually exclusive applications for an initial permit or license for a digital termination system, the Commission may use the random selection process to select the permittee or licensee. Each such random selection shall be conducted under the direction of the Office of Managing Director in conjunction with the Office of the Secretary. The random selection shall rank order the applications. No preferences shall be awarded to participants. Following the random selection, the Commission shall announce the rank order of the applications to determine whether the first ranked tentative selectee is qualified to receive the permit or license. If the Commission determines that the tentative selectee is qualified, it shall grant the application. The Commission shall then determine which of the alternate applications in rank order, can also be granted and whether those alternate tentative selectees are qualified to receive the permit or license. If the Commission determines that the alternate tentative selectees are qualified, it shall grant the applications.

[50 FR 45614, Nov. 1, 1985, as amended by 61 FR 26671, May 28, 1996; 62 FR 24581, May 6, 1997]

Subpart F—Private Radio Services Applications and Proceedings

SOURCE: 28 FR 12454, Nov. 22, 1963, unless otherwise noted.

GENERAL

§1.901 Scope.

In the case of any conflict between the rules set forth in this subpart and the rules set forth in part 13 of this chapter or the rules set forth for specific services in parts 80 through 101 of this chapter, the rules in this subpart shall govern.

[61 FR 26671, May 28, 1996]

GENERAL FILING REQUIREMENTS

§1.911 Applications required.

(a) Except as provided in paragraph (b) of this section, station licenses as defined in section 3(bb) of the Communications Act; operator licenses or modifications of renewals thereof; assignments of station licenses or any rights thereunder; and consent to transfer control of a corporation holding a license, shall be granted only upon written and signed application.

(b) In cases (1) of an emergency found by the Commission involving danger to life or property or due to damage to equipment, or (2) of a national emergency proclaimed by the President or declared by the Congress and during the continuance of any war in which the United States is engaged, when such action is necessary for the national defense or security or otherwise in furtherance of the war effort, or (3) of emergency where the Commission finds, in these services, that it would not be feasible to secure renewal applications from existing licensees or otherwise to follow normal licensing procedure, the Commission may grant station licenses, or modifications or renewals thereof, without the filing of a formal application; but no such authorization shall be granted for or continue in effect beyond the period of the emergency or war requiring it. The procedure to be followed for requests submitted under the provisions of this paragraph is the same as for obtaining special temporary authority under §1.925.

(c) In case of vessels at sea, the Commission may issue by cable, telegraph, or radio a permit for the operation of a station until the vessel returns to a port of the continental United States.

(d) Canadian licensees desiring to operate in the United States under the terms of Articles 2 and 3 of the Convention between the United States and Canada concerning Operation of Certain Radio Equipment or Stations (which entered into force May 15, 1952) shall make application upon FCC Form 410, which shall be filed with the Secretary, Federal Communications Commission, Washington, DC, 20554. Forms

§1.912

47 CFR Ch. I (10–1–97 Edition)

may be obtained from the FCC Secretary, any field office of the Commission, or from the Controller of Telecommunications, Department of Transport, Ottawa, Canada.

(e) An alien amateur desiring to operate in the United States under provisions of sections 303(1)(2) and 310(a) of the Communications Act of 1934, as amended, and under the terms of a bilateral agreement in force between the applicant's country and the United States concluded pursuant to the provisions of Pub. L. 88–313, must make application on FCC Form 610–A,¹ which must be filed with the Commission's offices in Gettysburg, Pennsylvania (Federal Communications Commission, Gettysburg, Pennsylvania 17325). Forms may be obtained from the Secretary, the Commission's offices in Gettysburg, Pennsylvania, any field office of the Commission and, in some instances, from United States missions abroad.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

[28 FR 12454, Nov. 22, 1963, as amended at 34 FR 19419, Dec. 9, 1969; 37 FR 15928, Aug. 8, 1972; 40 FR 5365, Feb. 5, 1975; 49 FR 30943, Aug. 2, 1984]

§1.912 Where applications are to be filed.

(a) Each application for a new amateur service operator/primary station license and each application involving a change in operator class must be submitted to the volunteer examiners (VEs) administering the qualifying examination. See §97.17(c) of this chapter. The VEs are required to submit the applications of persons passing their respective examinations for amateur operator licenses to the Volunteer-Examiner Coordinator (VEC). All other applications for amateur service licenses must be submitted to FCC, 1270 Fairfield Road, Gettysburg, PA 17325–7245.

(b) All applications for private land mobile licenses which require both frequency coordination and fees as set forth at part 1, subpart G of this chapter shall first be sent to the certified coordinator for the radio service or frequency group concerned. After the ap-

propriate frequency coordination and attachment of the statutory fee, such applications shall be forwarded to the appropriate address in accordance with §0.401(b) of the rules.

(1) All applications for private land mobile licenses that require frequency coordination but not a fee shall be sent to the certified frequency coordinator for the radio service or frequency group concerned. After appropriate frequency coordination, such applications must be forwarded to the Federal Communications Commission, 1270 Fairfield Road, Gettysburg, Pennsylvania 17325–7245.

(2) All applications for private land mobile licenses that require a fee but not frequency coordination shall be sent to the appropriate address in accordance with §0.401(b) of the rules.

(3) All applications for private land mobile licenses that do not require either frequency coordination or a fee must be sent to Federal Communications Commission, 1270 Fairfield Road, Gettysburg, Pennsylvania 17325–7245.

(c) Formal applications for ship station licenses for use of radiotelephone or radar transmitting apparatus or both, and applications for modification of such licenses shall be filed on FCC Form 506 and in accordance with the instructions on that form.

(d) Formal applications for ship station licenses (FCC Forms 506 and 405–B), for aircraft station licenses (FCC Forms 404 and 405–B), and applications for Maritime Coast and Aviation Ground Stations, requiring fees as set forth in part 1, subpart G of this chapter must be filed in accordance with §1.1102 of the rules.

(e) Applicants submitting long-form applications pursuant to competitive bidding procedures (see §1.2107(c)) must mail or otherwise deliver their application to: Office of the Secretary, Federal Communications Commission, 1919 M Street NW., Room 222, Washington, DC 20554, Attention: Auction Application Processing Section.

(f) All other applications that do not require fees must be filed with the Commission's offices in Gettysburg, Pennsylvania. Address the applications to: Federal Communications Commission, 1270 Fairfield Road, Gettysburg, Pennsylvania 17325–7245. Applications

¹ Form filed as part of original document.

Federal Communications Commission

§ 1.916

requiring fees as set forth at part 1, subpart G of of this chapter must be filed in accordance with § 0.401(b) of the rules.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308; secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[47 FR 9208, Mar. 4, 1982, as amended at 47 FR 15334, Apr. 9, 1982; 48 FR 45658, Oct. 6, 1983; 52 FR 10229, Mar. 31, 1987; 56 FR 64714, Dec. 12, 1991; 58 FR 30717, May 27, 1993; 59 FR 543, Jan. 5, 1994; 59 FR 24957, May 13, 1994]

§ 1.913 Who may sign applications.

(a) Except as provided in paragraph (b) of this section, applications, amendments thereto, and related statements of fact required by the Commission must be signed by the applicant, if the applicant is an individual; by one of the partners, if the applicant is a partnership; by an officer, director, or duly authorized employee, if the applicant is a corporation; or by a member who is an officer, if the applicant is an unincorporated association. Applications, amendments, and related statements of fact filed on behalf of eligible government entities such as states and territories of the United States, their political subdivisions, the District of Columbia, and units of local government, including unincorporated municipalities, must be signed by a duly elected or appointed official who is authorized to do so under the laws of the applicable jurisdiction.

(b) Applications, amendments thereto, and related statements of fact required by the Commission may be signed by the applicant's attorney in case of the applicant's physical disability or absence from the United States, or by applicant's designated vessel master when a temporary permit is requested for a vessel. The attorney shall, when applicable, separately set forth the reason why the application is not signed by the applicant. In addition, if any matter is stated on the basis of the attorney's or master's belief only (rather than knowledge), the attorney or master shall separately set forth the reasons for believing that such statements are true.

(c) Only the original of applications, amendments, and related statements of fact need be signed.

(d) Applications, amendments, and related statements of fact need not be signed under oath. Willful false statements made therein, however, are punishable by fine and imprisonment, U.S. Code, Title 18, section 1001, and by appropriate administrative sanctions, including revocation of station license pursuant to section 312(a)(1) of the Communications Act of 1934, as amended.

(e) "Signed," as used in this section, means an original hand-written signature, except that by public notice in the FEDERAL REGISTER the Private Radio Bureau may allow signature by any symbol executed or adopted by the applicant with the intent that such symbol be a signature, including symbols formed by computer-generated electronic impulses.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

[28 FR 12450, Nov. 22, 1963, as amended at 43 FR 27991, June 28, 1978; 49 FR 30944, Aug. 2, 1984; 58 FR 21406, Apr. 21, 1993]

§ 1.914 Full disclosures.

Each application shall contain full and complete disclosures with regard to the real party or parties in interest and as to all matters and things required to be disclosed by the application forms.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

§ 1.916 Repetitious applications.

Where the Commission has, for any reason, denied an application for a new station or for any modification of services or facilities, dismissed such application with prejudice, or revoked the license for a radio station in the Private Radio Services, the Commission will not consider a like or new application involving service of the same kind to substantially the same area by substantially the same applicant, its successor or assignee, or on behalf of or for the benefit of the original parties in interest, until after the lapse of 12 months from the effective date of the Commission's order. The Commission may, for good cause shown, waive the requirements of this section.

[28 FR 12454, Nov. 22, 1963, as amended at 44 FR 39181, July 5, 1979]

§ 1.918

47 CFR Ch. I (10–1–97 Edition)

§ 1.918 Amendment of applications.

(a) Any amendment to an application shall be signed and submitted in the same manner and with the same number of copies as was the original application.

(b) Any application may be amended as a matter of right prior to the grant of that application. However, an application which is substantially amended, as defined by § 1.962(c), will be considered a newly filed application as of the date of the filing of the amendment.

(c) An application to amend an application after it has been designated for hearing will be considered only upon written petition addressed to the hearing examiner and served upon the parties of record, and will be granted only for good cause shown. A petition which requests a substantial change or to change the applicant's position, or the issues, in a hearing, must be accompanied by a signed statement of a person with knowledge of the facts as to whether or not consideration has been promised to or received by the petitioner, directly or indirectly, in connection with the filing of such petition for amendment. If consideration has been promised, or received, the statement shall set forth in full detail all the relevant facts with sufficient itemization of the consideration to enable the examiner to determine to what extent, if any, that the consideration represents only the reasonable costs of prosecuting the petitioner's application.

(d) A request to amend an application after it has been designated for random selection pursuant to § 1.972 will be considered only upon written petition addressed to the Chief, Private Radio Bureau and will be granted only for good cause shown. A petition which requests a substantial change in the application or which affects the lottery probabilities of other applicants must be accompanied by a signed statement of a person with knowledge of the relevant facts and must specify with particularity why such change is necessary and whether or not consideration has been promised to or received by the petitioner, directly or indirectly, in connection with the filing of such petition for amendment. If consideration has been promised or received,

the statement shall set forth all the relevant facts with sufficient detail to enable the Chief, Private Radio Bureau to determine whether and to what extent, if any, the consideration represents only the reasonable costs of prosecuting the petitioner's application.

(e) The Commission (or the presiding officer, if the application has been designated for hearing) may, upon its own motion or upon motion of any party to a proceeding, order the applicant to amend the application so as to make the same more definite and certain, and may require an applicant to submit such documents and written statements of fact as in its judgment may be necessary.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

[28 FR 12454, Nov. 22, 1963, as amended at 37 FR 13984, July 15, 1972; 48 FR 27201, June 13, 1983; 49 FR 30944, Aug. 2, 1984]

APPLICATION FORMS AND PARTICULAR FILING REQUIREMENTS

§ 1.921 Procedure for obtaining a radio station authorization and for commencement of operation.

(a) Persons desiring to install and operate radio transmitting equipment should first submit an application for a radio station authorization in accordance with the rules for the particular service. A list of all application forms used by Private Radio Services Bureau is contained in § 1.922. Each form contains appropriate instructions concerning the number of required copies, where it may be filed, and the services in which it is intended to be used.

(b) Each application shall include all information called for by the particular form on which the application is required to be filed unless the information called for is inapplicable, in which case that fact shall be indicated.

(c) In some cases equipment and service tests are required before an authorized station may be placed in regular operation. Reference should be made to the specific service regarding these provisions.

(Sec. 308, 48 Stat. 1084, as amended; 47 U.S.C. 308)

[28 FR 12454, Nov. 22, 1963, as amended at 44 FR 39181, July 5, 1979]

Federal Communications Commission

§ 1.924

§ 1.922 Forms to be used.

FCC form	Title
175	Application To Participate in an FCC Auction.
175-S	Supplemental Application To Participate in an FCC Auction.
402	Application for Microwave Station Authorization in the Safety and Special Radio Services.
402-10	Instructions for Completion of FCC Form 402.
402-A	Annual Report of Licensees of Microwave and Other Fixed Stations When Such Facilities Are Used Cooperatively With Other Persons.
402-R	Renewal Notice and Certification in the Private Operational-Fixed Microwave Radio Services.
404	Application for Aircraft Radio Station License.
404-A	Temporary Aircraft Radio Station Operating Authority.
405-A	Application for Renewal of Station License.
405-B	License Expiration Notice and/or Renewal Application.
406	Application for Ground Station Authorization in the Aviation Services.
410	Registration of Canadian Radio Station Licensee and Application for Permit to Operate.
410-B	Application for Permit To Operate a Canadian General Radio Station in the United States.
452-R	Application for Renewal of Coast and Ground Services.
480	Application for Civil Air Patrol Radio Station Authorization.
490	Application for Assignment or Transfer of Control.
503	Application for Land Radio Station License in the Maritime Services.
506	Application for Ship Radio Station License.
506-A	Temporary Operating Authority, Ship Radio Station License and Restricted Radiotelephone Operator Permit.
525	Application for Disaster Communications Radio Station Construction Permit and License.
572	Temporary Permit To Operate a Business Radio Station.
572C	Conditional Temporary Authorization To Operate a part 90 Radio Station.
574	Application for Radio Station Authorization in the General Mobile Radio Services.
574-R	Application for Renewal of Radio Station License.
574-T	Temporary Permit To Operate a General Mobile Radio Service System.
577	Temporary Permit To Operate a Part 90 Radio Station.
600	Application for Mobile Radio Service Authorization.
610	Application for Amateur Radio Station and/or Operator License.
610-A	Application for Alien Amateur Radio Licensee for Permit To Operate in the United States.
610-B	Application for Amateur Club, Military Recreation, or Radio Amateur Civil Emergency Service Station License.
660-B	Interim Amateur Permit.
602	Application for Consent to Assignment of Radio Station Construction Permit or License (For Stations in Services Other Than Broadcast).
703	Application for Consent To Transfer of Control of Corporation Holding Construction Permit or Station License (For Station in Services Other Than Broadcast).
714	Supplement to Application for New or Modified Radio Station Authorization (Concerning Antenna Structure Notification to FAA).
820	Application for Exemption from Ship Radio Station Requirements.
845	Amateur Code Credit Certificate.
1046	Assignment of Authorization.

(Secs. 4, 5, 303, 308, 48 Stat. 1066, 1068, 1082, 1084, as amended; 47 U.S.C. 154, 155, 303, 308; secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[59 FR 59949, Nov. 21, 1994]

§ 1.923 Waiver of construction permit requirement.

(a) A construction permit is not required for any station in the Private Radio Services. However, certain private radio facilities must be constructed within the time periods specified in part 90. See, however, § 1.1311(c).

(b) Licensees must apply for modification of station license for any antenna change which would be inconsistent with the terms of the station authorization or for which notification is required to be given to the Federal Aviation Administration by that agency. Part 17 of this chapter described the notification criteria.

[34 FR 9283, June 12, 1969, as amended at 48 FR 9271, Mar. 4, 1983]

§ 1.924 Assignment or transfer of control, voluntary and involuntary.

(a)(1) Radio station licenses are not transferable; however, except for those set forth in paragraph (a)(2) of this section, they may be assigned. Licenses may be assigned whenever there is a change of ownership of an authorized radio station, for example, if the radio communication equipment is sold with a business. The new owner must apply for assignment of the existing authorization in accordance with the rules under which the station is authorized.

(2) Licenses for stations in the Amateur, Aviation (aircraft), Personal, and Maritime (ship) Radio Services cannot be assigned. Whenever there is a change of ownership of one of these latter stations, the new owner must apply for a new license. Upon receipt of the new license, the former license must be surrendered for cancellation.

(b)(1) Application for consent to voluntary assignment of a license, or for consent to voluntary transfer of control of a corporation holding a license, must be filed with the Commission at least 60 days prior to the contemplated effective date of assignment or transfer of control.

(2) The following application forms should be used:

§ 1.925

47 CFR Ch. I (10–1–97 Edition)

(i) *FCC Form 600*. For assignment of station authorization in services under part 90 of this chapter, except as provided in subparagraph (ii). Attached thereto shall be an executed Form 1046 or a signed letter from proposed assignor stating the desire to assign the current authorization in accordance with the rules governing the particular radio service involved. Applications for consent to assign authorizations of stations operating in the 806–821 and 851–866 MHz bands shall be accompanied by FCC Form 574–A. Applications for assignment of authorizations for stations operating on frequencies below 27.5 MHz shall be accompanied by FCC Form 574–B.

(ii) *FCC Form 402*. For assignment of station authorizations in the Private Operational Fixed Microwave Service (part 101 of this chapter). Attached thereto shall be an executed Form 1046 or a signed letter from proposed assignor stating the assignor's desire to assign the current authorization in accordance with the rules governing the particular service involved.

(iii) *FCC Form 406*. For assignment of ground station authorizations in the Aviation Services, except as provided in paragraph (b)(2)(ii) of this section.

(iv) *FCC Form 503*. For assignment of coast station authorizations in the Maritime Services and Alaska-Public Fixed Stations.

(v) [Reserved]

(vi) *FCC Form 703*. For consent to transfer control of a corporation holding any type of part 90 license except a license to provide commercial mobile radio service.

(vii) *FCC Form 490*. For consent to transfer control of a corporation holding a part 90 license to provide commercial mobile radio service.

(c)(1) In the event of the death or legal disability of a permittee or licensee, a member of a partnership, or a person directly or indirectly in control of a corporation which is a permittee or licensee, the Commission shall be notified in writing promptly of the occurrence of such death or legal disability.

(2) Within 30 days after the occurrence of such death or legal disability (except in the case of a ship or amateur station), application shall be filed for

consent to involuntary assignment of such permit or license, or for involuntary transfer of control of such corporation, to a person or entity legally qualified to succeed to the foregoing interests under the laws of the place having jurisdiction over the estate involved. The procedure and forms to be followed are the same as those specified in paragraph (b) of this section.

(3) In the case of stations in the Amateur, Aviation (aircraft), Personal, and Maritime (ship) Radio Services, involuntary assignment of licenses will not be made; such licenses shall be surrendered for cancellation upon the death or legal disability of the licensee.

(d) An applicant for voluntary transfer of control or assignment under this section where the subject license was acquired by the transferor or assignor through a system of random selection shall, together with its application for transfer of control or assignment, file with the Commission the associated contracts for sale, option agreements, management agreements, or other documents disclosing the total consideration that the applicant would receive in return for the transfer or assignment of its license. This information should include not only a monetary purchase price, but also any future, contingent, in-kind, or other consideration (e.g., management or consulting contracts either with or without an option to purchase; below-market financing).

(Sec. 310, 48 Stat. 1086, as amended; 47 U.S.C. 310)

[28 FR 12454, Nov. 22, 1963, as amended at 31 FR 2600, Feb. 10, 1966; 36 FR 19439, Oct. 6, 1971; 36 FR 21679, Nov. 12, 1971; 42 FR 8327, Feb. 9, 1977; 44 FR 31651, June 1, 1979; 45 FR 55201, Aug. 19, 1980; 47 FR 57051, Dec. 22, 1982; 48 FR 8455, Mar. 1, 1983; 49 FR 30944, Aug. 2, 1984; 51 FR 2703, Jan. 21, 1986; 59 FR 9101, Feb. 25, 1994; 59 FR 59949, Nov. 21, 1994; 61 FR 26671, May 28, 1996]

§ 1.925 Application for special temporary authorization, temporary permit or temporary operating authority.

(a) A licensee of or an applicant for a station in the Private Radio Services may file either a formal or informal application for a special temporary authority not to exceed 180 days for (1)

operation of a new station or (2) operation of a licensed station in a manner which is beyond the scope of that authorized by the existing license. (See § 1.962 (b)(5) and (f). The nature of the extraordinary circumstance which, in the opinion of the applicant justifies issuance of a special temporary authorization, must be fully described in the request. Information presently on file with the Commission may be included by reference, except the applications for special temporary authority under part 90 must be clear and complete within themselves and shall not rely on any pending applications. Applications for special temporary authority must be filed at least 10 days prior to the proposed operation. Applications filed less than 10 days prior to the proposed operation date will be accepted only upon a showing of good cause. In situations involving the safety of life or property or where equipment has been damaged, a request for special temporary authority may be made by telephone or telegraph provided a properly signed application is filed within 10 days of such request.

(b) [Reserved]

(c) An applicant for an Aircraft Radio Station License may operate the radio station pending issuance of an Aircraft Radio Station License by the Commission for a period of 90 days under a temporary operating authority, evidenced by a properly executed certification made on FCC Form 404-A.

(d) [Reserved]

(e) Unless the FCC otherwise prescribes, an applicant already licensed in the Amateur Radio Service, upon successfully completing the amateur radio operator examination(s) required for a higher class, may operate his/her amateur radio station consistent with the rights and privileges of that higher class for a period of one year from the date of the most recently completed examination(s) for that operator class in accord with the provisions of § 97.35.

(f) An applicant for a Ship Radio station license may operate the radio station pending issuance of the ship station authorization by the Commission for a period of 90 days, under a temporary operating authority, evidenced by a properly executed certification made on FCC Form 506-A.

(g) An applicant for a Business Radio Station license (other than an applicant who seeks to provide commercial mobile radio service as defined in part 20 of this chapter) utilizing an already authorized facility may operate the station for a period of 180 days, under a temporary permit, evidenced by a properly executed certification made on FCC Form 572, after the mailing of a formal application for station license together with evidence of frequency coordination, if required, to the Commission. The temporary operation of stations, other than mobile stations, within the Canadian coordination zone will be limited to stations with a maximum of 5 watts effective radiated power and a maximum antenna height of 20 feet (6.1 meters) above average terrain.

(h) An applicant for a radio station license under part 90, subpart S, of this chapter (other than an applicant who seeks to provide commercial mobile radio service as defined in part 20 of this chapter) to utilize an already existing Specialized Mobile Radio System (SMRS) facility or to utilize an already licensed transmitter may operate the radio station for a period of up to 180 days, under a temporary permit, evidenced by a properly executed certification of FCC Form 572 after the mailing of a formal application for station license, provided that the antenna employed by the control station is a maximum of 20 feet (6.1 meters) above a man-made structure (other than an antenna tower) to which it is affixed.

(i) An applicant for an itinerant station license, an applicant for a new private land mobile radio station license in the frequency bands below 470 MHz and in the one-way paging 929-930 MHz band or an applicant seeking to modify or acquire through assignment or transfer an existing station below 470 MHz or in the one-way paging 929-930 MHz band may operate the proposed station during the pendency of its application for a period of up to 180 days under a conditional permit. Conditional operations may commence upon the filing of a properly completed formal application that complies with § 90.127 if the application, when frequency coordination is required, is accompanied by evidence of frequency coordination in accordance with §§ 90.175

§ 1.926

47 CFR Ch. I (10–1–97 Edition)

and 90.176. Operation under such a permit is evidenced by retaining with the station records the original conditional licensing 572C Certification Form containing the certifications that satisfy the provisions of §90.159(b).

(j) An applicant for a General Mobile Radio Service system license, sharing a multiple-licensed base station used as a mobile relay station, may operate the system for a period of 180 days, under a temporary permit, evidenced by a properly executed certification made on FCC Form 574–T, after mailing FCC Form 574 to the Commission.

(Secs. 4(i), 303, Communications Act of 1934, as amended (47 U.S.C. 154(i) and 303); 47 CFR 1.429)

[28 FR 12454, Nov. 22, 1963, as amended at 47 FR 56637, Dec. 20, 1982; 48 FR 4785, Feb. 3, 1983; 48 FR 24890, June 3, 1983; 48 FR 39072, Aug. 29, 1983; 48 FR 41770, Sept. 19, 1983; 48 FR 45658, Oct. 6, 1983; 49 FR 30312, July 30, 1984; 49 FR 37384, Sept. 24, 1984; 50 FR 37190, Sept. 12, 1985; 51 FR 31304, Sept. 2, 1986; 54 FR 50238, Dec. 5, 1989; 54 FR 51550, Dec. 15, 1989; 59 FR 59949, Nov. 21, 1994]

§ 1.926 Application for renewal of license.

(a) Application for renewal of a station license shall be submitted on the appropriate FCC Form indicated below:

(1) Renewal of station or system authorizations in the Private Land Mobile Radio Services (part 90 of this chapter), the General Mobile Radio Service (part 95, subpart A of this chapter), and the Interactive Video and Data Service (part 95, subpart F of this chapter) shall be submitted on FCC Form 574–R when the licensee has received that Form in the mail from the Commission. If the licensee has not received the Commission-generated Form 574–R within sixty (60) days of expiration, application for renewal of station or system license shall be submitted on FCC Form 405–A.

(2) Renewal of marine coast station authorizations (§80.19 of this chapter) and aviation ground station authorizations (§87.33 of this chapter) must be submitted on FCC Form 452–R.

(3) Renewal of aircraft radio station authorizations and ship radio station authorizations shall be submitted on FCC Form 405–B.

(4) Renewal of an amateur operator license or a combined amateur opera-

tor/station license shall be submitted on FCC Form 610.

(5) Renewal of an amateur club, military recreation, or Radio Amateur Civil Emergency Service (RACES) station license shall be submitted on FCC Form 610–B.

(6) Renewal of station authorizations in the Private Operational Fixed Microwave Service (part 101 of this chapter) shall be submitted on such form as the Commission may designate by the public notice in accordance with the provisions of §101.13 of this chapter.

(b) All applications for renewal of license must be made during the license term and should be filed within 90 days but not later than 30 days prior to the end of the license term. In any case in which the licensee has, in accordance with the provisions of this chapter, made timely and sufficient application for renewal of license, no license with reference to any activity of a continuing nature shall expire until such application shall have been finally determined.

(c) Reinstatement of an expired license in the Private Land Mobile Radio Services may be requested up to thirty (30) days after the expiration date using FCC Form 574, 574–R or 405–A. See §1.4.

(Secs. 4, 5, 303, 307, 308, 48 Stat., as amended, 1066, 1068, 1082, 1083, 1084; 47 U.S.C. 154, 155, 303, 307, 308)

[28 FR 12454, Nov. 22, 1963, as amended at 29 FR 3229, Mar. 11, 1964; 48 FR 36105, Aug. 9, 1983; 56 FR 64715, Dec. 12, 1991; 56 FR 65858, Dec. 19, 1991; 57 FR 8274, Mar. 9, 1992; 61 FR 26671, May 28, 1996]

§ 1.931 Requests for waiver of private radio rules.

(a) All requests for waiver of the rules governing the Private Radio Services that require a fee (see §1.1102) shall be submitted to the Mellon Bank, Pittsburgh, Pennsylvania at the address set forth in §1.1102. Waiver requests that do not require a fee must be addressed to: Federal Communications Commission, 1270 Fairfield Road, Gettysburg, Pennsylvania 17325–7245. Waiver requests attached to applications must be submitted in accordance with §0.401(b) of the rules.

Federal Communications Commission

§1.952

(b) Applicants requiring expeditious processing of their request for waiver shall clearly caption both their request for waiver and the envelope containing it with the words “WAIVER—TIMELY ACTION REQUESTED.”

(Sec. 4(i), Communications Act of 1934, as amended, 47 U.S.C. 154(i); 47 CFR 0.231)

[49 FR 20291, May 14, 1984, as amended at 52 FR 10229, Mar. 31, 1987; 55 FR 19154, May 8, 1990; 56 FR 64715, Dec. 12, 1991]

§1.933 Installation or removal of apparatus.

(a) In the Public Safety, Industrial, and Land Transportation Radio Services, replacement of transmitting equipment may be made without prior authorization: *Provided*, The replacement transmitter appears in the Commission’s “Radio Equipment List, Part C” as designated for use in the Public Safety, Industrial, and Land Transportation Radio Services, and the substitute equipment employs the same type of emission and does not exceed the power limitation as set forth in the station authorization.

(b) In the Personal Radio Services, replacement of transmitting equipment may be made without prior authorization if: (1) The replacement transmitter appears in the Commission’s “Radio Equipment List,” as designated for use in the Personal Radio Service, or (2) the replacement transmitter is for an R/C station, operates on frequencies assigned for R/C station use and complies with the technical standards of part 95, subpart E.

[28 FR 12454, Nov. 22, 1963, as amended at 48 FR 24890, June 3, 1983]

§1.934 Procedure with respect to amateur radio operator license.

Each candidate for an amateur radio license which requires the applicant to pass one or more examination elements must present the examiner(s) with a properly completed FCC Form 610 prior to the examination. Upon completion of the examination, the examiner(s) will immediately grade the test papers. If the applicant is successful, the examiner(s) will forward the candidate’s application to: (a) The Commission’s Gettysburg, Pennsylvania facility for an application for a Novice Class oper-

ator license, or (b) a Volunteer-Examiner Coordinator (VEC) for all other classes of operator licenses. The examiners will then issue a certificate for successful completion of an amateur radio operator examination. A VEC will forward the application to the Commission’s Gettysburg, Pennsylvania facility.

[48 FR 45658, Oct. 6, 1983]

APPLICATION PROCESSING PROCEDURES

§1.951 How applications are distributed.

Licensing Division. All applications for radio stations are distributed as follows:

(a) *Special Services Branch.*

(1) All Aviation Radio Services and Maritime Radio Services applications.

(2) Personal Radio Services applications:

Amateur, General Mobile, and Interactive Video and Data

(b) *Land Mobile Branch.* (1) Industrial Radio Services applications:

Business, Forest Products, Industrial Radio-location, Manufacturers, Motion Picture, Petroleum, Power, Relay Press, Special Industrial and Telephone Maintenance

(2) Land Transportation Radio Services applications:

Motor Carrier, Railroad, Taxicab, and Automobile Emergency

(3) Public Safety Radio Services applications:

Fire, Forestry-Conservation, Highway Maintenance, Local Government, and Police

(4) Special Emergency Radio Services applications:

Medical services, rescue organizations, physically handicapped, veterinarians, disaster relief organizations, school buses, beach patrols, establishments in isolated areas, communications standby facilities

(c) *Microwave Branch.* Operational fixed point-to-point and point-to-multipoint applications.

[49 FR 30944, Aug. 2, 1984, as amended at 57 FR 8274, Mar. 9, 1992]

§1.952 How file numbers are assigned.

(a) File numbers are assigned to certain categories of applications by the Private Radio Bureau.

(b) File number symbols and service or class of station designators:

§ 1.952

AMATEUR AND DISASTER SERVICES

Y—Amateur
D—Disaster
R—Races

AVIATION SERVICES

A—Aeronautical and fixed group
AA—Aviation auxiliary group
AR—Aviation radionavigation land
AC—Civil Air Patrol

PERSONAL RADIO SERVICE

CA—General Mobile Radio Service
ZA—General Mobile Radio Service
ZV—Interactive Video and Data Service

MARINE SERVICES

MK—Alaskan group
M—Coastal group
MA—Marine auxiliary group
MR—Marine radiodetermination land

MICROWAVE SERVICES

OF—Private Operational-Fixed Microwave

RADIOLOCATION SERVICE

RS—Radiolocation

LAND MOBILE SERVICES BELOW 800 MHZ

IG—Conventional Industrial/Business Pool
PW—Conventional Public Safety Pool
YG—Trunked Industrial/Business Pool
YW—Trunked Public Safety Pool

800 MHZ SERVICES

GB—Conventional Business
GO—Conventional Industrial/Land Transportation
GP—Conventional Public Safety/Special Emergency
GX—Conventional Commercial (SMRS)
YB—Trunked Business
YO—Trunked Industrial/Land Transportation
YP—Trunked Public Safety/Special Emergency
YX—Trunked Commercial (SMRS)

900 MHZ PAGING SERVICES

GS—Private carrier paging systems

(c) Application or authorization designator symbols:

P—Construction Permit.
MP—Modified CP.
MP/L—Modified CP and License.
MP/ML—Modified CP and Modified License.
AP—Assignment of Permit.
L—License.
ML—Modified License.
AL—Assignment of License.
P/L—Combination CP and License.
R—Renewed License.

47 CFR Ch. I (10–1–97 Edition)

TC—Transfer of Control.

[28 FR 12454, Nov. 22, 1963, as amended at 49 FR 30945, Aug. 2, 1984; 57 FR 8274, Mar. 9, 1992; 62 FR 18843, Apr. 17, 1997]

EFFECTIVE DATE NOTE: At 62 FR 18843, Apr. 17, 1997, paragraph (b) was revised, effective Oct. 17, 1997. For the convenience of the user, the superseded text is set forth as follows:

§ 1.952 How file numbers are assigned.

* * * * *

(b) File number symbols and service or class of station designators:

AMATEUR AND DISASTER SERVICES

Y—Amateur
D—Disaster
R—Races

AVIATION SERVICES

A—Aeronautical and fixed group
AA—Aviation auxiliary group
AR—Aviation radionavigation land
AC—Civil Air Patrol

PERSONAL RADIO SERVICES

CA—General Mobile Radio Service
ZA—General Mobile Radio Service
ZV—Interactive Video and Data Service

INDUSTRIAL SERVICES

IB—Business
IF—Forest products
IX—Manufacturers
IM—Motion picture
IP—Petroleum
IY—Relay press
IS—Special industrial
IT—Telephone maintenance
IW—Power

LAND TRANSPORTATION SERVICES

LA—Automobile emergency
LI—Interurban passenger
LJ—Interurban property
LR—Railroad
LX—Taxicab
LU—Urban passenger
LV—Urban property

MARINE SERVICES

MK—Alaskan group
M—Coastal group
MA—Marine auxiliary group
MR—Marine radiodetermination land

MICROWAVE SERVICES

OF—Private Operational-Fixed Microwave

PUBLIC SAFETY SERVICES

PF—Fire
PO—Forestry conservation

Federal Communications Commission

§ 1.955

PH—Highway maintenance		MHz
PL—Local government		
PP—Police	30.56–32.00	75.40–76.00
PS—Special emergency	33.00–34.00	150.80–174.00
	35.00–36.00	450–470
	37.00–38.00	806.00–960.00
	39.00–40.00	1850.0–2200.0
	42.00–46.00	2450.0–2690.0
	47.00–49.60	3700.0–4200.0
	72.00–73.00	5925.0–7125.0

RADIOLOCATION SERVICE

RS—Radiolocation

800 MHz SERVICES

GB—Conventional Business

GO—Conventional Industrial/Land Transportation

GP—Conventional Public Safety/Special Emergency

GX—Conventional Commercial (SMRS)

YB—Trunked Business

YO—Trunked Industrial/Land Transportation

YP—Trunked Public Safety/Special Emergency

YX—Trunked Commercial (SMRS)

900 MHz PAGING SERVICES

GS—Private carrier paging systems

* * * * *

§ 1.953 How applications are processed.

(a) Applications are processed in sequence according to date of filing, or pursuant to the system of random selection prescribed in § 1.972 of this part. Applications which are in accordance with the provisions of this chapter and established policies of the Commission may be processed to completion in accordance with the applicable delegations of authority as set forth in part O of this chapter.

(b) [Reserved]

[48 FR 27201, June 13, 1983 and 51 FR 2703, Jan. 21, 1986]

§ 1.955 Frequency coordination, Canada.

(a) As a result of mutual agreements, the Commission has, since May 1950 had an arrangement with the Canadian Department of Communications for the exchange of frequency assignment information and engineering comments on proposed assignments along the Canada-United States borders in certain bands above 30 MHz. Except as provided in paragraph (b) of this section, this arrangement involves assignments in the following frequency bands.

GHZ

10.55–10.68 10.70–13.25

(b) The following frequencies are not involved in this arrangement because of the nature of the services:

MHz

156.3 156.9
156.35 156.95
156.4 157.0 and 161.6
156.45 157.05
156.5 157.1
156.55 157.15
156.6 157.20
156.65 157.25
156.7 157.30
156.8 157.35
156.8 157.40.

(c) Assignments proposed in accordance with the railroad industry radio frequency allotment plan along the United States-Canada borders utilized by the Federal Communications Commission and the Department of Transport, respectively, may be excepted from this arrangement at the discretion of the referring agency.

(d) Assignments proposed in any radio service in frequency bands below 470 MHz appropriate to this arrangement, other than those for stations in the Domestic Public (land mobile or fixed) category, may be excepted from this arrangement at the discretion of the referring agency if a base station assignment has been made previously under the terms of this arrangement or prior to its adoption in the same radio service and on the same frequency and in the local area, and provided the basic characteristics of the additional station are sufficiently similar technically to the original assignment to preclude harmful interference to existing stations across the border.

(e) For bands below 470 MHz, the areas which are involved lie between Lines A and B and between Lines C and D, which are described as follows:

§ 1.958

47 CFR Ch. I (10–1–97 Edition)

Line A— Begins at Aberdeen, Wash., running by great circle arc to the intersection of 48° N., 120° W., thence along parallel 48° N., to the intersection of 95° W., thence by great circle arc through the southernmost point of Duluth, Minn., thence by great circle arc to 45° N., 85° W., thence southward along meridian 85° W., to its intersection with parallel 41° N., thence along parallel 41° N., to its intersection with meridian 82° W., thence by great circle arc through the southernmost point of Bangor, Maine, thence by great circle arc through the southernmost point of Searsport, Maine, at which point it terminates; and

Line B— Begins at Tofino, B.C., running by great circle arc to the intersection of 50° N., 125° W., thence along parallel 50° N., to the intersection of 90° W., thence by great circle arc to the intersection of 45° N., 79°30' W., thence by great circle arc through the northernmost point of Drummondville, Quebec (lat: 45°52' N., long: 72°30' W.), thence by great circle arc to 48°30' N., 70° W., thence by great circle arc through the northernmost point of Campbellton, N.B., thence by great circle arc through the northernmost point of Liverpool, N.S., at which point it terminates.

Line C— Begins at the intersection of 70° N., 144° W., thence by great circle arc to the intersection of 60° N., 143° W., thence by great circle arc so as to include all of the Alaskan Panhandle; and

Line D— Begins at the intersection of 70° N., 138° W., thence by great circle arc to the intersection of 61°20' N., 139° W., (Burwash Landing), thence by great circle arc to the intersection of 60°45' N., 135° W., thence by great circle arc to the intersection of 56° N., 128° W., thence south along 128° meridian to Lat. 55° N., thence by great circle arc to the intersection of 54° N., 130° W., thence by great circle arc to Port Clements, thence to the Pacific Ocean where it ends.

(f) For all stations using bands between 470 MHz and 1000 MHz; and for any station of a terrestrial service using a band above 1000 MHz, the areas which are involved are as follows:

(1) For a station the antenna of which looks within the 200° sector toward the Canada-United States borders, that area in each country within 35 miles of the borders;

(2) For a station the antenna of which looks within the 160° sector away from the Canada-United States borders, that area in each country within 5 miles of the borders; and

(3) The area in either country within coordination distance as described in Recommendation 1A of the Final Acts of the EARC, Geneva, 1963 of a receiv-

ing earth station in the other country which uses the same band.

(g) Proposed assignments in the space radiocommunication services and proposed assignments to stations in frequency bands allocated coequally to space and terrestrial services above 1 GHz are not treated by these arrangements. Such proposed assignments are subject to the regulatory provisions of the International Radio Regulations.

(h) Assignments proposed in the frequency band 806–890 MHz shall be in accordance with the Canada-United States agreement, dated April 7, 1982.

[35 FR 6752, Apr. 29, 1970, as amended at 36 FR 19440, Oct. 6, 1971; 47 FR 57051, Dec. 22, 1982; 48 FR 8455, Mar. 1, 1983]

§ 1.958 Defective applications.

(a) Applications will be considered defective if:

(1) The applicant is disqualified by statute.

(2) The proposed use or purpose of the station applied for would be unlawful.

(3) The frequency applied for is not allocated to the service proposed.

(4) The application form is not signed in accordance with § 1.913 of these rules.

(5) The application is not complete with respect to answers, supplementary statements, execution or other matters of a formal character.

(6) The application is not in accordance with the Commission's rules or requirements and is not accompanied either by (i) a petition to amend any rule or regulation with which the application is in conflict, or (ii) a request by the applicant for waiver of any rule or requirement with which the application is in conflict. A request for rule amendment or waiver must show the nature of the amendment or waiver requested and set forth the reasons in support of it. Requests for waiver must state the nature of the waiver or exception desired and set forth reasons in support thereof including a showing that unique circumstances are involved and that there is no reasonable alternative solution within existing rules.

(7) The applicant is requested by the Commission to file any additional documents or information not included in the prescribed form and the applicant

Federal Communications Commission

§ 1.962

fails to comply with the Commission's request.

(b) An application which is defective on its face will not be accepted for filing and will be dismissed.

(c) An application which is accepted for filing, but which is later determined to be defective, will be dismissed.

[49 FR 30945, Aug. 2, 1984, as amended at 54 FR 38995, Sept. 22, 1989]

§ 1.959 Resubmitted applications.

Any application for frequencies below 470 MHz which has been returned to the applicant for correction will be processed in its original position in the processing line if it is resubmitted and received by the Commission's offices in Gettysburg, PA within 60 days from the date on which it was returned to the applicant. Otherwise it will be treated as a new application and require an additional fee as set forth in part 1, subpart G of this chapter. An application for frequencies above 470 MHz which has been returned to the applicant will be processed in its original position in the processing line if it is resubmitted and received by the Commission's offices in Gettysburg, PA within 30 days (45 days outside the continental United States) from the date on which it was returned to the applicant. Otherwise it will be treated as a new application and require an additional fee as set forth in part 1, subpart G of this chapter.

[52 FR 10230, Mar. 31, 1987]

§ 1.961 Dismissal of applications.

(a) Any application may, upon written request signed by the applicant or his attorney, be dismissed without prejudice as a matter of right prior to the designation of such application for hearing.

(b) Failure to prosecute an application, or failure to respond to official correspondence or request for additional information, will be cause for dismissal. Such dismissal will be without prejudice where an application has not yet been designated for hearing; such dismissal may be with prejudice after an application has been designated for hearing.

(c) Requests to dismiss an application without prejudice after it has been designated for hearing will be considered only upon written petition properly served upon all parties of record and will be granted only for good cause shown. Such petition must be accompanied by a written and signed statement of a person with knowledge of the facts as to whether or not consideration has been promised to or received by petitioner, directly or indirectly, in connection with the filing of such petition for dismissal of the application.

§ 1.962 Public notice of acceptance for filing; petitions to deny applications of specified categories.

(a) Except as qualified in paragraph (b) of this section, the provisions of this section shall apply to all applications for authorizations, and substantial amendments thereof, for the following categories of stations and services:

(1) Industrial radiopositioning stations for which frequencies are assigned on an exclusive basis.

(2) Aeronautical enroute stations.

(3) Aeronautical advisory stations.

(4) Airport control tower stations.

(5) Aeronautical fixed stations.

(6) Public coast stations, excluding those located in Alaska which will not render service for hire.

(b) The provisions of this section are not applicable to applications for the type of authorizations listed in this paragraph.

(1) A minor change in the facilities of an authorized station or a minor amendment of an application on file.

(2) Consent to an involuntary assignment or transfer under section 310(b) of the Communications Act or to a voluntary assignment or transfer thereunder which does not involve a substantial change in ownership or control.

(3) A license under section 319(c) of the Communications Act or, pending application for or grant of such license, any special or temporary authorization to permit interim operation to facilitate completion of authorized construction or to provide substantially the same service as would be authorized by such licensee.

(4) Extension of time to complete construction of authorized facilities.

(5) A special temporary authorization not to exceed 30 days where the applicant does not contemplate the filing of an application for regular operation, or not to exceed 60 days pending or after the filing of an application for regular operation.

(6) An authorization under any of the proviso clauses of section 308(a) of the Communications Act.

(c) For the purposes of this section, a substantial amendment of an application on file and applications for a substantial change in the facilities of an authorized station shall be:

(1) Any addition or change in frequency (except deletion of a frequency);

(2) Any change in antenna azimuth;

(3) Any change in antenna beam width;

(4) Any change in antenna location greater than 5 seconds;

(5) Any change in antenna location of less than 5 seconds but also involving a requirement for special aeronautical study;

(6) Any change in emission;

(7) Any increase in antenna height;

(8) Any increase in authorized power in excess of a 2 to 1 ratio;

(9) Any increase in emission bandwidth.

(d) All amendments of an application on file and all changes requested in the facilities of an authorized station other than those amendments and modifications listed in paragraph (c) of this section shall be considered minor.

(e) The Commission will issue at regular intervals Public Notices listing all applications subject to this section which have been received by the Commission in a condition acceptable for filing, or have been returned to an applicant for correction, within the 30-day public notice period. They will relist any application which has been amended substantially since its previous listing, or which has been resubmitted to the Commission, after public notice of the return of the application to an applicant, pursuant to § 1.959. Such acceptance for filing shall not preclude the subsequent dismissal of an application as defective.

(f) No application subject to the provisions of this section, as originally filed or substantially amended, will be granted by the Commission prior to the 31st day following the issuance of public notice of the acceptance for filing of such application or of any substantial amendment thereof; *Provided, however,* That the Commission, notwithstanding the requirements of this paragraph, may, if the grant of such application is otherwise authorized by law:

(1) Grant requests for special temporary authorization for periods not exceeding 180 days, accompanied by a statement of the reasons therefor, if it finds that there are extraordinary circumstances requiring temporary operations in the public interest and that delay in institution of such operations would seriously prejudice the public interest, and

(2) Extend such temporary authorizations for additional periods not exceeding 180 days each, upon a finding of continued extraordinary circumstances requiring temporary operations in the public interest.

(g) Any party in interest may file with the Commission a petition to deny any application, whether as filed originally or as subsequently amended by a substantial amendment as defined in paragraph (c) of this section, subject to the provisions of this section, no later than 30 days after the date of the public notice listing the application, or substantial amendment to the application, as having been accepted for filing. Such petitions must be filed with the Commission's offices in Gettysburg, Pennsylvania. Address them to: Federal Communications Commission, 1270 Fairfield Road, Gettysburg, Pennsylvania 17325-7245. A petitioner shall serve a copy of such petition on the applicant. A petition shall contain specific allegations of fact sufficient to make a prima facie showing that the petitioner is a party in interest and that a grant of the application would be inconsistent with the public interest, convenience and necessity. Such allegations of fact, except for those of which official notice may be taken, shall be supported by affidavit of a person or persons with personal knowledge thereof.

Federal Communications Commission

§1.972

(h) The applicant may file an opposition to any petition to deny and the petitioner may file a reply thereto (see §1.45) in which allegations of fact or denials thereof, except for those of which official notice may be taken, shall be supported by affidavit of a person or persons with personal knowledge thereof. The applicant shall serve a copy of his opposition on the petitioner, and the petitioner shall serve a copy of his reply on the applicant.

(Sec. 309, 48 Stat. 1085, as amended; 47 U.S.C. 309)

[28 FR 12454, Nov. 22, 1963, as amended at 29 FR 7822, June 19, 1964; 30 FR 4479, Apr. 7, 1965; 36 FR 19440, Oct. 6, 1971; 48 FR 1973, Jan. 17, 1983; 49 FR 30945, Aug. 2, 1984; 49 FR 36376, Sept. 17, 1984; 51 FR 2703, Jan. 21, 1986; 53 FR 28940, Aug. 1, 1988; 54 FR 10327, Mar. 13, 1989; 55 FR 10462, Mar. 21, 1990; 56 FR 64715, Dec. 12, 1991; 61 FR 26671, May 28, 1996]

ACTION ON APPLICATIONS

AUTHORITY: Sections 1.971 through 1.973 are issued under sec. 309, 48 Stat. 1085, as amended; 47 U.S.C. 309.

§1.971 Grants without a hearing.

(a) The Commission will grant without a hearing an application for a station authorization if it is proper upon its face and if the Commission finds from an examination of such application and supporting data, any pleading filed, or other matters which it may officially notice, that:

(1) There are no substantial and material questions of fact;

(2) The applicant is legally, technically, financially, and otherwise qualified;

(3) A grant of the application would not involve modification, revocation, or non-renewal of any existing license;

(4) A grant of the application would not preclude the grant of any mutually exclusive application; and

(5) A grant of the application would serve the public interest, convenience, and necessity.

(b) If a petition to deny an application has been filed pursuant to §1.962 and the Commission grants such application pursuant to paragraph (a) of this section, the Commission will deny the petition and issue a concise statement of the reason for such denial and

disposing of all substantial issues raised by the petition.

[28 FR 12454, Nov. 22, 1963, as amended at 49 FR 30946, Aug. 2, 1984]

§1.972 Grants by random selection.

(a) The provisions of this section, including provisions incorporated by reference, may apply to applications for initial licenses:

(1) For stations in the following Private Radio Services:

Part 80—Stations in the Maritime Services
Part 87—Aviation Services
Part 90—Private Land Mobile Services
Part 95—Subpart F—Personal Radio Services
Part 101—Subpart H—Private Operational Fixed Point-to-Point Microwave Service.

(2) In any other proceedings in the Private Radio Services in which the Commission determines that there is no material difference in competing applicants' abilities to serve the public interest.

(b) Applications in the services specified above shall be tendered, filed, accepted or dismissed, publicly noted, and subject to Petitions to Deny in accordance with §1.962 and the rules and policies established for each respective service.

(c) If there are mutually exclusive applications for an initial license for stations subject to part 80 or part 87 of this chapter, or if there are more applications for an initial license in part 90, part 95-subpart F, or part 101-subpart H of this chapter, than can be accommodated on available frequencies, the Commission may process the applications pursuant to a system of random selection. Each such random selection shall be conducted pursuant to an order issued by the Wireless Telecommunications Bureau and under the direction of the Chief of the Bureau.

(d) Expedited hearing proceedings may be used to apply comparative criteria to determine which applications will be granted, denied or subjected to random selection. The selection percentages, preferences, and probability calculations prescribed in §1.1621 *et seq.* of this part are not applicable to any system of random selection conducted in the Private Radio Bureau. Following the random selection, the Commission will announce the tentative selectee and determine whether the tentative

§ 1.973

selectee is qualified to receive the license under the rules applicable to the respective service. Where authorized under § 1.962, Petitions to Deny which have been filed against the tentative selectee before the random selection will be reviewed and processed prior to grant, in accordance with § 1.962 and rules applicable to each respective service. If the Commission determines that the tentative selectee has satisfied all requirements, it will grant the application. If it is determined that an initial tentative selectee is not qualified to receive the license grant, another tentative selectee chosen from among the same applicant pool during the same random selection will be designated until a qualified applicant is determined. If the Commission determines that a substantial and material question of fact exists, it will designate the question for hearing. Hearings may be conducted by the Commission or the Chief of the Private Radio Bureau, or, in the case of a question which requires oral testimony for its resolution, an Administrative Law Judge.

[48 FR 27201, June 13, 1983, as amended at 48 FR 43330, Sept. 23, 1983; 49 FR 30946, Aug. 2, 1984; 50 FR 4650, Feb. 1, 1985; 51 FR 31304, Sept. 2, 1986; 57 FR 8274, Mar. 9, 1992; 59 FR 24957, May 13, 1994; 61 FR 26671, May 28, 1996]

§ 1.973 Designation for hearing.

(a) If the Commission is unable to make the findings prescribed in § 1.971(a) and does not utilize the system of random selection prescribed in § 1.972 of this part, it will formally designate the application for hearing on the grounds or reasons then obtaining and will notify the applicant and all other known parties in interest of such action.

(b) Orders designating applications for hearing will specify with particularity the matters in issue.

(c) Parties in interest, if any, who are not notified by the Commission of its action in designating a particular application for hearing may acquire the status of a party to the proceeding by filing a petition for intervention showing the basis of their interest not more than 30 days after publication in the FEDERAL REGISTER of the hearing is-

47 CFR Ch. I (10–1–97 Edition)

sues or any substantial amendment thereto.

(d) The applicant and all other parties in interest shall be permitted to participate in any hearing subsequently held upon such applications. Hearings may be conducted by the Commission or by the Chief of the Private Radio Bureau, or, in the case of a question which requires oral testimony for its resolution, an Administrative Law Judge. The burden of proceeding with the introduction of evidence and burden of proof shall be upon the applicant, except that with respect to any issue presented by a Petition to Deny or a petition to enlarge the issues, such burdens shall be as determined by the Commission or the Chief of the Private Radio Bureau.

[48 FR 27202, June 13, 1983]

REPORTS TO BE FILED WITH THE COMMISSION

§ 1.981 Reports, annual and semi-annual.

(a) Licensees of stations authorized for developmental operation shall submit a report on the results of the developmental program. The report shall be filed with and made a part of each application for renewal of authorization.

(b) The report shall include comprehensive and detailed information on the following:

- (1) The final objective.
- (2) Results of operation to date.
- (3) Analysis of the results obtained.
- (4) Copies of any published reports.
- (5) Need for continuation of the program.
- (6) Number of hours of operation on each frequency.

(c) Where required by the particular service rules, licensees who have entered into agreements with other persons for the cooperative use of radio station facilities must submit annually an audited financial statement reflecting the nonprofit cost-sharing nature of the arrangement to the Commission's offices in Washington, D.C., no later than three months after the close of the licensee's fiscal year.

Federal Communications Commission

§ 1.1102

Subpart G—Schedule of Statutory Charges and Procedures for Payment

SOURCE: 52 FR 5289, Feb. 20, 1987, unless otherwise noted.

§ 1.1101 Authority.

Authority to impose and collect these charges is contained in title III, section 3001 of the Omnibus Budget Reconciliation Act of 1989 (Pub. L. 101–

239), revising 47 U.S.C. 158, which directs the Commission to prescribe charges for certain of the regulatory services it provides to many of the communications entities within its jurisdiction. This law revises section 8 of the Communications Act of 1934, as amended, which contains a Schedule of Charges as well as procedures for modifying and collecting these charges.

[55 FR 19155, May 8, 1990]

§ 1.1102 Schedule of charges for applications and other filings in the wireless telecommunications services.

Action	FCC Form No.	Fee amount	Payment type code	Address
1. Marine Coast Radio Service:				
a. New, Renewal	503	105	PBMR	Federal Communications Commission, Marine Coast Service, P.O. Box 358265, Pittsburgh, PA 15251–5265.
b. Modification, Assignment, Nonprofit, (CMRS) Public Coast/New, Modification, Renewal.	503	90	PBMM	Federal Communications Commission, Marine Coast Service, P.O. Box 358770, Pittsburgh, PA 15251–5770.
c. Automated Renewal	452R	105	PBMR	Federal Communications Commission, Marine Coast Renewal, P.O. Box 358270, Pittsburgh, PA 15251–5270.
2. Aviation Ground Radio Service:				
a. New, Renewal	406	105	PBVR	Federal Communications Commission, Aviation Ground Service, P.O. Box 358260, Pittsburgh, PA 15251–5260.
b. Modification, Assignment, Nonprofit.	406	90	PBVM	Federal Communications Commission, Aviation Ground Service, P.O. Box 358765, Pittsburgh, PA 15251–5765.
c. Automated Renewal	452R	105	PBVR	Federal Communications Commission, Aviation Ground Renewal, P.O. Box 358270, Pittsburgh, PA 15251–5270.
3. Ship Radio Service:				
a. New, Renewal	506	75	PASR	Federal Communications Commission, Ship Radio Service, P.O. Box 358275, Pittsburgh, PA 15251–5275.
b. Modification, Nonprofit	506	45	PASM	Federal Communications Commission, Ship Radio Service, P.O. Box 358775, Pittsburgh, PA 15251–5775.
c. Exemption from Ship Station Requirement.	820	130	PDWM	Federal Communications Commission, Waiver Requests, P.O. Box 358300, Pittsburgh, PA 15251–5300.
d. Automated Renewal	405B	75	PASR	Federal Communications Commission, Marine Ship Renewal, P.O. Box 358290, Pittsburgh, PA 15251–5290.
4. Aircraft Radio Service:				
a. New, Renewal	404	75	PAAR	Federal Communications Commission, Aircraft Radio Service, P.O. Box 358280, Pittsburgh, PA 15251–5280.
b. Modification, Nonprofit	404	45	PAAM	Federal Communications Commission, Aircraft Radio Service, P.O. Box 358780, Pittsburgh, PA 15251–5780.
c. Automated Renewal	405B	75	PAAR	Federal Communications Commission, Aviation Aircraft Renewal, P.O. Box 358290, Pittsburgh, PA 15251–5290.
5. Private Operational Fixed Microwave Radio Service:				
a. New, Renewal	402	225	PEOR	Federal Communications Commission, Operational Fixed Microwave Service, P.O. Box 358250, Pittsburgh, PA 15251–5250.

Action	FCC Form No.	Fee amount	Payment type code	Address
b. Modification, Assignment, Nonprofit.	402	190	PEOM	Federal Communications Commission, Operational Fixed Microwave Service, P.O. Box 358760, Pittsburgh, PA 15251–5760.
c. Automated Renewal	402R	225	PEOR	Federal Communications Commission, Operational Fixed Microwave Service Renewal, P.O. Box 358255, Pittsburgh, PA 15251–5255.
6. Land Mobile Radio Services:				
a. Land Transportation Services:				
(1) New, Renewal, Reinstatement.	600	60	PALR	Federal Communications Commission, Land Transportation Services, P.O. Box 358215, Pittsburgh, PA 15251–5215.
(2) Modification, Assignment, Nonprofit.	600	45	PALM	Federal Communications Commission, Land Transportation Services, P.O. Box 358730, Pittsburgh, PA 15251–5730.
b. Business Radio Service:				
(1) (PMRS) New, Renewal, Reinstatement.	600	60	PALR	Federal Communications Commission, Business Radio Service, P.O. Box 358220, Pittsburgh, PA 15251–5520.
(2) Modification, Assignment, Nonprofit, and (CMRS) New, Renewal, Reinstatement.	600, 490	45	PALM	Federal Communications Commission, Business Radio Service, P.O. Box 358735, Pittsburgh, PA 15251–5735.
c. Other Industrial Services:				
(1) New, Renewal, Reinstatement.	600	60	PALR	Federal Communications Commission, Other Industrial Services, P.O. Box 358225, Pittsburgh, PA 15251–5225.
(2) Modification, Assignment, Nonprofit.	600	45	PALM	Federal Communications Commission, Other Industrial Services, P.O. Box 358740, Pittsburgh, PA 15251–5740.
d. 800 Megahertz Services:				
(1) (PMRS) New, Renewal, Reinstatement.	600	80	PALS	Federal Communications Commission, 800 Megahertz Services, P.O. Box 358235, Pittsburgh, PA 15251–5235.
(2) Modification, Assignment, Nonprofit and (CMRS) New, Renewal Reinstatement.	600, 490	45	PALM	Federal Communications Commission, 800 Megahertz Services, P.O. Box 358750, Pittsburgh, PA 15251–5750.
e. 900 Megahertz Service:				
(1) (PMRS) New, Renewal, Reinstatement.	600	80	PALS	Federal Communications Commission, 900 Megahertz Services, P.O. Box 358240, Pittsburgh, PA 15251–5240.
(2) Modification, Assignment, Nonprofit and (CMRS) New, Renewal, Reinstatement.	600, 490	45	PALM	Federal Communications Commission, 900 Megahertz Services, P.O. Box 358755, Pittsburgh, PA 15251–5755.
f. 470–512 Megahertz Service:				
(1) (PMRS) New, Renewal, Reinstatement.	600	80	PALS	Federal Communications Commission, 470–512 Megahertz Service, P.O. Box 358810, Pittsburgh, PA 15251–5810.
(2) Modification, Assignment, Nonprofit and (CMRS) New, Renewal, Reinstatement.	600, 490	45	PALM	Federal Communications Commission, 470–512 Megahertz Service, P.O. Box 358815, Pittsburgh, PA 15251–5815.
g. 220 Megahertz Service (Local):				
(1) (PMRS) New, Renewal, Reinstatement.	600	80	PALS	Federal Communications Commission, 200 Megahertz Service (Local), P.O. Box 358360, Pittsburgh, PA 15251–5360.
(2) Modification, Assignment, Nonprofit and (CMRS) New, Renewal, Reinstatement.	600, 490	45	PALM	Federal Communications Commission, 220 Megahertz Service (Local), P.O. Box 358790, Pittsburgh, PA 15251–5790.
h. 220 Megahertz Service (Nationwide):				
(1) (PMRS) New, Renewal, Reinstatement.	600	115	PALT	Federal Communications Commission, 220 Megahertz Service (Nationwide), P.O. Box 358820, Pittsburgh, PA 15251–5820.
(2) Modification, Assignment, Nonprofit and (CMRS) New, Renewal, Reinstatement.	600, 490	45	PALM	Federal Communications Commission, 220 Megahertz Service (Nationwide), P.O. Box 358825, Pittsburgh, PA 15251–5825.

Federal Communications Commission

§ 1.1102

Action	FCC Form No.	Fee amount	Payment type code	Address
i. BUS, OI, LT, GMRS, 470–512, 800, 900, 220 (Local), 220 (Nationwide)-Nonprofit Renewal; and PS/SE (for profit).	574R/405A	45	PALM	Federal Communications Commission, 574R/405A Station Renewal, P.O. Box 358245, Pittsburgh, PA 15251–5245.
j. BUS, OI, LT, GMRS, Renewal.	574R/405A	60	PALR	Federal Communications Commission, 574R/405A Station Renewal, P.O. Box 358245, Pittsburgh, PA 15251–5245.
k. IVDS Renewal (Nonprofit)	574R/405A	45	PAIM	Federal Communications Commission, 574R/405A Station Renewal, P.O. Box 358245, Pittsburgh, PA 15251–5245.
l. IVDS Renewal	574R/405A	115	PAIR	Federal Communications Commission, 574R/405A Station Renewal, P.O. Box 358245, Pittsburgh, PA 15251–5245.
m. 220 (Nationwide) Renewal.	574R/405A	115	PALT	Federal Communications Commission, 574R/405A Station Renewal, P.O. Box 358245, Pittsburgh, PA 15251–5245.
n. 470–512, 800, 900, 220 (Local) Renewal.	574R/405A	80	PALS	Federal Communications Commission, 574R/405A Station Renewal, P.O. Box 358245, Pittsburgh, PA 15251–5245.
7. Finders Preference	159 & Corres	130	PDXM	Federal Communications Commission, Finders Preference, P.O. Box 358305, Pittsburgh, PA 15251–5305.
8. STA (Common Carrier): a. Point-to-Point Microwave	159 & Corres	90	CEP	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
b. Local Television Transmission.	159 & Corres	90	CEP	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
9. STA (Common Carrier): a. Digital Electronic Message	159 & Corres	90	CEL	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
10. STA (BAPS)	159 & Corres	125	MGA	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
11. STA (IVDS)	159 & Corres	45	PAIM	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
12. STA (Coast)	159 & Corres	125	PCMM	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
13. STA (Ground)	159 & Corres	125	PCVM	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
14. STA (Microwave)	159 & Corres	45	PAOM	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
15. STA (LM, GMRS)	159 & Corres	45	PALM	Federal Communications Commission, Special Temporary Authority, P.O. Box 358305, Pittsburgh, PA 15251–5305.
16. Corres. (Duplicate)	159 & Corres	45	PADM	Federal Communications Commission, Duplicate, P.O. Box 358305, Pittsburgh, PA 15251–5305.
17. Corres. (Hearing)	159 & Corres	8,215	PFHM	Federal Communications Commission, Hearing, P.O. Box 358305, Pittsburgh, PA 15251–5305.
18. Corres. (Wait List)	159 & Corres	45	PAWM	Federal Communications Commission, Wait List, P.O. Box 358305, Pittsburgh, PA 15251–5305.
19. Corres. (Blanket Renewal) Land Mobile (Nonprofit).	159 & Corres	45	PALM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
20. Corres. (Blanket Renewal) IVDS (Nonprofit).	159 & Corres	45	PAIM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
21. Corres. (Blanket Renewal) Microwave (Nonprofit).	159 & Corres	190	PEOM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
22. Corres. (Blanket Renewal) Ground (Nonprofit).	159 & Corres	90	PBVM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
23. Corres. (Blanket Renewal) Coast (Nonprofit).	159 & Corres	90	PBMM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.

§ 1.1102

47 CFR Ch. I (10–1–97 Edition)

Action	FCC Form No.	Fee amount	Payment type code	Address
24. Corres. (Blanket Renewal) Aircraft (Nonprofit).	159 & Corres	45	PAAM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
25. Corres. (Blanket Renewal) Ship (Nonprofit).	159 & Corres	45	PASM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
26. Corres. (Blanket Renewal) BUS, OI, LT, GMRS.	159 & Corres	60	PALR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
27. Corres. (Blanket Renewal) 470–512, 800, 900, 220 (Local).	159 & Corres	80	PALS	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
28. Corres. (Blanket Renewal) 220 (Nationwide).	159 & Corres	115	PALT	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
29. Corres. (Blanket Renewal) IVDS.	159 & Corres	115	PAIR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
30. Corres. (Blanket Renewal) Microwave.	159 & Corres	225	PEOR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
31. Corres. (Blanket Renewal) Ground.	159 & Corres	105	PBVR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
32. Corres. (Blanket Renewal) Coast.	159 & Corres	105	PBMR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
33. Corres. (Blanket Renewal) Aircraft.	159 & Corres	75	PAAR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
34. Corres. (Blanket Renewal) Ship.	159 & Corres	75	PASR	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
35. Corres. (Blanket Renewal) Common Carrier.	159 & Corres	190	CJPM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
36. Corres. (Blanket Renewal) Common Carrier.	159 & Corres	190	CJLM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
37. Corres. (Blanket Renewal) BAPS.	159 & Corres	45	MAAM	Federal Communications Commission, Blanket Renewal, P.O. Box 358305, Pittsburgh, PA 15251–5305.
38. Interactive Video Data Service:				
a. New, Renewal	574	115	PAIR	Federal Communications Commission, Interactive Video Data Service, P.O. Box 358365, Pittsburgh, PA 15251–5365.
b. Modification	574	45	PAIM	Federal Communications Commission, Interactive Video Data Service, P.O. Box 358795, Pittsburgh, PA 15251–5795.
39. General Mobile Radio Service:				
a. New, Renewal	574	60	PALR	Federal Communications Commission, General Mobile Radio Service, P.O. Box 358230, Pittsburgh, PA 15251–5330.
b. Modification	574	45	PALM	Federal Communications Commission, General Mobile Radio Service, P.O. Box 358745, Pittsburgh, PA 15251–5745.
40. Commercial Radio Operators Restricted Radiotelephone Operator Permit and Restricted Radiotelephone Operator Permit (Limited Use):				
a. New	753, 755	45	PARR	Federal Communications Commission, Restricted Permit, P.O. Box 358295, Pittsburgh, PA 15251–5295.

Federal Communications Commission

§ 1.1102

Action	FCC Form No.	Fee amount	Payment type code	Address
41. Commercial Radio Operators Marine Radio Operator Permit, GMDSS Radio Operator, GMDSS Radio Maintainer, GMDSS Radio Operator/Main- tainer, First, Second, Third Class Radiotelegraph Opera- tor: a. Renewal	756	45	PACS	Federal Communications Commission, Radio Op- erator Permits, P.O. Box 358805, Pittsburgh, PA 15251-5805.
42. Transfer of Control	703, 490	45	PATM	Federal Communications Commission, Transfer of Control, P.O. Box 358310, Pittsburgh, PA 15251-5805.
43. Point to Point Microwave & Local Television Transmission Service: a. New Conditional or Modi- fied Conditional.	494	190	CJP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
b. Certification of Completion of Construction.	494A	190	CJP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
c. Renewal of License	405	190	CJP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
d. Assignment of Authoriza- tion.	702	70	CCP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
(1) Additional Stations ...	702	45	CAP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
e. Transfer of Control	704	70	CCP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
(1) Additional Stations ...	704	45	CAP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
f. Extension of Construction Authority.	701	70	CCP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
g. Request for Waiver of Prior Construction Author- ization.	159 & Corres	90	CEP	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
44. Digital Electronic Message Service: a. New Conditional or Modi- fied Conditional.	494	190	CJL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
b. Certification of Completion of Construction.	494A	190	CJL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
c. Renewal of License	405	190	CJL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
d. Assignment of Authoriza- tion.	702	70	CCL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
(1) Additional Stations ...	702	45	CAL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
e. Transfer of Control	704	70	CCL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
(1) Additional Stations ...	704	45	CAL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
f. Extension of Construction Authority.	701	70	CCL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.
g. Request for Waiver of Prior Construction Author- ization Requirement.	159 & Corres	90	CEL	Federal Communications Commission, Common Carrier Domestic Radio, P.O. Box 358680, Pittsburgh, PA 15251-5680.

Action	FCC Form No.	Fee amount	Payment type code	Address
45. Broadcast Auxiliary Radio Service:				
a. New Modification	313	105	MEA	Federal Communications Commission, Mass Media Services, P.O. Box 358700, Pittsburgh, PA 15251–5700.
b. Renewal	159/313R	45	MAA	Federal Communications Commission, Mass Media Services, P.O. Box 358700, Pittsburgh, PA 15251–5700.
46. Billing	Invoice	Various	Various	Federal Communications Commission, Billings, P.O. Box 358325, Pittsburgh, PA 15251–5325.
47. Amateur Vanity C/S	610V	30	WAVR	Federal Communications Commission, Amateur Vanity, P.O. Box 358924, Pittsburgh, PA 15251–5924.
48. Electronic Filing:				
a. LT, OL, BUS, GMRS, (PMRS) New, Renewal, Reinstatement.	ELT	60	PALR	Federal Communications Commission, Electronic Filing, P.O. Box 358994, Pittsburgh, PA 15251–5994.
b. Modification, Assignment, Nonprofit and (CMRS) New, Renewal, Reinstatement.	ELT	45	PALM	Federal Communications Commission, Electronic Filing, P.O. Box 358994, Pittsburgh, PA 15251–5994.
c. 220 MHz (Local), 470–512, 800, 900, (PMRS) New, Renewal, Reinstatement.	ELT	80	PALS	Federal Communications Commission, Electronic Filing, P.O. Box 358994, Pittsburgh, PA 15251–5994.
d. 220 (Nationwide), (PMRS) New, Renewal, Reinstatement.	ELT	115	PALT	Federal Communications Commission, Electronic Filing, P.O. Box 358994, Pittsburgh, PA 15251–5994.
e. IVDS New, Renewal, Reinstatement.	ELT	115	PAIR	Federal Communications Commission, Electronic Filing, P.O. Box 358994, Pittsburgh, PA 15251–5994.
49. Public Safety/Special Emergency (for profit) New, Modification, Renewal, Reinstatement, Assignment.	600	45	PALM	Federal Communications Commission, PS/SE Services, P.O. Box 358285, Pittsburgh, PA 15251–5285.
50. Paging and Radiotelephone Stations:				
a. New or Additional Facility	600	280	CMD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
b. Major Modification	600	280	CMD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
c. Fill in Transmitters	489,600	280	CMD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
d. Major Amendment to Pending Application.	600	280	CMD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
e. Assignment or Transfer ...	490	280	CMD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
(1) Additional Call Sign	490	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
f. Partial Assignment	489, 490, 600	280	CMD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
g. Renewal	159/405	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
h. Minor Modifications	489	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
i. Special Temporary Authority.	159 & Corres	245	CLD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
j. Extension of Time to Construct.	600	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
k. Notice of Completion of Construction.	489	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.

Federal Communications Commission

§ 1.1102

Action	FCC Form No.	Fee amount	Payment type code	Address
I. Auxiliary Test Station	600	245	CLD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
m. Subsidiary Communications Service.	600	125	CFD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
n. Combining Call Signs	489	245	CLD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
o. 900 MHz Nationwide Renewal Paging Network Organizer, Network Operator.	159/405	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
p. Air-Ground Individual License—New, Renewal, Modification.	159/409	45	CAD	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
51. Cellular systems:				
a. New, Additional Facility, Major Modification.	600	280	CMC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
b. Minor Modification	489	75	CDC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
c. Assignment or Transfer ...	490	280	CMC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
d. Partial Assignment	489, 490, 600	280	CMC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
e. Renewal	159/405	45	CAC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
f. Extension of Time to Complete Construction.	600	45	CAC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
g. Special Temporary Authority.	600 or 159 & Corres.	245	CLC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
h. Combining Cellular Geographic Service Areas (per system).	600	65	CBC	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358135, Pittsburgh, PA 15251-5135.
52. Rural Radio:				
a. New, Additional Facility or Major Modification, Major Amendment to a Pending Application.	600	130	CGR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
b. Minor Modification	489	45	CAR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
c. Assignment or Transfer First Call Sign.	490	130	CGR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
(1) Each Additional Call Sign.	490	45	CAR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
(2) Partial Assignment (per call sign).	489, 490, 600	130	CGR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
d. Renewal (per call sign)	159/405	45	CAR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
e. Extension of Time to Construct.	600	45	CAR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
f. Notice of Completion of Construction.	489	45	CAR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
g. Special Temporary Authority.	159 & Corres	245	CLR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.
h. Combining Call Signs	489	245	CLR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251-5130.

§ 1.1103

47 CFR Ch. I (10–1–97 Edition)

Action	FCC Form No.	Fee amount	Payment type code	Address
i. Auxiliary Test Station	600	245	CLR	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
53. Offshore Radio Service:				
a. New, Additional Facility, Major Modification, (per transmitter).	600	130	CGF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
b. Fill in Transmitters (per transmitter).	489, 600	130	CGF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
c. Major Amendment to a Pending Application (per transmitter).	600	130	CGF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
d. Minor Modification (per transmitter).	489	45	CAF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
e. Assignment of Transfer:				
(1) First Call Sign	490	130	CGF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
(2) Each Additional Call Sign.	490	45	CAF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
(3) Partial Assignment (per call sign).	489, 490, 600	130	CGF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
f. Renewal (per call sign)	159/405	45	CAF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
g. Extension of Time to Construct (per Application).	600	45	CAF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
h. Notice of Completion of Construction (per Application).	489	45	CAF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
i. Special Temporary Authority.	159 & Corres	245	CLF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
j. Combining Call Signs (per call sign).	489	245	CLF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.
k. Auxiliary Test Station (per transmitter).	159 & 401	245	CLF	Federal Communications Commission, Common Carrier Land Mobile, P.O. Box 358130, Pittsburgh, PA 15251–5130.

[61 FR 41967, Aug. 13, 1996]

§ 1.1103 Schedule of charges for equipment authorization, experimental radio services, ship inspections and international telecommunications settlements.

Action	FCC Form No.	Fee amount	Payment type code	Address
1. Certification:				
a. Receivers (except TV and FM).	731	350	EEC	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251–5315.
b. All Other Devices	731	895	EGC	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251–5315.
c. Modifications and Class II Permissive Changes.	731	45	EAC	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251–5315.
d. Request for Confidentiality	731 or 159 & Corres..	130	EBC	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251–5315.
2. Type Acceptance:				
a. All Devices	731	450	EFT	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251–5315.

Federal Communications Commission

§ 1.1104

Action	FCC Form No.	Fee amount	Payment type code	Address
b. Modifications and Class II Permissive Changes.	731	45	EAT	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251-5315.
c. Request for Confidentiality	731 or 159 & Corres..	130	EBT	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251-5315.
3. Notifications (All Devices)	731	140	ECN	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251-5315.
4. Advance Approval for Subscription TV System.	159 & Corres	2,740	EIS	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251-5315.
a. Request for Confidentiality	159 & Corres	130	EBS	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251-5315.
5. Assignment of Applicant Code:				
a. New applicants for all application types except Subscription TV.	159 & Corres	45	EAG	Federal Communications Commission, Equipment Approval Services, P.O. Box 358315, Pittsburgh, PA 15251-5315.
6. Experimental Radio Service:				
a. New Station Authorization	442	45	EAE	Federal Communications Commission, Equipment Approval Services, P.O. Box 358320, Pittsburgh, PA 15251-5320.
b. Modification of Authorization.	442	45	EAE	Federal Communications Commission, Equipment Approval Services, P.O. Box 358320, Pittsburgh, PA 15251-5320.
c. Renewal of Station Authorization.	405	45	EAE	Federal Communications Commission, Equipment Approval Services, P.O. Box 358320, Pittsburgh, PA 15251-5320.
d. Assignment or Transfer of Control.	702 or 703	45	EAE	Federal Communications Commission, Equipment Approval Services, P.O. Box 358320, Pittsburgh, PA 15251-5320.
e. Special Temporary Authority.	159 & Corres	45	EAE	Federal Communications Commission, Equipment Approval Services, P.O. Box 358320, Pittsburgh, PA 15251-5320.
f. Additional fee required for any of the above applications that request confidentiality.	159 & Corres	45	EAE	Federal Communications Commission, Equipment Approval Services, P.O. Box 358320, Pittsburgh, PA 15251-5320.
7. Ship Inspections:				
a. Passenger Vessel Under Title III, Part III.	801	390	FCS	Federal Communications Commission, P.O. Box 358110, Pittsburgh, PA 15251-5110.
b. Oceangoing Vessel Under Title III, Part II.	801	755	FFS	Federal Communications Commission, P.O. Box 358110, Pittsburgh, PA 15251-5110.
c. Vessels Under the Great Lakes Agreement.	801	110	FDS	Federal Communications Commission, P.O. Box 358110, Pittsburgh, PA 15251-5110.
d. Vessels Under the Safety of Life at Sea (SOLAS) Convention.	801	660	FES	Federal Communications Commission, P.O. Box 358110, Pittsburgh, PA 15251-5100.
e. Temporary Waiver of Inspection.	159 & Corres	75	FBS	Federal Communications Commission, P.O. Box 358110, Pittsburgh, PA 15251-5110.
8. International Telecommunications Settlements Administrative Fee for Collections (per line item).	99	2	IAT	Licensees will be billed.

[61 FR 41974, Aug. 13, 1996]

§ 1.1104 Schedule of charges for applications and other filings in the mass media services.

Action	FCC Form No.	Fee amount	Payment type code	Address
1. Commercial Television Stations:				
a. New or Major Change Construction Permit.	301	3,080	MVT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251-5165.
b. Minor Change	301	690	MPT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251-5165.

Action	FCC Form No.	Fee amount	Payment type code	Address
(1) Main Studio Request	159 & Corres.	690	MPT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
c. New License	302/302–TV ...	210	MJT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
d. License Renewal	303–S	125	MGT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
e. License Agreement: (1) Long Form	314	690	MPT	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
(2) Short Form	316	100	MDT	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
f. Transfer of Control: (1) Long Form	315	690	MPT	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
(2) Short Form	316	100	MDT	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
g. Hearing (New and Major or minor change comparative construction permit hearings; comparative license renewal hearings).	159 & Corres	8,215	MWT	Federal Communications Commission, Mass Media Services, P.O. Box 358170, Pittsburgh, PA 15251–5170.
h. Call Sign	159 & Corres	70	MBT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
i. Extension of Time to Construct or Replacement of Construction Permit.	307	245	MKT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
j. Special Temporary Authority.	159 & Corres	125	MGT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
k. Petition for Rulemaking for New Community of License.	301/302/302–TV.	1,905	MRT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
i. Ownership Report	323	45	MAT	Federal Communications Commission, Mass Media Services, P.O. Box 358180, Pittsburgh, PA 15251–5180.
2. Commercial AM Radio Stations:				
a. New or Major Change Construction Permit.	301	2,740	MUR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
b. Minor Change	301	690	MPR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
(1) Main Studio Request	159 & Corres.	690	MPT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
c. New License	302–AM	450	MMR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
d. AM Directional Antenna ...	302–AM	520	MOR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
e. AM Remote Control	301–A/301	45	MAR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
f. License Renewal	303–S	125	MGR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
g. License Assignment: (1) Long Form	314	690	MPR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
(2) Short Form	316	100	MDR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.

Federal Communications Commission

§ 1.1104

Action	FCC Form No.	Fee amount	Payment type code	Address
h. Transfer of Control: (1) Long Form	315	690	MPR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251-5350.
(2) Short Form	316	100	MDR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251-5350.
i. Hearing (New and major/minor change comparative construction permit hearings; comparative license renewal hearings).	159 & Corres	8,215	MWR	Federal Communications Commission, Mass Media Services, P.O. Box 358170, Pittsburgh, PA 15251-5170.
j. Call Sign	159 & Corres	70	MBR	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251-5165.
k. Extension of Time to Construct or Replacement of Construction Permit.	307	245	MKR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251-5190.
l. Special Temporary Authority.	159 & Corres	125	MGR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251-5190.
m. Ownership Report	323	45	MAR	Federal Communications Commission, Mass Media Services, P.O. Box 358180, Pittsburgh, PA 15251-5180.
3. Commercial FM Radio Stations:				
a. New or Major Change Construction Permit.	301	2,470	MTR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251-5195.
b. Minor Change	301	690	MPR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251-5195.
(1) Main Studio Request	159 & Corres.	690	MPT	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251-5165.
c. New License	302-FM	140	MHR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251-5195.
d. FM Directional Antenna ...	302-FM	435	MLR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251-5195.
e. License Renewal	303-S	125	MGR	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251-5190.
f. License Assignment:				
(1) Long Form	314	690	MPR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251-5350.
(2) Short Form	316	100	MDR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251-5350.
g. Transfer of Control:				
(1) Long Form	315	690	MPR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251-5350.
(2) Short Form	316	100	MDR	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251-5350.
h. Hearing (New and major/minor change comparative construction permit hearings; comparative license renewal hearings).	159 & Corres	8,215	MWR	Federal Communications Commission, Mass Media Services, P.O. Box 358170, Pittsburgh, PA 15251-5170.
i. Call Sign	159 & Corres	70	MBR	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251-5165.
j. Extension of Time to Construct or Replacement of Construction Permit.	307	245	MKR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251-5195.
k. Special Temporary Authority.	159 & Corres	125	MGR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251-5195.

Action	FCC Form No.	Fee amount	Payment type code	Address
I. Petition for Rulemaking for New Community of License or Higher Class Channel.	301/302–FM ..	1,905	MRR	Federal Communications Commission, Mass Media Services, P.O. Box 358195, Pittsburgh, PA 15251–5195.
m. Ownership Report	323	45	MAR	Federal Communications Commission, Mass Media Services, P.O. Box 358180, Pittsburgh, PA 15251–5180.
4. FM Translators:				
a. New or Major Change Construction Permit.	349	520	MOF	Federal Communications Commission, Mass Media Services, P.O. Box 358200, Pittsburgh, PA 15251–5200.
b. New License	350	105	MEF	Federal Communications Commission, Mass Media Services, P.O. Box 358200, Pittsburgh, PA 15251–5200.
c. License Renewal	303–S	45	MAF	Federal Communications Commission, Mass Media Services, P.O. Box 358190, Pittsburgh, PA 15251–5190.
d. Special Temporary Authority.	159 & Corres	125	MGF	Federal Communications Commission, Mass Media Services, P.O. Box 358200, Pittsburgh, PA 15251–5200.
e. License Assignment	345/316, 315/314.	100	MDF	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
f. Transfer of Control	345/316, 315/314.	100	MDF	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
5. TV Translators and LPTV Stations:				
a. New or Major Change Construction Permit.	346	520	MOL	Federal Communications Commission, Mass Media Services, P.O. Box 358185, Pittsburgh, PA 15251–5185.
b. New License	347	105	MEL	Federal Communications Commission, Mass Media Services, P.O. Box 358185, Pittsburgh, PA 15251–5185.
c. License Renewal	303–S	45	MAL	Federal Communications Commission, Mass Media Services, P.O. Box 358165, Pittsburgh, PA 15251–5165.
d. Special Temporary Authority.	159 & Corres	125	MGL	Federal Communications Commission, Mass Media Services, P.O. Box 358185, Pittsburgh, PA 15251–5185.
e. License Assignment	345/316, 315/314.	100	MDL	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
f. Transfer of Control	345/316, 315/314.	100	MDL	Federal Communications Commission, Mass Media Services, P.O. Box 358350, Pittsburgh, PA 15251–5350.
6. FM Booster Stations:				
a. New or Major Change Construction Permit.	349	520	MOF	Federal Communications Commission, Mass Media Services, P.O. Box 358200, Pittsburgh, PA 15251–5200.
b. New License	350	105	MEF	Federal Communications Commission, Mass Media Services, P.O. Box 358200, Pittsburgh, PA 15251–5200.
c. Special Temporary Authority.	159 & Corres	125	MGF	Federal Communications Commission, Mass Media Services, P.O. Box 358200, Pittsburgh, PA 15251–5200.
7. TV Booster Stations:				
a. New or Major Change Construction Permit.	346	520	MOF	Federal Communications Commission, Mass Media Services, P.O. Box 358185, Pittsburgh, PA 15251–5185.
b. New License	347	105	MEF	Federal Communications Commission, Mass Media Services, P.O. Box 358185, Pittsburgh, PA 15251–5185.
c. Special Temporary Authority.	159 & Corres	125	MGF	Federal Communications Commission, Mass Media Services, P.O. Box 358185, Pittsburgh, PA 15251–5185.
8. Multipoint Distribution Service (including multichannel MDS):				
a. Conditional License	304	190	CJM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251–5155.

Federal Communications Commission

§ 1.1105

Action	FCC Form No.	Fee amount	Payment type code	Address
b. Major Modification of Conditional Licenses or License Authorization.	304	190	CJM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.
c. Certificate of Completion of Construction.	494-A/304-A	555	CPM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.
d. License Renewal	405	190	CJM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.
e. Assignment or Transfer: (1) First Station Application.	702/704	70	CCM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.
(2) Each Additional Station.	702/704	45	CAM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.
f. Extension of Construction Authorization.	701	140	CHM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.
g. Special Temporary Authority or Request for Waiver of Prior Construction Authorization.	159 & Corres	90	CEM	Federal Communications Commission, Mass Media Services, P.O. Box 358155, Pittsburgh, PA 15251-5155.

[61 FR 41975, Aug. 13, 1996, as amended at 62 FR 51058, Sept. 30, 1997]

EFFECTIVE DATE NOTE: At 62 FR 51058, Sept. 30, 1997, § 1.1104 was amended by adding entries 1.b.(1), 2.b.(1), 3.b.(1), effective Dec. 1, 1997.

§ 1.1105 Schedule of charges for applications and other filings in the common carrier services.

Action	FCC Form No.	Fee amount	Payment type code	Address
1. All Common Carrier Services:				
a. Hearing (Comparative New or Modifications).	159 & Corres	8,215	BHZ	Federal Communications Commission, Common Carrier Enforcement, P.O. Box 358120, Pittsburgh, PA 15251-5120.
b. Developmental Authority (Same charge as regular authority in service unless otherwise indicated)				
c. Formal Complaints Filing Fee.	159 & Corres	150	CIZ	Federal Communications Commission, Common Carrier Enforcement, P.O. Box 358120, Pittsburgh, PA 15251-5120.
2. Domestic 214 Applications:				
a. Domestic Cable Construction.	159 & Corres	745	CUT	Federal Communications Commission, Common Carrier Network Services, P.O. Box 358145, Pittsburgh, PA 15251-5145.
b. Other	159 & Corres	745	CUT	Federal Communications Commission, Common Carrier Network Services, P.O. Box 358145, Pittsburgh, PA 15251-5145.
3. Telephone Equipment Registration	159 & 730	190	CJQ	Federal Communications Commission, Common Carrier Network Services, P.O. Box 358145, Pittsburgh, PA 15251-5145.
4. Tariff Filings:				
a. Filing Fees	159 & Corres	600	CQK	Federal Communications Commission, Common Carrier Tariff Filings, P.O. Box 358150, Pittsburgh, PA 15251-5150.
b. Special Permission Filing (per filing) (waiver of any rule in Part 61 of the Commission's rules).	159 & Corres	600	CQK	Federal Communications Commission, Common Carrier Tariff Filings, P.O. Box 358150, Pittsburgh, PA 15251-5150.
c. Waiver of Part 69 Tariff Rules.	159 & Corres	600	CQK	Federal Communications Commission, Common Carrier Tariff Filings, P.O. Box 358150, Pittsburgh, PA 15251-5150.
5. Accounting and Audits:				
a. Field Audits	N/A	75,680	BMA	Carriers will be billed.
b. Review of Attest Audit	N/A	41,310	BLA	Carriers will be billed.
c. Review of Depreciation Update Study (single state).	159 & Written Study.	25,015	BKA	Federal Communications Commission, Accounting and Audits, P.O. Box 358140, Pittsburgh, PA 15251-5140.

§ 1.1106

47 CFR Ch. I (10–1–97 Edition)

Action	FCC Form No.	Fee amount	Payment type code	Address
(1) Each Additional State.	Same as 5c ...	830	CVA	Federal Communications Commission, Accounting and Audits, P.O. Box 358140, Pittsburgh, PA 15251–5140.
d. Interpretation of Accounting Rules (per request).	159 & Corres	3,510	BCA	Federal Communications Commission, Accounting and Audits, P.O. Box 358140, Pittsburgh, PA 15251–5140.
e. Petition for Waiver (per petition) (waiver of Part 69 rules and Part 32 accounting rules, Part 36 separation rules, Part 43 reporting requirements, Part 64 cost allocation rules, Part 65 rate of return & rate base rules.	159 & Corres	5,665	BEA	Federal Communications Commission, Accounting and Audits, P.O. Box 358140, Pittsburgh, PA 15251–5140.

[61 FR 41979, Aug. 13, 1996; 61 FR 44176, Aug. 28, 1996]

§ 1.1106 Schedule of charges for applications and other filings in the cable television services.

Action	FCC Form No.	Fee amount	Payment type code	Address
1. CARS Construction Permit	327	190	TIC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
2. CARS Modification	327	190	TIC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
3. CARS License Renewal	327	190	TIC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
4. CARS License Agreement	327	190	TIC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
5. CARS Transfer of Control	327	190	TIC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
6. Special Temporary Authorization.	159 & Corres	125	TGC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
7. Cable Special Relief	159 & Corres	960	TQC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
8. 76.12 Registration Statement	159 & Corres	45	TAC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
9. Aeronautical Frequency Usage Notification.	159 & Corres	45	TAC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
10. Aeronautical Frequency Usage Waiver.	159 & Corres	45	TAC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.
11. Pole Attachment Complaints Filing Fee.	159 & Corres	150	TPC	Federal Communications Commission, Cable Services Bureau, P.O. Box 358205, Pittsburgh, PA 15251–5205.

[61 FR 41979, Aug. 13, 1996]

§ 1.1107 Schedule of charges for applications and other filings in the international services.

Action	FCC Form No.	Fee amount	Payment type code	Address
1. International Fixed Public Radio (Public & Control Stations): a. Initial Construction Permit (per station).	159 & 407	620	CSN	Federal Communications Commission, International Bureau, Fixed Public Radio, P.O. Box 358160, Pittsburgh, PA 15251–5160.

Federal Communications Commission

§ 1.1107

Action	FCC Form No.	Fee amount	Payment type code	Address
b. Assignment or Transfer (per application).	702 or 704	620	CSN	Federal Communications Commission, International Bureau, Fixed Public Radio, P.O. Box 358160, Pittsburgh, PA 15251-5160.
c. Renewal (per license)	405	450	CON	Federal Communications Commission, International Bureau, Fixed Public Radio, P.O. Box 358160, Pittsburgh, PA 15251-5160.
d. Modification (per station)	159 & 403	450	CON	Federal Communications Commission, International Bureau, Fixed Public Radio, P.O. Box 358160, Pittsburgh, PA 15251-5160.
e. Extension of Construction Authorization (per station).	701	225	CKN	Federal Communications Commission, International Bureau, Fixed Public Radio, P.O. Box 358160, Pittsburgh, PA 15251-5160.
f. Special Temporary Authority or Request for Waiver (per request).	159 & Corres	225	CKN	Federal Communications Commission, International Bureau, Fixed Public Radio, P.O. Box 358160, Pittsburgh, PA 15251-5160.
2. Section 214 Applications:				
a. Overseas Cable Construction.	159 & Corres	11,090	BIT	Federal Communications Commission, International Bureau, Telecommunications, P.O. Box 358115, Pittsburgh, PA 15251-5115.
b. Cable Landing License:				
(1) Common Carrier	159 & Corres	1,250	CXT	Federal Communications Commission, International Bureau, Telecommunications, P.O. Box 358115, Pittsburgh, PA 15251-5115.
(2) Non-Common Carriers.	159 & Corres	12,335	BJT	Federal Communications Commission, International Bureau, Telecommunications, P.O. Box 358115, Pittsburgh, PA 15251-5115.
c. All other International 214 Applications.	159 & Corres	745	CUT	Federal Communications Commission, International Bureau, Telecommunications, P.O. Box 358115, Pittsburgh, PA 15251-5115.
d. Special Temporary Authority (all services).	159 & Corres	745	CUT	Federal Communications Commission, International Bureau, Telecommunications, P.O. Box 358115, Pittsburgh, PA 15251-5115.
e. Assignments or Transfers (all services).	159 & Corres	745	CUT	Federal Communications Commission, International Bureau, Telecommunications, P.O. Box 358115, Pittsburgh, PA 15251-5115.
3. Fixed Satellite Transmit/Receive Earth Stations:				
a. Initial Application (per station).	159 & 493	1,855	BAX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
b. Modification of License (per station).	159 & 493	130	CGX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
c. Assignment or Transfer:				
(1) First Station on Application.	702 & 704	365	CNX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
(2) Each Additional Station.	Same as 10c(i).	125	CFX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
d. Developmental Station (per station).	159 & 493	1,215	CWX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
e. Renewal of License (per station).	405	130	CGX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
f. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	130	CGX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
g. Amendment of Application (per station).	159 & Corres	130	CGX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
h. Extension of Construction Permit (per station).	701	130	CGX	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
4. Fixed Satellite Small Transmit/Receive Earth Stations (2 meters or less operating in the 4/6 GHz frequency band):				
a. Lead Application	159 & 493	4,110	BDS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.

Action	FCC Form No.	Fee amount	Payment type code	Address
b. Routine Application (per station).	159 & 493	45	CAS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
c. Modification of License (per station).	159 & 493	130	CGS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
d. Assignment or Transfer: (1) First Station on Application.	702 or 704	365	CNS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
(2) Each additional station.	702 or 704	45	CAS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
e. Developmental Station (per station).	159 & 493	1,215	CWS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
f. Renewal of License (per station).	405	130	CGS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
g. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	130	CGS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
h. Amendment of Application (per station).	159 & Corres	130	CGS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
i. Extension of Construction Permit (per station).	701	130	CGS	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
5. Receive Only Earth Stations:				
a. Initial Application for Registration.	159 & 493	280	CMO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
b. Modification of License or Registration (per station).	159 & 493	1,645	CGO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
c. Assignment or Transfer: (1) First Station on Application.	702 & 704	365	CNO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
(2) Each Additional Station.	Same as 12c(i).	125	CFO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
d. Renewal of License (per station).	405	130	CGO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
e. Amendment of Application	159 & Corres	130	CGO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
f. Extension of Construction Permit (per station).	701	130	CGO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
g. Waivers (per request)	159 & Corres	130	CGO	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
6. Fixed Satellite Very Small Aperture Terminal (VSAT) Systems:				
a. Initial Application (per system).	159 & 493	6,840	BGV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
b. Modification of License (per system).	159 & 493	130	CGV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
c. Assignment or Transfer of System.	702 & 704	1,830	CZV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
d. Development Station	159 & 493	1,215	CWV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.
e. Renewal of License (per system).	159 & 405	130	CGV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251–5160.

Federal Communications Commission

§1.1107

Action	FCC Form No.	Fee amount	Payment type code	Address
f. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	130	CGV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
g. Amendment of Application (per system).	159 & Corres	130	CGV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
h. Extension of Construction Permit (per system).	159 & 701	130	CGV	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
7. Mobile Satellite Earth Stations:				
a. Initial Application of Blanket Authorization.	159 & 493	6,840	BGB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
b. Initial Application for Individual Earth Station.	159 & 493	1,645	CYB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
c. Modification of License (per system).	159 & 493	130	CGB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
d. Assignment or Transfer (per system).	159 & 702 or 159 & 704.	1,830	CZB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
e. Developmental Station	159 & 493	1,215	CWB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
f. Renewal of License (per system).	159 & 405	130	CGB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
g. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	130	CGB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
h. Amendment of Application (per system).	159 & Corres	130	CGB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
i. Extension Construction Permit (per system).	159 & 701	130	CGB	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
8. Radio Determination Satellite Earth Stations:				
a. Initial Application of Blanket Authorization.	159 & 493	6,840	BGH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
b. Initial Application for Individual Earth Station.	159 & 493	1,645	CYH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
c. Modification of License (per system).	159 & 493	130	CGH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
d. Assignments or Transfer (per system).	159 & 702 or 159 & 704.	1,830	CZH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
e. Developmental Station	159 & 493	1,215	CWH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
f. Renewal of License (per system).	159 & 405	130	CGH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
g. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	130	CGH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
h. Amendment of Application (per system).	159 & Corres	130	CGH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
i. Extension of Construction Permit (per system).	159 & 701	130	CGH	Federal Communications Commission, International Bureau, Earth Stations, P.O. Box 358160, Pittsburgh, PA 15251-5160.
9. Space Stations (Geostationary):				

Action	FCC Form No.	Fee amount	Payment type code	Address
a. Application for Authority to Construct.	159 & Corres	2,470	BBY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
b. Application for Authority to Launch & Operate:				
(1) Initial Application	159 & Corres	85,045	BNY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
(2) Replacement Satellite.	159 & Corres	85,045	BNY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
c. Assignment or Transfer (per satellite).	159 & 702 or 159 & 704.	6,075	BFY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
d. Modification	159 & Corres	6,075	BFY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
e. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	610	CRY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
f. Amendment of Application	159 & Corres	1,215	CWY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
g. Extension of Construction Permit/Launch Authorization (per request).	159 & Corres	610	CRY	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
10. Space Stations (Low-Earth Orbit Satellite Systems):				
a. Application for Authority to Construct (per system of technically identical satellites).	159 & Corres	7,290	CZW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
b. Application for Authority to Launch and Operate (per system of technically identical satellites).	159 & Corres	255,080	CLW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
c. Assignment or Transfer (per request).	159 & 702 or 159 & 704.	7,290	CZW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
d. Modification (per request)	159 & Corres	18,220	CGW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
e. Special Temporary Authority or Waiver of Prior Construction Authorization (per request).	159 & Corres	1,830	CXW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
f. Amendment of Application (per request).	159 & Corres	3,645	CAW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
g. Extension of Construction Permit/Launch Authorization (per request).	159 & Corres	1,830	CXW	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
11. Direct Broadcast Satellites				
a. Authorization to Construct or Major Modification (per request).	159 & Corres	2,470	MTD	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
b. Construction Permit and Launch Authority (per request).	159 & Corres	23,950	MXD	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
c. License to Operate (per request).	159 & Corres	690	MPD	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
d. Special Temporary Authorization (per request).	159 & Corres	125	MGD	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.
e. Hearing (New and major/minor change comparative construction permit hearings; comparative license renewal hearing) (per request).	159 & Corres	8,215	MWD	Federal Communications Commission, International Bureau, Satellites, P.O. Box 358210, Pittsburgh, PA 15251–5210.

Federal Communications Commission

§ 1.1109

Action	FCC Form No.	Fee amount	Payment type code	Address
12. International Broadcast Stations:				
a. New Station and Facilities Change Construction Permit (per application).	159 & 309	2,075	MSN	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
b. New License (per application).	159 & 310	470	MNN	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
c. License Renewal (per application).	159 & 311	120	MFN	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
d. License Assignment or Transfer of Control (per station license).	159 & 314 or 315 or 316.	75	MCN	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
e. Frequency Assignment and Coordination (per frequency hour).	159 & Corres	45	MAN	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
f. Special Temporary Authorization (per request).	159 & Corres	125	MGN	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
13. Permit to Deliver Program to Foreign Broadcast Stations (per application):				
a. Commercial Television Stations.	159 & 308	70	MBT	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
b. Commercial AM or FM Radio Station.	159 & 308	70	MBR	Federal Communications Commission, International, Bureau, Notifications, P.O. Box 358175, Pittsburgh, PA 15251-5175.
14. Recognized Private Operating Status (per application).	159 & Corres	745	CUG	Federal Communications Commission, International, Bureau, Telecommunicational, P.O. Box 358115, Pittsburgh, PA 15251-5115.

[61 FR 41980, Aug. 13, 1996; 61 FR 44176, Aug. 28, 1996]

§ 1.1108 Attachment of charges.

The charges required to accompany a request for the Commission regulatory services listed in §§ 1.1102 through 1.1106 of this subpart will not be refundable to the applicant irrespective of the Commission's disposition of that request. Return or refund of charges will be made in certain limited instances as set out at § 1.1112 of this subpart.

[52 FR 5289, Feb. 20, 1987. Redesignated and amended at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1109 Payment of charges.

(a) Electronic fee payments do not require the use of a FCC Form 159, Remittance Advice. An electronic fee payment must be made on or before the day the application and appropriate processing form are filed.

(b) The schedule of fees for applications and other filings lists those applications and other filings that must be accompanied by a FCC Form 159, Remittance Advice. A separate FCC Form 159 will not be required once the information requirements of that form

(payor information) is incorporated into the underlying application form.

(c) Applications and other filings that are not submitted in accordance with these instructions will be returned as unprocessable.

NOTE: This requirement for the simultaneous submission of fee forms with applications or other filings does not apply to the payment of fees for which the Commission has established a billing process. See § 1.1118 of this subpart.

(d) Applications returned to applicants for additional information or corrections will not require an additional fee when resubmitted, unless the additional information results in an increase of the original fee amount. Those applications not requiring an additional fee should be resubmitted directly to the Bureau/Office requesting the additional information. The original fee will be forfeited if the additional information or corrections are not resubmitted to the appropriate Bureau/Office by the prescribed deadline. If an additional fee is required, the

§ 1.1110

47 CFR Ch. I (10–1–97 Edition)

original fee will be returned and the application must be resubmitted with a new remittance in the amount of the required fee to the Commission's lockbox bank. Applicants should attach a copy of the Commission request for additional or corrected information to their resubmission.

(1) If the Bureau/Office staff discovers within 30 days after the resubmission that the required fee was not submitted, the application will be dismissed.

(2) If after 30 days the Bureau/Office staff discovers the required fee has not been paid, the application will be retained and a 25 percent late fee will be assessed on the deficient amount even if the Commission has completed its action on the application. Any Commission actions taken prior to timely payment of these charges are contingent and subject to recession.

(e) Should the staff change the status of an application, resulting in an increase in the fee due, the applicant will be billed for the remainder under the conditions established by § 1.110(b) of the rules.

NOTE: Due to the statutory requirements applicable to tariff filings, the procedures for handling tariff filings may vary from the procedures set out in the rules.

[52 FR 5289, Feb. 20, 1987, as amended at 53 FR 40888, Oct. 19, 1988; 55 FR 19171, May 8, 1990. Redesignated and amended at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1110 Form of payment.

(a) Fee payments should be in the form of a check, bank draft, on money order denominated in U.S. dollars and drawn on a United States financial institution and made payable to the Federal Communications Commission or by a Visa or MasterCard credit card. No other credit card is acceptable. Fees for applications and other filings paid by credit card will not be accepted unless the credit card section of FCC Form 159 is completed in full. The Commission discourages applicants from submitting cash and will not be responsible for cash sent through the mail. Personal or corporate checks dated more than six months prior to their submission to the Commission's lockbox bank and postdated checks will not be accepted and will be re-

turned as deficient. Third party checks (i.e., checks with a third party as maker or endorser) will not be accepted.

(1) Specific procedures for electronic payment will be announced by Public Notice. Applicants must submit a written request to the Commission for authorization to make electronic payments of a fee for applications and other filings, as follows.

(2) No electronic payment of an application fee will be accepted unless the payor has obtained the written authorization of the Commission to submit application fees electronically. It is the responsibility of the payor to insure that any electronic payment is made in the manner required by the Commission. Failure to comply with the Commission's procedures will result in the return of the application or other filing and the fee payment.

(3) Payments by wire transfer will be accepted. Prior to making a payment by wire, the payor shall obtain the approval of the Managing Director or his designee. A completed FCC Form 159 shall be submitted to the Managing Director or his designee prior to initiating the wire transfer.

(b) Applicants are required to submit one payment instrument (check, bank draft or money order) and FCC Form 155 with each application or filing. Multiple payment instruments for a single application or filing are not permitted. Except that a separate Fee Form (FCC Form 155) will not be required once the information requirements of that form (the Fee Code, fee amount, and total fee remitted) are incorporated into the underlying application form.

(c) The Commission may accept multiple money orders in payment of a fee for a single application where the fee exceeds the maximum amount for a money order established by the issuing agency and the use of multiple money orders is the only practical method available for fee payment.

(d) The Commission may require payment of fees with a cashier's check upon notification to an applicant or filer or prospective group of applicants under the conditions set forth below in paragraphs (d) (1) and (2) of this section.

Federal Communications Commission

§1.1112

(1) Payment by cashier's check may be required when a person or organization has made payment, on one or more occasions with a payment instrument on which the Commission does not receive final payment and such failure is not excused by bank error.

(2) The Commission will notify the party in writing that future payments must be made by cashier's check until further notice. If, subsequent to such notice, payment is not made by cashier's check, the party's payment will not be accepted and its application or other filing will be returned.

(e) All fees collected will be paid into the general fund of the United States Treasury in accordance with Pub. L. 99-272.

(f) The Commission will furnish a stamped receipt of an application only upon request. In order to obtain a stamped receipt for an application (or other filing), the application package must include a copy of the first page of the application, clearly marked "copy", submitted expressly for the purpose of serving as a receipt of the filing. The copy should be the top document in the package. The copy will be date-stamped immediately and provided to the bearer of the submission, if hand delivered. For submissions by mail, the receipt copy will be provided through return mail if the filer has attached to the receipt copy a stamped self-addressed envelope of sufficient size to contain the date stamped copy of the application. No remittance receipt copies will be furnished.

[52 FR 5289, Feb. 20, 1987; 52 FR 38232, Oct. 15, 1987, as amended at 53 FR 40888, Oct. 19, 1988; 55 FR 19171, May 8, 1990. Redesignated at 59 FR 30998, June 16, 1994, as amended at 59 FR 30999, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§1.1111 Filing locations.

(a) Except as noted in this section applications and other filings, with attached fees and FCC Form 159, must be submitted to the locations and addresses set forth in §§1.1102 through 1.1106.

(1) Tariff filings shall be filed with the Secretary, Federal Communications Commission, Washington, DC 20554. On the same day, the filer should submit a copy of the cover letter, the FCC Form 159, and the appropriate fee

to the Commission's lockbox bank at the address established in §1.1105.

(2) Bills for collection will be paid at the Commission's lockbox bank at the address for the appropriate service as established in §§1.1102 through 1.1106, as set forth on the bill sent by the Commission. Payments must be accompanied by the bill and a FCC Form 159 to ensure proper credit.

(3) Petitions for reconsideration or applications for review of fee decisions pursuant to §1.1117(b) of this subpart must be accompanied by the required fee for the application or other filing being considered or reviewed.

(4) Applicants claiming an exemption from a fee requirement for an application or other filing under 47 U.S.C. 158(d)(1) or §1.1113 of this subpart shall file their applications in the appropriate location as set forth in the rules for the service for which they are applying, except that request for waiver accompanied by a tentative fee payment should be filed at the Commission's lockbox bank at the address for the appropriate service set forth in §§1.1102 through 1.1105.

(b) All materials must be submitted as one package. The Commission will not take responsibility for matching fees, forms and applications submitted at different times or locations. Materials submitted at other than the location and address required by §0.401(b) and paragraph (a) of this section will be returned to the applicant or filer.

[55 FR 19171, May 8, 1990. Redesignated at 59 FR 30998, June 16, 1994, as amended at 59 FR 30999, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§1.1112 Conditionality of Commission or staff authorizations.

(a) Any instrument of authorization granted by the Commission, or by its staff under delegated authority, will be conditioned upon final payment of the applicable fee and timely payment of bills issued by the Commission. As applied to checks, bank drafts and money orders, final payment shall mean receipt by the Treasury of funds cleared by the financial institution on which the check, bank draft or money order is drawn.

(1) If, prior to a grant of an instrument of authorization, the Commission

§ 1.1113

47 CFR Ch. I (10–1–97 Edition)

is notified that final payment has not been made, the application or filing will be:

- (i) Dismissed and returned to the applicant;
- (ii) Shall lose its place in the processing line;
- (iii) And will not be accorded *nunc pro tunc* treatment if resubmitted after the relevant filing deadline.

(2) If, subsequent to a grant of an instrument of authorization, the Commission is notified that final payment has not been made, the Commission will:

- (i) Automatically rescind that instrument of authorization for failure to meet the condition imposed by this subsection; and

(ii) Notify the grantee of this action; and

- (iii) Not permit *nunc pro tunc* treatment for the resubmission of the application or filing if the relevant deadline has expired.

(3) Upon receipt of a notification of rescission of the authorization, the grantee will immediately cease operations initiated pursuant to the authorization.

(b) In those instances where the Commission has granted a request for deferred payment of a fee or issued a bill payable at a future date, further processing of the application or filing, or the grant of authority, shall be conditioned upon final payment of the fee, plus other required payments for late payments, by the date prescribed by the deferral decision or bill. Failure to comply with the terms of the deferral decision or bill shall result in the automatic dismissal of the submission or rescission of the Commission authorization for failure to meet the condition imposed by this subpart. The Commission reserves the right to return payments received after the date established on the bill and exercise the conditions attached to the application. The Commission shall:

(1) Notify the grantee that the authorization has been rescinded;

(i) Upon such notification, the grantee will immediately cease operations initiated pursuant to the authorization.

(2) Not permit *nunc pro tunc* treatment to applicants who attempt to

refile after the original deadline for the underlying submission.

(c) Where the procedures outlined in paragraphs (a) and (b) of this section would not provide a meaningful incentive to pay a fee that is due or would not be a meaningful sanction for failure to pay such a fee, in the alternative to those procedures, the Commission may, in its discretion, withhold processing and/or grant of any other application or filing made by a person or organization who has failed to make full payment of any fee due under this subpart.

(1) Before taking such action, the staff will make a written request for the fee, together with any penalties that may be due under this subpart. Such request shall inform the applicant/filer that failure to pay will result in the Commission's withholding action on any other application or request filed by the applicant. The staff shall also inform the applicant of the procedures for seeking Commission review of the staff's fee determination.

(2) If, after final determination that the fee is due, the applicant fails to pay the fee in a timely manner, the staff may terminate the processing and/or withhold a grant of any other application or filing pending or later filed by the applicant, until the matter is resolved.

[52 FR 5289, Feb. 20, 1987, as amended at 55 FR 19171, May 8, 1990. Redesignated at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1113 Return or refund of charges.

(a) The full amount of any fee submitted will be returned or refunded, as appropriate, in the following circumstances:

(1) When no fee is required for the application or other filing.

(2) When the fee processing staff or bureau/office determines that an insufficient fee has been submitted within 30 calendar days of receipt of the application or filing and the application or filing is dismissed.

(3) When the application is filed by an applicant who cannot fulfill a prescribed age requirement.

(4) When the Commission adopts new rules that nullify applications already

Federal Communications Commission

§1.1114

accepted for filing, or new law or treaty would render useless a grant or other positive disposition of the application.

(5) When a waiver is granted in accordance with this subpart.

NOTE: Payments in excess of an application fee will be refunded only if the overpayment is \$8 or more.

(6) When an application for new or modified facilities is not timely filed in accordance with the filing window as established by the Commission in a public notice specifying the earliest and latest dates for filing such applications.

(b) Applicants in the Mass Media Services designated for comparative hearings will be entitled to a grant without payment of the hearing fee or a refund of the hearing fee paid in the following circumstances.

(1) The application is granted without being designated for hearing;

(2) The application is dismissed, voluntarily or involuntarily, prior to designation for hearing, in the order designating the case for hearing, or for failure to file a Notice of Appearance (see §1.221 of this part);

(3) When only one applicant files a Notice of Appearance and pays the hearing fee, that single remaining applicant will be entitled to a refund of the hearing fee upon request if it is immediately grantable or if all issues specified in the designation order and requiring resolution can be deleted. See §1.229 of this part.

(4) When a settlement agreement filed with the presiding judge by the Notice of Appearance deadline (see §1.221 of this part) provides for the dismissal of all but one of the applicants, and the single remaining applicant is immediately grantable, no hearing fee is due. However, if the applicant cannot be granted without resolution of issues specified in the designation order, it must pay the hearing fee. That payment will be refunded upon request if all outstanding issues can be deleted. See §1.229 of this part.

(5) However, under paragraphs, (c) (3) or (4) of this section, hearing fees will be retained by the Commission in any case requiring a decision on the merits of an applicant's post-designation amendment or evidentiary showing,

whether by Summary Decision or otherwise. See §§1.251 and 1.267 of this part.

(c) Applicants in the Mass Media Services for first-come, first-served construction permits will be entitled to a refund of the fee, if, within fifteen days of the issuance of a Public Notice indicating that there is a previously filed pending application for the same vacant channel, such application notifies the Commission that they no longer wish their application to remain on file behind the first applicant and any other applicants filed before his or her application, and the applicant specifically requests a refund of the fee paid and dismissal of his or her applicant.

[52 FR 5289, Feb. 20, 1987, as amended at 53 FR 40889, Oct. 19, 1988; 56 FR 795, Jan. 9, 1991; 56 FR 56602, Nov. 6, 1991. Redesignated at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§1.1114 General exemptions to charges.

No fee established in §§1.1102 through 1.1106 of this subpart, unless otherwise qualified herein, shall be required for:

(a) Applications filed for the sole purpose of modifying an existing authorization (or a pending application for authorization) in order to comply with new or additional requirements of the Commission's rules or the rules of another Federal agency. However, if the applicant also requests an additional modification, renewal, or other action, the appropriate fee for such additional request must accompany the application. Cases in which a fee will be paid include applications by FM and TV licensees or permittees seeking to upgrade channel after a rulemaking.

(b) Applicants in the Special Emergency Radio and Public Safety Radio Services that are government entities or nonprofit entities. Applicants claiming nonprofit status must include a current Internal Revenue Service Determination Letter documenting this nonprofit status.

(c) Applicants, permittees or licensees of noncommercial educational broadcast stations in the FM or TV services, as well as AM applicants, permittees or licensees who certify that

§ 1.1115

47 CFR Ch. I (10–1–97 Edition)

the station will operate or does operate in accordance with § 73.503 of the rules.

(d) Applicants, permittees, or licensees qualifying under paragraph (c) of this section requesting Commission authorization in any other mass media radio service (except the international broadcast (HF) service) private radio service, or common carrier radio communications service otherwise requiring a fee, if the radio service is used in conjunction with the noncommercial educational broadcast station on a noncommercial educational basis.

(e) Other applicants, permittees, or licensees providing, or proposing to provide, a noncommercial educational or instructional service, but not qualifying under paragraph (c) of this section, may be exempt from filing fees, or be entitled to a refund, in the following circumstances.

(1) An applicant is exempt from filing fees if it is an organization that, like the Public Broadcasting Service or National Public Radio, receives funding directly or indirectly through the Public Broadcasting Fund, 47 U.S.C. 396(k), distributed by the Corporation for Public Broadcasting, where the authorization requested will be used in conjunction with the organization on a noncommercial educational basis;

(2) An applicant for a translator or low power television station that proposes a noncommercial educational service will be entitled to a refund of fees paid for the filing of the application when, after grant, it provides proof that it has received funding for the construction of the station through the National Telecommunications and Information Administration (NTIA) or other showings as required by the Commission.

(3) An applicant that has qualified for a fee refund under paragraph (e)(2) of this section and continues to operate as a noncommercial education station is exempt from fees for broadcast auxiliary stations (subparts D, E, and F of part 74) or stations in the private radio or common carrier services where such authorization is to be used in conjunction with the noncommercial educational translator or low power station.

(4) An applicant that is the licensee of an instructional television fixed sta-

tion (§ 74.901 *et seq.*) is exempt from filing fees where the authorization requested will be used by the applicant in conjunction with the provision of the instructional service.

(f) Applicants, permittees or licensees who qualify as governmental entities. For purposes of this exemption a governmental entity is defined as any state, possession, city, county, town, village, municipal corporation or similar political organization or subpart thereof controlled by publicly elected or duly appointed public officials exercising sovereign direction and control over their respective communities or programs.

(g) Applications for Restricted Radiotelephone Operator Permits where the applicant intends to use the permit solely in conjunction with duties performed at radio facilities qualifying for fee exemption under paragraphs (c), (d), or (e) of this section.

NOTE: Applicants claiming exemptions under the terms of this subpart must certify as to their eligibility for the exemption through a cover letter accompanying the application or filing. This certification is not required if the applicable FCC Form requests the information justifying the exemption.

[52 FR 5289, Feb. 20, 1987, as amended at 53 FR 40889, Oct. 19, 1988; 55 FR 19172, May 8, 1990; 56 FR 56602, Nov. 6, 1991. Redesignated and amended at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1115 Adjustments to charges.

(a) The Schedule of Charges established by sections 1.1102 through 1.1106 of this subpart shall be adjusted by the Commission on October 1, 1993 and every two years thereafter.

(1) The fees will be adjusted by the Commission to reflect the percentage change in the Consumer Price Index for all Urban Consumers (CPI-U) from the date of enactment of the authorizing legislation (December 19, 1989) to the date of adjustment, and every two years thereafter, to reflect the percentage change in the CPI-U in the period between the enactment date and the adjustment date.

(2) Adjustments based upon the percentage change in the CPI-U will be applied against the base fees as enacted or amended by Congress. Adjustments

Federal Communications Commission

§1.1117

will not be calculated by using the previously adjusted fee as the base.

(b) Increases or decreases in charges will apply to all categories of fees covered by this subpart. Individual fees will not be adjusted until the increase or decrease, as determined by the net change in the CPI-U since the date of enactment of the authorizing legislation, amounts to at least \$5 in the case of fees under \$100, or 5% or more in the case of fees of \$100 or greater. All fees will be adjusted upward to the next \$5 increment.

(c) Adjustments to fees made pursuant to these procedures will not be subject to notice and comment rulemakings, nor will these decisions be subject to petitions for reconsideration under §1.429 of the rules. Requests for modifications will be limited to correction of arithmetical errors made during an adjustment cycle.

[52 FR 5289, Feb. 20, 1987, as amended at 53 FR 40889, Oct. 19, 1988; 55 FR 19172, May 8, 1990. Redesignated and amended at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§1.1116 Penalty for late or insufficient payments.

(a) Filings subject to fees and accompanied by defective fee submissions will be dismissed under §1.1108(b) of this subpart where the defect is discovered by the Commission's staff within 30 calendar days from the receipt of the application or filing by the Commission.

(1) A defective fee may be corrected by resubmitting the application or other filing, together with the entire correct fee.

(2) For purposes of determining whether the filing is timely, the date of resubmission with the correct fee will be considered the date of filing. However, in cases where the fee payment fails due to error of the applicant's bank, as evidenced by an affidavit of an officer of the bank, the date of the original submission will be considered the date of filing.

(b) Applications or filings accompanied by insufficient fees or no fees which are inadvertently forwarded to Commission staff for substantive review will be filed for the amount due if the discrepancy is not discovered

until after 30 calendar days from the receipt of the application or filing at the Commission. A penalty charge of 25 percent of the amount due will be added to each bill. Any Commission actions taken prior to timely payment of this bill are contingent and subject to rescission.

(c) Applicants to whom a deferral of payment is granted under the terms of this subsection will be billed for the amount due plus a charge equalling 25 percent of the amount due. Any Commission actions taken prior to timely payment of these charges are contingent and subject to rescission.

[52 FR 5289, Feb. 20, 1987, as amended at 53 FR 40889, Oct. 19, 1988; 55 FR 19172, May 8, 1990. Redesignated and amended at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§1.1117 Petitions and applications for review.

(a) The fees established by this subpart may be waived or deferred in specific instances where good cause is shown and where waiver or deferral of the fee would promote the public interest.

(b) Requests for waivers or deferrals will only be considered when received from applicants acting in respect to their own applications. Requests for waivers or deferrals of entire classes of services will not be considered.

(c) Petitions for waivers, deferrals, fee determinations, reconsideration and applications for review will be acted upon by the Managing Director. Petitions and applications for review submitted with a fee must be submitted to the Commission's lockbox bank at the address for the appropriate service set forth in §§1.1102 through 1.1105. If no fee payment is required, and the matter is within the scope of the fee rules in this subpart, the petition or application for review should be filed with the Commission's Secretary and clearly marked to the attention of the Managing Director. Requests for deferral of a fee payment for financial hardship must be accompanied by supporting documentation.

(d) Deferrals of fees will be granted for an established period of time not to exceed six months.

§ 1.1118

47 CFR Ch. I (10–1–97 Edition)

(e) Applicants seeking waivers must submit the request for waiver with the application or filing, required fee and FCC Form 155. Waiver requests that do not include these materials will be dismissed in accordance with § 1.1108 of this subpart. Submitted fees will be returned if a waiver is granted. The Commission will not be responsible for delays in acting upon these requests.

[52 FR 5289, Feb. 20, 1987, as amended at 55 FR 19172, May 8, 1990; 55 FR 38065, Sept. 17, 1990. Redesignated and amended at 59 FR 30998, June 16, 1994, as further amended at 59 FR 30999, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1118 Error claims.

(a) Applicants who wish to challenge a staff determination of an insufficient fee may do so in writing. These claims should be addressed to the same location as the original submission marked “Attention Fee Supervisor”.

(b) Actions taken by the Fee Section staff are subject to the reconsideration and review provisions of §§ 1.106 and 1.115 of this part, EXCEPT THAT reconsideration and/or review will only be available where the applicant has made the full and proper payment of the underlying fee as required by this subpart.

(1) Petitions for reconsideration and/or applications for review submitted by applicants that have not made the full and proper fee payment will be dismissed; and

(2) If the fee payment should fail while the Commission is considering the matter, the petition for reconsideration or application for review will be dismissed.

[52 FR 5289, Feb. 20, 1987, as amended at 53 FR 40889, Oct. 19, 1988. Redesignated at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1119 Billing procedures.

(a) The fees required for the International Telecommunications Settlements (§ 1.1103(19) of this subpart) and Common Carrier Field Audits (§ 1.1105(21) (a) and (b) of this subpart) should not be paid with the filing or submission of the request. The fees required for requests for Special Temporary Authority (see generally §§ 1.1102, 1.1104, 1.1105 of this subpart) that the applicant believes is of an urgent or emergency nature and are filed directly with the appropriate Bureau or Office should not be paid with the filing of the request with that Bureau or Office.

(b) In these cases, the appropriate fee will be determined by the Commission and the filer will be billed for that fee. The bill will set forth the amount to be paid, the date on which payment is due, and the address to which the payment should be submitted. See also § 1.1111 of this subpart.

[55 FR 19172, May 8, 1990, as amended at 58 FR 68541, Dec. 28, 1993. Redesignated and amended at 59 FR 30998, June 16, 1994. Redesignated at 60 FR 5326, Jan. 27, 1995]

§ 1.1151 Authority to prescribe and collect regulatory fees.

Authority to impose and collect regulatory fees is contained in title VI, section 6002(a) of the Omnibus Budget Reconciliation Act of 1993 (Pub. L. 103–66, 107 Stat. 397), enacting section 9 of the Communications Act, 47 U.S.C. 159, which directs the Commission to prescribe and collect annual regulatory fees from designated regulatees in order to recover the costs of certain of its regulatory activities in the private radio, mass media, common carrier, and cable television services.

[59 FR 30999, June 16, 1994]

§ 1.1152 Schedule of annual regulatory fees and filing locations for wireless radio services.

Exclusive use services (per license)	Fee amount	Address
1. Land Mobile (Above 470 MHz, Base Station and SMRS)(47 CFR Part 90):		
(a) 800 MHz New, Renewal, Reinstatement (FCC 600)	\$10.00	FCC, 800 MHz, P.O. Box 358235, Pittsburgh, PA 15251–5235
(b) 900 MHz New, Renewal, Reinstatement (FCC 600)	10.00	FCC, 900 MHz, P.O. Box 358240, Pittsburgh, PA 15251–5240

Federal Communications Commission

§ 1.1152

Exclusive use services (per license)	Fee amount	Address
(c) 470–512,800,900, 220 MHz, 220 MHz Nationwide Renewal (FCC 574R, FCC 405A).	10.00	FCC, 470–512, P.O. Box 358245, Pittsburgh, PA 15251–5245
(d) Correspondence Blanket Renewal (470–512,800,900,220 MHz) (Remittance Advice, Correspondence).	10.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
(e) 220 MHz New, Renewal, Reinstatement (FCC 600)	10.00	FCC, 220 MHz, P.O. Box 358360, Pittsburgh, PA 15251–5360
(f) 470–512 MHz New, Renewal, Reinstatement (FCC 600).	10.00	FCC, 470–512, P.O. Box 358810, Pittsburgh, PA 15251–5810
(g) 220 MHz Nationwide New, Renewal, Reinstatement (FCC 600).	10.00	FCC, Nationwide, P.O. Box 358820, Pittsburgh, PA 15251–5820
2. Microwave (47 CFR Part 101):		
(a) Microwave New, Renewal, Reinstatement (FCC 415).	10.00	FCC, Microwave, P.O. Box 358250, Pittsburgh, PA 15251–5250
(b) Microwave Renewal (FCC 402R)	10.00	FCC, Microwave, P.O. Box 358255, Pittsburgh, PA 15251–5255
(c) Correspondence Blanket Renewal (Microwave) (Remittance Advice, Correspondence).	10.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
3. Shared Use Services:		
(a) Land Transportation (LT) New, Renewal, Reinstatement (FCC 600).	5.00	FCC, Land Trans., P.O. Box 358215, Pittsburgh, PA 15251–5215
(b) Business (Bus.) New, Renewal, Reinstatement (FCC 600).	5.00	FCC, Business, P.O. Box 358220, Pittsburgh, PA 15251–5220
(c) Other Industrial (OI) New, Renewal, Reinstatement (FCC 600).	5.00	FCC, Other Indus., P.O. Box 358225, Pittsburgh, PA 15251–5225
(d) General Mobile Radio Service (GMRS) New, Renewal, Reinstatement (FCC 574).	5.00	FCC, GMRS, P.O. Box 358230, Pittsburgh, PA 15251–5230
(e) Business, Other Industrial, Land Transportation, GMRS Renewal (FCC 574R, FCC 405A).	5.00	FCC, Bus.,OI,LT,GMRS, P.O. Box 358245, Pittsburgh, PA 15251–5245
(f) Ground New, Renewal, Reinstatement (FCC 406) ..	5.00	FCC, Ground, P.O. Box 358260, Pittsburgh, PA 15251–5260
(g) Coast New, Renewal, Reinstatement (FCC 503)	5.00	FCC, Coast, P.O. Box 358265, Pittsburgh, PA 15251–5265
(h) Ground Renewal (FCC 452R)	5.00	FCC, Ground, P.O. Box 358270, Pittsburgh, PA 15251–5270
(i) Coast Renewal (FCC 452R)	5.00	FCC, Coast, P.O. Box 358270, Pittsburgh, PA 15251–5270
(j) Ship New, Renewal, Reinstatement (FCC 506)	5.00	FCC, Ship, P.O. Box 358275, Pittsburgh, PA 15251–5275
(k) Aircraft New, Renewal, Reinstatement (FCC 404) ..	5.00	FCC, Aircraft, P.O. Box 358280, Pittsburgh, PA 15251–5280
(l) Ship Renewal (FCC 405B)	5.00	FCC, Ship, P.O. Box 358290, Pittsburgh, PA 15251–5290
(m) Aircraft Renewal (FCC 405B)	5.00	FCC, Aircraft, P.O. Box 358290, Pittsburgh, PA 15251–5290
(n) Correspondence Blanket Renewal (Bus.,OI,LT,GMRS) (Remittance Advice, Correspondence).	5.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
(o) Correspondence Blanket Renewal (Ground) (Remittance Advice, Correspondence).	5.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
(p) Correspondence Blanket Renewal (Coast) (Remittance Advice, Correspondence).	5.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
(q) Correspondence Blanket Renewal (Aircraft) (Remittance Advice, Correspondence).	5.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
(r) Correspondence Blanket Renewal (Ship) (Remittance Advice, Correspondence).	5.00	FCC, Corres., P.O. Box 358305, Pittsburgh, PA 15251–5305
4. Amateur Vanity Call Signs	5.00	FCC, Amateur Vanity, P.O. Box 358924, Pittsburgh, PA 15251–5924
5. CMRS Mobile Services (per unit)	.24	FCC, Cellular, P.O. Box 358835, Pittsburgh, PA 15251–5835
6. CMRS Messaging Services (per unit)	.03	FCC, Messaging, P.O. Box 358835, Pittsburgh, PA 15251–5835

[62 FR 37422, July 11, 1997]

§ 1.1153

47 CFR Ch. I (10–1–97 Edition)

§ 1.1153 Schedule of annual regulatory fees and filing locations for mass media services.

	Fee amount	Address
I. Radio [AM and FM] (47 CFR Part 73):		
1. Group 1	\$2,000	FCC, Radio, P.O. Box 358835, Pittsburgh, PA, 15251–5835
2. Group 2	1,800	
3. Group 3	1,600	
4. Group 4	1,400	
5. Group 5	1,200	
6. Group 6	1,000	
7. Group 7	800	
8. Group 8	600	
9. Group 9	400	
10. Group 10	200	
11. AM Construction Permits	195	
12. FM Construction Permits	950	
II. TV (47 CFR Part 73) VHF Commercial:		
1. Markets 1 thru 10	35,025	FCC, TV Branch, P.O. Box 358835, Pittsburgh, PA 15251–5835
2. Markets 11 thru 25	28,450	
3. Markets 26 thru 50	18,600	
4. Markets 51 thru 100	9,850	
5. Remaining Markets	2,725	
6. Construction Permits	4,800	
III. UHF Commercial:		
1. Markets 1 thru 10	16,850	FCC, UHF Commercial, P.O. Box 358835, Pittsburgh, PA 15251–5835
2. Markets 11 thru 25	13,475	
3. Markets 26 thru 50	8,750	
4. Markets 51 thru 100	4,725	
5. Remaining Markets	1,350	
6. Construction Permits	2,975	
IV. Satellite UHF/VHF Commercial:		
1. All Markets	950	FCC Satellite TV, P.O. Box 358835, Pittsburgh, PA 15251–5835
2. Construction Permits	345	
V. Low Power TV, TV/FM Translator, & TV/FM Booster (47 CFR Part 74).	220	FCC, Low Power, P.O. Box 358835, Pittsburgh, PA 15251–5835
VI. Broadcast Auxiliary	25	FCC, Auxiliary, P.O. Box 358835, Pittsburgh, PA 15251–5835
VII. Multipoint Distribution	215	FCC, Multipoint, P.O. Box 358835, Pittsburgh, PA 15251–5835

[62 FR 37423, July 11, 1997]

§ 1.1154 Schedule of annual regulatory charges and filing locations for common carrier services.

	Fee amount	Address
I. Radio Facilities:		
1. Microwave (Domestic Public Fixed)	\$10	FCC, Common Carrier, P.O. Box 358680, Pittsburgh, PA 15251–5680
II. Carriers:		
1. Interstate Telephone Service Providers, (per dollar contributed to TRS Fund).	.000116	FCC, Carriers, P.O. Box 358835, Pittsburgh, PA

[62 FR 37423, July 11, 1997]

§ 1.1155 Schedule of regulatory fees and filing locations for cable television services.

	Fee amount	Address
1. Cable Antenna Relay Service	\$65	FCC, Cable, P.O. Box 358835, Pittsburgh, PA 15251–5835
2. Cable TV System (per subscriber)	.54	

[62 FR 37423, July 11, 1997]

Federal Communications Commission

§1.1157

§1.1156 Schedule of regulatory fees and filing locations for international services.

	Fee amount	Address
I. Radio Facilities:		
1. International (HF) Broadcast	\$390	FCC, International, P.O. Box 358835, Pittsburgh, PA 15251-5835
2. International Public Fixed	310	FCC, International, P.O. Box 358835, Pittsburgh, PA 15251-5835
II. Space Stations (Geosynchronous Orbit)	97,975	FCC, Space Stations, P.O. Box 358835, Pittsburgh, PA 15251-5835
III. Low Earth Orbit Satellite	135,675	FCC, Space Stations, P.O. Box 358835, Pittsburgh, PA 15251-5835
IV. Earth Stations; Transmit/Receive and Transmit Only (per authorization or registration).	515	FCC, Earth Station, P.O. Box 358835, Pittsburgh, PA 15251-5835
V. Carriers:		
1. International Bearer Circuits (per active 64KB circuit or equivalent).	5.00	FCC, International, P.O. Box 358835, Pittsburgh, PA 15251-5835

[62 FR 37423, July 11, 1997]

§1.1157 Payment of charges for regulatory fees.

Payment of a regulatory fee, required under §§1.1152 through 1.1156, shall be filed in the following manner:

(a) Payments of regulatory fees shall be submitted with the filing of any application for a new, renewal or reinstatement of a license or other authorization in the wireless radio services. (1) Any regulatory fee submitted with an application in the wireless radio services shall include an advance payment of the total annual regulatory fee payment due for the entire term of the license or other authorization. The amount of the regulatory fee payment due with any application in the wireless radio service shall be the multiple of the number of years in the entire term of the requested license or other authorization multiplied by the annual fee payment required in the Schedule of Regulatory Fees, effective at the time the application is filed. Except as set forth in §1.1160, advance payments shall be final and shall not be readjusted during the term of the license or authorization, notwithstanding any subsequent increase or decrease in the annual amount of a fee required under the Schedule of Regulatory Fees.

(2) Failure to file the appropriate regulatory fee with an application in the wireless radio service will result in the return of the accompanying application, including an application, for which the Commission has assigned a specific filing deadline.

(b)(1) Payments of standard regulatory fees, applicable to mass media,

common carrier, cable and international services, shall be filed in full on an annual basis at a time announced by the Commission or the Managing Director, pursuant to delegated authority, and published in the FEDERAL REGISTER.

(2) Large regulatory fees, as annually defined by the Commission, may be submitted in installment payments or in a single payment on a date certain as announced by the Commission or the Managing Director, pursuant to delegated authority, and published in the FEDERAL REGISTER.

(c) Standard regulatory fee payments, as well as any installment payment, must be filed with a FCC Form 159, FCC Remittance Advice, and a FCC Form 159C, Remittance Advice Continuation Sheet, if additional space is needed. Failure to submit a copy of FCC Form 159 with a standard regulatory fee payment, or an installment payment, will result in the return of the submission and a 25 percent penalty if the payment is resubmitted after the date the Commission establishes for the payment of standard regulatory fees and for any installment payment.

(1) Any late filed regulatory fee payment will be subject to the penalties set forth in section 1.1164.

(2) If one or more installment payments are untimely submitted or not submitted at all, the eligibility of the subject regulatee to submit installment payments may be cancelled.

[60 FR 34031, June 29, 1995]

§1.1158

47 CFR Ch. I (10–1–97 Edition)

§1.1158 Form of payment for regulatory.

Any regulatory fee payment must be submitted in the form of a check, bank draft or money order denominated in U.S. dollars and drawn on a United States financial institution and made payable to the Federal Communications Commission or by Visa or Mastercard credit cards only. The Commission discourages applicants from submitting cash payments and will not be responsible for cash sent through the mail. Personal or corporate checks dated more than six months prior to their submission to the Commission's lockbox bank and postdated checks will not be accepted and will be returned as deficient.

(a) Upon authorization from the Commission following a written request, electronic fund transfer (EFT) payment of a regulatory fee may be made as follows:

(1)(i) The payor may instruct its bank to make payment of the regulatory fee directly to the Commission's lockbox bank, or

(ii) The payor may authorize the Commission to direct its lockbox bank to withdraw funds directly from the payor's bank account.

(2) No EFT payment of a regulatory fee will be accepted unless the payor has obtained the written authorization of the Commission to submit regulatory fees electronically. Procedures for electronic payment of regulatory fees will be announced by Public Notice. It is the responsibility of the payor to insure that any electronic payment is made in the manner required by the Commission. Failure to comply with the Commission's procedures for electronic fee payment will result in the return of the fee payment, and a penalty fee of 25 percent if the subsequent refiling of the fee payment is late. Failure to comply will also subject the payor to the penalties set forth in §1.1164.

(b) Multiple payment instruments for a single regulatory fee are not permitted, except that the Commission will accept multiple money orders in payment of any fee where the fee exceeds the maximum amount for a money order established by the issuing entity and the use of multiple money

orders is the only practicable means available for payment.

(c) Payment of multiple standard regulatory fees (including an installment payment) due on the same date, may be made with a single payment instrument and cover mass media, common carrier, international, and cable service fee payments. Each regulatee is solely responsible for accurately accounting for and listing each license or authorization and the number of subscribers, access lines, or other relevant units on the accompanying FCC Form 159 and, if needed, FCC Form 159C and for making full payment for every regulatory fee listed on the accompanying form. Any omission or payment deficiency of a regulatory fee will result in a 25 percent penalty of the amount due and unpaid.

(d) Any regulatory fee payment (including a regulatory fee payment submitted with an application in the wireless radio service) made by credit card or money order must be submitted with a completed FCC Form 159. Failure to accurately enter the credit card number and date of expiration and the payor's signature in the appropriate blocks on FCC Form 159 will result in rejection of the credit card payment.

[60 FR 34031, June 29, 1995]

§1.1159 Filing locations and receipts for regulatory fees.

(a) Regulatory fee payments must be directed to the location and address set forth in §§1.1152 through 1.1156 for the specific category of fee involved. Any regulatory fee required to be submitted with an application must be filed as a part of the application package accompanying the application. The Commission will not take responsibility for matching fees, forms and applications submitted at different times or locations.

(b) Petitions for reconsideration or applications for review of fee decisions submitted with a standard regulatory fee payment pursuant to §§1.1152 through 1.1156 of the rules are to be filed with the Commission's lockbox bank in the manner set forth in §§1.1152 through 1.1156 for payment of the fee

Federal Communications Commission

§1.1161

subject to the petition for reconsideration or the application for review. Petitions for reconsideration and applications for review that are submitted with no accompanying payment should be filed with the Secretary, Federal Communications Commission, Attention: Managing Director, Washington, D.C. 20554.

(c) Any request for exemption from a regulatory fee shall be filed with the Secretary, Federal Communications Commission, Attention: Managing Director, Washington, D.C. 20554, except that requests for exemption accompanied by a tentative fee payment shall be filed at the lockbox set forth for the appropriate service in §§1.1152 through 1.1156.

(d) The Commission will furnish a receipt for a regulatory fee payment only upon request. In order to obtain a receipt for a regulatory fee payment, the package must include an extra copy of the Form FCC 159 or, if a Form 159 is not required with the payment, a copy of the first page of the application or other filing submitted with the regulatory fee payment, submitted expressly for the purpose of serving as a receipt for the regulatory fee payment and application fee payment, if required. The document should be clearly marked "copy" and should be the top document in the package. The copy will be date stamped immediately and provided to the bearer of the submission, if hand delivered. For submissions by mail, the receipt copy will be provided through return mail if the filer has attached to the receipt copy a stamped self-addressed envelope of sufficient size to contain the receipt document.

[60 FR 34032, June 29, 1995]

§1.1160 Refunds of regulatory fees.

(a) Regulatory fees will be refunded, upon request, only in the following instances:

(1) When no regulatory fee is required or an excessive fee has been paid. In the case of an overpayment, the refund amount will be based on the applicants', permittees', or licensees' entire submission. All refunds will be issued to the payor named in the appropriate block of the FCC Form 159.

(2) In the case of advance payment of regulatory fees, subject to §1.1152, a refund will be issued based on unexpired full years:

(i) When the Commission adopts new rules that nullify a license or other authorization, or a new law or treaty renders a license or other authorization useless;

(ii) When a licensee in the wireless radio service surrenders the license or other authorization subject to a fee payment to the Commission; or

(iii) When the Commission declines to grant an application submitted with a regulatory fee payment.

(3) When a waiver is granted in accordance with §1.1166.

(b) No pro-rata refund of an annual fee will be issued.

(c) No refunds will be issued based on unexpired partial years.

(d) No refunds will be processed without a written request from the applicant, permittee, licensee or agent.

[60 FR 34032, June 29, 1995]

§1.1161 Conditional license grants and delegated authorizations.

(a) Grant of any application or an instrument of authorization or other filing, for which a regulatory fee is required to accompany the application or filing, will be conditioned upon final payment of the regulatory fee. Final payment shall mean receipt by the U.S. Treasury of funds cleared by the financial institution on which the check, bank draft, money order, credit card, wire or electronic payment is drawn.

(1) If, prior to a grant of an instrument of authorization, the Commission is notified that final payment of the regulatory fee has not been made, the application or filing:

(i) Will be dismissed and returned;

(ii) Shall lose its place in the processing line; and

(iii) Will not be treated as timely filed if resubmitted after the relevant filing deadline.

(2) If, subsequent to a grant of an instrument of authorization or other filing, the Commission is notified that final payment has not been made, the Commission will:

(i) Automatically rescind that instrument of authorization for failure to

§ 1.1162

47 CFR Ch. I (10–1–97 Edition)

meet the condition imposed by this subsection;

(ii) Notify the grantee of this action; and

(iii) Treat as late filed any application resubmitted after the original deadline for filing the application.

(3) Upon receipt of a notification of rescission of the authorization, the grantee will immediately cease operations initiated pursuant to the authorization.

(b) In those instances where the Commission has granted a request for deferred payment of a regulatory fee, further processing of the application or filing or the grant of authority shall be conditioned upon final payment of the regulatory fee and any required penalties for late payment prescribed by the deferral decision. Failure to comply with the terms of the deferral decision shall result in the automatic dismissal of the submission or rescission of the Commission authorization. Further, the Commission shall:

(1) Notify the grantee that the authorization has been rescinded. Upon such notification, the grantee will immediately cease operations initiated pursuant to the authorization; and

(2) Treat as late filed any application resubmitted after the original deadline for filing the application.

(c) Where the procedures described in paragraphs (a) and (b) of this section would not provide a meaningful incentive to pay a regulatory fee that is due or would not be a meaningful sanction for failure to pay such a fee, the Commission may, in its discretion, whether the regulatory fee is required to be paid with an application for an instrument of authorization or otherwise, withhold processing and/or grant of any application or filing made by a person or organization who has failed to make full payment of any regulatory fee due.

(1) Before taking such action, the staff will make a written request for the fee, together with any penalties that may be rendered under this subpart. Such request shall inform the regulatee that failure to pay may result in the Commission withholding action on any application or request filed by the applicant. The staff shall also inform the regulatee of the procedures

for seeking Commission review of the staff's fee determination.

(2) If, after final determination that the fee is due, payment is not made in a timely manner, the staff may terminate processing and/or withhold any grant or petition requested by the person or organization subject to the fee payment requirement, until the matter is resolved.

[60 FR 34032, June 29, 1995]

§ 1.1162 General exemptions from regulatory fees.

No regulatory fee established in §§ 1.1152 through 1.1156, unless otherwise qualified herein, shall be required for: (a) Applicants, permittees or licensees in the Amateur Radio Service, *except that* any person requesting a vanity call-sign shall be subject to the payment of a regulatory fee, as prescribed in § 1.1152.

(b) Applicants, permittees, or licensees who qualify as government entities. For purposes of this exemption, a government entity is defined as any state, possession, city, county, town, village, municipal corporation, or similar political organization or subpart thereof controlled by publicly elected or duly appointed public officials exercising sovereign direction and control over their respective communities or programs.

(c) Applicants and permittees who qualify as nonprofit entities. For purposes of this exemption, a nonprofit entity is defined as: an organization duly qualified as a nonprofit, tax exempt entity under section 501 of the Internal Revenue Code, 26 U.S.C. 501; or an entity with current certification as a nonprofit corporation or other nonprofit entity by state or other governmental authority.

(d) Applicants, permittees or licensees in the Special Emergency Radio and Public Safety Radio services.

(e) Applicants, permittees or licensees of noncommercial educational broadcast stations in the FM or TV services, as well as AM applicants, permittees or licensees operating in accordance with § 73.503 of this chapter.

(f) Applicants, permittees, or licensees qualifying under paragraph (e) of this section requesting Commission authorization in any other mass media

Federal Communications Commission

§1.1163

radio service (except the international broadcast (HF) service), wireless radio service, common carrier radio service, or international radio service requiring payment of a regulatory fee, if the service is used in conjunction with their noncommercial educational broadcast station on a noncommercial educational basis.

(g) Other applicants, permittees or licensees providing, or proposing to provide, a noncommercial educational or instructional service, but not qualifying under paragraph (e) of this section, may be exempt from regulatory fees, or be entitled to a refund, in the following circumstances:

(1) The applicant, permittee or licensee is an organization that, like the Public Broadcasting Service or National Public Radio, receives funding directly or indirectly through the Public Broadcasting Fund, 47 U.S.C. 396(k), distributed by the Corporation for Public Broadcasting, where the authorization requested will be used in conjunction with the organization on a noncommercial educational basis;

(2) An applicant, permittee or licensee of a translator or low power television station operating or proposing to operate a noncommercial educational service who, after grant, provides proof that it has received funding for the construction of the station through the National Telecommunications and Information Administration (NTIA) or other showings as required by the Commission; or

(3) An applicant, permittee, or licensee provided a fee refund under §1.1160 and operating as a noncommercial education station, is exempt from fees for broadcast auxiliary stations (subparts D, E, and F of part 74 of this chapter) or stations in the wireless radio, common carrier, or international services where such authorization is to be used in conjunction with the noncommercial educational translator or low power station.

(h) An applicant, permittee or licensee that is the licensee of an instructional television fixed station (§§74.901 through 74.996 of this chapter) is exempt from regulatory fees where the authorization requested will be used by the applicant in conjunction

with the provision of the instructional service.

(i) Applications filed in the wireless radio service for the sole purpose of modifying an existing authorization (or a pending application for authorization). However, if the applicant also requests a renewal or reinstatement of its license or other authorization for which the submission of a regulatory fee is required, the appropriate regulatory fee for such additional request must accompany the application.

[60 FR 34033, June 29, 1995, as amended at 60 FR 34904, July 5, 1995]

§1.1163 Adjustments to regulatory fees.

(a) For Fiscal Year 1995, the amounts assessed for regulatory fees are set forth in §§1.1152 through 1.1156.

(b) For Fiscal year 1996 and thereafter, the Schedule of Regulatory Fees, contained in §§1.1152 through 1.1156, may be adjusted annually by the Commission pursuant to section 9 of the Communications Act. 47 U.S.C. 159. Adjustments to the fees established for any category of regulatory fee payment shall include projected cost increases or decreases and an estimate of the volume of licensees or units upon which the regulatory fee is calculated.

(c) The fees assessed shall:

(1) Be derived by determining the full-time equivalent number of employees performing enforcement activities, policy and rulemaking activities, user information services, and international activities within the Wireless Telecommunications Bureau, Mass Media Bureau, Common Carrier Bureau, Cable Services Bureau, International Bureau and other offices of the Commission, adjusted to take into account factors that are reasonably related to the benefits provided to the payor of the fee by the Commission's activities, including such factors as service coverage area, shared use versus exclusive use, and other factors that the Commission determines are necessary in the public interest;

(2) Be established at amounts that will result in collection, during each fiscal year, of an amount that can reasonably be expected to equal the amount appropriated for such fiscal

year for the performance of the activities described in paragraph (c)(1) of this section.

(d) The Commission shall by rule amend the Schedule of Regulatory Fees by proportionate increases or decreases that reflect, in accordance with paragraph (c)(2) of this section, changes in the amount appropriated for the performance of the activities described in paragraph (c)(1) of this section, for such fiscal year. Such proportionate increases or decreases shall be adjusted to reflect unexpected increases or decreases in the number of licensees or units subject to payment of such fees and result in collection of an aggregate amount of fees that will approximately equal the amount appropriated for the subject regulatory activities.

(e) The Commission shall, by rule, amend the Schedule of Regulatory Fees if the Commission determines that the Schedule requires amendment to comply with the requirements of paragraph (c)(1) of this section. In making such amendments, the Commission shall add, delete or reclassify services in the Schedule to reflect additional deletions or changes in the nature of its services as a consequence of Commission rule-making proceedings or changes in law.

(f) In making adjustments to regulatory fees, the Commission will round such fees to the nearest \$5.00 in the case of fees under \$1,000.00, or to the nearest \$25.00 in the case of fees of \$1,000.00 or more.

[60 FR 34033, June 29, 1995]

§ 1.1164 Penalties for late or insufficient regulatory fee payments.

Any late payment or insufficient payment of a regulatory fee, not excused by bank error, shall subject the regulatee to a 25 percent penalty of the amount of the fee of installment payment which was not paid in a timely manner. A timely fee payment or installment payment is one received at the Commission's lockbox bank by the due date specified by the Commission or by the Managing Director. A payment will also be considered late filed if the payment instrument (check, money order, bank draft or credit card) is uncollectible.

(a) The Commission may, in its discretion, following one or more late

filed installment payments, require a regulatee to pay the entire balance of its regulatory fee by a date certain, in addition to assessing a 25 percent penalty.

(b) In cases where a fee payment fails due to error by the payor's bank, as evidenced by an affidavit of an officer of the bank, the date of the original submission will be considered the date of filing.

(c) If a regulatory fee is paid in a timely manner, the regulatee will be notified of its deficiency. This notice will automatically assess a 25 percent penalty, subject the delinquent payor's pending applications to dismissal, and may require a delinquent payor to show cause why its existing instruments of authorization should not be subject to rescission.

(d)(1) Where a regulatee's new, renewal or reinstatement application is required to be filed with a regulatory fee (as is the case with wireless radio services), the application will be dismissed if the regulatory fee is not included with the application package. In the case of a renewal or reinstatement application, the application may not be refiled unless the appropriate regulatory fee plus the 25 percent penalty charge accompanies the refiled application.

(2) If the application that must be accompanied by a regulatory fee is a mutually exclusive application with a filing deadline, or any other application that must be filed by a date certain, the application will be dismissed if not accompanied by the proper regulatory fee and will be treated as late filed if resubmitted after the original date for filing application.

(e) Any pending or subsequently filed application submitted by a party will be dismissed if that party is determined to be delinquent in paying a standard regulatory fee or an installment payment. The application may be resubmitted only if accompanied by the required regulatory fee and by any assessed penalty payment.

(f) In instances where the Commission may revoke an existing instrument of authorization for failure to file a regulatory fee, the Commission will provide prior notice to the regulatee of such action and shall allow the licensee

Federal Communications Commission

§1.1167

no less than 60 days to either pay the fee or show cause why the payment assessed is inapplicable or should otherwise be waived or deferred.

(1) An adjudicatory hearing will not be designated unless the response by the regulatee to the Order to Show Cause presents a substantial and material question of fact.

(2) Disposition of the proceeding shall be based upon written evidence only and the burden of proceeding with the introduction of evidence and the burden of proof shall be on the respondent regulatee.

(3) Unless the regulatee substantially prevails in the hearing, the Commission may assess costs for the conduct of the proceeding against the respondent regulatee. *See* 47 U.S.C. 402(b)(5).

(4) Any regulatee failing to submit a regulatory fee, following notice to the regulatee of failure to submit the required fee, is subject to collection of the fee, including interest thereon, any associated penalties, and the full cost of collection to the Federal government pursuant to section 3720A of the Internal Revenue Code, 31 U.S.C. 3717, and to the provisions of the Debt Collection Act, 31 U.S.C. 3717. *See* 47 CFR 1.1901 through 1.1952. The debt collection processes described above may proceed concurrently with any other sanction in this paragraph.

[60 FR 34034, June 29, 1995]

1.1165 Payment by cashier's check for regulatory fees.

Payment by cashier's check may be required when a person or organization makes payment, on one or more occasions, with a payment instrument on which the Commission does not receive final payment and such error is not excused by bank error.

[60 FR 34034, June 29, 1995]

§1.1166 Waivers, reductions and deferrals of regulatory fees.

The fees established by sections 1.1152 through 1.1156 may be waived, reduced or deferred in specific instances, on a case-by-case basis, where good cause is shown and where waiver, reduction or deferral of the fee would promote the public interest. Requests for waivers, reductions or deferrals of

regulatory fees for entire categories of payors will not be considered.

(a) Requests for waivers, reductions or deferrals will be acted upon by the Managing Director with the concurrence of the General Counsel. If the request for waiver, reduction or deferral is accompanied by a fee payment, the request must be submitted to the Commission's lockbox bank at the address for the appropriate service set forth in sections 1.1152 through 1.1156 of this subpart. If no fee payment is submitted and the matter is within the scope of the fee rules, the request should be filed with the Commission's Secretary and clearly marked to the attention of the Managing Director.

(b) Deferrals of fees will be granted for a period of six months following the date that the fee is initially due.

(c) Petitions for waiver of a regulatory fee must be accompanied by the required fee and FCC Form 159. Submitted fees will be returned if a waiver is granted. Waiver requests that do not include the required fees or forms will be dismissed unless accompanied by a petition to defer payment due to financial hardship, supported by documentation of the financial hardship.

(d) Petitions for reduction of a fee must be accompanied by the full fee payment less the amount of the requested reduction and FCC Form 159. Petitions for reduction accompanied by a fee payment must be addressed to the Federal Communications Commission, Attention: Petitions, Post Office Box 358835, Pittsburgh, Pennsylvania, 15251-5835.

[60 FR 34034, June 29, 1995]

§1.1167 Error claims related to regulatory fees.

(a) Challenges to determinations of an insufficient regulatory fee payment should be made in writing. Challenges submitted with a fee payment must be submitted to the same location as the original fee payment, marked "Attention: Fee Supervisor". Challenges not accompanied by a fee payment should be filed with the Commission's Secretary and clearly marked to the attention of the Managing Director.

(b) The filing of a petition for reconsideration or an application for review of a fee determination will not relieve

§ 1.1181

47 CFR Ch. I (10–1–97 Edition)

licensees from the requirement that full and proper payment of the underlying fee payment be submitted, as required by the Commission's action, or delegated action, on a request for waiver, reduction or deferment. Petitions for reconsideration and applications for review submitted with a fee payment must be submitted to the same location as the original fee payment. Petitions for reconsideration and applications for review not accompanied by a fee payment should be filed with the Commission's Secretary and clearly marked to the attention of the Managing Director.

(1) Failure to submit the fee by the date required will result in the assessment of a 25 percent penalty.

(2) If the fee payment should fail while the Commission is considering the matter, the petition for reconsideration or application for review will be dismissed.

[60 FR 34035, June 29, 1995]

Product or service	Fee amount	Payment procedure
On-line remote access 900 Number Telephone Service)	2.30 per minute	Charges included on customer's long distance telephone bill.
Remote Bidding Software	\$175.00 per package	Payment to auction contractor by credit card or check. (Public Notice will specify exact payment procedures.)
Bidder Information Package	First package free; \$16.00 per additional package (including postage) to same person or entity.	Payment to auction contractor by credit card or check. (Public Notice will specify exact payment procedures.)

§ 1.1181 Authority to prescribe and collect fees for competitive bidding-related services and products.

Authority to prescribe, impose, and collect fees for expenses incurred by the government is governed by the Independent Offices Appropriation Act of 1952, as amended, 31 U.S.C. 9701, which authorizes agencies to prescribe regulations that establish charges for the provision of government services and products. Under this authority, the Federal Communications Commission may prescribe and collect fees for competitive bidding-related services and products as specified in § 1.1182.

[60 FR 38280, July 26, 1995]

§ 1.1182 Schedule of fees for products and services provided by the Commission in connection with competitive bidding procedures.

[60 FR 38280, July 26, 1995]

Subpart H—Ex Parte Communications

SOURCE: 52 FR 21052, June 4, 1987, unless otherwise noted.

GENERAL

§ 1.1200 Introduction.

(a) *Purpose.* To ensure the fairness and integrity of its decision-making, the Commission has prescribed rules to regulate *ex parte* presentations in Commission proceedings. These rules specify “exempt” proceedings, in which *ex parte* presentations may be made freely (§ 1.1204(b)), “permit-but-disclose” proceedings, in which *ex parte* presentations to Commission decision-making personnel are permissible but sub-

ject to certain disclosure requirements (§ 1.1206), and “restricted” proceedings in which *ex parte* presentations to and from Commission decision-making personnel are generally prohibited (§ 1.1208). In all proceedings, a certain period (“the Sunshine Agenda period”) is designated in which all presentations to Commission decision-making personnel are prohibited (§ 1.1203). The limitations on *ex parte* presentations described in this section are subject to certain general exceptions set forth in § 1.1204(a). Where the public interest so requires in a particular proceeding, the Commission and its staff retain the discretion to modify the applicable *ex parte* rules by order, letter, or public notice. Joint Boards may modify the *ex parte* rules in proceedings before them.

Federal Communications Commission

§ 1.1202

(b) Inquiries concerning the propriety of *ex parte* presentations should be directed to the Office of General Counsel.

[62 FR 15853, Apr. 3, 1997]

§ 1.1202 Definitions.

For the purposes of this subpart, the following definitions apply:

(a) *Presentation*. A communication directed to the merits or outcome of a proceeding, including any attachments to a written communication or documents shown in connection with an oral presentation directed to the merits or outcome of a proceeding. Excluded from this term are communications which are inadvertently or casually made, inquiries concerning compliance with procedural requirements if the procedural matter is not an area of controversy in the proceeding, statements made by decisionmakers that are limited to providing publicly available information about pending proceedings, and inquiries relating solely to the status of a proceeding, including inquiries as to the approximate time that action in a proceeding may be taken. However, a status inquiry which states or implies a view as to the merits or outcome of the proceeding or a preference for a particular party, which states why timing is important to a particular party or indicates a view as to the date by which a proceeding should be resolved, or which otherwise is intended to address the merits or outcome or to influence the timing of a proceeding is a presentation.

NOTE TO PARAGRAPH (A): A communication expressing concern about administrative delay or expressing concern that a proceeding be resolved expeditiously will be treated as a permissible status inquiry so long as no reason is given as to why the proceeding should be expedited other than the need to resolve administrative delay, no view is expressed as to the merits or outcome of the proceeding, and no view is expressed as to a date by which the proceeding should be resolved. A presentation by a party in a restricted proceeding requesting action by a particular date or giving reasons that a proceeding should be expedited other than the need to avoid administrative delay (and responsive presentations by other parties) may be made on an *ex parte* basis subject to the provisions of § 1.1204(a)(11).

(b) *Ex parte presentation*. Any presentation which:

(1) If written, is not served on the parties to the proceeding; or

(2) If oral, is made without advance notice to the parties and without opportunity for them to be present.

NOTE TO PARAGRAPH (B): Written communications include electronic submissions transmitted in the form of texts, such as by Internet electronic mail.

(c) *Decision-making personnel*. Any member, officer, or employee of the Commission, or, in the case of a Joint Board, its members or their staffs, who is or may reasonably be expected to be involved in formulating a decision, rule, or order in a proceeding. Any person who has been made a party to a proceeding or who otherwise has been excluded from the decisional process shall not be treated as a decision-maker with respect to that proceeding. Thus, any person designated as part of a separate trial staff shall not be considered a decision-making person in the designated proceeding. Unseparated Bureau or Office staff shall be considered decision-making personnel with respect to decisions, rules, and orders in which their Bureau or Office participates in enacting, preparing, or reviewing.

(d) *Party*. Unless otherwise ordered by the Commission, the following persons are parties:

(1) Any person who files an application, waiver request, petition, motion, request for a declaratory ruling, or other filing seeking affirmative relief (including a Freedom of Information Act request), and any person (other than an individual viewer or listener filing comments regarding a pending broadcast application) filing a written submission referencing and regarding such pending filing which is served on the filer, or, in the case of an application, any person filing a mutually exclusive application;

NOTE 1 TO PARAGRAPH (D): Persons who file mutually exclusive applications for services that the Commission has announced will be subject to competitive bidding or lotteries shall not be deemed parties with respect to each others' applications merely because their applications are mutually exclusive. Therefore, such applicants may make presentations to the Commission about their own applications provided that no one has

§ 1.1203

become a party with respect to their application by other means, e.g., by filing a petition or other opposition against the applicant or an associated waiver request, if the petition or opposition has been served on the applicant.

(2) Any person who files a complaint which shows that the complainant has served it on the subject of the complaint or which is a formal complaint under 47 U.S.C. 208 and § 1.721, and the person who is the subject of such a complaint that shows service or is a formal complaint under 47 U.S.C. 208 and § 1.721;

(3) Any person who files a petition to revoke a license or other authorization or who files a petition for an order to show cause and the licensee or other entity that is the subject of the petition;

(4) The subject of an order to show cause, hearing designation order, notice of apparent liability, or similar notice or order, or petition for such notice or order;

(5) Any other person who has otherwise been given formal party status in a proceeding; and

(6) In an informal rulemaking proceeding conducted under section 553 of the Administrative Procedure Act (other than a proceeding for the allotment of a broadcast channel) or a proceeding before a Joint Board or before the Commission to consider the recommendation of a Joint Board, members of the general public after the issuance of a notice of proposed rulemaking or other order as provided under § 1.1206(a) (1) or (2).

NOTE 2 TO PARAGRAPH (D): To be deemed a party, a person must make the relevant filing with the Secretary, the relevant Bureau or Office, or the Commission as a whole. Written submissions made only to the Chairman or individual Commissioners will not confer party status.

NOTE 3 TO PARAGRAPH (D): The fact that a person is deemed a party for purposes of this subpart does not constitute a determination that such person has satisfied any other legal or procedural requirements, such as the operative requirements for petitions to deny or requirements as to timeliness. Nor does it constitute a determination that such person has any other procedural rights, such as the right to intervene in hearing proceedings. The Commission or the staff may also determine in particular instances that persons who qualify as "parties" under § 1.1202(d)

47 CFR Ch. I (10–1–97 Edition)

should nevertheless not be deemed parties for purposes of this subpart.

NOTE 4 TO PARAGRAPH (D): Individual listeners or viewers submitting comments regarding a pending broadcast application pursuant to § 1.1204(a)(8) will not become parties simply by service of the comments. The Mass Media Bureau may, in its discretion, make such a commenter a party, if doing so would be conducive to the Commission's consideration of the application or would otherwise be appropriate.

(e) *Matter designated for hearing.* Any matter that has been designated for hearing before an administrative law judge or which is otherwise designated for hearing in accordance with procedures in 5 U.S.C. 554.

[62 FR 15854, Apr. 3, 1997]

SUNSHINE PERIOD PROHIBITION

§ 1.1203 Sunshine period prohibition.

(a) With respect to any Commission proceeding, all presentations to decision-makers concerning matters listed on a Sunshine Agenda, whether *ex parte* or not, are prohibited during the period specified by paragraph (b) of this section:

(1) The presentation is exempt under § 1.1204(a);

(2) The presentation relates to settlement negotiations and otherwise complies with any *ex parte* restrictions in this subpart;

(3) The presentation occurs in the course of a widely attended speech or panel discussion and concerns a Commission action in an exempt or a permit-but-disclose proceeding that has been adopted (not including private presentations made on the site of a widely attended speech or panel discussion); or

(4) The presentation is made by a member of Congress or his or her staff, or by other agencies or branches of the federal government or their staffs in a proceeding exempt under § 1.1204 or subject to permit-but-disclose requirements under § 1.1206. If the presentation is of substantial significance and clearly intended to affect the ultimate decision, the presentation (or, if oral, a summary of the presentation) must be placed in the record of the proceeding by Commission staff or by the presenter in accordance with the procedures set forth in § 1.1206(b).

Federal Communications Commission

§ 1.1204

(b) The prohibition set forth in paragraph (a) of this section applies from the release of a public notice that a matter has been placed on the Sunshine Agenda until the Commission:

(1) Releases the text of a decision or order relating to the matter;

(2) Issues a public notice stating that the matter has been deleted from the Sunshine Agenda; or

(3) Issues a public notice stating that the matter has been returned to the staff for further consideration, whichever occurs first.

[62 FR 15855, Apr. 3, 1997]

GENERAL EXEMPTIONS

§ 1.1204 Exempt ex parte presentations and proceedings.

(a) *Exempt ex parte presentations.* The following types of presentations are exempt from the prohibitions in restricted proceedings (§ 1.1208), the disclosure requirements in permit-but-disclose proceedings (§ 1.1206), and the prohibitions during the Sunshine Agenda and circulation period prohibition (§ 1.1203):

(1) The presentation is authorized by statute or by the Commission's rules to be made without service, see, e.g., § 1.333(d), or involves the filing of required forms;

(2) The presentation is made by or to the General Counsel and his or her staff and concerns judicial review of a matter that has been decided by the Commission;

(3) The presentation directly relates to an emergency in which the safety of life is endangered or substantial loss of property is threatened, provided that, if not otherwise submitted for the record, Commission staff promptly places the presentation or a summary of the presentation in the record and discloses it to other parties as appropriate.

(4) The presentation involves a military or foreign affairs function of the United States or classified security information;

(5) The presentation is to or from an agency or branch of the Federal Government or its staff and involves a matter over which that agency or branch and the Commission share jurisdiction provided that, any new fac-

tual information obtained through such a presentation that is relied on by the Commission in its decision-making process will, if not otherwise submitted for the record, be disclosed by the Commission no later than at the time of the release of the Commission's decision;

(6) The presentation is to or from the United States Department of Justice or Federal Trade Commission and involves a telecommunications competition matter in a proceeding which has not been designated for hearing and in which the relevant agency is not a party provided that, any new factual information obtained through such a presentation that is relied on by the Commission in its decision-making process will be disclosed by the Commission no later than at the time of the release of the Commission's decision;

NOTE 1 TO PARAGRAPH (A): Under paragraphs (a)(5) and (a)(6) of this section, information will be relied on and disclosure will be made only after advance coordination with the agency involved in order to ensure that the agency involved retains control over the timing and extent of any disclosure that may have an impact on that agency's jurisdictional responsibilities. If the agency involved does not wish such information to be disclosed, the Commission will not disclose it and will disregard it in its decision-making process, unless it fits within another exemption not requiring disclosure (e.g., foreign affairs). The fact that an agency's views are disclosed under paragraphs (a)(5) and (a)(6) does not preclude further discussions pursuant to, and in accordance with, the exemption.

(7) The presentation is between Commission staff and an advisory coordinating committee member with respect to the coordination of frequency assignments to stations in the private land mobile services or fixed services as authorized by 47 U.S.C. 332;

(8) The presentation is a written presentation made by a listener or viewer of a broadcast station who is not a party under § 1.1202(d)(1), and the presentation relates to a pending application that has not been designated for hearing for a new or modified broadcast station or license, for renewal of a broadcast station license or for assignment or transfer of control of a broadcast permit or license;

§ 1.1204

47 CFR Ch. I (10–1–97 Edition)

(9) Confidentiality is necessary to protect persons making *ex parte* presentations from possible reprisals; or

(10) The presentation is requested by (or made with the advance approval of) the Commission or staff for the clarification or adduction of evidence, or for resolution of issues, including possible settlement, subject to the following limitations:

(i) This exemption does not apply to restricted proceedings designated for hearing;

(ii) In restricted proceedings not designated for hearing, any new written information elicited from such request or a summary of any new oral information elicited from such request shall promptly be served by the person making the presentation on the other parties to the proceeding. Information relating to how a proceeding should or could be settled, as opposed to new information regarding the merits, shall not be deemed to be new information for purposes of this section. The Commission or its staff may waive the service requirement if service would be too burdensome because the parties are numerous or because the materials relating to such presentation are voluminous. If the service requirement is waived, copies of the presentation or summary shall be placed in the record of the proceeding and the Commission or its staff shall issue a public notice which states that copies of the presentation or summary are available for inspection. The Commission or its staff may determine that service or public notice would interfere with the effective conduct of an investigation and dispense with the service and public notice requirements;

(iii) If the presentation is made in a proceeding subject to permit-but-disclose requirements, disclosure must be made in accordance with the requirements of § 1.1206(b), provided, however, that the Commission or its staff may determine that disclosure would interfere with the effective conduct of an investigation and dispense with the disclosure requirement. As in paragraph (a)(10)(ii) of this section, information relating to how a proceeding should or could be settled, as opposed to new information regarding the merits, shall

not be deemed to be new information for purposes of this section;

NOTE 2 TO PARAGRAPH (A): If the Commission or its staff dispenses with the service or notice requirement to avoid interference with an investigation, a determination will be made in the discretion of the Commission or its staff as to when and how disclosure should be made if necessary. See *Amendment of Subpart H, Part I*, 2 FCC Rcd 6053, 6054 ¶¶ 10–14 (1987).

(iv) If the presentation is made in a proceeding subject to the Sunshine period prohibition, disclosure must be made in accordance with the requirements of § 1.1206(b) or by other adequate means of notice that the Commission deems appropriate;

(v) In situations where new information regarding the merits is disclosed during settlement discussions, and the Commission or staff intends that the product of the settlement discussions will be disclosed to the other parties or the public for comment before any action is taken, the Commission or staff in its discretion may defer disclosure of such new information until comment is sought on the settlement proposal or the settlement discussions are terminated.

(11) The presentation is an oral presentation in a restricted proceeding requesting action by a particular date or giving reasons that a proceeding should be expedited other than the need to avoid administrative delay. A summary of the presentation shall promptly be filed in the record and served by the person making the presentation on the other parties to the proceeding, who may respond in support or opposition to the request for expedition, including by oral *ex parte* presentation, subject to the same service requirement.

(b) *Exempt proceedings.* Unless otherwise provided by the Commission or the staff pursuant to § 1.1200(a), *ex parte* presentations to or from Commission decision-making personnel are permissible and need not be disclosed with respect to the following proceedings, which are referred to as “exempt” proceedings:

(1) A notice of inquiry proceeding;

(2) A petition for rulemaking, except for a petition requesting the allotment of a broadcast channel (see also

Federal Communications Commission

§ 1.1206

§ 1.1206(a)(1)), or other request that the Commission modify its rules, issue a policy statement or issue an interpretive rule, or establish a Joint Board;

(3) A tariff proceeding (including directly associated waiver requests or requests for special permission) prior to it being set for investigation (see also § 1.1206(a)(4));

(4) A proceeding relating to prescription of common carrier depreciation rates under section 220(b) of the Communications Act prior to release of a public notice of specific proposed depreciation rates (see also § 1.1206(a)(9));

(5) An informal complaint proceeding under 47 U.S.C. 208 and § 1.717; and

(6) A complaint against a cable operator regarding its rates that is not filed on the standard complaint form required by § 76.951 of this chapter (FCC Form 329).

[62 FR 15855, Apr. 3, 1997]

NON-RESTRICTED PROCEEDINGS

§ 1.1206 Permit-but-disclose proceedings.

(a) Unless otherwise provided by the Commission or the staff pursuant to § 1.1200(a), until the proceeding is no longer subject to administrative reconsideration or review or to judicial review, *ex parte* presentations (other than *ex parte* presentations exempt under § 1.1204(a)) to or from Commission decision-making personnel are permissible in the following proceedings, which are referred to as permit-but-disclose proceedings, provided that *ex parte* presentations to Commission decision-making personnel are disclosed pursuant to paragraph (b) of this section:

(1) An informal rulemaking proceeding conducted under section 553 of the Administrative Procedure Act other than a proceeding for the allotment of a broadcast channel, upon release of a Notice of Proposed Rulemaking (see also § 1.1204(b)(2));

(2) A proceeding involving a rule change, policy statement or interpretive rule adopted without a Notice of Proposed Rule Making upon release of the order adopting the rule change, policy statement or interpretive rule;

(3) A declaratory ruling proceeding;

(4) A tariff proceeding which has been set for investigation under section 204

or 205 of the Communications Act (including directly associated waiver requests or requests for special permission) (see also § 1.1204(b)(4));

(5) Unless designated for hearing, a proceeding under section 214(a) of the Communications Act that does not also involve applications under Title III of the Communications Act (see also § 1.1208);

(6) Unless designated for hearing, a proceeding involving an application for a Cable Landing Act license that does not also involve applications under Title III of the Communications Act (see also § 1.1208);

(7) A proceeding involving a request for information filed pursuant to the Freedom of Information Act;

NOTE 1 TO PARAGRAPH (A): Where the requested information is the subject of a request for confidentiality, the person filing the request for confidentiality shall be deemed a party.

(8) A proceeding before a Joint Board or a proceeding before the Commission involving a recommendation from a Joint Board;

(9) A proceeding conducted pursuant to section 220(b) of the Communications Act for prescription of common carrier depreciation rates upon release of a public notice of specific proposed depreciation rates (see also § 1.1204(b)(4));

(10) A proceeding to prescribe a rate of return for common carriers under section 205 of the Communications Act; and

(11) A cable rate complaint proceeding pursuant to section 623(c) of the Communications Act where the complaint is filed on FCC Form 329.

NOTE 2 TO PARAGRAPH (A): In a permit-but-disclose proceeding involving only one "party," as defined in § 1.1202(d) of this subpart, the party and the Commission may freely make presentations to each other and need not comply with the disclosure requirements of paragraph (b) of this section.

(b) The following disclosure requirements apply to *ex parte* presentations in permit but disclose proceedings:

(1) *Written presentations.* A person who makes a written *ex parte* presentation subject to this section shall, no later than the next business day after the presentation, submit two copies of the presentation to the Commission's

secretary under separate cover for inclusion in the public record. The presentation (and cover letter) shall clearly identify the proceeding to which it relates, including the docket number, if any, shall indicate that two copies have been submitted to the Secretary, and must be labeled as an *ex parte* presentation. If the presentation relates to more than one proceeding, two copies shall be filed for each proceeding.

(2) *Oral presentations.* A person who makes an oral *ex parte* presentation subject to this section that presents data or arguments not already reflected in that person's written comments, memoranda or other filings in that proceeding shall, no later than the next business day after the presentation, submit to the Commission's Secretary, with copies to the Commissioners or Commission employees involved in the oral presentation, an original and one copy of a memorandum which summarizes the new data or arguments. Memoranda must contain a summary of the substance of the *ex parte* presentation and not merely a listing of the subjects discussed. More than a one or two sentence description of the views and arguments presented is generally required. The memorandum (and cover letter) shall clearly identify the proceeding to which it relates, including the docket number, if any, shall indicate that an original and one copy have been submitted to the Secretary, and must be labeled as an *ex parte* presentation. If the presentation relates to more than one proceeding, two copies of the memorandum (or an original and one copy) shall be filed for each proceeding.

NOTE 1 TO PARAGRAPH (B): Where, for example, presentations occur in the form of discussion at a widely attended meeting, preparation of a memorandum as specified in the rule might be cumbersome. Under these circumstances, the rule may be satisfied by submitting a transcript or tape recording of the discussion as an alternative to a memorandum.

(3) Notwithstanding paragraphs (b)(1) and (b)(2) of this section, in permit-but-disclose proceedings presentations made by members of Congress or their staffs or by an agency or branch of the Federal Government or its staff shall be treated as *ex parte* presentations only if the presentations are of sub-

stantial significance and clearly intended to affect the ultimate decision. The Commission staff shall prepare a written summary of any such oral presentations and place them in the record in accordance with paragraph (b)(2) of this section and place any such written presentations in the record in accordance with paragraph (b)(1) of this section.

(4) *Notice of ex parte presentations.* The Commission's Secretary or, in the case of non-docketed proceedings, the relevant Bureau or Office shall place in the public file or record of the proceeding written *ex parte* presentations and memoranda reflecting oral *ex parte* presentations. The Secretary shall issue a public notice listing any written *ex parte* presentations or written summaries of oral *ex parte* presentations received by his or her office relating to any permit-but-disclose proceeding. Such public notices should generally be released at least twice per week.

NOTE 2 TO PARAGRAPH (B): Interested persons should be aware that some *ex parte* filings, for example, those not filed in accordance with the requirements of this paragraph (b), might not be placed on the referenced public notice. All *ex parte* presentations and memoranda filed under this section will be available for public inspection in the public file or record of the proceeding, and parties wishing to ensure awareness of all filings should review the public file or record.

NOTE 3 TO PARAGRAPH (B): As a matter of convenience, the Secretary may also list on the referenced public notices materials, even if not *ex parte* presentations, that are filed after the close of the reply comment period or, if the matter is on reconsideration, the reconsideration reply comment period.

[62 FR 15856, Apr. 3, 1997]

RESTRICTED PROCEEDINGS

§ 1.1208 Restricted proceedings.

Unless otherwise provided by the Commission or its staff pursuant to § 1.1200(a), *ex parte* presentations (other than *ex parte* presentations exempt under § 1.1204 (a)) are prohibited in all proceedings not listed as exempt in § 1.1204(b) or permit-but-disclose in § 1.1206(a) until the proceeding is no longer subject to administrative reconsideration or review or judicial review.

Federal Communications Commission

§1.1212

Proceedings in which *ex parte* presentations are prohibited, referred to as “restricted” proceedings, include, but are not limited to, all proceedings that have been designated for hearing, proceedings involving amendments to the broadcast table of allotments, applications for authority under Title III of the Communications Act, and all waiver proceedings (except for those directly associated with tariff filings).

NOTE 1 TO §1.1208: In a restricted proceeding involving only one “party,” as defined in §1.1202(d), the party and the Commission may freely make presentations to each other because there is no other party to be served or with a right to have an opportunity to be present. See §1.1202(b). Therefore, to determine whether presentations are permissible in a restricted proceeding without service or notice and an opportunity for other parties to be present the definition of a “party” should be consulted.

Examples: After the filing of an uncontested application or waiver request, the applicant or other filer would be the sole party to the proceeding. The filer would have no other party to serve with or give notice of any presentations to the Commission, and such presentations would therefore not be “*ex parte* presentations” as defined by §1.1202(b) and would not be prohibited. On the other hand, in the example given, because the filer is a party, a third person who wished to make a presentation to the Commission concerning the application or waiver request would have to serve or notice the filer. Further, once the proceeding involved additional “parties” as defined by §1.1202(d) (e.g., an opponent of the filer who served the opposition on the filer), the filer and other parties would have to serve or notice all other parties.

NOTE 2 TO §1.1208: Consistent with §1.1200(a), the Commission or its staff may determine that a restricted proceeding not designated for hearing involves primarily issues of broadly applicable policy rather than the rights and responsibilities of specific parties and specify that the proceeding will be conducted in accordance with the provisions of §1.1206 governing permit-but-disclose proceedings.

[62 FR 15857, Apr. 3, 1997]

PROHIBITION ON SOLICITATION OF PRESENTATIONS

§1.1210 Prohibition on solicitation of presentations.

No person shall solicit or encourage others to make any presentation which

he or she is prohibited from making under the provisions of this subpart.

[62 FR 15857, Apr. 3, 1997]

PROCEDURES FOR HANDLING OF PROHIBITED EX PARTE PRESENTATIONS

§1.1212 Procedures for handling of prohibited *ex parte* presentations.

(a) Commission personnel who believe that an oral presentation which is being made to them or is about to be made to them is prohibited shall promptly advise the person initiating the presentation that it is prohibited and shall terminate the discussion.

(b) Commission personnel who receive oral *ex parte* presentations which they believe are prohibited shall forward to the Office of General Counsel a statement containing the following information:

- (1) The name of the proceeding;
- (2) The name and address of the person making the presentation and that person’s relationship (if any) to the parties to the proceeding;
- (3) The date and time of the presentation, its duration, and the circumstances under which it was made;
- (4) A full summary of the substance of the presentation;
- (5) Whether the person making the presentation persisted in doing so after being advised that the presentation was prohibited; and
- (6) The date and time that the statement was prepared.

(c) Commission personnel who receive written *ex parte* presentations which they believe are prohibited shall forward them to the Office of General Counsel. If the circumstances in which the presentation was made are not apparent from the presentation itself, a statement describing those circumstances shall be submitted to the Office of General Counsel with the presentation.

(d) Prohibited written *ex parte* presentations and all documentation relating to prohibited written and oral *ex parte* presentations shall be placed in a public file which shall be associated with but not made part of the record of the proceeding to which the presentations pertain. Such materials may be considered in determining the merits of a restricted proceeding only if they

§ 1.1214

are made part of the record and the parties are so informed.

(e) If the General Counsel determines that an *ex parte* presentation or presentation during the Sunshine period is prohibited by this subpart, he or she shall notify the parties to the proceeding that a prohibited presentation has occurred and shall serve on the parties copies of the presentation (if written) and any statements describing the circumstances of the presentation. Service by the General Counsel shall not be deemed to cure any violation of the rules against prohibited *ex parte* presentations.

(f) If the General Counsel determines that service on the parties would be unduly burdensome because the parties to the proceeding are numerous, he or she may issue a public notice in lieu of service. The public notice shall state that a prohibited presentation has been made and may also state that the presentation and related materials are available for public inspection.

(g) The General Counsel shall forward a copy of any statement describing the circumstances in which the prohibited *ex parte* presentation was made to the person who made the presentation. Within ten days thereafter, the person who made the presentation may file with the General Counsel a sworn declaration regarding the presentation and the circumstances in which it was made. The General Counsel may serve copies of the sworn declaration on the parties to the proceeding.

(h) Where a restricted proceeding precipitates a substantial amount of correspondence from the general public, the procedures in paragraphs (c) through (g) of this section will not be followed with respect to such correspondence. The correspondence will be placed in a public file and be made available for public inspection.

[62 FR 15857, Apr. 3, 1997]

§ 1.1214 Disclosure of information concerning violations of this subpart.

Any party to a proceeding or any Commission employee who has substantial reason to believe that any violation of this subpart has been solicited, attempted, or committed shall promptly advise the Office of General Counsel in writing of all the facts and

47 CFR Ch. I (10–1–97 Edition)

circumstances which are known to him or her.

[62 FR 15858, Apr. 3, 1997]

SANCTIONS

§ 1.1216 Sanctions.

(a) *Parties.* Upon notice and hearing, any party to a proceeding who directly or indirectly violates or causes the violation of any provision of this subpart, or who fails to report the facts and circumstances concerning any such violation as required by this subpart, may be disqualified from further participation in that proceeding. In proceedings other than a rulemaking, a party who has violated or caused the violation of any provision of this subpart may be required to show cause why his or her claim or interest in the proceeding should not be dismissed, denied, disregarded, or otherwise adversely affected. In any proceeding, such alternative or additional sanctions as may be appropriate may also be imposed.

(b) *Commission personnel.* Commission personnel who violate provisions of this subpart may be subject to appropriate disciplinary or other remedial action as provided in part 19 of this chapter.

(c) *Other persons.* Such sanctions as may be appropriate under the circumstances shall be imposed upon other persons who violate the provisions of this subpart.

[62 FR 15858, Apr. 3, 1997]

Subpart I—Procedures Implementing the National Environmental Policy Act of 1969

SOURCE: 51 FR 15000, Apr. 22, 1986, unless otherwise noted.

§ 1.1301 Basis and purpose.

The provisions of this subpart implement Subchapter I of the National Environmental Policy Act of 1969, as amended, 42 U.S.C. 4321–4335.

§ 1.1302 Cross-reference; Regulations of the Council on Environmental Quality.

A further explanation regarding implementation of the National Environmental Policy Act is provided by the

Federal Communications Commission

§1.1306

regulations issued by the Council on Environmental Quality, 40 CFR 1500–1508.28.

§1.1303 Scope.

The provisions of this subpart shall apply to all Commission actions that may or will have a significant impact on the quality of the human environment. To the extent that other provisions of the Commission's rules and regulations are inconsistent with the subpart, the provisions of this subpart shall govern.

[55 FR 20396, May 16, 1990]

§1.1304 Information and assistance.

For general information and assistance concerning the provisions of this subpart, the Office of General Counsel may be contacted, (202) 632–6990. For more specific information, the Bureau responsible for processing a specific application should be contacted.

§1.1305 Actions which normally will have a significant impact upon the environment, for which Environmental Impact Statements must be prepared.

Any Commission action deemed to have a significant effect upon the quality of the human environment requires the preparation of a Draft Environmental Impact Statement (DEIS) and Final Environmental Impact Statement (FEIS) (collectively referred to as EISs) (see §§1.1314, 1.1315 and 1.1317). The Commission has reviewed representative actions and has found no common pattern which would enable it to specify actions that will thus automatically require EISs.

NOTE: Our current application forms refer applicants to §1.1305 to determine if their proposals are such that the submission of environmental information is required (see §1.1311). Until the application forms are revised to reflect our new environmental rules, applicants should refer to §1.1307. Section 1.1307 now delineates those actions for which applicants must submit environmental information.

§1.1306 Actions which are categorically excluded from environmental processing.

(a) Except as provided in §1.1307 (c) and (d), Commission actions not covered by §1.1307 (a) and (b) are deemed

individually and cumulatively to have no significant effect on the quality of the human environment and are categorically excluded from environmental processing.

(b) Specifically, any Commission action with respect to any new application, or minor or major modifications of existing or authorized facilities or equipment, will be categorically excluded, provided such proposals do not:

(1) Involve a site location specified under §1.1307(a) (1)–(7), or

(2) Involve high intensity lighting under §1.1307(a)(8).

(3) Result in human exposure to radiofrequency radiation in excess of the applicable safety standards specified in §1.1307(b).

NOTE 1: The provisions of §1.1307(a) of this part requiring the preparation of EAs do not encompass the mounting of antenna(s) on an existing building or antenna tower unless §1.1307(a)(4) of this part is applicable. Such antennas are subject to §1.1307(b) of this part and require EAs if their construction would result in human exposure to radiofrequency radiation in excess of the applicable health and safety guidelines cited in §1.1307(b) of this part. The provisions of §1.1307 (a) and (b) of this part do not encompass the installation of aerial wire or cable over existing aerial corridors of prior or permitted use or the underground installation of wire or cable along existing underground corridors of prior or permitted use, established by the applicant or others. The use of existing buildings, towers or corridors is an environmentally desirable alternative to the construction of new facilities and is encouraged.

NOTE 2: The specific height of an antenna tower or supporting structure, as well as the specific diameter of a satellite earth station, in and of itself, will not be deemed sufficient to warrant environmental processing, see §§1.1307 and 1.1308.

NOTE 3: The construction of an antenna tower or supporting structure in an established "antenna farm": (i.e., an area in which similar antenna towers are clustered, whether or not such area has been officially designated as an antenna farm), will be categorically excluded unless *one or more of the antennas to be mounted on the tower or structure are subject to the provisions of §1.1307(b) and the additional radiofrequency radiation from the antenna(s) on the new tower or structure would cause human exposure in excess of the applicable health and safety guidelines cited in §1.1307(b).*

[51 FR 15000, Apr. 22, 1986, as amended at 51 FR 18889, May 23, 1986; 53 FR 28393, July 28, 1988; 56 FR 13414, Apr. 2, 1991]

§1.1307 Actions that may have a significant environmental effect, for which Environmental Assessments (EAs) must be prepared.

(a) Commission actions with respect to the following types of facilities may significantly affect the environment and thus require the preparation of EAs by the applicant (see §§1.1308 and 1.1311) and may require further Commission environmental processing (see §§1.1314, 1.1315 and 1.1317):

(1) Facilities that are to be located in an officially designated wilderness area.

(2) Facilities that are to be located in an officially designated wildlife preserve.

(3) Facilities that: (i) May affect listed threatened or endangered species or designated critical habitats; or (ii) are likely to jeopardize the continued existence of any proposed endangered or threatened species or likely to result in the destruction or adverse modification of proposed critical habitats, as determined by the Secretary of the Interior pursuant to the Endangered Species Act of 1973.

NOTE: The list of endangered and threatened species is contained in 50 CFR 17.11, 17.22, 222.23(a) and 227.4. The list of designated critical habitats is contained in 50 CFR 17.95, 17.96 and part 226. To ascertain the status of proposed species and habitats, inquiries may be directed to the Regional Director of the Fish and Wildlife Service, Department of the Interior.

(4) Facilities that may affect districts, sites, buildings, structures or objects, significant in American history, architecture, archeology, engineering or culture, that are listed, or are eligible for listing, in the National Register of Historic Places. (See 16 U.S.C. 470w(5); 36 CFR 60 and 800.)

NOTE: The National Register is updated and re-published in the FEDERAL REGISTER each year in February. To ascertain whether a proposal affects a historical property of national significance, inquiries also may be made to the appropriate State Historic Preservation Officer, see 16 U.S.C. 470a(b); 36 CFR parts 63 and 800.

(5) Facilities that may affect Indian religious sites.

(6) Facilities to be located in a flood Plain (See Executive Order 11988.)

(7) Facilities whose construction will involve significant change in surface features (e.g., wetland fill, deforestation or water diversion). (In the case of wetlands on Federal property, see Executive Order 11990.)

(8) Antenna towers and/or supporting structures that are to be equipped with high intensity white lights which are to be located in residential neighborhoods, as defined by the applicable zoning law.

(b) In addition to the actions listed in paragraph (a) of this section, Commission actions granting construction permits, licenses to transmit or renewals thereof, equipment authorizations or modifications in existing facilities, require the preparation of an Environmental Assessment (EA) if the particular facility, operation or transmitter would cause human exposure to levels of radiofrequency radiation in excess of the limits in §§1.1310 and 2.1093 of this chapter. Applications to the Commission for construction permits, licenses to transmit or renewals thereof, equipment authorizations or modifications in existing facilities must contain a statement confirming compliance with the limits unless the facility, operation, or transmitter is categorically excluded, as discussed below. Technical information showing the basis for this statement must be submitted to the Commission upon request.

(1) The appropriate exposure limits in §§1.1310 and 2.1093 of this chapter are generally applicable to all facilities, operations and transmitters regulated by the Commission. However, a determination of compliance with the exposure limits in §1.1310 or §2.1093 of this chapter (routine environmental evaluation), and preparation of an EA if the limits are exceeded, is necessary only for facilities, operations and transmitters that fall into the categories listed in table 1, or those specified in paragraph (b)(2) of this section. All other facilities, operations and transmitters are categorically excluded from making such studies or preparing an EA, except as indicated in paragraphs (c) and (d) of this section. For purposes of table 1, *building-mounted antennas* means antennas mounted in or on a building structure that is occupied as a workplace or residence. The term *power*

Federal Communications Commission

§1.1307

in column 2 of table 1 refers to total operating power of the transmitting operation in question in terms of effective radiated power (ERP), equivalent isotropically radiated power (EIRP), or peak envelope power (PEP), as defined in §2.1 of this chapter. For the case of the Cellular Radiotelephone Service, subpart H of part 22 of this chapter; the Personal Communications Service, part 24 of this chapter and the Specialized Mobile Radio Service, part 90 of this chapter, the phrase *total power of all channels* in column 2 of table 1

means the sum of the ERP or EIRP of all co-located simultaneously operating transmitters owned and operated by a single licensee. When applying the criteria of table 1, radiation in all directions should be considered. For the case of transmitting facilities using sectorized transmitting antennas, applicants and licensees should apply the criteria to all transmitting channels in a given sector, noting that for a highly directional antenna there is relatively little contribution to ERP or EIRP summation for other directions.

TABLE 1—TRANSMITTERS, FACILITIES AND OPERATIONS SUBJECT TO ROUTINE ENVIRONMENTAL EVALUATION

Service (title 47 CFR rule part)	Evaluation required if
Experimental Radio Services (part 5)	Power > 100 W ERP (164 W EIRP)
Multipoint Distribution Service (subpart K of part 21).	<i>Non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> power > 1640 W EIRP <i>Building-mounted antennas:</i> power > 1640 W EIRP
Paging and Radiotelephone Service (subpart E of part 22).	<i>Non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> power > 1000 W ERP (1640 W EIRP) <i>Building-mounted antennas:</i> power > 1000 W ERP (1640 W EIRP)
Cellular Radiotelephone Service (subpart H of part 22).	<i>Non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> total power of all channels > 1000 W ERP (1640 W EIRP) <i>Building-mounted antennas:</i> total power of all channels > 1000 W ERP (1640 W EIRP)
Personal Communications Services (part 24) ...	(1) Narrowband PCS (subpart D): <i>non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> total power of all channels > 1000 W ERP (1640 W EIRP) <i>Building-mounted antennas:</i> total power of all channels > 1000 W ERP (1640 W EIRP) (2) Broadband PCS (subpart E): <i>non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> total power of all channels > 2000 W ERP (3280 W EIRP) <i>Building-mounted antennas:</i> total power of all channels > 2000 W ERP (3280 W EIRP)
Satellite Communications (part 25)	All included.
General Wireless Communications Service (part 26).	Total power of all channels > 1640 W EIRP
Wireless Communications Service (part 27)	Total power of all channels > 1640 W EIRP
Radio Broadcast Services (part 73)	All included
Experimental, auxiliary, and special broadcast and other program distributional services (part 74).	Subparts A, G, L: power > 100 W ERP Subpart I: <i>non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> power > 1640 W EIRP <i>Building-mounted antennas:</i> power > 1640 W EIRP
Stations in the Maritime Services (part 80)	Ship earth stations only
Private Land Mobile Radio Services Paging Operations (part 90).	<i>Non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> power > 1000 W ERP (1640 W EIRP) <i>Building-mounted antennas:</i> power > 1000 W ERP (1640 W EIRP)
Private Land Mobile Radio Services Specialized Mobile Radio (part 90).	<i>Non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m <i>and</i> total power of all channels > 1000 W ERP (1640 W EIRP) <i>Building-mounted antennas:</i> Total power of all channels > 1000 W ERP (1640 W EIRP)
Amateur Radio Service (part 97)	Transmitter output power > levels specified in §97.13(c)(1) of this chapter

TABLE 1—TRANSMITTERS, FACILITIES AND OPERATIONS SUBJECT TO ROUTINE ENVIRONMENTAL EVALUATION—Continued

Service (title 47 CFR rule part)	Evaluation required if
Local Multipoint Distribution Service (subpart L of part 101).	<i>Non-building-mounted antennas:</i> height above ground level to lowest point of antenna < 10 m and power > 1640 W EIRP <i>Building-mounted antennas:</i> power > 1640 W EIRP LMDs licensees are required to attach a label to subscriber transceiver antennas that: (1) provides adequate notice regarding potential radiofrequency safety hazards, e.g., information regarding the safe minimum separation distance required between users and transceiver antennas; and (2) references the applicable FCC-adopted limits for radiofrequency exposure specified in § 1.1310 of this chapter

(2) Mobile and portable transmitting devices that operate in the Cellular Radiotelephone Service, the Personal Communications Services (PCS), the Satellite Communications Services, the General Wireless Communications Service, the Wireless Communications Service, the Maritime Services (ship earth stations only) and the Specialized Mobile Radio Service authorized under subpart H of parts 22, 24, 25, 26, 27, 80, and 90 of this chapter are subject to routine environmental evaluation for RF exposure prior to equipment authorization or use, as specified in §§2.1091 and 2.1093 of this chapter. Unlicensed PCS, unlicensed NII and millimeter wave devices are also subject to routine environmental evaluation for RF exposure prior to equipment authorization or use, as specified in §§15.253(f), 15.255(g), and 15.319(i) and 15.407(f) of this chapter. All other mobile, portable, and unlicensed transmitting devices are categorically excluded from routine environmental evaluation for RF exposure under §§2.1091 and 2.1093 of this chapter except as specified in paragraphs (c) and (d) of this section.

(3) In general, when the guidelines specified in § 1.1310 are exceeded in an accessible area due to the emissions from multiple fixed transmitters, actions necessary to bring the area into compliance are the shared responsibility of all licensees whose transmitters produce, at the area in question, power density levels that exceed 5% of the power density exposure limit applicable to their particular transmitter or field strength levels that, when squared, exceed 5% of the square of the electric or magnetic field strength limit applicable to their particular

transmitter. Owners of transmitter sites are expected to allow applicants and licensees to take reasonable steps to comply with the requirements contained in § 1.1307(b) and, where feasible, should encourage co-location of transmitters and common solutions for controlling access to areas where the RF exposure limits contained in § 1.1310 might be exceeded.

(i) Applicants for proposed (not otherwise excluded) transmitters, facilities or modifications that would cause non-compliance with the limits specified in § 1.1310 at an accessible area previously in compliance must submit an EA if emissions from the applicant's transmitter or facility would result, at the area in question, in a power density that exceeds 5% of the power density exposure limit applicable to that transmitter or facility or in a field strength that, when squared, exceeds 5% of the square of the electric or magnetic field strength limit applicable to that transmitter or facility.

(ii) Renewal applicants whose (not otherwise excluded) transmitters or facilities contribute to the field strength or power density at an accessible area not in compliance with the limits specified in § 1.1310 must submit an EA if emissions from the applicant's transmitter or facility results, at the area in question, in a power density that exceeds 5% of the power density exposure limit applicable to that transmitter or facility or in a field strength that, when squared, exceeds 5% of the square of the electric or magnetic field strength limit applicable to that transmitter or facility.

(4) *Transition Provisions.* For applications filed with the Commission prior to October 15, 1997, (or January 1, 1998,

Federal Communications Commission

§1.1307

for the Amateur Radio Service only), Commission actions granting construction permits, licenses to transmit or renewals thereof, equipment authorizations, or modifications in existing facilities require the preparation of an Environmental Assessment if the particular facility, operation or transmitter would cause human exposure to levels of radiofrequency radiation that are in excess of the requirements contained in paragraphs (b)(4)(i) through (b)(4)(iii) of this section. These transition provisions do not apply to applications for equipment authorization or use of mobile, portable and unlicensed devices specified in paragraph (b)(2) of this section.

(i) For facilities and operations licensed or authorized under parts 5, 21 (subpart K), 25, 73, 74 (subparts A, G, I, and L), and 80 of this chapter, the “Radio Frequency Protection Guides” recommended in “American National Standard Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 300 kHz to 100 GHz”, (ANSI C95.1–1982), issued by the American National Standards Institute (ANSI) and copyright 1982 by the Institute of Electrical and Electronics Engineers, Inc., New York, New York shall apply. With respect to subpart K of part 21 and subpart I of part 74 of this chapter, these requirements apply only to multipoint distribution service and instructional television fixed service stations transmitting with an equivalent isotropically radiated power (EIRP) in excess of 200 watts. With respect to subpart L of part 74 of this chapter, these requirements apply only to FM booster and translator stations transmitting with an effective radiated power (ERP) in excess of 100 watts. With respect to part 80 of this chapter, these requirements apply only to ship earth stations.

(ii) For facilities and operations licensed or authorized under part 24 of this chapter, licensees and manufacturers are required to ensure that their facilities and equipment comply with IEEE C95.1–1991 (ANSI/IEEE C95.1–1992), “Safety Levels With Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz.” Measurement methods are specified in

IEEE C95.3–1991, “Recommended Practice for the Measurement of Potentially Hazardous Electromagnetic Fields—RF and Microwave.” Copies of these standards are available from IEEE Standards Board, 445 Hoes Lane, P.O. Box 1331, Piscataway, NJ 08855–1331. Telephone: 1–800–678–4333. The limits for both “controlled” and “uncontrolled” environments, as defined by IEEE C95.1–1991, will apply to all PCS base and mobile stations, as appropriate.

(iii) Applications for all other types of facilities and operations are categorically excluded from routine RF radiation evaluation except as provided in paragraphs (c) and (d) of this section.

(5) *Existing transmitting facilities, devices and operations:* All existing transmitting facilities, operations and devices regulated by the Commission must be in compliance with the requirements of paragraphs (b)(1) through (b)(3) of this section by September 1, 2000, or, if not in compliance, file an Environmental Assessment as specified in §1.1311.

(c) If an interested person alleges that a particular action, otherwise categorically excluded, will have a significant environmental effect, the person shall submit to the Bureau responsible for processing that action a written petition setting forth in detail the reasons justifying or circumstances necessitating environmental consideration in the decision-making process. (See §1.1313). The Bureau shall review the petition and consider the environmental concerns that have been raised. If the Bureau determines that the action may have a significant environmental impact, the Bureau will require the applicant to prepare an EA (see §§1.1308 and 1.1311), which will serve as the basis for the determination to proceed with or terminate environmental processing.

(d) If the Bureau responsible for processing a particular action, otherwise categorically excluded, determines that the proposal may have a significant environmental impact, the Bureau, on its own motion, shall require the applicant to submit an EA. The Bureau will review and consider the EA as in paragraph (c) of this section.

§1.1307

47 CFR Ch. I (10–1–97 Edition)

(e) No State or local government or instrumentality thereof may regulate the placement, construction, and modification of personal wireless service facilities on the basis of the environmental effects of radio frequency emissions to the extent that such facilities comply with the regulations contained in this chapter concerning the environmental effects of such emissions. For purposes of this paragraph:

(1) The term *personal wireless service* means commercial mobile services, unlicensed wireless services, and common carrier wireless exchange access services;

(2) The term *personal wireless service facilities* means facilities for the provision of personal wireless services;

(3) The term *unlicensed wireless services* means the offering of telecommunications services using duly authorized devices which do not require individual licenses, but does not mean the provision of direct-to-home satellite services; and

(4) The term *direct-to-home satellite services* means the distribution or broadcasting of programming or services by satellite directly to the subscriber's premises without the use of ground receiving or distribution equipment, except at the subscriber's premises or in the uplink process to the satellite.

[51 FR 15000, Apr. 22, 1986, as amended at 52 FR 13241, Apr. 22, 1987; 53 FR 28224, July 27, 1988; 53 FR 28393, July 28, 1988; 54 FR 30548, July 21, 1989; 55 FR 2381, Jan. 24, 1990; 55 FR 50692, Dec. 10, 1990; 61 FR 41014, Aug. 7, 1996; 62 FR 3240, Jan. 22, 1997; 62 FR 4655, Jan. 31, 1997; 62 FR 9654, Mar. 3, 1997; 62 FR 23162, Apr. 29, 1997; 62 FR 47965, Sept. 12, 1997]

EFFECTIVE DATE NOTE: At 62 FR 47965, Sept. 12, 1997, §1.1307 was amended by revising paragraphs (b)(1), (2), (3), and (4) introductory text, and adding (b)(5), effective Oct. 15, 1997. For the convenience of the user, the superseded text is set forth as follows:

§1.1307 Actions that may have a significant environmental effect, for which Environmental Assessments (EAs) must be prepared.

* * * * *

(b) * * *

(1) The exposure limits in §1.1310 are generally applicable to all facilities, operations and transmitters regulated by the Commission. However, a determination of compliance with the exposure limits in §1.1310 (routine environmental evaluation), and preparation of an EA if the limits are exceeded, is necessary only for facilities, operations and transmitters that fall into the categories listed in Table 1, or those specified in paragraph (b)(2) of this section. All other facilities, operations and transmitters are categorically excluded from making such studies or preparing an EA, except as indicated in paragraphs (c) and (d) of this section. For purposes of Table 1, "rooftop" means the roof or otherwise outside, topmost level or levels of a building structure that is occupied as a workplace or residence and where either workers or the general public may have access. The term "power" in column 2 of Table 1 refers to total operating power of the transmitting operation in question in terms of effective radiated power (ERP), equivalent isotropically radiated power (EIRP), or peak envelope power (PEP), as defined in §2.1 of this chapter. For the case of the Cellular Radiotelephone Service, subpart H of part 22 of this chapter; the Personal Communications Service, part 24 of this chapter; the Wireless Communications Service, part 27 of this chapter; and covered Specialized Mobile Radio Service operations, part 90 of this chapter; the phrase "total power of all channels" in column 2 of Table 1 means the sum of the ERP or EIRP of all co-located simultaneously operating transmitters of the facility. When applying the criteria of Table 1, radiation in all directions should be considered. For the case of transmitting facilities using sectorized transmitting antennas, applicants and licensees should apply the criteria to all transmitting channels in a given sector, noting that for a highly directional antenna there is relatively little contribution to ERP or EIRP summation for other directions.

TABLE 1—TRANSMITTERS, FACILITIES AND OPERATIONS SUBJECT TO ROUTINE ENVIRONMENTAL EVALUATION

Service (Title 47 CFR Rule Part)	Evaluation required if:
Experimental Radio Services (part 5)	Power > 100W ERP (164W EIRP).
Radio Frequency Devices (part 15)	Millimeter wave devices operating in one of the following bands 46.7–46.8 GHz, 59.0–64.0 GHz or 76.0–77.0 GHz (see §§15.253 and 15.255 of this chapter). Unlicensed personal communications service devices operating under subpart D of this chapter.

Federal Communications Commission

§ 1.1307

TABLE 1—TRANSMITTERS, FACILITIES AND OPERATIONS SUBJECT TO ROUTINE ENVIRONMENTAL EVALUATION—Continued

Service (Title 47 CFR Rule Part)	Evaluation required if:
Multipoint Distribution Service (subpart K of part 21)	<i>Non-rooftop antennas:</i> height above ground level to radiation center < 10 m and power > 1640 W EIRP. <i>Rooftop antennas:</i> Power > 1640W EIRP.
Paging and Radiotelephone Service (subpart E of part 22).	<i>Non-rooftop antennas:</i> height above ground level to radiation center < 10 m and power > 1000W ERP (1640 W EIRP). <i>Rooftop antennas:</i> power > 1000W ERP (1640W EIRP).
Cellular Radiotelephone Service (subpart H of part 22).	<i>Non-rooftop antennas:</i> height above ground level to radiation center < 10 m and total power of all channels > 1000W ERP (1640 W EIRP). <i>Rooftop antennas:</i> total power of all channels > 1000W ERP (1640W EIRP).
Personal Communications Services (part 24)	(1) Narrowband PCS (subpart D): <i>non-rooftop antennas:</i> height above ground level to radiation center <10 m and total power of all channels > 1000W ERP (1640 W EIRP). <i>Rooftop antennas:</i> total power of all channels > 1000W (1640W EIRP). (2) Broadband PCS (subpart E): <i>non-rooftop antennas:</i> height above ground level to radiation center <10 m and total power of all channels > 2000W ERP (3280 W EIRP). <i>Rooftop antennas:</i> total power of all channels > 2000W (3280W EIRP).
Satellite Communications (part 25)	All included.
Wireless Communications Service (part 27)	Total power of all channels > 1000 W ERP (1640 W EIRP)
Radio Broadcast Services (part 73)	All included.
Experimental, auxiliary, and special broadcast and other program distributional services (part 74).	Subparts A, G, L: power > 100W ERP. Subpart I: <i>non-rooftop antennas:</i> height above ground level to radiation center < 10 m and power > 1640 W EIRP. <i>Rooftop antennas:</i> power > 1640W EIRP.
Stations in the Maritime Services (part 80)	Ship earth stations only.
Private Land Mobile Radio Services Paging Operations (part 90).	<i>Non-rooftop antennas:</i> height above ground level to radiation center < 10 m and power > 1000W ERP (1640 W EIRP). <i>Rooftop antennas:</i> power > 1000W ERP (1640W EIRP).
Private Land Mobile Radio Services Specialized Mobile Radio ("covered" providers only—see below) ¹ (part 90).	<i>Non-rooftop antennas:</i> height above ground level to radiation center < 10 m and total power of all channels > 1000W ERP (1640 W EIRP). <i>Rooftop antennas:</i> total power of all channels > 1000W ERP (1640W EIRP).
Amateur Radio Service (part 97)	Transmitter power > 50W PEP.
Local Multipoint Distribution Service (subpart L of part 101).	<i>Non-rooftop antennas:</i> Height above ground level to radiation center <10 m and power >1640 W EIRP. <i>Rooftop antennas:</i> Power > 1640 W EIRP. LMDS licensees are required to attach a label to subscriber transceiver antennas that (1) provides adequate notice regarding potential radio frequency safety hazards, e.g., information regarding the safe minimum separation distance required between users and transceiver antennas; and (2) references the applicable FCC radio frequency emission guidelines contained in FCC OST Bulletin 65, 2d Edition.

¹ NOTE: "Covered" SMR providers includes geographic area SMR licensees in the 800 MHz and 900 MHz bands that offer real-time, two-way switched voice service that is interconnected with the public switched network and Incumbent Wide Area SMR licensees, as defined in § 20.3 of this chapter.

(2) Mobile and portable transmitting devices that operate in the Cellular Radiotelephone Service, the Personal Communications Services, the Satellite Communications Services, the Wireless Communications Service, the Maritime Services (ship earth stations only), and covered Specialized Mobile Radio Service providers authorized under subpart H of part 22, part 24, part 25, part 27, part 80, and part 90 of this chapter are subject to routine environmental evaluation for RF exposure prior to equipment authorization or use, as specified in §§ 2.1091 and 2.1093 of this chapter. All unlicensed PCS, unlicensed NII and millimeter wave devices are also subject to routine environmental evaluation for RF exposure prior to equipment authorization or use, as specified

in §§ 15.253(f), 15.255(g), 15.319(i), and 15.407(f) of this chapter. All other mobile, portable, and unlicensed transmitting devices are categorically excluded from routine environmental evaluation for RF exposure under §§ 2.1091 and 2.1093 of this chapter except as specified in paragraphs (c) and (d) of this section.

(3) In general, when the guidelines specified in § 1.1310 are exceeded in an accessible area due to the emissions from multiple fixed transmitters, actions necessary to bring the area into compliance with the guidelines are the shared responsibility of all licensees whose transmitters produce field strengths or power density levels at the area in question in excess of 1% of the exposure

§ 1.1308

47 CFR Ch. I (10–1–97 Edition)

limits applicable to their particular transmitter.

(i) Applicants for proposed (not otherwise excluded) transmitters, facilities or modifications that would cause non-compliance with the limits specified in § 1.1310 at an accessible area previously in compliance must submit an EA if emissions from the applicant's transmitter or facility would result in a field strength or power density at the area in question that exceeds 1% of the exposure limit applicable to that transmitter or facility.

(ii) Renewal applicants whose (not otherwise excluded) transmitters or facilities contribute to the field strength or power density at an accessible area not in compliance with the limits specified in § 1.1310 must submit an EA if emissions from the applicant's transmitter or facility results in a field strength or power density at the area in question that exceeds 1% of the exposure limit applicable to that transmitter or facility.

(4) *Transition Provisions.* For applications filed with the Commission prior to September 1, 1997 (January 1, 1998 for the Amateur Radio Service only), Commission actions granting construction permits, licenses to transmit or renewals thereof, equipment authorizations, or modifications in existing facilities require the preparation of an Environmental Assessment if the particular facility, operation or transmitter would cause human exposure to levels of radiofrequency radiation that are in excess of the requirements contained in paragraphs (b) (4)(i) through (4)(iii) of this section. These transition provisions do not apply to applications for equipment authorization or use of mobile, portable, and unlicensed devices specified in paragraph (b)(2) of this section.

* * * * *

§ 1.1308 Consideration of environmental assessments (EAs); findings of no significant impact.

(a) Applicants shall prepare EAs for actions that may have a significant environmental impact (see § 1.1307). An EA is described in detail in § 1.1311 of this part of the Commission rules.

(b) The EA is a document which shall explain the environmental consequences of the proposal and set forth sufficient analysis for the Bureau or the Commission to reach a determination that the proposal will or will not have a significant environmental effect. To assist in making that determination, the Bureau or the Commission may request further information from the applicant, interested persons, and agencies and authorities which

have jurisdiction by law or which have relevant expertise.

NOTE: With respect to actions specified under § 1.1307 (a)(3) and (a)(4), the Commission shall solicit and consider the comments of the Department of Interior, and the State Historic Preservation Officer and the Advisory Council on Historic Preservation, respectively, in accordance with their established procedures. See Interagency Cooperation—Endangered Species Act of 1973, as amended, 50 CFR part 402; Protection of Historic and Cultural Properties, 36 CFR part 800. In addition, when an action interferes with or adversely affects an American Indian tribe's religious site, the Commission shall solicit the views of that American Indian tribe. See § 1.1307(a)(5).

(c) If the Bureau or the Commission determines, based on an independent review of the EA and any applicable mandatory consultation requirements imposed upon federal agencies (see note above), that the proposal will have a significant environmental impact upon the quality of the human environment, it will so inform the applicant. The applicant will then have an opportunity to amend its application so as to reduce, minimize, or eliminate environmental problems. See § 1.1309. If the environmental problem is not eliminated, the Bureau will publish in the FEDERAL REGISTER a Notice of Intent (see § 1.1314) that EISs will be prepared (see §§ 1.1315 and 1.1317), or

(d) If the Bureau or Commission determines, based on an independent review of the EA, and any mandatory consultation requirements imposed upon federal agencies (see the note to paragraph (b) of this section), that the proposal would not have a significant impact, it will make a finding of no significant impact. Thereafter, the application will be processed without further documentation of environmental effect. Pursuant to CEQ regulations, see 40 CFR 1501.4 and 1501.6, the applicant must provide the community notice of the Commission's finding of no significant impact.

[51 FR 15000, Apr. 22, 1986; 51 FR 18889, May 23, 1986, as amended at 53 FR 28394, July 28, 1988]

§ 1.1309 Application amendments.

Applicants are permitted to amend their applications to reduce, minimize or eliminate potential environmental

Federal Communications Commission

§ 1.1311

problems. As a routine matter, an applicant will be permitted to amend its application within thirty (30) days after the Commission or the Bureau informs the applicant that the proposal will have a significant impact upon the quality of the human environment (see § 1.1308(c)). The period of thirty (30) days may be extended upon a showing of good cause.

§ 1.1310 Radiofrequency radiation exposure limits.

The criteria listed in table 1 shall be used to evaluate the environmental impact of human exposure to radiofrequency (RF) radiation as specified in § 1.1307(b), except in the case of portable devices which shall be evaluated according to the provisions of § 2.1093 of this chapter. Further information on evaluating compliance with these limits can be found in the FCC's OST/OET

Bulletin Number 65, "Evaluating Compliance with FCC-Specified Guidelines for Human Exposure to Radiofrequency Radiation."

NOTE TO INTRODUCTORY PARAGRAPH: These limits are generally based on recommended exposure guidelines published by the National Council on Radiation Protection and Measurements (NCRP) in "Biological Effects and Exposure Criteria for Radiofrequency Electromagnetic Fields," NCRP Report No. 86, Sections 17.4.1, 17.4.1.1, 17.4.2 and 17.4.3. Copyright NCRP, 1986, Bethesda, Maryland 20814. In the frequency range from 100 MHz to 1500 MHz, exposure limits for field strength and power density are also generally based on guidelines recommended by the American National Standards Institute (ANSI) in Section 4.1 of "IEEE Standard for Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz," ANSI/IEEE C95.1-1992, Copyright 1992 by the Institute of Electrical and Electronics Engineers, Inc., New York, New York 10017.

TABLE 1—LIMITS FOR MAXIMUM PERMISSIBLE EXPOSURE (MPE)

Frequency range (MHz)	Electric field strength (V/m)	Magnetic field strength (A/m)	Power density (mW/cm ²)	Averaging time (minutes)
(A) Limits for Occupational/Controlled Exposures				
0.3–3.0	614	1.63	*(100)	6
3.0–30	1842/f	4.89/f	*(900/f ²)	6
30–300	61.4	0.163	1.0	6
300–1500			f/300	6
1500–100,000			5	6
(B) Limits for General Population/Uncontrolled Exposure				
0.3–1.34	614	1.63	*(100)	30
1.34–30	824/f	2.19/f	*(180/f ²)	30
30–300	27.5	0.073	0.2	30
300–1500			f/1500	30
1500–100,000			1.0	30

f = frequency in MHz

* = Plane-wave equivalent power density

NOTE 1 TO TABLE 1: Occupational/controlled limits apply in situations in which persons are exposed as a consequence of their employment provided those persons are fully aware of the potential for exposure and can exercise control over their exposure. Limits for occupational/controlled exposure also apply in situations when an individual is transient through a location where occupational/controlled limits apply provided he or she is made aware of the potential for exposure.

NOTE 2 TO TABLE 1: General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or can not exercise control over their exposure.

[61 FR 41016, Aug. 7, 1996]

§ 1.1311 Environmental information to be included in the environmental assessment (EA).

(a) The applicant shall submit an EA with each application that is subject to environmental processing (see § 1.1307). The EA shall contain the following information:

(1) For antenna towers and satellite earth stations, a description of the facilities as well as supporting structures and appurtenances, and a description of the site as well as the surrounding area and uses. If high intensity white lighting is proposed or utilized within a residential area, the EA must also address the impact of this lighting upon the residents.

§ 1.1312

(2) A statement as to the zoning classification of the site, and communications with, or proceedings before and determinations (if any) made by zoning, planning, environmental or other local, state or federal authorities on matters relating to environmental effect.

(3) A statement as to whether construction of the facilities has been a source of controversy on environmental grounds in the local community.

(4) A discussion of environmental and other considerations which led to the selection of the particular site and, if relevant, the particular facility; the nature and extent of any unavoidable adverse environmental effects, and any alternative sites or facilities which have been or might reasonably be considered.

(5) Any other information that may be requested by the Bureau or Commission.

(6) If endangered or threatened species or their critical habitats may be affected, the applicant's analysis must utilize the best scientific and commercial data available, see 50 CFR 402.14(c).

(b) The information submitted in the EA shall be factual (not argumentative or conclusory) and concise with sufficient detail to explain the environmental consequences and to enable the Commission or Bureau, after an independent review of the EA, to reach a determination concerning the proposal's environmental impact, if any. The EA shall deal specifically with any feature of the site which has special environmental significance (e.g., wilderness areas, wildlife preserves, natural migration paths for birds and other wildlife, and sites of historic, architectural, or archeological value). In the case of historically significant sites, it shall specify the effect of the facilities on any district, site, building, structure or object listed, or eligible for listing, in the National Register of Historic Places. It shall also detail any substantial change in the character of the land utilized (e.g., deforestation, water diversion, wetland fill, or other extensive change of surface features). In the case of wilderness areas, wildlife preserves, or other like areas, the statement shall discuss the effect of any continuing

47 CFR Ch. I (10–1–97 Edition)

pattern of human intrusion into the area (e.g., necessitated by the operation and maintenance of the facilities).

(c) The EA shall also be accompanied with evidence of site approval which has been obtained from local or federal land use authorities.

(d) To the extent that such information is submitted in another part of the application, it need not be duplicated in the EA, but adequate cross-reference to such information shall be supplied.

(e) An EA need not be submitted to the Commission if another agency of the Federal Government has assumed responsibility for determining whether of the facilities in question will have a significant effect on the quality of the human environment and, if it will, for invoking the environmental impact statement process.

[51 FR 15000, Apr. 22, 1986, as amended at 51 FR 18889, May 23, 1986; 53 FR 28394, July 28, 1988]

§ 1.1312 Facilities for which no preconstruction authorization is required.

(a) In the case of facilities for which no Commission authorization prior to construction is required by the Commission's rules and regulations the licensee or applicant shall initially ascertain whether the proposed facility may have a significant environmental impact as defined in § 1.1307 of this part or is categorically excluded from environmental processing under § 1.1306 of this part.

(b) If a facility covered by paragraph (a) of this section may have a significant environmental impact, the information required by § 1.1311 of this part shall be submitted by the licensee or applicant and ruled on by the Commission, and environmental processing (if invoked) shall be completed, see § 1.1308 of this part, prior to the initiation of construction of the facility.

(c) If a facility covered by paragraph (a) of this section is categorically excluded from environmental processing, the licensee or applicant may proceed with construction and operation of the facility in accordance with the applicable licensing rules and procedures.

Federal Communications Commission

§1.1314

(d) If, following the initiation of construction under this section, the licensee or applicant discovers that the proposed facility may have a significant environmental effect, it shall immediately cease construction which may have that effect, and submit the information required by §1.1311 of this part. The Commission shall rule on that submission and complete further environmental processing (if invoked), see §1.1308 of this part, before such construction is resumed.

(e) Paragraphs (a) through (d) of this section shall not apply to the construction of mobile stations.

[55 FR 20396, May 16, 1990, as amended at 56 FR 13414, Apr. 2, 1991]

§1.1313 Objections.

(a) In the case of an application to which section 309(b) of the Communications Act applies, objections based on environmental considerations shall be filed as petitions to deny.

(b) Informal objections which are based on environmental considerations must be filed prior to grant of the construction permit, or prior to authorization for facilities that do not require construction permits, or pursuant to the applicable rules governing services subject to lotteries.

§1.1314 Environmental impact statements (EISs).

(a) Draft Environmental Impact Statements (DEISs) (§1.1315) and Final Environmental Impact Statements (FEISs) (referred to collectively as EISs) (§1.1317) shall be prepared by the Bureau responsible for processing the proposal when the Commission's or the Bureau's analysis of the EA (§1.1308) indicates that the proposal will have a significant effect upon the environment and the matter has not been resolved by an amendment.

(b) As soon as practically feasible, the Bureau will publish in the FEDERAL REGISTER a Notice of Intent to prepare EISs. The Notice shall briefly identify the proposal, concisely describe the environmental issues and concerns presented by the subject application, and generally invite participation from affected or involved agencies, authorities and other interested persons.

(c) The EISs shall not address non-environmental considerations. To safeguard against repetitive and unnecessarily lengthy documents, the State-ments, where feasible, shall incorporate by reference material set forth in previous documents, with only a brief summary of its content. In preparing the EISs, the Bureau will identify and address the significant environmental issues and eliminate the insignificant issues from analysis.

(d) To assist in the preparation of the EISs, the Bureau may request further information from the applicant, interested persons and agencies and authorities, which have jurisdiction by law or which have relevant expertise. The Bureau may direct that technical studies be made by the applicant and that the applicant obtain expert opinion concerning the potential environmental problems and costs associated with the proposed action, as well as comparative analyses of alternatives. The Bureau may also consult experts in an effort to identify measures that could be taken to minimize the adverse effects and alternatives to the proposed facilities that are not, or are less, objectionable. The Bureau may also direct that objections be raised with appropriate local, state or federal land use agencies or authorities (if their views have not been previously sought).

(e) The Bureau responsible for processing the particular application and, thus, preparing the EISs shall draft supplements to Statements where significant new circumstances occur or information arises relevant to environmental concerns and bearing upon the application.

(f) The Application, the EA, the DEIS, and the FEIS and all related documents, including the comments filed by the public and any agency, shall be part of the administrative record and will be routinely available for public inspection.

(g) If EISs are to be prepared, the applicant must provide the community with notice of the availability of environmental documents and the scheduling of any Commission hearings in that action.

(h) The timing of agency action with respect to applications subject to EISs

§ 1.1315

47 CFR Ch. I (10–1–97 Edition)

is set forth in 40 CFR 1506.10. No decision shall be made until ninety (90) days after the Notice of Availability of the Draft Environmental Impact Statement is published in the Federal Register, and thirty (30) days after the Notice of Availability of the Final Environmental Impact Statement is published in the FEDERAL REGISTER, which time period may run concurrently. *See* 40 CFR 1506.10(c); *see also* §§ 1.1315(b) and 1.1317(b).

(i) Guidance concerning preparation of the Draft and Final Environmental Statements is set out in 40 CFR part 1502.

[51 FR 15000, Apr. 22, 1986, as amended at 53 FR 28394, July 28, 1988]

§ 1.1315 The Draft Environmental Impact Statement (DEIS); Comments.

(a) The DEIS shall include:

(1) A concise description of the proposal, the nature of the area affected, its uses, and any specific feature of the area that has special environmental significance;

(2) An analysis of the proposal, and reasonable alternatives exploring the important consequent advantages and/or disadvantages of the action and indicating the direct and indirect effects and their significance in terms of the short and long-term uses of the human environment.

(b) When a DEIS and supplements, if any, are prepared, the Commission shall send five copies of the Statement, or a summary, to the Office of Federal Activities, Environmental Protection Agency. Additional copies, or summaries, will be sent to the appropriate regional office of the Environmental Protection Agency. Public Notice of the availability of the DEIS will be published in the FEDERAL REGISTER by the Environmental Protection Agency.

(c) When copies or summaries of the DEIS are sent to the Environmental Protection Agency, the copies or summaries will be mailed with a request for comment to federal agencies having jurisdiction by law or special expertise, to the Council on Environmental Quality, to the applicant, to individuals, groups and state and local agencies known to have an interest in the environmental consequences of a grant, and

to any other person who has requested a copy.

(d) Any person or agency may comment on the DEIS and the environmental effect of the proposal described therein within 45 days after notice of the availability of the statement is published in the FEDERAL REGISTER. A copy of those comments shall be mailed to the applicant by the person who files them pursuant to 47 CFR 1.47. An original and one copy shall be filed with the Commission. If a person submitting comments is especially qualified in any way to comment on the environmental impact of the facilities, a statement of his or her qualifications shall be set out in the comments. In addition, comments submitted by an agency shall identify the person(s) who prepared them.

(e) The applicant may file reply comments within 15 days after the time for filing comments has expired. Reply comments shall be filed with the Commission in the same manner as comments, and shall be served by the applicant on persons or agencies which filed comments.

(f) The preparation of a DEIS and the request for comments shall not open the application to attack on other grounds.

§ 1.1317 The Final Environmental Impact Statement (FEIS).

(a) After receipt of comments and reply comments, the Bureau will prepare a FEIS, which shall include a summary of the comments, and a response to the comments, and an analysis of the proposal in terms of its environmental consequences, and any reasonable alternatives, and recommendations, if any, and shall cite the Commission's internal appeal procedures (*See* 47 CFR 1.101–1.120).

(b) The FEIS and any supplements will be distributed and published in the same manner as specified in § 1.1315. Copies of the comments and reply comments, or summaries thereof where the record is voluminous, shall be attached to the FEIS.

§ 1.1319 Consideration of the environmental impact statements.

(a) If the action is subject to a hearing:

Federal Communications Commission

§ 1.1402

(1) In rendering his initial decision, the Administrative Law Judge shall utilize the FEIS in considering the environmental issues, together with all other non-environmental issues. In a comparative context, the respective parties shall be afforded the opportunity to comment on the FEIS, and the Administrative Law Judge's decision shall contain an evaluation of the respective applications based on environmental and non-environmental public interest factors.

(2) Upon review of an initial decision, the Commission will consider and assess all aspects of the FEIS and will render its decision, giving due consideration to the environmental and non-environmental issues.

(b) In all non-hearing matters, the Commission, as part of its decision-making process, will review the FEIS, along with other relevant issues, to ensure that the environmental effects are specifically assessed and given comprehensive consideration.

[51 FR 15000, Apr. 22, 1986, as amended at 62 FR 4171, Jan. 29, 1997]

Subpart J—Pole Attachment Complaint Procedures

SOURCE: 43 FR 36094, Aug. 15, 1978, unless otherwise noted.

§ 1.1401 Purpose.

The rules and regulations contained in subpart J of this part provide complaint and enforcement procedures to ensure that telecommunications carriers and cable system operators have nondiscriminatory access to utility poles, ducts, conduits, and rights-of-way on rates, terms, and conditions that are just and reasonable.

[61 FR 45618, Aug. 29, 1996]

§ 1.1402 Definitions.

(a) The term *utility* means any person that is a local exchange carrier or an electric, gas, water, steam, or other public utility, and who owns or controls poles, ducts, conduits, or rights-of-way used, in whole or in part, for any wire communications. Such term does not include any railroad, any per-

son that is cooperatively organized, or any person owned by the Federal Government or any State.

(b) The term *pole attachment* means any attachment by a cable television system or provider of telecommunications service to a pole, duct, conduit, or right-of-way owned or controlled by a utility.

(c) The term *usable space* means the space on a utility pole above the minimum grade level which can be used for the attachment of wires, cables, and associated equipment.

(d) The term *complaint* means a filing by a cable television system operator, a cable television system association, a utility, an association of utilities, a telecommunications carrier, or an association of telecommunications carriers alleging that it has been denied access to a utility pole, duct, conduit, or right-of-way in violation of this subpart and/or that a rate, term, or condition for a pole attachment is not just and reasonable.

(e) The term *complainant* means a cable television system operator, a cable television system association, a utility, an association of utilities, a telecommunications carrier, or an association of telecommunications carriers who files a complaint.

(f) The term *respondent* means a cable television system operator, a utility, or a telecommunications carrier against whom a complaint is filed.

(g) The term *State* means any State, territory, or possession of the United States, the District of Columbia, or any political subdivision, agency, or instrumentality thereof.

(h) For purposes of this subpart, the term *telecommunications carrier* means any provider of telecommunications services, except that the term does not include aggregators of telecommunications services (as defined in 47 U.S.C. 226) or incumbent local exchange carriers (as defined in 47 U.S.C. 251(h)).

[43 FR 36094, Aug. 15, 1978, as amended at 52 FR 31770, Aug. 24, 1987; 61 FR 43024, Aug. 20, 1996; 61 FR 45618, Aug. 29, 1996]

§ 1.1403

§ 1.1403 Duty to provide access; modifications; notice of removal, increase or modification; petition for temporary stay.

(a) A utility shall provide a cable television system or any telecommunications carrier with nondiscriminatory access to any pole, duct, conduit, or right-of-way owned or controlled by it. Notwithstanding this obligation, a utility may deny a cable television system or any telecommunications carrier access to its poles, ducts, conduits, or rights-of-way, on a non-discriminatory basis where there is insufficient capacity or for reasons of safety, reliability and generally applicable engineering purposes.

(b) Requests for access to a utility's poles, ducts, conduits or rights-of-way by a telecommunications carrier or cable operator must be in writing. If access is not granted within 45 days of the request for access, the utility must confirm the denial in writing by the 45th day. The utility's denial of access shall be specific, shall include all relevant evidence and information supporting its denial, and shall explain how such evidence and information relate to a denial of access for reasons of lack of capacity, safety, reliability or engineering standards.

(c) A utility shall provide a cable television system operator or telecommunications carrier no less than 60 days written notice prior to:

(1) Removal of facilities or termination of any service to those facilities, such removal or termination arising out of a rate, term or condition of the cable television system operator's of telecommunications carrier's pole attachment agreement;

(2) Any increase in pole attachment rates; or

(3) Any modification of facilities other than routine maintenance or modification in response to emergencies.

(d) A cable television system operator or telecommunications carrier may file a "Petition for Temporary Stay" of the action contained in a notice received pursuant to paragraph (c) of this section within 15 days of receipt of such notice. Such submission shall not be considered unless it includes, in concise terms, the relief sought, the rea-

47 CFR Ch. I (10-1-97 Edition)

sons for such relief, including a showing of irreparable harm and likely cessation of cable television service or telecommunication service, a copy of the notice, and certification of service as required by § 1.1404(b). The named respondent may file an answer within 7 days of the date the Petition for Temporary Stay was filed. No further filings under this section will be considered unless requested or authorized by the Commission and no extensions of time will be granted unless justified pursuant to § 1.46.5.

[61 FR 45618, Aug. 29, 1996]

§ 1.1404 Complaint.

(a) The complaint shall contain the name and address of the complainant, name and address of the respondent, and shall contain a verification (in the form in § 1.721(b)), signed by the complainant or officer thereof if complainant is a corporation, showing complainant's direct interest in the matter complained of. Counsel for the complainant may sign the complaint. Complainants may join together to file a joint complaint. Complaints filed by associations shall specifically identify each utility, cable television system operator, or telecommunications carrier who is a party to the complaint and shall be accompanied by a document from each identified member certifying that the complaint is being filed on its behalf.

(b) The complaint shall be accompanied by a certification of service on the named respondent, and each of the Federal, State, and local governmental agencies that regulate any aspect of the services provided by the complainant or respondent.

(c) In a case where it is claimed that a rate, term, or condition is unjust or unreasonable, the complaint shall contain a statement that the State has not certified to the Commission that it regulates the rates, terms and conditions for pole attachments. The complaint shall include a statement that the utility is not owned by any railroad, any person who is cooperatively organized or any person owned by the Federal Government or any State.

(d) The complaint shall be accompanied by a copy of the pole attachment agreement, if any, between the

Federal Communications Commission

§1.1404

cable system operator or telecommunications carrier and the utility. If there is no present pole attachment agreement, the complaint shall contain:

(1) A statement that the utility uses or controls poles, ducts, or conduits used or designated, in whole or in part, for wire communication; and

(2) A statement that the cable television system operator or telecommunications carrier currently has attachments on the poles, ducts, conduits, or rights-of-way.

(e) The complaint shall state with specificity the pole attachment rate, term or condition which is claimed to be unjust or unreasonable.

(f) In any case, where it is claimed that a term or condition is unjust or unreasonable, the claim shall specify all information and argument relied upon to justify said claim.

(g) In a case where it is claimed that either a rate is unjust or unreasonable, or a term or condition is unjust or unreasonable and examination of such term or condition requires review of the associated rate, the complaint shall provide data and information in support of said claim. The data and information shall include, where applicable:

(1) The gross investment by the utility for pole lines;

(2) The investment in crossarms and other items which do not reflect the cost of owning and maintaining poles, if available;

(3) The depreciation reserve from the gross pole line investment;

(4) The depreciation reserve from the investment in crossarms and other items which do not reflect the cost of owning and maintaining poles, if available;

(5) The total number of poles: (i) Owned; and (ii) controlled or used by the utility.

If any of these poles are jointly owned, the complaint shall specify the number of such jointly owned poles and the percentage of each joint pole or the number of equivalent poles owned by the subject utility;

(6) The total number of poles which are the subject of the complaint;

(7) The number of poles included in paragraph (g)(6) of this section that are controlled or used by the utility

through lease between the utility and other owner(s), and the annual amounts paid by the utility for such rental;

(8) The number of poles included in paragraph (g)(6) of this section that are owned by the utility and that are leased to other users by the utility, and the annual amounts paid to the utility for such rental;

(9) The annual carrying charges attributable to the cost of owning a pole. These charges may be expressed as a percentage of the net pole investment. With its pleading, the utility shall file a copy of the latest decision of the state regulatory body or state court which determines the treatment of accumulated deferred taxes if it is at issue in the proceeding and shall note the section which specifically determines the treatment and amount of accumulated deferred taxes.

(10) The rate of return authorized for the utility for intrastate service. With its pleading, the utility shall file a copy of the latest decision of the state regulatory body or state court which establishes this authorized rate of return if the rate of return is at issue in the proceeding and shall note the section which specifically establishes this authorized rate and whether the decision is subject to further proceedings before the state regulatory body or a court;

(11) The average amount of usable space per pole for those poles used for pole attachments (13.5 feet may be in lieu of actual measurement, but may be rebutted);

(12) Reimbursements received from CATV operators for non-recurring costs; and

Data and information should be based upon historical or original cost methodology, insofar as possible. Data should be derived from Form M, FERC 1, or other reports filed with state or Federal regulatory agencies (identify source). Calculations made in connection with these figures should be provided to the complainant. Where the attachments involve ducts, conduits, or rights of way, in whole or in part, appropriate and equivalent data and information should be filed. The complainant shall also specify any other information and argument relied upon

§ 1.1405

to attempt to establish that a rate, term, or condition is not just and reasonable.

(h) If any of the information required in paragraph (g) of this section is not provided to the cable television operator by the utility upon reasonable request, the cable television operator shall include a statement indicating the steps taken to obtain information from the utility, including the dates of all requests. No complaint filed by a cable television operator shall be dismissed where the utility has failed to provide the information in paragraph (g) of this section after such reasonable request. A utility should supply a cable television system operator the information required in paragraph (g) of this section, along with the supporting pages from its FERC Form 1, FCC Form M, or other report to a regulatory body, within 30 days of the request by the cable operator. (The cable operator, in turn, shall submit these pages with its complaint). If the utility did not supply these pages to the cable operator in response to the information request, it shall supply this information in its response to the complaint.

(i) The complaint shall include a brief summary of all steps taken to resolve the problem prior to filing. If no such steps were taken, the complaint shall state the reason(s) why it believed such steps were fruitless.

(j) Factual allegations shall be supported by affidavit of a person or persons with actual knowledge of the facts, and exhibits shall be verified by the person who prepares them.

(k) In a case where a cable television system operator or telecommunications carrier claims that it has been denied access to a pole, duct, conduit or right-of-way despite a request made pursuant to section 47 U.S.C. § 224(f), the complaint shall be filed within 30 days of such denial. In addition to meeting the other requirements of this section, the complaint shall include the data and information necessary to support the claim, including:

(1) The reasons given for the denial of access to the utility's poles, ducts, conduits and rights-of-way;

(2) The basis for the complainant's claim that the denial of access is improper;

47 CFR Ch. I (10–1–97 Edition)

(3) The remedy sought by the complainant;

(4) A copy of the written request to the utility for access to its poles, ducts, conduits or rights-of-way; and

(5) A copy of the utility's response to the written request including all information given by the utility to support its denial of access. A complaint alleging improper denial of access will not be dismissed if the complainant is unable to obtain a utility's written response, or if the utility denies the complainant any other information needed to establish a *prima facie* case.

[43 FR 36094, Aug. 15, 1978, as amended at 44 FR 31649, June 1, 1979; 45 FR 17014, Mar. 17, 1980; 52 FR 31770, Aug. 24, 1987; 61 FR 43025, Aug. 20, 1996; 61 FR 45619, Aug. 29, 1996]

§ 1.1405 File numbers.

Each complaint which appears to be essentially complete under § 1.1404 will be accepted and assigned a file number. Such assignment is for administrative purposes only and does not necessarily mean that the complaint has been found to be in full compliance with other sections in this subpart. Petitions for temporary stay will also be assigned a file number upon receipt.

[44 FR 31650, June 1, 1979]

§ 1.1406 Dismissal of complaints.

(a) The complaint shall be dismissed for lack of jurisdiction in any case where a suitable certificate has been filed by a State pursuant to § 1.1414 of this subpart. Such certificate shall be conclusive proof of lack of jurisdiction of this Commission. A complaint against a utility shall also be dismissed if the utility does not use or control poles, ducts, or conduits used or designated, in whole or in part, for wire communication or if the utility does not meet the criteria of § 1.1402(a) of this subpart.

(b) If the complaint does not contain substantially all the information required under § 1.1404 the Commission may dismiss the complaint or may require the complainant to file additional information. The complaint shall not be dismissed if the information is not available from public records or from the respondent utility after reasonable request.

Federal Communications Commission

§1.1409

(c) Failure by the complainant to respond to official correspondence or a request for additional information will be cause for dismissal.

(d) Dismissal under provisions of paragraph (b) of this section above will be with prejudice if the complaint has been dismissed previously. Such a complaint may be refiled no earlier than six months from the date it was so dismissed.

[43 FR 36094, Aug. 15, 1978, as amended at 44 FR 31650, June 1, 1979]

§1.1407 Response and reply.

(a) Respondent shall have 30 days from the date the complaint was filed within which to file a response. Complainant shall have 20 days from the date the response was filed within which to file a reply. Extensions of time to file are not contemplated unless justification is shown pursuant to §1.46. Except as otherwise provided in §1.1403, no other filings and no motions other than for extension of time will be considered unless authorized by the Commission. The response should set forth justification for the rate, term, or condition alleged in the complaint not to be just and reasonable. Factual allegations shall be supported by affidavit of a person or persons with actual knowledge of the facts and exhibits shall be verified by the person who prepares them. The response, reply, and other pleadings may be signed by counsel.

(b) The response shall be served on the complainant and all parties listed in complainant's certificate of service.

(c) The reply shall be served on the respondent and all parties listed in respondent's certificate of service.

(d) Failure to respond may be deemed an admission of the material factual allegations contained in the complaint.

[44 FR 31650, June 1, 1979]

§1.1408 Number of copies and form of pleadings.

(a) An original and three copies of the complaint, response, and reply shall be filed with the Commission.

(b) All papers filed in the complaint proceeding must be drawn in conformity with the requirements of §§1.49, 1.50 and 1.52.

§1.1409 Commission consideration of the complaint.

(a) In its consideration of the complaint, response, and reply, the Commission may take notice of any information contained in publicly available filings made by the parties and may accept, subject to rebuttal, studies that have been conducted. The Commission may also request that one or more of the parties make additional filings or provide additional information. Where one of the parties has failed to provide information required to be provided by these rules or requested by the Commission, or where costs, values or amounts are disputed, the Commission may estimate such costs, values or amounts it considers reasonable, or may decide adversely to a party who has failed to supply requested information which is readily available to it, or both.

(b) The complainant shall have the burden of establishing a *prima facie* case that the rate, term, or condition is not just and reasonable or that the denial of access violates 47 U.S.C. §224(f). If, however, a utility argues that the proposed rate is lower than its incremental costs, the utility has the burden of establishing that such rate is below the statutory minimum just and reasonable rate. In a case involving a denial of access, the utility shall have the burden of proving that the denial was lawful, once a *prima facie* case is established by the complainant.

(c) The Commission shall determine whether the rate, term or condition complained of is just and reasonable. For the purposes of this paragraph, a rate is just and reasonable if it assures a utility the recovery of not less than the additional costs of providing pole attachments, nor more than an amount determined by multiplying the percentage of the total usable space, or the percentage of the total duct or conduit capacity, which is occupied by the pole attachment by the sum of the operating expenses and actual capital costs of the utility attributable to the entire pole, duct, conduit, or right-of-way.

(d) The Commission shall deny the complaint if it determines that the complainant has not established a *prima facie* case, or that the rate, term

§ 1.1410

or condition is just and reasonable, or that the denial of access was lawful.

(e) Section 1.1404 shall apply to the rate for any pole attachment used by a cable system operator solely to provide cable service. Until 47 U.S.C. 224(e) is implemented, § 1.1404 shall also apply to the rate for any pole attachment used by a cable system or any telecommunications carrier (to the extent such carrier is not a party to a pole attachment agreement) to provide any telecommunications service.

[43 FR 36094, Aug. 15, 1978, as amended at 52 FR 31770, Aug. 24, 1987; 61 FR 43025, Aug. 20, 1996; 61 FR 45619, Aug. 29, 1996]

§ 1.1410 Remedies.

If the Commission determines that the rate, term, or condition complained of is not just and reasonable, it may prescribe a just and reasonable rate, term, or condition and may:

(a) Terminate the unjust and unreasonable rate, term, or condition;

(b) Substitute in the pole attachment agreement the just and reasonable rate, term, or condition established by the Commission; and

(c) Order a refund, or payment, if appropriate. The refund or payment will normally be the difference between the amount paid under the unjust and/or unreasonable rate, term, or condition and the amount that would have been paid under the rate, term, or condition established by the Commission from the date that the complaint, as acceptable, was filed, plus interest.

[44 FR 31650, June 1, 1979]

§ 1.1411 Meetings and hearings.

The Commission may decide each complaint upon the filings and information before it, may require one or more informal meetings with the parties to clarify the issues or to consider settlement of the dispute, or may, in its discretion, order evidentiary procedures upon any issues it finds to have been raised by the filings.

§ 1.1412 Enforcement.

If the respondent fails to obey any order imposed under this subpart, the Commission on its own motion or by motion of the complainant may order the respondent to show cause why it

47 CFR Ch. I (10–1–97 Edition)

should not cease and desist from violating the Commission's order.

§ 1.1413 Forfeiture.

(a) If any person willfully fails to obey any order imposed under this subpart, or any Commission rule, or

(b) If any person shall in any written response to Commission correspondence or inquiry or in any application, pleading, report, or any other written statement submitted to the Commission pursuant to this subpart make any misrepresentation bearing on any matter within the jurisdiction of the Commission, the Commission may, in addition to any other remedies, including criminal penalties under section 1001 of Title 18 of the United States Code, impose a forfeiture pursuant to section 503(b) of the Communications Act, 47 U.S.C. 503(b).

§ 1.1414 State certification.

(a) If the Commission does not receive certification from a state that:

(1) It regulates rates, terms and conditions for pole attachments;

(2) In so regulating such rates, terms and conditions, the state has the authority to consider and does consider the interests of the subscribers of cable television services as well as the interests of the consumers of the utility services; and,

(3) It has issued and made effective rules and regulations implementing the state's regulatory authority over pole attachments (including a specific methodology for such regulation which has been made publicly available in the state), it will be rebuttably presumed that the state is not regulating pole attachments.

(b) Upon receipt of such certification, the Commission shall give public notice. In addition, the Commission shall compile and publish from time to time, a listing of states which have provided certification.

(c) Upon receipt of such certification, the Commission shall forward any pending case thereby affected to the state regulatory authority, shall so notify the parties involved and shall give public notice thereof.

(d) Certification shall be by order of the state regulatory body or by a person having lawful delegated authority

Federal Communications Commission

§ 1.1501

under provisions of state law to submit such certification. Said person shall provide in writing a statement that he or she has such authority and shall cite the law, regulation or other instrument conferring such authority.

(e) Notwithstanding any such certification, jurisdiction will revert to this Commission with respect to any individual matter, unless the state takes final action on a complaint regarding such matter:

(1) Within 180 days after the complaint is filed with the state, or

(2) Within the applicable periods prescribed for such final action in such rules and regulations of the state, if the prescribed period does not extend beyond 360 days after the filing of such complaint.

[43 FR 36094, Aug. 15, 1978, as amended at 44 FR 31650, June 1, 1979; 50 FR 18659, May 5, 1985]

§ 1.1415 Other orders.

The Commission may issue such other orders and so conduct its proceedings as will best conduce to the proper dispatch of business and the ends of justice.

§ 1.1416 Imputation of rates; modification costs.

(a) A utility that engages in the provision of telecommunications services or cable services shall impute to its costs of providing such services (and charge any affiliate, subsidiary, or associate company engaged in the provision of such services) an equal amount to the pole attachment rate for which such company would be liable under this section.

(b) The costs of modifying a facility shall be borne by all parties that obtain access to the facility as a result of the modification and by all parties that directly benefit from the modification. Each party described in the preceding sentence shall share proportionately in the cost of the modification. A party with a preexisting attachment to the modified facility shall be deemed to directly benefit from a modification if, after receiving notification of such modification as provided in subpart J of this part, it adds to or modifies its attachment. Notwithstanding the foregoing, a party with a

preexisting attachment to a pole, conduit, duct or right-of-way shall not be required to bear any of the costs of rearranging or replacing its attachment if such rearrangement or replacement is necessitated solely as a result of an additional attachment or the modification of an existing attachment sought by another party. If a party makes an attachment to the facility after the completion of the modification, such party shall share proportionately in the cost of the modification if such modification rendered possible the added attachment.

[61 FR 43025, Aug. 20, 1996; 61 FR 45619, Aug. 29, 1996]

Subpart K—Implementation of the Equal Access to Justice Act (EAJA) in Agency Proceedings

AUTHORITY: Sec. 203(a)(1), Pub. L. 96-481, 94 Stat. 2325 (5 U.S.C. 504(c)(1)).

SOURCE: 47 FR 3786, Jan. 27, 1982, unless otherwise noted.

GENERAL PROVISIONS

§ 1.1501 Purpose of these rules.

The Equal Access to Justice Act, 5 U.S.C. 504 (called *the EAJA* in this subpart), provides for the award of attorney's fees and other expenses to eligible individuals and entities who are parties to certain administrative proceedings (called *adversary adjudications*) before the Commission. An eligible party may receive an award when it prevails over the Commission, unless the Commission's position in the proceeding was substantially justified or special circumstances make an award unjust, or when the demand of the Commission is substantially in excess of the decision in the adversary adjudication and is unreasonable when compared with such decision, under the facts and circumstances of the case, unless the party has committed a willful violation of law or otherwise acted in bad faith, or special circumstances make an award unjust. The rules in this part describe the parties eligible for awards and the proceedings that are covered. They also explain how to apply for awards, and the procedures

§ 1.1502

and standards that the Commission will use to make them.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39898, July 31, 1996]

§ 1.1502 When the EAJA applies.

The EAJA applies to any adversary adjudication pending or commenced before the Commission on or after August 5, 1985. The provisions of § 1.1505(b) apply to any adversary adjudications commenced on or after March 29, 1996.

[61 FR 39898, July 31, 1996]

§ 1.1503 Proceedings covered.

(a) The EAJA applies to adversary adjudications conducted by the Commission. These are adjudications under 5 U.S.C. 554 in which the position of the Commission or any other agency of the United States, or any component of an agency, is presented by an attorney or other representative who enters an appearance and participates in the proceeding. Any proceeding in which this Agency may fix a lawful present or future rate is not covered by the EAJA. Proceedings to grant or renew licenses are also excluded, but proceedings to modify, suspend, or revoke licenses are covered if they are otherwise "adversary adjudications".

(b) The Commission may designate a proceeding as an adversary adjudication for purposes of the EAJA by so stating in an order initiating the proceeding or designating the matter for hearing. The Commission's failure to designate a proceeding as an adversary adjudication shall not preclude the filing of an application by a party who believes the proceeding is covered by the EAJA; whether the proceeding is covered will then be an issue for resolution in proceedings on the application.

(c) If a proceeding includes both matters covered by the EAJA and matters specifically excluded from coverage, any awards made will include only fees and expenses related to covered issues.

[47 FR 3786, Jan. 27, 1982, as amended at 52 FR 11653, Apr. 10, 1987]

§ 1.1504 Eligibility of applicants.

(a) To be eligible for an award of attorney fees and other expenses under the EAJA, the applicant must be a party, as defined in 5 U.S.C. 551(3), to

47 CFR Ch. I (10–1–97 Edition)

the adversary adjudication for which it seeks an award. The applicant must show that it meets all conditions of eligibility set out in this paragraph and in paragraph (b) of this section.

(b) The types of eligible applicants are as follows:

(1) An individual with a net worth of not more than \$2 million;

(2) The sole owner of an unincorporated business who has a net worth of not more than \$7 million, including both personal and business interests, and not more than 500 employees;

(3) A charitable association as defined in section 501(c)(3) of the Internal Revenue Code (26 U.S.C. 501(c)(3)) with not more than 500 employees;

(4) A cooperative association as defined in section 15(a) of the Agricultural Marketing Act (12 U.S.C. 1141j(a)) with not more than 500 employees;

(5) Any other partnership, corporation, association, unit of local government, or organization with a net worth of not more than \$7 million and not more than 500 employees;

(6) For purposes of § 1.1505(b), a small entity as defined in 5 U.S.C. 601.

(c) For the purpose of eligibility, the net worth and number of employees of an applicant shall be determined as of the date the proceeding was initiated.

(d) An applicant who owns an unincorporated business will be considered as an "individual" rather than a "sole owner of an unincorporated business" if the issues on which the applicant prevails are related primarily to personal interests rather than to business interests.

(e) The number of employees of an applicant include all persons who regularly perform services for remuneration for the applicant, under the applicant's direction and control. Part-time employees shall be included on a proportional basis.

(f) The net worth and number of employees of the applicant and all of its affiliates shall be aggregated to determine eligibility. Any individual, corporation or other entity that directly or indirectly controls or owns a majority of the voting shares or other interest of the applicant, or any corporation or other entity of which the applicant directly or indirectly owns or controls a majority of the voting shares or

Federal Communications Commission

§ 1.1506

other interest, will be considered an affiliate for purposes of this part, unless the Administrative Law Judge determines that such treatment would be unjust and contrary to the purposes of the EAJA in light of the actual relationship between the affiliated entities. In addition, the Administrative Law Judge may determine that financial relationships of the applicant other than those described in this paragraph constitute special circumstances that would make an award unjust.

(g) An applicant that participates in a proceeding primarily on behalf of one or more other persons or entities that would be ineligible is not itself eligible for an award.

[47 FR 3786, Jan. 27, 1982, as amended at 52 FR 11653, Apr. 10, 1987; 61 FR 39898, July 31, 1996]

§ 1.1505 Standards for awards.

(a) A prevailing party may receive an award for fees and expenses incurred in connection either with an adversary adjudication, or with a significant and discrete substantive portion of an adversary adjudication in which the party has prevailed over the position of the Commission.

(1) The position of the Commission includes, in addition to the position taken by the Commission in the adversary adjudication, the action or failure to act by the agency upon which the adversary adjudication is based.

(2) An award will be reduced or denied if the Commission's position was substantially justified in law and fact, if special circumstances make an award unjust, or if the prevailing party unduly or unreasonably protracted the adversary adjudication.

(b) If, in an adversary adjudication arising from a Commission action to enforce a party's compliance with a statutory or regulatory requirement, the demand of the Commission is substantially in excess of the decision in the adversary adjudication and is unreasonable when compared with that decision, under the facts and circumstances of the case, the party shall be awarded the fees and other expenses related to defending against the excessive demand, unless the party has committed a willful violation of law or otherwise acted in bad faith, or special cir-

cumstances make an award unjust. The "demand" of the Commission means the express demand which led to the adversary adjudication, but it does not include a recitation by the Commission of the maximum statutory penalty in the administrative complaint, or elsewhere when accompanied by an express demand for a lesser amount.

(c) The burden of proof that an award should not be made is on the appropriate Bureau (see § 1.21) whose representative shall be called "Bureau counsel" in this subpart K.

[61 FR 39899, July 31, 1996]

§ 1.1506 Allowable fees and expenses.

(a) Awards will be based on rates customarily charged by persons engaged in the business of acting as attorneys, agents and expert witnesses.

(b) No award for the fee of an attorney or agent under these rules may exceed \$75.00, or for adversary adjudications commenced on or after March 29, 1996, \$125.00, per hour. No award to compensate an expert witness may exceed the highest rate at which the Commission pays expert witnesses. However, an award may also include the reasonable expenses of the attorney; agent, or witness as a separate item, if the attorney, agent or witness ordinarily charges its clients separately for such expenses.

(c) In determining the reasonableness of the fee sought for an attorney, agent or expert witness, the Administrative Law Judge shall consider the following:

(1) If the attorney, agent or witness is in private practice, his or her customary fee for similar services, or, if an employee of the applicant, the fully allocated cost of the services;

(2) The prevailing rate for similar services in the community in which the attorney, agent or witness ordinarily performs services;

(3) The time actually spent in the representation of the applicant;

(4) The time reasonably spent in light of the difficulty or complexity of the issues in the proceeding; and

(5) Such other factors as may bear on the value of the service provided.

(d) The reasonable cost of any study, analysis, engineering report, test, project or similar matter prepared on behalf of a party may be awarded, to

§ 1.1507

the extent that the charge for the service does not exceed the prevailing rate for similar services, and the study or other matter was necessary for preparation of the applicant's case.

(e) Fees may be awarded only for work performed after designation of a proceeding or after issuance of a show cause order.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39899, July 31, 1996]

§ 1.1507 Rulemaking on maximum rates for attorney fees.

(a) If warranted by an increase in the cost of living or by special circumstances (such as limited availability of attorneys qualified to handle certain types of proceedings), the Commission may adopt regulations providing that attorney fees may be awarded at a rate higher than \$125.00 per hour in some or all of the types of proceedings covered by this part. The Commission will conduct any rulemaking proceedings for this purpose under the informal rulemaking procedures of the Administrative Procedure Act.

(b) Any person may file with the Commission a petition for rulemaking to increase the maximum rate for attorney fees, in accordance with subpart C of this chapter. The petition should identify the rate the petitioner believes this agency should establish and the types of proceedings in which the rate should be used. It should also explain fully the reasons why the higher rate is warranted. This agency will respond to the petition by initiating a rulemaking proceeding, denying the petition, or taking other appropriate action.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39899, July 31, 1996]

§ 1.1508 Awards against other agencies.

If an applicant is entitled to an award because it prevails over another agency of the United States that participates in a proceeding before the Commission and takes a position that is not substantially justified, the award or an appropriate portion of the award shall be made against that agency. Counsel for that agency shall be

47 CFR Ch. I (10–1–97 Edition)

treated as Bureau counsel for the purpose of this subpart.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39899, July 31, 1996]

INFORMATION REQUIRED FROM APPLICANTS

§ 1.1511 Contents of application.

(a) An application for an award of fees and expenses under EAJA shall identify the applicant and the proceeding for which an award is sought. Unless the applicant is an individual, the application shall state the number of employees of the applicant and describe briefly the type and purpose of its organization or business. The application shall also:

(1) Show that the applicant has prevailed and identify the position of an agency or agencies in the proceeding that the applicant alleges was not substantially justified; or

(2) Show that the demand by the agency or agencies in the proceeding was substantially in excess of, and was unreasonable when compared with, the decision in the proceeding.

(b) The application shall also include a declaration that the applicant is a small entity as defined in 5 U.S.C. 601 or a statement that the applicant's net worth does not exceed \$2 million (if an individual) or \$7 million (for all other applicants, including their affiliates). However, an applicant may omit the statement concerning its net worth if:

(1) It attaches a copy of a ruling by the Internal Revenue Service that it qualifies as an organization described in section 501(c)(3) of the Internal Revenue Code (26 U.S.C. 501(c)(3)) or, in the case of a tax-exempt organization not required to obtain a ruling from the Internal Revenue Service on its exempt status, a statement that describes the basis for the applicant's belief that it qualifies under such section; or

(2) It states that it is a cooperative association as defined in section 15(a) of the Agricultural Marketing Act (12 U.S.C. 1141j(a)).

(c) The application shall state the amount of fees and expenses for which an award is sought.

(d) The application may also include any other matters that the applicant wishes the Commission to consider in

Federal Communications Commission

§ 1.1514

determining whether and in what amount an award should be made.

(e) The application shall be signed by the applicant or an authorized officer or attorney of the applicant. It shall also contain or be accompanied by a written verification under oath or under penalty of perjury that the information provided in the application is true and correct.

[47 FR 3786, Jan. 27, 1982, as amended at 52 FR 11653, Apr. 10, 1987; 61 FR 39899, July 31, 1996]

§ 1.1512 Net worth exhibit.

(a) Each applicant except a qualified tax-exempt organization or cooperative association must provide with its application a detailed exhibit showing the net worth of the applicant and any affiliates (as defined in § 1.1504(f) of this part) at the time the proceeding was designated. The exhibit may be in any form convenient to the applicant that provides full disclosure of the applicant's and its affiliates' assets and liabilities and is sufficient to determine whether the applicant qualifies under the standards in this subpart. The Administrative Law Judge may require an applicant to file additional information to determine its eligibility for an award.

(b) Ordinarily, the net worth exhibit will be included in the public record of the proceeding. However, an applicant that objects to public disclosure of information in any portion of the exhibit and believes there are legal grounds for withholding it from disclosure may submit that portion of the exhibit directly to the Administrative Law Judge in a sealed envelope labeled "Confidential Financial Information", accompanied by a motion to withhold the information from public disclosure. The motion shall describe the information sought to be withheld and explain, in detail, why it falls within one or more of the specific exemptions from mandatory disclosure under the Freedom of Information Act, 5 U.S.C. 552(b)(1)–(9), why public disclosure of the information would adversely affect the applicant, and why disclosure is not required in the public interest. The material in question shall be served on Bureau counsel, but need not be served on any other party to the proceeding. If

the Administrative Law Judge finds that the information should not be withheld from disclosure, it shall be placed in the public record of the proceeding. Otherwise, any request to inspect or copy the exhibit shall be disposed of in accordance with the Commission's established procedures under the Freedom of Information Act, §§ 0.441 through 0.466 of this chapter.

§ 1.1513 Documentation of fees and expenses.

The application shall be accompanied by full documentation of the fees and expenses, including the cost of any study, analysis, engineering report, test, project or similar matter, for which an award is sought. A separate itemized statement shall be submitted for each professional firm or individual whose services are covered by the application, showing hours spent in connection with the proceeding by each individual, a description of the specific services performed, the rate at which each fee has been computed, any expenses for which reimbursement is sought, the total amount claimed, and the total amount paid or payable by the applicant or by any other person or entity for the services provided. The Administrative Law Judge may require the applicant to provide vouchers, receipts, or other substantiation for any expenses claimed.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39899, July 31, 1996]

§ 1.1514 When an application may be filed.

(a) An application may be filed whenever the applicant has prevailed in the proceeding or in a significant and discrete substantive portion of the proceeding, or when the demand of the Commission is substantially in excess of the decision in the proceeding, but in no case later than 30 days after the Commission's final disposition of the proceeding.

(b) If review or reconsideration is sought or taken of a decision as to which an applicant believes it has prevailed, proceedings for the award of fees shall be stayed pending final disposition of the underlying controversy.

(c) For purposes of this rule, *final disposition* means the later of

§ 1.1521

(1) The date on which an initial decision or other recommended disposition of the merits of the proceeding by an Administrative Law Judge becomes administratively final;

(2) Issuance of an order disposing of any petitions for reconsideration of the Commission's order in the proceeding;

(3) If no petition for reconsideration is filed, the last date on which such petition could have been filed;

(4) Issuance of a final order by the Commission or any other final resolution of a proceeding, such as settlement or voluntary dismissal, which is not subject to a petition for reconsideration, or to a petition for judicial review; or

(5) Completion of judicial action on the underlying controversy and any subsequent Commission action pursuant to judicial mandate.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39899, July 31, 1996]

PROCEDURES FOR CONSIDERING APPLICATIONS

§ 1.1521 Filing and service of documents.

Any application for an award or other pleading relating to an application shall be filed and served on all parties to the proceeding in the same manner as other pleadings in the proceeding, except as provided in § 1.1512(b) for confidential financial information.

§ 1.1522 Answer to application.

(a) Within 30 days after service of an application Bureau counsel may file an answer to the application. Unless Bureau counsel requests an extension of time for filing or files a statement of intent to negotiate under paragraph (b) of this section, failure to file an answer within the 30-day period may be treated as a consent to the award request.

(b) If Bureau counsel and the applicant believe that the issues in the fee application can be settled, they may jointly file a statement of their intent to negotiate a settlement. The filing of this statement shall extend the time for filing an answer for an additional 30 days, and further extensions may be granted by the Administrative Law Judge upon request by Bureau counsel and the applicant.

47 CFR Ch. I (10–1–97 Edition)

(c) The answer shall explain in detail any objections to the award requested and identify the facts relied on in support of Bureau counsel's position. If the answer is based on any alleged facts not already in the record of the proceeding, Bureau counsel shall include with the answer either supporting affidavits or a request for further proceedings under § 1.1526.

§ 1.1523 Reply.

Within 15 days after service of an answer, the applicant may file a reply. If the reply is based on any alleged facts not already in the record of the proceeding, the applicant shall include with the reply either supporting affidavits or a request for further proceedings under § 1.1526.

§ 1.1524 Comments by other parties.

Any party to a proceeding other than the applicant and Bureau counsel may file comments on an application within 30 days after it is served or an answer within 15 days after it is served. A commenting party may not participate further in proceedings on the application unless the Administrative Law Judge determines that the public interest requires such participation in order to permit full exploration of matters raised in the comments.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39899, July 31, 1996]

§ 1.1525 Settlement.

The applicant and Bureau counsel may agree on a proposed settlement of the award before final action on the application, either in connection with a settlement of the underlying proceeding, or after the underlying proceeding has been concluded. If a prevailing party and Bureau counsel agree on a proposed settlement of an award before an application has been filed, the application shall be filed with the proposed settlement. If the Administrative Law Judge approves the proposed settlement, it shall be forwarded to the Commission for final approval.

§ 1.1526 Further proceedings.

(a) Ordinarily, the determination of an award will be made on the basis of

Federal Communications Commission

§1.1530

the written record. However, on request of either the applicant or Bureau counsel, or on his or her own initiative, the Administrative Law Judge may order further proceedings, such as an informal conference, oral argument, additional written submissions or, as to issues other than excessive demand or substantial justification, an evidentiary hearing. Such further proceedings shall be held only when necessary for full and fair resolution of the issues arising from the application, and shall be conducted as promptly as possible. Whether or not the position of the agency embodied an excessive demand or was substantially justified shall be determined on the basis of the administrative record, as a whole, which is made in the adversary adjudication for which fees and other expenses are sought.

(b) A request that the Administrative Law Judge order further proceedings under this section shall specifically identify the information sought or the disputed issues and shall explain why the additional proceedings are necessary to resolve the issues.

[47 FR 3786, Jan. 27, 1982, as amended at 52 FR 11653, Apr. 10, 1987; 61 FR 39899, July 31, 1996]

§1.1527 Decision.

The Administrative Law Judge shall issue an initial decision on the application as soon as possible after completion of proceedings on the application. The decision shall include written findings and conclusions regarding the applicant's eligibility and whether the applicant was a prevailing party or whether the demand by the agency or agencies in the proceeding was substantially in excess of, and was unreasonable when compared with, the decision in the adversary adjudication, and an explanation of the reasons for any difference between the amount requested and the amount awarded. The decision shall also include, if at issue, findings on whether the Commission's position substantially justified, whether the applicant unduly protracted the proceedings, committed a willful violation of law, or otherwise acted in bad faith, or whether special circumstances make an award unjust. If the applicant has sought an award against more than

one agency, the decision shall allocate responsibility for payment of any award made among the agencies, and shall explain the reasons for the allocation made.

[61 FR 39900, July 31, 1996]

§1.1528 Commission review.

Either the applicant or Bureau counsel may seek Commission review of the initial decision on the application, or the Commission may decide to review the decision on its own initiative, in accordance with §§1.276 through 1.282 of this chapter. Except as provided in §1.1525, if neither the applicant nor Bureau counsel seeks review and the Commission does not take review on its own initiative, the initial decision on the application shall become a final decision of the Commission 50 days after it is issued. Whether to review a decision is a matter within the discretion of the Commission. If review is taken, the Commission will issue a final decision on the application or remand the application to the Administrative Law Judge for further proceedings.

[47 FR 3786, Jan. 27, 1982, as amended at 61 FR 39900, July 31, 1996]

§1.1529 Judicial review.

Judicial review of final agency decisions on awards may be sought as provided in 5 U.S.C. 504(c)(2).

§1.1530 Payment of award.

An applicant seeking payment of an award from the Commission shall submit to the General Counsel a copy of the Commission's final decision granting the award, accompanied by a statement that the applicant will not seek review of the decision in the United States courts, or a copy of the court's order directing payment. The Commission will pay the amount awarded to the applicant unless judicial review of the award or the underlying decision of the adversary adjudication has been sought by the applicant or any other party to the proceeding.

Subpart L—Random Selection Procedures for Mass Media Services

AUTHORITY: 47 U.S.C. 309(i).

§ 1.1601

SOURCE: 48 FR 27202, June 13, 1983, unless otherwise noted.

GENERAL PROCEDURES

§ 1.1601 Scope.

The provisions of this subpart, and the provisions referenced herein, shall apply to applications for initial licenses or construction permits or for major changes in the facilities of authorized stations in the following services:

- (a) Low Power Television and Television Translator Broadcasting.
- (b) [Reserved]

§ 1.1602 Designation for random selection.

Applications in the services specified in § 1.1601 shall be tendered, accepted or dismissed, filed, publicly noted and subject to random selection and hearing in accordance with any relevant rules. Competing applications for an initial license or construction permit shall be designated for random selection and hearing in accordance with the procedures set forth in §§ 1.1603 through 1.1623 and § 73.3572 of this chapter.

§ 1.1603 Conduct of random selection.

The random selection probabilities will be calculated in accordance with the formula set out in rules §§ 1.1621 through 1.1623.

[48 FR 27202, June 13, 1983, as amended at 48 FR 43330, Sept. 23, 1983]

§ 1.1604 Post-selection hearings.

(a) Following the random selection, the Commission shall announce the "tentative selectee" and, where permitted by § 73.3584 invite Petitions to Deny its application. Following the responsive pleadings thereto, the Commission shall:

(1) In the case of low power television stations, take action pursuant to either § 73.3591, § 73.3592 or § 73.3593.

(b) If, after such hearing as may be necessary, the Commission determines that the "tentative selectee" has met the requirements of § 73.3591(a) it will make the appropriate grant. If the Commission is unable to make such a determination, it shall order that another random selection be conducted

47 CFR Ch. I (10–1–97 Edition)

from among the remaining mutually exclusive applicants, in accordance with the provisions of this subpart.

(c) If, on the basis of the papers before it, the Commission determines that a substantial and material question of fact exists, it shall designate that question for hearing. Hearings may be conducted by the Commission or, in the case of a matter which requires oral testimony for its resolution, an Administrative Law Judge.

(2) [Reserved]

§ 1.1621 Definitions.

(a) *Medium of mass communications* means:

- (1) A daily newspaper;
- (2) A cable television system; and
- (3) A license or construction permit for

- (i) A television station, including low power TV or TV translator,
- (ii) A standard (AM) radio station,
- (iii) An FM radio station,
- (iv) A direct broadcast satellite transponder under the editorial control of the licensee, and
- (v) A Multipoint Distribution Service station.

(b) *Minority group* means:

- (1) Blacks,
- (2) Hispanics
- (3) American Indians,
- (4) Alaska Natives,
- (5) Asians, and
- (6) Pacific Islanders.

(c) *Owner* means the applicant and any individual, partnership, trust, unincorporated association, or corporation which:

- (1) If the applicant is a proprietorship, is the proprietor,
- (2) If the applicant is a partnership, holds any partnership interest,
- (3) If the applicant is a trust, is the beneficiary thereof,
- (4) If the applicant is an unincorporated association or non-stock corporation, is a member, or, in the case of a nonmembership association or corporation, a director,
- (5) If the applicant is a stock corporation, is the beneficial owner of voting shares.

NOTE 1: For purposes of applying the diversity preference to such entities only the other ownership interests of those with a 1% or more beneficial interest in the entity will be cognizable.

Federal Communications Commission

§1.1623

NOTE 2: For the purposes of this section, a daily newspaper is one which is published four or more days per week, which is in the English language, and which is circulated generally in the community of publication. A college newspaper is not considered as being circulated generally.

NOTE 3: For the purposes of applying the diversity preference, the ownership interests of the spouse of an applicant's principal will not presumptively be attributed to the applicant.

[48 FR 27202, June 13, 1983, as amended at 50 FR 5992, Feb. 13, 1985]

§1.1622 Preferences.

(a) Any applicant desiring a preference in the random selection shall so indicate as part of its application. Such an applicant shall list any owner who owns all or part of a medium of mass communications or who is a member of a minority group, together with a precise identification of the ownership interest held in such medium of mass communications or name of the minority group, respectively. Such an applicant shall also state whether more than 50% of the ownership interests in it are held by members of minority groups and the number of media of mass communications more than 50% of whose ownership interests are held by the applicant and/or its owners.

(b) Preference factors as incorporated in the percentage calculations in §1.1623, shall be granted as follows:

(1) Applicants, more than 50% of whose ownership interests are held by members of minority groups—2:1.

(2) Applicants whose owners in the aggregate hold more than 50% of the ownership interests in no other media of mass communications—2:1.

(3) Applicants whose owners in the aggregate hold more than 50% of the ownership interest in one, two or three other media of mass communications—1.5:1.

(c) Applicants may receive preferences pursuant to §1.1622(b)(1) and either §1.1622 (b)(2) or (b)(3).

(d) Preferences will be determined on the basis of ownership interests as of the date of release of the latest Public Notice announcing the acceptance of the last-filed mutually exclusive application.

(e) No preferences pursuant to §1.1622 (b)(2) or (b)(3) shall be granted to any LPTV or MDS applicant whose owners, when aggregated, have an ownership interest of more than 50 percent in the following media of mass communications, if the service areas of those media as described herein wholly encompass or are encompassed by the protected predicted contour, computed in accordance with §74.707(a), of the low power TV or TV translator station for which the license or permit is sought, or computed in accordance with §21.902(d), of the MDS station for which the license or permit is sought.

(1) AM broadcast station—predicted or measured 2 mV/m groundwave contour, computed in accordance with §73.183 or §73.186;

(2) FM broadcast station—predicted 1 mV/m contour, computed in accordance with §73.313;

(3) TV broadcast station—Grade A contour, computed in accordance with §73.684;

(4) Low power TV or TV translator station—protected predicted contour, computed in accordance with §74.707(a);

(5) Cable television system franchise area, nor will the diversity preference be available to applicants whose proposed transmitter site is located within the franchise area of a cable system in which its owners, in the aggregate, have an ownership interest of more than 50 percent.

(6) Daily newspaper community of publication, nor will the diversity preference be available to applicants whose proposed transmitter site is located within the community of publication of a daily newspaper in which its owners, in the aggregate, have an ownership interest of more than 50 percent.

(7) Multipoint Distribution Service—station service area, computed in accordance with §21.902(d).

[48 FR 27202, June 13, 1983, as amended at 50 FR 5992, Feb. 13, 1985; 50 FR 11161, Mar. 20, 1985]

§1.1623 Probability calculation.

(a) All calculations shall be computed to no less than three significant digits. Probabilities will be truncated to the number of significant digits used in a particular lottery.

§ 1.1801

(b) Divide the total number of applicants into 1.00 to determine pre-preference probabilities.

(c) Multiply each applicant's pre-preference probability by the applicable preference from § 1.1622 (b)(2) or (b)(3).

(d) Divide each applicant's probability pursuant to paragraph (c) of this section by the sum of such probabilities to determine intermediate probabilities.

(e) Add the intermediate probabilities of all applicants who received a preference pursuant to § 1.1622 (b)(2) or (b)(3).

(f)(1) If the sum pursuant to paragraph (e) of this section is .40 or greater, proceed to paragraph (g) of this section.

(2) If the sum pursuant to paragraph (e) of this section is less than .40, then multiply each such intermediate probability by the ratio of .40 to such sum. Divide .60 by the number of applicants who did not receive a preference pursuant to § 1.1622 (b)(2) or (b)(3) to determine their new intermediate probabilities.

(g) Multiply each applicant's probability pursuant to paragraph (f) of this section by the applicable preference ratio from § 1.1622(b)(1).

(h) Divide each applicant's probability pursuant to paragraph (g) of this section by the sum of such probabilities to determine the final selection percentage.

Subpart M [Reserved]

Subpart N—Enforcement of Non-discrimination on the Basis of Handicap in Programs or Activities Conducted by the Federal Communications Commission

AUTHORITY: 29 U.S.C. 794.

SOURCE: 52 FR 16258, May 4, 1987, unless otherwise noted.

§ 1.1801 Purpose.

The purpose of this part is to effectuate section 119 of the Rehabilitation, Comprehensive Services, and Developmental Disabilities Amendments of 1978, which amended section 504 of the

47 CFR Ch. I (10–1–97 Edition)

Rehabilitation Act of 1973 to prohibit discrimination on the basis of handicap in programs or activities conducted by Executive agencies or the United States Postal Service.

§ 1.1802 Applications.

This part applies to all programs or activities conducted by the Federal Communications Commission. The programs or activities of entities that are licensed or certified by the Federal Communications Commission are not covered by these regulations.

§ 1.1803 Definitions.

For purposes of this part, the term—

Assistant Attorney General means the Assistant Attorney General, Civil Rights Division, United States Department of Justice.

Auxiliary aids means services or devices that enable persons with impaired sensory, manual, or speaking skills to have an equal opportunity to participate in, and enjoy the benefits of, programs or activities conducted by the Commission. For example, auxiliary aids useful for persons with impaired vision include readers, Brailled materials, audio recordings, and other similar services and devices. Auxiliary aids useful for persons with impaired hearing include telephone handset amplifiers, telephones compatible with hearing aids, telecommunication devices for deaf persons (TDD's), interpreters, notetakers, written materials, and other similar services and devices.

Commission means Federal Communications Commission.

Complete complaint means a written statement that contains the complainant's name and address and describes the Commission's alleged discriminatory action in sufficient detail to inform the Commission of the nature and date of the alleged violation of section 504. It shall be signed by the complainant or by someone authorized to do so on his or her behalf. Complaints filed on behalf of classes or third parties shall describe or identify (by name, if possible) the alleged victims of discrimination.

Facility means all or any portion of buildings, structures, equipment, roads, walks, parking lots, rolling

Federal Communications Commission

§1.1810

stock or other conveyances, or other real or personal property.

Individual with handicaps means any individual who has a physical or mental impairment that substantially limits one or more major life activities, has a record of such an impairment, or is regarded as having such an impairment. As used in this definition, the phrase:

(1) *Physical or mental impairment* includes—

(i) Any physiological disorder or condition, cosmetic disfigurement, or anatomical loss affecting one or more of the following body systems: Neurological; musculoskeletal; special sense organs; respiratory, including speech organs; cardiovascular; reproductive; digestive; genitourinary; hemic and lymphatic; skin; and endocrine; or

(ii) Any mental or psychological disorder, such as mental retardation, organic brain syndrome, emotional or mental illness, and specific learning disabilities. The term *physical or mental impairment* includes, but is not limited to, such diseases and conditions as orthopedic, visual, speech, and hearing impairments, cerebral palsy, epilepsy, muscular dystrophy, multiple sclerosis, cancer, heart disease, diabetes, mental retardation, emotional illness, and drug addiction and alcoholism.

(2) *Major life activities* includes functions such as caring for one's self, performing manual tasks, walking, seeing, hearing, speaking, breathing, learning, and working.

(3) *Has a record of such an impairment* means has a history of, or has been misclassified as having, a mental or physical impairment that substantially limits one or more major life activities.

(4) *Is regarded as having an impairment* means—

(i) Has a physical or mental impairment that does not substantially limit major life activities but is treated by the Commission as constituting such a limitation;

(ii) Has a physical or mental impairment that substantially limits major life activities only as a result of the attitudes of others toward such impairment; or

(iii) Has none of the impairments defined in paragraph (1) of this definition

but is treated by the Commission as having such an impairment.

Qualified individual with handicaps means—

(1) With respect to any Commission program or activity under which an individual is required to perform services or to achieve a level of accomplishment, an individual with handicaps who meets the essential eligibility requirements and who can achieve the purpose of the program or activity without modifications in the program or activity that the Commission can demonstrate would result in a fundamental alteration in its nature; and

(2) With respect to any other program or activity, an individual with handicaps who meets the essential eligibility requirements for participation in, or receipt of benefits from, that program or activity; and

(3) *Qualified handicapped person* as that term is defined for purposes of employment in 29 CFR 1613.702(f), which is made applicable to this part by §1.1840.

Section 504 means section 504 of the Rehabilitation Act of 1973, Pub. L. 93-112, 87 Stat. 394, 29 U.S.C. 794, as amended by the Rehabilitation Act Amendments of 1974, Pub. L. 93-516, 88 Stat. 1617, and the Rehabilitation, Comprehensive Services, and Developmental Disabilities Amendments of 1978, Pub. L. 95-602, 92 Stat. 2955, and the Rehabilitation Act Amendments of 1986, sec. 103(d), Pub. L. 99-506, 100 Stat. 1810. As used in this part, section 504 applies only to programs or activities conducted by Executive agencies and not to federally assisted programs.

§§1.1804–1.1809 [Reserved]

§1.1810 Self-evaluation.

(a) The Commission shall, within one year of the effective date of this part, evaluate its current policies and practices, and the effects thereof, that do not or may not meet the requirements of this part, and, to the extent modification of any such policies and practices is required, the Commission shall proceed to make the necessary modifications.

(b) The Commission shall provide an opportunity to interested persons, including individuals with handicaps or organizations representing individuals

§ 1.1811

with handicaps, to participate in the self-evaluation process by submitting comments (both oral and written).

(c) The Commission shall, until three years following completion of the self-evaluation, maintain on file and make available for public inspection—

(1) A description of areas examined and any problems identified; and

(2) A description of any modifications made.

§ 1.1811 Notice.

The Commission shall make available to employees, applicants, participants, beneficiaries, and other interested persons such information regarding the provisions of this part and its applicability to the programs or activities conducted by the Commission, and make such information available to them in such manner as the Managing Director finds necessary to apprise such persons of the protections against discrimination assured them by section 504 and these regulations.

§§ 1.1812–1.1829 [Reserved]

§ 1.1830 General prohibitions against discrimination.

(a) No qualified individual with handicaps shall, on the basis of handicap, be excluded from participation in, be denied the benefits of, or otherwise be subjected to discrimination under any program or activity conducted by the Commission.

(b)(1) The Commission, in providing any aid, benefit, or service, may not, directly or through contractual, licensing, or other arrangements, on the basis of handicap—

(i) Deny a qualified individual with handicaps the opportunity to participate in or benefit from the aid, benefit, or service;

(ii) Afford a qualified individual with handicaps an opportunity to participate in or benefit from the aid, benefit, or service that is not equal to that afforded others;

(iii) Provide a qualified individual with handicaps with an aid, benefit, or service that is not as effective in affording equal opportunity to obtain the same result, to gain the same benefit, or to reach the same level of achievement as that provided to others;

47 CFR Ch. I (10–1–97 Edition)

(iv) Provide different or separate aid, benefits, or services to individuals with handicaps or to any class of individuals with handicaps than is provided to others unless such action is necessary to provide qualified individuals with handicaps with aid, benefits, or services that are as effective as those provided to others;

(v) Deny a qualified individual with handicaps the opportunity to participate as a member of planning or advisory boards; or

(vi) Otherwise limit a qualified individual with handicaps in the enjoyment of any right, privilege, advantage, or opportunity enjoyed by others receiving the aid, benefit, or service.

(2) The Commission may not deny a qualified individual with handicaps the opportunity to participate in programs or activities that are not separate or different, despite the existence of permissibly separate or different programs or activities.

(3) The Commission may not, directly or through contractual or other arrangements, utilize criteria or methods of administration the purpose or effect of which would—

(i) Subject qualified individuals with handicaps to discrimination on the basis of handicap; or

(ii) Defeat or substantially impair accomplishment of the objectives of a program or activity with respect to individuals with handicaps.

(4) The Commission may not, in determining the site or location of a facility, make selections the purpose or effect of which would—

(i) Exclude individuals with handicaps from, deny them the benefits of, or otherwise subject them to discrimination under any program or activity conducted by the Commission; or

(ii) Defeat or substantially impair the accomplishment of the objectives of a program or activity with respect to individuals with handicaps.

(5) The Commission, in the selection of procurement contractors, may not use criteria that subject qualified individuals with handicaps to discrimination on the basis of handicap.

Federal Communications Commission

§ 1.1850

(6) The Commission may not administer a licensing or certification program in a manner that subjects qualified individuals with handicaps to discrimination on the basis of handicap, nor may the Commission establish requirements for the programs or activities of licensees or certified entities that subject qualified individuals with handicaps to discrimination on the basis of handicap. However, the programs or activities of entities that are licensed or certified by the Commission are not, themselves, covered by this part.

(c) The exclusion of nonhandicapped persons from the benefits of a program limited by Federal statute or Executive order to individuals with handicaps or the exclusion of a specific class of individuals with handicaps from a program limited by Federal statute or Executive order to a different class of individuals with handicaps is not prohibited by this part.

(d) The Commission shall administer programs and activities in the most integrated setting appropriate to the needs of qualified individuals with handicaps.

§§ 1.1831–1.1839 [Reserved]

§ 1.1840 Employment.

No qualified individual with handicaps shall, on the basis of handicap, be subjected to discrimination in employment under any program or activity conducted by the Commission. The definitions, requirements and procedures of section 501 of the Rehabilitation Act of 1973, 29 U.S.C. 791, as established by the Equal Employment Opportunity Commission in 29 CFR part 1613, as well as the procedures set forth in the Basic Negotiations Agreement Between the Federal Communications Commission and National Treasury Employees Union (effective June 22, 1982) and Subchapter III of the Civil Service Reform Act of 1978, 5 U.S.C. 7121(d), shall apply to employment in federally conducted programs or activities.

§§ 1.1841–1.1848 [Reserved]

§ 1.1849 Program accessibility: Discrimination prohibited.

Except as otherwise provided in § 1.1850, no qualified individual with handicaps shall, because the Commission's facilities are inaccessible to or unusable by individuals with handicaps, be denied the benefits of, be excluded from participation in, or otherwise be subjected to discrimination under any program or activity conducted by the Commission.

§ 1.1850 Program accessibility: Existing facilities.

(a) *General.* The Commission shall operate each program or activity so that the program or activity, when viewed in its entirety, is readily accessible to and usable by individuals with handicaps. This paragraph does not—

(1) Necessarily require the Commission to make each of its existing facilities accessible to and usable by individuals with handicaps;

(2) Require the Commission to take any action that it can demonstrate would result in a fundamental alteration in the nature of a program or activity or in undue financial and administrative burdens. In those circumstances where Commission personnel believe that the proposed action would fundamentally alter the program or activity or would result in undue financial and administrative burdens, the Commission has the burden of proving that compliance with § 1.1850(a) would result in such alteration or burdens. The decision that compliance would result in such alteration or burdens must be made by the Managing Director after considering all Commission resources available for use in the funding and operation of the conducted program or activity, and must be accompanied by a written statement of the reasons for reaching that conclusion. If an action would result in such an alteration or such burdens, the Commission shall take any other action that would not result in such an alteration or such burdens but would nevertheless ensure that individuals

§ 1.1851

with handicaps receive the benefits and services of the program or activity.

(b) *Methods.* The Commission may comply with the requirements of this section through such means as redesign of equipment, reassignment of services to accessible buildings, assignment of aides to beneficiaries, home visits, delivery of services at alternate accessible sites, alteration of existing facilities and construction of new facilities, use of accessible rolling stock, or any other methods that result in making its programs or activities readily accessible to and usable by individuals with handicaps. The Commission is not required to make structural changes in existing facilities where other methods are effective in achieving compliance with this section. The Commission, in making alterations to existing buildings, shall meet accessibility requirements to the extent compelled by the Architectural Barriers Act of 1968, as amended (42 U.S.C. 4151—4157), and any regulations implementing it. In choosing among available methods for meeting the requirements of this section, the Commission shall give priority to those methods that offer programs and activities to qualified individuals with handicaps in the most integrated setting appropriate.

(c) *Time period for compliance.* The Commission shall comply with the obligations established under this section within sixty (60) days of the effective date of this part except that where structural changes in facilities are undertaken, such changes shall be made within three (3) years of the effective date of this part, but in any event as expeditiously as possible.

(d) *Transition plan.* In the event that structural changes to facilities will be undertaken to achieve program accessibility, the Commission shall develop, within six (6) months of the effective date of this part, a transition plan setting forth the steps necessary to complete such changes. The Commission shall provide an opportunity to interested persons, including individuals with handicaps or organizations representing individuals with handicaps, to participate in the development of the transition plan by submitting comments (both oral and written). A copy of the transition plan shall be made

47 CFR Ch. I (10–1–97 Edition)

available for public inspection. The plan shall, at a minimum—

(1) Identify physical obstacles in the Commission's facilities that limit the accessibility of its programs or activities to individuals with handicaps;

(2) Describe in detail the methods that will be used to make the facilities accessible;

(3) Specify the schedule for taking the steps necessary to achieve compliance with this section and, if the time period of the transition plan is longer than one (1) year, identify steps that will be taken during each year of the transition period;

(4) Indicate the official responsible for implementation of the plan.

§ 1.1851 Program accessibility: New construction and alterations.

Each building or part of a building that is constructed or altered by, on behalf of, or for the use of the Commission shall be designed, constructed, or altered so as to be readily accessible to and usable by individuals with handicaps. The definitions, requirements and standards of the Architectural Barriers Act, 42 U.S.C. 4151—4157, as established in 41 CFR 101–19.600 to 101–19.607, apply to buildings covered by this section.

§§ 1.1852–1.1859 [Reserved]

§ 1.1860 Communications.

(a) The Commission shall take appropriate steps to ensure effective communication with applicants, participants, personnel of other Federal entities, and members of the public.

(1) The Commission shall furnish appropriate auxiliary aids where necessary to afford an individual with handicaps an equal opportunity to participate in, and enjoy the benefits of, a program or activity conducted by the Commission.

(i) In determining what type of auxiliary aid is necessary, the Commission shall give primary consideration to the requests of the individual with handicaps.

(ii) The Commission need not provide individually prescribed devices, readers for personal use or study, or other devices, of a personal nature.

Federal Communications Commission

§1.1870

(2) Where the Commission communicates with applicants and beneficiaries by telephone, telecommunications devices for deaf persons (TDD's) or equally effective telecommunications systems shall be used.

(b) The Commission shall ensure that interested persons, including persons with impaired vision or hearing, can obtain information as to the existence and location of accessible services, activities, and facilities.

(c) The Commission shall provide signage at a primary entrance to each of its inaccessible facilities, directing users to a location at which they can obtain information about accessible facilities. The international symbol for accessibility shall be used at each primary entrance of an accessible facility.

(d) This section does not require the Commission to take any action that it can demonstrate would result in a fundamental alteration in the nature of a program or activity or in undue financial and administrative burdens. In those circumstances where Commission personnel believe that the proposed action would fundamentally alter the program or activity or would result in undue financial and administrative burdens, the Commission has the burden of proving that compliance with §1.1860 would result in such alteration or burdens. The decision that compliance would result in such alteration or burdens must be made by the Managing Director after considering all Commission resources available for use in the funding and operation of the conducted program or activity, and must be accompanied by a written statement of the reasons for reaching that conclusion. If an action required to comply with this section would result in such an alteration or such burdens, the Commission shall take any other action that would not result in such an alteration or such burdens but would nevertheless ensure that, to the maximum extent possible, individuals with handicaps receive the benefits and services of the program or activity.

§§1.1861–1.1869 [Reserved]

§1.1870 Compliance procedures.

(a) Except as provided in paragraph (b) of this section, this section applies

to all allegations of discrimination on the basis of handicap in programs or activities conducted by the Commission.

(b) The Commission shall process complaints alleging violations of section 504 with respect to employment according to the procedures established by the Equal Employment Opportunity Commission in 29 CFR part 1613 pursuant to section 501 of the Rehabilitation Act of 1973, 29 U.S.C. 791.

(c) The Managing Director shall be responsible for coordinating implementation of this section. Complaints may be sent to the Handicapped Coordinator, Office of Managing Director, Federal Communications Commission, 1919 M Street NW., Room 852, Washington, DC 20554.

(d) *Acceptance of complaint.* (1) The Commission shall accept and investigate all complete complaints for which it has jurisdiction. All complete complaints must be filed within one-hundred eighty (180) days of the alleged act of discrimination. The Commission may extend this time period for good cause.

(2) If the Commission receives a complaint that is not complete, the complainant will be notified within thirty (30) days of receipt of the incomplete complaint that additional information is needed. If the complainant fails to complete the complaint within thirty (30) days of receipt of this notice, the Commission shall dismiss the complaint without prejudice.

(e) If the Commission receives a complaint over which it does not have jurisdiction, it shall promptly notify the complainant and shall make reasonable efforts to refer the complaint to the appropriate government entity.

(f) The Commission shall notify the Architectural and Transportation Barriers Compliance Board upon receipt of any complaint alleging that a building or facility that is subject to the Architectural Barriers Act of 1968, as amended, 42 U.S.C. 4151–4157, is not readily accessible to and usable by individuals with handicaps.

(g) Within one-hundred eighty (180) days of the receipt of a complete complaint for which it has jurisdiction, the

Commission shall notify the complainant of the results of the investigation in a letter containing—

(1) Findings of fact and conclusions of law;

(2) A description of a remedy for each violation found; and

(3) A notice of the right to appeal.

(h) Appeals of the findings of fact and conclusions of law or remedies must be filed by the complainant within ninety (90) days of receipt from the Commission of the letter required by § 1.1870(g). The Commission may extend this time for good cause.

(i) Timely appeals shall be accepted and processed by the Office of the Secretary, Federal Communications Commission, 1919 M Street NW., Room 202, Washington, DC 20554.

(j) The Commission shall notify the complainant of the results of the appeal within sixty (60) days of the receipt of the request. If the Commission determines that it needs additional information from the complainant, it shall have sixty (60) days from the date it receives the additional information to make its determination on the appeal.

(k) The time limits cited in paragraphs (g) and (j) of this section may be extended with the permission of the Assistant Attorney General.

(l) The Commission may delegate its authority for conducting complaint investigations to other Federal agencies, except that the authority for making the final determination may not be delegated to another agency.

§§ 1.1871–1.1899 [Reserved]

Subpart O—Collection of Claims Owed the United States

AUTHORITY: 31 U.S.C. 3701; 31 U.S.C. 3711 *et seq.*; 5 U.S.C. 5514; 4 CFR parts 101–105; 5 CFR part 550.

SOURCE: 54 FR 403, Jan. 6, 1989, unless otherwise noted.

GENERAL PROVISIONS

§ 1.1901 Definitions.

(a) The term *administrative offset* means withholding money payable by the United States Government to, or held by the Government for, a person

to satisfy a debt the person owes the Government.

(b) The term *agency* means the Federal Communications Commission (Commission) or any other agency of the U.S. Government as defined by section 105 of title 5 U.S.C., the U.S. Postal Service, the U.S. Postal Rate Commission, a military department as defined by section 102 of title 5 U.S.C., an agency or court of the judicial branch, or and an agency of the legislative branch, including the U.S. Senate and the U.S. House of Representatives.

(c) The term *agency head* means the Chairman of the Federal Communications Commission.

(d) The terms *appropriate agency official* or *designee* means the Managing Director of the Commission or such other official as may be named by the Managing Director.

(e) The terms *claim* and *debt* are deemed synonymous and interchangeable. They refer to an amount of money or property which has been determined by an appropriate agency official to be owed to the United States from any person, organization, or entity, except another federal agency. They include amounts owing to the United States on account of loans insured or guaranteed by the United States and all other amounts due the United States from fees, leases, rents, royalties, services, sales of real or personal property, overpayments, fines, penalties, damages, interest, taxes, and forfeitures (except those arising under the Uniform Code of Military Justice), and other similar sources.

(f) The term *creditor agency* means the agency to which the debt is owed.

(g) The term *delinquent* means a claim or debt which has not been paid by the date specified in the agency's written notification or applicable contractual agreement, unless other satisfactory payment arrangements have been made by that date, or, at any time thereafter, the debtor has failed to satisfy an obligation under a payment agreement with the agency.

(h) The term *disposable pay* means that part of current basic pay, special pay, incentive pay, retired pay, retainer pay, or in the case of an employee not entitled to basic pay, other

Federal Communications Commission

§1.1904

authorized pay remaining after the deduction of any amount required by law to be withheld. Agencies must exclude deductions described in 5 CFR 581.105 (b) through (f) to determine disposable pay subject to salary offset.

(i) The term *employee* means a current employee of the Commission or of another agency, including a current member of the Armed Forces or a Reserve of the Armed Forces (Reserve).

(j) The term *FCCS* means the Federal Claims Collection Standards jointly published by the Justice Department and the General Accounting Office at 4 CFR parts 101–105.

(k) The term *paying agency* means the agency employing the individual and authorizing the payment of his or her current pay.

(l) The term *referral for litigation* means referral to the Department of Justice for appropriate legal proceedings except where the Commission has the statutory authority to handle the litigation itself.

(m) The term *salary offset* means an administrative offset to collect a debt under 5 U.S.C. 5514 by deduction(s) at one or more officially established pay intervals from the current pay account of an employee without his or her consent.

(n) The term *waiver* means the cancellation, remission, forgiveness, or non-recovery of a debt allegedly owed by an employee to an agency as permitted or required by 5 U.S.C. 5584, 10 U.S.C. 2774, or 32 U.S.C. 710, 5 U.S.C. 8346(b), or any other law.

§1.1902 Exceptions.

(a) Claims arising from the audit of transportation accounts pursuant to 31 U.S.C. 3726 shall be determined, collected, compromised, terminated or settled in accordance with regulations published under the authority of 31 U.S.C. 3726 (see 41 CFR part 101–41).

(b) Claims arising out of acquisition contracts subject to the Federal Acquisition Regulations (FAR) shall be determined, collected, compromised, terminated, or settled in accordance with those regulations. (See 48 CFR part 32). If not otherwise provided for in the FAR system, contract claims that have been the subject of a contracting officer's final decision in accordance with

section 6(a) of the Contract Disputes Act of 1978 (41 U.S.C. 605(a)), may be determined, collected, compromised, terminated or settled under the provisions of this regulation, except that no additional review of the debt shall be granted beyond that provided by the contracting officer in accordance with the provisions of section 6 of the Contract Disputes Act of 1978 (41 U.S.C. 605), and the amount of any interest, administrative charge, or penalty charge shall be subject to the limitations, if any, contained in the contract out of which the claim arose.

(c) Claims based in whole or in part on conduct in violation of the antitrust laws, or in regard to which there is an indication of fraud, the presentation of a false claim, or a misrepresentation on the part of the debtor or any other party having an interest in the claim, shall be referred to the Department of Justice (DOJ) as only the DOJ has authority to compromise, suspend, or terminate collection action on such claims.

(d) Tax claims are also excluded from the coverage of this regulation.

§1.1903 Use of procedures.

Procedures authorized by this regulation (including, but not limited to, disclosure to a consumer reporting agency, contracting for collection services, administrative offset and salary offset) may be used singly or in combination, so long as the requirements of applicable law and regulation are satisfied.

§1.1904 Conformance to law and regulations.

The requirements of applicable law (31 U.S.C. 3701–3719, as amended by Pub. L. 97–365, 96 Stat. 1749) have been implemented in government wide standards:

(a) The Regulations of the Office of Personnel Management (5 CFR part 550) and

(b) The Federal Claims Collection Standards issued jointly by the General Accounting Office and the Department of Justice (4 CFR parts 101–105).

Not every item in the above described standards has been incorporated or referenced in this regulation. To the extent, however, that circumstances arise which are not covered by the

§ 1.1905

47 CFR Ch. I (10–1–97 Edition)

terms stated in these regulations, the Commission will proceed in any actions taken in accordance with applicable requirements found in the standards referred to in this section.

§ 1.1905 Other procedures; collection of forfeiture penalties.

Nothing contained in these regulations is intended to require the Commission to duplicate administrative or other proceedings required by contract or other laws or regulations, nor do these regulations supercede procedures required by other statutes or regulations. In particular, the assessment and collection of monetary forfeiture penalties imposed by the Commission will be governed initially by the procedures prescribed by 47 U.S.C. 503, 504 and 47 CFR 1.80. After compliance with those procedures, the Commission may determine that the collection of a monetary forfeiture under the collection alternatives prescribed by this subpart is appropriate but need not duplicate administrative or other proceedings.

§ 1.1906 Informal action.

Nothing contained in these regulations is intended to preclude utilization of informal administrative actions or remedies which may be available.

§ 1.1907 Return of property.

Nothing contained in this regulation is intended to deter the Commission from demanding the return of specific property or from demanding, in the alternative, either the return of property or the payment of its value.

§ 1.1908 Omissions not a defense.

The failure of the Commission to comply with any provision in this regulation shall not serve as a defense to the debt.

ADMINISTRATIVE OFFSET—CONSUMER
REPORTING AGENCIES—CONTRACTING
FOR COLLECTION

§ 1.1911 Demand for payment.

(a) Written demands for payment shall be made promptly upon a debtor in terms which inform the debtor of the consequences of failure to cooperate. A total of three progressively stronger written demands at not more

than 30-day intervals will normally be made unless a response to the first or second demand indicates that a further demand would be futile and the debtor's response does not require rebuttal. In determining the timing of demand letters, the Commission will give due regard to the need to act promptly so that, as a general rule, if it becomes necessary to refer the debt to the Department of Justice for litigation, such referral can be made within one year of the agency's final determination of the fact and the amount of the debt. When necessary to protect the Government's interest (for example, to prevent the statute of limitations, 28 U.S.C. 2415, from expiring), written demand may be preceded by other appropriate actions under this chapter, including immediate referral for litigation.

(b) The initial demand letter will inform the debtor of:

(1) The basis for the indebtedness and the right of the debtor to request review within the agency;

(2) The applicable standards for assessing interest, penalties, and administrative costs (§§ 1.1940 and 1.1941 of this subpart) and;

(3) The date by which payment is to be made, which normally should not be more than 30 days from the date that the initial demand letter was mailed or hand-delivered.

(c) As appropriate to the circumstances, the Commission may include either in the initial demand letter or in subsequent letters, matters relating to alternative methods of payment, policies with respect to use of consumer reporting agencies and collection services, the agency's intentions with respect to referral of the debt to the Department of Justice for litigation, and, depending on applicable statutory authority, the debtor's entitlement to consideration of waiver.

(d) The Commission will respond promptly to communications from the debtor, within 30 days whenever feasible, and will advise debtors who dispute the debt that they must furnish available evidence to support their contentions.

(e) If, either prior to the initiation of, at any time during, or after completion of the demand cycle, the Commission

Federal Communications Commission

§ 1.1912

determines to pursue administrative offset, then the procedures specified in §§ 1.1912 and 1.1913 as applicable, will be followed. The availability of funds for offset and the agency's determination to pursue that remedy, release the agency from the necessity of further compliance with paragraphs (a), (b) and (c) of this section. If the agency has not already sent the first demand letter, the agency's written notification of its intent to offset must give the debtor the opportunity to make voluntary payment, a requirement which will be satisfied by compliance with the notice requirements of §§ 1.1912 and 1.1913 as applicable.

§ 1.1912 Collection by administrative offset.

(a) Collection by administrative offset will be undertaken in accordance with these regulations on all claims which are liquidated or certain in amount, in every instance in which such collection is determined to be feasible and not otherwise prohibited.

(1) Whether collection by administrative offset is feasible is a determination to be made by the agency on a case-by-case basis, in the exercise of sound discretion. The Commission will consider not only whether administrative offset can be accomplished practically, but also whether offset is best suited to further and protect all of the Government's interest. In appropriate circumstances, the Commission may give due consideration to the debtor's financial condition and is not required to use offset in every instance in which there is an available source of funds. The Commission may also consider whether offset would tend to substantially interfere with or defeat the purposes of the program authorizing the payments against which offset is contemplated. For example, under a grant program in which payments are made in advance of the grantee's performance, offset will normally be inappropriate. This concept generally does not apply, however, where payment is in the form of reimbursement.

(2) [Reserved]

(b) Before the offset is made, a debtor shall be provided with the following: Written notice of the nature and amount of the debt, and the agency's

intention to collect by offset; opportunity to inspect and copy agency records pertaining to the debt; opportunity to obtain review within the agency of the determination of indebtedness; and opportunity to enter into a written agreement with the agency to repay the debt.

(1) The Commission will exercise sound judgment in determining whether to accept a repayment agreement in lieu of offset. The determination will weigh the Government's interest in collecting the debt against fairness to the debtor. If the debt is delinquent and the debtor has not disputed its existence or amount, the Commission will normally accept a repayment agreement in lieu of offset only if the debtor is able to establish that offset would result in undue financial hardship or would be against equity and good conscience.

(2) In cases where the procedural requirements specified in paragraph (b) of this section have previously been provided to the debtor in connection with the same debt under some other statutory or regulatory authority, such as pursuant to a notice of audit disallowance or pursuant to 47 U.S.C. 503, 504 and 47 CFR 1.80, the agency is not required to duplicate those requirements before taking administrative offset.

(3) The Commission may not initiate administrative offset to collect a debt under 31 U.S.C. 3716 more than 10 years after the Government's right to collect the debt first accrued, unless facts material to the Government's right to collect the debt were not known and could not reasonably have been known by the official or officials of the Government who were charged with the responsibility to discover and collect such debts. When the debt first accrued is to be determined according to existing law regarding the accrual of debts, such as under 28 U.S.C. 2415.

(4) The Commission is not authorized by 31 U.S.C. 3716 to use administrative offset with respect to:

(i) Debts owed by any State or local Government;

(ii) Debts arising under or payments made under the Social Security Act, the Internal Revenue Code of 1954, or the tariff laws of the United States; or

(iii) Any case in which collection of the claim or type of claim by administrative offset is explicitly provided for or prohibited by another statute.

(5) The Commission may effect administrative offset against a payment to be made to a debtor prior to completion of the procedures required by paragraph (b) of this section if:

- (i) Failure to take the offset would substantially prejudice the Government's ability to collect the debt, and
- (ii) The time before the payment is to be made does not reasonably permit the completion of those procedures.

Such prior offset must be promptly followed by the completion of those procedures. Amounts recovered by offset but later found not to be owed to the Government shall be promptly refunded.

(6) The Commission will obtain credit reports on delinquent accounts to identify opportunities for administrative offset of amounts due to a delinquent debtor when other collection techniques have been unsuccessful.

(c) Type of hearing or review. (1) For purposes of this section, whenever the Commission is required to provide a hearing or review within the agency, it shall provide the debtor with a reasonable opportunity for an oral hearing when:

(i) Any applicable statute authorizes or requires the agency to consider waiver of the indebtedness involved, the debtor requests waiver of the indebtedness, and the waiver determination turns on an issue of credibility or veracity; or

(ii) The debtor requests reconsideration of the debt and the agency determines that the question of the indebtedness cannot be resolved by review of the documentary evidence; for example, when the validity of the debt turns on an issue of credibility or veracity.

Unless otherwise required by law, an oral hearing under this section is not required to be a formal evidentiary-type hearing, although the Commission will carefully document all significant matters discussed at the hearing.

(2) The section does not require an oral hearing with respect to debt collection systems in which determinations of indebtedness or waiver rarely involve issues of credibility or veracity

and the agency has determined that review of the written record is ordinarily an adequate means to correct prior mistakes. In administering such a system, the agency is not required to sift through all of the requests received in order to accord oral hearings in those few cases which may involve issues of credibility or veracity.

(3) In those cases where an oral hearing is not required by this section, the agency will make its determination on the request for waiver or reconsideration based upon a "paper hearing," that is, a review of the written record.

(d) Appropriate use will be made of the cooperative efforts of other agencies in affecting collection by administrative offset. Generally, the Commission will not refuse to comply with requests from other agencies to initiate administrative offset to collect debts owed to the United States unless the requesting agency has not complied with the applicable provisions of these standards or the offset otherwise contrary to law.

(e) Collection by offset against a judgment obtained by a debtor against the United States shall be accomplished in accordance with 31 U.S.C. 3728.

(f) Whenever the creditor agency is not the agency which is responsible for making the payment against which administrative offset is sought, the latter agency shall not initiate the requested offset until it has been provided by the creditor agency with an appropriate written certification that the debtor owes a debt (including the amount) and full compliance with the provisions of this section has taken place.

(g) When collecting multiple debts by administrative offset, the Commission will apply the recovered amounts to those debts in accordance with the best interest of the United States, as determined by the facts and circumstances of the particular case, paying special attention to applicable statutes of limitation.

§ 1.1913 Administrative offset against amounts payable from Civil Service Retirement and Disability Fund.

(a) Unless otherwise prohibited by law, the Commission may request that moneys which are due and payable to a

Federal Communications Commission

§ 1.1914

debtor from the Civil Service Retirement and Disability Fund be administratively offset in reasonable amounts in order to collect in one full payment, or a minimal number of payments, debts owned to the United States by the debtor. Such requests shall be made to the appropriate officials of the Office of Personnel Management in accordance with such regulations as may be prescribed by the Director of that Office.

(b) When making a request for administrative offset under paragraph (a) of this section, the Commission shall include written certification that:

(1) The debtor owes the United States a debt, including the amount of the debt;

(2) The Commission has complied with the applicable statutes, regulations and procedures of the Office of Personnel Management; and

(3) The Commission has complied with the requirements of § 1.1912 of this subpart, including any required hearing or review.

(c) Once the Commission decides to request administrative offset under paragraph (a) of this section, it will make the request as soon as practical after completion of the applicable procedures in order that the Office of Personnel Management may identify and “flag” the debtor’s account in anticipation of the time when the debtor requests or becomes eligible to receive payments from the Fund. This will satisfy any requirement that offset be initiated prior to expiration of the applicable statute of limitations. At such time as the debtor makes a claim for payments from the Fund, if at least a year has elapsed since the offset request was originally made, the debtor should be permitted to offer a satisfactory payment plan in lieu of offset upon establishing that changed financial circumstances would render the offset unjust.

(d) If the Commission collects part or all of the debt by other means before deductions are made or completed pursuant to paragraph (a) of this section, it shall act promptly to modify or terminate its request for offset under paragraph (a) of this section.

(e) This section does not require or authorize the Office of Personnel Man-

agement to review the merits of the Commission’s determination with respect to the amount and validity of the debt, its determination as to waiver under an applicable statute, or its determination to provide or not provide an oral hearing.

§ 1.1914 Collection in installments.

(a) Whenever feasible, and except as otherwise provided by law, debts owed to the United States, together with interest, penalties, and administrative costs as required by this subpart should be collected in full in one lump sum. This is true whether the debt is being collected by administrative offset or by another method, including voluntary payment. However, if the debtor is financially unable to pay the indebtedness in one lump sum, payment may be accepted in regular installments. The Commission will obtain financial statements from debtors who represent that they are unable to pay the debt in one lump sum. If the Commission agrees to accept payment in regular installments, it will obtain a legally enforceable written agreement from the debtor which specifies all of the terms of the agreement and which contains a provision accelerating the debt in the event the debtor defaults. The size and frequency of installment payments should bear a reasonable relation to the size of the debtor and debtor’s ability to pay. If possible, the installment payments should be of sufficient size and frequency to liquidate the Government’s claim in not more than 3 years. Installment payments of less than \$50 per month will be accepted only if justifiable on the grounds of financial hardship or for some other reasonable cause.

(b) If the debtor owes more than one debt and designates how a voluntary installment is to be applied among those debts, that designation must be followed. If the debtor does not designate the application of the payment, the Commission will apply payments to various debts in accordance with the best interests of the United States, as determined by the facts and circumstances of the particular case, paying special attention to applicable statutes of limitations.

§ 1.1915

§ 1.1915 Exploration of compromise.

The Commission may attempt to effect compromise, preferably during the course of personal interviews, in accordance with the standards set forth in Part 103 of the Federal Claims Collection Standards (4 CFR part 103).

§ 1.1916 Suspending or terminating collection action.

The suspension or termination of collection action shall be made in accordance with the standards set forth in Part 104 of the Federal Claims Collection Standards (4 CFR part 104).

§ 1.1917 Referrals to the Department of Justice or the General Accounting Office.

Referrals to the Department of Justice or the General Accounting Office shall be made in accordance with the standards set forth in Part 105 of the Federal Claims Collection Standards (4 CFR part 105).

§ 1.1918 Use of consumer reporting agencies.

(a) The term *individual* means a natural person, and the term *consumer reporting agency* has the meaning provided in the Federal Claims Collection Act, as amended, at 31 U.S.C. 3701(a)(3) or the Fair Credit Reporting Act, at 15 U.S.C. 168a(f).

(b) The Commission may disclose to a consumer reporting agency, from a system of records, information that an individual is responsible for a claim if—

(1) Notice required by section 5 U.S.C. 552a(e)(4) indicates that information in the system may be disclosed to a consumer reporting agency;

(2) The claim has been reviewed and it is decided that the claim is valid and overdue;

(3) The Commission has notified the individual in writing—

(i) That payment of the claim is overdue;

(ii) That, within not less than 60 days after sending the notice, the Commission intends to disclose to a consumer reporting agency that the individual is responsible for that claim;

(iii) Of the specific information to be disclosed to the consumer reporting agency; and

47 CFR Ch. I (10–1–97 Edition)

(iv) Of the rights the individual has to a complete explanation of the claim, to dispute information in the records of the agency about the claim, and to administrative appeal or review of the claim; and

(4) The individual has not—

(i) Repaid or agreed to repay the claim under a written repayment plan that the individual has signed and the agency has agreed to; or

(ii) Filed for review of the claim under paragraph (g) of this section;

(c) The Commission shall—

(1) Disclose promptly, to each consumer reporting agency to which the original disclosure was made, a substantial change in the condition or amount of the claim;

(2) Verify or correct promptly information about the claim, on request of a consumer reporting agency for verification of any or all information so disclosed; and

(3) Obtain satisfactory assurances from each consumer reporting agency that they are complying with all laws of the United States relating to providing consumer credit information.

(d) The Commission shall ensure that information disclosed to the consumer reporting agency is limited to—

(1) Information necessary to establish the identity of the individual, including name, address, and taxpayer identification number;

(2) The amount, status, and history of the claim; and

(3) The agency or program under which the claim arose.

(e) All accounts in excess of \$100 that have been delinquent more than 31 days will normally be referred to a consumer reporting agency.

(f) Before disclosing information to a consumer reporting agency, the Commission shall take reasonable action to locate an individual for whom the head of the agency does not have a current address to send the notice.

(g) Before disclosing information to a consumer reporting agency, the Commission shall provide, on request of an individual alleged by the agency to be responsible for the claim, for a review of the obligation of the individual, including an opportunity for reconsideration of the initial decision on the claim.

Federal Communications Commission

§ 1.1926

(h) Under the same provisions as described above, the Commission may disclose to a credit reporting agency, information relating to a debtor other than a natural person. Such commercial debt accounts are not covered by the Privacy Act.

§ 1.1919 Contracting for collection services.

(a) The Commission has authority to contract for collection services to recover delinquent debts, provided that the following conditions are satisfied:

(1) The authority to resolve disputes, compromise claims, suspend or terminate collection action, and refer the matter for litigation is retained by the agency;

(2) The contractor shall be subject to the Privacy Act of 1974, as amended, to the extent specified in 5 U.S.C. 552a(m), and to applicable Federal and State laws and regulations pertaining to debt collection practices, such as the Fair Debt Collection Practices Act, 15 U.S.C. 1692;

(3) The contractor must be required to account strictly for all amounts collected;

(4) The contractor must agree that uncollectible accounts shall be returned with appropriate documentation to enable the Commission to determine whether to pursue collection through litigation or to terminate collection efforts; and

(5) The contractor must agree to provide any data contained in its files relating to paragraphs (a) (1), (2), and (3) of § 105.2 of the Federal Claims Collection Standards (4 CFR part 105) upon returning an account to the Commission for subsequent referral to the Department of Justice for litigation.

(b) Funding of collection service contracts. (1) The Commission may fund a collection service contract on a fixed-fee basis, that is, payment of a fixed fee determined without regard to the amount actually collected under the contract. Payment of the fee under this type of contract must be charged to available agency appropriations.

(2) The Commission may also fund a collection service contract on a contingent-fee basis, that is, by including a provision in the contract permitting the contractor to deduct its fee from

amounts collected under the contract. The fee should be based on a percentage of the amount collected, consistent with prevailing commercial practice.

(3) The Commission may enter into a contract under paragraph (b)(1) of this section only if and to the extent provided in advance appropriation acts or other legislation, except that this requirement does not apply to the use of a revolving fund authorized by statute.

(4) Except as authorized under paragraph (b)(2) of this section, or unless the receipt qualifies as a refund to the appropriation, or unless otherwise specifically provided by law, the Commission must deposit all amounts recovered under collection service contracts (or by agency employees on behalf of the agency) in the Treasury as miscellaneous receipts pursuant to 31 U.S.C. 3302.

(c) The Commission will consider the use of collection agencies at any time after the account is 61 days past due. In any case where an account is six months or more past due, the Commission may turn it over to a collection agency unless referred for litigation or unless arrangements have been made for a workout procedure or the Commission has exercised its authority to write off the debt pursuant to § 1.1916.

(d) The Commission will generally not use a collection agency to collect a delinquent debt owed by a currently employed or retired Federal employee, if collection by salary or annuity offset is available.

SALARY OFFSET

§ 1.1925 Purpose.

This section provides the standards to be followed by FCC in implementing 5 U.S.C. 5514 to recover a debt from the pay account of an FCC employee, and establishes procedural guidelines to recover debts when the employee's creditor and paying agencies are not the same.

§ 1.1926 Scope.

(a) *Coverage.* This section applies to agencies and employees as defined by § 1.1901.

(b) *Applicability.* This section and 5 U.S.C. 5514 apply in recovering certain

§ 1.1927

47 CFR Ch. I (10–1–97 Edition)

debts by offset, except where the employee consents to the recovery, from the current pay account of that employee. Because it is an administrative offset, debt collection procedures for salary offset which are not specified in 5 U.S.C. 5514 and these regulations should be consistent with the provisions of the Federal Claims Collection Standards (4 CFR parts 101–105).

(1) Excluded debts or claims. The procedures contained in this section do not apply to debts or claims arising under the Internal Revenue Code of 1954, as amended (26 U.S.C. 1 *et seq.*), the Social Security Act (42 U.S.C. 301 *et seq.*) or the tariff laws of the United States, or to any case where collection of a debt by salary offset is explicitly provided for or prohibited by another statute (e.g. travel advances in 5 U.S.C. 5705 and employee training expenses in 5 U.S.C. 4108).

(2) Waiver requests and claims to the General Accounting Office. This section does not preclude an employee from requesting waiver of a salary overpayment under 5 U.S.C. 5584, 10 U.S.C. 2774, or 32 U.S.C. 716, or in any way questioning the amount or validity of a debt by submitting a subsequent claim to the General Accounting Office in accordance with procedures prescribed by the General Accounting Office. Similarly, in the case of other types of debts, it does not preclude an employee from requesting waiver, if waiver is available under any statutory provision pertaining to the particular debt being collected.

(c) *Time Limit.* Under 4 CFR 102.3(b)(3) offset may not be initiated more than 10 years after the Government's right to collect the debt first accrued, unless an exception applies as stated in § 102.3(b)(3).

§ 1.1927 Notification.

(a) Salary offset deductions shall not be made unless the Managing Director of the Commission, or such other official as may be named in the future by the Managing Director of the Commission, provides the employee at least 30 days before any deduction written notice stating at a minimum:

(1) The agency's determination that a debt is owed, including the origin, nature, and amount of the debt;

(2) The agency's intention to collect the debt by means of deduction from the employee's current disposable pay account;

(3) The amount, frequency, proposed beginning date, and duration of the intended deductions;

(4) An explanation of the agency's policy concerning interest, penalties, and administrative costs (§§ 1.1940 and 1.1941 of this regulation), a statement that such assessments must be made unless excused in accordance with the FCCS;

(5) The employee's right to inspect and copy Government records relating to the debt or, if the employee or his or her representative cannot personally inspect the records, to request and receive a copy of such records.

(6) If not previously provided, the opportunity (under terms agreeable to the agency) to establish a schedule for the voluntary repayment of the debt or to enter into a written agreement to establish a schedule for repayment of the debt in lieu of offset. The agreement must be in writing, signed by both the employee and the Managing Director (or designee) of the Commission and documented in agency files (4 CFR 102.2(e)).

(7) The employee's right to a hearing conducted by an official arranged by the agency (an administrative law judge, or alternatively, a hearing official not under the control of the head of the agency) if a petition is filed as prescribed by this subpart.

(8) The method and time period for petitioning for a hearing;

(9) That the timely filing of a petition for hearing will stay the commencement of collection proceedings;

(10) That the final decision in the hearing (if one is requested) will be issued at the earliest practical date, but not later than 60 days after the filing of the petition requesting the hearing unless the employee requests and the hearing official grants a delay in the proceedings;

(11) That any knowingly false, misleading, or frivolous statements, representations, or evidence may subject the employee to:

(i) Disciplinary procedures appropriate under Chapter 75 of Title 5, United States Code, part 752 of title 5, Code

Federal Communications Commission

§1.1928

of Federal Regulations, or any other applicable statutes or regulations.

(ii) Penalties under the False Claims Act sections 3729–3731 of Title 31, United States Code, or any other applicable statutory authority; or

(iii) Criminal penalties under sections 286, 287, 1001, and 1002 of Title 18, United States Code, or any other applicable statutory authority.

(12) Any other rights and remedies available to the employee under statutes or regulations governing the program for which the collection is being made; and

(13) Unless there are applicable contractual or statutory provisions to the contrary, that amounts paid on or deducted for the debt which are later waived or found not owed to the United States will be promptly refunded to the employee.

(b) Notifications under this section shall be hand delivered with a record made of the date of delivery, or shall be mailed by certified mail return receipt requested.

(c) No notification, hearing, written responses or final decisions under this regulation are required by the Commission for any adjustment to pay arising out of an employee's election of coverage, or change in coverage, under a Federal benefit program requiring periodic deductions from pay, if the amount to be recovered was accumulated over four pay periods or less.

§1.1928 Hearing.

(a) *Petition for Hearing.* (1) A hearing may be requested by filing a written petition with the Managing Director of the Commission, or such other official as may be named by the Managing Director of the Commission, stating why the employee believes the determination of the agency concerning the existence or the amount of the debt is in error.

(2) The employee's petition must be signed by the employee and fully identify and explain with reasonable specificity all the facts, evidence and witnesses, if any, which the employee believes support his or her position.

(3) The petition must be filed no later than fifteen (15) calendar days from the date that the notification was hand de-

livered or the date of delivery by certified mail, return receipt requested.

(4) If a petition is received after the fifteenth (15) calendar day deadline referred to above, the Commission will nevertheless accept the petition if the employee can show that the delay was due to circumstances beyond his or her control, or because of failure to receive notice of the time limit (unless otherwise aware of it).

(5) If a petition is not filed within the time limit specified in paragraph (3) above, and is not accepted pursuant to paragraph (a)(4) of this section, the employee's right to hearing will be considered waived, and salary offset will be implemented by the Commission.

(b) *Type of Hearing.* (1) The form and content of the hearing will be determined by the hearing official who shall be a person outside the control or authority of the Commission except that nothing herein shall be construed to prohibit the appointment of an administrative law judge by the Commission. In determining the type of hearing, the hearing officer will consider the nature and complexity of the transaction giving rise to the debt. The hearing may be conducted as an informal conference or interview, in which the agency and employee will be given a full opportunity to present their respective positions, or as a more formal proceeding involving the presentation of evidence, arguments and written submissions.

(2) The employee may represent himself or herself, or may be represented by an attorney.

(3) The hearing official shall maintain a summary record of the hearing.

(4) The decision of the hearing officer shall be in writing, and shall state:

(i) The facts purported to evidence the nature and origin of the alleged debt;

(ii) The hearing official's analysis, findings, and conclusions, in the light of the hearing, as to—

(A) The employee's and/or agency's grounds,

(B) The amount and validity of the alleged debt, and,

(C) The repayment schedule, if applicable.

(5) The decision of the hearing official shall constitute the final administrative decision of the agency.

§ 1.1929

§ 1.1929 Deduction from pay.

(a) Deduction by salary offset, from an employee's current disposable pay, shall be subject to the following conditions:

(1) Ordinarily, debts to the United States should be collected in full, in one lump sum. This will be done when funds are available for payment in one lump sum, or, if the amount of the debt exceeds 15 percent of disposable pay for an officially established pay interval, collection will normally be made in installments.

(2) The installments shall not exceed 15 percent of the disposable pay from which the deduction is made, unless the employee has agreed in writing to the deduction of a greater amount.

(3) Deduction will generally commence with the next full pay interval (ordinarily the next biweekly pay period) following the date: of the employee's written consent to salary offset, the waiver of hearing, or the decision issued by the hearing officer.

(4) Installment deductions must be made over a period not greater than the anticipated period of employment except as provided in § 1.1930.

(b) [Reserved]

§ 1.1930 Liquidation from final check or recovery from other payment.

(a) If the employee retires or resigns or if his or her employment or period of active duty ends before collection of the debt is completed, offset of the entire remaining balance of the debt may be made from a final payment of any nature, including, but not limited to, final salary payment or lump-sum leave due the employee as the date of separation, to such extent as is necessary to liquidate the debt.

(b) If the debt cannot be liquidated by offset from a final payment, offset may be made from later payments of any kind due from the United States, including, but not limited to, the Civil Service Retirement and Disability Fund, pursuant to § 1.1913 of this regulation.

§ 1.1931 Non-waiver of rights by payments.

An employee's involuntary payment of all or any portion of a debt being collected under 5 U.S.C. 5514 shall not

47 CFR Ch. I (10–1–97 Edition)

be construed as a waiver of any rights which the employee may have under 5 U.S.C. 5514 or any other provision of contract or law, unless statutory or contractual provisions provide to the contrary.

§ 1.1932 Refunds.

(a) Refunds shall promptly be made when—

(1) A debt is waived or otherwise found not owing to the United States (unless expressly prohibited by statute or regulation); or

(2) The employee's paying agency is directed by an administrative or judicial order to refund amounts deducted from his or her current pay.

(b) Refunds do not bear interest unless required or permitted by law or contract.

§ 1.1933 Interest, penalties and administrative costs.

The assessment of interest, penalties and administrative costs shall be in accordance with §§ 1.1940 and 1.1941 of this regulation.

§ 1.1934 Recovery when paying agency is not creditor agency.

(a) *Responsibilities of creditor agency.* Upon completion of the procedures established under 5 U.S.C. 5514, the creditor agency must do the following:

(1) The creditor agency must certify, in writing, that the employee owes the debt, the amount and basis of the debt, the date on which payment(s) is due, the date of the Government's right to collect the debt first accrued, and that the creditor agency's regulations implementing 5 U.S.C. 5514 have been approved by OPM.

(2) If the collection must be made in installments, the creditor agency also must advise the paying agency of the number of installments to be collected, the amount of each installment, and the commencement date of the first installment (if a date other than the next officially established pay period is required).

(3) Unless the employee has consented to the salary offset in writing or signed a statement acknowledging receipt of the required procedures, and the written consent or statement is forwarded to the paying agency, the

Federal Communications Commission

§1.1935

creditor agency also must advise the paying agency of the action(s) taken under 5 U.S.C. 5514(b) and give the date(s) the action(s) was taken.

(4) Except as otherwise provided in this paragraph, the creditor agency must submit a debt claim containing the information specified in paragraphs (a) (1) through (3) of this section and an installment agreement (or other instruction on the payment schedule), if applicable to the employee's paying agency.

(5) If the employee is in the process of separating, the creditor agency must submit its claim to the employee's paying agency for collection pursuant to §1.1930. The paying agency must certify the total amount of its collection and provide copies to the creditor agency and the employee as stated in paragraph (c)(1) of this section. If the paying agency is aware that the employee is entitled to payments from the Civil Service Retirement and Disability Fund, or other similar payments, it must provide written notification to the agency responsible for making such payments that the debtor owes a debt (including the amount) and that there has been full compliance with the provisions of this section. However, the creditor agency must submit a properly certified claim to the agency responsible for making such payments before collection can be made.

(6) If the employee is already separated and all payments from his or her former paying agency have been paid, the creditor agency may request, unless otherwise prohibited, that money due and payable to the employee from the Civil Service Retirement and Disability Fund (5 CFR 831.1801 *et seq.*), or other similar funds, be administratively offset to collect the debt. (31 U.S.C. 3716 and 4 CFR 102.4)

(b) *Responsibilities of paying agency—*

(1) *Complete claim.* When the paying agency receives a properly certified debt claim from a creditor agency, deductions should be scheduled to begin prospectively at the next officials established pay interval. The employee must receive written notice that the paying agency has received a certified debt claim from the creditor agency (including the amount) and written notice of the date deductions from salary

will commence and of the amount of such deductions.

(2) *Incomplete claim.* When the paying agency receives an incomplete debt claim from a creditor agency, the paying agency must return the debt claim with a notice that procedures under 5 U.S.C. 5514 and this subpart must be provided, and a properly certified debt claim received, before action will be taken to collect from the employee's current pay account.

(3) *Review.* The paying agency is not required or authorized to review the merits of the creditor agency's determination with respect to the amount or validity of the debt certified by the creditor agency.

(c) *Employees who transfer from one paying agency to another.*

(1) If, after the creditor agency has submitted the debt claim to the employee's paying agency, the employee transfers to a position served by a different paying agency before the debt is collected in full, the paying agency from which the employee separates must certify the total amount of the collection made on the debt. One copy of the certification must be furnished to the employee, another to the creditor agency along with notice of employee's transfer. However, the creditor agency must submit a properly certified claim to the new paying agency before collection can be resumed.

(2) When an employee transfers to another paying agency, the creditor agency need not repeat the due process procedures described by 5 U.S.C. 5514 and this subpart to resume the collection. However, the creditor agency is responsible for reviewing the debt upon receiving the former paying agency's notice of the employee's transfer to make sure the collection is resumed by the new paying agency.

§1.1935 Obtaining the services of a hearing official.

(a) When the debtor does not work for the creditor agency and the creditor agency cannot provide a prompt and appropriate hearing before an administrative law judge or before a hearing official furnished pursuant to another lawful arrangement, the creditor agency may contact an agent of the paying agency designated in appendix

§ 1.1940

47 CFR Ch. I (10–1–97 Edition)

A of 5 CFR part 581 for a hearing official, and the paying agency must then cooperate as provided by 4 CFR 102.1 and provide a hearing official.

(b) When the debtor works for the creditor agency, the creditor agency may contact any agent (of another agency) designated in appendix A of 5 CFR part 581 to arrange for a hearing official. Agencies must then cooperate as required by 4 CFR 102.1 and provide a hearing official.

INTEREST, PENALTIES, ADMINISTRATIVE COSTS AND OTHER SANCTIONS

§ 1.1940 Assessment.

(a) Except as provided in paragraph (h) of this section, or § 1.1941, the Commission shall assess interest, penalties and administrative costs on debts owed to the United States pursuant to 31 U.S.C. 3717. Before assessing these charges, the Commission will mail or hand-deliver a written notice to the debtor explaining the agency's requirements concerning these charges.

(b) Interest shall accrue from the date on which notice of the debt and the interest requirements is first mailed or hand-delivered to the debtor, using the most current address that is available to the agency. If the Commission should use an "advance billing" procedure—that is, if it mails a bill before a debt is actually owed—it can include the required interest notification in the advance billing, but interest may not start to accrue before the debt is actually owed.

(c) The rate of interest assessed shall be the rate of the current value of funds to the United States Treasury (i.e., the Treasury Tax and loan account rate), as prescribed and published by the Secretary of the Treasury in the FEDERAL REGISTER and the Treasury Financial Manual Bulletins annually or quarterly, in accordance with 31 U.S.C. 3717. The Commission may assess a higher rate of interest if it reasonably determines that a higher rate is necessary to protect the interests of the United States. The rate of interest, as initially assessed, shall remain fixed for the duration of the indebtedness except that where a debtor has defaulted on a repayment agreement and seeks to enter into a new

agreement, the Commission may set a new interest rate which reflects the current value of funds to the Treasury at the time the new agreement is executed. Interest will not be assessed on accrued interest, penalties, or administrative costs required by this section. However, if the debtor defaults on a previous repayment agreement, charges which accrued but were not collected under the defaulted agreement shall be added to the principal to be paid under a new repayment schedule.

(d) The Commission shall assess against a debtor charges to cover administrative costs incurred as a result of a delinquent debt—that is, the additional costs incurred in processing and handling the debt because it became delinquent. Calculation of administrative costs shall be based upon actual costs incurred or upon costs analyses establishing an average of actual additional costs incurred by the agency in processing and handling claims against other debtors in similar stages of delinquency. Administrative costs may include costs incurred in obtaining a credit report or in using a private debt collector, to the extent they are attributable to the delinquency.

(e) The Commission shall assess a penalty charge, not to exceed 6 percent a year, on any portion of a debt that is delinquent for more than 90 days. This charge need not be calculated until the 91st day of delinquency, but shall accrue from the date that the debt became delinquent.

(f) When a debt is paid in partial or installment payments, amounts received by the agency shall be applied first to outstanding penalty and administrative cost charges, second to accrued interest, and third to the outstanding principal.

(g) The Commission will waive the collection of interest on the debt or any portion of the debt which is paid within 30 days after the date on which interest began to accrue. It may extend this 30-day period, on a case-by-case basis, if it reasonably determines that such action is appropriate. Also, the Commission may waive, in whole or in

Federal Communications Commission

§ 1.1952

part, the collection of interest, penalties, and/or administrative costs assessed under this section under the criteria specified in part 103 of the Federal Claims Collection Standards (4 CFR part 103) relating to the compromise of claims (without regard to the amount of the debt), or if it determines that collection of these charges would be against equity and good conscience, or not in the best interest of the United States. Waiver under the first sentence of this paragraph (g) is mandatory. Under the second and third sentences, it may be exercised under appropriate circumstances. Examples of appropriate circumstances include:

(1) Waiver of interest pending the agency's disposition of a request for reconsideration, administrative review, or waiver of the underlying debt under a permissive statute, and

(2) Waiver of interest where the Commission has accepted an installment plan under § 1.1914, and there is no indication of fault or lack of good faith on the part of the debtor.

(h) Where a mandatory waiver or review statute applies, interest and related charges may not be assessed for those periods during which collection action must be suspended under § 104.2(c)(1) of the Federal Claims Collection Standards (4 CFR part 104).

§ 1.1941 Exemptions.

(a) The provisions concerning interest and penalty on claims contained in 31 U.S.C. 3717 do not apply:

(1) To debts owed by any State or local government;

(2) To debts arising under contracts which were executed prior to, and were in effect on (i.e., were not completed as of), October 25, 1982;

(3) To debts where an applicable statute, regulation required by statute, loan agreement, or contract either prohibits such charges or explicitly fixes the charges that apply to the debts arising under the Social Security Act, the Internal Revenue Code of 1954, or the tariff laws of the United States.

(b) However, the Commission is authorized to assess interest and related charges on debts which are not subject to 31 U.S.C. 3717 to the extent authorized under the common law or other applicable statutory authority.

§ 1.1942 Other sanctions.

The remedies and sanctions available to the Commission in this subpart are not exclusive. The Commission may impose other sanctions, where permitted by law, for any inexcusable, prolonged, or repeated failure of a debtor to pay such a claim. In such cases, the Commission will provide notice, as required by law, to the debtor prior to imposition of any such sanction.

COOPERATION WITH THE INTERNAL REVENUE SERVICE

§ 1.1950 Reporting discharged debts to the Internal Revenue Service.

When the Commission discharges a debt for less than the full value of the indebtedness, it will report the outstanding balance discharged, not including interest, to the Internal Revenue Service, using IRS Form 1099-G or any other form prescribed by the Service, when:

(a) The principal amount of the debt not in dispute is \$600 or more; and

(b) The obligation has not been discharged in a bankruptcy proceeding; and

(c) The obligation is no longer collectible either because the time limit in the applicable statute for enforcing collection expired during the tax year, or because during the year a formal compromise agreement was reached in which the debtor was legally discharged of all or a portion of the obligation.

§ 1.1951 Offset against tax refunds.

The Commission will take action to effect administrative offset against tax refunds due to debtors under 26 U.S.C. 6402, in accordance with the provisions of 31 U.S.C. 3720A and Treasury Department regulations.

GENERAL PROVISIONS CONCERNING INTERAGENCY REQUESTS

§ 1.1952 Interagency requests.

(a) Requests to the Commission by other Federal agencies for administrative or salary offset shall be in writing and forwarded to the Financial Services Branch, FCC, 1919 M Street NW., Washington, DC 20554.

§ 1.2001

47 CFR Ch. I (10–1–97 Edition)

(b) Requests by the Commission to other Federal agencies holding funds payable to the debtor will be in writing and forwarded, certified return receipt, as specified by that agency in its regulations. If the agency's rules governing this matter are not readily available or identifiable, the request will be submitted to that agency's office of legal counsel with a request that it be processed in accordance with their internal procedures.

(c) Requests to and from the Commission shall be accompanied by a certification that the debtor owes the debt (including the amount) and that the procedures for administrative or salary offset contained in this subpart, or comparable procedures prescribed by the requesting agency, have been fully complied with. The Commission will cooperate with other agencies in effecting collection.

(d) Requests to and from the Commission shall be processed within 30 calendar days of receipt. If such processing is impractical or not feasible, notice to extend the time period for another 30 calendar days will be forwarded 10 calendar days prior to the expiration of the first 30-day period.

Subpart P—Implementation of the Anti-Drug Abuse Act of 1988

SOURCE: 57 FR 187, Jan. 3, 1992, unless otherwise noted.

§ 1.2001 Purpose.

To determine eligibility for professional and/or commercial licenses issued by the Commission with respect to any denials of Federal benefits imposed by Federal and/or state courts under authority granted in 21 U.S.C. 862.

[60 FR 39269, Aug. 2, 1995]

§ 1.2002 Applicants required to submit information.

(a) In order to be eligible for any new, modified, and/or renewed instrument of authorization from the Commission, including but not limited to, authorizations issued pursuant to sections 214, 301, 302, 303(1), 308, 310(d), 318, 319, 325(b), 351, 361(b), 362(b), 381, and 385 of the Communications Act of 1934, as

amended, by whatever name that instrument may be designated, all applicants shall certify that neither the applicant nor any party to the application is subject to a denial of Federal benefits that includes FCC benefits pursuant to section 5301 of the Anti-Drug Abuse Act of 1988, 21 U.S.C. 862. If a section 5301 certification has been incorporated into the FCC application form being filed, the applicant need not submit a separate certification. If a section 5301 certification has not been incorporated into the FCC application form being filed, the applicant shall be deemed to have certified by signing the application, unless an exhibit is included stating that the signature does not constitute such a certification and explaining why the applicant is unable to certify. If no FCC application form is involved, the applicant must attach a certification to its written application. If the applicant is unable to so certify, the applicant shall be ineligible for the authorization for which it applied, and will have 90 days from the filing of the application to comply with this rule. If a section 5301 certification has been incorporated into the FCC application form, failure to respond to the question concerning certification shall result in dismissal of the application pursuant to the relevant processing rules.

(b) A party to the application, as used in paragraph (a) of this section shall include:

(1) If the applicant is an individual, that individual;

(2) If the applicant is a corporation or unincorporated association, all officers, directors, or persons holding 5% or more of the outstanding stock or shares (voting and/or non-voting) of the applicant; and

(3) If the applicant is a partnership, all non-limited partners and any limited partners holding a 5% or more interest in the partnership.

(c) The provisions of paragraphs (a) and (b) of this section are not applicable to the Amateur Radio Service, the Citizens Band Radio Service, the Radio Control Radio Service, to users in the Public Mobile Services and the Private Radio Services that are not individually licensed by the Commission, or to

Federal Communications Commission

§1.2003

Federal, State or local governmental entities or subdivisions thereof.

[57 FR 187, Jan. 3, 1992, as amended at 58 FR 8701, Feb. 17, 1993; 60 FR 39269, Aug. 2, 1995]

§1.2003 Applications affected.

The certification required by §1.2002 must be filed with the following applications as well as any other requests for authorization filed with the Commission, regardless of whether a specific form exists.

FCC 301 Application for Construction Permit for Commercial Broadcast Station;
FCC 301-A Application for Authority to Operate a Broadcast Station by Remote Control or to Make Changes in a Remote Control Authorization;
FCC 302 Application for New Broadcast Station License;
FCC 302—FM Application for FM Broadcast Station License;
FCC 303-S Application for Renewal of License for AM, FM, TV, Translator, or LPTV Station;
FCC 307 Application for Extension of Broadcast Construction Permit or to Replace Expired Construction Permit;
FCC 308 Application for Permit to Deliver Programs to Foreign Broadcast Stations;
FCC 309 Application for Authority to Construct or Make Changes in an International or Experimental Broadcast Station;
FCC 310 Application for an International, Experimental Television, Experimental Facsimile, or a Developmental Broadcast Station License;
FCC 311 Application for Renewal of an International or Experimental Broadcast License;
FCC 313 Application for Authorization in the Auxiliary Radio Broadcast Services;
FCC 313-R Application for Renewal of Auxiliary Broadcast License;
FCC 314 Application for Consent to Assignment of Broadcast Station Construction Permit or License;
FCC 315 Application for Consent to Transfer of Control of Corporation Holding Broadcast Station Construction Permit or License;
FCC 316 Application for Consent to Assignment of Radio Broadcast Station Construction Permit or License or Transfer of Control of Corporation Holding Radio Broadcast Station Construction Permit or License;
FCC 327 Application for Cable Television Relay Service Station Authorization;
FCC 330 Application for Authorization to Construct New or Make Changes in an Instructional Television Fixed and/or Response Station(s), or to Assign or Transfer Such Stations;

FCC 330-L Application for Instructional Television Fixed Station License;
FCC 330-R Application for Renewal of Instructional Television Fixed Station and/or Response Station(s) and Low Power Relay Station(s) License;
FCC 340 Application for Construction Permit for Noncommercial Educational Broadcast Station;
FCC 345 Application for Transfer of Control of a Corporate Licensee or Permittee, or Assignment of License or Permit, for an FM or TV Translator Station, or a Low Power Television Station;
FCC 346 Application for Authority to Construct or Make Changes in a Low Power TV, TV Translator or TV Booster Station;
FCC 347 Application for a Low Power TV, TV Translator or TV Booster Station License;
FCC 349 Application for Authority to Construct or Make Changes in an FM Translator or FM Booster Station;
FCC 350 Application for an FM Translator or FM Booster Station License;
FCC 401 Application for New or Modified Common Carrier Radio Station Authorization Under part 22 of this chapter.
FCC 402 Application for Station Authorization in the Private Operational Fixed Microwave Radio Service;
FCC 402-R Renewal Notice and Certification in the Private Operational Fixed Microwave Radio Service;
FCC 403 Application for Radio Station License or Modification Thereof Under parts 23 or 25 of this chapter;
FCC 404 Application for Aircraft Radio Station License;
FCC 405 Application for Renewal of Radio Station License;
FCC 405-A Application for Renewal of Radio Station License and/or Notification of Change to License Information;
FCC 405-B Ship/Aircraft License Expiration Notice and/or Renewal Application;
FCC 406 Application for Ground Station Authorization in the Aviation Services;
FCC 407 Application for New or Modified Radio Station Construction Permit;
FCC 409 Airborne Mobile Radio Telephone License Application;
FCC 410 Registration of Canadian Radio Station Licensee and Application for Permit to Operate (Land Mobile);
FCC 442 Application for New or Modified Radio Station Authorization Under part 5 of this chapter—Experimental Radio Service (Other than Broadcast);
FCC 490 Application for Assignment or Transfer of Control Under part 22 of this chapter;
FCC 493 Application for Earth Station Authorization or Modification of Station License (Proposed);

§ 1.2101

47 CFR Ch. I (10–1–97 Edition)

FCC 494 Application for a New or Modified Microwave Radio Station License Under part 21 of this chapter;
FCC 494–A Certification of Completion of Construction Under part 21 of this chapter;
FCC 503 Application for Land Radio Station License in the Maritime Services;
FCC 506 Application for Ship Radio Station License;
FCC 574 Application for Private Land Mobile and General Mobile Radio Services;
FCC 574–R Application for Renewal of Radio Station License;
FCC 701 Application for Additional Time to Construct a Radio Station;
FCC 702 Application for Consent to Assignment of Radio Station Construction Permit or License;
FCC 703 Application for Consent to Transfer Control of Corporation Holding Station License;
FCC 704 Application for Consent to Transfer of Control of Corporation Holding Common Carrier Radio Station Construction Permit or License;
FCC 730 Application for Registration of Equipment to be Connected to the Telephone Network;
FCC 731 Application for Equipment Authorization;
FCC 753 Restricted Radiotelephone Operator Permit Application;
FCC 755 Application for Restricted Radiotelephone Operator Permit—Limited Use;
FCC 756 Application for Commercial Radio Operator License.

[57 FR 187, Jan. 3, 1992, as amended at 57 FR 48333, Oct. 23, 1992; 59 FR 63051, Dec. 7, 1994]

Subpart Q—Competitive Bidding Proceedings

SOURCE: 59 FR 44293, Aug. 26, 1994, unless otherwise noted.

GENERAL PROCEDURES

§ 1.2101 Purpose.

The provisions of this subpart implement section 309(j) of the Communications Act of 1934, as added by the Omnibus Budget Reconciliation Act of 1993 (P.L. 103–66), authorizing the Commission to employ competitive bidding procedures to choose from among two or more mutually exclusive applications for certain initial licenses.

§ 1.2102 Eligibility of applications for competitive bidding.

(a) Mutually exclusive initial applications in the following services or

classes of services are subject to competitive bidding:

(1) Interactive Video Data Service (*see* 47 CFR part 95, subpart F). This paragraph does not apply to applications which were filed prior to July 26, 1993;

(2) Marine Public Coast Stations (*see* 47 CFR part 80, subpart J);

(3) Multipoint Distribution Service and Multichannel Multipoint Distribution Service (*see* 47 CFR part 21, subpart K). This paragraph does not apply to applications which were filed prior to July 26, 1993;

(4) Exclusive Private Carrier Paging above 900 MHz (*see* 47 CFR part 90, subpart P.)

(5) Public Mobile Services (*see* 47 CFR part 22), except in the 800 MHz Air-Ground Radiotelephone Service, and in the Rural Radio Service. This paragraph does not apply to applications in the cellular radio service, such as cellular unserved area applications, that were filed prior to July 26, 1993;

(6) Specialized Mobile Radio Service (SMR) (*see* 47 CFR part 90, subpart S) including applications based on finder's preferences for frequencies allocated to the SMR service (*see* 47 CFR 90.173); and

(7) Personal Communications Services (PCS) (*see* 47 CFR part 24).

(8) General Wireless Communications Service (GWCS) (*see* part 26 of this chapter).

(9) Local Multipoint Distribution Service (LMDS) (*see* 47 CFR part 101).

NOTE TO PARAGRAPH (A): To determine the rules that apply to competitive bidding in the foregoing services, specific service rules should also be consulted.

(b) The following types of license applications are not subject to competitive bidding procedures:

(1) Applications for renewal of licenses;

(2) Applications for modification of license; provided, however, that the Commission may determine that applications for modification that are mutually exclusive with other applications should be subject to competitive bidding;

(3) Applications for subsidiary communications services. A “subsidiary communications service” is a class of service where the signal for that service is indivisible from that of the main

Federal Communications Commission

§1.2103

channel signal and that main channel signal is exempt from competitive bidding under other provisions of these rules. *See, e.g.,* §1.2102(c) (exempting broadcast services). Examples of such subsidiary communications services are those transmitted on subcarriers within the FM baseband signal (*see* 47 CFR 73.295), and signals transmitted within the Vertical Blanking Interval of a broadcast television signal; and

(4) Applications for frequencies used as an intermediate link or links in the provision of a continuous, end-to-end service where no service is provided directly to subscribers over the frequencies. Examples of such intermediate links are:

(i) Point-to-point microwave facilities used to connect a cellular radio telephone base station with a cellular radio telephone mobile telephone switching office; and

(ii) Point-to-point microwave facilities used as part of the service offering in the provision of telephone exchange or interexchange service.

(c) Applications in the following services or classes of services are not subject to competitive bidding:

(1) Alaska-Private Fixed Stations (*see* 47 CFR part 80, subpart O);

(2) Broadcast radio (AM and FM) and broadcast television (VHF, UHF, LPTV) under 47 CFR part 73;

(3) Broadcast Auxiliary and Cable Television Relay Services (*see* 47 CFR part 74, subparts D, E, F, G, H and L and part 78, subpart B);

(4) Instructional Television Fixed Service (*see* 47 CFR part 74, subpart I);

(5) Maritime Support Stations (*see* 47 CFR part 80, subpart N);

(6) Marine Operational Fixed Stations (*see* 47 CFR part 80, subpart L);

(7) Marine Radiodetermination Stations (*see* 47 CFR part 80, subpart M);

(8) Personal Radio Services (*see* 47 CFR part 95), except applications filed after July 26, 1993, in the Interactive Video Data Service (*see* 47 CFR part 95, subpart F);

(9) Public Safety, Industrial/Land Transportation, General and Business Radio categories above 800 MHz, including finder's preference requests for frequencies not allocated to the SMR service (*see* 47 CFR 90.173), and including, until further notice of the Com-

mission, the Automated Vehicle Monitoring Service (*see* 47 CFR 90.239);

(10) Private Land Mobile Radio Services between 470–512 MHz (*see* 47 CFR part 90, subparts B–F), including those based on finder's preferences, (*see* 47 CFR 90.173);

(11) Private Land Mobile Radio Services below 470 MHz (*see* 47 CFR part 90, subparts B–F) except in the 220 MHz band (*see* 47 CFR part 90, subpart T), including those based on finder's preferences (*see* 47 CFR §90.173); and

(12) Private Operational Fixed Services (*see* 47 CFR part 94).

[59 FR 44293, Aug. 26, 1994, as amended at 60 FR 40718, Aug. 9, 1995; 62 FR 23163, Apr. 29, 1997]

§1.2103 Competitive bidding design options.

(a) The Commission will select the competitive bidding design(s) to be used in auctioning particular licenses or classes of licenses on a service-specific basis. The choice of competitive bidding design will generally be made pursuant to the criteria set forth in PP Docket No. 93–253, FCC 94–61, adopted March 8, 1994, available for purchase from the International Transcription Service, Inc., 2100 M St. NW., suite 140, Washington, DC 20037, telephone (202) 857–3800, but the Commission may design and test alternative methodologies. The Commission will choose from one or more of the following types of auction designs for services or classes of services subject to competitive bidding:

(1) Simultaneous multiple round auctions (using remote or on-site electronic bidding);

(2) Sequential multiple round auctions (using either oral ascending or remote and/or on-site electronic bidding); and/or

(3) Sequential or simultaneous single round auctions (using either sealed paper or remote and/or on-site electronic bidding).

(b) The Commission may use combinatorial bidding, which would allow bidders to submit all or nothing bids on combinations of licenses or authorizations, in addition to bids on individual licenses or authorizations. The Commission may require that to be declared the high bid, a combinatorial

§1.2104

47 CFR Ch. I (10–1–97 Edition)

bid must exceed the sum of the individual bids by a specified amount. Combinatorial bidding may be used with any type of auction. The Commission may also allow bidders to submit contingent bids on individual and/or combinations of licenses.

(c) The Commission may use single combined auctions, which combine bidding for two or more substitutable licenses and award licenses to the highest bidders until the available licenses are exhausted. This technique may be used in conjunction with any type of auction.

[59 FR 44293, Aug. 26, 1994, as amended at 62 FR 13542, Mar. 21, 1997]

§1.2104 Competitive bidding mechanisms.

(a) *Sequencing.* The Commission will establish the sequence in which multiple licenses will be auctioned.

(b) *Grouping.* In the event the Commission uses either a simultaneous multiple round competitive bidding design or combinatorial bidding, the Commission will determine which licenses will be auctioned simultaneously or in combination.

(c) *Reservation Price.* The Commission may establish a reservation price, either disclosed or undisclosed, below which a license subject to auction will not be awarded.

(d) *Minimum Bid Increments.* The Commission may, by announcement before or during an auction, require minimum bid increments in dollar or percentage terms. The Commission may also establish suggested minimum opening bids on a service-specific basis.

(e) *Stopping Rules.* The Commission may establish stopping rules before or during multiple round auctions in order to terminate the auctions within a reasonable time.

(f) *Activity Rules.* The Commission may establish activity rules which require a minimum amount of bidding activity.

(g) *Withdrawal, Default and Disqualification Penalties.* As specified below, when the Commission conducts a simultaneous multiple round auction pursuant to §1.2103, the Commission will impose penalties on bidders who withdraw high bids during the course of an auction, or who default on pay-

ments due after an auction closes or who are disqualified.

(1) Bid withdrawal prior to close of auction. A bidder who withdraws a high bid during the course of an auction will be subject to a penalty equal to the difference between the amount bid and the amount of the winning bid the next time the license is offered by the Commission. No withdrawal penalty would be assessed if the subsequent winning bid exceeds the withdrawn bid. This penalty amount will be deducted from any upfront payments or down payments that the withdrawing bidder has deposited with the Commission.

(2) Default or disqualification after close of auction. If a high bidder defaults or is disqualified after the close of such an auction, the defaulting bidder will be subject to the penalty in paragraph (g)(1) plus an additional penalty equal to 3 percent of the subsequent winning bid. If the subsequent winning bid exceeds the defaulting bidder's bid amount, the 3 percent penalty will be calculated based on the defaulting bidder's bid amount. These amounts will be deducted from any upfront payments or down payments that the defaulting or disqualified bidder has deposited with the Commission. When the Commission conducts single round sealed bid auctions or sequential oral auctions, the Commission may modify the penalties to be paid in the event of bid withdrawal, default or disqualification; provided, however, that such penalties shall not exceed the penalties specified above.

(h) The Commission will generally release information concerning the identities of bidders before each auction but may choose, on an auction-by-auction basis, to withhold the identity of the bidders associated with bidder identification numbers.

(i) The Commission may delay, suspend, or cancel an auction in the event of a natural disaster, technical obstacle, evidence of security breach, unlawful bidding activity, administrative necessity, or for any other reason that affects the fair and efficient conduct of the competitive bidding. The Commission also has the authority, at its sole discretion, to resume the competitive bidding starting from the beginning of

Federal Communications Commission

§ 1.2105

the current or some previous round or cancel the competitive bidding in its entirety.

§ 1.2105 Bidding application and certification procedures; prohibition of collusion.

(a) *Submission of Short Form Application (FCC Form 175).* In order to be eligible to bid, an applicant must timely submit a short-form application (FCC Form 175), together with any appropriate filing fee set forth by Public Notice. Unless otherwise provided by Public Notice, the Form 175 need not be accompanied by an upfront payment (see § 1.2106).

(1) All Form 175s will be due:

(i) On the date(s) specified by Public Notice; or

(ii) In the case of application filing dates which occur automatically by operation of law (*see, e.g.*, 47 CFR 22.902), on a date specified by Public Notice after the Commission has reviewed the applications that have been filed on those dates and determined that mutual exclusivity exists.

(2) The Form 175 must contain the following information:

(i) Identification of each license on which the applicant wishes to bid;

(ii) The applicant's name, if the applicant is an individual. If the applicant is a corporation, then the short-form application will require the name and address of the corporate office and the name and title of an officer or director. If the applicant is a partnership, then the application will require the name, citizenship and address of all partners, and, if a partner is not a natural person, then the name and title of a responsible person should be included as well. If the applicant is a trust, then the name and address of the trustee will be required. If the applicant is none of the above, then it must identify and describe itself and its principals or other responsible persons;

(iii) The identity of the person(s) authorized to make or withdraw a bid;

(iv) If the applicant applies as a designated entity pursuant to § 1.2110, a statement to that effect and a declaration, under penalty of perjury, that the applicant is qualified as a designated entity under § 1.2110.

(v) Certification that the applicant is legally, technically, financially and otherwise qualified pursuant to section 308(b) of the Communications Act of 1934, as amended. The Commission will accept applications certifying that a request for waiver or other relief from the requirements of section 310 is pending;

(vi) Certification that the applicant is in compliance with the foreign ownership provisions of section 310 of the Communications Act of 1934, as amended;

(vii) Certification that the applicant is and will, during the pendency of its application(s), remain in compliance with any service-specific qualifications applicable to the licenses on which the applicant intends to bid including, but not limited to, financial qualifications. The Commission may require certification in certain services that the applicant will, following grant of a license, come into compliance with certain service-specific rules, including, but not limited to, ownership eligibility limitations;

(viii) An exhibit, certified as truthful under penalty of perjury, identifying all parties with whom the applicant has entered into partnerships, joint ventures, consortia or other agreements, arrangements or understandings of any kind relating to the licenses being auctioned, including any such agreements relating to the post-auction market structure.

(ix) Certification under penalty of perjury that it has not entered and will not enter into any explicit or implicit agreements, arrangements or understandings of any kind with any parties other than those identified pursuant to paragraph (a)(2)(viii) of this section regarding the amount of their bids, bidding strategies or the particular licenses on which they will or will not bid; and

(x) Certification that the applicant is not in default on any Commission licenses and that it is not delinquent on any non-tax debt owed to any Federal agency.

NOTE TO PARAGRAPH (A): The Commission may also request applicants to submit additional information for informational purposes to aid in its preparation of required reports to Congress.

(b) *Modification and Dismissal of Form 175.* (1) Any Form 175 that is not signed or otherwise does not contain all of the certifications required pursuant to this section is unacceptable for filing and cannot be corrected subsequent to any applicable filing deadline. The application will be dismissed with prejudice and the upfront payment, if paid, will be returned.

(2) The Commission will provide bidders a limited opportunity to cure defects specified herein (except for failure to sign the application and to make certifications) and to resubmit a corrected application. Form 175 may be amended or modified to make minor changes or correct minor errors in the application (such as typographical errors). The Commission will classify all amendments as major or minor, pursuant to rules applicable to specific services. An application will be considered to be a newly filed application if it is amended by a major amendment and may not be resubmitted after applicable filing deadlines.

(3) Applicants who fail to correct defects in their applications in a timely manner as specified by Public Notice will have their applications dismissed with no opportunity for resubmission.

(c) *Prohibition of collusion.* (1) Except as provided in paragraphs (c)(2), (c)(3) and (c)(4) of this section, after the filing of short-form applications, all applicants are prohibited from cooperating, collaborating, discussing or disclosing in any manner the substance of their bids or bidding strategies, or discussing or negotiating settlement agreements, with other applicants until after the high bidder makes the required down payment, unless such applicants are members of a bidding consortium or other joint bidding arrangement identified on the bidder's short-form application pursuant to § 1.2105(a)(2)(viii).

(2) Applicants may modify their short-form applications to reflect formation of consortia or changes in ownership at any time before or during an auction, provided such changes do not result in a change in control of the applicant, and provided that the parties forming consortia or entering into ownership agreements have not applied for licenses in any of the same geo-

graphic license areas. Such changes will not be considered major modifications of the application.

(3) After the filing of short-form applications, applicants may make agreements to bid jointly for licenses, provided the parties to the agreement have not applied for licenses in any of the same geographic license areas.

(4) After the filing of short-form applications, a holder of a non-controlling attributable interest in an entity submitting a short-form application may acquire an ownership interest in, form a consortium with, or enter into a joint bidding arrangement with, other applicants for licenses in the same geographic license area, provided that:

(i) The attributable interest holder certifies to the Commission that it has not communicated and will not communicate with any party concerning the bids or bidding strategies of more than one of the applicants in which it holds an attributable interest, or with which it has a consortium or joint bidding arrangement, and which have applied for licenses in the same geographic license area(s); and

(ii) The arrangements do not result in any change in control of an applicant.

(5) Applicants must modify their short-form applications to reflect any changes in ownership or in the membership of consortia or joint bidding arrangements.

(6) For purposes of this paragraph:

(i) The term *applicant* shall include the entity submitting a short-form application to participate in an auction (FCC Form 175), as well as all holders of partnership and other ownership interests and any stock interest amounting to 5 percent or more of the entity, or outstanding stock, or outstanding voting stock of the entity submitting a short-form application, and all officers and directors of that entity; and

(ii) The term *bids or bidding strategies* shall include capital calls or requests for additional funds in support of bids or bidding strategies.

EXAMPLE FOR PARAGRAPH (C): Company A is an applicant in area 1. Company B and Company C each own 10 percent of Company A. Company D is an applicant in area 1, area 2, and area 3. Company C is an applicant in area 3. Without violating the Commission's

Federal Communications Commission

§ 1.2107

Rules, Company B can enter into a consortium arrangement with Company D or acquire an ownership interest in Company D if Company B certifies either

(1) That it has communicated with and will communicate neither with Company A or anyone else concerning Company A's bids or bidding strategy, nor with Company C or anyone else concerning Company C's bids or bidding strategy, or

(2) That it has not communicated with and will not communicate with Company D or anyone else concerning D's bids or bidding strategy.

[59 FR 44293, Aug. 26, 1994, as amended at 59 FR 64162, Dec. 13, 1994; 62 FR 13543, Mar. 21, 1997]

§ 1.2106 Submission of upfront payments.

(a) The Commission may require applicants for licenses subject to competitive bidding to submit an upfront payment. In that event, the amount of the upfront payment and the procedures for submitting it will be set forth in a Public Notice. No interest will be paid on upfront payments.

(b) Upfront payments must be made by wire transfer in U.S. dollars from a financial institution whose deposits are insured by the Federal Deposit Insurance Corporation and must be made payable to the Federal Communications Commission.

(c) If an upfront payment is not in compliance with the Commission's Rules, or if insufficient funds are tendered to constitute a valid upfront payment, the applicant shall have a limited opportunity to correct its submission to bring it up to the minimum valid upfront payment prior to the auction. If the applicant does not submit at least the minimum upfront payment, it will be ineligible to bid, its application will be dismissed and any upfront payment it has made will be returned.

(d) The upfront payment(s) of a bidder will be credited toward any down payment required for licenses on which the bidder is the high bidder. Where the upfront payment amount exceeds the required deposit of a winning bidder, the Commission may refund the excess amount after determining that no bid withdrawal penalties are owed by that bidder.

(e) In accordance with the provisions of paragraph (d), in the event a penalty

is assessed pursuant to § 1.2104 for bid withdrawal or default, upfront payments or down payments on deposit with the Commission will be used to satisfy the bid withdrawal or default penalty before being applied toward any additional payment obligations that the high bidder may have.

[59 FR 44293, Aug. 26, 1994, as amended at 62 FR 13543, Mar. 21, 1997]

§ 1.2107 Submission of down payment and filing of long-form applications.

(a) After bidding has ended, the Commission will identify and notify the high bidder and declare the bidding closed.

(b) Within ten (10) business days after being notified that it is a high bidder on a particular license(s), a high bidder must submit to the Commission's lockbox bank such additional funds (the "down payment") as are necessary to bring its total deposits (not including upfront payments applied to satisfy penalties) up to twenty (20) percent of its high bid(s). (In single round sealed bid auctions conducted under § 1.2103, however, bidders may be required to submit their down payments with their bids.) This down payment must be made by wire transfer in U.S. dollars from a financial institution whose deposits are insured by the Federal Deposit Insurance Corporation and must be made payable to the Federal Communications Commission. Winning bidders who are qualified designated entities eligible for installment payments under § 1.2110(d) are only required to bring their total deposits up to ten (10) percent of their winning bid(s). Such designated entities must pay the remainder of the twenty (20) percent down payment within ten (10) business days of grant of their application. See § 1.2110(e) (1) and (2). Down payments will be held by the Commission until the high bidder has been awarded the license and has paid the remaining balance due on the license or authorization, in which case it will not be returned, or until the winning bidder is found unqualified to be a licensee or has defaulted, in which case it will be returned, less applicable payments. No interest on any down payment will be paid to the bidders.

§ 1.2108

47 CFR Ch. I (10–1–97 Edition)

(c) A high bidder that meets its down payment obligations in a timely manner must, within ten (10) business days after being notified that it is a high bidder, submit an additional application (the “long-form application”) pursuant to the rules governing the service in which the applicant is the high bidder (unless it has already submitted such an application, as contemplated by § 1.2105(a)(1)(b)). Notwithstanding any other provision in title 47 of the Code of Federal Regulations to the contrary, high bidders need not submit an additional application filing fee with their long-form applications. Specific procedures for filing electronically and manually filed applications will be set out by Public Notice. While Form 600 may be filed either electronically or manually, beginning January 1, 1998, all applications must be filed electronically. Those applicants who file applications manually must also include a copy of all attachments and any other supporting documents on a 3.5 inch diskette in separate ASCII text (.TXT) file formats. An applicant that fails to submit the required long-form application under this paragraph and fails to establish good cause for any late-filed submission, shall be deemed to have defaulted and will be subject to the payments set forth in § 1.2104.

(d) As an exhibit to its long-form application, the applicant must provide a detailed explanation of the terms and conditions and parties involved in any bidding consortia, joint venture, partnership or other agreement or arrangement it had entered into relating to the competitive bidding process prior to the time bidding was completed. Such agreements must have been entered into prior to the filing of short-form applications pursuant to § 1.2105.

[59 FR 44293, Aug. 26, 1994, as amended at 61 FR 49075, Sept. 18, 1996; 62 FR 13543, Mar. 21, 1997]

§ 1.2108 Procedures for filing petitions to deny against long-form applications.

(a) Where petitions to deny are otherwise provided for under the Act or the commission’s Rules, and unless other service-specific procedures for the filing of such petitions are provided for elsewhere in the Commission’s Rules,

the procedures in this section shall apply to the filing of petitions to deny the long-form applications of winning bidders.

(b) Within thirty (30) days after the Commission gives public notice that a long-form application has been accepted for filing, petitions to deny that application may be filed. Any such petitions must contain allegations of fact supported by affidavit of a person or persons with personal knowledge thereof.

(c) An applicant may file an opposition to any petition to deny, and the petitioner a reply to such opposition. Allegations of fact or denials thereof must be supported by affidavit of a person or persons with personal knowledge thereof. The times for filing such opposition and replies will be those provided in § 1.45.

(d) If the Commission determines that:

(1) An applicant is qualified and there is no substantial and material issue of fact concerning that determination, it will grant the application.

(2) An applicant is not qualified and that there is no substantial issue of fact concerning that determination, the Commission need not hold a evidentiary hearing and will deny the application.

(3) Substantial and material issues of fact require a hearing, it will conduct a hearing. The Commission may permit all or part of the evidence to be submitted in written form and may permit employees other than administrative law judges to preside at the taking of written evidence. Such hearing will be conducted on an expedited basis.

§ 1.2109 License grant, denial, default, and disqualification.

(a) Unless otherwise specified in these rules, auction winners are required to pay the balance of their winning bids in a lump sum within ten (10) business days following award of the license. Grant of the license will be conditioned on full and timely payment of the winning bid.

(b) If a winning bidder withdraws its bid after the Commission has declared competitive bidding closed or fails to

Federal Communications Commission

§1.2110

remit the required down payment within ten (10) business days after the Commission has declared competitive bidding closed, the bidder will be deemed to have defaulted, its application will be dismissed, and it will be liable for the default payment specified in §1.2104(g)(2). In such event, the Commission may either re-auction the license to existing or new applicants or offer it to the other highest bidders (in descending order) at their final bids. The down payment obligations set forth in §1.2107(b) will apply.

(c) A winning bidder who is found unqualified to be a licensee, fails to remit the balance of its winning bid in a timely manner, or defaults or is disqualified for any reason after having made the required down payment, will be deemed to have defaulted and will be liable for the penalty set forth in §1.2104(g)(2). In such event, the Commission will conduct another auction for the license, affording new parties an opportunity to file applications for the license.

(d) Bidders who are found to have violated the antitrust laws or the Commission's rules in connection with their participation in the competitive bidding process may be subject, in addition to any other applicable sanctions, to forfeiture of their upfront payment, down payment or full bid amount, and may be prohibited from participating in future auctions.

[59 FR 44293, Aug. 26, 1994, as amended at 62 FR 13544, Mar. 21, 1997]

§1.2110 Designated entities.

(a) Designated entities are small businesses, businesses owned by members of minority groups and/or women, and rural telephone companies.

(b) Definitions.

(1) *Small businesses.* The Commission will establish the definition of a small business on a service-specific basis, taking into consideration the characteristics and capital requirements of the particular service.

(2) Businesses owned by members of minority groups and/or women. Unless otherwise provided in rules governing specific services, a business owned by members of minority groups and/or women is one in which minorities and/or women who are U.S. citizens control

the applicant, have at least 50.1 percent equity ownership and, in the case of a corporate applicant, a 50.1 percent voting interest. For applicants that are partnerships, every general partner either must be a minority and/or woman (or minorities and/or women) who are U.S. citizens and who individually or together own at least 50.1 percent of the partnership equity, or an entity that is 100 percent owned and controlled by minorities and/or women who are U.S. citizens. The interests of minorities and women are to be calculated on a fully-diluted basis; agreements such as stock options and convertible debentures shall be considered to have a present effect on the power to control an entity and shall be treated as if the rights thereunder already have been fully exercised. However, upon a demonstration that options or conversion rights held by non-controlling principals will not deprive the minority and female principals of a substantial financial stake in the venture or impair their rights to control the designated entity, a designated entity may seek a waiver of the requirement that the equity of the minority and female principals must be calculated on a fully-diluted basis. Members of minority groups include Blacks, Hispanics, American Indians, Alaskan Natives, Asians, and Pacific Islanders.

(3) *Rural telephone companies.* A rural telephone company is any local exchange carrier including affiliates (as defined in 1.2110(b)(4)), with 100,000 access lines or fewer.

(4) *Affiliate.* (i) An individual or entity is an affiliate of an applicant or of a person holding an attributable interest in an applicant under §24.709 (both referred to herein as "the applicant") if such individual or entity—

(A) directly or indirectly controls or has the power to control the applicant, or

(B) is directly or indirectly controlled by the applicant, or

(C) is directly or indirectly controlled by a third party or parties that also controls or has the power to control the applicant, or

(D) has an "identity of interest" with the applicant.

(ii) Nature of control in determining affiliation.

(A) Every business concern is considered to have one or more parties who directly or indirectly control or have the power to control it. Control may be affirmative or negative and it is immaterial whether it is exercised so long as the power to control exists.

Example An applicant owning 50 percent of the voting stock of another concern would have negative power to control such concern since such party can block any action of the other stockholders. Also, the bylaws of a corporation may permit a stockholder with less than 50 percent of the voting stock to block any actions taken by the other stockholders in the other entity. Affiliation exists when the applicant has the power to control a concern while at the same time another person, or persons, are in control of the concern at the will of the party or parties with the power to control.

(B) Control can arise through stock ownership; occupancy of director, officer or key employee positions; contractual or other business relations; or combinations of these and other factors. A key employee is an employee who, because of his/her position in the concern, has a critical influence in or substantive control over the operations or management of the concern.

(C) Control can arise through management positions where a concern's voting stock is so widely distributed that no effective control can be established.

Example In a corporation where the officers and directors own various size blocks of stock totaling 40 percent of the corporation's voting stock, but no officer or director has a block sufficient to give him or her control or the power to control and the remaining 60 percent is widely distributed with no individual stockholder having a stock interest greater than 10 percent, management has the power to control. If persons with such management control of the other entity are persons with attributable interests in the applicant, the other entity will be deemed an affiliate of the applicant.

(iii) Identity of interest between and among persons. Affiliation can arise between or among two or more persons with an identity of interest, such as members of the same family or persons with common investments. In determining if the applicant controls or has the power to control a concern, persons with an identity of interest will be treated as though they were one person.

Example Two shareholders in Corporation Y each have attributable interests in the same PCS application. While neither shareholder has enough shares to individually control Corporation Y, together they have the power to control Corporation Y. The two shareholders with these common investments (or identity in interest) are treated as though they are one person and Corporation Y would be deemed an affiliate of the applicant.

(A) Spousal Affiliation. Both spouses are deemed to own or control or have the power to control interests owned or controlled by either of them, unless they are subject to a legal separation recognized by a court of competent jurisdiction in the United States. In calculating their net worth, investors who are legally separated must include their share of interests in property held jointly with a spouse.

(B) Kinship Affiliation. Immediate family members will be presumed to own or control or have the power to control interests owned or controlled by other immediate family members. In this context *immediate family member* means father, mother, husband, wife, son, daughter, brother, sister, father- or mother-in-law, son- or daughter-in-law, brother- or sister-in-law, step-father or -mother, step-brother or -sister, step-son or -daughter, half brother or sister. This presumption may be rebutted by showing that the family members are estranged, the family ties are remote, or the family members are not closely involved with each other in business matters.

Example A owns a controlling interest in Corporation X. A's sister-in-law, B, has an attributable interest in a PCS application. Because A and B have a presumptive kinship affiliation, A's interest in Corporation Y is attributable to B, and thus to the applicant, unless B rebuts the presumption with the necessary showing.

(iv) Affiliation through stock ownership.

(A) An applicant is presumed to control or have the power to control a concern if he or she owns or controls or has the power to control 50 percent or more of its voting stock.

(B) An applicant is presumed to control or have the power to control a concern even though he or she owns, controls or has the power to control less than 50 percent of the concern's voting stock, if the block of stock he or she

Federal Communications Commission

§1.2110

owns, controls or has the power to control is large as compared with any other outstanding block of stock.

(C) If two or more persons each owns, controls or has the power to control less than 50 percent of the voting stock of a concern, such minority holdings are equal or approximately equal in size, and the aggregate of these minority holdings is large as compared with any other stock holding, the presumption arises that each one of these persons individually controls or has the power to control the concern; however, such presumption may be rebutted by a showing that such control or power to control, in fact, does not exist.

(v) Affiliation arising under stock options, convertible debentures, and agreements to merge. Stock options, convertible debentures, and agreements to merge (including agreements in principle) are generally considered to have a present effect on the power to control the concern. Therefore, in making a size determination, such options, debentures, and agreements are generally treated as though the rights held thereunder had been exercised. However, an affiliate cannot use such options and debentures to appear to terminate its control over another concern before it actually does so.

Example 1. If company B holds an option to purchase a controlling interest in company A, who holds an attributable interest in a PCS application, the situation is treated as though company B had exercised its rights and had come owner of a controlling interest in company A. The gross revenues of company B must be taken into account in determining the size of the applicant.

Example 2. If a large company, BigCo, holds 70% (70 of 100 outstanding shares) of the voting stock of company A, who holds an attributable interest in a PCS application, and gives a third party, SmallCo, an option to purchase 50 of the 70 shares owned by BigCo, BigCo will be deemed to be an affiliate of company A, and thus the applicant, until SmallCo actually exercises its option to purchase such shares. In order to prevent BigCo from circumventing the intent of the rule which requires such options to be considered on a fully diluted basis, the option is not considered to have present effect in this case.

Example 3. If company A has entered into an agreement to merge with company B in the future, the situation is treated as though the merger has taken place.

(vi) Affiliation under voting trusts.

(A) Stock interests held in trust shall be deemed controlled by any person who holds or shares the power to vote such stock, to any person who has the sole power to sell such stock, and to any person who has the right to revoke the trust at will or to replace the trustee at will.

(B) If a trustee has a familial, personal or extra-trust business relationship to the grantor or the beneficiary, the stock interests held in trust will be deemed controlled by the grantor or beneficiary, as appropriate.

(C) If the primary purpose of a voting trust, or similar agreement, is to separate voting power from beneficial ownership of voting stock for the purpose of shifting control of or the power to control a concern in order that such concern or another concern may meet the Commission's size standards, such voting trust shall not be considered valid for this purpose regardless of whether it is or is not recognized within the appropriate jurisdiction.

(vii) Affiliation through common management. Affiliation generally arises where officers, directors, or key employees serve as the majority or otherwise as the controlling element of the board of directors and/or the management of another entity.

(viii) Affiliation through common facilities. Affiliation generally arises where one concern shares office space and/or employees and/or other facilities with another concern, particularly where such concerns are in the same or related industry or field of operations, or where such concerns were formerly affiliated, and through these sharing arrangements one concern has control, or potential control, of the other concern.

(ix) Affiliation through contractual relationships. Affiliation generally arises where one concern is dependent upon another concern for contracts and business to such a degree that one concern has control, or potential control, of the other concern.

(x) Affiliation under joint venture arrangements.

(A) A joint venture for size determination purposes is an association of concerns and/or individuals, with interests in any degree or proportion, formed by contract, express or implied,

§ 1.2110

47 CFR Ch. I (10–1–97 Edition)

to engage in and carry out a single, specific business venture for joint profit for which purpose they combine their efforts, property, money, skill and knowledge, but not on a continuing or permanent basis for conducting business generally. The determination whether an entity is a joint venture is based upon the facts of the business operation, regardless of how the business operation may be designated by the parties involved. An agreement to share profits/losses proportionate to each party's contribution to the business operation is a significant factor in determining whether the business operation is a point venture.

(B) The parties to a joint venture are considered to be affiliated with each other.

(c) The Commission may set aside specific licenses for which only eligible designated entities, as specified by the Commission, may bid.

(d) The Commission may permit partitioning of service areas in particular services for eligible designated entities.

(e) The Commission may permit small businesses (including small businesses owned by women, minorities, or rural telephone companies that qualify as small businesses) and other entities determined to be eligible on a service-specific basis, which are high bidders for licenses specified by the Commission, to pay the full amount of their high bids in installments over the term of their licenses pursuant to the following:

(1) Unless otherwise specified, each eligible applicant paying for its license(s) on an installment basis must deposit by wire transfer in the manner specified in § 1.2107(b) sufficient additional funds as are necessary to bring its total deposits to ten (10) percent of its winning bid(s) within ten (10) business days after the Commission has declared it the winning bidder and closed the bidding. Failure to remit the required payment will make the bidder liable to pay penalties pursuant to § 1.2104(g)(2).

(2) Within ten (10) business days of the grant of the license application of a winning bidder eligible for installment payments, the licensee shall pay another ten (10) percent of the high bid,

thereby commencing the eligible licensee's installment payment plan. Failure to remit the required payment will make the bidder liable to pay default payments pursuant to § 1.2104(g)(2).

(3) Upon grant of the license, the Commission will notify each eligible licensee of the terms of its installment payment plan and that it must execute a promissory note and security agreement as a condition of the installment payment plan. Unless other terms are specified in the rules of particular services, such plans will:

(i) Impose interest based on the rate of U.S. Treasury obligations (with maturities closest to the duration of the license term) at the time of licensing;

(ii) Allow installment payments for the full license term;

(iii) Begin with interest-only payments for the first two years; and

(iv) Amortize principal and interest over the remaining term of the license.

(4) A license granted to an eligible entity that elects installment payments shall be conditioned upon the full and timely performance of the licensee's payment obligations under the installment plan.

(i) If an eligible entity making installment payments is more than ninety (90) days delinquent in any payment, it shall be in default.

(ii) Upon default or in anticipation of default of one or more installment payments, a licensee may request that the Commission permit a three to six month grace period, during which no installment payments need be made. In considering whether to grant a request for a grace period, the Commission may consider, among other things, the licensee's payment history, including whether the licensee has defaulted before, how far into the license term the default occurs, the reasons for default, whether the licensee has met construction build-out requirements, the licensee's financial condition, and whether the licensee is seeking a buyer under an authorized distress sale policy. If the Commission grants a request for a grace period, or otherwise approves a restructured payment schedule, interest will continue to accrue and will be amortized over the remaining term of the license.

Federal Communications Commission

§1.2111

(iii) Following expiration of any grace period without successful resumption of payment or upon denial of a grace period request, or upon default with no such request submitted, the license will automatically cancel and the Commission will initiate debt collection procedures pursuant to part 1, subpart O.

(f) The Commission may award bidding credits (i.e., payment discounts) to eligible designated entities. Competitive bidding rules applicable to individual services will specify the designated entities eligible for bidding credits, the licenses for which bidding credits are available, the amounts of bidding credits and other procedures.

(g) The Commission may establish different upfront payment requirements for categories of designated entities in competitive bidding rules of particular auctionable services.

(h) The Commission may offer designated entities a combination of the available preferences or additional preferences.

(i) Designated entities must describe on their long-form applications how they satisfy the requirements for eligibility for designated entity status, and must list and summarize on their long-form applications all agreements that effect designated entity status, such as partnership agreements, shareholder agreements, management agreements and other agreements, including oral agreements, which establish that the designated entity will have both *de facto* and *de jure* control of the entity. Such information must be maintained at the licensee's facilities or by their designated agents for the term of the license in order to enable the Commission to audit designated entity eligibility on an ongoing basis.

(j) The Commission may, on a service-specific basis, permit consortia, each member of which individually meets the eligibility requirements, to qualify for any designated entity provisions.

(k) The Commission may, on a service-specific basis, permit publicly-traded companies that are owned by members of minority groups or women to

qualify for any designated entity provisions.

[59 FR 44293, Aug. 26, 1994; 60 FR 52865, Oct. 11, 1995; 62 FR 13544, Mar. 21, 1997]

§1.2111 Assignment or transfer of control: unjust enrichment.

(a) *Reporting requirement.* An applicant seeking approval for a transfer of control or assignment (otherwise permitted under the Commission's Rules) of a license within three years of receiving a new license through a competitive bidding procedure must, together with its application for transfer of control or assignment, file with the Commission's statement indicating that its license was obtained through competitive bidding. Such applicant must also file with the Commission the associated contracts for sale, option agreements, management agreements, or other documents disclosing the local consideration that the applicant would receive in return for the transfer or assignment of its license. This information should include not only a monetary purchase price, but also any future, contingent, in-kind, or other consideration (e.g., management or consulting contracts either with or without an option to purchase; below market financing).

(b) *Unjust enrichment payment: set-aside.* As specified in this paragraph an applicant seeking approval for a transfer of control or assignment (otherwise permitted under the Commission's Rules) of a license acquired by the transferor or assignor pursuant to a set-aside for eligible designated entities under §1.2110(c), or who proposes to take any other action relating to ownership or control that will result in loss of status as an eligible designated entity, must seek Commission approval and may be required to make an unjust enrichment payment (Payment) to the Commission by cashier's check or wire transfer before consent will be granted. The Payment will be based upon a schedule that will take account of the term of the license, any applicable construction benchmarks, and the estimated value of the set-aside benefit, which will be calculated as the difference between the amount paid by the designated entity for the license and the value of comparable non-set-

§ 1.3000

aside license in the free market at the time of the auction. The Commission will establish the amount of the Payment and the burden will be on the applicants to disprove this amount. No payment will be required if:

(1) The license is transferred or assigned more than five years after its initial issuance, unless otherwise specified; or

(2) The proposed transferee or assignee is an eligible designated entity under § 1.2110(c) or the service-specific competitive bidding rules of the particular service, and so certifies.

(c) *Unjust enrichment payment: installment financing.* An applicant seeking approval for a transfer of control or assignment (otherwise permitted under the Commission's Rules) of a license acquired by the transferor or assignor through a competitive bidding procedure utilizing installment financing available to designated entities under § 1.2110(d) will be required to pay the full amount of the remaining principal balance as a condition of the license transfer. No payment will be required if the proposed transferee or assignee assumes the installment payment obligations of the transferor or assignor, and if the proposed transferee or assignee is itself qualified to obtain installment financing under § 1.2110(d) or the service-specific competitive bidding rules of the particular service, and so certifies.

(d) *Unjust enrichment payment: bidding credits.* An applicant seeking approval for a transfer of control or assignment (otherwise permitted under the Commission's Rules) of a license acquired by the transferor or assignor through a competitive bidding procedure utilizing bidding credits available to eligible designated entities under § 1.2110(e) or who proposes to take any other action relating to ownership or control that will result in loss of status as an eligible designated entity, must seek Commission approval and will be required to make an unjust enrichment payment (Payment) to the government by wire transfer or cashier's check before consent will be granted. The Payment will be the sum of the amount of the bidding credit plus interest at the rate applicable for installment financing in effect at the time the license was

47 CFR Ch. I (10–1–97 Edition)

awarded. See § 1.2110(e). No payment will be required if the proposed transferee or assignee is an eligible designated entity under § 1.2110(e) or the service-specific competitive bidding rules of the particular service, and so certifies.

Subpart R—Implementation of Section 4(g)(3) of the Communications Act: Procedures Governing Acceptance of Unconditional Gifts, Donations and Bequests

SOURCE: 59 FR 38128, July 27, 1994, unless otherwise noted.

§ 1.3000 Purpose and scope.

The purpose of this subpart is to implement the Telecommunications Authorization Act of 1992 which amended the Communications Act by creating section 4(g)(3), 47 U.S.C. 154(g)(3). The provisions of this subpart shall apply to gifts, donations and bequests made to the Commission itself. Travel reimbursement for attendance at, or participation in, government-sponsored meetings or events required to carry out the Commission's statutory or regulatory functions may also be accepted under this subpart. The acceptance of gifts by Commission employees, most notably gifts of food, drink and entertainment, is governed by the government-wide standards of employee conduct established at 5 CFR part 2635. Travel, subsistence and related expenses for non-government-sponsored meetings or events will continue to be accepted pursuant to the Government Employees Training Act, 41 U.S.C. 4111 or 31 U.S.C. 1353, and its General Services Administration's implementing regulations, 41 CFR 304–1.8, as applicable.

§ 1.3001 Definitions.

For purposes of this subpart:

(a) The term *agency* means the Federal Communications Commission.

(b) The term *gift* means any unconditional gift, donation or bequest of real, personal and other property (including voluntary and uncompensated services as authorized under 5 U.S.C. 3109).

Federal Communications Commission

§1.3004

(c) The terms *agency ethics official*, *designated agency ethics official*, *employee*, *market value*, *person*, and *prohibited source*, have the same meaning as found in 5 CFR 2635.102, 2635.203.

§1.3002 Structural rules and prohibitions.

(a) *General prohibitions.* An employee shall not:

(1) Directly or indirectly, solicit or coerce the offering of a gift, donation or bequest to the Commission from a regulated entity or other prohibited source; or

(2) Accept gifts of cash pursuant to this subpart.

(b) *Referral of offers to designated agency ethics official.* Any person who seeks to offer any gift to the Commission under the provisions of this subpart shall make such offer to the Commission's designated agency ethics official. In addition, any Commission employee who is contacted by a potential donor or the representative thereof for the purpose of discussing the possibility of making a gift, donation or bequest to the Commission shall immediately refer such person or persons to the Commission's designated agency ethics official. The designated agency ethics official shall, in consultation with other agency ethics officials, make a determination concerning whether acceptance of such offers would create a conflict of interest or the appearance of a conflict of interest. Agency ethics officials may also advise potential donors and their representatives of the types of equipment, property or services that may be of use to the Commission and the procedures for effectuating gifts set forth in this subpart. The Commission may, in its discretion, afford public notice before accepting any gift under authority of this subpart.

§1.3003 Mandatory factors for evaluating conflicts of interest.

No gift shall be accepted under this subpart unless a determination is made that its acceptance would not create a conflict of interest or the appearance of a conflict of interest. In making conflict of interest determinations, des-

ignated agency ethics officials shall consider the following factors:

(a) Whether the benefits of the intended gift will accrue to an individual employee and, if so—

(1) Whether the employee is responsible for matters affecting the potential donor that are currently before the agency; and

(2) The significance of the employee's role in any such matters;

(b) The nature and sensitivity of any matters pending at the Commission affecting the intended donor;

(c) The timing of the intended gift;

(d) The market value of the intended gift;

(e) The frequency of other gifts made by the same donor; and

(f) The reason underlying the intended gift given in a written statement from the proposed donor.

§1.3004 Public disclosure and reporting requirements.

(a) *Public disclosure of gifts accepted from prohibited sources.* The Commission's Security Operations Office, Office of the Managing Director, shall maintain a written record of gifts accepted from prohibited sources by the Commission pursuant to section 4(g)(3) authority, which will include:

(1) The identity of the prohibited source;

(2) A description of the gift;

(3) The market value of the gift;

(4) Documentation concerning the prohibited source's reason for the gift as required in §1.3003(f);

(5) A signed statement of verification from the prohibited source that the gift is unconditional and is not contingent on any promise or expectation that the Commission's receipt of the gift will benefit the proposed donor in any regulatory matter; and

(6) The date the gift is accepted by the Commission.

(b) *Reporting Requirements for all gifts.* The Commission shall file a semi-annual report to Congress listing the gift, donor and value of all gifts accepted from any donor under this subpart.

Subpart S—Preemption of Restrictions That “Impair” a Viewer’s Ability To Receive Television Broadcast Signals, Direct Broadcast Satellite Services or Multichannel Multipoint Distribution Services

SOURCE: 61 FR 46562, Sept. 4, 1996, unless otherwise noted.

§ 1.4000 Restrictions impairing reception of television broadcast signals, direct broadcast satellite services or multichannel multipoint distribution services.

(a)(1) Any restriction, including but not limited to any state or local law or regulation, including zoning, land-use, or building regulation, or any private covenant, homeowners’ association rule or similar restriction on property within the exclusive use or control of the antenna user where the user has a direct or indirect ownership interest in the property, that impairs the installation, maintenance, or use of: An antenna that is designed to receive direct broadcast satellite service, including direct-to-home satellite services, that is one meter or less in diameter or is located in Alaska; or an antenna that is designed to receive video programming services via multipoint distribution services, including multichannel multipoint distribution services, instructional television fixed services, and local multipoint distribution services, and that is one meter or less in diameter or diagonal measurement; or an antenna that is designed to receive television broadcast signals; is prohibited, to the extent it so impairs, subject to paragraph (b) of this section.

(2) For purposes of this section, a law, regulation or restriction impairs installation, maintenance or use of an antenna if it:

- (i) Unreasonably delays or prevents installation, maintenance or use,
- (ii) Unreasonably increases the cost of installation, maintenance or use, or
- (iii) Precludes reception of an acceptable quality signal.

(3) No civil, criminal, administrative, or other legal action of any kind shall be taken to enforce any restriction or regulation prohibited by this section except pursuant to paragraph (c) or (d)

of this section. No fine or other penalties shall accrue against an antenna user while a proceeding is pending to determine the validity of any restriction.

(b) Any restriction otherwise prohibited by paragraph (a) of this section is permitted if:

(1) It is necessary to accomplish a clearly defined safety objective that is either stated in the text, preamble or legislative history of the restriction or described as applying to that restriction in a document that is readily available to antenna users, and would be applied to the extent practicable in a non-discriminatory manner to other appurtenances, devices, or fixtures that are comparable in size, weight and appearance to these antennas and to which local regulation would normally apply; or

(2) It is necessary to preserve an historic district listed or eligible for listing in the National Register of Historic Places, as set forth in the National Historic Preservation Act of 1966, as amended, 16 U.S.C. 470a, and imposes no greater restrictions on antennas covered by this rule than are imposed on the installation, maintenance or use of other modern appurtenances, devices or fixtures that are comparable in size, weight, and appearance to these antennas; and

(3) It is no more burdensome to affected antenna users than is necessary to achieve the objectives described above.

(c) Local governments or associations may apply to the Commission for a waiver of this rule under § 1.3. Waiver requests will be put on public notice. The Commission may grant a waiver upon a showing by the applicant of local concerns of a highly specialized or unusual nature. No petition for waiver shall be considered unless it specifies the restriction at issue. Waivers granted in accordance with this section shall not apply to restrictions amended or enacted after the waiver is granted.

Any responsive pleadings must be served on all parties and filed within 30 days after release of a public notice that such petition has been filed. Any replies must be filed within 15 days thereafter.

Federal Communications Commission

§ 1.5002

(d) Parties may petition the Commission for a declaratory ruling under § 1.2, or a court of competent jurisdiction, to determine whether a particular restriction is permissible or prohibited under this section. Petitions to the Commission will be put on public notice. Any responsive pleadings must be served on all parties and filed within 30 days after release of a public notice that such petition has been filed. Any replies must be filed within 15 days thereafter.

(e) In any Commission proceeding regarding the scope or interpretation of any provision of this section, the burden of demonstrating that a particular governmental or nongovernmental restriction complies with this section and does not impair the installation, maintenance or use of devices designed for over-the-air reception of video programming services shall be on the party that seeks to impose or maintain the restriction.

(f) All allegations of fact contained in petitions and related pleadings before the Commission must be supported by affidavit of a person or persons with actual knowledge thereof. An original and two copies of all petitions and pleadings should be addressed to the Secretary, Federal Communications Commission, 1919 M St. NW., Washington, DC 20554. Copies of the petitions and related pleadings will be available for public inspection in the Cable Reference Room in Washington, DC. Copies will be available for purchase from the Commission's contract copy center, and Commission decisions will be available on the Internet.

EFFECTIVE DATE NOTE: At 61 FR 46562, Sept. 4, 1996, § 1.4000 was added. The section contains information collection and record-keeping requirements and will not become effective until approval has been given by the Office of Management and Budget.

Subpart T—Exempt Telecommunications Companies

§ 1.5000 Purpose.

The purpose of part 1, subpart S, is to implement Section 34(a) of the Public Utility Holding Company Act of 1935, 15 U.S.C. § 79 et seq., as added by Section 103 of the Telecommunications Act of

1996, Public Law No. 104-104, 110 Stat. 56 (1996).

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5001 Definitions.

(a) For the purpose of this part, the terms “telecommunications services” and “information services” shall have the same meanings as provided in the Communications Act of 1934, as amended;

(b) Commission shall be defined as the Federal Communications Commission; and

(c) “ETC” shall be defined as an exempt telecommunications company.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5002 Contents of application and procedure for filing.

(a) A person seeking status as an exempt telecommunications company (applicant) must file with the Commission with respect to the company or companies which are eligible companies owned or operated by the applicant, and serve on the Securities and Exchange Commission and any affected State commission, the following:

(1) A brief description of the planned activities of the company or companies which are or will be eligible companies owned and/or operated by the applicant;

(2) A sworn statement, by a representative legally authorized to bind the applicant, attesting to any facts or representations presented to demonstrate eligibility for ETC status, including a representation that the applicant is engaged directly, or indirectly, wherever located, through one or more affiliates (as defined in Section 2(a)(11)(B) of the Public Utility Holding Company Act of 1935), and exclusively in the business of providing:

(i) Telecommunications services;

(ii) Information services;

(iii) Other services or products subject to the jurisdiction of the Commission; or

(iv) Products or services that are related or incidental to the provision of a product or service described in paragraph (a)(1)(i), (a)(1)(ii), or (a)(1)(iii); and

§ 1.5003

(3) A sworn statement, by a representative legally authorized to bind the applicant, certifying that the applicant satisfies part 1, subpart P, of the Commission's regulations, 47 CFR 1.2001 through 1.2003, regarding implementation of the Anti-Drug Abuse Act of 1988, 21 U.S.C. 862.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5003 Effect of filing.

A person applying in good faith for a Commission determination of exempt telecommunications company status will be deemed to be an exempt telecommunications company from the date of receipt of the application until the date of Commission action pursuant to § 1.5004.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5004 Commission action.

If the Commission has not issued an order granting or denying an application within 60 days of receipt of the application, the application will be deemed to have been granted as a matter of law.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5005 Notification of Commission action to the Securities and Exchange Commission.

The Secretary of the Commission will notify the Securities and Exchange Commission whenever a person is determined to be an exempt telecommunications company.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5006 Procedure for notifying Commission of material change in facts.

If there is any material change in facts that may affect an ETC's eligibility for ETC status under Section 34(a)(1) of the Public Utility Holding Company Act of 1935, the ETC must, within 30 days of the change in fact, either:

- (a) Apply to the Commission for a new determination of ETC status;
- (b) File a written explanation with the Commission of why the material

47 CFR Ch. I (10–1–97 Edition)

change in facts does not affect the ETC's status; or

- (c) Notify the Commission that it no longer seeks to maintain ETC status.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

§ 1.5007 Comments.

(a) Any person wishing to be heard concerning an application for ETC status may file comments with the Commission within fifteen (15) days from the release date of a public notice regarding the application, or such other period of time set by the Commission. Any comments must be limited to the adequacy or accuracy of the application.

(b) Any person who files comments with the Commission must also serve copies of all comments on the applicant.

(c) An applicant has seven (7) days to reply to any comments filed regarding the adequacy and accuracy of its application, or such other period of time as set by the Commission. Such reply shall be served on the commenters.

[61 FR 52899, Oct. 9, 1996; 61 FR 57335, Nov. 6, 1996]

APPENDIX A TO PART 1—A PLAN OF CO-OPERATIVE PROCEDURE IN MATTERS AND CASES UNDER THE PROVISIONS OF SECTION 410 OF THE COMMUNICATIONS ACT OF 1934

(Approved by the Federal Communications Commission October 25, 1938, and approved by the National Association of Railroad and Utilities Commissioners on November 17, 1938.)

PRELIMINARY STATEMENT CONCERNING THE PURPOSE AND EFFECT OF THE PLAN

Section 410 of the Communications Act of 1934 authorizes cooperation between the Federal Communications Commission, hereinafter called the Federal Commission, and the State commissions of the several States, in the administration of said Act. Subsection (a) authorizes the reference of any matter arising in the administration of said Act to a board to be composed of a member or members from each of the States in which the wire, or radio communication affected by or involved in the proceeding takes place, or is proposed. Subsection (b) authorizes conferences by the Federal Commission with State commissions regarding the relationship between rate structures, accounts,

Federal Communications Commission

Pt. 1, App. A

charges, practices, classifications, and regulations of carriers subject to the jurisdiction of such State commissions and of said Federal Commission and joint hearings with State commissions in connection with any matter with respect to which the Federal Commission is authorized to act.

Obviously, it is impossible to determine in advance what matters should be the subject of a conference, what matters should be referred to a board, and what matters should be heard at a joint hearing of State commissions and the Federal Commission. It is understood, therefore, that the Federal Commission or any State commission will freely suggest cooperation with respect to any proceedings or matter affecting any carrier subject to the jurisdiction of said Federal Commission and of a State commission, and concerning which it is believed that cooperation will be in the public interest.

To enable this to be done, whenever a proceeding shall be instituted before any commission, Federal or State, in which another commission is believed to be interested, notice should be promptly given each such interested commission by the commission before which the proceeding has been instituted. Inasmuch, however, as failure to give notice as contemplated by the provisions of this plan will sometimes occur purely through inadvertence, any such failure should not operate to deter any commission from suggesting that any such proceeding be made the subject matter of cooperative action, if cooperation therein is deemed desirable.

It is understood that each commission whether or not represented in the National Association of Railroad and Utilities Commissioners, must determine its own course of action with respect to any proceeding in the light of the law under which, at any given time, it is called upon to act, and must be guided by its own views of public policy; and that no action taken by such Association can in any respect prejudice such freedom of action. The approval by the Association of this plan of cooperative procedure, which was jointly prepared by the Association's standing Committee on Cooperation between Federal and State commissions and said Federal Commission, is accordingly commendatory only; but such plan is designed to be, and it is believed that it will be, a helpful step in the promotion of cooperative relations between the State commissions and said Federal Commission.

NOTICE OF INSTITUTION OF PROCEEDING

Whenever there shall be instituted before the Federal Commission any proceeding involving the rates of any telephone or telegraph carrier, the State commissions of the States affected thereby will be notified immediately thereof by the Federal Commission, and each notice given a State commis-

sion will advise such commission that, if it deems the proceeding one which should be considered under the cooperative provisions of the Act, it should either directly or through the National Association of Railroad and Utilities Commissioners, notify the Federal Commission as to the nature of its interest in said matter and request a conference, the creation of a joint board, or a joint hearing as may be desired, indicating its preference and the reasons therefor. Upon receipt of such request the Federal Commission will consider the same and may confer with the commission making the request and with other interested commission, or with representatives of the National Association of Railroad and Utilities Commissioners, in such manner as may be most suitable; and if cooperation shall appear to be practicable and desirable, shall so advise each interested State commission, directly, when such cooperation will be by joint conference or by reference to a joint board appointed under said sec. 410 (a), and, as hereinafter provided, when such cooperation will be by a joint hearing under said sec. 410(b).

Each State commission should in like manner notify the Federal Commission of any proceeding instituted before it involving the toll telephone rates or the telegraph rates of any carrier subject to the jurisdiction of the Federal Commission.

PROCEDURE GOVERNING JOINT CONFERENCES

The Federal Commission, in accordance with the indicated procedure, will confer with any State commission regarding any matter relating to the regulation of public utilities subject to the jurisdiction of either commission. The commission desiring a conference upon any such matter should notify the other without delay, and thereupon the Federal Commission will promptly arrange for a conference in which all interested State commissions will be invited to be present.

PROCEDURE GOVERNING MATTERS REFERRED TO A BOARD

Whenever the Federal Commission, either upon its own motion or upon the suggestion of a State commission, or at the request of any interested party, shall determine that it is desirable to refer a matter arising in the administration of the Communications Act of 1934 to a board to be composed of a member or members from the State or States affected or to be affected by such matter, the procedure shall be as follows:

The Federal Commission will send a request to each interested State commission to nominate a specified number of members to serve on such board.

The representation of each State concerned shall be equal, unless one or more of the States affected chooses to waive such right of equal representation. When the

member or members of any board have been nominated and appointed, in accordance with the provisions of the Communications Act of 1934, the Federal Commission will make an order referring the particular matter to such board, and such order shall fix the time and place of hearing, define the force and effect the action of the board shall have, and the manner in which its proceedings shall be conducted. The rules of practice and procedure, as from time to time adopted or prescribed by the Federal Commission, shall govern such board, as far as applicable.

PROCEDURE GOVERNING JOINT HEARINGS

Whenever the Federal Commission, either upon its own motion or upon suggestions made by or on behalf of any interested State commission or commissions, shall determine that a joint hearing under said sec. 410(b) is desirable in connection with any matter pending before said Federal Commission, the procedure shall be as follows:

(a) The Federal Commission will notify the general solicitor of the National Association of Railroad and Utilities Commissioners that said Association, or, if not more than eight States are within the territory affected by the proceeding, the State commissions interested, are invited to name Cooperating Commissioners to sit with the Federal Commission for the hearing and consideration of said proceeding.

(b) Upon receipt of any notice from said Federal Commission inviting cooperation, if not more than eight States are involved, the general solicitor shall at once advise the State commissions of said States, they being represented in the membership of the association, of the receipt of such notice, and shall request each such commission to give advice to him in writing, before a date to be indicated by him in his communication requesting such advice (1) whether such commission will cooperate in said proceeding, (2) if it will, by what commissioner it will be represented therein.

(c) Upon the basis of replies received, the general solicitor shall advise the Federal Commission what States, if any, are desirous of making the proceeding cooperative and by what commissioners they will be represented, and he shall give like advice to each State commission interested therein.

(d) If more than eight States are interested in the proceeding, because within territory for which rates will be under consideration therein, the general solicitor shall advise the president of the association that the association is invited to name a cooperating committee of State commissioners representing the States interested in said proceeding.

The president of the association shall thereupon advise the general solicitor in writing (1) whether the invitation is accepted on behalf of the association, and (2) the names of commissioners selected to sit as a

cooperating committee. The president of the association shall have the authority to accept or to decline said invitation for the association, and to determine the number of commissioners who shall be named on the cooperating committee, provided that his action shall be concurred in by the chairman of the association's executive committee. In the event of any failure of the president of the association and chairman of its executive committee to agree, the second vice president of the association (or the chairman of its committee on cooperation between State and Federal commissions, if there shall be no second vice president) shall be consulted, and the majority opinion of the three shall prevail. Consultations and expressions of opinion may be by mail or telegraph.

(e) If any proceeding, involving more than eight States, is pending before the Federal Commission, in which cooperation has not been invited by that Commission, which the association's president and the first and second vice presidents, or any two of them, consider should be made a cooperating proceeding, they may instruct the general solicitor to suggest to the Federal Commission that the proceeding be made a cooperative proceeding; and any State commission considering that said proceeding should be made cooperative may request the president of the association or the chairman of its executive committee to make such suggestion after consideration with the executive officers above named. If said Federal Commission shall assent to the suggestion, made as aforesaid, the president of the association shall have the same authority to proceed, and shall proceed in the appointment of a cooperating committee, as is provided in other cases involving more than eight States, wherein the Federal Commission has invited cooperation, and the invitation has been accepted.

(f) Whenever any case is pending before the Federal Commission involving eight States or less, which a commission of any of said States considers should be made cooperative, such commission, either directly or through the general solicitor of the association, may suggest to the Federal Commission that the proceeding be made cooperative. If said Federal Commission accedes to such suggestion, it will notify the general solicitor of the association to that effect and thereupon the general solicitor shall proceed as is provided in such case when the invitation has been made by the Federal Commission without State commission suggestion.

APPOINTMENT OF COOPERATING COMMISSIONERS BY THE PRESIDENT

In the appointment of any cooperating committee, the president of the association

Federal Communications Commission

Pt. 2

shall make appointments only from commissions of the States interested in the particular proceeding in which the committee is to serve. He shall exercise his best judgment to select cooperating commissioners who are especially qualified to serve upon cooperating committees by reason of their ability and fitness; and in no case shall he appoint a commissioner upon a cooperating committee until he shall have been advised by such commissioner that it will be practicable for him to attend the hearings in the proceeding in which the committee is to serve, including the arguments therein, and the cooperative conferences, which may be held following the submission of the proceeding, to an extent that will reasonably enable him to be informed upon the issues in the proceeding and to form a reasonable judgment in the matters to be determined.

TENURE OF COOPERATORS

(a) No State commissioner shall sit in a cooperative proceeding under this plan except a commissioner who has been selected by his commission to represent it in a proceeding involving eight States or less, or has been selected by the president of the association to sit in a case involving more than eight States, in the manner hereinbefore provided.

(b) A commissioner who has been selected, as hereinbefore provided, to serve as a member of a cooperating committee in any proceeding, shall without further appointment, and without regard to the duration of time involved, continue to serve in said proceeding until the final disposition thereof, including hearings and conferences after any order or reopening, provided that he shall continue to be a State commissioner.

(c) No member of a cooperating committee shall have any right or authority to designate another commissioner to serve in his place at any hearing or conference in any proceeding in which he has been appointed to serve.

(d) Should a vacancy occur upon any cooperating committee, in a proceeding involving more than eight States, by reason of the death of any cooperating commissioner, or of his ceasing to be a State commissioner, or of other inability to serve, it shall be the duty of the president of the association to fill the vacancy by appointment, if, after communication with the chairman of the cooperating committee, it be deemed necessary to fill such vacancy.

(e) In the event of any such vacancy occurring upon a cooperating committee involving not more than eight States, the vacancy shall be filled by the commission from which the vacancy occurs.

COOPERATING COMMITTEE TO DETERMINE RESPECTING ANY REPORT OF STATEMENT OF ITS ATTITUDE

(a) Whenever a cooperating committee shall have concluded its work, or shall deem such course advisable, the committee shall consider whether it is necessary and desirable to make a report to the interested State commissions, and, if it shall determine to make a report, it shall cause the same to be distributed through the secretary of the association, or through the general solicitor to all interested commissions.

(b) If a report of the Federal Commission will accompany any order to be made in said proceeding, the Federal Commission will state therein the concurrence or nonconcurrence of said cooperating committee in the decision or order of said Federal Commission.

CONSTRUCTION HEREOF IN CERTAIN RESPECTS EXPRESSLY PROVIDED

It is understood and provided that no State or States shall be deprived of the right of participation and cooperation as hereinbefore provided because of nonmembership in the association. With respect to any such State or States, all negotiations herein specified to be carried on between the Federal Commission and any officer of such association shall be conducted by the Federal Commission directly with the chairman of the commission of such State or States.

[28 FR 12462, Nov. 22, 1963, as amended at 29 FR 4801, Apr. 4, 1964]

PART 2—FREQUENCY ALLOCATIONS AND RADIO TREATY MATTERS; GENERAL RULES AND REGULATIONS

Subpart A—Terminology

Sec.

2.1 Terms and definitions.

Subpart B—Allocation, Assignment, and Use of Radio Frequencies

- 2.100 International regulations in force.
- 2.101 Nomenclature of frequencies.
- 2.102 Assignment of frequencies.
- 2.103 Government use of non-Government frequencies.
- 2.104 International Table of Frequency Allocations.
- 2.105 United States Table of Frequency Allocations.
- 2.106 Table of Frequency Allocations.
- 2.107 Radio astronomy station notification.
- 2.108 Policy regarding the use of the fixed-satellite allocations in the 3.6–3.7, 4.5–4.8, and 5.85–5.925 GHz bands.

Subpart C—Emissions

- 2.201 Emission, modulation, and transmission characteristics.
- 2.202 Bandwidths.

Subpart D—Call Signs and Other Forms of Identifying Radio Transmissions

- 2.301 Station identification requirement.
- 2.302 Call signs.
- 2.303 Other forms of identification of stations.

Subpart E—Distress, Disaster, and Emergency Communications

- 2.401 Distress messages.
- 2.402 Control of distress traffic.
- 2.403 Retransmission of distress message.
- 2.404 Resumption of operation after distress.
- 2.405 Operation during emergency.
- 2.406 National defense; free service.
- 2.407 National defense; emergency authorization.

Subparts F–G [Reserved]**Subpart H—Prohibition Against Eavesdropping**

- 2.701 Prohibition against use of a radio device for eavesdropping.

Subpart I—Marketing of Radiofrequency Devices

- 2.801 Radiofrequency device defined.
- 2.803 Marketing of radio frequency devices prior to equipment authorization.
- 2.807 Statutory exceptions.
- 2.811 Transmitters operated under part 73 of this chapter.
- 2.813 Transmitters operated in the Instructional Television Fixed Service.
- 2.815 External radio frequency power amplifiers.

Subpart J—Equipment Authorization Procedures**GENERAL PROVISIONS**

- 2.901 Basis and purpose.
- 2.902 Verification.
- 2.904 Notification.
- 2.905 Type acceptance.
- 2.906 Declaration of Conformity.
- 2.907 Certification.
- 2.908 Identical defined.
- 2.909 Responsible party.

APPLICATION PROCEDURES FOR EQUIPMENT AUTHORIZATIONS

- 2.911 Written application required.

- 2.913 Submittal of equipment authorization application or information to the Commission.
- 2.915 Grant of application.
- 2.917 Dismissal of application.
- 2.919 Denial of application.
- 2.921 Hearing on application.
- 2.923 Petition for reconsideration; application for review.
- 2.924 Marketing of electrically identical equipment having multiple trade names and models or type numbers under the same FCC Identifier.
- 2.925 Identification of equipment.
- 2.926 FCC identifier.

CONDITIONS ATTENDANT TO AN EQUIPMENT AUTHORIZATION

- 2.927 Limitations on grants.
- 2.929 Nonassignability of an equipment authorization.
- 2.931 Responsibility of the grantee.
- 2.932 Modification of equipment.
- 2.933 Change in identification of equipment.
- 2.934 Change in name and/or address of grantee.
- 2.935 Change in control of grantee.
- 2.936 FCC inspection.
- 2.937 Equipment defect and/or design change.
- 2.938 Retention of records.
- 2.939 Revocation or withdrawal of equipment authorization.
- 2.941 Availability of information relating to grants.
- 2.943 Submission of equipment for testing.
- 2.945 Sampling tests of equipment compliance.
- 2.946 Penalty for failure to provide test samples and data.
- 2.947 Measurement procedure.
- 2.948 Description of measurement facilities.

VERIFICATION

- 2.951 Cross reference.
- 2.952 Limitation on verification.
- 2.953 Responsibility for compliance.
- 2.954 Identification.
- 2.955 Retention of records.
- 2.956 FCC inspection and submission of equipment for testing.

NOTIFICATION

- 2.971 Cross reference.
- 2.973 Limitations on notification.
- 2.975 Application for notification.
- 2.977 Changes in notified equipment.

TYPE ACCEPTANCE

- 2.981 Cross reference.
- 2.983 Application for type acceptance.
- 2.985 Measurements required: RF power output.
- 2.987 Measurements required: Modulation characteristics.

Federal Communications Commission

§2.1

- 2.989 Measurements required: Occupied bandwidth.
- 2.991 Measurements required: Spurious emissions at antenna terminals.
- 2.993 Measurements required: Field strength of spurious radiation.
- 2.995 Measurements required: Frequency stability.
- 2.997 Frequency spectrum to be investigated.
- 2.999 Measurement procedure.
- 2.1001 Changes in type accepted equipment.
- 2.1005 Equipment for use in the Amateur Radio Service.

CERTIFICATION

- 2.1031 Cross reference.
- 2.1033 Application for certification.
- 2.1035 [Reserved]
- 2.1041 Measurement procedure.
- 2.1043 Changes in certificated equipment.

FILING FOR APPLICATION REFERENCE

- 2.1061 Submission of technical information for application reference.
- 2.1063 Disclaimer re technical information filed for application reference.
- 2.1065 Identification and changes in equipment information filed for application reference.

DECLARATION OF CONFORMITY

- 2.1071 Cross reference.
- 2.1072 Limitation on Declaration of Conformity.
- 2.1073 Responsibilities.
- 2.1074 Identification.
- 2.1075 Retention of records.
- 2.1076 FCC inspection and submission of equipment for testing.
- 2.1077 Compliance information.

RADIOFREQUENCY RADIATION EXPOSURE

- 2.1091 Radiofrequency radiation exposure evaluation: mobile devices.
- 2.1093 Radiofrequency radiation exposure evaluation: portable devices.

Subpart K—Importation of Devices Capable of Causing Harmful Interference

- 2.1201 Purpose.
- 2.1202 Exclusions.
- 2.1203 General requirement for entry into the U.S.A.
- 2.1204 Import conditions.
- 2.1205 Filing of required declaration.
- 2.1207 Examination of imported equipment.

Subpart L—Registration of Telephone Terminal Equipment

REGISTRATION PROCEDURE

- 2.1300 Cross reference.
- 2.1302 Application for registration under part 68.

Subpart M—Advance Approval of Subscription TV Transmission Systems

ADVANCE APPROVAL PROCEDURE

- 2.1400 Application for advance approval under part 73.

Subpart N—FCC Procedure for Testing Class A, B and S Emergency Position Indicating Radiobeacons (EPIRBs)

GENERAL

- 2.1501 Introduction.
- 2.1503 Test environment.
- 2.1505 Test instrumentation and equipment.

ENVIRONMENTAL AND OPERATIONAL TEST PROCEDURES

- 2.1507 Test frequencies.
- 2.1509 Environmental and duration tests.
- 2.1511 Measurements of radiated emissions.
- 2.1513 Measurements of modulation characteristics.
- 2.1515 Spectral measurements.

DATA RECORDING/REPORTING REQUIREMENTS

- 2.1517 Data recording/reporting requirements.

FIGURES

- FIGURE 1—MEASUREMENT SITE
- FIGURE 2—TYPICAL AUDIO WAVEFORM
- FIGURE 3—EXAMPLE OF IDEAL EPIRB SPECTRUM
- FIGURE 4—EXAMPLE OF EPIRB CARRIER COMPONENT

AUTHORITY: 47 U.S.C. 154, 302, 303, 307 and 336, unless otherwise noted.

SOURCE: 28 FR 12465, Nov. 22, 1963, unless otherwise noted.

Subpart A—Terminology

§2.1 Terms and definitions.

(a) Where a term or definition appears in this part of the Commission's Rules, it shall be the definitive term or definition and shall prevail throughout the Commission's Rules.

(b) The source of each definition is indicated as follows:

CONV—*International Telecommunication Convention*, Malaga-Torremolinos, 1973.

RR—*Radio Regulations*, Geneva, 1982.

FCC—Federal Communications Commission.

(c) The following terms and definitions are issued:

*Accepted Interference.*¹ Interference at a higher level than defined as permissible interference and which has been agreed upon between two or more administrations without prejudice to other administrations. (RR)

Active Satellite. A satellite carrying a station intended to transmit or retransmit radiocommunication signals. (RR)

Active Sensor. A measuring instrument in the earth exploration-satellite service or in the space research service by means of which information is obtained by transmission and reception of radio waves. (RR)

Administration. Any governmental department or service responsible for discharging the obligations undertaken in the Convention of the International Telecommunication Union and the Regulations. (CONV)

Aeronautical Earth Station. An Earth station in the fixed-satellite service, or, in some cases, in the aeronautical mobile-satellite service, located at a specified fixed point on land to provide a feeder link for the aeronautical mobile-satellite service. (RR)

Aeronautical Fixed Service. A radiocommunication service between specified fixed points provided primarily for the safety of air navigation and for the regular, efficient and economical operation of air transport. (RR)

Aeronautical Fixed Station. A station in the aeronautical fixed service. (RR)

Aeronautical Mobile Off-Route (OR) Service. An aeronautical mobile service intended for communications, including those relating to flight coordination, primarily outside national or international civil air routes. (RR)

Aeronautical Mobile Route (R) Service. An aeronautical mobile service reserved for communications relating to safety and regularity of flight, primarily along national or international civil air routes. (RR)

Aeronautical Mobile-Satellite Off-Route (OR) Service. An aeronautical mobile-satellite service intended for communications, including those relating to flight coordination, primarily outside

national and international civil air routes. (RR)

Aeronautical Mobile-Satellite Route (R) Service. An aeronautical mobile-satellite service reserved for communications relating to safety and regularity of flights, primarily along national or international civil air routes. (RR)

Aeronautical Mobile-Satellite Service. A mobile-satellite service in which mobile earth stations are located on board aircraft; survival craft stations and emergency position-indicating radiobeacon stations may also participate in this service. (RR)

Aeronautical Mobile Service. A mobile service between aeronautical stations and aircraft stations, or between aircraft stations, in which survival craft stations may participate; emergency position-indicating radiobeacon stations may also participate in this service on designated distress and emergency frequencies. (RR)

Aeronautical Radionavigation-Satellite Service. A radionavigation-satellite service in which earth stations are located on board aircraft. (RR)

Aeronautical Radionavigation Service. A radio-navigation service intended for the benefit and for the safe operation of aircraft. (RR)

Aeronautical Station. A land station in the aeronautical mobile service.

NOTE: In certain instances, an aeronautical station may be located, for example, on board ship or on a platform at sea. (RR)

Aircraft Earth Station. A mobile earth station in the aeronautical mobile-satellite service located on board an aircraft. (RR)

Aircraft Station. A mobile station in the aeronautical mobile service, other than a survival craft station, located on board an aircraft. (RR)

Allocation (of a frequency band). Entry in the Table of Frequency Allocations of a given frequency band for the purpose of its use by one or more terrestrial or space radiocommunication services or the radio astronomy service under specified conditions. This term shall also be applied to the frequency band concerned. (RR)

Allotment (of a radio frequency or radio frequency channel). Entry of a designated frequency channel in an agreed

¹The terms *permissible interference* and *accepted interference* are used in the coordination of frequency assignments between administrations.

Federal Communications Commission

§2.1

plan, adopted by a competent conference, for use by one or more administrations for a terrestrial or space radiocommunication service in one or more identified countries or geographical area and under specified conditions. (RR)

Altitude of the Apogee or Perigee. The altitude of the apogee or perigee above a specified reference surface serving to represent the surface of the Earth. (RR)

Amateur-Satellite Service. A radio-communication service using space stations on earth satellites for the same purposes as those of the amateur service. (RR)

Amateur Service. A radio-communication service for the purpose of self-training, intercommunication and technical investigations carried out by amateurs, that is, by duly authorized persons interested in radio technique solely with a personal aim and without pecuniary interest. (RR)

Amateur Station. A station in the amateur service. (RR)

Assigned Frequency. The centre of the frequency band assigned to a station. (RR)

Assigned Frequency Band. The frequency band within which the emission of a station is authorized; the width of the band equals the necessary bandwidth plus twice the absolute value of the frequency tolerance. Where space stations are concerned, the assigned frequency band includes twice the maximum Doppler shift that may occur in relation to any point of the Earth's surface. (RR)

Assignment (of a radio frequency or radio frequency channel). Authorization given by an administration for a radio station to use a radio frequency or radio frequency channel under specified conditions. (RR)

Base Earth Station. An earth station in the fixed-satellite service or, in some cases, in the land mobile-satellite service, located at a specified fixed point or within a specified area on land to provide a feeder link for the land mobile-satellite service. (RR)

Base Station. A land station in the land mobile service. (RR)

Broadcasting-Satellite Service. A radio-communication service in which signals transmitted or retransmitted by

space stations are intended for direct reception by the general public.

NOTE: In the broadcasting-satellite service, the term *direct reception* shall encompass both individual reception and community reception. (RR)

Broadcasting Service. A radio-communication service in which the transmissions are intended for direct reception by the general public. This service may include sound transmissions, television transmissions or other types of transmission. (CONV)

Broadcasting Station. A station in the broadcasting service. (RR)

Carrier Power (of a radio transmitter). The average power supplied to the antenna transmission line by a transmitter during one radio frequency cycle taken under the condition of no modulation. (RR)

Characteristic Frequency. A frequency which can be easily identified and measured in a given emission.

NOTE: A carrier frequency may, for example, be designated as the characteristic frequency. (RR)

Class of Emission. The set of characteristics of an emission, designated by standard symbols, e.g., type of modulation, modulating signal, type of information to be transmitted, and also if appropriate, any additional signal characteristics. (RR)

Coast Earth Station. An earth station in the fixed-satellite service or, in some cases, in the maritime mobile-satellite service, located at a specified fixed point on land to provide a feeder link for the maritime mobile-satellite service. (RR)

Coast Station. A land station in the maritime mobile service. (RR)

Community Reception (in the broadcasting-satellite service). The reception of emissions from a space station in the broadcasting-satellite service by receiving equipment, which in some cases may be complex and have antennae larger than those for individual reception, and intended for use: (1) by a group of the general public at one location; or (2) through a distribution system covering a limited area. (RR)

Coordinated Universal Time (UTC). Time scale, based on the second (SI), as defined and recommended by the

§2.1

47 CFR Ch. I (10–1–97 Edition)

CCIR,² and maintained by the Bureau International de l'Heure (BIH).

NOTE: For most practical purposes associated with the Radio Regulations, UTC is equivalent to mean solar time at the prime meridian (0 degrees longitude), formerly expressed in GMT. (RR)

Coordination Area. The area associated with an earth station outside of which a terrestrial station sharing the same frequency band neither causes nor is subject to interfering emissions greater than a permissible level. (RR)

Coordination Contour. The line enclosing the coordination area. (RR)

Coordination Distance. Distance on a given azimuth from an earth station beyond which a terrestrial station neither causes nor is subject to interfering emissions greater than a permissible level. (RR)

Deep Space. Space at distance from the Earth equal to, or greater than, 2×10^6 kilometers. (RR)

Direct Sequence Systems. A spread spectrum system in which the carrier has been modulated by a high speed spreading code and an information data stream. The high speed code sequence dominates the “modulating function” and is the direct cause of the wide spreading of the transmitted signal.

Duplex Operation. Operating method in which transmission is possible simultaneously in both directions of a telecommunication channel.³ (RR)

Earth Exploration-Satellite Service. A radiocommunication service between earth stations and one or more space stations, which may include links between space stations in which:

(1) Information relating to the characteristics of the Earth and its natural phenomena is obtained from active sensors or passive sensors on earth satellites;

(2) Similar information is collected from air-borne or earth-based platforms;

(3) Such information may be distributed to earth stations within the system concerned;

(4) Platform interrogation may be included.

NOTE: This service may also include feeder links necessary for its operation. (RR)

Earth Station. A station located either on the earth's surface or within the major portion of earth's atmosphere and intended for communication:

(1) With one or more space stations; or

(2) With one or more stations of the same kind by means of one or more reflecting satellites or other objects in space. (RR)

Effective Radiated Power (e.r.p.) (in a given direction). The product of the power supplied to the antenna and its gain relative to a half-wave dipole in a given direction. (RR)

Emergency Position-Indicating Radio-beacon Station. A station in the mobile service the emissions of which are intended to facilitate search and rescue operations. (RR)

Emission. Radiation produced, or the production of radiation, by a radio transmitting station.

NOTE: For example, the energy radiated by the local oscillator of a radio receiver would not be an emission but a radiation. (RR)

Equivalent Isotropically Radiated Power (e.i.r.p.). The product of the power supplied to the antenna and the antenna gain in a given direction relative to an isotropic antenna. (RR)

Equivalent Monopole Radiated Power (e.m.r.p.) (in a given direction). The product of the power supplied to the antenna and its gain relative to a short vertical antenna in a given direction. (RR)

Equivalent Satellite Link Noise Temperature. The noise temperature referred to the output of the receiving antenna of the earth station corresponding to the radio-frequency noise power which produces the total observed noise at the output of the satellite link excluding the noise due to interference coming from satellite links using other satellites and from terrestrial systems. (RR)

Experimental Station. A station utilizing radio waves in experiments with a view to the development of science or technique.

NOTE: This definition does not include amateur stations. (RR)

²The full definition is contained in CCIR Recommendation 460-2.

³In general, duplex operation and semi-duplex operation require two frequencies in radiocommunication; simplex operation may use either one or two.

Federal Communications Commission

§2.1

Facsimile. A form of telegraphy for the transmission of fixed images, with or without half-tones, with a view to their reproduction in a permanent form.

NOTE: In this definition the term *telegraphy* has the same general meaning as defined in the Convention. (RR)

Feeder Link. A radio link from an earth station at a given location to a space station, or vice versa, conveying information for a space radio-communication service other than for the fixed-satellite service. The given location may be at a specified fixed point, or at any fixed point within specified areas. (RR)

Fixed-Satellite Service. A radio-communication service between earth stations at given positions, when one or more satellites are used; the given position may be a specified fixed point or any fixed point within specified areas; in some cases this service includes satellite-to-satellite links, which may also be operated in the inter-satellite service; the fixed-satellite service may also include feeder links for other space radio-communication services. (RR)

Fixed Service. A radiocommunication service between specified fixed points. (RR)

Fixed Station. A station in the fixed service. (RR)

Frequency Hopping Systems. A spread spectrum system in which the carrier is modulated with the coded information in a conventional manner causing a conventional spreading of the RF energy about the frequency carrier. The frequency of the carrier is not fixed but changes at fixed intervals under the direction of a coded sequence. The wide RF bandwidth needed by such a system is not required by spreading of the RF energy about the carrier but rather to accommodate the range of frequencies to which the carrier frequency can hop. The test of a frequency hopping system is that the near term distribution of hops appears random, the long term distribution appears evenly distributed over the hop set, and sequential hops are randomly distributed in both direction and magnitude of change in the hop set.

Frequency-Shift Telegraphy. Telegraphy by frequency modulation in

which the telegraph signal shifts the frequency of the carrier between predetermined values. (RR)

Frequency Tolerance. The maximum permissible departure by the centre frequency of the frequency band occupied by an emission from the assigned frequency or, by the characteristic frequency of an emission from the reference frequency.

NOTE: The frequency tolerance is expressed in parts in 10^6 or in hertz. (RR)

Full Carrier Single-Sideband Emission. A single-sideband emission without suppression of the carrier. (RR)

Gain of an Antenna. The ratio, usually expressed in decibels, of the power required at the input of a loss free reference antenna to the power supplied to the input of the given antenna to produce, in a given direction, the same field strength or the same power flux-density at the same distance. When not specified otherwise, the gain refers to the direction of maximum radiation. The gain may be considered for a specified polarization.

NOTE: Depending on the choice of the reference antenna a distinction is made between:

(1) Absolute or isotropic gain (G_i), when the reference antenna is an isotropic antenna isolated in space;

(2) Gain relative to a half-wave dipole (G_d), when the reference antenna is a half-wave dipole isolated in space whose equatorial plane contains the given direction;

(3) Gain relative to a short vertical antenna (G_v), when the reference antenna is a linear conductor, much shorter than one quarter of the wavelength, normal to the surface of a perfectly conducting plane which contains the given direction. (RR)

General Purpose Mobile Service. A mobile service that includes all mobile communications uses including those within the Aeronautical Mobile, Land Mobile, or the Maritime Mobile Services.

Geostationary Satellite. A geosynchronous satellite whose circular and direct orbit lies in the plane of the Earth's equator and which thus remains fixed relative to the Earth; by extension, a satellite which remains approximately fixed relative to the Earth. (RR)

Geostationary Satellite Orbit. The orbit in which a satellite must be placed to be a geostationary satellite. (RR)

Geosynchronous Satellite. An Earth satellite whose period of revolution is equal to the period of rotation of the Earth about its axis. (RR)

*Harmful Interference*⁴. Interference which endangers the functioning of a radionavigation service or of other safety services or seriously degrades, obstructs, or repeatedly interrupts a radiocommunication service operating in accordance with these [international] Radio Regulations. (RR)

Hybrid Spread Spectrum Systems. Hybrid spread spectrum systems are those which use combinations of two or more types of direct sequence, frequency hopping, time hopping and pulsed FM modulation in order to achieve their wide occupied bandwidths.

Inclination of an Orbit (of an earth satellite). The angle determined by the plane containing the orbit and the plane of the Earth's equator. (RR)

Individual Reception (in the broadcasting-satellite service). The reception of emissions from a space station in the broadcasting-satellite service by simple domestic installations and in particular those possessing small antennae. (RR)

Industrial, Scientific and Medical (ISM) (of radio frequency energy) Applications. Operation of equipment or appliances designed to generate and use locally radio-frequency energy for industrial, scientific, medical, domestic or similar purposes, excluding applications in the field of telecommunications. (RR)

Instrument Landing System (ILS). A radionavigation system which provides aircraft with horizontal and vertical guidance just before and during landing and, at certain fixed points, indicates the distance to the reference point of landing. (RR)

Instrument Landing System Glide Path. A system of vertical guidance embodied in the instrument landing system which indicates the vertical deviation of the aircraft from its optimum path of descent. (RR)

Instrument Landing System Localizer. A system of horizontal guidance embodied in the instrument landing system which indicates the horizontal deviation of the aircraft from its opti-

mum path of descent along the axis of the runway. (RR)

Interference. The effect of unwanted energy due to one or a combination of emissions, radiations, or inductions upon reception in a radio-communication system, manifested by any performance degradation, misinterpretation, or loss of information which could be extracted in the absence of such unwanted energy. (RR)

Inter-Satellite Service. A radio-communication service providing links between artificial earth satellites. (RR)

Ionospheric Scatter. The propagation of radio waves by scattering as a result of irregularities or discontinuities in the ionization of the ionosphere. (RR)

Land Earth Station. An earth station in the fixed-satellite service or, in some cases, in the mobile-satellite service, located at a specified fixed point or within a specified area on land to provide a feeder link for the mobile-satellite service. (RR)

Land Mobile Earth Station. A mobile earth station in the land mobile-satellite service capable of surface movement within the geographical limits of a country or continent. (RR)

Land Mobile-Satellite Service. A mobile-satellite service in which mobile earth stations are located on land. (RR)

Land Mobile Service. A mobile service between base stations and land mobile stations, or between land mobile stations. (RR)

Land Mobile Station. A mobile station in the land mobile service capable of surface movement within the geographical limits of a country or continent.

Land Station. A station in the mobile service not intended to be used while in motion. (RR)

Left-Hand (or Anti-Clockwise) Polarized Wave. An elliptically or circularly-polarized wave, in fixed plane, normal to the direction of propagation, whilst looking in the direction of propagation, rotates with time in a left hand or anti-clockwise direction. (RR)

Line A. Begins at Aberdeen, Washington running by great circle arc to the intersection of 48° N., 120° W., thence along parallel 48° N., to the intersection of 95° W., thence by great circle arc through the southernmost point of

⁴ See Resolution 68 of the *Radio Regulations*.

Federal Communications Commission

§2.1

Duluth, Minn., thence by great circle arc to 45° N., 85° W., thence southward along meridian 85° W., to its intersection with parallel 41° N., thence along parallel 41° N., to its intersection with meridian 82° W., thence by great circle arc through the southernmost point of Bangor, Maine, thence by great circle arc through the southernmost point of Searsport, Maine, at which point it terminates. (FCC)

Line B. Begins at Tofino, B.C., running by great circle arc to the intersection of 50° N., 125° W., thence along parallel 50° N., to the intersection of 90° W., thence by great circle arc to the intersection of 45° N., 79°30' W., thence by great circle arc through the northernmost point of Drummondville, Quebec (Lat. 45°52' N., Long 72°30' W.), thence by great circle arc to 48°30' N., 70° W., thence by great circle arc through the northernmost point of Campbellton, N.B., thence by great circle arc through the northernmost point of Liverpool, N.S., at which point it terminates. (FCC)

Line C. Begins at the intersection of 70° N., 144° W., thence by great circle arc to the intersection of 60° N., 143° W., thence by great circle arc so as to include all of the Alaskan Panhandle. (FCC)

Line D. Begins at the intersection of 70° N., 138° W., thence by great circle arc to the intersection of 61°20' N., 139° W. (Burwash Landing), thence by great circle arc to the intersection of 60°45' N., 135° W., thence by great circle arc to the intersection of 56° N., 128° W., thence south along 128° meridian to Lat. 55° N., thence by great circle arc to the intersection of 54° N., 130° W., thence by great circle arc to Port Clements, thence to the Pacific Ocean where it ends. (FCC)

Maritime Mobile-Satellite Service. A mobile-satellite service in which mobile earth stations are located on board ships; survival craft stations and emergency position-indicating radiobeacon stations may also participate in this service. (RR)

Maritime Mobile Service. A mobile service between coast stations and ship stations, or between ship stations, or between associated on-board communication stations; survival craft stations and emergency position-indicating

radiobeacon stations may also participate in this service. (RR)

Maritime Radionavigation-Satellite Service. A radionavigation-satellite service in which earth stations are located on board ships. (RR)

Maritime Radionavigation Service. A radionavigation service intended for the benefit and for the safe operation of ships. (RR)

Marker Beacon. A transmitter in the aeronautical radionavigation service which radiates vertically a distinctive pattern for providing position information to aircraft. (RR)

Mean Power (of a radio transmitter). The average power supplied to the antenna transmission line by a transmitter during an interval of time sufficiently long compared with the lowest frequency encountered in the modulation taken under normal operating conditions. (RR)

Meteorological Aids Service. A radio-communication service used for meteorological, including hydrological, observation and exploration. (RR)

Meteorological-Satellite Service. An earth exploration-satellite service for meteorological purposes. (RR)

Mobile Earth Station. An earth station in the mobile-satellite service intended to be used while in motion or during halts at unspecified points. (RR)

Mobile-Satellite Service. A radio-communication service:

(1) Between mobile earth stations and one or more space stations, or between space stations used by this service; or

(2) Between mobile earth stations by means of one or more space stations.

NOTE: This service may also include feeder links necessary for its operation. (RR)

Mobile Service. A radiocommunication service between mobile and land stations, or between mobile stations. (CONV)

Mobile Station. A station in the mobile service intended to be used while in motion or during halts at unspecified points. (RR)

Multi-Satellite Link. A radio link between a transmitting earth station and a receiving earth station through two or more satellites, without any intermediate earth station.

§2.1

NOTE: A multisatellite link comprises one up-link, one or more satellite-to-satellite links and one down-link. (RR)

Necessary Bandwidth. For a given class of emission, the width of the frequency band which is just sufficient to ensure the transmission of information at the rate and with the quality required under specified conditions. (RR)

Non-Voice, Non-Geostationary Mobile-Satellite Service. A mobile-satellite service reserved for use by non-geostationary satellites in the provision of non-voice communications which may include satellite links between land earth stations at fixed locations.

Occupied Bandwidth. The width of a frequency band such that, below the lower and above the upper frequency limits, the mean powers emitted are each equal to a specified percentage Beta/2 of the total mean power of a given emission.

NOTE: Unless otherwise specified by the CCIR for the appropriate class of emission, the value of Beta/2 should be taken as 0.5%. (RR)

On-Board Communication Station. A low-powered mobile station in the maritime mobile service intended for use for internal communications on board a ship, or between a ship and its lifeboats and life-rafts during lifeboat drills or operations, or for communication within a group of vessels being towed or pushed, as well as for line handling and mooring instructions. (RR)

Orbit. The path, relative to a specified frame of reference, described by the centre of mass of a satellite or other object in space subjected primarily to natural forces, mainly the force of gravity. (RR)

Out-of-band Emission. Emission on a frequency or frequencies immediately outside the necessary bandwidth which results from the modulation process, but excluding spurious emissions. (RR)

Passive Sensor. A measuring instrument in the earth exploration-satellite service or in the space research service by means of which information is obtained by reception of radio waves of natural origin. (RR)

Peak Envelope Power (of a radio transmitter). The average power supplied to the antenna transmission line by a transmitter during one radio frequency

47 CFR Ch. I (10–1–97 Edition)

cycle at the crest of the modulation envelope taken under normal operating conditions. (RR)

Period (of a satellite). The time elapsing between two consecutive passages of a satellite through a characteristic point on its orbit. (RR)

Permissible Interference. Observed or predicted interference which complies with quantitative interference and sharing criteria contained in these [international Radio] Regulations or in CCIR Recommendations or in special agreements as provided for in these Regulations. (RR)

Port Operations Service. A maritime mobile service in or near a port, between coast stations and ship stations, or between ship stations, in which messages are restricted to those relating to the operational handling, the movement and the safety of ships and, in emergency, to the safety of persons.

NOTE: Messages which are of a public correspondence nature shall be excluded from this service. (RR)

Port Station. A coast station in the port operations service. (RR)

Power. Whenever the power of a radio transmitter, etc. is referred to it shall be expressed in one of the following forms, according to the class of emission, using the arbitrary symbols indicated:

- (1) Peak envelope power (PX or pX);
- (2) Mean power (PY or pY);
- (3) Carrier power (PZ or pZ).

NOTE 1: For different classes of emission, the relationships between peak envelope power, mean power and carrier power, under the conditions of normal operation and of no modulation, are contained in CCIR Recommendations which may be used as a guide.

NOTE 2: For use in formulae, the symbol “p” denotes power expressed in watts and the symbol “P” denotes power expressed in decibels relative to a reference level. (RR)

Primary Radar. A radiodetermination system based on the comparison of reference signals with radio signals reflected from the position to be determined. (RR)

Protection Ratio. The minimum value of the wanted-to-unwanted signal ratio, usually expressed in decibels, at the receiver input determined under specified conditions such that a specified reception quality of the wanted

Federal Communications Commission

§2.1

signal is achieved at the receiver output. (RR)

Public Correspondence. Any telecommunication which the offices and stations must, by reason of their being at the disposal of the public, accept for transmission. (CONV)

Pulsed FM Systems. A pulsed FM system is a spread spectrum system in which a RF carrier is modulated with a fixed period and fixed duty cycle sequence. At the beginning of each transmitted pulse, the carrier frequency is frequency modulated causing an additional spreading of the carrier. The pattern of the frequency modulation will depend upon the spreading function which is chosen. In some systems the spreading function is a linear FM chirp sweep, sweeping either up or down in frequency.

Radar. A radiodetermination system based on the comparison of reference signals with radio signals reflected, or retransmitted, from the position to be determined. (RR)

Radar Beacon (RACON). A transmitter-receiver associated with a fixed navigational mark which, when triggered by a radar, automatically returns a distinctive signal which can appear on the display of the triggering radar, providing range, bearing and identification information. (RR)

Radiation. The outward flow of energy from any source in the form of radio waves. (RR)

Radio. A general term applied to the use of radio waves. (CONV)

Radio Altimeter. Radionavigation equipment, on board an aircraft or spacecraft or the spacecraft above the Earth's surface or another surface. (RR)

Radio Astronomy. Astronomy based on the reception of radio waves of cosmic origin. (RR)

Radio Astronomy Service. A service involving the use of radio astronomy. (RR)

Radio Astronomy Station. A station in the radio astronomy service. (RR)

Radiobeacon Station. A station in the radionavigation service the emissions of which are intended to enable a mobile station to determine its bearing or direction in relation to radiobeacon station. (RR)

Radiocommunication. Telecommunication by means of radio waves. (CONV)

Radiocommunication Service. A service as defined in this Section involving the transmission, emission and/or reception of radio waves for specific telecommunication purposes.

NOTE: In these [international] Radio Regulations, unless otherwise stated, any radiocommunication service relates to terrestrial radiocommunication. (RR)

Radiodetermination. The determination of the position, velocity and/or other characteristics of an object, or the obtaining of information relating to these parameters, by means of the propagation properties of radio waves. (RR)

Radiodetermination-Satellite Service. A radiocommunication service for the purpose of radiodetermination involving the use of one or more space stations. This service may also include feeder links necessary for its own operation. (RR)

Radiodetermination Service. A radiocommunication service for the purpose of radiodetermination. (RR)

Radiodetermination Station. A station in the radiodetermination service. (RR)

Radio Direction-Finding. Radiodetermination using the reception of radio waves for the purpose of determining the direction of a station or object. (RR)

Radio Direction-Finding Station. A radiodetermination station using radio direction-finding. (RR)

Radiolocation. Radiodetermination used for purposes other than those of radionavigation. (RR)

Radiolocation Land Station. A station in the radiolocation service not intended to be used while in motion. (RR)

Radiolocation Mobil Station. A station in the radiolocation service intended to be used while in motion or during halts at unspecified points. (RR)

Radiolocation Service. A radiodetermination service for the purpose of radiolocation. (RR)

Radionavigation. Radiodetermination used for the purposes of navigation, including obstruction warning.

Radionavigation Land Station. A station in the radionavigation service not

intended to be used while in motion. (RR)

Radionavigation Mobile Station. A station in the radionavigation service intended to be used while in motion or during halts at unspecified points. (RR)

Radionavigation-Satellite Service. A radiodetermination-satellite service used for the purpose of radionavigation. This service may also include feeder links necessary for its operation. (RR)

Radionavigation Service. A radiodetermination service for the purpose of radionavigation. (RR)

Radiosonde. An automatic radio transmitter in the meteorological aids service usually carried on an aircraft, free balloon, kite or parachute, and which transmits meteorological data. (RR)

Radiotelegram. A telegram, originating in or intended for a mobile station or a mobile earth station transmitted on all or part of its route over the radiocommunication channels of the mobile service or of the mobile-satellite service. (RR)

Radiotelemetry. Telemetry by means of radio waves. (RR)

Radiotelephone Call. A telephone call, originating in or intended for a mobile station or a mobile earth station, transmitted on all or part of its route over the radiocommunication channels of the mobile service or of the mobile-satellite service. (RR)

Radiotelex Call. A telex call, originating in or intended for a mobile station or a mobile earth station, transmitted on all or part of its route over the radiocommunication channels of the mobile service or the mobile-satellite service. (RR)

Radio Waves or Hertzian Waves. Electromagnetic waves of frequencies arbitrarily lower than 3,000 GHz, propagated in space without artificial guide. (RR)

Reduced Carrier Single-Sideband Emission. A single-sideband emission in which the degree of carrier suppression enables the carrier to be reconstituted and to be used for demodulation. (RR)

Reference Frequency. A frequency having a fixed and specified position with respect to the assigned frequency. The displacement of this frequency with respect to the assigned frequency has the

same absolute value and sign that the displacement of the characteristic frequency has with respect to the centre of the frequency band occupied by the emission. (RR)

Reflecting Satellite. A satellite intended to reflect radiocommunication signals. (RR)

Right-Hand (or Clockwise) Polarized Wave. An Elliptically or circularly-polarized wave, in which the electric field vector, observed in any fixed plane, normal to the direction of propagation, whilst looking in the direction of propagation, rotates with time in a right-hand or clockwise direction. (RR)

Safety Service. Any radiocommunication service used permanently or temporarily for the safeguarding of human life and property. (CONV)

Satellite. A body which revolves around another body of preponderant mass and which has a motion primarily and permanently determined by the force of attraction of that other body. (RR)

Satellite Link. A radio link between a transmitting earth station and a receiving earth station through one satellite. A satellite link comprises one up-link and one down-link. (RR)

Satellite Network. A satellite system or a part of a satellite system, consisting of only one satellite and the co-operating earth stations. (RR)

Satellite System. A space system using one or more artificial earth satellites. (RR)

Secondary Radar. A radiodetermination system based on the comparison of reference signals with radio signals retransmitted from the position to be determined. (RR)

Semi-Duplex Operation. A method which is simplex operation at one end of the circuit and duplex operation at the other.³ (RR)

Ship Earth Station. A mobile earth station in the maritime mobile-satellite service located on board ship. (RR)

Ship Movement Service. A safety service in the maritime mobile service other than a port operations service, between coast stations and ship stations, or between ship stations, in which messages are restricted to those relating to the movement of ships.

Federal Communications Commission

§2.1

Messages which are of a public correspondence nature shall be excluded from this service. (RR)

Ship's Emergency Transmitter. A ship's transmitter to be used exclusively on a distress frequency for distress, urgency or safety purposes. (RR)

Ship Station. A mobile station in the maritime mobile service located on board a vessel which is not permanently moored, other than a survival craft station. (RR)

Simplex Operation. Operating method in which transmission is made possible alternatively in each direction of a telecommunication channel, for example, by means of manual control.⁵ (RR)

Single-Sideband Emission. An amplitude modulated emission with one sideband only. (RR)

Spacecraft. A man-made vehicle which is intended to go beyond the major portion of the Earth's atmosphere. (RR)

Space Operation Service. A radio-communication service concerned exclusively with the operation of spacecraft, in particular space tracking, space telemetry, and space telecommand.

NOTE: These functions will normally be provided within the service in which the space station is operating. (RR)

Space Radiocommunication. Any radio-communication involving the use of one or more space stations or the use of one or more reflecting satellites or other objects in space. (RR)

Space Research Service. A radio-communication service in which spacecraft or other objects in space are used for scientific or technological research purposes. (RR)

Space Station. A station located on an object which is beyond, is intended to go beyond, or has been beyond, the major portion of the Earth's atmosphere. (RR)

Space System. Any group of cooperating Earth stations and/or space stations employing space radio-communication for specific purposes. (RR)

Space Telecommand. The use of radio-communication for the transmission of signals to a space station to initiate, modify or terminate functions of

equipment on a space object, including the space station. (RR)

Space Telemetry. The use of telemetry for transmission for a space station of results of measurements made in a spacecraft, including those relating to the functioning of the spacecraft. (RR)

Space Tracking. Determination of the orbit, velocity or instantaneous position of an object in space by means of radiodetermination, excluding primary radar, for the purpose of following the movement of the object. (RR)

Special Service. A radio-communication service, not otherwise defined in this Section, carried on exclusively for specific needs of general utility, and not open to public correspondence. (RR)

Spread Spectrum Systems. A spread spectrum system is an information bearing communications system in which: (1) Information is conveyed by modulation of a carrier by some conventional means, (2) the bandwidth is deliberately widened by means of a spreading function over that which would be needed to transmit the information alone. (In some spread spectrum systems, a portion of the information being conveyed by the system may be contained in the spreading function.)

Spurious Emission. Emission on a frequency or frequencies which are outside the necessary bandwidth and the level of which may be reduced without affecting the corresponding transmission of information. Spurious emissions include harmonic emissions, parasitic emissions, intermodulation products and frequency conversion products, but exclude out-of-band emissions. (RR)

Standard Frequency and Time Signal-Satellite Service. A radiocommunication service using space stations on earth satellites for the same purposes as those of the standard frequency and time signal service.

NOTE: This service may also include feeder links necessary for its operation. (RR)

Standard Frequency and Time Signal Service. A radiocommunication service for scientific, technical and other purposes, providing the transmission of specified frequencies, time signals, or

⁵(See footnote under Duplex Operations.)

§2.1

47 CFR Ch. I (10–1–97 Edition)

both, of stated high precision, intended for general reception. (RR)

Standard Frequency and Time Signal Station. A station in the standard frequency and time signal service. (RR)

Station. One or more transmitters or receivers or a combination of transmitters and receivers, including the accessory equipment, necessary at one location for carrying on a radio-communication service, or the radio astronomy service.

NOTE: Each station shall be classified by the service in which it operates permanently or temporarily. (RR)

Suppressed Carrier Single-Sideband Emission. A single-sideband emission in which the carrier is virtually suppressed and not intended to be used for demodulation. (RR)

Survival Craft Station. A mobile station in the maritime mobile service or the aeronautical mobile service intended solely for survival purposes and located on any lifeboat, life-raft or other survival equipment. (RR)

Telecommand. The use of telecommunication for the transmission of signals to initiate, modify or terminate functions of equipment at a distance. (RR)

Telecommunication. Any transmission, emission or reception of signs, signals, writing, images and sounds or intelligence of any nature by wire, radio, optical or other electromagnetic systems. (CONV)

Telegram. Written matter intended to be transmitted by telegraphy for delivery to addressee. This term also includes radiotelegrams unless otherwise specified.

NOTE: In this definition the term *telegraphy* has the same general meaning as defined in the Convention. (CONV)

Telegraphy. A form of telecommunication which is concerned in any process providing transmission and reproduction at a distance of documentary matter, such as written or printed matter or fixed images, or the reproduction at a distance of any kind of information in such a form. For the purposes of the [international] Radio Regulations, unless otherwise specified therein, telegraphy shall mean a form of telecommunication for the transmission of

written matter by the use of a signal code.⁶ (RR)

Telemetry. The use of telecommunication for automatical indicating or recording measurements at a distance from the measuring instrument. (RR)

Telephony. A form of telecommunication set up for the transmission of speech or, in some cases, other sounds.⁷ (RR)

Television. A form of telecommunication for the transmission of transient images of fixed or moving objects. (RR)

Terrestrial Radiocommunication. Any radiocommunication other than space radiocommunication or radio astronomy. (RR)

Terrestrial Station. A station effecting terrestrial radiocommunication.

NOTE: In these [international Radio] Regulations, unless otherwise stated, any station is a terrestrial station. (RR)

Time Hopping Systems. A time hopping system is a spread spectrum system in which the period and duty cycle of a pulsed RF carrier are varied in a pseudorandom manner under the control of a coded sequence. Time hopping is often used effectively with frequency hopping to form a hybrid time-division, multiple-access (TDMA) spread spectrum system.

Transponder. A transmitter-receiver facility the function of which is to transmit signals automatically when the proper interrogation is received. (FCC)

Tropospheric Scatter. The propagation of radio waves by scattering as a result of irregularities or discontinuities in the physical properties of the troposphere. (RR)

Unwanted Emissions. Consist of spurious emissions and out-of-band emissions. (RR)

[49 FR 2368, Jan. 19, 1984, as amended at 50 FR 25239, June 18, 1985; 51 FR 37399, Oct. 22, 1986; 52 FR 7417, Mar. 11, 1987; 54 FR 49980, Dec. 4, 1990; 55 FR 28761, July 13, 1990; 56 FR 42703, Aug. 29, 1991; 58 FR 68058, Dec. 23, 1993; 62 FR 26242, May 13, 1997]

⁶(See footnote under Harmful Interference)

⁷(See footnote under Harmful Interference)

Federal Communications Commission

§ 2.102

Subpart B—Allocation, Assignment, and Use of Radio Frequencies

SOURCE: 49 FR 2373, Jan. 19, 1984, unless otherwise noted.

§ 2.100 International regulations in force.

The international *Radio Regulations* (Geneva, 1982), became effective internationally on 1 January 1982, and nationally on September 6, 1983. They are incorporated to the extent practicable in this part.

§ 2.101 Nomenclature of frequencies.

Band No.	Frequency subdivision	Frequency range
4	VLF (very low frequency).	Below 30 kHz.
5	LF (low frequency)	30 to 300 kHz.
6	MF (medium frequency).	300 to 3000 kHz.
7	HF (high frequency)	3 to 30 MHz.
8	VHF (very high frequency).	30 to 300 MHz.
9	UHF (ultra high frequency).	300 to 3000 MHz.
10	SHF (super high frequency).	3 to 30 GHz.
11	EHF (extremely high frequency).	30 to 300 GHz.
12		300 to 3000 GHz.

§ 2.102 Assignment of frequencies.

(a) Except as otherwise provided in this section, the assignment of frequencies and bands of frequencies to all stations and classes of stations and the licensing and authorizing of the use of all such frequencies between 9 kHz and 400 GHz, and the actual use of such frequencies for radiocommunication or for any other purpose, including the transfer of energy by radio, shall be in accordance with the Table of Frequency Allocations in § 2.106.

(b) On the condition that harmful interference will not be caused to services operating in accordance with the Table of Frequency Allocations the following exceptions to paragraph (a) of this section may be authorized:

(1) In individual cases the Commission may, without rule making proceedings, authorize on a temporary basis only, the use of frequencies not in accordance with the Table of Frequency Allocations for projects of short duration or emergencies where

the Commission finds that important or exceptional circumstances require such utilization. Such authorizations are not intended to develop a service to be operated on frequencies other than those allocated such service.

(2) A station for the development of techniques or equipment to be employed by services set forth in column 5 of the Table of Frequency Allocations may be authorized the use of frequencies allocated to those services or classes of stations.

(3) Experimental stations pursuant to part 5, may be authorized the use of any frequency or frequency band not exclusively allocated to the passive services (including the Radio Astronomy Service).

(4) In the event a band is reallocated so as to delete its availability for use by a particular service, the Commission may provide for the further interim use of the band by stations in that service for a temporary, specific period of time.

(c) Non-Government stations may be authorized to use Government frequencies in the bands above 25 MHz if the Commission finds, after consultations with the appropriate Government agency or agencies, that such use is necessary for coordination of Government and non-Government activities: Provided, however, that:

(1) Non-Government operation on Government frequencies shall conform with the conditions agreed upon by the Commission and the National Telecommunications and Information Administration (NTIA) (the more important of which are contained in paragraphs (c) (2), (3), and (4) of this section);

(2) Such operations shall be in accordance with NTIA rules governing the service to which the frequencies involved are allocated;

(3) Such operations shall not cause harmful interference to Government stations and, should harmful interference result, that the interfering non-Government operation shall immediately terminate; and

(4) Non-Government operation has been certified as necessary by the Government agency involved and this certification has been furnished, in writing, to the non-Government licensee with which communication is required.

(d) Aircraft stations may communicate with stations of the maritime mobile service. They shall then conform to those provisions of the international *Radio Regulations* which relate to the maritime mobile service. For this purpose aircraft stations should use the frequencies allocated to the maritime mobile service. However, having regard to interference which may be caused by aircraft stations at high altitudes, maritime mobile frequencies in the bands above 30 MHz shall not be used by aircraft stations in any specific area without the prior agreement of all administrations of the area in which interference is likely to be caused. In particular, aircraft stations operating in Region 1 should not use frequencies in the bands above 30 MHz allocated to the maritime mobile service by virtue of any agreement between administrations in that Region.

(e) Non-Government services operating on frequencies in the band 25–50 MHz must recognize that it is shared with various services of other countries; that harmful interference may be caused by skywave signals received from distant stations of all services of the United States and other countries radiating power on frequencies in this band; and that no protection from such harmful interference generally can be expected. Persons desiring to avoid such harmful interference should consider operation on available frequencies higher in the radio spectrum not generally subject to this type of difficulty.

(f) The stations of a service shall use frequencies so separated from the limits of a band allocated to that service as not to cause harmful interference to allocated services in immediately adjoining frequency bands.

(g) In the bands above 25 MHz which are allocated to the non-Government land mobile service, fixed stations may be authorized on the following conditions:

(1) That such stations are authorized in the service shown in Column 5 of the

Table of Frequency Allocations in the band in question;

(2) That harmful interference will not be caused to services operating in accordance with the Table of Frequency Allocations.

(h) Special provisions regarding the use of spectrum allocated to the fixed and land mobile services below 25 MHz by non-Government stations.

(1) Only in the following circumstances will authority be extended to stations in the fixed service to operate on frequencies below 25 MHz.

(i) With respect to aeronautical fixed stations, only when a showing can be made that more suitable facilities are not available.

(ii) With respect to fixed stations, except aeronautical fixed stations, only to:

(A) Provide communication circuits in emergency and/or disaster situations, where safety of life and property are concerned;

(B) Provide standby and/or backup facilities to satellite and cable circuits used for international public correspondence;

(C) Provide standby and/or backup communications circuits to regular domestic communication circuits which have been disrupted by disasters and/or emergencies;

(D) Provide communication circuits wholly within the State of Alaska and the United States insular areas in the Pacific; and

(E) Provide communication circuits to support operations which are highly important to the national interest and where other means of telecommunication are unavailable.

(2) Only in the following circumstances will authority be extended to stations in the land mobile service to operate below 25 MHz.

(i) Provide communication circuits in emergency and/or disaster situations, where safety of life and property are concerned;

(ii) Provide standby and/or backup communications circuits to regular domestic communication circuits which have been disrupted by disasters and/or emergencies;

(iii) Provide communication circuits wholly within the State of Alaska and

Federal Communications Commission

§2.104

the United States insular areas in the Pacific; and

(iv) Provide communication circuits to support operations which are highly important to the national interest and where other means of telecommunication are unavailable.

(3) Except in the State of Alaska and the United States Pacific insular areas, the Commission does not intend to seek international protection for assignments made pursuant to paragraphs (h) (1)(ii) and (2) of this section; this results in the following constraints upon the circuits/assignments.

(i) The Commission will not accept responsibility for protection of the circuits from harmful interference caused by foreign operations.

(ii) In the event that a complaint of harmful interference resulting from operation of these circuits is received from a foreign source, the offending circuit(s) must cease operation on the particular frequency concerned.

(iii) In order to accommodate the situations described in paragraphs (h)(3) (i) and (ii) of this section, equipments shall be capable of transmitting and receiving on any frequency in the bands assigned to the particular operation and capable of immediate change among the frequencies.

§2.103 Government use of non-Government frequencies.

Government stations may be authorized to use non-Government frequencies in the bands above 25 MHz if the Commission finds that such use is necessary for coordination of Government and non-Government activities: Provided, however, That:

(a) Government operation on non-Government frequencies shall conform with the conditions agreed upon by the Commission and the National Telecommunications and Information Administration (the more important of which are contained in paragraphs (b), (c), and (d) of this section);

(b) Such operations shall be in accordance with Commission rules governing the service to which the frequencies involved are allocated;

(c) Such operations shall not cause harmful interference to non-Government stations and, should harmful interference result, that the interfering

Government operation shall immediately terminate; and

(d) Government operation has been certified as necessary by the non-Government licensees involved and this certification has been furnished, in writing, to the Government agency with which communication is required.

§2.104 International Table of Frequency Allocations.

(a) The International Table of Frequency Allocations (columns 1, 2 and 3 of §2.106) is included for informational purposes only.

(b) *Regions.* To facilitate the international allocating of the radio spectrum, the International Telecommunication Union (ITU) has divided the world into three Regions¹ as shown in Figure 1 and described below:

(1) Region 1 includes the area limited on the East by line A (lines A, B and C are defined below) and on the West by line B, excluding any of the territory of Iran which lies between these limits. It also includes that part of the territory of Turkey and the Union of Soviet Socialist Republics (U.S.S.R.) lying outside of these limits, the territory of the Mongolian Peoples' Republic, and the area to the North of the U.S.S.R. which lies between lines A and C.

(2) Region 2 includes the area limited on the East by line B and the West by line C.

(3) Region 3 includes the area limited on the East by line C and on the West by line A, except the territories of the Mongolian Peoples' Republic, Turkey, the territory of the U.S.S.R. and the area to the North of the U.S.S.R. It also includes that part of the territory of Iran lying outside of those limits.

(4) The lines A, B and C are defined as follows:

(i) Line A extends from the North Pole along meridian 40° West of Greenwich to parallel 40° North; thence by great circle arc to the intersection of meridian 60° East and the Tropic of Cancer; thence along the meridian 60° East to the South Pole.

¹It should be noted that where the words "region" or "regional" are without a capital "R", they do not relate to the three Regions here defined for purpose of frequency allocation.

(ii) Line B extends from the North Pole along meridian 10° West of Greenwich to its intersection with parallel 72° North; thence by great circle arc to the intersection of meridian 50° West and parallel 40° North; thence by great circle arc to the intersection of meridian 20° West and to the South Pole.

(iii) Line C extends from the North Pole by great circle arc to the intersection of parallel 65°30' North of the international boundary in Bering Strait; thence by great circle arc to the intersection of meridian 165° East of Greenwich and parallel 50° North; thence by great circle arc to the intersection of meridian 170° West and parallel 10° North; thence along parallel 10° North to its intersection with meridian 120° West; thence along meridian 120° West to the South Pole.

(c) *Areas.* To further assist in the international allocation of the radio spectrum, the ITU has established several special geographical areas and they are defined below.

(1) The “African Broadcasting Area” consists of:

(i) African countries, parts of countries, territories and groups of territories situated between the parallels 40° South and 30° North;

(ii) Islands in the Indian Ocean west of meridian 60° East of Greenwich, situated between the parallel 40° South and the great circle arc joining the points 45° East, 11°30' North and 60° East, 15° North; and

(iii) Islands in the Atlantic Ocean east of Line B, situated between the parallel 40° South and 30° North.

(2) The “European Broadcasting Area” is bounded on the West by the western boundary of Region 1, on the East by the meridian 40° East of Greenwich and on the South by the parallel 30° North so as to include the western part of the U.S.S.R., the northern part of Saudi Arabia and that part of those countries bordering the Mediterranean within these limits. In addition, Iraq and Jordan are included in the European Broadcasting Area.

(3) The “European Maritime Area” is bounded to the north by a line extending along parallel 72° North from its intersection with meridian 55° East of Greenwich to its intersection with meridian 5° West, then along meridian 5°

West to its intersection with parallel 67° North, thence along parallel 6° North to its intersection with meridian 32° West; to the west by a line extending along meridian 32° West to its intersection with parallel 30° North; to the south by a line extending along parallel 30° North to its intersection with meridian 43° East; to the east by a line extending along meridian 43° East to its intersection with parallel 60° North, thence along parallel 60° North to its intersection with meridian 55° East and thence along meridian 55° East to its intersection with parallel 72° North.

(4) The “Tropical Zone” (see Figure 1) is defined as:

(i) The whole of that area in Region 2 between the Tropics of Cancer and Capricorn;

(ii) The whole of that area in Region 1 and 3 contained between the parallel 30° North and 35° South with the addition of:

(iii) The area contained between the meridian 40° East and 80° East of Greenwich and the parallels 30° North and 40° and

(iv) That part of Libya North of parallel 30° North.

(v) In Region 2, the Tropical Zone may be extended to parallel 33° North, subject to special agreements between the countries concerned in that Region.

(5) A sub-Region is an area consisting of two or more countries in the same Region.

(d) *Categories of service.* (1) Any segment of the radio spectrum can be allocated to one or more radio services² either on a worldwide or Regional basis. In the case where an allocation has been made to more than one service, such services are listed in the following order:

(i) Services the names of which are printed in “capitals” [example: FIXED]; these are called “primary” services;

(ii) Services, the names of which are printed in “capitals” between oblique strokes [example: /RADIOLOCATION/]; these are called “permitted” services;

²Definitions of the various radio services used in columns 1 through 3 of §2.106 are contained in §2.1.

(iii) Services, the names of which are printed in “normal characters” [example: Mobile]; these are called “secondary” services.

(2) Additional remarks pertaining to an allocation are printed in “normal characters” [example: MOBILE except aeronautical mobile].

(3) Permitted and primary services have equal rights, except that, in the preparation of frequency plans, the primary services, as compared with the permitted services, shall have prior choice of frequencies.

(4) *Stations of a secondary service:*

(i) Shall not cause harmful interference to stations of primary or permitted services to which frequencies are already assigned or to which frequencies may be assigned at a later date;

(ii) Cannot claim protection from harmful interference from stations of a primary or permitted service to which frequencies are already assigned or may be assigned at a later date;

(iii) Can claim protection, however, from harmful interference from stations of the same or other secondary service(s) to which frequencies may be assigned at a later date.

(5) Where a band is indicated in a footnote of the International Table (i.e., columns 1, 2, and 3 of §2.106) as allocated to a service “on a secondary basis” in an area smaller than a Region, or in a particular country, this is a secondary service.

(6) Where a band is indicated in a footnote of the International Table as allocated to a service “on a primary basis”, or “on a permitted basis” in an area smaller than a Region, or in a particular country, this is a primary service or a permitted service only in that area country.

(e) *Additional allocations.* (1) Where a band is indicated in a footnote of the International Table as “also allocated” to a service in an area smaller than a Region, or in a particular country, this is an “additional” allocation, i.e., an allocation which is added in this country area or in this country to the service or services which are indicated in the International Table.

(2) If the footnote does not include any restriction on the service or services concerned apart from the restric-

tion to operate only in a particular area or country, stations of this service or these services shall have equality of right to operate with stations of the other primary service or services indicated in the International Table.

(3) If restrictions are imposed on an additional allocation in addition to the restriction to operate only in a particular area or country, this is indicated in the footnote of the International Table.

(f) *Alternative allocations.* (1) Where a band is indicated in a footnote of the International Table as “allocated” to one or more services in an area smaller than a Region, or in a particular country, this is an “alternative” allocation, i.e., an allocation which replaces, in this area or in this country, the allocations indicated in the International Table.

(2) If the footnote does not include any restriction on stations of the service or services concerned, apart from the restriction to operate only in a particular area or country, these stations of such a service or services shall have an equality of right to operate with stations of the primary service or services, indicated in the International Table, to which the band is allocated in other areas or countries.

(3) If restrictions are imposed on stations of a service to which an alternative allocation is made, in addition to the restriction to operate only in a particular country or area, this is indicated in the footnote.

(g) *Miscellaneous provision.* (1) Where it is indicated that a service may operate in a specific frequency band subject to not causing harmful interference, this means also that this service cannot claim protection from harmful interference caused by other services to which the band is allocated under Chapter III of the international *Radio Regulations*.

(2) Except if otherwise specified in a footnote, the term *fixed service* does not include systems using ionospheric scatter propagation.

(h) *Format of the International Table.* (1) The heading of the International Table includes three columns (columns number 1, 2 and 3 of §2.106), each of

which corresponds to one of the Regions. Where an allocation occupies the whole of the width of the Table or only two of the three columns, this is a world-wide allocation or a Regional allocation, respectively.

(2) The frequency band referred to in each allocation is indicated in the left-hand top corner of the part of the Table concerned.

(3) Within each of the categories specified in paragraph (c)(1) of this section, services are listed in alphabetical order according to the French language.³ The order of listing does not indicate relative priority within each category.

(4) In the case where there is a parenthetical addition to an allocation in

the International Table [example: FIXED-SATELLITE (space-to-earth)], that service allocation is restricted to the type of operation so indicated.

(5) The footnote references which appear in the International Table below the allocated service or services apply to the whole of the allocation concerned.

(6) The footnote references which appear to the right of the name of a service are applicable only to that particular service.

(7) In certain cases, the names of countries appearing in the footnotes have been simplified in order to shorten the text.




Figure 1. Chart of the International Regions and Zones as defined in the International Table of Frequency Allocations. [Note: The shaded part represents the Tropical Zone as defined by §2.104b)(4).]
[49 FR 2373, Jan. 19, 1984, as amended at 54 FR 49981, Dec. 4, 1989; 61 FR 15384, Apr. 8, 1996]

³French is used to keep this table consistent with the International Table as published by ITU.

Federal Communications Commission

§2.105

§2.105 United States Table of Frequency Allocations.

(a) The United States Table of Frequency Allocations (columns 4 through 7 of §2.106) is based on the International plan for Region 2 because the relevant area of jurisdiction is located primarily in Region 2¹ (i.e., the 50 States, the District of Columbia, the Caribbean insular areas² and some of the Pacific insular areas³).⁴ Because there is a need to provide radio spectrum for both Federal government and non-Federal government operations, the United States Table is divided into the Government Table of Frequency Allocation and the Non-Government Table of Frequency Allocations. The Government plan, as shown in column 4 of §2.106, is administered by the National Telecommunications and Information Administration (NTIA)⁵, whereas the non-Government plan, as shown in column 5 of §2.106, is administered by the Federal Communications Commission (FCC)⁶

(b) In the United States, radio spectrum may be allocated to either Government or non-Government use exclusively, or for shared use. In the case of shared use, the type of service(s) permitted need not be the same [e.g., Government FIXED, non-Government MOBILE]. The terms used to designate

categories of service⁷ in columns 4 and 5 of §2.106, correspond to the terms employed by the International Telecommunication Union (ITU) in the international *Radio Regulations*.

(c) *Categories of services.* (1) Any segment of the radio spectrum may be allocated to the Government and/or non-Government sectors either on an exclusive or shared basis for use by one or more radio services. In the case where an allocation has been made to more than one service, such services are listed in the following order:

(i) Services, the names of which are printed in “capitals” [example: FIXED]; these are called “primary” services;

(ii) Services, the names of which are printed in capitals between oblique strokes [example: /RADIOLOCATION/]; these are called “permitted services”;

(iii) Services, the names of which are printed in “normal characters” [example: Mobile]; these are called “secondary” services.

(2) Permitted and primary services have equal rights, except that, in the preparation of frequency plans, the primary services, as compared with the permitted services, shall have prior choice of frequencies.

(3) Stations of a secondary service:

(i) Shall not cause harmful interference to stations of primary or permitted services to which frequencies are already assigned or to which frequencies may be assigned at a later date.

(ii) Cannot claim protection from harmful interference from stations of a primary or permitted service to which frequencies are already assigned or may be assigned at a later date; and

(iii) Can claim protection, however, from harmful interference from stations of the same or other secondary service(s) to which frequencies may be assigned at a later date.

(d) *Format of the United States Table.*

(1) The frequency band referred to in each allocation, column 4 for Government and column 5 for non-Government, is indicated in the left-hand top corner of the column. If there is no service or footnote indicated for a band

¹ See §2.104(a)(1) for definition of Region 2.

² The Caribbean insular areas are: The Commonwealth of Puerto Rico; the unincorporated territory of the United States Virgin Islands; and Navassa Island, Quita Sueno Bank, Roncador Bank, Serrana Bank and Serranilla Bank.

³ The Pacific insular areas located in Region 2 are: Johnston Island and Midway Island.

⁴ The operation of stations in the Pacific insular areas located in Region 3 are generally governed by the International plan for Region 3 (i.e., column 3 of §2.106). The Pacific insular areas located in Region 3 are: the Commonwealth of the Northern Mariana Islands; the unincorporated territory of American Samoa; the unincorporated territory of Guam; and Baker Island, Howland Island, Jarvis Island, Kingman Reef, Palmyra Island and Wake Island.

⁵ Section 305(a) of the Communications Act of 1934, as amended; Executive Order 12046 (26 March 1978) and Department of Commerce Organization Order 10-10 (9 May 1979).

⁶ The Communications Act of 1934, as amended.

⁷ Definitions of the various radio services used are contained in §2.1.

§2.105

47 CFR Ch. I (10–1–97 Edition)

of frequencies in either column 4 or 5, then the Government or the non-Government sector, respectively, has no access to that band except as provided for by §2.102.

(2) The Government allocation plan, given in column 4, is included for informational purposes only.

(3) In the case where there is a parenthetical addition to an allocation in the United States Table [example: FIXED-SATELLITE (space-to-earth)], that service allocation is restricted to the type of operation so indicated.

(4) The following symbols are used to designate footnotes in the United States Table:

(i) Any footnote not prefixed by a letter, denotes an international footnote. Where such a footnote is applicable, without modification, to the United States Table, the symbol appears in the United States Table (column 4 or 5) and denotes a stipulation affecting both the Government and non-Government plans.

(ii) Any footnote consisting of the letters US followed by one or more digits, e.g., US, denotes a stipulation affecting both the Government and non-Government plans.

(iii) Any footnote consisting of the letters NG followed by one or more digits, e.g., NG1, denotes a stipulation applicable only to the non-Government plan (column 5).

(iv) Any footnote consisting of the letter G followed by one or more digits, e.g., G1, denotes a stipulation applicable only to the Government plan (column 4).

(5) Column 6 provides a reference to indicate which Rule part(s) (e.g., Private Land Mobile Radio Services, Domestic Public Land Mobile Radio Services, etc.) are given assignments within the allocation plan specified in column 5 for any given band of frequencies. The exact use that can be made of any given frequency or frequencies (e.g., channelling plans, allowable emissions, etc.) is given in the Rule part(s) so indicated. The Rule parts in this column are not allocations. They are provided for informational purposes only.

(6) Column 7 is used to denote certain frequencies which have national and/or international significance.

[49 FR 2373, Jan. 19, 1984, as amended at 49 FR 44101, Nov. 2, 1984]

§2.106 Table of Frequency Allocations.

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
Below 9	(Not allocated) 444 445		Below 9 (Not allocated) 444 445	Below 9 (Not allocated) 444 445		
9–14	RADIONAVIGATION		9–14 RADIONAVIGATION US18 US294	9–14 RADIONAVIGATION US18 US294		
14–19.95	FIXED MARITIME MOBILE 448 446 447		14–19.95 FIXED MARITIME MOBILE 448 US294	14–19.95 Fixed 448 US294	INTERNATIONAL FIXED PUBLIC (23)	
19.95–20.05	STANDARD FRE- QUENCY AND TIME SIGNAL (20 kHz)		19.95–20.05 STANDARD FRE- QUENCY AND TIME SIGNAL US294	19.95–20.05 STANDARD FRE- QUENCY AND TIME SIGNAL US294		20 kHz Standard frequency
20.05–70	FIXED MARITIME MOBILE 448		20.05–59 FIXED MARITIME MOBILE 446 US294	20.05–59 FIXED 448 US294	INTERNATIONAL FIXED PUBLIC (23)	
			59–61 STANDARD FRE- QUENCY AND TIME SIGNAL US294	59–61 STANDARD FRE- QUENCY AND TIME SIGNAL US294		60 kHz Standard frequency
	447 449		61–70 FIXED MARITIME MOBILE 448 US294	61–70 FIXED 448 US294	INTERNATIONAL FIXED PUBLIC (23)	

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
70–72 RADIONAVIGATION 451	70–90 FIXED MARITIME MOBILE 448 MARITIME RADIO- NAVIGATION 451 Radiolocation	70–72 RADIONAVIGATION 451 Fixed Maritime Mobile 448	70–90 FIXED MARITIME MOBILE Radiolocation	70–90 FIXED Radiolocation	INTERNATIONAL FIXED PUBLIC (23) Private Land Mobile (90)	
72–84 FIXED MARITIME MOBILE 448 RADIONAVIGATION 451 447		72–84 FIXED MARITIME MOBILE 448 RADIONAVIGATION 451				
84–86 RADIONAVIGATION 451		84–86 RADIONAVIGATION 451 Fixed Maritime Mobile 448 450				
86–90 FIXED MARITIME MOBILE 448 RADIONAVIGATION 447	452	86–90 FIXED MARITIME MOBILE 448 RADIONAVIGATION 451	448 451 US288 US294	448 451 US288 US294		
90–110	RADIONAVIGATION 453 Fixed 453A 454		90–110 RADIONAVIGATION 453 US18 US104 US294	90–110 RADIONAVIGATION 453 US18 US104 US294	Private Land Mobile (90)	
110–112 FIXED MARITIME MOBILE RADIONAVIGATION 454	110–130 FIXED MARITIME MOBILE MARITIME RADIO- NAVIGATION 451 Radiolocation	110–112 FIXED MARITIME MOBILE RADIONAVIGATION 451 454	110–130 FIXED MARITIME MOBILE Radiolocation	110–130 FIXED MARITIME MOBILE Radiolocation	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) Private Land Mobile (90)	

112–115 RADIONAVIGATION 451	112–117.6 RADIONAVIGATION 451 Fixed Maritime Mobile				
115–117.6 RADIONAVIGATION 451 Fixed Maritime Mobile 454 456	454 455				
117.6–126.0 FIXED MARITIME MOBILE RADIONAVIGATION 451 454	117.6–126.0 FIXED MARITIME MOBILE RADIONAVIGATION 451 454				
126–129 RADIONAVIGATION 451	126–129 RADIONAVIGATION 451 Fixed Maritime Mobile 454 455				
129–130 FIXED MARITIME MOBILE RADIONAVIGATION 451 454	129–130 FIXED MARITIME MOBILE RADIONAVIGATION 451 454			451 454 US294	451 454 US294
130–148.5 MARITIME MOBILE /FIXED/ 454 457	130–160 FIXED MARITIME MOBILE RADIONAVIGATION	130–160 FIXED MARITIME MOBILE	130–160 FIXED MARITIME MOBILE	130–160 FIXED MARITIME MOBILE	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)
148.5–255 BROADCASTING	454	454	454 US294	454 US294	
	160–190 FIXED	160–190 FIXED Aeronautical Radio- navigation	160–190 FIXED MARITIME MOBILE	160–190 FIXED	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)
	459		459 US294	459 US294	
	190–200 AERONAUTICAL RADIO- NAVIGATION		190–200 AERONAUTICAL RADIO- NAVIGATION US18 US226 US294	190–200 AERONAUTICAL RADIO- NAVIGATION US18 US226 US294	

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
460 461 462 255–283.5 BROADCASTING /AERONAUTICAL RADIONAVIGATION/ 463	200–275 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile	200–285 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile	200–275 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile	200–275 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile	AVIATION (87)	
			US18 US294	US18 US294		
462 464 464A 283.5–315 MARITIME RADIO- NAVIGATION (radiobeacons) 466 /AERONAUTICAL RADIONAVIGATION/	275–285 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile Maritime Radionavigation (radiobeacons)		275–285 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile Maritime Radionavigation (radiobeacons)	275–285 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile Maritime Radionavigation (radiobeacons)		
			US18 US294	US18 US294		
464A 465 466A	285–315 MARITIME RADIO- NAVIGATION (radiobeacons) 466 /AERONAUTICAL RADIONAVIGATION/		285–325 MARITIME RADIO- NAVIGATION (radiobeacons) 466 Aeronautical Radio- navigation (radiobeacons)	285–325 MARITIME RADIO- NAVIGATION (radiobeacons) 466 Aeronautical Radio- navigation (radiobeacons)	AVIATION (87)	
			US18 US294	US18 US294		

315–325 AERONAUTICAL RADIO- NAVIGATION Maritime Radionavigation (radio Beacons) 466 465 467	315–325 AERONAUTICAL RADIO- NAVIGATION MARITIME RADIO- NAVIGATION (radio Beacons) 466	US18 US294	US18 US294		
325–405 AERONAUTICAL RADIO- NAVIGATION	325–405 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile Maritime Radionavigation (radio Beacons)	325–335 AERONAUTICAL RADIO- NAVIGATION (radio Beacons) Aeronautical Mobile Maritime Radionavigation (radio Beacons) US18 US294	325–335 AERONAUTICAL RADIO- NAVIGATION (radio Beacons) Aeronautical Mobile Maritime Radionavigation (radio Beacons) US18 US294	AVIATION (87)	
465	335–405 AERONAUTICAL RADIO- NAVIGATION Aeronautical Mobile	335–405 AERONAUTICAL RADIO- NAVIGATION (radio Beacons) Aeronautical Mobile US18 US294	335–405 AERONAUTICAL RADIO- NAVIGATION (radio Beacons) Aeronautical Mobile US18 US294	AVIATION (87)	
405–415 RADIONAVIGATION 468 465	405–415 RADIONAVIGATION 468 Aeronautical Mobile	405–415 RADIONAVIGATION 468 Aeronautical Mobile US18 US294	405–415 RADIONAVIGATION 468 Aeronautical Mobile US18 US294	AVIATION (87)	
415–435 AERONAUTICAL RADIO- NAVIGATION MARITIME MOBILE/ 470 465	415–435 MARITIME MOBILE 470 AERONAUTICAL RADIO- NAVIGATION 470A	415–435 AERONAUTICAL RADIO- NAVIGATION MARITIME MOBILE 470 469A US294	415–435 AERONAUTICAL RADIO- NAVIGATION MARITIME MOBILE 470 469A US294	AVIATION (87) MARITIME (80)	
435–495 MARITIME MOBILE 470 Aeronautical Radio- navigation 465 471 472A	469 469A 471 472A	435–495 MARITIME MOBILE 470 AERONAUTICAL RADIO- NAVIGATION 471 472A US231 US294	435–495 MARITIME MOBILE 470 MARITIME MOBILE 470 471 472A US231 US294	MARITIME (80)	
495–505	MOBILE (distress and calling) 472	495–505 MOBILE (distress and calling)	495–505 MOBILE (distress and calling) 472	MARITIME (80)	500 kHz: Distress and calling frequency

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
505–526.5 MARITIME MOBILE 470 /AERONAUTICAL RADIONAVIGATION/ Aeronautical Mobile Land Mobile 471	505–510 MARITIME MOBILE 470	505–526.5 MARITIME MOBILE 470 /AERONAUTICAL RADIONAVIGATION/ Aeronautical Mobile Land Mobile 471	505–510 MARITIME MOBILE 470	505–510 MARITIME MOBILE 470	MARITIME (80)	
	471		471	471		
	510–525 MOBILE 474 AERONAUTICAL RADIO- NAVIGATION		510–525 AERONAUTICAL RADIO- NAVIGATION (radiobeacons) MARITIME MOBILE (Ships only)	510–525 AERONAUTICAL RADIO- NAVIGATION (radiobeacons) MARITIME MOBILE (Ships only)	AVIATION (87) MARITIME (80)	518 kHz is used for inter- national NAVTEX in the Mar- itime Mo- bile Serv- ice
465 471 474 475 476 526.5–1606.5 BROADCASTING 478	525–535 BROADCASTING 477 AERONAUTICAL RADIO- NAVIGATION	471 526.5–535 BROADCASTING Mobile 479	474 US14 US18 US225	474 US14 US18 US225	AVIATION (87) PRIVATE LAND MOBILE (90)	530 kHz: Travelers information
			525–535 MOBILE AERONAUTICAL RADIO- NAVIGATION (radiobeacons)	525–535 MOBILE AERONAUTICAL RADIO- NAVIGATION (radiobeacons)		
			US18 US221 US239	US18 US221 US239		

Federal Communications Commission

§ 2.106

1606.5–1625 MARITIME MOBILE 480A /FIXED/ /LAND MOBILE/	535–1605 BROADCASTING	535–1606.5 BROADCASTING	535–1605	535–1705 BROADCASTING 480 Alaska Fixed (80) Auxiliary Broadcasting (74) Private Land Mobile (90)	RADIO BROADCASTING (AM) (73)	535–1705 kHz. Trav- elers infor- mation
	1605–1625 BROADCASTING 480	1606.5–1800 FIXED MOBILE RADIOLOCATION RADIONAVIGATION 482	1605–1615 Mobile	US238 US299 US321 NG128	DISASTER (99) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
	480A 481		US221			
	1625–1705 BROADCASTING /FIXED/ /MOBILE/ Radiolocation 480A		1615–1625 US 237 US299			
483 484			1625–1705 Radiolocation 480			
1625–1635 RADIOLOCATION 487						
485 486						
1635–1800 MARITIME MOBILE /FIXED/ /LAND MOBILE/ 480A	481		US238 US299			
483 484 488	1705–1800 FIXED MOBILE RADIOLOCATION AERONAUTICAL RADIO- NAVIGATION		1705–1800 FIXED MOBILE RADIOLOCATION	1705–1800 FIXED MOBILE RADIOLOCATION		
			US240	US240		

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
1800–1810 RADIOLOCATION 487	1800–1850 AMATEUR	1800–2000 AMATEUR FIXED MOBILE except aeronauti- cal mobile RADIO NAVIGATION Radiolocation	1800–1900	1800–1900 AMATEUR	AMATEUR (97)	
485 486						
1810–1850 AMATEUR 490 491 492 493						
1850–2000 FIXED MOBILE except aeronauti- cal mobile	1850–2000 AMATEUR FIXED MOBILE except aeronauti- cal mobile RADIOLOCATION RADIO NAVIGATION					
484 488 495	494	489	1900–2000 RADIOLOCATION US290	1900–2000 RADIOLOCATION US290	PRIVATE LAND MOBILE (90) Amateur (97)	
2000–2025 FIXED MOBILE except aeronauti- cal mobile (R) S5.92 S5.103	2000–2025 FIXED MOBILE	2000–2025 FIXED MOBILE	2000–2025 FIXED MOBILE US340	2000–2025 MARITIME MOBILE US340 NG19	MARITIME (80)	
2025–2045 FIXED MOBILE except aeronauti- cal mobile (R) Meteorological Aids S5.104 S5.92 S5.103	2025–2045 FIXED MOBILE	2025–2045 FIXED MOBILE	2025–2045 FIXED MOBILE US340	2025–2045 MARITIME MOBILE US340 NG19	MARITIME (80)	

2045–2065 FIXED MARITIME MOBILE LAND MOBILE S5.92	2045–2065 FIXED MOBILE	2045–2065 FIXED MOBILE	2045–2065 FIXED MOBILE US340	2045–2065 MARITIME MOBILE US340 NG19	MARITIME (80)	
2065–2107 FIXED MARITIME MOBILE LAND MOBILE S5.92	2065–2107 MARITIME MOBILE S5.105 S5.106	2065–2107 MARITIME MOBILE S5.105	2065–2107 MARITIME MOBILE S5.105 US296 US340	2065–2107 MARITIME MOBILE S5.105 US296 US340	MARITIME (80)	
2107–2160 FIXED MARITIME MOBILE LAND MOBILE S5.92	2107–2160 FIXED MOBILE	2107–2160 FIXED MOBILE	2107–2160 FIXED MOBILE US340	2107–2160 FIXED MARITIME MOBILE LAND MOBILE US340 NG19	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
2160–2170 RADIOLOCATION S5.93 S5.107	2160–2170 FIXED MOBILE	2160–2170 FIXED MOBILE	2160–2170 FIXED MOBILE US340	2160–2170 FIXED MARITIME MOBILE LAND MOBILE US340 NG19	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) PRIVATE LAND MOBILE (90)	
2170–2173.5 MARITIME MOBILE	2170–2173.5 MARITIME MOBILE	2170–2173.5 MARITIME MOBILE	2170–2173.5 MARITIME MOBILE (te- lephony) US340	2170–2173.5 MARITIME MOBILE US340	MARITIME (80)	
2173.5–2190.5 MOBILE (distress and calling) S5.108 S5.109 S5.110 S5.111	2173.5–2190.5 MOBILE (distress and calling) S5.108 S5.109 S5.110 S5.111	2173.5–2190.5 MOBILE (distress and calling) S5.108 S5.109 S5.110 S5.111	2173.5–2190.5 MOBILE (distress and calling) S5.108 S5.109 S5.110 S5.111 US279 US340	2173.5–2190.5 MOBILE (distress and calling) S5.108 S5.109 S5.110 S5.111 US279 US340	AVIATION (87) MARITIME (80)	2182 kHz: distress and calling
2190.5–2194 MARITIME MOBILE	2190.5–2194 MARITIME MOBILE	2190.5–2194 MARITIME MOBILE	2190.5–2194 MARITIME MOBILE (te- lephony) US340	2190.5–2194 MARITIME MOBILE US340	MARITIME (80)	

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
2194–2300 FIXED MOBILE except aeronauti- cal mobile (R)	2194–2300 FIXED MOBILE	2194–2300 FIXED MOBILE	2194–2300 FIXED MOBILE	2194–2300 FIXED LAND MOBILE MARITIME MOBILE	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
S5.92 S5.103 S5.112		S5.112	US340	US340 NG19		
2300–2495 FIXED MOBILE except aeronauti- cal mobile (R)	2300–2495 FIXED MOBILE BROADCASTING S5.113	2300–2495 FIXED MOBILE BROADCASTING S5.113	2300–2495 FIXED MOBILE	2300–2495 FIXED LAND MOBILE MARITIME MOBILE	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
S5.103			US340	US340 NG19		
2495–2498 FIXED MOBILE except aeronauti- cal mobile (R)	2495–2498 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz)	2495–2498 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz)	2495–2498 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz)	2495–2498 STANDARD FRE- QUENCY AND TIME SIGNAL		
BROADCASTING S5.113 S5.103			US340	US340		
2498–2501 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz)	2498–2501 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz)	2498–2501 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz)	2498–2501 STANDARD FRE- QUENCY AND TIME SIGNAL (2500 kHz) US340	2498–2501 STANDARD FRE- QUENCY AND TIME SIGNAL US340		2500 kHz: standard frequency
2501–2502 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	2501–2502 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	2501–2502 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	2501–2502 STANDARD FRE- QUENCY AND TIME SIGNAL US340 G106	2501–2502 STANDARD FRE- QUENCY AND TIME SIGNAL US340		

2502–2505 FIXED MOBILE except aeronauti- cal mobile (R) S5.92 S5.103 S5.114	2502–2505 STANDARD FRE- QUENCY AND TIME SIGNAL	2502–2505 STANDARD FRE- QUENCY AND TIME SIGNAL	2502–2505 STANDARD FREQUENCY AND TIME SIGNAL US340	2502–2505 STANDARD FREQUENCY AND TIME SIGNAL
2505–2605 FIXED MOBILE except aeronauti- cal mobile (R)	2505–2605 FIXED MOBILE	2505–2605 FIXED MOBILE	2505–2605 FIXED LAND MOBILE MARITIME MOBILE	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
S5.92 S5.103 S5.114			US285 US340	
2605–2625 FIXED MOBILE except aeronauti- cal mobile (R)	2605–2625 FIXED MOBILE	2605–2625 FIXED MOBILE	2605–2625 FIXED LAND MOBILE MARITIME MOBILE	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
S5.92 S5.103 S5.114			US285 US340	
2625–2650 MARITIME MOBILE MARITIME RADIO- NAVIGATION	2625–2650 FIXED MOBILE	2625–2650 FIXED MOBILE	2625–2650 FIXED LAND MOBILE MARITIME MOBILE	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
S5.92			US285 US340	
2650–2850 FIXED MOBILE except aeronauti- cal mobile (R)	2650–2850 FIXED MOBILE	2650–2850 FIXED MOBILE	2650–2850 FIXED LAND MOBILE MARITIME MOBILE	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
S5.92 S5.103			US285 US340	
2850–3025 AERONAUTICAL MOBILE (R) S5.111 S5.115	2850–3025 AERONAUTICAL MOBILE (R) S5.111 S5.115	2850–3025 AERONAUTICAL MOBILE (R) S5.111 S5.115	2850–3025 AERONAUTICAL MOBILE (R) S5.111 S5.115 US283 US340	AVIATION (87)

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
3025–3155 AERONAUTICAL MOBILE (OR)	3025–3155 AERONAUTICAL MOBILE (OR)	3025–3155 AERONAUTICAL MOBILE (OR)	3025–3155 AERONAUTICAL MOBILE (OR) US340	3025–3155 AERONAUTICAL MOBILE (OR) US340		
3155–3200 FIXED MOBILE except aeronauti- cal mobile (R)	3155–3200 FIXED MOBILE except aeronauti- cal mobile (R)	3155–3200 FIXED MOBILE except aeronauti- cal mobile (R)	3155–3200 FIXED MOBILE except aeronauti- cal mobile (R) US340	3155–3200 FIXED MOBILE except aeronauti- cal mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
S5.116 S5.117	S5.116	S5.116 S5.117	US340	US340		
3200–3230 FIXED MOBILE except aeronauti- cal mobile (R) BROADCASTING S5.113	3200–3230 FIXED MOBILE except aeronauti- cal mobile (R) BROADCASTING S5.113	3200–3230 FIXED MOBILE except aeronauti- cal mobile (R) BROADCASTING S5.113	3200–3230 FIXED MOBILE except aeronauti- cal mobile (R) US340	3200–3230 FIXED MOBILE except aeronauti- cal mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
S5.116	S5.116	S5.116	US340	US340		
3230–3400 FIXED MOBILE except aeronauti- cal mobile BROADCASTING S5.113	3230–3400 FIXED MOBILE except aeronauti- cal mobile BROADCASTING S5.113	3230–3400 FIXED MOBILE except aeronauti- cal mobile BROADCASTING S5.113	3230–3400 FIXED MOBILE except aeronauti- cal mobile Radiolocation US340	3230–3400 FIXED MOBILE except aeronauti- cal mobile Radiolocation US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
S5.116	S5.116 S5.118	S5.116 S5.118	US340	US340		
3400–3500 AERONAUTICAL MOBILE (R)	3400–3500 AERONAUTICAL MOBILE (R)	3400–3500 AERONAUTICAL MOBILE (R)	3400–3500 AERONAUTICAL MOBILE (R) US283 US340	3400–3500 AERONAUTICAL MOBILE (R) US283 US340	AVIATION (87)	

3500–3750 AMATEUR S5.120 FIXED MOBILE except aeronauti- cal mobile S5.92	3500–3750 AMATEUR S5.120 S5.119	3500–3750 AMATEUR S5.120 FIXED MOBILE	3500–3750 US340	3500–3750 AMATEUR S5.120 US340	AMATEUR (97)
3750–3800 AMATEUR S5.120 FIXED MOBILE except aeronauti- cal mobile S5.92	3750–3800 AMATEUR S5.120 FIXED MOBILE except aeronauti- cal mobile (R) S5.122	3750–3800 AMATEUR S5.120 FIXED MOBILE	3750–3800 AMATEUR S5.120 US340	3750–3800 AMATEUR S5.120 US340	AMATEUR (97)
3800–3900 FIXED AERONAUTICAL MOBILE (OR) LAND MOBILE	3800–3900 AMATEUR S5.120 FIXED MOBILE except aeronauti- cal mobile (R) S5.122	3800–3900 AMATEUR S5.120 FIXED MOBILE	3800–3900 AMATEUR S5.120 US340	3800–3900 AMATEUR S5.120 US340	AMATEUR (97)
3900–3950 AERONAUTICAL MOBILE (OR) S5.123	3900–3950 AMATEUR S5.120 FIXED MOBILE except aeronauti- cal mobile (R) S5.122	3900–3950 AERONAUTICAL MOBILE BROADCASTING	3900–3950 AMATEUR S5.120 US340	3900–3950 AMATEUR S5.120 US340	AMATEUR (97)
3950–4000 FIXED BROADCASTING	3950–4000 AMATEUR S5.120 FIXED MOBILE except aeronauti- cal mobile (R) S5.122 S5.124 S5.125	3950–4000 FIXED BROADCASTING S5.126	3950–4000 AMATEUR S5.120 US340	3950–4000 AMATEUR S5.120 US340	AMATEUR (97)
4000–4063 FIXED MARITIME MOBILE S5.127	4000–4063 FIXED MARITIME MOBILE S5.127	4000–4063 FIXED MARITIME MOBILE S5.127 S5.126	4000–4063 MARITIME MOBILE US236 US340	4000–4063 MARITIME MOBILE US236 US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)
4063–4438 MARITIME MOBILE S5.109 S5.110 S5.130 S5.131 S5.132 S5.128 S5.129	4063–4438 MARITIME MOBILE S5.109 S5.110 S5.130 S5.131 S5.132 S5.129	4063–4438 MARITIME MOBILE S5.109 S5.110 S5.130 S5.131 S5.132 S5.128 S5.129	4063–4438 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 US82 US296 US340	4063–4438 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 US82 US296 US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
4438–4650 FIXED MOBILE except aeronauti- cal mobile (R)	4438–4650 FIXED MOBILE except aeronauti- cal mobile (R)	4438–4650 FIXED MOBILE except aeronauti- cal mobile	4438–4650 FIXED MOBILE except aeronauti- cal mobile (R) US340	4438–4650 FIXED MOBILE except aeronauti- cal mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
4650–4700 AERONAUTICAL MOBILE (R)	4650–4700 AERONAUTICAL MOBILE (R)	4650–4700 AERONAUTICAL MOBILE (R)	4650–4700 AERONAUTICAL MOBILE (R) US282 US283 US340	4650–4700 AERONAUTICAL MOBILE (R) US282 US283 US340	AVIATION (87)	
4700–4750 AERONAUTICAL MOBILE (OR)	4700–4750 AERONAUTICAL MOBILE (OR)	4700–4750 AERONAUTICAL MOBILE (OR)	4700–4750 AERONAUTICAL MOBILE (OR) US340	4700–4750 AERONAUTICAL MOBILE (OR) US340		
4750–4850 FIXED AERONAUTICAL MOBILE (OR) LAND MOBILE BROADCASTING S5.113	4750–4850 FIXED MOBILE except aeronauti- cal mobile (R) BROADCASTING S5.113	4750–4850 FIXED BROADCASTING S5.113 Land Mobile	4750–4850 FIXED MOBILE except aeronauti- cal mobile (R) US340	4750–4850 FIXED MOBILE except aeronauti- cal mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
4850–4995 FIXED LAND MOBILE BROADCASTING S5.113	4850–4995 FIXED LAND MOBILE BROADCASTING S5.113	4850–4995 FIXED LAND MOBILE BROADCASTING S5.113	4850–4995 FIXED MOBILE US340	4850–4995 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
4995–5003 STANDARD FRE- QUENCY AND TIME SIGNAL (5000 kHz)	4995–5003 STANDARD FRE- QUENCY AND TIME SIGNAL (5000 kHz)	4995–5003 STANDARD FRE- QUENCY AND TIME SIGNAL (5000 kHz)	4995–5003 STANDARD FRE- QUENCY AND TIME SIGNAL (5000 kHz) US340	4995–5003 STANDARD FRE- QUENCY AND TIME SIGNAL US340		5000 kHz: standard frequency

5003-5005 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	5003-5005 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	5003-5005 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	5003-5005 STANDARD FRE- QUENCY AND TIME SIGNAL US340 G106	5003-5005 STANDARD FRE- QUENCY AND TIME SIGNAL US340	
5005-5060 FIXED BROADCASTING S5.113	5005-5060 FIXED BROADCASTING S5.113	5005-5060 FIXED BROADCASTING S5.113	5005-5060 FIXED	5005-5060 FIXED	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
5060-5250 FIXED MOBILE except aeronauti- cal mobile	5060-5250 FIXED MOBILE except aeronauti- cal mobile	5060-5250 FIXED MOBILE except aeronauti- cal mobile	5060-5250 FIXED MOBILE except aeronauti- cal mobile	5060-5250 FIXED MOBILE except aeronauti- cal mobile	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
S5.133			US212 US340	US212 US340	
5250-5450 FIXED MOBILE except aeronauti- cal mobile	5250-5450 FIXED MOBILE except aeronauti- cal mobile	5250-5450 FIXED MOBILE except aeronauti- cal mobile	5250-5450 FIXED MOBILE except aeronauti- cal mobile	5250-5450 FIXED MOBILE except aeronauti- cal mobile	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)
5450-5480 FIXED AERONAUTICAL MOBILE (OR) LAND MOBILE	5450-5480 FIXED AERONAUTICAL MOBILE (OR) LAND MOBILE	5450-5480 FIXED AERONAUTICAL MOBILE (OR) LAND MOBILE	5450-5480 FIXED AERONAUTICAL MOBILE (R) US283 US340	5450-5480 FIXED AERONAUTICAL MOBILE (R) US283 US340	AVIATION (87)
5480-5680 FIXED AERONAUTICAL MOBILE (R) S5.111 S5.115	5480-5680 FIXED AERONAUTICAL MOBILE (R) S5.111 S5.115	5480-5680 FIXED AERONAUTICAL MOBILE (R) S5.111 S5.115	5480-5680 FIXED AERONAUTICAL MOBILE (R) S5.111 S5.115 US283 US340	5480-5680 FIXED AERONAUTICAL MOBILE (R) S5.111 S5.115 US283 US340	AVIATION (87)

International table			United States table		FCC use designators	
Region 1—allocation kHz	Region 2—allocation kHz	Region 3—allocation kHz	Government Allocation kHz	Non-Government Allocation kHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
5680–5730 AERONAUTICAL MOBILE (OR) S5.111 S5.115	5680–5730 AERONAUTICAL MOBILE (OR) S5.111 S5.115	5680–5730 AERONAUTICAL MOBILE (OR) S5.111 S5.115	5680–5730 AERONAUTICAL MOBILE (OR) S5.111 S5.115 US340	5680–5730 AERONAUTICAL MOBILE (OR) S5.111 S5.115 US340		
5730–5900 FIXED LAND MOBILE	5730–5900 FIXED MOBILE except aeronauti- cal mobile (R)	5730–5900 FIXED MOBILE except aeronauti- cal mobile (R)	5730–5900 FIXED MOBILE except aeronauti- cal mobile (R) US340	5730–5900 FIXED MOBILE except aeronauti- cal mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
5900–5950 BROADCASTING S5.134 S5.135	5900–5950 BROADCASTING S5.134 S5.135	5900–5950 BROADCASTING S5.134 S5.135	5900–5950 FIXED MOBILE except aeronauti- cal mobile (R) US340	5900–5950 FIXED MOBILE except aeronautical mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
S5.136	S5.136	S5.136				
5950–6200 BROADCASTING	5950–6200 BROADCASTING	5950–6200 BROADCASTING	5950–6200 BROADCASTING US340	5950–6200 BROADCASTING US340	RADIO BROADCAST (HF)(73)	
6200–6525 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 S5.137	6200–6525 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 S5.137	6200–6525 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 S5.137	6200–6525 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 US82 US296 US340	6200–6525 MARITIME MOBILE S5.109 S5.110 S5.130 S5.132 US82 US296 US340	MARITIME (80)	
6525–6685 AERONAUTICAL MOBILE (R)	6525–6685 AERONAUTICAL MOBILE (R)	6525–6685 AERONAUTICAL MOBILE (R)	6525–6685 AERONAUTICAL MOBILE (R) US283 US340	6525–6685 AERONAUTICAL MOBILE (R) US283 US340	AVIATION (87)	
6685–6765 AERONAUTICAL MOBILE (OR)	6685–6765 AERONAUTICAL MOBILE (OR)	6685–6765 AERONAUTICAL MOBILE (OR)	6685–6765 AERONAUTICAL MOBILE (OR) US340	6685–6765 AERONAUTICAL MOBILE (OR) US340		

Federal Communications Commission

§ 2.106

6765–7000 FIXED LAND MOBILE S5.139 S5.138	6765–7000 FIXED LAND MOBILE S5.138	6765–7000 FIXED LAND MOBILE S5.138	6765–7000 FIXED MOBILE S5.138 US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	6780±15 kHz: industrial sci- entific, and medical
7000–7100 AMATEUR S5.120 AMATEUR-SATELLITE S5.140 S5.141	7000–7100 AMATEUR S5.120 AMATEUR-SATELLITE S5.142	7000–7100 AMATEUR S5.120 AMATEUR-SATELLITE S5.142	7000–7100 AMATEUR S5.120 AMATEUR-SATELLITE US340	AMATEUR (97)	
7100–7300 BROADCASTING	7100–7300 AMATEUR S5.120 S5.142	7100–7300 BROADCASTING S5.142	7100–7300 AMATEUR S5.120 S5.142 US340	AMATEUR (97)	
7300–7350 BROADCASTING S5.134 S5.135	7300–7350 BROADCASTING S5.134 S5.135	7300–7350 BROADCASTING S5.134 S5.135	7300–7350 FIXED Mobile US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
S5.143	S5.143	S5.143	US340		
7350–8100 FIXED Land Mobile	7350–8100 FIXED Land Mobile	7350–8100 FIXED Mobile US340	7350–8100 FIXED Mobile US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) PRIVATE LAND MOBILE (90)	
8100–8195 FIXED MARITIME MOBILE	8100–8195 FIXED MARITIME MOBILE	8100–8195 MARITIME MOBILE US236 US340	8100–8195 MARITIME MOBILE US236 US340	MARITIME (80)	
8195–8815 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145 S5.111	8195–8815 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145 S5.111	8195–8815 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145 S5.111 US82 US296 US340	8195–8815 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145 S5.111 US82 US296 US340	MARITIME (80)	

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
8815–8965 AERONAUTICAL MOBILE (R)	8815–8965 AERONAUTICAL MOBILE (R)	8815–8965 AERONAUTICAL MOBILE (R)	8815–8965 AERONAUTICAL MOBILE (R) US340	8815–8965 AERONAUTICAL MOBILE (R) US340	AVIATION (87)	
8965–9040 AERONAUTICAL MOBILE (OR)	8965–9040 AERONAUTICAL MOBILE (OR)	8965–9040 AERONAUTICAL MOBILE (OR)	8965–9040 AERONAUTICAL MOBILE (OR) US340	8965–9040 AERONAUTICAL MOBILE (OR) US340		
9040–9400 FIXED	9040–9400 FIXED	9040–9400 FIXED	9040–9400 FIXED US340	9040–9400 FIXED US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) Aviation (87)	
9400–9500 BROADCASTING S5.134 S5.135 S5.146	9400–9500 BROADCASTING S5.134 S5.135 S5.146	9400–9500 BROADCASTING S5.134 S5.135 S5.146	9400–9500 FIXED US340	9400–9500 FIXED US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80) Aviation (87)	
9500–9900 BROADCASTING S5.147 S5.148	9500–9900 BROADCASTING S5.147 S5.148	9500–9900 BROADCASTING S5.147 S5.148	9500–9900 BROADCASTING S5.147 S5.148 US235 US340	9500–9900 BROADCASTING S5.147 S5.148 US235 US340	RADIO BROADCAST (HF) (73) INTERNATIONAL FIXED PUBLIC (23)	
9900–9995 FIXED	9900–9995 FIXED	9900–9995 FIXED	9900–9995 FIXED US340	9900–9995 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	

9995-10003 STANDARD FRE- QUENCY AND TIME SIGNAL (10000 kHz) S5.111	9995-10003 STANDARD FRE- QUENCY AND TIME SIGNAL (10000 kHz) S5.111	9995-10003 STANDARD FRE- QUENCY AND TIME SIGNAL (10000 kHz) S5.111	9995-10003 STANDARD FRE- QUENCY AND TIME SIGNAL (10000 kHz) S5.111 US340	9995-10003 STANDARD FRE- QUENCY AND TIME SIGNAL S5.111 US340	10000 kHz: standard frequency
10003-10005 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	10003-10005 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	10003-10005 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	10003-10005 STANDARD FRE- QUENCY AND TIME SIGNAL S5.111 US340 G106	10003-10005 STANDARD FRE- QUENCY AND TIME SIGNAL S5.111 G106	
10005-10100 AERONAUTICAL MOBILE (R) S5.111	10005-10100 AERONAUTICAL MOBILE (R) S5.111	10005-10100 AERONAUTICAL MOBILE (R) S5.111	10005-10100 AERONAUTICAL MOBILE (R) S5.111 US283 US340	10005-10100 AERONAUTICAL MOBILE (R) S5.111 US283 US340	AVIATION (87)
10100-10150 FIXED Amateur S5.120	10100-10150 FIXED Amateur S5.120	10100-10150 FIXED Amateur S5.120	10100-10150 FIXED US247 US340	10100-10150 AMATEUR S5.120 US247 US340	AMATEUR (97)
10150-11175 FIXED Mobile except aeronautical mobile (R)	10150-11175 FIXED Mobile except aeronautical mobile (R)	10150-11175 FIXED Mobile except aeronautical mobile (R)	10150-11175 FIXED Mobile except aeronautical mobile (R) US340	10150-11175 FIXED Mobile except aeronautical mobile (R) US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)
11175-11275 AERONAUTICAL MOBILE (OR)	11175-11275 AERONAUTICAL MOBILE (OR)	11175-11275 AERONAUTICAL MOBILE (OR)	11175-11275 AERONAUTICAL MOBILE (OR) US340	11175-11275 AERONAUTICAL MOBILE (OR) US340	
11275-11400 AERONAUTICAL MOBILE (R)	11275-11400 AERONAUTICAL MOBILE (R)	11275-11400 AERONAUTICAL MOBILE (R)	11275-11400 AERONAUTICAL MOBILE (R) US283 US340	11275-11400 AERONAUTICAL MOBILE (R) US283 US340	AVIATION (87)
11400-11600 FIXED	11400-11600 FIXED	11400-11600 FIXED	11400-11600 FIXED US340	11400-11600 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
11600–11650 BROADCASTING S5.134 S5.135 S5.146	11600–11650 BROADCASTING S5.134 S5.135 S5.146	11600–11650 BROADCASTING S5.134 S5.135 S5.146	11600–11650 FIXED US340	11600–11650 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
11650–12050 BROADCASTING S5.147 S5.148	11650–12050 BROADCASTING S5.147 S5.148	11650–12050 BROADCASTING S5.147 S5.148	11650–12050 BROADCASTING US235 US340	11650–12050 BROADCASTING US235 US340	RADIO BROADCAST (HF)(73) INTERNATIONAL FIXED PUBLIC (23)	
12050–12100 BROADCASTING S5.134 S5.135 S5.146	12050–12100 BROADCASTING S5.134 S5.135 S5.146	12050–12100 BROADCASTING S5.134 S5.135 S5.146	12050–12100 FIXED US340	12050–12100 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
12100–12230 FIXED	12100–12230 FIXED	12100–12230 FIXED	12100–12230 FIXED US340	12100–12230 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
12230–13200 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	12230–13200 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	12230–13200 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	12230–13200 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145 US82 US296 US340	12230–13200 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145 US82 US296 US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
13200–13260 AERONAUTICAL MOBILE (OR)	13200–13260 AERONAUTICAL MOBILE (OR)	13200–13260 AERONAUTICAL MOBILE (OR)	13200–13260 AERONAUTICAL MOBILE (OR) US340	13200–13260 AERONAUTICAL MOBILE (OR) US340		
13260–13360 AERONAUTICAL MOBILE (R)	13260–13360 AERONAUTICAL MOBILE (R)	13260–13360 AERONAUTICAL MOBILE (R)	13260–13360 AERONAUTICAL MOBILE (R) US283 US340	13260–13360 AERONAUTICAL MOBILE (R) US283 US340	AVIATION (87)	

13360–13410 FIXED RADIO ASTRONOMY S5.149	13360–13410 FIXED RADIO ASTRONOMY S5.149	13360–13410 FIXED RADIO ASTRONOMY S5.149	13360–13410 FIXED RADIO ASTRONOMY S5.149	13360–13410 FIXED RADIO ASTRONOMY S5.149	13360–13410 FIXED RADIO ASTRONOMY S5.149
13410–13570 FIXED MOBILE except aeronautical mobile (R)	13410–13570 FIXED MOBILE except aeronautical mobile (R)	13410–13570 FIXED MOBILE except aeronautical mobile (R)	13410–13570 FIXED MOBILE except aeronautical mobile (R)	13410–13570 FIXED MOBILE except aeronautical mobile (R)	13410–13570 FIXED MOBILE except aeronautical mobile (R)
S5.150	S5.150	S5.150	S5.150	S5.150	S5.150
13570–13600 BROADCASTING S5.134 S5.135	13570–13600 BROADCASTING S5.134 S5.135	13570–13600 BROADCASTING S5.134 S5.135	13570–13600 BROADCASTING S5.134 S5.135	13570–13600 BROADCASTING S5.134 S5.135	13570–13600 BROADCASTING S5.134 S5.135
S5.151	S5.151	S5.151	S5.151	S5.151	S5.151
13600–13800 BROADCASTING	13600–13800 BROADCASTING	13600–13800 BROADCASTING	13600–13800 BROADCASTING	13600–13800 BROADCASTING	13600–13800 BROADCASTING
S5.148	S5.148	S5.148	S5.148	S5.148	S5.148
13800–13870 BROADCASTING S5.134 S5.135	13800–13870 BROADCASTING S5.134 S5.135	13800–13870 BROADCASTING S5.134 S5.135	13800–13870 BROADCASTING S5.134 S5.135	13800–13870 BROADCASTING S5.134 S5.135	13800–13870 BROADCASTING S5.134 S5.135
S5.151	S5.151	S5.151	S5.151	S5.151	S5.151
13870–14000 FIXED MOBILE except aeronautical mobile (R)	13870–14000 FIXED MOBILE except aeronautical mobile (R)	13870–14000 FIXED MOBILE except aeronautical mobile (R)	13870–14000 FIXED MOBILE except aeronautical mobile (R)	13870–14000 FIXED MOBILE except aeronautical mobile (R)	13870–14000 FIXED MOBILE except aeronautical mobile (R)
14000–14250 AMATEUR S5.120 AMATEUR-SATELLITE	14000–14250 AMATEUR S5.120 AMATEUR-SATELLITE	14000–14250 AMATEUR S5.120 AMATEUR-SATELLITE	14000–14250 AMATEUR S5.120 AMATEUR-SATELLITE	14000–14250 AMATEUR S5.120 AMATEUR-SATELLITE	14000–14250 AMATEUR S5.120 AMATEUR-SATELLITE
14250–14350 AMATEUR S5.120 S5.152	14250–14350 AMATEUR S5.120 S5.152	14250–14350 AMATEUR S5.120 S5.152	14250–14350 AMATEUR S5.120 S5.152	14250–14350 AMATEUR S5.120 S5.152	14250–14350 AMATEUR S5.120 S5.152

13560±7
kHz:
industrial,
scientific
and medi-
cal

AVIATION (87)
INTERNATIONAL FIXED
PUBLIC (23)

13410–13570
FIXED

13410–13570
FIXED
Mobile except aeronautical
mobile (R)

13410–13570
FIXED
MOBILE except aeronautical
mobile (R)

13410–13570
FIXED
MOBILE except aeronautical
mobile (R)

13410–13570
FIXED
MOBILE except aeronautical
mobile (R)

13410–13570
FIXED
MOBILE except aeronautical
mobile (R)

AVIATION (87)
INTERNATIONAL FIXED
PUBLIC (23)

13570–13600
FIXED

13570–13600
FIXED
Mobile except aeronautical
mobile (R)

13570–13600
FIXED
MOBILE except aeronautical
mobile (R)

13570–13600
FIXED
MOBILE except aeronautical
mobile (R)

13570–13600
FIXED
MOBILE except aeronautical
mobile (R)

13570–13600
FIXED
MOBILE except aeronautical
mobile (R)

RADIO BROADCAST
(HF)(73)
INTERNATIONAL FIXED
PUBLIC (23)

13600–13800
BROADCASTING

13600–13800
BROADCASTING

13600–13800
BROADCASTING

13600–13800
BROADCASTING

13600–13800
BROADCASTING

13600–13800
BROADCASTING

AVIATION (87)
INTERNATIONAL FIXED
PUBLIC (23)

13800–13870
FIXED

13800–13870
FIXED
Mobile except aeronautical
mobile (R)

13800–13870
FIXED
MOBILE except aeronautical
mobile (R)

13800–13870
FIXED
MOBILE except aeronautical
mobile (R)

13800–13870
FIXED
MOBILE except aeronautical
mobile (R)

13800–13870
FIXED
MOBILE except aeronautical
mobile (R)

AVIATION (87)
INTERNATIONAL FIXED
PUBLIC (23)

13870–14000
FIXED

13870–14000
FIXED
Mobile except aeronautical
mobile (R)

13870–14000
FIXED
MOBILE except aeronautical
mobile (R)

13870–14000
FIXED
MOBILE except aeronautical
mobile (R)

13870–14000
FIXED
MOBILE except aeronautical
mobile (R)

13870–14000
FIXED
MOBILE except aeronautical
mobile (R)

AMATEUR (97)

14000–14250
AMATEUR S5.120
AMATEUR-SATELLITE

14000–14250
AMATEUR S5.120
AMATEUR-SATELLITE

14000–14250
AMATEUR S5.120
AMATEUR-SATELLITE

14000–14250
AMATEUR S5.120
AMATEUR-SATELLITE

14000–14250
AMATEUR S5.120
AMATEUR-SATELLITE

14000–14250
AMATEUR S5.120
AMATEUR-SATELLITE

AMATEUR (97)

14250–14350
AMATEUR S5.120
US340

14250–14350
AMATEUR S5.120
US340

14250–14350
AMATEUR S5.120
S5.152

14250–14350
AMATEUR S5.120
S5.152

14250–14350
AMATEUR S5.120
S5.152

14250–14350
AMATEUR S5.120
S5.152

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
14350–14990 FIXED Mobile except aeronautical mobile (R)	14350–14990 FIXED Mobile except aeronautical mobile (R)	14350–14990 FIXED Mobile except aeronautical mobile (R)	14350–14990 FIXED Mobile except aeronautical mobile (R) US340	14350–14990 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
14990–15005 STANDARD FRE- QUENCY AND TIME SIGNAL (15000 kHz) S5.111	14990–15005 STANDARD FRE- QUENCY AND TIME SIGNAL (15000 kHz) S5.111	14990–15005 STANDARD FRE- QUENCY AND TIME SIGNAL (15000 kHz) S5.111	14990–15005 STANDARD FRE- QUENCY AND TIME SIGNAL (15000 kHz) S5.111 US340	14990–15005 STANDARD FRE- QUENCY AND TIME SIGNAL S5.111 US340		15000 kHz: standard frequency
15005–15010 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	15005–15010 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	15005–15010 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	15005–15010 STANDARD FRE- QUENCY AND TIME SIGNAL US340 G106	15005–15010 STANDARD FRE- QUENCY AND TIME SIGNAL US340		
15010–15100 AERONAUTICAL MOBILE (OR)	15010–15100 AERONAUTICAL MOBILE (OR)	15010–15100 AERONAUTICAL MOBILE (OR)	15010–15100 AERONAUTICAL MOBILE (OR) US340	15010–15100 AERONAUTICAL MOBILE (OR) US340		
15100–15600 BROADCASTING S5.148	15100–15600 BROADCASTING S5.148	15100–15600 BROADCASTING S5.148	15100–15600 BROADCASTING S5.148 US340	15100–15600 BROADCASTING S5.148 US340	RADIO BROADCAST (HF)(73) INTERNATIONAL FIXED PUBLIC (23)	
15600–15800 BROADCASTING S5.134 S5.135 S5.146	15600–15800 BROADCASTING S5.134 S5.135 S5.146	15600–15800 BROADCASTING S5.134 S5.135 S5.146	15600–15800 FIXED US340	15600–15800 FIXED US340	AVIATION (87) INTERNATIONAL PUBLIC FIXED (23)	
15800–16360 FIXED S5.153	15800–16360 FIXED S5.153	15800–16360 FIXED S5.153	15800–16360 FIXED US340	15800–16360 FIXED US340	AVIATION (87) INTERNATIONAL PUBLIC FIXED (23)	

16360–17410 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	16360–17410 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	16360–17410 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	16360–17410 MARITIME MOBILE S5.109 S5.110 S5.132 S5.145	MARITIME (80)	
17410–17480 FIXED	17410–17480 FIXED	17410–17480 FIXED	17410–17480 FIXED	AVIATION (87) INTERNATIONAL PUBLIC FIXED (23)	
17480–17550 BROADCASTING S5.134 S5.135 S5.146	17480–17550 BROADCASTING S5.134 S5.135 S5.146	17480–17550 BROADCASTING S5.134 S5.135 S5.146	17480–17550 FIXED US340	AVIATION (87) INTERNATIONAL PUBLIC FIXED (23)	
17550–17900 BROADCASTING S5.148	17550–17900 BROADCASTING S5.148	17550–17900 BROADCASTING S5.148	17550–17900 BROADCASTING S5.148 US340	RADIO BROADCAST (HF)(73) INTERNATIONAL FIXED PUBLIC (23)	
17900–17970 AERONAUTICAL MOBILE (R)	17900–17970 AERONAUTICAL MOBILE (R)	17900–17970 AERONAUTICAL MOBILE (R)	17900–17970 AERONAUTICAL MOBILE (R) US283 US340	AVIATION (87)	
17970–18030 AERONAUTICAL MOBILE (OR)	17970–18030 AERONAUTICAL MOBILE (OR)	17970–18030 AERONAUTICAL MOBILE (OR)	17970–18030 AERONAUTICAL MOBILE (OR) US340		
18030–18052 FIXED	18030–18052 FIXED	18030–18052 FIXED	18030–18052 FIXED US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
18052–18068 FIXED Space Research	18052–18068 FIXED Space Research	18052–18068 FIXED Space Research	18052–18068 FIXED US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
18068–18168 AMATEUR S5.120 AMATEUR-SATELLITE S5.154	18068–18168 AMATEUR S5.120 AMATEUR-SATELLITE	18068–18168 AMATEUR S5.120 AMATEUR-SATELLITE	18068–18168 US340	18068–18168 AMATEUR S5.120 AMATEUR-SATELLITE US340	AMATEUR (97) INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
18168–18780 FIXED Mobile except aeronautical mobile	18168–18780 FIXED Mobile except aeronautical mobile	18168–18780 FIXED Mobile except aeronautical mobile	18168–18780 FIXED Mobile US340	18168–18780 FIXED Mobile US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23) MARITIME 80	
18780–18900 MARITIME MOBILE	18780–18900 MARITIME MOBILE	18780–18900 MARITIME MOBILE	18780–18900 MARITIME MOBILE US82 US296 US340	18780–18900 MARITIME MOBILE US82 US296 US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
18900–19020 BROADCASTING S5.134 S5.135 S5.146	18900–19020 BROADCASTING S5.134 S5.135 S5.146	18900–19020 BROADCASTING S5.134 S5.135 S5.146	18900–19020 FIXED US340	18900–19020 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
19020–19680 FIXED	19020–19680 FIXED	19020–19680 FIXED	19020–19680 FIXED US340	19020–19680 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
19680–19800 MARITIME MOBILE S5.132	19680–19800 MARITIME MOBILE S5.132	19680–19800 MARITIME MOBILE S5.132	19680–19800 MARITIME MOBILE S5.132 US340	19680–19800 MARITIME MOBILE S5.132 US340	MARITIME (80)	

19800-19900 FIXED	19800-19900 FIXED	19800-19900 FIXED	19800-19900 FIXED	19800-19900 FIXED	19800-19900 FIXED	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
19900-19995 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	19900-19995 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	19900-19995 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	19900-19995 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	19900-19995 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111	19900-19995 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research S5.111		
19995-20010 STANDARD FRE- QUENCY AND TIME SIGNAL (20000 kHz) S5.111	19995-20010 STANDARD FRE- QUENCY AND TIME SIGNAL (20000 kHz) S5.111	19995-20010 STANDARD FRE- QUENCY AND TIME SIGNAL (20000 kHz) S5.111	19995-20010 STANDARD FRE- QUENCY AND TIME SIGNAL (20000 kHz) S5.111	19995-20010 STANDARD FRE- QUENCY AND TIME SIGNAL S5.111	19995-20010 STANDARD FRE- QUENCY AND TIME SIGNAL S5.111	2000 kHz: standard fre- quency	
20010-21000 FIXED Mobile	20010-21000 FIXED Mobile	20010-21000 FIXED Mobile	20010-21000 FIXED Mobile	20010-21000 FIXED Mobile US340	20010-21000 FIXED US340		
21000-21450 AMATEUR S5.120 AMATEUR-SATELLITE	21000-21450 AMATEUR S5.120 AMATEUR-SATELLITE	21000-21450 AMATEUR S5.120 AMATEUR-SATELLITE	21000-21450 AMATEUR S5.120 AMATEUR-SATELLITE	21000-21450 US340	21000-21450 AMATEUR S5.120 AMATEUR-SATELLITE US340	AMATEUR (97)	
21450-21850 BROADCASTING	21450-21850 BROADCASTING	21450-21850 BROADCASTING	21450-21850 BROADCASTING	21450-21850 BROADCASTING	21450-21850 BROADCASTING	INTERNATIONAL FIXED PUBLIC (23) RADIO BROADCAST (HF)(73)	
S5.148	S5.148	S5.148	S5.148	S5.148	S5.148		
21850-21870 FIXED S5.155A	21850-21870 FIXED	21850-21870 FIXED	21850-21870 FIXED	21850-21870 FIXED	21850-21870 FIXED	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
S5.155				US340	US340		
21870-21924 FIXED S5.155B	21870-21924 FIXED S5.155B	21870-21924 FIXED S5.155B	21870-21924 FIXED S5.155B	21870-21924 FIXED	21870-21924 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
21924–22000 AERONAUTICAL MOBILE (R)	21924–22000 AERONAUTICAL MOBILE (R)	21924–22000 AERONAUTICAL MOBILE (R)	21924–22000 AERONAUTICAL MOBILE (R) US340	21924–22000 AERONAUTICAL MOBILE (R) US340	AVIATION (87)	
22000–22855 MARITIME MOBILE S5.132 S5.156	22000–22855 MARITIME MOBILE S5.132	22000–22855 MARITIME MOBILE S5.132	22000–22855 MARITIME MOBILE S5.132 US82 US296 US340	22000–22855 MARITIME MOBILE S5.132 US82 US296 US340	INTERNATIONAL FIXED PUBLIC (23) MARITIME (80)	
22855–23000 FIXED S5.156	22855–23000 FIXED	22855–23000 FIXED	22855–23000 FIXED US340	22855–23000 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
23000–23200 FIXED Mobile except aeronautical mobile (R) S5.156	23000–23200 FIXED Mobile except aeronautical mobile (R)	23000–23200 FIXED Mobile except aeronautical mobile (R)	23000–23200 FIXED Mobile except aeronautical mobile (R) US340	23000–23200 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
23200–23350 AERONAUTICAL MOBILE (OR) FIXED S5.156A	23200–23350 AERONAUTICAL MOBILE (OR) FIXED S5.156A	23200–23350 AERONAUTICAL MOBILE (OR) FIXED S5.156A	23200–23350 AERONAUTICAL MOBILE (OR) US340	23200–23350 AERONAUTICAL MOBILE (OR) US340		
23350–24000 FIXED MOBILE except aeronauti- cal mobile S5.157	23350–24000 FIXED MOBILE except aeronauti- cal mobile S5.157	23350–24000 FIXED MOBILE except aeronauti- cal mobile S5.157	23350–24000 FIXED MOBILE except aeronauti- cal mobile US340	23350–24000 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
24000–24890 FIXED LAND MOBILE	24000–24890 FIXED LAND MOBILE	24000–24890 FIXED LAND MOBILE	24000–24890 FIXED MOBILE except aeronauti- cal mobile US340	24000–24890 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	

Federal Communications Commission

§ 2.106

24890–24990 AMATEUR S5.120 AMATEUR-SATELLITE	24890–24990 AMATEUR S5.120 AMATEUR-SATELLITE	24890–24990 US340	24890–24990 AMATEUR S5.120 AMATEUR-SATELLITE US340	AMATEUR (97)	
24990–25005 STANDARD FRE- QUENCY AND TIME SIGNAL (25000 kHz)	24990–25005 STANDARD FRE- QUENCY AND TIME SIGNAL (25000 kHz)	24990–25005 STANDARD FRE- QUENCY AND TIME SIGNAL US340	24990–25005 STANDARD FRE- QUENCY AND TIME SIGNAL US340		25000 kHz: standard fre- quency
25005–25010 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	25005–25010 STANDARD FRE- QUENCY AND TIME SIGNAL Space Research	25005–25010 STANDARD FRE- QUENCY AND TIME SIGNAL US340 G106	25005–25010 STANDARD FRE- QUENCY AND TIME SIGNAL US340		
25010–25070 FIXED MOBILE except aeronauti- cal mobile	25010–25070 FIXED MOBILE except aeronauti- cal mobile	25010–25070	25010–25070 LAND MOBILE US340 NG112	PRIVATE LAND MOBILE (90)	
25070–25210 MARITIME MOBILE	25070–25210 MARITIME MOBILE	25070–25210 MARITIME MOBILE US82 US281 US296 US340	25070–25210 MARITIME MOBILE US82 US281 US296 US340 NG112	MARITIME (80) PRIVATE LAND MOBILE (90)	
25210–25330 FIXED MOBILE except aeronauti- cal mobile	25210–25330 FIXED MOBILE except aeronauti- cal mobile	25210–25330 US340	25210–25330 LAND MOBILE US340	PRIVATE LAND MOBILE (90)	
25330–25550 FIXED MOBILE except aeronauti- cal mobile	25330–25550 FIXED MOBILE except aeronauti- cal mobile	25330–25550 FIXED MOBILE except aeronauti- cal mobile US340	25330–25550 US340		
25550–25670 RADIO ASTRONOMY S5.149	25550–25670 RADIO ASTRONOMY S5.149	25550–25670 RADIO ASTRONOMY US74 S5.149	25550–25670 RADIO ASTRONOMY US74 S5.149		

International table			United States table		FCC use designators	
Region 1—allocation kHz (1)	Region 2—allocation kHz (2)	Region 3—allocation kHz (3)	Government Allocation kHz (4)	Non-Government Allocation kHz (5)	Rule part(s) (6)	Special-use frequencies (7)
25670–26100 BROADCASTING	25670–26100 BROADCASTING	25670–26100 BROADCASTING	25670–26100 BROADCASTING US25 US340	25670–26100 BROADCASTING US25 US340	RADIO BROADCAST (HF) (73) Remote Pickup (74D)	
26100–26175 MARITIME MOBILE S5.132	26100–26175 MARITIME MOBILE S5.132	26100–26175 MARITIME MOBILE S5.132	26100–26175 MARITIME MOBILE S5.132 US340	26100–26175 MARITIME MOBILE S5.132 US340	AUXILIARY BROAD- CASTING (74) MARITIME (80)	
26175–26480 FIXED MOBILE except aeronauti- cal mobile	26175–26480 FIXED MOBILE except aeronauti- cal mobile	26175–26480 FIXED MOBILE except aeronauti- cal mobile	26175–26480 US340	26175–26480 LAND MOBILE US340	AUXILIARY BROAD- CASTING (74)	
26480–26950 FIXED MOBILE except aeronauti- cal mobile	26480–26950 FIXED MOBILE except aeronauti- cal mobile	26480–26950 FIXED MOBILE except aeronauti- cal mobile	26480–26950 FIXED MOBILE except aeronauti- cal mobile US10 US340	26480–26950 US10 US340		
26950–26960 FIXED MOBILE except aeronauti- cal mobile S5.150	26950–26960 FIXED MOBILE except aeronauti- cal mobile S5.150	26950–26960 FIXED MOBILE except aeronauti- cal mobile S5.150	26950–26960 S5.150 US340	26950–26960 FIXED S5.150 US340	INTERNATIONAL FIXED PUBLIC (23)	
26960–27230 FIXED MOBILE except aeronauti- cal mobile	26960–27230 FIXED MOBILE except aeronauti- cal mobile	26960–27230 FIXED MOBILE except aeronauti- cal mobile	26960–27230 S5.150 US340	26960–27230 MOBILE except aeronauti- cal mobile S5.150 US340	PERSONAL (95)	27120±163 kHz: industrial, scientific and medi- cal

27230–27410 FIXED MOBILE except aeronauti- cal mobile S5.150	27230–27410 FIXED MOBILE except aeronauti- cal mobile S5.150	27230–27410 FIXED MOBILE except aeronauti- cal mobile S5.150	27230–27410 FIXED MOBILE except aeronauti- cal mobile S5.150 US340	PERSONAL (95) PRIVATE LAND MOBILE (90)		
27410–27500 FIXED MOBILE except aeronauti- cal mobile	27410–27500 FIXED MOBILE except aeronauti- cal mobile	27410–27500 FIXED MOBILE except aeronauti- cal mobile	27410–27500 FIXED LAND MOBILE US340	PRIVATE LAND MOBILE (90)		
International table			United States table			
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
			FCC use designators			
27.5–27.54 METEOROLOGICAL AIDS FIXED MOBILE	27.5–27.54 METEOROLOGICAL AIDS FIXED MOBILE	27.5–27.54 METEOROLOGICAL AIDS FIXED MOBILE	27.5–27.54 FIXED LAND MOBILE US340	27.5–27.54 FIXED LAND MOBILE US340	PRIVATE LAND MOBILE (90)	
27.54–28 METEOROLOGICAL AIDS FIXED MOBILE	27.54–28 METEOROLOGICAL AIDS FIXED MOBILE	27.54–28 METEOROLOGICAL AIDS FIXED MOBILE	27.54–28 FIXED MOBILE US298 US340	27.54–28 US298 US340		
28–29.7 AMATEUR AMATEUR-SATELLITE	28–29.7 AMATEUR AMATEUR-SATELLITE	28–29.7 AMATEUR AMATEUR-SATELLITE	28–29.7 US340	28–29.7 AMATEUR AMATEUR-SATELLITE US340	AMATEUR (97)	
29.7–29.8 FIXED MOBILE	29.7–29.8 FIXED MOBILE	29.7–29.8 FIXED MOBILE	29.7–29.8 US340	29.7–29.8 LAND MOBILE US340	PRIVATE LAND MOBILE (90)	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
29.8–29.89 FIXED MOBILE	29.8–29.89 FIXED MOBILE	29.8–29.89 FIXED MOBILE	29.8–29.89 US340	29.8–29.89 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
29.89–29.91 FIXED MOBILE	29.89–29.91 FIXED MOBILE	29.89–29.91 FIXED MOBILE	29.89–29.91 FIXED MOBILE US340	29.89–29.91 FIXED MOBILE US340		
29.91–30 FIXED MOBILE	29.91–30 FIXED MOBILE	29.91–30 FIXED MOBILE	29.91–30 US340	29.91–30 FIXED US340	AVIATION (87) INTERNATIONAL FIXED PUBLIC (23)	
30–30.005 FIXED MOBILE	30–30.005 FIXED MOBILE	30–30.005 FIXED MOBILE	30–30.005 FIXED MOBILE	30–30.005 FIXED MOBILE		
30.005–30.01 SPACE OPERATIONS (satellite identification) FIXED MOBILE SPACE RESEARCH	30.005–30.01 SPACE OPERATIONS (satellite identification) FIXED MOBILE SPACE RESEARCH	30.005–30.01 SPACE OPERATIONS (satellite identification) FIXED MOBILE SPACE RESEARCH	30.005–30.01 FIXED MOBILE	30.005–30.01		
30.01–30.56 FIXED MOBILE	30.01–30.56 FIXED MOBILE	30.01–30.56 FIXED MOBILE	30.01–30.56 FIXED MOBILE	30.01–30.56 FIXED MOBILE		
30.56–32 FIXED MOBILE	30.56–32 FIXED MOBILE	30.56–32 FIXED MOBILE	30.56–32	30.56–32 FIXED LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	

32–33 FIXED MOBILE	32–33 FIXED MOBILE	32–33 FIXED MOBILE	32–33 FIXED MOBILE	32–33		
33–34 FIXED MOBILE	33–34 FIXED MOBILE	33–34 FIXED MOBILE	33–34 FIXED MOBILE	33–34 FIXED LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
34–35 FIXED MOBILE	34–35 FIXED MOBILE	34–35 FIXED MOBILE	34–35 FIXED MOBILE	34–35		
35–35.19 FIXED MOBILE	35–35.19 FIXED MOBILE	35–35.19 FIXED MOBILE	35–35.19 FIXED MOBILE	35–35.19 FIXED LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
35.19–35.69 FIXED MOBILE	35.19–35.69 FIXED MOBILE	35.19–35.69 FIXED MOBILE	35.19–35.69 FIXED MOBILE	35.19–35.69 FIXED LAND MOBILE NG124	PUBLIC MOBILE (22) PRIVATE LAND MOBILE (90)	
35.69–36 FIXED MOBILE	35.69–36 FIXED MOBILE	35.69–36 FIXED MOBILE	35.69–36 FIXED MOBILE	35.69–36 FIXED LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
36–37 FIXED MOBILE	36–37 FIXED MOBILE	36–37 FIXED MOBILE	36–37 FIXED MOBILE	36–37 US220		
37–37.5 FIXED MOBILE	37–37.5 FIXED MOBILE	37–37.5 FIXED MOBILE	37–37.5 FIXED MOBILE	37–37.5 LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
37.5–38.25	FIXED MOBILE Radio Astronomy		37.5–38.0 Radio Astronomy 547	37.5–38.0 LAND MOBILE Radio Astronomy 547 NG59 NG124	PRIVATE LAND MOBILE (90)	
	547		38.0–38.25 FIXED MOBILE RADIO ASTRONOMY 547 US81	38.0–38.25 RADIO ASTRONOMY 547 US81		

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
38.25–39 FIXED MOBILE	38.25–39 FIXED MOBILE	38.25–39 FIXED MOBILE	38.25–39 FIXED MOBILE	38.25–39		
39–39.986 FIXED MOBILE	39–39.986 FIXED MOBILE	39–39.986 FIXED MOBILE	39–39.986	39–39.986 LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
39.986–40 FIXED MOBILE Space Research	39.986–40 FIXED MOBILE Space Research	39.986–40 FIXED MOBILE Space Research	39.986–40	39.986–40 LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
40–40.02 FIXED MOBILE Space Research	40–40.02 FIXED MOBILE Space Research	40–40.02 FIXED MOBILE Space Research	40–40.02 FIXED MOBILE	40–40.02		
40.02–40.98 FIXED MOBILE	40.02–40.98 FIXED MOBILE	40.02–40.98 FIXED MOBILE	40.02–40.98 FIXED MOBILE	40.02–40.98		40.68±0.2 MHz: Industrial, scientific and medi- cal fre- quencies.
548	548	548	548 US210	548 US210		
40.98–41.015 FIXED MOBILE Space Research 549	40.98–41.015 FIXED MOBILE Space Research	40.98–41.015 FIXED MOBILE Space Research 550	40.98–41.015 FIXED MOBILE	40.98–41.015		
41.015–42 FIXED MOBILE 549	41.015–42 FIXED MOBILE	41.015–42 FIXED MOBILE 550	41.015–42 FIXED MOBILE US220	41.015–42 US220		

42–43.19 FIXED MOBILE 549	42–43.19 FIXED MOBILE	42–43.19 FIXED MOBILE 550	42–43.19	42–43.19 FIXED LAND MOBILE NG124 NG141	PRIVATE LAND MOBILE (90)	
43.19–43.69 FIXED MOBILE 549	43.19–43.69 FIXED MOBILE	43.19–43.69 FIXED MOBILE 550	43.19–43.69	43.19–43.69 FIXED LAND MOBILE	PUBLIC MOBILE (22) PRIVATE LAND MOBILE (90)	
43.69–44 FIXED MOBILE 549	43.69–44 FIXED MOBILE	43.69–44 FIXED MOBILE 550	43.69–44	43.69–44 LAND MOBILE NG141	PRIVATE LAND MOBILE (90)	
44–46.6 FIXED MOBILE	44–46.6 FIXED MOBILE	44–46.6 FIXED MOBILE 552	44–46.6	LAND MOBILE NG124 NG141	PRIVATE LAND MOBILE (90)	
46.6–47 FIXED MOBILE	46.6–47 FIXED MOBILE	46.6–47 FIXED MOBILE 552	46.6–47 FIXED MOBILE	46.6–47		
47.0–68.0 BROADCASTING	47.0–50.0 FIXED MOBILE	47.0–50.0 FIXED MOBILE BROADCASTING	47.0–49.6	47.0–49.6 LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
			49.6–50.0 FIXED MOBILE	49.6–50.0		
	50.0–54.0 AMATEUR 556 557 558 560		50.0–54.0	50.0–54.0 AMATEUR	AMATEUR (97)	
	54.0–68.0 BROADCASTING Fixed Mobile 562	54.0–68.0 FIXED MOBILE BROADCASTING	54.0–72.0	54.0–72.0 BROADCASTING	RADIO BROADCAST (TT) (73) Auxiliary Broadcasting (74)	
553 554 555 559 561						
68.0–74.8 FIXED, MOBILE except aeronauti- cal mobile	68.0–72.0 BROADCASTING Fixed Mobile	68.0–74.8 FIXED MOBILE				

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government	Non-Government	Rule part(s)	Special-use frequencies (7)
			Allocation MHz (4)	Allocation MHz (5)		
564 565 567 568 571 572 74.8–75.2	563	566 568 551 572		NG128 NG 149	DOMESTIC PUBLIC LAND MOBILE (22) PERSONAL (95) PRIVATE LAND MOBILE (90)	
	72.0–73.0 FIXED MOBILE		72.0–73.0 FIXED MOBILE			
	73.0–74.6 RADIO ASTRONOMY 570		NG3 NG49 NG56			
	74.6–74.8 FIXED MOBILE 572		73.0–74.6 RADIO ASTRONOMY US74			
74.8–75.2	AERONAUTICAL RADIO- NAVIGATION 572 572A		74.6–74.8 FIXED MOBILE 572 US273	74.6–74.8 FIXED MOBILE 572 US273	PRIVATE LAND MOBILE (90)	75 MHz Marker beacon
			74.8–75.2 AERONAUTICAL RADIO- NAVIGATION 572	74.8–75.2 AERONAUTICAL RADIO- NAVIGATION 572	AVIATION (87)	
	75.2–87.5 FIXED MOBILE except aeronauti- cal mobile	75.2–75.4 FIXED MOBILE 571 572	75.2–75.4 FIXED MOBILE 572 US273	75.2–75.4 FIXED MOBILE 572 US273	PRIVATE LAND MOBILE (90)	
	75.4–76 FIXED MOBILE	75.4–87 FIXED MOBILE	75.4–76	75.4–76 FIXED MOBILE NG3 NG49 NG56	DOMESTIC PUBLIC LAND MOBILE (22) PERSONAL (95) PRIVATE LAND MOBILE (90)	

565 571 572 575 578	76.0–88.0 BROADCASTING Fixed Mobile	573 574 577 579	76.0–88.0	76.0–88.0 BROADCASTING	RADIO BROADCAST (TV) (73) Auxiliary Broadcasting (74)	
	87.5–100 BROADCASTING	87–100 FIXED MOBILE BROADCASTING	NG128	NG129 NG149		
	576					
581 582	88–100 BROADCASTING		88–108	88–108 BROADCASTING	RADIO BROADCAST (FM) (73) Auxiliary Broadcasting (74)	
100–108	BROADCASTING 582 584 585 586 587 588 589	580	US93	US93 NG2 NG128 NG129		
108–117.975	AERONAUTICAL RADIO- NAVIGATION 590A		108–117.975 AERONAUTICAL RADIO- NAVIGATION US93	108–117.975 AERONAUTICAL RADIO- NAVIGATION US93		
117.975–136.0	AERONAUTICAL MOBILE (R)		117.975–121.9375 AERONAUTICAL MOBILE (R) 501 591 592 593 US26 US28	117.975–121.9375 AERONAUTICAL MOBILE (R) 501 591 592 593 US26 US28	AVIATION (87)	
			121.9375–123.0875 591 US30 US31 US33 US80 US102 US213	121.9375–123.0875 AERONAUTICAL MOBILE 591 US30 US31 US33 US80 US102 US213	AVIATION (87)	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
136–137	AERONAUTICAL MOBILE (R) FIXED Mobile except aeronautical mobile (R) 591 595 594A		123.0875–123.5875 AERONAUTICAL MOBILE	123.0875–123.5875 AERONAUTICAL MOBILE	AVIATION (87)	123.1 MHz for SAR Scene-of- Action Communi- cation
			591 593 US32 US33 US112	591 593 US32 US33 US112		
			123.5875–128.8125 AERONAUTICAL MOBILE (R) 591 US26	123.5875–128.8125 AERONAUTICAL MOBILE (R) 591 US26		
			128.8125–132.0125 591	128.8125–132.0125 AERONAUTICAL MOBILE (R) 591		
			132.0125–136.0 AERONAUTICAL MOBILE (R) 591 US26	132.0125–136.0 AERONAUTICAL MOBILE (R) 591 US26		
136–137			136.0–137.0	136.0–137.0 AERONAUTICAL MOBILE (R)	AVIATION (87) SATELLITE COMMU- NICATIONS (25)	
			591 US244	591 US244		

137.0-137.025 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.0-137.025 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.0-137.025 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.0-137.025 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	137.0-137.025 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	SATELLITE COMMU- NICATIONS (25)
137.025-137.175 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.025-137.175 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.025-137.175 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.025-137.175 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	137.025-137.175 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	SATELLITE COMMU- NICATIONS (25)
137.175-137.825 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.175-137.825 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.175-137.825 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.175-137.825 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	137.175-137.825 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	SATELLITE COMMU- NICATIONS (25)

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
137.825–138.0 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.825–138.0 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.825–138.0 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B Fixed Mobile except aeronautical mobile (R) 596 597 598 599 599A	137.825–138.0 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	137.825–138.0 SPACE OPERATION (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 599B US318 US319 US320 599A	SATELLITE COMMU- NICATIONS (25)	
138.0–143.6 AERONAUTICAL MOBILE (OR) 600 601 602 604	138.0–143.6 FIXED MOBILE /RADIOLOCATION/ Space Research (space- to-Earth) 599 603	138.0–143.6 FIXED MOBILE Space Research (space- to-Earth) 599 603	138.0–144.0 FIXED MOBILE	138.0–144.0		
143.6–143.65 AERONAUTICAL MOBILE (OR) SPACE RESEARCH (space-to-Earth) 601 602 604	143.6–143.65 FIXED MOBILE SPACE RESEARCH (space-to-Earth) /RADIOLOCATION/ 599 603	143.6–143.65 FIXED MOBILE SPACE RESEARCH (space-to-Earth) 599 603				
143.65–144.0 AERONAUTICAL MOBILE (OR) 600 601 602 604	143.65–144.0 FIXED MOBILE /RADIOLOCATION/ Space Research (space- to-Earth) 599 603	143.65–144.0 FIXED MOBILE Space Research (space- to-Earth) 599 603	US10 G30	US10		
144.0–146.0	AMATEUR 510 AMATEUR-SATELLITE		144.0–146.0	144.0–146.0 AMATEUR 510 AMATEUR-SATELLITE	AMATEUR (97)	

605 606	510				
146.0–148 FIXED MOBILE except aeronauti- cal Mobile (R) 608	146.0–148 AMATEUR FIXED MOBILE 607	146.0–148 AMATEUR	146.0–148 AMATEUR (97)		
148–149.9 FIXED MOBILE except aeronauti- cal mobile (R) MOBILE-SATELLITE (Earth-to-space) 599B 608 608A 608C	148–149.9 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space) 599B 608 608A 608C	148–149.9 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space) 599B US319 US320 US323 US325 608 608A US10 G30	SATELLITE COMMU- NICATION (25)		
149.9–150.05 RADIONAVIGATION-SAT- ELLITE LAND MOBILE-SAT- ELLITE (Earth-to-space) 599 609B 608B 609 609A	149.9–150.05 RADIONAVIGATION-SAT- ELLITE LAND MOBILE-SAT- ELLITE (Earth-to-space) 599 609B 608B 609 609A	149.9–150.05 RADIONAVIGATION-SAT- ELLITE LAND MOBILE-SAT- ELLITE (Earth-to-space) 599B US319 US322 608B 609A			
150.05–150.8 FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 610	150.05–150.8 FIXED MOBILE 611	150.05–150.8 FIXED MOBILE US216 G30			
150.8–152 FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 610	150.8–152 FIXED MOBILE 611	150.8–152 FIXED MOBILE 611	PRIVATE LAND MOBILE (90)		
152–152.255 FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 610	152–152.255 FIXED MOBILE 611	152–152.255 FIXED MOBILE 611	PUBLIC MOBILE (22)		

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
152.255–152.495 FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 610	152.255–152.495 FIXED MOBILE	152.255–152.495 FIXED MOBILE 611	152.255–152.495	152.255–152.495 FIXED LAND MOBILE NG124	PRIVATE LAND MOBILE (90)	
152.495–152.855 FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 610	152.495–152.855 FIXED MOBILE	152.495–152.855 FIXED MOBILE 611	152.495–152.855	152.495–152.855 FIXED LAND MOBILE NG4	PUBLIC MOBILE (22)	
152.855–153 FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 610	152.855–153 FIXED MOBILE	152.855–153 FIXED MOBILE 611	152.855–153	152.855–153 LAND MOBILE NG4 NG124	PRIVATE LAND MOBILE (90) AUXILIARY BROAD- CASTING (74)	
153–154 FIXED MOBILE except aeronauti- cal mobile (R) Meteorological Aids	153–154 FIXED MOBILE	153–154 FIXED MOBILE 613	153–154	153–154 LAND MOBILE NG4 NG124	PRIVATE LAND MOBILE (90) AUXILIARY BROAD- CASTING (74)	
154–156.2475 FIXED MOBILE except aeronauti- cal mobile (R) 613	154–156.2475 FIXED MOBILE 613	154–156.2475 FIXED MOBILE 613	154–156.2475	154–156.2475 FIXED LAND MOBILE 613 NG112 NG117	PRIVATE LAND MOBILE (90) MARITIME (80)	
156.2475–156.7625 FIXED MOBILE except aeronauti- cal mobile (R) 613 613A	156.2475–156.7625 FIXED MOBILE 613 613A	156.2475–156.7625 FIXED MOBILE 613 613A	156.2475–156.7625 613 613A US77 US106 US266	156.2475–156.7625 MARITIME MOBILE 613 613A US77 US106 US266 NG117		

156.7625–156.8375 MARITIME MOBILE (dis- tress and calling) 501 613	156.7625–156.8375 MARITIME MOBILE (dis- tress and calling) 501 613	156.7625–156.8375 613 US107 US266	156.7625–156.8375 MARITIME MOBILE 613 US107 US266 NG117	
156.8375–157.0375 FIXED MOBILE except aeronauti- cal mobile 613	156.8375–157.0375 FIXED MOBILE 613	156.8375–157.0375 613 US77 US266	156.8375–157.0375 MARITIME MOBILE 613 US77 US 266 NG117	
157.0375–157.1875 FIXED MOBILE except aeronauti- cal mobile 613	157.0375–157.1875 FIXED MOBILE 613	157.0375–157.1875 MARITIME MOBILE 613 US214 US266 G109	157.0375–157.1875 Private Land Mobile (90)	
157.1875–157.45 FIXED MOBILE except aeronauti- cal mobile 613	157.1875–157.45 FIXED MOBILE 613	157.1875–157.45 613 US223 US266 NG111 NG154	PRIVATE LAND MOBILE (90) MARITIME (80)	
157.45–157.755 FIXED MOBILE except aeronauti- cal mobile 613	157.45–157.755 FIXED MOBILE 613	157.45–157.755 US266	PRIVATE LAND MOBILE (90)	
157.755–158.115 FIXED MOBILE except aeronauti- cal mobile 613	157.755–158.115 FIXED MOBILE 613	157.755–158.115 US266	PUBLIC MOBILE (22)	
158.115–161.575 FIXED MOBILE except aeronauti- cal mobile S5.226 S5.229	158.115–161.575 FIXED MOBILE S5.226 S5.230 S5.231 S5.232	158.115–161.575 S5.226	PUBLIC MOBILE (22) PRIVATE LAND MOBILE (90) MARITIME (80)	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
161.575–161.625 FIXED MOBILE except aeronauti- cal mobile 613	161.575–161.625 FIXED MOBILE 613	161.575–161.625 FIXED MOBILE 613	161.575–161.625 613 US77	161.575–161.625 MARITIME MOBILE 613 US77 NG6 NG17	MARITIME (80) PUBLIC MOBILE (22)	
161.625–161.775 FIXED MOBILE except aeronauti- cal mobile 613	161.625–161.775 FIXED MOBILE 613	161.625–161.775 FIXED MOBILE 613	161.625–161.775 613	161.625–161.775 LAND MOBILE 613 NG6	AUXILIARY BROAD- CASTING (74) PUBLIC MOBILE (22)	
161.775–162.0125 FIXED MOBILE except aeronauti- cal mobile 613 615	161.775–162.0125 FIXED MOBILE 613	161.775–162.0125 FIXED MOBILE 613	161.775–162.0125 613 US266	161.775–162.0125 LAND MOBILE MARITIME MOBILE 613 US266 NG6 NG154	PRIVATE LAND MOBILE (90) PUBLIC MOBILE (22) MARITIME (80)	
162.0125–173.2 FIXED MOBILE except aeronauti- cal mobile 613 615	162.0125–173.2 FIXED MOBILE 613	162.0125–173.2 FIXED MOBILE 613 616 617 618	162.0125–173.2 FIXED MOBILE 613 US8 US11 US13 US216 US223 US300 US312 G5	162.0125–173.2 613 US8 US11 US13 US216 US223 US300 US312	Auxiliary Broadcasting (74) Private Land Mobile (90)	
173.2–173.4 FIXED MOBILE except aeronauti- cal mobile 615	173.2–173.4 FIXED MOBILE 615	173.2–173.4 FIXED MOBILE 617 618	173.2–173.4 G5	173.2–173.4 FIXED Land Mobile NG124	PRIVATE LAND MOBILE (90)	
173.4–174 FIXED MOBILE except aeronauti- cal mobile 615	173.4–174 FIXED MOBILE 615	173.4–174 FIXED MOBILE 617 618	173.4–174 FIXED MOBILE G5	173.4–174		

174–216 BROADCASTING	174–216 FIXED MOBILE BROADCASTING	174–216 FIXED MOBILE BROADCASTING	174–216	174–216 BROADCASTING	RADIO BROADCAST (TV) (73) Auxiliary Broadcasting (74)
621 623 628 629	620	619 624 625 626 630		NG115 NG128 NG149	
216–220 BROADCASTING	216–220 FIXED MOBILE BROADCASTING	216–220 FIXED MOBILE BROADCASTING	216–220 MARITIME MOBILE Aeronautical Mobile Fixed Land Mobile Radiolocation 627 US210 US229 US274 US317 G2	216–220 MARITIME MOBILE Aeronautical Mobile Fixed Land Mobile 627 US210 US229 US274 US317 NG152	MARITIME (80) Private Land Mobile (90) Personal Radio Service (95) Amateur (97)
621 623 628 629	627A	619 624 625 626 630			
220–222 BROADCASTING	220–222 AMATEUR FIXED MOBILE Radiolocation 627	220–222 FIXED MOBILE BROADCASTING 626	220–222 FIXED LAND MOBILE Radiolocation 627 G2 US335	220–222 FIXED LAND MOBILE 627 US335	PRIVATE LAND MOBILE (90)
621 623 628 629					
222–223 BROADCASTING	222–223 AMATEUR FIXED MOBILE Radiolocation 627	222–223 FIXED MOBILE BROADCASTING 619 624 625 626 630	222–223 Radiolocation 627 G2	222–223 AMATEUR 627	AMATEUR (97)
621 623 628 629					
223–225 BROADCASTING Fixed Mobile	223–225 AMATEUR FIXED MOBILE Radiolocation 627	223–225 FIXED MOBILE BROADCASTING AERONAUTICAL RADIO- NAVIGATION Radiolocation 636 637	223–225 Radiolocation 627 G2	223–225 AMATEUR 627	AMATEUR (97)
622 628 629 631 632 635					
225–230 BROADCASTING Fixed Mobile	225–230 FIXED MOBILE	225–230 FIXED MOBILE BROADCASTING AERONAUTICAL RADIO- NAVIGATION Radiolocation 636 637	225–230 FIXED MOBILE G27	225–230 627	
622 628 629 631 632 635					
230–235 FIXED	230–235 FIXED	230–235 FIXED	230–235 FIXED	230–235	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government	Non-Government	Rule part(s) (6)	Special-use frequencies (7)
			Allocation MHz (4)	Allocation MHz (5)		
MOBILE 629 632 635 638 639	MOBILE	MOBILE AERONAUTICAL RADIO- NAVIGATION 637	MOBILE G27			
235–267 FIXED MOBILE	235–267 FIXED MOBILE	235–267 FIXED MOBILE	235–267 FIXED MOBILE	235–267		
501 592 635 640 641 642	501 592 635 640 641 642	501 592 635 640 641 642	501 592 642 G27 G100	501 592 642		
267–272 FIXED MOBILE	267–272 FIXED MOBILE	267–272 FIXED MOBILE	267–272 FIXED MOBILE	267–272		
Space Operation (space- to-Earth) 641 643	Space Operation (space- to-Earth) 641 643	Space Operation (space- to-Earth) 641 643	G27 G100			
272–273 SPACE OPERATION (space-to-Earth) FIXED MOBILE	272–273 SPACE OPERATION (space-to-Earth) FIXED MOBILE	272–273 SPACE OPERATION (space-to-Earth) FIXED MOBILE	272–273 FIXED MOBILE	272–273		
641	641	641	G27 G100			
273–312 FIXED MOBILE	273–312 FIXED MOBILE	273–312 FIXED MOBILE	273–312 FIXED MOBILE	273–312		
641	641	641	G27 G100			
312–315 FIXED MOBILE	312–315 FIXED MOBILE	312–315 FIXED MOBILE	312–315 FIXED MOBILE	312–315		
Mobile-Satellite (Earth-to- space) 641 641A	Mobile-Satellite (Earth-to- space) 641 641A	Mobile-Satellite (Earth-to- space) 641 641A	G27 G1			
315–322 FIXED MOBILE	315–322 FIXED MOBILE	315–322 FIXED MOBILE	315–322 FIXED MOBILE	315–322		
641	641	641	G27 G100			
322–328.6	322–328.6	322–328.6	322–328.6	322–328.6		

MOBILE RADIO ASTRONOMY 644	MOBILE RADIO ASTRONOMY 644	MOBILE RADIO ASTRONOMY 644	MOBILE 644 G27	644	
328.6–335.4	AERONAUTICAL RADIO- NAVIGATION 645 645A		328.6–335.4 AERONAUTICAL RADIO- NAVIGATION 645	328.6–335.4 AERONAUTICAL RADIO- NAVIGATION 645	
335.4–399.9	FIXED MOBILE 641		335.4–399.9 FIXED MOBILE G27 G100	335.4–399.9	
399.9–400.05 RADIONAVIGATION-SAT- ELLITE	399.9–400.05 RADIONAVIGATION-SAT- ELLITE	399.9–400.05 RADIONAVIGATION-SAT- ELLITE	399.9–400.05 RADIONAVIGATION-SAT- ELLITE MOBILE-SATELLITE (Earth-to-space) US319 US326 645B	399.9–400.05 RADIONAVIGATION-SAT- ELLITE MOBILE-SATELLITE (Earth-to-space) US319 US326 645B	
609 645B	609 645B	609 645B			
400.05–400.15	STANDARD FRE- QUENCY AND TIME SIGNAL-SATELLITE (400.1 MHz) 646 647		400.05–400.15 STANDARD FRE- QUENCY AND TIME SIGNAL-SATELLITE 646	400.05–400.15 STANDARD FRE- QUENCY AND TIME SIGNAL-SATELLITE 646	400.1 MHz: Standard frequency
400.15–401 METEOROLOGICAL AIDS METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) 647A MOBILE-SATELLITE (space-to-Earth) 599B Space Operation (space- to-Earth)	400.15–401 METEOROLOGICAL AIDS METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) 647A MOBILE-SATELLITE (space-to-Earth) 599B Space Operation (space- to-Earth)	400.15–401 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) 647A MOBILE-SATELLITE (space-to-Earth) 599B US319 US320 US324 Space Operation (space- to-Earth)	400.15–401 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) 647A MOBILE-SATELLITE (space-to-Earth) 599B US319 US320 US324 Space Operation (space- to-Earth) 647 647B US70	400.15–401 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) SPACE RESEARCH (space-to-Earth) 647A MOBILE-SATELLITE (space-to-Earth) 599B US319 US320 US324 Space Operation (space- to-Earth) 647 647B US70	SATELLITE COMMU- NICATIONS (25)
647 647B	647 647B	647 647B	647 647B US70	647 647B US70	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
401–402	METEOROLOGICAL AIDS SPACE OPERATION (space-to-Earth) Earth Exploration-Satellite (Earth-to-space) Fixed Meteorological-Satellite (Earth-to-space) Mobile except aeronautical mobile		401–402 METEOROLOGICAL AIDS (radiosonde) SPACE OPERATION (space-to-Earth) Earth Exploration-Satellite (Earth-to-space) Meteorological-Satellite (Earth-to-space) US70	401–402 METEOROLOGICAL AIDS (radiosonde) SPACE OPERATION (space-to-Earth) Earth Exploration-Satellite (Earth-to-space) Meteorological-Satellite (Earth-to-space) US70	SATELLITE COMMU- NICATIONS (25)	
402–403	METEOROLOGICAL AIDS Earth Exploration-Satellite (Earth-to-space) Fixed Meteorological-Satellite (Earth-to-space) Mobile except aeronautical mobile		402–403 METEOROLOGICAL AIDS (radiosonde) Earth Exploration-Satellite (Earth-to-space) Meteorological-Satellite (Earth-to-space) US70	402–403 METEOROLOGICAL AIDS (radiosonde) Earth Exploration-Satellite (Earth-to-space) Meteorological-Satellite (Earth-to-space) US70		
403–406	METEOROLOGICAL AIDS Fixed Mobile except aeronautical mobile 648		403–406 METEOROLOGICAL AIDS (radiosonde) US70 G6	403–406 METEOROLOGICAL AIDS (radiosonde) US70		
406.0–406.1	MOBILE-SATELLITE (Earth-to-space) 649 649A		406.0–406.1 MOBILE-SATELLITE (Earth-to-space) 649 649A	406.0–406.1 MOBILE-SATELLITE (Earth-to-space) 649 649A		

406.1–410.0	FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 648 650	406.1–410.0 FIXED MOBILE RADIO ASTRONOMY US13 US74 US117 G5 G6	406.1–410.0 RADIO ASTRONOMY US13 US74 US117	
410–420	FIXED MOBILE except aeronauti- cal mobile	410–420 FIXED MOBILE US13 G5	410–420 US13	
420–430	FIXED MOBILE except aeronauti- cal mobile Radiolocation 651 652 653	420–450 RADIOLOCATION	420–450 Amateur LAND MOBILE (90) Amateur (97)	
430–440 AMATEUR RADIOLOCATION 653 654 655 656 657 658 659 661 662 663 664 665	430–440 RADIOLOCATION Amateur 653 658 659 660 660A 663 664			
440–450	FIXED MOBILE except aeronauti- cal mobile Radiolocation 651 652 653 666 667 668	664 668 US7 US87 US217 US228 US230 G2 G8	664 668 US7 US87 US217 US228 US230 NG135	
450–451 FIXED MOBILE 653 668	450–451 FIXED MOBILE 668	450–451 FIXED MOBILE 668 US87	450–451 LAND MOBILE 668 US87 AUXILIARY BROAD- CASTING (74)	
451–454 FIXED MOBILE 653	451–454 FIXED MOBILE 653	451–454 FIXED MOBILE 653	451–454 LAND MOBILE NG112 NG124 PRIVATE LAND MOBILE (90)	

International table			United States table		FCC use designators	
Region 1—allocation MHz	Region 2—allocation MHz	Region 3—allocation MHz	Government Allocation MHz	Non-Government Allocation MHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
454–455 FIXED MOBILE 653	454–455 FIXED MOBILE	454–455 FIXED MOBILE 653	454–455	454–455 FIXED LAND MOBILE NG12 NG112 NG148	PUBLIC MOBILE (22) MARITIME (80)	
455–456 FIXED MOBILE	455–456 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space)	455–456 FIXED MOBILE 653	455–456	455–456 LAND MOBILE	AUXILIARY BROAD- CASTING (74)	
456–459 FIXED MOBILE 653 669	456–459 FIXED MOBILE 669 670	456–459 FIXED MOBILE 653 669 670	456–459 669 670	456–459 FIXED LAND MOBILE 669 670 NG112 NG124	PRIVATE LAND MOBILE (90)	
459–460 FIXED MOBILE	459–460 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space)	459–460 FIXED MOBILE 653	459–460	459–460 FIXED LAND MOBILE NG12 NG112 NG148	PUBLIC MOBILE (22) MARITIME (80)	
460–462.5375 FIXED MOBILE Meteorological-Satellite (space-to-Earth) 671 672	460–462.5375 FIXED MOBILE Meteorological-Satellite (space-to-Earth) 671	460–462.5375 FIXED MOBILE Meteorological-Satellite (space-to-Earth) 671 672	460–462.5375 Meteorological-Satellite (space-to-Earth) 671 US201 US209	460–462.5375 FIXED LAND MOBILE 671 US201 US209 NG124	PRIVATE LAND MOBILE (90)	
462.5375–462.7375 FIXED MOBILE Meteorological-Satellite (space-to-Earth) 671 672	462.5375–462.7375 FIXED MOBILE Meteorological-Satellite (space-to-Earth) 671	462.5375–462.7375 FIXED MOBILE Meteorological-Satellite (space-to-Earth) 671 672	462.5375–462.7375 Meteorological-Satellite (space-to-Earth) 671 US201	462.5375–462.7375 LAND MOBILE 671 US201	PERSONAL (95)	

462.7375–467.5375 FIXED MOBILE Meteorological-Satellite (space-to-Earth)	462.7375–467.5375 FIXED MOBILE Meteorological-Satellite (space-to-Earth)	462.7375–467.5375 Meteorological-Satellite (space-to-Earth)	462.7375–467.5375 FIXED LAND MOBILE	PRIVATE LAND MOBILE (90)
669 671 672	669 671 672	669 671 US201 US209 US216	669 671 US201 US209 US216 NG124	
467.5375–467.7375 FIXED MOBILE Meteorological-Satellite (space-to-Earth)	467.5375–467.7375 FIXED MOBILE Meteorological-Satellite (space-to-Earth)	467.5375–467.7375 Meteorological-Satellite (space-to-Earth)	467.5375–567.7375 LAND MOBILE	PERSONAL (95)
669 671 672	669 671 672	669 671 US201	669 671 US201	
467.7375–470 FIXED MOBILE Meteorological-Satellite (space-to-Earth)	467.7375–470 FIXED MOBILE Meteorological-Satellite (space-to-Earth)	467.7375–470 MOBILE Meteorological-Satellite (space to Earth)	467.735–470 FIXED LAND MOBILE	PRIVATE LAND MOBILE (90)
671 672	670 671	670 671 US201 US216 NG124	670 671 US201 US216 NG124	
470–512 BROADCASTING	470–512 BROADCASTING Fixed Mobile	470–512 FIXED MOBILE BROADCASTING	470–512 BROADCASTING FIXED LAND MOBILE	RADIO BROADCAST (TV)(73) PRIVATE LAND MOBILE (90) PUBLIC MOBILE (22) Auxiliary Broadcasting (74)
676 677A	674 675	673 677	NG66 NG114 NG127 NG128 NG149	
512–585 BROADCASTING	512–585 BROADCASTING	512–585 FIXED MOBILE BROADCASTING	512–585 BROADCASTING	RADIO BROADCAST (TV) (73) Auxiliary Broadcasting (74)
676 677A 683 684	678	677 679	NG128 NG149	
585–608 BROADCASTING	585–608 BROADCASTING	585–608 FIXED MOBILE BROADCASTING RADIONAVIGATION	585–608 BROADCASTING	RADIO BROADCAST (TV) (73) Auxiliary Broadcasting (74)
677A 683 684 685 686 686A 687	678	688	NG128 NG149	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
608–610 BROADCASTING	608–610 RADIO ASTRONOMY Mobile-Satellite except aeronautical mobile-sat- ellite (Earth-to-space)	608–610 FIXED MOBILE BROADCASTING RADIONAVIGATION 688 689 690	608–610 RADIO ASTRONOMY US74 US246	608–610 RADIO ASTRONOMY US74 US246		
610–614 BROADCASTING	610–614 RADIO ASTRONOMY Mobile-Satellite except aeronautical mobile-sat- ellite (Earth-to-space)	610–614 FIXED MOBILE BROADCASTING 677 688 689 690 691	610–614 RADIO ASTRONOMY US74 US246	610–614 RADIO ASTRONOMY US74 US246		
614–790 BROADCASTING	614–790 BROADCASTING Fixed Mobile	614–790 FIXED MOBILE BROADCASTING 677 691 693	614–790 614–790	614–790 BROADCASTING NG30 NG128 NG149	RADIO BROADCAST (TV) (73) Auxiliary Broadcasting (74)	
790–806 FIXED BROADCASTING	790–806 BROADCASTING Fixed Mobile	790–806 FIXED MOBILE BROADCASTING 677	790–806 677	790–806 BROADCASTING NG30 NG43 NG128 NG149	RADIO BROADCAST (TV) (73) Auxiliary Broadcasting (74)	
806–821 FIXED BROADCASTING	806–821 FIXED MOBILE BROADCASTING 692A 700	806–821 FIXED MOBILE BROADCASTING 677 701	806–821 677	806–821 FIXED LAND MOBILE NG30 NG31 NG43 NG63	PRIVATE LAND MOBILE (90) PUBLIC MOBILE (22)	
821–824 FIXED BROADCASTING	821–824 FIXED MOBILE BROADCASTING	821–824 FIXED MOBILE BROADCASTING	821–824 677	821–824 LAND MOBILE 677	PRIVATE LAND MOBILE (90)	

700B	692A 700	677 701		824-849	NG30 NG43 NG63		
824-849 FIXED BROADCASTING	824-849 FIXED MOBILE BROADCASTING	824-849 FIXED MOBILE BROADCASTING		824-849	824-849 FIXED LAND MOBILE	PUBLIC MOBILE (22)	
694 695 695A 696 697 700B 702	692A 700	677 701			NG30 NG43 NG63 NG151		
849-851 FIXED BROADCASTING	849-851 FIXED MOBILE BROADCASTING 692A 700 700A	849-851 FIXED MOBILE BROADCASTING 677 701		849-851	849-851 AERONAUTICAL MOBILE NG30 NG63	PUBLIC MOBILE (22)	
694 695A 697 702							
851-862 FIXED BROADCASTING	851-862 FIXED MOBILE BROADCASTING 692A 700	851-862 FIXED MOBILE BROADCASTING 677 701		851-862	851-862 FIXED LAND MOBILE NG30 NG31 NG63	PRIVATE LAND MOBILE (90) PUBLIC MOBILE (22)	
694 695A 697 700B 702							
862-866 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 700B 704	862-866 FIXED MOBILE BROADCASTING 692A 700	862-866 FIXED MOBILE BROADCASTING 677 701		862-866	862-866 FIXED LAND MOBILE NG30 NG31 NG63	PRIVATE LAND MOBILE (90) PUBLIC MOBILE (22)	
866-869 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 700B 704	866-869 FIXED MOBILE BROADCASTING 692A 700	866-869 FIXED MOBILE BROADCASTING 677 701		866-869	866-869 LAND MOBILE NG30 NG63	PRIVATE LAND MOBILE (90)	
869-890 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 700B 704	869-890 FIXED MOBILE BROADCASTING 692A 700	869-890 FIXED MOBILE BROADCASTING 677 701		869-890	869-890 FIXED LAND MOBILE NG30 NG63 NG151	PUBLIC MOBILE (22)	
890-894 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	890-894 FIXED MOBILE except aeronauti- cal mobile Radiolocation 700A 704A 705	890-894 FIXED MOBILE BROADCASTING Radiolocation 706		890-894	890-894 FIXED LAND MOBILE US116 US268 NG151	PUBLIC MOBILE (22)	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
894–896 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	894–896 FIXED MOBILE except aeronauti- cal mobile Radiolocation 700A 704A 705	894–896 FIXED MOBILE BROADCASTING Radiolocation 706	894–896 US116 US268 G2	894–896 AERONAUTICAL MOBILE US116 US268	PUBLIC MOBILE (22)	
896–901 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	896–901 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	896–901 FIXED MOBILE BROADCAST- ING Radiolocation 706	896–901 US116 US268 G2	896–901 FIXED LAND MOBILE US116 US268	PRIVATE LAND MOBILE (90)	
901–902 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	901–902 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	901–902 FIXED MOBILE BROADCASTING Radiolocation 706	901–902 US116 US268 G2	901–902 FIXED MOBILE US116 US268	PERSONAL COMMU- NICATIONS (24)	
902–928 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	902–928 FIXED Amateur Mobile except aeronautical mobile Radiolocation 705 707 707A	902–928 FIXED MOBILE BROADCASTING Radiolocation 706	902–928 RADIOLOCATION 707 US215 US218 US267 US275 G11 G59	902–928 707 US215 US218 US267 US275	Amateur (97) Private Land Mobile (90)	915±13 MHz: Industrial scientific and medi- cal fre- quency.
928–929 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	928–929 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	928–929 FIXED MOBILE BROADCASTING Radiolocation 706	928–929 US116 US 215 US268 G2	928–929 FIXED US116 US215 US268	FIXED MICROWAVE (101) PRIVATE LAND MOBILE (90) PUBLIC MOBILE (22)	

929-930 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	929-930 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	929-930 FIXED MOBILE BROADCASTING Radiolocation 706	929-930 US116 US215 US268 G2	929-930 FIXED LAND MOBILE US116 US215 US268	PRIVATE LAND MOBILE (90)
930-931 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	930-931 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	930-931 FIXED MOBILE BROADCASTING Radiolocation 706	930-931 US116 US215 US268 G2	930-931 FIXED MOBILE US116 US215 US268	PERSONAL COMMU- NICATIONS (24)
931-932 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	931-932 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	931-932 FIXED MOBILE BROADCASTING Radiolocation 706	931-932 US116 US215 US268 G2	931-932 FIXED LAND MOBILE US116 US215 US268	PUBLIC MOBILE (22)
932-935 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	932-935 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	932-935 FIXED MOBILE BROADCASTING Radiolocation 706	932-935 FIXED US116 US215 US268 G2	932-935 FIXED US215 US268	FIXED MICROWAVE (101) PUBLIC MOBILE (22)
935-940 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	935-940 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	935-940 FIXED MOBILE BROADCASTING Radiolocation 706	935-940 US116 US215 US268 G2	935-940 FIXED LAND MOBILE US116 US215 US268	PRIVATE LAND MOBILE (90)
940-941 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 703 Radiolocation 704	940-941 FIXED MOBILE except aeronauti- cal mobile Radiolocation 705	940-941 FIXED MOBILE BROADCASTING Radiolocation 706	940-941 US116 US268 G2	940-941 FIXED MOBILE US116 US268	PERSONAL COMMU- NICATIONS (24)

International table			United States table		FCC use designators	
Region 1—allocation MHz	Region 2—allocation MHz	Region 3—allocation MHz	Government Allocation MHz	Non-Government Allocation MHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
941–942 FIXED MOBILE except aeronautical mobile BROADCASTING 703 Radiolocation 704	941–942 FIXED MOBILE except aeronautical mobile Radiolocation 705	941–942 FIXED MOBILE BROADCASTING Radiolocation 706	941–942 FIXED US268 G2	941–942 FIXED US268	FIXED MICROWAVE (101) PUBLIC MOBILE (22)	
942–944 FIXED MOBILE except aeronautical mobile BROADCASTING 703 704	942–944 FIXED MOBILE	942–944 FIXED MOBILE BROADCASTING 701	942–944 FIXED US301 US302	942–944 FIXED US301 US302	FIXED MICROWAVE (101)	
944–960 FIXED MOBILE except aeronautical mobile BROADCASTING 703 704	944–960 FIXED MOBILE	944–960 FIXED MOBILE BROADCASTING 701	944–960 FIXED	944–960 FIXED NG120	AUXILIARY BROADCASTING (74) FIXED MICROWAVE (101) INTERNATIONAL PUBLIC FIXED (23) PUBLIC MOBILE (22)	
960–1215	AERONAUTICAL RADIO-NAVIGATION 709		960–1215 AERONAUTICAL RADIO-NAVIGATION 709 US224	960–1215 AERONAUTICAL RADIO-NAVIGATION 709 US224	AVIATION (87)	
1215–1240	RADIOLOCATION RADIO/NAVIGATION-SATELLITE (space-to-Earth) 710 711 712 712A 713		1215–1240 RADIOLOCATION RADIO/NAVIGATION-SATELLITE (space-to-Earth) 713 G56	1215–1240 713		

1240–1260	RADIOLOCATION RADIONAVIGATION-SAT- ELLITE (space-to-Earth) 710 Amateur 711 712 712A 713 714	1240–1300 RADIOLOCATION	1240–1300 Amateur	Amateur (97)	
1260–1300	RADIOLOCATION Amateur 664 711 712 712A 713 714	664 713 714 G56	664 713 714		
1300–1350	AERONAUTICAL RADIO- NAVIGATION 717 Radiolocation 715 716 718	1300–1350 AERONAUTICAL RADIO- NAVIGATION 717 Radiolocation 718 G2	1300–1350 AERONAUTICAL RADIO- NAVIGATION 717 718	AVIATION (87)	
1350–1400 FIXED MOBILE RADIOLOCATION	1350–1400 RADIOLOCATION 714 718 720	1350–1400 RADIOLOCATION Fixed Mobile 714 718 720 G2 G27 G114 US311	1350–1400 714 718 720		
1400–1427	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 721 722	1400–1427 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 US74 US246	1400–1427 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 US74 US246		
1427–1429	SPACE OPERATION (Earth-to-space) FIXED MOBILE except aeronauti- cal mobile 722	1427–1429 SPACE OPERATION (Earth-to-space) FIXED MOBILE except aeronauti- cal mobile 722 G30	1427–1429 SPACE OPERATION (Earth-to-space) Fixed (telemetering) Land Mobile (telemetering and telecommand) 722	Private Land Mobile (90) Satellite Communications (25)	
1429–1525 FIXED MOBILE except aeronauti- cal mobile	1429–1525 FIXED MOBILE 723	1429–1435 FIXED MOBILE 722 G30	1429–1435 Land Mobile (telemetering and telecommand) Fixed (telemetering) 722	Private Land Mobile (90)	
		1435–1525	1435–1525		

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
722	722		MOBILE (aeronautical telemetry) 722 US78	MOBILE (aeronautical telemetry) 722 US78	AVIATION (87)	(7)
1525–1530 SPACE OPERATION (space-to-Earth) FIXED MARITIME MOBILE-SAT-ELLITE (space-to-Earth) Land Mobile-Satellite (space-to-Earth) 726B Earth Exploration-Satellite Mobile 723	1525–1530 SPACE OPERATION (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile 723	1525–1530 SPACE OPERATION (space-to-Earth) FIXED MOBILE-SATELLITE (space-to-Earth) Earth Exploration-Satellite Mobile 723 724	1525–1530 MOBILE-SATELLITE (space-to-Earth) Mobile (aeronautical telemetry)	1525–1530 MOBILE-SATELLITE (space-to-Earth) Mobile (aeronautical telemetry)	SATELLITE COMMUNICATION (25) Aviation (87)	
722 723B 725 726A 726D	722 723A 726A 726D	722 726A 726D	722 726A US78	722 726A US78		
1530–1533 SPACE OPERATION (space-to-Earth) MARITIME MOBILE-SAT-ELLITE (space-to-Earth) LAND MOBILE-SAT-ELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile except aeronautical mobile	1530–1533 SPACE OPERATION (space-to-Earth) MARITIME MOBILE-SAT-ELLITE (space-to-Earth) LAND MOBILE-SAT-ELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile 723	1530–1533 SPACE OPERATION (space-to-Earth) MARITIME MOBILE-SAT-ELLITE (space-to-Earth) LAND MOBILE-SAT-ELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile 723	1530–1533 MARITIME MOBILE-SAT-ELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) Mobile (aeronautical telemetry)	1530–1533 MARITIME MOBILE-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) Mobile (aeronautical telemetry)	SATELLITE COMMUNICATION (25) Aviation (87)	
722 723B 726A 726D	722 726A 726C 726D	722 726A 726C 726D				

1533–1535 SPACE OPERATION (space-to-Earth) MARITIME MOBILE-SAT- ELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile except aeronautical Land Mobile-Satellite (space-to-Earth) 726B 722 723B 726A 726D	1533–1535 SPACE OPERATION (space-to-Earth) MARITIME MOBILE-SAT- ELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile 723 Land Mobile-Satellite (space-to-Earth) 726B 722 726A 726C 726D	1533–1535 SPACE OPERATION (space-to-Earth) MARITIME MOBILE-SAT- ELLITE (space-to-Earth) Earth Exploration-Satellite Fixed Mobile 723 Land Mobile-Satellite (space-to-Earth) 726B 722 726A 726C 726D	722 726A US78 US315		
1535–1544 MARITIME MOBILE-SAT- ELLITE (space-to-Earth) Land Mobile-Satellite (space-to-Earth) 726B 722 726A 726C 726D 727	1535–1544 MARITIME MOBILE-SAT- ELLITE (space-to-Earth) Land Mobile-Satellite (space-to-Earth) 726B 722 726A 726C 726D 727	1535–1544 MARITIME MOBILE-SAT- ELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 722 726A US315	1535–1544 MARITIME MOBILE-SAT- ELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 722 726A US315	MARITIME (80) SATELLITE COMMU- NICATIONS (25)	
1544–1545 MOBILE-SATELLITE (space-to-Earth) 722 726D 727 727A	1544–1545 MOBILE-SATELLITE (space-to-Earth) 722 726D 727 727A	1544–1545 MOBILE-SATELLITE (space-to-Earth) 722 727A	1544–1545 MOBILE-SATELLITE (space-to-Earth) 722 727A	MARITIME (80) SATELLITE COMMU- NICATION (25)	
1545–1555 AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth)	1545–1555 AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth)	1545–1549.5 AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth) Mobile-satellite (space-to- Earth) 722 726A US308 US309	1545–1549.5 AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth) Mobile-satellite (space-to- Earth) 722 726A US308 US309	AVIATION (87)	
722 726A 726D 727 729 729A 730	722 726A 726D 727 729 729A 730	1549.5–1558.5 AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth) MOBILE-SATELLITE (space-to-Earth)	1549.5–1558.5 AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth) MOBILE-SATELLITE (space-to-Earth)	AVIATION (87)	
1555–1559 LAND MOBILE-SAT- ELLITE (space-to-Earth)	1555–1559 LAND MOBILE-SAT- ELLITE (space-to-Earth)	722 726A US308 US309 1558.5–1559	722 726A US308 US309 1558.5–1559		

International table			United States table		FCC use designators	
Region 1—allocation MHz	Region 2—allocation MHz	Region 3—allocation MHz	Government Allocation MHz	Non-Government Allocation MHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
722 726A 726D 727 730 730A 730B 730C	722 726A 726D 727 730 730A 730B 730C	722 726A 726D 727 730 730A 730B 730C	AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth) 722 726A US308 US309	AERONAUTICAL MO- BILE-SATELLITE (R) (space-to-Earth) 722 726A US308 US309	AVIATION (87)	
1559–1610	AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (space-to-Earth) 722 727 730 731 731A 731B 731C 731D		1559–1610 AERONAUTICAL RADIO-NAVIGATION-SAT- ELLITE (space-to-Earth) 722 US208 US260	1559–1610 AERONAUTICAL RADIO-NAVIGATION-SAT- ELLITE (space-to-Earth) 722 US208 US260	AVIATION (87)	
1610–1610.6 AERONAUTICAL RADIO- NAVIGATION MOBILE-SATELLITE (Earth-to-space)	1610–1610.6 AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) MOBILE-SATELLITE (Earth-to-space) 722 727 730 731E 732 732 733 733A 733B 733C 733D 733E	1610–1610.6 AERONAUTICAL RADIO- NAVIGATION MOBILE-SATELLITE (Earth-to-space) RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) 722 727 730 731E 732 732 733 733A 733B 733C 733A 733B 733E	1610–1610.6 AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) MOBILE-SATELLITE (Earth-to-space) 722 731E 732 733 733A 733E US208 US260 US319	1610–1610.6 AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) MOBILE-SATELLITE (Earth-to-space) 722 731E 732 733 733A 733E US208 US260 US319	AVIATION (87) SATELLITE COMMU- NICATION (25)	
1610.6–1613.8 AERONAUTICAL RADIO- NAVIGATION MOBILE-SATELLITE (Earth-to-space) RADIO ASTRONOMY	1610.6–1613.8 AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) MOBILE-SATELLITE (Earth-to-space) RADIO ASTRONOMY 722 731E 732 733 733A 733C 733D 733E 734	1610.6–1613.8 AERONAUTICAL RADIO- NAVIGATION MOBILE-SATELLITE (Earth-to-space) RADIO ASTRONOMY Radio-NAVIGATION-SAT- ellite (Earth-to-space) 722 727 730 731E 732 732 733 733A 733B 733E 734	1610.6–1613.8 AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) MOBILE-SATELLITE (Earth-to-space) RADIO ASTRONOMY 722 731E 732 733 733A 733E 734 US208 US260 US319	1610.6–1613.8 AERONAUTICAL RADIO- NAVIGATION RADIO-NAVIGATION-SAT- ELLITE (Earth-to-space) MOBILE-SATELLITE (Earth-to-space) RADIO ASTRONOMY 722 731E 732 733 733A 733E 734 US208 US260 US319	AVIATION (87) SATELLITE COMMU- NICATION (25)	

§ 2.106

397

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
722 726A 726D 727 729A 730 735	722 726A 726D 727 729A 730 735	722 726A 726D 727 729A 730 735	722 726A US308 US309	722 726A US308 US309		
1656.5–1660 LAND MOBILE-SAT- ELLITE (Earth-to-space)	1656.5–1660 LAND MOBILE-SAT- ELLITE (Earth-to-space)	1656.5–1660 LAND MOBILE-SAT- ELLITE (Earth-to-space)	1651–1660 AERONAUTICAL MO- BILE-SATELLITE (R) (Earth-to-space) MOBILE-SATELLITE (Earth-to-space)	1651–1660 AERONAUTICAL MO- BILE-SATELLITE (R) (Earth-to-space) MOBILE-SATELLITE (Earth-to-space)	AVIATION (87)	
722 726A 726D 727 730 730A 730B 730C 734A	722 726A 726D 727 730 730A 730B 730C 734A	722 726A 726D 727 730 730A 730B 730C 734A	722 726A US308 US39	722 726A US308 US39		
1660–1660.5 RADIO ASTRONOMY LAND MOBILE-SAT- ELLITE (Earth-to-space)	1660–1660.5 RADIO ASTRONOMY LAND MOBILE-SAT- ELLITE (Earth-to-space)	1660–1660.5 RADIO ASTRONOMY LAND MOBILE-SAT- ELLITE (Earth-to-space)	1660–1660.5 AERONAUTICAL MO- BILE-SATELLITE (R) (Earth-to-space) RADIO ASTRONOMY	1660–1660.5 AERONAUTICAL MO- BILE-SATELLITE (R) (Earth-to-space) RADIO ASTRONOMY	AVIATION (87)	
722 726A 726D 730A 730B 730C 736	722 726A 726D 730A 730B 730C 736	722 726A 726D 730A 730B 730C 736	722 726A 736 US309	722 726A 736 US309		
1660.5–1668.4	RADIO ASTRONOMY SPACE RESEARCH (pas- sive) Fixed Mobile except aeronautical mobile		1660.5–1668.4 RADIO ASTRONOMY SPACE RESEARCH (pas- sive)	1660.5–1668.4 RADIO ASTRONOMY SPACE RESEARCH (pas- sive)		
722 736 737 738 739	722 736 737 738 739		722 US74 US246	722 US74 US246		
1668.4–1670.0	METEOROLOGICAL AIDS FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY 722 736		1668.4–1670.0 METEOROLOGICAL AIDS (radiosonde) RADIO ASTRONOMY	1668.4–1670.0 METEOROLOGICAL AIDS (radiosonde) RADIO ASTRONOMY		
			722 736 US74 US99	722 736 US74 US99		

1670–1675	METEOROLOGICAL AIDS FIXED METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE 740A 722		1670–1690 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth)	1670–1690 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth)	
1675–1690 METEOROLOGICAL AIDS FIXED	1675–1690 METEOROLOGICAL AIDS FIXED	1675–1690 METEOROLOGICAL AIDS FIXED			
METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 722	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 722 735A	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 722		722 US211	722 US211
1690–1700 METEOROLOGICAL AIDS FIXED	1690–1700 METEOROLOGICAL AIDS FIXED	1690–1700 METEOROLOGICAL AIDS FIXED	1690–1700 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth)	1690–1700 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth)	1690–1700 METEOROLOGICAL AIDS (radiosonde) METEOROLOGICAL-SAT- ELLITE (space-to-Earth)
METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 671 722 741	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE-SATELLITE (Earth-to-space) 671 722 735A 740	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE-SATELLITE (Earth-to-space) 671 722 740 742		671 722	671 722
1700–1710 FIXED	1700–1710 FIXED	1700–1710 FIXED	1700–1710 FIXED	1700–1710 FIXED	1700–1710 FIXED
METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 671 722	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile MOBILE-SATELLITE (Earth-to-space) 671 722 735A	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 671 722 743	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 671 722 G118	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) Fixed 671 722	METEOROLOGICAL-SAT- ELLITE (space-to-Earth) Fixed 671 722
1710–1850 FIXED	1710–1850 FIXED	1710–1850 FIXED	1710–1850 FIXED	1710–1850 FIXED	1710–1850 FIXED
MOBILE 740A 722 744 746	MOBILE 740A 722 744 745	MOBILE 740A 722 744 745	MOBILE 740A 722 744 745	MOBILE 722 US256 G42	MOBILE 722 US256

International table			United States table		FCC use designators	
Region 1—allocation MHz	Region 2—allocation MHz	Region 3—allocation MHz	Government Allocation MHz	Non-Government Allocation MHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
1850–1930 FIXED MOBILE 740A	1850–1930 FIXED MOBILE 740A	1850–1930 FIXED MOBILE 740A	1850–1930	1850–1930 FIXED MOBILE	FIXED MICROWAVE (101) PERSONAL COMMU- NICATIONS (24) RADIO FREQUENCY DE- VICES (15)	
746A	746A	746A				
1930–1970 FIXED MOBILE	1930–1970 FIXED MOBILE Mobile-Satellite (Earth-to- Space) 746A	1930–1970 FIXED MOBILE	1930–1970	1930–1970 FIXED MOBILE	FIXED MICROWAVE (101) PERSONAL COMMU- NICATIONS (24)	
746A		746A				
1970–1980 FIXED MOBILE	1970–1980 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space) 746A 746B 746C	1970–1980 FIXED MOBILE	1970–1980	1970–1980 FIXED MOBILE	FIXED MICROWAVE (101) PERSONAL COMMU- NICATIONS (24)	
746A		746A				
1980–1990 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space) S5.388 S5.389A S5.389F	1980–1990 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space) S5.388 S5.389A S5.389B	1980–1990 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space) S5.388 S5.389A	1980–1990	1980–1990 FIXED MOBILE	FIXED MICROWAVE (101) PERSONAL COMMU- NICATIONS (24)	
1990–2010 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space)	1990–2010 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space)	1990–2010 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space)	1990–2010	1990–2010 MOBILE-SATELLITE (Earth-to-space) US111	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION (78) SATELLITE COMMU- NICATIONS (25)	
S5.388 S5.389A S5.389F	S5.388 S5.389A	S5.388 S5.389A	US111	US111		

2010–2025 FIXED MOBILE	2010–2025 FIXED MOBILE MOBILE-SATELLITE (Earth-to-space)	2010–2025 FIXED MOBILE	2010–2025	2010–2025 MOBILE-SATELLITE (Earth-to-space)	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION (78) SATELLITE COMMU- NICATIONS (25)
S5.388	S5.388 S5.389C S5.389D S5.389E	S5.388	US111	US111	
2025–2110 SPACE OPERATION (Earth-to-space) (space- to-space) EARTH EXPLORATION- SATELLITE (Earth-to- space) (space-to-space) FIXED MOBILE S5.391 SPACE RESEARCH (Earth-to-space) (space- to-space) S5.392	2025–2110 SPACE OPERATION (Earth-to-space) (space- to-space) EARTH EXPLORATION- SATELLITE (Earth-to- space) (space-to-space) FIXED MOBILE S5.391 SPACE RESEARCH (Earth-to-space) (space- to-space) S5.392	2025–2110	2025–2110 FIXED MOBILE	2025–2110 FIXED MOBILE	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION (78)
2110–2120 FIXED MOBILE SPACE RESEARCH (deep space) (Earth-to- space)	2110–2120 FIXED MOBILE SPACE RESEARCH (deep space) (Earth-to- space)	2110–2120 FIXED MOBILE SPACE RESEARCH (deep space) (Earth-to- space)	2110–2120	2110–2120 FIXED MOBILE	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION (78) FIXED MICROWAVE (101) PUBLIC MOBILE (22)
S5.388	S5.388	S5.388	US90 US111 US219 US222	US90 US111 US219 US222 NG23 NG118	
2120–2130 FIXED MOBILE	2120–2130 FIXED MOBILE Mobile-Satellite (space-to- Earth)	2120–2130 FIXED MOBILE	2120–2130	2120–2130 FIXED MOBILE	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION (78) FIXED MICROWAVE (101) PUBLIC MOBILE (22)
S5.388	S5.388	S5.388	US111 US252 NG118	US111 US252 NG23 NG118	
2130–2150 FIXED MOBILE	2130–2150 FIXED MOBILE Mobile-Satellite (space-to- Earth)	2130–2150 FIXED MOBILE	2130–2150	2130–2150 FIXED MOBILE	FIXED MICROWAVE (101) PUBLIC MOBILE (22)
					EMERGING TECH- NOLO- GIES

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
S5.388	S5.388	S5.388		NG23 NG153		
2150–2160 FIXED MOBILE	2150–2160 FIXED MOBILE Mobile-Satellite (space-to-Earth) S5.388	2150–2160 FIXED MOBILE	2150–2160	2150–2160 FIXED	DOMESTIC PUBLIC FIXED (21) FIXED MICROWAVE (101)	
S5.388		S5.388		NG23		
2160–2165 FIXED MOBILE	2160–2165 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) S5.388 S5.389C S5.389D S5.389E	2160–2165 FIXED MOBILE	2160–2165	2160–2165 FIXED MOBILE	DOMESTIC PUBLIC FIXED (21) FIXED MICROWAVE (101) PUBLIC MOBILE (22)	EMERGING TECH- NOL- OGIES
S5.388 S5.392A		S5.388		NG23 NG153		
2165–2170 FIXED MOBILE	2165–2170 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) S5.388 S5.389C S5.389D S5.389E	2165–2170 FIXED MOBILE	2165–2170	2165–2170 MOBILE-SATELLITE (space-to-Earth) NG23	FIXED MICROWAVE (101) PUBLIC MOBILE (22) SATELLITE COMMU- NICATIONS (25)	
S5.388 S5.392A		S5.388				
2170–2200 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) S5.388 S5.389A S5.389F S5.392A	2170–2200 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) S5.388 S5.389A	2170–2200 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) S5.388 S5.389A	2170–2200	2170–2200 MOBILE-SATELLITE (space-to-Earth) NG23	FIXED MICROWAVE (101) PUBLIC MOBILE (22) SATELLITE COMMU- NICATIONS (25)	

2200–2290	FIXED SPACE RESEARCH (space-to-Earth) (space- to-space) SPACE OPERATION (space-to-Earth) (space- to-space) EARTH EXPLORATION- SATELLITE (space-to- Earth) (space-to-space) MOBILE 747A 750A		2200–2290 FIXED MOBILE SPACE RESEARCH (space-to-Earth) (space- to-space) US303 G101	2200–2290	
2290–2300	FIXED MOBILE except aeronauti- cal mobile SPACE RESEARCH (space-to-Earth) (deep space)		2290–2300 FIXED MOBILE except aeronauti- cal mobile SPACE RESEARCH (space-to-Earth) (deep space only) US303	2290–2300 SPACE RESEARCH (space-to-Earth) (deep space only)	
2300–2305	FIXED MOBILE RADIOLOCATION Amateur S5.394	2300–2305 FIXED MOBILE RADIOLOCATION Amateur	2300–2305 G123	2300–2305 Amateur	Amateur (97)
2305–2310	FIXED MOBILE RADIOLOCATION Amateur S5.394	2305–2310 FIXED MOBILE RADIOLOCATION Amateur	2305–2310 US338 G123	2305–2310 FIXED MOBILE except aeronauti- cal mobile RADIOLOCATION Amateur US338	WIRELESS COMMU- NICATIONS (27) Amateur (97)
2310–2320	FIXED MOBILE RADIOLOCATION Amateur S5.393 S5.394 S5.396	2310–2320 FIXED MOBILE RADIOLOCATION Amateur S5.393 S5.396	2310–2320 Fixed Mobile US339 Radiolocation G2 S5.396 US327 US338 G120	2310–2320 BROADCASTING-SAT- ELLITE US327 FIXED MOBILE US339 RADIOLOCATION S5.396 US338	WIRELESS COMMU- NICATIONS (27)

International table			United States table		FCC use designators	
Region 1—allocation MHz	Region 2—allocation MHz	Region 3—allocation MHz	Government Allocation MHz	Non-Government Allocation MHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
2320–2345 FIXED MOBILE Amateur Radiolocation S5.395	2320–2345 FIXED MOBILE RADIOLOCATION Amateur S5.393 S5.394 S5.396	2320–2345 FIXED MOBILE RADIOLOCATION Amateur S5.393 S5.396	2320–2345 Fixed Mobile US276 Radiolocation G2 S5.396 US327 US328 G120	2320–2345 BROADCASTING-SAT- ELLITE US 327 Mobile US276 US328 S5.396		Digital Audio Radio Services
2345–2360 FIXED MOBILE Amateur Radiolocation S5.395	2345–2360 FIXED MOBILE RADIOLOCATION Amateur S5.393 S5.394 S5.396	2345–2360 FIXED MOBILE RADIOLOCATION Amateur S5.393 S5.396	2345–2360 Fixed Mobile US339 Radiolocation G2 S5.396 US327 G120	2345–2360 BROADCASTING-SAT- ELLITE US 327 FIXED MOBILE US339 RADIOLOCATION S5.396	WIRELESS COMMU- NICATIONS (27)	Digital Audio Radio Services
2360–2390 FIXED MOBILE Amateur Radiolocation	2360–2390 FIXED MOBILE RADIOLOCATION Amateur S5.394	2360–2390 FIXED MOBILE RADIOLOCATION Amateur	2360–2390 MOBILE US276 RADIOLOCATION G2 Fixed G120	2360–2390 MOBILE US276		
2390–2400 FIXED MOBILE Amateur Radiolocation	2390–2400 FIXED MOBILE RADIOLOCATION Amateur S5.394	2390–2400 FIXED MOBILE RADIOLOCATION Amateur	2390–2400 G122	2390–2400 AMATEUR	AMATEUR (97) Radio Frequency Devices (15)	
2400–2402 FIXED MOBILE Amateur Radiolocation S5.150 S5.282	2400–2402 FIXED MOBILE RADIOLOCATION Amateur S5.150 S5.282 S5.394	2400–2402 FIXED MOBILE RADIOLOCATION Amateur S5.150 S5.282	2400–2402	2400–2402 Amateur	Amateur (97)	
2402–2417 FIXED MOBILE Amateur Radiolocation	2402–2417 FIXED MOBILE RADIOLOCATION Amateur	2402–2417 FIXED MOBILE RADIOLOCATION Amateur	2402–2417 S5.150 G123	2402–2417 AMATEUR S5.150 S5.282	AMATEUR (97) Radio Frequency Devices (15)	

S5.150 S5.282	S5.150 S5.282 S5.394	S5.150 S5.282	S5.150 G122	S5.150 S5.282	S5.150 S5.282	
2417–2450 FIXED MOBILE Amateur Radiolocation S5.150 S5.282	2417–2450 FIXED MOBILE RADIOLOCATION Amateur S5.150 S5.282 S5.394	2417–2450 FIXED MOBILE RADIOLOCATION Amateur S5.150 S5.282	2417–2450 Radiolocation G2 S5.150 S5.282 G124	2417–2450 Amateur S5.150 S5.282	Amateur (97)	
2450–2483.5 FIXED MOBILE Radiolocation	2450–2483.5 FIXED MOBILE RADIOLOCATION		2450–2483.5	2450–2483.5 FIXED MOBILE Radiolocation		2450±50 MHz: In- dustrial, scientific and medi- cal fre- quency
752 753	752		752 US41	752 US41		
2483.5–2500 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) Radiolocation	2483.5–2500 FIXED MOBILE RADIOLOCATION MOBILE-SATELLITE (space-to-Earth) 753A RADIOLOCATION MOBILE-SATELLITE (space-to-Earth)	2483.5–2500 FIXED MOBILE MOBILE-SATELLITE (space-to-Earth) Radiolocation-Satellite (space-to-Earth) 753A	2483.5–2500 RADIOLOCATION MOBILE-SATELLITE (space-to-Earth) 753A MOBILE-SATELLITE (space-to-Earth)	2483.5–2500 RADIOLOCATION MOBILE-SATELLITE (space-to-Earth) 753A MOBILE-SATELLITE (space-to-Earth)	SATELLITE COMMUNICATION (25)	
733F 752 753 753A 753B 753C 753F	752 753D 753F	752 753C 753F	752 753F US41 US319	752 753F US41 US319 NG147		
2500–2655 FIXED 762 764 MOBILE except aeronautical mobile BROADCASTING-SATELLITE 757 760	2500–2655 FIXED 762 764 MOBILE except aeronautical mobile BROADCASTING-SATELLITE 757 760	2500–2655 FIXED 762 764 MOBILE except aeronautical mobile BROADCASTING-SATELLITE 757 760 754 754A	2500–2655	2500–2655 FIXED BROADCASTING-SATELLITE	AUXILIARY BROADCASTING (74) DOMESTIC PUBLIC FIXED RADIO (21)	
720 753 756 758 759	720 755	720	720 US205 US269	720 US205 US269 NG102		

International table			United States table		FCC use designators	
Region 1—allocation MHz	Region 2—allocation MHz	Region 3—allocation MHz	Government Allocation MHz	Non-Government Allocation MHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
2655–2690 FIXED 762 763 764 MOBILE except aeronautical mobile BROADCASTING-SATELLITE 757 760 Earth Exploration-Satellite (passive) Radio Astronomy Space Research (passive)	2655–2690 FIXED 762 764 FIXED-SATELLITE (Earth-to-space) (space-to-Earth) 761 MOBILE except aeronautical mobile BROADCASTING-SATELLITE 757 760 ELLITE 757 760 Earth Exploration-Satellite (passive) Radio Astronomy Space Research (passive)	2655–2690 FIXED 762 764 FIXED-SATELLITE (Earth-to-space) 761 MOBILE except aeronautical mobile BROADCASTING-SATELLITE 757 760 ELLITE 757 760 Earth Exploration-Satellite (passive) Radio Astronomy Space Research (passive)	2655–2690 Earth Exploration-Satellite (passive) Radio Astronomy Space Research (passive)	2655–2690 FIXED BROADCASTING-SATELLITE ELLITE Earth Exploration-Satellite (passive) Radio Astronomy Space Research (passive)	AUXILIARY BROADCASTING (74) PRIVATE OPERATIONAL-FIXED MICROWAVE (94)	
758 759 765	765	765 766	US205 US269	US205 US269 NG47 NG101 NG102		
2690–2700	EARTH EXPLORATION-SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (passive) 767 768 769		2690–2700 EARTH EXPLORATION-SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (passive) US74 US246	2690–2700 EARTH EXPLORATION-SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (passive) US74 US246		
2700–2900	AERONAUTICAL RADIO-NAVIGATION 717 Radiolocation 770 771		2700–2900 AERONAUTICAL RADIO-NAVIGATION 717 METEOROLOGICAL AIDS Radiolocation 770 US18 G2 G15	2700–2900 717 770 US18		
2900–3100	RADIONAVIGATION Radiolocation 772 773 775A		2900–3100 MARITIME RADIO-NAVIGATION 775A Radiolocation US44 US316 G56	2900–3100 MARITIME RADIO-NAVIGATION 775A Radiolocation US44 US316	MARITIME (80)	
3100–3300	RADIOLOCATION 713 777 778		3100–3300 RADIOLOCATION 713 778 US110 G59	3100–3300 Radiolocation 713 778 US110		

3300–3400 RADIOLOCATION	3300–3400 RADIOLOCATION Amateur Fixed Mobile 778 779 780	3300–3400 RADIOLOCATION Amateur 778 779	3300–3500 RADIOLOCATION	3300–3500 Amateur Radiolocation	Amateur (97)	
3400–3600 FIXED FIXED-SATELLITE (space-to-Earth) Mobile Radiolocation	3400–3500 FIXED FIXED-SATELLITE (space-to-Earth) Amateur Mobile Radiolocation 784 664 783		664 778 US108 G31	664 778 US108		
781 782 785	3500–3700 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile Radiolocation 784		3500–3600 AERONAUTICAL RADIO- NAVIGATION (ground- based) RADIOLOCATION US110 G59 G110	3500–3600 Radiolocation US110		
3600–4200 FIXED FIXED-SATELLITE (space-to-Earth) Mobile	786		3600–3700 AERONAUTICAL RADIO- NAVIGATION (ground- based) RADIOLOCATION US110 US245 G59 G110	3600–3700 FIXED-SATELLITE (space-to-Earth) Radiolocation US110 US245		
	3700–4200 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile 787		3700–4200	3700–4200 FIXED FIXED-SATELLITE (space-to-Earth) NG41	DOMESTIC PUBLIC FIXED (21) SATELLITE COMMU- NICATIONS (25) PRIVATE OPERATIONAL FIXED MICROWAVE (94)	
4200–4400	AERONAUTICAL RADIO- NAVIGATION 789 788 790 791		4200–4400 AERONAUTICAL RADIO- NAVIGATION 791 US261	4200–4400 AERONAUTICAL RADIO- NAVIGATION 791 US261	AVIATION (87)	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
4400–4500	FIXED MOBILE		4400–4500 FIXED MOBILE	4400–4500		
4500–4800 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	4500–4800 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	4500–4800 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	4500–4660 FIXED MOBILE US245	4500–4660 FIXED-SATELLITE (space-to-Earth) 792A US245		
			4660–4685 G122	4660–4685 FIXED-SATELLITE (space-to-Earth) MOBILE 792A US245		
792A	792A	792A	4685–4800 FIXED MOBILE US245	4685–4800 FIXED-SATELLITE (space-to-Earth) 792A US245		
4800–4990	FIXED MOBILE 793 Radio Astronomy 720 778 794		4800–4990 FIXED MOBILE	4800–4990		
4990–5000	FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY Space Research (passive) 795		4990–5000 RADIO ASTRONOMY Space Research (passive)	4990–5000 RADIO ASTRONOMY Space Research (passive)		
5000–5250	AERONAUTICAL RADIO- NAVIGATION		US74 US246 5000–5250 AERONAUTICAL RADIO- NAVIGATION	US74 US246 5000–5250 AERONAUTICAL RADIO- NAVIGATION	AVIATION (87) Satellite communication (25)	

5250–5255	733 796 797 797A 797B	733 796 797 797A US211 US260 US307	733 796 797 797A US211 US260 US307		
	RADIOLOCATION Space Research 713 798	5250–5350 RADIOLOCATION	5250–5350 Radiolocation		
5255–5350	RADIOLOCATION 713 798	713 US110 G59	713 US110		
	AERONAUTICAL RADIO- NAVIGATION 799 Radiolocation	5350–5460 AERONAUTICAL RADIO- NAVIGATION 799 RADIOLOCATION US48 G56	5350–5460 AERONAUTICAL RADIO- NAVIGATION 799 Radiolocation US48	AVIATION (87)	
5460–5470	RADIONAVIGATION 799 Radiolocation	5460–5470 RADIONAVIGATION 799 Radiolocation US49 US65 G56	5460–5470 RADIONAVIGATION 799 Radiolocation US49 US65		
	MARITIME RADIO- NAVIGATION Radiolocation	5470–5600 MARITIME RADIO- NAVIGATION Radiolocation US50 US65 G56	5470–5600 MARITIME RADIO- NAVIGATION Radiolocation US50 US65	MARITIME (80)	
5650–5725	800 801 802	5600–5650 MARITIME RADIO- NAVIGATION METEOROLOGICAL AIDS Radiolocation 772 802 US51 US65 G56	5600–5650 MARITIME RADIO- NAVIGATION METEOROLOGICAL AIDS Radiolocation 772 802 US51 US65	MARITIME (80)	
	RADIOLOCATION Amateur Space Research (deep space) 664 801 803 804 805	5650–5850 RADIOLOCATION	5650–5850 Amateur	Amateur (97) Industrial, Scientific, and Medical Equipment (18)	58000±75 MHz In- dustrial, scientific and medi- cal fre- quency

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
5725–5850 FIXED-SATELLITE (Earth- to-space) RADIOLOCATION Amateur 801 803 805 806 807 808	5725–5850 RADIOLOCATION Amateur 803 805 806 808		664 806 808 G2	644 806 808		
5850–5925 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 806	5850–5925 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Amateur Radiolocation 806	5850–5925 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Radiolocation 806	5850–5925 RADIOLOCATION	5850–5925 FIXED-SATELLITE (Earth- to-space) Amateur	Amateur (97)	
5925–7075	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE		806 US245 G2 5925–7125	806 US245 5925–6425 FIXED FIXED SATELLITE (Earth- to-space) NG41	DOMESTIC PUBLIC FIXED (21) SATELLITE COMMU- NICATIONS (25) PRIVATE OPERATIONAL FIXED MICROWAVE (94)	
				6425–6525 FIXED-SATELLITE (Earth- to-space) MOBILE 791 809	AUXILIARY BROADCAST (74) CABLE TELEVISION (78) DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	

7075–7250	791 792A 809 FIXED MOBILE	6525–6875 FIXED FIXED-SATELLITE (Earth- to-space) 792A 809 6875–7075 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 792A 809 NG118 7075–7125 FIXED MOBILE 809 NG118 7125–8450	DOMESTIC PUBLIC FIXED (21) SATELLITE COMMU- NICATIONS (25) PRIVATE OPERATION- FIXED MICROWAVE (94) AUXILIARY BROADCAST (74) CABLE TELEVISION (78) DOMESTIC PUBLIC FIXED (21) AUXILIARY BROADCAST (74) CABLE TELEVISION (78) DOMESTIC PUBLIC FIXED (21)	
7250–7300	809 810 811 FIXED-SATELLITE (space-to-Earth) MOBILE 812	791 809 7125–7190 FIXED 809 US252 G116 7190–7235 FIXED SPACE RESEARCH (Earth-to-space) 809 7235–7250 FIXED 809 7250–7300 FIXED-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) Fixed G117		

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
7300–7450	FIXED FIXED-SATELLITE (space-to-Earth) MOBILE except aeronautical mobile 812		7300–7450 FIXED FIXED-SATELLITE (space-to-Earth) Mobile-Satellite (space-to- Earth) G117			
7450–7550	FIXED FIXED-SATELLITE (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile		7450–7550 FIXED FIXED-SATELLITE (space-to-Earth) METEOROLOGICAL-SAT- ELLITE (space-to-Earth) Mobile-Satellite (space-to- Earth) G104 G117			
7550–7750	FIXED FIXED-SATELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile		7550–7750 FIXED FIXED-SATELLITE (space-to-Earth) Mobile-Satellite (space-to- Earth) G117			
7750–7900	FIXED MOBILE except aeronauti- cal mobile		7750–7900 FIXED			
7900–7975	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 812		7900–8025 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) Fixed			

7975-8025	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 812		G117	
8025-8175 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 815	8025-8175 EARTH EXPLORATION- SATELLITE (space-to- Earth) FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 814	8025-8175 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 815	8025-8175 EARTH EXPLORATION- SATELLITE (space-to- Earth) FIXED FIXED-SATELLITE (Earth- to-space) Mobile-Satellite (Earth-to- space) (no airborne transmission) US258 G117	
8175-8215 FIXED FIXED-SATELLITE (Earth- to-space) METEOROLOGICAL-SAT- ELLITE (Earth-to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 815	8175-8215 EARTH EXPLORATION- SATELLITE (space-to- Earth) FIXED FIXED-SATELLITE (Earth- to-space) METEOROLOGICAL-SAT- ELLITE (Earth-to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 MOBILE 814	8175-8215 FIXED FIXED-SATELLITE (Earth- to-space) METEOROLOGICAL-SAT- ELLITE (Earth-to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 815	8175-8215 EARTH EXPLORATION- SATELLITE (space-to- Earth) FIXED FIXED-SATELLITE (Earth- to-space) METEOROLOGICAL-SAT- ELLITE (Earth-to-space) Mobile-Satellite (Earth-to- space) (no airborne transmissions) US258 G104 G117	
8215-8400 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 815	8215-8400 EARTH EXPLORATION- SATELLITE (space-to- Earth) FIXED FIXED-SATELLITE (Earth-to-space) MOBILE 814	8215-8400 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Earth Exploration-Satellite (space-to-Earth) 813 815	8215-8400 EARTH EXPLORATION SATELLITE (space-to- Earth) FIXED FIXED-SATELLITE (Earth- to-space) Mobile-Satellite (Earth-to- space) (no airborne transmissions) US258 G117	

International table			United States table		FCC use designators	
Region 1—allocation MHz (1)	Region 2—allocation MHz (2)	Region 3—allocation MHz (3)	Government Allocation MHz (4)	Non-Government Allocation MHz (5)	Rule part(s) (6)	Special-use frequencies (7)
8400–8500	FIXED MOBILE except aeronauti- cal mobile SPACE RESEARCH (space-to-Earth) 816 817		8400–8450 FIXED SPACE RESEARCH (space-to-Earth) (deep space only)	809 US252 US258		
	818		8450–8500 FIXED SPACE RESEARCH (space-to-Earth)	8450–8500 SPACE RESEARCH (space-to-Earth)		
8500–8750	RADIOLOCATION 713 819 820		8500–9000 RADIOLOCATION	8500–9000 Radiolocation		
8750–8850	RADIOLOCATION AERONAUTICAL RADIO- NAVIGATION 821 822					
8850–9000	RADIOLOCATION MARITIME RADIO- NAVIGATION 823 824					
9000–9200	AERONAUTICAL RADIO- NAVIGATION 717 Radiolocation 822		713 US53 US110 G59 9000–9200 AERONAUTICAL RADIO- NAVIGATION 717 Radiolocation US48 US54 G2 G19	713 US53 US110 9000–9200 AERONAUTICAL RADIO- NAVIGATION 717 Radiolocation US48 US54	AVIATION (87)	
9200–9300	RADIOLOCATION MARITIME RADIO- NAVIGATION 823		9200–9300 MARITIME RADIO- NAVIGATION RADIOLOCATION	9200–9300 MARITIME RADIO- NAVIGATION Radiolocation		

9300–9500	824 824A		US110 G59 823 824A	US110 823 824A	
	RADIONAVIGATION RADIOLOCATION 825A		9300–9500 RADIONAVIGATION 825A Meteorological Aids Radiolocation 775A 824A US51 US66 US67 US71 G56	9300–9500 RADIONAVIGATION 825A Meteorological Aids Radiolocation 775A 824A US51 US66 US67 US71	
	775A 824A 825		9500–10.000 RADIOLOCATION	9500–10.000 Radiolocation	
9500–9800	RADIOLOCATION RADIONAVIGATION 713		713 828 US110	713 828 US110	
	RADIOLOCATION Fixed 826 827 828				
9800–10.000					
International table					
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	United States table		FCC use designators
			Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)
10.0–10.45 FIXED MOBILE RADIOLOCATION Amateur 828	10.00–10.45 RADIOLOCATION Amateur 828 829	10.00–10.45 FIXED MOBILE RADIOLOCATION Amateur 828	10.0–10.45 RADIOLOCATION	10.0–10.45 Amateur Radiolocation	Amateur (97) Private Land Mobile (90)
10.45–10.5	RADIOLOCATION Amateur Amateur-Satellite 830		828 US58 US108 G32	828 US58 US108 NG42	
			10.45–10.50 RADIOLOCATION	10.45–10.50 Amateur Amateur-Satellite Radiolocation US58 US108 NG42 NG134	Amateur (97) Private Land Mobile (90)
10.50–10.55 FIXED MOBILE Radiolocation	10.50–10.55 FIXED MOBILE RADIOLOCATION		10.50–10.55 RADIOLOCATION US59	10.50–10.55 RADIOLOCATION US59	PRIVATE LAND MOBILE (90)

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government	Non-Government	Rule part(s)	Special-use frequencies (7)
			Allocation GHz (4)	Allocation GHz (5)		
10.55–10.60	FIXED MOBILE except aeronauti- cal mobile Radiolocation		10.55–10.60	10.55–10.60 FIXED	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL–FIXED MICROWAVE (94)	
10.60–10.68	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY SPACE RESEARCH (pas- sive) Radiolocation 831 832		10.60–10.68 EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive)	10.60–10.68 EARTH EXPLORATION- SATELLITE (passive) FIXED SPACE RESEARCH (pas- sive)	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL–FIXED MICROWAVE (94)	
10.68–10.70	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 833 834		10.68–10.70 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246	US265 US277 10.68–10.70 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246		
10.7–11.7	FIXED FIXED-SATELLITE (space-to-Earth) S5.441 MOBILE except aeronauti- cal mobile	FIXED FIXED-SATELLITE (space-to-Earth) S5.441 MOBILE except aeronauti- cal mobile	10.7–11.7	10.7–11.7 FIXED FIXED-SATELLITE (space-to-Earth) S5.441 US211 NG104	FIXED MICROWAVE (101) SATELLITE COMMU- NICATIONS (25)	

11.7-12.5 FIXED BROADCASTING BROADCASTING-SAT- ELLITE Mobile except aeronautical mobile	11.7-12.1 FIXED 837 FIXED-SATELLITE (space-to Earth) Mobile except aeronautical mobile 836 839	11.7-12-2 FIXED MOBILE except aeronauti- cal mobile BROADCASTING BROADCASTING-SAT- ELLITE 838	11.7-12.2	11.7-12.2 FIXED-SATELLITE (space-to Earth) Mobile except aeronautical mobile 837 839 NG143 NG145	DOMESTIC PUBLIC FIXED (21) SATELLITE COMMU- NICATION (25)	
	12.1-12.2 FIXED-SATELLITE (space-to-Earth) 836 839 842	12.2-12.5 FIXED MOBILE except aeronauti- cal mobile BROADCASTING 838 845	12.2-12.7	12.2-12.7 FIXED BROADCASTING-SAT- ELLITE	INTERNATIONAL PUBLIC (23) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94) DIRECT BROADCAST SATELLITE SERVICE (100)	
	12.2-12.7 FIXED MOBILE except aeronauti- cal mobile BROADCASTING BROADCASTING-SAT- ELLITE 839 844 846	12.5-12.75 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE except aeronauti- cal mobile BROADCASTING-SAT- ELLITE 847	839 843 844	839 843 844 NG139		
838 12.5-12.75 FIXED-SATELLITE (space-to-Earth) (Earth- to-space)						

International table			United States table		FCC use designators	
Region 1—allocation GHz	Region 2—allocation GHz	Region 3—allocation GHz	Government Allocation GHz	Non-Government Allocation GHz	Rule part(s)	Special-use frequencies
(1)	(2)	(3)	(4)	(5)	(6)	(7)
	12.7–12.75 FIXED FIXED-SATELLITE MOBILE except aeronautical mobile		12.7–12.75	12.7–12.75 FIXED-SATELLITE (Earth-to-space) MOBILE	AUXILIARY BROADCASTING (74) CABLE TELEVISION RELAY (78) PRIVATE OPERATIONAL-FIXED MICROWAVE (94)	
848 849 850				NG53 NG118		
12.75–13.25 FIXED FIXED-SATELLITE (Earth-to-space) S5.441 MOBILE Space Research (deep space)(space-to-Earth)	12.75–13.25 FIXED FIXED-SATELLITE (Earth-to-space) S5.441 MOBILE Space Research (deep space)(space-to-Earth)	12.75–13.25 FIXED FIXED-SATELLITE (Earth-to-space) S5.441 MOBILE Space Research (deep space)(space-to-Earth)	12.75–13.25	12.75–13.25 FIXED-SATELLITE (Earth-to-space) S5.441 NG104 MOBILE US251 NG53 NG118	AUXILIARY BROADCASTING (74) CABLE TV RELAY (78) FIXED MICROWAVE (101)	
13.25–13.4 AERONAUTICAL RADIO-NAVIGATION S5.497 S5.498	13.25–13.4 AERONAUTICAL RADIO-NAVIGATION S5.497 S5.498	13.25–13.4 AERONAUTICAL RADIO-NAVIGATION S5.497 S5.498 S5.499	13.25–13.4 AERONAUTICAL RADIO-NAVIGATION S5.497 Space Research (Earth-to-space)	13.25–13.4 AERONAUTICAL RADIO-NAVIGATION S5.497 Space Research (Earth-to-space)	AVIATION (87)	
13.4–13.75 RADIOLOCATION Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333 S5.500 S5.501	13.4–13.75 RADIOLOCATION Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333	13.4–13.75 RADIOLOCATION Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333 S5.499 S5.500 S5.501	13.4–13.75 RADIOLOCATION US110 G59 Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333	13.4–13.75 Radiolocation US110 Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333	Private Land Mobile (90)	

Federal Communications Commission

§ 2.106

13.75–14.0 FIXED-SATELLITE (Earth-to-space) RADIOLOCATION Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333 S5.500 S5.501 S5.502 S5.503 S5.503A	13.75–14.0 FIXED-SATELLITE (Earth-to-space) RADIOLOCATION Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333 S5.502 S5.503 S5.503A	13.75–14.0 RADIOLOCATION US110 GS9 Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research US337 S5.333 S5.502 S5.503 S5.503A	13.75–14.0 FIXED-SATELLITE (Earth-to-space) US337 Radiolocation US110 Standard Frequency and Time Signal-Satellite (Earth-to-space) Space Research S5.333 S5.502 S5.503 S5.503A	SATELLITE COMMUNICATION (25) Private Land Mobile (90)	
14.0–14.2 FIXED-SATELLITE (Earth-to-space) S5.506 RADIONAVIGATION S5.504 Land Mobile-Satellite (Earth-to-space) Space Research S5.505	14.0–14.2 FIXED-SATELLITE (Earth-to-space) S5.506 RADIONAVIGATION S5.504 Land Mobile-Satellite (Earth-to-space) Space Research S5.505	14.0–14.2 RADIONAVIGATION US292 Space Research	14.0–14.2 FIXED-SATELLITE (Earth-to-space) RADIONAVIGATION Land Mobile-Satellite (Earth-to-space) Space Research	SATELLITE COMMUNICATIONS (25) Aviation (87) Maritime (80)	
14.2–14.25 FIXED-SATELLITE (Earth-to-space) S5.506 RADIONAVIGATION S5.504 Land Mobile-Satellite (Earth-to-space) Space Research S5.505	14.2–14.25 FIXED-SATELLITE (Earth-to-space) S5.506 RADIONAVIGATION S5.504 Land Mobile-Satellite (Earth-to-space) Space Research S5.505	14.2–14.25	14.2–14.25 FIXED-SATELLITE (Earth-to-space) Land Mobile-Satellite (Earth-to-space) Mobile except aeronautical mobile	SATELLITE COMMUNICATIONS (25) Fixed Microwave (101)	
14.25–14.3 FIXED-SATELLITE (Earth-to-space) S5.506 RADIONAVIGATION S5.504 Land Mobile-Satellite (Earth-to-space) Space Research S5.505	14.25–14.3 FIXED-SATELLITE (Earth-to-space) S5.506 RADIONAVIGATION S5.504 Land Mobile-Satellite (Earth-to-space) Space Research S5.505	14.25–14.3	14.25–14.3 FIXED-SATELLITE (Earth-to-space) Land Mobile-Satellite (Earth-to-space) Mobile except aeronautical mobile	SATELLITE COMMUNICATIONS (25) Fixed Microwave (101)	

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
14.3–14.4 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Radionavigation-Satellite	14.3–14.4 FIXED-SATELLITE (Earth- to-space) S5.506 Land Mobile-Satellite (Earth-to-space) Radionavigation-Satellite	14.3–14.4 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Radionavigation-Satellite	14.3–14.4 Fixed Mobile	14.3–14.4 FIXED-SATELLITE (Earth- to-space) Land Mobile-Satellite (Earth-to-space) Mobile except aeronautical mobile	SATELLITE COMMU- NICATIONS (25) Fixed Microwave (101)	
14.4–14.47 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Space Research (space- to-Earth)	14.4–14.47 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Space Research (space- to-Earth)	14.4–14.47 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Space Research (space- to-Earth)	14.4–14.47 Fixed Mobile	14.4–14.47 FIXED-SATELLITE (Earth- to-space) Land Mobile-Satellite (Earth-to-space)	SATELLITE COMMU- NICATIONS (25)	
14.47–14.5 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Radio Astronomy S5.149	14.47–14.5 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Radio Astronomy S5.149	14.47–14.5 FIXED FIXED-SATELLITE (Earth- to-space) S5.506 MOBILE except aeronauti- cal mobile Land Mobile-Satellite (Earth-to-space) Radio Astronomy S5.149	14.47–14.5 Fixed Mobile	14.47–14.5 FIXED-SATELLITE (Earth- to-space) Land Mobile-Satellite (Earth-to-space) S5.149 US203	SATELLITE COMMU- NICATIONS (25)	
14.5–14.8	FIXED FIXED-SATELLITE (Earth- to-space) 863 MOBILE Space Research		14.5000–14.7145 FIXED Mobile Space Research 14.7145–15.1365	14.50–15.35		

14.80–15.35				MOBILE Fixed Space Research			
	FIXED MOBILE Space Research			US310 G119			
				15.1365–15.35 FIXED Mobile Space Research 720 US211	720 US211 US310		
15.35–15.40		720	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 864 865	15.35–15.40 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246	15.35–15.40 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246		
15.4–15.7			AERONAUTICAL RADIO- NAVIGATION 733 797	15.4–15.7 AERONAUTICAL RADIO- NAVIGATION 733 797 US211 US260	15.4–15.7 AERONAUTICAL RADIO- NAVIGATION 733 797 US211 US260	AVIATION (87)	
15.7–16.6			RADIOLOCATION 866 867	15.7–16.6 RADIOLOCATION US110 G59	15.7–17.2 Radiolocation	Private Land Mobile (90)	
16.6–17.1			RADIOLOCATION Space Research (deep space) (Earth-to-space) 866 867	16.6–17.1 RADIOLOCATION Space Research (deep space) (Earth-to-space) US110 G59			
17.1–17.2			RADIOLOCATION 866 867	17.1–17.2 RADIOLOCATION US110 G59	US110		
17.2–17.3			RADIOLOCATION Earth Exploration-Satellite (active) 866 867	17.2–17.3 RADIOLOCATION Earth Exploration-Satellite (active) US110 G59	17.2–17.3 Radiolocation Earth Exploration-Satellite (active) Space Research (active) US110	Private Land Mobile (90)	

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
17.3–17.7	FIXED-SATELLITE (Earth-to-space) 869 Radiolocation 868		17.3–17.7 Radiolocation US259 US271 G59	17.3–17.7 FIXED-SATELLITE (Earth-to-space) US259 US271 NG140		
17.7–17.8 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) 869 MOBILE	17.7–17.8 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) 869 MOBILE	17.7–17.8 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) 869 MOBILE	17.7–17.8 US271	17.7–17.8 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) MOBILE US271 NG140 NG144	AUXILIARY BROADCASTING (74) CABLE TELEVISION RELAY (78) DOMESTIC PUBLIC FIXED (21) PRIVATE OPERATIONAL-FIXED MICROWAVE (94)	
17.8–18.1 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) 869 MOBILE	17.8–18.1 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) 869 MOBILE	17.8–18.1 FIXED FIXED-SATELLITE (space-to-Earth) (Earth-to-space) 869 MOBILE	17.8–18.1 US334 G117	17.8–18.1 FIXED-SATELLITE (space-to-Earth) MOBILE US334 NG144	AUXILIARY BROADCASTING (74) CABLE TELEVISION RELAY (78) DOMESTIC PUBLIC FIXED (21) PRIVATE OPERATIONAL-FIXED MICROWAVE (94)	
18.1–18.6 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	18.1–18.6 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	18.1–18.6 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	18.1–18.6 870 US334 G117	18.1–18.6 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE 870 US334 NG144	AUXILIARY BROADCASTING (74) CABLE TELEVISION RELAY (78) DOMESTIC PUBLIC FIXED (21) PRIVATE OPERATIONAL-FIXED MICROWAVE (94)	

18.6–18.8 FIXED FIXED-SATELLITE (space-to-Earth) 872 MOBILE except aeronauti- cal mobile Earth Exploration-Satellite (passive) Space Research (passive) 871	18.6–18.8 EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) 872 MOBILE except aeronauti- cal mobile Earth Exploration-Satellite (passive) Space Research (passive) 871	18.6–18.8 EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) US254 US255 US334 G117	18.6–18.8 EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) 872 MOBILE except aeronauti- cal mobile Earth Exploration-Satellite (passive) SPACE RESEARCH (pas- sive) US254 US255 US334 NG144	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION RELAY (78) DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)
18.8–19.7 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	18.8–19.7 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	18.8–19.7 US334 G117	18.8–19.7 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE US334 NG144	AUXILIARY BROAD- CASTING (74) CABLE TELEVISION RELAY (78) DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)
19.7–20.1 FIXED-SATELLITE (space-to-Earth) Mobile-Satellite (space- to-Earth) 873 873A 873B 873C 873D 873E	19.7–20.1 FIXED-SATELLITE (space-to-Earth) Mobile-Satellite (space-to- Earth) 873	19.7–20.1 US334 G117	19.7–20.1 FIXED-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 873A 873B 873C 873D 873E US334	
20.1–20.2 FIXED-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 873 873A 873B 873C 873D	20.1–20.2 FIXED-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 873 873A 873B 873C 873D	20.1–20.2 US334 G117	20.1–20.2 FIXED-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth) 873A 873B 873C 873D US334	
21.2–21.4	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive)	21.2–21.4 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) US263	21.2–21.4 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) US263	21.2–21.4 DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
21.4–22.0	FIXED MOBILE		21.4–22.0 FIXED MOBILE	21.4–22.0 FIXED MOBILE	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	
22.00–22.21	FIXED MOBILE except aeronauti- cal mobile 874		22.00–22.21 FIXED MOBILE except aeronauti- cal mobile 874	22.00–22.21 FIXED MOBILE except aeronauti- cal mobile 874	DOMESTIC PUBLIC MO- BILE (22) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	
22.21–22.50	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 875 876		22.21–22.50 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 875 US263	22.21–22.50 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE except aeronauti- cal mobile RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 875 US263	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	
22.50–22.55 FIXED MOBILE	22.50–22.55 FIXED MOBILE	22.50–22.55 FIXED MOBILE	22.50–22.55 FIXED MOBILE US211	22.50–22.55 FIXED MOBILE US211	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	
22.55–23 FIXED INTER-SATELLITE MOBILE	22.55–23 FIXED INTER-SATELLITE MOBILE	22.55–23 FIXED INTER-SATELLITE MOBILE	22.55–23 FIXED INTER-SATELLITE MOBILE US211	22.55–23 FIXED INTER-SATELLITE MOBILE	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94) SATELLITE COMMU- NICATIONS (25)	

879	879	879	879 US278	879 US278	879 US278	
23.00–23.55	FIXED INTER-SATELLITE MOBILE		23.00–23.55 FIXED INTER-SATELLITE MOBILE	23.00–23.55 FIXED INTER-SATELLITE MOBILE	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	
23.55–23.60	879		879 US278	879 US278	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)	
23.6–24.0	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 880		23.6–24.0 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246	23.6–24.0 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246		
24.00–24.05	AMATEUR AMATEUR-SATELLITE 881		24.00–24.05 881 US211	24.00–24.05 AMATEUR AMATEUR-SATELLITE 881 US211	AMATEUR (97)	
24.05–24.25	RADIOLOCATION Amateur Earth Exploration-Satellite (active) 881		24.05–24.25 RADIOLOCATION Earth Exploration-Satellite (active) 881 US110 G59	24.05–24.25 Amateur Radiolocation Earth Exploration-Satellite (active) 881 US110	Amateur (97) Private Land Mobile (90)	24.125±125 GHz: In- dustrial, scientific and medi- cal fre- quency
24.25–24.45 FIXED	24.25–24.45 RADIO NAVIGATION FIXED MOBILE	24.25–24.45 RADIO NAVIGATION FIXED MOBILE	24.25–24.45 US341	24.25–24.45 FIXED US341	AVIATION (87) FIXED MICROWAVE (101)	

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
24.45–24.65 FIXED INTER-SATELLITE	24.45–24.65 RADIONAVIGATION INTER-SATELLITE 882E	24.45–24.65 RADIONAVIGATION FIXED INTER-SATELLITE MOBILE 882E	24.45–24.65 INTER-SATELLITE RADIONAVIGATION 882E	24.45–24.65 INTER-SATELLITE RADIONAVIGATION 882E	SATELLITE COMMU- NICATION (25)	
24.65–24.75 FIXED INTER-SATELLITE	24.65–24.75 INTER-SATELLITE RADIOLOCATION-SAT- ELLITE (Earth-to-space)	24.65–24.75 FIXED INTER-SATELLITE MOBILE 882E 882F	24.65–24.75 INTER-SATELLITE RADIOLOCATION-SAT- ELLITE (Earth-to-space)	24.65–24.75 INTER-SATELLITE RADIOLOCATION-SAT- ELLITE (Earth-to-space)	SATELLITE COMMU- NICATION (25)	
24.75–25.05 FIXED	24.75–25.05 FIXED-SATELLITE (Earth- to-space) S5.535	24.75–25.05 FIXED FIXED-SATELLITE (Earth- to-space) S5.535 MOBILE S5.534	24.75–25.05 RADIONAVIGATION	24.75–25.05 RADIONAVIGATION	AVIATION (87)	
25.05–25.25 FIXED	25.05–25.25 FIXED-SATELLITE (Earth- to-space) S5.535	25.05–25.25 FIXED FIXED-SATELLITE (Earth- to-space) S5.535 MOBILE S5.534	25.05–25.25	25.05–25.25 RADIONAVIGATION FIXED	AVIATION (87) FIXED MICROWAVE (101)	
25.25–27.00			25.25–27.00	25.25–27.00		
	FIXED MOBILE Earth Exploration-Satellite (space-to-space) Standard Frequency and Time Signal-Satellite (Earth-to-space)		FIXED MOBILE Earth Exploration-Satellite (space-to-space) Standard Frequency and Time Signal-Satellite (Earth-to-space)	Earth Exploration-Satellite (space-to-space) Standard Frequency and Time Signal-Satellite (Earth-to-space)		

27.0–27.5 FIXED MOBILE Earth Exploration-Satellite (space-to-space)	27.0–27.5 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Earth Exploration-Satellite (space-to-space)	27.0–27.5 FIXED MOBILE Earth Exploration-Satellite (space-to-space)	27.0–27.5 Earth Exploration-Satellite (space-to-space)	
27.5–29.5	27.5–29.5 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE	27.5–29.5	27.5–29.5 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE	SATELLITE-COMMU- NICATIONS (25) FIXED MICROWAVE (101)
29.5–29.9 FIXED-SATELLITE (Earth- to-space) 882D MOBILE-SATELLITE (Earth-to-space) Earth Exploration-Satellite (Earth-to-space) 882C 873A 873B 873C 873E 882B 883	29.5–29.9 FIXED-SATELLITE (Earth- to-space) 882D MOBILE-SATELLITE (Earth-to-space) Earth Exploration-Satellite (Earth-to-space) 882C 873A 873B 873C 873E 882B 883	29.5–29.9 FIXED-SATELLITE (Earth- to-space) 882D MOBILE-SATELLITE (Earth-to-space) Earth Exploration-Satellite (Earth-to-space) 882C 873A 873B 873C 873E 882B 883	29.5–29.9 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) 873A 873B 873C 873E	
29.9–30.0 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) Earth Exploration-Satellite (Earth-to-space) 882C 873A 873B 873C 882 882A 882B 883	29.9–30.0 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) Earth Exploration-Satellite (Earth-to-space) 882C 873A 873B 873C 882 882A 882B 883	29.9–30.0 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) Earth Exploration-Satellite (Earth-to-space) 882C 873A 873B 873C 882 882A 882B 883	29.9–30.0 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) 873A 873B 873C 882	
30.0–31.0	FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) Standard Frequency and Time Signal-Satellite (space-to-Earth) 883	30.0–31.0 FIXED-SATELLITE (Earth- to-space) MOBILE-SATELLITE (Earth-to-space) Standard Frequency and Time Signal-Satellite (space-to-Earth) G117	30.0–31.0 Standard Frequency and Time Signal-Satellite (space-to-Earth)	

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
31.0–31.3	31.0–31.3 FIXED MOBILE Standard Frequency and Time Signal-Satellite (Space-to-Earth) Space Research 884 885 886		31.0–31.3 Standard Frequency and Time Signal-Satellite (space-to-Earth) 886 US211	31.0–31.3 FIXED MOBILE Standard Frequency and Time Signal-Satellite (space-to-Earth) 884 886 US211	FIXED MICROWAVE (101)	
31.3–31.5	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 887		31.3–31.8 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246	31.3–31.8 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246		
31.5–31.8 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) Fixed Mobile except aeronautical mobile 888 889	31.5–31.8 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) Fixed Mobile except aeronautical mobile 888	31.5–31.8 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) Fixed Mobile except aeronautical mobile 888				
31.8–32.0	RADIONAVIGATION Space Research 890 891 892		31.8–32.0 RADIONAVIGATION US69 US211 US262	31.8–32.0 RADIONAVIGATION US69 US211 US262		
32.0–32.3	INTER-SATELLITE RADIONAVIGATION Space Research 890 891 892 893		32.0–33.0 INTER-SATELLITE RADIONAVIGATION	32.0–33.0 INTER-SATELLITE RADIONAVIGATION		

32.3–33.0	INTER-SATELLITE RADIONAVIGATION 892 893						
33.0–33.4	RADIONAVIGATION 892		33.0–33.4 RADIONAVIGATION US69				
33.4–34.2	RADIOLOCATION 892 894		33.4–36.0 RADIOLOCATION		Private Land Mobile (90)		
34.2–35.2	RADIOLOCATION Space Research 895 896 894						
35.2–36.0	METEOROLOGICAL AIDS RADIOLOCATION 894 897						
36.0–37.0	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) 898		36.0–37.0 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) 898 US263	897 US110 US252 G34	897 US110 US252		
37.0–37.5	FIXED MOBILE 899		37.0–38.6 FIXED MOBILE		DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94)		
37.5–39.5	FIXED FIXED-SATELLITE (Space-to-Earth) MOBILE			38.6–39.5	38.6–39.5		

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
				FIXED MOBILE FIXED-SATELLITE (space-to-Earth)	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (90) Auxiliary Broadcasting (74)	
39.5–40.5	899 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE MOBILE-SATELLITE (space-to-Earth)		US291 39.5–40.0 FIXED-SATELLITE (space-to-Earth) MOBILE-SATELLITE (space-to-Earth)	US291 39.5–40.0 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE MOBILE-SATELLITE (space-to-Earth)	DOMESTIC PUBLIC FIXED (21) PRIVATE OPER- ATIONAL-FIXED MICROWAVE (94) Auxiliary Broadcasting (74)	
40.5–42.5	BROADCASTING-SAT- ELLITE /BROADCASTING/ Fixed Mobile		40.5–42.5 US211	40.5–42.5 BROADCASTING-SAT- ELLITE /BROADCASTING/ Fixed Mobile US211		
42.5–43.5	FIXED FIXED-SATELLITE (Earth- to-space) 901 MOBILE except aeronauti- cal mobile RADIO ASTRONOMY		42.5–43.5 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE except aeronauti- cal mobile RADIO ASTRONOMY	42.5–43.5 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE except aeronauti- cal mobile RADIO ASTRONOMY		

	900		900	900		900	
43.5-45.5 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE 903	43.5-45.5 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE 903	43.5-45.5 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE 903	43.5-45.5 FIXED-SATELLITE MOBILE-SATELLITE (Earth-to-space) G117	43.5-45.5 MOBILE-SATELLITE (Earth-to-space)			
45.5-47.0 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE 903	45.5-47.0 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE 903	45.5-47.0 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE 903	45.5-47.0 MOBILE MOBILE-SATELLITE (Earth-to-space) RADIONAVIGATION-SAT- ELLITE 903	45.5-47.0 MOBILE MOBILE-SATELLITE (Earth-to-space) RADIONAVIGATION-SAT- ELLITE 903	RADIO FREQUENCY DE- VICES (15)		
47.0-47.2	AMATEUR AMATEUR-SATELLITE		47.0-47.2	AMATEUR AMATEUR-SATELLITE	AMATEUR (97)		
47.2-50.2	FIXED FIXED-SATELLITE (Earth- to-space) 901 MOBILE 905 904		47.2-50.2 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 904 US264 US297	47.2-50.2 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 904 US264 US297			
50.2-50.4	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive)		50.2-50.4 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) US263	50.2-50.4 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) US263			
50.4-51.4	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE Mobile-Satellite (Earth-to- space)		50.4-51.4 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE MOBILE-SATELLITE (Earth-to-space) G117	50.4-51.4 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE MOBILE-SATELLITE (Earth-to-space)			

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
51.4–54.25	EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 906 907		51.4–54.25 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	51.4–54.25 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246		
54.25–58.2	EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 908		54.25–58.2 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) US263	54.25–58.2 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) US263		
58.2–59.0	EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 906 907		58.2–59.0 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	58.2–59.0 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246		
59–64 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION 910	59–64 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION	59–64 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION	59–64 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION	59–64 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION	Radio frequency devices (15)	61.25 GHz±250 MHz: In- dustrial, scientific and medi- cal fre- quency
911	911	911	911	911		

64–65	EARTH EXPLORATION-SATELLITE (passive) SPACE RESEARCH (passive) 906 907		64–65 EARTH EXPLORATION-SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (passive) US246	64–65 EARTH EXPLORATION-SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (passive) US246	
65–66	EARTH EXPLORATION-SATELLITE SPACE RESEARCH Fixed Mobile		65–66 EARTH EXPLORATION-SATELLITE SPACE RESEARCH Fixed Mobile	65–66 EARTH EXPLORATION-SATELLITE SPACE RESEARCH Fixed Mobile	
66–71	MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SATELLITE 903		66–71 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SATELLITE 903	66–71 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SATELLITE 903	
71–74	FIXED FIXED-SATELLITE (Earth-to-space) MOBILE MOBILE-SATELLITE (Earth-to-space) 906	FIXED FIXED-SATELLITE (Earth-to-space) MOBILE MOBILE-SATELLITE (Earth-to-space)	71–74 FIXED FIXED-SATELLITE (Earth-to-space) MOBILE MOBILE-SATELLITE (Earth-to-space) US270	71–74	
74.0–75.5	FIXED FIXED-SATELLITE (Earth-to-space) MOBILE		74.0–75.5 FIXED FIXED-SATELLITE (Earth-to-space) MOBILE US297	74.0–75.5 FIXED FIXED-SATELLITE (Earth-to-space) MOBILE US297	
75.5–76.0	AMATEUR AMATEUR-SATELLITE		75.5–76.0	75.5–76.0 AMATEUR AMATEUR-SATELLITE	AMATEUR (97)

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
76–77 RADIOLOCATION Amateur Amateur-Satellite Space Research (space- to-Earth)	76–77 RADIOLOCATION Amateur Amateur-Satellite Space Research (space- to-Earth)	76–77 RADIOLOCATION Amateur Amateur-Satellite Space Research (space- to-Earth)	76–77 RADIOLOCATION Amateur	76–77 RADIOLOCATION Amateur	RADIO FREQUENCY DE- VICES (15)	
77–81 RADIOLOCATION Amateur Amateur-Satellite Space Research (space- to-Earth)	77–81 RADIOLOCATION Amateur Amateur-Satellite Space Research (space- to-Earth)	77–81 RADIOLOCATION Amateur Amateur-Satellite Space Research (space- to-Earth)	77–81 RADIOLOCATION Amateur	77–81 RADIOLOCATION Amateur-Satellite	Amateur (97)	
81–84 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE MOBILE-SATELLITE (space-to-Earth)	FIXED FIXED-SATELLITE (space-to-Earth) MOBILE MOBILE-SATELLITE (space-to-Earth)		81–84 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE MOBILE-SATELLITE (space-to-Earth)	81–84 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE MOBILE-SATELLITE (space-to-Earth)		
84–86 FIXED MOBILE BROADCASTING BROADCASTING-SAT- ELLITE 913	FIXED MOBILE BROADCASTING BROADCASTING-SAT- ELLITE 913		84–86 FIXED MOBILE 913 US211	84–86 FIXED MOBILE BROADCASTING BROADCASTING-SAT- ELLITE 913 US211		
86–92 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 907	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 907		86–92 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246	86–92 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US74 US246		

92-95	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE RADIOLOCATION 914		92-95 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE RADIOLOCATION 914	92-95 FIXED-SATELLITE (Earth- to-space) MOBILE RADIOLOCATION 914	
95-100	MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SAT- ELLITE Radiolocation 903 904		95-100 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SAT- ELLITE Radiolocation 903 904	95-100 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SAT- ELLITE Radiolocation 903 904	
100-102	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) 722		100-102 EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 722 US246	100-102 EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 722 US246	
102-105	FIXED FIXED-SATELLITE (space-to-Earth) 722		102-105 FIXED FIXED-SATELLITE (space-to-Earth) 722 US211	102-105 FIXED FIXED-SATELLITE (space-to-Earth) 722	
105-116	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 907		105-116 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 US74 US246	105-116 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 US74 US246	
116-126	EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 722 915 916	722 915 916 US211	116-126 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 722 915 916 US211	116-126 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 722 915 916 US211	122.5±5 GHz: In- dustrial scientific and medi- cal fre- quency

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government	Non-Government	Rule part(s) (6)	Special-use frequencies (7)
			Allocation GHz (4)	Allocation GHz (5)		
			US263	US263		
126–134	FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION 910		126–134 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION 910	126–134 FIXED INTER-SATELLITE MOBILE 909 RADIOLOCATION 910		
134–142	MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE Radiolocation 903 917 918		134–142 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE Radiolocation 903 917 918	134–142 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION-SAT- ELLITE Radiolocation 903 917 918		
142–144	AMATEUR AMATEUR-SATELLITE		142–144	142–144 AMATEUR AMATEUR-SATELLITE	AMATEUR (97)	
144–149	RADIOLOCATION Amateur Amateur-Satellite 918		144–149 RADIOLOCATION 918	144–149 RADIOLOCATION Amateur Amateur-Satellite 918	Amateur (97)	
149–150	FIXED FIXED-SATELLITE (space-to-Earth) MOBILE		149–150 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE	149–150 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE		
150–151	EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) MOBILE SPACE RESEARCH (pas- sive)		150–151 EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) MOBILE SPACE RESEARCH (pas- sive)	150–151 EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) MOBILE SPACE RESEARCH (pas- sive)		

151–164	919	919 US263	919 US263	919 US263	
	FIXED FIXED-SATELLITE (space-to-Earth)	151–164 FIXED-SATELLITE 211	151–164 FIXED-SATELLITE 211	151–164 FIXED-SATELLITE 211	
164–168	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive)	164–168 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	164–168 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	164–168 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	
168–170	FIXED MOBILE	168–170 FIXED MOBILE	168–170 FIXED MOBILE	168–170 FIXED MOBILE	
170.0–174.5	FIXED INTER-SATELLITE MOBILE 909 919	170.0–174.5 FIXED INTER-SATELLITE MOBILE 909 919	170.0–174.5 FIXED INTER-SATELLITE MOBILE 909 919	170.0–174.5 FIXED INTER-SATELLITE MOBILE 909 919	
174.5–176.5	EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 919	174.5–176.5 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 919 US263	174.5–176.5 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 919 US263	174.5–176.5 EARTH EXPLORATION- SATELLITE (passive) FIXED INTER-SATELLITE MOBILE 909 SPACE RESEARCH (pas- sive) 919 US263	
176.5–182.0	FIXED INTER-SATELLITE MOBILE 909 919	176.5–182.0 FIXED INTER-SATELLITE MOBILE 909 919 US211	176.5–182.0 FIXED INTER-SATELLITE MOBILE 909 919 US211	176.5–182.0 FIXED INTER-SATELLITE MOBILE 909 919 US211	
182–185	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 920 921	182–185 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	182–185 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	182–185 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) US246	

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
185–190	FIXED INTER-SATELLITE MOBILE 909 919		185–190 FIXED INTER-SATELLITE MOBILE 909 919 US211	185–190 FIXED INTER-SATELLITE MOBILE 909 919 US211		
190–200	MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION- SATELLITE 722 903		190–200 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION- SATELLITE 722 903	190–200 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION- SATELLITE 722 903		
200–202	EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) 722		200–202 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) 722 US263	200–202 EARTH EXPLORATION- SATELLITE (passive) FIXED MOBILE SPACE RESEARCH (pas- sive) 722 US263		
202–217	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 722		202–217 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 722	202–217 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE 722		
217–231	EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 907		217–231 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 US74 US246	217–231 EARTH EXPLORATION- SATELLITE (passive) RADIO ASTRONOMY SPACE RESEARCH (pas- sive) 722 US74 US246		

231–235	FIXED FIXED-SATELLITE (space-to-Earth) MOBILE Radiolocation		213–235 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE Radiolocation US211	231–235 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE Radiolocation US211		
235–238	EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) MOBILE SPACE RESEARCH (pas- sive)		235–238 EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) MOBILE SPACE RESEARCH (pas- sive) US263	235–238 EARTH EXPLORATION- SATELLITE (passive) FIXED FIXED-SATELLITE (space-to-Earth) MOBILE SPACE RESEARCH (pas- sive) US263		
238–241	FIXED FIXED-SATELLITE (space-to-Earth) MOBILE Radiolocation		238–241 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE Radiolocation	238–241 FIXED FIXED-SATELLITE (space-to-Earth) MOBILE Radiolocation		
241–248	RADIOLOCATION Amateur Amateur-Satellite		241–248 RADIOLOCATION	241–248 RADIOLOCATION Amateur Amateur-Satellite	Amateur (97)	245±1 GHz: Industrial scientific and medi- cal fre- quency
248–250	AMATEUR AMATEUR-SATELLITE		248–250	248–250 AMATEUR AMATEUR-SATELLITE	AMATEUR (97)	
250–252	EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 923		250–252 EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 923	250–252 EARTH EXPLORATION- SATELLITE (passive) SPACE RESEARCH (pas- sive) 923		

International table			United States table		FCC use designators	
Region 1—allocation GHz (1)	Region 2—allocation GHz (2)	Region 3—allocation GHz (3)	Government Allocation GHz (4)	Non-Government Allocation GHz (5)	Rule part(s) (6)	Special-use frequencies (7)
252–265	MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SAT- ELLITE 903 923 924 925		252–265 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SAT- ELLITE 903 923 924 US211	252–265 MOBILE 902 MOBILE-SATELLITE RADIONAVIGATION RADIONAVIGATION-SAT- ELLITE 903 923 924 US211		
265–275	FIXED FIXED-SATELLITE (Earth- to-space) MOBILE RADIO ASTRONOMY 926		265–275 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE RADIO ASTRONOMY 926	265–275 FIXED FIXED-SATELLITE (Earth- to-space) MOBILE RADIO ASTRONOMY 926		
275–400	(Not allocated) 927		275–300 FIXED MOBILE 927 Above 300 (Not allocated) 927	275–300 FIXED MOBILE 927 Above 300 (Not allocated) 927		Amateur (97)

Federal Communications Commission

§2.106

INTERNATIONAL FOOTNOTES

NOTE: The International Telecommunication Union is transitioning to new Simplified Radio Regulations. As part of the Simplified Radio Regulations, the “S” numbering scheme is used for international footnotes. Until such time as the Commission revises the entire list of international footnotes to comport with the new “S” numbering scheme, the international footnotes that are adopted in individual proceeding shall be listed in I. prior to the listing of international footnotes employing the old numbering scheme. Footnotes employing the old numbering scheme will appear in II. and shall not be deleted until all frequency bands listed within a footnote have been updated to the new “S” numbering scheme.

I. New “S” Numbering Scheme

S5.92 Some countries of Region 1 use radiodetermination systems in the bands 1606.5–1625 kHz, 1635–1800 kHz, 1850–2160 kHz, 2194–2300 kHz, 2502–2850 kHz and 3500–3800 kHz, subject to agreement obtained under Article 14/No. S9.21. The radiated mean power of these stations shall not exceed 50W.

S5.93 *Additional allocation:* in Angola, Armenia, Azerbaijan, Belarus, Bulgaria, Georgia, Hungary, Kazakhstan, Latvia, Lithuania, Moldova, Mongolia, Nigeria, Uzbekistan, Poland, Kyrgyzstan, Slovakia, the Czech Republic, Russia, Tajikistan, Chad, Turkmenistan and Ukraine, the bands 1625–1635 kHz, 1800–1810 kHz and 2160–2170 kHz are also allocated to the fixed and land mobile services on a primary basis, subject to agreement obtained under Article 14/No. S9.21.

S5.103 In Region 1, in making assignments to stations in the fixed and mobile services in the bands 1850–2045 kHz, 2194–2498 kHz, 2502–2625 kHz and 2650–2850 kHz, administrations should bear in mind the special requirements of the maritime mobile service.

S5.104 In Region 1, the use of the band 2025–2045 kHz by the meteorological aids service is limited to oceanographic buoy stations.

S5.105 In Region 2, except in Greenland, coast stations and ship stations using radiotelephony in the band 2065–2107 kHz shall be limited to class J3E emissions and to a peak envelope power not exceeding 1kW. Preferably, the following carrier frequencies should be used: 2065.0 kHz, 2079.0 kHz, 2082.5 kHz, 2086.0 kHz, 2093.0 kHz, 2096.5 kHz, 2100.0 kHz and 2103.5 kHz. In Argentina and Uruguay, the carrier frequencies 2068.5 kHz and 2075.5 kHz are also used for this purpose, while the frequencies within the band 2072–2075.5 kHz are used as provided in No. 4323BD/S52.165.

S5.106 In Regions 2 and 3, provided no harmful interference is caused to the maritime mobile service, the frequencies between

2065 kHz and 2107 kHz may be used by stations of the fixed service communicating only within national borders and whose mean power does not exceed 50 W. In notifying the frequencies, the attention of the Bureau should be drawn to these provisions.

S5.107 *Additional allocation:* in Saudi Arabia, Botswana, Eritrea, Ethiopia, Iraq, Lesotho, Libya, Malawi, Somalia, Swaziland and Zambia, the band 2160–2170 kHz is also allocated to the fixed and mobile, except aeronautical mobile (R), services on a primary basis. The mean power of stations in these services shall not exceed 50 W.

S5.108 The carrier frequency 2182 kHz is an international distress and calling frequency for radiotelephony. The conditions for the use of the band 2173.5–2190.5 kHz are prescribed in Articles N38/S31 and 60/S52 and in Articles 37 and 38/Appendix S13.

S5.109 The frequencies 2187.5 kHz, 4207.5 kHz, 6312 kHz, 8414.5 kHz, 12577 kHz and 16804.5 kHz are international distress frequencies for digital selective calling. The conditions for the use of these frequencies are prescribed in Article N38/S31.

S5.110 The frequencies 2174.5 kHz, 4177.5 kHz, 6268 kHz, 8376.5 kHz, 12520 kHz and 16695 kHz are international distress frequencies for narrow-band direct-printing telegraphy. The conditions for the use of these frequencies are prescribed in Article N38/S31.

S5.111 The carrier frequencies 2182 kHz, 3023 kHz, 5680 kHz, 8364 kHz and the frequencies 121.5 MHz, 156.8 MHz and 243 MHz may also be used, in accordance with the procedures in force for terrestrial radiocommunication services, for search and rescue operations concerning manned space vehicles. The conditions for the use of the frequencies are prescribed in Article N38/S31 and in Article 38/Appendix S13.

The same applies to the frequencies 10003 kHz, 14993 kHz and 19993 kHz, but in each of these cases emissions must be confined in a band of ± 3 kHz about the frequency.

S5.112 *Alternative allocation:* in Belgium, Bosnia and Herzegovina, Cyprus, Denmark, Spain, France, Greece, Iceland, Italy, Malta, Norway, the United Kingdom, Singapore, Sri Lanka, Turkey and Yugoslavia, the band 2194–2300 kHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

S5.113 For the conditions for the use of the bands 2300–2495 kHz (2498 kHz in Region 1), 3200–3400 kHz, 4750–4995 kHz and 5005–5060 kHz by the broadcasting service, see Nos. S5.16 to S5.20, S5.21 and 2666/S23.3 to 2673/S23.10.

S5.114 *Alternative allocation:* in Belgium, Bosnia and Herzegovina, Cyprus, Denmark, Spain, France, Greece, Iraq, Italy, Malta, Norway, the United Kingdom, Turkey and Yugoslavia, the band 2502–2625 kHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

S5.115 The carrier (reference) frequencies 3023 kHz and 5680 kHz may also be used, in accordance with Article N38/S31 and Article 38/Appendix S13 by stations of the maritime mobile service engaged in coordinated search and rescue operations.

S5.116 Administrations are urged to authorize the use of the band 3155–3195 kHz to provide a common worldwide channel for low power wireless hearing aids. Additional channels for these devices may be assigned by administrations in the bands between 3155 kHz and 3400 kHz to suit local needs.

It should be noted that frequencies in the range 3000 kHz to 4000 kHz are suitable for hearing aid devices which are designed to operate over short distances within the induction field.

S5.117 *Alternative allocation:*in Belgium, Bosnia and Herzegovina, Cameroon, Cyprus, Côte d'Ivoire, Denmark, Egypt, Spain, France, Greece, Iceland, Italy, Liberia, Malta, Norway, the United Kingdom, Singapore, Sri Lanka, Togo, Turkey and Yugoslavia, the band 3155–3200 kHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

S5.118 *Additional allocation:*in the United States, Japan, Mexico, Peru and Uruguay, the band 3230–3400 kHz is also allocated to the radiolocation service on a secondary basis.

S5.119 *Additional allocation:*in Honduras, Mexico, Peru and Venezuela, the band 3500–3750 kHz is also allocated to the fixed and mobile services on a primary basis.

S5.120 For the use of the bands allocated to the amateur service at 3.5 MHz, 7.0 MHz, 10.1 MHz, 14.0 MHz, 18.068 MHz, 21.0 MHz, 24.89 MHz and 144 MHz in the event of natural disasters, see Resolution 640.

S5.122 *Alternative allocation:*in Argentina, Bolivia, Chile, Ecuador, Paraguay, Peru and Uruguay, the band 3750–4000 kHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

S5.123 *Additional allocation:*in Botswana, Lesotho, Malawi, Mozambique, Namibia, South Africa, Swaziland, Zambia and Zimbabwe, the band 3900–3950 kHz is also allocated to the broadcasting service on a primary basis, subject to agreement obtained under Article 14/No. S9.21.

S5.124 *Additional allocation:*in Canada, the band 3950–4000 kHz is also allocated to the broadcasting service on a primary basis. The power of broadcasting stations operating in this band shall not exceed that necessary for a national service within the frontier of this country and shall not cause harmful interference to other services operating in accordance with the Table.

S5.125 *Additional allocation:*in Greenland, the band 3950–4000 kHz is also allocated to the broadcasting service on a primary basis. The power of the broadcasting stations operating in this band shall not exceed that nec-

essary for a national service and shall in no case exceed 5 kW.

S5.126 In Region 3, the stations of those services to which the band 3995–4005 kHz is allocated may transmit standard frequency and time signals.

S5.127 The use of the band 4000–4063 kHz by the maritime mobile service is limited to ship stations using radiotelephony (see No. 4374/S52.220 and Appendix 16/S17).

S5.128 In Afghanistan, Argentina, Armenia, Australia, Azerbaijan, Belarus, Botswana, Burkina Faso, Central African Republic, China, Georgia, India, Kazakhstan, Mali, Moldova, Niger, Kyrgyzstan, Russia, Tajikistan, Chad, Turkmenistan and Ukraine, in the bands 4063–4123 kHz, 4130–4133 kHz and 4408–4438 kHz, stations of limited power in the fixed service which are situated at least 600 km from the coast may operate on condition that harmful interference is not caused to the maritime mobile service.

S5.129 On condition that harmful interference is not caused to the maritime mobile service, the frequencies in the bands 4063–4123 kHz and 4130–4438 kHz may be used exceptionally by stations in the fixed service communicating only within the boundary of the country in which they are located with a mean power not exceeding 50 W.

S5.130 The conditions for the use of the carrier frequencies 4125 kHz and 6215 kHz are prescribed in Articles N38/S31 and 60/S52 and in Articles 37 and 38/Appendix S13.

S5.131 The frequency 4209.5 kHz is used exclusively for the transmission by coast stations of meteorological and navigational warnings and urgent information to ships by means of narrow-band direct-printing techniques (see Resolution 339 WRC-95).

S5.132 The frequencies 4210 kHz, 6314 kHz, 8416.5 kHz, 12579 kHz, 16806.5 kHz, 19680.5 kHz, 22376 kHz and 26100.5 kHz are the international frequencies for the transmission of Maritime Safety Information (MSI) (see Resolution 333 (Mob-87) and Appendix 31/S17).

S5.133 *Different category of service:*in Armenia, Azerbaijan, Belarus, Georgia, Kazakhstan, Latvia, Lithuania, Moldova, Uzbekistan, Kyrgyzstan, Russia, Tajikistan, Turkmenistan and Ukraine, the allocation of the band 5130–5250 kHz to the mobile, except aeronautical mobile, service is on a primary basis (see No. S5.33).

S5.134 The use of the bands 5900–5950 kHz, 7300–7350 kHz, 9400–9500 kHz, 11600–11650 kHz, 12050–12100 kHz, 13570–13600 kHz, 13800–13870 kHz, 15600–15800 kHz, 17480–17550 kHz and 18900–19020 kHz by the broadcasting service is limited to single-sideband emissions with the characteristics specified in Appendix 45/S11 to the Radio Regulations.

S5.135 The use of the bands 5900–5950 kHz, 7300–7350 kHz, 9400–9500 kHz, 11600–11650 kHz, 12050–12100 kHz, 13570–13600 kHz, 13800–13870 kHz, 15600–15800 kHz, 17480–17550 kHz and 18900–19020 kHz by the broadcasting service

Federal Communications Commission

§2.106

shall be subject to the planning procedures to be drawn up by a competent world administrative radio conference.

S5.136 The band 5900–5950 kHz is allocated, until 1 April 2007, to the fixed service on a primary basis, as well as to the following services: in Region 1 to the land mobile service on a primary basis, in Region 2 to the mobile except aeronautical mobile (R) service on a primary basis, and in Region 3 to the mobile except aeronautical mobile (R) service on a secondary basis, subject to application of the procedure referred to in Resolution 21 (Rev.WRC-95). After 1 April 2007, frequencies in this band may be used by stations in the above-mentioned services, communicating only within the boundary of the country in which they are located, on the condition that harmful interference is not caused to the broadcasting service. When using frequencies for these services, administrations are urged to use the minimum power required and to take account of the seasonal use of frequencies by the broadcasting service published in accordance with the Radio Regulations.

S5.137 On condition that harmful interference is not caused to the maritime mobile service, the bands 6200–6213.5 kHz and 6220.5–6525 kHz may be used exceptionally by stations in the fixed service, communicating only within the boundary of the country in which they are located, with a mean power not exceeding 50 W. At the time of notification of these frequencies, the attention of the Bureau will be drawn to the above conditions.

S5.138 The following bands:
6765–6795 kHz (centre frequency 6780 kHz),
433.05–434.79 MHz (centre frequency 433.92 MHz) in Region 1 except in the countries mentioned in No. S5.280,
61–61.5 GHz (centre frequency 61.25 GHz),
122–123 GHz (centre frequency 122.5 GHz),
and
244–246 GHz (centre frequency 245 GHz)
are designated for industrial, scientific and medical (ISM) applications. The use of these frequency bands for ISM applications shall be subject to special authorization by the administration concerned, in agreement with other administrations whose radiocommunication services might be affected. In applying this provision, administrations shall have due regard to the latest relevant ITU-R Recommendations.

S5.139 *Different category of service:* in Armenia, Azerbaijan, Belarus, Georgia, Kazakhstan, Latvia, Lithuania, Moldova, Mongolia, Uzbekistan, Kyrgyzstan, Russia, Tajikistan, Turkmenistan and Ukraine, the allocation of the band 6765–7000 kHz to the land mobile service is on a primary basis (see No. S5.33).

S5.140 *Additional allocation:* in Angola, Iraq, Rwanda, Somalia and Togo, the band

7000–7050 kHz is also allocated to the fixed service on a primary basis.

S5.141 *Alternative allocation:* in Egypt, Eritrea, Ethiopia, Guinea, Libya, Madagascar and Malawi, the band 7000–7050 kHz is allocated to the fixed service on a primary basis.

S5.142 The use of the band 7100–7300 kHz in Region 2 by the amateur service shall not impose constraints on the broadcasting service intended for use within Region 1 and Region 3.

S5.143 The band 7300–7350 kHz is allocated, until 1 April 2007, to the fixed service on a primary basis and to the land mobile service on a secondary basis, subject to application of the procedure referred to in Resolution 21 (Rev. WRC-95). After 1 April 2007, frequencies in this band may be used by stations in the above-mentioned services, communicating only within the boundary of the country in which they are located, on condition that harmful interference is not caused to the broadcasting service. When using frequencies for these services, administrations are urged to use the minimum power required and to take account of the seasonal use of frequencies by the broadcasting service published in accordance with the Radio Regulations.

S5.144 In Region 3, the stations of those services to which the band 7995–8005 kHz is allocated may transmit standard frequency and time signals.

S5.145 The conditions for the use of the carrier frequencies 8291 kHz, 12290 kHz and 16420 kHz are prescribed in Articles N38/S31 and 60/S52 and in Article 38/Appendix S13.

S5.146 The bands 9400–9500 kHz, 11600–11650 kHz, 12050–12100 kHz, 15600–15800 kHz, 17480–17550 kHz and 18900–19020 kHz are allocated to the fixed service on a primary basis until 1 April 2007, subject to application of the procedure referred to in Resolution 21 (Rev. WRC-95). After 1 April 2007, frequencies in these bands may be used by stations in the fixed service, communicating only within the boundary of the country in which they are located, on condition that harmful interference is not caused to the broadcasting service. When using frequencies in the fixed service, administrations are urged to use the minimum power required and to take account of the seasonal use of frequencies by the broadcasting service published in accordance with the Radio Regulations.

S5.147 On condition that harmful interference is not caused to the broadcasting service, frequencies in the bands 9775–9900 kHz, 11650–11700 kHz and 11975–12050 kHz may be used by stations in the fixed service communicating only within the boundary of the country in which they are located, each station using a total radiated power not exceeding 24 dBW.

S5.148 The bands 9775–9900 kHz, 11650–11700 kHz, 11975–12050 kHz, 13600–13800 kHz, 15450–15600 kHz, 17550–17700 kHz and 21750–21850 kHz

§2.106

are allocated to the fixed service on a primary basis subject to the procedure described in Resolution 8. The use of these bands by the broadcasting service shall be subject to provisions established by the World Administrative Radio Conference for the Planning of the HF Bands Allocated to the Broadcasting Service (see Resolution 508). The provisions of Resolution 512 (HFBC-87) also apply. Within these bands, the date of commencement of operations in the broadcasting service on a planned channel shall not be earlier than the date of completion of satisfactory transfer, according to the procedures described in Resolution 8, of all assignments to stations in the fixed service operating in accordance with the Table and other provisions of the Radio Regulations, which are recorded in the Master Register and which may be affected by broadcasting operations on that channel.

S5.149 In making assignments to stations of other services to which the bands:

13360–13410 kHz,
25550–25670 kHz,
37.5–38.25 MHz,
73–74.6 MHz in

Regions 1 and 3,

79.75–80.25 MHz in

Region 3,

150.05–153 MHz in

Region 1,

322–328.6 MHz*,
406.1–410 MHz,
608–614 MHz in
3345.8–3352.5 MHz*,
4825–4835 MHz*,
4950–4990 MHz,
4990–5000 MHz,
6650–6675.2 MHz*,
10.6–10.68 GHz,
14.47–14.5 GHz*,
22.01–22.21 GHz*,
22.21–22.5 GHz,
22.81–22.86 GHz*,
23.07–23.12 GHz*,
31.2–31.3 GHz,
72.77–72.91 GHz*,
93.07–93.27 GHz*,
97.88–98.08 GHz*,
140.69–140.98 GHz*,
144.68–144.98 GHz*,
145.45–145.75 GHz*,
146.82–147.12 GHz*,
150–151 GHz*,
174.42–175.02 GHz*,
177–177.4 GHz*,
178.2–178.6 GHz*,
181–181.46 GHz*,

Regions 1 and 3,

1330–1400 MHz*,
1610.6–1613.8 MHz*,

47 CFR Ch. I (10–1–97 Edition)

1660–1670 MHz,
1718.8–1722.2 MHz*,
2655–2690 MHz,
3260–3267 MHz*,
3332–3339 MHz*,
31.5–31.8 GHz in

Regions 1 and 3,

36.43–36.5 GHz*,
42.5–43.5 GHz,
42.77–42.87 GHz*,
43.07–43.17 GHz*,
43.37–43.47 GHz*,
48.94–49.04 GHz*,
186.2–186.6 GHz*,
250–251 GHz*,
257.5–258 GHz*,
261–265 GHz,
262.24–262.76 GHz*,
265–275 GHz,
265.64–266.16 GHz*,
267.34–267.86 GHz*,
271.74–272.26 GHz*

are allocated (* indicates radio astronomy use for spectral line observations), administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from spaceborne or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343/S4.5 and 344/S4.6 and Article 36/S29).

S5.150 The following bands:

13533–13567 kHz (centre frequency 13560 kHz),
26957–27283 kHz (centre frequency 27120 kHz),
40.66–40.70 MHz (centre frequency 40.68 MHz),
902–928 MHz in Region 2 (centre frequency 915 MHz),
2400–2500 MHz (centre frequency 2450 MHz),
5725–5875 MHz (centre frequency 5800 MHz),
and
24–24.25 GHz (centre frequency 24.125 GHz)

are also designated for industrial, scientific and medical (ISM) applications. Radiocommunication services operating within these bands must accept harmful interference which may be caused by these applications. ISM equipment operating in these bands is subject to the provisions of No. 1815/S15.13.

S5.151 The bands 13570–13600 kHz and 13800–13870 kHz are allocated, until 1 April 2007, to the fixed service on a primary basis and to the mobile except aeronautical mobile (R) service on a secondary basis, subject to application of the procedure referred to in Resolution 21 (Rev.WRC-95). After 1 April 2007, frequencies in these bands may be used by stations in the above-mentioned services, communicating only within the boundary of the country in which they are located, on the condition that harmful interference is not caused to the broadcasting service. When using frequencies in these services, administrations are urged to use the minimum power required and to take account of the

Federal Communications Commission

§2.106

seasonal use of frequencies by the broadcasting service published in accordance with the Radio Regulations.

S5.152 *Additional allocation:*in Armenia, Azerbaijan, Belarus, China, Côte d'Ivoire, Georgia, the Islamic Republic of Iran, Kazakhstan, Moldova, Uzbekistan, Kyrgyzstan, Russia, Tajikistan, Turkmenistan and Ukraine, the band 14250–14350 kHz is also allocated to the fixed service on a primary basis. Stations of the fixed service shall not use a radiated power exceeding 24 dBW.

S5.153 In Region 3, the stations of those services to which the band 15995–16005 kHz is allocated may transmit standard frequency and time signals.

S5.154 *Additional allocation:*in Armenia, Azerbaijan, Belarus, Georgia, Kazakhstan, Moldova, Uzbekistan, Kyrgyzstan, Russia, Tajikistan, Turkmenistan and Ukraine, the band 18068–18168 kHz is also allocated to the fixed service on a primary basis for use within their boundaries, with a peak envelope power not exceeding 1 kW.

S5.155 *Additional allocation:*in Armenia, Azerbaijan, Belarus, Bulgaria, Georgia, Hungary, Kazakhstan, Moldova, Mongolia, Uzbekistan, Kyrgyzstan, Slovakia, the Czech Republic, Russia, Tajikistan, Turkmenistan and Ukraine, the band 21850–21870 kHz is also allocated to the aeronautical mobile (R) services on a primary basis.

S5.155A In Armenia, Azerbaijan, Belarus, Bulgaria, Georgia, Hungary, Kazakhstan, Moldova, Mongolia, Uzbekistan, Kyrgyzstan, Slovakia, the Czech Republic, Russia, Tajikistan, Turkmenistan and Ukraine, the use of the band 21850–21870 kHz by the fixed service is limited to provision of services related to aircraft flight safety.

S5.155B The band 21870–21924 kHz is used by the fixed service for provision of services related to aircraft flight safety.

S5.156 *Additional allocation:*in Nigeria, the band 22720–23200 kHz is also allocated to the meteorological aids service (radiosondes) on a primary basis.

S5.156A The use of the band 23200–23350 kHz by the fixed service is limited to provision of services related to aircraft flight safety.

S5.157 The use of the band 23350–24000 kHz by the maritime mobile service is limited to inter-ship radiotelegraphy.

S5.226 The frequency 156.8 MHz is the international distress, safety and calling frequency for the maritime mobile VHF radiotelephone service. The conditions for the use of this frequency are contained in Article N38/S31 and Article 38/Appendix S13.

In the bands 156–156.7625 MHz, 156.8375–157.45 MHz, 160.6–160.975 MHz and 161.475–162.05 MHz, each administration shall give priority to the maritime mobile service on only such frequencies as are assigned to stations of the maritime mobile service by the

administration (see Articles N38/S31 and 60/S52 and Article 38/Appendix S13).

Any use of frequencies in these bands by stations of other services to which they are allocated should be avoided in areas where such use might cause harmful interference to the maritime mobile VHF radiocommunication service.

However, the frequency 156.8 MHz and the frequency bands in which priority is given to the maritime mobile service may be used for radiocommunications on inland waterways subject to agreement between interested and affected administrations and taking into account current frequency usage and existing agreements.

S5.229 *Alternative allocation:*in Morocco, the band 162–174 MHz is allocated to the broadcasting service on a primary basis. The use of this band shall be subject to agreement with administrations having services, operating or planned, in accordance with the Table which are likely to be affected. Stations in existence on 1 January 1981, with their technical characteristics as of that date, are not affected by such agreement.

S5.282 In the bands 435–438 MHz, 1260–1270 MHz, 2400–2450 MHz, 3400–3410 MHz (in Regions 2 and 3 only) and 5650–5670 MHz, the amateur-satellite service may operate subject to not causing harmful interference to other services operating in accordance with the Table (see No. S5.43). Administrations authorizing such use shall ensure that any harmful interference caused by emissions from a station in the amateur-satellite service is immediately eliminated in accordance with the provisions of No. 2741/S25.11. The use of the bands 1260–1270 MHz and 5650–5670 MHz by the amateur-satellite service is limited to the Earth-to-space direction.

S5.333 In the bands 1215–1300 MHz, 3100–3300 MHz, 5250–5350 MHz, 8550–8650 MHz, 9500–9800 MHz and 13.4–14.0 GHz, radiolocation stations installed on spacecraft may also be employed for the earth exploration-satellite and space research services on a secondary basis.

S5.388 The bands 1885–2025 MHz and 2110–2200 MHz are intended for use, on a world-wide basis, by administrations wishing to implement the future public land mobile telecommunication systems (FPLMTS). Such use does not preclude the use of these bands by other services to which these bands are allocated. The bands should be made available for FPLMTS in accordance with Resolution 212 (Rev.WRC-95).

S5.389A The use of the bands 1980–2010 MHz and 2170–2200 MHz by the mobile-satellite service is subject to coordination under Resolution 46 (Rev.WRC-95)/No. S9.11A and to the provisions of Resolution 716 (WRC-95). The use of these bands shall not commence before 1 January 2000; however the use of the band 1980–1990 MHz in Region 2 shall not commence before 1 January 2005.

S5.389B The use of the band 1980–1990 MHz by the mobile-satellite service shall not cause harmful interference to or constrain the development of the fixed and mobile services in Argentina, Brazil, Canada, Chile, Ecuador, the United States, Honduras, Jamaica, Mexico, Peru, Suriname, Trinidad and Tobago, Uruguay and Venezuela.

S5.389C The use of the bands 2010–2025 MHz and 2160–2170 MHz in Region 2 by the mobile-satellite service shall not commence before 1 January 2005 and is subject to co-ordination under Resolution 46 (Rev.WRC-95)/No. S9.11A and to the provisions of Resolution 716 (WRC-95).

S5.389D In Canada and the United States the use of the bands 2010–2025 MHz and 2160–2170 MHz by the mobile-satellite service shall not commence before 1 January 2000.

S5.389E The use of the bands 2010–2025 MHz and 2160–2170 MHz by the mobile-satellite service in Region 2 shall not cause harmful interference to or constrain the development of the fixed and mobile services in Regions 1 and 3.

S5.389F In Algeria, Benin, Cape Verde, Egypt, Mali, Syria and Tunisia, the use of the bands 1980–2010 MHz and 2170–2200 MHz by the mobile-satellite service shall neither cause harmful interference to the fixed and mobile services, nor hamper the development of those services prior to 1 January 2005, nor shall the former service request protection from the latter services.

S5.391 In making assignments to the mobile service in the bands 2025–2110 MHz and 2200–2290 MHz, administrations shall take into account Resolution 211 (WARC-92).

S5.392 Administrations are urged to take all practicable measures to ensure that space-to-space transmissions between two or more non-geostationary satellites, in the space research, space operations and Earth exploration-satellite services in the bands 2025–2110 MHz and 2200–2290 MHz, shall not impose any constraints on Earth-to-space, space-to-Earth and other space-to-space transmissions of those services and in those bands between geostationary and non-geostationary satellites.

S5.392A *Additional allocation:* in Russia, the band 2160–2200 MHz is also allocated to the space research service (space-to-Earth) on a primary basis until 1 January 2005. Stations in the space research service shall not cause harmful interference to, or claim protection from, stations in the fixed and mobile services operating in this frequency band.

S5.393 *Additional allocation:* in the United States and India, the band 2310–2360 MHz is also allocated to the broadcasting-satellite service (sound) and complementary terrestrial sound broadcasting service on a primary basis. Such use is limited to digital audio broadcasting and is subject to the provisions of Resolution 528 (WARC-92).

S5.394 In the United States, the use of the band 2300–2390 MHz by the aeronautical mobile service for telemetry has priority over other uses by the mobile services. In Canada, the use of the band 2300–2483.5 MHz by the aeronautical mobile service for telemetry has priority over other uses by the mobile services.

S5.395 In France, the use of the band 2310–2360 MHz by the aeronautical mobile service for telemetry has priority over other uses by the mobile service.

S5.396 Space stations of the broadcasting-satellite service in the band 2310–2360 MHz operating in accordance with No. S5.393 that may affect the services to which this band is allocated in other countries shall be coordinated and notified in accordance with Resolution 33. Complementary terrestrial broadcasting stations shall be subject to bilateral coordination with neighboring countries prior to their bringing into use.

S5.441 The use of the bands 4500–4800 MHz (space-to-Earth), 6725–7025 MHz (Earth-to-space), 10.7–10.95 GHz (space-to-Earth), 11.2–11.45 GHz (space-to-Earth) and 12.75–13.25 GHz (Earth-to-space) by the fixed-satellite service shall be in accordance with the provisions of Appendix 30B/S30B.

S5.484 In Region 1, the use of the band 10.7–11.7 GHz by the fixed-satellite service (Earth-to-space) is limited to feeder links for the broadcasting-satellite service.

S5.497 The use of the band 13.25–13.4 GHz by the aeronautical radionavigation service is limited to Doppler navigation aids.

S5.498 The band 13.25–13.4 GHz may also be used in the space research service (Earth-to-space) on a secondary basis, subject to agreement obtained under Article 14/No. S9.21.

S5.499 *Additional allocation:* in Bangladesh, India and Pakistan, the band 13.25–14 GHz is also allocated to the fixed service on a primary basis.

S5.500 *Additional allocation:* in Algeria, Angola, Saudi Arabia, Bahrain, Brunei Darussalam, Cameroon, the Republic of Korea, Egypt, the United Arab Emirates, Gabon, Guinea, Indonesia, the Islamic Republic of Iran, Iraq, Israel, Jordan, Kuwait, Lebanon, Madagascar, Malaysia, Malawi, Mali, Malta, Morocco, Mauritania, Niger, Nigeria, Pakistan, Qatar, Syria, Senegal, Singapore, Sudan, Chad and Tunisia, the band 13.4–14 GHz is also allocated to the fixed and mobile services on a primary basis.

S5.501 *Additional allocation:* in Armenia, Austria, Azerbaijan, Belarus, Bulgaria, Georgia, Hungary, Japan, Kazakhstan, Moldova, Mongolia, Kyrgyzstan, Romania, the United Kingdom, Russia, Tajikistan, Turkmenistan and Ukraine, the band 13.4–14 GHz is also allocated to the radionavigation service on a primary basis.

S5.502 In the band 13.75–14 GHz, the e.i.r.p. of any emission from an earth station in the fixed-satellite service shall be at least 68

dBW, and should not exceed 85 dBW, with a minimum antenna diameter of 4.5 metres. In addition the e.i.r.p., averaged over one second, radiated by a station in the radio-location or radionavigation services towards the geostationary-satellite orbit shall not exceed 59 dBW.

S5.503 In the band 13.75–14 GHz, geostationary space stations in the space research service for which information for advance publication has been received by the Bureau prior to 31 January 1992 shall operate on an equal basis with stations in the fixed-satellite service; after that date, new geostationary space stations in the space research service will operate on a secondary basis. The e.i.r.p. density of emissions from any earth station in the fixed-satellite service shall not exceed 71 dBW per 6 MHz in the frequency range 13.772–13.778 GHz until those geostationary space stations in the space research service for which information for advance publication has been received by the Bureau prior to 31 January 1992 cease to operate in this band. Automatic power control may be used to increase the e.i.r.p. density above 71 dBW per 6 MHz in this frequency range to compensate for rain attenuation, to the extent that the power-flux density at the fixed-satellite service space station does not exceed the value resulting from use of 71 dBW per 6 MHz e.i.r.p. in clear sky conditions.

S5.503A Until 1 January 2000, stations in the fixed-satellite service shall not cause harmful interference to non-geostationary space stations in the space research and Earth exploration-satellite services. After that date, these non-geostationary space stations will operate on a secondary basis in relation to the fixed-satellite service. Additionally, when planning earth stations in the fixed-satellite service to be brought into service between 1 January 2000 and 1 January 2001, in order to accommodate the needs of spaceborne precipitation radars operating in the band 13.793–13.805 GHz, advantage should be taken of the consultation process and the information given in Recommendation ITU-R SA.1071.

S5.504 The use of the band 14–14.3 GHz by the radionavigation service shall be such as to provide sufficient protection to space stations of the fixed-satellite service (see Recommendation 708).

S5.505 *Additional allocation:* in Algeria, Angola, Saudi Arabia, Australia, Bahrain, Bangladesh, Botswana, Brunei Darussalam, Cameroon, China, the Congo, the Republic of Korea, Egypt, the United Arab Emirates, Gabon, Guatemala, Guinea, India, Indonesia, the Islamic Republic of Iran, Iraq, Israel, Japan, Jordan, Kuwait, Lesotho, Lebanon, Malaysia, Malawi, Mali, Morocco, Mauritania, Niger, Oman, Pakistan, the Philippines, Qatar, Syria, the Democratic People's Republic of Korea, Senegal, Singapore,

Somalia, Sudan, Swaziland, Tanzania, Chad and Yemen, the band 14–14.3 GHz is also allocated to the fixed service on a primary basis.

S5.506 The band 14–14.5 GHz may be used, within the fixed-satellite service (Earth-to-space), for feeder links for the broadcasting-satellite service, subject to coordination with other networks in the fixed-satellite service. Such use of feeder links is reserved for countries outside Europe.

S5.508 *Additional allocation:* in Germany, Austria, Belgium, Bosnia and Herzegovina, Denmark, Spain, France, Greece, Ireland, Iceland, Italy, The Former Yugoslav Republic of Macedonia, Libya, Liechtenstein, Luxembourg, Norway, Portugal, the United Kingdom, Slovenia, Switzerland, Turkey and Yugoslavia, the band 14.25–14.3 GHz is also allocated to the fixed service on a primary basis.

S5.509 *Additional allocation:* in Japan and Pakistan the band 14.25–14.3 GHz is also allocated to the mobile, except aeronautical mobile, service on a primary basis.

S5.534 *Additional allocation:* in Japan, the band 24.65–25.25 GHz is also allocated to the radionavigation service on a primary basis until 2008.

S5.535 In the band 24.75–25.25 GHz, feeder links to stations of the broadcasting-satellite service shall have priority over other users in the fixed-satellite service (Earth-to-space). Such other users shall protect and shall not claim protection from existing and future operating feeder-link networks to such broadcasting satellite stations.

II. Old Numbering Scheme

444 Administrations authorizing the use of frequencies below 9 kHz shall ensure that no harmful interference is caused thereby to the services to which the bands above 9 kHz are allocated (see also No. 1816).

445 Administrations conducting scientific research using frequencies below 9 kHz are urged to advise other administrations that may be concerned in order that such research may be afforded all practicable protection from harmful interference.

446 *Additional allocation:* In Bulgaria, Hungary, Poland, the German Democratic Republic, Czechoslovakia, and the U.S.S.R., the band 14–17 kHz is also allocated to the radionavigation service on a permitted basis.

447 The stations of services to which the bands 14–19.95 kHz and 20.5–70 kHz and in Region 1 also the bands 72–84 kHz and 86–90 kHz are allocated may transmit standard frequency and time signals. Such stations shall be afforded protection from harmful interference. In Bulgaria, Hungary, Mongolia, Poland, Czechoslovakia, and the U.S.S.R., the frequencies 25 kHz and 50 kHz will be used for this purpose under the same conditions.

448 The use of the bands 14–19.95 kHz, 20.05–70 kHz, and 70–90 kHz (72–84 kHz and 86–90 kHz in Region 1) by the maritime mobile

service is limited to coast radiotelegraph stations (A1A and F1B only). Exceptionally, the use of class J2B or J7B emissions is authorized subject to the necessary bandwidth not exceeding that normally used for class A1A or F1B emissions in the band concerned.

449 *Additional allocation:* In Bulgaria, Hungary, Poland, the German Democratic Republic, Czechoslovakia, and the U.S.S.R., the band 67–70 kHz is also allocated to the radionavigation service on a permitted basis.

450 *Different category of service:* In Bangladesh, Iran and Pakistan the allocation of the bands 70–72 kHz and 84–86 kHz to the fixed and maritime mobile services is on a primary basis (see No. 425).

451 In the bands 70–90 kHz (70–86 kHz in Region 1) and 110–130 kHz (112–130 kHz in Region 1), pulsed radionavigation systems may be used on condition that they do not cause harmful interference to other services to which these bands are allocated.

452 In Region 2, the establishment and operation of stations in the maritime radionavigation service in the bands 70–90 kHz and 110–130 kHz shall be subject to agreement obtained under the procedure set forth in Article 14 with administrations whose services, operating in accordance with the Table, may be affected. However, stations of the fixed, maritime mobile and radiolocation services shall not cause harmful interference to stations in the maritime radionavigation service under such agreements.

453 Administrations which operate stations in the radionavigation service in the band 90–110 kHz are urged to coordinate technical and operating characteristics in such a way as to avoid harmful interference to the services provided by these stations.

453A In the band 90–110 kHz, the United Kingdom may continue to use its coast radiotelegraph stations in operation on 14 September 1987, on a secondary basis.

454 Only classes A1A or F1B, A2C, A3C, F1C or F3C emissions are authorized for stations of the fixed service in the bands allocated to this service between 90 kHz and 160 kHz (148.5 kHz in Region 1) and for stations of the maritime mobile service in the bands allocated to this service between 110 kHz and 160 kHz (148.5 kHz in Region 1). Exceptionally, class J2B or J7B emissions are also authorized in the bands between 110 kHz and 160 kHz (148.5 kHz in Region 1) for stations of the maritime mobile service.

455 *Different category of service:* In Bangladesh, Iran and Pakistan, the allocation of the bands 112–117.6 kHz and 126–129 kHz to the fixed and maritime mobile services is on a primary basis (see No. 425).

456 *Different category of service:* In Federal Republic of Germany, the allocation of the band 115–117.6 kHz to the fixed and maritime mobile services is on a primary basis (see No. 425) and to the radionavigation service on a secondary basis (see No. 424).

457 *Additional allocation:* In Bulgaria, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia, and the U.S.S.R., the band 130–148.5 kHz is also allocated to the radionavigation service on a secondary basis. Within and between these countries this service shall have an equal right to operate.

459 In the Region 2 polar areas (north of 60° N and south of 60° S) which are subject to auroral disturbances, the aeronautical fixed service is the primary service in the band 160–190 kHz.

460 *Alternative allocation:* In Angola, Botswana, Burundi, the Congo, Malawi, Rwanda, South Africa and Zaire, the band 160–200 kHz is allocated to the fixed service on a primary basis.

461 *Additional allocation:* In Somalia, the band 200–255 kHz is also allocated to the aeronautical radionavigation service on a primary basis.

462 *Alternative allocation:* In Angola, Botswana, Burundi, Cameroon, Central African Republic, the Congo, Ethiopia, Kenya, Lesotho, Madagascar, Malawi, Mozambique, Namibia, Nigeria, Oman, Rwanda, South Africa, Swaziland, Tanzania, Chad, Zaire, Zambia and Zimbabwe, the band 200–283.5 kHz is allocated to the aeronautical radionavigation service on a primary basis.

463 *Different category of service:* In Sudan and Yemen (P.D.R. of), the allocation of the band 255–283.5 kHz to the aeronautical radionavigation service is on a primary basis (see No. 425).

464 *Alternative allocation:* In Tunisia, the band 255–283.5 kHz is allocated to the broadcasting service on a primary basis.

464A In Region 1, the change of the band limit from 285 kHz to 283.5 kHz shall take place on 1 February 1990 (see Resolution 500).

465 Norwegian stations of the fixed service situated in northern areas (north of 60° N) subject to auroral disturbances are allowed to continue operation on four frequencies in the bands 283.5–490 kHz and 510–526.5 kHz.

466 In the band 285–325 kHz (283.5–325 kHz in Region 1), in the maritime radionavigation service, radiobeacon stations may also transmit supplementary navigational information using narrow-band techniques, on condition that the prime function of the beacon is not significantly degraded.

466A *Additional Allocation:* in Region 1, the frequency band 285.3–285.7 kHz is also allocated to the maritime radionavigation service (other than radiobeacons) on a permitted basis.

467 *Different category of service:* In the U.S.S.R., and the Black Sea areas of Bulgaria, Roumania and Turkey, the allocation of the band 315–325 kHz to the maritime radionavigation service is on a primary basis (see No. 425) under the following conditions:

(a) In the Black Sea and White Sea areas, the maritime radionavigation service is the primary service and the aeronautical radionavigation service is the permitted service;

(b) In the Baltic Sea area, the assignment of frequencies in this band to new stations in the maritime or aeronautical radionavigation services shall be subject to prior consultation between the administrations concerned.

468 The frequency 410 kHz is designated for radio direction-finding in the maritime radionavigation service. The other radionavigation services to which the band 405–415 kHz is allocated shall not cause harmful interference to radio direction-finding in the band 406.5–413.5 kHz.

469 *Different category of service:* in Afghanistan, Australia, China, the Overseas French Territories of Region 3, India, Indonesia, the Islamic Republic of Iran, Japan, Pakistan, Papua New Guinea and Sri Lanka, the allocation of the band 415–495 kHz to the aeronautical radionavigation service is on a permitted basis. Administrations in these countries shall take all practical steps necessary to ensure that aeronautical radionavigation stations in the band 435–495 kHz do not cause interference to reception by coast stations of ship stations transmitting on frequencies designated for ship stations on a world-wide basis (see No. 4237).

469A *Different category of service:* in Cuba, the United States of America, and Mexico the allocation of the band 415–435 kHz to the aeronautical radionavigation service is on a primary basis.

470 The use of the bands 415–495 kHz and 505–526.5 kHz (505–510 kHz in Region 2) by the maritime mobile service is limited to radiotelegraphy.

470A In Region 2, the use of the band 435–495 kHz by the aeronautical radionavigation service is limited to non-directional beacons not employing voice transmission.

471 The bands 490–495 kHz and 505–510 kHz shall be subject to the provision of No. 3018 until the entry into force of the reduced guardband in accordance with Resolution 210 (Mob-87).

472 The frequency 500 kHz is an international distress and calling frequency for Morse radiotelegraphy. The conditions for its use are prescribed in Articles 37, 38, N 38 and 60.

472A In the maritime mobile service, the frequency 490 kHz is, from the date of full implementation of the GMDSS (see Resolution 331 (Mob-87)), to be used exclusively for the transmission by coast stations of navigational and meteorological warnings and urgent information to ships, by means of narrow-band direct-printing telegraphy. The conditions for use of the frequency 490 kHz are prescribed in Articles N 38 and 60, and Resolution 329 (Mob-87). In using the band 415–495 kHz for the aeronautical radio-

navigation service, administrations are requested to ensure that no harmful interference is caused to the frequency 490 kHz.

474 The conditions for the use of frequency 518 kHz by the maritime mobile service are prescribed in Articles 38, N 38 and 60 (see Resolution 324 (Mob-87) and Article 14A).

475 In the band 515.5–526.5 kHz, Austria may continue to operate only those broadcasting stations listed in Additional Protocol III to the Final Acts of the Regional Administrative LF/MF Broadcasting Conference (Regions 1 and 3), Geneva, 1975. This operation is allowed until the entry into force of a revision of the Geneva Plan, 1975, and subject to not causing harmful interference to the maritime mobile and aeronautical radionavigation services.

476 *Additional allocation:* In the United Kingdom, the band 519.5–526.5 kHz is also allocated to the broadcasting service on a secondary basis for the transmission of public utility information.

477 In Region 2, in the band 525–535 kHz the carrier power of broadcasting stations shall not exceed 1 kilowatt during the day and 250 watts at night.

478 *Additional allocation:* In Angola, Botswana, Lesotho, Malawi, Mozambique, Namibia, South Africa, Swaziland, Zambia and Zimbabwe, the band 526.5–535 kHz is also allocated to the mobile service on a secondary basis.

479 *Additional allocation:* In China, the band 526.5–535 kHz also allocated to the aeronautical radionavigation service on a secondary basis.

480 In Region 2, the use of the 1605–1705 kHz band by stations of the broadcasting service is subject to the Plan established by the Regional Administrative Radio Conference (Rio de Janeiro, 1988).

In Region 2, in the 1625–1705 kHz band, the relationship between the broadcasting, fixed and mobile services is shown in No. 419. However, the examination of frequency assignments to stations of the fixed and mobile services in the 1625–1705 kHz band under No. 1241 shall take account of the allotments appearing in the plan established by the Regional Administrative Radio Conference (Rio de Janeiro, 1988).

480A In the band 1605–1705 kHz, in cases where a broadcasting station of Region 2 is concerned, the service area of the maritime mobile stations in Region 1 shall be limited to that provided by ground-wave propagation.

481 In Region 2, until the dates decided by the regional administrative radio conference referred to in No. 480, the band 1 605–1 705 kHz is allocated to the fixed, mobile and aeronautical radionavigation services on a primary basis and to the radiolocation service on a secondary basis (see Recommendation 504).

482 *Additional allocation:* In Australia, Indonesia, New Zealand, the Philippines, Singapore, Sri Lanka and Thailand, the band 1 606.5–1 705 kHz is also allocated to the broadcasting service on a secondary basis.

483 *Different category of service:* In Bulgaria, Hungary, Mongolia, Nigeria, Poland, the German Democratic Republic, Chad, Czechoslovakia and the U.S.S.R., the allocation of the bands 1 606.5–1 625 kHz, 1 635–1 800 kHz and 2 107–2 160 kHz to the fixed and land mobile services is on a primary basis (see No. 425).

484 Some countries of Region 1 use radio-determination systems in the bands 1 606.5–1 625 kHz, 1 635–1 800 kHz, 1 850–2 160 kHz, 2 194–2 300 kHz, 2 502–2 850 kHz and 3 500–3 800 kHz. The establishment and operation of such systems are subject to agreement obtained under the procedure set forth in Article 14. The radiated mean power of these stations shall not exceed 50 W.

485 *Additional allocation:* In Angola, Bulgaria, Hungary, Mongolia, Nigeria, Poland, the German Democratic Republic, Chad, Czechoslovakia and the U.S.S.R., the bands 1 625–1 635 kHz, 1 800–1 810 kHz and 2 160–2 170 kHz are also allocated to the fixed and land mobile services on a primary basis subject to agreement obtained under the procedure set forth in Article 14.

486 In Region 1, in the bands 1 625–1 635 kHz, 1 800–1 810 kHz and 2 160–2 170 kHz (except in the countries listed in No. 485 and those listed in No. 499 for the band 2 160–2 170 kHz), existing stations in the fixed and mobile except aeronautical mobile services (and stations of the aeronautical mobile (OR) service in the band 2 160–2 170 kHz) may continue to operate on a primary basis until satisfactory replacement assignments have been found and implemented in accordance with Resolution 38.

487 In Region 1, the establishment and operation of radiolocation stations in the bands 1 625–1 635 kHz, 1 800–1 810 kHz and 2 160–2 170 kHz shall be subject to agreement obtained under the procedure set forth in Article 14 (see also No. 486). The radiated mean power of radiolocation stations shall not exceed 50 W. Pulse systems are prohibited.

488 In the Federal Republic of Germany, Denmark, Finland, Hungary, Ireland, Israel, Jordan, Malta, Norway, Poland, the German Democratic Republic, the United Kingdom, Sweden, Czechoslovakia and the U.S.S.R., administrations may allocate up to 200 kHz to their amateur service in the band 1 715–1 800 kHz and 1 850–2 000 kHz. However, when allocating the bands within this range to their amateur service, administration shall, after prior consultation with administrations of neighbouring countries, take such steps as may be necessary to prevent harmful interference from their amateur service to the fixed and mobile services of other

countries. The mean power of any amateur station shall not exceed 10 W.

489 In Region 3, the Loran system operates either on 1850 kHz or 1950 kHz, the bands occupied being 1825–1875 kHz and 1925–1975 kHz respectively. Other services to which the band 1800–2000 kHz is allocated may use any frequency therein on condition that no harmful interference is caused to the Loran system operating on 1850 kHz or 1950 kHz.

490 *Alternative allocation:* In the Federal Republic of Germany, Angola, Austria, Belgium, Bulgaria, Cameroon, the Congo, Denmark, Egypt, Spain, Ethiopia, France, Greece, Italy, Lebanon, Luxembourg, Malawi, the Netherlands, Portugal, Syria, the German Democratic Republic, Somalia, Tanzania, Tunisia, Turkey and the U.S.S.R., the band 1 810–1 830 kHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

491 *Additional allocations:* In Saudi Arabia, Iraq, Israel, Libya, Poland, Roumania, Chad, Czechoslovakia, Togo and Yugoslavia, the band 1 810–1 830 kHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

492 In Region 1, the use of the band 1 810–1 850 kHz by the amateur service is subject to the condition that satisfactory replacement assignments have been found and implemented in accordance with Resolution 38, for frequencies to all existing stations of the fixed and mobile, except aeronautical mobile, services operating in this band (except for the stations of the countries listed in Nos. 490, 491 and 493). On completion of satisfactory transfer, the authorization to use the band 1 810–1 830 kHz by the amateur service in countries situated totally or partially north of 40°N shall be given only after consultation with the countries mentioned in Nos. 490 and 491 to define the necessary steps to be taken to prevent harmful interference between amateur stations and stations of other services operating in accordance with Nos. 490 and 491.

493 *Alternative allocations:* In Burundi and Lesotho, the band 1 810–1 850 kHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

494 *Alternative allocation:* In Argentina, Bolivia, Chile, Mexico, Paraguay, Peru, Uruguay and Venezuela, the band 1 850–2 000 kHz is allocated to the fixed, mobile except aeronautical mobile, radiolocation and radio-navigation services on a primary basis.

495 In Region 1, in making assignments to stations in the fixed and mobile services in the bands 1 850–2 045 kHz, 2 194–2 498 kHz, 2 502–2 625 kHz and 2 650–2 850 kHz, administrations should bear in mind the special requirements of the maritime mobile service.

501 The carrier frequencies 2182 kHz, 3023 kHz, 5680 kHz, 8364 kHz and the frequencies 121.5 MHz, 156.8 MHz and 243 MHz may also be used, in accordance with the procedures in

Federal Communications Commission

§2.106

force for terrestrial radiocommunication services, for search and rescue operations concerning manned space vehicles. The conditions for the use of the frequencies are prescribed in Articles 38 and N 38. The same applies to the frequencies 10003 kHz, 14993 kHz and 19993 kHz, but in each of these cases emissions must be confined in a band of ± 3 kHz about the frequency.

510 For the use of these bands allocated to the amateur service at 3.5 MHz, 7.0 MHz, 10.1 MHz, 14.0 MHz, 18.068 MHz, 21.0 MHz, 24.89 MHz and 144 MHz in the event of natural disasters, see Resolution 640.

547 In making assignments to stations of other services to which the band 37.5–38.25 MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

548 The band 40.66–40.70 MHz (centre frequency 40.68 MHz) is designated for industrial, scientific and medical (ISM) applications. Radiocommunication services operating within this band must accept harmful interference which may be caused by these applications. ISM equipment operating in this band is subject to the provisions of No. 1815.

549 *Additional allocation:* In Botswana, Burundi, Lesotho, Malawi, Namibia, Rwanda, South Africa, Swaziland, Zaire, Zambia and Zimbabwe and band 41–44 MHz is also allocated to the aeronautical radionavigation service on a primary basis.

550 *Additional allocation:* In Iran and Japan, the band 41–44 MHz is also allocated to the radiolocation service on a secondary basis.

552 *Additional allocation:* In Australia and New Zealand, the band 44–47 MHz is also allocated to the broadcasting service on a primary basis.

553 *Additional allocation:* In Hungary, Kenya, Mongolia, Czechoslovakia and the U.S.S.R., the bands 47–48.5 and 56.5–58 MHz are also allocated to the fixed and land mobile services on a secondary basis.

554 *Additional allocation:* in Albania, the Federal Republic of Germany, Austria, Belgium, Bulgaria, Cote d'Ivoire, Denmark, Spain, Finland, France, Gabon, Greece, Ireland, Israel, Italy, Jordan, Lebanon, Libya, Liechtenstein, Luxembourg, Madagascar, Mali, Malta, Morocco, Mauritania, Monaco, Nigeria, Norway, the Netherlands, Poland, the German Democratic Republic, the United Kingdom, Senegal, Sweden, Switzerland, Swaziland, Syria, Togo, Tunisia, Turkey and Yugoslavia, the band 47–68 MHz and in Romania, the band 47–58 MHz, are also allocated to the land mobile service on a permitted basis. However, stations of the land mobile service in the countries mentioned in connection with each band referred to in this

footnote shall not cause harmful interference to, or claim protection from, existing or planned broadcasting stations of countries other than those mentioned in connection with the band.

555 *Additional allocation:* In Angola, Cameroon, Congo, Madagascar, Mozambique, Somalia, Sudan, Tanzania, Chad and Yemen (P.D.R.), the band 47–68 MHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a permitted basis.

556 *Alternative allocation:* In New Zealand, the band 50–51 MHz is allocated to the fixed, mobile and broadcasting services on a primary basis; the band 53–54 MHz is allocated to the fixed and mobile services on a primary basis.

557 *Alternative allocation:* In Afghanistan, Bangladesh, Brunei, India, Indonesia, Iran, Malaysia, Pakistan, Singapore and Thailand, the band 50–54 MHz is allocated to the fixed, mobile and broadcasting services on a primary basis.

558 *Additional allocation:* In Australia, China and the Democratic People's Republic of Korea, the band 50–54 MHz is also allocated to the broadcasting service on a primary basis.

559 *Additional allocation:* In Botswana, Burundi, Lesotho, Malawi, Namibia, Rwanda, South Africa, Swaziland, Zaire, Zambia and Zimbabwe, the band 50–54 MHz is also allocated to the amateur service on a primary basis.

560 *Additional allocation:* In New Zealand, the band 51–53 MHz is also allocated to the fixed and mobile services on a primary basis.

561 *Additional allocation:* In Botswana, Burundi, Lesotho, Malawi, Mali, Namibia, Rwanda, South Africa, Swaziland, Zaire, Zambia and Zimbabwe, the band 54–68 MHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

562 *Different category of service:* In the French Overseas Departments in Region 2, Guyana, Jamaica and Mexico, the allocation of the band 54–68 MHz to the fixed and mobile services is on a primary basis (see No. 425).

563 *Different category of service:* In Cuba, the French Overseas Departments in Region 2, Guyana, Jamaica and Mexico, the allocation of the band 68–72 MHz to the fixed and mobile services is on a primary basis (see No. 425).

564 *Additional allocation:* In Bulgaria, Hungary, Poland, Roumania and Czechoslovakia, the band 68–73 MHz is allocated to the broadcasting service on a primary basis and used in accordance with the decisions in the Final Acts of the Special Regional Conference, Geneva, 1960.

565 *Additional allocation:* In Mongolia and the U.S.S.R., the bands 68–73 MHz and 76–87.5 MHz are allocated to the broadcasting service on a primary basis. The services to which these bands are allocated in other countries

and the broadcasting service in Mongolia and the U.S.S.R., are subject to agreements with the neighboring countries concerned.

566 *Additional allocation:* In Australia, China, the Republic of Korea, the Philippines, the Democratic People's Republic of Korea and Western Samoa, the band 68–74 MHz is also allocated to the broadcasting service on a primary basis.

567 *Additional allocation:* In Bulgaria, Hungary, Mongolia, Poland, Czechoslovakia and the U.S.S.R., the band 73–74 MHz is also allocated to the broadcasting service on a primary basis. The use of this band by the broadcasting service in Bulgaria, Hungary, Mongolia, Poland, Czechoslovakia and the U.S.S.R., is subject to agreement obtained under the procedure set forth in Article 14.

568 In making assignments to stations of other services to which the band 73–74.6 MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

569 In Region 2, the fixed, mobile and broadcasting services previously authorized in the band 73–74.6 MHz may continue to operate on a non-interference basis to the radio astronomy service until 31 December 1985.

570 *Additional allocation:* In Columbia, Costa Rica, Cuba, El Salvador, Ecuador, Guatemala, Guyana, Honduras and Nicaragua, the band 73–74.6 MHz is also allocated to the fixed and mobile services on a secondary basis.

571 *Additional allocation:* In Bulgaria, China, Hungary, Mongolia, Poland, Czechoslovakia and the U.S.S.R., the bands 74.6–74.8 and 75.2–75.4 MHz are also allocated to the aeronautical radionavigation service, on a primary basis, for ground-based transmitters only.

572 *Additional allocation:* The frequency 75 MHz is assigned to aeronautical marker beacons. Administrations shall refrain from assigning frequencies close to the limits of the guardband to stations of other services which, because of their power or geographical position, might cause harmful interference or otherwise place a constraint on marker beacons.

Until 31 December 1989, administrations in Regions 2 and 3 should refrain from assigning frequencies to other services in the bands 74.6–74.8 MHz and 75.2–75.4 MHz.

In the future every effort should be made to improve further the characteristics of airborne receivers and to limit the power of transmitting stations close to the limits 74.8 and 75.2 MHz.

572A *Additional allocation:* in Afghanistan, the Federal Republic of Germany, Austria, Belgium, Cyprus, Denmark, Egypt, Spain, France, Greece, Israel, Italy, Japan, Jordan,

Lebanon, Malta, Morocco, Monaco, Norway, the Netherlands, Portugal, the United Kingdom, Sweden, Switzerland, Syria and Turkey, the band 74.8–75.2 MHz is also allocated to the mobile service on a secondary basis subject to agreement obtained under the procedure set forth in Article 14. In order to ensure that harmful interference is not caused to stations of the aeronautical radio-navigation service, stations of the mobile service shall not be introduced in the band until it is no longer required for the aeronautical radionavigation service by any administration which may be identified in the application of Article 14.

573 *Additional allocation:* In Western Samoa, the band 75.4–87 MHz is also allocated to the broadcasting service on a primary basis.

574 *Additional allocation:* In China, the Republic of Korea, Japan, the Philippines and the Democratic People's Republic of Korea, the band 76–87 MHz is also allocated to the broadcasting service on a primary basis.

575 *Additional allocation:* In Bulgaria, Hungary, Poland, Roumania and Czechoslovakia, the band 76–87.5 MHz is also allocated to the broadcasting service on a primary basis and used in accordance with the decisions contained in the Final Acts of the Special Regional Conference, Geneva, 1960.

576 *Different category of service:* In the United States, the French Overseas Departments in Region 2, Guyana, Jamaica, Mexico and Paraguay the allocation of the band 76–88 MHz to the fixed and mobile services is on a primary basis (see No. 425).

577 In Region 3 (except in the Republic of Korea, India, Japan, Malaysia, the Philippines, Singapore and Thailand) the band 79.75–80.25 MHz is also allocated to the radio astronomy service on a primary basis. In making assignments to stations of other services, administrations are urged to take all practicable steps in the band to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

578 *Alternative allocation:* In Albania, the band 81–87.5 MHz is allocated to the broadcasting service on a primary basis and used in accordance with the decisions contained in the Final Acts of the Special Regional Conference, Geneva, 1960.

579 *Additional allocation:* In Afghanistan and Australia the band 85–87 MHz is also allocated to the broadcasting service on a primary basis. The introduction of the broadcasting service in these countries is subject to special agreements between the administrations concerned.

580 *Additional allocation:* In New Zealand, the band 87–88 MHz is allocated to the land mobile service on a primary basis.

Federal Communications Commission

§2.106

581 *Additional allocation:* In the Federal Republic of Germany, Spain, France, Ireland, Italy, Liechtenstein, Monaco, the United Kingdom, Switzerland and Yemen (P.D.R. of), the band 87.5–88 MHz is also allocated to the land mobile service on a permitted basis and subject to agreement obtained under the procedure set forth in Article 14.

582 *Additional allocation:* In the United Kingdom the band 97.6–102.1 MHz is also allocated to the land mobile service on a permitted basis until 31 December 1989. The use of this band by the land mobile service is restricted to those stations in operation on 1 January 1980. The withdrawal of land mobile stations will be arranged in consultation with the administrations concerned.

584 Broadcasting stations in the band 100–108 MHz in Region 1 shall be established and operated in accordance with an agreement and associated plan for the band 87.5–108 MHz to be drawn up by a regional broadcasting conference (see Resolution 510). Prior to the date of entry into force of this agreement, broadcasting stations may be introduced subject to agreement between administrations concerned, on the understanding that such an operation shall in no case prejudice the establishment of the plan.

585 *Additional allocation:* In China, the Republic of Korea, the Philippines and Singapore, the band 100–108 MHz is also allocated to the fixed and mobile services on a permitted basis.

586 *Alternative allocation:* In New Zealand the band 100–108 MHz is allocated to the land mobile service on a primary basis and to the broadcasting service on a secondary basis.

587 *Additional allocation:* in Austria, Bulgaria, Hungary, Israel, Kenya, Mongolia, Poland, Syria, the German Democratic Republic, the United Kingdom, Somalia, Czechoslovakia, Turkey and the USSR, the band 104–108 MHz is also allocated to the mobile, except aeronautical mobile (R), service on a permitted basis until 31 December 1995 and, thereafter, on a secondary basis.

588 *Additional allocation:* In Finland and Yugoslavia, the band 104–108 MHz is also allocated to the fixed service on a permitted basis, until 31 December 1995. The effective radiated power of any station shall not exceed 25 W.

589 *Additional allocation:* in France, Romania, Sweden and Yugoslavia, the band 104–108 MHz is also allocated to the mobile, except aeronautical mobile (R), service on a permitted basis until 31 December 1995.

590A *Additional allocation:* in Afghanistan, the Federal Republic of Germany, Austria, Cyprus, Denmark, Egypt, Spain, France, Israel, Italy, Japan, Jordan, Lebanon, Malta, Morocco, Monaco, Norway, Pakistan, Portugal, the United Kingdom, Sweden, Switzerland, Syria and Turkey, the band 108–111.975 MHz is also allocated to the mobile service on a secondary basis subject to agreement

obtained under the procedure set forth in Article 14. In order to ensure that harmful interference is not caused to stations of the aeronautical radionavigation service, stations of the mobile service shall not be introduced in the band until it is no longer required for the aeronautical radionavigation service by any administrations which may be identified in the application of Article 14.

591 Subject to agreement obtained under the procedure set forth in article 14, the band 117.975–137 MHz is also allocated to the aeronautical mobile-satellite (R) service on a secondary basis and on the condition that harmful interference is not caused to the aeronautical mobile (R) service.

592 The bands 121.45–121.55 MHz and 242.95–243.05 MHz are also allocated to the mobile-satellite service for the reception on board satellites of emissions from emergency position-indicating radiobeacons transmitting at 121.5 MHz and 243 MHz.

593 In the band 117.975–136 MHz, the frequency 121.5 MHz is the aeronautical emergency frequency and, where required, the frequency 123.1 MHz is the aeronautical frequency auxiliary to 121.5 MHz. Mobile stations of the maritime mobile service may communicate on these frequencies under the conditions laid down in Articles 38 and N 38 for distress and safety purposes with stations of the aeronautical mobile service.

594 *Additional allocation:* In Angola, Bulgaria, Hungary, Iran, Iraq, Japan, Mongolia, Mozambique, Papua New Guinea, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 132–136 MHz is also allocated to the aeronautical mobile (RO) service on a permitted basis.

594A *Different category of service:* as from 1 January 1990, in Bulgaria, Poland, German Democratic Republic, Romania, Czechoslovakia, Turkey and the USSR, the allocation of the band 136–137 MHz to the aeronautical mobile (OR) service is on a permitted basis.

595 Until 1 January 1990, the band 136–137 MHz is also allocated to the space operation service (space-to-Earth), meteorological-satellite service (space-to-Earth) and the space research service (space-to-Earth) on a primary basis. The introduction of stations of the aeronautical mobile (R) service shall only occur after that date. After 1 January 1990, the band 136–137 MHz will also be allocated to the above-mentioned space radiocommunication services on a secondary basis (see Resolution 408 (Mob-87)).

596 *Different category of service:* In Afghanistan, Saudi Arabia, Bahrain, Brunei, China, the United Arab Emirates, India, Indonesia, Iran, Iraq, Kuwait, Malaysia, Oman, Pakistan, Qatar, Singapore, Thailand, Yemen A.R. and Yemen (P.D.R. of), the allocation of the band 137–138 MHz to the fixed and mobile,

except aeronautical mobile (R), services is on a primary basis (see No. 425).

597 *Different category of service:* In Israel, Jordan and Syria, the allocation of the band 137–138 MHz to the fixed and mobile, except aeronautical mobile, services is on a primary basis (see No. 425).

598 *Different category of service:* In Austria, Bulgaria, Egypt, Finland, Greece, Hungary, Lebanon, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia, the U.S.S.R. and Yugoslavia, the allocation of the band 137–138 MHz to the aeronautical mobile (OR) service is on a primary basis.

599 *Additional allocation:* In Australia, the band 137–144 MHz is also allocated to the broadcasting service on a primary basis until that service can be accommodated within regional broadcasting allocations.

599A The use of the band 137–138 MHz by the mobile-satellite service is subject to the application of the coordination and notification procedures set forth in Resolution RES46 (WARC-92). However, coordination of a space station of the mobile-satellite service with respect to terrestrial services is required only if the power flux-density produced by the station exceeds $-125 \text{ dB(W/m}^2 \text{ 4 kHz)}$ at the Earth's surface. The above power flux-density limit shall apply until such time as a competent world administrative radio conference revises it. In making assignments to the space stations in the mobile-satellite service in the above band, administrations shall take all practicable steps to protect the radio astronomy service in the 150.05–153 MHz band from harmful interference from unwanted emissions.

599B The use of the bands 137–138 MHz, 148–149.9 MHz and 400.15–401 MHz by the mobile-satellite service and the band 149.9–150.05 MHz by the land mobile-satellite service is limited to non-geostationary-satellite systems.

600 *Additional allocation:* In the Federal Republic of Germany, Austria, Belgium, France, Israel, Italy, Liechtenstein, Luxembourg, the United Kingdom, Sweden, Switzerland and Czechoslovakia, the bands 138–143.6 MHz and 143.65–144 MHz are also allocated to the space research service (space-to-Earth) on a secondary basis.

601 *Additional allocation:* In the Federal Republic of Germany, Saudi Arabia, Austria, Bahrain, Belgium, Denmark, the United Arab Emirates, Spain, Finland, Greece, Ireland, Israel, Kenya, Kuwait, Liechtenstein, Luxembourg, Mali, Malta, Norway, the Netherlands, Qatar, the United Kingdom, Sweden, Switzerland, Somalia, Tanzania, Tunisia, Turkey and Yugoslavia, the band 138–144 MHz is also allocated to the maritime mobile and land mobile services on a primary basis.

602 *Alternative allocation:* In Angola, Botswana, Burundi, Cameroon, the Central African Republic, the Congo, Gabon, Gambia,

Ghana, Guinea, Iraq, Jordan, Lesotho, Liberia, Libya, Malawi, Mozambique, Namibia, Nigeria, Oman, Rwanda, Sierra Leone, South Africa, Swaziland, Chad, Togo, Zaire, Zambia and Zimbabwe, the band 138–144 MHz is allocated to the fixed and mobile services on a primary basis.

603 *Additional allocation:* In China, the band 138–144 MHz is also allocated to the radiolocation service on a primary basis.

604 *Additional allocation:* In Ethiopia, Finland, Kenya, Malta, Somalia, Sudan, Tanzania, Yemen A.R. and Yugoslavia, the band 138–144 MHz is also allocated to the fixed service on a primary basis.

605 *Additional allocation:* In Singapore, the band 144–145 MHz is also allocated to the fixed and mobile services on a primary basis. Such use is limited to systems in operation on or before 1 January 1980, which in any case shall cease by 31 December 1995.

606 *Additional allocation:* In China, the band 144–146 MHz is also allocated to the aeronautical mobile (OR) service on a secondary basis.

607 *Alternative allocation:* In Afghanistan, Bangladesh, Cuba, Guyana and India, the band 146–148 MHz is allocated to the fixed and mobile services on a primary basis.

608 Subject to agreement obtained under the procedure set forth in Article 14, the band 148–149.9 MHz may be used by the space operation service (Earth-to-space). The bandwidth of an individual transmission shall not exceed $\pm 25 \text{ kHz}$.

608A The use of the band 148–149.9 MHz by the mobile-satellite service is subject to the application of the coordination and notification procedures set forth in Resolution RES46 (WARC-92). The mobile-satellite service shall not constrain the development and use of fixed, mobile and space operation services in the band 148–149.9 MHz. Mobile earth stations in the mobile-satellite service shall not produce a power flux-density in excess of $-150 \text{ dB(W/m}^2 \text{ 4 kHz)}$ outside national boundaries.

608B The use of the band 149.9–150.05 MHz by the land mobile-satellite service is subject to the application of the coordination and notification procedures set forth in Resolution RES46 (WARC-92). The land mobile-satellite service shall not constrain the development and use of the radionavigation-satellite service in the band 149.9–150.05 MHz. Land mobile earth stations of the land mobile-satellite service shall not produce power flux-density in excess of $-150 \text{ dB(W/m}^2 \text{ 4kHz)}$ outside national boundaries.

608C Stations of the mobile-satellite service in the band 148–149.9 MHz shall not cause harmful interference to, or claim protection from stations of the fixed or mobile services in the following countries: Algeria, the Federal Republic of Germany, Saudi Arabia,

Federal Communications Commission

§2.106

Australia, Austria, Bangladesh, Belarus, Belgium, Brunei Darussalam, Bulgaria, Cameroon, Canada, Cyprus, Colombia, Congo, Cuba, Denmark, Egypt, the United Arab Emirates, Ecuador, Spain, Ethiopia, the Russian Federation, Finland, France, Ghana, Greece, Honduras, Hungary, Iran, Ireland, Iceland, Israel, Italy, Japan, Jordan, Kenya, Libya, Liechtenstein, Luxembourg, Malaysia, Mali, Malta, Mauritania, Mozambique, Namibia, Norway, New Zealand, Oman, Pakistan, Panama, Papua New Guinea, the Netherlands, Philippines, Poland, Portugal, Qatar, Syria, Romania, the United Kingdom, Singapore, Sri Lanka, Sweden, Switzerland, Suriname, Swaziland, Tanzania, Chad, the Czech and Slovak Federal Republic, Thailand, Tunisia, Turkey, Ukraine, Yemen and Yugoslavia that operate in accordance with the Table of Frequency Allocations.

609 Emissions of the radionavigation-satellite service in the bands 149.9–150.05 MHz and 399.9–400.05 MHz may also be used by receiving earth stations of the space research service.

609A Recognizing that the use of the band 149.9–150.05 MHz by the fixed and mobile services may cause harmful interference to the radionavigation-satellite service, administrations are urged not to authorize such use in application No. 342.

609B In the band 149.9–150.05 MHz, the allocation to the land mobile-satellite service shall be on a secondary basis until 1 January 1997.

610 In making assignments to stations of other services to which the band 150.05–153 MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

611 *Additional allocation:* In Australia and India, the band 150.05–153 MHz is also allocated to the radio astronomy service on a primary basis.

613 The frequency 156.8 MHz is the international distress, safety and calling frequency for the maritime mobile VHF radiotelephone service. The conditions for the use of this frequency are contained in Articles 38 and N 38.

In the bands 156–156.7625 MHz, 156.8375–157.45 MHz, 160.6–160.975 MHz and 161.475–162.05 MHz, each administration shall give priority to the maritime mobile service on only such frequencies as are assigned to stations of the maritime mobile service by the administration (see Articles 38, N 38 and 60).

Any use of frequencies in these bands by station of other services to which they are allocated should be avoided in areas where such use might cause harmful interference to the maritime mobile VHF radiocommunication service.

However, the frequency 156.8 MHz and the frequency bands in which priority is given to the maritime mobile service may be used for radiocommunications on inland waterways subject to agreement between interested and affected administrations and taking into account current frequency usage and existing agreements.

613A In the maritime mobile VHF service the frequency 156.525 MHz is to be used exclusively for digital selective calling for distress, safety and calling (see Resolution 323 (Mob-87)). The conditions for the use of this frequency are prescribed in Articles 38, N 38 and 60 and in Appendix 18.

613B *Additional allocation:* in Ireland and in the United Kingdom, the band 161.3875–161.4125 MHz is also allocated to the maritime radionavigation service on a primary basis, subject to agreement obtained under the procedure set forth in Article 14.

615 *Alternative allocation:* In Morocco, the band 162–174 MHz is allocated to the broadcasting service on a primary basis. The use of this band shall be subject to agreement with administrations having services, operating or planned, in accordance with the Table which are likely to be affected. Stations in existence on 1 January 1981, with their technical characteristics as of that date, are not affected by such agreement.

616 *Additional allocation:* In China, the band 163–167 MHz is also allocated to the space operation service (space-to-Earth) on a primary basis subject to agreement obtained under the procedure set forth in Article 14.

617 *Additional allocation:* In Afghanistan, China and Pakistan, the band 167–174 MHz is also allocated to the broadcasting service on a primary basis. The introduction of the broadcasting service into this band shall be subject to agreement with the neighbouring countries in Region 3, whose services are likely to be affected.

618 *Additional allocation:* In Japan, the band 170–174 MHz is also allocated to the broadcasting service on a primary basis.

619 *Additional allocation:* In China, the band 174–184 MHz is also allocated to the space research (space-to-Earth) and the space operation (space-to-Earth) services on a primary basis subject to agreement obtained under the procedure set forth in Article 14. These services shall not cause harmful interference to, or claim protection from, existing or planned broadcasting stations.

620 *Different category of service:* In Mexico, the allocation of the band 174–216 MHz to the fixed and mobile services is on a primary basis (see No. 425).

621 *Additional allocation:* in the Federal Republic of Germany, Austria, Belgium, Denmark, Spain, Finland, France, Israel, Italy, Liechtenstein, Malta, Monaco, Norway, the Netherlands, the United Kingdom, Sweden, and Switzerland, the band 174–223 MHz is also allocated to the land mobile

service on a permitted basis. However, the stations of the land mobile service shall not cause harmful interference to, or claim protection from, broadcasting stations, existing or planned, in countries other than those listed in this footnote.

622 *Different category of service:* in the Federal Republic of Germany, Austria, Belgium, Denmark, Spain, Finland, France, Israel, Italy, Liechtenstein, Luxembourg, Malta, Monaco, Norway, the Netherlands, Portugal, the United Kingdom, Sweden and Switzerland, the band 223–230 MHz is allocated to the land mobile service on a permitted basis (see No. 425). However, the stations of the land mobile service shall not cause harmful interference to, or claim protection from, broadcasting stations, existing or planned, in countries other than those listed in this footnote.

623 *Additional allocation:* In Congo, Ethiopia, Gambia, Guinea, Kenya, Libya, Malawi, Mali, Uganda, Senegal, Sierra Leone, Somalia, Tanzania, and Zimbabwe, the band 174–223 MHz is also allocated to the fixed and mobile services on a secondary basis.

624 *Additional allocation:* In Bangladesh, India, Pakistan, and the Philippines, the band 200–216 MHz is also allocated to the aeronautical radionavigation service on a primary basis.

626 *Additional allocation:* In China, India and Thailand, the band 216–223 MHz is also allocated to the aeronautical radionavigation service on a primary basis and to the radiolocation service on a secondary basis.

627 In Region 2, no new stations in the radiolocation service may be authorized in the band 216–225 MHz. Stations authorized prior to 1 January 1990 may continue to operate on a secondary basis.

627A *Additional allocation:* in Canada, the band 216–220 MHz is also allocated to the land mobile service on a primary basis.

628 *Additional allocation:* In Somalia, the band 216–225 MHz is also allocated to the aeronautical radionavigation service on a primary basis, subject to not causing interference to existing or planned broadcasting services in other countries.

629 *Additional allocation:* In Oman, the United Kingdom and Turkey, the band 216–235 MHz is also allocated to the radiolocation service on a secondary basis.

630 *Additional allocation:* In Japan, the band 222–223 MHz is also allocated to the aeronautical radionavigation service on a primary basis and to the radiolocation service on a secondary basis.

631 *Different category of service:* In Spain and Portugal, the band 223–230 MHz is allocated to the fixed service on a permitted basis (see No. 425). Stations of this service shall not cause harmful interference to, or claim protection from, broadcasting stations of other countries, whether existing or

planned, that operate in accordance with the Table.

632 *Additional allocation:* In Saudi Arabia, Bahrain, the United Arab Emirates, Israel, Jordan, Oman, Qatar and Syria, the band 223–235 MHz is also allocated to the aeronautical radionavigation service on a permitted basis.

635 *Alternative allocation:* in Botswana, Lesotho, Malawi, Mozambique, Namibia, South Africa, Swaziland, Zambia and Zimbabwe, the bands 223–238 MHz and 246–254 MHz are allocated to the broadcasting service on a primary basis, subject to agreement obtained under the provisions set forth in Article 14.

636 *Alternative allocation:* In New Zealand, Western Samoa, Niue and Cook Islands, the band 225–230 MHz is allocated to the fixed, mobile and aeronautical radionavigation services on a primary basis.

637 *Additional allocation:* In China, the band 225–235 MHz is also allocated to the radio astronomy service on a secondary basis.

638 *Additional allocation:* In Nigeria, the band 230–235 MHz is also allocated to the aeronautical radionavigation service on a primary basis, subject to agreement obtained under the procedure set forth in Article 14.

639 *Additional allocation:* In Yugoslavia, the band 230–235 MHz is also allocated to the aeronautical radionavigation service on a primary basis, until 1 January 1995. The use of this band by the aeronautical radionavigation service in Yugoslavia is restricted to the stations in operation by 1 January 1980.

640 *Additional allocation:* In New Zealand, the band 235–239.5 MHz is also allocated to the aeronautical radionavigation service on a primary basis.

641 Subject to agreement obtained under the procedure set forth in Article 14, the bands 235–322 MHz and 335.4–399.9 MHz may be used by the mobile-satellite service, on condition that stations in this service do not cause harmful interference to those of other services operating or planned to be operated in accordance with the Table.

641A The bands 312–315 MHz (Earth-to-space) and 387–390 MHz (space-to-Earth) in the mobile-satellite service may also be used by non-geostationary-satellite systems. Such use is subject to the application of the coordination and notification procedures set forth in Resolution 46 (WARC-92).

642 The frequency 243 MHz is the frequency in this band for use by survival craft stations and equipment used for survival purposes (see Article 38).

643 Subject to agreement obtained under the procedure set forth in Article 14, the band 267–272 MHz may be used by administrations for space telemetry in their countries on a primary basis.

644 In making assignments to stations of other services to which the band 322–328.6

MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

645 Limited to Instrument Landing Systems (glide path).

645A *Additional allocation:* In Afghanistan, the Federal Republic of Germany, Austria, Belgium, Cyprus, Denmark, Egypt, Spain, France, Greece, Israel, Italy, Japan, Jordan, Malta, Morocco, Monaco, Norway, the Netherlands, Portugal, the United Kingdom, Sweden, Switzerland, Syria and Turkey, the band 328.6–335.4 MHz is also allocated to the mobile service on a secondary basis subject to agreement obtained under the procedure set forth in Article 14. In order to ensure that harmful interference is not caused to stations of the aeronautical radionavigation service, stations of the mobile service shall not be introduced in the band until it is no longer required for the aeronautical radionavigation service by any administration which may be identified in the application of Article 14.

645B Recognizing that the use of the band 399.9–400.05 MHz by the fixed and mobile service may cause harmful interference to the radionavigation satellite service, administrations are urged not to authorize such use in application of No. 342.

646 Emissions shall be confined in a band of ± 25 kHz about the standard frequency 400.1 MHz.

647 *Additional allocation:* In Afghanistan, Saudi Arabia, Austria, Bahrain, Bulgaria, Colombia, Costa Rica, Cuba, Egypt, the United Arab Emirates, Ecuador, Hungary, Indonesia, Iran, Iraq, Israel, Kuwait, Liberia, Malaysia, Nigeria, Oman, Pakistan, the Philippines, Poland, Qatar, Syria, the German Democratic Republic, Roumania, Singapore, Somalia, Sri Lanka, Czechoslovakia, Thailand, the U.S.S.R. and Yugoslavia, the band 400.05–401 MHz is also allocated to the fixed and mobile services on a primary basis.

647A The band 400.15–401 MHz is also allocated to the space research service in the space-to-space direction for communications with manned space vehicles. In this application, the space research service will not be regarded as a safety service.

647B The use of the band 400.15–401 MHz by the mobile-satellite service is subject to the application of the coordination and notification procedures set forth in Resolution RES46 (WARC-92). However, coordination of a space station of the mobile-satellite service with respect to terrestrial services is required only if the power flux-density produced by the station exceeds -125 dB(W/m² 4kHz) at the Earth's surface. The above power flux-density limit shall apply until such time as a competent world administra-

tive radio conference revises it. In making assignments to the space stations in the mobile-satellite service in the above band, administrations shall take all practicable steps to protect the radio astronomy service in the band 406.1–410 MHz from harmful interference from unwanted emissions.

648 *Additional allocation:* In Canada, the bands 405.5–406 MHz and 406.1–410 MHz are also allocated to the mobile-satellite, except aeronautical mobile-satellite, service (Earth-to-space), on a primary basis, subject to agreement obtained under the procedure set forth in Article 14.

649 The use of the band 406–406.1 MHz by the mobile-satellite service is limited to low power satellite emergency position-indicating radiobeacons (see also Articles 38 and N 38).

649A Any emission capable of causing harmful interference to the authorized uses of the band 406–406.1 MHz is prohibited.

650 In making assignments to stations of other services to which the band 406.1–410 MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

651 *Different category of service:* In Australia, the United States, India, Japan and the United Kingdom, the allocation of the bands 420–430 MHz and 440–450 MHz to the radiolocation service is on a primary basis (see No. 425).

652 *Additional allocation:* In Australia, the United States, Jamaica and the Philippines, the bands 420–430 MHz and 440–450 MHz are also allocated to the amateur service on a secondary basis.

653 *Additional allocation:* In China, India, the German Democratic Republic, the United Kingdom and the U.S.S.R., the band 420–460 MHz is also allocated to the aeronautical radionavigation service (radio altimeters) on a secondary basis.

654 *Different category of service:* In France, the allocation of the band 430–434 MHz to the amateur service is on a secondary basis (see No. 424).

655 *Different category of service:* In Denmark, Libya, Norway and Sweden, the allocation of the bands 430–432 MHz and 438–440 MHz to the radiolocation service on a secondary basis (see No. 424).

656 *Alternative allocation:* In Denmark, Norway and Sweden, the bands 430–432 MHz and 438–440 MHz are allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

657 *Additional allocation:* In Finland, Libya and Yugoslavia, the bands 430–432 MHz and 438–440 MHz are also allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

658 *Additional allocation:* In Afghanistan, Algeria, Saudi Arabia, Bahrain, Bangladesh, Brunei, Burundi, Egypt, the United Arab Emirates, Ecuador, Ethiopia, Greece, Guinea, India, Indonesia, Iran, Iraq, Israel, Italy, Jordan, Kenya, Kuwait, Lebanon, Liechtenstein, Libya, Malaysia, Malta, Nigeria, Oman, Pakistan, the Philippines, Qatar, Syria, Singapore, Somalia, Switzerland, Tanzania, Thailand and Togo, the band 430–440 MHz is also allocated to the fixed service on a primary basis and the bands 430–435 MHz and 438–440 MHz are also allocated to the mobile, except aeronautical mobile, service on a primary basis.

659 *Additional allocation:* In Angola, Bulgaria, Cameroon, Congo, Gabon, Hungary, Mali, Mongolia, Niger, Poland, the German Democratic Republic, Roumania, Rwanda, Chad, Czechoslovakia and the U.S.S.R., the band 430–440 MHz is also allocated to the fixed service on a primary basis.

660 *Different category of service:* In Argentina, Colombia, Costa Rica, Cuba, Honduras, Panama and Venezuela, the allocation of the band 430–440 MHz to the amateur service is on a primary basis (see No. 425).

660A *Additional allocation:* in Mexico, the bands 430–435 MHz and 438–440 MHz are also allocated on a primary basis to the land mobile service, subject to agreement obtained under the procedure set forth in Article 14.

661 In Region 1, except in the countries mentioned in No. 662, the band 433.05–434.79 MHz (centre frequency 433.92 MHz) is designated for industrial scientific and medical (ISM) applications. The use of this frequency band for ISM applications shall be subject to special authorization by the administration concerned, in agreement with other administrations whose radiocommunications services might be affected. In applying this provision, administrations shall have due regard to the latest relevant CCIR Recommendations.

662 In the Federal Republic of Germany, Austria, Liechtenstein, Portugal, Switzerland and Yugoslavia, the band 433.05–434.79 MHz (centre frequency 433.92 MHz) is designated for industrial, scientific and medical (ISM) applications. Radiocommunication services of these countries operating within this band must accept harmful interference which may be caused by these applications. ISM equipment operating in this band is subject to the provisions of No. 1815.

663 *Additional allocation:* In Brazil, France and the French Overseas Departments in Region 2, and India, the band 433.75–434.25 MHz is also allocated to the space operation service (Earth-to-space) on a primary basis until 1 January 1990, subject to agreement obtained under the procedure set forth in Article 14. After 1 January 1990, the band 433.75–434.25 MHz will be allocated in the same countries to the same service on a secondary basis.

664 In the bands 435–438 MHz, 1 260–1 270 MHz, 2 400–2 450 MHz, 3 400–3 410 MHz (in Regions 2 and 3 only) and 5 650–5 670 MHz, the amateur-satellite service may operate subject to not causing harmful interference to other services operating in accordance with the Table (see No. 435). Administrations authorizing such use shall ensure that any harmful interference caused by emissions from a station in the amateur-satellite service is immediately eliminated in accordance with the provisions of No. 2741. The use of the bands 1 260–1 270 MHz and 5 650–5 670 MHz by the amateur-satellite service is limited to the Earth-to-space direction.

665 *Additional allocation:* In Austria, the band 438–440 MHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

666 *Additional allocation:* In Canada, New Zealand and Papua New Guinea, the band 440–450 MHz is also allocated to the amateur service on a secondary basis.

667 *Different category of service:* In Canada, the allocation of the band 440–450 MHz to the radiolocation service is on a primary basis (see No. 425).

668 Subject to agreement obtained under the procedure set forth in Article 14, the band 449.75–450.25 MHz may be used for the space operation service (Earth-to-space) and the space research service (Earth-to-space).

669 In the maritime mobile service, the frequencies 457.525 MHz, 457.550 MHz, 457.575 MHz, 467.525 MHz, 467.550 MHz and 467.575 MHz may be used by on-board communication stations. The use of these frequencies in territorial waters may be subject to the national regulations of the administration concerned. The characteristics of the equipment used shall conform to those specified in Appendix 20.

670 In the territorial waters of Canada, the United States and the Philippines, the preferred frequencies for use by on-board communication stations shall be 457.525 MHz, 457.550 MHz, 457.575 MHz and 457.600 MHz paired, respectively, with 467.750 MHz, 467.775 MHz, 467.800 MHz and 467.825 MHz. The characteristics of the equipment used shall conform to those specified in Appendix 20.

671 Earth exploration-satellite service applications, other than the meteorological-satellite service, may also be used in the bands 460–470 MHz and 1 690–1 710 MHz for space-to-Earth transmissions subject to not causing harmful interference to stations operating in accordance with the Table.

672 *Different category of service:* In Afghanistan, Bulgaria, China, Cuba, Japan, Mongolia, Czechoslovakia and the U.S.S.R., the allocation of the band 460–470 MHz to the meteorological-satellite service (space-to-Earth) is on a primary basis (see No. 425) and is subject to agreement obtained under the procedure set forth in Article 14.

Federal Communications Commission

§2.106

673 *Additional allocation:* In China, the band 470–485 MHz is also allocated to the space research (space-to-Earth) and the space operation (space-to-Earth) services on a primary basis subject to agreement obtained under the procedure set forth in Article 14, subject to not causing harmful interference to existing and planned broadcasting stations.

674 *Different category of service:* in Mexico and Venezuela, the allocation of the band 470–512 MHz to the fixed and mobile service, and in Argentina and Uruguay to the mobile service, is on a primary basis (see No. 425), subject to agreement obtained under the procedure set forth in Article 14.

675 *Additional allocation:* In Chile, Columbia, Cuba, Ecuador, the United States, Guyana, Honduras, Jamaica, Mexico and Panama, the allocation of the bands 470–512 MHz and 614–806 MHz to the fixed and mobile services is on a primary basis (see No. 425), subject to agreement obtained under the procedure set forth in Article 14.

676 *Additional allocation:* In Burundi, Cameroon, the Congo, Ethiopia, Israel, Kenya, Lebanon, Libya, Malawi, Senegal, Sudan, Syria, and Yemen, the band 470–582 MHz is also allocated to the fixed service on a secondary basis.

677 *Alternative allocation:* In Pakistan, the bands 470–582 MHz and 610–890 MHz are allocated to the broadcasting service on a primary basis.

677A *Additional allocation:* in the Federal Republic of Germany, Austria, Belgium, Cyprus, Denmark, Spain, Finland, France, Ireland, Israel, Italy, Libya, Malta, Morocco, Monaco, Norway, the Netherlands, Portugal, the United Kingdom, Sweden, Switzerland, Swaziland, Syria, Tunisia and Turkey, the band 470–790 MHz is also allocated on a secondary basis to the land mobile service, intended for applications ancillary to broadcasting. Stations of the land mobile service in the countries mentioned in this footnote, shall not cause harmful interference to existing or planned stations operating in accordance with the Table of Frequency Allocations in countries other than those listed in this footnote.

678 *Additional allocation:* In Costa Rica, Cuba, El Salvador, Ecuador, the United States, Guatemala, Guyana, Honduras, Jamaica, Mexico and Venezuela, the band 512–608 MHz is also allocated to the fixed and mobile services on a primary basis, subject to agreement obtained under the procedures set forth in Article 14.

679 *Additional allocation:* In India, the band 549.75–550.25 MHz is also allocated to the space operation service (space-to-Earth) on a secondary basis.

683 *Additional allocation:* In Oman, the band 582–606 MHz is also allocated to the radionavigation service on a secondary basis.

684 *Additional allocation:* In Israel, Libya, Syria and Sudan, the band 582–790 MHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a secondary basis.

685 *Additional allocation:* In Denmark and Kuwait, the band 590–598 MHz is also allocated to the aeronautical radionavigation service on a primary basis until 1 January 1995.

686 *Additional allocation:* In the United Kingdom, the band 598–590 MHz is also allocated to the aeronautical radionavigation service on a primary basis. All new assignments to stations in the aeronautical radionavigation service, including those transferred from the adjacent bands, shall be subject to coordination with the administrations of the following countries: the Federal Republic of Germany, Belgium, Denmark, Spain, France, Ireland, Luxembourg, Morocco, Norway and the Netherlands.

686A *Additional allocation:* in the United Kingdom, the band 598–606 MHz is also allocated to the aeronautical radionavigation service on a primary basis until 31 December 1994. All new assignments to stations in the aeronautical radionavigation service in this band are subject to the agreement of the Administrations of the following countries: the Federal Republic of Germany, Belgium, Denmark, Spain, France, Ireland, Luxembourg, Morocco, Norway and the Netherlands.

687 *Additional allocation:* In the African Broadcasting Area (see Nos. 400 to 403), the band 606–614 MHz is also allocated to the radio astronomy service on a permitted basis.

688 *Additional allocation:* In China, the band 606–614 MHz is also allocated to the radio astronomy service on a primary basis.

689 In Region 1, except in the African Broadcasting Area (see Nos. 400 to 403), and in Region 3, the band 608–614 MHz is also allocated to the radio astronomy service on a secondary basis. In making assignments to stations or other services to which the band is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

690 *Additional allocation:* In India, the band 608–614 MHz is also allocated to the radio astronomy service on a primary basis.

691 *Additional allocation:* In New Zealand, the band 610–620 MHz is also allocated to the amateur service on a secondary basis.

692 *Different category of service:* In Costa Rica, El Salvador and Honduras, the allocation of the band 614–806 MHz to the fixed service is on a primary basis (see No. 425), subject to agreement obtained under the procedure set forth in Article 14.

692A *Additional allocation:* in Cuba, the band 614–890 MHz is also allocated to the radionavigation service on a primary basis, subject to agreement obtained under the procedure set forth in Article 14.

693 Within the frequency band 620–790 MHz, assignments may be made to television stations using frequency modulation in the broadcasting-satellite service subject to agreement between administrations concerned and those having services, operating in accordance with the Table, which may be affected (see Resolutions 33 and 507). Such stations shall not produce a power flux-density in excess of the value $-129 \text{ dB(W/m}^2\text{)}$ for angles of arrival less than 20° (see Recommendation 705) within the territories of other countries without the consent of the administrations of those countries.

694 *Additional allocation:* In Bulgaria, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 645–862 MHz is also allocated to the aeronautical radionavigation service on a permitted basis.

695 *Alternative allocation:* In Spain and France, the band 790–830 MHz is allocated to the broadcasting service on a primary basis.

695A *Additional allocation:* in Austria, Italy, the United Kingdom and Swaziland, the band 790–862 MHz is also allocated to the land mobile service on a secondary basis.

696 *Alternative allocation:* In Greece, Italy, Morocco and Tunisia, the band 790–838 MHz is allocated to the broadcasting service on a primary basis.

697 *Additional allocation:* In the Federal Republic of Germany, Burkina Faso, Cameroon, Côte d'Ivoire, Denmark, Egypt, Finland, Israel, Kenya, Libya, Liechtenstein, Monaco, Norway, the Netherlands, Portugal, Sweden, Switzerland and Yugoslavia, the band 790–830 MHz, and in these same countries and in Spain, France, Malta, the Gabonese Republic and Syria, the band 830–862 MHz, are also allocated to the mobile, except aeronautical mobile, service on a primary basis. However, stations of the mobile service in the countries mentioned in connection with each band referred to in this footnote shall not cause harmful interference to, or claim protection from, stations of services operating in accordance with the Table in countries other than those mentioned in connection with this band.

700 *Additional allocation:* in Region 2, the band 806–890 MHz is also allocated to the mobile-satellite service on a primary basis. The use of this service is intended for operation within national boundaries and subject to agreement obtained under the procedure set forth in Article 14.

700A *Additional allocation:* in Canada, the United States and Mexico, the bands 849–851 MHz and 894–896 MHz are also allocated to the aeronautical mobile service on a primary basis, for public correspondence with air-

craft. The use of the band 849–851 MHz is limited to transmissions from aeronautical stations and the use of the band 894–896 MHz is limited to transmissions from aircraft stations.

700B *Additional allocation:* in Belarus, the Russian Federation and Ukraine, the bands 806–840 MHz (Earth-to-space) and 856–890 MHz (space-to-Earth) are also allocated to the mobile-satellite, except aeronautical mobile-satellite (R) service. The use of these bands by this service shall not cause harmful interference to, or claim protection from, services in other countries operating in accordance with the Table of Frequency Allocations and is subject to special agreements between the administrations concerned.

701 *Additional allocation:* in Region 3, the bands 806–890 MHz and 942–960 MHz are also allocated to the mobile-satellite, except aeronautical mobile-satellite (R), service on a primary basis. The use of this service is limited to operation within national boundaries and subject to agreement obtained under the procedure set forth in Article 14. In seeking such agreement, appropriate protection shall be afforded to services operating in accordance with the Table, to ensure that no harmful interference is caused to such services.

702 *Alternative allocation:* In Italy, the band 838–854 MHz is allocated to the broadcasting service on a primary basis as from 1 January 1995. 1703 In Region 1, in the band 862–960 MHz, stations of the broadcasting service shall be operated only in the African Broadcasting Area (see Nos. 400 to 403) excluding Algeria, Egypt, Spain, Libya and Morocco, subject to agreement obtained under the procedure set forth in Article 14.

703 In region 1, in the band 862–960 MHz, stations of the broadcasting service shall be operated only in the African Broadcasting Area (see Nos. 400 to 403) excluding Algeria, Egypt, Spain, Libya and Morocco, subject to agreement obtained under the procedure set forth in Article 14.

704 *Additional allocation:* In Bulgaria, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 862–960 MHz is also allocated to the aeronautical radionavigation service on a permitted basis until 1 January 1998. Up to this date, the aeronautical radionavigation service may use the band, subject to agreement obtained under the procedure set forth in Article 14. After this date, the aeronautical radionavigation service may continue to operate on a secondary basis.

704A *Additional allocation:* in Brazil, Canada and the United States of America, the band 890–896 MHz is also allocated to the mobile-satellite service on a primary basis. The use of this service is intended for operation within national boundaries and subject to agreement obtained under the procedure set

Federal Communications Commission

§2.106

forth in Article 14. In seeking such agreement, appropriate protection shall be afforded to services operating in accordance with the Table.

705 *Different category of service:* In the United States, the allocation of the band 890–942 MHz to the radiolocation service is on a primary basis (see No. 425) and subject to agreement obtained under the procedure set forth in Article 14.

706 *Different category of service:* In Australia, the allocation of the band 890–942 MHz to the radiolocation service is on a primary basis (see No. 425).

707 In Region 2, the band 902–928 MHz (centre frequency 915 MHz) is designated for industrial, scientific and medical (ISM) applications. Radiocommunication service operating within this band must accept harmful interference which may be caused by these applications. ISM equipment operating in this band is subject to the provisions of No. 1815.

707A *Different category of service:* in Chile, the band 903–905 MHz is allocated to the mobile, except aeronautical mobile, service on a primary basis and is subject to agreement obtained under the procedure set forth in Article 14.

709 The band 960–1 215 MHz is reserved on a worldwide basis for the use and development of airborne electronic aids to air navigation and any directly associated ground-based facilities.

710 Use of the radionavigation-satellite service in the band 1 215–1 260 MHz shall be subject to the condition that no harmful interference is caused to the radionavigation service authorized under footnote 712.

711 *Additional allocation:* In Afghanistan, Angola, Saudi Arabia, Bahrain, Bangladesh, Cameroon, China, the United Arab Emirates, Ethiopia, Guinea, Guyana, India, Indonesia, Iran, Iraq, Israel, Japan, Jordan, Kuwait, Lebanon, Libya, Malawi, Morocco, Mozambique, Nepal, Nigeria, Oman, Pakistan, the Philippines, Qatar, Syria, Somalia, Sudan, Sri Lanka, Chad, Thailand, Togo and Yemen (P.D.R. of), the band 1 215–1 300 MHz is also allocated to the fixed and mobile services on a primary basis.

712 *Additional allocation:* In Algeria, the Federal Republic of Germany, Austria, Bahrain, Belgium, Benin, Burundi, Cameroon, China, Denmark, the United Arab Emirates, France, Greece, India, Iran, Iraq, Kenya, Liechtenstein, Luxembourg, Mali, Mauritania, Norway, Oman, Pakistan, the Netherlands, Portugal, Qatar, Senegal, Somalia, Sudan, Sri Lanka, Sweden, Switzerland, Tanzania, Turkey and Yugoslavia, the band 1 215–1 300 MHz is also allocated to the radionavigation service on a primary basis.

712A *Additional allocation:* in Cuba, the band 1215–1300 MHz is also allocated to the radionavigation service on a primary basis

subject to the agreement obtained under the procedure set forth in Article 14.

713 In the bands 1 215–1 300 MHz, 3 100–3 300 MHz, 5 250–5 350 MHz, 8 550–8 650 MHz, 9 500–9 800 MHz and 13.4–14.0 GHz, radiolocation stations installed on spacecraft may also be employed for the earth exploration-satellite and space research services on a secondary basis.

714 *Additional allocation:* In Canada and the United States the bands 1 240–1 300 MHz and 1 350–1 370 MHz are also allocated to the aeronautical radionavigation service on a primary basis.

715 *Additional allocation:* In Indonesia, the band 1 300–1 350 MHz is also allocated to the fixed and mobile services on a primary basis.

716 *Alternative allocation:* In Ireland and the United Kingdom, the band 1 300–1 350 MHz is allocated to the radiolocation service on a primary basis.

717 The use of the bands 1 300–1 350 MHz, 2 700–2 900 MHz and 9 000–9 200 MHz by the aeronautical radionavigation service is restricted to ground-based radars and to associated airborne transponders which transmit only on frequencies in these bands and only when actuated by radars operating in the same band.

718 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the spectral line observations of the radio astronomy service from harmful interference in the band 1 330–1 400 MHz. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

719 In Bulgaria, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the existing installations of the radionavigation service may continue to operate in the band 1 350–1 400 MHz.

720 The bands 1 370–1 400 MHz, 2 640–2 655 MHz, 4 950–4 990 MHz and 15.20–15.35 GHz are also allocated to the space research (passive) and earth exploration-satellite (passive) services on a secondary basis.

721 All emissions in the band 1 400–1 427 MHz are prohibited.

722 In the bands 1 400–1 727 MHz, 101–120 GHz and 197–220 GHz, passive research is being conducted by some countries in a programme for the search for intentional emissions of extra-terrestrial origin.

723 In Region 2, in Australia and Papua New Guinea, the use of the band 1 435–1 535 MHz by the aeronautical mobile service for telemetry has priority over other uses by the mobile service.

723A *Different category of service:* in Cuba, the band 1525–1530 MHz is allocated to the aeronautical mobile service on a primary basis, under the conditions specified in No. 723.

723B Additional allocation: In Belarus, the Russian Federation and Ukraine, the band 1429–1535 MHz is also allocated to the aeronautical mobile service on a primary basis exclusively for the purposes of aeronautical telemetry within the national territory. As of 1 April 2007, the use of the band 1452–1492 MHz is subject to agreement between the administrations concerned.

724 Different category of service: In Afghanistan, Saudi Arabia, Bahrain, Bulgaria, Cameroon, Egypt, The United Arab Emirates, France, Iran, Iraq, Israel, Kuwait, the Lebanon, Morocco, Mongolia, Oman, Poland, Qatar, Syria, the German Democratic Republic, Romania, Czechoslovakia, the U.S.S.R., Yemen and Yugoslavia, the allocation of the band 1525–1530 MHz to the mobile, except aeronautical mobile, service is on a primary basis (see No. 425).

725 *Additional allocation:* In the U.S.S.R., the band 1 525–1 530 MHz is also allocated to the aeronautical mobile service on a primary basis.

726A The bands 1525–1544 MHz, 1545–1559 MHz, 1626.5–1645.5 MHz and 1646.5–1660.5 MHz shall not be used for feeder links of any service. In exceptional circumstances, however, an earth station at a specified fixed point in any of the mobile-satellite services may be authorized by an administration to communicate via space stations using these bands.

726B The use of the bands 1525–1530 MHz, 1533–1544 MHz, 1626.5–1631.5 MHz and 1634.5–1645.5 MHz by the land mobile-satellite service is limited to non-speech low bit-rate data transmissions.

726C Additional allocation: In Argentina, Australia, Brazil, Canada, the United States, Malaysia and Mexico, the band 1530–1544 MHz is allocated to the mobile-satellite (space-to-Earth) service, and the band 1626.5–1645.5 MHz is also allocated to the mobile-satellite (Earth-to-space) service, on a primary basis subject to the following conditions: maritime mobile-satellite distress and safety communications shall have priority access and immediate availability over all other mobile-satellite communications operating under this provision. Communications of mobile-satellite system stations not participating in the global maritime distress and safety system (GMDSS) shall operate on secondary basis to distress and safety communications of stations operating in the GMDSS. Account shall be taken of the priority of safety-related communications in the other mobile-satellite services.

726D The use of the bands 1525–1559 and 1626.5–1660.5 MHz by the mobile-satellite services are subject to the application of the coordination and notification procedures set forth in Resolution 46 (WARC-92). In Regions 1 and 3 in the band 1525–1530 MHz coordination of space stations of the mobile-satellite services with respect to terrestrial services is required only if the power flux-density

produced at the Earth's surface exceeds the limits in No. 2566. In respect of assignments operating in the band 1525–1530 MHz, the provisions of section II, paragraph 2.2 of Resolution 46 (WARC-92) shall also be applied to geostationary transmitting space stations with respect to terrestrial stations.

727 *Additional allocation:* In Afghanistan, Saudi Arabia, Bahrain, Bangladesh, Congo, Egypt, the United Arab Emirates, Ethiopia, Iran, Iraq, Israel, Jordan, Pakistan, Qatar, Sudan, Sri Lanka, Syria, Somalia, Chad, Thailand, Togo, Yemen (P.D.R. of) and Zambia, the bands 1 540–1 645.5 and 1 646.5–1 660 MHz are also allocated to the fixed service on a secondary basis.

727A The use of the band 1544–1545 MHz by the mobile-satellite service (space-to-earth) is limited to distress and safety communications (see Article N 38).

729 Transmissions in the band 1545–1555 MHz from terrestrial aeronautical stations directly to aircraft stations, or between aircraft stations, in the aeronautical mobile (R) service are also authorized when such transmissions are used to extend or supplement the satellite-to-aircraft links.

729A Notwithstanding any other provisions of the Radio Regulations relating to restrictions in the use of the bands allocated to the aeronautical mobile-satellite (R) service for public correspondence, the bands 1545–1555 MHz and 1646.5–1656.5 MHz may be authorized by administrations for public correspondence with aircraft earth stations. Such communications must cease immediately, if necessary, to permit transmission of messages with priority 1 to 6 in Article 51.

730 *Additional allocation:* In the Federal Republic of Germany, Austria, Bulgaria, Cameroon, Guinea, Hungary, Indonesia, Libya, Mali, Mongolia, Nigeria, Poland, the German Democratic Republic, Roumania, Senegal, Czechoslovakia and the U.S.S.R., the bands 1 550–1 645.5 and 1 646.5–1660 MHz are also allocated to the fixed service on a primary basis.

730A In the bands 1555–1559 and 1656.5–1660.5 MHz administrations may also authorize aircraft earth stations and ship earth stations to communicate with space stations in the land mobile-satellite service (see Resolution 208 (Mob-87)).

730B Alternative allocation: In Australia, Canada and Mexico, the band 1555–1559 MHz is allocated to the mobile-satellite (space-to-Earth) service, the band 1656.5–1660 MHz is allocated to the mobile-satellite (Earth-to-space) service, and the band 1660–1660.5 MHz is allocated to the mobile-satellite (Earth-to-space) and the radio astronomy services, on a primary basis.

730C Alternative allocation: In Argentina and the United States, the band 1555–1559 MHz is allocated to the mobile-satellite (space-to-Earth) service, the band 1656.5–1660 MHz is allocated to the mobile-satellite

(Earth-to-space) service, and the band 1660–1660.5 MHz is allocated to the mobile-satellite (Earth-to-space) and radio astronomy services, on a primary basis subject to the following conditions: the aeronautical mobile-satellite (R) service shall have priority access and immediate availability over all other mobile-satellite communications within a network operating under this provision; mobile-satellite systems shall be interoperable with the aeronautical mobile-satellite (R) service; account shall be taken of the priority of safety-related communications in the other mobile-satellite services.

731 *Alternative allocation:* in Sweden, the band 1590–1626.5 MHz is allocated to the aeronautical radionavigation service on a primary basis.

731E The use of the band 1610–1626.5 MHz by the mobile-satellite service (Earth-to-space) and by the radiodetermination-satellite service (Earth-to-space) is subject to the application of the coordination and notification procedures set forth in Resolution 46 (WARC-92). A mobile earth station operating in either of the services in this band shall not produce an e.i.r.p. density in excess of -15 dB(W/4 kHz) in the part of the band used by systems operating in accordance with the provisions of No. 732, unless otherwise agreed by the affected administrations. In the part of the band where such systems are not operating, a value of -3 dB (W/4 kHz) is applicable. Stations of the mobile-satellite service shall not cause harmful interference to, or claim protection from, stations in the aeronautical radionavigation service, stations operating in accordance with the provisions of No. 732 and stations in the fixed service operating in accordance with the provisions of No. 730.

731F The use of the band 1613.8–1626.5 MHz by the mobile-satellite service (space-to-Earth) is subject to the application of the coordination and notification procedures set forth in Resolution 46 (WARC-92).

732 The band 1610–1626.5 MHz is reserved on a worldwide basis for the use and development of airborne electronic aids to air navigation and any directly associated ground-based or satellite-borne facilities. Such satellite use is subject to agreement obtained under the procedure set forth in Article 14.

733 The band 1 610–1 626.5 MHz, 5 000–5 250 MHz and 15.4–15.7 GHz are also allocated to the aeronautical mobile-satellite (R) service on a primary basis. Such use is subject to agreement obtained under the procedure set forth in Article 14.

733A With respect to the radiodetermination-satellite and mobile-satellite services the provisions of No. 953 do not apply in the frequency band 1610–1626.5 MHz.

733B *Different category of service:* in Angola, Australia, Burundi, Cote d'Ivoire, Ethiopia, India, Islamic Republic of Iran, Israel, Italy, Jordan, Kenya, Lebanon, Liberia,

Libya, Madagascar, Mali, Pakistan, Papua New Guinea, Senegal, Sudan, Swaziland, Syria, Tanzania, Thailand, Togo, Zaire and Zambia the allocation of the band 1610–1626.5 MHz to the radiodetermination-satellite service (Earth-to-space) is on a primary basis (see No. 425) subject to agreement obtained under the procedure set forth in Article 14 with other countries not listed in this provision.

733C *Different category of service:* in Venezuela, the allocation to the radiodetermination-satellite service in the band 1610–1626.5 MHz is allocated exclusively to the aeronautical radionavigation service on a secondary basis.

733D *Alternative allocation:* in Cuba, the band 1610–1626.5 MHz is allocated exclusively to the aeronautical radionavigation service on a primary basis.

733E Harmful interference shall not be caused to stations of the radio astronomy service using the band 1610.6–1613.8 MHz by stations of the radiodetermination-satellite and mobile-satellite services. (No. 2904 applies.)

733F In Region 1, the bands 1610–1626.5 MHz (Earth-to-space) and 2483.5–2500 MHz (space-to-Earth) are also allocated to the radiodetermination-satellite service on a secondary basis.

734 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the radio astronomy service in the band 1610.6–1613.8 MHz from harmful interference. Emissions from space or air-borne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

734A Land earth stations and ship earth stations in the mobile-satellite services operating in the bands 1631.5–1634.5 and 1656.5–1660 MHz shall not cause harmful interference to the stations in the fixed service operating in the countries listed in No. 730.

734B The use of the band 1645.5–1646.5 MHz by the mobile satellite service (Earth-to-space) and for inter-satellite links is limited to distress and safety communications (see Article N 38).

735 Transmissions in the band 1646.5–1656.5 MHz from aircraft stations in the aeronautical mobile (R) service directly to terrestrial aeronautical stations, or between aircraft stations, are also authorized when such transmissions are used to extend or supplement the aircraft-to-satellite links.

735A In the band 1675–1710 MHz, stations in the mobile-satellite service shall not cause harmful interference to, nor constrain the development of, the meteorological-satellite and meteorological aids services (see Resolution 213 (WARC-92)) and the use of this band shall be subject to the provisions of Resolution 46 (WARC-92).

736 In making assignments to stations of other services to which the band 1 660–1 670 MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

737 *Different category of service:* In Afghanistan, Saudi Arabia, Bahrain, Benin, Bulgaria, Cameroon, the Central African Republic, the Congo, Cuba, Egypt, the United Arab Emirates, Ethiopia, Hungary, India, Indonesia, Pakistan, Poland, Qatar, Syria, the German Democratic Republic, Singapore, Somalia, Sri Lanka, Chad, Thailand, Czechoslovakia, Tunisia, the U.S.S.R., Yemen A.R., Yemen (P.D.R. of) and Yugoslavia, the allocation of the band 1 660.5–1 668.4 MHz to the fixed and the mobile, except aeronautical mobile, services is on a primary basis until 1 January 1990.

738 *Additional allocation:* In Bangladesh, India, Indonesia, Nigeria, Pakistan, Sri Lanka and Thailand, the band 1 660.5–1 668.4 MHz is also allocated to the meteorological aids service on a secondary basis.

739 In view of the successful detection by radio astronomers of two hydroxyl spectral lines in the region of 1 665 MHz and 1 667 MHz, administrations are urged to give all practicable protection in the band 1 660.5–1 668.4 MHz for future research in radio astronomy, particularly by eliminating air-to-ground transmissions in the meteorological aids service in the band 1 664.4–1 668.4 MHz as soon as practicable.

740 *Additional allocation:* In Afghanistan, Costa Rica, Cuba, India, Iran, Malaysia, Pakistan, Singapore, Sri Lanka and Thailand, the band 1 690–1 700 MHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

740A The bands 1670–1675 MHz and 1800–1805 MHz are intended for use, on a worldwide basis, by administrations wishing to implement aeronautical public correspondence. The use of the band 1670–1675 MHz by stations in the systems for public correspondence with aircraft is limited to transmissions from aeronautical stations and the use of the band 1800–1805 MHz is limited to transmissions from aircraft stations.

741 *Different category of service:* In Saudi Arabia, Austria, Bahrain, Bulgaria, the Congo, Egypt, the United Arab Emirates, Ethiopia, Guinea, Hungary, Iraq, Israel, Jordan, Kenya, Kuwait, Lebanon, Mauritania, Mongolia, Oman, Poland, Qatar, Syria, the German Democratic Republic, Roumania, Somalia, Tanzania, Czechoslovakia, the U.S.S.R., Yemen A.R., Yemen (P.D.R. of) band 1 690–1 700 MHz to the fixed and mobile, except aeronautical mobile, service is on a primary basis (see No. 425).

742 *Additional allocation:* In Australia and Indonesia, the band 1 690–1 700 MHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a secondary basis.

743 *Additional allocation:* In India, Indonesia, Japan and Thailand, the band 1 700–1 710 MHz is also allocated to the space research service (space-to-Earth) on a primary basis.

744 The band 1 718.8–1 722.2 MHz is also allocated to the radio astronomy service on a secondary basis for spectral line observations. In making assignments to stations of other services to which the band is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

745 Subject to agreement obtained under the procedure set forth in Article 14 and having particular regard to tropospheric scatter systems, the band 1 750–1 850 MHz may also be used for space operation (Earth-to-space) and space research (Earth-to-space) services in Region 2, in Afghanistan, Australia, India, Indonesia, Japan and Thailand.

746 *Additional allocation:* In Bulgaria, Cuba, Hungary, Mali, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 1 770–1 790 MHz is also allocated to the meteorological-satellite service on a primary basis, subject to agreement obtained under the procedure set forth in Article 14.

746A The frequency bands 1885–2025 MHz and 2110–2200 MHz are intended for use, on a worldwide basis, by administrations wishing to implement the future public land mobile telecommunication systems (FPLMTS). Such use does not preclude the use of these bands by other services to which these bands are allocated. The frequency bands should be made available for FPLMTS in accordance with Resolution 212 (WARC-92).

746B The use of the bands 1970–2010 MHz and 2160–2200 MHz by the mobile-satellite service shall not commence before 1 January 2005 and is subject to the application of the coordination and notification procedures set forth in Resolution 46 (WARC-92). In the band 2160–2200 MHz coordination of space stations of the mobile-satellite service with respect to terrestrial services is required only if the power flux-density produced at the Earth's surface exceeds the limits in No. 2566. In respect of assignments operating in this band, the provisions of Section II, paragraph 2.2 of Resolution 46 (WARC-92) shall also be applied to geostationary transmitting space stations with respect to terrestrial stations.

746C In the United States of America, the use of the bands 1970–2010 MHz and 2160–2200

Federal Communications Commission

§2.106

MHz by the mobile-satellite service shall not commence before 1 January 1996.

752 The band 2 400–2 500 MHz (centre frequency 2 450 MHz) is designated for industrial, scientific and medical (ISM) applications. Radio services operating within this band must accept harmful interference which may be caused by these applications. ISM equipment operating in this band is subject to the provisions of No. 1815.

753—Different category of service: in France, the band 2450–2500 MHz is allocated on a primary basis to the radiolocation service (see No. 425). Such use is subject to agreement with administrations having service operating or planned to operate in accordance with the Table of Frequency Allocations which may be affected.

753A In respect of the radiodetermination-satellite service in the band 2483.5–2500 MHz, the provisions of No. 953 do not apply.

753B In Region 1, in countries other than those listed in No. 753C, harmful interference shall not be caused to, or protection shall not be claimed from, stations of the radiolocation service by stations of the radiodetermination-satellite service.

753C Different category of service: in Angola, Australia, Bangladesh, Burundi, China, Côte d'Ivoire, Ethiopia, India, the Islamic Republic of Iran, Israel, Italy, Jordan, Kenya, Lebanon, Liberia, Libya, Madagascar, Mali, Pakistan, Papua New Guinea, Senegal, Sudan, Swaziland, Syria, Tanzania, Thailand, Togo, Zaire and Zambia, the allocation of the band 2483.5–2500 MHz to the radiodetermination-satellite service (space-to-Earth) is on a primary basis (see No. 425) subject to agreement obtained under the procedure of Article 14 with other countries not listed in this provision.

753D *Alternative allocation:* in Cuba, the band 2483.5–2500 MHz is allocated only to fixed, mobile and radiolocation services on a primary basis.

753F The use of the band 2483.5–2500 MHz by the mobile-satellite and the radiodetermination-satellite services is subject to the application of the coordination and notification procedures set forth in Resolution 46 (WARC-92). Coordination of space stations of the mobile-satellite and radiodetermination-satellite services with respect to terrestrial services is required only if the power flux-density produced at the Earth's surface exceeds the limits in No. 2566. In respect of assignments operating in this band, the provisions of Section II, paragraph 2.2 of Resolution 46 (WARC-92) shall also be applied to geostationary transmitting space stations with respect to terrestrial stations.

754 Subject to agreement obtained under the procedure set forth in Article 14, the band 2 500–2 535 MHz may also be used in Region 3 for the mobile-satellite (space-to-Earth), except aeronautical mobile-Satellite,

service for operation limited to within national boundaries.

754A *Additional allocation:* subject to agreement obtained under the procedure set forth in Article 14, the band 2500–2516.5 MHz may also be used in India, the Islamic Republic of Iran, Papua New Guinea and Thailand for the radiodetermination-satellite service (space-to-Earth) for operation limited to within national boundaries.

755 *Additional allocation:* In Canada, the band 2 500–2 550 MHz is also allocated to the radiolocation service on a primary basis.

756 *Additional allocation:* In the United Kingdom, the band 2 500–2 600 MHz is also allocated to the radiolocation service on a secondary basis.

757 The use of the band 2 500–2 690 MHz by the broadcasting-satellite service is limited to national and regional systems for community reception and such use shall be subject to agreement obtained under the procedure set forth in Article 14. The power flux-density at the Earth's surface shall not exceed the values given in Nos. 6561 to 6564.

758 *Alternative allocation:* In the Federal Republic of Germany and Greece, the band 2 500–2 690 MHz is allocated to the fixed service on a primary basis.

759 *Alternative allocation:* In Bulgaria and the U.S.S.R., the band 2 500–2 690 MHz is allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

760 In the design of systems in the broadcasting-satellite service in the bands between 2 500–2 690 MHz, administrations are urged to take all necessary steps to protect the radio astronomy service in the band 2 690–2 700 MHz

761 The use of the bands 2 500–2 690 MHz in Region 2 and 2 500–2 535 MHz and 2 655–2 690 MHz in Region 3 by the fixed-satellite service is limited to national and regional systems; such use shall be subject to agreement obtained under the procedure set forth in Article 14, giving particular attention to the broadcasting-satellite service in Region 1. In the direction space-to-Earth, the power flux-density at the Earth's surface shall not exceed the values given in Nos. 2561 to 2564.

762 Administrations shall make all practicable efforts to avoid developing new tropospheric scatter systems in the band 2 500–2 690 MHz.

763 Subject to agreement obtained under the procedure set forth in Article 14, the band 2 500–2 690 MHz may be used for tropospheric scatter systems in Region 1.

764 When planning new tropospheric scatter radio-relay links in the band 2 500–2 690 MHz; all possible measures shall be taken to avoid directing the antennae of these links toward the geostationary-satellite orbit.

765 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the

radio astronomy service from harmful interference in the band 2 655–2 690 MHz. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

766 Subject to agreement obtained under the procedure set forth in Article 14, the band 2 655–2 690 MHz may also be used in Region 3 for the mobile-satellite (Earth-to-space), except aeronautical mobile-satellite, service for operation limited to within national boundaries.

767 *Additional allocation:* In the Federal Republic of Germany and Austria, the band 2 690–2 695 MHz is also allocated to the fixed service on a primary basis. Such use is limited to equipment in operation by 1 January 1985.

768 All emissions in the band 2 690–2 700 MHz are prohibited, except those provided for by Nos. 767 and 769.

769 *Additional allocation:* In Afghanistan, Saudi Arabia, Bahrain, Bulgaria, Cameroon, the Central African Republic, the Congo, the Ivory Coast, Cuba, Egypt, the United Arab Emirates, Ethiopia, Gabon, Guinea, Guinea-Bissau, Hungary, Iran, Iraq, Israel, Lebanon, Malaysia, Malawi, Mali, Morocco, Mauritania, Mongolia, Nigeria, Oman, Pakistan, the Philippines, Poland, Qatar, the Syria, German Democratic Republic, Roumania, Singapore, Somalia, Sri Lanka, Czechoslovakia, Tunisia, Thailand, the U.S.S.R., Yemen A.R., Yemen (P.D.R. of), Yugoslavia, Zaire and Zambia, the band 2 690–2 700 MHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis. Such use is limited to equipment in operation by 1 January 1985.

770 In the band 2 700–2 900 MHz, ground-based radars used for meteorological purposes are authorized to operate on a basis of equality with stations of the aeronautical radionavigation service.

771 *Additional allocation:* In Canada, the band 2 850–2 900 MHz is also allocated to the maritime radionavigation service, on a primary basis, for use by shore-based radars.

772 In the band 2900–3100 MHz, the use of the shipborne interrogator-transponder system (SIT) shall be confined to the sub-band 2930–2950 MHz.

773 The use of the band 2 900–3 100 MHz by the aeronautical radionavigation service is limited to ground based radars.

775A In the bands 2900–3100 MHz and 9300–9500 MHz, the response from radar transponders shall not be capable of being confused with the response from radar beacons (racons) and shall not cause interference for ship or aeronautical radars in the radionavigation service, having regard, however, to No. 347 of these Regulations.

777 *Additional location:* In Bulgaria, Canada, Cuba, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania,

Czechoslovakia and the U.S.S.R., the band 3 100–3 300 MHz is also allocated to the radionavigation service on a primary basis.

778 In making assignments to stations of other service, administrations are urged to take all practicable steps to protect the spectral line observations of the radio astronomy service from harmful interference in the bands 3 260–3 267 MHz, 3 332–3 339 MHz, 3 345.8–3 352.5 MHz and 4 825–4 835 MHz. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

779 *Additional allocation:* In Afghanistan, Saudi Arabia, Bahrain, Bangladesh, China, the Congo, the United Arab Emirates, India, Indonesia, Iran, Iraq, Israel, Japan, Kuwait, Lebanon, Libya, Malaysia, Oman, Pakistan, Qatar, Syria, Singapore, Sri Lanka and Thailand, the band 3 300–3 400 MHz is also allocated to the fixed and mobile services on a primary basis. The countries bordering the Mediterranean shall not claim protection for their fixed and mobile services from the radiolocation service.

780 *Additional location:* In Bulgaria, Cuba, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 3 300–3 400 MHz is also allocated to the radionavigation service on a primary basis.

781 *Additional allocation:* In the Federal Republic of Germany, Israel and the United Kingdom, the band 3 400–3 475 MHz is also allocated to the amateur service on a secondary basis.

782 *Different category of service:* In Austria, the allocation of the band 3 400–3 500 MHz to the radiolocation service is on a primary basis (see No. 425), subject to the agreement of the administrations of the following countries: Hungary, Italy, the German Democratic Republic, Czechoslovakia and Yugoslavia. Such use is limited to ground-based stations. However, this administration is urged to cease operations by 1985. After this date this administration shall take all practicable steps to protect the fixed-satellite service and coordination requirements shall not be imposed on the fixed-satellite service.

783 *Different category of service:* In Indonesia, Japan, Pakistan and Thailand, the allocation of the band 3 400–3 500 MHz to the mobile, except aeronautical mobile, service is on a primary basis (see No. 425).

784 In Regions 2 and 3, in the band 3 400–3 600 MHz the radiolocation service is allocated on a primary basis. However, all administrations operating radiolocation systems in this band are urged to cease operations by 1985. Thereafter, administrations shall take all practicable steps to protect the fixed-satellite service and coordination requirements shall not be imposed on the fixed-satellite service.

Federal Communications Commission

§2.106

785 In Denmark, Norway and the United Kingdom, the fixed, radiolocation and fixed-satellite services operate on a basis of equality of rights in the band 3 400–3 600 MHz. However, these administrations operating radiolocation systems in this band are urged to cease operations by 1985. After this date these administrations shall take all practicable steps to protect the fixed-satellite service and coordination requirements shall not be imposed on the fixed-satellite service.

786 In Japan, in the band 3 620–3 700 MHz, the radiolocation service is excluded.

787 *Additional allocation:* In New Zealand, the band 3 700–3 770 MHz is also allocated to the radiolocation service on a secondary basis.

788 *Additional allocation:* In the Federal Republic of Germany, Denmark, Norway and Sweden, the band 4 200–4 210 MHz is also allocated to the fixed service on a secondary basis.

789 Use of the band 4 200–4 400 MHz by the aeronautical radionavigation service is reserved exclusively for radio altimeters installed on board aircraft and for the associated transponders on the ground. However, passive sensing in the Earth exploration-satellite and space research services may be authorized in this band on a secondary basis (no protection is provided by the radio altimeters).

790 *Additional allocation:* In China, Iran, Libya, the Philippines and Sri Lanka, the band 4 200–4 400 MHz is also allocated to the fixed service on a secondary basis.

791 The standard frequency and time signal-satellite service may be authorized to use the frequency 4 202 MHz for space-to-Earth transmissions and the frequency 6 427 MHz for Earth-to-space transmissions. Such transmissions shall be confined within the limits of ± 2 MHz of these frequencies and shall be subject to agreement obtained under the procedure set forth in Article 14.

792A The use of the bands 4 500–4 800 MHz, 6 725–7 025 MHz, 10.7–10.95 GHz, 11.2–11.45 GHz and 12.75–13.25 GHz by the fixed-satellite service shall be in accordance with the provisions of Appendix 30B.

793 In the bands 4 825–4 835 MHz and 4 950–4 990 MHz, the allocation to the mobile service is restricted to the mobile, except aeronautical mobile, service.

794 *Different category of service:* In Argentina, Australia and Canada, the allocation of the bands 4 825–4 835 MHz and 4 950–4 990 MHz to the radio astronomy service is on a primary basis. In making assignments to stations of other services to which these bands are allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

795 In making assignments to stations of other services to which the band 4 990–5 000 MHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

796 The band 5 000–5 250 MHz is to be used for the operation of the international standard system (microwave landing system) for precision approach and landing. The requirements of this system shall take precedence over other uses of this band.

797 The bands 5 000–5 250 MHz, and 15.4–15.7 GHz are also allocated to the fixed-satellite service and the inter-satellite service, for connection between one or more earth stations at specified fixed points on the Earth and space stations, when these services are used in conjunction with the aeronautical radionavigation and/or aeronautical mobile (R) service. Such use shall be subject to agreement obtained under the procedure set forth in Article 14.

797A *Additional allocation:* in the countries listed in Nos. 733B and 753C, and subject to agreement obtained under the procedure set forth in Article 14, and band 5150–5216 MHz is also allocated to the radiodetermination-satellite service (space-to-Earth) on a primary basis. In Region 2, the band is also allocated to the radiodetermination-satellite service (space-to-Earth) on a primary basis. In regions 1 and 3, except those countries listed in Nos. 733B and 753C, the band is also allocated to the radiodetermination-satellite service (space-to-Earth) on a secondary basis. The use by the radiodetermination-satellite service is limited to feeder links in conjunction with the radiodetermination-satellite service operating in the bands 1610–1626.5 MHz and/or 2483.5–2500 MHz. The total power flux-density at the Earth's surface shall in no case exceed -159 dBW/m² in any 4 kHz band for all angles of arrival.

797B *Additional allocation:* in the Federal Republic of Germany, Austria, Denmark, Spain, France, Finland, Israel, Italy, Jordan, Morocco, Norway, the Netherlands, Pakistan, the United Kingdom, Sweden, Switzerland, Syria and Tunisia, the band 5150–5250 MHz is also allocated to the mobile service, on a primary basis, subject to the agreement obtained under the procedure set forth in Article 14.

798 *Additional allocation:* In Austria, Bulgaria, Hungary, Libya, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 5 250–5 350 MHz is also allocated to the radionavigation service on a primary basis.

799 The use of the band 5 350–5 470 MHz by the aeronautical radionavigation service is

limited to airborne radars and associated airborne beacons.

800 *Additional allocation:* In Afghanistan, Austria, Bulgaria, Hungary, Iran, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 5 470–5 650 MHz is also allocated to the aeronautical radionavigation service on a primary basis.

801 *Additional allocation:* In the United Kingdom, the band 5 470–5 850 MHz is also allocated to the land mobile service on a secondary basis. The power limits specified in Nos. 2502, 2505, 2506 and 2507 shall apply in the band 5 725–5 850 MHz.

802 Between 5 600 MHz and 5 650 MHz, ground-based radars used for meteorological purposes are authorized to operate on a basis of equality with stations of the maritime radionavigation service.

803 *Additional allocation:* In Afghanistan, Saudi Arabia, Bahrain, Bangladesh, Cameroon, Central African Republic, China, Congo, the Republic of Korea, Egypt, the United Arab Emirates, Gabon, Guinea, India, Indonesia, Iran, Iraq, Israel, Japan, Jordan, Kuwait, Lebanon, Libya, Madagascar, Malaysia, Malawi, Malta, Niger, Nigeria, Pakistan, the Philippines, Qatar, Syria, Singapore, Sri Lanka, Tanzania, Chad, Thailand and Yemen (P.D.R. of) the band 5 650–5 850 MHz is also allocated to the fixed and mobile services on a primary basis.

804 *Different category of service:* In Bulgaria, Cuba, Hungary, Mongolia, Poland, the German Democratic Republic, Czechoslovakia and the U.S.S.R., the allocation of the band 5 670–5 725 MHz to the space research service is on a primary basis (see No. 425).

805 *Additional allocation:* In Bulgaria, Cuba, Hungary, Mongolia, Poland, the German Democratic Republic, Czechoslovakia and the U.S.S.R., the band 5 670–5 850 MHz is also allocated to the fixed service on a primary basis.

806 The band 5 725–5 875 MHz (centre frequency 5 800 MHz) is designated for industrial, scientific and medical (ISM) applications. Radiocommunication services operating within this band must accept harmful interference which may be caused by these applications. ISM equipment operating in this band is subject to the provisions of No. 1815.

807 *Additional allocation:* In the Federal Republic of Germany, the band 5 755–5 850 MHz is also allocated to the fixed service on a primary basis.

808 The band 5 830–5 850 MHz is also allocated to the amateur-satellite service (space-to-Earth) on a secondary basis.

809 In the band 6 425–7 075 MHz, passive microwave sensor measurements are carried out over the oceans. In the band 7 075–7 250 MHz, passive microwave sensor measurements are carried out. Administrations should bear in mind the needs of the earth

exploration-satellite (passive) and space research (passive) services in their future planning of this band.

810 Subject to agreement obtained under the procedure set forth in Article 14, in Region 2, the band 7 125–7 155 MHz may be used for Earth-to-space transmissions in the space operation service.

811 Subject to agreement obtained under the procedure set forth in Article 14, the band 7 145–7 235 MHz may be used for Earth-to-space transmissions in the space research service. The use of the band 7 145–7 190 MHz is restricted to deep space; no emissions to deep space shall be effected in the band 7 190–7 235 MHz.

812 The bands 7 250–7 375 MHz (space-to-Earth) and 7 900–8 025 MHz (Earth-to-space) may also be used by the mobile-satellite service. The use of these bands by this service shall be subject to agreement obtained under the procedure set forth in Article 14.

813 In the band 8 025–8 400 MHz the power flux-density limits specified in No. 2570 shall apply in Regions 1 and 3 to the earth exploration-satellite service.

814 In Region 2, aircraft stations are not permitted to transmit in the band 8 025–8 400 MHz.

815 Subject to agreement obtained under the procedure set forth in Article 14, the band 8 025–8 400 MHz may be used for the earth exploration-satellite service (space-to-Earth) in Bangladesh, Benin, Cameroon, China, the Central African Republic, the Ivory Coast, Egypt, France, Guinea, Upper Volta, India, Iran, Israel, Italy, Japan, Kenya, Libya, Mali, Niger, Pakistan, Senegal, Somalia, Sudan, Sweden, Tanzania, Zaire and Zambia, on a primary basis.

816 In the space research service, the use of the band 8 400–8 450 MHz is limited to deep space.

817 *Different category of service:* In Belgium, Israel, Luxembourg, Malaysia, Singapore and Sri Lanka, the allocation of the band 8 400–8 500 MHz to the space research service is on a secondary basis (see No. 424).

818 *Alternative allocation:* In the United Kingdom, the band 8 400–8 500 MHz is allocated to the radiolocation and space research services on a primary basis.

819 *Additional allocation:* In Saudi Arabia, Bahrain, Bangladesh, Burundi, Cameroon, China, the Congo, Costa Rica, Egypt, the United Arab Emirates, Gabon, Guinea, Guyana, Indonesia, Iran, Iraq, Israel, Jamaica, Kuwait, Libya, Malaysia, Mali, Morocco, Mauritania, Nepal, Niger, Nigeria, Oman, Pakistan, Qatar, Syria, Senegal, Singapore, Somalia, Sri Lanka, Tanzania, Chad, Thailand, Togo and Tunisia, the band 8 500–8 750 MHz is also allocated to the fixed and mobile services on a primary basis.

820 *Additional allocation:* In Bulgaria, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia

Federal Communications Commission

§2.106

and the U.S.S.R., the band 8 500–8 750 MHz is also allocated to the land mobile and radio-navigation services on a primary basis.

821 The use of the band 8 750–8 850 MHz by the aeronautical radionavigation service is limited to airborne doppler navigation aids on a centre frequency of 8 800 MHz.

822 *Additional allocation:* In Algeria, the Federal Republic of Germany, Bahrain, Belgium, China, the United Arab Emirates, France, Greece, Indonesia, Iran, Libya, the Netherlands, Qatar, Sudan and Thailand, the bands 8 825–8 850 MHz and 9 000–9 200 MHz are also allocated to the maritime radio-navigation service, on a primary basis, for use by shore-based radars only.

823 In the bands 8 850–9 000 MHz and 9 200–9 225 MHz, the maritime radionavigation service is limited to shore-based radars.

824 *Additional allocation:* In Austria, Bulgaria, Cuba, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., bands 8 850–9 000 MHz and 9 200–9 300 MHz are also allocated to the radionavigation service on a primary basis.

824A In the band 9200–9500 MHz, search and rescue transponders (SART) may be used, having due regard to the appropriate CCIR Recommendation (see also Article N 38).

825 The use of the band 9 300–9 500 MHz by the aeronautical radionavigation service is limited to airborne weather radars and ground-based radars. In addition, ground-based radar beacons in the aeronautical radionavigation service are permitted in the band 9 300–9 320 MHz on condition that harmful interference is not caused to the maritime radionavigation service. In the band 9 300–9 500 MHz, ground-based radars used for meteorological purposes have priority over other radiolocation devices.

825A In the band 9300–9320 MHz in the radionavigation service, the use of shipborne radars, other than those existing on 1 January 1976, is not permitted until 1 January 2001.

826 *Different category of service:* In Afghanistan, Saudi Arabia, Austria, Bahrain, Bangladesh, Cameroon, the Republic of Korea, Egypt, the United Arab Emirates, Ethiopia, Guyana, India, Indonesia, Iran, Iraq, Israel, Jamaica, Japan, Jordan, Kuwait, the Lebanon, Liberia, Malaysia, Nigeria, Pakistan, Qatar, Singapore, Somalia, Sudan, Sri Lanka, Sweden, Thailand, Trinidad and Tobago, and Yemen (P.D.R. of), the allocation of the band 9 800–10 000 MHz to the fixed service is on a primary basis (see No. 425).

827 *Additional allocation:* In Bulgaria, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the band 9 800–10 000 MHz is also allocated to the radionavigation service on a primary basis.

828 The band 9 975–10 025 MHz is also allocated to the meteorological-satellite service on a secondary basis for use by weather radars.

829 *Additional allocation:* In Costa Rica, Ecuador, Guatemala, and Honduras, the band 10–10.45 GHz is also allocated to the fixed and mobile services on a primary basis.

830 *Additional allocation:* In the Federal Republic of Germany, Angola, China, Ecuador, Spain, Japan, Kenya, Morocco, Nigeria, Sweden, Tanzania and Thailand, the band 10.45–10.5 GHz is also allocated to the fixed and mobile services on a primary basis.

831 In the band 10.6–10.68 GHz, the fixed and mobile, except aeronautical mobile, services shall be limited to a maximum equivalent isotropically radiated power of 40 dBW and the power delivered to the antenna shall not exceed –3 dBW. These limits may be exceeded subject to agreement obtained under the procedure set forth in Article 14. However, in Afghanistan, Saudi Arabia, Bahrain, Bangladesh, China, the United Arab Emirates, Finland, India, Indonesia, Iran, Iraq, Japan, Kuwait, Lebanon, Nigeria, Pakistan, the Philippines, Qatar, Syria and the U.S.S.R., the restrictions on the fixed and mobile, except aeronautical mobile, services are not applicable.

832 In making assignments to stations of other services to which the band 10.6–10.68 GHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

833 All emissions in the band 10.68–10.7 GHz are prohibited except for those provided for by No. 834.

834 *Additional allocation:* In Saudi Arabia, Bahrain, Bulgaria, Cameroon, China, Colombia, the Republic of Korea, Costa Rica, Cuba, Egypt, the United Arab Emirates, Ecuador, Hungary, Iran, Iraq, Israel, Japan, Kuwait, Lebanon, Mongolia, Pakistan, Poland, Qatar, the German Democratic Republic, Roumania, Czechoslovakia, the U.S.S.R. and Yugoslavia, the band 10.68–10.7 GHz is also allocated to the fixed and mobile, except aeronautical mobile, service on a primary basis. Such use is limited to equipment in operation by 1 January 1985.

836 In Region 2, in the band 11.7–12.2 GHz, transponders on space stations in the fixed-satellite service may be used additionally for transmissions in the broadcasting-satellite service, provided that such transmissions do not have a maximum e.i.r.p. greater than 53 dBW per television channel and do not cause greater interference or require more protection from interference than the coordinated fixed-satellite service frequency assignments. With respect to the space services,

this band shall be used principally for the fixed-satellite service.

837 Different category of service: in Canada, Mexico and the United States, the allocation of the band 11.7–12.1 GHz to the fixed service is on a secondary basis (see No. 424).

838 In the band 11.7–12.5 GHz in Regions 1 and 3 the fixed, fixed-satellite, mobile, except aeronautical mobile, and broadcasting services, in accordance with their respective allocations, shall not cause harmful interference to broadcasting-satellite stations operating in accordance with the provisions of Appendix 30.

839 The use of the bands 11.7–12.2 GHz by the fixed-satellite service in Region 2 and 12.2–12.7 GHz by the broadcasting-satellite service in Region 2 is limited to national and subregional systems. The use of the band 11.7–12.2 GHz by the fixed-satellite service in Region 2 is subject to previous agreement between the administrations concerned and those having services, operating or planned or operate in accordance with the table, which may be affected (see Articles 11, 13 and 14). For the use of the band 12.2–12.7 GHz by the broadcasting-satellite service in Region 2, see Article 15.

842 *Additional allocation:* the band 12.1–12.2 GHz in Brazil and Peru, is also allocated to the fixed service on a primary basis.

844 In Region 2, in the band 12.2–12.7 GHz, existing and future terrestrial radiocommunication services shall not cause harmful interference to the space services operating in conformity with the Broadcasting-Satellite Plan for Region 2 contained in Appendix 30 (Orb-85).

845 In Region 3 the band 12.2–12.5 GHz is also allocated to the fixed-satellite (space to Earth) service limited to national and subregional systems. The power flux-density limits in No. 2574 shall apply to this frequency band. The introduction of the service in relation to the broadcasting-satellite service in Region 1 shall follow the procedures specified in Article 7 of Appendix 30 with the applicable frequency band extended to cover 12.2–12.5 GHz.

846 In Region 2, in the band 12.2–12.7 GHz, assignments to stations of the broadcasting-satellite service in the Plan for Region 2 contained in Appendix 30 (Orb-85) may also be used for transmissions in the fixed-satellite service (space-to-Earth), provided that such transmissions do not cause more interference or require more protection from interference than the broadcasting-satellite service transmissions operating in conformity with the Region 2 Plan. With respect to the space services, this band shall be used principally for the broadcasting-satellite service.

847 The broadcasting-satellite service in the band 12.5–12.75 GHz in Region 3 is limited to community reception with a power flux-density not exceeding -111 dB(W/m²) as de-

fined in Annex 5 of Appendix 30 (Orb-85). See also Resolution 34.

848 *Additional allocation:* In Algeria, Angola, Saudi Arabia, Bahrain, Cameroon, the Central African Republic, the Congo, the Ivory Coast, Egypt, the United Arab Emirates, Ethiopia, Gabon, Ghana, Guinea, Iraq, Israel, Jordan, Kenya, Kuwait, Lebanon, Libya, Madagascar, Mali, Morocco, Mongolia, Niger, Nigeria, Qatar, Syria, Senegal, Somalia, Sudan, Chad, Togo, Yemen (P.D.R. of) and Zaire, the band 12.5–12.75 GHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a primary basis.

849 *Additional allocation:* In the Federal Republic of Germany, Belgium, Denmark, Spain, Finland, France, Greece, Liechtenstein, Luxembourg, Monaco, Norway, Uganda, the Netherlands, Portugal, Roumania, Sweden, Switzerland, Tanzania, Tunisia and Yugoslavia, the band 12.5–12.75 GHz is also allocated to the fixed and mobile, except aeronautical mobile, services on a secondary basis.

850 *Additional allocation:* In Austria, Bulgaria, Hungary, Poland, the German Democratic Republic, Czechoslovakia and the U.S.S.R., the band 12.5–12.75 GHz is also allocated to the fixed service and the mobile, except aeronautical mobile, service on a primary basis. However, stations in these services shall not cause harmful interference to fixed-satellite earth stations of countries in Region 1 other than those mentioned in this footnote. Coordination of these earth stations is not required with stations of the fixed and mobile services of the countries mentioned in this footnote.

863 The use of the band 14.5–14.8 GHz by the fixed-satellite service (Earth-to-space) is limited to feeder links for the broadcasting-satellite service. This use is reserved for countries outside Europe.

864 All emissions in the band 15.35–15.4 GHz are prohibited, except those provided for by No. 865.

865 *Additional allocation:* In Afghanistan, Saudi Arabia, Bahrain, Cameroon, Egypt, the United Arab Emirates, Guinea, Pakistan, Iran, Iraq, Israel, Kuwait, Lebanon, Libya, Qatar, Syria, Somalia and Yugoslavia, the band 15.35–15.4 GHz is also allocated to the fixed and mobile services on a secondary basis.

866 *Additional allocation:* In Afghanistan, Algeria, Angola, Saudi Arabia, Austria, Bahrain, Bangladesh, Cameroon, Costa Rica, Egypt, El Salvador, the United Arab Emirates, Finland, Guatemala, India, Indonesia, Iran, Kuwait, Libya, Malaysia, Malawi, Malta, Morocco, Mozambique, Nepal, Nicaragua, Oman, Pakistan, Qatar, Singapore, Somalia, Sudan, Sri Lanka, Sweden, Tanzania, Chad, Thailand, Yemen (P.D.R. of) and

Yugoslavia, the band 15.7–17.3 GHz is also allocated to the fixed and mobile services on a primary basis.

867 *Additional allocation:* In Israel, the band 15.7–17.3 GHz is also allocated to the fixed and mobile services on a primary basis. These services shall not claim protection from, or cause harmful interference to services operating in accordance with the Table in countries other than those included in 866.

868 *Additional allocation:* in Afghanistan, Algeria, the Federal Republic of Germany, Angola, Saudi Arabia, Austria, Bahrain, Bangladesh, Cameroon, Costa Rica, El Salvador, the United Arab Emirates, Finland, Guatemala, Honduras, India, Indonesia, the Islamic Republic of Iran, Iraq, Israel, Japan, Kuwait, Libya, Nepal, Nicaragua, Oman, Pakistan, Qatar, Sudan, Sri Lanka, Sweden, Thailand, and Yugoslavia, the band 17.3–17.7 GHz is also allocated to the fixed and mobile services on a secondary basis. The power limits given in Nos. 2505 and 2508 shall apply.

869 The use of the band 17.3–18.1 GHz by the fixed-satellite service (Earth-to-space) is limited to feeder links for the broadcasting-satellite service. For the use of the band 17.3–17.8 GHz in Region 2 by the feeder links for the broadcasting-satellite service in the band 12.2–12.7 GHz, see Article 15A.

870 The band 18.1–18.3 GHz is also allocated to the meteorological-satellite service (Earth-to-space) on a primary basis. Its use is limited to geostationary satellites and shall be in accordance with the provisions of No. 2578.

871 In making assignments to stations in the fixed and mobile services, administrations are invited to take account of passive sensors in the earth-exploration satellite and space research services operating in the band 18.6–18.8 GHz. In this band, administrations should endeavor to limit as far as possible both the power delivered by the transmitter to the antenna and the e.i.r.p. in order to reduce the risk of interference to passive sensors to the minimum.

872 In assigning frequencies to stations in the fixed-satellite service in the direction (space-to-Earth), administrations are requested to limit as far as practicable the power flux-density at the Earth's surface in the band 18.6–18.8 GHz, in order to reduce the risk of interference to passive sensors in the earth exploration-satellite and space research services.

873 *Additional allocation:* in Afghanistan, Algeria, Angola, Saudi Arabia, Bahrain, Bangladesh, Brazil, Brunei Darussalam, Cameroon, China, the Congo, the Republic of Korea, Costa Rica, Egypt, the United Arab Emirates, Gabon, Guatemala, Guinea, India, Indonesia, Iran, Iraq, Israel, Japan, Jordan, Kenya, Kuwait, Lebanon, Malaysia, Mali, Morocco, Mauritania, Nepal, Niger, Nigeria, Oman, Pakistan, the Philippines, Qatar, Syria, Singapore, Somalia, Sudan, Sri

Lanka, Tanzania, Chad, Thailand, Togo, Tunisia, and Zaire, the band 19.7–21.2 GHz is also allocated to the fixed and mobile services on a primary basis. This additional use shall not impose any limitation on the power flux-density of space stations in the fixed-satellite service in the band 19.7–21.2 GHz and of space stations in the mobile-satellite service in the band 19.7–20.2 GHz where such allocation to the mobile-satellite service is on a primary basis in the latter band.

873A In order to facilitate interregional coordination between networks in the mobile-satellite and fixed-satellite services, carriers in the mobile-satellite service that are most susceptible to interference shall, to the extent practicable, be located in the higher parts of the bands 19.7–20.2 GHz and 29.5–30 GHz.

873B In the bands 19.7–20.2 GHz and 29.5–30 GHz in Region 2, and in the bands 20.1–20.2 GHz and 29.9–30 GHz in Regions 1 and 3, networks which are both in the fixed-satellite service and in the mobile-satellite service may include links between earth stations at specified or unspecified points or while in motion, through one or more satellites for point-to-point and point-to-multipoint communications.

873C In the bands 19.7–20.2 GHz and 29.5–30 GHz, the provisions of No. 953 do not apply with respect to the mobile-satellite service.

873D The allocation to the mobile-satellite service is intended for use by networks which use narrow spot-beam antennas and other advanced technology at the space stations. Administrations operating systems in the mobile-satellite service in the band 19.7–20.1 GHz in Region 2 and in the band 20.1–20.2 GHz shall take all practicable steps to ensure the continued availability of these bands for administrations operating fixed and mobile systems in accordance with the provisions of No. 873.

873E The use of the bands 19.7–20.1 GHz and 29.5–29.9 GHz by the mobile-satellite service in Region 2 is limited to satellite networks which are both in the fixed-satellite service and in the mobile-satellite service as described in No. 873B.

874 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the spectral line observations of the radio astronomy service in the band 22.01–22.21 GHz from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see also Nos. 343 and 344 and Article 36).

875 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference in the band 22.21–22.5 GHz. Emissions from space or airborne stations can be particularly serious sources of interference to

the radio astronomy service (see also Nos. 343 and 344 and Article 36).

876 The use of the band 22.21–22.5 GHz by the earth exploration-satellite (passive) and space research (passive) services shall not impose constraints upon the fixed and mobile, except aeronautical mobile services.

879 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the spectral line observations of the radio astronomy service in the bands 22.81–22.86 GHz and 23.07–23.12 GHz from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

880 All emissions in the band 23.6–24 GHz are prohibited.

881 The band 24–24.25 GHz (centre frequency 24.125 GHz) is designated for industrial, scientific and medical (ISM) applications. Radiocommunication services operating within this band must accept harmful interference which may be caused by these applications. ISM equipment operating in this band is subject to the provisions of No. 1815.

881A–Use of the 25.25–27.5 GHz band by the inter-satellite service is limited to space research and Earth exploration-satellite applications, and also transmissions of data originating from industrial and medical activities in space.

881B–Space services using non-geostationary satellites operating in the inter-satellite service in the band 27–27.5 GHz are exempt from the provisions of No. 2613.

882 The band 29.95–30 GHz may be used for space-to-space links in the earth exploration-satellite service for telemetry, tracking, and control purposes, on a secondary basis.

882A Additional allocation: the bands 27.500–27.501 GHz and 29.999–30.000 GHz are also allocated to the fixed-satellite service (space-to-Earth) on a primary basis for the beacon transmissions intended for up link power control.

Such space-to-Earth transmissions shall not exceed an equivalent isotropically radiated power (e.i.r.p.) of +10 dBW in the direction of adjacent satellites on the geostationary-satellite orbit. In the band 27.500–27.501 GHz, such space-to-Earth transmissions shall not produce a power flux-density in excess of the values specified in No. 2578 on the Earth's surface.

882B Additional allocation: the band 27.501–29.999 GHz is also allocated to the fixed-satellite service (space-to-Earth) on a secondary basis for beacon transmissions intended for up link power control.

882C In the band 28.5–30 GHz, the earth exploration-satellite service is limited to the transfer of data between stations and not to the primary collection of information by means of active or passive sensors.

882D The band 27.5–30 GHz may be used by the fixed-satellite service (Earth-to-space) for the provision of feeder links for the broadcasting-satellite service.

882E The inter-satellite service shall not claim protection from harmful interference from airport surface detection equipment stations of the radionavigation service.

882F Additional allocation: in Japan, the band 24.65–25.25 GHz is also allocated to the radionavigation service on a primary basis until 2008.

883 Additional allocation: in Afghanistan, Algeria, Saudi Arabia, Bahrain, Bangladesh, Brunei Darussalam, Cameroon, China, the Congo, the Republic of Korea, Egypt, the United Arab Emirates, Ethiopia, Guinea, India, Indonesia, Iran, Iraq, Israel, Japan, Jordan, Kenya, Kuwait, Lebanon, Malaysia, Mali, Morocco, Mauritania, Nepal, Niger, Pakistan, Qatar, Syria, Singapore, Somalia, Sudan, Sri Lanka, Chad, and Thailand, the band 29.5–31 GHz is also allocated to the fixed and mobile services on a secondary basis. The power limits specified in Nos. 2505 and 2508 shall apply.

884 In the band 31–31.3 GHz the power flux-density limits specified in No. 2582 shall apply to the space research service.

885 *Different category of service:* In Bulgaria, Cuba, Hungary, Mongolia, Poland, the German Democratic Republic, Czechoslovakia and the U.S.S.R., the allocation of the band 31–31.3 GHz to the space research service is on a primary basis (see No. 425).

886 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference in the band 31.2–31.3 GHz. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

887 All emissions in the band 31.3–31.5 GHz are prohibited.

888 In Regions 1 and 3, in making assignments to stations of other services to which the band 31.5–31.8 GHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

In Region 2, all emissions in the band 31.5–31.8 GHz are prohibited.

889 *Different category of service:* In Bulgaria, Egypt, Hungary, Mongolia, Poland, the German Democratic Republic, Roumania, Czechoslovakia and the U.S.S.R., the allocation of the band 31.5–31.8 GHz to the fixed and mobile, except aeronautical mobile, services is on a primary basis (see No. 425).

Federal Communications Commission

§2.106

892 Subject to agreement obtained under the procedure set forth in Article 14, the band 31.8–33.8 GHz may also be used in Japan for space-to-Earth transmissions in the fixed-satellite service up to 31 December 1990.

893 In designing systems for the inter-satellite and radionavigation services in the band 32–33 GHz, administrations shall take all necessary measures to prevent harmful interference between these two services, bearing in mind the safety aspects of the radionavigation service (see Recommendation 707).

894 *Additional allocation:* In Afghanistan, Saudi Arabia, Bahrain, Bangladesh, Egypt, the United Arab Emirates, Spain, Finland, Gabon, Guinea, Indonesia, Iran, Iraq, Israel, Kenya, Kuwait, Lebanon, Libya, Malaysia, Malawi, Mali, Malta, Morocco, Mauritania, Nepal, Niger, Nigeria, Oman, Pakistan, the Philippines, Qatar, Syria, Senegal, Singapore, Somalia, Sudan, Sri Lanka, Sweden, Tanzania, Thailand, Togo, Tunisia, Yemen A.R. and Zaire, the band 33.4–36 GHz is also allocated to the fixed and mobile services on a primary basis.

895 *Different category of service:* In Australia, Spain and the United States, the allocation of the band 34.2–34.7 GHz to the space research (deep space) (Earth-to-space) service is on a primary basis (see No. 425).

896 *Different category of service:* In Bulgaria, Cuba, Hungary, Poland, Mongolia, the German Democratic Republic, Czechoslovakia and the U.S.S.R., the allocation of the band 34.2–35.2 GHz to the space research service is on a primary basis (see No. 425).

897 Radars located on spacecraft may be operated on a primary basis in the band 35.5–35.6 GHz.

898 In making assignments to stations of other services, administrations are urged to take all practicable steps to protect the spectral line observations of 36.43–36.5 GHz from harmful interference. Emission from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

899 Subject to agreement obtained under the procedure set forth in Article 14, the band 37–39 GHz may also be used in Japan for Earth-to-space transmissions in the fixed-satellite service up to 31 December 1990.

900 In making assignments to stations of other services to which the band 42.5–43.5 GHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference, especially in the bands 42.77–42.87 GHz, 43.07–43.17 GHz, and 43.37–43.47 GHz, which are used for spectral line observations of silicon monoxide. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astron-

omy service (see Nos. 343 and 344 and Article 36).

901 The allocation of the spectrum for the fixed-satellite service in the bands 42.5–43.5 GHz and 47.2–50.2 GHz for Earth-to-space transmission is greater than that in the band 37.5–39.5 GHz for space-to-Earth transmission in order to accommodate feeder links to broadcasting satellites. Administrations are urged to take all practicable steps to reserve the band 47.2–49.2 GHz for feeder links for the broadcasting-satellite service operating in the band 40.5–42.5 GHz.

902 In the bands 43.5–47 GHz, 66–71 GHz, 95–100 GHz, 134–142 GHz, 190–200 GHz and 252–265 GHz, stations in the land mobile service may be operated subject to not causing harmful interference to the space radiocommunication services to which these bands are allocated (see No. 435).

903 In the bands 43.5–47 GHz, 66–71 GHz, 95–100 GHz, 134–142 GHz, 190–200 GHz and 252–265 GHz, satellite links connecting land stations at specified fixed points are also authorized when used in conjunction with the mobile-satellite service or the radionavigation-satellite service.

904 The bands 48.94–49.04 GHz and 97.88–98.08 GHz are also allocated to the radio astronomy service on a primary basis for spectral line observations. In making assignments to stations of other services to which these bands are allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

905 In the band 48.94–49.04 GHz, all emissions from airborne stations are prohibited.

906 In the bands 51.4–54.25 GHz, 58.2–59 GHz, 64–65 GHz and 72.77–72.91 GHz, radio astronomy observations may be carried out under national arrangements. Administrations are urged to take all practicable steps to protect radio astronomy observations in these bands from harmful interference.

907 In the bands 51.4–54.25 GHz, 58.2–59 GHz, 64–65 GHz, 86–92 GHz, 105–116 GHz and 217–231 GHz, all emissions are prohibited.

908 *Additional allocation:* In the Federal Republic of Germany, Japan and the United Kingdom, the band 54.25–58.2 GHz is also allocated to the radiolocation service on a primary basis.

909 In the bands 54.25–58.2 GHz 59–64 GHz, 116–134 GHz, 170–182 GHz and 185–190 GHz, stations in the aeronautical mobile service may be operated subject to not causing harmful interference to the inter-satellite service (see No. 435).

910 In the bands 59–64 GHz and 126–134 GHz, airborne radars in the radiolocation

service may be operated subject to not causing harmful interference to the inter-satellite service (see No. 435).

911 The band 61–61.5 GHz (centre frequency 61.25 GHz) is designated for industrial, scientific and medical (ISM) applications. The use of this frequency band for ISM applications shall be subject to special authorization by the administrations concerned in agreement with other administrations whose radiocommunication services might be affected. In applying this provision administrations shall have due regard to the latest CCIR Recommendations.

912 In the band 78–79 GHz, radars located on space stations may be operated on a primary basis in the earth exploration-satellite service and in the space research service.

913 In the band 84–86 GHz, stations in the fixed, mobile and broadcasting services shall not cause harmful interference to broadcasting-satellite stations operating in accordance with the decisions of the appropriate frequency assignment planning conference for the broadcasting-satellite service.

914 The band 93.07–93.27 GHz is also used by the radio astronomy service for spectral line observations. In making assignments to stations of the services to which this band is allocated, administrations are urged to take all practicable steps to protect radio astronomy observations from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

915 The band 119.98–120.02 GHz is also allocated to the amateur service on a secondary basis.

916 The band 122–123 GHz (centre frequency 122.5 GHz) is designated for industrial, scientific and medical (ISM) applications. The use of this frequency band for ISM applications shall be subject to special authorization by the administration concerned in agreement with other administrations whose radiocommunication services might be affected. In applying this provision administrations shall have due regard to the latest CCIR Recommendations.

917 In the bands 140.69–140.98 GHz all emissions from airborne stations, and from space stations in the space-to-Earth direction, are prohibited.

918 The band 140.69–140.98 GHz, 144.68–144.98 GHz, 145.45–145.75 GHz and 146.82–147.12 GHz are also allocated to the radio astronomy service on a primary basis for spectral line observations. In making assignments to stations of other services to which the bands are allocated, administrations are urged to take all practicable steps to protect the radio astronomy service (see Nos. 343 and 344 and Article 36).

919 The bands 150–151 GHz, 174.42–175.02 GHz, 177–177.4 GHz, 178.2–178.6 GHz, 181–181.46 GHz and 186.2–186.6 GHz are also allocated to

the radio astronomy service on a secondary basis for spectral line observation. In making assignments to stations of other services to which these bands are allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

920 *Additional allocation:* In the United Kingdom the band 182–185 GHz is also allocated to the fixed and mobile services on a primary basis.

921 In the band 182–185 GHz all emissions are prohibited except those under the provisions of No. 920.

922 The band 244–246 GHz (centre frequency 245 GHz) is designated for industrial, scientific and medical (ISM) applications. The use of this frequency band for ISM applications shall be subject to special authorization by the administration concerned in agreement with other administrations whose radiocommunication services might be affected. In applying this provision administrations shall have due regard to the latest CCIR Recommendations.

923 The bands 250–251 GHz and 262.24–262.76 GHz are also allocated to the radio astronomy service on a primary basis for spectral line observations. In making assignments to stations of other services to which the band is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343, 344 and Article 36).

924 The band 257.5–258 GHz is also allocated to the radio astronomy service on a secondary basis for spectral line observations. In making assignments to stations of other services to which the band is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343, 344 and Article 36).

925 In the Federal Republic of Germany, Argentina, Spain, France, Finland, India, Italy, the Netherlands and Sweden, the band 261–265 GHz is also allocated to the radio astronomy service on a primary basis. In making assignments to stations of other services to which the band is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference. Emissions from space

Federal Communications Commission

§2.106

or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343 and 344 and Article 36).

926 In making assignments to stations of other services to which the band 265–275 GHz is allocated, administrations are urged to take all practicable steps to protect the radio astronomy service from harmful interference, especially in the bands 265.64–266.16 GHz, 267.34–267.86 GHz and 271.74–272.26 GHz, which are used for spectral line observations. Emissions from space or airborne stations can be particularly serious sources of interference to the radio astronomy service (see Nos. 343, 344 and Article 36).

927 The frequency band 275 GHz–400 GHz may be used by administrations for experimentation with, and development of, various active and passive services. In this band a need has been identified for the following spectral line measurements for passive services:

(a) Radio astronomy service: 278–280 GHz and 343–348 GHz.

(b) Space research service (passive) and earth exploration-satellite service (passive): 275–277 GHz, 300–302 GHz, 324–326 GHz, 345–347 GHz, 363–365 GHz and 379–381 GHz.

Future research in this largely unexplored spectral region may yield additional spectral lines and continuum bands of interest to the passive services. Administrations are urged to take all practicable steps to protect these passive services from harmful interference until the next competent world administrative radio conference.

UNITED STATES (US) FOOTNOTES

(These footnotes, each consisting of the letters US followed by one or more digits, denote stipulations applicable to both Government and non-Government stations.)

US7–In the band 420–450 MHz and within the following areas, the peak envelope power output of a transmitter employed in the amateur service shall not exceed 50 watts, unless expressly authorized by the Commission after mutual agreement, on a case-by-case basis, between the Federal Communications Commission Engineer in Charge at the applicable district office and the military area frequency coordinator at the applicable military base. For areas (e) thru (j), the appropriate military coordinator is located at Peterson AFB, CO.

(a) Those portions of Texas and New Mexico bounded on the south by latitude 31°45′ North, on the east by 104°00′ West, on the north by latitude 34°30′ North, and on the west by longitude 107°30′ West;

(b) The entire State of Florida including the Key West area and the areas enclosed within a 200-mile radius of Patrick Air Force Base, Florida (latitude 28°21′ North, longitude 80°43′ West), and within a 200-mile ra-

dius of Eglin Air Force Base, Florida (latitude 30°30′ North, longitude 86°30′ West);

(c) The entire State of Arizona;

(d) Those portions of California and Nevada south of latitude 37°10′ North, and the areas enclosed within a 200 mile radius of the Pacific Missile Test Center, Point Mugu, California (latitude 34°09′ North, longitude 119°11′ West);

(e) In the State of Massachusetts within a 160-kilometer (100 mile) radius around locations at Otis Air Force Base, Massachusetts (latitude 41°45′ North, longitude 70°32′ West);

(f) In the State of California within a 240-kilometer (150 mile) radius around locations at Beale Air Force Base, California (latitude 39°08′ North, longitude 121°26′ West);

(g) In the State of Alaska within a 160 kilometer (100 mile) radius of Clear, Alaska (latitude 64 degrees, 17 north, longitude 149 degrees 10 west).

(h) In the State of North Dakota within a 160 kilometer (100 mile) radius of Concrete, North Dakota (latitude 48 degrees 43 north, longitude 97 degrees 54 west).

(i) In the States of Alabama, Florida, Georgia and South Carolina within a 200 kilometer (124 mile) radius of Warner Robins Air Force Base, Georgia (latitude 32°38′ North, longitude 83°35′ West).

(j) In the State of Texas within a 200 kilometer (124 mile) radius of Goodfellow Air Force Base, Texas (latitude 31°25′ North, longitude 100°24′ West).

US8 The use of the frequencies 170.475, 171.425, 171.575, and 172.275 MHz east of the Mississippi River, and 170.425, 170.575, 171.475, 172.225 and 172.375 MHz west of the Mississippi River may be authorized to fixed, land and mobile stations operated by non-Federal forest firefighting agencies. In addition, land stations and mobile stations operated by non-Federal conservation agencies, for mobile relay operation only, may be authorized to use the frequency 172.275 MHz east of the Mississippi River and the frequency 171.475 MHz west of the Mississippi River. The use of any of the foregoing nine frequencies shall be on the condition that no harmful interference will be caused to Government stations.

US10 The use of the frequencies 26.62, 143.75, 143.90 and 148.15 MHz may be authorized to Civil Air Patrol land stations and Civil Air Patrol mobile stations.

US11 The use of the frequencies 166.250 and 170.150 MHz may be authorized to non-Government remote pickup broadcast base and land mobile stations and to non-Government base, fixed and land mobile stations in the public safety radio services (the sum of the bandwidth of emission and tolerance is not to exceed 25 kHz, except that authorizations in existence as of December 20, 1974, using a larger bandwidth are permitted to continue in operation until December 20,

1979) in the continental United States (excluding Alaska) only, except within the area bounded on the west by the Mississippi River, on the north by the parallel of latitude 37°30' N., and on the east and south by that arc of the circle with center at Springfield, Illinois, and radius equal to the airline distance between Springfield, Illinois, and Montgomery, Alabama, subtended between the foregoing west and north boundaries, on the condition that harmful interference will not be caused to Government stations present or future in the Government band 162–174 MHz. The use of these frequencies by remote pickup broadcast stations will not be authorized for locations within 150 miles of New York City; and use of these frequencies by the public safety radio services will not be authorized except for locations within 150 miles of New York City.

US13 For the specific purpose of transmitting hydrological and meteorological data in co-operation with agencies of the Federal Government, the following frequencies may be authorized to non-Government fixed stations on the condition that harmful interference will not be caused to Government stations.

MHz	
169.425	171.125
169.450	171.825
169.475	171.850
169.500	171.875
169.525	171.900
170.225	171.925
170.250	406.125
170.275	406.175
170.300	409.675
170.325	409.725
171.025	412.625
171.050	412.675
171.075	412.725
171.100	412.775

Licensees holding a valid authorization on June 11, 1962, to operate on the frequencies 169.575, 170.375 or 171.975 MHz may continue to be authorized for such operations on the condition that harmful interference will not be caused to Government stations.

US14 When 500 kHz is being used for distress purposes, ship and coast stations using morse telegraph may use 512 kHz for calling.

US18 Navigation aids in the US and possessions in the bands 9–14 kHz, 90–110 kHz, 190–415 kHz, 510–535 kHz, 2700–2900 MHz are normally operated by the U.S. Government. However, authorizations may be made by the FCC for non-Government operation in these bands subject to the conclusion of appropriate arrangements between the FCC and the Government agencies concerned and upon special showing of need for service which the Government is not yet prepared to render.

US25 The use of frequencies in the band 25.85–26.1 MHz may be authorized in any area to non-Government remote pickup broadcast base and mobile stations on the condition that harmful interference is not caused to stations in the broadcasting service.

US26 The bands 117.975–121.4125 MHz, 123.5875–128.8125 MHz and 132.0125–136.0 MHz are for air traffic control communications.

US28 The band 121.5875–121.9375 MHz is for use by aeronautical utility land and mobile stations, and for air traffic control communications.

US30 The band 121.9375–123.0875 MHz is available to FAA aircraft for communications pursuant to flight inspection functions in accordance with the Federal Aviation Act of 1958.

US31 Except as provided below the band 121.9375–123.0875 MHz is for use by private aircraft stations.

The frequencies 122.700, 122.725, 122.750, 122.800, 122.950, 122.975, 123.000, 123.050 and 123.075 MHz may be assigned to aeronautical advisory stations. In addition, at landing areas having a part-time or no airdrome control tower or FAA flight service station, these frequencies may be assigned on a secondary non-interference basis to aeronautical utility mobile stations, and may be used by FAA ground vehicles for safety related communications during inspections conducted at such landing areas.

The frequencies 122.850, 122.900 and 122.925 MHz may be assigned to aeronautical multicom stations. In addition, 122.850 MHz may be assigned on a secondary noninterference basis to aeronautical utility mobile stations. In case of 122.925 MHz, US213 applies.

Air carrier aircraft stations may use 122.000 and 122.050 MHz for communication with aeronautical stations of the Federal Aviation Administration and 122.700, 122.800, 122.900 and 123.000 MHz for communications with aeronautical stations pertaining to safety of flight with and in the vicinity of landing areas not served by a control tower.

Frequencies in the band 121.9375–122.6875 MHz may be used by aeronautical stations of the Federal Aviation Administration for communication with private aircraft stations only, except that 122.000 and 122.050 MHz may also be used for communication with air carrier aircraft stations concerning weather information.

US32 Except for the frequencies 123.3 and 123.5 MHz, which are not authorized for Government use, the band 123.1125–123.5875 MHz is available for FAA communications incident to flight test and inspection activities pertinent to aircraft and facility certification on a secondary noninterference basis.

US33 The band 123.1125–123.5875 MHz is for use by flight test and aviation instructional stations. The frequency 121.950 MHz is available for aviation instructional stations.

Federal Communications Commission

§2.106

US41 The Government radiolocation service is permitted in the band 2450–2500 MHz on condition that harmful interference is not caused to non-Government services.

US44 The non-Government radiolocation service may be authorized in the band 2900–3100 MHz on the condition that no harmful interference is caused to Government services.

US48 The non-Government radiolocation service may be authorized in the bands 5350–5460 MHz and 9000–9200 MHz on the condition that it does not cause harmful interference to the aeronautical radionavigation service or to the Government radiolocation service.

US49 The non-Government radiolocation service may be authorized in the band 5460–5470 MHz on the condition that it does not cause harmful interference to the aeronautical or maritime radionavigation services or to the Government radiolocation service.

US50 The non-Government radiolocation service may be authorized in the band 5470–5600 MHz on the condition that it does not cause harmful interference to the maritime radionavigation service or to the Government radiolocation service.

US51 In the band 5600–5650 MHz and 9300–9500 MHz, the non-Government radiolocation service shall not cause harmful interference to the Government radiolocation service.

US53 In view of the fact that the band 13.25–13.4 GHz is allocated to doppler navigation aids, Government, and non-Government airborne doppler radars in the aeronautical radionavigation service are permitted in the band 8750–8850 MHz only on the condition that they must accept any interference that may be experienced from stations in the radiolocation service in the band 8500–10000 MHz.

US54 Temporarily, and until certain operations of the radiolocation service in the band 9000–9200 MHz can be transferred to other appropriate frequency bands, the aeronautical radionavigation service may, in certain geographical areas, be subject to receiving some degree of interference from the radiolocation service.

US58 In the band 10000–10500 MHz, pulsed emissions are prohibited, except for weather radars on board meteorological satellites in the band 10000–10025 MHz. The amateur service and the non-Government radiolocation service, which shall not cause harmful interference to the Government radiolocation service, are the only non-Government services permitted in this band. The non-Government radiolocation service is limited to survey operations as specified in footnote US108.

US59 The band 10.5–10.55 GHz is restricted to systems using type NON (AO) emission with a power not to exceed 40 watts into the antenna.

US65 The use of the band 5460–5650 MHz by the maritime radionavigation service is limited to shipborne radars.

US66 The use of the band 9300–9500 MHz by the aeronautical radionavigation service is limited to airborne radars and associated airborne beacons. In addition, ground-based radar beacons in the aeronautical radionavigation service are permitted in the band 9300–9320 MHz on the condition that harmful interference is not caused to the maritime radionavigation service.

US67 The use of the band 9300–9500 MHz by the meteorological aids service is limited to ground-based radars. Radiolocation installations will be coordinated with the meteorological aids service and, insofar as practicable, will be adjusted to meet the requirements of the meteorological aids service.

US69 In the band 31.8–33.4 GHz, ground-based radionavigation aids are not permitted except where they operate in cooperation with airborne or shipborne radionavigation devices.

US70 The meteorological aids service allocation in the band 400.15–406.0 MHz does not preclude the operation therein of associated ground transmitters.

US71 In the band 9300–9320 MHz, low-powered maritime radionavigation stations shall be protected from harmful interference caused by the operation of land-based equipment.

US74 In the bands 25.55–25.67, 73.0–74.6, 406.1–410.0, 608–614, 1400–1427, 1660.5–1670.0, 2690–2700 and 4990–5000 MHz and in the bands 10.68–10.7, 15.35–15.4, 23.6–24.0, 31.3–31.5, 86–92, 105–116 and 217–231 GHz, the radio astronomy service shall be protected from extraband radiation only to the extent that such radiation exceeds the level which would be present if the offending station were operating in compliance with the technical standards or criteria applicable to the service in which it operates.

US77 Government stations may also be authorized:

(a) Port operations use on a simplex basis by coast and ship stations on the frequencies 156.6 and 156.7 MHz;

(b) Duplex port operations use of the frequency 157.0 MHz for ship stations and 161.6 MHz for coast stations;

(c) Inter-ship use of 156.3 MHz on a simplex basis; and

(d) Vessel traffic services under the control of the U.S. Coast Guard on a simplex basis by coast and ship stations on the frequencies 156.25, 156.55, 156.6 and 156.7 MHz.

(e) Navigational bridge-to-bridge and navigational communications on a simplex basis by coast and ship stations on the frequencies 156.375 and 156.65 MHz.

US78 In the mobile service, the frequencies between 1435 and 1535 MHz will be assigned for aeronautical telemetry and associated telecommand operations for flight

testing of manned or unmanned aircraft and missiles, or their major components. Permissible usage includes telemetry associated with launching and reentry into the earth's atmosphere as well as any incidental orbiting prior to reentry of manned objects undergoing flight tests. The following frequencies are shared with flight telemetry mobile stations: 1444.5, 1453.5, 1501.5, 1515.5, 1535.5 and 1525.5 MHz.

US80 Government stations may use the frequency 122.9 MHz subject to the following conditions:

(a) All operations by Government stations shall be restricted to the purpose for which the frequency is authorized to non-Government stations, and shall be in accordance with the appropriate provisions of the Commission's Rules and Regulations, Part 87, Aviation Services;

(b) Use of the frequency is required for coordination of activities with Commission licensees operating on this frequency; and

(c) Government stations will not be authorized for operation at fixed locations.

US81 The band 38.0–38.25 MHz is used by both Government and non-Government radio astronomy observatories. No new fixed or mobile assignments are to be made and Government stations in the band 38.0–38.25 MHz will be moved to other bands on a case-by-case basis, as required, to protect radio astronomy observations from harmful interference. As an exception, however, low powered military transportable and mobile stations used for tactical and training purposes will continue to use the band. To the extent practicable, the latter operations will be adjusted to relieve such interference as may be caused to radio astronomy observations. In the event of harmful interference from such local operations, radio astronomy observatories may contact local military commands directly, with a view to effecting relief. A list of military commands, areas of coordination, and points of contact for purposes of relieving interference may be obtained upon request from the Office of the Chief Engineer, Federal Communications Commission, Washington, D.C. 20554.

US82 Until July 1, 1991, the assignable frequencies in the bands 4143.6–4146.6 kHz, 6218.6–6224.6 kHz, 8291.1–8297.3 kHz, 12429.2–12439.5 kHz, 16587.1–16596.4 kHz and 22124–22139.5 kHz may be authorized on a shared nonpriority basis to Government and non-Government ship and coast stations (SSB telephony, with peak envelope power not to exceed 1 kW). Effective July 1, 1991, the assignable frequencies in the bands 4146–4152 kHz, 6224–6233 kHz, 8294–8300 kHz, 12353–12368 kHz, 16528–16549 kHz, 18825–18846 kHz, 22159–22180 kHz, and 25100–25121 kHz may be authorized on a shared non-priority basis to Government and non-Government ship and coast stations (SSB telephony, with peak envelope power not to exceed 1 kW).

US87 The frequency 450 MHz, with maximum emission bandwidth of 500 kHz, may be used by Government and non-Government stations for space telecommand at specific locations, subject to such conditions as may be applied on a case-by-case basis.

US90 In the band 2025–2110 MHz earth-to-space and space-to-space transmissions may be authorized in the space research and earth exploration-satellite services subject to such conditions as may be applied on a case-by-case basis. Such transmissions shall not cause harmful interference to non-Government stations operating in accordance with the Table of Frequency Allocations. All space-to-space transmissions reaching the earth's surface shall adhere to a power flux density of between –144 and –154 (dbw/(m²)/4 kHz depending on the angle of arrival per ITU Radio Regulation 2557 and shall not cause harmful interference to the other space services.

US93 In the conterminous United States, the frequency 108.0 MHz may be authorized for use by VOR test facilities, the operation of which is not essential for the safety of life or property, subject to the condition that no interference is caused to the reception of FM broadcasting stations operating in the band 88–108 MHz. In the event that such interference does occur, the licensee or other agency authorized to operate the facility shall discontinue operation on 108 MHz and shall not resume operation until the interference has been eliminated or the complaint otherwise satisfied. VOR test facilities operating on 108 MHz will not be protected against interference caused by FM broadcasting stations operating in the band 88–108 MHz not shall the authorization of a VOR test facility on 108 MHz preclude the Commission from authorizing additional FM broadcasting stations.

US99 In the band 1668.4–1670.0 MHz, the meteorological aids service (radiosonde) will avoid operations to the maximum extent practicable. Whenever it is necessary to operate radiosondes in the band 1668.4–1670 MHz within the United States, notification of the operations shall be sent as far in advance as possible to the Electromagnetic Management Unit, National Science Foundation, Washington, D.C. 20550.

US102 In Alaska only, the frequency 122.1 MHz may also be used for air carrier air traffic control purposes at locations where other frequencies are not available to air carrier aircraft stations for air traffic control.

US104 The LORAN Radionavigation System has priority in band 90–110 kHz in the United States and possessions. Radiolocation land stations making use of LORAN type equipment may be authorized to both Government and non-Government on a secondary service basis for offshore radiolocation

Federal Communications Commission

§ 2.106

activities only at specific locations and subject to such technical and operational conditions (e.g., power, emission, pulse rate and phase code, hours of operation), including on-the-air testing, as may be required on a case-by-case basis to ensure protection of the LORAN radionavigation system from harmful interference and to ensure mutual compatibility among radiolocation operators. Such authorizations to stations in the radiolocation service are further subject to showing of need for service which is not currently provided and which the Government is not yet prepared to render by way of the radionavigation service.

US106 The frequency 156.75 MHz is available for assignment to non-Government and Government stations for environmental communications in accordance with an agreed plan.

US107 The frequency 156.8 MHz is the national distress, safety and calling frequency for the maritime mobile VHF radiotelephone service for use by Government and non-Government ship and coast stations. Guard bands of 156.7625–156.7875 and 156.8125–156.8375 MHz are maintained.

US108 Within the bands 3300–3500 MHz and 10000–10500 MHz, survey operations, using transmitters with a peak power not to exceed five watts into the antenna, may be authorized for Government and non-Government use on a secondary basis to other Government radiolocation operations.

US110 In the frequency bands 3100–3300 MHz, 3500–3700 MHz, 5250–5350 MHz, 8500–9000 MHz, 9200–9300 MHz, 9500–10000 MHz, 13.4–14.0 GHz, 15.7–17.3 GHz, 24.05–24.25 GHz and 33.4–36.0 GHz, the non-Government radiolocation service shall be secondary to the Government radiolocation service and to airborne doppler radars at 8800 MHz, and shall provide protection to airport surface detection equipment (ASDE) operating between 15.7–16.2 GHz.

US111 In the band 1990–2120 MHz, Government space research earth stations may be authorized to use specific frequencies at specific locations for earth-to-space transmissions. Such authorizations shall be secondary to non-Government use of this band and subject to such other conditions as may be applied on a case-by-case basis.

Corpus Christi, Tex., 27°39'N., 097°23'W.
Fairbanks, Alaska, 64°59'N., 147°53'W.
Goldstone, Calif., 35°18'N., 116°54'W.
Greenbelt, Md., 39°00'N., 076°50'W.
Guam, Mariana Is., 13°19'N., 144°44'E.
Kauai, Hawaii, 22°08'N., 159°40'W.
Merritt Is., Fla., 28°29'N., 080°35'W.
Rosman, N.C., 35°12'N., 082°52'W.
Wallops Is., Va., 37°57'N., 075°20'W.

US112 The frequency 123.1 MHz is for search and rescue communications. This frequency may be assigned for air traffic control communications at special aeronautical

events on the condition that no harmful interference is caused to search and rescue communications during any period of search and rescue operations in the locale involved.

US116 In the bands 890–902 MHz and 935–941 MHz, no new assignments are to be made to Government radio stations after July 10, 1970 except on case-by-case basis, to experimental stations and to additional stations of existing networks in Alaska. Government assignments existing prior to July 10 1970 to stations in Alaska may be continued. All other existing Government assignments shall be on a secondary basis to stations in the non-Government land mobile service and shall be subject to adjustment or removal from the bands 890–902 MHz, 928–932 MHz and 935–941 MHz at the request of the FCC.

US117 In the band 406.1–410 MHz, all new authorizations will be limited to a maximum 7 watts per kHz of necessary bandwidth; existing authorizations as of November 30, 1970 exceeding this power are permitted to continue in use.

New authorizations in this band stations, other than mobile stations, within the following areas are subject to prior coordination by the applicant through the Electromagnetic Spectrum Management Unit, National Science Foundation, Washington, D.C. 20550, (202–357–9696):

Arecibo Observatory:

Rectangle between latitudes 17°30'N. and 19°00'N. and between longitudes 65°10'W. and 68°00'W.

Owens Valley Radio Observatory:

Two contiguous rectangles, one between latitudes 36°N. and 37°N. and longitudes 117°40'W. and 118°30'W. and the second between latitudes 37°N. and 38°N. and longitudes 118°W. and 118°50'W.

Sagamore Hill Radio Observatory:

Rectangle between latitudes 42°10'N. and 43°00'N. and longitudes 70°31'W. and 71°31'W.

Table Mountain Solar Observatory (NOAA), Boulder, Colorado (407–409 MHz only):

Rectangle between latitudes 39°30'N. and 40°30'N. and longitudes 104°30'W. and 106°00'W. or the Continental Divide whichever is farther east.

The non-Government use of this band is limited to the radio astronomy service and as provided by footnote US13.

US201 In the band 460–470 MHz, space stations in the earth exploration-satellite service may be authorized for space-to-earth transmissions on a secondary basis with respect to the fixed and mobile services. When operating in the meteorological-satellite service, such stations shall be protected from harmful interference from other applications of the earth exploration-satellite service. The power flux produced at the earth's surface by any space station in this band shall not exceed $-152 \text{ dBW/m}^2 \text{ kHz}$.

§ 2.106

47 CFR Ch. I (10–1–97 Edition)

US203 Radio astronomy observations of the formaldehyde line frequencies 4825–4835 MHz and 14.470–14.500 GHz may be made at certain radio astronomy observatories as indicated below:

BANDS TO BE OBSERVED		
4 GHz	14 GHz	Observatory
X		National Astronomy and Ionosphere Center, Arecibo, Puerto Rico.
X	X	National Radio Astronomy Observatory, Green Bank, W. Va.
X	X	National Radio Astronomy Observatory, Socorro, New Mexico.
X	X	Hat Creek Observatory (U of Calif.), Hat Creek, Cal.
X	X	Haystack Radio Observatory (MIT-Lincoln Lab), Tyngsboro, Mass.
X	X	Owens Vally Radio Observatory (Cal. Tech.), Big Pine, Cal.
.....	X	Five College Radio Astronomy Observatory Quabbin Reservoir (near Amherst), Massachusetts.

Every practicable effort will be made to avoid the assignment of frequencies to stations in the fixed or mobile services in these bands. Should such assignments result in harmful interference to these observations, the situation will be remedied to the extent practicable.

US205 Tropospheric scatter systems are prohibited in the band 2500–2690 MHz.

US208 Planning and use of the band 1559–1626.5 MHz necessitate the development of technical and/or operational sharing criteria to ensure the maximum degree of electromagnetic compatibility with existing and planned systems within the band.

US209 The use of frequencies 460.6625, 460.6875, 460.7125, 460.7375, 460.7625, 460.7875, 460.8125, 460.8375, 460.8625, 465.6625, 465.6875, 465.7125, 465.7375, 465.7625, 465.7875, 465.8125, 465.8375, and 465.8625 MHz may be authorized, with 100 mW or less output power, to Government and non-Government radio stations for one-way, non-voice bio-medical telemetry operations in hospitals, or medical or convalescent centers.

US210 Use of frequencies in the bands 40.66–40.70 and 216–220 MHz may be authorized to Government and non-Government stations on a secondary basis for the tracking of, and telemetering of scientific data from, ocean buoys and wildlife. Airborne wildlife telemetry in the 216–220 MHz band will be limited to the 216.0–216.1 MHz portion of the band. Operation in these two bands is subject to the technical standards specified in: (a) Section 8.2.42 of the NTIA Manual for Government use, or (b) Section 5.108 of the Commission's Rules for non-Government use.

US211 In the bands 1670–1690, 5000–5250 MHz and 10.7–11.7, 15.1365–15.35, 15.4–15.7, 22.5–22.55, 24–24.05, 31.0–31.3, 31.8–32.0, 40.5–42.5, 84–86, 102–105, 116–126, 151–164, 176.5–182, 185–190,

231–235, 252–265 GHz, applicants for airborne or space station assignments are urged to take all practicable steps to protect radio astronomy observations in the adjacent lands from harmful interference; however, US74 applies.

US212 In the State of Alaska, the carrier frequency 5167.5 kHz (assigned frequency 5168.9 kHz) is designated for emergency communications. This frequency may also be used in the Alaska-Private Fixed Service for calling and listening, but only for establishing communications before switching to another frequency. The maximum power is limited to 150 watts peak envelope power (PEP).

US213 The frequency 122.925 MHz is for use only for communications with or between aircraft when coordinating natural resources programs of Federal or State natural resources, agencies, including forestry management and fire suppression, fish and game management and protection and environmental monitoring and protection.

US214 The frequency 157.1 MHz is the primary frequency for liaison communications between ship stations and stations of the United States Coast Guard.

US215 Emissions from microwave ovens manufactured on and after January 1, 1980, for operation on the frequency 915 MHz must be confined within the band 902–928 MHz. Emissions from microwave ovens manufactured prior to January 1, 1980, for operation on the frequency 915 MHz must be confined within the band 902–940 MHz. Radiocommunications services operating in the band 928–940 MHz must accept any harmful interference from the operation of microwave ovens manufactured before January 1, 1980.

US216 The frequencies 150.775 and 150.790, and the bands 152–152.0150, 163.2375–163.2625, 462.9375–463.1875 and 467.9375–468.1875 MHz are authorized for Government/non-Government operations in medical radio communications systems.

US217 Pulse-ranging radimlocation systems may be authorized for Government and non-Government use in the 420–450 MHz band along the shorelines of Alaska and the contiguous 48 states. Spread spectrum radio-location systems may be authorized in the 420–435 MHz portion of the band for operation within the contiguous 48 States and Alaska. Authorizations will be eranted on a case-by-case basis; howeter, operations proposed to be located within the zones set forth in US228 should not expect tm be accommodated. All stations operating in accordance with this provision will be secondary to stations operating in accordance with the Table of Frequency Allocations.

US218 The band 902–928 MHz is available for Location and Monitoring Service (LMS) systems subject to not causing harmful interference to the operation of all Government stations authorized in these bands.

Federal Communications Commission

§2.106

These systems must tolerate interference from the operation of industrial, scientific, and medical (ISM) devices and the operation of Government stations authorized in these bands.

US219 In the band 2025–2110 MHz Government Earth resources satellite Earth stations in the Earth exploration-satellite service may be authorized to use the frequency 2106.4 MHz for Earth-to-space transmission for tracking, telemetry, and telecommand at the sites listed below. Such transmissions shall not cause harmful interference to non-Government operations:

Sioux Falls, South Dakota, 43°32′03.1″ N., 96°45′42.8″ W.

Fairbanks, Alaska, 64°58′36.6″ N., 147°30′54.2″ W.

US220 The frequencies 36.25 and 41.71 MHz may be authorized to Government stations and non-Government stations in the petroleum radio service, for oil spill containment and cleanup operations. The use of these frequencies for oil spill containment or cleanup operations is limited to the inland and coastal waterway regions.

US221 In the 525–535 kHz band, the mobile service is limited to distribution of public service information from Travelers Information Stations operating on 530 kHz.

US222 In the band 2025–2035 MHz geostationary operational environmental satellite Earth stations in the space research and Earth exploration-satellite services may be authorized on a coequal basis for Earth-to-space transmissions for tracking, telemetry, and telecommand at the sites listed below:

Wallops Is., Va. 37°50′48″ N., 75°27′33″ W.

Seattle, Wash. 47°34′15″ N., 122°33′10″ W.

Honolulu, Hawaii 21°21′12″ N., 157°52′36″ W.

US223 Within 75 miles of the United States/Canada border on the Great Lakes, the St. Lawrence Seaway, and the Puget Sound and the Strait of Juan de Fuca and its approaches, use of coast transmit frequency 162.025 MHz and ship station transmit frequency 157.425 MHz (VHF maritime mobile service Channel 88) may be authorized for use by the maritime service for public correspondence.

US224 Government systems utilizing spread spectrum techniques for terrestrial communication, navigation and identification may be authorized to operate in the band 960–1215 MHz on the condition that harmful interference will not be caused to the aeronautical radionavigation service. These systems will be handled on a case-by-case basis. Such systems shall be subject to a review at the national level for operational requirements and electromagnetic compatibility prior to development, procurement or modification.

US225 In addition to its present Government use, the frequency band 510–525 kHz is

available to Government and non-Government aeronautical radionavigation stations inland of the Territorial Base Line as coordinated with the military services. In addition, the frequency 510 kHz is available for non-Government ship-helicopter operations when beyond 100 nautical miles from shore and required for aeronautical radionavigation.

US226 In the State of Hawaii, stations in the aeronautical radionavigation service shall not cause harmful interference to U.S. Navy reception from its station at Honolulu on 198 kHz.

US228 Applicants for operation in the band 420 to 450 MHz under the provisions of US217 should not expect to be accommodated if their area of service is within the following geographic areas:

(a) Those portions of Texas and New Mexico bounded on the south by latitude 31°45′ North, on the east by longitude 104°00′ West, on the north by latitude 34°30′ North, and on the West by longitude 107°30′ West.

(b) In the State of Massachusetts within a 160 kilometers (100 miles) radius around the locations of Otis Air Force Base, Massachusetts (latitude 41°45′ North, longitude 70°32′ West).

(c) In the State of California within a 240 kilometer (150 mile) radius of Beale Air Force Base, California (latitude 39°08′ North, longitude 121°26′ West).

(d) In the State of Alaska, within a 160 kilometer (100 mile) radius of Clear, Alaska (latitude 64°17′ North, longitude 149°10′ West).

(e) In the State of North Dakota, within a 160 kilometer (100 mile) radius of Concrete, North Dakota (latitude 48°43′ North, longitude 97°54′ West).

(f) Those portions of Texas and New Mexico bounded on the south by latitude 31°45′ North, on the east by longitude 104°100′ West, on the north by latitude 34°30′ North, and on the West by longitude 107°30′ West.

(g) In the state of Alaska within a 160 kilometer (100 mile) radius of Clear, Alaska (latitude 64 degrees 17 north, longitude 149 degrees 10 west).

(h) In the state of North Dakota within a 160 kilometer (100 mile) radius of Concrete, North Dakota (latitude 48 degrees 43 north, longitude 97 degrees 54 west).

(i) In the States of Alabama, Florida, Georgia and South Carolina within a 200 kilometer (124 mile) radius of Warner Robins Air Force Base, Georgia (latitude 32°38′ North, longitude 83°35′ West).

(j) In the State of Texas within a 200 kilometer (124 mile) radius of Goodfellow Air Force Base, Texas (latitude 31°25′ North, longitude 100°24′ West).

US229 Assignments to stations in the fixed and mobile services may be made on the condition that no harmful interference is caused to the Navy SPASUR system currently operating in the southern United

§2.106

47 CFR Ch. I (10–1–97 Edition)

States in the frequency band 216.88–217.08 MHz.

US230 Non-government land mobile service is allocated on a primary basis in the bands 422.1875–425.4875 and 427.1875–429.9875 MHz within 50 statute miles of Detroit, MI, and Cleveland, OH, and in the bands 423.8125–425.4875 and 428.8125–429.9875 MHz within 50 statute miles of Buffalo, NY.

US231 When an assignment cannot be obtained in the bands between 200 and 525 kHz, which are allocated to aeronautical radio-navigation, assignments may be made to aeronautical radiobeacons in the maritime mobile band 435–490 kHz, on a secondary basis, subject to the coordination and agreement of those agencies having assignments within the maritime mobile band which may be affected. Assignments to aeronautical radionavigation radiobeacons in the band 435–490 kHz shall not be a bar to any required changes to the maritime mobile radio service and shall be limited to Government not employing voice emissions.

US235 Until implementation procedures and schedules are determined by future conferences of the International Telecommunications Union, the bands 9775–9900 kHz, 11650–11700 kHz, 11975–12050 kHz, 13600–13800 kHz, 15450–15600 kHz, 17550–17700 kHz, and 21750–21850 kHz to be implemented by the broadcasting service are allocated as an alternative allocation to the fixed service. The bands 12230–12330 kHz, 16360–16460 kHz, 17360–17410 kHz, 18780–18900 kHz, 19680–19800 kHz, 22720–22855 kHz, 25110–25210 kHz, and 26100–26175 kHz to be implemented by the maritime mobile service are also allocated as an alternative allocation to the fixed service until July 1, 1991, when these bands are to be allocated exclusively to the maritime mobile service.

US236 Until implementation procedures and schedules are determined by future conferences of the International Telecommunications Union (See Resolution 319), the bands 4000–4063 and 8100–8195 kHz are also allocated on a primary basis to the fixed service.

US238 The 1605–1705 kHz band is allocated to the radiolocation service on a secondary basis.

US239 Aeronautical radionavigation stations (radiobeacons) may be authorized, primarily for off-shore use, in the band 525–535 kHz on a non-interference basis to travelers information stations.

US240 The bands 1715–1725 and 1740–1750 kHz are allocated on a primary basis and the bands 1705–1715 kHz and 1725–1740 kHz on a secondary basis to the aeronautical radio-navigation service, (radiobeacons).

US244 The band 136.000–137.000 MHz is allocated to the non-Government aeronautical mobile (R) service on a primary basis, and is subject to pertinent international treaties and agreements. The frequencies 136.000 MHz, 136.025 MHz, 136.050 MHz, 136.075 MHz, 136.125

MHz, 136.150 MHz, 136.175 MHz, 136.225 MHz, 136.250 MHz, 136.300 MHz, 136.325 MHz, 136.350 MHz, 136.400 MHz, 136.425 MHz and 136.450 MHz are available on a shared basis to the Federal Aviation Administration for air traffic control purposes, such as automatic weather observation services (AWOS), automatic terminal information services (ATIS) and airport control tower communications. Stations licensed prior to January 2, 1990, using the 136–137 MHz band for space operation (space-to-earth), meteorological-satellite service (space-to-earth) and the space research service (space-to-earth) may continue to use this band on a secondary basis to aeronautical mobile (R) service stations. No new assignments will be made to stations in the above space services.

US245 The fixed-satellite service is limited to international inter-continental systems and subject to case-by-case electromagnetic compatibility analysis.

US246 No stations will be authorized to transmit in the bands 608–614 MHz, 1400–1427 MHz, 1660.5–1668.4 MHz, 2690–2700 MHz, 4990–5000 MHz, 10.68–10.70 GHz, 15.35–15.40 GHz, 23.6–24.0 GHz, 31.3–31.8 GHz, 51.4–54.25 GHz, 58.2–59.0 GHz, 64–65 GHz, 86–92 GHz, 100–102 GHz, 105–116 GHz, 164–168 GHz, 182–185 GHz and 217–231 GHz.

US247 The band 10100–10150 kHz is allocated to the fixed service on a primary basis outside the United States and possessions. Transmissions of stations in the amateur service shall not cause harmful interference to this fixed service use and stations in the amateur service shall make all necessary adjustments (including termination of transmission) if harmful interference is caused.

US251 The band 12.75–13.25 GHz is also allocated to the space research, (deep space) (space-to-earth) service for reception only at Goldstone, California. 35°18 N. 116°54–W.

US252 The bands 2110–2120, 7145–7190 MHz, and 34.2–34.7 GHz are also allocated for earth-to-space transmissions in the space research service, limited to deep space communications at Goldstone, California.

US254 In the band 18.6–18.8 GHz the fixed and mobile services shall be limited to a maximum equivalent isotropically radiated power of +35 dBW and the power delivered to the antenna shall not exceed –3 dBW.

US255 In the band 18.6–18.8 GHz the fixed satellite service shall be limited to a power flux density at the Earth's surface of –101 dBW/M² in a 200 MHz band for all angles of arrival.

US256 Radio astronomy observations may be made in the band 1718.8–1722.2 MHz on an unprotected basis. Agencies providing other services in this band in the geographic areas listed below should bear in mind that their operations may affect those observations, and those agencies are encouraged to minimize potential interference to the observations in so far as it is practicable.

Federal Communications Commission

§2.106

National Astronomy and Ionosphere Center,
Arecibo, Puerto Rico

Rectangle between latitudes 17°30 N. and
19°00 N. and between longitudes 65°10 W.
and 68°00 W.

Haystack Radio Observatory, Tyngsboro,
Massachusetts

Rectangle between latitudes 41°00 N. and
43°00 N. and between longitudes 71°00 W.
and 73°00 W.

National Radio Astronomy Observatory,
Green Bank, West Virginia

Rectangle between latitudes 37°00 N. and
39°15 N. and longitudes 78°30 W. and 80°30
W.

National Radio Astronomy Observatory,
Socorro, New Mexico

Rectangle between latitudes 32°30 N. and
35°30 N. and between longitudes 106°00 W.
and 109°00 W.

Owens Valley Radio Observatory, Big Pine,
California

Two contiguous rectangles, one between
latitudes 36°00 N. and 37°00 N. and be-
tween longitudes 117°40 W. and 118°30 W.
and the second between latitudes 37°00 N.
and 38°00 N. and longitudes 118°00W and
118°50 W.

Hat Creek Observatory, Hat Creek, Califor-
nia

Rectangles between latitudes 40°00 N. and
42°00 N. and between longitudes 120°15 W.
and 122°15 W.

US257 Radio astronomy observations may
be made in the 4950–4990 MHz band at certain
Radio Astronomy Observatories indicated
below:

Hat Creek Observatory, Hat Creek, Califor-
nia

Rectangle between latitudes 40°00 N. and
42°00 N. and between longitudes 120°15 W.
and 122°15 W.

Owens Valley Radio Observatory, Pine, Cali-
fornia

Two contiguous rectangles, Big one be-
tween latitudes 36°00 N. and 37°00 N. and
longitudes 117°40 W. and 118°30 W. and the
second between latitudes 37°00 N. and
38°00 N. and longitudes 118°00 W. and
118°50 W.

Haystack Radio Observatory, Tyngsboro,
Massachusetts

Rectangle between latitudes 41°00 N. and
43°00 N. and between longitudes 71°00 W.
and 73°00 W.

National Astronomy and Ionosphere Center,
Arecibo, Puerto Rico

Rectangle between latitudes 17°30 N. and
19°00 N. and between longitudes 65°10 W.
and 68°00 W.

National Radio Astronomy Observatory,
Socorro, New Mexico

Rectangle between latitudes 32°30 N. and
35°30 N. and longitudes 106°00 W. and
109°00 W.

National Radio Astronomy Observatory,
Green Bank, West Virginia

Rectangle between latitudes 37°30 N. and
39°15 N. and longitudes 78°30 W. and 80°30
W.

Every practicable effort will be made to
avoid the assignment of frequencies in the
band 4950–4990 MHz to stations in the fixed
and mobile services within the geographic
areas given above. In addition, every prac-
ticable effort will be made to avoid the as-
signment of frequencies in this band to sta-
tions in the aeronautical mobile service
which operate outside of those geographic
areas, but which may cause harmful inter-
ference to the listed observatories. Should
such assignments result in harmful inter-
ference to these observatories, the situation
will be remedied to the extent practicable.

US258 In the band 8025–8400 MHz, the non-
Government earth exploration-satellite serv-
ice (space-to-earth) is allocated on a primary
basis. Authorizations are subject to a case-
by-case electromagnetic compatibility anal-
ysis.

US259 Stations in the radiolocation serv-
ice in the band 17.3–17.7 GHz, shall be re-
stricted to operating powers of less than 51
dBW eirp after feeder link stations for the
broadcasting-satellite service are authorized
and brought into use.

US260 Aeronautical mobile communica-
tions which are an integral part of aero-
nautical radionavigation systems may be
satisfied in the bands 1559–1626.5 MHz, 5000–
5250 MHz and 15.4–15.7 GHz.

US261 The use of the band 4200–4400 MHz
by the aeronautical radionavigation service
is reserved exclusively for airborne radio al-
timeters. Experimental stations will not be
authorized to develop equipment for oper-
ational use in this band other than equip-
ment related to altimeter stations. However,
passive sensing in the earth-exploration sat-
ellite and space research services may be au-
thorized in this band on a secondary basis
(no protection is provided from the radio al-
timeters).

US262 The band 31.8–32.3 GHz is also allo-
cated for space-to-earth transmissions in the
space research service, limited to deep space
communications at Goldstone, California.

US263 In the frequency bands 21.2–21.4,
22.21–22.5, 36–37, 50.2–50.4, 54.25–58.2, 116–126,
150–151, 174.5–176.5, 200–202 and 235–238 GHz,
the space research and earth exploration-sat-
ellite services shall not receive protection
from the fixed and mobile services operating
in accordance with the Table of Frequency
Allocations.

US264 In the band 48.94–49.04 GHz, air-
borne stations shall not be authorized.

US265 In the band 10.6–10.68 GHz, the fixed
service shall be limited to a maximum equiv-
alent isotropically radiated power of 40 dBW

and the power delivered to the antenna shall not exceed –3dBW per 250 kHz.

US266 Licensees in the public safety radio services holding a valid authorization on June 30, 1958, to operate in the frequency band 156.27–157.47 MHz or on the frequencies 161.85, 161.91 or 161.97 MHz may, upon proper application, continue to be authorized for such operation, including expansion of existing systems, until such time as harmful interference is caused to the operation of any authorized station other than those licensed in the public safety radio service.

US267 In the band 902–928 MHz, amateur radio stations shall not operate within the States of Colorado and Wyoming, bounded by the area of: latitude 39°N. to 42°N. and longitude 103°W. to 108°W.

US268 The bands 890–902 MHz and 928–942 MHz are also allocated to the radiolocation service for Government ship stations (off-shore ocean areas) on the condition that harmful interference is not caused to non-Government land mobile stations. The provisions of footnote US116 apply.

US269 In the band 2500–2690 MHz, applicants for space station assignments are urged to take all practicable steps to protect radio astronomy observations in the adjacent band, 2690–2700 MHz, from harmful interference. Further, all applicants are urged to coordinate their proposed system through the Electromagnetic Management Unit, National Science Foundation, Washington, D.C. 20550, prior to system development.

US270 The band 72.77–72.91 GHz is also allocated to the radio astronomy service. Applicants for frequency assignments in this band are urged to take all practicable steps to protect radio astronomy observations from harmful interference.

US271 The use of the band 17.3–17.8 GHz by the fixed-satellite service (earth-to-space) is limited to feeder links for broadcasting-satellite service.

US272 The allocation to the maritime mobile-satellite service in the band 1530–1535 MHz shall be effective from 1 January 1990. Up to that date the allocation to the mobile service will be on a primary basis.

US273 In the 74.6–74.8 MHz and 75.2–75.4 MHz bands stations in the fixed and mobile services are limited to a maximum power of 1 watt from the transmitter into the antenna transmission line.

US274 In the 216–220 MHz band fixed, aeronautical mobile and land mobile stations are limited to telemetering and associated telecommand operations.

US275 The band 902–928 MHz is allocated on a secondary basis to the amateur service subject to not causing harmful interference to the operations of Government stations authorized in this band or to Location and Monitoring Service (LMS) systems. Stations in the Amateur service must tolerate any interference from the operations of industrial,

scientific, and medical (ISM) devices, LMS systems, and the operations of Government stations authorized in this band. Further, the Amateur Service is prohibited in those portions of Texas and New Mexico bounded on the south by latitude 31°41' North, on the east by longitude 104°11' West, and on the north by latitude 34°30' North, and on the west by longitude 107°30' West; in addition, outside this area but within 150 miles of these boundaries of White Sands Missile Range the service is restricted to a maximum transmitter peak envelope power output of 50 watts.

US276 Except as otherwise provided for herein, use of the bands 2320–2345 and 2360–2390 MHz by the mobile service is limited to aeronautical telemetering and associated telecommand operations for flight testing of manned or unmanned aircraft, missiles or major components thereof. The following four frequencies are shared on a co-equal basis by Government and non-Government stations for telemetering and associated telecommand operations of expendable and reusable launch vehicles whether or not such operations involve flight testing: 2332.5, 2364.5, 2370.5, and 2382.5 MHz. All other mobile telemetering uses shall be secondary to the above uses.

US277 The band 10.6–10.68 GHz is also allocated on a primary basis to the radio astronomy service. However, the radio astronomy service shall not receive protection from stations in the fixed service which are licensed to operate in the one hundred most populous urbanized areas as defined by the U.S. Census Bureau. The following radio astronomy sites have been coordinated for observations in this band: National Radio Astronomy Observatory, Green Bank, West Virginia; (38°26'08"N.; 79°49'42"W.) National Radio Astronomy Observatory, Socorro, New Mexico; (34°04'43"N.; 107°37'04"W.), Harvard Radio Astronomy Station, Fort Davis, Texas; (30°38'08"N.; 103°56'42"W.), Hat Creek Observatory, Hat Creek, California; (40°49'03"N.; 121°28'24"W.), Owens Valley Radio Observatory, Big Pine, California; (37°13'54"N.; 118°17'36"W.), Naval Research Laboratory, Maryland Point, Maryland (38°22'26"N.; 77°14'00"W.).

US278 In the 22.55–23.55 and 32–33 GHz bands non-geostationary intersatellite links may operate on a secondary basis to geostationary intersatellite links.

US279 The frequency 2182 kHz may be authorized to fixed stations associated with the maritime mobile service for the sole purpose of transmitting distress calls and distress traffic, and urgency and safety signals and messages.

US281 In the band 25.07–25.11 MHz non-Government stations in the industrial radio services shall not cause harmful interference

Federal Communications Commission

§2.106

to, and must accept interference from, stations in the maritime mobile service operating in accordance with the International Table of Frequency Allocations.

US282 In the band 4650–4700 kHz frequencies may be authorized for non-Government communication with helicopters in support of off-shore drilling operations on the condition that harmful interference will not be caused to services operating in accordance with the Table of Frequency Allocations.

US283 In the bands 2850–3025 kHz, 3400–3500 kHz, 4650–4700 kHz, 5450–5680 kHz, 6525–6685 kHz, 10005–10100 kHz, 11275–11400 kHz, 13260–13360 kHz and 17900–17970 kHz frequencies in these bands may be authorized for non-Government flight test purposes on the condition that harmful interference will not be caused to services operating in accordance with the Table of Frequency Allocations.

US284 Until July 1, 1991, the carrier frequencies 6451.9 and 6455.0 kHz may be authorized to non-Government ship telephone and coast telephone stations operating in the Mississippi River maritime mobile service system on the condition that harmful interference will not be caused to services operating in accordance with the Table of Frequency Allocations and that any interference from such services must be accepted.

US285 Under exceptional circumstances, the carrier frequency 2635, 2638, and 2738 kHz may be authorized to coast stations.

US290 In the band 1900–2000 kHz amateur stations may continue to operate on a secondary basis to the radiolocation service, pending a decision as to their disposition through a future rule making proceeding in conjunction with the implementation of the standard broadcasting service in the 1625–1705 kHz band.

US291 Television pickup stations in the mobile service may be authorized to use frequencies in the band 38.6–40 GHz on a secondary basis to stations operating in accordance with the Table of Frequency Allocations.

US292 In the band 14.0–14.2 GHz stations in the radionavigation service shall operate on a secondary basis to the fixed-satellite service.

US294 In the spectrum below 490 kHz electric utilities operate Power Line Carrier (PLC) systems on power transmission lines for communications important to the reliability and security of electric service to the public. These PLC systems operate under the provisions of Part 15 of the Federal Communications Commission's Rules and Regulations or Chapter 7 of the National Telecommunications and Information Administration's Manual of Regulations and Procedures for Federal Radio Frequency Management, on an unprotected and noninterference basis with respect to authorized radio users. Notification of intent to place new or revised radio frequency assignments or PLC fre-

quency uses in the bands below 490 kHz is to be made in accordance with the Rules and Regulations of the FCC and NTIA, and users are urged to minimize potential interference to the degree practicable. This footnote does not provide any allocation status to PLC radio frequency uses.

US296 Until July 1, 1991, in the bands designated for ship wide-band telegraphy, facsimile and special transmission systems, the following assignable frequencies are available to non-Government stations on a shared basis with Government stations: 2070.5, 2072.5, 2074.5, 2076.5, 4160.6, 4168, 6238.6, 6242.6, 8326, 8341.5, 12485, 12489, 16654, 16658, 22186 and 22190 kHz. Effective July 1, 1991, in the bands designated for ship wide-band telegraphy, facsimile and special transmission systems, the following assignable frequencies are available to non-Government stations on a shared basis with Government stations: 2070.5, 2072.5, 2074.5, 2076.5, 4154.5, 4169.5, 6235.5, 6259.5, 8302.5, 8338.5, 12370.5, 12418.5, 16551.5, 16614.5, 18847.5, 18868.5, 22181.5, 22238.5, 25123.5, and 25159.5 kHz.

US297 The bands 47.2–49.2 GHz and 74.0–75.5 GHz are also available for feeder links for the broadcasting-satellite service.

US298 Channels 27555, 27615, 27635, 27655, 27765, and 27860 kHz are available to eligibles in the Forest Products Radio Service on a secondary basis to Government operations including experimental stations. Operations in the Forest Products Radio Service on these channels will not exceed 150 watts and are limited to the states of Washington, Oregon, Maine, North Carolina, South Carolina, Tennessee, Georgia, Florida, Alabama, Mississippi, Louisiana, and Texas (eastern portion).

US299 The 1615–1705 kHz band in Alaska is also allocated to the maritime mobile services and the Alaska fixed service on a secondary basis to Region 2 broadcast operations.

US300 The frequencies 169.445, 169.505, 170.245, 170.305, 171.045, 171.105, 171.845 and 171.905 MHz are available for wireless microphone operations on a secondary basis to Government and non-Government operations.

US301 Except as provided in US302, broadcast auxiliary stations licensed as of November 21, 1984, to operate in the band 942–944 MHz may continue to operate on a co-equal primary basis to other stations and services operating in the band in accordance with the Table of Frequency Allocations.

US302 The band 942–944 MHz in Puerto Rico is allocated as an alternative allocation to the fixed service for broadcast auxiliary stations only.

US303 In the band 2285–2290 MHz, non-Government space stations in the space research, space operations and earth exploration-satellite services may be authorized to transmit to the Tracking and Data Relay

§2.106

Satellite System subject to such conditions as may be applied on a case-by case basis. Such transmissions shall not cause harmful interference to authorized Government stations. The power flux density at the Earth's surface from such non-Government stations shall not exceed -144 to -154 dBW/m²/4 kHz, depending on angle of arrival, in accordance with ITU Radio Regulation 2557.

US306 The band 1610–1626.5 MHz is also allocated for use by the radiodetermination satellite service in the Earth-to-space direction.

US307 The sub-band 5150–5216 MHz is also allocated for space-to-Earth transmissions in the fixed satellite service for feeder links in conjunction with the radiodetermination satellite service operating in the bands 1610–1626.5 MHz and 2483.5–2500 MHz. The total power flux density at the earth's surface shall in no case exceed -159 dBW/m per 4 kHz for all angles of arrival.

US308 In the frequency bands 1549.5–1558.5 MHz and 1651–1660 MHz, the Aeronautical-Mobile-Satellite (R) requirements that cannot be accommodated in the 1545–1549.5 MHz, 1558.5–1559 MHz, 1646.5–1651 MHz and 1660–1660.5 MHz bands shall have priority access with real-time preemptive capability for communications in the mobile satellite service. Systems not interoperable with the aeronautical mobile-satellite (R) service shall operate on a secondary basis. Account shall be taken of the priority of safety-related communications in the mobile-satellite service.

US309 Transmissions in the bands 1545–1559 MHz from terrestrial aeronautical stations directly to aircraft stations, or between aircraft stations, in the aeronautical mobile (R) service are also authorized when such transmissions are used to extend or supplement the satellite-to-aircraft links. Transmissions in the band 1646.5–1660.5 MHz from aircraft stations in the aeronautical mobile (R) service directly to terrestrial aeronautical stations, or between aircraft stations, are also authorized when such transmissions are used to extend or supplement the aircraft-to-satellite links.

US310 In the band 14.896–15.121 GHz, non-Government space stations in the space research service may be authorized on a secondary basis to transmit to Tracking and Data Relay Satellites subject to such conditions as may be applied on a case-by-case basis. Such transmissions shall not cause harmful interference to authorized Government stations. The power flux density at the earth's surface from such non-Government stations shall not exceed -138 to -148 dBW/m²/kHz, depending on the angle of arrival, in accordance with CCIR Recommendation 510–1.

US311–Radio astronomy observations may be made in the 1350–1400 MHz band on an unprotected basis at certain Radio Astronomy Observatories indicated below:

47 CFR Ch. I (10–1–97 Edition)

National Astronomy and Ionosphere Center, Arecibo, Puerto Rico

Rectangle between latitudes 17°30' N and 19°00' N and between longitudes 65°10' W and 68°00' W.

National Radio Astronomy Observatory, Socorro, New Mexico

Rectangle between latitudes 32°30' N and 35°30' N and between longitudes 106°00' W and 109°00' W.

National Radio Astronomy Observatory, Green Bank, West Virginia

Rectangle between latitudes 37°30' N and 39°15' N and between longitudes 78°30' W and 80°30' W.

National Radio Astronomy Observatory

50 mile radius circles centered on:

Very long baseline array stations	Latitude (North)	Longitude (West)
Pie Town, NM	34°18'	108°07'
Kitt Peak, AZ	31°57'	111°37'
Los Alamos, NM	35°47'	106°15'
Fort Davis, TX	30°38'	103°57'
North Liberty, IA	41°46'	91°34'
Brewster, WA	48°08'	119°41'
Owens Valley, CA	37°14'	118°17'
Saint Croix, VI	17°46'	64°35'
Mauna Kea, HI	19°49'	155°28'
Hancock, NH	42°56'	71°59'

Every practicable effort will be made to avoid the assignment of frequencies in the band 1350–1400 MHz to stations in the fixed and mobile services which could interfere with radio astronomy observations within the geographic areas.

US312 The frequency 173.075 MHz may also be authorized on a primary basis to non-Government stations in the Police Radio Service (with a maximum authorized bandwidth of 20 kHz) for stolen vehicle recovery systems.

US315 In the frequency bands 1530–1544 MHz and 1626.5–1645.5 MHz maritime mobile-satellite distress and safety communications, e.g., GMDSS, shall have priority access with real-time preemptive capability in the mobile-satellite service. Communications of mobile-satellite system stations not participating in the GMDSS shall operate on a secondary basis to distress and safety communications of stations operating in the GMDSS. Account shall be taken of the priority of safety-related communications in the mobile-satellite service.

US316 The band 2900–3100 MHz is also allocated on a primary basis to the Meteorological Aids Service. Operations in this service are limited to Government Next Generation Weather Radar (NEXRAD) systems where accommodation in the 2700–2900 MHz band is not technically practical and are subject to coordination with existing authorized stations."

US317 The band 218.0–219.0 MHz is allocated on a primary basis to the Interactive Video and Data operations.

Federal Communications Commission

§2.106

US318 Until January 1, 2000, the use of the 137–138 MHz band by the mobile-satellite service will be secondary to Government satellite operations in the subbands: 137.333–137.367, 137.485–137.515, 137.605–137.635 and 137.753–137.787 MHz.

US319 In the 137–138, 148–149.9, 149.9–150.05, 399.9–400.05, and 400.15–401 MHz bands, Government stations in the mobile-satellite service shall be limited to earth stations operating with non-Government satellites.

US320 Use of the 137–138, 148–149.9, and 400.15–401 MHz bands by the mobile-satellite service is limited to non-voice, non-geostationary satellite systems and may include satellite links between land earth stations at fixed locations.

US321 The 535–1705 kHz band is also allocated to the mobile service on a secondary basis for the distribution of public service information from non-government Travelers Information Stations operating in the Local Government Radio Service on 10 kHz spaced channels from 540 to 1700 kHz.

US322 The 149.9–150.05 MHz band is allocated to the mobile-satellite service (Earth-to-space) on a primary basis after 1 January 1997 and shall be limited to non-voice, non-geostationary satellite systems, including satellite links between land earth stations. Before 1 January 1997 use of this band on a secondary basis for the mobile satellite service is allowed for land earth stations at fixed locations.

US323 In the 148–149.9 MHz band, no individual mobile earth station shall transmit, on the same frequency being actively used by fixed and mobile stations and shall transmit no more than 1% of the time during any 15 minute period; except, individual mobile earth stations in this band that do not avoid frequencies actively being used by the fixed and mobile services shall not exceed a power density of -16 dBW/4kHz and shall transmit no more than 0.25% of the time during any 15 minute period. Any single transmission from any individual mobile earth station operating in this band shall not exceed 450 ms in duration and consecutive transmissions from a single mobile earth station on the same frequency shall be separated by at least 15 seconds. Land earth stations in this band shall be subject to electromagnetic compatibility analysis and coordination with terrestrial fixed and mobile stations.

US324 Government and non-Government satellite systems in the 400.15–401 MHz band shall be subject to electromagnetic compatibility analysis and coordination.

US325 In the band 148–149.9 MHz fixed and mobile stations shall not claim protection from land earth stations in the mobile-satellite service that have been previously coordinated; Government fixed and mobile stations exceeding 27 dBW EIRP, or an emission bandwidth greater than 38 kHz, will be co-

ordinated with existing mobile-satellite service space stations.

US326 The 399.9–400.05 MHz band is allocated to the mobile-satellite service (Earth-to-space) on a primary basis after January 1, 1997 and shall be limited to non-voice, non-geostationary satellite systems, including satellite links between land earth stations.

US327 The band 2310–2360 MHz is allocated to the broadcasting-satellite service (sound) and complementary terrestrial broadcasting service on a primary basis. Such use is limited to digital audio broadcasting and is subject to the provisions of Resolution 528.

US328 In the band 2320–2345 MHz, the mobile and radiolocation services are allocated on a primary basis until a broadcasting-satellite (sound) service has been brought into use in such a manner as to affect or be affected by the mobile and radiolocation services in those service areas. The broadcasting-satellite (sound) service during implementation should also take cognizance of the expendable and reusable launch vehicle frequency 2332.5 MHz, to minimize the impact on this mobile service use to the extent possible.

US334 In the band 17.8–20.2 GHz, Government space stations and associated earth stations in the fixed satellite (space-to-Earth) service may be authorized on a primary basis. For a Government geostationary satellite network to operate on a primary basis, the space station shall be located outside the arc measured from East to West, 70°W to 120°W. Coordination between Government fixed-satellite systems and non-Government systems operating in accordance with the United States Table of Frequency Allocations is required.

US335 The primary Government and non-Government allocations for the various segments of the 220–222 MHz band are divided as follows: (1) the 220.0–220.55/221.0–221.55, 220.6–220.8/221.6–221.8, 220.85–220.90/221.85–221.90 and 220.925–221.0/221.925–222.0 MHz bands (Channels 1–110, 121–160, 171–180 and 186–200, respectively) are available for exclusive non-Government use; (2) the 220.55–220.60/221.55–221.60 MHz bands (Channels 111–120) are available for exclusive Government use; and (3) the 220.80–220.85/221.80–221.85 and 220.900–220.925/221.900–221.925 MHz bands (Channels 161–170 and 181–185, respectively) are available for shared Government and non-Government use. The exclusive non-Government band segments are also available for temporary fixed geophysical telemetry operations on a secondary basis to the fixed and mobile services.

US337 In the band 13.75–13.80 GHz, earth stations in the fixed-satellite service shall be coordinated on a case-by-case basis through the frequency assignment subcommittee in order to minimize harmful interference to

the Tracking and Data Relay Satellite System's forward space-to-space link (TDRSS forward link-to-LEO).

US338 In the 2305–2310 MHz band, space-to-Earth operations are prohibited. Additionally, in the 2305–2320 MHz band, all Wireless Communications Service (WCS) operations within 50 kilometers of 35° 20' North Latitude and 116° 53' West Longitude shall be coordinated through the Frequency Assignment Subcommittee of the Interdepartment Radio Advisory Committee in order to minimize harmful interference to NASA's Goldstone Deep Space facility.

US339 The bands 2310–2320 and 2345–2360 MHz are also available for aeronautical telemetering and associated telecommand operations for flight testing of manned or unmanned aircraft, missiles or major components thereof on a secondary basis to the Wireless Communications Service. The following two frequencies are shared on a co-equal basis by Government and non-Government stations for telemetering and associated telecommand operations of expendable and re-usable launch vehicles whether or not such operations involve flight testing: 2312.5 and 2352.5 MHz. Other mobile telemetering uses may be provided on a non-interference basis to the above uses. The broadcasting-satellite (sound) service during implementation should also take cognizance of the expendable and reusable launch vehicle frequencies 2312.5 and 2352.5 MHz, to minimize the impact on this mobile service use to the extent possible.

US340 The 2–30 MHz band is available on a secondary noninterference basis to Government and non-Government maritime and aeronautical stations for the purposes of measuring the quality of reception on radio channels. See 47 C.F.R. § 87.149 for the list of protected frequencies and bands within this frequency range. Actual communications shall be limited to those frequencies specifically allocated to the maritime mobile and aeronautical mobile services.

US341 Non-government operations in the 24.25–24.45 GHz band must provide protection to FAA radionavigation radar facilities near Washington, D.C., and Newark, New Jersey, until January 1, 1998, and January 1, 2000, respectively. Protection will be afforded in accordance with criteria developed by the F.C.C. and N.T.I.A.

NON-GOVERNMENT (NG) FOOTNOTES

(These footnotes, each consisting of the letters "NG" followed by one or more digits, denote stipulations applicable only to the non-Government.)

NG2 Facsimile broadcasting stations may be authorized in the band 88–108 MHz.

NG3 Control stations in the domestic public mobile radio service may be authorized frequencies in the band 72–73 and 75.4–76 MHz on the condition that harmful interference

will not be caused to operational fixed stations.

NG4 The use of the frequencies in the band 152.84–153.38 MHz may be authorized, in any area, to remote pickup broadcast base and mobile stations on the condition that harmful interference will not be caused to stations operating in accordance with the Table of Frequency Allocations.

NG6 Stations in the public safety radio services authorized as of June 30, 1958, to use frequencies in the band 159.51–161.79 MHz in areas other than Puerto Rico and the Virgin Islands may continue such operation, including expansion of existing systems, on the condition that harmful interference will not be caused to stations in the services to which these bands are allocated. In Puerto Rico and the Virgin Islands this authority is limited to frequencies in the band 160.05–161.37 MHz. No new public radio service system will be authorized to operate on these frequencies.

NG12 Frequencies in the bands 454.40–455 MHz and 459.40–460 MHz may be assigned to domestic public land and mobile stations to provide a two-way air-ground public radio-telephone service.

NG17 Stations in the land transportation radio services authorized as of May 15, 1958 to operate on the frequency 161.61 MHz may, upon proper application, continue to be authorized for such operation, including expansion of existing systems, on the condition that harmful interference will not be caused to the operation of any authorized station in the maritime mobile service. No new land transportation radio service system will be authorized to operate on 161.61 MHz.

NG19 Fixed stations associated with the maritime mobile service may be authorized, for purposes of communication with coast stations, to use frequencies assignable to ship stations in this band on the condition that harmful interference will not be caused to services operating in accordance with the Table of Frequency Allocations.

NG23 Frequencies in the band 2100–2200 MHz may also be assigned to stations in the international fixed public radio service located south of 25°30' north latitude in the State of Florida and in U.S. Possessions in the Caribbean area, provided, however, no new assignments in the band 2150–2162 MHz will be made to such stations after February 25, 1974.

NG28 The frequency band 160.86–161.40 MHz is available for assignment to remote pickup base and remote pickup mobile stations in Puerto Rico and the Virgin Islands only on a shared basis with the land transportation radio service.

NG30 Stations in the international fixed public radiocommunication service in Florida, south of 25°30' north latitude, may be authorized to use frequencies in the band 716–

Federal Communications Commission

§2.106

890 MHz on the condition that harmful interference will not be caused to the broadcasting service of any country. This is an interim allocation the termination of which will later be specified by the Commission when it is determined that equipments are generally available for use in bands allocated internationally to the fixed service.

NG31 Stations in the Rural Radio Service licensed for Basic Exchange Telecommunications Radio Service may be authorized to use some frequencies in the bands 816–820 MHz (fixed subscriber) and 861–865 MHz (central office or base), on a co-primary basis with private land mobile radio licensees, pursuant to part 22 subpart H.

NG41 Frequencies in the bands 3700–4200 MHz, 5925–6425 MHz, and 10.7–11.7 GHz may also be assigned to stations in the international fixed public and international control services located in U.S. Possessions in the Caribbean area.

NG42 Non-Government stations in the radiolocation service shall not cause harmful interference to the amateur service.

NG43 Fixed stations in the domestic public radio services in Alaska, south of 56° north latitude and east of 134° west longitude, may be authorized to use frequencies in the band 800–830 MHz, on the condition that harmful interference will not be caused to the broadcasting service of any country.

NG47 In Alaska frequencies between the band 2655–2690 MHz are not available for assignment to terrestrial stations.

NG49 The following frequencies may be authorized for mobile operations in the Manufacturers Radio Service subject to the condition that no interference is caused to the reception of television stations operating on channels 4 and 5 and that their use is limited to a manufacturing facility:

MHz	
72.02	72.22
72.04	72.24
72.06	72.26
72.08	72.28
72.10	72.30
72.12	72.32
72.14	72.34
72.16	72.36
72.18	72.38
72.20	72.40

Further, the following frequencies may be authorized for mobile operations in the Special Industrial Radio Service, Manufacturers Radio Service, Railroad Radio Service and Forest Products Radio Service subject to the condition that no interference is caused to the reception of television stations operating on channels 4 and 5; and that their use is limited to a railroad yard, manufacturing plant, logging site, mill, or similar industrial facility.

MHz

72.44	75.44
72.48	75.48
72.52	75.52
72.56	75.56
72.60	75.60

NG51 In Puerto Rico and the Virgin Islands only, the bands 150.8–150.98 MHz and 150.98–151.49 MHz are allocated exclusively to the business radio service.

NG53 In the band 12.7–13.15 GHz, television pickup stations and CARS pickup stations shall be assigned channels on a co-equal basis and shall operate on a secondary basis to fixed stations operating in accordance with the Table of Frequency Allocations. In the 13.15–13.20 GHz band television pickup stations and CARS pickup stations shall be assigned on an exclusive basis in the top one hundred markets, as set out in Section 76.51.

NG56 In the bands 72.0–73.0 and 75.4–76.0 MHz, the use of mobile radio remote control of models is on a secondary basis to all other fixed and mobile operations. Such operations are subject to the condition that interference will not be caused to common carrier domestic public stations, to remote control of industrial equipment operating in the 72–76 MHz band, or to the reception of television signal on channels 4 (66–72 MHz) or 5 (76–82 MHz). Television interference shall be considered to occur whenever reception of regularly used television signals is impaired or destroyed, regardless of the strength of the television signal or the distance to the television station.

NG59 The frequencies 37.60 and 37.85 MHz may be authorized only for use by base, mobile, and operational fixed stations participating in an interconnected or coordinated power service utility system.

NG63 Television Broadcast translator stations holding valid licenses on November 15, 1971, to operate in the frequency band 806–890 MHz (channels 70–83), may continue to operate in this band, pursuant to periodic license renewals, on a secondary basis to the land mobile radio service.

NG66 The frequency band 470–512 MHz is allocated for use in the broadcasting and land mobile radio services. In the land mobile services, it is available for assignment in the domestic public, public safety, industrial, and land transportation radio services at, or in the vicinity of 11 urbanized areas of the United States, as set forth in the following table. Additionally, in the land mobile services, TV channel 16 is available for assignment in the public safety radio services at, or in the vicinity of, Los Angeles. Such use in the land mobile services is subject to the conditions set forth in parts 22 and 90 of this chapter.

Urbanized area	TV chan- nel
New York, NY-Northeastern New Jersey	14, 15
Los Angeles, CA	14, 20
Chicago, IL-Northwestern Indiana	14, 15
Philadelphia, PA-New Jersey	19, 20
San Francisco-Oakland, CA	16, 17
Boston, MA	14, 16
Washington, D.C.-Maryland-Virginia	17, 18
Pittsburgh, PA	14, 18
Miami, FL	14
Houston, TX	17
Dallas, TX	16

NG70 In Puerto Rico and the Virgin Islands only, the bands 159.240–159.435 and 160.410–160.620 MHz are also available for assignment to base stations and mobile stations in the special industrial radio service.

NG101 The use of the band 2500–2690 MHz by the broadcasting-satellite service is limited to domestic and regional systems for community reception of educational television programming and public service information. Such use is subject to agreement among administrations concerned and those having services operating in accordance with the table, which may be affected. Unless such agreement includes the use of higher values, the power flux density at the earth's surface produced by emissions from a space station in this service shall not exceed those values set forth in Part 73 of the rules for this frequency band.

NG102 The frequency bands 2500–2655 MHz (space-to-earth) and 2655–2690 MHz (earth-to-space) are allocated for use in the fixed-satellite service as follows:

(a) For common carrier use in Alaska, for intra-Alaska service only, and in the mid and western Pacific areas including American Samoa, the Trust Territory of the Pacific Islands, Guam and Hawaii;

(b) For educational use in the contiguous United States, Alaska and the mid and western Pacific areas including American Samoa, the Trust Territory of the Pacific Islands, Guam and Hawaii.

Such use is subject to agreement with administrations having services operating in accordance with the table, which may be affected. In the band 2500–2655 MHz, unless such agreement includes the use of higher values, the power flux density at the earth's surface produced by emissions from a space station in this service shall not exceed the values set forth in Part 25 of the Rules for this frequency band.

NG104 The use of the bands 10.7–11.7 and 12.75–13.25 GHz in the fixed-satellite service is limited to international systems, i.e., other than domestic systems.

NG111 The band 157.4375–157.4625 MHz may be used for one way paging operations in the special emergency radio service.

NG112 The frequencies 25.04, 25.08, 150.980, 154.585, 158.445, 159.480, 454.000 and 459.000 MHz

may be authorized to stations in the petroleum radio service for use primarily in oil spill containment and cleanup operations and secondarily in regular land mobile communication.

NG114 In the Gulf of Mexico offshore from the Louisiana-Texas coast, the frequency band 476–494 MHz (TV channels 15, 16 and 17) is allocated to the Domestic Public and Private Land Mobile Radio Services in accordance with the regulations set forth in parts 22 and 90 respectively.

NG115 In the 174 to 216 MHz band wireless microphones may be authorized to operate on a secondary, non-interfering basis, subject to terms and conditions set forth in part 74 of these Rules and Regulations.

NG117 The frequency 156.050 and 156.175 MHz may be assigned to stations in the maritime mobile service for commercial and port operations in the New Orleans Vessel Traffic Service (VTS) area and the frequency 156.250 MHz may be assigned to stations in the maritime mobile service for port operating in the New Orleans and Houston VTS areas.

NG118 Television translator relay stations may be authorized to use frequencies in the 2025–2130 MHz band on a secondary basis to stations operating in accordance with the Table of Frequency Allocations.

NG120 Frequencies in the 928–960 MHz band may be assigned for multiple address systems and mobile operations on a primary basis as specified in part 94 of this chapter.

NG124 In the public safety radio service allocations within the bands 30–50 MHz, 150–174 MHz and 450–470 MHz, police radio service licenses are authorized to operate low powered radio transmitters on a secondary, non-interference basis in accordance with the provisions of Sections 2.803 and 90.19(f)(5) of the Rules.

NG127 In Hawaii, the frequency band 488–494 MHz is allocated exclusively to the fixed service for use by common carrier control and repeater stations for point-to-point inter-island communications only.

NG128 In the 535–1705 kHz band, AM broadcast licensees or permittees may use their AM carrier on a secondary basis to transmit signals intended for both broadcast and non-broadcast purposes. In the 88–108 MHz band, FM broadcast licensees or permittees are permitted to use subcarriers on a secondary basis to transmit signals intended for both broadcast and non-broadcast purposes. In the 54–72, 76–88, 174–216 and 740–890 MHz bands, TV broadcast licensees or permittees are permitted to use subcarriers on a secondary basis for both broadcast and non-broadcast purposes.

NG129 In Alaska, the bands 76–88 MHz and 88–100 MHz are also allocated to the Fixed service on a secondary basis. Broadcast stations operating in these bands shall not cause interference to non-Government fixed

Federal Communications Commission

§2.106

operations authorized prior to January 1, 1982.

NG133 Stations authorized in the band 73–74.6 MHz as of December 1, 1961 may continue to operate until December 31, 1985. Such stations shall not be required to afford protection to radio astronomy observations within the United States and possessions, however, such stations must afford protection to the observatories of other countries.

NG134 In the band 10.45–10.5 GHz non-Government stations in the radiolocation service shall not cause harmful interference to the amateur and amateur-satellite services.

NG135 In the 420–430 MHz band the amateur service is not allocated north of line A (def. §2.1).

NG139 Pending adopting of further specific rules concerning usage of the band 12.2–12.7 GHz by the fixed and broadcasting-satellite services, systems in these services may be authorized subject to the condition that adjustments in certain systems design or technical parameters may become necessary during the systems lifetime. The necessity for such adjustments, and their extent, will be dependent upon the Final Acts of the 1983 Regional Administrative Radio Conference and subsequent Commission decisions.

NG140 Pending adopting of further specific rules concerning usage of the band 17.3–17.8 GHz by the fixed-satellite service for the purpose of providing feeder links to the broadcasting-satellite service, systems may be authorized for this purpose subject to the condition that adjustments in certain systems design or technical parameters may become necessary during the system lifetime. The necessity for such adjustments, and their extent, will be dependent upon the Final Acts of the 1983 Regional Administrative Radio Conference and subsequent Commission decisions.

NG141 The frequencies 42.40 MHz and 44.10 MHz are authorized on a primary basis in the State of Alaska for meteor burst communications by fixed stations in the Rural Radio Service operating under the provisions of part 22 of this chapter. The frequencies 44.20 MHz and 45.90 MHz are authorized on a primary basis in Alaska for meteor burst communications by fixed private radio stations operating under the provisions of part 90 of the chapter. The private radio station frequencies may be used by Common Carrier stations on a secondary, noninterference basis and the Common Carrier frequencies may be used by private radio stations for meteor burst communications on a secondary, noninterference basis. Users shall cooperate to the extent practical to minimize potential interference. Stations utilizing meteor burst communications shall not cause harmful interference to stations of other radio services operating in accordance with the Table of Frequency Allocations.

NG142 TV broadcast stations authorized to operate in the bands 54–72, 76–88, 174–216, 470–512, and 512–806 MHz may use a portion of the television vertical blanking interval for the transmission of telecommunications signals, on the condition that harmful interference will not be caused to the reception of primary services, and that such telecommunications services must accept any interference caused by primary services operating in these bands.

NG143 In the band 11.7–12.2 GHz protection from harmful interference shall be afforded to transmissions from space stations not in conformance with international footnote 839 only if the operations of such space stations impose no unacceptable constraints on operations or orbit locations of space stations in conformance with 839.

NG144 Stations authorized as of September 9, 1983 to use frequencies in the band 17.7–19.7 GHz may, upon proper application, continue to be authorized for such operation.

NG145 In the band 11.7–12.2 GHz, transponders on space stations in the fixed-satellite service may be used additionally for transmissions in the broadcasting-satellite service, provided that such transmissions do not have a maximum e.i.r.p. greater than 53 dBW per television channel and do not cause greater interference or require more protection from interference than the coordinated fixed-satellite service frequency assignments. With respect to the space services, this band shall be used principally for the fixed-satellite service.

NG147 Stations in the broadcast auxiliary service and private radio services licensed as of July 25, 1985, or on a subsequent date following as a result of submitting an application for license on or before July 25, 1985, may continue to operate on a primary basis with the radiodetermination satellite service.

NG148 The frequencies 154.585 MHz, 159.480 MHz, 160.725 MHz, 160.785 MHz, 454.000 MHz and 459.000 MHz may be authorized to maritime mobile stations for offshore radiolocation and associated telecommand operations.

NG149 The frequency bands 54–72 MHz, 76–88 MHz, 174–216 MHz, 470–512 MHz, 512–608 MHz, and 614–806 MHz are also allocated to the Fixed Service to permit subscription television operations in accordance with Part 73 of the rules.

NG151 In the frequency bands 824–849 MHz and 869–894 MHz, cellular land mobile licensees are permitted to offer auxiliary services on a secondary basis subject to the provisions of part 22.

NG152 The band 219–220 MHz is also allocated to the amateur service on a secondary basis for stations participating, as forwarding stations, in point-to-point fixed digital message forwarding systems, including intercity packet backbone networks.

NG153 The 2145–2150 MHz and 2160–2165 MHz bands are reserved for future emerging technologies on a co-primary basis with the fixed and mobile services. Allocations to specific services will be made in future proceedings.

NG154 The 157.1875–157.45 MHz and 161.775–162.0125 MHz bands are also allocated to the land mobile service for assignment to stations as described in part 90 of this chapter.

NG155 The bands 159.500–159.675 MHz and 161.375–161.550 MHz are allocated to the maritime service as described in Part 80 of this chapter. Additionally, the frequencies 159.550, 159.575 and 159.600 MHz are available for low-power intership communications.

GOVERNMENT (G) FOOTNOTES

(These footnotes, each consisting of the letter “G” followed by one or more digits, denote stipulations applicable only to the Government.)

G2 In the bands 216–225, 420–450 (except as provided by US217), 890–902, 928–942, 1300–1400, 2310–2390, 2417–2450, 2700–2900, 5650–5925, and 9000–9200 MHz, the Government radiolocation is limited to the military services.

G5 In the bands 162.0125–173.2, 173.4–174, 406.1–410 and 410–420 MHz, the fixed and mobile services are all allocated on a primary basis to the Government non-military agencies.

G6 Military tactical fixed and mobile operations may be conducted nationally on a secondary basis: (1) To the meteorological aids service in the band 403–406 MHz; and (2) to the radio astronomy service in the band 406.1–410 MHz. Such fixed and mobile operations are subject to local coordination to ensure that harmful interference will not be caused to the services to which the bands are allocated.

G8 Low power Government radio control operations are permitted in the band 420–450 MHz.

G11 Government fixed and mobile radio services, including low power radio control operations, are permitted in the band 902–928 MHz on a secondary basis.

G15 Use of the band 2700–2900 MHz by the military fixed and shipborne air defense radiolocation installations will be fully coordinated with the meteorological aids and aeronautical radionavigation services. The military air defense installations will be moved from the band 2700–2900 MHz at the earliest practicable date. Until such time as military air defense installations can be accommodated satisfactorily elsewhere in the spectrum, such operations will, insofar as practicable, be adjusted to meet the requirements of the aeronautical radionavigation service.

G19 Use of the band 9000–9200 MHz by military fixed and shipborne air defense radiolocation installations will be fully coordinated with the aeronautical radionavigation

service, recognizing fully the safety aspects of the latter. Military air defense installations will be accommodated ultimately outside this band. Until such time as military defense installations can be accommodated satisfactorily elsewhere in the spectrum such operations will, insofar as practicable, be adjusted to meet the requirements of the aeronautical radionavigation services.

G27 In the bands 225–328.6, 335.4–399.9, and 1350–1400 MHz, the fixed and mobile services are limited to the military services.

G30 In the bands 138–144, 148–149.9, 150.05–150.8, 1427–1429, and 1429–1435 MHz, the fixed and mobile services are limited primarily to operations by the military services.

G31 In the 3300–3500 MHz, the Government radiolocation is limited to the military services, except as provided by footnote.

G32 Except for weather radars on meteorological satellites in the band 9975–10025 MHz and for Government survey operations (see footnote US108), Government radiolocation in the band 10000–10500 MHz is limited to the military services.

G34 In the band 34.4–34.5 GHz, weather radars on board meteorological satellites for cloud detection are authorized to operate on the basis of equality with military radiolocation devices. All other non-military radiolocation in the band 33.4–36.0 GHz shall be secondary to the military services.

G42 Space command, control, range and range rate systems for earth station transmission only (including installations on certain Navy ships) may be accommodated on a co-equal basis with the fixed and mobile services in the band 1761–1842 MHz. Specific frequencies required to be used at any location will be satisfied on a coordinated case-by-case basis.

G56 Government radiolocation in the bands 1215–1300, 2900–3100, 5350–5650 and 9300–9500 MHz is primarily for the military services; however, limited secondary use is permitted by other Government agencies in support of experimentation and research programs. In addition, limited secondary use is permitted for survey operations in the band 2900–3100 MHz.

G59 In the bands 902–928 MHz, 3100–3300 MHz, 3500–3700 MHz, 5250–5350 MHz, 8500–9000 MHz, 9200–9300 MHz, 13.4–14.0 GHz, 15.7–17.7 GHz and 24.05–24.25 GHz, all Government non-military radiolocation shall be secondary to military radiolocation, except in the subband 15.7–16.2 GHz airport surface detection equipment (ASDE) is permitted on a co-equal basis subject to coordination with the military departments.

G100 The bands 235–322 MHz and 335.4–399.9 MHz are also allocated on a primary basis to the mobile-satellite service, limited to military operations.

G101 In the band 2200–2290 MHz, space operations (space-to-earth) and (space-to-space), and earth exploration-satellite

Federal Communications Commission

§2.106

(space-to-earth) and (space-to-space) services, may be accommodated on a co-equal basis with fixed, mobile and space research services.

G104 In the bands 7450–7550 and 8175–8215 MHz, it is agreed that although the military space radio communication systems, which include earth stations near the proposed meteorological-satellite installations will precede the meteorological-satellite installations, engineering adjustments to either the military or the meteorological-satellite systems or both will be made as mutually required to assure compatible operations of the systems concerned.

G106 The bands 2501–2502, 5003–5055 kHz, 10003–10005 kHz, 15005–15010 kHz, 19990–19995 kHz, 20005–20010 kHz and 25005–25010 kHz are also allocated on a secondary basis to the space research service. The space research transmissions are subject to immediate temporary or permanent shutdown in the event of interference to the reception of the standard frequency and time broadcasts.

G109 All assignments in the band 157.0375–157.1875 MHz are subject to adjustment to other frequencies in this band as long term U.S. maritime VHF planning develops, particularly that planning incident to support of the National VHF-FM Radiotelephone Safety and Distress System (See Doc. 15624/1–1.9.111/1.9.125).

G110 Government ground-based stations in the aeronautical radionavigation service may be authorized between 3500–3700 MHz where accommodation in the 2700–2900 MHz band is not technically and/or economically feasible.

G114 In the band 1350–1400 MHz, the frequency 1381.05 MHz with emissions limited to ± 12 MHz is also allocated to fixed and mobile satellite services (space-to-earth) for the relay of nuclear burst data.

G115 In the band 13360–13410 kHz, the fixed service is allocated on a primary basis outside the conterminous United States. Within the conterminous United States, assignments in the fixed service are permitted, and will be protected for national defense purposes or, if they are to be used only in an emergency jeopardizing life, public safety, or important property under conditions calling for immediate communication where other means of communication do not exist.

G116 The band 7125–7155 MHz is also allocated for earth-to-space transmissions in the Space Operations Service at a limited number of sites (not to exceed two), subject to established coordination procedures.

G117 In the bands 7.25–7.75 GHz, 7.9–8.4 GHz, 17.8–21.2 GHz, 30–31 GHz, 39.5–40.5 GHz, 43.5–45.5 GHz and 50.4–51.4 GHz the Government fixed-satellite and mobile-satellite services are limited to military systems.

G118 Government fixed stations may be authorized in the band 1700–1710 MHz only if

spectrum is not available in the band 1710–1850 MHz.

G119 In the band 14714.5–15136.5 MHz, assignments in the Fixed Service which were in existence as of January 1, 1982 may continue on a primary basis until January 1, 1990.

G120 Development of airborne primary radars in the band 2310–2390 MHz with peak transmitter power in excess of 250 watts for use in the United States is not permitted.

G122 The bands 2390–2400, 2402–2417 and 4660–4685 MHz were identified for immediate reallocation, effective August 10, 1994, for exclusive non-Government use under Title VI of the Omnibus Budget Reconciliation Act of 1993. Effective August 10, 1994, any Government operations in these bands are on a non-interference basis to authorized non-Government operations and shall not hinder the implementation of any non-Government operations.

G123 The bands 2300–2310 and 2400–2402 MHz were identified for reallocation, effective August 10, 1995, for exclusive non-Government use under Title VI of the Omnibus Budget Reconciliation Act of 1993. Effective August 10, 1995, any Government operations in these bands are on a non-interference basis to authorized non-Government operations and shall not hinder the implementation of any non-Government operations.

G124 The band 2417–2450 MHz was identified for reallocation, effective August 10, 1995, for mixed Government and non-Government use under Title VI of the Omnibus Budget Reconciliation Act of 1993.

[49 FR 2373, Jan. 19, 1984]

EDITORIAL NOTE 1: For FEDERAL REGISTER citations affecting §2.106, see the List of CFR Sections Affected in the Finding Aids section of this volume.

EDITORIAL NOTE 2: At 58 FR 27949, May 12, 1993, the following footnote US321 to the table in §2.106 was published. Footnote US321 was not codified due to ambiguities in the amendatory instructions. For the convenience of the reader footnote US321 as published at 58 FR 27949, May 12, 1993, is set forth below.

§2.106 Table of Frequency Allocations.

UNITED STATES (US) FOOTNOTES

* * * * *

US321 The 535–1705 kHz band is also allocated to the mobile service on a secondary basis for the distribution of public service information from non-government Travelers Information stations operation in the Local

§2.107

Government Radio Service on 10 kHz spaced channels from 540 to 1700 kHz.

* * * * *

EDITORIAL NOTE 3: At 59 FR 9417, Feb. 28, 1994, the following footnote NG147 to the table in §2.106 was published. Footnote NG147 was not codified due to ambiguities in the amendatory instructions. For the convenience of the reader footnote NG147 as published at 59 FR 9417, Feb. 28, 1994, is set forth below.

§2.106 Table of Frequency Allocations.

NON-GOVERNMENT (NG) FOOTNOTES

* * * * *

NG147 Stations in the broadcast auxiliary service and private radio services licensed as of July 25, 1985, or on a subsequent date following as a result of submitting an application for license on or before July 25, 1985, may continue to operate on a radiodetermination satellite service.

* * * * *

§2.107 Radio astronomy station notification.

(a) Pursuant to No. 1492 of Article 13 and Section F of Appendix 3 to the international *Radio Regulations* (Geneva, 1982), operators of radio astronomy stations desiring international recognition of their use of specific radio astronomy frequencies or bands of frequencies for reception, should file the following information with the Commission for inclusion in the Master International Frequency Register:

(1) The center of the frequency band observed, in kilohertz up to 28,000 kHz inclusive, in megahertz above 28,000 kHz to 10,500 MHz inclusive and in gigahertz above 10,500 MHz.

(2) The date (actual or foreseen, as appropriate) when reception of the frequency band begins.

(3) The name and location of the station, including geographical coordinates in degrees and minutes.

(4) The width of the frequency band (in kHz) observed by the station.

(5) The antenna type and dimensions, effective area and angular coverage in azimuth and elevation.

(6) The regular hours of reception (in UTC) of the observed frequency.

47 CFR Ch. I (10–1–97 Edition)

(7) The overall receiving system noise temperature (in kelvins) referred to the output of the receiving antenna.

(8) The class of observations to be taken. Class A observations are those in which the sensitivity of the equipment is not a primary factor. Class B observations are those of such a nature that they can be made only with advanced low-noise receivers using the best techniques.

(9) The name and mailing address of the operator.

(b) The permanent discontinuance of observations, or any change to the information above, should also be filed with the Commission.

(c) Observations being conducted on frequencies or frequency bands not allocated to the radio astronomy service should be reported as in paragraph (a) of this section for information purposes. Information in this category will not be submitted for entry in the Master International Frequency Register and protection from interference will not be afforded such operations by stations in other services.

§2.108 Policy regarding the use of the fixed-satellite allocations in the 3.6–3.7, 4.5–4.8, and 5.85–5.925 GHz bands.

The use of the fixed-satellite allocations in the United States in the above bands will be governed by footnote US245. Use of the fixed-satellite service allocations in these bands is for the international fixed-satellite service, that is, for international inter-continental communications. Case-by-case electromagnetic compatibility analysis is required with all users of the bands. It is anticipated that one earth station on each coast can be successfully coordinated. Specific locations of these earth stations depend upon service requirements and case-by-case EMC analyses that demonstrate compatible operations.

Subpart C—Emissions

§2.201 Emission, modulation, and transmission characteristics.

The following system of designating emission, modulation, and transmission characteristics shall be employed.

Federal Communications Commission

§ 2.201

(a) Emissions are designated according to their classification and their necessary bandwidth.

(b) A minimum of three symbols are used to describe the basic characteristics of radio waves. Emissions are classified and symbolized according to the following characteristics:

(1) First symbol—type of modulation of the main carrier;

(2) Second symbol—nature of signal(s) modulating the main carrier;

(3) Third symbol—type of information to be transmitted.

NOTE: A fourth and fifth symbol are provided for additional information and are shown in Appendix 6, part A of the ITU Radio Regulations. Use of the fourth and fifth symbol is optional. Therefore, the symbols may be used as described in Appendix 6, but are not required by the Commission.

(c) First Symbol—types of modulation of the main carrier:

(1) Emission of an unmodulated carrier	N
(2) Emission in which the main carrier is amplitude-modulated (including cases where sub-carriers are angle-modulated):	
—Double-sideband	A
—Single-sideband, full carrier	H
—Single-sideband, reduced or variable level carrier	R
—Single-sideband, suppressed carrier	J
—Independent sidebands	B
—Vestigial sideband	C
(3) Emission in which the main carrier is angle-modulated:	
—Frequency modulation	F
—Phase modulation	G

NOTE: Whenever frequency modulation “F” is indicated, Phase modulation “G” is also acceptable.

(4) Emission in which the main carrier is amplitude and angle-modulated either simultaneously or in a pre-established sequence ..	D
(5) Emission of pulses: ¹	
—Sequence of unmodulated pulses	P
—A sequence of pulses:	
—Modulated in amplitude	K
—Modulated in width/duration ..	L
—Modulated in position/phase ..	M

—In which the carrier is angle-modulated during the period of the pulse

—Which is a combination of the foregoing or is produced by other means

(6) Cases not covered above, in which an emission consists of the main carrier modulated, either simultaneously or in a pre-established sequence, in a combination of two or more of the following modes: amplitude, angle, pulse ...	W
(7) Cases not otherwise covered ...	X

(d) Second Symbol—nature of signal(s) modulating the main carrier:

(1) No modulating signal	0
(2) A single channel containing quantized or digital information without the use of a modulating sub-carrier, excluding time-division multiplex	1
(3) A single channel containing quantized or digital information with the use of a modulating sub-carrier, excluding time-division multiplex	2
(4) A single channel containing analogue information	3
(5) Two or more channels containing quantized or digital information	7
(6) Two or more channels containing analogue information	8
(7) Composite system with one or more channels containing quantized or digital information, together with one or more channels containing analogue information ...	9
(8) Cases not otherwise covered ...	X

(e) Third Symbol—type of information to be transmitted:²

(1) No information transmitted ...	N
(2) Telegraphy—for aural reception	A

¹Emissions where the main carrier is directly modulated by a signal which has been coded into quantized form (e.g. pulse code modulation) should be designated under (2) or (3).

²In this context the word “information” does not include information of a constant, unvarying nature such as is provided by standard frequency emissions, continuous wave and pulse radars, etc.

§2.202

47 CFR Ch. I (10–1–97 Edition)

- (3) Telegraphy—for automatic reception B
- (4) Facsimile C
- (5) Data transmission, telemetry, telecommand D
- (6) Telephony (including sound broadcasting) E
- (7) Television (video) F
- (8) Combination of the above W
- (9) Cases not otherwise covered ... X

(f) Type B emission: As an exception to the above principles, damped waves are symbolized in the Commission's rules and regulations as type B emission. The use of type B emissions is forbidden.

(g) Whenever the full designation of an emission is necessary, the symbol for that emission, as given above, shall be preceded by the necessary bandwidth of the emission as indicated in §2.202(b)(1).

[49 FR 48697, Dec. 14, 1984]

§2.202 Bandwidths.

(a) *Occupied bandwidth.* The frequency bandwidth such that, below its lower and above its upper frequency limits, the mean powers radiated are each equal to 0.5 percent of the total mean power radiated by a given emission. In some cases, for example multi-channel frequency-division systems, the percentage of 0.5 percent may lead to certain difficulties in the practical application of the definitions of occupied and necessary bandwidth; in such cases a different percentage may prove useful.

(b) *Necessary bandwidth.* For a given class of emission, the minimum value of the occupied bandwidth sufficient to ensure the transmission of information at the rate and with the quality required for the system employed, under specified conditions. Emissions useful for the good functioning of the receiving equipment as, for example, the emission corresponding to the carrier of reduced carrier systems, shall be included in the necessary bandwidth.

(1) The necessary bandwidth shall be expressed by three numerals and one letter. The letter occupies the position of the decimal point and represents the unit of bandwidth. The first character shall be neither zero nor K, M or G.

(2) Necessary bandwidths:

between 0.001 and 999 Hz shall be expressed in Hz (letter H);
between 1.00 and 999 kHz shall be expressed in kHz (letter K);
between 1.00 and 999 MHz shall be expressed in MHz (letter M);
between 1.00 and 999 GHz shall be expressed in GHz (letter G).

(3) Examples:

0.002 Hz—H002	180.4 kHz—180K
0.1 Hz—H100	180.5 kHz—181K
25.3 Hz—25H3	180.7 kHz—181K
400 Hz—400H	1.25 MHz—1M25
2.4 kHz—2K40	2 MHz—2M00
6 kHz—6K00	10 MHz—10M0
12.5 kHz—12K5	202 MHz—202M
	5.65 GHz—5G65

(c) The necessary bandwidth may be determined by one of the following methods:

(1) Use of the formulas included in the table, in paragraph (g) of this section, which also gives examples of necessary bandwidths and designation of corresponding emissions;

(2) For frequency modulated radio systems which have a substantially linear relationship between the value of input voltage to the modulator and the resulting frequency deviation of the carrier and which carry either single sideband suppressed carrier frequency division multiplex speech channels or television, computation in accordance with provisions of paragraph (f) of this section and formulas and methods indicated in the table, in paragraph (g) of this section;

(3) Computation in accordance with Recommendations of the International Radio Consultative Committee (C.C.I.R.);

(4) Measurement in cases not covered by paragraph (c) (1), (2), or (3) of this section.

(d) The value so determined should be used when the full designation of an emission is required. However, the necessary bandwidth so determined is not the only characteristic of an emission to be considered in evaluating the interference that may be caused by that emission.

(e) In the formulation of the table in paragraph (g) of this section, the following terms are employed:

B_n = Necessary bandwidth in hertz
B = Modulation rate in bauds

Federal Communications Commission

§ 2.202

N = Maximum possible number of black plus white elements to be transmitted per second, in facsimile

M = Maximum modulation frequency in hertz

C = Sub-carrier frequency in hertz

D = Peak frequency deviation, i.e., half the difference between the maximum and minimum values of the instantaneous frequency. The instantaneous frequency in hertz is the time rate of change in phase in radians divided by 2

t = Pulse duration in seconds at half-amplitude

t_r = Pulse rise time in seconds between 10% and 90% of maximum amplitude

K = An overall numerical factor which varies according to the emission and which depends upon the allowable signal distortion.

N_c = Number of baseband telephone channels in radio systems employing multichannel multiplexing

P = Continuity pilot sub-carrier frequency (Hz) (continuous signal utilized to verify performance of frequency-division multiplex systems).

(f) Determination of values of D and B_n for systems specified in paragraph (c)(2) of this section:

(1) Determination of D in systems for multichannel telephony:

(i) The rms value of the per-channel deviation for the system shall be specified. (In the case of systems employing preemphasis or phase modulation, this value of per-channel deviation shall be specified at the characteristic baseband frequency.)

(ii) The value of D is then calculated by multiplying the rms value of the per-channel deviation by the appropriate factors, as follows:

Number of message circuits	Multiplying factors	Limits of X (P_{avg} (dBmO))
More than 3, but less than 12	4.47 × [a factor specified by the equipment manufacturer or station licensee, subject to Commission approval].	
At least 12, but less than 60	$\frac{3.76 \text{ antilog } (X+2 \log_{10} N_c)}{20}$	X: -2 to +2.6.
At least 60, but less than 240	$\frac{3.76 \text{ antilog } (X+4 \log_{10} N_c)}{20}$	X: -5.6 to -1.0.
240 or more	$\frac{3.76 \text{ antilog } (X+10 \log_{10} N_c)}{20}$	X: -19.6 to -15.0.

Where X represents the average power in a message circuit in dBmO; N_c is the number of circuits in the multiplexed message load; 3.76 corresponds to a peak load factor of 11.5 dB.

(2) The necessary bandwidth (B_n) normally is considered to be numerically equal to:

(i) $2M+2DK$, for systems having no continuity pilot subcarrier or having a continuity pilot subcarrier whose frequency is not the highest modulating the main carrier;

(ii) $2P+2DK$, for systems having a continuity pilot subcarrier whose frequency exceeds that of any other signal modulating the main carrier, unless the conditions set forth in paragraph (f)(3) of this section are met.

(3) As an exception to paragraph (f)(2)(ii) of this section, the necessary bandwidth (B_n) for such systems is nu-

merically equal to $2P$ or $2M+2DK$, whichever is greater, provided the following conditions are met:

(i) The modulation index of the main carrier due to the continuity pilot subcarrier does not exceed 0.25, and

(ii) In a radio system of multichannel telephony, the rms frequency deviation of the main carrier due to the continuity pilot subcarrier does not exceed 70 percent of the rms value of the per-channel deviation, or, in a radio system for television, the rms deviation of the main carrier due to the pilot does not exceed 3.55 percent of the peak deviation of the main carrier.

(g) Table of necessary bandwidths:

Description of emission	Necessary bandwidth		Designation of emission
	Formula	Sample calculation	
I. NO MODULATING SIGNAL			
Continuous wave emission.			N0N (zero)
II. AMPLITUDE MODULATION			
1. Signal With Quantized or Digital Information			
Continuous wave telegraphy.	$B_n=BK$, $K=5$ for fading circuits, $K=3$ for non-fading circuits	25 words per minute; $B=20$, $K=5$, Bandwidth: 100 Hz	100HA1A
Telegraphy by on-off keying of a tone modulated carrier.	$B_n=BK+2M$, $K=5$ for fading circuits, $K=3$ for non-fading circuits	25 words per minute; $B=20$, $M=1000$, $K=5$, Bandwidth: 2100 Hz=2.1 kHz	2K10A2A
Selective calling signal, single-sideband full carrier.	$B_n=M$	Maximum code frequency is: 2110 Hz, $M=2110$, Bandwidth: 2110 Hz=2.11 kHz	2K11H2B
Direct-printing telegraphy using a frequency shifted modulating sub-carrier single-sideband suppressed carrier.	$B_n=2M+2DK$, $M=B+2$	$B=50$, $D=35$ Hz (70 Hz shift), $K=1.2$, Bandwidth: 134 Hz	134HJ2B
Telegraphy, single sideband reduced carrier.	$B_n=\text{central frequency}+M+DK$, $M=B+2$	15 channels; highest central frequency is: 2805 Hz, $B=100$, $D=42.5$ Hz (85 Hz shift), $K=0.7$ Bandwidth: 2.885 Hz=2.885 kHz	2K89R7B
2. Telephony (Commercial Quality)			
Telephony double-sideband.	$B_n=2M$	$M=3000$, Bandwidth=6000 Hz=6 kHz	6K00A3E
Telephony, single-sideband, full carrier.	$B_n=2M$	$M=3000$, Bandwidth: 3000 Hz=3 kHz	3K00H3E
Telephony, single-sideband suppressed carrier.	$B_n=M$ – lowest modulation frequency	$M=3000$, lowest modulation frequency is 3000 Hz, 2700 Hz Bandwidth: 2700Hz=2.7 kHz	2K70J3E
Telephony with separate frequency modulated signal to control the level of demodulated speech signal, single-sideband, reduced carrier.	$B_n=M$	Maximum control frequency is 2990 Hz, $M=2990$, Bandwidth: 2990 Hz=2.99 kHz	2K99R3E
Telephony with privacy, single-sideband, suppressed carrier (two or more channels).	$B_n=N_c$, M – lowest modulation frequency in the lowest channel	$N_c=2$, $M=3000$ lowest modulation frequency is 250 Hz, Bandwidth: 5750 Hz=5.75 kHz	5K75J8E
Telephony, independent sideband (two or more channels).	$B_n=\text{sum of } M \text{ for each sideband}$	2 channels, $M=3000$, Bandwidth: 6000 Hz=6 kHz	6K00B8E
3. Sound Broadcasting			
Sound broadcasting, double-sideband.	$B_n=2M$, M may vary between 4000 and 10000 depending on the quality desired	Speech and music, $M=4000$, Bandwidth: 8000 Hz= 8 kHz	8K00A3E
Sound broadcasting, single-sideband reduced carrier (single channel).	$B_n=M$, M may vary between 4000 and 10000 depending on the quality desired	Speech and music, $M=4000$, Bandwidth: 4000 Hz= 4 kHz	4K00R3E
Sound broadcasting, single-sideband, suppressed carrier.	$B_n=M$ – lowest modulation frequency	Speech and music, $M=4500$, lowest modulation frequency=50 Hz, Bandwidth: 4450 Hz=4.45 kHz	4K45J3E

Federal Communications Commission

§ 2.202

Description of emission	Necessary bandwidth		Designation of emission
	Formula	Sample calculation	
4. Television			
Television, vision and sound.	Refer to CCIR documents for the bandwidths of the commonly used television systems	Number of lines=525; Nominal video band- width: 4.2 MHz, Sound carrier relative to video carrier=4.5 MHz	5M75C3F
		Total vision bandwidth: 5.75 MHz; FM aural bandwidth including guardbands: 250,000 Hz	250KF3E
		Total bandwidth: 6 MHz	6M25C3F
5. Facsimile			
Analogue facsimile by sub-carrier frequency modulation of a single-sideband emission with reduced carrier.	$B_n=C-N+2+DK$, $K=1.1$ (typically)	$N=1100$, corresponding to an index of co- operation of 352 and a cyler rotation speed of 60 rpm. Index of cooperation is the product of the drum diameter and num- ber of lines per unit length $C=1900$, $D=400$ Hz, Bandwidth=2.890 Hz=2.89 kHz	2K89R3C
Analogue facsimile; fre- quency modulation of an audio frequency sub-carrier which mod- ulates the main car- rier, single-sideband suppressed carrier.	$B_n=2M+2DK$, $M=N/2$, $K=1.1$ (typi- cally)	$N=1100$, $D=400$ Hz, Bandwidth: 1980 Hz=1.98 kHz	1K98J3C
6. Composite Emissions			
Double-sideband, tele- vision relay.	$B_n=2C+2M+2D$	Video limited to 5 MHz, audio on 6.5 MHz fre- quency modulated subcarrier deviation=50 kHz: $C=6.5\times10^6$ $D=50\times10^3$ Hz, $M=15,000$, Bandwidth: 13.13×10^6 Hz=13.13 MHz	13M2A8W
Double-sideband radio relay system.	$B_n=2M$	10 voice channels occupying baseband be- tween 1 kHz and 164 kHz; $M=164,000$ bandwidth=328,000 Hz=328 kHz	328KA8E
Double-sideband emis- sion of VOR with voice (VOR=VHF omnidirectional radio range).	$B_n=2C_{max}+2M+2DK$, $K=1$ (typi- cally)	The main carrier is modulated by: —a 30 Hz sub-carrier—a carrier resulting from a 9960 Hz tone frequency modulated by a 30 Hz tone—a telephone channel—a 1020 Hz keyed tone for continual Morse identifica- tion. $C_{max}=9960$, $M=30$, $D=480$ Hz, Band- width: 20,940 Hz=20.94 kHz	20K9A9W
Independent sidebands; several telegraph channels together with several telephone channels.	$B_n=\text{sum of } M \text{ for each sideband}$	Normally composite systems are operated in accordance with standardized channel ar- rangements, (e.g. CCIR Rec. 348–2) 3 tele- phone channels and 15 telegraphy chan- nels require the bandwidth 12,000 Hz=12 kHz	12K0B9W

III-A. FREQUENCY MODULATION

1. Signal With Quantized or Digital Information

Telegraphy without error-correction (single channel).	$B_n = 2M + 2DK$, $M=B+2$, $K=1.2$ (typically)	$B=100$, $D=85$ Hz (170 Hz shift), Bandwidth: 304 Hz	304HF1B
Four-frequency duplex telegraphy.	$B_n = 2M + 2DK$, $B = \text{Modulation rate in bands of the faster channel. If the channels are synchronized: } M=B+2$, otherwise $M=2B$, $K=1.1$ (typically)	Spacing between adjacent frequencies=400 Hz; Synchronized channels; $B=100$, $M=50$, $D=600$ Hz, Bandwidth: 1420 Hz=1.42 kHz	1K42F7B

Description of emission	Necessary bandwidth		Designation of emission
	Formula	Sample calculation	
2. Telephony (Commercial Quality)			
Commercial telephony ...	$B_n=2M+2DK$, $K=1$ (typically, but under conditions a higher value may be necessary)	For an average case of commercial telephony, $M=3,000$, Bandwidth: 16,000 Hz=16 kHz	16K0F3E
3. Sound Broadcasting			
Sound broadcasting	$B_n=2M+2DK$, $K=1$ (typically)	Monaural, $D=75,000$ Hz, $M=15,000$, Bandwidth: 18,000 Hz=180 kHz	180KF3E
4. Facsimile			
Facsimile by direct frequency modulation of the carrier; black and white.	$B_n=2M+2DK$, $M=N+2$, $K=1.1$ (typically)	$N=1100$ elements/sec; $D=400$ Hz, Bandwidth: 1980 Hz=1.98 kHz	1K98F1C
Analogue facsimile	$B_n=2M+2DK$, $M=N+2$, $K=1.1$ (typically)	$N=1100$ elements/sec; $D=400$ Hz, Bandwidth: 1980 Hz=1.98 kHz	1K98F3C
5. Composite Emissions (See Table III–B)			
Radio-relay system, frequency division multiplex.	$B_n=2P+2DK$, $K=1$	Microwave radio relay system specifications: 60 telephone channels occupying baseband between 60 and 300 kHz; rms per-channel deviation 200 kHz; pilot at 331 kHz produces 200 kHz rms deviation of main carrier. Computation of B_n : $D=(200 \times 10^3 \times 3.76 \times 1.19)$, $\text{Hz}=0.895 \times 10^6$, $P=0.331 \times 10^6$ Hz; Bandwidth: 2.452×10^6 Hz	2M45F8E
Radio-relay system frequency division multiple.	$B_n=2M+2DK$, $K=1$	Microwave radio relay relay systems specifications: 1200 telephone channels occupying baseband between 60 and 5564 kHz; rms per channel deviation 200 kHz; continuity pilot at 6199 kHz produces 140 kHz rms deviation of main carrier. Computation of B_n : $D=(200 \times 10^3 \times 3.76 \times 3.63)=2.73 \times 10^6$; $M=5.64 \times 10^6$ Hz; $P=6.2 \times 10^6$ Hz; $(2M+2DK < 2P)$; Bandwidth 16.59×10^6 Hz	16M6F8E
Radio-relay system, frequency division multiplex.	$B_n=2P$	Microwave radio relay system specifications: Multiplex 600 telephone channels occupying baseband between 60 and 2540 kHz; continuity pilot at 8500 kHz produces 140 kHz rms deviation of main carrier. Computation of B_n : $D=(200 \times 10^3 \times 3.76 \times 2.565)=1.93 \times 10^6$ Hz; $M=2.54 \times 10^6$ Hz; $2DK \leq 2P$ Bandwidth: 17×10^6 Hz	17M0F8E
Unmodulated pulse emission.	$B_n=2K+t$, K depends upon the ratio of pulse rise time. Its value usually falls between 1 and 10 and in many cases it does not need to exceed 6	Primary Radar Range resolution: 150 m, $K=1.5$ (triangular pulse where $t \approx t_r$, only components down to 27 dB from the strongest are considered) Then $t=2 \times \text{range resolution} \div \text{velocity of light} = 2 \times 150 \div 3 \times 10^8 = 1 \times 10^{-6}$ seconds, Bandwidth: 3×10^6 Hz=3 MHz	3M00P0N
6. Composite Emissions			
Radio-relay system	$B_n=2K+t$, $K=1.6$	Pulse position modulated by 36 voice channel baseband; pulse width at half amplitude=0.4 us, Bandwidth: 8×10^6 Hz=8 MHz (Bandwidth independent of the number of voice channels)	8M00M7E

Federal Communications Commission

§ 2.302

[28 FR 12465, Nov. 22, 1963, as amended at 37 FR 8883, May 2, 1972; 37 FR 9996, May 18, 1972; 48 FR 16492, Apr. 18, 1983; 49 FR 48698, Dec. 14, 1984]

Subpart D—Call Signs and Other Forms of Identifying Radio Transmissions

AUTHORITY: Secs. 4, 5, 303, 48 Stat., as amended, 1066, 1068, 1082; 47 U.S.C. 154, 155, 303.

§ 2.301 Station identification requirement.

Each station using radio frequencies shall identify its transmissions according to the procedures prescribed by the rules governing the class of station to which it belongs with a view to the elimination of harmful interference and the general enforcement of applicable radio treaties, conventions, regulations, arrangements, and agreements in force, and the enforcement of the Communications Act of 1934, as amended, and the Commission's rules.

[34 FR 5104, Mar. 12, 1969]

§ 2.302 Call signs.

The table which follows indicates the composition and blocks of international call signs available for assignment when such call signs are required by the rules pertaining to particular classes of stations. When stations operating in two or more classes are authorized to the same licensee for the same location, the Commission may elect to assign a separate call sign to each station in a different class. (In addition to the U.S. call sign allocations listed below, call sign blocks AAA through AEZ and ALA through ALZ have been assigned to the Department of the Army; call sign block AFA through AKZ has been assigned to the Department of the Air Force; and call sign block NAA through NZZ has been assigned jointly to the Department of the Navy and the U.S. Coast Guard.

Class of station	Composition of call sign	Call sign blocks
Coast (Class I) except for coast telephone in Alaska.	3 letters	KAA through KZZ. WAA through WZZ.
Coast (Classes II and III) and maritime radio-determination.	3 letters, 3 digits	KAA200 through KZZ999. WAA200 through WZZ999.
Coast telephone in Alaska	3 letters, 2 digits. 3 letters, 3 digits (for stations assigned frequencies above 30 MHz).	KAA20 through KZZ99. WAA20 through WZZ99. WZZ200 through WZZ999.
Fixed	3 letters, 2 digits	KAA20 through KZZ99.
	3 letters, 3 digits (for stations assigned frequencies above 30 MHz).	WAA20 through WZZ99. WAA200 through WZZ999.
Marine receiver test	3 letters, 3 digits (plus general geographic location when required).	KAA200 through KZZ999. WAA200 through WZZ999.
Ship telegraph	4 letters ¹	KAAA through KZZZ. WAAA through WZZZ.
Ship telephone	2 letters, 4 digits, or 3 letters, 4 digits ¹	WA2000 through WZ9999, through WZZ9999.
Ship telegraph plus telephone	4 letters	KAAA through KZZZ. WAAA through WZZZ.
Ship radar	Same as ship telephone and/or telegraph call sign, or, if ship has no telephone or telegraph: 2 letters, 4 digits, or 3 letters, 4 digits.	WA2000 through WZ9999, through WZZ9999.
Ship survival craft	Call sign of the parent ship followed by 2 digits.	KAAA20 through KZZZ99. WAAA20 through WZZZ99.
Cable-repair ship marker buoy	Call sign of the parent ship followed by the letters "BT" and the identifying number of the buoy.	
Marine utility	2 letters, 4 digits	KA2000 through KZ9999.
Shipyard mobile	2 letters, 4 digits	KA2000 through KZ9999.
Aircraft telegraph	5 letters	KAAAA through KZZZZ. WAAAA through WZZZZ.
Aircraft telegraph and telephone	5 letters ²	KAAAA through KZZZZ. WAAAA through WZZZZ.
Aircraft telephone	5 letters ² (whenever a call sign is assigned).	KAAAA through KZZZZ. WAAAA through WZZZZ.

§ 2.302

47 CFR Ch. I (10–1–97 Edition)

Class of station	Composition of call sign	Call sign blocks
Aircraft survival craft	Whenever a call sign ² is assigned, call sign of the parent aircraft followed by a single digit other than 0 or 1.	
Aeronautical	3 letters, 1 digit ²	KAA2 through KZZ9. WAA2 through WZZ9.
Land mobile (base)	3 letters, 3 digits	KAA200 through KZZ999. WAA200 through WZZ999
Land mobile (mobile telegraph)	4 letters, 1 digit	KAAA2 through KZZZ9. WAAA2 through WZZZ9.
Land mobile (mobile telephone)	2 letters, 4 digits	KA2000 through KZ9999. WA2000 through WZ9999
Broadcasting (standard)	4 letters ³ (plus location of station)	KAAA through KZZZ. WAAA through WZZZ.
Broadcasting (FM)	4 letters (plus location of station)	KAAA through KZZZ. WAAA through WZZZ.
Broadcasting with suffix "FM"	6 letters ³ (plus location of station)	KAAA-FM through KZZZ-FM. WAAA-FM through WZZZ-FM.
Broadcasting (television)	4 letters (plus location of station)	KAAA through KZZZ. WAAA through WZZZ.
Broadcasting with suffix "TV"	6 letters ³ (plus location of station)	KAAA-TV through KZZZ-TV. WAAA-TV through WZZZ-TV.
Television broadcast translator	1 letter—output channel number—2 letters.	K02AA through K83ZZ. W02AA through W83ZZ.
Disaster station, except U.S. Government	4 letters, 1 digit	KAAA2 through KZZZ9. WAAA2 through WZZZ9.
Experimental (letter "X" follows the digit)	2 letters, 1 digit, 3 letters	KA2XAA through KZ9XZZ. WA2XAA through WZ9XZZ.
Amateur (letter "X" may not follow digit)	1 letter, 1 digit, 1 letter ⁴	K1A through K0Z. N1A through N0Z. W1A through W0Z.
Amateur	1 letter, 1 digit, 2 letters ⁴	K1AA through K0ZZ. N1AA through N0ZZ. W1AA through W0ZZ.
Do	1 letter, 1 digit, 3 letters ⁴	K1AAA through K0ZZZ. N1AAA through N0ZZZ. W1AAA through W0ZZZ.
Do	2 letters, 1 digit, 1 letter ⁴	AA1A through A10Z. KA1A through KZ0Z. NA1A through NZ0Z. WA1A through WZ0Z.
Do	2 letters, 1 digit, 2 letters ⁴	AA1AA through ALOZZ. KA1AA through KZ0ZZ. NA1AA through NZ0ZZ. WA1AA through WZ0ZZ.
Amateur (letter "X" may not follow digit)	2 letters, 1 digit, 3 letters ⁴	AA1AAA through ALOZZZ. KA1AAA through KZ0ZZZ. NA1AAA through NZ0ZZZ. WA1AAA through WZ0ZZZ.
Standard frequency		WWV, WWVB through WWV1, WWVL, WWVS.
Personal radio	3 letters, 4 digits, or 4 letters, 4 digits.	KAA0001 through KZZ9999. WAA0001 through WPZ9999. KAAA0001 through KZZZ9999.
Personal radio, temporary permit	3 letters, 5 digits	KAA00000 through KZZ99999.
Personal radio in trust territories.	1 letter, 4 digits	K0001 through K9999.
Business radio temporary permit	2 letters, 7 digits	WT plus local telephone number.
Part 90 temporary permit	2 letters, 7 digits	WT plus local telephone number.
Part 90 conditional permit	2 letters, 7 digits	WT plus local telephone number.
General Mobile Radio Service, temporary permit.	2 letters, 7 digits	WT plus business or residence telephone number.

NOTE: The symbol 0 indicates the digit zero.

¹ Ships with transmitter-equipped survival craft shall be assigned four letter call signs.

² See § 2.303.

³ A 3 letter call sign now authorized for and in continuous use by a licensee of a standard broadcasting station may continue to be used by that station. The same exception applies also to frequency modulation and television broadcasting stations using 5 letter call signs consisting of 3 letters with the suffix "FM" or "TV".

⁴ Plus other identifying data as may be specified.

[34 FR 5104, Mar. 12, 1969; as amended at 54 50239, Dec. 5, 1989]

EDITORIAL NOTE: For FEDERAL REGISTER citations affecting § 2.302, see the List of CFR Sections Affected in the Finding Aids section of this volume.

Federal Communications Commission

§ 2.303

§ 2.303 Other forms of identification of stations.

(a) The following table indicates forms of identification which may be used in lieu of call signs by the specified classes of stations. Such recognized means of identification may be one or more of the following: name of station, location of station, operating agency, official registration mark,

flight identification number, selective call number or signal, selective call identification number or signal, characteristic signal, characteristic of emission or other clearly distinguishing form of identification readily recognized internationally. Reference should be made to the appropriate part of the rules for complete information on identification procedures for each service.

<i>Class of station</i>	<i>Identification, other than assigned call sign</i>
Aircraft (U.S. registry) telephone	Registration number preceded by the type of the aircraft, or the radiotelephony designator of the aircraft operating agency followed by the flight identification number.
Aircraft (foreign registry) telephone	Foreign registry identification consisting of five characters. This may be preceded by the radiotelephony designator of the aircraft operating agency or it may be preceded by the type of the aircraft.
Aeronautical	Name of the city, area, or airdrome served together with such additional identification as may be required.
Aircraft survival craft	Appropriate reference to parent aircraft, e.g., the air carrier parent aircraft flight number or identification, the aircraft registration number, the name of the aircraft manufacturer, the name of the aircraft owner, or any other pertinent information.
Ship telegraph	When an official call sign is not yet assigned: Complete name of the ship and name of licensee. On 156.65 MHz: Name of ship. Digital selective call.
Ship telegraph	Digital selective call.
Public coast (radiotelephone) and Limited Coast (Radiotelephone)	The approximate geographic location in a format approved by the Commission.
Public coast (radiotelegraph)	Coast station identification number.
Fixed	Coast station identification number.
Fixed: Rural subscriber service	Geographic location. When an approved method of superimposed identification is used, QTT DE (abbreviated name of company or station).
Land mobile: Public safety, forestry conservation, highway maintenance, local government, shipyard, land transportation, and aviation services.	Assigned telephone number.
Land mobile: Industrial service	Name of station licensee (in abbreviated form if practicable), or location of station, or name of city, area, or facility served. Individual stations may be identified by additional digits following the more general identification.
Land mobile: Domestic public and rural radio	Mobile unit cochannel with its base station: Unit identifier on file in the base station records. Mobile unit not cochannel with its base station: Unit identifier on file in the base station records and the assigned call sign of either the mobile or base station. Temporary base station: Unit designator in addition to base station identification.
Land mobile: Railroad radio service	Special mobile unit designation assigned by licensee or by assigned telephone number.
Land mobile: Broadcasting (remote pickup)	Name of railroad, train number, caboose number, engine number, or name of fixed wayside station or such other number or name as may be specified for use of railroad employees to identify a specific fixed point or mobile unit. A railroad's abbreviated name or initial letters may be used where such are in general usage. Unit designators may be used in addition to the station identification to identify an individual unit or transmitter of a base station.
Broadcasting (Emergency Broadcast System)	Identification of associated broadcasting station.
Broadcasting (aural STL and intercity relay) ...	State and operational area identification.
Broadcasting (television auxiliary)	Call sign of the broadcasting station with which it is associated.
Broadcasting (television booster).	Call sign of the TV broadcasting station with which it is licensed as an auxiliary, or call sign of the TV broadcasting station whose signals are being relayed, or by network identification.
Disaster station	Retransmission of the call sign of the primary station.
	By radiotelephony: Name, location, or other designation of station when same as that of an associated station in some other service. Two or more separate units of a station operated at different locations are separately identified by the addition of a unit name, number, or other designation at the end of its authorized means of identification.

(b) Digital selective calls will be authorized by the Commission and will be formed by groups of numbers (0

through 9), however, the first digit must be other than 0, as follows:

§ 2.401

(1) Coast station identification number: 4 digits.

(2) Ship station selective call number: 5 digits.

(3) Predetermined group of ship stations: 5 digits.

(c) Ship stations operating under a temporary operating authority shall identify by a call sign consisting of the letter “K” followed by the vessel’s Federal or State registration number, or a call sign consisting of the letters “KUS” followed by the vessel’s documentation number. However, if the vessel has no registration number or documentation number, the call sign shall consist of the name of the vessel and the name of the licensee as they appear on the station application form.

[28 FR 12465, Nov. 22, 1963, as amended at 40 FR 57675, Dec. 11, 1975; 41 FR 44042, Oct. 6, 1976; 42 FR 31008, June 17, 1977; 44 FR 62284, Oct. 30, 1979]

Subpart E—Distress, Disaster, and Emergency Communications

§ 2.401 Distress messages.

Each station licensee shall give absolute priority to radiocommunications or signals relating to ships or aircraft in distress; shall cease all sending on frequencies which will interfere with hearing a radiocommunication or signal of distress and except when engaged in answering or aiding the ship or aircraft in distress, shall refrain from sending any radiocommunications or signals until there is assurance that no interference will be caused with the radiocommunications or signals relating thereto; and shall assist the ship or aircraft in distress, so far as possible, by complying with its instructions.

§ 2.402 Control of distress traffic.

The control of distress traffic is the responsibility of the mobile station in distress or of the mobile station which, by the application of the provisions of § 2.403, has sent the distress call. These stations may, however, delegate the control of the distress traffic to another station.

§ 2.403 Retransmission of distress message.

Any station which becomes aware that a mobile station is in distress may transmit the distress message in the following cases:

(a) When the station in distress is not itself in a position to transmit the message.

(b) In the case of mobile stations, when the master or the person in charge of the ship, aircraft, or other vehicles carrying the station which intervenes believes that further help is necessary.

(c) In the case of other stations, when directed to do so by the station in control of distress traffic or when it has reason to believe that a distress call which it has intercepted has not been received by any station in a position to render aid.

§ 2.404 Resumption of operation after distress.

No station having been notified to cease operation shall resume operation on frequency or frequencies which may cause interference until notified by the station issuing the original notice that the station involved will not interfere with distress traffic as it is then being routed or until the receipt of a general notice that the need for handling distress traffic no longer exists.

§ 2.405 Operation during emergency.

The licensee of any station (except amateur, standard broadcast, FM broadcast, noncommercial educational FM broadcast, or television broadcast) may, during a period of emergency in which normal communication facilities are disrupted as a result of hurricane, flood, earthquake, or similar disaster, utilize such station for emergency communication service in communicating in a manner other than that specified in the instrument of authorization: *Provided:*

(a) That as soon as possible after the beginning of such emergency use, notice be sent to the Commission at Washington, D.C., and to the Engineer in Charge of the district in which the station is located, stating the nature of the emergency and the use to which the station is being put, and

Federal Communications Commission

§ 2.801

(b) That the emergency use of the station shall be discontinued as soon as substantially normal communication facilities are again available, and

(c) That the Commission at Washington, D.C., and the Engineer in Charge shall be notified immediately when such special use of the station is terminated: *Provided further,*

(d) That in no event shall any station engage in emergency transmission on frequencies other than, or with power in excess of, that specified in the instrument of authorization or as otherwise expressly provided by the Commission, or by law: *And provided further,*

(e) That any such emergency communication undertaken under this section shall terminate upon order of the Commission.

NOTE: Part 73 of this chapter contains provisions governing emergency operation of standard, FM, noncommercial educational FM, and television broadcast stations. Part 97 of this chapter contains such provisions for amateur stations.

[28 FR 13785, Dec. 18, 1963]

§ 2.406 National defense; free service.

Any common carrier subject to the Communications Act may render to any agency of the United States Government free service in connection with the preparation for the national defense. Every such carrier rendering any such free service shall make and file, in duplicate, with the Commission, on or before the 31st day of July and on or before the 31st day of January in each year, reports covering the periods of 6 months ending on the 30th day of June and the 31st day of December, respectively, next prior to said dates. These reports shall show the names of the agencies to which free service was rendered pursuant to this rule, the general character of the communications handled for each agency, and the charges in dollars which would have accrued to the carrier for such service rendered to each agency if charges for all such communications had been collected at the published tariff rates.

§ 2.407 National defense; emergency authorization.

The Federal Communications Commission may authorize the licensee of any radio station during a period of national emergency to operate its facilities upon such frequencies, with such power and points of communication, and in such a manner beyond that specified in the station license as may be requested by the Army, Navy, or Air Force.

Subparts F–G [Reserved]

Subpart H—Prohibition Against Eavesdropping

§ 2.701 Prohibition against use of a radio device for eavesdropping.

(a) No person shall use, either directly or indirectly, a device required to be licensed by section 301 of the Communications Act of 1934, as amended, for the purpose of overhearing or recording the private conversations of others unless such use is authorized by all of the parties engaging in the conversation.

(b) Paragraph (a) of this section shall not apply to operations of any law enforcement officers conducted under lawful authority.

[31 FR 3400, Mar. 4, 1966]

Subpart I—Marketing of Radio-frequency Devices

SOURCE: 35 FR 7898, May 22, 1970, unless otherwise noted.

§ 2.801 Radiofrequency device defined.

As used in this part, a radiofrequency device is any device which in its operation is capable of emitting radiofrequency energy by radiation, conduction, or other means. Radiofrequency devices include, but are not limited to:

(a) The various types of radio communication transmitting devices described throughout this chapter.

(b) The incidental, unintentional and intentional radiators defined in part 15 of this chapter.

§ 2.803

47 CFR Ch. I (10–1–97 Edition)

(c) The industrial, scientific, and medical equipment described in part 18 of this chapter.

(d) Any part or component thereof which in use emits radiofrequency energy by radiation, conduction, or other means.

[35 FR 7898, May 22, 1970, as amended at 54 FR 17711, Apr. 25, 1989]

§ 2.803 Marketing of radio frequency devices prior to equipment authorization.

(a) Except as provided elsewhere in this section, no person shall sell or lease, or offer for sale or lease (including advertising for sale or lease), or import, ship, or distribute for the purpose of selling or leasing or offering for sale or lease, any radio frequency device unless:

(1) In the case of a device subject to type acceptance, certification, or notification, such device has been authorized by the Commission in accordance with the rules in this chapter and is properly identified and labelled as required by § 2.925 and other relevant sections in this chapter; or

(2) In the case of a device that is not required to have a grant of equipment authorization issued by the Commission, but which must comply with the specified technical standards prior to use, such device also complies with all applicable administrative (including verification of the equipment or authorization under a Declaration of Conformity, where required), technical, labelling and identification requirements specified in this chapter.

(b) The provisions of paragraph (a) of this section do not prohibit conditional sales contracts between manufacturers and wholesalers or retailers where delivery is contingent upon compliance with the applicable equipment authorization and technical requirements, nor do they prohibit agreements between such parties to produce new products, manufactured in accordance with designated specifications.

(c) Notwithstanding the provisions of paragraphs (a), (b), (d) and (f) of this section, a radio frequency device may be advertised or displayed, e.g., at a trade show or exhibition, prior to equipment authorization or, for devices not subject to the equipment author-

ization requirements, prior to a determination of compliance with the applicable technical requirements *provided* that the advertising contains, and the display is accompanied by, a conspicuous notice worded as follows:

This device has not been authorized as required by the rules of the Federal Communications Commission. This device is not, and may not be, offered for sale or lease, or sold or leased, until authorization is obtained.

(1) If the product being displayed is a prototype of a product that has been properly authorized and the prototype, itself, is not authorized due to differences between the prototype and the authorized product, the following disclaimer notice may be used in lieu of the notice stated in paragraph (c) introductory text of this section:

Prototype. Not for sale.

(2) Except as provided elsewhere in this chapter, devices displayed under the provisions of paragraphs (c) introductory text, and (c)(1) of this section may not be activated or operated.

(d) Notwithstanding the provisions of paragraph (a) of this section, the offer for sale solely to business, commercial, industrial, scientific or medical users (but not an offer for sale to other parties or to end users located in a residential environment) of a radio frequency device that is in the conceptual, developmental, design or pre-production stage is permitted prior to equipment authorization or, for devices not subject to the equipment authorization requirements, prior to a determination of compliance with the applicable technical requirements *provided* that the prospective buyer is advised in writing at the time of the offer for sale that the equipment is subject to the FCC rules and that the equipment will comply with the appropriate rules before delivery to the buyer or to centers of distribution. If a product is marketed in compliance with the provisions of this paragraph, the product does not need to be labelled with the statement in paragraph (c) of this section.

(e)(1) Notwithstanding the provisions of paragraph (a) of this section, prior

to equipment authorization or determination of compliance with the applicable technical requirements any radio frequency device may be operated, but not marketed, for the following purposes and under the following conditions:

- (i) Compliance testing;
- (ii) Demonstrations at a trade show provided the notice contained in paragraph (c) of this section is displayed in a conspicuous location on, or immediately adjacent to, the device;
- (iii) Demonstrations at an exhibition conducted at a business, commercial, industrial, scientific, or medical location, but excluding locations in a residential environment, provided the notice contained in paragraphs (c) or (d) of this section, as appropriate, is displayed in a conspicuous location on, or immediately adjacent to, the device;
- (iv) Evaluation of product performance and determination of customer acceptability, provided such operation takes place at the manufacturer's facilities during developmental, design, or pre-production states; or
- (v) Evaluation of product performance and determination of customer acceptability where customer acceptability of a radio frequency device cannot be determined at the manufacturer's facilities because of size or unique capability of the device, provided the device is operated at a business, commercial, industrial, scientific, or medical user's site, but not at a residential site, during the development, design or pre-production stages. A product operated under this provision shall be labelled, in a conspicuous location, with the notice in paragraph (c) of this section.

(2) For the purpose of paragraphs (e)(1)(iv) and (e)(1)(v) of this section, the term *manufacturer's facilities* includes the facilities of the party responsible for compliance with the regulations and the manufacturer's premises, as well as the facilities of other entities working under the authorization of the responsible party in connection with the development and manufacture, but not marketing, of the equipment.

(3) The provisions of paragraphs (e)(1)(i), (e)(1)(ii), (e)(1)(iii), (e)(1)(iv), and (e)(1)(v) of this section do not

eliminate any requirements for station licenses for products that normally require a license to operate, as specified elsewhere in this chapter. Manufacturers should note that station licenses are not required for some products, e.g., products operating under part 15 of this chapter and certain products operating under part 95 of this chapter.

(4) Marketing, as used in this section, includes sale or lease, or offering for sale or lease, including advertising for sale or lease, or importation, shipment, or distribution for the purpose of selling or leasing or offering for sale or lease.

(5) Products operating under the provisions of this paragraph (e) shall not be recognized to have any vested or recognizable right to continued use of any frequency. Operation is subject to the conditions that no harmful interference is caused and that any interference received must be accepted. Operation shall be required to cease upon notification by a Commission representative that the device is causing harmful interference and shall not resume until the condition causing the harmful interference is corrected.

(f) For radio frequency devices subject to verification and sold solely to business, commercial, industrial, scientific, and medical users (excluding products sold to other parties or for operation in a residential environment), parties responsible for verification of the devices shall have the option of ensuring compliance with the applicable technical specifications of this chapter at each end user's location after installation, provided that the purchase or lease agreement includes a proviso that such a determination of compliance be made and is the responsibility of the party responsible for verification of the equipment. If the purchase or lease agreement contains this proviso and the responsible party has the product measured to ensure compliance at the end user's location, the product does not need to be labelled with the statement in paragraph (c) of this section.

(g) The provisions in paragraphs (b) through (f) of this section apply only to devices that are designed to comply with, and to the best of the responsible party's knowledge will, upon testing,

§2.807

comply with all applicable requirements in this chapter. The provisions in paragraphs (b) through (f) of this section do not apply to radio frequency devices that could not be authorized or legally operated under the current rules. Such devices shall not be operated, advertised, displayed, offered for sale or lease, sold or leased, or otherwise marketed absent a license issued under part 5 of this chapter or a special temporary authorization issued by the Commission.

(h) The provisions in subpart K of this part continue to apply to imported radio frequency devices.

[62 FR 10468, Mar. 7, 1997]

§2.807 Statutory exceptions.

As provided by Section 302(c) of the Communications Act of 1934, as amended, §2.803 shall not be applicable to:

(a) Carriers transporting radio-frequency devices without trading in them.

(b) Radiofrequency devices manufactured solely for export.

(c) The manufacture, assembly, or installation of radiofrequency devices for its own use by a public utility engaged in providing electric service: *Provided, however,* That no such device shall be operated if it causes harmful interference to radio communications.

(d) Radiofrequency devices for use by the Government of the United States or any agency thereof: *Provided, however,* That this exception shall not be applicable to any device after it has been disposed of by such Government or agency.

[35 FR 7898, May 22, 1970, as amended at 62 FR 10470, Mar. 7, 1997]

§2.811 Transmitters operated under part 73 of this chapter.

Section 2.803(a) through (d) shall not be applicable to a transmitter operated in any of the Radio Broadcast Services regulated under part 73 of this chapter, provided the conditions set out in part 73 of this chapter for the acceptability of such transmitter for use under licensing are met.

[62 FR 10470, Mar. 7, 1997]

47 CFR Ch. I (10–1–97 Edition)

§2.813 Transmitters operated in the Instructional Television Fixed Service.

Section 2.803 (a) through (d) shall not be applicable to a transmitter operated in the Instructional Television Fixed Service regulated under part 74 of this chapter, provided the conditions in §74.952 of this chapter for the acceptability of such transmitter for licensing are met.

[62 FR 10470, Mar. 7, 1997]

§2.815 External radio frequency power amplifiers.

(a) As used in this part, an external radio frequency power amplifier is any device which, (1) when used in conjunction with a radio transmitter as a signal source is capable of amplification of that signal, and (2) is not an integral part of a radio transmitter as manufactured.

(b) After April 27, 1978, no person shall manufacture, sell or lease, offer for sale or lease (including advertising for sale or lease), or import, ship, or distribute for the purpose of selling or leasing or offering for sale or lease, any external radio frequency power amplifier or amplifier kit capable of operation on any frequency or frequencies between 24 and 35 MHz.

NOTE: For purposes of this part, the amplifier will be deemed incapable of operation between 24 and 35 MHz if:

(1) The amplifier has no more than 6 decibels of gain between 24 and 26 MHz and between 28 and 35 MHz. (This gain is determined by the ratio of the input RF driving signal (mean power measurement) to the mean RF output power of the amplifier.); and

(2) The amplifier exhibits no amplification (0 decibels of gain) between 26 and 28 MHz.

(c) No person shall manufacture, sell or lease, offer for sale or lease (including advertising for sale or lease) or import, ship or distribute for the purpose of selling or leasing or offering for sale or lease, any external radio frequency power amplifier or amplifier kit capable of operation on any frequency or frequencies below 144 MHz unless the amplifier has received a grant of type acceptance in accordance with subpart J of this part and subpart C of part 97 or other relevant parts of this chapter.

Federal Communications Commission

§ 2.902

No more than 10 external radio frequency power amplifiers or amplifier kits may be constructed for evaluation purposes in preparation for the submission of an application for a grant of type acceptance.

NOTE: For the purposes of this part, an amplifier will be deemed incapable of operation below 144 MHz if the amplifier is not capable of being easily modified to increase its amplification characteristics below 120 MHz, and either:

(1) The mean output power of the amplifier decreases, as frequency decreases from 144 MHz, to a point where 0 decibels or less gain is exhibited at 120 MHz and below 120 MHz; or

(2) The amplifier is not capable of even short periods of operation below 120 MHz without sustaining permanent damage to its amplification circuitry.

(d) The proscription in paragraph (b) of this section shall not apply to the marketing, as defined in paragraph (b) of this section, by a licensed amateur radio operator to another licensed amateur radio operator of an external radio frequency power amplifier fabricated in not more than one unit of the same model in a calendar year by that operator provided the amplifier is for the amateur operator's personal use at his licensed amateur radio station and the requirements of §§97.315 and 97.317 of this chapter are met.

(e) The proscription in paragraph (c) of this section shall not apply in the marketing, as defined in paragraph (c) of this section, by a licensed amateur radio operator to another licensed amateur radio operator of an external radio frequency power amplifier if the amplifier is for the amateur operator's personal use at his licensed amateur radio station and the requirements of §§97.315 and 97.317 of this chapter are met.

[40 FR 1246, Jan. 7, 1975; 40 FR 6474, Feb. 12, 1975, as amended at 43 FR 12687, Mar. 27, 1978; 43 FR 33725, Aug. 1, 1978; 46 FR 18981, Mar. 27, 1981; 62 FR 10470, Mar. 7, 1997]

Subpart J—Equipment Authorization Procedures

SOURCE: 39 FR 5919, Feb. 15, 1974, unless otherwise noted.

GENERAL PROVISIONS

§ 2.901 Basis and purpose.

(a) In order to carry out its responsibilities under the Communications Act and the various treaties and international regulations, and in order to promote efficient use of the radio spectrum, the Commission has developed technical standards for radio frequency equipment and parts or components thereof. The technical standards applicable to individual types of equipment are found in that part of the rules governing the service wherein the equipment is to be operated. In addition to the technical standards provided, the rules governing the service may require that such equipment be verified by the manufacturer or importer, be authorized under a Declaration of Conformity, or receive an equipment authorization from the Commission by one of the following procedures: type acceptance, certification, registration or notification.

(b) The following sections describe the verification procedure, the procedure for a Declaration of Conformity, and the procedures to be followed in obtaining type acceptance, certification or notification from the Commission and the conditions attendant to such a grant.

[61 FR 31045, June 19, 1996, as amended at 62 FR 10470, Mar. 7, 1997]

§ 2.902 Verification.

(a) Verification is a procedure where the manufacturer makes measurements or takes the necessary steps to insure that the equipment complies with the appropriate technical standards. Submittal of a sample unit or representative data to the Commission demonstrating compliance is not required unless specifically requested by the Commission pursuant to § 2.957, of this part.

(b) Verification attaches to all items subsequently marketed by the manufacturer or importer which are identical as defined in § 2.908 to the sample tested and found acceptable by the manufacturer.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[46 FR 23249, Apr. 24, 1981]

§ 2.904

47 CFR Ch. I (10–1–97 Edition)

§ 2.904 Notification.

(a) Notification is an equipment authorization issued by the Commission whereby the applicant makes measurements to determine that the equipment complies with the appropriate technical standards and reports that such measurements have been made and demonstrate the necessary compliance. Submittal of a sample unit or representative data to the Commission demonstrating compliance is not required unless specifically requested by the Commission pursuant to § 2.936, § 2.943 or § 2.945.

(b) Notification attaches to all items subsequently marketed by the grantee which are identical, as defined in § 2.908, to the sample(s) tested and found acceptable by the grantee.

(c) Permissive changes or other variations authorized by the Commission to equipment under the notification procedure shall be made in accordance with the restrictions contained in § 2.977.

(d) For equipment which requires a grant of notification, authorization under type acceptance, type approval, or certification shall be deemed to constitute authorization of the equipment under notification.

[48 FR 3621, Jan. 26, 1983, as amended at 49 FR 3996, Feb. 1, 1984]

§ 2.905 Type acceptance.

(a) Type acceptance is an equipment authorization issued by the Commission for equipment to be used pursuant to a station authorization. Type acceptance is based on representations and test data submitted by the applicant.

(b) Type acceptance attaches to all units subsequently marketed by the grantee which are identical (See § 2.908) to the sample tested except for permissive changes or other variations authorized by the Commission pursuant to § 2.1001.

[39 FR 5919, Feb. 15, 1974; 39 FR 8617, Mar. 6, 1974, as amended at 39 FR 27802, Aug. 1, 1974]

§ 2.906 Declaration of Conformity.

(a) A Declaration of Conformity is a procedure where the responsible party, as defined in § 2.909, makes measurements or takes other necessary steps

to ensure that the equipment complies with the appropriate technical standards. Submittal of a sample unit or representative data to the Commission demonstrating compliance is not required unless specifically requested pursuant to § 2.1076.

(b) The Declaration of Conformity attaches to all items subsequently marketed by the responsible party which are identical, as defined in § 2.908, to the sample tested and found acceptable by the responsible party.

[61 FR 31045, June 19, 1996]

§ 2.907 Certification.

(a) Certification is an equipment authorization issued by the Commission for equipment designed to be operated without individual license under Parts 15 and 18 of its rules, based on representations and test data submitted by the applicant.

(b) Certification attaches to all units subsequently marketed by the grantee which are identical (see § 2.908) to the sample tested except for permissive changes or other variations authorized by the Commission pursuant to § 2.1043.

[39 FR 5919, Feb. 15, 1974, as amended at 39 FR 27802, Aug. 1, 1974]

§ 2.908 Identical defined.

As used in this subpart, the term *identical* means identical within the variation that can be expected to arise as a result of quantity production techniques.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[46 FR 23249, Apr. 24, 1981]

§ 2.909 Responsible party.

The following parties are responsible for the compliance of radio frequency equipment with the applicable standards:

(a) In the case of equipment which requires the issuance by the Commission of a grant of equipment authorization, the party to whom that grant of authorization is issued (the grantee) If the radio frequency equipment is modified by any party other than the grantee and that party is not working under the authorization of the grantee pursuant to § 2.929(b), the party performing

Federal Communications Commission

§2.911

the modification is responsible for compliance of the product with the applicable administrative and technical provisions in this chapter.

(b) In the case of equipment subject to authorization under the verification procedure, the manufacturer or, in the case of imported equipment, the importer. If subsequent to manufacture and importation, the radio frequency equipment is modified by any party not working under the authority of the responsible party, the party performing the modification becomes the new responsible party.

(c) In the case of equipment subject to authorization under the Declaration of Conformity procedure:

(1) The manufacturer or, if the equipment is assembled from individual component parts and the resulting system is subject to authorization under a Declaration of Conformity, the assembler.

(2) If the equipment, by itself, is subject to a Declaration of Conformity and that equipment is imported, the importer.

(3) Retailers or original equipment manufacturers may enter into an agreement with the responsible party designated in paragraph (c)(1) or (c)(2) of this section to assume the responsibilities to ensure compliance of equipment and become the new responsible party.

(4) If the radio frequency equipment is modified by any party not working under the authority of the responsible party, the party performing the modifications, if located within the U.S., or the importer, if the equipment is imported subsequent to the modifications, becomes the new responsible party.

(d) If, because of modifications performed subsequent to authorization, a new party becomes responsible for ensuring that a product complies with the technical standards and the new party does not obtain a new equipment authorization, the equipment shall be labelled, following the specifications in §2.925(d), with the following: "This product has been modified by [insert name, address and telephone number of

the party performing the modifications]."

[54 FR 17712, Apr. 25, 1989, as amended at 61 FR 31045, June 19, 1996; 62 FR 10470, Mar. 7, 1997; 62 FR 41880, Aug. 4, 1997]

APPLICATION PROCEDURES FOR EQUIPMENT AUTHORIZATIONS

§2.911 Written application required.

(a) An application for equipment authorization shall be filed on a form prescribed by the Commission.

(b) Each application shall be accompanied by all information required by this subpart and by those parts of the rules governing operation of the equipment, and by requisite test data, diagrams, etc., as specified in this subpart and in those sections of rules whereunder the equipment is to be operated.

(c) Each application including amendments thereto, and related statements of fact required by the Commission, shall be personally signed by the applicant if the applicant is an individual; by one of the partners if the applicant is a partnership; by an officer, if the applicant is a corporation; or by a member who is an officer, if the applicant is an unincorporated association: *Provided, however,* That the application may be signed by the applicant's authorized representative who shall indicate his title, such as plant manager, project engineer, etc.

(d) Technical test data shall be signed by the person who performed or supervised the tests. The person signing the test data shall attest to the accuracy of such data. The Commission may require such person to submit a statement showing that he is qualified to make or supervise the required measurements.

(e) The signatures of the applicant and the person certifying the test data shall be made personally by those persons on the original application; copies of such documents may be conformed. Signatures and certifications need not be made under oath.

§2.913

(f) Each application shall be accompanied by the processing fee prescribed in subpart G of part 1 of this chapter.

[39 FR 5919, Feb. 15, 1974, as amended at 39 FR 27802, Aug. 1, 1974; 52 FR 5294, Feb. 20, 1987. Redesignated at 54 FR 17712, Apr. 25, 1989]

§2.913 Submittal of equipment authorization application or information to the Commission.

(a) Unless otherwise directed, applications with fees attached for the equipment authorization, pursuant to §1.1103 of this chapter, must be submitted following the procedures described in §0.401(b) of this chapter. The address for applications submitted by mail is: Federal Communications Commission, Equipment Approval Services, P. O. Box 358315, Pittsburgh, PA 15251-5315. If the applicant chooses to make use of an air courier/package delivery service, the following address must appear on the outside of the package/envelope: Federal Communications Commission, c/o Mellon Bank, Three Mellon Bank Center, 525 William Penn Way, 27th floor, Room 153-2713, Pittsburgh, Pennsylvania 15259-0001, Attention: Wholesale Lockbox Supervisor.

(b) Any information or equipment samples requested by the Commission pursuant to the provisions of subpart J of this part shall, unless otherwise directed, be submitted to the FCC, Equipment Authorization Division, 7434 Oakland Mills Road, Columbia, Maryland 21046.

[61 FR 31045, June 19, 1996, as amended at 62 FR 10470, Mar. 7, 1997]

§2.915 Grant of application.

(a) The Commission will grant an application for type acceptance, certification or notification if it finds from an examination of the application and supporting data, or other matter which it may officially notice, that:

(1) The equipment is capable of complying with pertinent technical standards of the rule part(s) under which it is to be operated; and,

(2) A grant of the application would serve the public interest, convenience and necessity.

(b) Grants will be made in writing showing the effective date of the grant

47 CFR Ch. I (10-1-97 Edition)

and any special condition(s) attaching to the grant.

(c) Neither type acceptance, certification or notification shall attach to any equipment, nor shall any equipment authorization be deemed effective, until the application has been granted.

[39 FR 5919, Feb. 15, 1974, as amended at 48 FR 3621, Jan. 26, 1983; 62 FR 10470, Mar. 7, 1997]

§2.917 Dismissal of application.

(a) An application which is not in accordance with the provisions of this subpart may be dismissed.

(b) Any application, upon written request signed by the applicant or his attorney, may be dismissed prior to a determination granting or denying the authorization requested.

(c) If an applicant is requested by the Commission to file additional documents or information and fails to submit the requested material within 60 days, the application may be dismissed.

[39 FR 5919, Feb. 15, 1974, as amended at 62 FR 10470, Mar. 7, 1997]

§2.919 Denial of application.

If the Commission is unable to make the findings specified in §2.915(a), it will deny the application. Notification to the applicant will include a statement of the reasons for the denial.

§2.921 Hearing on application.

Whenever it is determined that an application for equipment authorization presents substantial factual questions relating to the qualifications of the applicant or the equipment (or the effects of the use thereof), the Commission may designate the application for hearing. A hearing on an application for an equipment authorization shall be conducted in the same manner as a hearing on a radio station application as set out in subpart B of part 1 of this chapter.

§2.923 Petition for reconsideration; application for review.

Persons aggrieved by virtue of an equipment authorization action may file with the Commission a petition for reconsideration or an application for review. Rules governing the filing of

Federal Communications Commission

§ 2.925

petitions for reconsideration and applications for review are set forth in §§ 1.106 and 1.115, respectively, of this chapter.

§ 2.924 Marketing of electrically identical equipment having multiple trade names and models or type numbers under the same FCC Identifier.

The grantee of an equipment authorization may market devices having different model/type numbers or trade names without additional authorization from the Commission, provided that such devices are electrically identical and the equipment bears an FCC Identifier validated by a grant of equipment authorization. A device will be considered to be electrically identical if no changes are made to the device authorized by the Commission, or if the changes made to the device would be treated as class I permissive changes within the scope of §§ 2.1001(b)(1) and 2.1043(b)(1). Changes to the model number or trade name by anyone other than the grantee, or under the authorization of the grantee, shall be performed following the procedures in § 2.933.

[62 FR 10470, Mar. 7, 1997]

§ 2.925 Identification of equipment.

(a) Each equipment covered in an application for equipment authorization shall bear a nameplate or label listing the following:

(1) FCC Identifier consisting of the two elements in the exact order specified in § 2.926. The FCC Identifier shall be preceded by the term *FCC ID* in capital letters on a single line, and shall be of a type size large enough to be legible without the aid of magnification.

Example: FCC ID XXX123. XXX—Grantee Code 123—Equipment Product Code

(2) Any other statements or labeling requirements imposed by the rules governing the operation of the specific class of equipment, except that such statement(s) of compliance may appear on a separate label at the option of the applicant/grantee.

(3) Equipment subject only to registration will be identified pursuant to part 68 of this chapter.

(b) Any device subject to more than one equipment authorization procedure

may be assigned a single FCC Identifier. However, a single FCC Identifier is required to be assigned to any device consisting of two or more sections assembled in a common enclosure, on a common chassis or circuit board, and with common frequency controlling circuits. Devices to which a single FCC Identifier has been assigned shall be identified pursuant to paragraph (a) of this section.

(1) Separate FCC Identifiers may be assigned to a device consisting of two or more sections assembled in a common enclosure, but constructed on separate sub-units or circuit boards with independent frequency controlling circuits. The FCC Identifier assigned to any transmitter section shall be preceded by the term *TX FCC ID*, the FCC Identifier assigned to any receiver section shall be preceded by the term *RX FCC ID* and the identifier assigned to any remaining section(s) shall be preceded by the term *FCC ID*.

(2) Where telephone equipment subject to part 68 of this chapter, and a radiofrequency device subject to equipment authorization requirements are assembled in a common enclosure, the nameplate/label shall display the FCC Registration Number in the format specified in part 68 and the FCC Identifier in the format specified in paragraph (a) of this section.

(3) Applications filed on or after May 1, 1981, and applications filed earlier requesting equipment authorization using the single system of identification pursuant to section (a)(1) will receive a review of the identification portion by the Commission's Laboratory with respect to nameplate/label design within 30 days after receipt at the Laboratory. Failure by the Laboratory to reject a nameplate design proposed in any particular application within this time period will constitute de-facto acceptance of the nameplate/label design for that particular equipment. Such de facto acceptance will be limited to the equipment covered by the particular application and will not be considered to establish a precedent for other applications. This review deadline applies only to the proposed nameplate/label design, not to the remainder of the application.

§ 2.926

(4) For a transceiver, the receiver portion of which is subject to verification pursuant to § 15.101 of this chapter, the FCC Identifier required for the transmitter portion shall be preceded by the term *FCC ID*.

(c) [Reserved]

(d) In order to validate the grant of equipment authorization, the nameplate or label shall be permanently affixed to the equipment and shall be readily visible to the purchaser at the time of purchase.

(1) As used here, *permanently affixed* means that the required nameplate data is etched, engraved, stamped, indelibly printed, or otherwise permanently marked on a permanently attached part of the equipment enclosure. Alternatively, the required information may be permanently marked on a nameplate of metal, plastic, or other material fastened to the equipment enclosure by welding, riveting, etc., or with a permanent adhesive. Such a nameplate must be able to last the expected lifetime of the equipment in the environment in which the equipment will be operated and must not be readily detachable.

(2) As used here, *readily visible* means that the nameplate or nameplate data must be visible from the outside of the equipment enclosure. It is preferable that it be visible at all times during normal installation or use, but this is not a prerequisite for grant of equipment authorization.

(e) Where it is shown that a permanently affixed nameplate is not desirable or is not feasible, an alternative method of positively identifying the equipment may be used if approved by the Commission. The proposed alternative method of identification and the justification for its use must be included with the application for equipment authorization.

NOTE: As an example, a device intended to be implanted within the body of a test animal or person would probably require an alternate method of identification.

(f) The term *FCC ID* and the coded identification assigned by the Commission shall be in a size of type large enough to be readily legible, consistent with the dimensions of the equipment and its nameplate. However, the type

47 CFR Ch. I (10–1–97 Edition)

size for the FCC Identifier is not required to be larger than eight-point.

[44 FR 17177, Mar. 21, 1979, as amended at 44 FR 55574, Sept. 27, 1979; 46 FR 21013, Apr. 8, 1981; 52 FR 21687, June 9, 1987; 54 FR 1698, Jan. 17, 1989; 62 FR 10470, Mar. 7, 1997]

§ 2.926 FCC identifier.

(a) A grant of equipment authorization issued by the Commission will list the validated FCC Identifier consisting of the grantee code assigned by the FCC pursuant to paragraph (b) of this section, and the equipment product code assigned by the grantee pursuant to paragraph (c) of this section. See § 2.925.

(b) The grantee code assigned pursuant to paragraph (c) of this section is assigned permanently to applicants/grantees and is valid only for the party specified as the applicant/grantee in the code assignment(s).

(c) A grantee code will have three characters consisting of Arabic numerals, capital letters, or combination thereof. A prospective grantee or his authorized representative may submit a written request to the Commission for assignment of a grantee code at any time. However, it is preferred that grantee codes be requested prior to filing applications for equipment authorization. If a grantee code is not requested in advance, one will be assigned at the time an application is received by the FCC Laboratory and the applicant will be notified to make any necessary label revisions in order to comply fully with application procedural rules.

(1) After assignment of a grantee code each grantee will continue to use the same grantee code for subsequent equipment authorization applications.

In the event the grantee name is changed or ownership is transferred, the circumstances shall be reported to the Commission so that a new grantee code can be assigned, if appropriate. See §§ 2.934 and 2.935 for additional information.

(2) [Reserved]

(d) The equipment product code assigned by the grantee shall consist of a series of Arabic numerals, capital letters or a combination thereof, and may include the dash or hyphen (-). The

Federal Communications Commission

§2.931

total of Arabic numerals, capital letters and dashes or hyphens shall not exceed 14 and shall be one which has not been previously used in conjunction with:

(1) The same grantee code, or

(2) An application denied pursuant to §2.919 of this chapter.

(e) No FCC Identifier may be used on equipment to be marketed unless that specific identifier has been validated by a grant of equipment authorization issued by the Commission. This shall not prohibit placement of an FCC identifier on a transceiver which includes a verified receiver subject to §15.101, provided that the transmitter portion of such transceiver is covered by a valid grant of type acceptance or certification. The FCC Identifier is uniquely assigned to the grantee and may not be placed on the equipment without authorization by the grantee. See §2.803 for conditions applicable to the display at trade shows of equipment which has not been granted equipment authorization where such grant is required prior to marketing. Labelling of such equipment may include model or type numbers, but shall not include a purported FCC Identifier.

[44 FR 17179, Mar. 21, 1979, as amended at 46 FR 21014, Apr. 8, 1981; 52 FR 21687, June 9, 1987; 54 FR 1698, Jan. 17, 1989; 62 FR 10471, Mar. 7, 1997]

CONDITIONS ATTENDANT TO AN EQUIPMENT AUTHORIZATION

§2.927 Limitations on grants.

(a) A grant of equipment authorization is valid only when the FCC Identifier is permanently affixed on the device and remains effective until revoked or withdrawn, rescinded, surrendered, or a termination date is otherwise established by the Commission.

(b) A grant of an equipment authorization signifies that the Commission has determined that the equipment has been shown to be capable of compliance with the applicable technical standards if no unauthorized change is made in the equipment and if the equipment is properly maintained and operated. The issuance of a grant of equipment authorization shall not be construed as a finding by the Commission with respect to matters not encompassed by

the Commission's rules, especially with respect to compliance with 18 U.S.C. 2512.

(c) No person shall, in any advertising matter, brochure, etc., use or make reference to an equipment authorization in a deceptive or misleading manner or convey the impression that such equipment authorization reflects more than a Commission determination that the device or product has been shown to be capable of compliance with the applicable technical standards of the Commission's rules.

[39 FR 5919, Feb. 15, 1974, as amended at 44 FR 29066, May 18, 1979; 62 FR 10471, Mar. 7, 1997]

§2.929 Nonassignability of an equipment authorization.

(a) An equipment authorization issued by the Commission may not be assigned, exchanged or in any other way transferred to a second party.

(b) The grantee of an equipment authorization may license or otherwise authorize a second party to manufacture or market the equipment covered by the grant of the equipment authorization provided:

(1) The equipment manufactured by such second party bears the identical FCC Identifier as set out in the grant of the equipment authorization.

NOTE TO PARAGRAPH (B)(1): Any change in the FCC Identifier desired as a result of such production or marketing agreement will require the filing of a new application for an equipment authorization as specified in §2.933.

(2) The grantee of the equipment authorization shall continue to be responsible to the Commission for the equipment produced pursuant to such an agreement.

[39 FR 5919, Feb. 15, 1974, as amended at 54 FR 1699, Jan. 17, 1989; 62 FR 10471, Mar. 7, 1997]

§2.931 Responsibility of the grantee.

In accepting a grant of an equipment authorization, the grantee warrants that each unit of equipment marketed under such grant and bearing the identification specified in the grant will conform to the unit that was measured and that the data (design and rated operational characteristics) determined by the grantee for notification

§2.932

47 CFR Ch. I (10–1–97 Edition)

or filed with the application for type acceptance or certification continues to be representative of the equipment being produced under such grant within the variation that can be expected due to quantity production and testing on a statistical basis.

[62 FR 10471, Mar. 7, 1997]

§2.932 Modification of equipment.

(a) A new application for an equipment authorization shall be filed whenever there is a change in the design, circuitry or construction of an equipment or device for which an equipment authorization has been issued, except as provided in paragraphs (b), (c), (d) and (e) of this section.

(b) Permissive changes may be made in a type accepted equipment pursuant to §2.1001.

(c) Permissive changes may be made in a certificated equipment pursuant to §2.1043.

(d) For changes in type approved equipment the procedure in §2.967 shall apply.

(e) Permissive changes may be made in notified equipment pursuant to §2.977.

(f) All requests for permissive changes submitted to the Commission must be accompanied by the anti-drug abuse certification required under §1.2002 of this chapter.

[39 FR 5919, Feb. 15, 1974, as amended at 48 FR 3621, Jan. 26, 1983; 62 FR 10471, Mar. 7, 1997]

§2.933 Change in identification of equipment.

(a) A new application for equipment authorization shall be filed whenever there is a change in the FCC Identifier for the equipment with or without a change in design, circuitry or construction. However, a change in the model/type number or trade name performed in accordance with the provisions in §2.924 is not considered to be a change in identification and does not require additional authorization from the Commission.

(b) An application filed pursuant to paragraph (a) of this section where no change in design, circuitry or construction is involved, need not be accompanied by a resubmission of equipment

or measurement or test data customarily required with a new application, unless specifically requested by the Commission. In lieu thereof, the applicant shall attach a statement setting out:

(1) The original identification used on the equipment prior to the change in identification.

(2) The date of the original grant of the equipment authorization.

(3) The original type approval number assigned by the Commission, if one was assigned.

(4) How the equipment bearing the modified identification differs from the original equipment.

(5) Whether the data previously filed with the Commission (or measured by the Commission in the case of type approved equipment or measured by the applicant in the case of notified equipment) continues to be representative of and applicable to the equipment bearing the changed identification.

(6) In the case of type accepted equipment, the photographs required by §2.983(f).

(7) In the case of certified equipment, the photographs required by §2.1033(b)(7) showing the exterior appearance of the equipment, including the operating controls available to the user and the identification label. Photographs of the construction, the component placement on the chassis, and the chassis assembly are not required to be submitted unless specifically requested by the Commission.

(c) If the change in the FCC Identifier also involves a change in design or circuitry which falls outside the purview of a permissive change described in §§2.977, 2.1001 or 2.1043, a complete application shall be filed pursuant to §2.911.

[39 FR 5919, Feb. 15, 1974, as amended at 48 FR 3621, Jan. 26, 1983; 51 FR 39535, Oct. 29, 1986; 62 FR 10471, Mar. 7, 1997]

§2.934 Change in name and/or address of grantee.

Whenever there is a change in the name and/or address of the grantee of an equipment authorization, written notice of such change(s) shall be filed within 30 days after the grantee starts using the new name and/or address, in order for the Commission to update its

Federal Communications Commission

§2.938

records of grantee names, addresses and grantee codes. See §2.913(b).

[54 FR 1699, Jan. 17, 1989, as amended at 62 FR 10471, Mar. 7, 1997]

§2.935 Change in control of grantee.

In the case of a transfer of control of the grantee of an equipment authorization, as in the case of sale or merger of the grantee, notice of such transfer must be received by the Commission not later than 60 days subsequent to the consummation of the agreement effecting the transfer of control. Depending on the circumstances in each case, the Commission may require new applications for equipment authorization for each device or equipment held by the predecessor in interest, production of which will be continued by the acquiring party.

§2.936 FCC inspection.

Upon reasonable request, each responsible party shall submit the following to the Commission or shall make the following available for inspection:

(a) The records required by §§2.938, 2.955, and 2.1075.

(b) A sample unit of the equipment covered under an authorization.

(c) The manufacturing plant and facilities.

[62 FR 10471, Mar. 7, 1997]

§2.937 Equipment defect and/or design change.

When a complaint is filed with the Commission concerning the failure of equipment subject to this chapter to comply with pertinent requirements of the Commission's rules, and the Commission determines that the complaint is justified and arises out of an equipment fault attributable to the responsible party, the Commission may require the responsible party to investigate such complaint and report the results of such investigation to the Commission. The report shall also indicate what action if any has been taken or is proposed to be taken by the responsible party to correct the defect, both in terms of future production and with reference to articles in the possession of users, sellers and distributors.

[61 FR 31046, June 19, 1996]

§2.938 Retention of records.

(a) For each equipment subject to the Commission's equipment authorization standards, the responsible party shall maintain the records listed as follows:

(1) A record of the original design drawings and specifications and all changes that have been made that may affect compliance with the standards and the requirements of §2.931.

(2) A record of the procedures used for production inspection and testing to ensure conformance with the standards and the requirements of §2.931.

(3) A record of the test results that demonstrate compliance with the appropriate regulations in this chapter.

(b) The provisions of paragraph (a) of this section shall also apply to a manufacturer of equipment produced under the provisions of §2.929(b). The retention of the records by the manufacturer under these circumstances shall satisfy the grantee's responsibility under paragraph (a) of this section.

(c) The records listed in paragraph (a) of this section shall be retained for one year for equipment subject to authorization under the type acceptance or certification procedure, or for two years for equipment subject to authorization under any other procedure, after the manufacture of said equipment has been permanently discontinued, or until the conclusion of an investigation or a proceeding if the responsible party (or under paragraph (b) of this section the manufacturer) is officially notified that an investigation or any other administrative proceeding involving its equipment has been instituted.

(d) If radio frequency equipment is modified by any party other than the original responsible party, and that party is not working under the authorization of the original responsible party, the party performing the modifications is not required to obtain the original design drawings specified in paragraph (a)(1) of this section. However, the party performing the modifications must maintain records showing the changes made to the equipment along with the records required in paragraphs (a)(3) of this section. A new equipment authorization may also be

§2.939

required. See, for example, §§2.909, 2.924, 2.933, and 2.1043.

[62 FR 10471, Mar. 7, 1997]

§2.939 Revocation or withdrawal of equipment authorization.

(a) The Commission may revoke any equipment authorization:

(1) For false statements or representations made either in the application or in materials or response submitted in connection therewith or in records required to be kept by §2.938.

(2) If upon subsequent inspection or operation it is determined that the equipment does not conform to the pertinent technical requirements or to the representations made in the original application.

(3) If it is determined that changes have been made in the equipment other than those authorized by the rules or otherwise expressly authorized by the Commission.

(4) Because of conditions coming to the attention of the Commission which would warrant it in refusing to grant an original application.

(b) Revocation of an equipment authorization shall be made in the same manner as revocation of radio station licenses.

(c) The Commission may withdraw any equipment authorization in the event of changes in its technical standards. The procedure to be followed will be set forth in the order promulgating such new technical standards (after appropriate rulemaking proceedings) and will provide a suitable amortization period for equipment in hands of users and in the manufacturing process.

[39 FR 5919, Feb. 15, 1974, as amended at 51 FR 39535, Oct. 29, 1986]

§2.941 Availability of information relating to grants.

(a) Grants of equipment authorization, other than for receivers and equipment authorized for use under parts 15 or 18 of this chapter, will be publicly announced in a timely manner by the Commission. Information about the authorization of a device using a particular FCC Identifier may be obtained by contacting the Commission's Office of Engineering and Technology Laboratory.

47 CFR Ch. I (10–1–97 Edition)

(b) Information relating to equipment authorizations, such as data submitted by the applicant in connection with an authorization application, laboratory tests of the device, etc., shall be available in accordance with §§0.441 through 0.470 of this chapter.

[62 FR 10472, Mar. 7, 1997]

§2.943 Submission of equipment for testing.

(a) The Commission may require an applicant for type acceptance, certification or notification to submit one or more sample units for measurement at the Commission's laboratory.

(b) In the event the applicant believes that shipment of the sample to the Commission's laboratory is impractical because of the size or weight of the equipment, or the power requirement, or for any other reason, the applicant may submit a written explanation why such shipment is impractical and should not be required.

[39 FR 5919, Feb. 15, 1974, as amended at 48 FR 3621, Jan. 26, 1983]

§2.945 Sampling tests of equipment compliance.

The Commission will, from time to time, request the responsible party to submit equipment subject to this chapter to determine the extent to which subsequent production of such equipment continues to comply with the data filed by the applicant (or on file with the responsible party for equipment subject to notification or a Declaration of Conformity). Shipping costs to the Commission's laboratory and return shall be borne by the responsible party.

[61 FR 31046, June 19, 1996]

§2.946 Penalty for failure to provide test samples and data.

(a) Any responsible party, as defined in §2.909, or any party who markets equipment subject to the provisions of this chapter, shall provide test sample(s) or data upon request by the Commission. Failure to comply with such a request with the time frames shown below may be cause for forfeiture, pursuant to §1.80 of this chapter, or other administrative sanctions such as suspending action on any applications for

Federal Communications Commission

§ 2.948

equipment authorization submitted by such party while the matter is being resolved.

(1) When the equipment is subject to authorization under a Declaration of Conformity, data shall be provided within 14 days of delivery of the request and test sample(s) shall be provided within 60 days of delivery of the request.

(2) For all other devices, test sample(s) or data shall be provided within 60 days of the request.

(b) In the case of equipment involving harmful interference or safety of life or property, the Commission may specify that test samples subject to the provisions of this section be submitted within less than 60 days, but not less than 14 days. Failure to comply within the specified time period will be subject to the sanctions specified in paragraph (a) of this section.

(c) The Commission may consider extensions of time upon submission of a showing of good cause.

[54 FR 1699, Jan. 17, 1989, as amended at 61 FR 31046, June 19, 1996]

§ 2.947 Measurement procedure.

(a) The Commission will accept data which have been measured in accordance with the following standards or measurement procedures:

(1) Those set forth in bulletins or reports prepared by the Commission's Office of Engineering and Technology. These will be issued as required, and specified in the particular part of the rules where applicable.

(2) Those acceptable to the Commission and published by national engineering societies such as the Electronic Industries Association, the Institute of Electrical and Electronic Engineers, Inc., and the American National Standards Institute.

(3) Any measurement procedure acceptable to the Commission may be used to prepare data demonstrating compliance with the requirements of this chapter.

(b) Information submitted pursuant to paragraph (a) of this section shall completely identify the specific standard or measurement procedure used.

(c) In the case of equipment requiring measurement procedures not specified in the references set forth in para-

graphs (a) (1) and (2) of this section, the applicant shall submit a detailed description of the measurement procedures actually used.

(d) A listing of the test equipment used shall be submitted.

(e) If deemed necessary, the Commission may require additional information concerning the measurement procedures employed in obtaining the data submitted for equipment authorization purposes.

[42 FR 44987, Sept. 8, 1977, as amended at 44 FR 39181, July 5, 1979; 51 FR 12616, Apr. 14, 1986]

§ 2.948 Description of measurement facilities.

(a) Each party making measurements of equipment that is subject to an equipment authorization under part 15 or part 18 of this chapter, regardless of whether the measurements are filed with the Commission or kept on file by the party responsible for compliance of equipment marketed within the U.S. or its possessions, shall compile a description of the measurement facilities employed.

(1) If the measured equipment is subject to the verification procedure, the description of the measurement facilities shall be retained by the party responsible for verification of the equipment.

(i) If the equipment is verified through measurements performed by an independent laboratory, it is acceptable for the party responsible for verification of the equipment to rely upon the description of the measurement facilities retained by or placed on file with the Commission by that laboratory. In this situation, the party responsible for verification of the equipment is not required to retain a duplicate copy of the description of the measurement facilities.

(ii) If the equipment is verified based on measurements performed at the installation site of the equipment, no specific site calibration data is required. It is acceptable to retain the description of the measurement facilities at the site at which the measurements were performed.

(2) If the equipment is to be authorized by the Commission under the certification or the notification procedure, the description of the measurement facilities shall be filed with the Commission's Laboratory in Columbia, Maryland. The data describing the measurement facilities need only be filed once but must be updated as changes are made to the measurement facilities or as otherwise described in this section. At least every three years, the organization responsible for filing the data with the Commission shall certify that the data on file is current.

(3) If the equipment is to be authorized under a Declaration of Conformity, the description of the measurement facilities shall be retained by the party performing the measurements.

(b) The description shall contain the following information:

(1) Location of the test site.

(2) Physical description of the test site accompanied by photographs of size A4 (21 cm × 29.7 cm) or 8×10 inches (20.3 cm × 25.4 cm). Smaller photographs may be used if they clearly show the details of the test site and are mounted on full size sheets of paper.

(3) A drawing showing the dimensions of the site, physical layout of all supporting structures, and all structures within 5 times the distance between the measuring antenna and the device being measured.

(4) Description of structures used to support the device being measured and the test instrumentation.

(5) List of measuring equipment used.

(6) Information concerning the calibration of the measuring equipment, i.e., the date the equipment was last calibrated and how often the equipment is calibrated.

(7) If desired, a statement as to whether the test site is available to do measurement services for the public on a fee basis.

(8) A plot of site attenuation data.

(i) For a measurement facility that will be used for testing radiated emissions from a digital device on or after May 1, 1994, or for testing intentional and other unintentional radiators authorized under part 15 of the rules on or after June 1, 1995, the site attenuation data shall be taken pursuant to the procedures contained in Sections 5.4.6

through 5.5 of the following procedure: American National Standards Institute (ANSI) C63.4-1992, entitled "Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and Electronic Equipment in the Range of 9 kHz to 40 GHz," published by the Institute of Electrical and Electronics Engineers, Inc. on July 17, 1992 as document number SH15180. This incorporation by reference was approved by the Director of the Federal Register in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. Copies of ANSI C63.4-1992 may be obtained from: IEEE Standards Department, 455 Hoes Lane, P.O. Box 1331, Piscataway, NJ 08855-1331, telephone 1-800-678-4333. Copies of ANSI C63.4-1992 may be inspected at the following locations:

(A) Federal Communications Commission, 2025 M Street, NW., Office of Engineering and Technology (room 7317), Washington, DC 20554,

(B) Federal Communications Commission Laboratory, 7435 Oakland Mills Road, Columbia, MD 21046, or

(C) Office of the Federal Register, 800 North Capitol Street, NW., suite 700, Washington, DC.

(ii) For a measurement facility that will be used for testing radiated emissions from a digital device prior to May 1, 1994, or from intentional and other unintentional radiators authorized under part 15 prior to June 1, 1995, or from devices authorized under part 18 of the rules, the site attenuation data shall be taken pursuant to either ANSI C63.4-1992, Sections 5.4.6 through 5.5, or FCC/OET Bulletin 55.

(iii) This requirement does not apply to equipment that is not measured on an open field test site.

(9) A description of the types of equipment intended to be measured or other information regarding the types of measurements that would be performed at the test facility.

(c) The Commission will publish a list of those parties who have filed the information required by this section, provided they indicate that they wish to perform measurement services for the public on a fee basis. However, it should be noted that the Commission does not endorse or approve any facility on this list.

Federal Communications Commission

§2.952

(d) If the equipment is to be authorized under a Declaration of Conformity, the party performing the measurements shall be accredited for performing such measurements by an authorized accreditation body based on the International Organization for Standardization/International Electrotechnical Commission (ISO/IEC) Guide 25, "General Requirements for the Competence of Calibration and Testing Laboratories." Accreditation bodies must be approved by the FCC's Office of Engineering and Technology, as indicated in §0.241 of this chapter, to perform such accreditation based on ISO/IEC 58, "Calibration and Testing Laboratory Accreditation Systems—General Requirements for Operation and Recognition." The frequency for revalidation of the test site and the information required to be filed or retained by the testing party shall comply with the requirements established by the accrediting organization.

(1) In addition to meeting the above requirements, the accreditations of laboratories located outside of the United States or its possessions will be acceptable only under one of the following conditions:

(i) If there is a mutual recognition agreement between that country and the United States and that laboratory is covered by the agreement;

(ii) If there is an agreement between accrediting bodies that permits similar accreditation of U.S. facilities to perform testing for products marketed in that country; or

(iii) If the country already accepts the accreditation of U.S. laboratories.

(2) Organizations outside of the United States that seek to become accreditors may seek agreements with approved United States accrediting bodies to mutually recognize the accreditation of laboratories. The Commission will review such agreements and will consult with the Office of the United States Trade Representative and other Executive Branch agencies before accepting them for purposes of the DoC procedure in order to ensure that the respective foreign countries accept United States accreditations and do not impose additional barriers upon United States companies. Accrediting bodies located outside of the

United States will only be permitted to accredit laboratories within their own country for DoC testing.

(3) To facilitate use of the DoC procedure, the FCC will accept a laboratory that submits documentation to OET's Equipment Authorization Division stating that it has filed an application for accreditation with an approved laboratory accreditation body and provides evidence that it meets all aspects of ISO/IEC Guide 25. Such labs will be provisionally accepted by the FCC for a period of one year (until August 19, 1997) or until the application for accreditation has been acted upon, whichever is sooner. A laboratory that is denied accreditation by an approved accreditation body will lose its provisional acceptance. However, any DoCs that were issued will remain valid.

[54 FR 17712, Apr. 25, 1989, as amended at 57 FR 24990, June 12, 1992; 58 FR 37430, July 12, 1993; 58 FR 44893, Aug. 25, 1993; 61 FR 31046, June 19, 1996; 62 FR 41880, Aug. 4, 1997]

VERIFICATION

AUTHORITY: Sections 2.951 through 2.957 are issued under secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307.

SOURCE: Sections 2.951 through 2.957 appear at 46 FR 23249, Apr. 24, 1981, unless otherwise noted.

§2.951 Cross reference.

The provisions of §2.901, *et seq.*, shall apply to equipment subject to verification.

§2.952 Limitation on verification.

(a) Verification signifies that the manufacturer or importer has determined that the equipment has been shown to be capable of compliance with the applicable technical standards if no unauthorized change is made in the equipment and if the equipment is properly maintained and operated. Compliance with these standards shall not be construed to be a finding by the manufacturer or importer with respect to matters not encompassed by the Commission's rules.

(b) Verification of the equipment by the manufacturer or importer is effective until a termination date is otherwise established by the Commission.

§ 2.953

(c) No person shall, in any advertising matter, brochure, etc., use or make reference to a verification in a deceptive or misleading manner or convey the impression that such verification reflects more than a determination by the manufacturer or importer that the device or product has been shown to be capable of compliance with the applicable technical standards of the Commission's rules.

§ 2.953 Responsibility for compliance.

(a) In verifying compliance, the responsible party, as defined in § 2.909 warrants that each unit of equipment marketed under the verification procedure will be identical to the unit tested and found acceptable with the standards and that the records maintained by the responsible party continue to reflect the equipment being produced under such verification within the variation that can be expected due to quantity production and testing on a statistical basis.

(b) The importer of equipment subject to verification may upon receiving a written statement from the manufacturer that the equipment complies with the appropriate technical standards rely on the manufacturer or independent testing agency to verify compliance. The test records required by § 2.955 however should be in the English language and made available to the Commission upon a reasonable request, in accordance with § 2.956.

(c) In the case of transfer of control of equipment, as in the case of sale or merger of the grantee, the new manufacturer or importer shall bear the responsibility of continued compliance of the equipment.

(d) Verified equipment shall be re-verified if any modification or change adversely affects the emanation characteristics of the modified equipment. The party designated in § 2.909 bears responsibility for continued compliance of subsequently produced equipment.

[39 FR 5919, Feb. 15, 1974, as amended at 62 FR 10472, Mar. 7, 1997]

§ 2.954 Identification.

Devices subject only to verification shall be uniquely identified by the person responsible for marketing or importing the equipment within the Unit-

47 CFR Ch. I (10–1–97 Edition)

ed States. However, the identification shall not be of a format which could be confused with the FCC Identifier required on certified, notified or type accepted equipment. The importer or manufacturer shall maintain adequate identification records to facilitate positive identification for each verified device.

[62 FR 10472, Mar. 7, 1997]

§ 2.955 Retention of records.

(a) For each equipment subject to verification, the responsible party, as shown in § 2.909 shall maintain the records listed as follows:

(1) A record of the original design drawings and specifications and all changes that have been made that may affect compliance with the requirements of § 2.953.

(2) A record of the procedures used for production inspection and testing (if tests were performed) to insure the conformance required by § 2.953. (Statistical production line emission testing is not required.)

(3) A record of the measurements made on an appropriate test site that demonstrates compliance with the applicable regulations in this chapter. The record shall:

(i) Indicate the actual date all testing was performed;

(ii) State the name of the test laboratory, company, or individual performing the verification testing. The Commission may request additional information regarding the test site, the test equipment or the qualifications of the company or individual performing the verification tests;

(iii) Contain a description of how the device was actually tested, identifying the measurement procedure and test equipment that was used;

(iv) Contain a description of the equipment under test (EUT) and support equipment connected to, or installed within, the EUT;

(v) Identify the EUT and support equipment by trade name and model number and, if appropriate, by FCC Identifier and serial number;

(vi) Indicate the types and lengths of connecting cables used and how they were arranged or moved during testing;

(vii) Contain at least two drawings or photographs showing the test set-up

Federal Communications Commission

§2.975

for the highest line conducted emission and showing the test set-up for the highest radiated emission. These drawings or photographs must show enough detail to confirm other information contained in the test report. Any photographs used must be focused originals without glare or dark spots and must clearly show the test configuration used;

(viii) List all modifications, if any, made to the EUT by the testing company or individual to achieve compliance with the regulations in this chapter;

(ix) Include all of the data required to show compliance with the appropriate regulations in this chapter; and

(x) Contain, on the test report, the signature of the individual responsible for testing the product along with the name and signature of an official of the responsible party, as designated in §2.909.

(4) For equipment subject to the provisions in part 15 of this chapter, the records shall indicate if the equipment was verified pursuant to the transition provisions contained in §15.37 of this chapter.

(b) The records listed in paragraph (a) of this section shall be retained for two years after the manufacture of said equipment item has been permanently discontinued, or until the conclusion of an investigation or a proceeding if the manufacturer or importer is officially notified that an investigation or any other administrative proceeding involving his equipment has been instituted.

[54 FR 17713, Apr. 25, 1989, as amended at 62 FR 10472, Mar. 7, 1997]

§2.956 FCC inspection and submission of equipment for testing.

(a) Each responsible party shall upon receipt of reasonable request:

(1) Submit to the Commission the records required by §2.955.

(2) Submit one or more sample units for measurements at the Commission's Laboratory.

(i) Shipping costs to the Commission's Laboratory and return shall be borne by the responsible party.

(ii) In the event the responsible party believes that shipment of the sample to the Commission's Laboratory is im-

practical because of the size or weight of the equipment, or the power requirement, or for any other reason, the responsible party may submit a written explanation why such shipment is impractical and should not be required.

(b) Requests for the submission of the records in §2.955 or for the submission of sample units are covered under the provisions of §2.946.

[62 FR 10472, Mar. 7, 1997]

NOTIFICATION

SOURCE: Sections 2.971 through 2.979 appear at 48 FR 3621, Jan. 26, 1983, unless otherwise noted.

§2.971 Cross reference.

The general provisions of this subpart, §2.901, *et seq.*, shall apply to applications for and grants of notification.

§2.973 Limitations on notification.

Notification is a grant of equipment authorization issued by the Commission that signifies that the applicant has determined that the equipment has been shown to be capable of compliance with the applicable technical standards in the Commission's rules if no unauthorized change is made in the equipment and if the equipment is properly maintained and operated. Compliance with these standards shall not be construed to be a finding by the applicant with respect to matters not encompassed by the Commission's rules.

§2.975 Application for notification.

(a) Subsequent to the determination by the applicant that the equipment complies with the applicable standards, the applicant, who shall retain the responsibility for ensuring that the equipment continues to comply with such standards, shall file a request for the issuance of an equipment authorization on FCC Form 731, for each FCC Identifier, with all questions answered. Where a form item is not applicable, it shall be stated. The application shall be filed in the name of the party to whom the grantee code is assigned (see §2.926 concerning the assignment of identifier codes). The following information shall be included in the filing, either in answer to the questions on the form or as attachments thereto:

(1) Name of the applicant indicating whether the applicant is the manufacturer of the equipment, a vendor other than the manufacturer, a licensee or a prospective licensee. Where the applicant is not the manufacturer of the equipment, the name of the manufacturer shall be stated;

(2) The following technical information:

(i) Type or types of emission (if applicable);

(ii) Frequency range;

(iii) Rated frequency tolerance (if applicable);

(iv) Rated radio frequency power output, if applicable (if variable, give the range) and

(v) If the equipment is a microwave transmitter, an explanation of the type of modulation employed and of the resulting emission.

(3) A statement concerning the intended use of the device including both the type of use for which the device has been designed and the part(s) or subpart(s) of the rules governing the device;

(4) The FCC Identifier of the equipment for which notification is sought (see §2.926) and a photograph or drawing of the equipment identification plate or label showing the information to be placed thereon in accordance with §2.925;

(5) For devices operated under the provisions of part 15 of this chapter, photographs showing the general appearance and the controls available to the user. Photographs should be size A4 (21 cm × 29.7 cm) or 8×10 inch (20.3 cm × 25.4 cm). Smaller photographs may be submitted provided they are sharp and clear, show the necessary detail, and are mounted on A4 (21 cm × 29.7 cm) or 8.5×11 inch (21.6 cm × 27.9 cm) paper. Line sketches may be submitted in lieu of photographs provided those sketches are sufficiently detailed to allow identification of the equipment. For devices operated under the provisions of any other part and where it is specifically required under the rule section(s) under which the device is to be operated, photographs of the equipment of sufficient clarity to reveal its external appearances and size, both front and back;

(6) A signed statement attesting to the following or its equivalent:

This equipment has been tested in accordance with the requirements contained in the appropriate Commission regulations. To the best of my knowledge, these tests were performed using measurement procedures consistent with industry or Commission standards and demonstrate that the equipment complies with the appropriate standards. Each unit manufactured, imported or marketed, as defined in the Commission's regulations, will conform to the sample(s) tested within the variations that can be expected due to quantity production and testing on a statistical basis. I further certify that the necessary measurements were made by (state the name and address of the test facility even if your own facility was used).

(7) For equipment subject to the provisions of part 15 of this chapter, the application shall indicate if the equipment is being authorized pursuant to the transition provisions in §15.37 of this chapter.

(8) Applications for the notification of receivers contained in frequency converters designed or marketed for use with scanning receivers shall include a statement describing the methods used to comply with the design requirements of §15.121(a) of this chapter or the marketing requirements of §15.121(b) of this chapter.

(b) The statement required in paragraph (a)(6) of this section shall be signed pursuant to §2.911(c).

(c) Upon the satisfactory completion of the necessary testing to determine that the applicable standards are met, the submission of the material required in paragraph (a) of this section and the issuance of a grant of equipment authorization, marketing, as defined in §2.803, is permitted.

(d) The authorization of the equipment through the notification procedure may be revoked pursuant to §2.939.

(e) Further information may be requested prior to the issuance of a grant of notification. This information may include measurement data, photographs, circuit diagrams and descriptions, or any other material which may be deemed necessary.

(f) For a composite system that incorporates only devices subject to certification, verification and/or notification and that are contained in a single

Federal Communications Commission

§2.981

enclosure, a separate application, FCC Form 731, with the appropriate fee shall be submitted for each type of device within the enclosure. At the option of the applicant, a single FCC identifier may be requested for that system. Fees are based on the number of devices and types of authorizations.

(g) The records of measurement data, measurement procedures, photographs, circuit diagrams, etc. for a device subject to notification shall be retained for two years after the manufacture of said equipment has been permanently discontinued, or, if the responsible party is officially notified that an investigation or any other administrative proceeding involving the equipment has been instituted prior to the expiration of such two year period, until the conclusion of that investigation or proceeding.

[48 FR 3621, Jan. 26, 1983, as amended at 49 FR 3996, Feb. 1, 1984; 54 FR 17713, Apr. 25, 1989; 58 FR 25575, Apr. 27, 1993; 58 FR 44893, Aug. 25, 1993; 62 FR 10473, Mar. 7, 1997]

§2.977 Changes in notified equipment.

(a) Under the notification procedure, the grantee warrants that each unit of equipment marketed under the identification specified in the grant of equipment authorization will conform to the unit(s) tested and found acceptable by the grantee and that data on file with the grantee, as required in §2.938, continues to be representative of the equipment being produced under such notification within the variation that can be expected due to quantity production and testing on a statistical basis.

(b) Changes in the electrical and mechanical construction of equipment requiring an application for, and grant of, notification are permissive, providing that the changes do not cause the equipment to exceed the standards applicable to that equipment.

(c) Permissive changes to transmitters notified for operation under part 73 of this chapter include the following:

(1) The interconnection of a type accepted AM broadcast stereophonic exciter-generator with a notified AM broadcast transmitter in accordance with the manufacturer's instructions and upon completion of measurements showing that the modified transmitter

meets the emission limitations applicable thereto.

(2) The interconnection of a utility load management exciter with a notified AM broadcast transmitter in accordance with the manufacturer's instructions and completion of equipment performance measurements showing the transmitter meets the minimum performance requirements applicable thereto.

(3) The addition of TV broadcast subcarrier generators to a notified TV broadcast transmitter or the addition of FM broadcast subcarrier generators to a notified FM broadcast transmitter, provided the transmitter exciter is designed for subcarrier operation without mechanical or electrical alterations to the exciter or other transmitter circuits.

(4) The addition of TV broadcast stereophonic generators to a notified TV broadcast transmitter or the addition of FM broadcast stereophonic generators to a notified FM broadcast transmitter, provided the transmitter exciter is designed for stereophonic sound operation without mechanical or electrical alterations to the exciter or other transmitter circuits.

(5) The addition of subscription TV encoding equipment for which the FCC has granted advance approval under the provisions of §2.1400 in subpart M and §73.644(c) of part 73 of this chapter to a notified transmitter.

(d) Notwithstanding the provisions of this section, broadcast licensees or permittees are permitted to modify notified transmitters pursuant to §73.1690 of the FCC's Rules.

[48 FR 3621, Jan. 26, 1983, as amended at 49 FR 3996, Feb. 1, 1984; 49 FR 8252, Mar. 6, 1984; 49 FR 27147, July 2, 1984; 51 FR 2706, Jan. 21, 1986; 51 FR 41628, Nov. 18, 1986]

TYPE ACCEPTANCE

§2.981 Cross reference.

(a) The general provisions of this subpart, §2.901 *et seq.*, shall apply to applications for and grants of type acceptance.

(b) [Reserved]

§ 2.983

47 CFR Ch. I (10–1–97 Edition)

§ 2.983 Application for type acceptance.

An application for type acceptance shall be filed on FCC Form 731 by the party whose name will be placed on the equipment and shall include the following information either in answer to the questions on the form or as attachments thereto.

(a) Name of applicant indicating whether the applicant is the manufacturer of the equipment, a vendor other than the manufacturer (include the name of manufacturer), a licensee or a prospective licensee.

(b) Identification of equipment for which type acceptance is sought.

(c) Information whether quantity (more than one) production is planned.

(d) Technical description of the equipment sufficiently complete to develop all the factors concerning compliance with the technical standards of the applicable rule part(s). The description shall include the following items:

(1) Type or types of emission.

(2) Frequency range.

(3) Range of operating power values or specific operating power levels, and description of any means provided for variation of operating power.

(4) Maximum power rating as defined in the applicable part(s) of the rules.

(5) The dc voltages applied to and dc currents into the several elements of the final radio frequency amplifying device for normal operation over the power range.

(6) Function of each electron tube or semiconductor or other active circuit device.

(7) Complete circuit diagrams.

(8) Instruction book(s). If the instruction book is not available when the application is filed, a set of draft instructions should be provided and the complete instruction book should be submitted as soon as available. The Commission may specify a date when the complete instruction book should be submitted to conform this requirement with the regulations of the service under which type acceptance is requested.

(9) Tune-up procedure over the power range, or at specific operating power levels.

(10) A description of all circuitry and devices provided for determining and stabilizing frequency.

(11) A description of any circuits or devices employed for suppression of spurious radiation, for limiting modulation, and for limiting power.

(12) For equipment employing digital modulation techniques, a detailed description of the modulation system to be used, including the response characteristics (frequency, phase and amplitude) of any filters provided, and a description of the modulating wavetrain, shall be submitted for the maximum rated conditions under which the equipment will be operated.

(e) The data required by §§ 2.985 through 2.997, inclusive, measured in accordance with the procedures set out in § 2.999.

(f) A photograph or drawing of the equipment identification plate or label showing the information to be placed thereon.

(g) Photographs (8"×10") of the equipment of sufficient clarity to reveal equipment construction and layout, including meters, if any, and labels for controls and meters and sufficient views of the internal construction to define component placement and chassis assembly. Insofar as these requirements are met by photographs or drawings contained in instruction manuals supplied with the type acceptance request, additional photographs are necessary only to complete the required showing.

(h) [Reserved]

(i) The application for type acceptance of an external radio frequency power amplifier under part 97 of this chapter need not be accompanied by the data required by paragraph (e) of this section. In lieu thereof, measurements shall be submitted to show compliance with the technical specifications in subpart D of part 97 of this chapter and such information as required by § 2.1005 of this part.

(j) An application for type acceptance of an AM broadcast stereophonic exciter-generator intended for interfacing with existing type-accepted or notified transmitters must include measurements made on a complete stereophonic transmitter. The instruction book required under paragraph (d)(8) of

Federal Communications Commission

§2.985

this section must include complete specifications and circuit requirements for interconnecting with existing transmitters. The instruction book must also provide a full description of the equipment and measurement procedures to monitor modulation and to verify that the combination of stereo exciter-generator and transmitter meet the emission limitations of §73.44.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[39 FR 5919, Feb. 15, 1974, as amended at 39 FR 27802, Aug. 1, 1974; 39 FR 35664, Oct. 3, 1974; 40 FR 34117, Aug. 14, 1975; 41 FR 19948, May 14, 1976; 43 FR 12687, Mar. 27, 1978; 52 FR 15725, Apr. 30, 1987; 62 FR 10473, Mar. 7, 1997]

§2.985 Measurements required: RF power output.

(a) For transmitters other than single sideband, independent sideband and controlled carrier radiotelephone, power output shall be measured at the RF output terminals when the transmitter is adjusted in accordance with the tune-up procedure to give the values of current and voltage on the circuit elements specified in §2.983(d)(5). The electrical characteristics of the radio frequency load attached to the output terminals when this test is made shall be stated.

(b) For single sideband, independent sideband, and single channel, controlled carrier radiotelephone transmitters the procedure specified in paragraph (a) of this section shall be employed and, in addition, the transmitter shall be modulated during the test as follows. In all tests, the input level of the modulating signal shall be such as to develop rated peak envelope power or carrier power, as appropriate, for the transmitter.

(1) Single sideband transmitters in the A3A or A3J emission modes—by two tones at frequencies of 400 Hz and 1800 Hz (for 3.0 kHz authorized bandwidth), or 500 Hz and 2100 Hz (3.5 kHz authorized bandwidth), or 500 Hz and 2400 Hz (for 4.0 kHz authorized bandwidth), applied simultaneously, the input levels of the tones so adjusted that the two principal frequency components of the radio frequency signal produced are equal in magnitude.

(2) Single sideband transmitters in the A3H emission mode—by one tone at

a frequency of 1500 Hz (for 3.0 kHz authorized bandwidth), or 1700 Hz (for 3.5 kHz authorized bandwidth), or 1900 Hz (for 4.0 kHz authorized bandwidth), the level of which is adjusted to produce a radio frequency signal component equal in magnitude to the magnitude of the carrier in this mode.

(3) As an alternative to paragraphs (b) (1) and (2) of this section other tones besides those specified may be used as modulating frequencies, upon a sufficient showing of need. However, any tones so chosen must not be harmonically related, the third and fifth order intermodulation products which occur must fall within the -25 dB step of the emission bandwidth limitation curve, the seventh and ninth order intermodulation product must fall within the 35 dB step of the referenced curve and the eleventh and all higher order products must fall beyond the -35 dB step of the referenced curve.

(4) Independent sideband transmitters having two channels by 1700 Hz tones applied simultaneously in both channels, the input levels of the tones so adjusted that the two principal frequency components of the radio frequency signal produced are equal in magnitude.

(5) Independent sideband transmitters having more than two channels by an appropriate signal or signals applied to all channels simultaneously. The input signal or signals shall simulate the input signals specified by the manufacturer for normal operation.

(6) Single-channel controlled-carrier transmitters in the A3 emission mode—by a 2500 Hz tone.

(c) For measurements conducted pursuant to paragraphs (a) and (b) of this section, all calculations and methods used by the applicant for determining carrier power or peak envelope power, as appropriate, on the basis of measured power in the radio frequency load attached to the transmitter output terminals shall be shown. Under the test conditions specified, no components of the emission spectrum shall exceed the limits specified in the applicable rule parts as necessary for meeting occupied bandwidth or emission limitations.

§2.987 Measurements required: Modulation characteristics.

(a) *Voice modulated communication equipment.* A curve or equivalent data showing the frequency response of the audio modulating circuit over a range of 100 to 5000 Hz shall be submitted. For equipment required to have an audio low-pass filter, a curve showing the frequency response of the filter, or of all circuitry installed between the modulation limiter and the modulated stage shall be submitted.

(b) *Equipment which employs modulation limiting.* A curve or family of curves showing the percentage of modulation versus the modulation input voltage shall be supplied. The information submitted shall be sufficient to show modulation limiting capability throughout the range of modulating frequencies and input modulating signal levels employed.

(c) *Single sideband and independent sideband radiotelephone transmitters which employ a device or circuit to limit peak envelope power.* A curve showing the peak envelope power output versus the modulation input voltage shall be supplied. The modulating signals shall be the same in frequency as specified in paragraph (c) of §2.989 for the occupied bandwidth tests.

(d) *Other types of equipment.* A curve or equivalent data which shows that the equipment will meet the modulation requirements of the rules under which the equipment is to be licensed.

§2.989 Measurements required: Occupied bandwidth.

The occupied bandwidth, that is the frequency bandwidth such that, below its lower and above its upper frequency limits, the mean powers radiated are each equal to 0.5 percent of the total mean power radiated by a given emission shall be measured under the following conditions as applicable:

(a) Radiotelegraph transmitters for manual operation when keyed at 16 dots per second.

(b) Other keyed transmitters—when keyed at the maximum machine speed.

(c) Radiotelephone transmitters equipped with a device to limit modulation or peak envelope power shall be modulated as follows. For single sideband and independent sideband trans-

mitters, the input level of the modulating signal shall be 10 dB greater than that necessary to produce rated peak envelope power.

(1) Other than single sideband or independent sideband transmitters—when modulated by a 2500 Hz tone at an input level 16 dB greater than that necessary to produce 50 percent modulation. The input level shall be established at the frequency of maximum response of the audio modulating circuit.

(2) Single sideband transmitters in A3A or A3J emission modes—when modulated by two tones at frequencies of 400 Hz and 1800 Hz (for 3.0 kHz authorized bandwidth), or 500 Hz and 2100 Hz (for 3.5 kHz authorized bandwidth), or 500 Hz and 2400 Hz (for 4.0 kHz authorized bandwidth), applied simultaneously. The input levels of the tones shall be so adjusted that the two principal frequency components of the radio frequency signal produced are equal in magnitude.

(3) Single sideband transmitters in the A3H emission mode—when modulated by one tone at a frequency of 1500 Hz (for 3.0 kHz authorized bandwidth), or 1700 Hz (for 3.5 kHz authorized bandwidth), or 1900 Hz (for 4.0 kHz authorized bandwidth), the level of which is adjusted to produce a radio frequency signal component equal in magnitude to the magnitude of the carrier in this mode.

(4) As an alternative to paragraphs (c) (2) and (3) of this section, other tones besides those specified may be used as modulating frequencies, upon a sufficient showing of need. However, any tones so chosen must not be harmonically related, the third and fifth order intermodulation products which occur must fall within the –25 dB step of the emission bandwidth limitation curve, the seventh and ninth order products must fall within the –35 dB step of the referenced curve and the eleventh and all higher order products must fall beyond the –35 dB step of the referenced curve.

(5) Independent sideband transmitters having two channels—when modulated by 1700 Hz tones applied simultaneously to both channels. The input levels of the tones shall be so adjusted

that the two principal frequency components of the radio frequency signal produced are equal in magnitude.

(d) Radiotelephone transmitters without a device to limit modulation or peak envelope power shall be modulated as follows. For single sideband and independent sideband transmitters, the input level of the modulating signal should be that necessary to produce rated peak envelope power.

(1) Other than single sideband or independent sideband transmitters—when modulated by a 2500 Hz tone of sufficient level to produce at least 85 percent modulation. If 85 percent modulation is unattainable, the highest percentage modulation shall be used.

(2) Single sideband transmitters in A3A or A3J emission modes—when modulated by two tones at frequencies of 400 Hz and 1800 Hz (for 3.0 kHz authorized bandwidth), or 500 Hz and 2100 Hz (for 3.5 kHz authorized bandwidth), or 500 Hz and 2400 Hz (for 4.0 kHz authorized bandwidth), applied simultaneously. The input levels of the tones shall be so adjusted that the two principal frequency components of the radio frequency signal produced are equal in magnitude.

(3) Single sideband transmitters in the A3H emission mode—when modulated by one tone at a frequency of 1500 Hz (for 3.0 kHz authorized bandwidth), or 1700 Hz (for 3.5 kHz authorized bandwidth), or 1900 Hz (for 4.0 kHz authorized bandwidth), the level of which is adjusted to produce a radio frequency signal component equal in magnitude to the magnitude of the carrier in this mode.

(4) As an alternative to paragraphs (d) (2) and (3) of this section, other tones besides those specified may be used as modulating frequencies, upon a sufficient showing of need. However any tones so chosen must not be harmonically related, the third and fifth order intermodulation products which occur must fall within the -25 dB step of the emission bandwidth limitation curve, the seventh and ninth order products must fall within the -35 dB step of the referenced curve and the eleventh and all higher order products must fall beyond the -35 dB step of the referenced curve.

(5) Independent sideband transmitters having two channels—when modulated by 1700 Hz tones applied simultaneously to both channels. The input levels of the tones shall be so adjusted that the two principal frequency components of the radio frequency signal produced are equal in magnitude.

(e) Transmitters for use in the Radio Broadcast Services:

(1) AM broadcast transmitters for monaural operation—when amplitude modulated 85% by a 7,500 Hz input signal.

(2) AM broadcast stereophonic operation—when the transmitter operated under any stereophonic modulation condition not exceeding 100% on negative peaks and tested under the conditions specified in §73.128 in part 73 of the FCC rules for AM broadcast stations.

(3) FM broadcast transmitter not used for multiplex operation—when modulated 85 percent by a 15 kHz input signal.

(4) FM broadcast transmitters for multiplex operation under Subsidiary Communication Authorization (SCA)—when carrier is modulated 70 percent by a 15 kHz main channel input signal, and modulated an additional 15 percent simultaneously by a 67 kHz subcarrier (unmodulated).

(5) FM broadcast transmitter for stereophonic operation—when modulated by a 15 kHz input signal to the main channel, a 15 kHz input signal to the stereophonic subchannel, and the pilot subcarrier simultaneously. The input signals to the main channel and stereophonic subchannel each shall produce 38 percent modulation of the carrier. The pilot subcarrier should produce 9 percent modulation of the carrier.

(6) Television broadcast monaural transmitters—when modulated 85% by a 15 kHz input signal.

(7) Television broadcast stereophonic sound transmitters—when the transmitter is modulated with a 15 kHz input signal to the main channel and the stereophonic subchannel, any pilot subcarrier(s) and any unmodulated auxiliary subcarrier(s) which may be provided. The signals to the main channel and the stereophonic subchannel must be representative of the system

§2.991

47 CFR Ch. I (10–1–97 Edition)

being tested and when combined with any pilot subcarrier(s) or other auxiliary subcarriers shall result in 85% deviation of the maximum specified aural carrier deviation.

(f) Transmitters for which peak frequency deviation (D) is determined in accordance with §2.202(f), and in which the modulating baseband comprises more than 3 independent speech channels—when modulated by a test signal determined in accordance with the following:

(1) A modulation reference level is established for the characteristic baseband frequency. (Modulation reference level is defined as the average power level of a sinusoidal test signal

delivered to the modulator input which provides the specified value of per-channel deviation.)

(2) Modulation reference level being established, the total rms deviation of the transmitter is measured when a test signal consisting of a band of random noise extending from below 20 kHz to the highest frequency in the baseband, is applied to the modulator input through any preemphasis networks used in normal service. The average power level of the test signal shall exceed the modulation reference level by the number of decibels determined using the appropriate formula in the following table:

Number of message circuits that modulate the transmitter	Number of dB by which the average power (P_{avg}) level test signal shall exceed the modulation reference level	Limits of P_{avg} (dBm0)
More than 3, but less than 12	To be specified by the equipment manufacturer subject to FCC approval.	
At least 12, but less than 60	$X+2 \log_{10} N_c$	X: -2 to +2.6
At least 60, but less than 240	$X+4 \log_{10} N_c$	X: -5.6 to -1.0
240 or more	$X+10 \log_{10} N_c$	X: -19.6 to -15.0

Where X represents the average power in a message circuit in dBm0; N_c is the number of circuits in the multiplexed message load. P_{avg} shall be selected by the transmitter manufacturer and included with the technical data submitted with the application for type acceptance. (See §2.202(e) in this chapter.)

(g) Transmitters in which the modulating baseband comprises not more than three independent channels—when modulated by the full complement of signals for which the transmitter is rated. The level of modulation for each channel should be set to that prescribed in rule parts applicable to the services for which the transmitter is intended. If specific modulation levels are not set forth in the rules, the tests should provide the manufacturer's maximum rated condition.

(h) Transmitters employing digital modulation techniques—when modulated by an input signal such that its amplitude and symbol rate represent the maximum rated conditions under which the equipment will be operated. The signal shall be applied through any filter networks, pseudo-random generators or other devices required in normal service. Additionally, the occupied bandwidth shall be shown for operation with any devices used for modifying the spectrum when such devices are optional at the discretion of the user.

(i) Transmitters designed for other types of modulation—when modulated by an appropriate signal of sufficient

amplitude to be representative of the type of service in which used. A description of the input signal should be supplied.

(Secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[39 FR 5919, Feb. 15, 1974, as amended at 39 FR 35664, Oct. 3, 1974; 47 FR 13164, Mar. 29, 1982; 48 FR 16493, Apr. 18, 1983; 49 FR 18105, Apr. 27, 1984]

§2.991 Measurements required: Spurious emissions at antenna terminals.

The radio frequency voltage or powers generated within the equipment and appearing on a spurious frequency shall be checked at the equipment output terminals when properly loaded with a suitable artificial antenna. Curves or equivalent data shall show the magnitude of each harmonic and other spurious emission that can be detected when the equipment is operated under the conditions specified in §2.989 as appropriate. The magnitude of spurious emissions which are attenuated more than 20 dB below the permissible value need not be specified.

Federal Communications Commission

§2.995

§2.993 Measurements required: Field strength of spurious radiation.

(a) Measurements shall be made to detect spurious emissions that may be radiated directly from the cabinet, control circuits, power leads, or intermediate circuit elements under normal conditions of installation and operation. Curves or equivalent data shall be supplied showing the magnitude of each harmonic and other spurious emission. For this test, single sideband, independent sideband, and controlled carrier transmitters shall be modulated under the conditions specified in paragraph (c) of §2.989, as appropriate. For equipment operating on frequencies below 890 MHz, an open field test is normally required, with the measuring instrument antenna located in the far-field at all test frequencies. In the event it is either impractical or impossible to make open field measurements (e.g. a broadcast transmitter installed in a building) measurements will be accepted of the equipment as installed. Such measurements must be accompanied by a description of the site where the measurements were made showing the location of any possible source of reflections which might distort the field strength measurements. Information submitted shall include the relative radiated power of each spurious emission with reference to the rated power output of the transmitter, assuming all emissions are radiated from halfwave dipole antennas.

(b) The measurements specified in paragraph (a) of this section shall be made for the following equipment:

(1) Those in which the spurious emissions are required to be 60 dB or more below the mean power of the transmitter.

(2) All equipment operating on frequencies higher than 25 MHz.

(3) All equipment where the antenna is an integral part of, and attached directly to the transmitter.

(4) Other types of equipment as required, when deemed necessary by the Commission.

§2.995 Measurements required: Frequency stability.

(a) The frequency stability shall be measured with variation of ambient temperature as follows:

(1) From -30° to $+50^{\circ}$ centigrade for all equipment except that specified in paragraphs (a) (2) and (3) of this section.

(2) From -20° to $+50^{\circ}$ centigrade for equipment to be licensed for use in the Maritime Services under part 80 of this chapter, except for Class A, B, and S Emergency Position Indicating Radiobeacons (EPIRBS), and equipment to be licensed for use above 952 MHz at operational fixed stations in all services, stations in the Local Television Transmission Service and Point-to-Point Microwave Radio Service under part 21 of this chapter, and equipment licensed for use aboard aircraft in the Aviation Services under part 87 of this chapter.

(3) From 0° to $+50^{\circ}$ centigrade for equipment to be licensed for use in the Radio Broadcast Services under part 73 of this chapter.

(b) Frequency measurements shall be made at the extremes of the specified temperature range and at intervals of not more than 10° centigrade through the range. A period of time sufficient to stabilize all of the components of the oscillator circuit at each temperature level shall be allowed prior to frequency measurement. The short term transient effects on the frequency of the transmitter due to keying (except for broadcast transmitters) and any heating element cycling normally occurring at each ambient temperature level also shall be shown. Only the portion or portions of the transmitter containing the frequency determining and stabilizing circuitry need be subjected to the temperature variation test.

(c) In addition to all other requirements of this section, the following information is required for equipment incorporating heater type crystal oscillators to be used in mobile stations, for which type acceptance is first requested after March 25, 1974, except for battery powered, hand carried, portable equipment having less than 3 watts mean output power.

(1) Measurement data showing variation in transmitter output frequency from a cold start and the elapsed time necessary for the frequency to stabilize within the applicable tolerance. Tests

§2.997

47 CFR Ch. I (10–1–97 Edition)

shall be made after temperature stabilization at each of the ambient temperature levels; the lower temperature limit, 0° centigrade and +30° centigrade with no primary power applied.

(2) Beginning at each temperature level specified in paragraph (c)(1) of this section, the frequency shall be measured within one minute after application of primary power to the transmitter and at intervals of no more than one minute thereafter until ten minutes have elapsed or until sufficient measurements are obtained to indicate clearly that the frequency has stabilized within the applicable tolerance, whichever time period is greater. During each test, the ambient temperature shall not be allowed to rise more than 10° centigrade above the respective beginning ambient temperature level.

(3) The elapsed time necessary for the frequency to stabilize within the applicable tolerance from each beginning ambient temperature level as determined from the tests specified in this paragraph shall be specified in the instruction book for the transmitter furnished to the user.

(4) When it is impracticable to subject the complete transmitter to this test because of its physical dimensions or power rating, only its frequency determining and stabilizing portions need be tested.

(d) The frequency stability shall be measured with variation of primary supply voltage as follows:

(1) Vary primary supply voltage from 85 to 115 percent of the nominal value for other than hand carried battery equipment.

(2) For hand carried, battery powered equipment, reduce primary supply voltage to the battery operating end point which shall be specified by the manufacturer.

(3) The supply voltage shall be measured at the input to the cable normally provided with the equipment, or at the power supply terminals if cables are not normally provided. Effects on frequency of transmitter keying (except for broadcast transmitters) and any heating element cycling at the nominal supply voltage and at each extreme also shall be shown.

(e) When deemed necessary, the Commission may require tests of frequency stability under conditions in addition to those specifically set out in paragraphs (a), (b), (c), and (d) of this section. (For example measurements showing the effect of proximity to large metal objects, or of various types of antennas, may be required for portable equipment.)

[39 FR 5919, Feb. 14, 1974, as amended at 51 FR 31304, Sept. 2, 1986; 56 FR 11682, Mar. 20, 1991]

§2.997 Frequency spectrum to be investigated.

(a) In all of the measurements set forth in §§2.991 and 2.993, the spectrum shall be investigated from the lowest radio frequency signal generated in the equipment, without going below 9 kHz, up to at least the frequency shown below:

(1) If the equipment operates below 10 GHz: to the tenth harmonic of the highest fundamental frequency or to 40 GHz, whichever is lower.

(2) If the equipment operates at or above 10 GHz and below 30 GHz: to the fifth harmonic of the highest fundamental frequency or to 100 GHz, whichever is lower.

(3) If the equipment operates at or above 30 GHz: to the fifth harmonic of the highest fundamental frequency or to 200 GHz, whichever is lower.

(b) Particular attention should be paid to harmonics and subharmonics of the carrier frequency as well as to those frequencies removed from the carrier by multiples of the oscillator frequency. Radiation at the frequencies of multiplier stages should also be checked.

(c) The amplitude of spurious emissions which are attenuated more than 20 dB below the permissible value need not be reported.

(d) Unless otherwise specified, measurements above 40 GHz shall be performed using a minimum resolution bandwidth of 1 MHz.

[61 FR 14502, Apr. 2, 1996]

§2.999 Measurement procedure.

The measurement procedures employed shall be in accordance with the

Federal Communications Commission

§2.1001

requirements set forth in §2.947. In addition, any specific test requirements set forth in the particular rules governing the equipment for which type acceptance is requested shall apply.

[42 FR 44987, Sept. 8, 1977]

§2.1001 Changes in type accepted equipment.

(a) Equipment of the same type is defined for purposes of type acceptance as being equipment which is electrically and mechanically interchangeable and in addition will have the same basic tube or semiconductor lineup, frequency multiplication, basic frequency determining and stabilizing circuitry, basic modulator circuit and maximum power rating. Variations in electrical and mechanical construction, other than the items indicated above are permitted provided the variation or change is made in compliance with the requirements of paragraphs (b), (c), and (d) of this section.

(b) Two classes of permissive changes may be made in type accepted equipment without requiring a new application for and grant of type acceptance.

(1) A Class I permissive change includes those modifications in the equipment which do not change the equipment characteristics beyond the rated limits established by the manufacturer and accepted by the Commission when type acceptance is granted, and which do not change the type of equipment as defined in paragraph (a) of this section. No filing with the Commission is required for a Class I permissive change.

(2) A Class II permissive change includes those modifications which bring the performance of the equipment outside the manufacturer's rated limits as originally filed but not below the minimum requirements of the applicable rules, and do not change the type of equipment as defined in paragraph (a) of this section. When a Class II permissive change is made by the grantee, he shall supply the Commission with complete information and results of tests of the characteristics affected by such change. The modified equipment shall not be marketed under the existing grant of type acceptance prior to acknowledgement by the Commission that the change is acceptable.

(3) When a Class II permissive change is made by other than the grantee of type acceptance, the information and data specified in paragraph (b)(2) of this section shall be supplied by the person making the change. The modified equipment shall not be operated under an authorization of the Commission prior to acknowledgement by the Commission that the change is acceptable.

(c) A grantee desiring to make a change other than a permissive change as described in paragraph (b) of this section shall file an application on FCC Form 731 accompanied by the required fees. The grantee shall attach a description of the change(s) to be made and a statement indicating whether the change(s) will be made in all units (including previous production) or will be made only in those units produced after the change(s) is authorized.

(d) If the Commission authorizes the changes requested, it may require the assignment of a new FCC Identifier.

(e) Users shall not modify their own equipment except as provided by paragraphs (b) and (f) of this section.

(f) Equipment type accepted for use in the Amateur Radio Service pursuant to the requirements of part 97 of this chapter may be modified without regard to the conditions specified in paragraph (b) of this section, provided the following conditions are met:

(1) Any person performing such modifications on equipment used under part 97 of this chapter must possess a valid amateur radio operator license of the class required for the use of the equipment being modified.

(2) Modifications made pursuant to this paragraph are limited to equipment used at licensed amateur radio stations.

(3) Modifications specified or performed by equipment manufacturers or suppliers must be in accordance with the requirements set forth in paragraph (b) of this section.

(4) Modifications specified or performed by licensees in the Amateur Radio Service on equipment other than that at specific licensed amateur radio stations must be in accordance with the requirements set forth in paragraph (b) of this section.

§2.1005

47 CFR Ch. I (10–1–97 Edition)

(5) The station licensee shall be responsible for insuring that modified equipment used at his station will comply with the applicable technical standards in part 97 of this chapter.

(g) The interconnection of a type accepted AM broadcast stereophonic exciter-generator with a type accepted AM broadcast transmitter in accordance with the manufacturer's instructions and upon completion of measurements showing that the modified transmitter meets the emission limitation requirements of §73.44 is defined as a Class I permissive change for compliance with this section.

(h) The interconnection of a multiplexing exciter with a type accepted AM broadcast transmitter in accordance with the manufacturer's instructions without electrical or mechanical modification of the transmitter circuits and completion of equipment performance measurements showing the transmitter meets the minimum performance requirements applicable thereto is defined as a Class I permissive change for compliance with this section.

(i) The addition of TV broadcast subcarrier generators to a type accepted TV broadcast transmitter or the addition of FM broadcast subcarrier generators to a type accepted FM broadcast transmitter, provided the transmitter exciter is designed for subcarrier operation without mechanical or electrical alterations to the exciter or other transmitter circuits.

(j) The addition of TV broadcast stereophonic generators to a type accepted TV broadcast transmitter or the addition of FM broadcast stereophonic generators to a type accepted FM broadcast transmitter, provided the transmitter exciter is designed for stereophonic sound operation without mechanical or electrical alterations to the exciter or other transmitter circuits.

(k) The addition of subscription TV encoding equipment for which the FCC has granted advance approval under the provisions of §2.1400 in subpart M and §73.644(c) of part 73 to a type accepted transmitter is considered a Class I permissive change described in paragraph (b)(1) of this section.

(l) Notwithstanding the provisions of this section, broadcast licensees or permittees are permitted to modify type accepted equipment pursuant to §73.1690 of the FCC's Rules.

[39 FR 5919, Feb. 15, 1974, as amended at 39 FR 27803, Aug. 1, 1974; 41 FR 19948, May 14, 1976; 43 FR 12687, Mar. 27, 1978; 46 FR 18981, Mar. 27, 1981; 48 FR 56391, Dec. 21, 1983; 49 FR 27147, July 2, 1984; 49 FR 34014, Aug. 28, 1984; 51 FR 2707, Jan. 21, 1986; 51 FR 39535, Oct. 29, 1986; 51 FR 41628, Nov. 18, 1986]

§2.1005 Equipment for use in the Amateur Radio Service.

(a) The general provisions of §§2.981, 2.983, 2.991, 2.993, 2.997, 2.999, and 2.1001 shall apply to applications for, and grants of, type acceptance for equipment operated under the requirements of part 97 of this chapter, the Amateur Radio Service.

(b) When performing the tests specified in §§2.991 and 2.993 of this part, the center of the transmitted bandwidth shall be within the operating frequency band by an amount equal to 50 percent of the bandwidth utilized for the tests. In addition, said tests shall be made on at least one frequency in each of the bands within which the equipment is capable of tuning.

(c) Any supplier of an external radio frequency power amplifier kit as defined by §97.3(a)(17) of this chapter shall comply with the following requirements:

(1) Assembly of one unit of a specific type shall be made in exact accordance with the instructions being supplied with the product being marketed. If all of the necessary components are not normally furnished with the kit, assembly shall be made using the recommended components.

(2) The measurement data required for type acceptance shall be obtained for this unit and submitted with the type acceptance application. Unless otherwise requested, it is not necessary to submit this unit with the application.

(3) A copy of the exact instructions which will be provided for assembly of the equipment shall be provided in addition to other material required by §2.983 of this part.

(4) The identification label required by §2.925 shall be permanently affixed

Federal Communications Commission

§2.1033

to the assembled unit and shall be of sufficient size so as to be easily read. The following information shall be shown on the label:

(Name of Grantee of Type Acceptance)

FCC ID: (The number assigned to the equipment by the Grantor)

This amplifier can be expected to comply with part 97 of the FCC Regulations when assembled and aligned in strict accordance with the instruction manual using components supplied with the kit or an exact equivalent thereof.

(Title and signature of responsible representative of Grantee)

STATEMENT OF COMPLIANCE

I state that I have constructed this equipment in accordance with the instruction manual and using the parts furnished by the supplier of this kit.

(Signature) (Date)

(Amateur call sign) (Class of license)

(Expiration date of license)

(To be signed by the person responsible for proper assembly of kit.)

(5) If requested, an unassembled unit shall be provided for assembly and test by the Commission. Shipping charges to and from the Commission's Laboratory shall be borne by the applicant for type acceptance.

(d) Type acceptance of external radio frequency power amplifiers and amplifier kits may be denied when denial serves the public interest, convenience and necessity by preventing the use of these amplifiers in services other than the Amateur Radio Service. Other uses of these amplifiers, such as in the Citizens Band Radio Service, are prohibited (§95.411 of this chapter). Examples of features which may result in the denial of type acceptance are contained in §97.317 of this chapter.

(Sec. 302, 82 Stat. 290; 47 U.S.C. 302; secs. 4, 303, 307, 48 Stat., as amended, 1066, 1082, 1083; 47 U.S.C. 154, 303, 307)

[43 FR 12688, Mar. 27, 1978, as amended at 46 FR 18981, Mar. 27, 1981; 62 FR 10473, Mar. 7, 1997]

CERTIFICATION

§2.1031 Cross reference.

The general provisions of this subpart §2.901 *et seq.* shall apply to applications for and grants of certification.

§2.1033 Application for certification.

(a) An application for certification shall be filed on FCC Form 731 with all questions answered. Items that do not apply shall be so noted.

(b) The application shall be accompanied by a technical report containing the following information:

(1) The full name and mailing address of the manufacturer of the device and the applicant for certification.

(2) FCC identifier.

(3) A copy of the installation and operating instructions to be furnished the user. A draft copy of the instructions may be submitted if the actual document is not available. The actual document shall be furnished to the FCC when it becomes available.

(4) A brief description of the circuit functions of the device along with a statement describing how the device operates. This statement should contain a description of the ground system and antenna, if any, used with the device.

(5) A block diagram showing the frequency of all oscillators in the device. The signal path and frequency shall be indicated at each block. The tuning range(s) and intermediate frequency(ies) shall be indicated at each block. A schematic diagram also is required for intentional radiators.

(6) A report of measurements of radiated and conducted emissions. This shall identify the test procedure used (e.g., indicate the FCC test procedure used or, if an alternate test procedure was used, a description of the test procedure and the reason it was necessary to use an alternate procedure), the date the measurements were made, the location where the measurements were made, and the device tested (model and serial number, if available). It shall also include a sample calculation showing how the obtained measurements were converted to the levels specified in the applicable rule sections.

§2.1035

(7) A sufficient number of photographs to clearly show the exterior appearance, the construction, the component placement on the chassis, and the chassis assembly. The exterior views shall show the overall appearance, the antenna used with the device (if any), the controls available to the user, and the required identification label in sufficient detail so that the name and FCC identifier can be read. In lieu of a photograph of the label, a sample label (or facsimile thereof) may be submitted together with a sketch showing where this label will be placed on the equipment. Photographs shall be of size A4 (21 cm × 29.7 cm) or 8×10 inches (20.3 cm × 25.4 cm). Smaller photographs may be submitted provided they are sharp and clear, show the necessary detail, and are mounted on A4 (21 cm × 29.7 cm) or 8.5×11 inch (21.6 cm × 27.9 cm) paper. A sample label or facsimile together with the sketch showing the placement of this label shall be on the same size paper.

(8) If the equipment for which certification is being sought must be tested with peripheral or accessory devices connected or installed, a brief description of those peripherals or accessories. The peripheral or accessory devices shall be unmodified, commercially available equipment.

(9) For equipment subject to the provisions of part 15 of this chapter, the application shall indicate if the equipment is being authorized pursuant to the transition provisions in §15.37 of this chapter.

(10) [Reserved]

(11) Applications for the certification of direct sequence spread spectrum transmitters under part 15 shall be accompanied by an exhibit demonstrating compliance with the processing gain provisions of §15.247(e) of this chapter. Applications for the certification of frequency hopping transmitters under part 15 shall be accompanied by an exhibit describing compliance of the associated receiver or receivers with §15.247(a)(1) of this chapter.

(12) Applications for the certification of scanning receivers shall include a statement describing the methods used to comply with the design requirements of §15.121(a) of this chapter or

47 CFR Ch. I (10–1–97 Edition)

the marketing requirements of §15.121(b) of this chapter.

(c) For a composite system that incorporates only devices subject to certification, verification and/or notification and that are contained in a single enclosure, a separate application, FCC Form 731, shall be submitted with the appropriate fee for each type of device within the enclosure. At the option of the applicant, a single FCC identifier may be requested for that system. Fees are based on the number of devices and types of authorizations.

[39 FR 5919, Feb. 15, 1974, as amended at 39 FR 27803, Aug. 1, 1974; 41 FR 19948, May 14, 1976; 50 FR 36067, Sept. 5, 1985; 54 FR 17713, Apr. 25, 1989; 55 FR 28762, July 13, 1990; 58 FR 25575, Apr. 27, 1993; 58 FR 44893, Aug. 25, 1993; 62 FR 10473, Mar. 7, 1997]

§2.1035 [Reserved]

§2.1041 Measurement procedure.

The measurement procedures are specified in the rules governing the particular device for which certification is requested.

§2.1043 Changes in certificated equipment.

(a) Changes to the basic frequency determining and stabilizing circuitry (including clock or data rates), frequency multiplication stages, basic modulator circuit or maximum power or field strength ratings shall not be performed without application for and authorization of a new grant of certification. Variations in electrical or mechanical construction, other than these indicated items, are permitted provided the variations either do not affect the characteristics required to be reported to the Commission or the variations are made in compliance with the other provisions of this section.

(b) Two classes of permissive changes may be made in certificated equipment without requiring a new application for and grant of certification. Neither class of change shall result in a change in identification.

(1) A Class I permissive change includes those modifications in the equipment which do not degrade the

Federal Communications Commission

§2.1065

characteristics reported by the manufacturer and accepted by the Commission when certification is granted. No filing with the Commission is required for a Class I permissive change.

(2) A Class II permissive change includes those modifications which degrade the performance characteristics as reported to the Commission at the time of the initial certification. Such degraded performance must still meet the minimum requirements of the applicable rules. When a Class II permissive change is made by the grantee, he shall supply the Commission with complete information and the results of tests of the characteristics affected by such change. The modified equipment shall not be marketed under the existing grant of certification prior to acknowledgement by the Commission that the change is acceptable.

(3) Permissive changes, as detailed above, shall be made only by the holder of the grant of certification. Changes by any party other than the grantee require a new application for and grant of certification.

(c) A grantee desiring to make a change other than a permissive change shall file an application on FCC Form 731 accompanied by the required fees. The grantee shall attach a description of the change(s) to be made and a statement indicating whether the change(s) will be made in all units (including previous production) or will be made only in those units produced after the change is authorized.

(d) A modification which results in a change in the identification with or without change in circuitry requires a new application for, and grant of certification. If the changes affect the characteristics required to be reported, a complete application shall be filed. If the characteristics required to be reported are not changed the abbreviated procedure of §2.933 may be used.

[39 FR 27803, Aug. 1, 1974, as amended at 41 FR 19948, May 14, 1976; 54 FR 1699, Jan. 17, 1989; 54 FR 17714, Apr. 25, 1989; 54 FR 32339, Aug. 7, 1989]

FILING FOR APPLICATION REFERENCE

§2.1061 Submission of technical information for application reference.

An application for station authorization in some services requires a detailed technical description of the equipment proposed to be used. In order to simplify the preparation and processing of applications by eliminating the need for the submission of equipment specifications with each application, the Commission will accept for application reference purposes detailed technical specifications of equipment designed for use in these services. Manufacturers desiring to avail themselves of this procedure should submit all information required by the application form and the rules for the services in which the equipment is to be used. An application for a station authorization submitted subsequent to such filing may refer to the technical information so filed.

§2.1063 Disclaimer re technical information filed for application reference.

Receipt by the Commission of data for application purposes does not imply that the Commission has made or intends to make any finding regarding the acceptability of the equipment for licensing and such equipment will not be included on the list of equipment acceptable for licensing. Each applicant is expected to exercise appropriate care in the selection of equipment to insure that the unit selected will comply with the rules governing the service in which it is proposed to operate.

§2.1065 Identification and changes in equipment information filed for application reference.

(a) Each type of equipment, for which information is filed for application reference purposes, shall be identified by a type number assigned by the manufacturer of the equipment. The type number shall consist of a series of Arabic numerals or capital letters or a combination thereof, and may include punctuation marks and spaces. The

§2.1071

total of Arabic numerals, capital letters, punctuation marks and spaces in any assigned type number shall not exceed 17. The type number shall be shown on an identification plate or label affixed in a conspicuous place to such equipment.

(b) If the assignment of a different type number is required as a result of equipment modification, a new identification plate or label bearing the new type number shall be affixed to the modified equipment.

NOTE: It is recommended that such equipment be identified with a nameplate pursuant to §2.925, except for deletion of the FCC Identifier, which will not be assigned to nor listed for such equipment.

(Secs. 4, 303, 48 Stat., as amended, 1066, 1082, sec. 302, 82 Stat., 290 (47 U.S.C. 154, 302, 303))

[39 FR 28160, Aug. 5, 1974, as amended at 44 FR 17180, Mar. 21, 1979]

DECLARATION OF CONFORMITY

§2.1071 Cross reference.

The general provisions of this subpart, shall apply to equipment subject to a Declaration of Conformity.

[61 FR 31046, June 19, 1996]

§2.1072 Limitation on Declaration of Conformity.

(a) The Declaration of Conformity signifies that the responsible party, as defined in §2.909, has determined that the equipment has been shown to comply with the applicable technical standards if no unauthorized change is made in the equipment and if the equipment is properly maintained and operated. Compliance with these standards shall not be construed to be a finding by the responsible party with respect to matters not encompassed by the Commission's rules.

(b) A Declaration of Conformity by the responsible party is effective until a termination date is otherwise established by the Commission.

(c) No person shall, in any advertising matter, brochure, etc., use or make reference to a Declaration of Conformity in a deceptive or misleading manner or convey the impression that such a Declaration of Conformity reflects more than a determination by the responsible party that the device or prod-

47 CFR Ch. I (10–1–97 Edition)

uct has been shown to be capable of complying with the applicable technical standards of the Commission's rules.

[61 FR 31046, June 19, 1996]

§2.1073 Responsibilities.

(a) The responsible party, as defined in §2.909, must warrant that each unit of equipment marketed under a Declaration of Conformity is identical to the unit tested and found acceptable with the standards and that the records maintained by the responsible party continue to reflect the equipment being produced under the Declaration of Conformity within the variation that can be expected due to quantity production and testing on a statistical basis.

(b) The responsible party, if different from the manufacturer, may upon receiving a written statement from the manufacturer that the equipment complies with the appropriate technical standards rely on the manufacturer or independent testing agency to determine compliance. However, the test records required by §2.1075 shall be in the English language and shall be made available to the Commission upon a reasonable request in accordance with the provisions of §2.1076.

(c) In the case of transfer of control of the equipment, as in the case of sale or merger of the responsible party, the new responsible party shall bear the responsibility of continued compliance of the equipment.

(d) Equipment shall be retested to demonstrate continued compliance with the applicable technical standards if any modifications or changes that could adversely affect the emanation characteristics of the equipment are made by the responsible party. The responsible party bears responsibility for the continued compliance of subsequently produced equipment.

(e) If any modifications or changes are made by anyone other than the responsible party for the Declaration of Conformity, the party making the modifications or changes, if located within the U.S., becomes the new responsible party. The new responsible party must comply with all provisions

Federal Communications Commission

§2.1075

for the Declaration of Conformity, including having test data on file demonstrating that the product continues to comply with all of the applicable technical standards.

[61 FR 31046, June 19, 1996]

§2.1074 Identification.

Devices subject only to a Declaration of Conformity shall be uniquely identified by the responsible party. This identification shall not be of a format which could be confused with the FCC Identifier required on certified, notified, type accepted or type approved equipment. The responsible party shall maintain adequate identification records to facilitate positive identification for each device.

[61 FR 31047, June 19, 1996]

§2.1075 Retention of records.

(a) Except as shown in paragraph (b) of this section, for each product subject to a Declaration of Conformity, the responsible party, as shown in §2.909, shall maintain the following records:

(1) A record of the original design drawings and specifications and all changes that have been made that may affect compliance with the requirements of §2.1073.

(2) A record of the procedures used for production inspection and testing (if tests were performed) to insure the conformance required by §2.1073. (Statistical production line emission testing is not required.)

(3) A record of the measurements made on an appropriate test site that demonstrates compliance with the applicable regulations. The record shall contain:

(i) The actual date or dates testing was performed;

(ii) The name of the test laboratory, company, or individual performing the testing. The Commission may request additional information regarding the test site, the test equipment or the qualifications of the company or individual performing the tests;

(iii) A description of how the device was actually tested, identifying the measurement procedure and test equipment that was used;

(iv) A description of the equipment under test (EUT) and support equip-

ment connected to, or installed within, the EUT;

(v) The identification of the EUT and support equipment by trade name and model number and, if appropriate, by FCC Identifier and serial number;

(vi) The types and lengths of connecting cables used and how they were arranged or moved during testing;

(vii) At least two photographs showing the test set-up for the highest line conducted emission and showing the test set-up for the highest radiated emission. These photographs must be focused originals which show enough detail to confirm other information contained in the test report;

(viii) A description of any modifications made to the EUT by the testing company or individual to achieve compliance with the regulations;

(ix) All of the data required to show compliance with the appropriate regulations;

(x) The signature of the individual responsible for testing the product along with the name and signature of an official of the responsible party, as designated in §2.909; and

(xi) A copy of the compliance information, as described in §2.1077, required to be provided with the equipment.

(b) If the equipment is assembled using modular components that, by themselves, are subject to authorization under a Declaration of Conformity and/or a grant of certification, and the assembled product is also subject to authorization under a Declaration of Conformity but, in accordance with the applicable regulations, does not require additional testing, the assembler shall maintain the following records in order to show the basis on which compliance with the standards was determined:

(1) A listing of all of the components used in the assembly;

(2) Copies of the compliance information, as described in §2.1077 for all of the modular components used in the assembly;

(3) A listing of the FCC Identifier numbers for all of the components used in the assembly that are authorized under a grant of certification;

(4) A listing of equipment modifications, if any, that were made during assembly; and

§2.1076

47 CFR Ch. I (10–1–97 Edition)

(5) A copy of any instructions included with the components that were required to be followed to ensure the assembly of a compliant product, along with a statement, signed by the assembler, that these instructions were followed during assembly. This statement shall also contain the name and signature of an official of the responsible party, as designated in §2.909.

(c) The records listed in paragraphs (a) and (b) of this section shall be retained for two years after the manufacture or assembly, as appropriate, of said equipment has been permanently discontinued, or until the conclusion of an investigation or a proceeding if the responsible party is officially notified that an investigation or any other administrative proceeding involving the equipment has been instituted. Requests for the records described in this section and for sample units also are covered under the provisions of §2.946.

[61 FR 31047, June 19, 1996]

§2.1076 FCC inspection and submission of equipment for testing.

(a) Each responsible party, upon receipt of a reasonable request, shall submit to the Commission the records required by §2.1075 or one or more sample units for measurements at the Commission's laboratory.

(b) Shipping costs to the Commission's Laboratory and return shall be borne by the responsible party. In the event the responsible party believes that shipment of the sample to the Commission's Laboratory is impractical because of the size or weight of the equipment, or the power requirement, or for any other reason, the responsible party may submit a written explanation why such shipment is impractical and should not be required.

[61 FR 31047, June 19, 1996]

§2.1077 Compliance information.

(a) If a product must be tested and authorized under a Declaration of Conformity, a compliance information statement shall be supplied with the product at the time of marketing or importation, containing the following information:

(1) Identification of the product, e.g., name and model number;

(2) A statement, similar to that contained in §15.19(a)(3) of this chapter, that the product complies with part 15 of this chapter; and

(3) The identification, by name, address and telephone number, of the responsible party, as defined in §2.909. The responsible party for a Declaration of Conformity must be located within the United States.

(b) If a product is assembled from modular components that, by themselves, are authorized under a Declaration of Conformity and/or a grant of certification, and the assembled product is also subject to authorization under a Declaration of Conformity but, in accordance with the applicable regulations, does not require additional testing, the product shall be supplied, at the time of marketing or importation, with a compliance information statement containing the following information:

(1) Identification of the assembled product, e.g., name and model number.

(2) Identification of the modular components used in the assembly. A modular component authorized under a Declaration of Conformity shall be identified as specified in paragraph (a)(1) of this section. A modular component authorized under a grant of certification shall be identified by name and model number (if applicable) along with the FCC Identifier number.

(3) A statement that the product complies with part 15 of this chapter.

(4) The identification, by name, address and telephone number, of the responsible party who assembled the product from modular components, as defined in §2.909. The responsible party for a Declaration of Conformity must be located within the United States.

(5) Copies of the compliance information statements for each modular component used in the system that is authorized under a Declaration of Conformity.

(c) The compliance information statement shall be included in the user's manual or as a separate sheet.

[61 FR 31048, June 19, 1996, as amended at 62 FR 41880, Aug. 4, 1997]

Federal Communications Commission

§2.1091

RADIOFREQUENCY RADIATION EXPOSURE

§2.1091 Radiofrequency radiation exposure evaluation: mobile devices.

(a) Requirements of this section are a consequence of Commission responsibilities under the National Environmental Policy Act to evaluate the environmental significance of its actions. See subpart I of part 1 of this chapter, in particular §1.1307(b).

(b) For purposes of this section, a mobile device is defined as a transmitting device designed to be used in other than fixed locations and to generally be used in such a way that a separation distance of at least 20 centimeters is normally maintained between the transmitter's radiating structure(s) and the body of the user or nearby persons. In this context, the term "fixed location" means that the device is physically secured at one location and is not able to be easily moved to another location. Transmitting devices designed to be used by consumers or workers that can be easily re-located, such as wireless devices associated with a personal computer, are considered to be mobile devices if they meet the 20 centimeter separation requirement.

(c) Mobile devices that operate in the Cellular Radiotelephone Service, the Personal Communications Services, the Satellite Communications Services, the General Wireless Communications Service, the Wireless Communications Service, the Maritime Services and the Specialized Mobile Radio Service authorized under subpart H of part 22 of this chapter, part 24 of this chapter, part 25 of this chapter, part 26 of this chapter, part 27 of this chapter, part 80 of this chapter (ship earth stations devices only) and part 90 of this chapter are subject to routine environmental evaluation for RF exposure prior to equipment authorization or use if they operate at frequencies of 1.5 GHz or below and their effective radiated power (ERP) is 1.5 watts or more, or if they operate at frequencies above 1.5 GHz and their ERP is 3 watts or more. Unlicensed personal communications service devices, unlicensed millimeter wave devices and unlicensed NII devices authorized under §15.253, §15.255, and subparts D and E of part 15

of this chapter are also subject to routine environmental evaluation for RF exposure prior to equipment authorization or use if their ERP is 3 watts or more or if they meet the definition of a portable device as specified in §2.1093 (b) requiring evaluation under the provisions of that section. All other mobile and unlicensed transmitting devices are categorically excluded from routine environmental evaluation for RF exposure prior to equipment authorization or use, except as specified in §§1.1307(c) and 1.1307(d) of this chapter. Applications for equipment authorization of mobile and unlicensed transmitting devices subject to routine environmental evaluation must contain a statement confirming compliance with the limits specified in paragraph (d) of this section as part of their application. Technical information showing the basis for this statement must be submitted to the Commission upon request.

(d) The limits to be used for evaluation are specified in §1.1310 of this chapter. All unlicensed personal communications service (PCS) devices and unlicensed NII devices shall be subject to the limits for general population/uncontrolled exposure.

(1) For purposes of analyzing mobile transmitting devices under the occupational/controlled criteria specified in §1.1310 of this chapter, time-averaging provisions of the guidelines may be used in conjunction with typical maximum duty factors to determine maximum likely exposure levels.

(2) Time-averaging provisions may not be used in determining typical exposure levels for devices intended for use by consumers in general population/uncontrolled environments as defined in §1.1310 of this chapter. However, "source-based" time-averaging based on an inherent property or duty-cycle of a device is allowed. An example of this is the determination of exposure from a device that uses digital technology such as a time-division multiple-access (TDMA) scheme for transmission of a signal. In general, maximum average power levels must be used to determine compliance.

(3) If appropriate, compliance with exposure guidelines for devices in this section can be accomplished by the use

§2.1093

of warning labels and by providing users with information concerning minimum separation distances from transmitting structures and proper installation of antennas.

(4) In some cases, e.g., modular or desktop transmitters, the potential conditions of use of a device may not allow easy classification of that device as either mobile or portable (also see §2.1093). In such cases, applicants are responsible for determining minimum distances for compliance for the intended use and installation of the device based on evaluation of either specific absorption rate (SAR), field strength or power density, whichever is most appropriate.

[61 FR 41017, Aug. 7, 1996, as amended at 62 FR 4655, Jan. 31, 1997; 62 FR 9658, Mar. 3, 1997; 62 FR 47966, Sept. 12, 1997]

EFFECTIVE DATE NOTE: At 62 FR 47966, Sept. 12, 1997, §2.1091 was amended by revising the heading, paragraphs (b), (c), and (d)(3), and adding paragraph (d)(4), effective Oct. 15, 1997. For the convenience of the user, the superseded text is set forth as follows:

§2.1091 Radiofrequency radiation exposure evaluation: mobile and unlicensed devices.

* * * * *

(b) For purposes of this section mobile devices are defined as transmitters designed to be used in other than fixed locations and to generally be used in such a way that a separation distance of at least 20 centimeters is normally maintained between radiating antennas and the body of the user or nearby persons.

(c) Mobile devices that operate in the Cellular Radiotelephone Service, the Personal Communications Services, the Satellite Communications Services, the Wireless Communications Service, the Maritime Services and the Specialized Mobile Radio Service authorized under subpart H of part 22 of this chapter, part 24 of this chapter, part 25 of this chapter, part 27 of this chapter, part 80 of this chapter (ship earth station devices only) and part 90 of this chapter ("covered" SMR devices only, as defined in the note to Table 1 of §1.1307(b)(1) of this chapter), are subject to routine environmental evaluation for RF exposure prior to equipment authorization or use if their effective radiated power (ERP) is 1.5 watts or more. Unlicensed personal communications service, unlicensed millimeter wave devices and unlicensed NII devices authorized under §15.253, §15.255 and subparts D and E of part 15 of this chapter are also subject to routine environmental

47 CFR Ch. I (10–1–97 Edition)

evaluation for RF exposure prior to equipment authorization or use, regardless of their power used, unless they meet the definition of a portable device as specified in §2.1093(b). All other mobile and unlicensed transmitting devices are categorically excluded from routine environmental evaluation for RF exposure prior to equipment authorization, except as specified in §§1.1307(c) and 1.1307(d) of this chapter. Applications for equipment authorization of mobile and unlicensed transmitting devices subject to routine environmental evaluation must contain a statement confirming compliance with the limits specified in paragraph (d) of this section as part of their application. Technical information showing the basis for this statement must be submitted to the Commission upon request.

* * * * *

(d) * * *

(3) Compliance with exposure guidelines for mobile and unlicensed devices can be accomplished by the use of warning labels and by providing users with information concerning minimum separation distances from transmitting structures and proper installation of antennas.

* * * * *

§2.1093 Radiofrequency radiation exposure evaluation: portable devices.

(a) Requirements of this section are a consequence of Commission responsibilities under the National Environmental Policy Act to evaluate the environmental significance of its actions. See subpart I of part 1 of this chapter, in particular §1.1307(b).

(b) For purposes of this section, a portable device is defined as a transmitting device designed to be used so that the radiating structure(s) of the device is/are within 20 centimeters of the body of the user.

(c) Portable devices that operate in the Cellular Radiotelephone Service, the Personal Communications Services, the Satellite Communications services, the General Wireless Communications Service, the Wireless Communications Service, the Maritime Services and the Specialized Mobile Radio Service authorized under subpart H of part 22 of this chapter, part 24 of this chapter, part 25 of this chapter, part 26 of this chapter, part 27 of this chapter, part 80 of this chapter (ship earth station devices only), part 90 of

this chapter, and portable unlicensed personal communication service, unlicensed NII devices and millimeter wave devices authorized under §15.253, §15.255 or subparts D and E of part 15 of this chapter are subject to routine environmental evaluation for RF exposure prior to equipment authorization or use. All other portable transmitting devices are categorically excluded from routine environmental evaluation for RF exposure prior to equipment authorization or use, except as specified in §§1.1307(c) and 1.1307(d) of this chapter. Applications for equipment authorization of portable transmitting devices subject to routine environmental evaluation must contain a statement confirming compliance with the limits specified in paragraph (d) of this section as part of their application. Technical information showing the basis for this statement must be submitted to the Commission upon request.

(d) The limits to be used for evaluation are based generally on criteria published by the American National Standards Institute (ANSI) for localized specific absorption rate (“SAR”) in Section 4.2 of “IEEE Standard for Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz,” ANSI/IEEE C95.1-1992, Copyright 1992 by the Institute of Electrical and Electronics Engineers, Inc., New York, New York 10017. These criteria for SAR evaluation are similar to those recommended by the National Council on Radiation Protection and Measurements (NCRP) in “Biological Effects and Exposure Criteria for Radio-frequency Electromagnetic Fields,” NCRP Report No. 86, Section 17.4.5. Copyright NCRP, 1986, Bethesda, Maryland 20814. SAR is a measure of the rate of energy absorption due to exposure to an RF transmitting source. SAR values have been related to threshold levels for potential biological hazards. The criteria to be used are specified in paragraphs (d)(1) and (d)(2) of this section and shall apply for portable devices transmitting in the frequency range from 100 kHz to 6 GHz. Portable devices that transmit at frequencies above 6 GHz are to be evaluated in terms of the MPE limits specified in §1.1310 of this chapter. Measure-

ments and calculations to demonstrate compliance with MPE field strength or power density limits for devices operating above 6 GHz should be made at a minimum distance of 5 cm from the radiating source.

(1) Limits for Occupational/Controlled exposure: 0.4 W/kg as averaged over the whole-body and spatial peak SAR not exceeding 8 W/kg as averaged over any 1 gram of tissue (defined as a tissue volume in the shape of a cube). Exceptions are the hands, wrists, feet and ankles where the spatial peak SAR shall not exceed 20 W/kg, as averaged over any 10 grams of tissue (defined as a tissue volume in the shape of a cube). Occupational/Controlled limits apply when persons are exposed as a consequence of their employment provided these persons are fully aware of and exercise control over their exposure. Awareness of exposure can be accomplished by use of warning labels or by specific training or education through appropriate means, such as an RF safety program in a work environment.

(2) Limits for General Population/Uncontrolled exposure: 0.08 W/kg as averaged over the whole-body and spatial peak SAR not exceeding 1.6 W/kg as averaged over any 1 gram of tissue (defined as a tissue volume in the shape of a cube). Exceptions are the hands, wrists, feet and ankles where the spatial peak SAR shall not exceed 4 W/kg, as averaged over any 10 grams of tissue (defined as a tissue volume in the shape of a cube). General Population/Uncontrolled limits apply when the general public may be exposed, or when persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or do not exercise control over their exposure. Warning labels placed on consumer devices such as cellular telephones will not be sufficient reason to allow these devices to be evaluated subject to limits for occupational/controlled exposure in paragraph (d)(1) of this section.

(3) Compliance with SAR limits can be demonstrated by either laboratory measurement techniques or by computational modeling. Methodologies and references for SAR evaluation are described in numerous technical publications including “IEEE Recommended

§2.1201

Practice for the Measurement of Potentially Hazardous Electromagnetic Fields—RF and Microwave,” IEEE C95.3–1991.

(4) For purposes of analyzing portable transmitting devices under the occupational/controlled criteria, the time-averaging provisions of the MPE guidelines identified in §1.1310 of this chapter can be used in conjunction with typical maximum duty factors to determine maximum likely exposure levels.

(5) Time-averaging provisions of the MPE guidelines identified in §1.1310 of this chapter may not be used in determining typical exposure levels for portable devices intended for use by consumers, such as hand-held cellular telephones, that are considered to operate in general population/uncontrolled environments as defined above. However, “source-based” time-averaging based on an inherent property or duty-cycle of a device is allowed. An example of this would be the determination of exposure from a device that uses digital technology such as a time-division multiple-access (TDMA) scheme for transmission of a signal. In general, maximum average power levels must be used to determine compliance.

[61 FR 41017, Aug. 7, 1996, as amended at 62 FR 4655, Jan. 31, 1997; 62 FR 9658, Mar. 3, 1997; 62 FR 47967, Sept. 12, 1997]

EFFECTIVE DATE NOTE: At 62 FR 47967, Sept. 12, 1997, §2.1093 was amended by revising paragraphs (b), (c), and (d) introductory text, effective Oct. 15, 1997. For the convenience of the user, the superseded text is set forth as follows:

§2.1093 Radiofrequency radiation exposure evaluation: portable devices.

* * * * *

(b) For purposes of this section portable devices are defined as transmitters designed to be used within 20 centimeters of the body of the user.

(c) Portable devices that operate in the Cellular Radiotelephone Service, the Personal Communications Services, the Satellite Communications Services, the Wireless Communications Service, the Maritime Services and the Specialized Mobile Radio Service authorized under subpart H of part 22 of this chapter, part 24 of this chapter, part 25 of this chapter, part 27 of this chapter, part 80 of this chapter (ship earth station devices only), part 90 of this chapter (“cov-

47 CFR Ch. I (10–1–97 Edition)

ered” SMR devices only, as defined in the note to Table 1 of section 1.1307(b)(1) of this chapter), and portable unlicensed personal communication service and millimeter wave devices authorized under §15.253, §15.255 or subpart D of part 15 of this chapter are subject to routine environmental evaluation for RF exposure prior to equipment authorization or use. All other portable transmitting devices are categorically excluded from routine environmental evaluation for RF exposure prior to equipment authorization, except as specified in §§1.1307(c) and 1.1307(d) of this chapter. Applications for equipment authorization of portable transmitting devices subject to routine environmental evaluation must contain a statement confirming compliance with the limits specified in paragraph (d) of this section as part of their application. Technical information showing the basis for this statement must be submitted to the Commission upon request.

(d) The limits to be used for evaluation are based generally on criteria published by the American National Standards Institute (ANSI) for localized specific absorption rate (“SAR”) in Section 4.2 of “IEEE Standard for Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz,” ANSI/IEEE C95.1–1992, Copyright 1992 by the Institute of Electrical and Electronics Engineers, Inc., New York, New York 10017. These criteria for SAR evaluation are similar to those recommended by the National Council on Radiation Protection and Measurements (NCRP) in “Biological Effects and Exposure Criteria for Radiofrequency Electromagnetic Fields,” NCRP Report No. 86, Section 17.4.5. Copyright NCRP, 1986, Bethesda, Maryland 20814. SAR is a measure of the rate of energy absorption due to exposure to an RF transmitting source. SAR values have been related to threshold levels for potential biological hazards. The criteria to be used are specified in paragraphs (d)(1) and (d)(2) of this section.

* * * * *

Subpart K—Importation of Devices Capable of Causing Harmful Interference

§2.1201 Purpose.

(a) In order to carry out its responsibilities under the Communications Act and the various treaties and international regulations, and in order to promote efficient use of the radio spectrum, the Commission has developed technical standards for radio frequency

Federal Communications Commission

§2.1204 Import conditions.

equipment. The technical standards applicable to individual types of equipment are found in that part of the rules governing the service wherein the equipment is to be operated. In addition to the technical standards, the rules governing the service may require that such equipment receive an equipment authorization from the Commission as a prerequisite for marketing and importing this equipment into the U.S.A. The marketing rules, §2.801 *et seq.*, were adopted pursuant to the authority in section 302 of the Communications Act of 1934, as amended (47 U.S.C. 302).

(b) The rules in this section set out the conditions under which radio frequency devices as defined in §2.801 that are capable of causing harmful interference to radio communications may be imported into the U.S.A.

(c) Nothing in this section prevents importers from shipping goods into foreign trade zones or Customs bonded warehouses, such as is the prescribed procedure under §2.1204(a)(5). Radio frequency devices capable of causing harmful interference, however, cannot be withdrawn from these areas except in accordance with the provisions of this section.

[41 FR 25904, June 23, 1976, as amended at 54 FR 17714, Apr. 25, 1989; 56 FR 26619, June 10, 1991; 57 FR 38286, Aug. 24, 1992]

§2.1202 Exclusions.

The provisions of this section do not apply to the importation of:

(a) Cameras, musical greeting cards, quartz watches and clocks, modules of quartz watches and clocks, hand-held calculators and electronic games, and other similar unintentional radiators which utilize low level battery power and which do not contain provisions for operation while connected to AC power lines.

(b) Unintentional radiators which are exempted from technical standards and other requirements as specified in §15.103 of this chapter.

(c) Radio frequency devices manufactured and assembled in the U.S.A. that meet applicable FCC technical standards and which have not been modified or received further assembly.

(d) Radio frequency devices previously properly imported that have

been exported for repair and re-imported for use.

(e) Subassemblies, parts, or components of radio frequency devices unless they constitute an essentially completed device which requires only the addition of cabinets, knobs, speakers, or similar minor attachments before marketing or use. Form 740 information will be required to be submitted for computer circuit boards that are actually peripheral devices as defined in §15.3(r) of this chapter and all devices that, by themselves, are subject to FCC marketing rules.

[56 FR 26619, June 10, 1991]

§2.1203 General requirement for entry into the U.S.A.

(a) No radio frequency device may be imported into the Customs territory of the United States unless the importer or ultimate consignee, or their designated customs broker, declares that the device meets one of the conditions for entry set out in this section.

(b) A separate declaration shall be used for each line item in the entry or entry summary containing an RF device, or for each different radio frequency device within a line item when the elements of the declaration are not identical.

(c) Failure to properly declare the importation category for an entry of radio frequency devices may result in refused entry, refused withdrawal for consumption, required redelivery to the Customs port, and other administrative, civil and criminal remedies provided by law.

(d) Whoever makes a declaration pursuant to §2.1203(a) must provide, upon request made within one year of the date of entry, documentation on how an imported radio frequency device was determined to be in compliance with Commission requirements.

[56 FR 26619, June 10, 1991; 56 FR 32474, July 16, 1991]

§2.1204 Import conditions.

(a) Radio frequency devices may be imported only if one or more of these conditions are met:

(1) The radio frequency device has been issued an equipment authorization by the FCC.

§ 2.1205

(2) The radio frequency device is not required to have an equipment authorization and the device complies with FCC technical administrative regulations.

(3) The radio frequency device is being imported in limited quantities for testing and evaluation to determine compliance with the FCC Rules and Regulations or suitability for marketing. The device will not be offered for sale or marketed. The phrase *limited quantities* in this context, means 200 or fewer units. Prior to importation of more than 200 units, written approval must be obtained from the Chief, Enforcement Division, Field Operations Bureau, FCC. Distinctly different models of a product and separate generations of a particular model under development are considered to be separate devices.

(4) The radio frequency device is being imported in limited quantities for demonstration at industry trade shows and the device will not be offered for sale or marketed. The phrase *limited quantities*, in this context, means ten or fewer units. Prior to importation of more than ten units, written approval must be obtained from the Chief, Compliance Division, Compliance and Information Bureau, FCC. Distinctly different models of a product and separate generations of a particular model under development are considered to be separate devices.

(5) The radio frequency device is being imported solely for export. The device will not be marketed or offered for sale for use in the U.S.

(6) The radio frequency device is being imported for use exclusively by the U.S. Government.

(7) Three or fewer radio receivers, computers, or other unintentional radiators as defined in part 15 of this chapter, are being imported for the individual's personal use and are not intended for sale.

(8) The radio frequency device is being imported for repair and will not be offered for sale or marketed.

(b) The ultimate consignee must be able to document compliance with the selected import condition and the basis

47 CFR Ch. I (10–1–97 Edition)

for determining the import condition applied.

[56 FR 26619, June 10, 1991, as amended at 57 FR 38286, Aug. 24, 1992; 61 FR 8477, Mar. 5, 1996]

§ 2.1205 Filing of required declaration.

NOTE: The U.S. Customs Service is implementing a paperless entry system. Until the Customs electronic system is operational, submit the required declaration following the guidelines in paragraph (a) of this section. When the Customs system is implemented, follow the guidelines in paragraph (b) of this section.

(a) For points of entry where electronic filing with Customs has not been implemented, use FCC Form 740 to provide the needed information and declarations.

(1) Mail the original of FCC Form 740 to: FCC, Washington, DC 20554, Attention: Imports, on or before the date the Customs entry papers are filed.

(2) Attach a copy of FCC Form 740 to the Customs entry papers.

(b)(1) For points of entry where electronic filing with Customs is available, submit the following information to Customs when filing the entry documentation and the entry summary documentation electronically. Follow procedures established by Customs for electronic filing.

(i) The terms under which the device is being imported, as indicated by citing the import condition number specified in § 2.1204(a).

(ii) The FCC identifier as specified in § 2.925, if the device has been granted an equipment authorization;

(iii) The quantity of devices being imported, regardless of what unit is specified in the Harmonized Tariff Schedule of the United States; and

(iv) A commercial product description which is to include the trade name, a model/type number (or model/type name) and other descriptive information about the device being imported.

(2) For importers unable to participate in the electronic filing process with Customs for good cause, declarations are to be made in accordance with paragraph (a) of this section.

[56 FR 26619, June 10, 1991]

Federal Communications Commission

§2.1400

§2.1207 Examination of imported equipment.

In order to determine compliance with its regulations, Commission representatives may examine or test any radio frequency device that is imported. If such radio frequency device has already entered the U.S., the ultimate consignee or subsequent owners of that device must, upon request, made within one year of the date of entry, make that device available for examination or testing by the Commission.

[56 FR 26620, June 10, 1991]

Subpart L—Registration of Telephone Terminal Equipment

REGISTRATION PROCEDURE

§2.1300 Cross reference.

The general provisions of this part, §§2.911, 2.923, 2.929, 2.935, 2.936, and 2.946 shall apply to applications for and grants of registration for telephone terminal equipment pursuant to part 68 of this chapter.

[62 FR 10473, Mar. 7, 1997]

§2.1302 Application for registration under part 68.

An original application for registration and one copy shall be filed on FCC Form 730 by the party who will be responsible for the conformance of the equipment with the standards specified in part 68 of this chapter and shall include the information specified by the form and in §68.200 of this chapter.

(Secs. 201–205, 208, 215, 218, 313, 314, 403, 410, 602, 48 Stat., as amended 1070–1072, 1073, 1076, 1077, 1087, 1094, 1099, 1102; 47 U.S.C. 201–205, 208, 215, 218, 313, 314, 403, 410, 602)

[41 FR 8048, Feb. 24, 1976, as amended at 61 FR 42386, Aug. 15, 1996]

Subpart M—Advance Approval of Subscription TV Transmission Systems

ADVANCE APPROVAL PROCEDURE

§2.1400 Application for advance approval under part 73.

(a) An original application for advance approval of a subscription TV

(STV) system and one copy thereof must be filed by the party who will be responsible for the conformance of the system with the subscription TV standards specified in part 73 of the Rules. The application must include information to show that the system conforms to the requirements of §73.644(b).

(b) Advance approval may be applied for and granted in accordance with and subject to the following conditions and limitations:

(1) A separate request for each different technical system must be made by the applicant in writing.

(2) The applicant must certify that the application was prepared by or under the direction of the applicant and that the facts set forth are true and correct to the best of the applicant's knowledge and belief.

(3) The applicant must identify the technical system by a name or type number and define the system in terms of its technical characteristics; a functional block diagram must be included. In addition, a complete description of the encoded aural and visual baseband and transmitted signals and of the encoding equipment used by the applicant must be supplied. These descriptions must include equipment circuit diagrams and photographs, and diagrams or oscillographs of both baseband and transmitted aural and visual signal waveforms and of the signal basebands and occupied bandwidths. If aural subcarriers are to be used for transmitting aural portion of the subscription program, for decoder control, or for other purposes, a full description and specifications of the multiplex subcarrier signals and all modulation levels must be included.

(4) Preliminary test data must be submitted to show system capability with regard to compliance with the criteria set forth in §73.644(b).

(5) The applicant must identify the specific requirements of §§73.682, 73.687 and 73.699 (Figures 6 and 7) from which the transmitted signal will normally deviate.

(6) The applicant must specify the method to be used in determining and maintaining the operating power of the transmitter if the procedures given in §73.663 cannot be used due to suppression of the synchronizing pulses or for

§2.1501

other reasons. If the operating power of the station must be reduced to accommodate the encoded aural or video signal, the operating power limitations must be specified.

(7) The applicant must supply any additional information and test data requested by the FCC, to show to its satisfaction that the criteria given in §73.644(b) are met.

(8) The information submitted by the applicant may be subject to check by field tests conducted without expense to the FCC or, if deemed necessary, at the laboratory or in the field by FCC personnel. This may include the actual submission of equipment for system testing under the provisions of §2.945 of part 2 of the Rules.

(9) No technical system will be deemed approved unless and until the FCC has notified the applicant in writing of the approval. Such notification of approval will be by letter to the applicant.

(10) Approval by the FCC is limited to a determination that the particular technical system (the scheme for encoding and decoding the subscription TV signal) is capable of meeting the criteria given in §73.644(b).

(11) The FCC will maintain a listing of approved technical systems.

(c) Multichannel sound may be transmitted for stereophonic or bilingual service with encoded subscription programs provided the technical operating specifications for this service are included in the application for advance system approval.

(d) Subscriber decoder devices must comply with any applicable provisions of subpart H, part 15 of the FCC Rules for TV interface devices.

(e) No modifications may be made by either the applicant or the user of a system having advance FCC approval that would change any of the operating conditions as submitted in the application for advance approval. Should system modifications be necessary, a new application must be submitted in accordance with the requirements of this section.

[48 FR 56391, Dec. 21, 1983]

47 CFR Ch. I (10–1–97 Edition)

Subpart N—FCC Procedure for Testing Class A, B and S Emergency Position Indicating Radiobeacons (EPIRBs)

SOURCE: 56 FR 11683, Mar. 20, 1991, unless otherwise noted.

GENERAL

§2.1501 Introduction.

The procedure described herein sets forth uniform methods for testing Class A, B and S Emergency Position Indicating Radiobeacons (EPIRBs) for compliance with the applicable portions of the FCC Rules and Regulations. Other methods and test results may be used provided they are fully documented and deemed by the Commission to yield results equivalent to the procedures set forth in this section.

§2.1503 Test environment.

(a) *Measurement sites.* Radiated emission tests for peak effective radiated power (PERP), spurious emissions and power in the test mode are to be performed on an open field test site as shown in Figure 1. The site is to be located on level ground with an obstruction-free, 60 m by 52 m, elliptical area. The site is to be equipped with an antenna mast capable of adjustment from 1 to 4 m. The center of a metal ground plane at least one wavelength in diameter at 121.5 MHz (2.47 m) is to be located 30 m from the receiving antenna. The ground plane is to have provisions for mounting removable quarter-wave verticle elements to produce a monopole antenna at both 121.5 and 243 MHz with the VSWR of less than 1.5.

NOTE: It is desirable that the level of radiated ambient EME at the test site be at least 6 dB below the FCC limits applicable to the EPIRB. It is, of course, not always possible to meet this condition. If the ambient field strength at some frequencies within the specified measurement ranges is too high, it is recommended that one or more of the following corrective steps be employed:

(1) Perform measurements in critical frequency bands during hours when broadcast and other radio stations are off-the-air and ambients from industrial equipment are lower.

(2) Insofar as is possible, orient the axis of an open area test site to discriminate against strong ambient signals.

Federal Communications Commission

§2.1509

(3) Vary the bandwidth of the measuring instrument to separate ambient EME from emissions from the EPIRB.

(b) *Temperature.* Except as otherwise noted, the ambient temperature during testing is to be within the range of 4 to 35 °C (40 to 95 °F).

§2.1505 Test instrumentation and equipment.

(a) *Receiver (field intensity meter).* A calibrated field intensity meter (FIM) with a frequency range of 30 to 1000 MHz is required for measuring radiated emission levels. This instrument should be capable of making peak measurements with a bandwidth of 100 kHz.

(b) *Spectrum analyzer.* Spectral measurements are to be made with a spectrum analyzer with a minimum resolution bandwidth no greater than 10 Hz. The video filter, if used, should have a bandwidth wide enough so as to not affect peak readings. A linear video output is desirable for performing measurements of modulation characteristics.

(c) *Storage oscilloscope.* Measurements of modulation characteristics are to be made using a calibrated storage oscilloscope. This instrument is to be DC coupled and capable of manually triggered single sweeps.

(d) *Frequency counter.* A frequency counter with an accuracy of at least 5 parts per million is required for measuring the carrier frequency.

(e) *Signal generator.* A calibrated signal generator with an output of at least 75 mW at 121.5 and 243 MHz is required for generating a reference signal for site calibration.

(f) *Antenna.* Radiated emissions are to be measured with calibrated, tuned, half-wave dipole antennas covering the frequency range of 30 to 1000 MHz.

(g) *Temperature chamber.* Tests which call for subjecting the EPIRB to temperature levels other than the ambient temperature are to be performed in a temperature test chamber which can be adjusted to stable temperatures from -20 to +55 °C. This chamber is to be of sufficient size to accommodate the EPIRB under test.

(h) *Vibration table.* A vibration table capable of vibrating the EPIRB with a sinusoidal motion is required. The

table must be capable of varying the frequency of vibration either linearly or logarithmically over a range of 4 to 33 Hz with maximum peak amplitudes of up to 2.5 mm.

(i) *Salt fog chamber.* A chamber capable of producing salt fog at a temperature of 35 °C for 48 hours is required. This chamber is to be of sufficient size to accommodate the EPIRB under test.

(j) *Drop test facility.* A facility which will permit dropping an EPIRB from a height of 20 m into water is required. The water must be deep enough so that the EPIRB will not touch bottom when dropped.

ENVIRONMENTAL AND OPERATIONAL TEST PROCEDURES

§2.1507 Test frequencies.

Testing of an EPIRB for compliance outside a shielded room on a distress frequency is prohibited, since this may interfere with emergency communications. Therefore, all compliance testing outside a shielded room should be conducted on one of the pairs of alternate frequencies specified below:

121.600/243.200 MHz
121.650/243.300 MHz
121.700/243.400 MHz
121.750/243.500 MHz
121.800/243.600 MHz
121.850/243.700 MHz
121.900/243.800 MHz

The above frequencies are to be used for limited testing of EPIRBs for compliance with FCC Rules, subject to the following conditions:

(a) The testing shall not cause harmful interference to authorized communications on these frequencies.

(b) The testing shall be coordinated with the nearest FCC district office.

For simplicity, 121.5 MHz and 243 MHz will be used throughout this test procedure to indicate the alternate test frequency.

§2.1509 Environmental and duration tests.

The environmental and operational tests in §2.1509 (a) through (e) are to be conducted on a single test unit in the order given below. This sequence of tests also includes the electrical tests in §§2.1511, 2.1513 and 2.1515 of this part. The test unit is not to be adjusted, nor

§2.1509

is the battery to be replaced during these tests, and a log of battery on-time should be maintained. The above tests are to be performed on the same test unit. The tests in §2.1509 (f) through (i) may be run in any sequence or may be performed on separate test units.

(a) *Vibration test.*

Step (1) Secure the EPIRB to the vibration table. The EPIRB is not to be operated and should not activate while being vibrated.

Step (2) Subject the EPIRB to sinusoidal motion parallel to one of the three major orthogonal axes under the following conditions:

A. Frequency (Hz)	Peak amplitude (mm)
4–10	2.5
10–15	0.8
15–25	0.4
25–33	0.2

B. The frequency is to be changed either linearly or logarithmically with time between 4 Hz and 33 Hz such that a complete cycle (4 Hz to 33 Hz to 4 Hz) takes approximately 5 minutes.

C. The EPIRB is to be vibrated for at least 30 minutes or six complete cycles.

Step (3) Remount the EPIRB, if necessary, and repeat step 2 for each of the other two major orthogonal axes.

Step (4) Upon completion of the test, perform an exterior mechanical inspection and verify operation by turning the unit on and observing the RF power indicator on the unit or monitoring the transmission with a receiver. Record test results.

(b) *Thermal shock tests.* These tests are to be performed on EPIRBs which are required or intended to float.

(1) *Low temperature thermal shock test.*

Step (1) Place the EPIRB in a temperature chamber for at least 3 hours at -20°C or colder. The EPIRB is not to be operated while being cooled.

Step (2) Immediately place the EPIRB in water that has been maintained at $+10^{\circ}\text{C}$ or warmer.

Step (3) After 15 minutes, perform an exterior mechanical inspection and verify operation by turning the unit on and observing the RF power indicator on the unit or monitoring the transmission with a receiver. Record test results.

(2) *High temperature thermal shock test.*

Step (1) Place the EPIRB in a temperature chamber for at least 3 hours at $+55^{\circ}\text{C}$ or warmer. The EPIRB is not to be operated while being heated.

47 CFR Ch. I (10–1–97 Edition)

Step (2) Immediately float the EPIRB in water that is maintained at $+25^{\circ}\text{C}$ or colder.

Step (3) After 15 minutes, perform an exterior mechanical inspection and verify operation by turning the unit on and observing the RF power indicator on the unit or monitoring the transmission with a receiver. Record test results.

(c) *Salt fog test.*

Step (1) Place the EPIRB in a salt fog chamber for a period of at least 2 hours at a temperature of 35°C ($\pm 2^{\circ}\text{C}$) before exposing it to salt fog. The EPIRB is to be turned off during this test.

Step (2) With the chamber temperature maintained at 35°C , introduce salt fog at the saturation point for 48 hours. The salt fog is to be prepared from a 5% ($\pm 1\%$) salt (sodium chloride solution. For detailed guidance on the preparation of the solution and the apparatus for generating salt fog, refer to MIL-STD-810D (19 July 1983), method 509.2.

Step (3) Upon completion of the salt fog exposure, the EPIRB is to be airdried at room temperature for 12 hours and operation verified by turning the unit on and observing the RF power indicator on the unit or monitoring the transmission with a receiver. Record observations.

(d) *Drop test.* This test is to be performed on EPIRB which are required or intended to float.

Step (1) Turn the EPIRB on, log the time and drop it three times into water from a height of 20 meters. The water is to be deep enough so that the EPIRB does not touch bottom when dropped. Each drop should be initiated from a different orientation as follows: antenna vertical up; antenna vertical down; antenna horizontal.

Step (2) Upon completion of the drop test, an exterior mechanical inspection is to be performed and operation verified by observing the RF power indicator on the unit or monitoring the transmission with a receiver. Record observations. Turn the test unit off and log the total on-time.

(e) *Forty-eight hour operational test.* This test includes the battery life test and all the electrical tests given in §§2.1511, 2.1513 and 2.1515 of this part, at various temperatures. The tests are to be performed on the same EPIRB in the sequence specified herein. Be sure to record the on-time of the unit during each test. No more than 8 hours of total on-time is permitted before commencing step 4. When operating the EPIRB in the environmental chamber, a non-radiating load may be substituted for the antenna provided it is

Federal Communications Commission

§2.1511

electrically equivalent to the standard antenna and does not reduce the battery current drain.

Step (1) Perform the radiated emissions test in §2.1511 of this part.

Step (2) Perform the modulation characteristic tests in §2.1513 of this part.

Step (3) Perform the spectral tests in §2.1515 of this part.

Step (4) With the EPIRB off, place unit in an environmental chamber at a temperature of -20°C for at least 2 hours.

Step (5) With the EPIRB in the chamber, repeat the carrier frequency test in §2.1515(d) of this part. (Leave the EPIRB turned on.)

Step (6) Near the end of 48 hours of total on-time for the EPIRB, repeat the carrier frequency test in §2.1515(d) of this part.

Step (7) At the end of 48 hours of total on-time, remove EPIRB from the chamber and immediately repeat the PERP test for the fundamental emissions in §2.1511(c) of this part. The unit should be maintained at -20°C to the extent possible for this test.

(f) *Float free and activation test.* This test is required only for Class A EPIRBs.

Step (1) The EPIRB is to be installed in the automatic release mechanism and the assembly is to be mounted on a fixture simulating a deck or bulkhead as per manufacturer's installation instructions.

Step (2) Submerge the fixture in water in its normal mounted orientation. The EPIRB must float free before reaching a depth of 4 meters and should automatically activate. Activation is to be verified by observing the RF power indicator on the unit or monitoring the transmission with a receiver.

If the EPIRB is equipped with an automatically deployable antenna, the antenna must properly deploy during each immersion. Record observations.

(g) *Stability and buoyancy test.* This test is to be performed on EPIRBs which are required or intended to float. This test is to be conducted in fresh water.

Step (1) With the antenna deployed in its normal operating position, submerge the EPIRB in a horizontal position just below the surface of the water.

Step (2) Release the EPIRB and observe the amount of time required for it to come to an upright position. It must reach its upright position within one second from each position.

The EPIRB must have a reserve buoyancy of at least 5% of its gross weight. It must also float upright in calm water with the base of the antenna a

minimum of 5 cm above the water. Record the time required for the test unit to right itself.

(h) *Temperature/frequency test.* The frequency stability shall be measured over an ambient temperature from -20° to $+55^{\circ}\text{C}$ at intervals of not more than 10°C . A period of time sufficient to stabilize all of the components of the oscillator circuit at each temperature level shall be allowed prior to frequency measurement.

Step (1) Place the EPIRB in the environmental test chamber.

Step (2) Adjust the temperature in the chamber to $+20^{\circ}\text{C}$ and allow sufficient time for the oscillator to stabilize at that temperature.

Step (3) Measure the carrier frequency in accordance with the procedure in §2.1515(d) of this part. Record the carrier frequency in Hertz. The carrier frequency at $+20^{\circ}\text{C}$ is the reference for determining the frequency tolerance.

Step (4) Increase the temperature in the chamber to $+55^{\circ}\text{C}$ and allow sufficient time for the oscillator to stabilize at that temperature. Measure the carrier frequency using the procedure in §2.1515(d) of this part.

Step (5) Reduce the temperature in the chamber in 10°C maximum increments until -20°C is reached. At each new temperature, allow sufficient time for the oscillator to stabilize at that temperature. Measure the temperature and frequency in each case and plot the frequency vs temperature from -20° to $+55^{\circ}\text{C}$.

(i) *Leakage and immersion test.*

Step (1) Completely submerge the EPIRB in water for 48 hours. The EPIRB is to be turned off during this test.

Step (2) Remove the EPIRB from the water and wipe dry.

Step (3) Verify operation by briefly turning the EPIRB on and observing the RF power indicator on the unit or monitoring the transmission with a receiver.

Step (4) Open the EPIRB for examination. There is to be no water inside the unit. Record observations.

§2.1511 Measurements of radiated emissions.

The Commission's Rules require that the peak effective radiated power (PERP) of a Class A, B or S EPIRB not be less than 75 mW under certain specified conditions. The PERP of an EPIRB transmitter is determined by comparing its level to a reference PERP generated by a standard quarter-wave monopole antenna located on a one

§2.1511

47 CFR Ch. I (10–1–97 Edition)

wavelength minimum diameter metal ground plane. The Rules also require that all spurious and harmonic emissions be attenuated by a specified amount with respect to the reference PERP. In addition, there is a limit on the PERP of radiated emissions with the switch in the test mode. These measurements are to be made in accordance with the following procedure.

(a) *General set-up instructions.*

Measurements of radiated electromagnetic emissions (EME) are to be performed on the 30 meter open field test site described in §2.1503(a) of this part and on one of the pair of frequencies listed in §2.1507 of this part. A receiver, tuned dipole antennas and a calibrated signal generator as described in §2.1505 of this part are required. The EPIRB should be powered by its own internal battery with its standard antenna attached and deployed.

(b) *Set-up for radiated EME tests.*

Step (1) Place a 121.5 MHz quarter-wave vertical antenna element at the center of the ground plane and connect the output of the calibrated signal generator to the antenna.

Step (2) Mount the tuned dipole antenna on the antenna mast, tune the elements to 121.5 MHz and connect the antenna to the receiver.

Step (3) After an appropriate warm up, turn the receiver to the frequency of the test unit, set the detector to peak mode and the bandwidth to 100 kHz.

(NOTE: It is sometimes helpful to monitor the receiver audio output with a speaker. The EPIRB signal may be identified by its distinctive modulation.)

(c) *Radiated EME tests.*

Fundamental emissions-peak effective radiated power

Step (1) Turn on the signal generator and adjust the output to 75 mW at 121.5 MHz.

Step (2) Vary the antenna height from one to four meters in both vertical and horizontal polarization. Record the highest receiver reading in dBm as the reference level.

Step (3) Disconnect the signal generator and replace the quarter-wave vertical element on the ground plane with the EPIRB under test. The EPIRB is to be positioned directly on the surface of and in the center of the metal ground plane.

Step (4) Activate the EPIRB.

Step (5) Vary the receive antenna height from one to four meters in both vertical and horizontal polarization. Record the highest receiver reading in dBm and the instrument

settings, antenna height and direction for maximum radiation, antenna polarization and conversion factors, if any, associated with that reading.

Step (6) Repeat Step 5 with the EPIRB switch in the test position. Return the switch to the normal operation position.

Step (7) Rotate the EPIRB 30 degrees and repeat Steps 5 and 6. Repeat this step for all successive 30 degrees segments of a full, 360 degree rotation of the EPIRB.

Step (8) Repeat §2.1511(b) and Steps 1 through 7 for 243 MHz.

Step (9) Compute the peak effective radiated power for the maximum level of each measured emission using the following formula:

$$\text{PERP} = 75 \times \log_{10}^{-1} \left[\frac{\text{dBm}_{\text{meas}} - \text{dBm}_{\text{ref}}}{10} \right]$$

where:

dBm_{meas} is the measured receiver reading in dBm, and

dBm_{ref} is the reference receiver reading found in step 2 of §2.1511(c).

Step (10) Record the PERP in mW. The FCC limit for minimum power in the normal operation mode (i.e., with the EPIRB switch in the normal operating position) is 75 mW. The FCC limit for maximum power in the test mode is 0.0001 mW.

Spurious emissions

Step (11) Reset the signal generator to operate at 121.5 MHz.

Step (12) For each spurious and harmonic emission to be measured, retune the receive antenna to the appropriate frequency and repeat Steps 5 and 7.

Step (13) Determine the FCC limit on power for spurious emissions on the frequency of each measured emission as follows:

The rules require that spurious emissions be attenuated at least 30 decibels below the transmit power level. Therefore, the maximum received power limit for a spurious emission can be calculated from the formula:

$$\text{dBm}_{\text{spur}} = \text{dBm}_{\text{meas}} + \text{AF}_{121.5} - \text{AF}_{\text{spurfreq}} - 30$$

where:

dBm_{meas} = measured receiver reading (Section 2.1511(c), step 5).

AF_{121.5} = tuned dipole antenna factor at 121.5 MHz.

AF_{spurfreq} = tuned dipole antenna factor at spurious freq.

Step (14) Record in dB below the fundamental emissions the level of all spurious and harmonic emissions within 10 dB of the FCC limits.

Federal Communications Commission

§2.1515

§2.1513 Measurements of modulation characteristics.

(a) *Set-up.* Test of modulation characteristics are to be performed in an RF shielded room.

Step (1) Place the EPIRB directly on a metal ground plane, such as the shielded room floor.

Step (2) Place a suitable receiving antenna at a convenient distance from the EPIRB and connect it to the input of the spectrum analyzer or receiver to observe the radiated signal from the EPIRB.

Step (3) Set the spectrum analyzer or receiver controls as follows:

I.F. bandwidth: 300 kHz minimum
Video filter: OFF or as wide as possible
Amplitude scale: Linear
Frequency: 121.5 MHz
Scan width: 0 Hz

Step (4) Connect the detected output of the spectrum analyzer or receiver to the input of the storage oscilloscope.

Step (5) Set the oscilloscope controls as necessary to allow the demodulated waveform to be viewed. The input signal is to be DC coupled.

(b) *Measurement of Audio Frequencies.*

Step (1) Activate the EPIRB.

Step (2) Trigger the oscilloscope and store at least one complete cycle of the audio waveform.

Step (3) Measure the period (T) of the waveform. The period is the time difference between the half voltage points at the beginning and end of one complete cycle of the waveform. See Figure 2.

Step (4) Calculate the frequency (F), where:

$$F=1/T.$$

Step (5) Repeat Steps 2 through 4 until the highest and lowest audio frequencies are found.

NOTE: The lowest and highest frequencies may occur several cycles before or after the transition from low to high frequency.)

Step (6) Determine the audio frequency range (F_{range}), where:

$$F_{\text{range}}=F_{\text{high}}-F_{\text{low}}$$

Step (7) Record instrument settings and the lowest and highest audio frequencies. Record the audio frequency range in Hertz.

Step (8) Repeat Steps 1-7, above, for 243 MHz.

(c) *Modulation factor.*

Step (1) Activate the EPIRB.

Step (2) Trigger the oscilloscope and store at least one complete cycle of the audio waveform. The input signal is to be DC coupled or erroneous results will be obtained.

Step (3) Measure the maximum voltage (V_{max}), and the minimum voltage (V_{min}) for the cycle. The modulation factor (M) is calculated from the following formula:

$$M = \frac{V_{\text{max}} - V_{\text{min}}}{V_{\text{max}} + V_{\text{min}}}$$

See Figure 2.

Step (4) Repeat Steps 2 and 3 until the lowest modulation factor is found.

Step (5) Record instrument settings and the lowest modulation factor, expressed as a ratio between 0 and 1.

Step (6) Repeat the above measurements for 243 MHz.

(d) *Modulation duty cycle.*

Step (1) Activate the EPIRB.

Step (2) Trigger the oscilloscope and store at least one complete cycle of the audio waveform.

Step (3) Measure the period (T) of the waveform. The period is the time difference between the half voltage points at the beginning and end of one cycle of the waveform. See Figure 2.

Step (4) Measure the pulse width (t_p) of the waveform. The pulse width is the time difference between the half voltage points on the rising and falling portions of the waveform. See Figure 2.

Step (5) Calculate the duty cycle (D) as follows:

$$D = \frac{t_p}{T}$$

Step (6) Repeat Steps 2 through 5 a sufficient number of times to determine the highest and lowest duty cycles.

Step (7) Record instrument settings and the highest and lowest duty cycles in percent.

Step (8) Repeat Steps 1-7 for 243 MHz.

(e) *Sweep repetition rate.*

Step (1) Connect a speaker to the detected output of the spectrum analyzer or receiver so the audio frequencies are audible. Alternatively, an FM radio tuned to 108 MHz placed in the vicinity of the EPIRB may be used.

Step (2) Activate the EPIRB.

Step (3) Time the number of audio sweeps (N) for a one minute interval.

Step (4) Calculate the audio sweep rate (R) using $R=N/60$.

Step (5) Record instrument settings and the sweep repetition rate in Hertz.

§2.1515 Spectral measurements.

(a) *Set-up.* Spectral measurements are to be performed in a shielded room.

§2.1515

47 CFR Ch. I (10–1–97 Edition)

Step (1) Place the EPIRB directly on a metal ground plane, such as the shielded room floor. The EPIRB should be powered by its own internal battery with its standard antenna attached and deployed.

Step (2) Place a suitable receiving antenna at a convenient distance from the EPIRB and connect it to the input of the spectrum analyzer to observe the radiated signal from the EPIRB. A signal generator and frequency counter capable of operating at 121.5 and 243 MHz are also required for these tests.

(b) *Occupied bandwidth test.*

Step (1) Activate the EPIRB and observe the fundamental frequency on a spectrum analyzer. Adjust location of receiving antenna and spectrum analyzer controls to obtain a suitable signal level (i.e., a level which will not overload the spectrum analyzer, but is far enough above the noise floor to allow determination of whether or not the sidebands are attenuated by at least the amount required in the rules).

Step (2) Set spectrum analyzer controls as follows:

I.F. bandwidth: 10 kHz
Video filter: OFF or as wide as possible
Scan time: 100 ms./div.
Amplitude scale: 10 dB/div.
Scan width: 20 Hz/div.
Center frequency: 121.5 MHz

Step (3) Record the signal level in dbm.

Step (4) Calculate the mean power reference level by adding $10 \log_{10}(D)$, where D is the modulation duty cycle determined in section 2.1513(d) of this part, to the recorded signal level.

Step (5) Set spectrum analyzer controls as follows:

I.F. bandwidth: 100 Hz
Video filter: OFF or as wide as possible
Scan time: 10 sec./div.
Amplitude scale: 10 dB/div.
Scan width: 20 kHz/div.

Step (6) Check the modulation sidebands for compliance with the required attenuation below the mean power reference level specified in §80.211 of the rules.

Step (7) Record how the test was performed, instrument settings and the occupied bandwidth in kHz and the 3 dB bandwidth of the carrier in Hz. (See §2.1517 of this part).

Step (8) Repeat Steps 1 through 7 for the signal at 243 MHz.

(c) *Signal enhancement test.*

The setup specified in §2.1515(a) is to be used in this method of measuring signal enhancement. Other methods may be used if shown to give results equivalent to or more accurate than this method.

Step (1) Activate the EPIRB and locate the carrier frequency at 121.5 MHz on the spectrum analyzer. Adjust location of receiving antenna and spectrum analyzer controls to obtain a suitable signal level (i.e., a level which will not overload the analyzer, but is far enough above the noise floor to allow sidebands at least 40 dB below the carrier to be viewed).

Step (2) Set the spectrum analyzer controls as follows:

I.F. bandwidth: 10 kHz
Video filter: OFF or as wide as possible
Scan time: 100 ms./div.
Amplitude scale: 5 dB/div.
Scan width: 10 kHz/div.
Center frequency: 121.5 MHz

Step (3) Record the amplitude in dBm.

Step (4) Calculate the total power output by adding $10 \log(D)$, where D is the modulation duty cycle determined in §2.1513(d) of this part, to the recorded signal level.

Step (5) Set the spectrum analyzer controls as follows:

I.F. bandwidth: 60 Hz or less
Video filter: OFF or as wide as possible
Scan time: 10 sec./div.
Amplitude scale: 5 dB/div.
Scan width: 20 Hz/div.
Center frequency: 121.5 MHz

Step (6) Measure and record the carrier power dBm as displayed on the spectrum analyzer.

Step (7) Calculate the ratio of carrier power to total power from Steps 4 and 6 using the following formula:

$$\frac{\text{carrier power}}{\text{total power}} = \log_{10}^{-1} \left[\frac{\text{dB}_c - \text{dB}_T}{10} \right] \quad \begin{array}{l} \text{dB}_c = \text{carrier power in step 6} \\ \text{dB}_T = \text{total power in step 4} \end{array}$$

dB_c = carrier power in step 6

dB_T = total power in step 4

Step (8) Record instrument settings, sample calculation and the percent of power within ± 30 Hz at 121.5 MHz or ± 60 Hz at 243 MHz of the carrier frequency.

Step (9) Repeat the above measurement Steps 1 through 8 for 243 MHz. For the higher frequency, the I.F. bandwidth in step 5 must be 120 Hz or less.

(d) *Carrier frequency test.*

The setup specified in §2.1515(a) is to be used in measuring the carrier frequency.

Step (1) Activate the EPIRB and locate the 121.5 MHz signal on the spectrum analyzer. Adjust location of receiving antenna and spectrum analyzer controls to obtain a suitable signal level.

Step (2) Set the spectrum analyzer controls as follows:

I.F. bandwidth: 100 Hz
Video filter: OFF or as wide as possible
Scan time: 10 sec./div.

Federal Communications Commission

§2.1517

Amplitude scale: 10 dB/div.
Scan width: 20 Hz/div.
Center frequency: 121.5 MHz

Step (3) Combine the output of the signal generator with the EPIRB signal at the input to the spectrum analyzer.

Step (4) Adjust amplitude and frequency of signal generator output to determine center of carrier frequency component.

Step (5) Measure signal generator frequency with frequency counter with accuracy of 5 PPM or better and record as carrier frequency.

Step (6) If applicable, change the type of modulation of the EPIRB and record the shift in carrier frequency as observed on the spectrum analyzer display.

Step (7) Repeat the above measurement Steps 1 through 6 for 243 MHz.

[56 FR 11683, Mar. 20, 1991; 60 FR 47302, Sept. 12, 1995]

DATA RECORDING/REPORTING REQUIREMENTS

§2.1517 Data recording/reporting requirements.

The test report for an EPIRB shall contain the following information:

(a) Specific identification, including the FCC ID, model and serial numbers, of the EPIRB under test.

(b) The name and location of the test sites used for the measurements.

(c) A description of the instrumentation and equipment, including antennas, used to perform the tests. For purchased equipment, the type, manufacturer and model number are generally sufficient as a description.

(d) The test results and associated comparative information.

(e) A description of any modifications made to the EUT or other system components during the testing.

(f) A description and justification of all deviations from the procedures described herein.

(g) The name and qualifications of the person responsible for the tests.

(h) The date the tests were performed.

(i) A statement signed by the individual responsible for the test that the EPIRB as tested complies or does not comply with the applicable FCC rules.

(j) A statement signed by the individual responsible, either directly or indirectly, for production or marketing of the device tested that the unit tested is representative of the equipment that all be marketed.





Figure 1 - Measurement Site



Frequency: $f = \frac{1}{T}$

Duty cycle: $D = \frac{t_p}{T}$

Modulation factor: $M = \frac{V_{\max} - V_{\min}}{V_{\max} + V_{\min}}$

Figure 2 - Typical Audio Waveform




Figure 3 - Example of ideal EPIRB Spectrum




Figure 4 - Example of EPIRB Carrier Component

PART 3—AUTHORIZATION AND ADMINISTRATION OF ACCOUNTING AUTHORITIES IN MARITIME AND MARITIME MOBILE-SATELLITE RADIO SERVICES

GENERAL

Sec.

- 3.1 Scope, basis, purpose.
- 3.2 Terms and definitions.

ELIGIBILITY

- 3.10 Basic qualifications.
- 3.11 Location of settlement operation.

APPLICATION PROCEDURES

- 3.20 Application form.
- 3.21 Order of consideration.
- 3.22 Number of accounting authority identification codes per applicant.
- 3.23 Legal applicant.
- 3.24 Evidence of financial responsibility.
- 3.25 Number of copies.
- 3.26 Where application is to be mailed.
- 3.27 Amended application.

- 3.28 Denial of privilege.
- 3.29 Notifications.

SETTLEMENT OPERATIONS

- 3.40 Operational requirements.
- 3.41 Amount of time allowed before initial settlements.
- 3.42 Location of processing facility.
- 3.43 Applicable rules and regulations.
- 3.44 Time to achieve settlements.
- 3.45 Amount of charges.
- 3.46 Use of gold francs.
- 3.47 Use of SDRs.
- 3.48 Cooperation with the Commission.
- 3.49 Agreement to be audited.
- 3.50 Retention of settlement records.
- 3.51 Cessation of operations.
- 3.52 Complaint/inquiry resolution procedures.
- 3.53 FCC notification of refusal to provide telecommunications service to U.S. registered vessel(s).
- 3.54 Notification of change in address.

REPORTING REQUIREMENTS

- 3.60 Reports.

§3.1

47 CFR Ch. I (10–1–97 Edition)

- 3.61 Reporting address.
- 3.62 Request for confidentiality.

ENFORCEMENT

- 3.70 Investigations.
- 3.71 Warnings.
- 3.72 Grounds for further enforcement action.
- 3.73 Waiting period after cancellation.
- 3.74 Ship stations affected by suspension, cancellation or relinquishment.
- 3.75 Licensee's failure to make timely payment.
- 3.76 Licensee's liability for payment.

AUTHORITY: 47 U.S.C. 154(i), 154(j) and 303(r).

SOURCE: 61 FR 20165, May 6, 1996, unless otherwise noted.

GENERAL

§3.1 Scope, basis, purpose.

By these rules the Federal Communications Commission (FCC) is delineating its responsibilities in certifying and monitoring accounting authorities in the maritime mobile and maritime mobile-satellite radio services. These entities settle accounts for public correspondence due to foreign administrations for messages transmitted at sea by or between maritime mobile stations located on board ships subject to U.S. registry and utilizing foreign coast and coast earth station facilities. These rules are intended to ensure that settlements of accounts for U.S. licensed ship radio stations are conducted in accordance with the International Telecommunication Regulations (ITR), taking into account the applicable ITU-T Recommendations.

§3.2 Terms and definitions.

(a) *Accounting Authority*. The Administration of the country that has issued the license for a mobile station or the recognized operating agency or other entity/entities designated by the Administration in accordance with ITR, Appendix 2 and ITU-T Recommendation D.90 to whom maritime accounts in respect of mobile stations licensed by that country may be sent.

(b) *Accounting Authority Certification Officer*. The official designated by the Managing Director, Federal Communications Commission, who is responsible, based on the coordination and review of information related to appli-

cants, for granting certification as an accounting authority in the maritime mobile and maritime mobile-satellite radio services. The Accounting Authority Certification Officer may initiate action to suspend or cancel an accounting authority certification if it is determined to be in the public's best interest.

(c) *Accounting Authority Identification Codes (AAICs)*. The discrete identification code of an accounting authority responsible for the settlement of maritime accounts (Annex A to ITU-T Recommendation D.90).

(d) *Administration*. Any governmental department or service responsible for discharging the obligations undertaken in the Convention of the International Telecommunication Union and the Radio Regulations. For purposes of these rules, "Administration" refers to a foreign government or the U.S. Government, and more specifically, to the Federal Communications Commission.

(e) *Authorization*. Approval by the Federal Communications Commission to operate as an accounting authority. Synonymous with "certification".

(f) *CCITT*. The internationally recognized French acronym for the International Telegraph and Telephone Consultative Committee, one of the former sub-entities of the International Telecommunication Union (ITU). The CCITT (ITU-T)¹ is responsible for developing international telecommunications recommendations relating to standardization of international telecommunications services and facilities, including matters related to international charging and accounting principles and the settlement of international telecommunications accounts.

¹At the ITU Additional Plenipotentiary Conference in Geneva (December, 1992), the structure, working methods and construct of the basic ITU treaty instrument were modified. The result is that the names of the sub-entities of the ITU have changed (e.g., the CCITT has become the Telecommunication Standardization Sector—ITU-T and Recognized Private Operating Agency has become Recognized Operating Agency-ROA). The changes were placed into provisional effect on March 1, 1993 with the formal entry into force of these changes being July 1, 1994. We will refer to the new nomenclatures within these rules, wherever practicable.

Federal Communications Commission

§3.10

Such recommendations are, effectively, the detailed implementation provisions for topics addressed in the International Telecommunication Regulations (ITR).

(g) *Certification*. Approval by the FCC to operate as an accounting authority. Synonymous with “authorization”.

(h) *Coast Earth Station*. An earth station in the fixed-satellite service or, in some cases, in the maritime mobile-satellite service, located at a specified fixed point on land to provide a feeder link for the maritime mobile-satellite service.

(i) *Coast Station*. A land station in the maritime mobile service.

(j) *Commission*. The Federal Communications Commission. The FCC.

(k) *Gold Franc*. A monetary unit representing the value of a particular nation's currency to a gold par value. One of the monetary units used to effect accounting settlements in the maritime mobile and the maritime mobile-satellite services.

(l) *International Telecommunication Union (ITU)*. One of the United Nations family organizations headquartered in Geneva, Switzerland along with several other United Nations (UN) family organizations. The ITU is the UN agency responsible for all matters related to international telecommunications. The ITU has over 180 Member Countries, including the United States, and provides an international forum for dealing with all aspects of international telecommunications, including radio, telecom services and telecom facilities.

(m) *Linking Coefficient*. The ITU mandated conversion factor used to convert gold francs to Special Drawing Rights (SDRs). Among other things, it is used to perform accounting settlements in the maritime mobile and the maritime mobile-satellite services.

(n) *Maritime Mobile Service*. A mobile service between coast stations and ship stations, or between ship stations, or between associated on-board communication stations. Survival craft stations and emergency position-indicating radiobeacon stations may also participate in this service.

(o) *Maritime Mobile-Satellite Service*. A mobile-satellite service in which mobile earth stations are located on board ships. Survival craft stations and emer-

gency position-indicating radiobeacon stations may also participate in this radio service.

(p) *Public Correspondence*. Any telecommunication which the offices and stations must, by reason of their being at the disposal of the public, accept for transmission. This usually applies to maritime mobile and maritime mobile-satellite stations.

(q) *Recognized Operating Agencies (ROAs)*.² Individuals, companies or corporations, other than governments or agencies, recognized by administrations, which operate telecommunications installations or provide telecommunications services intended for international use or which are capable of causing interference to international telecommunications. ROAs which settle debtor accounts for public correspondence in the maritime mobile and maritime mobile-satellite radio services must be certified as accounting authorities.

(r) *Ship Station*. A mobile station in the maritime mobile service located on board a vessel which is not permanently moored, other than a survival craft station.

(s) *Special Drawing Right (SDR)*. A monetary unit of the International Monetary Fund (IMF) currently based on a market basket of exchange rates for the United States, West Germany, Great Britain, France and Japan but is subject to IMF's definition. One of the monetary units used to effect accounting settlements in the maritime mobile and maritime mobile-satellite services.

(t) *United States*. The continental U.S., Alaska, Hawaii, the Commonwealth of Puerto Rico, the Virgin Islands or any territory or possession of the United States.

ELIGIBILITY

§3.10 Basic qualifications.

(a) Applicants must meet the requirements and conditions contained in these rules in order to be certified as an accounting authority. No individual or other entity, including accounting authorities approved by other administrations, may act as a United States

²Id.

§3.11

47 CFR Ch. I (10–1–97 Edition)

accounting authority and settle accounts of U.S. licensed vessels in the maritime mobile or maritime mobile-satellite services without a certification from the Federal Communications Commission. Accounting authorities with interim certification as of the effective date of this rule must submit to the application process discussed in §3.20. They will be “grandfathered”, i.e., granted permanent certification provided they demonstrate their eligibility and present a proper application.

(b) U.S. citizenship is not required of individuals in order to receive certification from the Commission to be an accounting authority. Likewise, joint ventures need not be organized under the laws of the United States in order to be eligible to perform settlements for U.S. licensed vessels. See, however, §3.11.

(c) Prior experience in maritime accounting, general commercial accounting, international shipping or any other related endeavor will be taken into consideration by the Commission in certifying accounting authorities. The lack of such expertise, however, will not automatically disqualify an individual, partnership, corporation or other entity from becoming an accounting authority.

(d) Applicants must provide formal financial statements or documentation proving all assets, liabilities, income and expenses.

(e) Applicants must be willing to offer their services to the public at a reasonable charge. This requirement will be waived for applicants who settle their own accounts *only* and are eligible to be “grandfathered” during the initial application period. However, should the need for additional accounting authorities be proven, these accounting authorities will be required to offer their services to the public or relinquish their certification.

§3.11 Location of settlement operation.

(a) *Within the United States.* A certified accounting authority maintaining all settlement operations, as well as associated documentation, within the United States will be assigned an AAIC with a “US” prefix.

(b) *Outside the United States.* A certified accounting authority maintaining settlement operations outside the United States will be assigned the same AAIC as that originally assigned to such entity by the administration of the country of origin. However, in no case will an entity be certified as an accounting authority for settlement of U.S. licensed vessel accounts unless the entity is requesting to conduct a settlement operation in the United States or has already been issued an AAIC by another administration.

APPLICATION PROCEDURES

§3.20 Application form.

Written application must be made to the Federal Communications Commission on FCC Form 44, “Application For Certification As An Accounting Authority” in order to be considered for certification as an accounting authority. No other application form may be used. No consideration will be given to applicants not submitting applications in accordance with these rules or in accordance with any other instructions the Commission may issue. FCC Form 44 may be obtained from the Commission by writing to the address shown in §3.61.

§3.21 Order of consideration.

(a) Accounting Authority applications will be processed on a first-come, first-served basis. When applications are received on the same day, the application with the earliest mailing date, as evidenced by the postmark, will be processed first. Interim accounting authorities seeking permanent certifications through the “grandfathering” process will not compete with other applicants during the first 60 days following the effective date of these rules which is allowed for submission of their applications. After the “grandfathering” process is completed, all other applicants will be processed as in paragraph (a) of this section.

(b) At any given time, there will be no more than 25 certified accounting authorities with a minimum of 15 “US” AAICs reserved for use by accounting authorities conducting settlement operations within the United States. The

Federal Communications Commission

§ 3.28

Commission will retain all valid applications received after the maximum number of accounting authorities have been approved and will inform such applicants that should an AAIC become available for reassignment in the future, the Commission will conditionally certify as an accounting authority the oldest of the qualified pending applicants, as determined by the order of receipt. Final certification would be conditional upon filing of an amended application (if necessary). The Commission will inform the applicant of his/her conditional selection in writing to confirm the applicant's continued interest in becoming an accounting authority.

§ 3.22 Number of accounting authority identification codes per applicant.

(a) No entity will be entitled to or assigned more than one AAIC.

(b) AAICs may not be reassigned, sold, bartered or transferred and do not convey upon sale or absorption of a company or firm without the express written approval of the Commission. Only the FCC may certify accounting authorities and assign U.S. AAICs for entities settling accounts of U.S. licensed vessels in the maritime mobile and maritime mobile-satellite services.

(c) Accounting authorities who are "grandfathered" during the initial application period may retain their interim AAIC.

§ 3.23 Legal applicant.

The application shall be signed by the individual, partner or primary officer of a corporation who is legally able to obligate the entity for which he or she is a representative.

§ 3.24 Evidence of financial responsibility.

All applicants must provide evidence of sound financial status. To the extent that the applicant is a business, formal financial statements will be required. Other applicants may submit documentation proving all assets, liabilities, income and expenses which supports their ability to meet their personal obligations. Applicants must provide any additional information deemed necessary by the Commission.

§ 3.25 Number of copies.

One original and one copy of FCC Form 44, "Application For Certification As An Accounting Authority" will be required. Only applications mailed to the Commission on official, Commission approved application forms will be considered. Applications should be mailed at least 90 days prior to planned commencement of settlement activities to allow time for the Commission to review the application and to allow for the informal public comment period.

§ 3.26 Where application is to be mailed.

All applications shall be mailed to the Accounting Authority Certification Officer in Washington, D.C. The designated address will be provided on the FCC Form 44, "Application for Certification As An Accounting Authority".

§ 3.27 Amended application.

Changes in circumstances that cause information previously supplied to the FCC to be incorrect or incomplete and that could affect the approval process, require the submission of an amended application. The amended application should be mailed to the Commission immediately following such change. See also §§ 3.24 and 3.51.

§ 3.28 Denial of privilege.

(a) The Commission, in its sole discretion, may refuse to grant an application to become an accounting authority for any of the following reasons:

(1) Failure to provide evidence of acceptable financial responsibility;

(2) If the applicant, in the opinion of the FCC reviewing official, does not possess the qualifications necessary to the proper functioning of an accounting authority;

(3) Application is not personally signed by the proper official(s);

(4) Applicant does not provide evidence that accounting operations will take place in the United States or its territories and the applicant does not already possess an AAIC issued by another administration;

§ 3.29

(5) Application is incomplete, the applicant fails to provide additional information requested by the Commission or the applicant indicates that it cannot meet a particular provision; or

(6) When the Commission determines that the grant of an authorization is contrary to the public interest.

(b) These rules provide sufficient latitude to address defects in applications. Entities seeking review should follow procedures set forth in § 1.106 or § 1.115 of this chapter.

§ 3.29 Notifications.

(a) The Commission will publish the name of an applicant in a Public Notice before granting certification and will invite informal public comment on the qualifications of the applicant from any interested parties. Comments received will be taken into consideration by the Commission in making its determination as to whether to approve an applicant as an accounting authority. Thirty days will be allowed for submission of comments.

(b) The Commission will notify each applicant in writing as to whether the applicant has been approved as an accounting authority. If the application is not approved, the Commission will provide a brief statement of the grounds for denial.

(c) The names and addresses of all newly certified accounting authorities will be published in a Public Notice issued by the Commission. Additionally, the Commission will notify the ITU within 30 days of any changes to its approved list of accounting authorities.

SETTLEMENT OPERATIONS

§ 3.40 Operational requirements.

All accounting authorities must conduct their operations in conformance with the provisions contained in this section and with relevant rules and guidance issued from time to time by the Commission.

§ 3.41 Amount of time allowed before initial settlements.

An accounting authority must begin settling accounts no later than six months from the date of certification. Failure to commence settlement operations is cause for suspension or can-

47 CFR Ch. I (10–1–97 Edition)

cellation of an accounting authority certification.

§ 3.42 Location of processing facility.

Settlement of maritime mobile and maritime mobile-satellite service accounts must be performed within the United States by all accounting authorities possessing the “US” prefix. Other accounting authorities approved by the Commission may settle accounts either in the U.S. or elsewhere. See also §§ 3.11 and 3.21(b).

§ 3.43 Applicable rules and regulations.

Accounting authority operations must be conducted in accordance with applicable FCC rules and regulations, the International Telecommunication Regulations (ITR), and other international rules, regulations, agreements, and, where appropriate, ITU-T Recommendations. In particular, the following must be adhered to or taken into account in the case of ITU-T.

(a) The latest basic treaty instrument(s) of the International Telecommunication Union (ITU);

(b) Binding agreements contained in the Final Acts of World Administrative Radio Conferences and/or World International Telecommunication Conferences;

(c) ITU Radio Regulations;

(d) ITU International Telecommunication Regulations (ITR);

(e) ITU-T Recommendations (particularly D.90 and D.195); and

(f) FCC Rules and Regulations (47 CFR part 3).

§ 3.44 Time to achieve settlements.

All maritime telecommunications accounts should be timely paid in accordance with applicable ITU Regulations, Article 66 and International Telecommunication Regulations (Melbourne, 1988). Accounting authorities are deemed to be responsible for remitting, in a timely manner, all valid amounts due to foreign administrations or their agents.

§ 3.45 Amount of charges.

Accounting Authorities may charge any reasonable fee for their settlement services. Settlements themselves, however, must adhere to the standards set

Federal Communications Commission

§ 3.51

forth in these rules and must be in accordance with the International Telecommunication Regulations (ITR) taking into account the applicable ITU-T Recommendations and other guidance issued by the Commission.

§ 3.46 Use of gold francs.

An accounting authority must accept accounts presented to it from foreign administrations in gold francs. These gold francs must be converted on the date of receipt of the bill to the applicable Special Drawing Right (SDR) rate (as published by the International Monetary Fund) on that date utilizing the linking coefficient of 3.061 gold francs = 1 SDR. An equivalent amount in U.S. dollars must be paid to the foreign administration. Upon written concurrence by the FCC, an accounting authority may make separate agreements, in writing, with foreign administrations or their agents for alternative settlement methods, in accordance with ITU-T Recommendation D.195.

§ 3.47 Use of SDRs.

An accounting authority must accept accounts presented to it from foreign administrations in Special Drawing Rights (SDRs). These SDRs must be converted to dollars on the date of receipt by the accounting authority and an equivalent amount in US dollars must be paid to the foreign administration. The conversion rate will be the applicable rate published by the International Monetary Fund (IMF) for the date of receipt of the account from the foreign administration. Upon written concurrence by the FCC, any accounting authority may make separate agreements, in writing, with foreign administrations or their agents for alternative settlement methods, provided account is taken of ITU-T Recommendation D.195.

§ 3.48 Cooperation with the Commission.

Accounting authorities must cooperate fully with the FCC in all respects concerning international maritime settlements issues, including the resolution of questions of fact or other issues arising as a result of settlement operations.

§ 3.49 Agreement to be audited.

Accounting authorities accept their certifications on condition that they are subject to audit of their settlement activities by the Commission or its representative. Additionally, the Commission reserves the right to verify any statement(s) made or any materials submitted to the Commission under these rules. Verification may involve discussions with ship owners or others as well as the requirement to submit additional information to the Commission. Failure to respond satisfactorily to any audit findings is grounds for forfeiture or suspension or cancellation of authority to act as an accounting authority for U.S. vessels.

§ 3.50 Retention of settlement records.

Accounting authorities must maintain, for the purpose of compliance with these rules, all settlement records for a period of at least seven years following settlement of an account with a foreign administration or agent.

§ 3.51 Cessation of operations.

The FCC must be notified immediately should an accounting authority plan to relinquish its certification or cease to perform settlements as authorized. Additionally, the Commission must be advised in advance of any proposed transfer of control of an accounting authority's firm or organization, by any means, to another entity.

(a) When an accounting authority is transferred, merged or sold, the new entity must apply for certification in its own right if it is interested in becoming an accounting authority. Provided the new applicant is eligible and completes the application process satisfactorily, the AAIC will be transferred to the new applicant. In the case of a merger of two accounting authorities, the merged entity must decide which AAIC to retain.

(b) Section 3.21(a) will be waived for these applicants.

(c) The applicant must comply with application process including public comment.

(d) The applicant must certify acceptance of all accounts and must furnish a list of the accounts to the Commission at the time of application.

§ 3.52

47 CFR Ch. I (10–1–97 Edition)

§ 3.52 Complaint/inquiry resolution procedures.

(a) Accounting authorities must maintain procedures for resolving complaints and/or inquiries from its contractual customers (vessels for which it performs settlements), the FCC, the ITU, and foreign administrations or their agents. These procedures must be available to the Commission upon request.

(b) If a foreign administration requests assistance in collection of accounts from ships licensed by the FCC, the appropriate accounting authority will provide all information requested by the Commission in a timely manner to enable the Commission to determine the cause of the complaint and to resolve the issue. If accounts are in dispute, the Commission will determine the amount due the foreign administration, accounting authority or ROA, and may direct the accounting authority to pay the accounts to the foreign administration. If the accounting authority does not pay the disputed accounts within a reasonable timeframe, the Commission may take action to levy a forfeiture, cancel the AAIC privilege and/or to revoke any operating authority or licenses held by that accounting authority. (See also § 3.72).

§ 3.53 FCC notification of refusal to provide telecommunications service to U.S. registered vessel(s).

An accounting authority must inform the FCC immediately should it receive notice from any source that a foreign administration or facility is refusing or plans to refuse legitimate public correspondence to or from any U.S. registered vessel.

§ 3.54 Notification of change in address.

The Commission must be notified in writing within 15 days of any change in address of an accounting authority. Such written notification should be sent to the address shown in § 3.61.

REPORTING REQUIREMENTS

§ 3.60 Reports.

(a) *Initial Inventory of Vessels.* Within 60 days after receiving final approval from the FCC to be an accounting au-

thority, each certified accounting authority must provide to the FCC an initial list of vessels for which it is performing settlements. This list should contain only U.S. registered vessels. Such list shall be typewritten or computer generated, be annotated to indicate it is the initial inventory and be in the general format of the following and provide the information shown:

<i>Vessel Name</i>	<i>Call Sign</i>

(b) *Semi-Annual Additions/Modifications/Deletions to Vessel Inventory.* Beginning with the period ending on the last day of March or September following submission of an accounting authority's Initial Inventory of Vessels (See paragraph (a) of this section.) and each semi-annual period thereafter, each accounting authority is required to submit to the FCC a report on additions, modifications or deletions to its list of vessels for which it is performing or intending to perform settlements, whether or not settlements actually have taken place. The list should contain only U.S. registered vessels. The report shall be typewritten or computer generated and be in the following general format:

ADDITIONS TO CURRENT VESSEL INVENTORY

<i>Vessel Name</i>	<i>Call Sign</i>	<i>Effective Date</i>

MODIFICATIONS TO CURRENT VESSEL INVENTORY

<i>Previous Vessel Name</i>	<i>Previous Call Sign</i>	<i>New Vessel Name</i>	<i>New Call Sign</i>	<i>Effective Date</i>

DELETIONS TO CURRENT VESSEL INVENTORY

<i>Vessel Name</i>	<i>Call Sign</i>	<i>Effective Date</i>

The preceding report must be received by the Commission no later than 15 days following the end of the period (March or September) for which the report pertains. Modifications refer to changes to call sign or ship name of vessels for which the accounting authority settles accounts and for which

Federal Communications Commission

§ 3.72

basic information has previously been provided to the Commission. Reports are to be submitted even if there have been no additions, modifications or deletions to vessel inventories since the previous report. If there are no changes to an inventory, this should be indicated on the report.

(c) *End of Year Inventory.* By February 1st of each year, each accounting authority must submit an end-of-year inventory report listing vessels for which the accounting authority performed settlements as of the previous December 31st. The list should contain only U.S. registered vessels. The report must be typewritten or computer generated and prepared in the same general format as that shown in paragraph (a) of this section except it should be annotated to indicate it is the End of Year inventory.

(d) *Annual Statistical Report of Settlement Operations.* By February 1st of each year, each accounting authority settling accounts for U.S. registered vessels must submit to the FCC an Annual Statistical Report, FCC Form 45, which details the number and dollar amount of settlements, by foreign administration, during the preceding twelve months. Information contained in this report provides statistical data that will enable the Commission to monitor operations to ensure adherence to these rules and to appropriate international settlement procedures. FCC Form 45 can be obtained by writing to the address in 3.61 of these rules.

§ 3.61 Reporting address.

All reports must be received at the following address no later than the required reporting date:

Accounting Authority Certification Officer,
Financial Operations Division, Stop 1110A,
Federal Communications Commission, 1919
M Street NW., Washington, D.C. 20554

§ 3.62 Request for confidentiality.

Applicants should comply with § 0.459 of this chapter when requesting confidentiality and cannot assume that it will be offered automatically.

ENFORCEMENT

§ 3.70 Investigations.

The Commission may investigate any complaints made against accounting authorities to ensure compliance with the Commission's rules and with applicable ITU Regulations and other international maritime accounting procedures.

§ 3.71 Warnings.

The Commission may issue written warnings or forfeitures to accounting authorities which are found not to be operating in accordance with established rules and regulations. Warnings will generally be issued for violations which do not seriously or immediately affect settlement functions or international relations. Continued or unresolved violations may lead to further enforcement action by the Commission, including any or all legally available sanctions, including but not limited to, forfeitures (Communications Act of 1934, Sec. 503), suspension or cancellation of the accounting authority certification.

§ 3.72 Grounds for further enforcement action.

(a) The Commission may take further enforcement action, including forfeiture, suspension or cancellation of an accounting authority certification, if it is determined that the public interest so requires. Reasons for which such action may be taken include, inter alia:

- (1) Failure to initiate settlements within six months of certification or failure to perform settlements during any subsequent six month period;
- (2) Illegal activity or fraud;
- (3) Non-payment or late payment to a foreign administration or agent;
- (4) Failure to follow ITR requirements and procedures;
- (5) Failure to take into account ITU-T Recommendations;
- (6) Failure to follow FCC rules and regulations;
- (7) Bankruptcy; or
- (8) Providing false or incomplete information to the Commission or failure to comply with or respond to requests for information.

§3.73

(b) Prior to taking any of the enforcement actions in paragraph (a) of this section, the Commission will give notice of its intent to take the specified action and the grounds therefor, and afford a 30-day period for a response in writing; provided that, where the public interest so requires, the Commission may temporarily suspend a certification pending completion of these procedures. Responses must be forwarded to the Accounting Authority Certification Officer. See §3.61.

§3.73 Waiting period after cancellation.

An accounting authority whose certification has been cancelled must wait a minimum of three years before reapplying to be an accounting authority.

§3.74 Ship stations affected by suspension, cancellation or relinquishment.

(a) Whenever the accounting authority privilege has been suspended, cancelled or relinquished, the accounting authority is responsible for immediately notifying all U.S. ship licensees for which it was performing settlements of the circumstances and informing them of the requirement contained in paragraph (b) of this section.

(b) Those ship stations utilizing an accounting authority's AAIC for which the subject accounting authority certification has been suspended, cancelled or relinquished, should make contractual arrangements with another properly authorized accounting authority to settle its accounts.

(c) The Commission will notify the ITU of all accounting authority suspensions, cancellations and relinquishments, and

(d) The Commission will publish a Public Notice detailing all accounting authority suspensions, cancellations and relinquishments.

§3.75 Licensee's failure to make timely payment.

Failure to remit proper and timely payment to the Commission or to an accounting authority may result in one or more of the following actions against the licensee:

47 CFR Ch. I (10–1–97 Edition)

(a) Forfeiture or other authorized sanction.

(b) The refusal by foreign countries to accept or refer public correspondence communications to or from the vessel or vessels owned, operated or licensed by the person or entity failing to make payment. This action may be taken at the request of the Commission or independently by the foreign country or coast station involved.

(c) Further action to recover amounts owed utilizing any or all legally available debt collection procedures.

§3.76 Licensee's liability for payment.

The U.S. ship station licensee bears ultimate responsibility for final payment of its accounts. This responsibility cannot be superseded by the contractual agreement between the ship station licensee and the accounting authority. In the event that an accounting authority does not remit proper and timely payments on behalf of the ship station licensee:

(a) The ship station licensee will make arrangements for another accounting authority to perform future settlements, and

(b) The ship station licensee will settle any outstanding accounts due to foreign entities.

(c) The Commission will, upon request, take all possible steps, within the limits of applicable national law, to ensure settlement of the accounts of the ship station licensee. As circumstances warrant, this may include issuing warnings to ship station licensees when it becomes apparent that an accounting authority is failing to settle accounts. See also §§3.70 through 3.74.

PART 5—EXPERIMENTAL RADIO SERVICES (OTHER THAN BROADCAST)

Subpart A—General

Sec.

5.1 Basis and purpose.

5.2 [Reserved]

5.3 Definition of terms.

5.4 General citizenship requirements.

5.5 Transfer and assignment of station authorization.

Federal Communications Commission

§5.3

Subpart B—Applications and Licenses

- 5.51 Station authorization required.
- 5.52 [Reserved]
- 5.53 Filing of applications.
- 5.54 Who may sign applications.
- 5.55 Forms to be used.
- 5.56 Procedure for obtaining a special temporary authorization.
- 5.57 Supplementary statements required.
- 5.58 Partial grants.
- 5.59 Defective applications.
- 5.60 Amendment or dismissal of applications.
- 5.61 [Reserved]
- 5.62 Licenses required for separate experimental projects.
- 5.63 License period.
- 5.64 Change in equipment.
- 5.65 Operation at a temporary location.
- 5.66 Discontinuance of station operation.
- 5.67 Policy governing the assignment of frequencies.
- 5.68 Cancellation provisions.
- 5.69 Notification to the National Radio Astronomy Observatory.

Subpart C—Technical Standards

- 5.101 Frequency stability.
- 5.102 Types of emission.
- 5.103 Authorized bandwidth.
- 5.104–5.105 [Reserved]
- 5.106 Transmitter control requirements.
- 5.107 [Reserved]
- 5.108 Wildlife tracking and ocean buoy tracking operations.
- 5.109 Acceptability of transmitters for licensing.

Subpart D—Operating Requirements

- 5.151 General limitations on use.
- 5.152 Station identification.
- 5.153 Suspension of transmission required.
- 5.154 [Reserved]
- 5.155 Operator requirements.
- 5.156 [Reserved]
- 5.157 Posting station licenses.
- 5.158 Authorized points of communication.
- 5.159 Operation during an emergency.
- 5.160 Inspection of stations.
- 5.161 Inspection and maintenance of tower marking and lighting and associated control equipment.
- 5.162 Notice of violation.
- 5.163 Content of station records.
- 5.164 Form of station records.
- 5.165 Retention of station records.
- 5.166 Adherence to program of research.

Subpart E—Experimental Authorizations

- 5.201 Eligibility of license.
- 5.202 Scope of service.
- 5.203 Frequencies for the Experimental Radio Service.
- 5.204 Experimental report.

- 5.205 Frequencies for field strength surveys or equipment demonstration.
- 5.206 Limited market studies.

Subparts F–G [Reserved]

Subpart H—Student Authorizations

- 5.401 Eligibility for license.
- 5.402 Filing of applications.
- 5.403 Waiver of construction permit.
- 5.404 [Reserved]
- 5.405 Power limitation.
- 5.406 Frequencies.
- 5.407 Measurements required.
- 5.408 Waiver of technical and operating requirements.
- 5.409 Noninterference condition.
- 5.410 Record of operation.
- 5.411 Notification.

AUTHORITY: Secs. 4, 303, 48 Stat. 1066, 1082, as amended; 47 U.S.C. 154, 303. Interpret or apply sec. 301, 48 Stat. 1081, as amended; 47 U.S.C. 301.

SOURCE: 28 FR 12506, Nov. 22, 1963, unless otherwise noted.

Subpart A—General

§5.1 Basis and purpose.

(a) The rules following in this part are promulgated pursuant to the provisions of Title III of the Communications Act of 1934, as amended, which vests authority in the Federal Communications Commission to regulate radio transmissions and to issue licenses for radio stations.

(b) The purpose of this part is to prescribe the manner in which parts of the radio frequency spectrum may be made available for experimentation as defined in this part and provided for.

§5.2 [Reserved]

§5.3 Definition of terms.

For the purpose of this part, the following definitions shall be applicable. For other definitions, refer to part 2 of this chapter (Frequency Allocations and Radio Treaty Matters; General Rules and Regulations).

(a) *Authorized frequency.* The frequency assigned to a station by the Commission and specified in the instrument of authorization.

(b) *Authorized power.* The power assigned to a radio station by the Commission and specified in the instrument of authorization. The authorized power

§5.4

does not necessarily correspond to the power used by the Commission for purposes of its Master Frequency Record (MFR) and notification to the International Telecommunication Union.

(c) *Experimental Radio Service.* A service in which Radio waves are employed for purposes of experimentation in the radio art or for purposes of providing essential communications for research projects which could not be conducted without the benefit of such communications.

(d) *Experimental Station.* A station utilizing radio waves in experiments with a view to the development of science or technique

(e) [Reserved]

(f) *Fixed service.* A service of radio-communication between specified fixed points.

(g) *Fixed station.* A station in the fixed service.

(h) *Harmful interference.* Any radiation or any induction which endangers the functioning of a radio-navigation service or of a safety service or obstructs or repeatedly interrupts a radio service operating in accordance with the Table of Frequency Allocations and other provisions of part 2 of this chapter.

(i) *Landing area.* As defined by Title I, section I (22) of the Civil Aeronautics Act of 1938, as amended, landing area means any locality, either of land or water, including airdromes and intermediate landing fields, which is used, or intended to be used, for the landing and take-off of aircraft, whether or not facilities are provided for the shelter, servicing, or repair of aircraft, or for receiving or discharging passengers or cargo.

(j) *Land station.* A station in the mobile service not intended for operation while in motion.

(k) *Mobile service.* A service of radiocommunication between mobile and land stations, or between mobile stations.

(l) *Mobile station.* A station in a mobile service intended to be used while in motion or during halts at unspecified points.

(m) *Mean power of radio transmitter.* The power supplied to the antenna during normal operation, averaged over a time sufficiently long compared to the

47 CFR Ch. I (10–1–97 Edition)

period corresponding to the lowest frequency encountered in actual modulation.

(n) *Peak power of a radio transmitter.* The mean power supplied to the antenna during one radio frequency cycle at the highest crest of the modulation envelope, taken under conditions of normal operation.

(o) *Person.* An individual, partnership, association, joint stock company, trust, or corporation.

(p) *Public correspondence.* Any telecommunication which the offices and stations, by reason of their being at the disposal of the public, must accept for transmission.

(q) *Radio service.* An administrative subdivision of the field of radio-communication. In an engineering sense, the subdivisions may be made according to the method of operation, as, for example, mobile service and fixed service. In a regulatory sense, the subdivisions may be descriptive of particular groups of licensees, as, for example, the groups of persons licensed under this part.

(r) *Station authorization.* Any construction permit, license, or special temporary authorization issued by the Commission.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.4 General citizenship requirements.

A station license shall not be granted to or held by a foreign government or a representative thereof.

[40 FR 5366, Feb. 5, 1975]

§5.5 Transfer and assignment of station authorization.

A station authorization, the frequencies authorized to be used by the grantee of such authorization, and the rights therein granted by such authorization shall not be transferred, assigned, or in any manner either voluntarily or involuntarily disposed of, or indirectly by transfer of control of any corporation holding such authorization, to any person, unless the Commission shall, after securing full information, decide that said transfer is in the public interest, and shall give its consent in writing. Requests for authority to transfer or assign a station

Federal Communications Commission

§ 5.54

authorization shall be submitted on the forms prescribed by § 5.55.

Subpart B—Applications and Licenses

§ 5.51 Station authorization required.

(a) No radio transmitter shall be operated in the Experimental Radio Service except under and in accordance with a proper station authorization granted by the Federal Communications Commission.

(b) Persons desiring to install and operate radio transmitting equipment under this part should first submit an application for a radio station authorization in accordance with § 5.55.

(c) If installation and/or operation of the equipment may significantly impact the environment, see § 1.1307 of this chapter, an environmental assessment as defined in § 1.1311 of this chapter must be submitted with the application.

[41 FR 45007, Oct. 14, 1976, as amended at 48 FR 52737, Nov. 22, 1983; 55 FR 20396, May 16, 1990]

§ 5.52 [Reserved]

§ 5.53 Filing of applications.

(a) To assure that necessary information is supplied in a consistent manner by all persons, standard forms are prescribed for use in connection with the majority of applications and reports submitted for Commission consideration. Standard numbered forms applicable to the Experimental Radio Service are discussed in § 5.55 and may be obtained from the Washington, D.C., Office of the Commission, or from any of its engineering field offices. Concerning matters where no standard form is applicable, the informal application procedure outlined in § 5.55(k) should be followed.

(b) Any application for radio station authorization and all correspondence relating thereto shall be submitted to the Commission's office at Washington, DC. (Applications requiring fees as set forth at part 1, subpart G of this chapter must be filed in accordance with § 0.401(b) of the rules.)

(c) Unless otherwise specified, an application shall be filed at least sixty days prior to the date on which it is de-

sired that Commission action thereon be completed.

(d) Each application for station authorization shall be specific and complete with regard to station location, proposed equipment, power, antenna height, and operating frequency; and other information required by the application form and this part.

(e) Applications involving operation at temporary locations:

(1) When a land station or a fixed station is to remain at a single location for less than six months, the location is considered to be temporary and the procedure outlined in § 5.65 shall apply.

(2) When a land station or fixed station authorized to operate at temporary locations remains at a single location for more than six months, an application for modification of the station authorization to specify the permanent location shall be filed within thirty days after expiration of the six-month period.

(f) Unless otherwise specified in a particular case, only the original signed copy of the application shall be filed. Applications with facsimile signatures will not be accepted.

[28 FR 12506, Nov. 22, 1963, as amended at 40 FR 60033, Dec. 31, 1975; 48 FR 52737, Nov. 22, 1983; 55 FR 19172, May 8, 1990]

§ 5.54 Who may sign applications.

(a) Except as provided in paragraph (b) of this section, applications, amendments thereto, and related statements of fact required by the Commission shall be personally signed by the applicant, if the applicant is an individual; by one of the partners, if the applicant is a partnership; by an officer or duly authorized employee, if the applicant is a corporation; or by a member who is an officer, if the applicant is an unincorporated association. Applications, amendments, and related statements of fact filed on behalf of eligible government entities, such as states and territories of the United States and political subdivisions thereof, the District of Columbia, and units of local government, including incorporated municipalities, shall be signed by such duly elected or appointed officials as may be competent to do so under the laws of the applicable jurisdiction.

(b) Applications, amendments thereto, and related statements of fact required by the Commission may be signed by the applicant's attorney in case of the applicant's physical disability or of his absence from the United States. The attorney shall in that event separately set forth the reason why the application is not signed by the applicant. In addition, if any matter is stated on the basis of the attorney's belief only (rather than his knowledge), he shall separately set forth his reasons for believing that such statements are true.

(c) Only the original of applications, amendments, or related statements of fact need be signed; copies may be conformed.

(d) Applications, amendments, and related statements of fact need not be submitted under oath. Willful false statements made therein, however, are punishable by fine and imprisonment, U.S. Code, Title 18, section 1001, and by appropriate administrative sanctions, including revocation of station license pursuant to section 312(a)(1) of the Communications Act of 1934, as amended.

§5.55 Forms to be used.

(a) *Application for combined construction permit and radio station license for land stations and fixed stations.* A separate application shall be submitted on FCC Form 442 for each base station and each fixed station. Whenever the proposed antenna exceeds 6 meters in height above the ground level or more than 6 meters in height above an existing building, the applicant must comply with the requirement of part 17 of this chapter.

(b) *Application for combined construction permit and radio station license for mobile stations.* An application for each mobile station comprising any specified number of mobile units to be operated in the same service and within the same geographical area, including handcarried or pack-carried units, may be combined into one application and shall be submitted on FCC Form 442.

NOTE: An application for mobile units may be combined with an application for a single base station for such mobile units as will operate with that base station only.

(c) *Application for modification of combined construction permit and station license.* An application for modification of station authorization shall be submitted on FCC Form 442. A blanket application for modification of a group of authorizations of the same class where the modifications requested are the same for all stations covered by the application. The individual stations covered by such application shall be clearly identified therein. However, application for modification to change location of a base or fixed station shall be filed as a separate application.

(d) *Application for renewal of station authorization.* Application for renewal of station license shall be submitted on FCC Form 405. A blanket application may be submitted for renewal of a group of station licenses in the same class in those cases where the renewal requested is in exact accordance with the terms of the existing authorizations. The individual stations covered by such applications shall be clearly identified thereon. Unless otherwise directed by the Commission, each application for renewal of license shall be filed at least 60 days prior to the expiration date of the license to be renewed.

(e) *Application for consent to assignment of radio station authorization.* Application on FCC Form 702 shall be submitted when the legal right to construct or to control the use and operation of a station is to be transferred as a result of a voluntary act (contract or other agreement) or an involuntary act (death or legal disability) of the grantee of a station authorization or by involuntary assignment of the physical property constituting the station under a court decree in bankruptcy proceedings, or other court order, or by operation of law in any other manner. Such application must be accompanied by the FCC Form 442 of which only the certification need be signed by the proposed assignee. No other information is required to be submitted on this form.

(f) *Application for consent to transfer of control of Corporation holding radio station authorization.* Application for consent to transfer of control shall be submitted on FCC Form 703 whenever it is proposed to change the control of a

Federal Communications Commission

§5.57

corporation holding a station authorization.

(g) *Informal application.* (1) An application not submitted on a standard form prescribed by the Commission is considered to be an informal application. Each informal application shall be submitted normally in letter form, and with the original signed in accordance with §5.54. Each application shall be clear and complete within itself as to the facts presented and the action desired.

(2) An informal application for authority to operate transmitting equipment will be accepted only under the conditions set forth in §5.56.

[41 FR 45007, Oct. 14, 1976, as amended at 48 FR 52737, Nov. 22, 1983]

§5.56 Procedure for obtaining a special temporary authorization.

(a) The Commission may issue a special temporary authorization under this part in cases where a need is shown for operation of an authorized station for a limited time only, in a manner other than that specified in the existing authorization, but not in conflict with the Commission's rules.

(b) An application for special temporary authorization may be filed as an informal application in the manner prescribed by §5.55(k) and shall contain the following information:

- (1) Name and address.
- (2) Need for special action.
- (3) Type of operation to be conducted.
- (4) Purpose of operation.
- (5) Time and date of proposed operation.
- (6) Class of station, call sign of station, and nature of service.
- (7) Location of proposed operation.
- (8) Equipment to be used, including name of manufacturer, model and number of units.
- (9) Frequency(ies) desired.
- (10) Plate power input to final radio frequency stage.
- (11) Type of emission.
- (12) Overall height of antenna structure above ground.

(c) No request for special temporary authorization will be considered unless full particulars as to the purpose for which the request is made are stated.

[28 FR 12506, Nov. 22, 1963, as amended at 34 FR 3802, Mar. 5, 1969]

§5.57 Supplementary statements required.

(a) Each applicant for an authorization in the Experimental Radio Service must enclose with the application a narrative statement describing in detail the program of research and experimentation proposed, the specific objectives sought to be accomplished; and how the program of experimentation has a reasonable promise of contribution to the development, extension, or expansion, or utilization of the radio art, or is along lines not already investigated. An applicant may request non-disclosure of proprietary information submitted under this part. These requests should follow the procedures for submission set forth in §0.459 of this chapter.

(b) Applications involving government contracts. In addition to the requirement of paragraph (a) of this section, if the authorization is to be used for the purpose of fulfilling the requirements of a contract with an agency of the United States Government, the applicant shall submit the name of the contracting agency and the contract number.

(c) Applications involving development of equipment for export purposes. In addition to the requirements of paragraph (a) of this section, if the authorization is to be used for the purpose of developing equipment for exportation to be employed by stations under the jurisdiction of a foreign government, the applicant shall submit the contract number and the name of the foreign government concerned.

(d) *Applications involving communications essential to a research project.* The provisions of paragraph (a) of this section shall not be applicable to applications for an authorization in the Experimental Radio Service to be used for communications essential to a research project. Applicants in this service shall include as a part of the application for an authorization the following:

(1) A description of the nature of the research project being conducted.

(2) A showing that communication facilities are necessary for the research project involved.

§5.58

(3) A showing that existing communication facilities are inadequate.

[41 FR 45008, Oct. 14, 1976, as amended at 48 FR 52737, Nov. 22, 1983]

§5.58 Partial grants.

Where the Commission without a hearing grants any application in part, or with any privileges, terms, or conditions other than those requested, or subject to any interference that may result to a station if designated application or applications are subsequently granted, the action of the Commission shall be considered as a grant of such application unless the applicant shall, within 30 days from the date on which such grant is made or from its effective date if a later date is specified, file with the Commission a written request rejecting the grant as made. Upon receipt of such request, the Commission will vacate its original action upon the application and set the application for hearing in the same manner as other applications are set for hearing.

§5.59 Defective applications.

(a) Applications which are defective with respect to completeness of answers to required questions, execution or other matters of a purely formal character will not be received for filing by the Commission, and will be returned to the applicant with a brief statement as to the omissions.

(b) If an applicant is requested by the Commission to file any documents or information not included in the prescribed application form, a failure to comply with such request will constitute a defect in the application.

(c) Applications which are not in accordance with the Commission's rules, regulations or other requirements will be considered defective unless accompanied either (1) by a petition to amend any rule or regulation with which the application is in conflict, or (2) by a request of the applicant for waiver of, or an exception to, any rule, regulation or requirement with which the application is in conflict. Such request shall show the nature of the waiver or exception desired and set forth the reasons in support thereof.

47 CFR Ch. I (10–1–97 Edition)

§5.60 Amendment or dismissal of applications.

(a) Any application may be amended or dismissed without prejudice upon request of the applicant prior to the time the application is granted or designated for hearing. Each amendment to, or request for dismissal of an application shall be signed, authenticated, and submitted in the same manner and with the same number of copies as required for the original application. All subsequent correspondence or other material which the applicant desires to have incorporated as a part of an application already filed shall be submitted in the form of an amendment to the application.

(b) Failure to prosecute an application, or failure to respond to official correspondence or request for additional information, will be cause for dismissal. Such dismissal will be without prejudice where an application has not yet been designated for hearing; such dismissal may be made with prejudice after an application has been designated for hearing.

§5.61 [Reserved]

§5.62 Licenses required for separate experimental projects.

A separate station license will be required for each class of station in the Experimental Radio Service. Application for a class of station embracing widely divergent and unrelated experimentations normally will require a separate license for each phase of the experimental program: *Provided, however,* That the Commission may, when circumstances warrant, issue a single license embracing the entire project.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.63 License period.

(a) The basic license period for stations in the Experimental Radio Service is 2 years.

(b) A license will not be granted for a period longer than that which is required for completion of the experimental project. If such period is estimated to be less than 2 years, a statement to that effect by the applicant may facilitate a grant of the application. See also §5.58.

Federal Communications Commission

§5.67

(c) The expiration dates for licenses in the Experimental Radio Service will be distributed over the 12 calendar months, in accordance with the alphabetical distribution of the names of licensees. Hence, an initial license may be granted for a basic period of 1½ to 2½ years, depending on the date of grant and the alphabetical position of the name of the licensee.

[32 FR 1129, Feb. 1, 1967, as amended at 48 FR 52737, Nov. 22, 1983]

§5.64 Change in equipment.

(a) A change may be made in a licensed transmitter without specific authorization from the Commission provided: (1) The change does not result in operation inconsistent with any term of the outstanding authorization for the station involved; and (2) a description of the change is incorporated in the next application for renewal or modification of license.

(b) Prior authorization from the Commission is required before the following antenna changes may be made at a station at a fixed location:

(1) Any change which will either increase the height of a structure supporting the radiating portion of the antenna or decrease the height of a lighted antenna structure.

(2) Any change in the location of an antenna when such relocation involves a change in the geographic coordinates of latitude or longitude by as much as one second, or when such relocation involves a change in street address.

§5.65 Operation at a temporary location.

(a) An application for authority to operate at temporary locations shall specify the general geographical area within which the operation will be confined.

(b) When a station is authorized to operate at temporary locations, the following notification procedure shall be followed:

(1) When the station is placed in operation for the first time, the Engineer in Charge of the Radio District(s) involved shall be notified.

(2) When the station is moved from one location to another, the Engineer in Charge of the Radio District(s) involved shall be notified.

§5.66 Discontinuance of station operation.

In case of a permanent discontinuance of operation of a fixed or land station in the Experimental Radio Service, or in case of permanent discontinuance of operation of all transmitter units listed in the license for a mobile station in the Experimental Radio Service, the licensee shall forward the station license to the Washington, D.C., office of the Commission for cancellation. A copy of the request for cancellation of the license shall be forwarded to the Commission's Engineer in Charge of the radio district in which the station is located.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.67 Policy governing the assignment of frequencies.

(a) Each frequency or band of frequencies, available for assignment to stations in the Experimental Radio Service is available on a shared basis only, and will not be assigned for the exclusive use of any one applicant, and such use may also be restricted to one or more specified geographical areas. Normally not more than one frequency in a band of frequencies will be assigned for the use of a single applicant unless a showing is made demonstrating that need for the assignment of additional frequencies is essential to the proposed program of experimentation.

(b) Frequency assignments will be made only on the condition that harmful interference will not be caused to any station operating in accordance with the Table of Frequency Allocation of part 2 of this chapter.

(c) The frequencies available for use in the Experimental Radio Service are set forth in §5.203.

(d) Protection for Federal Communications Commission monitoring stations:

(1) Applicants in the vicinity of an FCC monitoring station for a radio station authorization to operate new transmitting facilities or changed transmitting facilities which would increase the field strength produced over the monitoring station over that previously authorized are advised to give consideration, prior to filing applications, to the possible need to protect

the FCC stations from harmful interference. Geographical coordinates of the facilities which require protection are listed in §0.121(c) of the Commission's Rules. Applications for stations (except mobile stations) which will produce on any frequency a direct wave fundamental field strength of *greater than 10 mV/m* in the authorized bandwidth of service (-65.8 dBW/m^2 power flux density assuming a free space characteristic impedance of 120 ohms) at the referenced coordinates, may be examined to determine extent of possible interference. Depending on the theoretical field strength value and existing root-sum-square or other ambient radio field signal levels at the indicated coordinates, a clause protecting the monitoring station may be added to the station authorization.

(2) In the event that calculated value of expected field exceeds 10 mV/m (-65.8 dBW/m^2) at the reference coordinates, or if there is any question whether field strength levels might exceed the threshold value, advance consultation with the FCC to discuss any protection necessary should be considered. Prospective applicants may communicate with: Chief, Compliance and Information Bureau, Federal Communications Commission, Washington, D.C. 20554, Telephone (202) 632-6980.

(3) Advance consultation is suggested particularly for those applicants who have no reliable data which indicates whether the field strength or power flux density figure indicated would be exceeded by their proposed radio facilities (except mobile stations). In such instances, the following is a suggested guide for determining whether an applicant should coordinate:

(i) All stations within 2.4 kilometers (1.5 statute miles);

(ii) Stations within 4.8 kilometers (3 statute miles) with 50 watts or more average effective radiated power (ERP) in the primary plane of polarization in the azimuthal direction of the Monitoring Stations.

(iii) Stations within 16 kilometers (10 statute miles) with 1 kW or more average ERP in the primary plane of polarization in the azimuthal direction of the Monitoring Station;

(iv) Stations within 80 kilometers (50 statute miles) with 25 kW or more av-

erage ERP in the primary plane of polarization in the azimuthal direction of the Monitoring Station;

(4) Advance coordination for stations operating above 1000 MHz is recommended only where the proposed station is in the vicinity of a monitoring station designated as a satellite monitoring facility in §0.121(c) of the Commission's Rules and also meets the criteria outlined in paragraphs (d) (2) and (3) of this section.

(5) The Commission will not screen applications to determine whether advance consultation has taken place. However, applicants are advised that such consultation can avoid objections from the Federal Communications Commission or modification of any authorization which will cause harmful interference.

[28 FR 12506, Nov. 22, 1963, as amended at 44 FR 77176, Dec. 31, 1979; 48 FR 52737, Nov. 22, 1983; 61 FR 8477, Mar. 5, 1996]

§5.68 Cancellation provisions.

The applicant for a station in the Experimental Radio Services accepts the license with the express understanding: (a) That the authority to use the frequency or frequencies assigned is granted upon an experimental basis only and does not confer any right to conduct an activity of a continuing nature; and (b) that said grant is subject to change or cancellation by the Commission at any time without hearing if in its discretion the need for such action arises.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.69 Notification to the National Radio Astronomy Observatory.

In order to minimize possible harmful interference at the National Radio Astronomy Observatory site located at Green Bank, Pocahontas County, West Virginia, and at the Naval Radio Research Observatory site at Sugar Grove, Pendleton County, West Virginia, any applicant for a station authorization other than mobile, temporary base, temporary fixed, Personal Radio, Civil Air Patrol, or Amateur seeking a station license for a new station, a construction permit to construct a new station or to modify an existing station license in a manner

Federal Communications Commission

§ 5.108

which would change either the frequency, power, antenna height or directivity, or location of such a station within the area bounded by 39°15' N on the north, 78°30' W on the east, 37°30' N on the south and 80°30' W on the west shall, at the time of filing such application with the Commission, simultaneously notify the Director, National Radio Astronomy Observatory, P.O. Box #2, Green Bank, West Virginia, 24944, in writing, of the technical particulars of the proposed station. Such notification shall include the geographical coordinates of the antenna, antenna height, antenna directivity if any, proposed frequency, type of emission, and power. In addition, the applicant shall indicate in his application to the Commission the date notification was made to the Observatory. After receipt of such applications, the Commission will allow a period of twenty (20) days for comments or objections in response to the notifications indicated. If an objection to the proposed operation is received during the twenty-day period from the National Radio Astronomy Observatory for itself or on behalf of the Naval Radio Research Observatory, the Commission will consider all aspects of the problem and take whatever action is deemed appropriate.

[42 FR 8329, Feb. 9, 1977]

Subpart C—Technical Standards

§ 5.101 Frequency stability.

If an applicant proposes to use a frequency tolerance greater than the tolerance set forth in the rules governing the service to which the frequencies are assigned in the Table of Frequency Allocations of part 2 of this chapter, the frequency tolerance should be provided as part of the filing in the application for a station license.

[48 FR 52738, Nov. 22, 1983]

§ 5.102 Types of emission.

(a) Stations in the Experimental Radio Service may be authorized to use any of the classifications of emissions covered in part 2 of this chapter.

(b) [Reserved]

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§ 5.103 Authorized bandwidth.

Each authorization issued to a station operating in this service will show, as the prefix to the emission classification, a figure specifying the maximum necessary bandwidth in kilohertz for the emission used. The authorized bandwidth is considered to be the occupied or necessary bandwidth whichever is greater. This bandwidth should be determined in accordance with § 2.202 of part 2 of this chapter.

[48 FR 52738, Nov. 22, 1983]

§§ 5.104–5.105 [Reserved]

§ 5.106 Transmitter control requirements.

Each licensee shall be responsible for maintaining control of the transmitter authorized under its station authorization. This includes both ensuring that transmissions are in conformance with the operating characteristics prescribed in the station authorization and that the station is operated only by persons duly authorized by the licensee.

[48 FR 52738, Nov. 22, 1983]

§ 5.107 [Reserved]

§ 5.108 Wildlife tracking and ocean buoy tracking operations.

Except as provided in §§ 5.101, 5.102, 5.103 and 5.106, the use of frequencies in the bands 40.66–40.70 MHz and 216–220 MHz for the tracking of and telemetry of scientific data from ocean buoys and animal wildlife are subject to the following conditions:

(a) All transmitters used at stations first licensed after February 18, 1975, shall comply with the technical requirements in paragraph (b) of this section and shall be type accepted as provided in § 5.109.

(b) Technical requirements for transmitters used for these operations are as follows:

(1) In the 40.66–40.70 MHz frequency band, the bandwidth required for frequency tolerance plus the occupied bandwidth of any emissions must be adjusted so as to be confined within this band, except as permitted by paragraph (b)(6) of this section.

§5.109

(2) In the 216–220 MHz frequency band, the carrier frequency shall be maintained within 0.005 percent of the assigned frequency.

(3) Classes of emission will be limited to A0, A1, A2, F1, F2 and/or F9.

(4) Occupied bandwidth shall not exceed 1 kHz.

(5) The maximum carrier power shall not exceed 1 milliwatt for airborne wildlife applications, 10 milliwatts for terrestrial wildlife applications and 100 milliwatts for ocean buoys.

(6) The mean power of emissions shall be attenuated below the mean output power of the transmitter in accordance with the schedule shown in §5.103(b) of this subpart.

[40 FR 2814, Jan. 16, 1975; 40 FR 6474, Feb. 12, 1975; 48 FR 52738, Nov. 22, 1983]

§5.109 Acceptability of transmitters for licensing.

All transmitters used at stations licensed for wildlife and ocean buoy tracking and telemetering operations pursuant to §5.108 shall be type accepted or notified pursuant to subpart J of part 2 of this chapter. After March 5, 1984, only grants of notification will be issued for equipment authorized for use in this service.

(Secs. 4(i), 302, 303(e) 303(f) and 303(r) of the Communications Act of 1934, as amended)

[49 FR 3996, Feb. 1, 1984]

Subpart D—Operating Requirements

§5.151 General limitations on use.

(a) The following transmission limitations are applicable to all classes of stations in the Experimental Radio Service:

(1) Stations may make only such transmissions as are necessary and directly related to the conduct of the licensee's stated program of experimentation as specified in this application for construction permit and license and the related station instrument of authorization, and as governed by the provisions of the rules and regulations contained in this part. All transmissions shall be limited to the minimum practical transmission time.

(2) When transmitting, the licensee must use every precaution to insure

47 CFR Ch. I (10–1–97 Edition)

that the radio frequency energy emitted will not cause harmful interference to the services carried on by stations operating in accordance with the Table of Frequency Allocations of part 2 of this chapter and, further, that the power radiated is reduced to the lowest practical value consistent with the program of experimentation for which the station authorization is granted. If harmful interference to an established radio service develops, the licensee shall cease transmissions and such transmissions shall not be resumed until it is certain that harmful interference will not be caused.

(b) If experimental stations are to be used to retransmit signals of any other station or to transmit programs intended for public reception or render any communications service, a full disclosure of this must be made in the application for license.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52738, Nov. 22, 1983]

§5.152 Station identification.

Each class of station in the experimental services shall, unless specifically exempted by the terms of the station authorization, transmit its assigned call sign at the end of each complete transmission: *Provided, however*, That the transmission of the call sign at the end of each transmission is not required for projects requiring continuous, frequent, or extended use of the transmitting apparatus, if, during such periods and in connection with such use, the call sign is transmitted at least once every thirty minutes.

§5.153 Suspension of transmission required.

The radiations of the transmitter shall be suspended immediately upon detection or notification of a deviation from the technical requirements of the station authorization until such deviation is corrected, except for transmissions concerning the immediate safety of life or property, in which case the transmissions shall be suspended as soon as the emergency is terminated.

Federal Communications Commission

§5.160

§5.154 [Reserved]

§5.155 Operator requirements.

(a) The licensee shall ensure that all transmitter adjustments which affect the proper operation of a station shall be made by a person qualified to perform such adjustments.

(b) The licensee shall be responsible for ensuring that the person operating the transmitter is qualified to operate said station.

(c) When transmitting radio-telegraphy by any type of Morse Code, the operator shall have proved his ability to transmit by hand and receive by ear texts in Morse Code signals.

(d) The provisions of this section shall not be construed to change or diminish in any respect the responsibility of station licensees to have and to maintain control over the stations licensed to them, or for proper functioning and operation of those stations in accordance with the terms of the licenses of those stations.

[48 FR 52738, Nov. 22, 1983]

§5.156 [Reserved]

§5.157 Posting station licenses.

(a) The current original authorization for each station shall be retained as a permanent part of the station records but need not be posted.

(b) A clearly legible copy of the authorization for each station at a fixed location shall be posted at every control point of the station.

[44 FR 29071, May 18, 1979]

§5.158 Authorized points of communication.

Stations in the Experimental Radio Service may communicate only with other stations licensed in the Experimental Radio Service: *Provided, however,* That upon a satisfactory showing that the proposed communications are essential to the conduct of the research project, authority may be granted to communicate with stations in other services and U.S. Government stations.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.159 Operation during an emergency.

(a) The licensee of any station in the Experimental Radio Service may, during a period of emergency in which the normal communication facilities are disrupted as a result of hurricane, flood, earthquake, or similar disaster, utilize such station for emergency communication service, subject to other provisions of this section, by communicating in a manner other than that specified in the station license.

(b) As soon as possible after the beginning of such emergency use, notice shall be sent to the Commission at Washington, DC, and to the Engineer in Charge of the district in which the station is located, stating the nature of the emergency and the use to which the station is being put.

(c) The emergency use of the station shall be discontinued as soon as substantially normal communication facilities are again available.

(d) The Commission at Washington, DC, and the Engineer in Charge shall be notified immediately when such special use of the station is terminated.

(e) In no event shall any station engage in emergency transmission on frequencies other than, or with power in excess of, that specified in the instrument of authorization or as otherwise expressly provided by the Commission, or by law.

(f) The Commission may, at any time, order the discontinuance of any such emergency communication undertaken under this section.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.160 Inspection of stations.

All stations and records of stations in the Experimental Radio Service shall be made available for inspection at any time while the station is in operation or shall be made available for inspection upon reasonable request of an authorized representative of the Commission.

[28 FR 12506, Nov. 22, 1963, as amended at 48 FR 52737, Nov. 22, 1983]

§5.161

§5.161 Inspection and maintenance of tower marking and lighting and associated control equipment.

The licensee of any radio station which has an antenna structure required to be painted and illuminated pursuant to the provisions of section 303(q) of the Communications Act of 1934, as amended, and part 17 of this chapter, shall perform the inspections and maintain the tower marking and lighting, and associated control equipment, in accordance with the requirements of §§17.43 through 17.57 of this chapter.

[34 FR 3802, Mar. 5, 1969]

§5.162 Notice of violation.

(a) Any licensee who appears to have violated any provision of the Communications Act or any provision of this chapter, shall be served with a written notice calling the facts to his attention and requesting a statement concerning the matter.

(b) Within 10 days from receipt of notice or such other period as may be specified, the licensee shall send a written answer, in duplicate, direct to the office of the Commission originating the official notice. If an answer cannot be sent nor an acknowledgment made within such 10-day period by reason of illness or other unavoidable circumstances, acknowledgment and answer shall be made at the earliest practicable date with a satisfactory explanation of the delay.

(c) The answer to each notice shall be complete in itself and shall not be abbreviated by reference to other communications or answers to other notices. If the notice relates to violations that may be due to the physical or electrical characteristics of transmitting apparatus, the answer shall state fully what steps, if any, have been taken to prevent future violations, and, if any new apparatus is to be installed, the date such apparatus was ordered, the name of the manufacturer, and the promised date of delivery. If the installation of such apparatus requires a construction permit, the file number of the application shall be given, or if a file number has not been assigned by the Commission, such identification shall be given as will permit

47 CFR Ch. I (10–1–97 Edition)

ready identification of the application. If the notice of violation relates to lack of attention to or improper operation of the transmitter, the name and license number of the operator in charge shall be given.

§5.163 Content of station records.

(a) The licensee of each station in the Experimental Radio Service shall maintain adequate records of the station's operations, including:

(1) Dates and hours of operation.

(2) All measurements of the frequency(ies), including the name of the person making the measurements, the exact frequency measured or the observed deviations from the assigned frequency(ies) expressed in Hertz, kilohertz or percent plus or minus, and a statement of any corrective action taken.

(3) Power.

(4) Types of emission.

(5) Chronological record of experimentation conducted.

(6) The name of the operator on duty.

(b) For all stations, when service or maintenance duties are performed which may affect their proper operation, the responsible operator shall sign and date an entry in the station record concerned, giving:

(1) Pertinent details of all duties performed by the operator or under the operator's supervision; and

(2) The operator's name and address.

(c) For stations whose antenna structure is required to be illuminated, a record in accordance with the requirements of §17.49 of this chapter.

[28 FR 12506, Nov. 22, 1963, as amended at 34 FR 3802, Mar. 5, 1969; 35 FR 5618, Apr. 7, 1970; 48 FR 52737 and 52738, Nov. 22, 1983]

§5.164 Form of station records.

(a) The records shall be kept in an orderly manner, in suitable form, and in such detail that the data required are readily available. Key letters or abbreviations may be used if proper meaning or explanation is set forth in the record.

(b) Each entry in the record shall be signed by a person having actual knowledge of the facts to be recorded.

(c) No record or portion thereof shall be erased, obliterated, or willfully destroyed within the required retention

Federal Communications Commission

§5.203

period. Any necessary correction may be made only by the persons originating the entry, who shall strike out the erroneous portion, initial the correction made, and indicate the date of correction.

(d) A copy of this part shall be maintained in the records of each fixed or land station licensed under this part.

§5.165 Retention of station records.

Records required to be kept by this part shall be retained by the licensee for a period of at least one year.

§5.166 Adherence to program of research.

(a) The program of experimentation as stated by an applicant in its application for construction permit or license or in the station instrument of authorization, shall be substantially adhered to unless the licensee is authorized to do otherwise by the Commission.

(b) Where some phases of the experimental program are not covered by the general rules of the Commission or by the rules of this part, the Commission may specify supplemental or additional requirements or conditions in each case as deemed necessary in the public interest, convenience, or necessity.

Subpart E—Experimental Authorizations

SOURCE: 48 FR 52738, Nov. 22, 1983, unless otherwise noted.

§5.201 Eligibility of license.

(a) Authorizations for stations in the Experimental Radio Service will be issued only to persons qualified to conduct experimentations utilizing hertzian waves for scientific or technical operation data directly related to a use of radio not provided by existing rules; for communications in connection with research projects when existing communication facilities are inadequate.

(b) Applicants eligible for authorizations in an established service, and seeking to develop operational data or techniques directed toward the improvement or extension of that service shall file applications and conduct such projects under the developmental rules of the established service.

§5.202 Scope of service.

Stations operating in the Experimental Radio Service will be permitted to conduct the following type of operations:

(a) Experimentations in scientific or technical radio research.

(b) Experimentations under contractual agreement with the United States Government, or for export purposes.

(c) Communications essential to a research project.

(d) Technical demonstrations of equipment or techniques.

(e) Field strength surveys by persons not eligible for authorization in any other service.

(f) Demonstration of equipment to prospective purchasers for proposed stations in existing services by persons engaged in the business of selling radio equipment.

(g) Testing of equipment in connection with production or type approval of such equipment.

(h) Development of radio technique, equipment or engineering data not relating to an existing or proposed service, including field or factory testing or calibration of equipment.

(i) Development of radio technique, equipment, operational data or engineering data related to an existing or proposed radio service.

(j) Limited market studies.

(k) Other types of experiments that are not specifically covered under paragraphs (a) through (j) of this section will be considered.

§5.203 Frequencies for the Experimental Radio Service.

Stations operating in the Experimental Radio Service may be authorized to use any government or non-government frequency designated in the Table of Frequency Allocations set forth in part 2 of this chapter as available for assignment to this service. Provided that the need for the specific frequency(ies) requested is fully justified by the applicant.¹

¹Notwithstanding the broad frequency provision for this Service, applicants desiring authorization for the purpose of wildlife or ocean buoy telemetering and/or tracking

Continued

§ 5.204

§ 5.204 Experimental report.

(a) Unless specifically stated as a condition of the authorization, licensees are not required to file a report on the results of the experimental program carried on under this subpart.

(b) The Commission may, as a condition of authorization, request the licensee to forward periodic reports in order to evaluate the progress of the experimental program.

(c) An applicant may request that the commission withhold from the public certain reports and associated material and the Commission will withhold the same unless the public interest requires otherwise.

§ 5.205 Frequencies for field strength surveys or equipment demonstrations.

(a) Authorizations issued under § 5.202 (e) and (f) will normally not have specific frequencies designated in a station license. Prior to the commencement of a survey or demonstration, the licensee will request a specific frequency assignment and submit the following information:

- (1) Time, date and duration of survey.
- (2) Frequency to be used.
- (3) Location of transmitter and geographical area to be covered.
- (4) Purpose of survey.
- (5) Method and equipment to be used.
- (6) Names and addresses of persons for whom the survey is conducted.

(b) Upon receipt of authority from the Commission to conduct a particular survey, the licensee shall furnish the Engineer-in-Charge of the radio district in which the survey is to be conducted, sufficiently in advance to assure receipt before commencement thereof, the following information: Time, date, duration, frequency, location of transmitter, area to be covered, and purpose of survey.

should, to the extent practicable, use frequencies in the bands 40.66–40.70 MHz or 216–220 MHz, in accordance with footnote US210 to the Table of Frequency Allocations, § 2.106 of this chapter. Transmitters to be used in these bands for this purpose shall comply with the requirements set forth in § 5.108 of this part.

47 CFR Ch. I (10–1–97 Edition)

§ 5.206 Limited market studies.

Unless otherwise stated in the instrument of authorization, licenses granted for the purpose of limited market studies pursuant to § 5.202(j) are subject to the following conditions:

(a) All transmitting and/or receiving equipment used in the study shall be owned by the licensee.

(b) The licensee is responsible for informing anyone participating in the experiment that the service or device is granted under an experimental authorization and is strictly temporary.

(c) The size and scope of the market study may be subject to limitations on a case-by-case basis as the Commission shall determine.

Subparts F–G [Reserved]

Subpart H—Student Authorizations

§ 5.401 Eligibility for license.

The Commission may issue an authorization under this subpart to students for the purpose of presenting experiments or technical demonstrations for school or school approved projects which require the use of radio for a limited period of time. Such authorizations may, in the discretion of the Commission, be granted to students of seventh grade or higher level.

§ 5.402 Filing of applications.

(a) Notwithstanding the requirements in subpart B of this part, an application for a student authorization may be filed in letter form, in duplicate, with the original signed. The application shall contain the information set forth in paragraph (b) of this section.

(b) The application shall contain the following information:

- (1) Name and address of applicant.
- (2) A statement that the applicant is a citizen of the United States.
- (3) Applicant's school and grade.
- (4) A detailed description in narrative form of the project including the type and purpose of operation.
- (5) Place of operation—street address, name of building, or other specific location.
- (6) Date(s) of operation including the exact hours, when known, as well as

Federal Communications Commission

§ 5.410

the duration of each period of operation.

(7) Equipment to be used. If manufactured, list name of manufacturer and type number. For other equipment, describe in detail and furnish a circuit diagram.

(8) Frequency(ies) desired and range of frequencies which could be employed.

(9) The method by which the frequency of operation will be determined.

(10) Frequency tolerance.

(11) The means by which this tolerance will be maintained.

(12) DC plate power input to final radio frequency stage. If not known, indicate any known power rating of equipment and state whether this is power output of transmitter or radiated power, and whether average or peak.

(13) Type of emission including a description of the modulation that will be applied, if modulated.

(14) Description of the antenna to be used, including height above ground.

(c) The application shall be accompanied by a signed statement from the principal of the school, or a member of its faculty, on appropriate letterhead, stating that the project has the approval of the school and indicating the person under whose general supervision the project will be conducted.

§ 5.403 Waiver of construction permit.

Subject to the requirements of §§ 5.401 and 5.402, the provisions contained in section 319(d) of the Communications Act are waived insofar as such provisions require the issuance of a construction permit prior to the issuance of the student authorization provided for in this subpart.

§ 5.404 [Reserved]

§ 5.405 Power limitation.

No authorization under this subpart will be issued unless the description of the project shows that the dc plate power input to the final radio frequency stage does not exceed 5 watts: *Provided, however*, That a greater power may be authorized if a satisfactory showing is made that such greater power is necessary and that appro-

priate measures will be taken to prevent interference.

§ 5.406 Frequencies.

(a) Frequencies in the following bands are available for assignment in authorizations issued under this subpart:

27.23–27.28 MHz.

460–461 MHz.

462.525–467.475 MHz.

2450–2500 MHz.

(b) In each case, the carrier frequency must be far enough inside the band so as to keep the sideband energy within the band limits specified.

[28 FR 12506, Nov. 22, 1963, as amended at 35 FR 5618, Apr. 7, 1970]

§ 5.407 Measurements required.

The frequency of operation must be measured or checked prior to each time of operation.

§ 5.408 Waiver of technical and operating requirements.

Subject to the provisions of §§ 5.405, 5.406, and 5.407, the provisions in subparts C and D of this part are waived insofar as such provisions require a station authorized under this subpart to observe the technical and operating requirements set forth therein.

§ 5.409 Noninterference condition.

Each authorization issued to a student under this subpart is subject to the condition that no harmful interference, as defined in § 5.3(h), is caused to any authorized station.

[38 FR 12744, May 15, 1973]

§ 5.410 Record of operation.

(a) The licensee holding an authorization issued under this subpart shall maintain a record of operation containing the following information:

(1) The date and time of each period of operation.

(2) The frequency of operation as measured or checked at the beginning of each period of operation.

(3) A brief description of the experimentation being conducted.

(b) Each entry shall be signed by the person operating the equipment.

§5.411

(c) These records shall be retained for one month after the termination of the authorization.

§5.411 Notification.

(a) The holder of an authorization issued under this subpart shall notify the Engineer in Charge of the district in which the station will be operated in advance of each scheduled operation.

(b) The notice to the Engineer in Charge shall be in writing and shall contain the following information:

- (1) Place of operation.
- (2) Date(s) of operation, including exact time if known.
- (3) Frequency(ies) to be used.
- (4) Call letters of station.

PART 11—EMERGENCY ALERT SYSTEM (EAS)

Subpart A—General

Sec.

- 11.1 Purpose.
- 11.11 The Emergency Alert System (EAS).
- 11.12 Two-tone Attention Signal encoder and decoder.
- 11.13 Emergency Action Notification (EAN) and Emergency Action Termination (EAT).
- 11.14 EAN Network and Primary Entry Point (PEP) System.
- 11.15 EAS Operating Handbook.
- 11.16 National Control Point Procedures.
- 11.17 Authenticator Word Lists.
- 11.18 EAS Designations.
- 11.19 EAS Non-participating National Authorization Letter.
- 11.20 State Relay Network.
- 11.21 State and Local Area Plans and FCC Mapbook.

Subpart B—Equipment Requirements

- 11.31 EAS protocol.
- 11.32 EAS Encoder.
- 11.33 EAS Decoder.
- 11.34 Acceptability of the equipment.
- 11.35 Equipment operational readiness.

Subpart C—Organization

- 11.41 Participation in EAS.
- 11.42 Participation by communications common carriers.
- 11.43 National level participation.
- 11.44 EAS message priorities.
- 11.45 Prohibition of false or deceptive EAS transmissions.
- 11.46 EAS public service announcements.
- 11.47 Optional use of other communications methods and systems.

47 CFR Ch. I (10–1–97 Edition)

Subpart D—Emergency Operations

- 11.51 EAS code and Attention Signal Transmission requirements.
- 11.52 EAS code and Attention Signal Monitoring requirements.
- 11.53 Dissemination of Emergency Action Notification.
- 11.54 EAS operation during a National Level emergency.
- 11.55 EAS operation during a State or Local Area emergency.

Subpart E—Tests

- 11.61 Tests of EAS procedures.
- 11.62 Closed Circuit Tests of National Level EAS facilities.

AUTHORITY: 47 U.S.C. 151, 154 (i) and (o), 303(r), 544(g) and 606.

SOURCE: 59 FR 67092, Dec. 28, 1994, unless otherwise noted.

Subpart A—General

§11.1 Purpose.

This part contains rules and regulations providing for an Emergency Alert System (EAS). The EAS provides the President with the capability to provide immediate communications and information to the general public at the National, State and Local Area levels during periods of national emergency. The rules in this part describe the required technical standards and operational procedures of the EAS for AM, FM and TV broadcast stations, cable systems and other participating entities. The EAS may be used to provide the heads of State and local government, or their designated representatives, with a means of emergency communication with the public in their State or Local Area.

§11.11 The Emergency Alert System (EAS).

(a) The EAS is composed of broadcast networks; cable networks and program suppliers; AM, FM and TV broadcast stations; Low Power TV (LPTV) stations; cable systems; and other entities and industries operating on an organized basis during emergencies at the National, State, or local levels. It requires that at a minimum all participants use a common EAS protocol, as defined in §11.31, to send and receive emergency alerts in accordance with

Federal Communications Commission

§ 11.11

the effective dates in the following tables:

TIMETABLE—BROADCAST STATIONS

Requirement	Until 7/1/95	7/1/95	1/1/97	1/1/98
Two-tone/encoder timing.	20–25 seconds	8–25 seconds	8–25 seconds	8–25 seconds. ¹
Two-tone decode timing	8–16 seconds required 3–4 seconds optional ..	All decoders at 3–4 seconds. Use is optional	3–4 seconds	Two-tone decoder no longer used. Use is required.
Digital decoder and encoder.	Use is optional	Use is optional	Use is required	Use is required.

CABLE SYSTEMS

Requirement	Until 7/1/97	7/1/97 ²
Two-tone signal from storage device. ¹ ...	Use is optional, 8–25 seconds	Use is required, 8–25 seconds.
Digital decoder and encoder	Use is optional	Use is required. ²

¹ Two-tone signal used only to provide audio alert to audience before EAS emergency messages and required monthly test.
² On this date, subject cable systems shall provide: (1) a video message on all channels or other alerting techniques to hearing impaired and deaf subscribers, (2) an audio message and video interruption on all channels, and (3) a video message on at least one channel to all subscribers.

NOTE: Class D FM and low power TV stations are not required to have two-tone or digital encoders. LPTV stations that operate as television broadcast translator stations are exempt from the requirement to have EAS equipment. FM translator stations are exempt from the requirement to have EAS equipment.

EAS TIMETABLE AND REQUIREMENTS BROADCAST STATIONS

Requirement	AM	FM	FM Class D	TV	LPTV ¹
Two-tone decoder (until 1/1/98)	Y	Y	Y	Y	Y
Two-tone encoder	Y	Y	N	Y	N
Digital decoder (1/1/97)	Y	Y	Y	Y	Y
Digital encoder (1/1/97)	Y	Y	N	Y	N
Audio message (1/1/97)		Y	Y	Y	YY
Video message (1/1/97)					YY

CABLE SYSTEMS

Requirement	
Two-tone decoder	N
Two-tone encoder	N
Digital decoder (7/1/97)	Y
Digital encoder (7/1/97)	Y
Audio message on all channels (7/1/97)	Y ²
Video interruption on all channels, video message on one channel (7/1/97)	Y ³

¹ LPTV stations that operate as television broadcast translator stations are exempt from the requirement to have EAS equipment.

² Shall transmit two-tone signal, but it may be from a storage device.

³ Shall provide video on all channels or other alerting techniques to certified hearing impaired and deaf subscribers.

(b) Class D non-commercial educational FM stations as defined in § 73.506 of this chapter and LPTV stations as defined in § 74.701(f) of this chapter are not required to have or operate EAS encoders as defined in § 11.32. LPTV stations that operate as television broadcast translator stations, as defined in § 74.701(b) of this chapter are not required to comply with the requirements of this part. FM broadcast booster stations as defined in § 74.1201(f) of this chapter and FM translator sta-

tions as defined in § 74.1201(a) of this chapter which entirely rebroadcast the programming of other local FM broadcast stations are not required to comply with the requirements of this part.

(c) Organizations using other communications systems or technologies such as, Direct Broadcast Satellite (DBS), low earth orbit satellite systems, paging, computer networks, etc. may join the EAS on a voluntary basis by contacting the FCC. Organizations that choose to voluntarily participate must

§ 11.12

comply with the requirements of this part.

NOTE: Compliance by Cable Systems with the July 1, 1997 date specified in this section is extended until a date to be specified by the Commission and published in the FEDERAL REGISTER.

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 55998, Nov. 6, 1995; 62 FR 33753, June 23, 1997]

§ 11.12 Two-tone Attention Signal encoder and decoder.

Existing two-tone Attention Signal encoder and decoder equipment type accepted for use as Emergency Broadcast System equipment under part 73 of this chapter may be used by broadcast stations until January 1, 1998, provided that such equipment meets the requirements of § 11.32(a)(9) and 11.33(b). Effective January 1, 1998, the two-tone Attention Signal decoder will no longer be required and the two-tone Attention Signal will be used to provide an audio alert.

[60 FR 55999, Nov. 6, 1995]

§ 11.13 Emergency Action Notification (EAN) and Emergency Action Termination (EAT).

(a) The Emergency Action Notification (EAN) is the notice to all broadcast stations, subject cable systems, other regulated services of the FCC, participating industry entities, and to the general public that the EAS has been activated for a national emergency.

(b) The Emergency Action Termination (EAT) is the notice to all broadcast stations, subject cable systems, other regulated services of the FCC, participating industry entities, and to the general public that the EAN has terminated.

§ 11.14 EAN Network and Primary Entry Point (PEP) System.

(a) The EAN network is a dedicated communications service connecting industry networks, wire services and common carriers with government activation points. It is used to distribute EAN and EAT messages. The industry control locations retransmit the EAN message, the Presidential message, and the EAT message on their facilities to their affiliates.

(b) The PEP system is a nationwide network of broadcast stations connected with government activation points. It can also be used to distribute EAN and EAT.

§ 11.15 EAS Operating Handbook.

The EAS Operating Handbook states in summary form the actions to be taken by personnel at broadcast stations, and other participating entities upon receipt of an EAN, subject cable systems and other participating entities upon receipt of an EAN, an EAT, tests, or State and Local Area alerts. It is issued by the FCC and contains instructions for the above situations, monitoring guidelines, and EAS message examples. A copy of the Handbook must be located at normal duty positions or EAS equipment locations when an operator is required to be on duty and be immediately available to staff responsible for authenticating messages and initiating actions.

§ 11.16 National Control Point Procedures.

The National Control Point Procedures are written instructions issued by the FCC to national level EAS control points. They are for use by the participating radio and television networks, cable networks and program suppliers, common carriers and wire services. The procedures are divided into sections as follows:

(a) National Level EAS Activation. This section contains the activation and termination instructions for Presidential messages.

(b) EAS Test Transmissions. This section contains the instructions for testing the EAS at the National level.

(c) National Information Center (NIC). This section contains instructions for distributing United States Government official information messages after completion of the National Level EAS activation and termination actions.

§ 11.17 Authenticator Word Lists.

There are three lists issued by the FCC annually. The lists are to be used by EAS participants to ensure that the National level alerts and tests are legitimate. The lists must be used in accordance with directions in the EAS

Federal Communications Commission

§ 11.20

Operating Handbook and the National Control Point Procedures. LPTV stations do not receive authenticator lists.

(a) Red Envelope Authenticator List. This list is used for authentication purposes in accordance with instructions in the EAS Operating Handbook and National Control Point Procedures. It is issued to all broadcast stations and specified control points of the radio and television networks, cable networks and program suppliers, common carriers, wire services and other specified entities. A current copy of this list must be located in the pocket on the inside front cover of the EAS Operating Handbook. This list should be opened only to authenticate receipt of an EAN message and an EAT message from the above control points. The FCC may request immediate return of the Red Envelope at any time.

(b) White Envelope Authenticator List. This list is used for caller identification purposes in accordance with instructions in the National Control Point Procedures. It is issued only to specified control points.

(c) NIC Authenticator List. This booklet is used for authentication purposes in accordance with instructions in the National Control Point Procedures. It is issued only to participating control points.

§ 11.18 EAS Designations.

(a) National Primary (NP) is a source of EAS Presidential messages.

(b) Local Primary (LP) is a source of EAS Local Area messages. An LP source is responsible for coordinating the carriage of common emergency messages from sources such as the National Weather Service or local emergency management offices as specified in its EAS Local Area Plan. If it is unable to carry out this function, other LP sources in the Local Area may be assigned the responsibility as indicated in State and Local Area Plans. LP sources are assigned numbers (LP-1, 2, 3, etc.) in the sequence they are to be monitored by other broadcast stations in the Local Area.

(c) State Primary (SP) is a source of EAS State messages. These messages can originate from the Governor or a designated representative in the State

Emergency Operating Center (EOC) or State Capital. Messages are sent via the State Relay Network.

(d) State Relay (SR) is a source of EAS State messages. It is part of the State Relay Network and relays National and State common emergency messages into Local Areas.

(e) Participating National (PN) sources transmit EAS National, State or Local Area messages. The EAS transmissions of PN sources are intended for direct public reception.

(f) Non-participating National (NN) sources have elected not to participate in the National level EAS and hold an authorization letter to that effect. Upon activation of the national level EAS, NN sources are required to broadcast the EAS codes, Attention Signal, the sign-off announcement in the EAS Operating Handbook and then stop operating. All NN sources are required to comply with § 11.51, 11.52 and 11.61. They may transmit EAS State or Local Area messages at any time without prior notice.

§ 11.19 EAS Non-participating National Authorization Letter.

This authorization letter is issued by the FCC to broadcast station licensees. It states that the licensee has agreed to go off the air during a national level EAS message. This authorization will remain in effect through the period of the initial license and subsequent renewals from the time of issuance unless returned by the holder or suspended, modified or withdrawn by the Commission.

§ 11.20 State Relay Network.

This network is composed of State Relay (SR) sources, leased common carrier communications facilities or any other available communication facilities. The network distributes State EAS messages originated by the Governor or designated official. In addition to EAS monitoring, satellites, microwave, FM subcarrier or any other communications technology may be used to distribute State emergency messages.

§ 11.21 State and Local Area Plans and FCC Mapbook.

EAS plans contain guidelines which must be followed by broadcast personnel, emergency officials and NWS personnel to activate the EAS. The plans include the EAS header code and messages that will be transmitted by key EAS sources (NP, LP, SP, and SR). State and local plans may contain unique methods of EAS message distribution such as the use of RBDS. The plans must be reviewed and approved by the Chief, Compliance and Information Bureau prior to implementation to ensure that they are consistent with national plans, FCC regulations, and EAS operation.

(a) The State plan contains procedures for State emergency management and other State officials, the NWS, broadcast personnel to transmit emergency information to the public during a State emergency using the EAS.

(b) The Local Area plan contains procedures for local officials or the NWS to transmit emergency information to the public during a local emergency using the EAS. Local plans may be a part of the State plan. A Local Area is a geographical area of contiguous communities or counties that may include more than one state.

(c) The FCC Mapbook is based on the above plans. It organizes all broadcast stations and cable systems according to their State, EAS Local Area and EAS designation.

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 55999, Nov. 6, 1995]

Subpart B—Equipment Requirements

§ 11.31 EAS protocol.

(a) The EAS uses a four part message for an emergency activation of the EAS. The four parts are: Preamble and EAS Header Codes; audio Attention Signal; message; and, Preamble and EAS End Of Message (EOM) Codes.

(1) The Preamble and EAS Codes must use Audio Frequency Shift Keying at a rate of 520.83 bits per second to transmit the codes. Mark frequency is 2083.3 Hz and space frequency is 1562.5 Hz. Mark and space time must be 1.92

milliseconds. Characters are ASCII seven bit characters as defined in ANSI X3.4–1977 ending with an eighth null bit (either 0 or 1) to constitute a full eight-bit byte.

(2) The Attention Signal must be made up of the fundamental frequencies of 853 and 960 Hz. The two tones must be transmitted simultaneously. The Attention Signal must be transmitted after the EAS header codes.

(3) The message may be audio, video or text.

(b) The ASCII dash and plus symbols are required and may not be used for any other purpose. Unused characters must be ASCII space characters. FM or TV call signs must use a backslash ASCII character number 47 (/) in lieu of a dash.

(c) The EAS protocol, including any codes, must not be amended, extended or abridged without FCC authorization. The EAS protocol and message format are specified in the following representation. Examples are also provided in the EAS Operating Handbook.

[PREAMBLE] ZCZC - ORG - EEE - PSSCCC
+ TTTT - JJJHHMM - LLLLLLLL -

(one second pause)

[PREAMBLE] ZCZC - ORG - EEE - PSSCCC
+ TTTT - JJJHHMM - LLLLLLLL -

(one second pause)

[PREAMBLE] ZCZC - ORG - EEE - PSSCCC
+ TTTT - JJJHHMM - LLLLLLLL -

(at least a one second pause)

(transmission of 8 to 25 seconds of Attention
Signal)

(transmission of audio, video or text mes-
sages)

(at least a one second pause)

[PREAMBLE] NNNN

(one second pause)

[PREAMBLE] NNNN

(one second pause)

[PREAMBLE] NNNN

(at least one second pause)

[PREAMBLE] This is a consecutive string of bits (sixteen bytes of AB hexadecimal [8 bit byte 10101011]) sent to clear the system, set AGC and set asynchronous decoder clocking cycles. The preamble must be transmitted before each header and End Of Message code.

ZCZC- This is the identifier, sent as ASCII characters ZCZC to indicate the start of ASCII code.

ORG- This is the Originator code and indicates who originally initiated the activation of the EAS. These codes are specified in paragraph (d) of this section.

Federal Communications Commission

§ 11.31

EEE- This is the Event code and indicates the nature of the EAS activation. The codes are specified in paragraph (e) of this section. The Event codes must be compatible with the codes used by the NWS Weather Radio Specific Area Message Encoder (WRSAME).

PSSCCC- This is the Location code and indicates the geographic area affected by the EAS alert. There may be 31 Location codes in an EAS alert. The Location code uses the Federal Information Processing System (FIPS) numbers as described by the U.S. Department of Commerce in National Institute of Standards and Technology publication 772. Each state is assigned an SS number as specified in paragraph (f) of this section. Each county is assigned a CCC number. A CCC number of 000 refers to an entire State or Territory. P defines county subdivisions as follows: 0 = all or an unspecified portion of a county, 1 = Northwest, 2 = North Central, 3 = Northeast, 4 = West Central, 5 = Central, 6 = East Central, 7 = Southwest, 8 = South Central, 9 = Southeast. Other numbers may be designated later for special applications. The use of county subdivisions will probably be rare and generally for oddly shaped or unusually large counties. Any subdivisions must be defined and agreed to by the local officials prior to use.

+TTTT- This indicates the valid time period of a message in 15 minute segments up to one hour and then in 30 minute segments beyond one hour; i.e., +0015, +0030, +0045, +0100, +0430 and +0600.

JJJHHMM- This is the day in Julian Calendar days (JJJ) of the year and the time in hours and minutes (HHMM) when the message was initially released by the originator using 24 hour Universal Coordinated Time (UTC).

LLLLLLLL- This is the call sign or other identification of the broadcast station, or NWS office transmitting or retransmitting the message. These codes will be automatically affixed to all outgoing messages by the EAS encoder.

NNNN- This is the End of Message (EOM) code sent as a string of four ASCII N characters.

(d) The only originator codes are:

Originator	ORG code
Broadcast station or cable system	EAS
Civil authorities	CIV
Emergency Action Notification Network	EAN
National Weather Service	WXR
Primary Entry Point System	PEP

(e) The following Event (EEE) codes are presently authorized:

Nature of activation	Event codes
National Codes:	
Emergency Action Notification (National only)	EAN
Emergency Action Termination (National only)	EAT
National Information Center	NIC
National Periodic Test	NPT
Required Monthly Test	RMT
Required Weekly Test	RWT
Local Codes:	
Administrative Message	ADR
Blizzard Warning	BZW
Civil Emergency Message	CEM
Evacuation Immediate	EVI
Flash Flood Statement	FFS
Flash Flood Warning	FFW
Flash Flood Watch	FFA
Flood Statement	FLS
Flood Warning	FLW
Flood Watch	FLA
High Wind Warning	HWV
High Wind Watch	HWA
Hurricane Statement	HLS
Hurricane Warning	HUW
Hurricane Watch	HUA
Practice/Demo Warning	DMO
Severe Thunderstorm Warning	SVR
Severe Thunderstorm Watch	SVA
Severe Weather Statement	SVS
Special Weather Statement	SPS
Tornado Warning	TOR
Tornado Watch	TOA
Tsunami Warning	TSW
Tsunami Watch	TSA
Winter Storm Warning	WSW
Winter Storm Watch	WSA

(f) The State and Territory FIPS number codes (SS) are as follows. County FIPS numbers (CCC) are contained in the State EAS Mapbook.

State	FIPS #
AL	01
AK	02
AZ	04
AR	05
CA	06
CO	08
CT	09
DE	10
FL	12
GA	13
HI	15
ID	16
IL	17
IN	18
IA	19
KS	20
KY	21
LA	22
ME	23
MD	24
MA	25
MI	26
MN	27
MS	28
MO	29
MT	30
NE	31
NV	32
NH	33
NJ	34

§ 11.32

47 CFR Ch. I (10–1–97 Edition)

State	FIPS #
NM	35
NY	36
NC	37
ND	38
OH	39
OK	40
OR	41
PA	42
RI	44
SC	45
SD	46
TN	47
TX	48
UT	49
VT	50
VA	51
WA	53
WV	54
WI	55
WY	56

District of Columbia—11

Terr.	FIPS #
AS	60
PR	72
FM	64
PW	70
GU	66
UM	74
MH	68
VI	78
MP	69

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 55999, Nov. 6, 1995; 61 FR 54952, Oct. 23, 1996]

§ 11.32 EAS Encoder.

(a) EAS Encoders must at a minimum be capable of encoding the EAS protocol described in § 11.31 and providing the EAS code transmission requirements described in § 11.51. EAS encoders must additionally provide the following minimum specifications:

(1) *Encoder programming.* Access to encoder programming shall be protected by a lock or other security measures and be configured so that authorized personnel can readily select and program the EAS Encoder with Originator, Event and Location codes for either manual or automatic operation.

(2) *Inputs.* The encoder shall have two inputs, one for audio messages and one for data messages (RS–232C with standard protocol and 1200 baud rate).

(3) *Outputs.* The encoder shall have two outputs, one audio port and one data port (RS–232C with standard protocol and 1200 baud rate).

(4) *Calibration.* EAS Encoders must provide a means to comply with the modulation levels required in § 11.51(f).

(5) *Day-Hour-Minute and Identification Stamps.* The encoder shall affix the JJJHHMM and LLLLLLLL codes automatically to all initial messages.

(6) *Program Data Retention.* Program data and codes shall be retained even with the power removed.

(7) *Indicator.* An aural or visible means that it activated when the Preamble is sent and deactivated at the End of Message code.

(8) *Spurious Response.* All frequency components outside 200 to 4000 Hz shall be attenuated by 40 dB or more with respect to the output levels of the mark or space frequencies.

(9) *Attention Signal generator.* The encoder must provide an attention signal that complies with the following:

(i) *Tone Frequencies.* The audio tones shall have fundamental frequencies of 853 and 960 Hz and not vary over ± 0.5 Hz.

(ii) *Harmonic Distortion.* The total harmonic distortion of each of the audio tones may not exceed 5% at the encoder output terminals.

(iii) *Minimum Level of Output.* The encoder shall have an output level capability of at least +8 dBm into a 600 Ohm load impedance at each audio tone. A means shall be provided to permit individual activation of the two tones for calibration of associated systems.

(iv) *Time Period for Transmission of Tones.* The encoder shall have timing circuitry that automatically generates the two tones simultaneously for a time period of not less than 8 nor longer than 25 seconds. NOTE: Prior to July 1, 1995, the Attention Signal must be at least 20 and not more than 25 seconds.

(v) *Inadvertent activation.* The switch used for initiating the automatic generation of the simultaneous tones shall be protected to prevent accidental operation.

(vi) *Indicator Display.* The encoder shall be provided with a visual and/or aural indicator which clearly shows that the Attention Signal is activated.

(b) *Operating Temperature and Humidity.* Encoders shall have the ability to operate with the above specifications

Federal Communications Commission

§ 11.33

within an ambient temperature range of 0 to +50 degrees C and a range of relative humidity of up to 95%.

(c) *Primary Supply Voltage Variation.* Encoders shall be capable of complying with the requirements of this section during a variation in primary supply voltage of 85 percent to 115 percent of its rated value.

(d) *Testing Encoder Units.* Encoders not covered by § 11.34(e) of this part shall be tested in a 10 V/m minimum RF field at an AM broadcast frequency and a 0.5 V/m minimum RF field at an FM or TV broadcast frequency to simulate actual working conditions.

§ 11.33 EAS Decoder.

(a) An EAS Decoder must at a minimum be capable of decoding the EAS protocol described in § 11.31, provide the EAS monitoring functions described in § 11.52, and the following minimum specifications:

(1) *Inputs.* Decoders must have the capability to receive at least 2 audio inputs from EAS monitoring assignments, and one data input (RS-232C with standard protocol and 1200 baud rate). The data input may be used to monitor other communications modes such as Radio Broadcast Data System (RBDS), NWR, satellite, public switched telephone network, or any other source that uses the EAS protocol.

(2) *Valid codes.* There must be a means to determine if valid EAS header codes are received and to determine if preselected header codes are received.

(3) *Storage.* Decoders must provide the means to:

(i) Record and store, either internally or externally, at least two minutes of audio or text messages. A decoder manufactured without an internal means to record and store audio or text must be equipped with a means (such as an audio or digital jack connection) to couple to an external recording and storing device.

(ii) Store at least 10 preselected event and originator header codes, in addition to the eight mandatory event/originator codes for tests and national activations, and store any preselected location codes for comparison with incoming header codes. A non-

preselected header code that is manually transmitted must be stored for comparison with later incoming header codes. The header codes of the last ten received valid messages which still have valid time periods must be stored for comparison with the incoming valid header codes of later messages. These last received header codes will be deleted from storage as their valid time periods expire.

(4) *Display.* A visual message shall be developed from any valid EAS header codes received. The message will include the Originator, Event, Location, the valid time period of the message and the local time the message was transmitted. The message shall be in the primary language of the broadcast station or cable system and be fully displayed on the decoder and readable in normal light and darkness.

(5) *Indicators.* EAS decoders must have a distinct and separate aural or visible means to indicate when any of the following conditions occurs:

(i) Any valid EAS header codes are received as specified in § 11.33(a)(10).

(ii) Preprogrammed header codes, such as those selected in accordance with § 11.52(d)(2) are received.

(iii) A signal is present at each audio input that is specified in § 11.33(a)(1).

(6) *Program Data Retention.* The program data must be retained even with power removed.

(7) *Outputs.* Decoders shall have the following outputs: a data port or ports (RS-232C with standard protocol and 1200 baud rate) where received valid EAS header codes and received preselected header codes are available; one audio port that is capable of monitoring each decoder audio input; and, an internal speaker to enable personnel to hear audio from each input.

(8) *Decoder Programming.* Access to decoder programming shall be protected by a lock or other security measures and be configured so that authorized personnel can readily select and program the EAS Decoder with preselected Originator, Event and Location codes for either manual or automatic operation.

(9) *Reset.* There shall be a method to automatically or manually reset the decoder to the normal monitoring condition. Operators shall be able to select

§ 11.34

47 CFR Ch. I (10–1–97 Edition)

a time interval, not less than two minutes, in which the decoder would automatically reset if it received an EAS header code but not an end-of-message (EOM) code. Messages received with the EAN Event codes shall disable the reset function so that lengthy audio messages can be handled. The last message received with valid header codes shall be displayed as required by paragraph (a)(4) of this section before the decoder is reset.

(10) *Message Validity.* An EAS Decoder must provide error detection and validation of the header codes of each message to ascertain if the message is valid. Header code comparisons may be accomplished through the use of a bit-by-bit compare or any other error detection and validation protocol. A header code must only be considered valid when two of the three headers match exactly. Duplicate messages must not be relayed automatically.

(11) A header code with the EAN Event code specified in § 11.31(c) that is received through any of the audio inputs must override all other messages.

(b) *Attention Signal.* EAS Decoders at broadcast stations shall have detection and activation circuitry that will demute a receiver upon detection of the two audio tones of 853 Hz and 960 Hz. To prevent false responses, decoders designed to use the two tones for broadcast receiver demuting shall comply with the following:

(1) *Time Delay.* A minimum time delay of 8 but not more than 16 seconds of tone reception shall be incorporated into the demuting or activation process to insure that the tones will be audible for a period of at least 4 seconds. After July 1, 1995, the time delay shall be 3–4 seconds.

(2) *Operation Bandwidth.* The decoder circuitry shall not respond to tones which vary more than ± 5 Hz from each of the frequencies, 853 Hz and 960 Hz.

(3) *Reset Ability.* The decoder shall have a means to manually or automatically reset the associated broadcast receiver to a muted state.

(c) Decoders shall be capable of operation within the tolerances specified in this section as well as those in § 11.32 (b), (c) and (d).

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 55999, Nov. 6, 1995]

§ 11.34 Acceptability of the equipment.

(a) An EAS Encoder used for generating the EAS codes and the Attention Signal must be Certified in accordance with the procedures in part 2, subpart J, of this chapter. The data and information submitted must show the capability of the equipment to meet the requirements of this part as well as the requirements contained in part 15 of this chapter for digital devices.

(b) Decoders used for the detection of the EAS codes and receiving the Attention Signal must be Certified in accordance with the procedures in part 2, subpart J, of this chapter. The data and information submitted must show the capability of the equipment to meet the requirements of this part as well as the requirements contained in part 15 of this chapter for digital devices.

(c) The functions of the EAS decoder, Attention Signal generator and receiver, and the EAS encoder specified in §§ 11.31, 11.32 and 11.33 may be combined and Certified as a single unit provided that the unit complies with all specifications in this rule section.

(d) Manufacturers must include instructions and information on how to install, operate and program an EAS Encoder, EAS Decoder, or combined unit and a list of all State and county FIPS numbers with each unit sold or marketed in the U.S.

(e) Waiver requests of the Certification requirements for EAS Encoders or EAS Decoders which are constructed for use at a broadcast station or subject cable system, but are not offered for sale will be considered on an individual basis in accordance with part 1, subpart G, of this chapter.

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 56000, Nov. 6, 1995]

§ 11.35 Equipment operational readiness.

(a) Broadcast stations and subject cable systems are responsible for ensuring that EAS Encoders, EAS Decoders and Attention Signal generating and receiving equipment used as part of the EAS is installed so that the monitoring and transmitting functions are available during the times the broadcast station or cable system is in

Federal Communications Commission

§ 11.42

operation. Additionally, broadcast stations and subject cable systems must determine the cause of any failure to receive the required tests or activations specified in § 11.61(a) (1) and (2). Appropriate entries must be made in the broadcast station log as specified in §§ 73.1820 and 73.1840 of this chapter, cable system record in § 76.305 of this chapter indicating reasons why any tests were not received.

(b) If the EAS Encoder or EAS Decoder becomes defective the broadcast station or subject cable system may operate without the defective equipment pending its repair or replacement for a period not in excess of 60 days without further FCC authority. Entries shall be made in the broadcast station log or subject cable system records showing the date and time the equipment was removed and restored to service. For personnel training purposes, the required monthly test script must still be transmitted even though the equipment for generating the EAS message codes, Attention Signal and EOM code is not functioning.

(c) An informal request may be made to the Engineer-in-charge of the FCC field office serving area in which the broadcast station or subject cable system is located for additional time to complete repairs to the defective equipment. These requests must explain what steps have been taken to repair or replace the defective equipment, the alternative procedures being used while the defective equipment is out of service, and when the defective equipment will be repaired or replaced.

Subpart C—Organization

§ 11.41 Participation in EAS.

(a) All broadcast stations and cable systems specified in § 11.11 are categorized as Participating National (PN) sources unless authorized by the FCC to be Non-Participating National (NN) sources.

(b) A broadcast station or cable system may submit a written request to the FCC asking to be a Non-Participating National (NN) source. The FCC may then issue a Non-participating National Authorization letter. NN sources must go off the air during a national EAS activation.

(1) Any existing station that is a Non-participating National (NN) source under § 11.18(f) that wants to become a Participating National (PN) source in the national level EAS must submit a written request to the FCC.

(2) NN sources may voluntarily participate in the State and Local Area EAS. Participation is at the discretion of broadcast station and cable system management and will be in accordance with the provisions of State and Local Area EAS Plans.

(c) All sources, including NN, must have immediate access to an EAS Operating Handbook and a Red Envelope Authenticator List and be placed on the EAS mailing list maintained by the FCC.

§ 11.42 Participation by communications common carriers.

(a) During activation of the National level EAS, communications common carriers which have facilities available in place may, without charge, connect:

(1) An originating source from the nearest service area to a selected Test Center and then to the radio and television broadcast networks, and cable networks and program suppliers for the duration of the emergency, provided an Emergency Action Notification is issued by the White House and the originating source has a local channel from the originating point to the nearest service area.

(2) An independent broadcast station to the radio and television broadcast networks, and cable networks and program suppliers provided the station has in service a local channel from the station's studio or transmitter directly to the broadcast source.

(b) Upon receipt of the Emergency Action Termination, the common carriers shall disconnect the originating source and the participating independent stations and restore the networks and program suppliers to their original configurations.

(c) During a National level EAS Closed Circuit Test, common carriers which have facilities in place may, without charge, connect an originating source from the nearest service area to a selected Test Center and then to the radio networks and, if participating,

§ 11.43

47 CFR Ch. I (10–1–97 Edition)

any television networks and cable networks and program suppliers. Independent stations will not be connected during the test unless authorized by the FCC. Upon test termination, participants shall be restored to their original configurations.

(d) A common carrier rendering free service shall file with the FCC, on or before July 31st and January 31st of each year, reports covering the six months ending on June 30th and December 31st respectively. These reports shall state what free service was rendered under this rule and the charges in dollars which would have accrued to the carrier for this service if charges had been collected at the published tariff rates if such carriers are required to file tariffs.

§ 11.43 National level participation.

The industry entities voluntarily participating in the national level EAS are:

- (a) *Radio Networks.*
 - (1) ABC.
 - (2) Associated Press (APR).
 - (3) CBS.
 - (4) CNN.
 - (5) Jones Satellite Audio.
 - (6) Moody Broadcasting Network.
 - (7) Mutual Broadcasting System (MBS).
 - (8) MUZAK.
 - (9) NBC.
 - (10) National Public (NPR).
 - (11) Unistar.
 - (12) United Press International (UPIR).
 - (13) USA.
- (b) *Television Networks.*
 - (1) ABC.
 - (2) CBS.
 - (3) FOX.
 - (4) NBC.
 - (5) PBS.
- (c) *Cable Program Suppliers.*
 - (1) Cable News Network (CNN) and CNN Headline News.
 - (2) Cinemax.
 - (3) Disney Channel.
 - (4) Entertainment and Sports Programming Network (ESPN).
 - (5) Home Box Office (HBO).
 - (6) Movie Channel.
 - (7) MTV.
 - (8) The Nashville Network.
 - (9) Nickelodeon.

- (10) Showtime.
- (11) VH-1.
- (12) Weather Channel.
- (d) *Wire Services.*
 - (1) Associated Press (AP).
 - (2) Reuters.
 - (3) United Press International (UPI).
- (e) *Common Carriers.*
 - (1) American Telephone and Telegraph (AT&T).
 - (2) [Reserved]
- (f) Entities that wish to voluntarily participate in the national level EAS may submit a written request to the FCC.

§ 11.44 EAS message priorities.

(a) A national activation of the EAS for a Presidential message with the Event code EAN as specified in § 11.31 must take priority over any other message and preempt it if it is in progress.

(b) EAS participants should transmit other EAS messages in the following order: first, Local Area Messages; second, State Messages; and third, National Information Center (NIC) Messages.

(c) Key EAS sources (NP, LP, SP and SR) and Participating National (PN) sources that remain on the air during a National emergency must carry Presidential Messages “live” at the time of transmission or immediately upon receipt. Activation of the National level EAS must preempt State and Local Area EAS operation.

(d) During a national emergency, the radio and television broadcast network program distribution facilities must be reserved exclusively for distribution of Presidential Messages. NIC messages received from national networks which are not broadcast at the time of original transmission must be recorded locally by LP sources for transmission at the earliest opportunity consistent with the message priorities in paragraph (b) of this section.

§ 11.45 Prohibition of false or deceptive EAS transmissions.

No person may transmit or cause to transmit the EAS codes or Attention Signal, or a recording or simulation thereof, in any circumstance other than in an actual National, State or Local Area emergency or authorized

Federal Communications Commission

§ 11.51

test of the EAS. Broadcast station licensees should also refer to § 73.1217 of this chapter.

§ 11.46 EAS public service announcements.

Broadcast stations may use Public Service Announcements or obtain commercial sponsors for announcements, informercials, or programs explaining the EAS to the public. Such announcements and programs may not be a part of alerts or tests, and may not simulate or attempt to copy alert tones or codes.

§ 11.47 Optional use of other communications methods and systems.

(a) Broadcast stations may additionally transmit EAS messages through other communications means than the main audio channel. For example, on a voluntary basis, FM stations may use subcarriers to transmit the EAS codes including 57 kHz using the RBDS standard produced by the National Radio Systems Committee (NRSC) and television stations may use subsidiary communications services.

(b) Other technologies and public service providers, such as DBS, low earth orbiting satellites, etc., that wish to participate in the EAS may contact the FCC's EAS office or their State Emergency Communication Committee for information and guidance.

[60 FR 56000, Nov. 6, 1995]

Subpart D—Emergency Operations

§ 11.51 EAS code and Attention Signal Transmission requirements.

(a) Broadcast stations must transmit, either automatically or manually, national level EAS messages and required tests by sending the EAS header codes, Attention Signal, emergency message and End of Message (EOM) using the EAS Protocol. The Attention Signal must precede any emergency audio message. After January 1, 1998, the shortened Attention Signal may only be used as an audio alert signal and the EAS codes will become the minimum signalling requirement for National level messages and tests.

(b) Broadcast stations may transmit only the EAS header codes and the EOM code without the Attention Signal and emergency message for State and local emergencies. Television stations and cable systems should ensure that pauses in video programming before EAS message transmission do not cause television receivers to mute EAS audio messages. No Attention Signal is warranted for EAS messages that do not contain audio programming, such as a Required Weekly Test.

(c) Effective January 1, 1997, all radio and television stations shall transmit EAS messages in the main audio channel.

(d) By the above date, television stations shall transmit a visual message containing the Originator, Event, Location and the valid time period of an EAS message. If the message is a video crawl, it shall be displayed at the top of the television screen or where it will not interfere with other visual messages.

(e) Class D non-commercial educational FM stations as defined in § 73.506 of this chapter and low power TV stations as defined in § 74.701(f) of this chapter are not required to have equipment capable of generating the EAS codes and Attention Signal specified in § 11.31.

(f) Broadcast stations are responsible for ensuring that the equipment for generating the EAS codes and the Attention Signal shall modulate a broadcast station transmitter so that the signal broadcast to other broadcast stations and cable systems alerts them that the EAS is being activated or tested at the National, State or Local Area level. The minimum level of modulation for EAS codes, measured at peak modulation levels using the internal calibration output specified in § 11.32(a)(4) shall modulate the transmitter at no less than 80% of full channel modulation limits. Measured at peak modulation levels, each of the Attention Signal tones shall be calibrated separately to modulate the transmitter at no less than 40%. These two calibrated modulation levels shall have values that are within 1 dB of each other.

§ 11.51

47 CFR Ch. I (10–1–97 Edition)

(g) Effective July 1, 1997, cable systems shall transmit EAS audio messages in the same order specified in paragraph (a) of this section. The Attention Signal may be produced from a storage device. Additionally, subject cable systems must:

(1) Install, operate, and maintain equipment capable of generating the EAS codes. The modulation levels for the EAS codes and Attention Signal for cable systems shall comply with the aural signal requirements in § 76.605 of this chapter. This will provide sufficient signal levels to operate cable subscriber television or radio receivers equipped with EAS decoders and to audibly alert subscribers.

(2) Provide a video interruption and an audio EAS message on all channels. The audio message must state which channel is carrying the visual EAS message.

(3) Subject cable systems shall transmit a visual EAS message on at least one channel. The message shall contain the Originator, Event, Location and the valid time period of the EAS message. If the visual message is a video crawl, it shall be displayed at the top of the subscriber's television screen or where it will not interfere with other visual messages.

(4) Cable systems shall provide a method to alert hearing impaired or deaf subscribers to EAS messages. Methods may include: a box that displays EAS messages and activates other alerting mechanisms or lights; visual messages on all channels; etc.

(5) Cable systems may elect not to interrupt EAS messages from broadcast stations based on a written agreement between all concerned.

(h) If manual interrupt is used as specified in paragraph (l) of this section, EAS Encoders must be located so that station or cable staff, at normal duty locations, can initiate the EAS code and Attention Signal transmission.

(i) Broadcast stations or cable systems that are co-owned and co-located with a combined studio or control facility (such as an AM and FM licensed to the same entity and at the same location or a cable headend serving more than one system) may provide the EAS transmitting requirements contained

in this section for the combined station or cable system with one EAS Encoder. The requirements of § 11.32 must be met for both the broadcast station and cable system.

(j) Broadcast stations and cable systems are required to transmit all received EAS messages in which the header code contains the Event codes for Emergency Action Notification (EAN), Emergency Action Termination (EAT), and Required Monthly Test (RMT), with the accompanying location codes for their State and State/county. These EAS messages shall be retransmitted unchanged except for the LLLLLLLL- code which identifies the broadcast station or cable system retransmitting the message. See § 11.31(c). If an EAS source originates any EAS messages with the above Event codes, it must include the location codes for the State and counties in its service area. When transmitting the required weekly test, broadcast stations and subject cable systems will use the event code RWT. The location codes will be the state and county for the broadcast station city of license or subject cable system community. Other location codes may be included upon approval of station or cable system management approval. EAS code requirements and examples are provided in the EAS Operating Handbook. Operations may be conducted automatically or manually.

(1) *Automatic* interrupt of programming and transmission of EAS messages is required when facilities are unattended and must include a permanent record that contains at a minimum the following information: Originator, Event, Location and valid time period of the message. The decoder performs the functions necessary to determine which EAS messages are automatically transmitted by the encoder.

(2) *Manual* interrupt of programming and transmission of EAS messages may be used. EAS messages with the EAN and EAT Event codes must be transmitted immediately and Monthly EAS test messages within 15 minutes. All actions must be logged or recorded.

(k) Broadcast stations and cable systems may employ a minimum delay feature, not to exceed 15 minutes, for automatic interrupt of EAS codes but

Federal Communications Commission

§ 11.52

not for the EAN Event which must be transmitted immediately.

(l) Either manual or automatic operation of EAS equipment may be used at broadcast stations or cable systems that use remote control. If manual operation is used, an EAS decoder must be located at the remote control location and directly monitor the signals of the two assigned EAS sources. If direct monitoring of the assigned EAS sources is not possible at the remote location, automatic operation is required. If automatic operation is used, the remote control location may be used to override the transmission of an EAS message. Broadcast stations and cable systems may change back and forth between automatic and manual operation.

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 56000, Nov. 6, 1995]

§ 11.52 EAS code and Attention Signal Monitoring requirements

(a) Before January 1, 1998, broadcast stations must be capable of receiving the Attention Signal required by § 11.32(a)(9) and emergency messages of other broadcast stations during their hours of operation. Effective January 1, 1997, all broadcast stations must install and operate during their hours of operation, equipment capable of receiving and decoding, either automatically or manually, the EAS header codes, emergency messages and EOM code. The effective date for subject cable systems is July 1, 1997.

NOTE TO PARAGRAPH (A). After January 1, 1998, the two-tone Attention Signal will not be used to actuate two-tone decoders but will be used as an aural alert signal.

(b) If manual interrupt is used as specified in § 11.51(l)(2), decoders must be located so that operators at their normal duty stations at broadcast stations and cable systems can be alerted immediately when EAS messages are received.

(c) Broadcast stations or cable systems that are co-owned and co-located with a combined studio or control facility, (such as an AM and FM licensed to the same entity and at the same location or a cable headend serving more than one system) may provide the EAS monitoring requirements contained in

this section for the combined station or cable system with one EAS Decoder. The requirements of § 11.33 must be met for the combined station or cable system.

(d) Broadcast stations and subject cable systems must monitor the two EAS sources assigned in accordance with the monitoring priorities in the EAS Operating Handbook. The off-air monitoring assignments of each broadcast station and cable system are specified in the State EAS Plan and FCC Mapbook.

(1) If the required EAS sources cannot be received, alternate arrangements or a waiver may be obtained by written request to the FCC's EAS office. In an emergency, a waiver may be issued over the telephone with a follow up letter to confirm temporary or permanent reassignment.

(2) Broadcast station and cable system management will determine which header codes will automatically interrupt their programming for State and Local Area emergency situations affecting their audiences.

(e) A broadcast station or cable system is required to interrupt normal programming either automatically or manually when it receives an EAS message in which the header code contains the Event codes for Emergency Action Notification (EAN), Emergency Action Termination (EAT), or Required Monthly Test (RMT) for its State or State/county location.

(1) *Automatic* interrupt of programming is required when facilities are unattended. Automatic operation must provide a permanent record of the EAS message that contains at a minimum the following information: Originator, Event, Location and valid time period of the message.

(2) *Manual* interrupt of programming and transmission of EAS messages may be used. EAS messages with the EAN Event code must be transmitted immediately and Monthly EAS test messages within 15 minutes. All actions must be logged or recorded. Decoders must be programmed for the EAN and EAT Event header codes for EAS National level emergencies and the RMT and RWT Event header codes for required monthly and weekly tests, with

§ 11.53

47 CFR Ch. I (10–1–97 Edition)

the appropriate accompanying State and State/county location codes.

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 56000, Nov. 6, 1995]

§ 11.53 Dissemination of Emergency Action Notification.

Initiation of the EAN by any one of the following sources is sufficient to begin the emergency actions in § 11.54.

(a) National Level. The EAN is issued by the White House. The EAN message is sent from an origination point to control points of the participating radio and television networks, cable networks and program suppliers, wire services, communications common carriers and other entities. It is then disseminated via:

(1) Radio and television broadcast networks to all affiliates with the use of internal alerting facilities.

(2) Cable networks and program suppliers to cable systems and subscribers.

(3) Wire services to all subscribers (AM, FM, TV, LPTV and other stations).

(4) Off-air monitoring of EAS sources.

(b) State level and Local Area levels. EAN dissemination arrangements at these levels originate from State and local governments in accordance with State and Local Area plans.

(c) Broadcast stations must, prior to commencing routine operation or originating any emissions under program test, equipment test, experimental, or other authorizations, determine whether the EAS has been activated by any of the following methods:

(1) Monitor the radio and TV networks and cable systems.

(2) Check the wire services.

(3) Monitor the assigned EAS sources.

§ 11.54 EAS operation during a National Level emergency.

(a) The EAS Operating Handbook summarizes the procedures to be followed upon receipt of a National level EAN or EAT Message.

(b) Immediately upon receipt of an EAN message, broadcast stations and cable systems must:

(1) Monitor the radio and television networks, cable networks and program suppliers, and wire services for further instructions.

(2) Verify the authenticity of the EAN message with the current Red Envelope Authenticator List (broadcast stations only).

(3) Monitor the two EAS sources assigned in the State or Local Area plan or FCC Mapbook for any further instructions.

(4) Discontinue normal programming and follow the transmission procedures in the appropriate section of the EAS Operating Handbook. Announcements may be made in the same language as the primary language of the station.

(i) Key EAS sources (National Primary (NP), Local Primary (LP), State Primary (SP), State Relay (SR) and Participating National (PN) sources) follow the transmission procedures and make the announcements in the National Level Instructions of the EAS Operating Handbook.

(ii) Non-participating National (NN) sources follow the transmission procedures and make the sign-off announcement in the EAS Operating Handbook's National Level Instructions section for NN sources. After the sign-off announcement, NN sources are required to remove their carriers from the air and monitor for the Emergency Action Termination message. NN sources using automatic interrupt under § 11.51(l)(1) must transmit the header codes, Attention Signal, sign-off announcement and EOM code after receiving the appropriate EAS header codes for a national emergency.

(5) After completing the above transmission procedures, key EAS and Participating National sources must transmit a common emergency message until receipt of the Emergency Action Termination Message. Message priorities are specified in § 11.44. If LP or SR sources of a Local Area cannot provide an emergency message feed, any source in the Local Area may elect to provide a message feed. This should be done in an organized manner as designated in State and Local Area EAS Plans.

(6) The Standby Script shall be used until emergency messages are available. The text of the Standby Script is in the EAS Operating Handbook's section for Participating sources.

(7) TV broadcast stations shall display an appropriate EAS slide and then

Federal Communications Commission

§ 11.55

transmit all EAS announcements visually and aurally as specified in § 73.1250(h) of this chapter.

(8) Announcements may be made in the same language as the primary language of the station.

(9) Broadcast Stations in the International Broadcast Service must cease broadcasting immediately upon receipt of an Emergency Action Notification and must maintain radio silence until an EAT is issued. Such stations may be issued an emergency authorization by the FCC with concurrence of the Director, Office of Science and Technology Policy, to transmit Federal government broadcasts or communications.

(10) Broadcast stations may transmit their call letters and cable systems may transmit the names of the communities they serve during an EAS activation. EAS State and Local Area identifications must be given as provided in State and Local Area EAS plans.

(11) All broadcast stations and cable systems operating and identified with a particular Local Area must transmit a common national emergency message until receipt of the Emergency Action Termination.

(12) Broadcast stations, except those holding an EAS Non-participating National Authorization letter, are exempt from complying with §§ 73.62 and 73.1560 of this chapter (operating power maintenance) while operating under this part.

(13) National Primary (NP) sources must operate under the procedures in the National Control Point Procedures.

(14) The time of receipt of the EAN and Emergency Action Termination messages shall be entered in the broadcast station logs (as specified in §§ 73.1820 and 73.1840 of this chapter), or the cable system records (as specified in § 76.305 of this chapter).

(c) Upon receipt of an Emergency Action Termination Message, broadcast stations and cable systems must follow the termination procedures in the EAS Operating Handbook.

(d) Broadcast stations and cable systems originating emergency communications under this section shall be considered to have conferred rebroadcast authority, as required by Section 325(a) of the Communications Act of

1934, 47 U.S.C. 325(a), to other participating broadcast stations and cable systems.

§ 11.55 EAS operation during a State or Local Area emergency.

(a) The EAS may be activated at the State or Local Area levels by broadcast stations and cable systems at their discretion for day-to-day emergency situations posing a threat to life and property. Examples of natural emergencies which may warrant activation are: tornadoes, floods, hurricanes, earthquakes, heavy snows, icing conditions, widespread fires, etc. Man-made emergencies may include: toxic gas leaks or liquid spills, widespread power failures, industrial explosions, and civil disorders.

(b) EAS operations must be conducted as specified in State and Local Area EAS Plans. The plans must list all authorized entities participating in the State or Local Area EAS.

(c) Immediately upon receipt of a State or Local Area EAS message, participating broadcast stations and cable systems must do the following:

(1) State Relay (SR) sources monitor the State Relay Network or follow the State EAS plan for instructions from the State Primary (SP) source.

(2) Local Primary (LP) sources monitor the Local Area SR sources or follow the State EAS plan for instructions.

(3) Participating National (PN) and Non-participating National (NN) sources monitor the Local Area LP sources for instructions.

(4) Broadcast stations and cable systems participating in the State or Local Area EAS must discontinue normal programming and follow the procedures in the State and Local Area Plans. Television stations must comply with § 11.54(b)(7). Broadcast stations providing foreign language programming shall comply with § 11.54(b)(8).

(5) Upon completion of the State or Local Area EAS transmission procedures, resume normal programming until receipt of the cue from the SR or LP sources in your Local Area. At that time begin transmitting the common emergency message received from the above sources.

§ 11.61

47 CFR Ch. I (10–1–97 Edition)

(6) Resume normal operations upon conclusion of the message.

(7) The times of the above EAS actions must be entered in the broadcast station or cable system records as specified in § 11.54(b)(15). FCC Form 201 may be used to report EAS activations.

(8) Use of the EAS codes or Attention Signal automatically grants rebroadcast authority as specified in § 11.54(d).

Subpart E—Tests

§ 11.61 Tests of EAS procedures.

(a) Tests shall be made at regular intervals as indicated below. Additional tests may be performed anytime. EAS activations and special tests may be performed in lieu of required tests as specified in paragraph (a)(6) of this section. All tests will conform with the procedures in the EAS Operating Handbook.

(1) Required Monthly Tests of the EAS header codes, Attention Signal, Test Script and EOM code.

(i) Effective January 1, 1997, AM, FM and TV stations.

(ii) Effective July 1, 1997, cable systems.

(iii) Tests in odd numbered months shall occur between 8:30 a.m. and local sunset. Tests in even numbered months shall occur between local sunset and 8:30 a.m. They will originate from Local or State Primary sources. Time and script content will be developed by State Emergency Communications Committees in cooperation with affected broadcast stations, cable systems, and other participants. Script content can be in the primary language of the broadcast station or cable system. These monthly tests must be transmitted within 15 minutes of receipt by broadcast stations and cable systems in an EAS Local Area or State. Class D non-commercial educational FM and LPTV stations need to transmit only the test script.

(2) Required Weekly Tests:

(i) Attention Signal. Until January 1, 1997, broadcast stations must conduct tests of the Attention Signal and Test Script at least once a week at random days and times between 8:30 a.m. and local sunset. Class D non-commercial educational FM and LPTV stations do not need to transmit the Attention

Signal. Script content can be in the primary language of the station.

(ii) EAS Header Codes and EOM Codes:

(A) Effective January 1, 1997, AM, FM and TV stations must conduct tests of the EAS header and EOM codes at least once a week at random days and times.

(B) Effective July 1, 1997, subject cable systems must conduct tests of the EAS header and EOM codes at least once a week at random days and times.

(iii) Class D non-commercial educational FM and LPTV stations are not required to transmit this test but must log receipt.

(iv) The EAS weekly test is not required during the week that a monthly test is conducted.

(3) Periodic Wire Service Tests. AP, Reuters and UPI shall separately conduct test transmissions to broadcast stations and cable systems on their wire networks. Tests may occur no more than once a month at random times selected by the wire services. These tests shall conform with the procedures in the EAS Operating Handbook and the National Control Point Procedures.

(4) Weekly Emergency Action Notification (EAN) network transmissions. Tests of the National level interconnection facilities shall be conducted on a random basis once each week. They shall originate from the Federal government over a dedicated network to specified control points of the radio and television networks, cable networks and program suppliers, wire services, common carriers and other organizations. The tests shall conform with the National Control Point Procedures.

(5) Periodic National Tests. National Primary (NP) sources shall participate in tests as appropriate. The FCC may request a report of these tests.

(6) EAS activations and special tests. The EAS may be activated at the State or Local Area level by a broadcast station or cable system in lieu of the monthly or weekly tests required by this section. Such activation must include transmission of the EAS header codes, Attention Signal, emergency message and EOM code for substitution of the monthly test. Activation must include transmission of the Attention

Signal and emergency message for substitution of the weekly test in paragraph (a)(2)(i) of this section. Activation must include transmission of the EAS header and EOM codes for substitution of the weekly test in paragraph (a)(2)(ii) of this section. Television stations and cable systems shall comply with the visual message requirements in §11.51 of this part. Special EAS tests at the State and Local Area levels may be conducted on a day-to-day basis following procedures in State and Local Area EAS plans.

(b) Entries shall be made in the broadcast station or cable system records as specified in §11.54(b)(14) concerning EAS tests received and transmitted.

[59 FR 67092, Dec. 28, 1994, as amended at 60 FR 56000, Nov. 6, 1995]

§ 11.62 Closed Circuit Tests of National Level EAS facilities.

(a) Closed Circuit Tests (CCT) of National Level EAS facilities shall be conducted on a random or scheduled basis not more than once a month and not less than once every three months. Test times will be selected by the White House in coordination with participating industry personnel, the Federal Emergency Management Agency (FEMA), and the FCC. The FCC will notify the participating networks, wire services, cable networks and program suppliers and common carriers of the selected time window for the test at least four working days (holidays excluded) before the test.

(b) The EAS Operating Handbook and National Control Point Procedures contain the CCT procedures.

(c) The control points of the participating radio and television networks, cable networks and program suppliers, wire services and common carriers will receive notification of a CCT by a "Closed Circuit Test Activation Message".

(d) Test announcements will originate from a point selected by the White House with program feed circuitry connected to the telephone company Toll Test Center at points coordinated for each test. Participating common carriers will connect, as required, the facilities of the radio networks and other test participants. Telephone companies

are not authorized to add any participating independent broadcast stations unless authorized by the FCC. Authentication will be provided to the Toll Test Center or other program entry location responsible for test arrangements. Authentication used in the CCT Message will be the test words on the outside of the Red Envelope Authenticator List.

(e) CCT procedures for radio network affiliates, wire service subscribers, and, if participating, television network affiliates and cable systems are as follows:

(1) Notification of a CCT will be disseminated as specified in §11.53 (a)(1) and (a)(3) and the EAS Operating Handbook.

(2) Recipients immediately monitor their radio network, and if participating, their television network or cable system, and check their wire service for the receipt of the CCT Activation Message. Verify authenticity using the current Red Authenticator List.

(3) Continue to monitor for the CCT audio talkup and program.

(4) Enter the time of receipt of the CCT message in the broadcast station log or cable system records.

(5) The CCT terminates on the following aural closing cue in the text of the test program: "This concludes the Closed Circuit Test of the EAS."

(6) Following the closing cue, wire service subscribers will receive a "Closed Circuit Test Termination Message". Record the time of receipt as indicated above.

(f) The FCC may request a CCT report in a prescribed format.

PART 13—COMMERCIAL RADIO OPERATORS

GENERAL

- 13.1 Basis and purpose.
- 13.3 Definitions.
- 13.5 Licensed commercial radio operator required.
- 13.7 Classification of operator licenses and endorsements.
- 13.9 Eligibility and application for new license or endorsement.
- 13.11 Holding more than one commercial radio operator license.
- 13.13 Application for a renewed or modified license.
- 13.15 License term.

§ 13.1

- 13.17 Replacement license.
- 13.19 Operator's responsibility.

EXAMINATION SYSTEM

- 13.201 Qualifying for a commercial operator license or endorsement.
- 13.203 Examination elements.
- 13.207 Preparing an examination.
- 13.209 Examination procedures.
- 13.211 Commercial radio operator license examination.
- 13.213 COLEM qualifications.
- 13.215 Question pools.
- 13.217 Records.

AUTHORITY: Secs. 4, 303, 48 Stat. 1066, 1082 as amended; 47 U.S.C. 154, 303.

SOURCE: 58 FR 9124, Feb. 19, 1993, unless otherwise noted.

§ 13.1 Basis and purpose.

(a) *Basis*. The basis for the rules contained in this part is the Communications Act of 1934, as amended, and applicable treaties and agreements to which the United States is a party.

(b) *Purpose*. The purpose of the rules in this part is to prescribe the manner and conditions under which commercial radio operators are licensed by the Commission.

§ 13.3 Definitions.

The definitions of terms used in part 13 are:

- (a) *COLEM*. Commercial operator license examination manager.
- (b) *Commercial radio operator*. A person holding a license or licenses specified in § 13.7(b).
- (c) *GMDSS*. Global Maritime Distress and Safety System.
- (d) *FCC*. Federal Communications Commission.
- (e) *International Morse Code*. A dot-dash code as defined in International Telegraph and Telephone Consultative Committee (CCITT) Recommendation F.1 (1984), Division B, I. Morse code.
- (f) *ITU*. International Telecommunication Union.
- (g) *PPC*. Proof-of-Passing Certificate.
- (h) *Question pool*. All current examination questions for a designated written examination element.
- (i) *Question set*. A series of examination questions on a given examination selected from the current question pool.

47 CFR Ch. I (10–1–97 Edition)

(j) *Radio Regulations*. The latest ITU *Radio Regulations* to which the United States is a party.

§ 13.5 Licensed commercial radio operator required.

Rules that require FCC station licensees to have certain transmitter operating, maintenance, and repair duties performed by a commercial radio operator are contained in parts 23, 73, 74, 80, and 87 of this chapter.

§ 13.7 Classification of operator licenses and endorsements.

(a) Commercial radio operator licenses issued by the FCC are classified in accordance with the Radio Regulations of the ITU.

(b) There are nine types of commercial radio operator licenses, certificates and permits (licenses). The license's ITU classification, if different from its name, is given in parenthesis.

(1) First Class Radiotelegraph Operator's Certificate.

(2) Second Class Radiotelegraph Operator's Certificate.

(3) Third Class Radiotelegraph Operator's Certificate (radiotelegraph operator's special certificate).

(4) General Radiotelephone Operator License (radiotelephone operator's general certificate).

(5) Marine Radio Operator Permit (radiotelephone operator's restricted certificate).

(6) Restricted Radiotelephone Operator Permit (radiotelephone operator's restricted certificate).

(7) Restricted Radiotelephone Operator Permit-Limited Use (radiotelephone operator's restricted certificate).

(8) GMDSS Radio Operator's License (general operator's certificate).

(9) GMDSS Radio Maintainer's License (technical portion of the first-class radio electronic certificate).

(c) There are six license endorsements affixed by the FCC to provide special authorizations or restrictions. Endorsements may be affixed to the license(s) indicated in parenthesis.

(1) Ship Radar Endorsement (First and Second Class Radiotelegraph Operator's Certificates, General Radiotelephone Operator License, GMDSS Radio Maintainer's License).

Federal Communications Commission

§ 13.9

(2) Six Months Service Endorsement (First and Second Class Radiotelegraph Operator's License).

(3) Restrictive endorsements relating to physical handicaps, English language or literacy waivers, or other matters (all licenses).

(4) Marine Radio Operator Permits shall bear the following endorsement: This permit does not authorize the operation of AM, FM or TV broadcast stations.

(5) General Radiotelephone Operator Licenses issued after December 31, 1985, shall bear the following endorsement: This license confers authority to operate licensed radio stations in the Aviation, Marine and International Fixed Public Radio Services only. This authority is subject to: any endorsement placed upon this license; FCC orders, rules, and regulations; United States statutes; and the provisions of any treaties to which the United States is a party. This license does not confer any authority to operate broadcast stations. It is not assignable or transferable.

(6)(i) If a person is afflicted with an uncorrected physical handicap which would clearly prevent the performance of all or any part of the duties of a radio operator, under the license for which application is made, at a station under emergency conditions involving the safety of life or property, that person still may be issued the license if found qualified. Such a license shall bear a restrictive endorsement as follows:

This license is not valid for the performance of any operating duties, other than installation, service and maintenance duties, at any station licensed by the FCC which is required, directly or indirectly, by any treaty, statute or rule or regulation pursuant to statute, to be provided for safety purposes.

(ii) In the case of a license that does not require an examination in technical radio matters, the endorsement specified in paragraph (c)(6)(i) of this section will be modified by deleting the reference therein to installation, service, and maintenance duties.

(iii) In any case where an applicant who normally would receive or has received a commercial radio operator li-

cense bearing the endorsement prescribed by paragraph (c)(6)(i) of this section, indicates a desire to operate a station falling within the prohibited terms of the endorsement, the applicant may request in writing that such endorsement not be placed upon, or be removed from his or her license, and may submit written comments or statements from other parties in support thereof.

(iv) An applicant who shows that he has performed satisfactorily the duties of a radio operator at a station required to be provided for safety purposes during a period when he or she was afflicted by uncorrected physical handicaps of the same kind and to the same degree as the physical handicaps shown by his or her current application shall not be deemed to be within the provisions of paragraph (c)(6)(i) of this section.

(d) A Restricted Radiotelephone Operator Permit-Limited Use issued by the FCC to an aircraft pilot who is not legally eligible for employment in the United States is valid only for operating radio stations on aircraft.

(e) A Restricted Radiotelephone Operator Permit-Limited Use issued by the FCC to a person under the provision of Section 303(1)(2) of the Communications Act of 1934, as amended, is valid only for the operation of radio stations for which that person is the station licensee.

[58 FR 9124, Feb. 19, 1993; 58 FR 12632, Mar. 5, 1993]

§ 13.9 Eligibility and application for new license or endorsement.

(a) If found qualified, the following persons are eligible to apply for commercial radio operator licenses:

(1) Any person legally eligible for employment in the United States.

(2) Any person, for the purpose of operating aircraft radio stations, who holds:

(i) United States pilot certificates; or
(ii) Foreign aircraft pilot certificates which are valid in the United States, if the foreign government involved has entered into a reciprocal agreement under which such foreign government does not impose any similar requirement relating to eligibility for employment upon United States citizens.

(3) Any person who holds a FCC radio station license, for the purpose of operating that station.

(4) Notwithstanding any other provisions of the FCC's rules, no person shall be eligible to be issued a commercial radio operator license when

(i) The person's commercial radio operator license is suspended, or

(ii) The person's commercial radio operator license is the subject of an ongoing suspension proceeding, or

(iii) The person is afflicted with complete deafness or complete muteness or complete inability for any other reason to transmit correctly and to receive correctly by telephone spoken messages in English.

(b)(1) Each application for a new General Radiotelephone Operator License, Marine Radio Operator Permit, First Class Radiotelegraph Operator's Certificate, Second Class Radiotelegraph Operator's Certificate, Third Class Radiotelegraph Operator's Certificate, Ship Radar Endorsement, Six Months Service Endorsement, GMDSS Radio Operator's License or GMDSS Radio Maintainer's License must be made on FCC Form 756.

(2) Each application for a Restricted Radiotelephone Operator Permit must be made on FCC Form 753.

(3) Each application for a Restricted Radiotelephone Operator Permit-Limited Use must be made on FCC Form 755.

(c) Each application for a new General Radiotelephone Operator License, Marine Radio Operator Permit, First Class Radiotelegraph Operator's Certificate, Second Class Radiotelegraph Operator's Certificate, Third Class Radiotelegraph Operator's Certificate, Ship Radar Endorsement, GMDSS Radio Operator's License or GMDSS Radio Maintainer's License must be accompanied by the required fee, if any, and submitted to the address specified in part 1 of the rules. The application must include:

(1) An original PPC(s) from a COLEM(s) showing that the applicant has passed the necessary examination element(s) within the previous 365 days, and

(2) A copy of the applicable license(s) when the applicant claims credit for an examination element. The FCC will

give credit only as specified below to an applicant holding any of the following documents:

(i) An unexpired (or within the grace period) FCC-issued commercial radio operator license: The written examination and telegraphy Element(s) required to obtain the license held.

(ii) An unexpired (or within the grace period) FCC-issued Amateur Extra Class operator license: Telegraphy Elements 1 and 2.

(d) Provided that a person's commercial radio operator license was not revoked, or suspended, and is not the subject of an ongoing suspension proceeding, a person whose application for a commercial radio operator license has been received by the FCC but which has not yet been acted upon and who holds a PPC(s) indicating that he or she passed the necessary examination(s) within the previous 365 days, is authorized to exercise the rights and privileges of the operator license for which the application was received. This authority is valid for a period of 90 days from the date the application was received. The FCC, in its discretion, may cancel this temporary conditional operating authority without a hearing.

(e) Each application for a new Six Months Service Endorsement must be submitted to the address specified in Part 1 of the rules. The application must include documentation showing that:

(1) The applicant was employed as a radio operator on board a ship or ships of the United States for a period totaling at least six months;

(2) The ships were equipped with a radio station complying with the provisions of part II of title III of the Communications Act, or the ships were owned and operated by the U.S. Government and equipped with radio stations;

(3) The ships were in service during the applicable six month period and no portion of any single in-port period included in the qualifying six months period exceeded seven days;

(4) The applicant held a FCC-issued First or Second Class Radiotelegraph Operator's Certificate during this entire six month qualifying period; and

Federal Communications Commission

§ 13.13

(5) The applicant holds a radio officer's license issued by the U.S. Coast Guard at the time the six month endorsement is requested.

(f) No person shall alter, duplicate for fraudulent purposes, or fraudulently obtain or attempt to obtain an operator license. No person shall use a license issued to another or a license that he or she knows to be altered, duplicated for fraudulent purposes, or fraudulently obtained. No person shall obtain or attempt to obtain, or assist another person to obtain or attempt to obtain, an operator license by fraudulent means.

[58 FR 9124, Feb. 19, 1993, as amended at 59 FR 3795, Jan. 27, 1994; 60 FR 27699, May 25, 1995]

§ 13.11 Holding more than one commercial radio operator license.

(a) An eligible person may hold more than one commercial operator license except as follows:

(1) No person may hold two or more unexpired radiotelegraph operator's certificates at the same time;

(2) No person may hold any class of radiotelegraph operator's certificate and a Marine Radio Operator Permit;

(3) No person may hold any class of radiotelegraph operator's certificate and a Restricted Radiotelephone Operator Permit.

(b) Each person who is not legally eligible for employment in the United States, and certain other persons who were issued permits prior to September 13, 1982, may hold two Restricted Radiotelephone Operator Permits simultaneously when each permit authorizes the operation of a particular station or class of stations.

§ 13.13 Application for a renewed or modified license.

(a) Each application to renew a First Class Radiotelegraph Operator's Certificate, Second Class Radiotelegraph Operator's Certificate, Third Class Radiotelegraph Operator's Certificate, Marine Radio Operator Permit, GMDSS Radio Operator's License, or GMDSS Radio Maintainer's License must be made on FCC Form 756. The application must be accompanied by the original document or a legible photocopy unless it has been lost, mutilated, or destroyed.

If the license has been lost, mutilated, or destroyed, submit a written explanation. The application must be accompanied by the appropriate fee and submitted to the address specified in part 1 of the rules.

(b) A licensee may submit an application for renewal of an unexpired license during the last year of the license term. If a license expires, application for renewal may be made during a grace period of five years after the expiration date without having to retake the required examinations. The application must be accompanied by the required fee and submitted to the address specified in part 1 of the rules. During the grace period, the expired license is not valid. A license renewed during the grace period will be effective as of the date of the renewal. Licensees who fail to renew their license within the grace period must apply for a new license and take the required examination(s).

(c) Each application involving a change in operator class must be made on FCC Form 756. Each application for a commercial operator license involving a change in operator class must be accompanied by the required fee, if any, and submitted to the address specified in part 1 of the rules. The application must include:

(1) An original PPC(s) from a COLEM(s) showing that the applicant has passed the necessary examination element(s) within the previous 365 days, and

(2) A copy of the applicable license(s) when the applicant claims credit for an examination element. The FCC will give credit only as specified below to an applicant holding any of the following documents:

(i) An unexpired (or within the grace period) FCC-issued commercial radio operator license: the written examination and telegraphy Element(s) required to obtain the license held.

(ii) An unexpired (or within the grace period) FCC-issued Amateur Extra Class operator license: Telegraphy Elements 1 and 2.

(d) Provided that a person's commercial radio operator license was not revoked, or suspended, and is not the subject of an ongoing suspension proceeding, a person holding a General Radiotelephone Operator License, Marine

§ 13.15

Radio Operator Permit, First Class Radiotelegraph Operator's Certificate, Second Class Radiotelegraph Operator's Certificate, Third Class Radiotelegraph Operator's Certificate, GMDSS Radio Operator's License, or GMDSS Radio Maintainer's License, who has an application for another commercial radio operator license which has not yet been acted upon pending at the FCC and who holds a PPC(s) indicating that he or she passed the necessary examination(s) within the previous 365 days, is authorized to exercise the rights and privileges of the license for which the application is filed. This authority is valid for a period of 90 days from the date the application is received. The FCC, in its discretion, may cancel this temporary conditional operating authority without a hearing.

(e) The holder of a First Class Radiotelegraph Operator's Certificate, Second Class Radiotelegraph Operator's Certificate, Third Class Radiotelegraph Operator's Certificate, General Radiotelephone Operator License, Marine Radio Operator Permit, GMDSS Radio Operator's License, or GMDSS Radio Maintainer's License whose name is legally changed may obtain a modified license by filing a FCC Form 756 with a written explanation. The application must be accompanied by the required fee and submitted to the address specified in part 1 of the rules.

(f) A licensee who has made application for a renewed or modified operator license or permit may exhibit a photocopy of their license in lieu of the original document.

[58 FR 9124, Feb. 19, 1993, as amended at 59 FR 3795, Jan. 27, 1994; 60 FR 27699, May 25, 1995]

§ 13.15 License term.

(a) Commercial radio operator licenses are normally valid for a term of five years from the date of issuance, except as provided in paragraph (b) of this section.

(b) General Radiotelephone Operator Licenses, Restricted Radiotelephone Operator Permits, and Restricted Radiotelephone Operator Permits-Limited Use are normally valid for the lifetime of the holder. The terms of all Restricted Radiotelephone Operator Per-

47 CFR Ch. I (10–1–97 Edition)

mits issued prior to November 15, 1953, and valid on that date, are extended to the lifetime of the operator.

§ 13.17 Replacement license.

(a) Each licensee or permittee whose original document is lost, mutilated, or destroyed must request a replacement. The application must be accompanied by the required fee and submitted to the address specified in part 1 of the rules.

(b) Each application for a replacement General Radiotelephone Operator License, Marine Radio Operator Permit, First Class Radiotelegraph Operator's Certificate, Second Class Radiotelegraph Operator's Certificate, Third Class Radiotelegraph Operator's Certificate, GMDSS Radio Operator's License, GMDSS Radio Maintainer's License, must be made on FCC Form 756 and must include a written explanation as to the circumstances involved in the loss, mutilation, or destruction of the original document.

(c) Each application for a replacement Restricted Radiotelephone Operator Permit must be on FCC Form 753.

(d) Each application for a replacement Restricted Radiotelephone Operator Permit-Limited Use must be on FCC Form 755.

(e) A licensee who has made application for a replacement license may exhibit a copy of the application submitted to the FCC or a photocopy of the license in lieu of the original document.

§ 13.19 Operator's responsibility.

(a) The operator responsible for maintenance of a transmitter may permit other persons to adjust that transmitter in the operator's presence for the purpose of carrying out tests or making adjustments requiring specialized knowledge or skill, provided that he or she shall not be relieved thereby from responsibility for the proper operation of the equipment.

(b) In every case where a station operating log or service and maintenance log is required, the operator responsible for the station operation or maintenance shall make the required entries in the station log. If no station log is required, the operator responsible for service or maintenance duties which may affect the proper operation

Federal Communications Commission

§ 13.203

of the station shall sign and date an entry in the station maintenance records giving:

(1) Pertinent details of all service and maintenance work performed by the operator or conducted under his or her supervision;

(2) His or her name and address; and

(3) The class, serial number and expiration date of the license when the FCC has issued the operator a license, or the PPC serial number(s) and date(s) of issue when the operator is awaiting FCC action on an application.

(c) When the operator is on duty and in charge of transmitting systems, or performing service, maintenance or inspection functions, the license or permit document, or a photocopy thereof, or a copy of the application and PPC(s) received by the FCC, must be posted or in the operator's personal possession, and available for inspection upon request by a FCC representative.

(d) The operator on duty and in charge of transmitting systems, or performing service, maintenance or inspection functions, shall not be subject to the requirements of paragraph (b) of this section at a station, or stations of one licensee at a single location, at which the operator is regularly employed and at which his or her license, or a photocopy, is posted.

[58 FR 9124, Feb. 19, 1993, as amended at 60 FR 27700, May 25, 1995]

EXAMINATION SYSTEM

§ 13.201 Qualifying for a commercial operator license or endorsement.

(a) To be qualified to hold any commercial radio operator license, an applicant must have a satisfactory knowledge of FCC rules and must have the ability to send correctly and receive correctly spoken messages in the English language.

(b) An applicant must pass an examination for the issuance of a new commercial radio operator license, other than the Restricted Radiotelephone Operator Permit and the Restricted Radiotelephone Operator Permit-Limited Use, and for each change in operator class. An applicant must pass an examination for the issuance of a new Ship Radar Endorsement. Each application for the class of license or en-

dorsement specified below must pass, or otherwise receive credit for, the corresponding examination elements:

(1) First Class Radiotelegraph Operator's Certificate.

(i) Telegraphy Elements 3 and 4;

(ii) Written Elements 1, 5, and 6;

(iii) Applicant must be at least 21 years old;

(iv) Applicant must have one year of experience in sending and receiving public correspondence by radiotelegraph at a public coast station, a ship station, or both.

(2) Second Class Radiotelegraph Operator's Certificate.

(i) Telegraphy Elements 1 and 2;

(ii) Written Elements 1, 5, and 6.

(3) Third Class Radiotelegraph Operator's Certificate.

(i) Telegraphy Elements 1 and 2;

(ii) Written Elements 1 and 5.

(4) General Radiotelephone Operator License: Written Elements 1 and 3.

(5) Marine Radio Operator Permit: Written Element 1.

(6) GMDSS Radio Operator's License: Written Elements 1 and 7.

(7) GMDSS Radio Maintainer's License: Written Elements 1, 3, and 9.

(8) Ship Radar Endorsement: Written Element 8.

[58 FR 9124, Feb. 19, 1993, as amended at 59 FR 3795, Jan. 27, 1994]

§ 13.203 Examination elements.

(a) A written examination (written Element) must prove that the examinee possesses the operational and technical qualifications to perform the duties required by a person holding that class of commercial radio operator license. Each written examination must be comprised of a question set as follows:

(1) Element 1 (formerly Elements 1 and 2): Basic radio law and operating practice with which every maritime radio operator should be familiar. 24 questions concerning provisions of laws, treaties, regulations, and operating procedures and practices generally followed or required in communicating by means of radiotelephone stations. The minimum passing score is 18 questions answered correctly.

(2) Element 3: General radiotelephone. 76 questions concerning

electronic fundamentals and techniques required to adjust, repair, and maintain radio transmitters and receivers at stations licensed by the FCC in the aviation, maritime, and international fixed public radio services. The minimum passing score is 57 questions answered correctly.

(3) Element 5: Radiotelegraph operating practice. 50 questions concerning radio operating procedures and practices generally followed or required in communicating by means of radiotelegraph stations primarily other than in the maritime mobile services of public correspondence. The minimum passing score is 38 questions answered correctly.

(4) Element 6: Advanced radiotelegraph. 100 questions concerning technical, legal and other matters applicable to the operation of all classes of radiotelegraph stations, including operating procedures and practices in the maritime mobile services of public correspondence, and associated matters such as radio navigational aids, message traffic routing and accounting, etc. The minimum passing score is 75 questions answered correctly.

(5) Element 7: GMDSS radio operating practices. 76 questions concerning GMDSS radio operating procedures and practices sufficient to show detailed practical knowledge of the operation of all GMDSS sub-systems and equipment; ability to send and receive correctly by radio telephone and narrow-band direct-printing telegraphy; detailed knowledge of the regulations applying to radio communications, knowledge of the documents relating to charges for radio communications and knowledge of those provisions of the International Convention for the Safety of Life at Sea which relate to radio; sufficient knowledge of English to be able to express oneself satisfactorily both orally and in writing; knowledge of and ability to perform each function listed in §80.1081; and knowledge covering the requirements set forth in IMO Assembly Resolution on Training for Radio Personnel (GMDSS), Annex 3. The minimum passing score is 57 questions answered correctly.

(6) Element 8: Ship radar techniques. 50 questions concerning specialized

theory and practice applicable to the proper installation, servicing and maintenance of ship radar equipment in general use for marine navigational purposes. The minimum passing score is 38 questions answered correctly.

(7) Element 9: GMDSS radio maintenance practices and procedures. 50 questions concerning the requirements set forth in IMO Assembly on Training for Radio Personnel (GMDSS), Annex 5 and IMO Assembly on Radio Maintenance Guidelines for the Global Maritime Distress and Safety System related to Sea Areas A3 and A4. The minimum passing score is 38 questions answered correctly.

(b) A telegraphy examination (telegraphy Elements) must prove that the examinee has the ability to send correctly by hand and to receive correctly by ear texts in the international Morse code at not less than the prescribed speed, using all the letters of the alphabet, numerals 0–9, period, comma, question mark, slant mark, and prosigns AR, BT, and SK.

(1) Telegraphy Element 1: 16 code groups per minute.

(2) Telegraphy Element 2: 20 words per minute.

(3) Telegraphy Element 3: 20 code groups per minute.

(4) Telegraphy Element 4: 25 words per minute.

§ 13.207 Preparing an examination.

(a) Each telegraphy message and each written question set administered to an examinee for a commercial radio operator license must be provided by a COLEM.

(b) Each question set administered to an examinee must utilize questions taken from the applicable Element question pool. The COLEM may obtain the written question sets from a supplier or other COLEM.

(c) A telegraphy examination must consist of a plain language text or code group message sent in the international Morse code at no less than the prescribed speed for a minimum of five minutes. The message must contain each required telegraphy character at least once. No message known to the examinee may be administered in a telegraphy examination. Each five letters of the alphabet must be counted as

Federal Communications Commission

§ 13.211

one word or one code group. Each numeral, punctuation mark, and prosign must be counted as two letters of the alphabet. The COLEM may obtain the telegraphy message from a supplier or other COLEM.

§ 13.209 Examination procedures.

(a) Each examination for a commercial radio operator license must be administered at a location and a time specified by the COLEM. The COLEM is responsible for the proper conduct and necessary supervision of each examination. The COLEM must immediately terminate the examination upon failure of the examinee to comply with its instructions.

(b) Each examinee, when taking an examination for a commercial radio operator license, shall comply with the instructions of the COLEM.

(c) No examination that has been compromised shall be administered to any examinee. Neither the same telegraphy message nor the same question set may be re-administered to the same examinee.

(d) Passing a telegraphy examination.

(1) To pass a receiving telegraphy examination, an examinee is required to receive correctly the message by ear, for a period of 1 minute without error at the rate of speed specified in § 13.203 for the class of license sought.

(2) To pass a sending telegraphy examination, an examinee is required to send correctly for a period of 1 minute at the rate of speed prescribed in § 13.203(b) for the class of license sought.

(e) Passing a telegraphy receiving examination is adequate proof of an examinee's ability to both send and receive telegraphy. The COLEM, however, may also include a sending segment in a telegraphy examination.

(f) The COLEM is responsible for determining the correctness of the examinee's answers. When the examinee does not score a passing grade on an examination element, the COLEM must inform the examinee of the grade.

(g) When the examinee is credited for all examination elements required for the commercial operator license sought, the examinee may apply to the FCC for the license.

(h) No applicant who is eligible to apply for any commercial radio operator license shall, by reason of any physical handicap, be denied the privilege of applying and being permitted to attempt to prove his or her qualifications (by examination if examination is required) for such commercial radio operator license in accordance with procedures established by the COLEM.

(i) The COLEM must accommodate an examinee whose physical disabilities require a special examination procedure. The COLEM may require a physician's certification indicating the nature of the disability before determining which, if any, special procedures are appropriate to use. In the case of a blind examinee, the examination questions may be read aloud and the examinee may answer orally. A blind examinee wishing to use this procedure must make arrangements with the COLEM prior to the date the examination is desired.

(j) The FCC may:

(1) Administer any examination element itself.

(2) Readminister any examination element previously administered by a COLEM, either itself or by designating another COLEM to readminister the examination element.

(3) Cancel the commercial operator license(s) of any licensee who fails to appear for re-administration of an examination when directed by the FCC, or who fails any required element that is re-administered. In case of such cancellation, the person will be issued an operator license consistent with completed examination elements that have not been invalidated by not appearing for, or by failing, the examination upon re-administration.

§ 13.211 Commercial radio operator license examination.

(a) Each session where an examination for a commercial radio operator license is administered must be managed by a COLEM or the FCC.

(b) Each examination for a commercial radio operator license must be administered as determined by the COLEM.

(c) The COLEM may limit the number of candidates at any examination.

§ 13.213

(d) The COLEM may prohibit from the examination area items the COLEM determines could compromise the integrity of an examination or distract examinees.

(e) Within 10 days of completion of the examination element(s), the COLEM must provide the results of the examination to the examinee and the COLEM must issue a PPC to an examinee who scores a passing grade on an examination element.

(f) A PPC is valid for 365 days from the date it is issued.

§ 13.213 COLEM qualifications.

No entity may serve as a COLEM unless it has entered into a written agreement with the FCC. In order to be eligible to be a COLEM, the entity must:

(a) Agree to abide by the terms of the agreement;

(b) Be capable of serving as a COLEM;

(c) Agree to coordinate examinations for one or more types of commercial radio operator licenses and/or endorsements;

(d) Agree to assure that, for any examination, every examinee eligible under these rules is registered without regard to race, sex, religion, national origin or membership (or lack thereof) in any organization;

(e) Agree to make any examination records available to the FCC, upon request.

(f) Agree not to administer an examination to an employee, relative, or relative of an employee.

§ 13.215 Question pools.

The question pool for each written examination element will be composed of questions acceptable to the FCC. Each question pool must contain at least 5 times the number of questions required for a single examination. The FCC will issue public announcements detailing the questions in the pool for each element. COLEMs must use only the most recent question pool made available to the public when preparing a question set for a written examination element.

§ 13.217 Records.

Each COLEM recovering fees from examinees must maintain records of

47 CFR Ch. I (10–1–97 Edition)

expenses and revenues, frequency of examinations administered, and examination pass rates. Records must cover the period from January 1 to December 31 of the preceding year and must be submitted as directed by the Commission. Each COLEM must retain records for 1 year and the records must be made available to the FCC upon request.

PART 15—RADIO FREQUENCY DEVICES

Subpart A—General

Sec.

15.1 Scope of this part.

15.3 Definitions.

15.5 General conditions of operation.

15.7 Special temporary authority.

15.9 Prohibition against eavesdropping.

15.11 Cross reference.

15.13 Incidental radiators.

15.15 General technical requirements.

15.17 Susceptibility to interference.

15.19 Labelling requirements.

15.21 Information to user.

15.23 Home-built devices.

15.25 Kits.

15.27 Special accessories.

15.29 Inspection by the Commission.

15.31 Measurement standards.

15.32 Test procedures for CPU boards and computer power supplies.

15.33 Frequency range of radiated measurements.

15.35 Measurement detector functions and bandwidths.

15.37 Transition provisions for compliance with the rules.

Subpart B—Unintentional Radiators

15.101 Equipment authorization of unintentional radiators.

15.102 CPU boards and power supplies used in personal computers.

15.103 Exempted devices.

15.105 Information to the user.

15.107 Conducted limits.

15.109 Radiated emission limits.

15.111 Antenna power conduction limits for receivers.

15.113 Power line carrier systems.

15.115 TV interface devices, including cable system terminal devices.

15.117 TV broadcast receivers.

15.118 Cable ready consumer electronics equipment.

15.119 Closed caption decoder requirements for television receivers.

15.121 Scanning receivers and frequency converters designed or marketed for use with scanning receivers.

Federal Communications Commission

§ 15.1

Subpart C—Intentional Radiators

- 15.201 Equipment authorization requirement.
- 15.203 Antenna requirement.
- 15.204 External radio frequency power amplifiers and antenna modifications.
- 15.205 Restricted bands of operation.
- 15.207 Conducted limits.
- 15.209 Radiated emission limits; general requirements.
- 15.211 Tunnel radio systems.
- 15.213 Cable locating equipment.
- 15.214 Cordless telephones.

RADIATED EMISSION LIMITS, ADDITIONAL PROVISIONS

- 15.215 Additional provisions to the general radiated emission limitations.
- 15.217 Operation in the band 160–190 kHz.
- 15.219 Operation in the band 510–1705 kHz.
- 15.221 Operation in the band 525–1705 kHz.
- 15.223 Operation in the band 1.705–10 MHz.
- 15.225 Operation within the band 13.553–13.567 MHz.
- 15.227 Operation within the band 26.96–27.28 MHz.
- 15.229 Operation within the band 40.66–40.70 MHz.
- 15.231 Periodic operation in the band 40.66–40.70 MHz and above 70 MHz.
- 15.233 Operation within the bands 43.71–44.49 MHz, 46.60–46.98 MHz, 48.75–49.51 MHz and 49.66–50.0 MHz.
- 15.235 Operation within the band 49.82–49.90 MHz.
- 15.237 Operation in the bands 72.0–73.0 MHz, 74.6–74.8 MHz and 75.2–76.0 MHz.
- 15.239 Operation in the band 88–108 MHz.
- 15.241 Operation in the band 174–216 MHz.
- 15.243 Operation in the band 890–940 MHz.
- 15.245 Operation within the bands 902–928 MHz, 2435–2465 MHz, 5785–5815 MHz, 10500–10550 MHz, and 24075–24175 MHz.
- 15.247 Operation within the bands 902–928 MHz, 2400–2483.5 MHz, and 5725–5850 MHz.
- 15.249 Operation within the bands 902–928 MHz, 2400–2483.5 MHz, 5725–5875 MHz, and 24.0–24.25 GHz.
- 15.251 Operation within the bands 2.9–3.26 GHz, 3.267–3.332 GHz, 3.339–3.3458 GHz, and 3.358–3.6 GHz.
- 15.253 Operation within the bands 46.7–46.9 GHz and 76.0–77.0 GHz.
- 15.255 Operation within the band 59.0–64.0 GHz.

Subpart D—Unlicensed Personal Communications Service Devices

- 15.301 Scope.
- 15.303 Definitions.
- 15.305 Equipment authorization requirement.
- 15.307 Coordination with fixed microwave service.
- 15.309 Cross reference.

- 15.311 Labelling requirements.
- 15.313 Measurement procedures.
- 15.315 Conducted limits.
- 15.317 Antenna requirement.
- 15.319 General technical requirements.
- 15.321 Specific requirements for asynchronous devices operating in the 1910–1920 MHz and 2390–2400 MHz bands.
- 15.323 Specific requirements for isochronous devices operating in the 1920–1930 MHz sub-band.

Subpart E—Unlicensed National Information Infrastructure Devices

- 15.401 Scope.
- 15.403 Definitions.
- 15.405 Cross reference.
- 15.407 General technical requirements.

AUTHORITY: 47 U.S.C. 154, 302, 303, 304, 307 and 544A.

SOURCE: 54 FR 17714, Apr. 25, 1989, unless otherwise noted.

Subpart A—General

§ 15.1 Scope of this part.

(a) This part sets out the regulations under which an intentional, unintentional, or incidental radiator may be operated without an individual license. It also contains the technical specifications, administrative requirements and other conditions relating to the marketing of part 15 devices.

(b) The operation of an intentional or unintentional radiator that is not in accordance with the regulations in this part must be licensed pursuant to the provisions of section 301 of the Communications Act of 1934, as amended, unless otherwise exempted from the licensing requirements elsewhere in this chapter.

(c) Unless specifically exempted, the operation or marketing of an intentional or unintentional radiator that is not in compliance with the administrative and technical provisions in this part, including prior Commission authorization or verification, as appropriate, is prohibited under section 302 of the Communications Act of 1934, as amended, and subpart I of part 2 of this chapter. The equipment authorization and verification procedures are detailed in subpart J of part 2 of this chapter.

§ 15.3 Definitions.

(a) *Auditory assistance device.* An intentional radiator used to provide auditory assistance to a handicapped person or persons. Such a device may be used for auricular training in an education institution, for auditory assistance at places of public gatherings, such as a church, theater, or auditorium, and for auditory assistance to handicapped individuals, only, in other locations.

(b) *Biomedical telemetry device.* An intentional radiator used to transmit measurements of either human or animal biomedical phenomena to a receiver.

(c) *Cable input selector switch.* A transfer switch that is intended as a means to alternate between the reception of broadcast signals via connection to an antenna and the reception of cable television service.

(d) *Cable locating equipment.* An intentional radiator used intermittently by trained operators to locate buried cables, lines, pipes, and similar structures or elements. Operation entails coupling a radio frequency signal onto the cable, pipes, etc. and using a receiver to detect the location of that structure or element.

(e) *Cable system terminal device (CSTD).* A TV interface device that serves, as its primary function, to connect a cable system operated under part 76 of this chapter to a TV broadcast receiver or other subscriber premise equipment. Any device which functions as a CSTD in one of its operating modes must comply with the technical requirements for such devices when operating in that mode.

(f) *Carrier current system.* A system, or part of a system, that transmits radio frequency energy by conduction over the electric power lines. A carrier current system can be designed such that the signals are received by conduction directly from connection to the electric power lines (unintentional radiator) or the signals are received over-the-air due to radiation of the radio frequency signals from the electric power lines (intentional radiator).

(g) *CB receiver.* Any receiver that operates in the Personal Radio Services on frequencies allocated for Citizens Band (CB) Radio Service stations, as

well as any receiver provided with a separate band specifically designed to receive the transmissions of CB stations in the Personal Radio Services. This includes the following: (1) A CB receiver sold as a separate unit of equipment; (2) the receiver section of a CB transceiver; (3) a converter to be used with any receiver for the purpose of receiving CB transmissions; and, (4) a multiband receiver that includes a band labelled “CB” or “11-meter” in which such band can be separately selected, except that an Amateur Radio Service receiver that was manufactured prior to January 1, 1960, and which includes an 11-meter band shall not be considered to be a CB receiver.

(h) *Class A digital device.* A digital device that is marketed for use in a commercial, industrial or business environment, exclusive of a device which is marketed for use by the general public or is intended to be used in the home.

(i) *Class B digital device.* A digital device that is marketed for use in a residential environment notwithstanding use in commercial, business and industrial environments. Examples of such devices include, but are not limited to, personal computers, calculators, and similar electronic devices that are marketed for use by the general public.

NOTE: The responsible party may also qualify a device intended to be marketed in a commercial, business or industrial environment as a Class B device, and in fact is encouraged to do so, provided the device complies with the technical specifications for a Class B digital device. In the event that a particular type of device has been found to repeatedly cause harmful interference to radio communications, the Commission may classify such a digital device as a Class B digital device, regardless of its intended use.

(j) *Cordless telephone system.* A system consisting of two transceivers, one a base station that connects to the public switched telephone network and the other a mobile handset unit that communicates directly with the base station. Transmissions from the mobile unit are received by the base station and then placed on the public switched telephone network. Information received from the switched telephone network is transmitted by the base station to the mobile unit.

Federal Communications Commission

§ 15.3

NOTE: The Domestic Public Cellular Radio Telecommunications Service is considered to be part of the switched telephone network. In addition, intercom and paging operations are permitted provided these are not intended to be the primary modes of operation.

(k) *Digital device*. (Previously defined as a computing device). An unintentional radiator (device or system) that generates and uses timing signals or pulses at a rate in excess of 9,000 pulses (cycles) per second and uses digital techniques; inclusive of telephone equipment that uses digital techniques or any device or system that generates and uses radio frequency energy for the purpose of performing data processing functions, such as electronic computations, operations, transformations, recording, filing, sorting, storage, retrieval, or transfer. A radio frequency device that is specifically subject to an emanation requirement in any other FCC Rule part or an intentional radiator subject to subpart C of this part that contains a digital device is not subject to the standards for digital devices, provided the digital device is used only to enable operation of the radio frequency device and the digital device does not control additional functions or capabilities.

NOTE: Computer terminals and peripherals that are intended to be connected to a computer are digital devices.

(l) *Field disturbance sensor*. A device that establishes a radio frequency field in its vicinity and detects changes in that field resulting from the movement of persons or objects within its range.

(m) *Harmful interference*. Any emission, radiation or induction that endangers the functioning of a radio navigation service or of other safety services or seriously degrades, obstructs or repeatedly interrupts a radiocommunications service operating in accordance with this chapter.

(n) *Incidental radiator*. A device that generates radio frequency energy during the course of its operation although the device is not intentionally designed to generate or emit radio frequency energy. Examples of incidental radiators are dc motors, mechanical light switches, etc.

(o) *Intentional radiator*. A device that intentionally generates and emits

radio frequency energy by radiation or induction.

(p) *Kit*. Any number of electronic parts, usually provided with a schematic diagram or printed circuit board, which, when assembled in accordance with instructions, results in a device subject to the regulations in this part, even if additional parts of any type are required to complete assembly.

(q) *Perimeter protection system*. A field disturbance sensor that employs RF transmission lines as the radiating source. These RF transmission lines are installed in such a manner that allows the system to detect movement within the protected area.

(r) *Peripheral device*. An input/output unit of a system that feeds data into and/or receives data from the central processing unit of a digital device. Peripherals to a digital device include any device that is connected external to the digital device, any device internal to the digital device that connects the digital device to an external device by wire or cable, and any circuit board designed for interchangeable mounting, internally or externally, that increases the operating or processing speed of a digital device, e.g., “turbo” cards and “enhancement” boards. Examples of peripheral devices include terminals, printers, external floppy disk drives and other data storage devices, video monitors, keyboards, interface boards, external memory expansion cards, and other input/output devices that may or may not contain digital circuitry. This definition does not include CPU boards, as defined in paragraph (bb) of this section, even though a CPU board may connect to an external keyboard or other components.

(s) *Personal computer*. An electronic computer that is marketed for use in the home, notwithstanding business applications. Such computers are considered Class B digital devices. Computers which use a standard TV receiver as a display device or meet all of the following conditions are considered examples of personal computers:

(1) Marketed through a retail outlet or direct mail order catalog.

(2) Notices of sale or advertisements are distributed or directed to the general public or hobbyist users rather than restricted to commercial users.

§ 15.3

47 CFR Ch. I (10–1–97 Edition)

(3) Operates on a battery or 120 volt electrical supply.

If the responsible party can demonstrate that because of price or performance the computer is not suitable for residential or hobbyist use, it may request that the computer be considered to fall outside of the scope of this definition for personal computers.

(t) *Power line carrier systems.* An unintentional radiator employed as a carrier current system used by an electric power utility entity on transmission lines for protective relaying, telemetry, etc. for general supervision of the power system. The system operates by the transmission of radio frequency energy by conduction over the electric power transmission lines of the system. The system does not include those electric lines which connect the distribution substation to the customer or house wiring.

(u) *Radio frequency (RF) energy.* Electromagnetic energy at any frequency in the radio spectrum between 9 kHz and 3,000,000 MHz.

(v) *Scanning receiver.* For the purpose of this part, this is a receiver that automatically switches among four or more frequencies in the range of 30 to 960 MHz and which is capable of stopping at and receiving a radio signal detected on a frequency. Receivers designed solely for the reception of the broadcast signals under part 73 of this chapter or for operation as part of a licensed station are not included in this definition.

(w) *Television (TV) broadcast receiver.* A device designed to receive television pictures that are broadcast simultaneously with sound on the television channels authorized under part 73 of this chapter.

(x) *Transfer switch.* A device used to alternate between the reception of over-the-air radio frequency signals via connection to an antenna and the reception of radio frequency signals received by any other method, such as from a TV interface device.

(y) *TV interface device.* An unintentional radiator that produces or translates in frequency a radio frequency carrier modulated by a video signal derived from an external or internal signal source, and which feeds the modulated radio frequency energy by con-

duction to the antenna terminals or other non-baseband input connections of a television broadcast receiver. A TV interface device may include a stand-alone RF modulator, or a composite device consisting of an RF modulator, video source and other components devices. Examples of TV interface devices are video cassette recorders and terminal devices attached to a cable system or used with a Master Antenna (including those used for central distribution video devices in apartment or office buildings).

(z) *Unintentional radiator.* A device that intentionally generates radio frequency energy for use within the device, or that sends radio frequency signals by conduction to associated equipment via connecting wiring, but which is not intended to emit RF energy by radiation or induction.

(aa) *Cable ready consumer electronics equipment.* Consumer electronics TV receiving devices, including TV receivers, videocassette recorders and similar devices, that incorporate a tuner capable of receiving television signals and an input terminal intended for receiving cable television service, and are marketed as “cable ready” or “cable compatible.” Such equipment shall comply with the technical standards specified in § 15.118.

(bb) *CPU board.* A circuit board that contains a microprocessor, or frequency determining circuitry for the microprocessor, the primary function of which is to execute user-provided programming, but not including:

(1) A circuit board that contains only a microprocessor intended to operate under the primary control or instruction of a microprocessor external to such a circuit board; or

(2) A circuit board that is a dedicated controller for a storage or input/output device.

(cc) *External radio frequency power amplifier.* A device which is not an integral part of an intentional radiator as manufactured and which, when used in conjunction with an intentional radiator as a signal source, is capable of amplifying that signal.

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 18340, May 2, 1990; 57 FR 33448, July 29, 1992; 59 FR 25340, May 16, 1994; 61 FR 31048, June 19, 1996; 62 FR 26242, May 13, 1997]

Federal Communications Commission

§ 15.15

§ 15.5 General conditions of operation.

(a) Persons operating intentional or unintentional radiators shall not be deemed to have any vested or recognizable right to continued use of any given frequency by virtue of prior registration or certification of equipment, or, for power line carrier systems, on the basis of prior notification of use pursuant to § 90.63(g) of this chapter.

(b) Operation of an intentional, unintentional, or incidental radiator is subject to the conditions that no harmful interference is caused and that interference must be accepted that may be caused by the operation of an authorized radio station, by another intentional or unintentional radiator, by industrial, scientific and medical (ISM) equipment, or by an incidental radiator.

(c) The operator of a radio frequency device shall be required to cease operating the device upon notification by a Commission representative that the device is causing harmful interference. Operation shall not resume until the condition causing the harmful interference has been corrected.

(d) Intentional radiators that produce Class B emissions (damped wave) are prohibited.

§ 15.7 Special temporary authority.

(a) The Commission will, in exceptional situations, consider an individual application for a special temporary authorization to operate an incidental, intentional or unintentional radiation device not conforming to the provisions of this part, where it can be shown that the proposed operation would be in the public interest, that it is for a unique type of station or for a type of operation which is incapable of being established as a regular service, and that the proposed operation can not feasibly be conducted under this part.

(b) No authorization is required in order to perform testing of equipment for determining compliance with these regulations. Except as provided in subpart I of part 2 of this chapter, this provision does not permit the providing of equipment to potential users in order to determine customer acceptance of the product or marketing strategy, nor does this provision permit any

type of operation other than a determination of compliance with the regulations. During this testing, the provisions of §§ 15.5 and 15.205 apply.

§ 15.9 Prohibition against eavesdropping.

Except for the operations of law enforcement officers conducted under lawful authority, no person shall use, either directly or indirectly, a device operated pursuant to the provisions of this part for the purpose of overhearing or recording the private conversations of others unless such use is authorized by all of the parties engaging in the conversation.

§ 15.11 Cross reference.

The provisions of subparts A, H, I, J and K of part 2 apply to intentional and unintentional radiators, in addition to the provisions of this part. Also, a cable system terminal device and a cable input selector switch shall be subject to the relevant provisions of part 76 of this chapter.

§ 15.13 Incidental radiators.

Manufacturers of these devices shall employ good engineering practices to minimize the risk of harmful interference.

§ 15.15 General technical requirements.

(a) An intentional or unintentional radiator shall be constructed in accordance with good engineering design and manufacturing practice. Emanations from the device shall be suppressed as much as practicable, but in no case shall the emanations exceed the levels specified in these rules.

(b) An intentional or unintentional radiator must be constructed such that the adjustments of any control that is readily accessible by or intended to be accessible to the user will not cause operation of the device in violation of the regulations.

(c) Parties responsible for equipment compliance should note that the limits specified in this part will not prevent harmful interference under all circumstances. Since the operators of part 15 devices are required to cease operation should harmful interference occur to authorized users of the radio

§ 15.17

frequency spectrum, the parties responsible for equipment compliance are encouraged to employ the minimum field strength necessary for communications, to provide greater attenuation of unwanted emissions than required by these regulations, and to advise the user as to how to resolve harmful interference problems (for example, see § 15.105(b)).

§ 15.17 Susceptibility to interference.

(a) Parties responsible for equipment compliance are advised to consider the proximity and the high power of non-Government licensed radio stations, such as broadcast, amateur, land mobile, and non-geostationary mobile satellite feeder link earth stations, and of U.S. Government radio stations, which could include high-powered radar systems, when choosing operating frequencies during the design of their equipment so as to reduce the susceptibility for receiving harmful interference. Information on non-Government use of the spectrum can be obtained by consulting the Table of Frequency Allocations in § 2.106 of this chapter.

(b) Information on U.S. Government operations can be obtained by contacting: Director, Spectrum Plans and Policy, National Telecommunications and Information Administration, Department of Commerce, Room 4096, Washington, DC 20230.

[54 FR 17714, Apr. 25, 1989, as amended at 62 FR 4655, Jan. 31, 1997]

§ 15.19 Labelling requirements.

(a) In addition to the requirements in part 2 of this chapter, a device subject to certification, notification, or verification shall be labelled as follows:

(1) Receivers associated with the operation of a licensed radio service, e.g., FM broadcast under part 73 of this chapter, land mobile operation under part 90, etc., shall bear the following statement in a conspicuous location on the device:

47 CFR Ch. I (10–1–97 Edition)

This device complies with part 15 of the FCC Rules. Operation is subject to the condition that this device does not cause harmful interference.

(2) A stand-alone cable input selector switch, shall bear the following statement in a conspicuous location on the device:

This device is verified to comply with part 15 of the FCC Rules for use with cable television service.

(3) All other devices shall bear the following statement in a conspicuous location on the device:

This device complies with part 15 of the FCC Rules. Operation is subject to the following two conditions: (1) This device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation.


(4) Where a device is constructed in two or more sections connected by wires and marketed together, the statement specified under paragraph (a) of this section is required to be affixed only to the main control unit.

(5) When the device is so small or for such use that it is not practicable to place the statement specified under paragraph (a) of this section on it, the information required by this paragraph shall be placed in a prominent location in the instruction manual or pamphlet supplied to the user or, alternatively, shall be placed on the container in which the device is marketed. However, the FCC identifier or the unique identifier, as appropriate, must be displayed on the device.


(b) Products subject to authorization under a Declaration of Conformity shall be labelled as follows:

(1) The label shall be located in a conspicuous location on the device and shall contain the unique identification described in § 2.1074 of this chapter and the following logo:

(i) If the product is authorized based on testing of the product or system; or



(ii) If a personal computer is authorized based on assembly using separately authorized components, in accordance with § 15.101(c)(2) or (c)(3), and the resulting product is not separately tested:



(2) Label text and information should be in a size of type large enough to be readily legible, consistent with the dimensions of the equipment and the label. However, the type size for the text is not required to be larger than eight point.

(3) When the device is so small or for such use that it is not practicable to place the statement specified under paragraph (b)(1) of this section on it, such as for a CPU board or a plug-in circuit board peripheral device, the text associated with the logo may be placed in a prominent location in the instruction manual or pamphlet supplied to the user. However, the unique identification (trade name and model number) and the logo must be displayed on the device.

(4) The label shall not be a stick-on, paper label. The label on these products shall be permanently affixed to the product and shall be readily visible to the purchaser at the time of purchase, as described in § 2.925(d) of this chapter. "Permanently affixed" means that the label is etched, engraved, stamped, silkscreened, indelibly printed, or otherwise permanently marked on a permanently attached part of the equipment or on a nameplate of metal, plastic, or other material fastened to the equipment by welding, riveting, or a permanent adhesive. The label must be designed to last the expected lifetime of the equipment in the environment in which the equipment may be operated and must not be readily detachable.

§ 15.21

(c) [Reserved]

(d) Consumer electronics TV receiving devices, including TV receivers, videocassette recorders, and similar devices, that incorporate features intended to be used with cable television service, but do not fully comply with the technical standards for cable ready equipment set forth in §15.118, shall not be marketed with terminology that describes the device as “cable ready” or “cable compatible,” or that otherwise conveys the impression that the device is fully compatible with cable service. Factual statements about the various features of a device that are intended for use with cable service or the quality of such features are acceptable so long as such statements do not imply that the device is fully compatible with cable service. Statements relating to product features are generally acceptable where they are limited to one or more specific features of a device, rather than the device as a whole. This requirement applies to consumer TV receivers, videocassette recorders and similar devices manufactured or imported for sale in this country on or after October 31, 1994.

[54 FR 17714, Apr. 25, 1989, as amended at 59 FR 25341, May 16, 1994; 61 FR 18509, Apr. 26, 1996; 61 FR 31048, June 19, 1996; 62 FR 41881, Aug. 4, 1997]

§ 15.21 Information to user.

The users manual or instruction manual for an intentional or unintentional radiator shall caution the user that changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment.

§ 15.23 Home-built devices.

(a) Equipment authorization is not required for devices that are not marketed, are not constructed from a kit, and are built in quantities of five or less for personal use.

(b) It is recognized that the individual builder of home-built equipment may not possess the means to perform the measurements for determining compliance with the regulations. In this case, the builder is expected to employ good engineering practices to meet the specified technical standards

47 CFR Ch. I (10–1–97 Edition)

to the greatest extent practicable. The provisions of §15.5 apply to this equipment.

§ 15.25 Kits.

A TV interface device, including a cable system terminal device, which is marketed as a kit shall comply with the following requirements:

(a) All parts necessary for the assembled device to comply with the technical requirements of this part must be supplied with the kit. No mechanism for adjustment that can cause operation in violation of the requirements of this part shall be made accessible to the builder.

(b) At least two units of the kit shall be assembled in exact accordance with the instructions supplied with the product to be marketed. If all components required to fully complete the kit (other than those specified in paragraph (a) of this section which are needed for compliance with the technical provisions and must be included with the kit) are not normally furnished with the kit, assembly shall be made using the recommended components. The assembled units shall be certified or notified, as appropriate, pursuant to the requirements of this part.

(1) The measurement data required for a TV interface device subject to certification shall be obtained for each of the two units and submitted with an application for certification pursuant to subpart J of part 2 of this chapter.

(2) The measurement data required for a TV interface device subject to notification shall be obtained for the units tested and retained on file pursuant to the provisions of subpart J of part 2 of this chapter.

(c) A copy of the exact instructions that will be provided for assembly of the device shall be submitted with an application for certification or notification. Those parts which are not normally furnished shall be detailed in the application for equipment authorization.

(d) In lieu of the label required by §15.19, the following label, along with the label bearing the FCC identifier and other information specified in §§2.925 and 2.926, shall be included in the kit with instructions to the builder

Federal Communications Commission

§ 15.29

that it shall be attached to the completed kit:

(Name of Grantee)

(FCC Identifier)

This device can be expected to comply with part 15 of the FCC Rules provided it is assembled in exact accordance with the instructions provided with this kit. Operation is subject to the following conditions: (1) This device may not cause harmful interference, and (2) this device must accept any interference received including interference that may cause undesired operation.

(e) For the purpose of this section, circuit boards used as repair parts for the replacement of electrically identical defective circuit boards are not considered to be kits.

§ 15.27 Special accessories.

(a) Equipment marketed to a consumer must be capable of complying with the necessary regulations in the configuration in which the equipment is marketed. Where special accessories, such as shielded cables and/or special connectors, are required to enable an unintentional or intentional radiator to comply with the emission limits in this part, the equipment must be marketed with, i.e., shipped and sold with, those special accessories. However, in lieu of shipping or packaging the special accessories with the unintentional or intentional radiator, the responsible party may employ other methods of ensuring that the special accessories are provided to the consumer, without additional charge, at the time of purchase. Information detailing any alternative method used to supply the special accessories shall be included in the application for a grant of equipment authorization or retained in the verification records, as appropriate. The party responsible for the equipment, as detailed in § 2.909 of this chapter, shall ensure that these special accessories are provided with the equipment. The instruction manual for such devices shall include appropriate instructions on the first page of the text concerned with the installation of the device that these special accessories must be used with the device. It is the responsibility of the user to

use the needed special accessories supplied with the equipment.

(b) If a device requiring special accessories is installed by or under the supervision of the party marketing the device, it is the responsibility of that party to install the equipment using the special accessories. For equipment requiring professional installation, it is not necessary for the responsible party to market the special accessories with the equipment. However, the need to use the special accessories must be detailed in the instruction manual, and it is the responsibility of the installer to provide and to install the required accessories.

(c) Accessory items that can be readily obtained from multiple retail outlets are not considered to be special accessories and are not required to be marketed with the equipment. The manual included with the equipment must specify what additional components or accessories are required to be used in order to ensure compliance with this part, and it is the responsibility of the user to provide and use those components and accessories.

(d) The resulting system, including any accessories or components marketed with the equipment, must comply with the regulations.

§ 15.29 Inspection by the Commission.

(a) Any equipment or device subject to the provisions of this part, together with any certificate, notice of registration or any technical data required to be kept on file by the operator, supplier or party responsible for compliance of the device shall be made available for inspection by a Commission representative upon reasonable request.

(b) The owner or operator of a radio frequency device subject to this part shall promptly furnish to the Commission or its representative such information as may be requested concerning the operation of the radio frequency device.

(c) The party responsible for the compliance of any device subject to this part shall promptly furnish to the Commission or its representatives such information as may be requested concerning the operation of the device, including a copy of any measurements

§ 15.31

47 CFR Ch. I (10–1–97 Edition)

made for obtaining an equipment authorization or demonstrating compliance with the regulations.

(d) The Commission, from time to time, may request the party responsible for compliance, including an importer, to submit to the FCC Laboratory in Columbia, Maryland, various equipment to determine that the equipment continues to comply with the applicable standards. Shipping costs to the Commission's Laboratory and return shall be borne by the responsible party. Testing by the Commission will be performed using the measurement procedure(s) that was in effect at the time the equipment was authorized or verified.

§ 15.31 Measurement standards.

(a) The following measurement procedures are used by the Commission to determine compliance with the technical requirements in this part. Except where noted, copies of these procedures are available from the Commission's current duplicating contractor whose name and address are available from the Commission's Consumer Assistance Office at 202–632–7000.

(1) FCC/OET MP–1: FCC Methods of Measurements for Determining Compliance of Radio Control and Security Alarm Devices and Associated Receivers. Note: This procedure may be used only for testing devices for which verification is obtained, or for which an application for equipment authorization is filed before June 1, 1995. For compliance testing of these devices after that date, see paragraph (a)(6) of this section.

(2) FCC/OET MP–2: Measurement of UHF Noise Figures of TV Receivers.

(3) FCC/OET MP–3: FCC Methods of Measurements of Output Signal Level, Output Terminal Conducted Spurious Emissions, Transfer Switch Characteristics, and Radio Noise Emissions from TV Interface Devices. Note: This procedure may be used only for testing devices for which verification is obtained, or for which an application for equipment authorization is filed before June 1, 1995. For compliance testing of these devices after that date, see paragraph (a)(6) of this section.

(4) FCC/OET MP–4 (1987): FCC Procedure for Measuring RF Emissions from

Computing Devices. Note: This procedure may be used only for testing digital devices for which verification is obtained, or for which an application for equipment authorization is filed before May 1, 1994. For compliance testing of digital devices on or after May 1, 1994, see paragraph (a)(6) of this section.

(5) FCC/OET MP–9: FCC Procedure for Measuring Cable Television Switch Isolation. Note: This procedure may be used only for testing devices for which verification is obtained, or for which an application for equipment authorization is filed before June 1, 1995. For compliance testing of these devices after that date, see paragraph (a)(6) of this section.

(6) Digital devices authorized by verification, Declaration of Conformity, or for which an application for equipment authorization is filed on or after May 1, 1994, and intentional and other unintentional radiators for which verification is obtained, or for which an application for equipment authorization is filed on or after June 1, 1995 are to be measured for compliance using the following procedure excluding section 5.7, section 9 and section 14: American National Standards Institute (ANSI) C63.4–1992, entitled “Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and Electronic Equipment in the Range of 9 kHz to 40 GHz,” published by the Institute of Electrical and Electronic Engineers, Inc. on July 17, 1992 as document number SH15180. This incorporation by reference was approved by the Director of the Federal Register in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. The Commission encourages the use of this procedure for testing digital devices, intentional radiators, and other unintentional radiators as soon as practical. Copies of ANSI C63.4–1992 may be obtained from: IEEE Standards Department, 455 Hoes Lane, P.O. Box 1331, Piscataway, NJ 08855–1331, telephone 1–800–678–4333. Copies of C63.4–1992 may be inspected during normal business hours at the following locations:

(i) Federal Communications Commission, 2025 M Street, NW., Office of Engineering and Technology (Room 7317), Washington, DC 20554,

Federal Communications Commission

§ 15.31

(ii) Federal Communications Commission Laboratory, 7435 Oakland Mills Road, Columbia, MD 21046, or

(iii) Office of the Federal Register, 800 North Capitol Street, NW., suite 700, Washington, DC.

NOTE: Digital devices tested to show compliance with the provisions of §§15.107(e) and 15.109(g) must be tested following the ANSI C63.4 procedure described in paragraph (a)(6) of this section.

(b) All parties making compliance measurements on equipment subject to the requirements of this part are urged to use these measurement procedures. Any party using other procedures should ensure that such other procedures can be relied on to produce measurement results compatible with the FCC measurement procedures. The description of the measurement procedure used in testing the equipment for compliance and a list of the test equipment actually employed shall be made part of an application for certification or included with the data required to be retained by the party responsible for devices authorized pursuant to a Declaration of Conformity or devices subject to notification or verification.

(c) For swept frequency equipment, measurements shall be made with the frequency sweep stopped at those frequencies chosen for the measurements to be reported.

(d) Field strength measurements shall be made, to the extent possible, on an open field site. Test sites other than open field sites may be employed if they are properly calibrated so that the measurement results correspond to what would be obtained from an open field site. In the case of equipment for which measurements can be performed only at the installation site, such as perimeter protection systems, carrier current systems, and systems employing a “leaky” coaxial cable as an antenna, measurements for verification or for obtaining a grant of equipment authorization shall be performed at a minimum of three installations that can be demonstrated to be representative of typical installation sites.

(e) For intentional radiators, measurements of the variation of the input power or the radiated signal level of the fundamental frequency component of the emission, as appropriate, shall

be performed with the supply voltage varied between 85% and 115% of the nominal rated supply voltage. For battery operated equipment, the equipment tests shall be performed using a new battery.

(f) To the extent practicable, the device under test shall be measured at the distance specified in the appropriate rule section. The distance specified corresponds to the horizontal distance between the measurement antenna and the closest point of the equipment under test, support equipment or interconnecting cables as determined by the boundary defined by an imaginary straight line periphery describing a simple geometric configuration enclosing the system containing the equipment under test. The equipment under test, support equipment and any interconnecting cables shall be included within this boundary.

(1) At frequencies at or above 30 MHz, measurements may be performed at a distance other than that specified provided: Measurements are not made in the near field, and it can be demonstrated that the signal levels to be measured at the distance employed can be detected by the measurement equipment. Measurements shall not be performed at a distance greater than 30 meters unless it can be demonstrated that measurements at a distance of 30 meters or less are impractical. When performing measurements at a distance other than that specified, the results shall be extrapolated to the specified distance using one of the following formulas: For measurements above 30 MHz that are not performed in the near field, an inverse linear-distance extrapolation factor (20 dB/decade); for measurements performed in the near field, an inverse linear-distance-squared extrapolation factor (40 dB/decade).

(2) At frequencies below 30 MHz, measurements may be performed at a distance closer than that specified in the regulations; however, an attempt should be made to avoid making measurements in the near field. Pending the development of an appropriate measurement procedure for measurements performed below 30 MHz, when performing measurements at a closer distance than specified, the results shall

be extrapolated to the specified distance by either making measurements at a minimum of two distances on at least one radial to determine the proper extrapolation factor or by using the square of an inverse linear distance extrapolation factor (40 dB/decade).

(3) The applicant for a grant of certification shall specify the extrapolation method used in the application filed with the Commission. For equipment subject to notification or verification, this information shall be retained with the measurement data.

(4) When measurement distances of 30 meters or less are specified in the regulations, the Commission will test the equipment at the distance specified unless measurement at that distance results in measurements being performed in the near field. When measurement distances of greater than 30 meters are specified in the regulations, the Commission will test the equipment at a closer distance, usually 30 meters, extrapolating the measured field strength to the specified distance using the methods shown in this section.

(5) Measurements shall be performed at a sufficient number of radials around the equipment under test to determine the radial at which the field strength values of the radiated emissions are maximized. The maximum field strength at the frequency being measured shall be reported in an application for certification.

(g) Equipment under test shall be adjusted, using those controls that are readily accessible to or are intended to be accessible to the consumer, in such a manner as to maximize the level of the emissions. For those devices to which wire leads may be attached by the consumer, tests shall be performed with wire leads attached. The wire leads shall be of the length to be used with the equipment if that length is known. Otherwise, wire leads one meter in length shall be attached to the equipment. Longer wire leads may be employed if necessary to interconnect to associated peripherals.

(h) For a composite system that incorporates devices contained either in a single enclosure or in separate enclosures connected by wire or cable, testing for compliance with the standards in this part shall be performed with all

of the devices in the system functioning. If an intentional radiator incorporates more than one antenna or other radiating source and these radiating sources are designed to emit at the same time, measurements of conducted and radiated emissions shall be performed with all radiating sources that are to be employed emitting. A device which incorporates a carrier current system shall be tested as if the carrier current system were incorporated in a separate device; that is, the device shall be tested for compliance with whatever rules would apply to the device were the carrier current system not incorporated, and the carrier current system shall be tested for compliance with the rules applicable to carrier current systems.

(i) If the device under test provides for the connection of external accessories, including external electrical input signals, the device shall be tested with the accessories attached. The device under test shall be fully exercised with these external accessories. The emission tests shall be performed with the device and accessories configured in a manner that tends to produce maximized emissions within the range of variations that can be expected under normal operating conditions. In the case of multiple accessory external ports, an external accessory shall be connected to one of each type of port. Only one test using peripherals or external accessories that are representative of the devices that will be employed with the equipment under test is required. All possible equipment combinations do not need to be tested. The accessories or peripherals connected to the device being tested shall be unmodified, commercially available equipment.

(j) If the equipment under test consists of a central control unit and an external or internal accessory(ies) (peripheral) and the party verifying the equipment or applying for a grant of equipment authorization manufactures or assembles the central control unit and at least one of the accessory devices that can be used with that control unit, testing of the control unit and/or the accessory(ies) must be performed using the devices manufactured or assembled by that party, in addition

Federal Communications Commission

§ 15.31

to any other needed devices which the party does not manufacture or assemble. If the party verifying the equipment or applying for a grant of equipment authorization does not manufacture or assemble the central control unit and at least one of the accessory devices that can be used with that control unit or the party can demonstrate that the central control unit or accessory(ies) normally would be marketed or used with equipment from a different entity, testing of the central control unit and/or the accessory(ies) must be performed using the specific combination of equipment which is intended to be marketed or used together. Only one test using peripherals or accessories that are representative of the devices that will be employed with the equipment under test is required. All possible equipment combinations are not required to be tested. The accessories or peripherals connected to the device being tested shall be unmodified, commercially available equipment.

(k) A composite system is a system that incorporates different devices contained either in a single enclosure or in separate enclosures connected by wire or cable. If the individual devices in a composite system are subject to different technical standards, each such device must comply with its specific standards. In no event may the measured emissions of the composite system exceed the highest level permitted for an individual component. For digital devices which consist of a combination of Class A and Class B devices, the total combination of which results in a Class A digital device, it is only necessary to demonstrate that the equipment combination complies with the limits for a Class A device. This equipment combination may not be employed for obtaining a grant of equipment authorization or verifying a Class B digital device. However, if the digital device combination consists of a Class B central control unit, e.g., a personal computer, and a Class A internal peripheral(s), it must be demonstrated that the Class B central control unit continues to comply with the limits for a Class B digital device with the Class A internal peripheral(s) installed but not active.

(l) Measurements of radio frequency emissions conducted to the public utility power lines shall be performed using a 50 ohm/50 uH line-impedance stabilization network (LISN).

NOTE: Receivers tested under the transition provisions contained in §15.37 may be tested with a 50 ohm/5 uH LISN.

(m) Measurements on intentional radiators or receivers, other than TV broadcast receivers, shall be performed and, if required, reported for each band in which the device can be operated with the device operating at the number of frequencies in each band specified in the following table:

Frequency range over which device operates	Number of frequencies	Location in the range of operation
1 MHz or less	1	Middle.
1 to 10 MHz	2	1 near top and 1 near bottom.
More than 10 MHz	3	1 near top, 1 near middle and 1 near bottom.

(n) Measurements on TV broadcast receivers shall be performed with the receiver tuned to each VHF frequency and also shall include the following oscillator frequencies: 520, 550, 600, 650, 700, 750, 800, 850, 900 and 931 MHz. If measurements cannot be made on one or more of the latter UHF frequencies because of the presence of signals from licensed radio stations or for other reasons to be detailed in the measurement report, measurements shall be made with the receiver oscillator at a nearby frequency. If the receiver is not capable of receiving channels above 806 MHz, the measurements employing the oscillator frequencies 900 and 931 MHz may be omitted.

(o) The amplitude of spurious emissions from intentional radiators and emissions from unintentional radiators which are attenuated more than 20 dB below the permissible value need not be reported unless specifically required elsewhere in this part.

(p) In those cases where the provisions in this section conflict with the measurement procedures in paragraph (a) of this section and the procedures were implemented after June 23, 1989,

§ 15.32

the provisions contained in the measurement procedures shall take precedence.

[54 FR 17714, Apr. 25, 1989, as amended at 56 FR 13083, Mar. 29, 1991; 57 FR 24990, June 12, 1992; 57 FR 33448, July 29, 1992; 58 FR 37430, July 12, 1993; 58 FR 51249, Oct. 1, 1993; 61 FR 14502, Apr. 2, 1996; 62 FR 41881, Aug. 4, 1997; 62 FR 45333, Aug. 27, 1997]

§ 15.32 Test procedures for CPU boards and computer power supplies.

Power supplies and CPU boards used with personal computers and for which separate authorizations are required to be obtained shall be tested as follows:

(a) CPU boards shall be tested as follows:

(1) Testing for radiated emissions shall be performed with the CPU board installed in a typical enclosure but with the enclosure's cover removed so that the internal circuitry is exposed at the top and on at least two sides. Additional components, including a power supply, peripheral devices, and subassemblies, shall be added, as needed, to result in a complete personal computer system. If the oscillator and the microprocessor circuits are contained on separate circuit boards, both boards, typical of the combination that would normally be employed, must be used in the test. Testing shall be in accordance with the procedures specified in § 15.31.

(i) Under these test conditions, the system under test shall not exceed the radiated emission limits specified in § 15.109 by more than 6 dB. Emissions greater than 6 dB that can be identified and documented to originate from a component(s) other than the CPU board being tested, may be dismissed.

(ii) Unless the test in paragraph (a)(1)(i) of this section demonstrates compliance with the limits in § 15.109, a second test shall be performed using the same configuration described above but with the cover installed on the enclosure. Testing shall be in accordance with the procedures specified in § 15.31. Under these test conditions, the system under test shall not exceed the radiated emission limits specified in § 15.109.

(2) In lieu of the procedure in (a)(1) of this section, CPU boards may be tested

47 CFR Ch. I (10–1–97 Edition)

to demonstrate compliance with the limits in § 15.109 using a specified enclosure with the cover installed. Testing for radiated emissions shall be performed with the CPU board installed in a typical system configuration. Additional components, including a power supply, peripheral devices, and subassemblies, shall be added, as needed, to result in a complete personal computer system. If the oscillator and the microprocessor circuits are contained on separate circuit boards, both boards, typical of the combination that would normally be employed, must be used in the test. Testing shall be in accordance with the procedures specified in § 15.31. Under this procedure, CPU boards that comply with the limits in § 15.109 must be marketed together with the specific enclosure used for the test.

(3) The test demonstrating compliance with the AC power line conducted limits specified in § 15.107 shall be performed in accordance with the procedures specified in § 15.31 using a enclosure, peripherals, power supply and subassemblies that are typical of the type with which the CPU board under test would normally be employed.

(b) The power supply shall be tested installed in an enclosure that is typical of the type within which it would normally be installed. Additional components, including peripheral devices, a CPU board, and subassemblies, shall be added, as needed, to result in a complete personal computer system. Testing shall be in accordance with the procedures specified in § 15.31 and must demonstrate compliance with all of the standards contained in this part.

[61 FR 31048, June 19, 1996, as amended at 62 FR 41881, Aug. 4, 1997]

§ 15.33 Frequency range of radiated measurements.

(a) For an intentional radiator, the spectrum shall be investigated from the lowest radio frequency signal generated in the device, without going below 9 kHz, up to at least the frequency shown in this paragraph:

(1) If the intentional radiator operates below 10 GHz: to the tenth harmonic of the highest fundamental frequency or to 40 GHz, whichever is lower.

Federal Communications Commission

§ 15.33

(2) If the intentional radiator operates at or above 10 GHz and below 30 GHz: to the fifth harmonic of the highest fundamental frequency or to 100 GHz, whichever is lower.

(3) If the intentional radiator operates at or above 30 GHz: to the fifth harmonic of the highest fundamental frequency or to 200 GHz, whichever is lower.

(4) If the intentional radiator contains a digital device, regardless of whether this digital device controls the functions of the intentional radiator or the digital device is used for additional control or function purposes other than to enable the operation of the intentional radiator, the frequency range shall be investigated up to the range specified in paragraphs (a)(1) through (a)(3) of this section or the range applicable to the digital device, as shown in paragraph (b)(1) of this section, whichever is the higher frequency range of investigation.

(b) For unintentional radiators:

(1) Except as otherwise indicated in paragraphs (b)(2) or (b)(3) of this section, for an unintentional radiator, including a digital device, the spectrum shall be investigated from the lowest radio frequency signal generated or used in the device, without going below the lowest frequency for which a radiated emission limit is specified, up to the frequency shown in the following table:

Highest frequency generated or used in the device or on which the device operates or tunes (MHz)	Upper frequency of measurement range (MHz)
Below 1.705	30.
1.705–108	1000.
108–500	2000.
500–1000	5000.
Above 1000	5th harmonic of the highest frequency or 40 GHz, whichever is lower.

(2) A unintentional radiator, excluding a digital device, in which the highest frequency generated in the device, the highest frequency used in the device and the highest frequency on which the device operates or tunes are less than 30 MHz and which, in accordance with § 15.109, is required to comply with standards on the level of radiated emissions within the frequency range 9 kHz to 30 MHz, such as a CB receiver or a device designed to conduct its radio

frequency emissions via connecting wires or cables, e.g., a carrier current system not intended to radiate, shall be investigated from the lowest radio frequency generated or used in the device, without going below 9 kHz (25 MHz for CB receivers), up to the frequency shown in the following table. If the unintentional radiator contains a digital device, the upper frequency to be investigated shall be that shown in the table below or in the table in paragraph (b)(1) of this section, as based on both the highest frequency generated and the highest frequency used in the digital device, whichever range is higher.

Highest frequency generated or used in the device or on which the device operates or tunes (MHz)	Upper frequency of measurement range (MHz)
Below 1.705	30
1.705–10	400
10–30	500

(3) Except for a CB receiver, a receiver employing superheterodyne techniques shall be investigated from 30 MHz up to at least the second harmonic of the highest local oscillator frequency generated in the device. If such receiver is controlled by a digital device, the frequency range shall be investigated up to the higher of the second harmonic of the highest local oscillator frequency generated in the device or the upper frequency of the measurement range specified for the digital device in paragraph (b)(1) of this section.

(c) The above specified frequency ranges of measurements apply to the measurement of radiated emissions and, in the case of receivers, the measurement to demonstrate compliance with the antenna conduction limits specified in § 15.111. The frequency range of measurements for AC power line conducted limits is specified in §§ 15.107 and 15.207 and applies to all equipment subject to those regulations. In some cases, depending on the frequency(ies) generated and used by the equipment, only signals conducted onto the AC power lines are required to be measured.

(d) Particular attention should be paid to harmonics and subharmonics of the fundamental frequency as well as

§ 15.35

to those frequencies removed from the fundamental by multiples of the oscillator frequency. Radiation at the frequencies of multiplier states should also be checked.

[54 FR 17714, Apr. 25, 1989, as amended at 61 FR 14502, Apr. 2, 1996]

§ 15.35 Measurement detector functions and bandwidths.

The conducted and radiated emission limits shown in this part are based on the following, unless otherwise specified elsewhere in this part:

(a) On any frequency or frequencies below or equal to 1000 MHz, the limits shown are based on measuring equipment employing a CISPR quasi-peak detector function and related measurement bandwidths, unless otherwise specified. The specifications for the measuring instrument using the CISPR quasi-peak detector can be found in Publication 16 of the International Special Committee on Radio Interference (CISPR) of the International Electrotechnical Commission. As an alternative to CISPR quasi-peak measurements, the responsible party, at its option, may demonstrate compliance with the emission limits using measuring equipment employing a peak detector function, properly adjusted for such factors as pulse desensitization, as long as the same bandwidths as indicated for CISPR quasi-peak measurements are employed.

NOTE: For pulse modulated devices with a pulse-repetition frequency of 20 Hz or less and for which CISPR quasi-peak measurements are specified, compliance with the regulations shall be demonstrated using measuring equipment employing a peak detector function, properly adjusted for such factors as pulse desensitization, using the same measurement bandwidths that are indicated for CISPR quasi-peak measurements.

(b) On any frequency or frequencies above 1000 MHz, unless otherwise stated, the radiated limits shown are based on the use of measurement instrumentation employing an average detector function. When average radiated emission measurements are specified in the regulations, including emission measurements below 1000 MHz, there is also a limit on the radio frequency emissions, as measured using instrumentation with a peak detector function, cor-

47 CFR Ch. I (10–1–97 Edition)

responding to 20 dB above the maximum permitted average limit for the frequency being investigated. Unless otherwise specified, measurements above 1000 MHz shall be performed using a minimum resolution bandwidth of 1 MHz. Measurements of AC power line conducted emissions are performed using a CISPR quasi-peak detector, even for devices for which average radiated emission measurements are specified.

(c) When the radiated emission limits are expressed in terms of the average value of the emission, and pulsed operation is employed, the measured field strength shall be determined by averaging over one complete pulse train, including blanking intervals, as long as the pulse train does not exceed 0.1 seconds. As an alternative (provided the transmitter operates for longer than 0.1 seconds) or in those cases where the pulse train exceeds 0.1 seconds, the measured field strength shall be determined from the average absolute voltage during a 0.1 second interval during which the field strength is at its maximum value. The exact method of calculating the average field strength shall be submitted with any application for certification or shall be retained in the measurement data file for equipment subject to notification or verification.

[54 FR 17714, Apr. 25, 1989, as amended at 56 FR 13083, Mar. 29, 1991; 61 FR 14502, Apr. 2, 1996]

§ 15.37 Transition provisions for compliance with the rules.

Equipment may be authorized, manufactured and imported under the rules in effect prior to June 23, 1989, in accordance with the following schedules:

(a) *For all intentional and unintentional radiators, except for receivers:* Radio frequency equipment verified by the responsible party or for which an application for a grant of equipment authorization is submitted to the Commission on or after June 23, 1992, shall comply with the regulations specified in this part. Radio frequency equipment that is manufactured or imported on or after June 23, 1994, shall comply with the regulations specified in this part.

Federal Communications Commission

§ 15.101

(b) *For receivers:* Receivers subject to the regulations in this part that are manufactured or imported on or after June 23, 1999, shall comply with the regulations specified in this part. However, if a receiver is associated with a transmitter that could not have been authorized under the regulations in effect prior to June 23, 1989, e.g., a transmitter operating under the provisions of § 15.209 or § 15.249 (below 960 MHz), the transition provisions in this section do not apply. Such receivers must comply with the regulations in this part. In addition, receivers are subject to the provisions in paragraph (f) of this section.

(c) There are no restrictions on the operation or marketing of equipment complying with the regulations in effect prior to June 23, 1989.

(d) Prior to May 25, 1991, person shall import, market or operate intentional radiators within the band 902–905 MHz under the provisions of § 15.249. Until that date, the Commission will not issue a grant of equipment authorization for equipment operating under § 15.249 if the equipment is designed to permit operation within the band 902–905 MHz.

(e) *For cordless telephones:* The manufacture and importation of cordless telephones not complying with § 15.214(d) of this part shall cease on or before September 11, 1991. These provisions will not apply to cordless telephones which are repaired or refurbished, or re-imported after repair or refurbishment. Applications for a grant of equipment authorization of cordless telephones not complying with § 15.214(d) of this part will not be accepted by the Commission after May 10, 1991. Cordless telephones that have previously received equipment authorization and that, without modification, already comply with the requirements of § 15.214(d) of this part, need not be re-authorized.

(f) The manufacture or importation of scanning receivers, and frequency converters designed or marketed for use with scanning receivers, that do not comply with the provisions of § 15.121 shall cease on or before April 26, 1994. Effective April 26, 1993, the Commission will not grant equipment authorization for receivers that do not

comply with the provisions of § 15.121 of this part. This paragraph does not prohibit the sale or use of authorized receivers manufactured in the United States, or imported into the United States, prior to April 26, 1994.

(g) For CPU boards and power supplies designed to be used with personal computers: The manufacture and importation of these products shall cease on or before June 19, 1997 unless these products have been authorized under a Declaration of Conformity or a grant of certification, demonstrating compliance with all of the provisions in this part. Limited provisions, as detailed in § 15.101(d), are provided to permit the importation and manufacture of these products subsequent to this date where the CPU boards and/or power supplies are marketed only to personal computer equipment manufacturers.

[54 FR 17714, Apr. 25, 1989; 54 FR 32339, Aug. 7, 1989; 55 FR 25095, June 20, 1990; 56 FR 3785, Jan. 31, 1991; 58 FR 25575, Apr. 27, 1993; 61 FR 31049, June 19, 1996]

Subpart B—Unintentional Radiators

§ 15.101 Equipment authorization of unintentional radiators.

(a) Except as otherwise exempted in §§ 15.23, 15.103, and 15.113, unintentional radiators shall be authorized by the Commission or verified prior to the initiation of marketing, as follows:

Type of device	Equipment authorization required
TV broadcast receiver	Verification
FM broadcast receiver	Verification
CB receiver	Certification
Superregenerative receiver ...	Certification
Scanning receiver	Certification
All other receivers subject to part 15.	Notification
TV interface device	Certification
Cable system terminal device	Notification
Stand-alone cable input selector switch.	Verification
Class B personal computers and peripherals.	Declaration of Conformity or Certification
CPU boards and internal power supplies used with Class B personal computers.	Declaration of Conformity or Certification
Class B personal computers assembled using authorized CPU boards or power supplies.	Declaration of Conformity
Class B external switching power supplies.	Verification
Other Class B digital devices & peripherals.	Verification

§ 15.101

47 CFR Ch. I (10–1–97 Edition)

Type of device	Equipment authorization required
Class A digital devices, peripherals & external switching power supplies.	Verification
All other devices	Verification

(b) Only those receivers that operate (tune) within the frequency range of 30–960 MHz and CB receivers are subject to the authorizations shown in paragraph (a) of this section. However, receivers indicated as being subject to notification that are contained within a transceiver, the transmitter portion of which is subject to type acceptance, certification or notification, shall be authorized under the verification procedure. Receivers operating above 960 MHz or below 30 MHz, except for CB receivers, are exempt from complying with the technical provisions of this part but are subject to § 15.5.

(c) Personal computers shall be authorized in accordance with one of the following methods:

(1) The specific combination of CPU board, power supply and enclosure is tested together and authorized under a Declaration of Conformity or a grant of certification;

(2) The personal computer is authorized under a Declaration of Conformity or a grant of certification, and the CPU board or power supply in that computer is replaced with a CPU board or power supply that has been separately authorized under a Declaration of Conformity or a grant of certification; or

(3) The CPU board and power supply used in the assembly of a personal computer have been separately authorized under a Declaration of Conformity or a grant of certification; and

(4) Personal computers assembled using either of the methods specified in paragraphs (c)(2) or (c)(3) of this section must, by themselves, also be authorized under a Declaration of Conformity if they are marketed. However, additional testing is not required for this Declaration of Conformity, provided the procedures in § 15.102(b) are followed.

(d) Peripheral devices, as defined in § 15.3(r), shall be authorized under a Declaration of Conformity, or a grant of certification, or verified, as appropriate, prior to marketing. Regardless of the provisions of paragraphs (a) or

(c) of this section, if a CPU board, power supply, or peripheral device will always be marketed with a specific personal computer, it is not necessary to obtain a separate authorization for that product provided the specific combination of personal computer, peripheral device, CPU board and power supply has been authorized under a Declaration of Conformity or a grant of certification as a personal computer.

(1) No authorization is required for a peripheral device or a subassembly that is sold to an equipment manufacturer for further fabrication; that manufacturer is responsible for obtaining the necessary authorization prior to further marketing to a vendor or to a user.

(2) Power supplies and CPU boards that have not been separately authorized and are designed for use with personal computers may be imported and marketed only to a personal computer equipment manufacturer that has indicated, in writing, to the seller or importer that they will obtain a Declaration of Conformity or a grant of certification for the personal computer employing these components.

(e) Subassemblies to digital devices are not subject to the technical standards in this part unless they are marketed as part of a system in which case the resulting system must comply with the applicable regulations. Subassemblies include:

(1) Devices that are enclosed solely within the enclosure housing the digital device, except for: power supplies used in personal computers; devices included under the definition of a peripheral device in § 15.3(r); and personal computer CPU boards, as defined in § 15.3(bb);

(2) CPU boards, as defined in § 15.3(bb), other than those used in personal computers, that are marketed without an enclosure or power supply; and

(3) Switching power supplies that are separately marketed and are solely for use internal to a device other than a personal computer.

(f) The procedures for obtaining a grant of certification or notification and for verification and a Declaration

Federal Communications Commission

§ 15.103

of Conformity are contained in subpart J of part 2 of this chapter.

[54 FR 17714, Apr. 25, 1989, as amended at 61 FR 31050, June 19, 1996; 62 FR 41881, Aug. 4, 1997]

§ 15.102 CPU boards and power supplies used in personal computers.

(a) Authorized CPU boards and power supplies that are sold as separate components shall be supplied with complete installation instructions. These instructions shall specify all of the installation procedures that must be followed to ensure compliance with the standards, including, if necessary, the type of enclosure, e.g., a metal enclosure, proper grounding techniques, the use of shielded cables, the addition of any needed components, and any necessary modifications to additional components.

(1) Any additional parts needed to ensure compliance with the standards, except for the enclosure, are considered to be special accessories and, in accordance with § 15.27, must be marketed with the CPU board or power supply.

(2) Any modifications that must be made to a personal computer, peripheral device, CPU board or power supply during installation of a CPU board or power supply must be simple enough that they can be performed by the average consumer. Parts requiring soldering, disassembly of circuitry or other similar modifications are not permitted.

(b) Assemblers of personal computer systems employing modular CPU boards and/or power supplies are not required to test the resulting system provided the following conditions are met:

(1) Each device used in the system has been authorized as required under this part (according to § 15.101(e), some subassemblies used in a personal computer system may not require an authorization);

(2) The original label and identification on each piece of equipment remain unchanged;

(3) Each responsible party's instructions to ensure compliance (including, if necessary, the use of shielded cables or other accessories or modifications) are followed when the system is assembled;

(4) If the system is marketed, the resulting equipment combination is authorized under a Declaration of Conformity pursuant to § 15.101(c)(4) and a compliance information statement, as described in § 2.1077(b), is supplied with the system. Marketed systems shall also comply with the labelling requirements in § 15.19 and must be supplied with the information required under §§ 15.21, 15.27 and 15.105; and

(5) The assembler of a personal computer system may be required to test the system and/or make necessary modifications if a system is found to cause harmful interference or to be noncompliant with the appropriate standards in the configuration in which it is marketed (see §§ 2.909, 15.1, 15.27(d) and 15.101(e)).

[61 FR 31050, June 19, 1996]

§ 15.103 Exempted devices.

The following devices are subject only to the general conditions of operation in §§ 15.5 and 15.29 and are exempt from the specific technical standards and other requirements contained in this part. The operator of the exempted device shall be required to stop operating the device upon a finding by the Commission or its representative that the device is causing harmful interference. Operation shall not resume until the condition causing the harmful interference has been corrected. Although not mandatory, it is strongly recommended that the manufacturer of an exempted device endeavor to have the device meet the specific technical standards in this part.

(a) A digital device utilized exclusively in any transportation vehicle including motor vehicles and aircraft.

(b) A digital device used exclusively as an electronic control or power system utilized by a public utility or in an industrial plant. The term *public utility* includes equipment only to the extent that it is in a dedicated building or large room owned or leased by the utility and does not extend to equipment installed in a subscriber's facility.

(c) A digital device used exclusively as industrial, commercial, or medical test equipment.

(d) A digital device utilized exclusively in an appliance, e.g., microwave

§ 15.105

47 CFR Ch. I (10–1–97 Edition)

oven, dishwasher, clothes dryer, air conditioner (central or window), etc.

(e) Specialized medical digital devices (generally used at the direction of or under the supervision of a licensed health care practitioner) whether used in a patient's home or a health care facility. Non-specialized medical devices, i.e., devices marketed through retail channels for use by the general public, are not exempted. This exemption also does not apply to digital devices used for record keeping or any purpose not directly connected with medical treatment.

(f) Digital devices that have a power consumption not exceeding 6 nW.

(g) Joystick controllers or similar devices, such as a mouse, used with digital devices but which contain only non-digital circuitry or a simple circuit to convert the signal to the format required (e.g., an integrated circuit for analog to digital conversion) are viewed as passive add-on devices, not themselves directly subject to the technical standards or the equipment authorization requirements.

(h) Digital devices in which both the highest frequency generated and the highest frequency used are less than 1.705 MHz and which do not operate from the AC power lines or contain provisions for operation while connected to the AC power lines. Digital devices that include, or make provision for the use of, battery eliminators, AC adaptors or battery chargers which permit operation while charging or that connect to the AC power lines indirectly, obtaining their power through another device which is connected to the AC power lines, do not fall under this exemption.

(i) Responsible parties should note that equipment containing more than one device is not exempt from the technical standards in this part unless all of the devices in the equipment meet the criteria for exemption. If only one of the included devices qualifies for exemption, the remainder of the equipment must comply with any applicable regulations. If a device performs more than one function and all of those functions do not meet the criteria for exemption, the device does not qualify for inclusion under the exemptions.

§ 15.105 Information to the user.

(a) For a Class A digital device or peripheral, the instructions furnished the user shall include the following or similar statement, placed in a prominent location in the text of the manual:

NOTE: This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference in which case the user will be required to correct the interference at his own expense.

(b) For a Class B digital device or peripheral, the instructions furnished the user shall include the following or similar statement, placed in a prominent location in the text of the manual:

NOTE: This equipment has been tested and found to comply with the limits for a Class B digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference in a residential installation. This equipment generates, uses and can radiate radio frequency energy and, if not installed and used in accordance with the instructions, may cause harmful interference to radio communications. However, there is no guarantee that interference will not occur in a particular installation. If this equipment does cause harmful interference to radio or television reception, which can be determined by turning the equipment off and on, the user is encouraged to try to correct the interference by one or more of the following measures:

- Reorient or relocate the receiving antenna.
- Increase the separation between the equipment and receiver.
- Connect the equipment into an outlet on a circuit different from that to which the receiver is connected.
- Consult the dealer or an experienced radio/TV technician for help.

(c) The provisions of paragraphs (a) and (b) of this section do not apply to digital devices exempted from the technical standards under the provisions of § 15.103.

Federal Communications Commission

§ 15.107

(d) For systems incorporating several digital devices, the statement shown in paragraph (a) or (b) of this section needs to be contained only in the instruction manual for the main control unit.

§ 15.107 Conducted limits.

(a) Except for Class A digital devices, for equipment that is designed to be connected to the public utility (AC) power line, the radio frequency voltage that is conducted back onto the AC power line on any frequency or frequencies within the band 450 kHz to 30 MHz shall not exceed 250 microvolts. Compliance with this provision shall be based on the measurement of the radio frequency voltage between each power line and ground at the power terminals.

(b) For a Class A digital device that is designed to be connected to the public utility (AC) power line, the radio frequency voltage that is conducted back onto the AC power line on any frequency or frequencies within the band 450 kHz to 30 MHz shall not exceed the limits in the following table. Compliance with this provision shall be based on the measurement of the radio frequency voltage between each power line and ground at the power terminals. The lower limit applies at the band edges.

Frequency of emission (MHz)	Conducted limit (microvolts)
0.45 to 1.705	1000
1.705 to 30.0	3000

(c) The limits shown in paragraphs (a) and (b) of this section shall not apply to carrier current systems operating as unintentional radiators on frequencies below 30 MHz. In lieu thereof, these carrier current systems shall be subject to the following standards:

(1) For carrier current systems containing their fundamental emission within the frequency band 535–1705 kHz and intended to be received using a standard AM broadcast receiver: no limit on conducted emissions.

(2) For all other carrier current systems: 1000 uV within the frequency band 535–1705 kHz.

(3) Carrier current systems operating below 30 MHz are also subject to the radiated emission limits in § 15.109(e).

(d) The following option may be employed if the conducted emissions exceed the limits in paragraph (a) or (b) of this section, as appropriate, when measured using instrumentation employing a quasi-peak detector function: if the level of the emission measured using the quasi-peak instrumentation is 6 dB, or more, higher than the level of the same emission measured with instrumentation having an average detector and a 9 kHz minimum bandwidth, that emission is considered broadband and the level obtained with the quasi-peak detector may be reduced by 13 dB for comparison to the limits. When employing this option, the following conditions shall be observed:

(1) The measuring instrumentation with the average detector shall employ a linear IF amplifier.

(2) Care must be taken not to exceed the dynamic range of the measuring instrument when measuring an emission with a low duty cycle.

(3) The test report required for verification or for an application for a grant of equipment authorization shall contain all details supporting the use of this option.

(e) As an alternative to the conducted limits shown in paragraphs (a) and (b) of this section, digital devices may be shown to comply with the standards contained in the First Edition of International Special Committee on Radio Interference (CISPR) Pub. 22 (1985), “Limits and Methods of Measurement of Radio Interference Characteristics of Information Technology Equipment,” and the associated Draft International Standards (DISs) adopted in 1992 and published by the International Electrotechnical Commission as documents CISPR/G (Central Office) 2, CISPR/G (Central Office) 5, CISPR/G (Central Office) 9, CISPR/G (Central Office) 11, CISPR/G (Central Office) 12, CISPR/G (Central Office) 13, and CISPR/G (Central Office) 14. This incorporation by reference was approved by the Director of the Federal Register in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. Copies of these CISPR publications may be purchased from

§ 15.109

the American National Standards Institute (ANSI), Sales Department, 11 West 42nd Street, New York, NY 10036, (212) 642-4900. Copies may also be inspected during normal business hours at the following locations: Federal Communications Commission, 2025 M Street, NW., Office of Engineering and Technology (room 7317), Washington, DC, and Office of the Federal Register, 800 N. Capitol Street, NW., suite 700, Washington, DC. In addition:

(1) The test procedure and other requirements specified in this part shall continue to apply to digital devices.

(2) If the conducted emissions are measured to demonstrate compliance with the alternative standards in this paragraph, compliance must also be demonstrated with the radiated emission limits shown in §15.109(g).

(f) Measurements to demonstrate compliance with the conducted limits are not required for devices which only employ battery power for operation and which do not operate from the AC power lines or contain provisions for operation while connected to the AC power lines. Devices that include, or make provision for, the use of battery chargers which permit operating while charging, AC adaptors or battery eliminators or that connect to the AC power lines indirectly, obtaining their power through another device which is connected to the AC power lines, shall be tested to demonstrate compliance with the conducted limits.

[54 FR 17714, Apr. 25, 1989, as amended at 57 FR 33448, July 29, 1992; 58 FR 51249, Oct. 1, 1993]

§ 15.109 Radiated emission limits.

(a) Except for Class A digital devices, the field strength of radiated emissions from unintentional radiators at a distance of 3 meters shall not exceed the following values:

Frequency of emission (MHz)	Field strength (microvolts/meter)
30-88	100
88-216	150
216-960	200
Above 960	500

(b) The field strength of radiated emissions from a Class A digital de-

47 CFR Ch. I (10-1-97 Edition)

vice, as determined at a distance of 10 meters, shall not exceed the following:

Frequency of emission (MHz)	Field strength (microvolts/meter)
30-88	90
88-216	150
216-960	210
Above 960	300

(c) In the emission tables above, the tighter limit applies at the band edges. Sections 15.33 and 15.35 which specify the frequency range over which radiated emissions are to be measured and the detector functions and other measurement standards apply.

(d) For CB receivers, the field strength of radiated emissions within the frequency range of 25-30 MHz shall not exceed 40 microvolts/meter at a distance of 3 meters. The field strength of radiated emissions above 30 MHz from such devices shall comply with the limits in paragraph (a) of this section.

(e) Carrier current systems used as unintentional radiators or other unintentional radiators that are designed to conduct their radio frequency emissions via connecting wires or cables and that operate in the frequency range of 9 kHz to 30 MHz, including devices that deliver the radio frequency energy to transducers, such as ultrasonic devices not covered under part 18 of this chapter, shall comply with the radiated emission limits for intentional radiators provided in §15.209 for the frequency range of 9 kHz to 30 MHz. As an alternative, carrier current systems used as unintentional radiators and operating in the frequency range of 525 kHz to 1705 kHz may comply with the radiated emission limits provided in §15.221(a). At frequencies above 30 MHz, the limits in paragraph (a), (b), or (g) of this section, as appropriate, apply.

(f) For a receiver which employs terminals for the connection of an external receiving antenna, the receiver shall be tested to demonstrate compliance with the provisions of this section with an antenna connected to the antenna terminals unless the antenna conducted power is measured as specified in §15.111(a). If a permanently attached receiving antenna is used, the receiver shall be tested to demonstrate

Federal Communications Commission

§ 15.113

compliance with the provisions of this section.

(g) As an alternative to the radiated emission limits shown in paragraphs (a) and (b) of this section, digital devices may be shown to comply with the standards contained in the First Edition of CISPR Pub. 22 (1985), "Limits and Methods of Measurement of Radio Interference Characteristics of Information Technology Equipment," and the associated Draft International Standards (DISs) adopted in 1992 and published by the International Electrotechnical Commission as documents CISPR/G (Central Office) 2, CISPR/G (Central Office) 5, CISPR/G (Central Office) 9, CISPR/G (Central Office) 11, CISPR/G (Central Office) 12, CISPR/G (Central Office) 13, and CISPR/G (Central Office) 14. This incorporation by reference was approved by the Director of the Federal Register in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. Copies of these CISPR publications may be purchased from the American National Standards Institute (ANSI), Sales Department, 11 West 42nd Street, New York, NY 10036, (212) 642-4900. Copies may also be inspected during normal business hours at the following locations: Federal Communications Commission, 2025 M Street, NW., Office of Engineering and Technology (room 7317), Washington, DC, and Office of the Federal Register, 800 N. Capitol Street, NW., suite 700, Washington, DC. In addition:

(1) The test procedure and other requirements specified in this part shall continue to apply to digital devices.

(2) If, in accordance with §15.33 of this part, measurements must be performed above 1000 MHz, compliance above 1000 MHz shall be demonstrated with the emission limit in paragraph (a) or (b) of this section, as appropriate. Measurements above 1000 MHz may be performed at the distance specified in the CISPR 22 publications for measurements below 1000 MHz provided the limits in paragraphs (a) and (b) of this section are extrapolated to the new measurement distance using an inverse linear distance extrapolation factor (20 dB/decade), e.g., the radiated limit above 1000 MHz for a Class B digital device is 150 uV/m, as measured at a distance of 10 meters.

(3) The measurement distances shown in CISPR Pub. 22, including measurements made in accordance with this paragraph above 1000 MHz, are considered, for the purpose of §15.31(f)(4) of this part, to be the measurement distances specified in this part.

(4) If the radiated emissions are measured to demonstrate compliance with the alternative standards in this paragraph, compliance must also be demonstrated with the conducted limits shown in §15.107(e).

[54 FR 17714, Apr. 25, 1989, as amended at 56 FR 373, Jan. 4, 1991; 58 FR 51249, Oct. 1, 1993]

§ 15.111 Antenna power conduction limits for receivers.

(a) In addition to the radiated emission limits, receivers that operate (tune) in the frequency range 30 to 960 MHz and CB receivers that provide terminals for the connection of an external receiving antenna may be tested to demonstrate compliance with the provisions of §15.109 with the antenna terminals shielded and terminated with a resistive termination equal to the impedance specified for the antenna, provided these receivers also comply with the following: With the receiver antenna terminal connected to a resistive termination equal to the impedance specified or employed for the antenna, the power at the antenna terminal at any frequency within the range of measurements specified in §15.33 shall not exceed 2.0 nanowatts.

(b) CB receivers and receivers that operate (tune) in the frequency range 30 to 960 MHz that are provided only with a permanently attached antenna shall comply with the radiated emission limitations in this part, as measured with the antenna attached.

§ 15.113 Power line carrier systems.

Power line carrier systems, as defined in §15.3(t), are subject only to the following requirements:

(a) A power utility operating a power line carrier system shall submit the details of all existing systems plus any proposed new systems or changes to existing systems to an industry-operated entity as set forth in §90.63(g) of this chapter. No notification to the FCC is required.

(b) The operating parameters of a power line carrier system (particularly the frequency) shall be selected to achieve the highest practical degree of compatibility with authorized or licensed users of the radio spectrum. The signals from this operation shall be contained within the frequency band 9 kHz to 490 kHz. A power line carrier system shall operate on an unprotected, non-interference basis in accordance with §15.5 of this part. If harmful interference occurs, the electric power utility shall discontinue use or adjust its power line carrier operation, as required, to remedy the interference. Particular attention should be paid to the possibility of interference to Loran C operations at 100 kHz.

(c) Power line carrier system apparatus shall be operated with the minimum power possible to accomplish the desired purpose. No equipment authorization is required.

(d) The best engineering principles shall be used in the generation of radio frequency currents by power line carrier systems to guard against harmful interference to authorized radio users, particularly on the fundamental and harmonic frequencies.

(e) Power line carrier system apparatus shall conform to such engineering standards as may be promulgated by the Commission. In addition, such systems should adhere to industry approved standards designed to enhance the use of power line carrier systems.

(f) The provisions of this section apply only to systems operated by a power utility for general supervision of the power system and do not permit operation on electric lines which connect the distribution substation to the customer or house wiring. Such operation can be conducted under the other provisions of this part.

[54 FR 17714, Apr. 25, 1989; 54 FR 32339, Aug. 7, 1989]

§ 15.115 TV interface devices, including cable system terminal devices.

(a) Measurements of the radiated emissions of a TV interface device shall be conducted with the output terminal(s) of the device terminated by a resistance equal to the rated output impedance. The emanations of a TV interface device incorporating an in-

tentional radiator shall not exceed the limits in §15.109 or subpart C of this part, whichever is higher for each frequency. Where it is possible to determine which portion of the device is contributing a particular radio frequency emission, the emissions from the TV interface device portion shall comply with the emission limits in §15.109, and the emissions from the intentional radiator shall comply with subpart C of this part.

(b) Output signal limits:

(1) At any RF output terminal, the maximum measured RMS voltage, in microvolts, corresponding to the peak envelope power of the modulated signal during maximum amplitude peaks across a resistance (R in ohms) matching the rated output impedance of the TV interface device, shall not exceed the following:

(i) For a cable system terminal device or a TV interface device used with a master antenna, 692.8 times the square root of (R) for the video signal and 155 times the square root of (R) for the audio signal.

(ii) For all other TV interface devices, 346.4 times the square root of (R) for the video signal and 77.5 times the square root of (R) for the audio signal.

(2) At any RF output terminal, the maximum measured RMS voltage, in microvolts, corresponding to the peak envelope power of the modulated signal during maximum amplitude peaks across a resistance (R in ohms) matching the rated output impedance of the TV interface device, of any emission appearing on frequencies removed by more than 4.6 MHz below or 7.4 MHz above the video carrier frequency on which the TV interface device is operated shall not exceed the following:

(i) For a cable system terminal device or a TV interface device used with a master antenna, 692.8 times the square root of (R).

(ii) For all other TV interface devices, 10.95 times the square root of (R).

(3) The term *master antenna* used in this section refers to TV interface devices employed for central distribution of television or other video signals within a building. Such TV interface devices must be designed to:

(i) Distribute multiple television signals at the same time;

Federal Communications Commission

§15.115

(ii) Distribute such signals by cable to outlets or TV receivers in multiple rooms in the building in which the TV interface devices are installed; and,

(iii) Distribute all over-the-air or cable signals.

NOTE: Cable-ready video cassette recorders continue to be subject to the provisions for general TV interface devices.

(c) A TV interface device shall be equipped with a transfer switch for connecting the antenna terminals of a receiver selectively either to the receiving antenna or to the radio frequency output of the TV interface device, subject to the following:

(1) When measured in any of its set positions, transfer switches shall comply with the following requirements:

(i) For a cable system terminal device or a TV interface device equipped for use with a cable system or a master antenna, as defined in paragraph (b)(3) of this section, the isolation between the antenna and cable input terminals shall be at least 80 dB from 54 MHz to 216 MHz, at least 60 dB from 216 MHz to 550 MHz and at least 55 dB from 550 MHz to 806 MHz. The 80 dB standard applies at 216 MHz and the 60 dB standard applies at 550 MHz. In the case of a transfer switch requiring a power source, the required isolation shall be maintained in the event the device is not connected to a power source or power is interrupted. The provisions of this paragraph regarding frequencies in the range 550 MHz to 806 MHz are applicable as of June 30, 1997.

(ii) For all other TV interface devices, the maximum voltage, corresponding to the peak envelope power of the modulated video signal during maximum amplitude peaks, in microvolts, appearing at the receiving antenna input terminals when terminated with a resistance (R in ohms) matching the rated impedance of the antenna input of the switch, shall not exceed 0.346 times the square root of (R).

(iii) Measurement to determine compliance with the transfer switch limits shall be made using a connecting cable, where required, between the TV interface device and the transfer switch of the type and length:

(A) Provided with the TV interface device,

(B) Recommended in the instruction manual, or

(C) Normally employed by the consumer.

(2) A TV interface device shall be designed and constructed, to the extent practicable, so as to preclude the possibility that the consumer may inadvertently attach the output of the device to the receiving antenna, if any, without first going through the transfer switch.

(3) A transfer switch is not required for a TV interface device that, when connected, results in the user no longer having any need to receive standard over-the-air broadcast signals via a separate antenna. A transfer switch is not required to be marketed with a cable system terminal device unless that device provides for the connection of an external antenna. A transfer switch is not required for a device that is intended to be used as an accessory to an authorized TV interface device.

(4) An actual transfer switch is not required for a TV interface device, including a cable system terminal device, that has an antenna input terminal(s); provided, the circuitry following the antenna input terminal(s) has sufficient bandwidth to allow the reception of all TV broadcast channels authorized under part 73 of this chapter and: For a cable system terminal device that can alternate between the reception of cable television service and an antenna, compliance with the isolation requirement specified in paragraph (c)(1)(i) of this section can be demonstrated; and, for all other TV interface devices, the maximum voltage appearing at the antenna terminal(s) does not exceed the limit in paragraph (c)(1)(ii) of this section.

(5) If a transfer switch is not required, the following label shall be used in addition to the label shown in §15.19(a):

This device is intended to be attached to a receiver that is not used to receive over-the-air broadcast signals. Connection of this device in any other fashion may cause harmful interference to radio communications and is in violation of the FCC Rules, part 15.

(d) A TV interface device, including a cable system terminal device, shall incorporate circuitry to automatically prevent emanations from the device

§ 15.117

47 CFR Ch. I (10–1–97 Edition)

from exceeding the technical specifications in this part. These circuits shall be adequate to accomplish their functions when the TV interface device is presented, if applicable, with video input signal levels in the range of one to five volts; this requirement is not applicable to a TV interface device that uses a built-in signal source and has no provisions for the connection of an external signal source. For devices that contain provisions for an external signal source but do not contain provisions for the input of an external baseband signal, e.g., some cable system terminal devices, compliance with the provisions of this paragraph shall be demonstrated with a radio frequency input signal of 0 to 25 dBmV.

(e) For cable system terminal devices and TV interface devices used with a master antenna, as defined in paragraph (b)(3) of this section, the holder of the grant of authorization shall specify in the instruction manual or pamphlet, if a manual is not provided, the types of wires or coaxial cables necessary to ensure that the unit complies with the requirements of this part. The holder of the grant of authorization must comply with the provisions of § 15.27. For all other TV interface devices, the wires or coaxial cables used to couple the output signals to the TV receiver shall be provided by the responsible party.

(f) A TV interface device which is submitted to the Commission as a composite device in a single enclosure containing a RF modulator, video source and other component devices shall be submitted on a single application (FCC Form 731) and shall be authorized as a single device.

(g) An external device or accessory that is intended to be attached to a TV interface device shall comply with the technical and administrative requirements set out in the rules under which it operates. For example, a personal computer must be certificated to show compliance with the regulations for digital devices.

(h) Stand-alone switches used to alternate between cable service and an antenna shall provide isolation between the antenna and cable input terminals that is at least 80 dB from 54 MHz to 216 MHz, at least 60 dB from 216

MHz to 550 MHz and at least 55 dB from 550 MHz to 806 MHz. The 80 dB standard applies at 216 MHz and the 60 dB standard applies at 550 MHz. In the case of stand-alone switches requiring a power source, the required isolation shall be maintained in the event the device is not connected to a power source or power is interrupted. The provisions of this paragraph are applicable as of June 30, 1997.

(i) Switches and other devices intended to be used to by-pass the processing circuitry of a cable system terminal device, whether internal to such a terminal device or a stand-alone unit, shall not attenuate the input signal more than 6 dB from 54 MHz to 550 MHz, or more than 8 dB from 550 MHz to 804 MHz. The 6 dB standard applies at 550 MHz. The provisions of this paragraph are applicable June 30, 1997.

[54 FR 17714, Apr. 25, 1989, as amended at 57 FR 33448, July 29, 1992; 59 FR 25341, May 16, 1994; 61 FR 18509, Apr. 26, 1996]

§ 15.117 TV broadcast receivers.

(a) All TV broadcast receivers shipped in interstate commerce or imported from any foreign country into the United States, for sale or resale to the public, shall comply with the provisions of this section. The reference in this section to TV broadcast receivers also includes devices, such as TV interface devices, that incorporate the tuner portion of a TV broadcast receiver and that are equipped with an antenna or antenna terminals that can be used for the off-the-air reception of TV broadcast signals, as authorized under part 73 of this chapter.

(b) TV broadcast receivers shall be capable of adequately receiving all channels allocated by the Commission to the television broadcast service.

(c) On a given receiver, use of the UHF and VHF tuning systems shall provide approximately the same degree of tuning accuracy with approximately the same expenditure of time and effort: *Provided, however,* That this requirement will be considered to be met if the need for routine fine tuning is eliminated on UHF channels.

(1) *Basic tuning mechanism.* If a TV broadcast receiver is equipped to provide for repeated access to VHF television channels at discrete tuning positions, that receiver shall be equipped to provide for repeated access to a minimum of six UHF television channels at discrete tuning positions. Unless a discrete tuning position is provided for each channel allocated to UHF television, each position shall be readily adjustable to a particular UHF channel by the user without the use of tools. If 12 or fewer discrete tuning positions are provided, each position shall be adjustable to receive any channel allocated to UHF television.

NOTE: The combination of detented rotary switch and pushbutton controls is acceptable, provided UHF channels, after their initial selection, can be accurately tuned with an expenditure of time and effort approximately the same as that used in accurately tuning VHF channels. A UHF tuning system comprising five pushbuttons and a separate manual tuning knob is considered to provide repeated access to six channels at discrete tuning positions. A one-knob (VHF/UHF) tuning system providing repeated access to 11 or more discrete tuning positions is also acceptable, provided each of the tuning positions is readily adjustable, without the use of tools, to receive any UHF channel.

(2) *Tuning controls and channel readout.* UHF tuning controls and channel readout on a given receiver shall be comparable in size, location, accessibility and legibility to VHF controls and readout on that receiver.

NOTE: Differences between UHF and VHF channel readout that follow directly from the larger number of UHF television channels available are acceptable if it is clear that a good faith effort to comply with the provisions of this section has been made.

(d) If equipment and controls that tend to simplify, expedite or perfect the reception of television signals (e.g., AFC, visual aids, remote control, or signal seeking capability referred to generally as tuning aids) are incorporated into the VHF portion of a TV broadcast receiver, tuning aids of the same type and comparable capability and quality shall be provided for the UHF portion of that receiver.

(e) If a television receiver has an antenna affixed to the VHF antenna terminals, it must have an antenna designed for and capable of receiving all

UHF television channels affixed to the UHF antenna terminals. If a VHF antenna is provided with but not affixed to a receiver, a UHF antenna shall be provided with the receiver.

(f) The picture sensitivity of a TV broadcast receiver averaged for all channels between 14 and 69 inclusive shall not be more than 8dB larger than the peak picture sensitivity of that receiver averaged for all channels between 2 and 13 inclusive.

(g) The noise figure for any television channel 14 to 69 inclusive shall not exceed 14 dB. A TV receiver model is considered to comply with this noise figure if the maximum noise figure for channels 14–69 inclusive of 97.5% of all receivers within that model does not exceed 14 dB.

(1) The responsible party shall measure the noise figure of a number of UHF channels of the test sample to give reasonable assurance that the UHF noise figure for each channel complies with the above limit.

(2) The responsible party shall insert in his files a statement explaining the basis on which it will rely to ensure that at least 97.5% of all production units of the test sample that are manufactured have a noise figure of no greater than 14 dB.

(3) [Reserved]

(4) In the case of a TV tuner built-in as part of a video tape recorder that uses a power splitter between the antenna terminals of the video tape recorder and the input terminals of the TV tuner or a TV broadcast receiver that uses a power splitter between the antenna terminals of two or more UHF tuners contained within that receiver, 4 dB may be subtracted from the noise figure measured at the antenna terminals of the video tape recorder or TV broadcast receiver for determining compliance of the UHF tuner(s) with the 14 dB noise figure limit.

(h) For a TV broadcast receiver equipped with a cable input selector switch, the selector switch shall provide, in any of its set positions, isolation between the antenna and cable input terminals of at least 80 dB from 54 MHz to 216 MHz, at least 60 dB from 216 MHz to 550 MHz and at least 55 dB from 550 MHz to 806 MHz. The 80 dB standard applies at 216 MHz and the 60

§ 15.118

47 CFR Ch. I (10–1–97 Edition)

dB standard applies at 550 MHz. In the case of a selector switch requiring a power source, the required isolation shall be maintained in the event the device is not connected to a power source or power is interrupted. An actual switch that can alternate between reception of cable television service and an antenna is not required for a TV broadcast receiver, provided compliance with the isolation requirement specified in this paragraph can be demonstrated and the circuitry following the antenna input terminal(s) has sufficient band-width to allow the reception of all TV broadcast channels authorized under this chapter. The provisions of this paragraph regarding frequencies in the range 550 MHz to 806 MHz are applicable as of June 30, 1997.

[54 FR 17714, Apr. 25, 1993, as amended at 59 FR 25341, May 16, 1994; 61 FR 30532, June 17, 1996]

§ 15.118 Cable ready consumer electronics equipment.

(a) All consumer electronics TV receiving equipment marketed in the United States as cable ready or cable compatible shall comply with the provisions of this section. Consumer electronics TV receiving equipment that includes features intended for use with cable service but does not fully comply with the provisions of this section are subject to the labelling requirements of § 15.19(d).

(b) Cable ready consumer electronics equipment shall be capable of receiving all NTSC or similar video channels on channels 1 through 125 of the channel allocation plan set forth in the Electronics Industries Association's "Cable Television Channel Identification Plan, EIA IS-132, May 1994" (EIA IS-132). This incorporation by reference was approved by the Director of the Federal Register in accordance with 5 U.S.C. 522(a) and 1 CFR part 51. Copies of EIA IS-132 may be obtained from: Global Engineering Documents, 3130 South Harbor Boulevard, Santa Anna, CA 92704. Copies of EIA IS-132 may be inspected during normal business hours at the following locations: Federal Communications Commission, 1919 M Street, NW., Dockets Branch (Room 239), Washington, DC, or the Office of

the Federal Register, 800 North Capitol Street, NW., suite 700, Washington, DC.

(c) Cable ready consumer electronics equipment must meet the following technical performance requirements. Compliance with these requirements shall be determined by performing measurements at the unfiltered IF output port. Where appropriate, the Commission will consider allowing alternative measurement methods.

(1) *Adjacent channel interference.* In the presence of a lower adjacent channel CW signal that is 1.5 MHz below the desired visual carrier in frequency and 10 dB below the desired visual carrier in amplitude, spurious signals within the IF passband shall be attenuated at least 55 dB below the visual carrier of the desired signal. The desired input signal shall be an NTSC visual carrier modulated with a 10 IRE flat field with color burst and the aural carrier which is 10 dB below the visual carrier should be unmodulated. Measurements are to be performed for input signal levels of 0 dBmV and +15 dBmV, with the receiver tuned to ten evenly spaced EIA IS-132 channels covering the band 54 MHz to 804 MHz.

(2) *Image channel interference.* Image channel interference within the IF passband shall be attenuated below the visual carrier of the desired channel by at least 60 dB from 54 MHz to 714 MHz and 50 dB from 714 MHz to 804 MHz. The 60 dB standard applies at 714 MHz. In testing for compliance with this standard, the desired input signal is to be an NTSC signal on which the visual carrier is modulated with a 10 IRE flat field with color burst and the aural carrier is unmodulated and 10 dB below the visual carrier. The undesired test signal shall be a CW signal equal in amplitude to the desired visual carrier and located 90 MHz above the visual carrier frequency of the desired channel. Measurements shall be performed for input signals of 0 dBmV and +15 dBmV, with the receiver tuned to at least ten evenly spaced EIA IS-132 channels covering the band 54 MHz to 804 MHz.

(3) *Direct pickup interference.* The direct pickup (DPU) of a co-channel interfering ambient field by a cable ready device shall not exceed the following criteria. The ratio of the desired

Federal Communications Commission

§15.118

to undesired signal levels at the IF passband on each channel shall be at least 45 dB. The average ratio over the six channels shall be at least 50 dB. The desired input signal shall be an NTSC signal having a visual carrier level of 0 dBmV. The visual carrier is modulated with a 10 IRE flat field with color burst, visual to aural carrier ratio of 10 dB, aural carrier unmodulated. The equipment under test (EUT) shall be placed on a rotatable table that is one meter in height. Any excess length of the power cord and other connecting leads shall be coiled on the floor under the table. The EUT shall be immersed in a horizontally polarized uniform CW field of 100 mV/m at a frequency 2.55 MHz above the visual carrier of the EUT tuned channel. Measurements shall be made with the EUT tuned to six EIA IS-132 channels, two each in the low VHF, high VHF and UHF broadcast bands. On each channel, the levels at the IF passband due to the desired and interfering signals are to be measured.

(4) *Tuner overload.* Spurious signals within the IF passband shall be attenuated at least 55 dB below the visual carrier of the desired channel using a comb-like spectrum input with each visual carrier signal individually set at +15 dBmV from 54 to 550 MHz. The desired input signal is to be an NTSC signal on which the visual carrier is modulated with a 10 IRE flat field with color burst and the aural carrier is unmodulated and 10 dB below the visual carrier. Measurements shall be made with the receiver tuned to at least seven evenly spaced EIA IS-132 channels covering the band 54 MHz to 550 MHz. In addition, spurious signals within the IF passband shall be attenuated at least 51 dB below the visual carrier of the desired channel using a comb spectrum input with each signal individually set at +15 dBmV from 550 to 804 MHz. Measurements shall be made with the receiver tuned to at least three evenly spaced EIA IS-132 channels covering the band 550 MHz to 804 MHz.

(5) *Cable input conducted emissions.* (i) Conducted spurious emissions that appear at the cable input to the device must meet the following criteria. The input shall be an NTSC video carrier

modulated with a 10 IRE flat field with color burst at a level of 0 dBmV and with a visual to aural ratio of 10 dB. The aural carrier shall be unmodulated. The peak level of the spurious signals will be measured using a spectrum analyzer connected by a directional coupler to the cable input of the equipment under test. Spurious signal levels must not exceed the limits in the following table:

From 54 MHz up to and including 300 MHz-26 dBmV

From 300 MHz up to and including 450 MHz-20 dBmV

From 450 MHz up to and including 804 MHz-15 dBmV

(ii) The average of the measurements on multiple channels from 450 MHz up to and including 804 MHz shall be no greater than -20 dBmV. Measurements shall be made with the receiver tuned to at least four EIA IS-132 channels in each of the above bands. The test channels are to be evenly distributed across each of the bands. Measurements for conducted emissions caused by sources internal to the device are to be made in a shielded room. Measurements for conducted emissions caused by external signal sources shall be made in an ambient RF field whose field strength is 100 mV/m, following the same test conditions as described in paragraph (c)(3) of this section.

(d) The field strength of radiated emissions from cable ready consumer electronics equipment shall not exceed the limits in §15.109(a) when measured in accordance with the applicable procedures specified in §§15.31 and 15.35 for unintentional radiators, with the following modifications. During testing the NTSC input signal level is to be +15 dBmV, with a visual to aural ratio of 10 dB. The visual carrier is to be modulated by a 10 IRE flat field with color burst; the aural carrier is to be unmodulated. Measurements are to be taken on six EIA IS-132 channels evenly spaced across the required RF input range of the equipment under test.

NOTE: The provisions of paragraphs (a) through (d) of this section are applicable as of June 30, 1997.

[59 FR 25341, May 16, 1994, as amended at 61 FR 18509, Apr. 26, 1996]

§ 15.119 Closed caption decoder requirements for television receivers.

(a) Effective July 1, 1993, all TV broadcast receivers with picture screens 33 cm (13 in) or larger in diameter shipped in interstate commerce, manufactured, assembled, or imported from any foreign country into the United States shall comply with the provisions of this section.

NOTE: This paragraph places no restriction on the shipping or sale of television receivers that were manufactured before July 1, 1993.

(b) *Transmission format.* Closed-caption information is transmitted on line 21 of field 1 of the vertical blanking interval of television signals, in accordance with § 73.682(a)(22) of this chapter.

(c) *Operating modes.* The television receiver will employ customer-selectable modes of operation for TV and Caption. A third mode of operation, Text, may be included on an optional basis. The Caption and Text Modes may contain data in either of two operating channels, referred to in this document as C1 and C2. The television receiver must decode both C1 and C2 captioning, and must display the captioning for whichever channel the user selects. The TV Mode of operation allows the video to be viewed in its original form. The Caption and Text Modes define one or more areas (called “boxes”) on the screen within which caption or text characters are displayed.

NOTE: For more information regarding Text mode, see “Television Captioning for the Deaf: Signal and Display Specifications”, Engineering Report No. E-7709-C, Public Broadcasting Service, dated May 1980, and “TeleCaption II Decoder Module Performance Specification”, National Captioning Institute, Inc., dated November 1985. These documents are available, respectively, from the Public Broadcasting Service, 1320 Braddock Place, Alexandria, VA 22314 and from the National Captioning Institute, Inc., 5203 Leesburg Pike, Falls Church, VA 22041.

(d) *Screen format.* The display area for captioning and text shall fall approximately within the safe caption area as defined in paragraph (n)(12) of this section. This display area will be further divided into 15 character rows of equal height and 32 columns of equal width, to provide accurate placement of text on the screen. Vertically, the display area begins on line 43 and is 195 lines

high, ending on line 237 on an interlaced display. All captioning and text shall fall within these established columns and rows. The characters must be displayed clearly separated from the video over which they are placed. In addition, the user must have the capability to select a black background over which the captioned letters are displaced.

(1) *Caption mode.* In the Caption Mode, text can appear on up to 4 rows simultaneously anywhere on the screen within the defined display area. In addition, a solid space equal to one column width may be placed before the first character and after the last character of each row to enhance legibility. The caption area will be transparent anywhere that either:

(i) No standard space character or other character has been addressed and no accompanying solid space is needed; or,

(ii) An accompanying solid space is used and a “transparent space” special character has been addressed which does not immediately precede or follow a displayed character.

(2) [Reserved]

(e) *Presentation format.* In analyzing the presentation of characters, it is convenient to think in terms of a non-visible cursor which marks the screen position at which the next event in a given mode and data channel will occur. The receiver remembers the cursor position for each mode even when data are received for a different address in an alternate mode or data channel.

(1) *Screen addressing.* Two kinds of control codes are used to move the cursor to specific screen locations. In Caption Mode, these addressing codes will affect both row and column positioning. In Text Mode, the codes affect only column positioning. In both modes, the addressing codes are optional. Default positions are defined for each mode and style when no addressing code is provided.

(i) The first type of addressing code is the Preamble Address Code (PAC). It assigns a row number and one of eight “indent” figures. Each successive indent moves the cursor four columns to the right (starting from the left margin). Thus, an indent of 0 places the

cursor at Column 1, an indent of 4 sets it at Column 5, etc. The PAC indent is non-destructive to displayable characters. It will not affect the display to the left of the new cursor position on the indicated row. Note that Preamble Address Codes also set initial attributes for the displayable characters which follow. See paragraph (h) of this section and the Preamble Address Code table.

(ii) The second type of addressing code is the Tab Offset, which is one of three Miscellaneous Control Codes. Tab Offset will move the cursor one, two, or three columns to the right. The character cells skipped over will be unaffected; displayable characters in these cells, if any, will remain intact while empty cells will remain empty, in the same manner that a PAC indent is non-destructive.

(2) [Reserved]

(f) *Caption Mode.* There are three styles of presenting text in Caption Mode: roll-up, pop-on, and paint-on. Character display varies significantly with the style used, but certain rules of character erasure are common to all styles. A character can be erased by addressing another character to the same screen location or by backspacing over the character from a subsequent location on the same row. The entire displayed memory will be erased instantly by receipt of an Erase Displayed Memory command. Both displayed memory and non-displayed memory will be entirely erased simultaneously by either: The user switching receiver channels or data channels (C1/C2) or fields (F1/F2) in decoders so equipped; the loss of valid data (see paragraph (j) of this section); or selecting non-captioning receiver functions which use the display memory of the decoder. Receipt of an End of Caption command will cause a displayed caption to become non-displayed (and vice versa) without being erased from memory. Changing the receiver to a non-captioning mode which does not require use of the decoder's display memory will leave that memory intact, and the decoder will continue to process data as if the caption display were selected.

(1) *Roll-up.* Roll-up style captioning is initiated by receipt of one of three Miscellaneous Control Codes that de-

termine the maximum number of rows displayed simultaneously, either 2, 3 or 4 contiguous rows. These are the three Roll-Up Caption commands.

(i) The bottom row of the display is known as the "base row". The cursor always remains on the base row. Rows of text roll upwards into the contiguous rows immediately above the base row to create a "window" 2 to 4 rows high.

(ii) The Roll-Up command, in normal practice, will be followed (not necessarily immediately) by a Preamble Address Code indicating the base row and the horizontal indent position. If no Preamble Address Code is received, the base row will default to Row 15 or, if a roll-up caption is currently displayed, to the same base row last received, and the cursor will be placed at Column 1. If the Preamble Address Code received contains a different base row than that of a currently displayed caption, the entire window will move intact (and without erasing) to the new base row immediately.

(iii) Each time a Carriage Return is received, the text in the top row of the window is erased from memory and from the display or scrolled off the top of the window. The remaining rows of text are each rolled up into the next highest row in the window, leaving the base row blank and ready to accept new text. This roll-up must appear smooth to the user, and must take no more than 0.433 second to complete. The cursor is automatically placed at Column 1 (pending receipt of a Preamble Address Code).

(iv) Increasing or decreasing the number of roll-up rows instantly changes the size of the active display window, appropriately turning on or off the display of the top one or two rows. A row which is turned off should also be erased from memory.

(v) Characters are always displayed immediately when received by the receiver. Once the cursor reaches the 32nd column position on any row, all subsequent characters received prior to a Carriage Return, Preamble Address Code, or Backspace will be displayed in that column replacing any previous character occupying that address.

(vi) The cursor moves automatically one column to the right after each

character or Mid-Row Code received. A Backspace will move the cursor one column to the left, erasing the character or Mid-Row Code occupying that location. (A Backspace received when the cursor is in Column 1 will be ignored.)

(vii) The Delete to End of Row command will erase from memory any characters or control codes starting at the current cursor location and in all columns to its right on the same row. If no displayable characters remain on the row after the Delete to End of Row is acted upon, the solid space (if any) for that row should also be erased to conform with the following provisions.

(viii) If a solid space is used for legibility, it should appear when the first displayable character (not a transparent space) or Mid-Row Code is received on a row, not when the Preamble Address Code, if any, is given. A row on which there are no displayable characters or Mid-Row Codes will not display a solid space, even when rolled up between two rows which do display a solid space.

(ix) If the reception of data for a row is interrupted by data for the alternate data channel or for Text Mode, the display of caption text will resume from the same cursor position if a Roll-Up Caption command is received and no Preamble Address Code is given which would move the cursor.

(x) A roll-up caption remains displayed until one of the standard caption erasure techniques is applied. Receipt of a Resume Caption Loading command (for pop-on style) or a Resume Direct Captioning command (for paint-on style) will not affect a roll-up display. Receipt of a Roll-Up Caption command will cause any pop-on or paint-on caption to be erased from displayed memory and non-displayed memory.

(2) *Pop-on*. Pop-on style captioning is initiated by receipt of a Resume Caption Loading command. Subsequent data are loaded into a non-displayed memory and held there until an End of Caption command is received, at which point the non-displayed memory becomes the displayed memory and vice versa. (This process is often referred to as “flipping memories” and does not automatically erase memory.) An End

of Caption command forces the receiver into pop-on style if no Resume Caption Loading command has been received which would do so. The display will be capable of 4 full rows, not necessarily contiguous, simultaneous anywhere on the screen.

(i) Preamble Address Codes can be used to move the cursor around the screen in random order to place captions on Rows 1 to 15. Carriage Returns have no effect on cursor location during caption loading.

(ii) The cursor moves automatically one column to the right after each character or Mid-Row Code received. Receipt of a Backspace will move the cursor one column to the left, erasing the character or Mid-Row Code occupying that location. (A Backspace received when the cursor is in Column 1 will be ignored.) Once the cursor reaches the 32nd column position on any row, all subsequent characters received prior to a Backspace, an End of Caption, or a Preamble Address Code, will replace any previous character at that location.

(iii) The Delete to End of Row command will erase from memory any characters or control codes starting at the current cursor location and in all columns to its right on the same row. If no displayable characters remain on a row after the Delete to End of Row is acted upon, the solid space (if any) for that element should also be erased.

(iv) If data reception is interrupted during caption loading by data for the alternate caption channel or for Text Mode, caption loading will resume at the same cursor position if a Resume Caption Loading command is received and no Preamble Address Code is given that would move the cursor.

(v) Characters remain in non-displayed memory until an End of Caption command flips memories. The caption will be erased without being displayed upon receipt of an Erase Non-Displayed Memory command, a Roll-Up Caption command, or if the user switches receiver channels, data channels or fields, or upon the loss of valid data (see paragraph (j) of this section).

(vi) A pop-on caption, once displayed, remains displayed until one of the standard caption erasure techniques is

applied or until a Roll-Up Caption command is received. Characters within a displayed pop-on caption will be replaced by receipt of the Resume Direct Captioning command and paint-on style techniques (see below).

(3) *Paint-on.* Paint-on style captioning is initiated by receipt of a Resume Direct Captioning command. Subsequent data are addressed immediately to displayed memory without need for an End of Caption command.

(i) Preamble Address Codes can be used to move the cursor around the screen in random order to display captions on Rows 1 to 15. Carriage Returns have no effect on cursor location during direct captioning. The cursor moves automatically one column to the right after each character or Mid-Row Code is received. Receipt of a Backspace will move the cursor one column to the left, erasing the character or Mid-Row Code occupying that location. (A Backspace received when the cursor is in Column 1 will be ignored.) Once the cursor reaches the 32nd column position on any row, all subsequent characters received prior to a Preamble Address Code or Backspace will be displayed in that column replacing any previous character occupying that location.

(ii) The Delete to End of Row command will erase from memory any characters or control codes starting at the current cursor location and in all columns to its right on the same row. If no displayable characters remain on the row after the Delete to End of Row is acted upon, the solid space (if any) for that element should also be erased.

(iii) If the reception of data is interrupted during the direct captioning by data for the alternate caption channel or for Text Mode, the display of caption text will resume at the same cursor position if a Resume Direct Captioning command is received and no Preamble Address Code is given which would move the cursor.

(iv) Characters remain displayed until one of the standard caption erasure techniques is applied or until a Roll-Up Caption command is received. An End of Caption command leaves a paint-on caption fully intact in non-displayed memory. In other words, a paint-on style caption behaves pre-

cisely like a pop-on style caption which has been displayed.

(g) *Character format.* Characters are to be displayed on the screen within a character "cell" which is the height and width of a single row and column. The following codes define the displayable character set. Television receivers manufactured prior to January 1, 1996 and having a character resolution of 5×7 dots, or less, may display the allowable alternate characters in the character table. A statement must be in a prominent location on the box or other package in which the receiver is to be marketed, and information must be in the owner's manual, indicating the receiver displays closed captioning in upper case only.

CHARACTER SET TABLE

Special Characters

These require two bytes for each symbol. Each hex code as shown will be preceded by a 11h for data channel 1 or by a 19h for data channel 2. For example: 19h 37h will place a musical note in data channel 2.

HEX	Example	Alternate	Description
30	®	See note ¹	Registered mark symbol
31	°		Degree sign
32	½		½
33			Inverse query
34	™	See note ¹	Trademark symbol
35	¢		Cents sign
36	£		Pounds Sterling sign
37	X		Music note
38	â	A	Lower-case a with grave accent
39			Transparent space
3A	è	E	Lower-case e with grave accent
3B	â	A	Lower-case a with circumflex
3C	ê	E	Lower-case e with circumflex
3D	î	I	Lower-case i with circumflex
3E	ô	O	Lower-case o with circumflex
3F	û	U	Lower-case u with circumflex

¹NOTE: The registered and trademark symbols are used to satisfy certain legal requirements. There are various legal ways in which these symbols may be drawn or displayed. For example, the trademark symbol may be drawn with the "TM" next to the "M" or over the "M". It is preferred that the trademark symbol be superscripted, i.e., XYZTM. It is left to each individual manufacturer to interpret these symbols in any way that meets the legal needs of the user.

Standard characters

HEX	Example	Alternate	Description
20			Standard space
21	!		Exclamation mark
22	'		Quotation mark
23	#		Pounds (number) sign
24	\$		Dollar sign
25	%		Percentage sign

HEX	Example	Alternate	Description
26	&		Ampersand
27	'		Apostrophe
28	(		Open parentheses
29	)		Close parentheses
2A	á	A	Lower-case a with acute accent
2B	+		Plus sign
2C	,		Comma
2D	–		Minus (hyphen) sign
2E	.		Period
2F	/		Slash
30	0		Zero
31	1		One
32	2		Two
33	3		Three
34	4		Four
35	5		Five
36	6		Six
37	7		Seven
38	8		Eight
39	9		Nine
3A	:		Colon
3B	;		Semi-colon
3C	<		Less than sign
3D	=		Equal sign
3E	>		Greater than sign
3F	?		Question mark
40	@		At sign
41	A		Upper-case A
42	B		Upper-case B
43	C		Upper-case C
44	D		Upper-case D
45	E		Upper-case E
46	F		Upper-case F
47	G		Upper-case G
48	H		Upper-case H
49	I		Upper-case I
4A	J		Upper-case J
4B	K		Upper-case K
4C	L		Upper-case L
4D	M		Upper-case M
4E	N		Upper-case N
4F	O		Upper-case O
50	P		Upper-case P
51	Q		Upper-case Q
52	R		Upper-case R
53	S		Upper-case S
54	T		Upper-case T
55	U		Upper-case U
56	V		Upper-case V
57	W		Upper-case W
58	X		Upper-case X
59	Y		Upper-case Y
5A	Z		Upper-case Z
5B	[		Open bracket
5C	é	E	Lower-case e with acute accent
5D	]		Close bracket
5E	í	I	Lower-case i with acute accent
5F	ó	O	Lower-case o with acute accent
60	ú	U	Lower-case u with acute accent
61	a	A	Lower-case a
62	b	B	Lower-case b
63	c	C	Lower-case c
64	d	D	Lower-case d
65	e	E	Lower-case e
66	f	F	Lower-case f
67	g	G	Lower-case g
68	h	H	Lower-case h
69	i	I	Lower-case i
6A	j	J	Lower-case j
6B	k	K	Lower-case k
6C	l	L	Lower-case l
6D	m	M	Lower-case m
6E	n	N	Lower-case n

HEX	Example	Alternate	Description
6F	o	O	Lower-case o
70	p	P	Lower-case p
71	q	Q	Lower-case q
72	r	R	Lower-case r
73	s	S	Lower-case s
74	t	T	Lower-case t
75	u	U	Lower-case u
76	v	V	Lower-case v
77	w	W	Lower-case w
78	x	X	Lower-case x
79	y	Y	Lower-case y
7A	z	Z	Lower-case z
7B	ç	C	Lower-case c with cedilla
7C	÷		Division sign
7D	Ñ		Upper-case N with tilde
7E	ñ	Ñ	Lower-case n with tilde
7F	■		Solid block

(h) *Character Attributes*—(1) *Transmission of Attributes*. A character may be transmitted with any or all of four attributes: Color, italics, underline, and flash. All of these attributes are set by control codes included in the received data. An attribute will remain in effect until changed by another control code or until the end of the row is reached. Each row begins with a control code which sets the color and underline attributes. (White non-underlined is the default display attribute if no Preamble Address Code is received before the first character on an empty row.) Attributes are not affected by transparent spaces within a row.

(i) All Mid-Row Codes and the Flash On command are spacing attributes which appear in the display just as if a standard space (20h) had been received. Preamble Address Codes are non-spacing and will not alter any attributes when used to position the cursor in the midst of a row of characters.

(ii) The color attribute has the highest priority and can only be changed by the Mid-Row Code of another color. Italics has the next highest priority. If characters with both color and italics are desired, the italics Mid-Row Code must follow the color assignment. Any color Mid-Row Code will turn off italics. If the least significant bit of a Preamble Address Code or of a color or italics Mid-Row Code is a 1 (high), underlining is turned on. If that bit is a 0 (low), underlining is off.

(iii) The flash attribute is transmitted as a Miscellaneous Control Code. The Flash On command will not alter the status of the color, italics, or underline attributes. However, any color

or italics Mid-Row Code will turn off flash.

(iv) Thus, for example, if a red, italicized, underlined, flashing character is desired, the attributes must be received in the following order: a red Mid-Row or Preamble Address Code, an italics Mid-Row Code with underline bit, and the Flash On command. The character will then be preceded by three spaces (two if red was assigned via a Preamble Address Code).

(2) *Display of attributes.* The underline attribute will be displayed by drawing a line beneath the character in the same color as the character. The flash attribute will be displayed by causing the character to blink from the display at least once per second. The italic attribute must be capable of being displayed by either a special italic font, or by the modification of the standard font by slanting. The user may be given the option to select other methods of italic display as well. The support of the color attributes is optional. If the color attributes are supported, they will be displayed in the color they have been assigned. If color attributes are not supported, the display may be in color, but all color changes will be ignored.

(i) *Control codes.* There are three different types of control codes used to identify the format, location, attributes, and display of characters: Preamble Address Codes, Mid-Row Codes, and Miscellaneous Control Codes.

(1) Each control code consists of a pair of bytes which are always transmitted together in a single field of line 21 and which are normally transmitted twice in succession to help insure correct reception of the control instructions. The first of the control code bytes is a non-printing character in the range 10h to 1Fh. The second byte is always a printing character in the range 20h to 7Fh. Any such control code pair received which has not been assigned a function is ignored. If the non-printing character in the pair is in the range 00h to 0Fh, that character alone will be ignored and the second character will be treated normally.

(2) If the second byte of a control code pair does not contain odd parity (see paragraph (j) of this section), then

the pair is ignored. The redundant transmission of the pair will be the instruction upon which the receiver acts.

(3) If the first byte of the first transmission of a control code pair fails the parity check, then that byte is inserted into the currently active memory as a solid block character (7Fh) followed by whatever the second byte is. Again, the redundant transmission of the pair will be the controlling instruction.

(4) If the first transmission of a control code pair passes parity, it is acted upon within one video frame. If the next frame contains a perfect repeat of the same pair, the redundant code is ignored. If, however, the next frame contains a different but also valid control code pair, this pair, too, will be acted upon (and the receiver will expect a repeat of this second pair in the next frame). If the first byte of the expected redundant control code pair fails the parity check and the second byte is identical to the second byte in the immediately preceding pair, then the expected redundant code is ignored. If there are printing characters in place of the redundant code, they will be processed normally.

(5) There is provision for decoding a second data channel. The second data channel is encoded with the same control codes and procedures already described. The first byte of every control code pair indicates the data channel (C1/C2) to which the command applies. Control codes which do not match the data channel selected by the user, and all subsequent data related to that control code, are ignored by the receiver.

MID-ROW CODES

Data channel 1	Data channel 2	Attribute description
11 20	19 20	White.
11 21	19 21	White Underline.
11 22	19 22	Green.
11 23	19 23	Green Underline.
11 24	19 24	Blue.
11 25	19 25	Blue Underline.
11 26	19 26	Cyan.
11 27	19 27	Cyan Underline.
11 28	19 28	Red.
11 29	19 29	Red Underline.
11 2A	19 2A	Yellow.
11 2B	19 2B	Yellow Underline.
11 2C	19 2C	Magenta.
11 2D	19 2D	Magenta Underline.
11 2E	19 2E	Italics.
11 2F	19 2F	Italics Underline.

§ 15.119

MISCELLANEOUS CONTROL CODES

Data chan- nel 1	Data chan- nel 2	Mne- monic	Command description
14 20	1C 20	RCL	Resume caption load- ing.
14 21	1C 21	BS	Backspace.
14 22	1C 22	AOF	Reserved (formerly Alarm Off).
14 23	1C 23	AON	Reserved (formerly Alarm On).
14 24	1C 24	DER	Delete to End of Row.
14 25	1C 25	RU2	Roll-Up Captions–2 Rows.
14 26	1C 26	RU3	Roll-Up Captions–3 Rows.
14 27	1C 27	RU4	Roll-Up Captions–4 Rows.
14 28	1C 28	FON	Flash On.

47 CFR Ch. I (10–1–97 Edition)

MISCELLANEOUS CONTROL CODES—Continued

Data chan- nel 1	Data chan- nel 2	Mne- monic	Command description
14 29	1C 29	RDC	Resume Direct Cap- tioning.
14 2A	1C 2A	TR	Text Restart.
14 2B	1C 2B	RTD	Resume Text Display.
14 2C	1C 2C	EDM	Erase Displayed Mem- ory.
14 2D	1C 2D	CR	Carriage Return.
14 2E	1C 2E	ENM	Erase Non-Displayed Memory.
14 2F	1C 2F	EOC	End of Caption (Flip Memories).
17 21	1F 21	TO1	Tab Offset 1 Column.
17 22	1F 22	TO2	Tab Offset 2 Columns.
17 23	1F 23	TO3	Tab Offset 3 Columns.

PREAMBLE ADDRESS CODES

	Row 1	Row 2	Row 3	Row 4	Row 5	Row 6	Row 7	Row 8	Row 9	Row 10	Row 11	Row 12	Row 13	Row 14	Row 15
First byte of code pair:															
Data Channel 1	11	11	12	12	15	15	16	16	17	17	10	13	13	14	14
Data Channel 2	19	19	1A	1A	1D	1D	1E	1E	1F	1F	18	1B	1B	1C	1C
Second byte of code pair:															
White	40	60	40	60	40	60	40	60	40	60	40	40	60	40	60
White Underline	41	61	41	61	41	61	41	61	41	61	41	41	61	41	61
Green	42	62	42	62	42	62	42	62	42	62	42	42	62	42	62
Green Underline	43	63	43	63	43	63	43	63	43	63	43	43	63	43	63
Blue	44	64	44	64	44	64	44	64	44	64	44	44	64	44	64
Blue Underline	45	65	45	65	45	65	45	65	45	65	45	45	65	45	65
Cyan	46	66	46	66	46	66	46	66	46	66	46	46	66	46	66
Cyan Underline	47	67	47	67	47	67	47	67	47	67	47	47	67	47	67
Red	48	68	48	68	48	68	48	68	48	68	48	48	68	48	68
Red Underline	49	69	49	69	49	69	49	69	49	69	49	49	69	49	69
Yellow	4A	6A	4A	6A	4A	6A	4A	6A	4A	6A	4A	4A	6A	4A	6A
Yellow Underline	4B	6B	4B	6B	4B	6B	4B	6B	4B	6B	4B	4B	6B	4B	6B
Magenta	4C	6C	4C	6C	4C	6C	4C	6C	4C	6C	4C	4C	6C	4C	6C
Magenta Underline	4D	6D	4D	6D	4D	6D	4D	6D	4D	6D	4D	4D	6D	4D	6D
White Italics	4E	6E	4E	6E	4E	6E	4E	6E	4E	6E	4E	4E	6E	4E	6E
White Italics Underline	4F	6F	4F	6F	4F	6F	4F	6F	4F	6F	4F	4F	6F	4F	6F
White 0	50	70	50	70	50	70	50	70	50	70	50	50	70	50	70
White 0 Underline	51	71	51	71	51	71	51	71	51	71	51	51	71	51	71
Indent 4	52	72	52	72	52	72	52	72	52	72	52	52	72	52	72
Indent 4 Underline	53	73	53	73	53	73	53	73	53	73	53	53	73	53	73
Indent 8	54	74	54	74	54	74	54	74	54	74	54	54	74	54	74
Indent 8 Underline	55	75	55	75	55	75	55	75	55	75	55	55	75	55	75
Indent 12	56	76	56	76	56	76	56	76	56	76	56	56	76	56	76
Indent 12 Underline	57	77	57	77	57	77	57	77	57	77	57	57	77	57	77
Indent 16	58	78	58	78	58	78	58	78	58	78	58	58	78	58	78
Indent 16 Underline	59	79	59	79	59	79	59	79	59	79	59	59	79	59	79
Indent 20	5A	7A	5A	7A	5A	7A	5A	7A	5A	7A	5A	5A	7A	5A	7A
Indent 20 Underline	5B	7B	5B	7B	5B	7B	5B	7B	5B	7B	5B	5B	7B	5B	7B
Indent 24	5C	7C	5C	7C	5C	7C	5C	7C	5C	7C	5C	5C	7C	5C	7C
Indent 24 Underline	5D	7D	5D	7D	5D	7D	5D	7D	5D	7D	5D	5D	7D	5D	7D
Indent 28	5E	7E	5E	7E	5E	7E	5E	7E	5E	7E	5E	5E	7E	5E	7E
Indent 28 Underline	5F	7F	5F	7F	5F	7F	5F	7F	5F	7F	5F	5F	7F	5F	7F

NOTE: All indent codes (second byte equals 50h–5fh, 70th–7fh) assign white as the color attribute.

(j) *Data rejection.* The receiver should provide an effective procedure to verify data. A receiver will reject data if the data is invalid, or if the data is directed to the data channel or field not selected by the user. Invalid data is any data that fails to pass a check for odd parity, or which, having passed the parity check, is assigned no function.

(1) If a print character fails to pass a check for parity, a solid block (7Fh) should be displayed in place of the failed character. In addition, valid data can be corrupted in many ways and may not be suitable for display. For example, repeated fields, skipped fields and altered field sequences are all possible from consumer video equipment and might present meaningless captions.

(2) The receiver will ignore data rejected due to being directed to a deselected field or channel. However, this will not cause the display to be disabled.

(k) *Automatic display enable/disable.* The receiver shall provide an automatic enable/disable capability to prevent the display of invalid or incomplete data, when the user selects the Caption Mode. The display should automatically become enable after the receiver verifies the data as described in paragraph (j) of this section. The display will be automatically disabled when there is a sustained detection of invalid data. The display will be re-enabled when the data verification process has been satisfied once again.

(l) *Compatibility with Cable Security Systems.* Certain cable television security techniques, such as signal encryption and copy protection, can alter the television signal so that some methods of finding line 21 will not work. In particular, counting of lines or timing from the start of the vertical blanking interval may cause problems. Caption decoding circuitry must function properly when receiving signals from cable security systems that were designed and marketed prior to April 5, 1991. Further information concerning such systems is available from the National Cable Television Association, Inc., Washington, DC, and from the Electronic Industries Association, Washington, DC.

(m) *Labelling and consumer information requirements.* The box or other package in which the individual television receiver is to be marketed shall carry a statement in a prominent location, visible to the buyer before purchase, which reads as follows:

This television receiver provides display of television closed captioning in accordance with § 15.119 of the FCC rules.

Receivers that do not support color attributes or text mode, as well as receivers that display only upper-case characters pursuant to paragraph (g) of this section, must include with the statement, and in the owner's manual, language indicating that those features are not supported.

(n) *Glossary of terms.* The following terms are used to describe caption decoder specifications:

(1) *Base row:* The bottom row of a roll-up display. The cursor always remains on the base row. Rows of text roll upwards into the contiguous rows immediately above the base row.

(2) *Box:* The area surrounding the active character display. In Text Mode, the box is the entire screen area defined for display, whether or not displayable characters appear. In Caption Mode, the box is dynamically redefined by each caption and each element of displayable characters within a caption. The box (or boxes, in the case of a multiple-element caption) includes all the cells of the displayed characters, the non-transparent spaces between them, and one cell at the beginning and end of each row within a caption element in those decoders that use a solid space to improve legibility.

(3) *Caption window:* The invisible rectangle which defines the top and bottom limits of a roll-up caption. The window can be 2 to 4 rows high. The lowest row of the window is called the base row.

(4) *Cell:* The discrete screen area in which each displayable character or space may appear. A cell is one row high and one column wide.

(5) *Column:* One of 32 vertical divisions of the screen, each of equal width, extending approximately across the full width of the safe caption area as defined in paragraph (n)(12) of this section. Two additional columns, one

at the left of the screen and one at the right, may be defined for the appearance of a box in those decoders which use a solid space to improve legibility, but no displayable characters may appear in those additional columns. For reference, columns may be numbered 0 to 33, with columns 1 to 32 reserved for displayable characters.

(6) *Displayable character*: Any letter, number or symbol which is defined for on-screen display, plus the 20h space.

(7) *Display disable*: To turn off the display of captions or text (and accompanying background) at the receiver, rather than through codes transmitted on line 21 which unconditionally erase the display. The receiver may disable the display because the user selects an alternate mode, e.g., TV Mode, or because no valid line 21 data is present.

(8) *Display enable*: To allow the display of captions or text when they are transmitted on line 21 and received as valid data. For display to be enabled, the user must have selected Caption Mode or Text Mode, and valid data for the selected mode must be present on line 21.


(9) *Element*: In a pop-on or paint-on style caption, each contiguous area of cells containing displayable characters

and non-transparent spaces between those characters. A single caption may have multiple elements. An element is not necessarily a perfect rectangle, but may include rows of differing widths.

(10) *Erase Display*: In Caption Mode, to clear the screen of all characters (and accompanying background) in response to codes transmitted on line 21. (The caption service provider can accomplish the erasure either by sending an Erase Displayed Memory command or by sending an Erase Non-Displayed Memory command followed by an End of Caption command, effectively making a blank caption “appear”.) Display can also be erased by the receiver when the caption memory erasure conditions are met, such as the user changing TV channels.

(11) *Row*: One of 15 horizontal divisions of the screen, extending across the full height of the safe caption area as defined in paragraph (n)(12) of this section.

(12) *Safe caption area*: The area of the television picture within which captioning and text shall be displayed to ensure visibility of the information on the majority of home television receivers. The safe caption area is specified as shown in the following figure:



The dimensions of the above figure shall be as follows:

Label	Dimensions	Percent of television picture height
A	Television picture height	100.0
B	Television picture width	133.33
C	Height of safe caption area	80.0
D	Width of safe caption area	106.67
E	Vertical position of safe caption area.	10.0
F	Horizontal position of safe caption area.	13.33

(13) *Special characters*: Displayable characters (except for “transparent space”) which require a two-byte sequence of one non-printing and one printing character. The non-printing byte varies depending on the data channel. Regular characters require unique one-byte codes which are the same in either data channel.

(14) *Text*: When written with an upper-case “T”, refers to the Text Mode. When written with a lower-case “t”, refers to any combination of displayable characters.

(15) *Transparent space*: Transmitted as a special character, it is a one-column-wide space behind which program video is always visible (except when a transparent space immediately precedes or follows a displayable character and solid box is needed to make that character legible).

[56 FR 27201, June 13, 1991, as amended at 57 FR 19094, May 4, 1992; 58 FR 44893, Aug. 25, 1993]

§ 15.121 Scanning receivers and frequency converters designed or marketed for use with scanning receivers.

(a) Except as provided in paragraph (b) of this section, scanning receivers, and frequency converters designed or marketed for use with scanning receivers, must be incapable of operating (tuning), or readily being altered by the user to operate, within the frequency bands allocated to the Domestic Public Cellular Radio Telecommunications Service in part 22 of

this chapter (cellular telephone bands). Receivers capable of “readily being altered by the user” include but are not limited to, those for which the ability to receive transmissions in the cellular telephone bands can be added by clipping the leads of, or installing, a simple component such as a diode, resistor and/or jumper wire; replacing a plug-in semiconductor chip; or programming a semiconductor chip using special access codes or an external device, such as a personal computer. Scanning receivers, and frequency converters designed or marketed for use with scanning receivers, must also be incapable of converting digital cellular transmissions to analog voice audio.

(b) Scanning receivers, and frequency converters designed or marketed for use with scanning receivers, that are manufactured exclusively for, and marketed exclusively to, entities described in 18 U.S.C. 2512(2) are not subject to the requirements of paragraph (a) of this section.

[58 FR 25575, Apr. 27, 1993; 58 FR 29454, May 20, 1993]

Subpart C—Intentional Radiators

§ 15.201 Equipment authorization requirement.

(a) Intentional radiators operated as carrier current systems and devices operated under the provisions of §§ 15.211, 15.213 and 15.221 shall be verified pursuant to the procedures in subpart J of part 2 of this chapter prior to marketing.

(b) Except as otherwise exempted in paragraph (c) of this section and in § 15.23 of this part, all intentional radiators operating under the provisions of this part shall be certificated by the Commission pursuant to the procedures in subpart J of part 2 of this chapter prior to marketing.

(c) For devices such as perimeter protection systems which, in accordance with § 15.31(d), are required to be measured at the installation site, each application for certification must be accompanied by a statement indicating that the system has been tested at three installations and found to comply at each installation. Until such time as certification is granted, a given installation of a system that was

measured for the submission for certification will be considered to be in compliance with the provisions of this chapter, including the marketing regulations in subpart I of part 2 of this chapter, if tests at that installation show the system to be in compliance with the relevant technical requirements. Similarly, where measurements must be performed on site for equipment subject to verification, a given installation that has been verified to demonstrate compliance with the applicable standards will be considered to be in compliance with the provisions of this chapter, including the marketing regulations in subpart I of part 2 of this chapter.

(d) For perimeter protection systems operating in the frequency bands allocated to television broadcast stations operating under part 73 of this chapter, the holder of the grant of certification must test each installation prior to initiation of normal operation to verify compliance with the technical standards and must maintain a list of all installations and records of measurements. For perimeter protection systems operating outside of the frequency bands allocated to television broadcast stations, upon receipt of a grant of certification, further testing of the same or similar type of system or installation is not required.

§ 15.203 Antenna requirement.

An intentional radiator shall be designed to ensure that no antenna other than that furnished by the responsible party shall be used with the device. The use of a permanently attached antenna or of an antenna that uses a unique coupling to the intentional radiator shall be considered sufficient to comply with the provisions of this section. The manufacturer may design the unit so that a broken antenna can be replaced by the user, but the use of a standard antenna jack or electrical connector is prohibited. This requirement does not apply to carrier current devices or to devices operated under the provisions of § 15.211, § 15.213, § 15.217, § 15.219, or § 15.221. Further, this requirement does not apply to intentional radiators that must be professionally installed, such as perimeter

§ 15.204

protection systems and some field disturbance sensors, or to other intentional radiators which, in accordance with § 15.31(d), must be measured at the installation site. However, the installer shall be responsible for ensuring that the proper antenna is employed so that the limits in this part are not exceeded.

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 28762, July 13, 1990]

§ 15.204 External radio frequency power amplifiers and antenna modifications.

(a) Except as otherwise described in paragraph (b) of this section, no person shall use, manufacture, sell or lease, offer for sale or lease (including advertising for sale or lease), or import, ship, or distribute for the purpose of selling or leasing, any external radio frequency power amplifier or amplifier kit intended for use with a Part 15 intentional radiator.

47 CFR Ch. I (10–1–97 Edition)

(b) A transmission system consisting of an intentional radiator, an external radio frequency power amplifier, and an antenna, may be authorized, marketed and used under this part. However, when a transmission system is authorized as a system, it must always be marketed as a complete system and must always be used in the configuration in which it was authorized. An external radio frequency power amplifier shall be marketed only in the system configuration with which the amplifier is authorized and shall not be marketed as a separate product.

(c) Only the antenna with which an intentional radiator is authorized may be used with the intentional radiator.

[62 FR 26242, May 13, 1997]

§ 15.205 Restricted bands of operation.

(a) Except as shown in paragraph (d) of this section, only spurious emissions are permitted in any of the frequency bands listed below:

MHz	MHz	MHz	GHz
0.090–0.110	16.42–16.423	399.9–410	4.5–5.15
¹ 0.495–0.505	16.69475–16.69525	608–614	5.35–5.46
2.1735–2.1905	16.80425–16.80475	960–1240	7.25–7.75
4.125–4.128	25.5–25.67	1300–1427	8.025–8.5
4.17725–4.17775	37.5–38.25	1435–1626.5	9.0–9.2
4.20725–4.20775	73–74.6	1645.5–1646.5	9.3–9.5
6.215–6.218	74.8–75.2	1660–1710	10.6–12.7
6.26775–6.26825	108–121.94	1718.8–1722.2	13.25–13.4
6.31175–6.31225	123–138	2200–2300	14.47–14.5
8.291–8.294	149.9–150.05	2310–2390	15.35–16.2
8.362–8.366	156.52475–156.52525	2483.5–2500	17.7–21.4
8.37625–8.38675	156.7–156.9	2655–2900	22.01–23.12
8.41425–8.41475	162.0125–167.17	3260–3267	23.6–24.0
12.29–12.293	167.72–173.2	3332–3339	31.2–31.8
12.51975–12.52025	240–285	3345.8–3358	36.43–36.5
12.57675–12.57725	322–335.4	3600–4400	(²)
13.36–13.41			

¹Until February 1, 1999, this restricted band shall be 0.490–0.510 MHz.

²Above 38.6

(b) Except as provided in paragraphs (d) and (e) of this section, the field strength of emissions appearing within these frequency bands shall not exceed the limits shown in § 15.209. At frequencies equal to or less than 1000 MHz, compliance with the limits in § 15.209 shall be demonstrated using measurement instrumentation employing a CISPR quasi-peak detector. Above 1000 MHz, compliance with the emission limits in § 15.209 shall be demonstrated based on the average value of

the measured emissions. The provisions in § 15.35 apply to these measurements.

(c) Except as provided in paragraphs (d) and (e) of this section, regardless of the field strength limits specified elsewhere in this subpart, the provisions of this section apply to emissions from any intentional radiator.

(d) The following devices are exempt from the requirements of this section:

(1) Swept frequency field disturbance sensors operating between 1.705 and 37 MHz provided their emissions only

Federal Communications Commission

§ 15.207

sweep through the bands listed in paragraph (a) of this section, the sweep is never stopped with the fundamental emission within the bands listed in paragraph (a) of this section, and the fundamental emission is outside of the bands listed in paragraph (a) of this section more than 99% of the time the device is actively transmitting, without compensation for duty cycle.

(2) Transmitters used to detect buried electronic markers at 101.4 kHz which are employed by telephone companies.

(3) Cable locating equipment operated pursuant to § 15.213.

(4) Any equipment operated under the provisions of § 15.253 or § 15.255.

(e) Harmonic emissions appearing in the restricted bands above 17.7 GHz from field disturbance sensors operating under the provisions of § 15.245 shall not exceed the limits specified in § 15.245(b).

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 46791, Nov. 7, 1990; 56 FR 6288, Feb. 15, 1991; 57 FR 13048, Apr. 15, 1992; 58 FR 33774, June 21, 1993; 60 FR 28068, May 30, 1995; 61 FR 14503, Apr. 2, 1996; 62 FR 4655, Jan. 31, 1997]

§ 15.207 Conducted limits.

(a) For an intentional radiator which is designed to be connected to the public utility (AC) power line, the radio frequency voltage that is conducted back onto the AC power line on any frequency or frequencies within the band 450 kHz to 30 MHz shall not exceed 250 microvolts. Compliance with this provision shall be based on the measurement of the radio frequency voltage between each power line and ground at the power terminals.

(b) The following option may be employed if the conducted emissions exceed the limits in paragraph (a) of this section when measured using instrumentation employing a quasi-peak detector function: If the level of the emission measured using the quasi-peak instrumentation is 6 dB, or more, higher than the level of the same emission measured with instrumentation having an average detector and a 9 kHz minimum bandwidth, that emission is considered broadband and the level obtained with the quasi-peak detector may be reduced by 13 dB for comparison to the limits. When employing this

option, the following conditions shall be observed:

(1) The measuring instrumentation with the average detector shall employ a linear IF amplifier.

(2) Care must be taken not to exceed the dynamic range of the measuring instrument when measuring an emission with a low duty cycle.

(3) The test report required for verification or for an application for a grant of equipment authorization shall contain all details supporting the use of this option.

(c) The limit shown in paragraph (a) of this section shall not apply to carrier current systems operating as intentional radiators on frequencies below 30 MHz. In lieu thereof, these carrier current systems shall be subject to the following standards:

(1) For carrier current systems containing their fundamental emission within the frequency band 535–1705 kHz and intended to be received using a standard AM broadcast receiver: no limit on conducted emissions.

(2) For all other carrier current systems: 1000 uV within the frequency band 535–1705 kHz.

(3) Carrier current systems operating below 30 MHz are also subject to the radiated emission limits in § 15.205, § 15.209, § 15.221, § 15.223, or § 15.227, as appropriate.

(d) Measurements to demonstrate compliance with the conducted limits are not required for devices which only employ battery power for operation and which do not operate from the AC power lines or contain provisions for operation while connected to the AC power lines. Devices that include, or make provisions for, the use of battery chargers which permit operating while charging, AC adapters or battery eliminators or that connect to the AC power lines indirectly, obtaining their power through another device which is connected to the AC power lines, shall be tested to demonstrate compliance with the conducted limits.

[54 FR 17714, Apr. 25, 1989, as amended at 56 FR 373, Jan. 4, 1991; 57 FR 33448, July 29, 1992; 58 FR 51249, Oct. 1, 1993]

§ 15.209 Radiated emission limits; general requirements.

(a) Except as provided elsewhere in this subpart, the emissions from an intentional radiator shall not exceed the field strength levels specified in the following table:

Frequency (MHz)	Field strength (microvolts/meter)	Measurement distance (meters)
0.009–0.490	2400/F(kHz)	300
0.490–1.705	24000/F(kHz)	30
1.705–30.0	30	30
30–88	100**	3
88–216	150**	3
216–960	200**	3
Above 960	500	3

** Except as provided in paragraph (g), fundamental emissions from intentional radiators operating under this section shall not be located in the frequency bands 54–72 MHz, 76–88 MHz, 174–216 MHz or 470–806 MHz. However, operation within these frequency bands is permitted under other sections of this part, e.g., §§ 15.231 and 15.241.

(b) In the emission table above, the tighter limit applies at the band edges.

(c) The level of any unwanted emissions from an intentional radiator operating under these general provisions shall not exceed the level of the fundamental emission. For intentional radiators which operate under the provisions of other sections within this part and which are required to reduce their unwanted emissions to the limits specified in this table, the limits in this table are based on the frequency of the unwanted emission and not the fundamental frequency. However, the level of any unwanted emissions shall not exceed the level of the fundamental frequency.

(d) The emission limits shown in the above table are based on measurements employing a CISPR quasi-peak detector except for the frequency bands 9–90 kHz, 110–490 kHz and above 1000 MHz. Radiated emission limits in these three bands are based on measurements employing an average detector.

(e) The provisions in §§ 15.31, 15.33, and 15.35 for measuring emissions at distances other than the distances specified in the above table, determining the frequency range over which radiated emissions are to be measured, and limiting peak emissions apply to all devices operated under this part.

(f) In accordance with § 15.33(a), in some cases the emissions from an intentional radiator must be measured to

beyond the tenth harmonic of the highest fundamental frequency designed to be emitted by the intentional radiator because of the incorporation of a digital device. If measurements above the tenth harmonic are so required, the radiated emissions above the tenth harmonic shall comply with the general radiated emission limits applicable to the incorporated digital device, as shown in § 15.109 and as based on the frequency of the emission being measured, or, except for emissions contained in the restricted frequency bands shown in § 15.205, the limit on spurious emissions specified for the intentional radiator, whichever is the higher limit. Emissions which must be measured above the tenth harmonic of the highest fundamental frequency designed to be emitted by the intentional radiator and which fall within the restricted bands shall comply with the general radiated emission limits in § 15.109 that are applicable to the incorporated digital device.

(g) Operation in the frequency bands allocated to TV broadcast stations:

(1) Perimeter protection systems operating under the provisions of this section in the frequency bands allocated to TV broadcast stations, as shown in part 73 of this chapter, shall contain their fundamental emissions within the frequency bands 54–72 MHz and 76–88 MHz. Further, the use of such perimeter protection systems is limited to industrial, business and commercial applications.

(2) Biomedical telemetry devices operating under the provisions of this section in the frequency bands allocated to TV broadcast stations, as shown in part 73 of this chapter, shall contain their fundamental emissions within the frequency band 512–566 MHz. Further, the marketing and the use of biomedical telemetry devices operating under this paragraph shall be limited to hospitals.

[54 FR 17714, Apr. 25, 1989; 54 FR 32339, Aug. 7, 1989; 55 FR 18340, May 2, 1990]

§ 15.211 Tunnel radio systems.

An intentional radiator utilized as part of a tunnel radio system may operate on any frequency provided it meets all of the following conditions:

Federal Communications Commission

§ 15.214

(a) Operation of a tunnel radio system (intentional radiator and all connecting wires) shall be contained solely within a tunnel, mine or other structure that provides attenuation to the radiated signal due to the presence of naturally surrounding earth and/or water.

(b) Any intentional or unintentional radiator external to the tunnel, mine or other structure, as described in paragraph (a) of this section, shall be subject to the other applicable regulations contained within this part.

(c) The total electromagnetic field from a tunnel radio system on any frequency or frequencies appearing outside of the tunnel, mine or other structure described in paragraph (a) of this section, shall not exceed the limits shown in § 15.209 when measured at the specified distance from the surrounding structure, including openings. Particular attention shall be paid to the emissions from any opening in the structure to the outside environment. When measurements are made from the openings, the distances shown in § 15.209 refer to the distance from the plane of reference which fits the entire perimeter of each above ground opening.

(d) The conducted limits in § 15.207 apply to the radiofrequency voltage on the public utility power lines outside of the tunnel.

§ 15.213 Cable locating equipment.

An intentional radiator used as cable locating equipment, as defined in § 15.3(d), may be operated on any frequency within the band 9–490 kHz, subject to the following limits: Within the frequency band 9 kHz, up to, but not including, 45 kHz, the peak output power from the cable locating equipment shall not exceed 10 watts; and, within the frequency band 45 kHz to 490 kHz, the peak output power from the cable locating equipment shall not exceed one watt. If provisions are made for connection of the cable locating equipment to the AC power lines, the conducted limits in § 15.207 also apply to this equipment.

§ 15.214 Cordless telephones.

(a) For equipment authorization, a single application form, FCC Form 731, may be filed for a cordless telephone

system, provided the application clearly identifies and provides data for all parts of the system to show compliance with the applicable technical requirements. When a single application form is submitted, both the base station and the portable handset must carry the same FCC identifier. The application shall include a fee for certification of each type of transmitter and notification or certification, if appropriate, for each type of receiver included in the system.

(b) A cordless telephone which is intended to be connected to the public switched telephone network shall also comply with the applicable regulations in part 68 of this chapter. A separate application for registration under part 68 of this chapter is required.

(c) The label required under subpart A of this part shall also contain the following statement: “Privacy of communications may not be ensured when using this phone.”

(d) Cordless telephones shall incorporate circuitry which makes use of a digital security code to provide protection against unintentional access to the public switched telephone network by the base unit and unintentional ringing by the handset. These functions shall operate such that each access of the telephone network or ringing of the handset is preceded by the transmission of a code word. Access to the telephone network shall occur only if the code transmitted by the handset matches code set in the base unit. Similarly, ringing of the handset shall occur only if the code transmitted by the base unit matches the code set in the handset. The security code required by this section may also be employed to perform other communications functions, such as providing telephone billing information. This security code system is to operate in accordance with the following provisions.

(1) There must be provision for at least 256 possible discrete digital codes. Factory-set codes must be continuously varied over at least 256 possible codes as each telephone is manufactured. The codes may be varied either randomly, sequentially, or using another systematic procedure.

§ 15.215

47 CFR Ch. I (10–1–97 Edition)

(2) Manufacturers must use one of the following approaches for facilitating variation in the geographic distribution of individual security codes:

(i) Provide a means for the user to readily select from among at least 256 possible discrete digital codes. The cordless telephone shall be either in a non-operable mode after manufacture until the user selects a security code or the manufacturer must continuously vary the initial security code as each telephone is produced.

(ii) Provide a fixed code that is continuously varied among at least 256 discrete digital codes as each telephone is manufactured.

(iii) Provide a means for the cordless telephone to automatically select a different code from among at least 256 possible discrete digital codes each time it is activated.

(iv) It is permissible to provide combinations of fixed, automatic, and user-selectable coding provided the above criteria are met.

(3) A statement of the means and procedures used to achieve the required protection shall be provided in any application for equipment authorization of a cordless telephone.

[56 FR 3785, Jan. 31, 1991]

RADIATED EMISSION LIMITS, ADDITIONAL PROVISIONS

§ 15.215 Additional provisions to the general radiated emission limitations.

(a) The regulations in §§ 15.217 through 15.255 provide alternatives to the general radiated emission limits for intentional radiators operating in specified frequency bands. Unless otherwise stated, there are no restrictions as to the types of operation permitted under these sections.

(b) In most cases, unwanted emissions outside of the frequency bands shown in these alternative provisions must be attenuated to the emission limits shown in § 15.209. In no case shall the level of the unwanted emissions from an intentional radiator operating under these additional provisions exceed the field strength of the fundamental emission.

(c) For those bands of frequencies where alternative radiated emission

limitations apply and for which a frequency stability is not specified, it is recommended that the fundamental frequency be kept within at least the central 80% of the permitted band in order to minimize the possibility of out-of-band operation.

(d) Where the following sections specify limits on the bandwidth of the emissions, the bandwidth limits include the effects of frequency sweeping, frequency hopping, and other modulation techniques which may be employed.

[54 FR 17714, Apr. 25, 1989, as amended at 62 FR 45333, Aug. 27, 1997]

§ 15.217 Operation in the band 160–190 kHz.

(a) The total input power to the final radio frequency stage (exclusive of filament or heater power) shall not exceed one watt.

(b) The total length of the transmission line, antenna, and ground lead (if used) shall not exceed 15 meters.

(c) All emissions below 160 kHz or above 190 kHz shall be attenuated at least 20 dB below the level of the unmodulated carrier. Determination of compliance with the 20 dB attenuation specification may be based on measurements at the intentional radiator's antenna output terminal unless the intentional radiator uses a permanently attached antenna, in which case compliance shall be demonstrated by measuring the radiated emissions.

§ 15.219 Operation in the band 510–1705 kHz.

(a) The total input power to the final radio frequency stage (exclusive of filament or heater power) shall not exceed 100 milliwatts.

(b) The total length of the transmission line, antenna and ground lead (if used) shall not exceed 3 meters.

(c) All emissions below 510 kHz or above 1705 kHz shall be attenuated at least 20 dB below the level of the unmodulated carrier. Determination of compliance with the 20 dB attenuation specification may be based on measurements at the intentional radiator's antenna output terminal unless the intentional radiator uses a permanently

Federal Communications Commission

§ 15.225

attached antenna, in which case compliance shall be demonstrated by measuring the radiated emissions.

§ 15.221 Operation in the band 525–1705 kHz.

(a) Carrier current systems and transmitters employing a leaky coaxial cable as the radiating antenna may operate in the band 525–1705 kHz provided the field strength levels of the radiated emissions do not exceed 15 $\mu\text{V}/\text{m}$, as measured at a distance of 47,715/ (frequency in kHz) meters (equivalent to $\text{Lambda}/2\text{Pi}$) from the electric power line or the coaxial cable, respectively. The field strength levels of emissions outside this band shall not exceed the general radiated emission limits in § 15.209.

(b) As an alternative to the provisions in paragraph (a) of this section, intentional radiators used for the operation of an AM broadcast station on a college or university campus or on the campus of any other education institution may comply with the following:

(1) On the campus, the field strength of emissions appearing outside of this frequency band shall not exceed the general radiated emission limits shown in § 15.209 as measured from the radiating source. There is no limit on the field strength of emissions appearing within this frequency band, except that the provisions of § 15.5 continue to comply.

(2) At the perimeter of the campus, the field strength of any emissions, including those within the frequency band 525–1705 kHz, shall not exceed the general radiated emission in § 15.209.

(3) The conducted limits specified in § 15.207 apply to the radio frequency voltage on the public utility power lines outside of the campus. Due to the large number of radio frequency devices which may be used on the campus, contributing to the conducted emissions, as an alternative to measuring conducted emissions outside of the campus, it is acceptable to demonstrate compliance with this provision by measuring each individual intentional radiator employed in the system at the point where it connects to the AC power lines.

(c) A grant of equipment authorization is not required for intentional ra-

diators operated under the provisions of this section. In lieu thereof, the intentional radiator shall be verified for compliance with the regulations in accordance with subpart J of part 2 of this chapter. This data shall be kept on file at the location of the studio, office or control room associated with the transmitting equipment. In some cases, this may correspond to the location of the transmitting equipment.

(d) For the band 535–1705 kHz, the frequency of operation shall be chosen such that operation is not within the protected field strength contours of licensed AM stations.

[56 FR 373, Jan. 4, 1991]

§ 15.223 Operation in the band 1.705–10 MHz.

(a) The field strength of any emission within the band 1.705–10.0 MHz shall not exceed 100 microvolts/meter at a distance of 30 meters. However, if the bandwidth of the emission is less than 10% of the center frequency, the field strength shall not exceed 15 microvolts/meter or (the bandwidth of the device in kHz) divided by (the center frequency of the device in MHz) microvolts/meter at a distance of 30 meters, whichever is the higher level. For the purposes of this section, bandwidth is determined at the points 6 dB down from the modulated carrier. The emission limits in this paragraph are based on measurement instrumentation employing an average detector. The provisions in § 15.35(b) for limiting peak emissions apply.

(b) The field strength of emissions outside of the band 1.705–10.0 MHz shall not exceed the general radiated emission limits in § 15.209.

§ 15.225 Operation within the band 13.553–13.567 MHz.

(a) The field strength of any emissions within this band shall not exceed 10,000 microvolts/meter at 30 meters.

(b) The field strength of any emissions appearing outside of this band shall not exceed the general radiated emission limits shown in § 15.209.

(c) The frequency tolerance of the carrier signal shall be maintained within $\pm 0.01\%$ of the operating frequency over a temperature variation of -20 degrees to $+50$ degrees C at normal

§ 15.227

supply voltage, and for a variation in the primary supply voltage from 85% to 115% of the rated supply voltage at a temperature of 20 degrees C. For battery operated equipment, the equipment tests shall be performed using a new battery.

§ 15.227 Operation within the band 26.96–27.28 MHz.

(a) The field strength of any emission within this band shall not exceed 10,000 microvolts/meter at 3 meters. The emission limit in this paragraph is based on measurement instrumentation employing an average detector. The provisions in §15.35 for limiting peak emissions apply.

(b) The field strength of any emissions which appear outside of this band shall not exceed the general radiated emission limits in § 15.209.

§ 15.229 Operation within the band 40.66–40.70 MHz.

(a) Unless operating pursuant to the provisions in §15.231, the field strength of any emissions within this band shall not exceed 1,000 microvolts/meter at 3 meters.

(b) As an alternative to the limit in paragraph (a) of this section, perimeter protection systems may demonstrate compliance with the following: the field strength of any emissions within this band shall not exceed 500 microvolts/meter at 3 meters, as determined using measurement instrumentations employing an average detector. The provisions in §15.35 for limiting peak emissions apply where compliance of these devices is demonstrated under this alternative emission limit.

(c) The field strength of any emissions appearing outside of this band shall not exceed the general radiated emission limits in § 15.209.

(d) The frequency tolerance of the carrier signal shall be maintained within $\pm 0.01\%$ of the operating frequency over a temperature variation of -20 degrees to $+50$ degrees C at normal supply voltage, and for a variation in the primary supply voltage from 85% to 115% of the rated supply voltage at a temperature of 20 degrees C. For battery operated equipment, the equip-

47 CFR Ch. I (10–1–97 Edition)

ment tests shall be performed using a new battery.

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 33910, Aug. 20, 1990]

§ 15.231 Periodic operation in the band 40.66–40.70 MHz and above 70 MHz.

(a) The provisions of this section are restricted to periodic operation within the band 40.66–40.70 MHz and above 70 MHz. Except as shown in paragraph (e) of this section, the intentional radiator is restricted to the transmission of a control signal such as those used with alarm systems, door openers, remote switches, etc. Radio control of toys is not permitted. Continuous transmissions, such as voice or video, and data transmissions are not permitted. The prohibition against data transmissions does not preclude the use of recognition codes. Those codes are used to identify the sensor that is activated or to identify the particular component as being part of the system. The following conditions shall be met to comply with the provisions for this periodic operation:

(1) A manually operated transmitter shall employ a switch that will automatically deactivate the transmitter within not more than 5 seconds of being released.

(2) A transmitter activated automatically shall cease transmission within 5 seconds after activation.

(3) Periodic transmissions at regular predetermined intervals are not permitted. However, polling or supervision transmissions to determine system integrity of transmitters used in security or safety applications are allowed if the periodic rate of transmission does not exceed one transmission of not more than one second duration per hour for each transmitter.

(4) Intentional radiators which are employed for radio control purposes during emergencies involving fire, security, and safety of life, when activated to signal an alarm, may operate during the pendency of the alarm condition

(b) In addition to the provisions of §15.205, the field strength of emissions from intentional radiators operated under this section shall not exceed the following:

Federal Communications Commission

§ 15.233

Fundamental frequency (MHz)	Field strength of fundamental (microvolts/meter)	Field strength of spurious emissions (microvolts/meter)
40.66–40.70	2,250	225
70–130	1,250	125
130–174	¹ 1,250 to 3,750	¹ 125 to 375
174–260	3,750	375
260–470	¹ 3,750 to 12,500	¹ 375 to 1,250
Above 470	12,500	1,250

¹Linear interpolations.

(1) The above field strength limits are specified at a distance of 3 meters. The tighter limits apply at the band edges.

(2) Intentional radiators operating under the provisions of this section shall demonstrate compliance with the limits on the field strength of emissions, as shown in the above table, based on the average value of the measured emissions. As an alternative, compliance with the limits in the above table may be based on the use of measurement instrumentation with a CISPR quasi-peak detector. The specific method of measurement employed shall be specified in the application for equipment authorization. If average emission measurements are employed, the provisions in § 15.35 for averaging pulsed emissions and for limiting peak emissions apply. Further, compliance with the provisions of § 15.205 shall be demonstrated using the measurement instrumentation specified in that section.

(3) The limits on the field strength of the spurious emissions in the above table are based on the fundamental frequency of the intentional radiator. Spurious emissions shall be attenuated to the average (or, alternatively, CISPR quasi-peak) limits shown in this table or to the general limits shown in § 15.209, whichever limit permits a higher field strength.

(c) The bandwidth of the emission shall be no wider than 0.25% of the center frequency for devices operating above 70 MHz and below 900 MHz. For devices operating above 900 MHz, the emission shall be no wider than 0.5% of the center frequency. Bandwidth is determined at the points 20 dB down from the modulated carrier.

(d) For devices operating within the frequency band 40.66–40.70 MHz, the bandwidth of the emission shall be confined within the band edges and the fre-

quency tolerance of the carrier shall be $\pm 0.01\%$. This frequency tolerance shall be maintained for a temperature variation of -20 degrees to $+50$ degrees C at normal supply voltage, and for a variation in the primary supply voltage from 85% to 115% of the rated supply voltage at a temperature of 20 degrees C. For battery operated equipment, the equipment tests shall be performed using a new battery.

(e) Intentional radiators may operate at a periodic rate exceeding that specified in paragraph (a) of this section and may be employed for any type of operation, including operation prohibited in paragraph (a) of this section, provided the intentional radiator complies with the provisions of paragraphs (b) through (d) of this section, except the field strength table in paragraph (b) of this section is replaced by the following:

Fundamental frequency (MHz)	Field strength of fundamental (microvolts/meter)	Field strength of spurious emission (microvolts/meter)
40.66–40.70	1,000	100
70–130	500	50
130–174	500 to 1,500 ¹	50 to 150 ¹
174–260	1,500	150
260–470	1,500 to 5,000 ¹	150 to 500 ¹
Above 470	5,000	500

¹Linear interpolations.

In addition, devices operated under the provisions of this paragraph shall be provided with a means for automatically limiting operation so that the duration of each transmission shall not be greater than one second and the silent period between transmissions shall be at least 30 times the duration of the transmission but in no case less than 10 seconds.

[54 FR 17714, Apr. 25, 1989; 54 FR 32340, Aug. 7, 1989]

§ 15.233 Operation within the bands 43.71–44.49 MHz, 46.60–46.98 MHz, 48.75–49.51 MHz and 49.66–50.0 MHz.

(a) The provisions shown in this section are restricted to cordless telephones.

(b) An intentional radiator used as part of a cordless telephone system shall operate centered on one or more of the following frequency pairs, subject to the following conditions:

§ 15.233

47 CFR Ch. I (10–1–97 Edition)

(1) Frequencies shall be paired as shown below, except that channel pairing for channels one through fifteen may be accomplished by pairing any of the fifteen base transmitter frequencies with any of the fifteen handset transmitter frequencies.

(2) Cordless telephones operating on channels one through fifteen must:

(i) Incorporate an automatic channel selection mechanism that will prevent establishment of a link on any occupied frequency; and

(ii) The box or an instruction manual which is included within the box which the individual cordless telephone is to be marketed shall contain information indicating that some cordless telephones operate at frequencies that may cause interference to nearby TVs and VCRs; to minimize or prevent such interference, the base of the cordless telephone should not be placed near or on top of a TV or VCR; and, if interference is experienced, moving the cordless telephone farther away from the TV or VCR will often reduce or eliminate the interference. A statement describing the means and procedures used to achieve automatic channel selection shall be provided in any application for equipment authorization of a cordless telephone operating on channels one through fifteen.

Channel	Base transmitter (MHz)	Handset transmitter (MHz)
1	43.720	48.760
2	43.740	48.840
3	43.820	48.860
4	43.840	48.920
5	43.920	49.020
6	43.960	49.080
7	44.120	49.100
8	44.160	49.160
9	44.180	49.200
10	44.200	49.240
11	44.320	49.280
12	44.360	49.360
13	44.400	49.400
14	44.460	49.460
15	44.480	49.500
16	46.610	49.670
17	46.630	49.845
18	46.670	49.860
19	46.710	49.770
20	46.730	49.875
21	46.770	49.830
22	46.830	49.890
23	46.870	49.930
24	46.930	49.990
25	46.970	49.970

(c) The field strength of the fundamental emission shall not exceed

10,000 microvolts/meter at 3 meters. The emission limit in this paragraph is based on measurement instrumentation employing an average detector. The provisions in §15.35 for limiting peak emissions apply.

(d) The fundamental emission shall be confined within a 20 kHz band and shall be centered on a carrier frequency shown above, as adjusted by the frequency tolerance of the transmitter at the time testing is performed. Modulation products outside of this 20 kHz band shall be attenuated at least 26 dB below the level of the unmodulated carrier or to the general limits in §15.209, whichever permits the higher emission levels. Emissions on any frequency more than 20 kHz removed from the center frequency shall consist solely of unwanted emissions and shall not exceed the general radiated emission limits in §15.209. Tests to determine compliance with these requirements shall be performed using an appropriate input signal as prescribed in §2.989 of this chapter.

(e) All emissions exceeding 20 microvolts/meter at 3 meters are to be reported in the application for certification.

(f) If the device provides for the connection of external accessories, including external electrical input signals, the device must be tested with the accessories attached. The emission tests shall be performed with the device and accessories configured in a manner which tends to produce the maximum level of emissions within the range of variations that can be expected under normal operating conditions.

(g) The frequency tolerance of the carrier signal shall be maintained within $\pm 0.01\%$ of the operating frequency. The tolerance shall be maintained for a temperature variation of -20 degrees C to $+50$ degrees C at normal supply voltage, and for variation in the primary voltage from 85% to 115% of the rated supply voltage at a temperature of 20 degrees C. For battery operated equipment, the equipment tests shall be performed using a new battery.

(h) For cordless telephones that do not comply with §15.214(d) of this part, the box or other package in which the individual cordless telephone is to be

Federal Communications Commission

§ 15.239

marketed shall carry a statement in a prominent location, visible to the buyer before purchase, which reads as follows:

NOTICE: The base units of some cordless telephones may respond to other nearby units or to radio noise resulting in telephone calls being dialed through this unit without your knowledge and possibly calls being misbilled. In order to protect against such occurrences, this cordless telephone is provided with the following features: (to be completed by the responsible party).

An application for certification of a cordless telephone shall specify the complete text of the statement that will be carried on the package and indicate where, specifically, it will be located on the carton.

[54 FR 17714, Apr. 25, 1989; 54 FR 32340, Aug. 7, 1989, as amended at 56 FR 3785, Jan. 31, 1991; 56 FR 5659, Feb. 12, 1991; 60 FR 21985, May 4, 1995]

§ 15.235 Operation within the band 49.82–49.90 MHz.

(a) The field strength of any emission within this band shall not exceed 10,000 microvolts/meter at 3 meters. The emission limit in this paragraph is based on measurement instrumentation employing an average detector. The provisions in § 15.35 for limiting peak emissions apply.

(b) The field strength of any emissions appearing between the band edges and up to 10 kHz above and below the band edges shall be attenuated at least 26 dB below the level of the unmodulated carrier or to the general limits in § 15.209, whichever permits the higher emission levels. The field strength of any emissions removed by more than 10 kHz from the band edges shall not exceed the general radiated emission limits in § 15.209. All signals exceeding 20 microvolts/meter at 3 meters shall be reported in the application for certification.

(c) For a home-built intentional radiator, as defined in § 15.23(a), operating within the band 49.82–49.90 MHz, the following standards may be employed:

(1) The RF carrier and modulation products shall be maintained within the band 49.82–49.90 MHz.

(2) The total input power to the device measured at the battery or the power line terminals shall not exceed

100 milliwatts under any condition of modulation.

(3) The antenna shall be a single element, one meter or less in length, permanently mounted on the enclosure containing the device.

(4) Emissions outside of this band shall be attenuated at least 20 dB below the level of the unmodulated carrier.

(5) The regulations contained in § 15.23 of this part apply to intentional radiators constructed under the provisions of this paragraph.

(d) Cordless telephones are not permitted to operate under the provisions of this section.

§ 15.237 Operation in the bands 72.0–73.0 MHz, 74.6–74.8 MHz and 75.2–76.0 MHz.

(a) The intentional radiator shall be restricted to use as an auditory assistance device.

(b) Emissions from the intentional radiator shall be confined within a band 200 kHz wide centered on the operating frequency. The 200 kHz band shall lie wholly within the above specified frequency ranges.

(c) The field strength of any emissions within the permitted 200 kHz band shall not exceed 80 millivolts/meter at 3 meters. The field strength of any emissions radiated on any frequency outside of the specified 200 kHz band shall not exceed 1500 microvolts/meter at 3 meters. The emission limits in this paragraph are based on measurement instrumentation employing an average detector. The provisions in § 15.35 for limiting peak emissions apply.

[54 FR 17714, Apr. 25, 1989, as amended at 57 FR 13048, Apr. 15, 1992]

§ 15.239 Operation in the band 88–108 MHz.

(a) Emissions from the intentional radiator shall be confined within a band 200 kHz wide centered on the operating frequency. The 200 kHz band shall lie wholly within the frequency range of 88–108 MHz.

(b) The field strength of any emissions within the permitted 200 kHz band shall not exceed 250 microvolts/meter at 3 meters. The emission limit in this paragraph is based on measurement instrumentation employing an

§ 15.241

average detector. The provisions in §15.35 for limiting peak emissions apply.

(c) The field strength of any emissions radiated on any frequency outside of the specified 200 kHz band shall not exceed the general radiated emission limits in §15.209.

(d) A custom built telemetry intentional radiator operating in the frequency band 88–108 MHz and used for experimentation by an educational institute need not be certified provided the device complies with the standards in this part and the educational institution notifies the Engineer in Charge of the local FCC office, in writing, in advance of operation, providing the following information:

(1) The dates and places where the device will be operated;

(2) The purpose for which the device will be used;

(3) A description of the device, including the operating frequency, RF power output, and antenna; and,

(4) A statement that the device complies with the technical provisions of this part.

[54 FR 17714, Apr. 25, 1989; 54 FR 32340, Aug. 7, 1989]

§ 15.241 Operation in the band 174–216 MHz.

(a) Operation under the provisions of this section is restricted to biomedical telemetry devices.

(b) Emissions from the device shall be confined within a 200 kHz band which shall lie wholly within the frequency range of 174–216 MHz.

(c) The field strength of any emissions radiated within the specified 200 kHz band shall not exceed 1500 microvolts/meter at 3 meters. The field strength of emissions radiated on any frequency outside of the specified 200 kHz band shall not exceed 150 microvolts/meter at 3 meters. The emission limits in this paragraph are based on measurement instrumentation employing an average detector. The provisions in §15.35 for limiting peak emissions apply.

§ 15.243 Operation in the band 890–940 MHz.

(a) Operation under the provisions of this section is restricted to devices

47 CFR Ch. I (10–1–97 Edition)

that use radio frequency energy to measure the characteristics of a material. Devices operated pursuant to the provisions of this section shall not be used for voice communications or the transmission of any other type of message.

(b) The field strength of any emissions radiated within the specified frequency band shall not exceed 500 microvolts/meter at 30 meters. The emission limit in this paragraph is based on measurement instrumentation employing an average detector. The provisions in §15.35 for limiting peak emissions apply.

(c) The field strength of emissions radiated on any frequency outside of the specified band shall not exceed the general radiated emission limits in §15.209.

(d) The device shall be self-contained with no external or readily accessible controls which may be adjusted to permit operation in a manner inconsistent with the provisions in this section. Any antenna that may be used with the device shall be permanently attached thereto and shall not be readily modifiable by the user.

§ 15.245 Operation within the bands 902–928 MHz, 2435–2465 MHz, 5785–5815 MHz, 10500–10550 MHz, and 24075–24175 MHz.

(a) Operation under the provisions of this section is limited to intentional radiators used as field disturbance sensors, excluding perimeter protection systems.

(b) The field strength of emissions from intentional radiators operated within these frequency bands shall comply with the following:

Fundamental frequency (MHz)	Field strength of fundamental (millivolts/meter)	Field strength of harmonics (millivolts/meter)
902–928	500	1.6
2435–2465	500	1.6
5785–5815	500	1.6
10500–10550	2500	25.0
24075–24175	2500	25.0

(1) Regardless of the limits shown in the above table, harmonic emissions in the restricted bands below 17.7 GHz, as specified in §15.205, shall not exceed the field strength limits shown in §15.209. Harmonic emissions in the restricted bands at and above 17.7 GHz shall not

exceed the following field strength limits:

(i) For field disturbance sensors designed for use only within a building or to open building doors, 25.0 mV/m.

(ii) For all other field disturbance sensors, 7.5 mV/m.

(iii) Field disturbance sensors designed to be used in motor vehicles or aircraft must include features to prevent continuous operation unless their emissions in the restricted bands fully comply with the limits given in § 15.209. Continuous operation of field disturbance sensors designed to be used in farm equipment, vehicles such as fork lifts that are intended primarily for use indoors or for very specialized operations, or railroad locomotives, railroad cars and other equipment which travels on fixed tracks is permitted. A field disturbance sensor will be considered not to be operating in a continuous mode if its operation is limited to specific activities of limited duration (e.g., putting a vehicle into reverse gear, activating a turn signal, etc.).

(2) Field strength limits are specified at a distance of 3 meters.

(3) Emissions radiated outside of the specified frequency bands, except for harmonics, shall be attenuated by at least 50 dB below the level of the fundamental or to the general radiated emission limits in § 15.209, whichever is the lesser attenuation.

(4) The emission limits shown above are based on measurement instrumentation employing an average detector. The provisions in § 15.35 for limiting peak emissions apply.

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 46792, Nov. 7, 1990; 61 FR 42558, Aug. 16, 1996]

§ 15.247 Operation within the bands 902–928 MHz, 2400–2483.5 MHz, and 5725–5850 MHz.

(a) Operation under the provisions of this section is limited to frequency hopping and direct sequence spread spectrum intentional radiators that comply with the following provisions:

(1) Frequency hopping systems shall have hopping channel carrier frequencies separated by a minimum of 25 kHz or the 20 dB bandwidth of the hopping channel, whichever is greater. The system shall hop to channel fre-

quencies that are selected at the system hopping rate from a pseudorandomly ordered list of hopping frequencies. Each frequency must be used equally on the average by each transmitter. The system receivers shall have input bandwidths that match the hopping channel bandwidths of their corresponding transmitters and shall shift frequencies in synchronization with the transmitted signals.

(i) For frequency hopping systems operating in the 902–928 MHz band: if the 20 dB bandwidth of the hopping channel is less than 250 kHz, the system shall use at least 50 hopping frequencies and the average time of occupancy on any frequency shall not be greater than 0.4 seconds within a 20 second period; if the 20 dB bandwidth of the hopping channel is 250 kHz or greater, the system shall use at least 25 hopping frequencies and the average time of occupancy on any frequency shall not be greater than 0.4 seconds within a 10 second period. The maximum allowed 20 dB bandwidth of the hopping channel is 500 kHz.

(ii) Frequency hopping systems operating in the 2400–2483.5 MHz and 5725–5850 MHz bands shall use at least 75 hopping frequencies. The maximum 20 dB bandwidth of the hopping channel is 1 MHz. The average time of occupancy on any frequency shall not be greater than 0.4 seconds within a 30 second period.

(2) For direct sequence systems, the minimum 6 dB bandwidth shall be at least 500 kHz.

(b) The maximum peak output power of the intentional radiator shall not exceed the following:

(1) For frequency hopping systems operating in the 2400–2483.5 MHz or 5725–5850 MHz band and for all direct sequence systems: 1 watt.

(2) For frequency hopping systems operating in the 902–928 MHz band: 1 watt for systems employing at least 50 hopping channels; and, 0.25 watts for systems employing less than 50 hopping channels, but at least 25 hopping channels, as permitted under paragraph (a)(1)(i) of this section.

(3) Except as shown in paragraphs (b)(3) (i), (ii) and (iii) of this section, if transmitting antennas of directional gain greater than 6 dBi are used the

peak output power from the intentional radiator shall be reduced below the stated values in paragraphs (b)(1) or (b)(2) of this section, as appropriate, by the amount in dB that the directional gain of the antenna exceeds 6 dBi.

(i) Systems operating in the 2400–2483.5 MHz band that are used exclusively for fixed, point-to-point operations may employ transmitting antennas with directional gain greater than 6 dBi provided the maximum peak output power of the intentional radiator is reduced by 1 dB for every 3 dB that the directional gain of the antenna exceeds 6 dBi.

(ii) Systems operating in the 5725–5850 MHz band that are used exclusively for fixed, point-to-point operations may employ transmitting antennas with directional gain greater than 6 dBi without any corresponding reduction in transmitter peak output power.

(iii) Fixed, point-to-point operation, as used in paragraphs (b)(3)(i) and (b)(3)(ii) of this section, excludes the use of point-to-multipoint systems, omnidirectional applications, and multiple co-located intentional radiators transmitting the same information. The operator of the spread spectrum intentional radiator or, if the equipment is professionally installed, the installer is responsible for ensuring that the system is used exclusively for fixed, point-to-point operations. The instruction manual furnished with the intentional radiator shall contain language in the installation instructions informing the operator and the installer of this responsibility.

(4) Systems operating under the provisions of this section shall be operated in a manner that ensures that the public is not exposed to radio frequency energy levels in excess of the Commission's guidelines. See § 1.1307(b)(1) of this chapter.

(c) In any 100 kHz bandwidth outside the frequency band in which the spread spectrum intentional radiator is operating, the radio frequency power that is produced by the intentional radiator shall be at least 20 dB below that in the 100 kHz bandwidth within the band that contains the highest level of the desired power, based on either an RF

conducted or a radiated measurement. Attenuation below the general limits specified in § 15.209(a) is not required. In addition, radiated emissions which fall in the restricted bands, as defined in § 15.205(a), must also comply with the radiated emission limits specified in § 15.209(a) (see § 15.205(c)).

(d) For direct sequence systems, the peak power spectral density conducted from the intentional radiator to the antenna shall not be greater than 8 dBm in any 3 kHz band during any time interval of continuous transmission.

(e) The processing gain of a direct sequence system shall be at least 10 dB. The processing gain represents the improvement to the received signal-to-noise ratio, after filtering to the information bandwidth, from the spreading/despreading function. The processing gain may be determined using one of the following methods:

(1) As measured at the demodulated output of the receiver: the ratio in dB of the signal-to-noise ratio with the system spreading code turned off to the signal-to-noise ratio with the system spreading code turned on.

(2) As measured using the CW jamming margin method: a signal generator is stepped in 50 kHz increments across the passband of the system, recording at each point the generator level required to produce the recommended Bit Error Rate (BER). This level is the jammer level. The output power of the intentional radiator is measured at the same point. The jammer to signal ratio (J/S) is then calculated, discarding the worst 20% of the J/S data points. The lowest remaining J/S ratio is used to calculate the processing gain, as follows: $G_p = (S/N)_o + M_j + L_{sys}$, where G_p = processing gain of the system, $(S/N)_o$ = signal to noise ratio required for the chosen BER, M_j = J/S ratio, and L_{sys} = system losses. Note that total losses in a system, including intentional radiator and receiver, should be assumed to be no more than 2 dB.

(f) Hybrid systems that employ a combination of both direct sequence and frequency hopping modulation techniques shall achieve a processing gain of at least 17 dB from the combined techniques. The frequency hopping operation of the hybrid system,

Federal Communications Commission

§ 15.251

with the direct sequence operation turned off, shall have an average time of occupancy on any frequency not to exceed 0.4 seconds within a time period in seconds equal to the number of hopping frequencies employed multiplied by 0.4. The direct sequence operation of the hybrid system, with the frequency hopping operation turned off, shall comply with the power density requirements of paragraph (d) of this section.

(g) Frequency hopping spread spectrum systems are not required to employ all available hopping channels during each transmission. However, the system, consisting of both the transmitter and the receiver, must be designed to comply with all of the regulations in this section should the transmitter be presented with a continuous data (or information) stream. In addition, a system employing short transmission bursts must comply with the definition of a frequency hopping system and must distribute its transmissions over the minimum number of hopping channels specified in this section.

(h) The incorporation of intelligence within a frequency hopping spread spectrum system that permits the system to recognize other users within the spectrum band so that it individually and independently chooses and adapts its hopsets to avoid hopping on occupied channels is permitted. The coordination of frequency hopping systems in any other manner for the express purpose of avoiding the simultaneous occupancy of individual hopping frequencies by multiple transmitters is not permitted.

NOTE: Spread spectrum systems are sharing these bands on a noninterference basis with systems supporting critical Government requirements that have been allocated the usage of these bands, secondary only to ISM equipment operated under the provisions of part 18 of this chapter. Many of these Government systems are airborne radiolocation systems that emit a high EIRP which can cause interference to other users. Also, investigations of the effect of spread spectrum interference to U. S. Government operations in the 902–928 MHz band may require a future decrease in the power limits allowed for spread spectrum operation.

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 28762, July 13, 1990; 62 FR 26242, May 13, 1997]

§ 15.249 Operation within the bands 902–928 MHz, 2400–2483.5 MHz, 5725–5875 MHz, and 24.0–24.25 GHz.

(a) The field strength of emissions from intentional radiators operated within these frequency bands shall comply with the following:

Fundamental frequency	Field strength of fundamental (millivolts/meter)	Field strength of harmonics (microvolts/meter)
902–928 MHz	50	500
2400–2483.5 MHz	50	500
5725–5875 MHz	50	500
24.0–24.25 GHz	250	2500

(b) Field strength limits are specified at a distance of 3 meters.

(c) Emissions radiated outside of the specified frequency bands, except for harmonics, shall be attenuated by at least 50 dB below the level of the fundamental or to the general radiated emission limits in § 15.209, whichever is the lesser attenuation.

(d) As shown in § 15.35(b), for frequencies above 1000 MHz, the above field strength limits are based on average limits. However, the peak field strength of any emission shall not exceed the maximum permitted average limits specified above by more than 20 dB under any condition of modulation.

(e) Parties considering the manufacture, importation, marketing or operation of equipment under this section should also note the requirement in § 15.37(d).

[54 FR 17714, Apr. 25, 1989, as amended at 55 FR 25095, June 20, 1990]

§ 15.251 Operation within the bands 2.9–3.26 GHz, 3.267–3.332 GHz, 3.339–3.3458 GHz, and 3.358–3.6 GHz.

(a) Operation under the provisions of this section is limited to automatic vehicle identification systems (AVIS) which use swept frequency techniques for the purpose of automatically identifying transportation vehicles.

(b) The field strength anywhere within the frequency range swept by the signal shall not exceed 3000 microvolts/meter/MHz at 3 meters in any direction. Further, an AVIS, when in its operating position, shall not produce a field strength greater than 400 microvolts/meter/MHz at 3 meters in any direction within ± 10 degrees of the

§ 15.253

horizontal plane. In addition to the provisions of §15.205, the field strength of radiated emissions outside the frequency range swept by the signal shall be limited to a maximum of 100 microvolts/meter/MHz at 3 meters, measured from 30 MHz to 20 GHz for the complete system. The emission limits in this paragraph are based on measurement instrumentation employing an average detector. The provisions in §15.35 for limiting peak emissions apply.

(c) The minimum sweep repetition rate of the signal shall not be lower than 4000 sweeps per second, and the maximum sweep repetition rate of the signal shall not exceed 50,000 sweeps per second.

(d) An AVIS shall employ a horn antenna or other comparable directional antenna for signal emission.

(e) Provision shall be made so that signal emission from the AVIS shall occur only when the vehicle to be identified is within the radiated field of the system.

(f) In addition to the labelling requirements in §15.19(a), the label attached to the AVIS transmitter shall contain a third statement regarding operational conditions, as follows:

* * * and, (3) during use this device (the antenna) may not be pointed within $\pm^{**}$ degrees of the horizontal plane.

The double asterisks in condition three (**) shall be replaced by the responsible party with the angular pointing restriction necessary to meet the horizontal emission limit specified in paragraph (b).

(g) In addition to the information required in subpart J of part 2, the application for certification shall contain:

(1) Measurements of field strength per MHz along with the intermediate frequency of the spectrum analyzer or equivalent measuring receiver;

(2) The angular separation between the direction at which maximum field strength occurs and the direction at which the field strength is reduced to 400 microvolts/meter/MHz at 3 meters;

(3) A photograph of the spectrum analyzer display showing the entire swept frequency signal and a calibrated scale for the vertical and horizontal axes; the spectrum analyzer settings that

47 CFR Ch. I (10–1–97 Edition)

were used shall be labelled on the photograph; and,

(4) The results of the frequency search for spurious and sideband emissions from 30 MHz to 20 GHz, exclusive of the swept frequency band, with the measuring instrument as close as possible to the unit under test.

[54 FR 17714, Apr. 25, 1989; 54 FR 32340, Aug. 7, 1989]

§ 15.253 Operation within the bands 46.7–46.9 GHz and 76.0–77.0 GHz.

(a) Operation within the bands 46.7–46.9 GHz and 76.0–77.0 GHz is restricted to vehicle-mounted field disturbance sensors used as vehicle radar systems. The transmission of additional information, such as data, is permitted provided the primary mode of operation is as a vehicle-mounted field disturbance sensor. Operation under the provisions of this section is not permitted on aircraft or satellites.

(b) The radiated emission limits within the bands 46.7–46.9 GHz and 76.0–77.0 GHz are as follows:

(1) If the vehicle is not in motion, the power density of any emission within the bands specified in this section shall not exceed 200 nW/cm² at a distance of 3 meters from the exterior surface of the radiating structure.

(2) For forward-looking vehicle-mounted field disturbance sensors, if the vehicle is in motion the power density of any emission within the bands specified in this section shall not exceed 60 μ W/cm² at a distance of 3 meters from the exterior surface of the radiating structure.

(3) For side-looking or rear-looking vehicle-mounted field disturbance sensors, if the vehicle is in motion the power density of any emission within the bands specified in this section shall not exceed 30 μ W/cm² at a distance of 3 meters from the exterior surface of the radiating structure.

(c) The power density of any emissions outside the operating band shall consist solely of spurious emissions and shall not exceed the following:

(1) For vehicle-mounted field disturbance sensors operating in the band 46.7–46.9 GHz: 2 pW/cm² at a distance of 3 meters from the exterior surface of the radiating structure.

Federal Communications Commission

§ 15.255

(2) For forward-looking vehicle-mounted field disturbance sensors operating in the band 76–77 GHz: 600 pW/cm² at a distance of 3 meters from the exterior surface of the radiating structure.

(3) For side-looking or rear-looking vehicle-mounted field disturbance sensors operating in the band 76–77 GHz: 300 pW/cm² at a distance of 3 meters from the exterior surface of the radiating structure.

(4) Radiated emissions below 40 GHz shall not exceed the general limits in § 15.209.

(d) The provisions in § 15.35 limiting peak emissions apply.

(e) Fundamental emissions must be contained within the frequency bands specified in this section during all conditions of operation. Equipment is presumed to operate over the temperature range –20 to +50 degrees celsius with an input voltage variation of 85% to 115% of rated input voltage, unless justification is presented to demonstrate otherwise.

(f) Regardless of the power density levels permitted under this section, devices operating under the provisions of this section are subject to the radio-frequency radiation exposure requirements specified in §§ 1.1307(b), 2.1091 and 2.1093 of this chapter, as appropriate. Applications for equipment authorization of devices operating under this section must contain a statement confirming compliance with these requirements for both fundamental emissions and unwanted emissions. Technical information showing the basis for this statement must be submitted to the Commission upon request.

[61 FR 14503, Apr. 2, 1996, as amended at 61 FR 41018, Aug. 7, 1996]

§ 15.255 Operation within the band 59.0–64.0 GHz.

(a) Operation under the provisions of this section is not permitted for the following products:

(1) Equipment used on aircraft or satellites; and

(2) Field disturbance sensors, including vehicle radar systems, unless the field disturbance sensors are employed for fixed operation. For the purposes of this section, the reference to fixed operation includes field disturbance sen-

sors installed in fixed equipment, even if the sensor itself moves within the equipment.

(b) Within the 59–64 GHz band, emission levels shall not exceed the following:

(1) For products other than fixed field disturbance sensors, the power density of any emission shall not exceed 9 μW/cm² at a distance of 3 meters;

(2) For fixed field disturbance sensors that occupy 500 MHz or less of bandwidth and that are contained wholly within the frequency band 61.0–61.5 GHz, the power density of any emission within the band 61.0–61.5 GHz shall not exceed 9 μW/cm² at a distance of 3 meters and the power density of any emission outside of the 61.0–61.5 GHz band, but still within the 59–64 GHz band, shall not exceed 9 nW/cm² at a distance of 3 meters; and

(3) For fixed field disturbance sensors other than those operating under the provisions of paragraph (b)(2) of this section, the peak transmitter output power shall not exceed 0.1 mW and the peak power density shall not exceed 9 nW/cm² at a distance of 3 meters.

NOTE TO PARAGRAPH (B): Equipment may be authorized and operated on an interim basis under the provisions of this section provided it complies with the Spectrum Etiquette parameters contained in the December 13, 1996 submission from the Millimeter Wave Communications Working Group in ET Docket 94–124. Copies of the submission are available for inspection at the Federal Communications Commission Reference Center (Room 239), 1919 M Street, N.W., Washington, D.C., and may also be purchased from the Federal Communications Commission's duplication contractor, International Transcription Service, (202) 857–3800, 1231 20th Street, N.W., Washington, D.C. 20036. The submission is also available for viewing on the FCC's internet website [<http://www.fcc.gov/oet/dockets/et94-124/>].

(c) The power density of any emissions outside the 59.0–64.0 GHz band shall consist solely of spurious emissions and shall not exceed 90 pW/cm² at a distance of 3 meters. The levels of the spurious emissions shall not exceed the level of the fundamental emission.

(d) Radiated emissions below 40 GHz shall not exceed the general limits in § 15.209.

(e) The provisions in § 15.35 limiting peak emissions apply.

§ 15.301

47 CFR Ch. I (10–1–97 Edition)

(f) Fundamental emissions must be contained within the frequency bands specified in this section during all conditions of operation. Equipment is presumed to operate over the temperature range -20 to $+50$ degrees celsius with an input voltage variation of 85% to 115% of rated input voltage, unless justification is presented to demonstrate otherwise.

(g) Regardless of the power density levels permitted under this section, devices operating under the provisions of this section are subject to the radio-frequency radiation exposure requirements specified in §§ 1.1307(b), 2.1091 and 2.1093 of this chapter, as appropriate. Applications for equipment authorization of devices operating under this section must contain a statement confirming compliance with these requirements for both fundamental emissions and unwanted emissions. Technical information showing the basis for this statement must be submitted to the Commission upon request.

[61 FR 14503, Apr. 2, 1996, as amended at 61 FR 41018, Aug. 7, 1996; 62 FR 45333, Aug. 27, 1997]

EFFECTIVE DATE NOTE: At 61 FR 14503, Apr. 2, 1996, § 15.255 was added and stayed indefinitely, effective May 2, 1996.

Subpart D—Unlicensed Personal Communications Service Devices

SOURCE: 58 FR 59180, Nov. 8, 1993, unless otherwise noted.

§ 15.301 Scope.

This subpart sets out the regulations for unlicensed personal communications services (PCS) devices operating in the 1910–1930 MHz and 2390–2400 MHz frequency bands.

[60 FR 13073, Mar. 10, 1995]

§ 15.303 Definitions.

(a) *Asynchronous devices*. Devices that transmit RF energy at irregular time intervals, as typified by local area network data systems.

(b) *Coordinatable PCS device*. PCS devices whose geographical area of operation is sufficiently controlled either by necessity of operation with a fixed infrastructure or by disabling mechanisms to allow adequate coordination

of their locations relative to incumbent fixed microwave facilities.

(c) *Emission bandwidth*. For purposes of this subpart the emission bandwidth shall be determined by measuring the width of the signal between two points, one below the carrier center frequency and one above the carrier center frequency, that are 26 dB down relative to the maximum level of the modulated carrier. Compliance with the emissions limits is based on the use of measurement instrumentation employing a peak detector function with an instrument resolutions bandwidth approximately equal to 1.0 percent of the emission bandwidth of the device under measurement.

(d) *Isochronous devices*. Devices that transmit at a regular interval, typified by time-division voice systems.

(e) *Noncoordinatable PCS device*. A PCS device that is capable of randomly roaming and operating in geographic areas containing incumbent microwave facilities such that operation of the PCS device will potentially cause harmful interference to the incumbent microwave facilities.

(f) *Peak transmit power*. The peak power output as measured over an interval of time equal to the frame rate or transmission burst of the device under all conditions of modulation. Usually this parameter is measured as a conducted emission by direct connection of a calibrated test instrument to the equipment under test. If the device cannot be connected directly, alternative techniques acceptable to the Commission may be used.

(g) *Personal Communications Services (PCS) Devices [Unlicensed]*. Intentional radiators operating in the frequency bands 1910–1930 MHz and 2390–2400 MHz that provide a wide array of mobile and ancillary fixed communication services to individuals and businesses.

(h) *Spectrum window*. An amount of spectrum equal to the intended emission bandwidth in which operation is desired.

(i) *Sub-band*. For purposes of this subpart the term sub-band refers to the spectrum allocated for isochronous or asynchronous transmission.

(j) *Thermal noise power*. The noise power in watts defined by the formula $N=kTB$ where N is the noise power in

Federal Communications Commission

§ 15.309

watts, K is Boltzmann's constant, T is the absolute temperature in degrees Kelvin (e.g., 295 °K) and B is the emission bandwidth of the device in hertz.

(k) *Time window*. An interval of time in which transmission is desired.

[58 FR 59180, Nov. 8, 1993, as amended at 59 FR 32852, June 24, 1994; 60 FR 13073, Mar. 10, 1995]

§ 15.305 Equipment authorization requirement.

PCS devices operating under this subpart shall be certified by the Commission under the procedures in subpart J of part 2 of this chapter before marketing. The application for certification must contain sufficient information to demonstrate compliance with the requirements of this subpart.

§ 15.307 Coordination with fixed microwave service.

(a) UTAM, Inc. is designated to coordinate and manage the transition of the 1910–1930 MHz band from the Private Operational-Fixed Microwave Service (OFS) operating under part 101 of this chapter to unlicensed PCS operations,

(b) Each application for certification of equipment operating under the provisions of this subpart must be accompanied by an affidavit from UTAM, Inc. certifying that the applicant is a participating member of UTAM, Inc. In the event a grantee fails to fulfill the obligations attendant to participation in UTAM, Inc., the Commission may invoke administrative sanctions as necessary to preclude continued marketing and installation of devices covered by the grant of certification, including but not limited to revoking certification.

(c) An application for certification of a PCS device that is deemed by UTAM, Inc. to be noncoordinatable will not be accepted until the Commission announces that a need for coordination no longer exists.

(d) A coordinatable PCS device is required to incorporate means that ensure that it cannot be activated until its location has been coordinated by UTAM, Inc. The application for certification shall contain an explanation of all measures taken to prevent unauthorized operation. This explanation

shall include all procedural safeguards, such as the mandatory use of licensed technicians to install the equipment, and a complete description of all technical features controlling activation of the device.

(e) A coordinatable PCS device shall incorporate an automatic mechanism for disabling operation in the event it is moved outside the geographic area where its operation has been coordinated by UTAM, Inc. The application for certification shall contain a full description of the safeguards against unauthorized relocation and must satisfy the Commission that the safeguards cannot be easily defeated.

(f) At such time as the Commission deems that the need for coordination between unlicensed PCS operations and existing Part 101 Private Operational-Fixed Microwave Services ceases to exist, the disabling mechanism required by paragraph (e) of this section will no longer be required.

(g) Operations under the provisions of this subpart are required to protect systems in the Private Operational-Fixed Microwave Service operating within the 1850–1990 MHz band until the dates and conditions specified in §§ 101.69 through 101.73 of this chapter for termination of primary status. Interference protection is not required for part 101 stations in this band licensed on a secondary basis.

(h) The operator of a PCS device that is relocated from the coordinated area specified by UTAM, Inc., must cease operating the device until coordination for the new location is verified by UTAM, Inc.

[58 FR 59180, Nov. 8, 1993, as amended at 59 FR 32852, June 24, 1994; 60 FR 27425, May 24, 1995; 61 FR 29689, June 12, 1996]

§ 15.309 Cross reference.

(a) The provisions of subpart A of this part apply to unlicensed PCS devices, except where specific provisions are contained in subpart D.

(b) The requirements of subpart D apply only to the radio transmitter contained in the PCS device. Other aspects of the operation of a PCS device may be subject to requirements contained elsewhere in this chapter. In particular, a PCS device that includes

§ 15.311

digital circuitry not directly associated with the radio transmitter also is subject to the requirements for unintentional radiators in subpart B.

§ 15.311 Labelling requirements.

In addition to the labelling requirements of § 15.19(a)(3), all devices operating in the frequency band 1910–1930 MHz authorized under this subpart must bear a prominently located label with the following statement:

Installation of this equipment is subject to notification and coordination with UTAM, Inc. Any relocation of this equipment must be coordinated through, and approved by UTAM. UTAM may be contacted at [insert UTAM's toll-free number].

[60 FR 13073, Mar. 10, 1995]

§ 15.313 Measurement procedures.

Measurements must be made in accordance with subpart A, except where specific procedures are specified in subpart D. If no guidance is provided, the measurement procedure must be in accordance with good engineering practice.

§ 15.315 Conducted limits.

An unlicensed PCS device that is designed to be connected to the public utility (AC) power line must meet the limits specified in § 15.207.

§ 15.317 Antenna requirement.

An unlicensed PCS device must meet the antenna requirement of § 15.203.

§ 15.319 General technical requirements.

(a) The 1910–1920 MHz and 2390–2400 MHz bands are limited to use by asynchronous devices under the requirements of § 15.321. The 1920–1930 MHz sub-band is limited to use by isochronous devices under the requirements of § 15.323.

(b) All transmissions must use only digital modulation techniques.

(c) Peak transmit power shall not exceed 100 microwatts multiplied by the square root of the emission bandwidth in hertz. Peak transmit power must be measured over any interval of continuous transmission using instrumentation calibrated in terms of an rms-equivalent voltage. The measurement results shall be properly adjusted for

47 CFR Ch. I (10–1–97 Edition)

any instrument limitations, such as detector response times, limited resolution bandwidth capability when compared to the emission bandwidth, sensitivity, etc., so as to obtain a true peak measurement for the emission in question over the full bandwidth of the channel.

(d) Power spectral density shall not exceed 3 milliwatts in any 3 kHz bandwidth as measured with a spectrum analyzer having a resolution bandwidth of 3 kHz.

(e) The peak transmit power shall be reduced by the amount in decibels that the maximum directional gain of the antenna exceeds 3 dBi.

(f) The device shall automatically discontinue transmission in case of either absence of information to transmit or operational failure. The provisions in this section are not intended to preclude transmission of control and signaling information or use of repetitive codes used by certain digital technologies to complete frame or burst intervals.

(g) Notwithstanding other technical requirements specified in this subpart, attenuation of emissions below the general emission limits in § 15.209 is not required.

(h) Where there is a transition between limits, the tighter limit shall apply at the transition point.

(i) Unlicensed PCS devices are subject to the radiofrequency radiation exposure requirements specified in §§ 1.1307(b), 2.1091 and 2.1093 of this chapter, as appropriate. All equipment shall be considered to operate in a “general population/uncontrolled” environment. Applications for equipment authorization of devices operating under this section must contain a statement confirming compliance with these requirements for both fundamental emissions and unwanted emissions. Technical information showing the basis for this statement must be submitted to the Commission upon request.

[58 FR 59180, Nov. 8, 1993, as amended at 59 FR 32852, June 24, 1994; 59 FR 40835, Aug. 10, 1994; 60 FR 13073, Mar. 10, 1995; 61 FR 41018, Aug. 7, 1996]

Federal Communications Commission

§ 15.321

§ 15.321 Specific requirements for asynchronous devices operating in the 1910–1920 MHz and 2390–2400 MHz bands.

(a) Operation shall be contained within either or both of the 1910–1920 MHz and 2390–2400 MHz bands. The emission bandwidth of any intentional radiator operating in these bands shall be no less than 500 kHz.

(b) All systems of less than 2.5 MHz emission bandwidth shall start searching for an available spectrum window within 3 MHz of the band edge at 1910, 1920, 2390, or 2400 MHz while systems of more than 2.5 MHz emission bandwidth will first occupy the center half of the band. Devices with an emission bandwidth of less than 1.0 MHz may not occupy the center half of the band if other spectrum is available.

(c) Asynchronous devices must incorporate a mechanism for monitoring the spectrum that its transmission is intended to occupy. The following criteria must be met:

(1) Immediately prior to initiating a transmission, devices must monitor the spectrum window they intend to use for at least 50 microseconds.

(2) The monitoring threshold must not be more than 32 dB above the thermal noise power for a bandwidth equivalent to the emission bandwidth of the device.

(3) If no signal above the threshold level is detected, a transmission burst may commence in the monitored spectrum window. Once a transmission burst has started, an individual device or a group of cooperative devices is not required to monitor the spectrum window provided the intraburst gap timing requirement specified below is not exceeded.

(4) After completion of a transmission, an individual device or co-operating group of devices must cease transmission and wait a deference time randomly chosen from a uniform random distribution ranging from 50 to 750 microseconds, after which time an attempt to access the band again may be initiated. For each occasion that an access attempt fails after the initial inter-burst interval, the range of the deference time chosen shall double until an upper limit of 12 milliseconds is reached. The deference time remains

at the upper limit of 12 milliseconds until an access attempt is successful. The deference time is re-initialized after each successful access attempt.

(5) The monitoring system bandwidth must be equal to or greater than the emission bandwidth of the intended transmission and shall have a maximum reaction time less than $50 \times \text{SQRT}(1.25/\text{emission bandwidth in MHz})$ microseconds for signals at the applicable threshold level but shall not be required to be less than 50 microseconds. If a signal is detected that is 6 dB or more above the threshold level, the maximum reaction time shall be $35 \times \text{SQRT}(1.25/\text{emission bandwidth in MHz})$ microseconds but shall not be required to be less than 35 microseconds.

(6) The monitoring system shall use the same antenna used for transmission, or an antenna that yields equivalent reception at that location.

(7) Devices that have a power output lower than the maximum permitted under the rules may increase their detection threshold by one decibel for each one decibel that the transmitter power is below the maximum permitted.

(d) Emissions shall be attenuated below a reference power of 112 milliwatts as follows: 30 dB between the sub-band edges and 1.25 MHz above or below the sub-band; 50 dB between 1.25 and 2.5 MHz above or below the sub-band; and 60 dB at 2.5 MHz or greater above or below the sub-band. Compliance with the emissions limits is based on the use of measurement instrumentation employing a peak detector function with an instrument resolution bandwidth approximately equal to 1.0 percent of the emission bandwidth of the device under measurement.

(e) The frequency stability of the carrier frequency of intentional radiators operating in accordance with this section shall be ± 10 ppm over 10 milliseconds or the interval between channel access monitoring, whichever is shorter. The frequency stability shall be maintained over a temperature variation of -20° to $+50^\circ$ Celsius at normal supply voltage, and over a variation in the primary supply voltage of 85 percent to 115 percent of the rated supply voltage at a temperature of 20 degrees

Celsius. For equipment that is capable of operating only from a battery, the frequency stability tests shall be performed using a new battery without any further requirement to vary supply voltage.

(f) An asynchronous transmission burst is a series of transmissions from one or more transmitters acting cooperatively. The transmission burst duration from one device or group of devices acting cooperatively shall be no greater than 10 milliseconds. Any intraburst gap between cooperating devices shall not exceed 25 microseconds.

(g) Operation of devices in the 2390–2400 MHz band from aircraft while airborne is prohibited, in order to protect space research operations at the National Astronomy and Ionospheric Center at Arecibo, Puerto Rico.

[58 FR 59180, Nov. 8, 1993; 59 FR 15269, Mar. 31, 1994. Redesignated at 59 FR 32852, June 24, 1994, as amended at 59 FR 32853, June 24, 1994; 59 FR 40835, Aug. 10, 1994; 60 FR 13073, Mar. 10, 1995; 61 FR 55926, Oct. 30, 1996]

§ 15.323 Specific requirements for isochronous devices operating in the 1920–1930 MHz sub-band.

(a) Operation shall be contained within one of eight 1.25 MHz channels starting with 1920–1921.25 MHz and ending with 1928.75–1930 MHz. Further subdivision of a 1.25 MHz channel is permitted with a reduced power level, as specified in § 15.319(c), but in no event shall the emission bandwidth be less than 50 kHz.

(b) Intentional radiators with an intended emission bandwidth less than 625 kHz shall start searching for an available time and spectrum window within 3 MHz of the sub-band edge at 1920 MHz and search upward from that point. Devices with an intended emission bandwidth greater than 625 kHz shall start searching for an available time and spectrum window within 3 MHz of the sub-band edge at 1930 MHz and search downward from that point.

(c) Isochronous devices must incorporate a mechanism for monitoring the time and spectrum windows that its transmission is intended to occupy. The following criteria must be met:

(1) Immediately prior to initiating transmission, devices must monitor the combined time and spectrum win-

dows in which they intend to transmit for a period of at least 10 milliseconds for systems designed to use a 10 milliseconds or shorter frame period or at least 20 milliseconds for systems designed to use a 20 milliseconds frame period.

(2) The monitoring threshold must not be more than 30 dB above the thermal noise power for a bandwidth equivalent to the emission bandwidth used by the device.

(3) If no signal above the threshold level is detected, transmission may commence and continue with the same emission bandwidth in the monitored time and spectrum windows without further monitoring. However, occupation of the same combined time and spectrum windows by a device or group of cooperating devices continuously over a period of time longer than 8 hours is not permitted without repeating the access criteria.

(4) Once access to specific combined time and spectrum windows is obtained an acknowledgment from a system participant must be received by the initiating transmitter within one second or transmission must cease. Periodic acknowledgments must be received at least every 30 seconds or transmission must cease. Channels used exclusively for control and signaling information may transmit continuously for 30 seconds without receiving an acknowledgment, at which time the access criteria must be repeated.

(5) If access to spectrum is not available as determined by the above, and a minimum of 40 duplex system access channels are defined for the system, the time and spectrum windows with the lowest power level below a monitoring threshold of 50 dB above the thermal noise power determined for the emission bandwidth may be accessed. A device utilizing the provisions of this paragraph must have monitored all access channels defined for its system within the last 10 seconds and must verify, within the 20 milliseconds (40 milliseconds for devices designed to use a 20 milliseconds frame period) immediately preceding actual channel access that the detected power of the selected time and spectrum windows is no higher than the previously detected value. The power measurement resolution for

this comparison must be accurate to within 6 dB. No device or group of co-operating devices located within 1 meter of each other shall occupy more than three 1.25 MHz channels during any frame period. Devices in an operational state that are utilizing the provisions of this section are not required to use the search provisions of paragraph (b) of this section.

(6) If the selected combined time and spectrum windows are unavailable, the device may either monitor and select different windows or seek to use the same windows after waiting an amount of time, randomly chosen from a uniform random distribution between 10 and 150 milliseconds, commencing when the channel becomes available.

(7) The monitoring system bandwidth must be equal to or greater than the emission bandwidth of the intended transmission and have a maximum reaction time less than $50 \times \text{SQRT}(1.25/\text{emission bandwidth in MHz})$ microseconds for signals at the applicable threshold level but shall not be required to be less than 50 microseconds. If a signal is detected that is 6 dB or more above the applicable threshold level, the maximum reaction time shall be $35 \times \text{SQRT}(1.25/\text{emission bandwidth in MHz})$ microseconds but shall not be required to be less than 35 microseconds.

(8) The monitoring system shall use the same antenna used for transmission, or an antenna that yields equivalent reception at that location.

(9) Devices that have a power output lower than the maximum permitted under this subpart may increase their monitoring detection threshold by one decibel for each one decibel that the transmitter power is below the maximum permitted.

(10) An initiating device may attempt to establish a duplex connection by monitoring both its intended transmit and receive time and spectrum windows. If both the intended transmit and receive time and spectrum windows meet the access criteria, then the initiating device can initiate a transmission in the intended transmit time and spectrum window. If the power detected by the responding device can be decoded as a duplex connection signal from the initiating device, then the re-

sponding device may immediately begin transmitting on the receive time and spectrum window monitored by the initiating device.

(11) An initiating device that is prevented from monitoring during its intended transmit window due to monitoring system blocking from the transmissions of a co-located (within one meter) transmitter of the same system, may monitor the portions of the time and spectrum windows in which they intend to receive over a period of at least 10 milliseconds. The monitored time and spectrum window must total at least 50 percent of the 10 millisecond frame interval and the monitored spectrum must be within the 1.25 MHz frequency channel(s) already occupied by that device or co-located co-operating devices. If the access criteria is met for the intended receive time and spectrum window under the above conditions, then transmission in the intended transmit window by the initiating device may commence.

(12) The provisions of (c)(10) or (c)(11) of this section shall not be used to extend the range of spectrum occupied over space or time for the purpose of denying fair access to spectrum to other devices.

(d) Emissions shall be attenuated below a reference power of 112 milliwatts as follows: 30 dB between the channel edges and 1.25 MHz above or below the channel; 50 dB between 1.25 and 2.5 MHz above or below the channel; and 60 dB at 2.5 MHz or greater above or below the channel. Systems that further sub-divide a 1.25 MHz channel into X sub-channels must comply with the following emission mask: In the bands between 1B and 2B measured from the center of the emission bandwidth the total power emitted by the device shall be at least 30 dB below the transmit power permitted for that device; in the bands between 2B and 3B measured from the center of the emission bandwidth the total power emitted by an intentional radiator shall be at least 50 dB below the transmit power permitted for that radiator; in the bands between 3B and the 1.25 MHz channel edge the total power emitted by an intentional radiator in the measurement bandwidth shall be at least 60

§ 15.401

dB below the transmit power permitted for that radiator. “B” is defined as the emission bandwidth of the device in hertz. Compliance with the emission limits is based on the use of measurement instrumentation employing a peak detector function with an instrument resolution bandwidth approximately equal to 1.0 percent of the emission bandwidth of the device under measurement.

(e) The frame period (a set of consecutive time slots in which the position of each time slot can be identified by reference to a synchronizing source) of an intentional radiator operating in these sub-bands shall be 20 milliseconds or 10 milliseconds/X where X is a positive whole number. Each device that implements time division for the purposes of maintaining a duplex connection on a given frequency carrier shall maintain a frame repetition rate with a frequency stability of at least 50 parts per million (ppm). Each device which further divides access in time in order to support multiple communication links on a given frequency carrier shall maintain a frame repetition rate with a frequency stability of at least 10 ppm. The jitter (time-related, abrupt, spurious variations in the duration of the frame interval) introduced at the two ends of such a communication link shall not exceed 25 microseconds for any two consecutive transmissions. Transmissions shall be continuous in every time and spectrum window during the frame period defined for the device.

(f) The frequency stability of the carrier frequency of the intentional radiator shall be maintained within ± 10 ppm over 1 hour or the interval between channel access monitoring, whichever is shorter. The frequency stability shall be maintained over a temperature variation of -20° to $+50^{\circ}$ °C at normal supply voltage, and over a variation in the primary supply voltage of 85 percent to 115 percent of the rated supply voltage at a temperature of 20° °C. For equipment that is capable only of operating from a battery, the frequency stability tests shall be performed using a new battery without

47 CFR Ch. I (10–1–97 Edition)

any further requirement to vary supply voltage.

[58 FR 59180, Nov. 8, 1993; 59 FR 15269, Mar. 31, 1994. Redesignated at 59 FR 32852, June 24, 1994, as amended at 59 FR 32853, June 24, 1994; 59 FR 40835, Aug. 10, 1994; 59 FR 55373, Nov. 7, 1994; 60 FR 3303, Jan. 13, 1995]

Subpart E—Unlicensed National Information Infrastructure Devices

SOURCE: 62 FR 4656, Jan. 31, 1997, unless otherwise noted.

§ 15.401 Scope.

This subpart sets out the regulations for unlicensed National Information Infrastructure (U-NII) devices operating in the 5.15–5.35 GHz and 5.725–5.825 GHz bands.

§ 15.403 Definitions.

(a) *U-NII devices (Unlicensed)*. Intentional radiators operating in the frequency bands 5.15–5.35 GHz and 5.725–5.825 GHz that provide a wide array of wideband, high data rate, digital, mobile and fixed communications for individuals, businesses, and institutions.

(b) *Peak transmit power*. The peak power output as measured over an interval of time equal to the frame rate or transmission burst of the device under all conditions of modulation. Usually this parameter is measured as a conducted emission by direct connection of a calibrated test instrument to the equipment under test. If the device cannot be connected directly, alternative techniques acceptable to the Commission may be used.

§ 15.405 Cross reference.

(a) The provisions of subparts A, B, and C of this part apply to unlicensed U-NII devices, except where specific provisions are contained in this subpart E. Manufacturers should note that this includes the provisions of §§ 15.203 and 15.205.

(b) The requirements of this subpart E apply only to the radio transmitter contained in the U-NII device. Other aspects of the operation of a U-NII device may be subject to requirements contained elsewhere in this chapter. In particular, a U-NII device that includes

Federal Communications Commission

§15.407

digital circuitry not directly associated with the radio transmitter also is subject to the requirements for unintentional radiators in subpart B of this part.

§15.407 General technical requirements.

(a) *Power limits:*

(1) For the band 5.15–5.25 GHz, the peak transmit power over the frequency band of operation shall not exceed 50 mW. In addition, the peak power spectral density shall not exceed 2.5 mW/MHz. If transmitting antennas of directional gain greater than 6 dBi are used, both the peak transmit power and the peak power spectral density shall be reduced by the amount in dB that the directional gain of the antenna exceeds 6 dBi.

(2) For the band 5.25–5.35 GHz, the peak transmit power over the frequency band of operation shall not exceed 250 mW. In addition, the peak power spectral density shall not exceed 12.5 mW/MHz. If transmitting antennas of directional gain greater than 6 dBi are used, both the peak transmit power and the peak power spectral density shall be reduced by the amount in dB that the directional gain of the antenna exceeds 6 dBi.

(3) For the band 5.725–5.825 GHz, the peak transmit power over the frequency band of operation shall not exceed 1 W. In addition, the peak power spectral density shall not exceed 50 mW/MHz. If transmitting antennas of directional gain greater than 6 dBi are used, both the peak transmit power and the peak power spectral density shall be reduced by the amount in dB that the directional gain of the antenna exceeds 6 dBi.

(4) The peak transmit power must be measured over any interval of continuous transmission using instrumentation calibrated in terms of an rms-equivalent voltage. The measurement results shall be properly adjusted for any instrument limitations, such as detector response times, limited resolution bandwidth capability when compared to the emission bandwidth, sensitivity, etc., so as to obtain a true peak measurement for the emission in question over the full bandwidth of the channel.

(5) The peak power spectral density is measured as a conducted emission by direct connection of a calibrated test instrument to the equipment under test. Measurements are made using a resolution bandwidth of 1 MHz. If the device can not be connected directly, alternative techniques acceptable to the Commission may be used.

(b) The peak levels of emissions outside of the frequency band of operation shall be attenuated below the maximum peak power spectral density contained within the band of operation in accordance with the following limits:

(1) For transmitters operating in the band 5.15–5.25 GHz: all emissions within the frequency range 5.14–5.15 GHz and 5.35–5.36 GHz must be attenuated by a factor of at least 27 dB; within the frequency range outside these bands by a factor of at least 37 dB.

(2) For transmitters operating in the 5.25–5.35 GHz band: all emissions within the frequency range from the band edge to 10 MHz above or below the band edge must be attenuated by a factor of at least 34 dB; for frequencies 10 MHz or greater above or below the band edge by a factor of at least 44 dB.

(3) For transmitters operating in the 5.725–5.825 GHz band: all emissions within the frequency range from the band edge to 10 MHz above or below the band edge must be attenuated by a factor of at least 40 dB; for frequencies 10 MHz or greater above or below the band edge by a factor of at least 50 dB.

(4) The above emission measurements shall be performed using a minimum resolution bandwidth of 1 MHz. A lower resolution bandwidth may be employed near the band edge, when necessary, provided the measured energy is integrated to show the total power over 1 MHz. Regardless of the attenuation levels shown above, emissions outside the frequency range of operation do not need to be attenuated below the general radiated emission limits in §15.209.

(5) Unwanted emissions must comply with the general field strength limits set forth in §15.209. Further, any U-NII devices using an AC power line are required to comply also with the conducted limits set forth in §15.207.

(6) The provisions of §15.205 of this part apply to intentional radiators operating under this section.

(7) When measuring the emission limits, the nominal carrier frequency shall be adjusted as close to the upper and lower frequency block edges as the design of the equipment permits.

(c) The device shall automatically discontinue transmission in case of either absence of information to transmit or operational failure. These provisions are not intended to preclude the transmission of control or signalling information or the use of repetitive codes used by certain digital technologies to complete frame or burst intervals.

(d) Any U–NII device that operates in the 5.15–5.25 GHz band shall use a transmitting antenna that is an integral part of the device.

(e) Within the 5.15–5.25 GHz band, U–NII devices will be restricted to indoor operations to reduce any potential for harmful interference to co-channel MSS operations.

(f) U–NII devices are subject to the radio frequency radiation exposure requirements specified in §§1.1307(b), 2.1091 and 2.1093 of this chapter, as appropriate. All equipment shall be considered to operate in a “general population/uncontrolled” environment. Applications for equipment authorization of devices operating under this section must contain a statement confirming compliance with these requirements for both fundamental emissions and unwanted emissions. Technical information showing the basis for this statement must be submitted to the Commission upon request.

(g) The frequency stability of the carrier frequency of an intentional radiator operating under this section shall be #10 ppm over 10 milliseconds. The frequency stability shall be maintained over a temperature variation of –20 degrees to +50 degrees Celsius at normal supply voltage, and over a variation in the primary supply voltage of 85 percent to 115 percent of the rated supply voltage at a temperature of +20 degrees Celsius. For equipment that is capable of operating only from a battery, the frequency stability tests shall be performed using a new battery without any further requirement to vary supply voltage.

PART 17—CONSTRUCTION, MARKING, AND LIGHTING OF ANTENNA STRUCTURES

Subpart A—General Information

Sec.

- 17.1 Basis and purpose.
- 17.2 Definitions.
- 17.4 Antenna structure registration.
- 17.5 Commission consideration of applications for station authorization.
- 17.6 Responsibility of Commission licensees and permittees.

Subpart B—Federal Aviation Administration Notification Criteria

- 17.7 Antenna structures requiring notification to the FAA.
- 17.8 Establishment of antenna farm areas.
- 17.9 Designated antenna farm areas.
- 17.10 Antenna structures over 304.80 meters (1,000 feet) in height.
- 17.14 Certain antenna structures exempt from notification to the FAA.
- 17.17 Existing structures.

Subpart C—Specifications for Obstruction Marking and Lighting of Antenna Structures

- 17.21 Painting and lighting, when required.
- 17.22 Particular specifications to be used.
- 17.23 Specifications for painting and lighting antenna structures.

AVIATION RED OBSTRUCTION LIGHTING [RESERVED]

17.24–17.38 [Reserved]

HIGH INTENSITY WHITE OBSTRUCTION LIGHTING

17.39–17.43 [Reserved]

- 17.45 Temporary warning lights.
- 17.47 Inspection of antenna structure lights and associated control equipment.
- 17.48 Notification of extinguishment or improper functioning of lights.
- 17.49 Recording of antenna structure light inspections in the owner record.
- 17.50 Cleaning and repainting.
- 17.51 Time when lights should be exhibited.
- 17.53 Lighting equipment and paint.
- 17.54 Rated lamp voltage.
- 17.56 Maintenance of lighting equipment.
- 17.57 Report of radio transmitting antenna construction, alteration and/or removal.
- 17.58 Facilities to be located on land under the jurisdiction of the U.S. Forest Service or the Bureau of Land Management.

AUTHORITY: Secs. 4, 303, 48 Stat. 1066, 1082, as amended; 47 U.S.C. 154, 303. Interpret or apply secs. 301, 309, 48 Stat. 1081, 1085 as amended; 47 U.S.C. 301, 309.

Federal Communications Commission

§ 17.4

Subpart A—General Information

§ 17.1 Basis and purpose.

(a) The rules in this part are issued pursuant to the authority contained in Title III of the Communications Act of 1934, as amended, which vest authority in the Federal Communications Commission to issue licenses to radio stations when it is found that the public interest, convenience, and necessity would be served thereby, and to require the painting, and/or illumination of antenna structures if and when in its judgment such structures constitute, or there is reasonable possibility that they may constitute, a menace to air navigation.

(b) The purpose of this part is to prescribe certain procedures for antenna structure registration and standards with respect to the Commission's consideration of proposed antenna structures which will serve as a guide to antenna structure owners. The standards are referenced from two Federal Aviation Administration (FAA) Advisory Circulars.

[61 FR 4362, Feb. 6, 1996]

§ 17.2 Definitions.

(a) *Antenna structure.* The term antenna structure includes the radiating and/or receive system, its supporting structures and any appurtenances mounted thereon.

(b) An antenna farm area is defined as a geographical location, with established boundaries, designated by the Federal Communications Commission, in which antenna towers with a common impact on aviation may be grouped.

(c) *Antenna structure owner.* For the purposes of this part, an antenna structure owner is the individual or entity vested with ownership, equitable ownership, dominion, or title to the antenna structure. Notwithstanding any agreements made between the owner and any entity designated by the owner to maintain the antenna structure, the owner is ultimately responsible for compliance with the requirements of this part.

(d) *Antenna structure registration number.* A unique number, issued by the Commission during the registration

process, which identifies an antenna structure. Once obtained, this number must be used in all filings related to this structure.

[32 FR 8813, June 21, 1967, and 32 FR 11268, Aug. 3, 1967, as amended at 39 FR 26157, July 17, 1974; 61 FR 4362, Feb. 6, 1996]

§ 17.4 Antenna structure registration.

(a) Effective July 1, 1996, the owner of any proposed or existing antenna structure that requires notice of proposed construction to the Federal Aviation Administration must register the structure with the Commission. This includes those structures used as part of stations licensed by the Commission for the transmission of radio energy, or to be used as part of a cable television head end system. If a Federal Government antenna structure is to be used by a Commission licensee, the structure must be registered with the Commission.

(1) For a proposed antenna structure or alteration of an existing antenna structure, the owner must register the structure prior to construction or alteration.

(2) For an existing antenna structure that had been assigned painting or lighting requirements prior to July 1, 1996, the owner must register the structure prior to July 1, 1998.

(3) For a structure that did not originally fall under the definition of "antenna structure," the owner must register the structure prior to hosting a Commission licensee.

(b) Except as provided in paragraph (e) of this section, each owner must file FCC Form 854 with the Commission. Additionally, each owner of a proposed structure referred to in paragraphs (a)(1) or (a)(3) of this section must submit a valid FAA determination of "no hazard." In order to be considered valid by the Commission, the FAA determination of "no hazard" must not have expired prior to the date on which FCC Form 854 is received by the Commission. The height of the structure will include the highest point of the structure including any obstruction lighting or lighting arrester.

§ 17.5

47 CFR Ch. I (10–1–97 Edition)

(c) If an Environmental Assessment is required under § 1.1307 of this chapter, the Bureau will address the environmental concerns prior to processing the registration.

(d) If a final FAA determination of “no hazard” is not submitted along with FCC Form 854, processing of the registration may be delayed or disapproved.

(e) If the owner of the antenna structure cannot file FCC Form 854 because it is subject to a denial of federal benefits under the Anti-Drug Abuse Act of 1988, 21 U.S.C. 862, the first tenant licensee authorized to locate on the structure (excluding tenants that no longer occupy the structure) must register the structure using FCC Form 854, and provide a copy of the Antenna Structure Registration (FCC Form 854R) to the owner. The owner remains responsible for providing a copy of FCC Form 854R to all tenant licensees on the structure and for posting the registration number as required by paragraph (g) of this section.

(f) The Commission shall issue, to the registrant, FCC Form 854R, Antenna Structure Registration, which assigns a unique Antenna Structure Registration Number. The structure owner shall immediately provide a copy of Form 854R to each tenant licensee and permittee.

(g) Except as described in paragraph (h) of this section, the Antenna Structure Registration Number must be displayed in a conspicuous place so that it is readily visible near the base of the antenna structure. Materials used to display the Antenna Structure Registration Number must be weather-resistant and of sufficient size to be easily seen at the base of the antenna structure.

(h) The owner is not required to post the Antenna Structure Registration Number in cases where a federal, state, or local government entity provides written notice to the owner that such a posting would detract from the appearance of a historic landmark. In this case, the owner must make the Antenna Structure Registration Number available to representatives of the Commission, the FAA, and the general public upon reasonable demand.

[61 FR 4362, Feb. 6, 1996]

§ 17.5 Commission consideration of applications for station authorization.

(a) Applications for station authorization, excluding services authorized on a geographic basis, are reviewed to determine whether there is a requirement that the antenna structure in question must be registered with the Commission.

(b) If registration is required, the registrant must supply the structure's registration number upon request by the Commission.

(c) If registration is not required, the application for authorization will be processed without further regard to this chapter.

[61 FR 4362, Feb. 6, 1996]

§ 17.6 Responsibility of Commission licensees and permittees.

(a) The antenna structure owner is responsible for maintaining the painting and lighting in accordance with this part. However, if a licensee or permittee authorized on an antenna structure is aware that the structure is not being maintained in accordance with the specifications set forth on the Antenna Structure Registration (FCC Form 854R) or the requirements of this part, or otherwise has reason to question whether the antenna structure owner is carrying out its responsibility under this part, the licensee or permittee must take immediate steps to ensure that the antenna structure is brought into compliance and remains in compliance. The licensee must:

(1) Immediately notify the structure owner;

(2) Immediately notify the site management company (if applicable);

(3) Immediately notify the Commission; and,

(4) Make a diligent effort to immediately bring the structure into compliance.

(b) In the event of non-compliance by the antenna structure owner, the Commission may require each licensee and permittee authorized on an antenna structure to maintain the structure, for an indefinite period, in accordance with the Antenna Structure Registration (FCC Form 854R) and the requirements of this part.

Federal Communications Commission

§ 17.8

(c) If the owner of the antenna structure cannot file FCC Form 854 because it is subject to a denial of federal benefits under the Anti-Drug Abuse Act of 1988, 21 U.S.C. 862, the first licensee authorized to locate on the structure must register the structure using FCC Form 854, and provide a copy of the Antenna Structure Registration (FCC Form 854R) to the owner. The owner remains responsible for providing a copy of FCC Form 854R to all tenant licensees on the structure and for posting the registration number as required by § 17.4(g).

[61 FR 4363, Feb. 6, 1996]

Subpart B—Federal Aviation Administration Notification Criteria

§ 17.7 Antenna structures requiring notification to the FAA.

A notification to the Federal Aviation Administration is required, except as set forth in § 17.14, for any of the following construction or alteration:

(a) Any construction or alteration of more than 60.96 meters (200 feet) in height above ground level at its site.

(b) Any construction or alteration of greater height than an imaginary surface extending outward and upward at one of the following slopes:

(1) 100 to 1 for a horizontal distance of 6.10 kilometers (20,000 feet) from the nearest point of the nearest runway of each airport specified in paragraph (d) of this section with at least one runway more than 0.98 kilometers (3,200 feet) in actual length, excluding heliports.

(2) 50 to 1 for a horizontal distance of 3.05 kilometers (10,000 feet) from the nearest point of the nearest runway of each airport specified in paragraph (d) of this section with its longest runway no more than 0.98 kilometers (3,200 feet) in actual length, excluding heliports.

(3) 25 to 1 for a horizontal distance of 1.52 kilometers (5,000 feet) from the nearest point of the nearest landing and takeoff area of each heliport specified in paragraph (d) of this section.

(c) When requested by the FAA, any construction or alteration that would be in an instrument approach area (defined in the FAA standards governing

instrument approach procedures) and available information indicates it might exceed an obstruction standard of the FAA.

(d) Any construction or alteration on any of the following airports (including heliports):

(1) An airport that is available for public use and is listed in the Airport Directory of the current Airman's Information Manual or in either the Alaska or Pacific Airman's Guide and Chart Supplement.

(2) An airport under construction, that is the subject of a notice or proposal on file with the Federal Aviation Administration, and except for military airports, it is clearly indicated that the airport will be available for public use.

(3) An airport that is operated by an armed force of the United States.

NOTE: Consideration to aeronautical facilities not in existence at the time of the filing of the application for radio facilities will be given only when proposed airport construction or improvement plans are on file with the Federal Aviation Administration as of the filing date of the application for such radio facilities.

[39 FR 7581, Feb. 27, 1974, as amended at 39 FR 26157, July 17, 1974; 42 FR 54823, Oct. 11, 1977; 42 FR 57127, Nov. 1, 1977]

§ 17.8 Establishment of antenna farm areas.

(a) Each antenna farm area will be established by an appropriate rulemaking proceeding, which may be commenced by the Commission on its own motion after consultation with the FAA, upon request of the FAA, or as a result of a petition filed by any interested person. After receipt of a petition from an interested person disclosing sufficient reasons to justify institution of a rulemaking proceeding, the Commission will request the advice of the FAA with respect to the considerations of menace to air navigation in terms of air safety which may be presented by the proposal. The written communication received from the FAA in response to the Commission's request shall be placed in the Commission's public rulemaking file containing the petition, and interested persons shall be allowed a period of 30 days within which to file statements with respect thereto. Such

§ 17.9

statements shall also be filed with the Administrator of the FAA with proof of such filing to be established in accordance with § 1.47 of this chapter. The Administrator of the FAA shall have a period of 15 days within which to file responses to such statements. If the Commission, upon consideration of the matters presented to it in accordance with the above procedure, is satisfied that establishment of the proposed antenna farm would constitute a menace to air navigation for reasons of air safety, rulemaking proceedings will not be instituted. If rulemaking proceedings are instituted, any person filing comments therein which concern the question of whether the proposed antenna farm will constitute a menace to air navigation shall file a copy of the comments with the Administrator of the FAA. Proof of such filing shall be established in accordance with § 1.47 of this chapter.

(b) Nothing in this subpart shall be construed to mean that only one antenna farm area will be designated for a community. The Commission will consider on a case-by-case basis whether or not more than one antenna farm area shall be designated for a particular community.

[32 FR 8813, June 21, 1967, as amended at 32 FR 13591, Sept. 28, 1967]

§ 17.9 Designated antenna farm areas.

The areas described in the following paragraphs of this section are established as antenna farm areas [appropriate paragraphs will be added as necessary].

[32 FR 8813, June 21, 1967]

§ 17.10 Antenna structures over 304.80 meters (1,000 feet) in height.

Where one or more antenna farm areas have been designated for a community or communities (see § 17.9), the Commission will not accept for filing an application to construct a new station or to increase height or change antenna location of an existing station proposing the erection of an antenna structure over 304.80 meters (1,000 feet) above ground unless:

(a) It is proposed to locate the antenna structure in a designated antenna farm area, or

47 CFR Ch. I (10–1–97 Edition)

(b) It is accompanied by a statement from the Federal Aviation Administration that the proposed structure will not constitute a menace to air navigation, or

(c) It is accompanied by a request for waiver setting forth reasons sufficient, if true, to justify such a waiver.

[32 FR 8813, June 21, 1967, as amended at 42 FR 54824, Oct. 11, 1977; 61 FR 4363, Feb. 6, 1996]

§ 17.14 Certain antenna structures exempt from notification to the FAA.

A notification to the Federal Aviation Administration is not required for any of the following construction or alteration:

(a) Any object that would be shielded by existing structures of a permanent and substantial character or by natural terrain or topographic features of equal or greater height, *and* would be located in the congested area of a city, town, or settlement where it is evident beyond all reasonable doubt that the structure so shielded will not adversely affect safety in air navigation. Applicant claiming such exemption under § 17.14(a) shall submit a statement with their application to the FCC explaining basis in detail for their finding.

(b) Any antenna structure of 6.10 meters (20 feet) or less in height except one that would increase the height of another antenna structure.

(c) Any air navigation facility, airport visual approach or landing aid, aircraft arresting device, or meteorological device, of a type approved by the Administrator of the Federal Aviation Administration, the location and height of which is fixed by its functional purpose.

[32 FR 11269, Aug. 3, 1967, as amended at 39 FR 7581, Feb. 27, 1974; 42 FR 54824, Oct. 11, 1977; 61 FR 4363, Feb. 6, 1996]

§ 17.17 Existing structures.

(a) The requirements found in § 17.23 relating to painting and lighting of antenna structures shall not apply to those structures authorized prior to July 1, 1996. Previously authorized structures may retain their present painting and lighting specifications, so long as the overall structure height or site coordinates do not change. The

Federal Communications Commission

§§ 17.24–17.38

Antenna Structure Registration requirements found in §17.5, however, shall apply to all antenna structures that have been assigned painting or lighting requirements by the Commission, regardless of prior authorization.

(b) No change in any of these criteria or relocation of airports shall at any time impose a new restriction upon any then existing or authorized antenna structure or structures.

[32 FR 11269, Aug. 3, 1967, as amended at 61 FR 4363, Feb. 6, 1996]

Subpart C—Specifications for Obstruction Marking and Lighting of Antenna Structures

§ 17.21 Painting and lighting, when required.

Antenna structures shall be painted and lighted when:

(a) They exceed 60.96 meters (200 feet) in height above the ground or they require special aeronautical study.

(b) The Commission may modify the above requirement for painting and/or lighting of antenna structures, when it is shown by the applicant that the absence of such marking would not impair the safety of air navigation, or that a lesser marking requirement would insure the safety thereof.

[32 FR 11269, Aug. 3, 1967, as amended at 42 FR 54824, Oct. 11, 1977]

§ 17.22 Particular specifications to be used.

Whenever painting or lighting is required, the Commission will generally assign specifications in accordance with the FAA Advisory Circulars referenced in §17.23. If an antenna installation is of such a nature that its painting and lighting in accordance with these specifications are confusing, or endanger rather than assist airmen, or are otherwise inadequate, the Commission will specify the type of painting and lighting or other marking to be used in the individual situation.

[32 FR 11269, Aug. 3, 1967, as amended at 61 FR 4363, Feb. 6, 1996]

§ 17.23 Specifications for painting and lighting antenna structures.

Unless otherwise specified by the Commission, each new or altered an-

tenna structure to be registered on or after July 1, 1996, must conform to the FAA's painting and lighting recommendations set forth on the structure's FAA determination of "no hazard," as referenced in the following FAA Advisory Circulars: AC 70/7460-1H, "Obstruction Marking and Lighting," August 1, 1991, as amended by Change 2, July 15, 1992, and AC 150/5345-43D, "Specification for Obstruction Lighting Equipment," July 15, 1988. These documents are incorporated by reference in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. The documents contain FAA recommendations for painting and lighting structures which pose a potential hazard to air navigation. For purposes of this part, the specifications, standards, and general requirements stated in these documents are mandatory. The Advisory Circulars listed above are available for inspection at the Commission Headquarters in Washington, DC, 2025 M Street NW., room 8112, or at the Office of the Federal Register, 800 North Capitol Street, NW., room 700, Washington, DC., or may be obtained from Department of Transportation, Utilization and Storage Section (Publications), M443.2, 400 7th Street SW., Washington, DC 20590, telephone (202) 366-0039 or (202) 366-0451.

[61 FR 4363, Feb. 6, 1996]

AVIATION RED OBSTRUCTION LIGHTING [RESERVED]

§§ 17.24–17.38 [Reserved]

HIGH INTENSITY WHITE OBSTRUCTION LIGHTING

NOTE: When authorized by the Commission, high intensity white obstruction lighting will be used in lieu of obstruction marking and lighting specified in §§17.23 through 17.37.

In general, the number of levels of high intensity lighting specified is dependent upon the overall height of the skeletal frame or comparable main support structure, excluding antennas or similar appurtenances. A white capacitor discharge omnidirectional light is mounted on or adjacent to the appurtenance, if more than 6.10 meters (20 feet), to complement the lighting system.

Where a dual lighting system is employed, i.e., high intensity white obstruction lighting during daylight and red obstruction lighting at night, the omnidirectional high intensity light, if equipped with an aviation

§§ 17.39–17.43

red color filter for nighttime illumination, may be used in lieu of the 300 mm top beacon specified in § 17.24(a) and paragraph (a)(1) in §§ 17.25 through 17.37.

§§ 17.39–17.43 [Reserved]

§ 17.45 Temporary warning lights.

During construction of an antenna structure, for which red obstruction lighting is required, at least two 116- or 125-watt lamps (A21/TS) enclosed in aviation red obstruction light globes, shall be installed at the uppermost point of the structure. The intensity of each lamp shall not be less than 32.5 candelas. In addition, as the height of the structure exceeds each level at which permanent obstruction lights will be required, two similar lights shall be installed at each such level. These temporary warning lights shall be displayed nightly from sunset to sunrise until the permanent obstruction lights have been installed and placed in operation, and shall be positioned so as to insure unobstructed visibility of at least one of the lights at any normal angle of approach. If practical, the permanent obstruction lights may be installed and operated at each required level as construction progresses.

[32 FR 11273, Aug. 3, 1967, as amended at 39 FR 26157, July 17, 1974; 42 FR 54826, Oct. 11, 1977]

§ 17.47 Inspection of antenna structure lights and associated control equipment.

The owner of any antenna structure which is registered with the Commission and has been assigned lighting specifications referenced in this part:

(a)(1) Shall make an observation of the antenna structure's lights at least once each 24 hours either visually or by observing an automatic properly maintained indicator designed to register any failure of such lights, to insure that all such lights are functioning properly as required; or alternatively,

(2) Shall provide and properly maintain an automatic alarm system designed to detect any failure of such lights and to provide indication of such failure to the owner.

(b) Shall inspect at intervals not to exceed 3 months all automatic or me-

47 CFR Ch. I (10–1–97 Edition)

chanical control devices, indicators, and alarm systems associated with the antenna structure lighting to insure that such apparatus is functioning properly.

[61 FR 4363, Feb. 6, 1996]

§ 17.48 Notification of extinguishment or improper functioning of lights.

The owner of any antenna structure which is registered with the Commission and has been assigned lighting specifications referenced in this part:

(a) Shall report immediately by telephone or telegraph to the nearest Flight Service Station or office of the Federal Aviation Administration any observed or otherwise known extinguishment or improper functioning of any top steady burning light or any flashing obstruction light, regardless of its position on the antenna structure, not corrected within 30 minutes. Such reports shall set forth the condition of the light or lights, the circumstances which caused the failure, the probable date for restoration of service, the FCC Antenna Structure Registration Number, the height of the structure (AGL and AMSL if known) and the name, title, address, and telephone number of the person making the report. Further notification by telephone or telegraph shall be given immediately upon resumption of normal operation of the light or lights.

(b) An extinguishment or improper functioning of a steady burning side intermediate light or lights, shall be corrected as soon as possible, but notification to the FAA of such extinguishment or improper functioning is not required.

[32 FR 11273, Aug. 3, 1967, as amended at 39 FR 26157, July 17, 1974; 40 FR 30267, July 18, 1975; 61 FR 4364, Feb. 6, 1996]

§ 17.49 Recording of antenna structure light inspections in the owner record.

The owner of each antenna structure which is registered with the Commission and has been assigned lighting specifications referenced in this part must maintain a record of any observed or otherwise known extinguishment or improper functioning of a structure light and include the following information for each such event:

Federal Communications Commission

§ 17.57

(a) The nature of such extinguishment or improper functioning.

(b) The date and time the extinguishment or improper operation was observed or otherwise noted.

(c) Date and time of FAA notification, if applicable.

(d) The date, time and nature of adjustments, repairs, or replacements made.

[48 FR 38477, Aug. 24, 1983, as amended at 61 FR 4364, Feb. 6, 1996]

§ 17.50 Cleaning and repainting.

Antenna structures requiring painting under this part shall be cleaned or repainted as often as necessary to maintain good visibility.

[61 FR 4364, Feb. 6, 1996]

§ 17.51 Time when lights should be exhibited.

(a) All red obstruction lighting shall be exhibited from sunset to sunrise unless otherwise specified.

(b) All high intensity and medium intensity obstruction lighting shall be exhibited continuously unless otherwise specified.

[40 FR 30267, July 18, 1975, as amended at 61 FR 4364, Feb. 6, 1996]

§ 17.53 Lighting equipment and paint.

The lighting equipment, color or filters, and shade of paint referred to in the specifications are further defined in the following government and/or Army-Navy aeronautical specifications, bulletins, and drawings (lamps are referred to by standard numbers):

Outside white	TT-P-102 ¹ (Color No. 17875, FS-595).
Aviation surface orange	TT-P-59 ¹ (Color No. 12197, FS-595).
Aviation surface orange, enamel.	TT-E-489 ¹ (Color No. 12197, FS-595).
Aviation red obstruction light—color.	MIL-C-25050 ² .
Flashing beacons	CAA-446 ³ Code Beacons, 300 mm.
Do	MIL-6273 ² .
Double and single obstruction light.	L-810 ³ (FAA AC No. 150/5345-2 ⁴).
Do	MIL-L-7830 ² .
High intensity white obstruction light.	FAA/DOD L-856 (FAA AC No. 150/5345-43B ⁴).
116-Watt lamp	No. 116 A21/TS (6,000 h).
125-Watt lamp	No. 125 A21/TS (6,000 h).
620-Watt lamp	No. 620 PS-40 (3,000 h).

700-Watt lamp	No. 700 PS-40 (6,000 h).

¹Copies of this specification can be obtained from the Specification Activity, Building 197, Room 301, Naval Weapons Plant, 1st and N Streets, SE., Washington, D.C. 20407.

²Copies of Military specifications can be obtained by contacting the Commanding Officer, Naval Publications and Forms Center, 5801 Tabor Ave., Attention: NPPC-105, Philadelphia, Pa. 19120.

³Copies of Federal Aviation Administration specifications may be obtained from the Chief, Configuration Control Branch, AAF-110, Department of Transportation, Federal Aviation Administration, 800 Independence Avenue SW., Washington, D.C. 20591.

⁴Copies of Federal Aviation Administration advisory circulars may be obtained from the Department of Transportation, Publications Section, TAD-443.1, 400 7th St. SW., Washington, D.C. 20590.

[33 FR 11540, Aug. 14, 1968, as amended at 40 FR 30267, July 18, 1975]

§ 17.54 Rated lamp voltage.

To insure the necessary lumen output by obstruction lights, the rated voltage of incandescent lamps used shall correspond to be within 3 percent higher than the voltage across the lamp socket during the normal hours of operation.

[42 FR 54826, Oct. 11, 1977]

§ 17.56 Maintenance of lighting equipment.

(a) Replacing or repairing of lights, automatic indicators or automatic control or alarm systems shall be accomplished as soon as practicable.

(b) The flash tubes in a high intensity obstruction lighting system shall be replaced whenever the peak effective daytime intensity falls below 200,000 candelas.

[40 FR 30267, July 18, 1975]

§ 17.57 Report of radio transmitting antenna construction, alteration, and/or removal.

The owner of an antenna structure for which an Antenna Structure Registration Number has been obtained must notify the Commission within 24 hours of completion of construction (FCC Form 854-R) and/or dismantlement (FCC Form 854). The owner must also immediately notify the Commission using FCC Form 854 upon any change in structure height or change in ownership information.

[61 FR 4364, Feb. 6, 1996]

§ 17.58

§ 17.58 Facilities to be located on land under the jurisdiction of the U.S. Forest Service or the Bureau of Land Management.

Any application proposing new or modified transmitting facilities to be located on land under the jurisdiction of the U.S. Forest Service or the Bureau of Land Management shall include a statement that the facilities will be so located, and the applicant shall comply with the requirements of § 1.70 of this chapter.

[32 FR 11274, Aug. 3, 1967]

PART 18—INDUSTRIAL, SCIENTIFIC, AND MEDICAL EQUIPMENT

Subpart A—General Information

Sec.

- 18.101 Basis and purpose.
- 18.103 Organization and applicability of the rules.
- 18.105 Other applicable rules.
- 18.107 Definitions.
- 18.109 General technical requirements.
- 18.111 General operating conditions.
- 18.113 Inspection by Commission representatives.
- 18.115 Elimination and investigation of harmful interference.
- 18.117 Report of interference investigation.
- 18.119 Importation.
- 18.121 Exemptions.

Subpart B—Applications and Authorizations

- 18.201 Scope.
- 18.203 Equipment authorization.
- 18.205 Description of measurement facilities.
- 18.207 Technical report.
- 18.209 Identification of authorized equipment.
- 18.211 Multiple listing of equipment.
- 18.213 Information to the user.

Subpart C—Technical Standards

- 18.301 Operating frequencies.
- 18.303 Prohibited frequency bands.
- 18.305 Field strength limits.
- 18.307 Conduction limits.
- 18.309 Frequency range of measurements.
- 18.311 Methods of measurements.

AUTHORITY: 47 U.S.C. 4, 301, 302, 303, 304, 307.

SOURCE: 50 FR 36067, Sept. 5, 1985, unless otherwise noted.

47 CFR Ch. I (10–1–97 Edition)

Subpart A—General Information

§ 18.101 Basis and purpose.

The rules in this part, in accordance with the applicable treaties and agreements to which the United States is a party, are promulgated pursuant to section 302 of the Communications Act of 1934, as amended, vesting the Federal Communications Commission with authority to regulate industrial, scientific, and medical equipment (ISM) that emits electromagnetic energy on frequencies within the radio frequency spectrum in order to prevent harmful interference to authorized radio communication services. This part sets forth the conditions under which the equipment in question may be operated.

§ 18.103 Organization and applicability of the rules.

The rules in this part are divided into the following subparts:

(a) Subpart A contains general information and definitions for use in this part.

(b) Subpart B describes the procedures and requirements for authorization to market or operate ISM equipment under this part.

(c) Subpart C contains the technical standards for ISM equipment.

§ 18.105 Other applicable rules.

Other Commission rule parts relating to the authorization and operation of ISM equipment include the following:

(a) Part 0 describes the Commission's organization and delegations of authority. This part also lists available Commission publications, standards and procedures for access to Commission records, and location of Commission field offices.

(b) Part 1 contains the rules of practice and procedure for adjudicatory proceedings including hearing proceedings; procedures for reconsideration and review of the Commission's actions; provisions concerning violation notices and for forfeiture proceedings; and the requirements for environmental impact statements.

(c) Part 2 contains special requirements in international regulations, agreements, treaties, and the table of frequency allocations. This part also

Federal Communications Commission

§ 18.111

contains requirements and procedures concerning the marketing, the equipment authorization, and the importation of radio frequency devices into the United States.

§ 18.107 Definitions.

(a) *Radio frequency (RF) energy*. Electromagnetic energy at any frequency in the radio spectrum from 9 kHz to 3 THz (3,000 GHz).

(b) *Harmful interference*. Interference which endangers the functioning of a radionavigation service or of other safety services or seriously degrades, obstructs or repeatedly interrupts a radiocommunication service operating in accordance with this chapter.

(c) *Industrial, scientific, and medical (ISM) equipment*. Equipment or appliances designed to generate and use locally RF energy for industrial, scientific, medical, domestic or similar purposes, excluding applications in the field of telecommunication. Typical ISM applications are the production of physical, biological, or chemical effects such as heating, ionization of gases, mechanical vibrations, hair removal and acceleration of charged particles.

(d) *Industrial heating equipment*. A category of ISM equipment used for or in connection with industrial heating operations utilized in a manufacturing or production process.

(e) *Medical diathermy equipment*. A category of ISM equipment used for therapeutic purposes, not including surgical diathermy apparatus designed for intermittent operation with low power.

(f) *Ultrasonic equipment*. A category of ISM equipment in which the RF energy is used to excite or drive an electromechanical transducer for the production of sonic or ultrasonic mechanical energy for industrial, scientific, medical or other noncommunication purposes.

(g) *Consumer ISM equipment*. A category of ISM equipment used or intended to be used by the general public in a residential environment, notwithstanding use in other areas. Examples are domestic microwave ovens, jewelry cleaners for home use, ultrasonic humidifiers.

(h) *ISM frequency*. A frequency assigned by this part for the use of ISM

equipment. A specified tolerance is associated with each ISM frequency. See § 18.301.

(i) *Marketing*. As used in this part, marketing shall include sale or lease, offer for sale or lease, advertising for sale or lease, the import or shipment or other distribution for the purpose of sale or lease or offer for sale or lease. See subpart I of part 2 of this chapter.

(j) *Magnetic resonance equipment*. A category of ISM equipment in which RF energy is used to create images and data representing spatially resolved density of transient atomic resources within an object.

NOTE: In the foregoing, sale (or lease) shall mean sale (or lease) to the user or a vendor who in turn sells (or leases) to the user. Sale shall not be construed to apply to devices sold to a second party for manufacture or fabrication into a device which is subsequently sold (or leased) to the user.

[50 FR 36067, Sept. 5, 1985, as amended at 59 FR 39472, Aug. 3, 1994]

§ 18.109 General technical requirements.

ISM equipment shall be designed and constructed in accordance with good engineering practice with sufficient shielding and filtering to provide adequate suppression of emissions on frequencies outside the frequency bands specified in § 18.301.

§ 18.111 General operating conditions.

(a) Persons operating ISM equipment shall not be deemed to have any vested or recognizable right to the continued use of any given frequency, by virtue of any prior equipment authorization and/or compliance with the applicable rules.

(b) Subject to the exceptions in paragraphs (c) and (d) of this section and irrespective of whether the equipment otherwise complies with the rules in this part, the operator of ISM equipment that causes harmful interference to any authorized radio service shall promptly take whatever steps may be necessary to eliminate the interference.

(c) The provisions of paragraph (b) of this section shall not apply in the case of interference to an authorized radio

§ 18.113

station or a radiocommunication device operating in an ISM frequency band.

(d) The provisions of paragraph (b) of this section shall not apply in the case of interference to a receiver arising from direct intermediate frequency pickup by the receiver of the fundamental frequency emissions of ISM equipment operating in an ISM frequency band and otherwise complying with the requirements of this part.

§ 18.113 Inspection by Commission representatives.

Upon request by a representative of the Commission the manufacturer, owner, or operator of any ISM equipment shall make the equipment available for inspection and promptly furnish the Commission with such information as may be required to indicate that the equipment complies with this part.

§ 18.115 Elimination and investigation of harmful interference.

(a) The operator of ISM equipment that causes harmful interference to radio services shall promptly take appropriate measures to correct the problem.

(b) If the operator of ISM equipment is notified by the Commission's Engineer in Charge (EIC) that operation of such equipment is endangering the functioning of a radionavigation or safety service, the operator shall immediately cease operating the equipment. Operation may be resumed on a temporary basis only for the purpose of eliminating the harmful interference. Operation may be resumed on a regular basis only after the harmful interference has been eliminated and approval from the EIC obtained.

(c) When notified by the EIC that a particular installation is causing harmful interference, the operator or manufacturer shall arrange for an engineer skilled in techniques of interference measurement and control to make an investigation to ensure that the harmful interference has been eliminated. The EIC may require the engineer making the investigation to furnish proof of his or her qualifications.

47 CFR Ch. I (10–1–97 Edition)

§ 18.117 Report of interference investigation.

(a) An interim report on investigations and corrective measures taken pursuant to § 18.115 of this part shall be filed with the EIC of the local FCC office within 30 days of notification of harmful interference. The final report shall be filed with the EIC within 60 days of notification.

(b) The date for filing the final report may be extended by the Engineer in Charge when additional time is required to put into effect the corrective measures or to complete the investigation. The request for extension of time shall be accompanied by a progress report showing what has been accomplished to date.

§ 18.119 Importation.

ISM equipment shall be refused entry or withdrawal for consumption into the Customs territory of the United States, unless accompanied by a copy of FCC Form 740, in accordance with the provisions of subpart K, part 2 of this chapter.

§ 18.121 Exemptions.

Non-consumer ultrasonic equipment, and non-consumer magnetic resonance equipment, that is used for medical diagnostic and monitoring applications is subject only to the provisions of §§ 18.105, 18.109 through 18.119, 18.301 and 18.303 of this part.

[59 FR 39472, Aug. 3, 1994; 60 FR 47302, Sept. 12, 1995]

Subpart B—Applications and Authorizations

§ 18.201 Scope.

This subpart contains the procedures and requirements for authorization to market or operate ISM equipment under this part.

§ 18.203 Equipment authorization.

(a) Consumer ISM equipment, unless otherwise specified, shall be subject to certification prior to use or marketing. An application for certification shall be filed with the Commission on an FCC Form 731, pursuant to the relevant sections in part 2, subpart J of this

Federal Communications Commission

§ 18.207

chapter and shall also be accompanied by:

(1) A description of measurement facilities pursuant to § 18.205 or reference to such information already on file with the Commission.

(2) A technical report pursuant to §§ 18.207 and 18.311.

NOTE: The Commission will accept applications for either type approval or certification until September 1, 1986, for consumer microwave ovens. After that date, only applications for certification will be accepted for filing.

(b) Consumer ultrasonic equipment generating less than 500 watts and operating below 90 kHz, and non-consumer ISM equipment shall be subject to verification, in accordance with the relevant sections of part 2, subpart J of this chapter.

(c) Grants of equipment authorization issued, as well as on-site certifications performed, before March 1, 1986, remain in effect and no further action is required.

§ 18.205 Description of measurement facilities.

(a) Any party filing a report of measurements with the Commission shall include in that report a description of the measurement facilities. If such a description is already on file with the Commission, it may be included by reference.

(b) The description shall include the following information:

(1) Location of test site.

(2) Physical description of the test site accompanied by photographs A4 (21 cm × 29.7 cm) or 8×10 inches (20.3 cm × 25.4 cm) in size. Photographs smaller than A4 (21 cm × 29.7 cm) or 8×10 inches (20.3 cm × 25.4 cm) will be acceptable if they are of sufficient clarity and mounted on A4 (21 cm × 29.7 cm) paper or paper 8×10 inches (20.3 cm × 25.4 cm).

(3) Scaled drawing showing the dimensions of the site, the physical layout of supporting structures and all structures within 5 times the distance between the measuring set and the device under test.

(4) Description of structures used to support the device being measured and the test instrumentation.

(5) List of measuring equipment used and information concerning the cali-

bration of the measuring equipment, i.e., when the equipment was last calibrated and frequency of calibration.

(6) A statement indicating whether this facility is available to do measurement work for others on a contract basis.

(c) This information shall be kept current at all times. At least every three (3) years, the organization filing the data shall advise that the data on file are current.

NOTE: OET Bulletin 55, "Characteristics of Open Field Test Sites", provides further guidance on open field test sites.

[50 FR 36069, Sept. 5, 1985, as amended at 51 FR 12616, Apr. 14, 1986; 58 FR 44894, Aug. 25, 1993]

§ 18.207 Technical report.

When required by the Commission a technical report shall include at least the following information:

(a) A description of the measurement facilities in accordance with § 18.205. If such a description is already on file with the Commission, it may be included by reference.

(b) A copy of the installation and operating instructions furnished to the user. A draft copy of such instructions may be submitted with the application, provided a copy of the actual document to be furnished to the user is submitted as soon as it is available, but no later than 60 days after the grant of the application.

(c) The full name and mailing address of the manufacturer of the device and/or applicant filing for the equipment authorization.

(d) The FCC Identifier, trade name(s), and/or model number(s) under which the equipment is or will be marketed.

(e) A statement of the rated technical parameters that includes:

(1) A block and schematic diagram of the circuitry.

(2) Nominal operating frequency.

(3) Maximum RF energy generated.

(4) Electrical power requirements of equipment.

(5) Any other pertinent operating characteristics.

(f) A report of measurements, including a list of the measuring equipment used, and a statement of the date when

§ 18.209

the measuring equipment was last calibrated and when the measurements were made. The frequency range that was investigated in obtaining the report of measurements shall be indicated. See also §§ 18.309 and 18.311.

§ 18.209 Identification of authorized equipment.

Each device for which a grant of equipment authorization is issued under this part shall be identified pursuant to the applicable provisions of subpart J of part 2 of this chapter. Changes in the identification of authorized equipment may be made pursuant to § 2.933 of part 2 of this chapter. FCC Identifiers as described in §§ 2.925 and 2.926 of this chapter shall not be used on equipment subject to verification.

§ 18.211 Multiple listing of equipment.

(a) When the same or essentially the same equipment will be marketed under more than one FCC Identifier, equipment authorization must be requested on an FCC Form 731 for each FCC Identifier.

(b) If equipment authorization for additional FCC Identifiers is requested in the initial application, a statement shall be included describing how these additional devices differ from the basic device which was measured and stating that the report of measurements submitted for the basic device applies also to the additional devices.

(c) If equipment authorization for additional FCC Identifiers is requested after a grant has been issued by the FCC for the basic device, the application may, in lieu of the report of measurements, be accompanied by a statement including:

(1) FCC Identifier of device for which measurements are on file with the FCC.

(2) Date when equipment authorization was granted for the device(s) listed under paragraph (c)(1) of this section and the file number of such grant.

(3) Description of the difference between the device listed under paragraph (c)(1) of this section and the additional device(s).

(4) A statement that the report of measurements filed for the device listed under paragraph (c)(1) of this sec-

47 CFR Ch. I (10–1–97 Edition)

tion applies also to the additional device(s).

(5) Photographs pursuant to § 2.1033(c).

§ 18.213 Information to the user.

Information on the following matters shall be provided to the user in the instruction manual or on the packaging if an instruction manual is not provided for any type of ISM equipment:

(a) The interference potential of the device or system

(b) Maintenance of the system

(c) Simple measures that can be taken by the user to correct interference.

[50 FR 36069, Sept. 5, 1985, as amended at 51 FR 17970, May 16, 1986]

Subpart C—Technical Standards

§ 18.301 Operating frequencies.

ISM equipment may be operated on any frequency above 9 kHz except as indicated in § 18.303. The following frequency bands, in accordance with § 2.106 of the rules, are allocated for use by ISM equipment:

ISM frequency	Tolerance
6.78 MHz	±15.0 kHz
13.56 MHz	±7.0 kHz
27.12 MHz	±163.0 kHz
40.68 MHz	±20.0 kHz
915 MHz	±13.0 MHz
2,450 MHz	±50.0 MHz
5,800 MHz	±75.0 MHz
24,125 MHz	±125.0 MHz
61.25 GHz	±250.0 MHz
122.50 GHz	±500.0 MHz
245.00 GHz	±1.0 GHz

NOTE: The use of the 6.78 MHz ±15 kHz frequency band is subject to the conditions of footnote 524 of the Table of Allocations. See § 2.106.

§ 18.303 Prohibited frequency bands.

Operation of ISM equipment within the following safety, search and rescue frequency bands is prohibited: 490–510 kHz, 2170–2194 kHz, 8354–8374 kHz, 121.4–121.6 MHz, 156.7–156.9 MHz, and 242.8–243.2 MHz.

§ 18.305 Field strength limits.

(a) ISM equipment operating on a frequency specified in § 18.301 is permitted

Federal Communications Commission

§ 18.307

unlimited radiated energy in the band specified for that frequency.

(b) The field strength levels of emissions which lie outside the bands speci-

fied in §18.301, unless otherwise indicated, shall not exceed the following:

Equipment	Operating frequency	RF Power generated by equipment (watts)	Field strength limit (μV/m)	Distance (meters)
Any type unless otherwise specified (miscellaneous).	Any ISM frequency	Below 500	25	300
		500 or more	25×SQRT(power/500)	1300
	Any non-ISM frequency ..	Below 500	15	300
Industrial heaters and RF stabilized arc welders.		500 or more	15×SQRT(power/500)	1300
	On or below 5,725 MHz	Any	10	1,600
	Above 5,725 MHz	Any	(²)	(²)
Medical diathermy	Any ISM frequency	Any	25	300
	Any non-ISM frequency ..	Any	15	300
	Below 490 kHz	Below 500	2,400/F(kHz)	300
Ultrasonic		500 or more	2,400/F(kHz)× SQRT(power/500).	1300
	490 to 1,600 kHz	Any	24,000/F(kHz)	30
	Above 1,600 kHz	Any	15	30
Induction cooking ranges	Below 90 kHz	Any	1,500	130
	On or above 90 kHz	Any	300	130

¹Field strength may not exceed 10 μV/m at 1600 meters. Consumer equipment operating below 1000 MHz is not permitted the increase in field strength otherwise permitted here for power over 500 watts.

²Reduced to the greatest extent possible.

³Field strength may not exceed 10 μV/m at 1600 meters. Consumer equipment is not permitted the increase in field strength otherwise permitted here for over 500 watts.

⁴Induction cooking ranges manufactured prior to February 1, 1980, shall be subject to the field strength limits for miscellaneous ISM equipment.

(c) The field strength limits for RF lighting devices shall be the following:

Frequency (MHz)	Field strength limit at 30 meters (μV/m)
Non-consumer equipment:	
30–88	30
88–216	50
216–1000	70
Consumer equipment:	
30–88	10
88–216	15
216–1000	20

NOTES

1. The tighter limit shall apply at the boundary between two frequency ranges.

2. Testing for compliance with these limits may be made at closer distances, provided a sufficient number of measurements are taken to plot the radiation pattern, to determine the major lobes of radiation, and to determine the expected field strength level at 30, 300, or 1600 meters. Alternatively, if measurements are made at only one closer fixed distance, then the permissible field strength limits shall be adjusted using 1/d as an attenuation factor.

[50 FR 36070, Sept. 5, 1985, as amended at 51 FR 17970, May 16, 1986; 52 FR 43197, Nov. 10, 1987]

§ 18.307 Conduction limits.

For the following equipment, which is designed to be connected to a low voltage public utility power line, the RF voltage conducted back into the power lines measured with a line impedance stabilization network (LISN) shall be limited to:

(a) Ultrasonic equipment:

Frequency (MHz)	Maximum RF line voltage measured with a 5 μH/50 ohm LISN (μV)
0.010–0.49	1000
0.49–30	200

(b) Induction cooking ranges manufactured after February 1, 1980:

Frequency (MHz)	Maximum RF line voltage measured with a 5μH/50 ohm LISN (mV)
0.010–0.1	10–1 (linear interpolation)
0.1–0.5	1
0.5–30	0.25

(c) RF lighting devices:

Frequency (MHz)	Maximum RF line voltage measured with a 50μH/50 ohm LISN (μV)
Non-consumer equipment:	
0.45 to 1.6	1000
1.6 to 30	3000
Consumer equipment:	
0.45 to 30	250

§ 18.309**47 CFR Ch. I (10–1–97 Edition)****NOTES**

1. These conduction limits shall apply outside the bands specified in § 18.301.

2. For ultrasonic equipment, compliance with these conduction limits shall preclude the need to show compliance with the field strength limits below 30 MHz unless requested by the Commission.

3. The tighter limits shall apply at the boundary between two frequency ranges.

[50 FR 36067, Sept. 5, 1985, as amended at 52 FR 43198, Nov. 10, 1987]

§ 18.309 Frequency range of measurements.

(a) For field strength measurements:

Frequency band in which device operates (MHz)	Range of frequency measurements	
	Lowest frequency	Highest frequency
Below 1.705	Lowest frequency generated in the device, but not lower than 9 kHz.	30 MHz.
1.705 to 30	Lowest frequency generated in the device, but not lower than 9 kHz.	400 MHz.
30 to 500	Lowest frequency generated in the device or 25 MHz, whichever is lower.	Tenth harmonic or 1,000 MHz, whichever is higher.
500 to 1,000	Lowest frequency generated in the device or 100 MHz, whichever is lower.	Tenth harmonic.
Above 1,000	do	Tenth harmonic or highest detectable emission.

(b) For conducted powerline measurements, the frequency range over which the limits are specified will be scanned.

[50 FR 36070, Sept. 5, 1985, as amended at 51 FR 17971, May 16 1986]

§ 18.311 Methods of measurements.

The measurement techniques which will be used by the FCC to determine compliance with the technical requirements of this part are set out in FCC Measurement Procedure MP–5, “Methods of Measurements of Radio Noise Emissions from ISM equipment”. Although the procedures in MP–5 are not mandated, manufacturers are encouraged to follow the same techniques which will be used by the FCC.

PART 19—EMPLOYEE RESPONSIBILITIES AND CONDUCT

Subpart A—General Provisions

Sec.

19.735–101 Purpose.

19.735–102 Cross-reference to ethics and other conduct related regulations.

19.735–103 Definitions.

19.735–104 Delegations.

19.735–105 Availability of ethics and other conduct related regulations and statutes.

19.735–106 Interpretation and advisory service.

19.735–107 Disciplinary and other remedial action.

Subpart B—Employee Responsibilities and Conduct

19.735–201 Outside employment and other activity prohibited by the Communications Act.

19.735–202 Financial interests prohibited by the Communications Act.

19.735–203 Nonpublic information.

AUTHORITY: 5 U.S.C. 7301; 47 U.S.C. 154 (b), (i), (j), and 303(r).

SOURCE: 61 FR 56112, Oct. 31, 1996, unless otherwise noted.

Subpart A—General Provisions

§ 19.735–101 Purpose.

The regulations in this part prescribe procedures and standards of conduct that are appropriate to the particular functions and activities of the Commission, and are issued by the Commission under authority independent of the uniform Standards of Ethical Conduct for Employees of the Executive Branch at 5 CFR part 2635 or otherwise in accordance with 5 CFR 2635.105(c).

§ 19.735–102 Cross-reference to ethics and other conduct related regulations.

In addition to the rules in this part, employees of the Federal Communications Commission (Commission) are subject to the Standards of Ethical

Federal Communications Commission

§ 19.735–105

Conduct for Employees of the Executive Branch at 5 CFR part 2635 and the Commission's regulations at 5 CFR part 3901 which supplement the executive branch-wide standards, the executive branch financial disclosure regulations at 5 CFR part 2634 and the Commission's regulations at 5 CFR part 3902 which supplement the executive branch-wide financial disclosure regulations, and the employee responsibilities and conduct regulations at 5 CFR part 735.

§ 19.735–103 Definitions.

Commission means the Federal Communications Commission.

Communications Act means the Communications Act of 1934, as amended, 47 U.S.C. 151 *et seq.*

Employee means an officer or employee of the Commission including special Government employees within the meaning of 18 U.S.C. 202(a) and the Commissioners.

Person means an individual, a corporation, a company, an association, a firm, a partnership, a society, a joint stock company, or any other organization or institution.

§ 19.735–104 Delegations.

(a) The Commission has delegated to the Chairman responsibility for the detection and prevention of acts, short of criminal violations, which could bring discredit upon the Commission and the Federal service.

(b) *Approvals under 18 U.S.C. 205(e).* (1) Commissioners may approve the representational activities permitted by 18 U.S.C. 205(e) by other employees in their immediate offices. The Designated Agency Ethics Official has delegated authority to grant such approvals for all other employees except Commissioners.

(2)(i) Requests for approval of the activities permitted by 18 U.S.C. 205(e) shall be in writing and submitted as follows:

(A) In the case of employees in the immediate offices of a Commissioner, to the Commissioner;

(B) In the case of Heads of Offices and Bureaus, to the Chairman; and

(C) In the case of all other employees except Commissioners, to the Head of

the Office or Bureau to which the employee is assigned.

(ii) An official (other than the Chairman or another Commissioner) to whom a request for approval under 18 U.S.C. 205(e) is submitted shall forward it to the Designated Agency Ethics Official with the official's recommendation as to whether the request should be granted.

(3) Copies of all requests for approval under 18 U.S.C. 205(e) and the action taken thereon shall be maintained by the Designated Agency Ethics Official.

(c) *Waivers under 18 U.S.C. 208.* (1) Commissioners may waive the applicability of 18 U.S.C. 208(a), in accordance with 18 U.S.C. 208(b)(1) or 208(b)(3) and section 301(d) of Executive Order 12731, for other employees in their immediate offices. The Designated Agency Ethics Official has delegated authority to make such waiver determinations for all other employees except Commissioners.

(2)(i) Requests for waiver of the applicability of 18 U.S.C. 208(a) shall be in writing and submitted as follows:

(A) In the case of employees in the immediate offices of a Commissioner, to the Commissioner;

(B) In the case of Heads of Offices and Bureaus, to the Chairman; and

(C) In the case of all other employees except Commissioners, to the Head of the Office or Bureau to which the employee is assigned.

(ii) An official (other than the Chairman or another Commissioner) to whom a waiver request is submitted shall forward it to the Designated Agency Ethics Official with the official's recommendation as to whether the waiver should be granted.

(3) Copies of all requests for waivers and the action taken thereon shall be maintained by the Designated Agency Ethics Official.

§ 19.735–105 Availability of ethics and other conduct related regulations and statutes.

(a)(1) The Commission shall furnish each new employee, at the time of his or her entrance on duty, with a copy of:

(i) The Standards of Ethical Conduct for Employees of the Executive Branch (5 CFR part 2635);

§ 19.735–106

(ii) The Supplemental Standards of Ethical Conduct for Employees of the Federal Communications Commission (5 CFR part 3901); and

(iii) The Commission's Employee Responsibilities and Conduct regulations in this part.

(2) The Head of each Office and Bureau has the responsibility to secure from every person subject to his or her administrative supervision a statement indicating that the individual has read and is familiar with the contents of the regulations in this part, and the regulations at 5 CFR parts 2635 and 3901, and to advise the Designated Agency Ethics Official that all such persons have provided such statements. Each new employee shall execute a similar statement at the time of entrance on duty. Periodically, and at least once a year, the Designated Agency Ethics Official shall take appropriate action to ensure that the Head of each Office and Bureau shall remind employees subject to his or her administrative supervision of the content of the regulations in 5 CFR parts 2635 and 3901 and this part.

(b) Copies of pertinent provisions of the Communications Act of 1934; title 18 of the United States Code; the Standards of Ethical Conduct for Employees of the Executive Branch (5 CFR part 2635); the Commission's Supplemental Standards of Ethical Conduct (5 CFR part 3901); and the Commission's employee responsibilities and conduct regulations in this part shall be available in the office of the Designated Agency Ethics Official for review by employees.

§ 19.735–106 Interpretation and advisory service.

(a) Requests for interpretative rulings concerning the applicability of 5 CFR parts 2635 and 3901, and this part, may be submitted through the employee's supervisor to the General Counsel, who is the Commission's Designated Agency Ethics Official pursuant to the delegation of authority at 47 CFR 0.251(a).

(b) At the time of an employee's entrance on duty and at least once each calendar year thereafter, the Commission's employees shall be notified of the availability of counseling services

47 CFR Ch. I (10–1–97 Edition)

on questions of conflict of interest and other matters covered by this part, and of how and where these services are available.

§ 19.735–107 Disciplinary and other remedial action.

(a) A violation of the regulations in this part by an employee may be cause for appropriate disciplinary action which may be in addition to any penalty prescribed by law.

(b) The Chairman will designate an officer or employee of the Commission who will promptly investigate all incidents or situations in which it appears that employees may have engaged in improper conduct. Such investigation will be initiated in all cases where complaints are brought to the attention of the Chairman, including: Adverse comment appearing in publications; complaints from members of Congress, private citizens, organizations, other Government employees or agencies; and formal complaints referred to the Chairman by the Designated Agency Ethics Official.

(c) The Inspector General will be promptly notified of all complaints or allegations of employee misconduct. The Inspector General will also be notified of the planned initiation of an investigation under this part. Such notification shall occur prior to the initiation of the investigation required by paragraph (a) of this section. The Inspector General may choose to conduct the investigation in accordance with the rules in this part. Should the Inspector General choose to conduct the investigation, he will promptly notify the Chairman. In such case, the Inspector General will serve as the designated officer and be solely responsible for the investigation. In carrying out this function, the Inspector General may obtain investigative services from other Commission offices, other governmental agencies or non governmental sources and use any other means available to him in accordance with Public Law 100–504 or the Inspector General Act of 1978, as amended, 5 U.S.C. Appendix. The Inspector General will be provided with the results of all investigations in which he chooses not to participate.

Federal Communications Commission

§ 19.735–202

(d) The employee concerned shall be provided an opportunity to explain the alleged misconduct. When, after consideration of the employee's explanation, the Chairman decides that remedial action is required, he shall take remedial action. Remedial action may include, but is not limited to:

(1) Changes in assigned duties;

(2) Divestiture by the employee of his conflicting interest;

(3) Action under the Commission's Ethics Program resulting in one of the following actions:

(i) When investigation reveals that the charges are groundless, the person designated by the Chairman to assist in administration of the program may give a letter of clearance to the employee concerned, and the case will not be recorded in his Official Personnel Folder;

(ii) If, after investigation, the case investigator deems the act to be merely a minor indiscretion, he may resolve the situation by discussing it with the employee. The case will not be recorded in the employee's Official Personnel Folder;

(iii) If the case administrator considers the problem to be of sufficient importance, he may call it to the attention of the Chairman, who in turn may notify the employee of the seriousness of his act and warn him of the consequences of a repetition. The case will not be recorded in the employee's Official Personnel Folder, unless the employee requests it;

(iv) The Chairman may, when in his opinion circumstances warrant, establish a special review board to investigate the facts in a case and to make a full report thereon, including recommended action; or

(v)(A) If the Chairman decides that formal disciplinary action should be taken, he may prepare for Commission consideration a statement of facts and recommend one of the following:

(1) *Written reprimand*. A formal letter containing a complete statement of the offense and official censure;

(2) *Suspension*. A temporary non pay status and suspension from duty; or

(3) *Removal for cause*. Separation for cause in case of a serious offense.

(B) Only after a majority of the Commission approves formal disciplinary

action will any record resulting from the administration of this program be placed in the employee's Official Personnel Folder; or

(4) Disqualification for a particular assignment.

(e) Remedial action, whether disciplinary or otherwise, shall be effected in accordance with any applicable laws, Executive orders, and regulations.

Subpart B—Employee Responsibilities and Conduct

§ 19.735–201 Outside employment and other activity prohibited by the Communications Act.

Under section 4(b) of the Communications Act, at 47 U.S.C. 154(b)(2)(A)(iv), no employee of the Commission may be in the employ of or hold any official relation to any person significantly regulated by the Commission under that Act. In addition, the Commissioners are prohibited by section 4(b) of the Communications Act, at 47 U.S.C. 154(b)(4), from engaging in any other business, vocation, profession, or employment.

NOTE: Under the Supplemental Standards of Ethical Conduct for Employees of the Federal Communications Commission, at 5 CFR 3901.102, professional employees of the Commission must obtain approval before engaging in the private practice of the same profession as that of the employee's official position, whether or not for compensation.

§ 19.735–202 Financial interests prohibited by the Communications Act.

(a) No Commissioner shall have a pecuniary interest in any hearing or proceeding in which he participates. (47 U.S.C. 154(j).)

(b)(1) Section 4(b) of the Communications Act, at 47 U.S.C. 154(b)(2)(A), provides:

No member of the Commission or person employed by the Commission shall:

(i) Be financially interested in any company or other entity engaged in the manufacture or sale of telecommunications equipment which is subject to regulation by the Commission;

(ii) Be financially interested in any company or other entity engaged in the business of communication by wire or radio or in the use of the electromagnetic spectrum;

(iii) Be financially interested in any company or other entity which controls any

company or other entity specified in clause (i) or clause (ii), or which derives a significant portion of its total income from ownership of stocks, bonds, or other securities of any such company or other entity; or

(iv) Be employed by, hold any official relation to, or own any stocks, bonds, or other securities of, any person significantly regulated by the Commission under this act; except that the prohibitions established in this subparagraph shall apply only to financial interests in any company or other entity which has a significant interest in communications, manufacturing, or sales activities which are subject to regulation by the Commission.

(2) To determine whether an entity has a significant interest in communications related activities that are subject to Commission regulations, the Commission shall consider, without excluding other relevant factors, the criteria in section 4(b) of the Communications Act, at 47 U.S.C. 154(b)(3). These criteria include:

(i) The revenues and efforts directed toward the telecommunications aspect of the business;

(ii) The extent of Commission regulation over the entity involved;

(iii) The potential economic impact of any Commission action on that particular entity; and

(iv) The public perception regarding the business activities of the company.

(3)(i) Section 4(b) of the Communications Act, at 47 U.S.C. 154(b)(2)(B)(i), permits the Commission to waive the prohibitions at 47 U.S.C. 154(b)(2)(A). The Act's waiver provision at 47 U.S.C. 154(b)(2)(B)(i) provides:

The Commission shall have authority to waive, from time to time, the application of the prohibitions established in subparagraph (A) of section 4(b) to persons employed by the Commission if the Commission determines that the financial interests of a person which are involved in a particular case are minimal, except that such waiver authority shall be subject to the provisions of section 208 of title 18, United States Code. The waiver authority established in this subparagraph shall not apply with respect to members of the Commission.

(ii)(A) Requests for waiver of the provisions of 47 U.S.C. 154(b)(2)(A) may be submitted by an employee to the Head of the employee's Office or Bureau, who will endorse the request with an appropriate recommendation and forward the request to the Designated Agency

Ethics Official. The Designated Agency Ethics Official has delegated authority to waive the applicability of 47 U.S.C. 154(b)(2)(A).

(B) All requests for waiver shall be in writing and in the required detail. The dollar value for the financial interest sought to be waived shall be expressed explicitly or in categories of value provided at 5 CFR 2634.301(d).

(C) Copies of all waiver requests and the action taken thereon shall be maintained by the Designated Agency Ethics Official. In any case in which the Commission exercises the waiver authority established in section 4(b) of the Communications Act, the Commission shall publish notice of such action in the FEDERAL REGISTER and shall furnish notice of such action to the appropriate committees of each House of the Congress. Each such notice shall include information regarding the identity of the person receiving the waiver, the position held by such person, and the nature of the financial interests which are the subject of the waiver.

§ 19.735–203 Nonpublic information.

(a) Except as authorized in writing by the Chairman pursuant to paragraph (b) of this section, or otherwise as authorized by the Commission or its rules, nonpublic information shall not be disclosed, directly or indirectly, to any person outside the Commission. Such information includes, but is not limited to, the following:

(1) The content of agenda items (except for compliance with the Government in the Sunshine Act, 5 U.S.C. 552b); or

(2) Actions or decisions made by the Commission at closed meetings or by circulation prior to the public release of such information by the Commission.

(b) An employee engaged in outside teaching, lecturing, or writing shall not use nonpublic information obtained as a result of his Government employment in connection with such teaching, lecturing, or writing except when the Chairman gives written authorization for the use of that nonpublic information on the basis that its use is in the public interest.

(c) This section does not prohibit the disclosure of an official Commission

Federal Communications Commission

§ 19.735–203

meeting agenda listing titles and summaries of items for discussion at an open Commission meeting. Also, this section does not prohibit the disclosure of information about the scheduling of Commission agenda items.

NOTE: Employees also should refer to the provisions of the Standards of Ethical Conduct for Employees of the Executive Branch, at 5 CFR 2635.703, on the use of nonpublic information. As is the case with section 2635.703, this part is intended only to cover knowing unauthorized disclosures of nonpublic information.

FINDING AIDS

A list of CFR titles, subtitles, chapters, subchapters and parts and an alphabetical list of agencies publishing in the CFR are included in the CFR Index and Finding Aids volume to the Code of Federal Regulations which is published separately and revised annually.

Material Approved for Incorporation by Reference
Table of CFR Titles and Chapters
Alphabetical List of Agencies Appearing in the CFR
List of CFR Sections Affected

Material Approved for Incorporation by Reference

(Revised as of October 1, 1997)

The Director of the Federal Register has approved under 5 U.S.C. 552(a) and 1 CFR Part 51 the incorporation by reference of the following publications. This list contains only those incorporations by reference effective as of the revision date of this volume. Incorporations by reference found within a regulation are effective upon the effective date of that regulation. For more information on incorporation by reference, see the preliminary pages of this volume.

47 CFR (PARTS 0–19)

FEDERAL COMMUNICATIONS COMMISSION

47 CFR

American National Standards Institute (ANSI)

11 West 42nd St., New York, NY 10036

ANSI C63.4–1992, Methods of Measurement of Radio-Noise Emissions from Low-Voltage Electrical and Electronic Equipment in the Range of 9 kHz to 40 GHz, except for sections 5.7, 9 and 14. 2.948; 15.31

Federal Aviation Administration, Department of Transportation

800 Independence Ave., SW., Washington, DC 20591

FAA Advisory Circular AC 70/7460–111, Obstruction Marking and Lighting, August, 1991, including Change 2, July 15, 1992. 17.23

FAA Advisory Circular AC 150/5345–43D, Specification for Obstruction Lighting Equipment, July 15, 1988. 17.23

Global Engineering Documents

3130 South Harbor Boulevard, Santa Ana, CA 92704

Electronic Industries Association, Cable Television Channel Identification Plan, EIA IS–132, May 1994. 15.118

International Electrotechnical Commission

Purchase from: ANSI, 11 West 42nd Street, New York, NY 10036

First Edition of the International Special Committee on Radio Interference (CISPR) Pub. 22 (1985), “Limits and Methods of Measurement of Radio Interference Characteristics of Information Technology Equipment,” and the associated Draft International Standards (DISs) adopted in 1992 and published by the International Electrotechnical Commission as documents CISPR/G (Central Office) 2, CISPR/G (Central Office) 5, CISPR/G (Central Office) 9, CISPR/G (Central Office) 11, CISPR/G (Central Office) 12, CISPR/G (Central Office) 13, and CISPR/G (Central Office) 14. 15.107; 15.109

Table of CFR Titles and Chapters

(Revised as of September 30, 1997)

Title 1—General Provisions

- I Administrative Committee of the Federal Register (Parts 1—49)
- II Office of the Federal Register (Parts 50—299)
- IV Miscellaneous Agencies (Parts 400—500)

Title 2—[Reserved]

Title 3—The President

- I Executive Office of the President (Parts 100—199)

Title 4—Accounts

- I General Accounting Office (Parts 1—99)
- II Federal Claims Collection Standards (General Accounting Office—Department of Justice) (Parts 100—299)

Title 5—Administrative Personnel

- I Office of Personnel Management (Parts 1—1199)
- II Merit Systems Protection Board (Parts 1200—1299)
- III Office of Management and Budget (Parts 1300—1399)
- IV Advisory Committee on Federal Pay (Parts 1400—1499)
- V The International Organizations Employees Loyalty Board (Parts 1500—1599)
- VI Federal Retirement Thrift Investment Board (Parts 1600—1699)
- VII Advisory Commission on Intergovernmental Relations (Parts 1700—1799)
- VIII Office of Special Counsel (Parts 1800—1899)
- IX Appalachian Regional Commission (Parts 1900—1999)
- XI Armed Forces Retirement Home (Part 2100)
- XIV Federal Labor Relations Authority, General Counsel of the Federal Labor Relations Authority and Federal Service Impasses Panel (Parts 2400—2499)
- XV Office of Administration, Executive Office of the President (Parts 2500—2599)
- XVI Office of Government Ethics (Parts 2600—2699)
- XXI Department of the Treasury (Parts 3100—3199)
- XXII Federal Deposit Insurance Corporation (Part 3201)
- XXIII Department of Energy (Part 3301)

Title 5—Administrative Personnel—Continued

Chap.	
XXIV	Federal Energy Regulatory Commission (Part 3401)
XXVI	Department of Defense (Part 3601)
XXVIII	Department of Justice (Part 3801)
XXIX	Federal Communications Commission (Parts 3900—3999)
XXX	Farm Credit System Insurance Corporation (Parts 4000—4099)
XXXI	Farm Credit Administration (Parts 4100—4199)
XXXIII	Overseas Private Investment Corporation (Part 4301)
XXXV	Office of Personnel Management (Part 4501)
XL	Interstate Commerce Commission (Part 5001)
XLI	Commodity Futures Trading Commission (Part 5101)
XLII	Department of Labor (Part 5201)
XLIII	National Science Foundation (Part 5301)
XLV	Department of Health and Human Services (Part 5501)
XLVI	Postal Rate Commission (Part 5601)
XLVII	Federal Trade Commission (Part 5701)
XLVIII	Nuclear Regulatory Commission (Part 5801)
L	Department of Transportation (Part 6001)
LII	Export-Import Bank of the United States (Part 6201)
LIII	Department of Education (Parts 6300—6399)
LIV	Environmental Protection Agency (Part 6401)
LVI	General Services Administration (Part 6701)
LVIII	Board of Governors of the Federal Reserve System (Part 6801)
LIX	National Aeronautics and Space Administration (Part 6901)
LX	United States Postal Service (Part 7001)
LXI	National Labor Relations Board (Part 7101)
LXII	Equal Employment Opportunity Commission (Part 7201)
LXIII	Inter-American Foundation (Part 7301)
LXV	Department of Housing and Urban Development (Part 7501)
LXVI	National Archives and Records Administration (Part 7601)
LXIX	Tennessee Valley Authority (Part 7901)
LXXI	Consumer Product Safety Commission (Part 8101)
LXXIV	Federal Mine Safety and Health Review Commission (Part 8401)
LXXVI	Federal Retirement Thrift Investment Board (Part 8601)
LXXVII	Office of Management and Budget (Part 8701)

Title 6—[Reserved]

Title 7—Agriculture

SUBTITLE A—Office of the Secretary of Agriculture (Parts 0—26)

SUBTITLE B—Regulations of the Department of Agriculture

- I Agricultural Marketing Service (Standards, Inspections, Marketing Practices), Department of Agriculture (Parts 27—209)
- II Food and Consumer Service, Department of Agriculture (Parts 210—299)

Title 7—Agriculture—Continued

Chap.	
III	Animal and Plant Health Inspection Service, Department of Agriculture (Parts 300—399)
IV	Federal Crop Insurance Corporation, Department of Agriculture (Parts 400—499)
V	Agricultural Research Service, Department of Agriculture (Parts 500—599)
VI	Natural Resources Conservation Service, Department of Agriculture (Parts 600—699)
VII	Farm Service Agency, Department of Agriculture (Parts 700—799)
VIII	Grain Inspection, Packers and Stockyards Administration (Federal Grain Inspection Service), Department of Agriculture (Parts 800—899)
IX	Agricultural Marketing Service (Marketing Agreements and Orders; Fruits, Vegetables, Nuts), Department of Agriculture (Parts 900—999)
X	Agricultural Marketing Service (Marketing Agreements and Orders; Milk), Department of Agriculture (Parts 1000—1199)
XI	Agricultural Marketing Service (Marketing Agreements and Orders; Miscellaneous Commodities), Department of Agriculture (Parts 1200—1299)
XIII	Northeast Dairy Compact Commission (Parts 1300—1399)
XIV	Commodity Credit Corporation, Department of Agriculture (Parts 1400—1499)
XV	Foreign Agricultural Service, Department of Agriculture (Parts 1500—1599)
XVI	Rural Telephone Bank, Department of Agriculture (Parts 1600—1699)
XVII	Rural Utilities Service, Department of Agriculture (Parts 1700—1799)
XVIII	Rural Housing Service, Rural Business-Cooperative Service, Rural Utilities Service, and Farm Service Agency, Department of Agriculture (Parts 1800—2099)
XXVI	Office of Inspector General, Department of Agriculture (Parts 2600—2699)
XXVII	Office of Information Resources Management, Department of Agriculture (Parts 2700—2799)
XXVIII	Office of Operations, Department of Agriculture (Parts 2800—2899)
XXIX	Office of Energy, Department of Agriculture (Parts 2900—2999)
XXX	Office of the Chief Financial Officer, Department of Agriculture (Parts 3000—3099)
XXXI	Office of Environmental Quality, Department of Agriculture (Parts 3100—3199)
XXXII	[Reserved]
XXXIII	Office of Transportation, Department of Agriculture (Parts 3300—3399)
XXXIV	Cooperative State Research, Education, and Extension Service, Department of Agriculture (Parts 3400—3499)
XXXV	Rural Housing Service, Department of Agriculture (Parts 3500—3599)

Title 7—Agriculture—Continued

Chap.	
XXXVI	National Agricultural Statistics Service, Department of Agriculture (Parts 3600—3699)
XXXVII	Economic Research Service, Department of Agriculture (Parts 3700—3799)
XXXVIII	World Agricultural Outlook Board, Department of Agriculture (Parts 3800—3899)
XLI	[Reserved]
XLII	Rural Business-Cooperative Service and Rural Utilities Service, Department of Agriculture (Parts 4200—4299)

Title 8—Aliens and Nationality

I	Immigration and Naturalization Service, Department of Justice (Parts 1—499)

Title 9—Animals and Animal Products

I	Animal and Plant Health Inspection Service, Department of Agriculture (Parts 1—199)
II	Grain Inspection, Packers and Stockyards Administration (Packers and Stockyards Programs), Department of Agriculture (Parts 200—299)
III	Food Safety and Inspection Service, Meat and Poultry Inspection, Department of Agriculture (Parts 300—599)

Title 10—Energy

I	Nuclear Regulatory Commission (Parts 0—199)
II	Department of Energy (Parts 200—699)
III	Department of Energy (Parts 700—999)
X	Department of Energy (General Provisions) (Parts 1000—1099)
XI	United States Enrichment Corporation (Parts 1100—1199)
XV	Office of the Federal Inspector for the Alaska Natural Gas Transportation System (Parts 1500—1599)
XXVII	Defense Nuclear Facilities Safety Board (Parts 1700—1799)

Title 11—Federal Elections

I	Federal Election Commission (Parts 1—9099)

Title 12—Banks and Banking

I	Comptroller of the Currency, Department of the Treasury (Parts 1—199)
II	Federal Reserve System (Parts 200—299)
III	Federal Deposit Insurance Corporation (Parts 300—399)
IV	Export-Import Bank of the United States (Parts 400—499)
V	Office of Thrift Supervision, Department of the Treasury (Parts 500—599)
VI	Farm Credit Administration (Parts 600—699)
VII	National Credit Union Administration (Parts 700—799)

Title 12—Banks and Banking—Continued

Chap.	
VIII	Federal Financing Bank (Parts 800—899)
IX	Federal Housing Finance Board (Parts 900—999)
XI	Federal Financial Institutions Examination Council (Parts 1100—1199)
XIV	Farm Credit System Insurance Corporation (Parts 1400—1499)
XV	Thrift Depositor Protection Oversight Board (Parts 1500—1599)
XVII	Office of Federal Housing Enterprise Oversight, Department of Housing and Urban Development (Parts 1700—1799)
XVIII	Community Development Financial Institutions Fund, Department of the Treasury (Parts 1800—1899)

Title 13—Business Credit and Assistance

I	Small Business Administration (Parts 1—199)
III	Economic Development Administration, Department of Commerce (Parts 300—399)

Title 14—Aeronautics and Space

I	Federal Aviation Administration, Department of Transportation (Parts 1—199)
II	Office of the Secretary, Department of Transportation (Aviation Proceedings) (Parts 200—399)
III	Commercial Space Transportation, Federal Aviation Administration, Department of Transportation (Parts 400—499)
V	National Aeronautics and Space Administration (Parts 1200—1299)

Title 15—Commerce and Foreign Trade

SUBTITLE A—Office of the Secretary of Commerce (Parts 0—29)

SUBTITLE B—Regulations Relating to Commerce and Foreign Trade

I	Bureau of the Census, Department of Commerce (Parts 30—199)
II	National Institute of Standards and Technology, Department of Commerce (Parts 200—299)
III	International Trade Administration, Department of Commerce (Parts 300—399)
IV	Foreign-Trade Zones Board, Department of Commerce (Parts 400—499)
VII	Bureau of Export Administration, Department of Commerce (Parts 700—799)
VIII	Bureau of Economic Analysis, Department of Commerce (Parts 800—899)
IX	National Oceanic and Atmospheric Administration, Department of Commerce (Parts 900—999)
XI	Technology Administration, Department of Commerce (Parts 1100—1199)
XIII	East-West Foreign Trade Board (Parts 1300—1399)
XIV	Minority Business Development Agency (Parts 1400—1499)

Title 15—Commerce and Foreign Trade—Continued

Chap.

SUBTITLE C—Regulations Relating to Foreign Trade Agreements

XX Office of the United States Trade Representative (Parts 2000—2099)

SUBTITLE D—Regulations Relating to Telecommunications and Information

XXIII National Telecommunications and Information Administration, Department of Commerce (Parts 2300—2399)

Title 16—Commercial Practices

I Federal Trade Commission (Parts 0—999)

II Consumer Product Safety Commission (Parts 1000—1799)

Title 17—Commodity and Securities Exchanges

I Commodity Futures Trading Commission (Parts 1—199)

II Securities and Exchange Commission (Parts 200—399)

IV Department of the Treasury (Parts 400—499)

Title 18—Conservation of Power and Water Resources

I Federal Energy Regulatory Commission, Department of Energy (Parts 1—399)

III Delaware River Basin Commission (Parts 400—499)

VI Water Resources Council (Parts 700—799)

VIII Susquehanna River Basin Commission (Parts 800—899)

XIII Tennessee Valley Authority (Parts 1300—1399)

Title 19—Customs Duties

I United States Customs Service, Department of the Treasury (Parts 1—199)

II United States International Trade Commission (Parts 200—299)

III International Trade Administration, Department of Commerce (Parts 300—399)

Title 20—Employees' Benefits

I Office of Workers' Compensation Programs, Department of Labor (Parts 1—199)

II Railroad Retirement Board (Parts 200—399)

III Social Security Administration (Parts 400—499)

IV Employees' Compensation Appeals Board, Department of Labor (Parts 500—599)

V Employment and Training Administration, Department of Labor (Parts 600—699)

VI Employment Standards Administration, Department of Labor (Parts 700—799)

VII Benefits Review Board, Department of Labor (Parts 800—899)

VIII Joint Board for the Enrollment of Actuaries (Parts 900—999)

Chap.

Title 20—Employees' Benefits—Continued

- IX Office of the Assistant Secretary for Veterans' Employment and Training, Department of Labor (Parts 1000—1099)

Title 21—Food and Drugs

- I Food and Drug Administration, Department of Health and Human Services (Parts 1—1299)
- II Drug Enforcement Administration, Department of Justice (Parts 1300—1399)
- III Office of National Drug Control Policy (Parts 1400—1499)

Title 22—Foreign Relations

- I Department of State (Parts 1—199)
- II Agency for International Development, International Development Cooperation Agency (Parts 200—299)
- III Peace Corps (Parts 300—399)
- IV International Joint Commission, United States and Canada (Parts 400—499)
- V United States Information Agency (Parts 500—599)
- VI United States Arms Control and Disarmament Agency (Parts 600—699)
- VII Overseas Private Investment Corporation, International Development Cooperation Agency (Parts 700—799)
- IX Foreign Service Grievance Board Regulations (Parts 900—999)
- X Inter-American Foundation (Parts 1000—1099)
- XI International Boundary and Water Commission, United States and Mexico, United States Section (Parts 1100—1199)
- XII United States International Development Cooperation Agency (Parts 1200—1299)
- XIII Board for International Broadcasting (Parts 1300—1399)
- XIV Foreign Service Labor Relations Board; Federal Labor Relations Authority; General Counsel of the Federal Labor Relations Authority; and the Foreign Service Impasse Disputes Panel (Parts 1400—1499)
- XV African Development Foundation (Parts 1500—1599)
- XVI Japan-United States Friendship Commission (Parts 1600—1699)
- XVII United States Institute of Peace (Parts 1700—1799)

Title 23—Highways

- I Federal Highway Administration, Department of Transportation (Parts 1—999)
- II National Highway Traffic Safety Administration and Federal Highway Administration, Department of Transportation (Parts 1200—1299)
- III National Highway Traffic Safety Administration, Department of Transportation (Parts 1300—1399)

	Title 24—Housing and Urban Development
Chap.	
	SUBTITLE A—Office of the Secretary, Department of Housing and Urban Development (Parts 0—99)
	SUBTITLE B—Regulations Relating to Housing and Urban Development
I	Office of Assistant Secretary for Equal Opportunity, Department of Housing and Urban Development (Parts 100—199)
II	Office of Assistant Secretary for Housing-Federal Housing Commissioner, Department of Housing and Urban Development (Parts 200—299)
III	Government National Mortgage Association, Department of Housing and Urban Development (Parts 300—399)
V	Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 500—599)
VI	Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 600—699) [Reserved]
VII	Office of the Secretary, Department of Housing and Urban Development (Housing Assistance Programs and Public and Indian Housing Programs) (Parts 700—799)
VIII	Office of the Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Section 8 Housing Assistance Programs and Section 202 Direct Loan Program) (Parts 800—899)
IX	Office of Assistant Secretary for Public and Indian Housing, Department of Housing and Urban Development (Parts 900—999)
X	Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Interstate Land Sales Registration Program) (Parts 1700—1799)
XII	Office of Inspector General, Department of Housing and Urban Development (Parts 2000—2099)
XX	Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Parts 3200—3899)
XXV	Neighborhood Reinvestment Corporation (Parts 4100—4199)

Title 25—Indians

I	Bureau of Indian Affairs, Department of the Interior (Parts 1—299)
II	Indian Arts and Crafts Board, Department of the Interior (Parts 300—399)
III	National Indian Gaming Commission, Department of the Interior (Parts 500—599)
IV	Office of Navajo and Hopi Indian Relocation (Parts 700—799)
V	Bureau of Indian Affairs, Department of the Interior, and Indian Health Service, Department of Health and Human Services (Part 900)
VI	Office of the Assistant Secretary-Indian Affairs, Department of the Interior (Part 1001)

Title 25—Indians—Continued

Chap.

- VII Office of the Special Trustee for American Indians, Department of the Interior (Part 1200)

Title 26—Internal Revenue

- I Internal Revenue Service, Department of the Treasury (Parts 1—799)

Title 27—Alcohol, Tobacco Products and Firearms

- I Bureau of Alcohol, Tobacco and Firearms, Department of the Treasury (Parts 1—299)

Title 28—Judicial Administration

- I Department of Justice (Parts 0—199)
- III Federal Prison Industries, Inc., Department of Justice (Parts 300—399)
- V Bureau of Prisons, Department of Justice (Parts 500—599)
- VI Offices of Independent Counsel, Department of Justice (Parts 600—699)
- VII Office of Independent Counsel (Parts 700—799)

Title 29—Labor

SUBTITLE A—Office of the Secretary of Labor (Parts 0—99)

SUBTITLE B—Regulations Relating to Labor

- I National Labor Relations Board (Parts 100—199)
- II Office of Labor-Management Standards, Department of Labor (Parts 200—299)
- III National Railroad Adjustment Board (Parts 300—399)
- IV Office of Labor-Management Standards, Department of Labor (Parts 400—499)
- V Wage and Hour Division, Department of Labor (Parts 500—899)
- IX Construction Industry Collective Bargaining Commission (Parts 900—999)
- X National Mediation Board (Parts 1200—1299)
- XII Federal Mediation and Conciliation Service (Parts 1400—1499)
- XIV Equal Employment Opportunity Commission (Parts 1600—1699)
- XXVII Occupational Safety and Health Administration, Department of Labor (Parts 1900—1999)
- XX Occupational Safety and Health Review Commission (Parts 2200—2499)
- XXV Pension and Welfare Benefits Administration, Department of Labor (Parts 2500—2599)
- XXVII Federal Mine Safety and Health Review Commission (Parts 2700—2799)
- XL Pension Benefit Guaranty Corporation (Parts 4000—4999)

Title 30—Mineral Resources

Chap.

- I Mine Safety and Health Administration, Department of Labor (Parts 1—199)
- II Minerals Management Service, Department of the Interior (Parts 200—299)
- III Board of Surface Mining and Reclamation Appeals, Department of the Interior (Parts 300—399)
- IV Geological Survey, Department of the Interior (Parts 400—499)
- VI Bureau of Mines, Department of the Interior (Parts 600—699)
- VII Office of Surface Mining Reclamation and Enforcement, Department of the Interior (Parts 700—999)

Title 31—Money and Finance: Treasury

SUBTITLE A—Office of the Secretary of the Treasury (Parts 0—50)

SUBTITLE B—Regulations Relating to Money and Finance

- I Monetary Offices, Department of the Treasury (Parts 51—199)
- II Fiscal Service, Department of the Treasury (Parts 200—399)
- IV Secret Service, Department of the Treasury (Parts 400—499)
- V Office of Foreign Assets Control, Department of the Treasury (Parts 500—599)
- VI Bureau of Engraving and Printing, Department of the Treasury (Parts 600—699)
- VII Federal Law Enforcement Training Center, Department of the Treasury (Parts 700—799)
- VIII Office of International Investment, Department of the Treasury (Parts 800—899)

Title 32—National Defense

SUBTITLE A—Department of Defense

- I Office of the Secretary of Defense (Parts 1—399)
- V Department of the Army (Parts 400—699)
- VI Department of the Navy (Parts 700—799)
- VII Department of the Air Force (Parts 800—1099)

SUBTITLE B—Other Regulations Relating to National Defense

- XII Defense Logistics Agency (Parts 1200—1299)
- XVI Selective Service System (Parts 1600—1699)
- XIX Central Intelligence Agency (Parts 1900—1999)
- XX Information Security Oversight Office, National Archives and Records Administration (Parts 2000—2099)
- XXI National Security Council (Parts 2100—2199)
- XXIV Office of Science and Technology Policy (Parts 2400—2499)
- XXVII Office for Micronesia Status Negotiations (Parts 2700—2799)
- XXVIII Office of the Vice President of the United States (Parts 2800—2899)
- XXIX Presidential Commission on the Assignment of Women in the Armed Forces (Part 2900)

Chap.

Title 33—Navigation and Navigable Waters

- I Coast Guard, Department of Transportation (Parts 1—199)
- II Corps of Engineers, Department of the Army (Parts 200—399)
- IV Saint Lawrence Seaway Development Corporation, Department of Transportation (Parts 400—499)

Title 34—Education

SUBTITLE A—Office of the Secretary, Department of Education (Parts 1—99)

SUBTITLE B—Regulations of the Offices of the Department of Education

- I Office for Civil Rights, Department of Education (Parts 100—199)
- II Office of Elementary and Secondary Education, Department of Education (Parts 200—299)
- III Office of Special Education and Rehabilitative Services, Department of Education (Parts 300—399)
- IV Office of Vocational and Adult Education, Department of Education (Parts 400—499)
- V Office of Bilingual Education and Minority Languages Affairs, Department of Education (Parts 500—599)
- VI Office of Postsecondary Education, Department of Education (Parts 600—699)
- VII Office of Educational Research and Improvement, Department of Education (Parts 700—799)
- XI National Institute for Literacy (Parts 1100—1199)
- SUBTITLE C—Regulations Relating to Education
- XII National Council on Disability (Parts 1200—1299)

Title 35—Panama Canal

- I Panama Canal Regulations (Parts 1—299)

Title 36—Parks, Forests, and Public Property

- I National Park Service, Department of the Interior (Parts 1—199)
- II Forest Service, Department of Agriculture (Parts 200—299)
- III Corps of Engineers, Department of the Army (Parts 300—399)
- IV American Battle Monuments Commission (Parts 400—499)
- V Smithsonian Institution (Parts 500—599)
- VII Library of Congress (Parts 700—799)
- VIII Advisory Council on Historic Preservation (Parts 800—899)
- IX Pennsylvania Avenue Development Corporation (Parts 900—999)
- XI Architectural and Transportation Barriers Compliance Board (Parts 1100—1199)
- XII National Archives and Records Administration (Parts 1200—1299)
- XIV Assassination Records Review Board (Parts 1400—1499)

Title 37—Patents, Trademarks, and Copyrights

Chap.

- I Patent and Trademark Office, Department of Commerce (Parts 1—199)
- II Copyright Office, Library of Congress (Parts 200—299)
- IV Assistant Secretary for Technology Policy, Department of Commerce (Parts 400—499)
- V Under Secretary for Technology, Department of Commerce (Parts 500—599)

Title 38—Pensions, Bonuses, and Veterans' Relief

- I Department of Veterans Affairs (Parts 0—99)

Title 39—Postal Service

- I United States Postal Service (Parts 1—999)
- III Postal Rate Commission (Parts 3000—3099)

Title 40—Protection of Environment

- I Environmental Protection Agency (Parts 1—799)
- V Council on Environmental Quality (Parts 1500—1599)

Title 41—Public Contracts and Property Management

SUBTITLE B—Other Provisions Relating to Public Contracts

- 50 Public Contracts, Department of Labor (Parts 50-1—50-999)
- 51 Committee for Purchase From People Who Are Blind or Severely Disabled (Parts 51-1—51-99)
- 60 Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor (Parts 60-1—60-999)
- 61 Office of the Assistant Secretary for Veterans Employment and Training, Department of Labor (Parts 61-1—61-999)

SUBTITLE C—Federal Property Management Regulations System

- 101 Federal Property Management Regulations (Parts 101-1—101-99)
- 105 General Services Administration (Parts 105-1—105-999)
- 109 Department of Energy Property Management Regulations (Parts 109-1—109-99)
- 114 Department of the Interior (Parts 114-1—114-99)
- 115 Environmental Protection Agency (Parts 115-1—115-99)
- 128 Department of Justice (Parts 128-1—128-99)

SUBTITLE D—Other Provisions Relating to Property Management [Reserved]

SUBTITLE E—Federal Information Resources Management Regulations System

- 201 Federal Information Resources Management Regulation (Parts 201-1—201-99) [Reserved]

SUBTITLE F—Federal Travel Regulation System

- 301 Travel Allowances (Parts 301-1—301-99)
- 302 Relocation Allowances (Parts 302-1—302-99)

Title 41—Public Contracts and Property Management—Continued

Chap.

- 303 Payment of Expenses Connected with the Death of Certain Employees (Parts 303-1—303-2)
- 304 Payment from a Non-Federal Source for Travel Expenses (Parts 304-1—304-99)

Title 42—Public Health

- I Public Health Service, Department of Health and Human Services (Parts 1—199)
- IV Health Care Financing Administration, Department of Health and Human Services (Parts 400—499)
- V Office of Inspector General-Health Care, Department of Health and Human Services (Parts 1000—1999)

Title 43—Public Lands: Interior

SUBTITLE A—Office of the Secretary of the Interior (Parts 1—199)

SUBTITLE B—Regulations Relating to Public Lands

- I Bureau of Reclamation, Department of the Interior (Parts 200—499)
- II Bureau of Land Management, Department of the Interior (Parts 1000—9999)
- III Utah Reclamation Mitigation and Conservation Commission (Parts 10000—10005)

Title 44—Emergency Management and Assistance

- I Federal Emergency Management Agency (Parts 0—399)
- IV Department of Commerce and Department of Transportation (Parts 400—499)

Title 45—Public Welfare

SUBTITLE A—Department of Health and Human Services (Parts 1—199)

SUBTITLE B—Regulations Relating to Public Welfare

- II Office of Family Assistance (Assistance Programs), Administration for Children and Families, Department of Health and Human Services (Parts 200—299)
- III Office of Child Support Enforcement (Child Support Enforcement Program), Administration for Children and Families, Department of Health and Human Services (Parts 300—399)
- IV Office of Refugee Resettlement, Administration for Children and Families Department of Health and Human Services (Parts 400—499)
- V Foreign Claims Settlement Commission of the United States, Department of Justice (Parts 500—599)
- VI National Science Foundation (Parts 600—699)
- VII Commission on Civil Rights (Parts 700—799)
- VIII Office of Personnel Management (Parts 800—899)

Title 45—Public Welfare—Continued

Chap.	
X	Office of Community Services, Administration for Children and Families, Department of Health and Human Services (Parts 1000—1099)
XI	National Foundation on the Arts and the Humanities (Parts 1100—1199)
XII	ACTION (Parts 1200—1299)
XIII	Office of Human Development Services, Department of Health and Human Services (Parts 1300—1399)
XVI	Legal Services Corporation (Parts 1600—1699)
XVII	National Commission on Libraries and Information Science (Parts 1700—1799)
XVIII	Harry S. Truman Scholarship Foundation (Parts 1800—1899)
XXI	Commission on Fine Arts (Parts 2100—2199)
XXII	Christopher Columbus Quincentenary Jubilee Commission (Parts 2200—2299)
XXIII	Arctic Research Commission (Part 2301)
XXIV	James Madison Memorial Fellowship Foundation (Parts 2400—2499)
XXV	Corporation for National and Community Service (Parts 2500—2599)

Title 46—Shipping

I	Coast Guard, Department of Transportation (Parts 1—199)
II	Maritime Administration, Department of Transportation (Parts 200—399)
IV	Federal Maritime Commission (Parts 500—599)

Title 47—Telecommunication

I	Federal Communications Commission (Parts 0—199)
II	Office of Science and Technology Policy and National Security Council (Parts 200—299)
III	National Telecommunications and Information Administration, Department of Commerce (Parts 300—399)

Title 48—Federal Acquisition Regulations System

1	Federal Acquisition Regulation (Parts 1—99)
2	Department of Defense (Parts 200—299)
3	Department of Health and Human Services (Parts 300—399)
4	Department of Agriculture (Parts 400—499)
5	General Services Administration (Parts 500—599)
6	Department of State (Parts 600—699)
7	United States Agency for International Development (Parts 700—799)
8	Department of Veterans Affairs (Parts 800—899)
9	Department of Energy (Parts 900—999)
10	Department of the Treasury (Parts 1000—1099)

Title 48—Federal Acquisition Regulations System—Continued

Chap.

- 12 Department of Transportation (Parts 1200—1299)
- 13 Department of Commerce (Parts 1300—1399)
- 14 Department of the Interior (Parts 1400—1499)
- 15 Environmental Protection Agency (Parts 1500—1599)
- 16 Office of Personnel Management Federal Employees Health Benefits Acquisition Regulation (Parts 1600—1699)
- 17 Office of Personnel Management (Parts 1700—1799)
- 18 National Aeronautics and Space Administration (Parts 1800—1899)
- 19 United States Information Agency (Parts 1900—1999)
- 20 Nuclear Regulatory Commission (Parts 2000—2099)
- 21 Office of Personnel Management, Federal Employees Group Life Insurance Federal Acquisition Regulation (Parts 2100—2199)
- 23 Social Security Administration (Parts 2300—2399)
- 24 Department of Housing and Urban Development (Parts 2400—2499)
- 25 National Science Foundation (Parts 2500—2599)
- 28 Department of Justice (Parts 2800—2899)
- 29 Department of Labor (Parts 2900—2999)
- 34 Department of Education Acquisition Regulation (Parts 3400—3499)
- 35 Panama Canal Commission (Parts 3500—3599)
- 44 Federal Emergency Management Agency (Parts 4400—4499)
- 51 Department of the Army Acquisition Regulations (Parts 5100—5199)
- 52 Department of the Navy Acquisition Regulations (Parts 5200—5299)
- 53 Department of the Air Force Federal Acquisition Regulation Supplement (Parts 5300—5399)
- 54 Defense Logistics Agency, Department of Defense (Part 5452)
- 57 African Development Foundation (Parts 5700—5799)
- 61 General Services Administration Board of Contract Appeals (Parts 6100—6199)
- 63 Department of Transportation Board of Contract Appeals (Parts 6300—6399)
- 99 Cost Accounting Standards Board, Office of Federal Procurement Policy, Office of Management and Budget (Parts 9900—9999)

Title 49—Transportation

SUBTITLE A—Office of the Secretary of Transportation (Parts 1—99)

SUBTITLE B—Other Regulations Relating to Transportation

- I Research and Special Programs Administration, Department of Transportation (Parts 100—199)
- II Federal Railroad Administration, Department of Transportation (Parts 200—299)

Title 49—Transportation—Continued

Chap.

- III Federal Highway Administration, Department of Transportation (Parts 300—399)
- IV Coast Guard, Department of Transportation (Parts 400—499)
- V National Highway Traffic Safety Administration, Department of Transportation (Parts 500—599)
- VI Federal Transit Administration, Department of Transportation (Parts 600—699)
- VII National Railroad Passenger Corporation (AMTRAK) (Parts 700—799)
- VIII National Transportation Safety Board (Parts 800—999)
- X Surface Transportation Board, Department of Transportation (Parts 1000—1399)

Title 50—Wildlife and Fisheries

- I United States Fish and Wildlife Service, Department of the Interior (Parts 1—199)
- II National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 200—299)
- III International Fishing and Related Activities (Parts 300—399)
- IV Joint Regulations (United States Fish and Wildlife Service, Department of the Interior and National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce); Endangered Species Committee Regulations (Parts 400—499)
- V Marine Mammal Commission (Parts 500—599)
- VI Fishery Conservation and Management, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 600—699)

CFR Index and Finding Aids

Subject/Agency Index

List of Agency Prepared Indexes

Parallel Tables of Statutory Authorities and Rules

Acts Requiring Publication in the Federal Register

List of CFR Titles, Chapters, Subchapters, and Parts

Alphabetical List of Agencies Appearing in the CFR

Alphabetical List of Agencies Appearing in the CFR

(Revised as of September 30, 1997)

Agency	CFR Title, Subtitle or Chapter
ACTION	45, XII
Administrative Committee of the Federal Register	1, I
Advanced Research Projects Agency	32, I
Advisory Commission on Intergovernmental Relations	5, VII
Advisory Committee on Federal Pay	5, IV
Advisory Council on Historic Preservation	36, VIII
African Development Foundation	22, XV
Federal Acquisition Regulation	48, 57
Agency for International Development, United States	22, II
Federal Acquisition Regulation	48, 7
Agricultural Marketing Service	7, I, IX, X, XI
Agricultural Research Service	7, V
Agriculture Department	
Agricultural Marketing Service	7, I, IX, X, XI
Agricultural Research Service	7, V
Animal and Plant Health Inspection Service	7, III; 9, I
Chief Financial Officer, Office of	7, XXX
Commodity Credit Corporation	7, XIV
Cooperative State Research, Education, and Extension Service	7, XXXIV
Economic Research Service	7, XXXVII
Energy, Office of	7, XXIX
Environmental Quality, Office of	7, XXXI
Farm Service Agency	7, VII, XVIII
Federal Acquisition Regulation	48, 4
Federal Crop Insurance Corporation	7, IV
Food and Consumer Service	7, II
Food Safety and Inspection Service	9, III
Foreign Agricultural Service	7, XV
Forest Service	36, II
Grain Inspection, Packers and Stockyards Administration	7, VIII; 9, II
Information Resources Management, Office of	7, XXVII
Inspector General, Office of	7, XXVI
National Agricultural Library	7, XLI
National Agricultural Statistics Service	7, XXXVI
Natural Resources Conservation Service	7, VI
Operations, Office of	7, XXVIII
Rural Business-Cooperative Service	7, XVIII, XLII
Rural Development Administration	7, XLII
Rural Housing Service	7, XVIII, XXXV
Rural Telephone Bank	7, XVI
Rural Utilities Service	7, XVII, XVIII, XLII
Secretary of Agriculture, Office of	7, Subtitle A
Transportation, Office of	7, XXXIII
World Agricultural Outlook Board	7, XXXVIII
Air Force Department	32, VII
Federal Acquisition Regulation Supplement	48, 53
Alaska Natural Gas Transportation System, Office of the Federal Inspector	10, XV
Alcohol, Tobacco and Firearms, Bureau of	27, I
AMTRAK	49, VII
American Battle Monuments Commission	36, IV
American Indians, Office of the Special Trustee	25, VII

Agency	CFR Title, Subtitle or Chapter
Animal and Plant Health Inspection Service	7, III; 9, I
Appalachian Regional Commission	5, IX
Architectural and Transportation Barriers Compliance Board	36, XI
Arctic Research Commission	45, XXIII
Armed Forces Retirement Home	5, XI
Arms Control and Disarmament Agency, United States	22, VI
Army Department	32, V
Engineers, Corps of	33, II; 36, III
Federal Acquisition Regulation	48, 51
Assassination Records Review Board	36, XIV
Benefits Review Board	20, VII
Bilingual Education and Minority Languages Affairs, Office of	34, V
Blind or Severely Disabled, Committee for Purchase From People Who Are	41, 51
Board for International Broadcasting	22, XIII
Census Bureau	15, I
Central Intelligence Agency	32, XIX
Chief Financial Officer, Office of	7, XXX
Child Support Enforcement, Office of	45, III
Children and Families, Administration for	45, II, III, IV, X
Christopher Columbus Quincentenary Jubilee Commission	45, XXII
Civil Rights, Commission on	45, VII
Civil Rights, Office for	34, I
Coast Guard	33, I; 46, I; 49, IV
Commerce Department	44, IV
Census Bureau	15, I'
Economic Affairs, Under Secretary	37, V
Economic Analysis, Bureau of	15, VIII
Economic Development Administration	13, III
Emergency Management and Assistance	44, IV
Export Administration, Bureau of	15, VII
Federal Acquisition Regulation	48, 13
Fishery Conservation and Management	50, VI
Foreign-Trade Zones Board	15, IV
International Trade Administration	15, III; 19, III
National Institute of Standards and Technology	15, II
National Marine Fisheries Service	50, II, IV
National Oceanic and Atmospheric Administration	15, IX; 50, II, III, IV, VI
National Telecommunications and Information Administration	15, XXIII; 47, III
National Weather Service	15, IX
Patent and Trademark Office	37, I
Productivity, Technology and Innovation, Assistant Secretary for	37, IV
Secretary of Commerce, Office of	15, Subtitle A
Technology, Under Secretary for	37, V
Technology Administration	15, XI
Technology Policy, Assistant Secretary for	37, IV
Commercial Space Transportation	14, III
Commodity Credit Corporation	7, XIV
Commodity Futures Trading Commission	5, XLI; 17, I
Community Planning and Development, Office of Assistant Secretary for	24, V, VI
Community Services, Office of	45, X
Comptroller of the Currency	12, I
Construction Industry Collective Bargaining Commission	29, IX
Consumer Product Safety Commission	5, LXXI; 16, II
Cooperative State Research, Education, and Extension Service	7, XXXIV
Copyright Office	37, II
Cost Accounting Standards Board	48, 99
Council on Environmental Quality	40, V
Customs Service, United States	19, I
Defense Contract Audit Agency	32, I
Defense Department	5, XXVI; 32, Subtitle A
Advanced Research Projects Agency	32, I
Air Force Department	32, VII

Agency	CFR Title, Subtitle or Chapter
Army Department	32, V; 33, II; 36, III, 48, 51
Defense Intelligence Agency	32, I
Defense Logistics Agency	32, I, XII; 48, 54
Defense Mapping Agency	32, I
Engineers, Corps of	33, II; 36, III
Federal Acquisition Regulation	48, 2
Navy Department	32, VI; 48, 52
Secretary of Defense, Office of	32, I
Defense Contract Audit Agency	32, I
Defense Intelligence Agency	32, I
Defense Logistics Agency	32, XII; 48, 54
Defense Mapping Agency	32, I
Defense Nuclear Facilities Safety Board	10, XVII
Delaware River Basin Commission	18, III
Drug Enforcement Administration	21, II
East-West Foreign Trade Board	15, XIII
Economic Affairs, Under Secretary	37, V
Economic Analysis, Bureau of	15, VIII
Economic Development Administration	13, III
Economic Research Service	7, XXXVII
Education, Department of	5, LIII
Bilingual Education and Minority Languages Affairs, Office of	34, V
Civil Rights, Office for	34, I
Educational Research and Improvement, Office of	34, VII
Elementary and Secondary Education, Office of	34, II
Federal Acquisition Regulation	48, 34
Postsecondary Education, Office of	34, VI
Secretary of Education, Office of	34, Subtitle A
Special Education and Rehabilitative Services, Office of	34, III
Vocational and Adult Education, Office of	34, IV
Educational Research and Improvement, Office of	34, VII
Elementary and Secondary Education, Office of	34, II
Employees' Compensation Appeals Board	20, IV
Employees Loyalty Board	5, V
Employment and Training Administration	20, V
Employment Standards Administration	20, VI
Endangered Species Committee	50, IV
Energy, Department of	5, XXIII; 10, II, III, X
Federal Acquisition Regulation	48, 9
Federal Energy Regulatory Commission	5, XXIV; 18, I
Property Management Regulations	41, 109
Energy, Office of	7, XXIX
Engineers, Corps of	33, II; 36, III
Engraving and Printing, Bureau of	31, VI
Enrichment Corporation, United States	10, XI
Environmental Protection Agency	5, LIV; 40, I
Federal Acquisition Regulation	48, 15
Property Management Regulations	41, 115
Environmental Quality, Office of	7, XXXI
Equal Employment Opportunity Commission	5, LXII; 29, XIV
Equal Opportunity, Office of Assistant Secretary for	24, I
Executive Office of the President	3, I
Administration, Office of	5, XV
Environmental Quality, Council on	40, V
Management and Budget, Office of	25, III, LXXVII; 48, 99
National Drug Control Policy, Office of	21, III
National Security Council	32, XXI; 47, 2
Presidential Documents	3
Science and Technology Policy, Office of	32, XXIV; 47, II
Trade Representative, Office of the United States	15, XX
Export Administration, Bureau of	15, VII
Export-Import Bank of the United States	5, LII; 12, IV
Family Assistance, Office of	45, II
Farm Credit Administration	5, XXXI; 12, VI
Farm Credit System Insurance Corporation	5, XXX; 12, XIV

Agency	CFR Title, Subtitle or Chapter
Farm Service Agency	7, VII, XVIII
Federal Acquisition Regulation	48, I
Federal Aviation Administration	14, I
Commercial Space Transportation	14, III
Federal Claims Collection Standards	4, II
Federal Communications Commission	5, XXIX; 47, I
Federal Contract Compliance Programs, Office of	41, 60
Federal Crop Insurance Corporation	7, IV
Federal Deposit Insurance Corporation	5, XXII; 12, III
Federal Election Commission	11, I
Federal Emergency Management Agency	44, I
Federal Acquisition Regulation	48, 44
Federal Employees Group Life Insurance Federal Acquisition Regulation	48, 21
Federal Employees Health Benefits Acquisition Regulation	48, 16
Federal Energy Regulatory Commission	5, XXIV; 18, I
Federal Financial Institutions Examination Council	12, XI
Federal Financing Bank	12, VIII
Federal Highway Administration	23, I, II; 49, III
Federal Home Loan Mortgage Corporation	1, IV
Federal Housing Enterprise Oversight Office	12, XVII
Federal Housing Finance Board	12, IX
Federal Inspector for the Alaska Natural Gas Transportation System, Office of	10, XV
Federal Labor Relations Authority, and General Counsel of the Federal Labor Relations Authority	5, XIV; 22, XIV
Federal Law Enforcement Training Center	31, VII
Federal Maritime Commission	46, IV
Federal Mediation and Conciliation Service	29, XII
Federal Mine Safety and Health Review Commission	5, LXXIV; 29, XXVII
Federal Pay, Advisory Committee on	5, IV
Federal Prison Industries, Inc.	28, III
Federal Procurement Policy Office	48, 99
Federal Property Management Regulations	41, 101
Federal Property Management Regulations System	41, Subtitle C
Federal Railroad Administration	49, II
Federal Register, Administrative Committee of	1, I
Federal Register, Office of	1, II
Federal Reserve System	12, II
Board of Governors	5, LVIII
Federal Retirement Thrift Investment Board	5, VI, LXXVI
Federal Service Impasses Panel	5, XIV
Federal Trade Commission	5, XLVII; 16, I
Federal Transit Administration	49, VI
Federal Travel Regulation System	41, Subtitle F
Fine Arts, Commission on	45, XXI
Fiscal Service	31, II
Fish and Wildlife Service, United States	50, I, IV
Fishery Conservation and Management	50, VI
Food and Drug Administration	21, I
Food and Consumer Service	7, II
Food Safety and Inspection Service	9, III
Foreign Agricultural Service	7, XV
Foreign Assets Control, Office of	31, V
Foreign Claims Settlement Commission of the United States	45, V
Foreign Service Grievance Board	22, IX
Foreign Service Impasse Disputes Panel	22, XIV
Foreign Service Labor Relations Board	22, XIV
Foreign-Trade Zones Board	15, IV
Forest Service	36, II
General Accounting Office	4, I, II
General Services Administration	5, LVII
Contract Appeals, Board of	48, 61
Federal Acquisition Regulation	48, 5
Federal Property Management Regulations System	41, 101, 105
Federal Travel Regulation System	41, Subtitle F
Payment From a Non-Federal Source for Travel Expenses	41, 304

Agency	CFR Title, Subtitle or Chapter
Payment of Expenses Connected With the Death of Certain Employees	41, 303
Relocation Allowances	41, 302
Travel Allowances	41, 301
Geological Survey	30, IV
Government Ethics, Office of	5, XVI
Government National Mortgage Association	24, III
Grain Inspection, Packers and Stockyards Administration	7, VIII; 9, II
Great Lakes Pilotage	46, III
Harry S. Truman Scholarship Foundation	45, XVIII
Health and Human Services, Department of	5, XLV; 45, Subtitle A
Child Support Enforcement, Office of	45, III
Children and Families, Administration for	45, II, III, IV, X
Community Services, Office of	45, X
Family Assistance, Office of	45, II
Federal Acquisition Regulation	48, 3
Food and Drug Administration	21, I
Health Care Financing Administration	42, IV
Human Development Services, Office of	45, XIII
Indian Health Service	25, V
Inspector General (Health Care), Office of	42, V
Public Health Service	42, I
Refugee Resettlement, Office of	45, IV
Health Care Financing Administration	42, IV
Housing and Urban Development, Department of	5, LXV; 24, Subtitle B
Community Planning and Development, Office of Assistant Secretary for	24, V, VI
Equal Opportunity, Office of Assistant Secretary for	24, I
Federal Acquisition Regulation	48, 24
Federal Housing Enterprise Oversight, Office of	12, XVII
Government National Mortgage Association	24, III
Housing—Federal Housing Commissioner, Office of Assistant Secretary for	24, II, VIII, X, XX
Inspector General, Office of	24, XII
Public and Indian Housing, Office of Assistant Secretary for	24, IX
Secretary, Office of	24, Subtitle A, VII
Housing—Federal Housing Commissioner, Office of Assistant Secretary for	24, II, VIII, X, XX
Human Development Services, Office of	45, XIII
Immigration and Naturalization Service	8, I
Independent Counsel, Office of	28, VII
Indian Affairs, Bureau of	25, I, V
Indian Affairs, Office of the Assistant Secretary	25, VI
Indian Arts and Crafts Board	25, II
Indian Health Service	25, V
Information Agency, United States	22, V
Federal Acquisition Regulation	48, 19
Information Resources Management, Office of	7, XXVII
Information Security Oversight Office, National Archives and Records Administration	32, XX
Inspector General	
Agriculture Department	7, XXVI
Health and Human Services Department	42, V
Housing and Urban Development Department	24, XII
Institute of Peace, United States	22, XVII
Inter-American Foundation	5, LXIII; 22, X
Intergovernmental Relations, Advisory Commission on	5, VII
Interior Department	
American Indians, Office of the Special Trustee	25, VII
Endangered Species Committee	50, IV
Federal Acquisition Regulation	48, 14
Federal Property Management Regulations System	41, 114
Fish and Wildlife Service, United States	50, I, IV
Geological Survey	30, IV
Indian Affairs, Bureau of	25, I, V
Indian Affairs, Office of the Assistant Secretary	25, VI
Indian Arts and Crafts Board	25, II

Agency	CFR Title, Subtitle or Chapter
Land Management, Bureau of	43, II
Minerals Management Service	30, II
Mines, Bureau of	30, VI
National Indian Gaming Commission	25, III
National Park Service	36, I
Reclamation, Bureau of	43, I
Secretary of the Interior, Office of	43, Subtitle A
Surface Mining and Reclamation Appeals, Board of	30, III
Surface Mining Reclamation and Enforcement, Office of	30, VII
Internal Revenue Service	26, I
International Boundary and Water Commission, United States and Mexico, United States Section	22, XI
International Development, United States Agency for	22, II
Federal Acquisition Regulation	48, 7
International Development Cooperation Agency, United States	22, XII
International Development, United States Agency for	22, II; 48, 7
Overseas Private Investment Corporation	5, XXXIII; 22, VII
International Fishing and Related Activities	50, III
International Investment, Office of	31, VIII
International Joint Commission, United States and Canada	22, IV
International Organizations Employees Loyalty Board	5, V
International Trade Administration	15, III; 19, III
International Trade Commission, United States	19, II
Interstate Commerce Commission	5, XL
James Madison Memorial Fellowship Foundation	45, XXIV
Japan–United States Friendship Commission	22, XVI
Joint Board for the Enrollment of Actuaries	20, VIII
Justice Department	5, XXVIII; 28, I
Drug Enforcement Administration	21, II
Federal Acquisition Regulation	48, 28
Federal Claims Collection Standards	4, II
Federal Prison Industries, Inc.	28, III
Foreign Claims Settlement Commission of the United States	45, V
Immigration and Naturalization Service	8, I
Offices of Independent Counsel	28, VI
Prisons, Bureau of	28, V
Property Management Regulations	41, 128
Labor Department	5, XLII
Benefits Review Board	20, VII
Employees' Compensation Appeals Board	20, IV
Employment and Training Administration	20, V
Employment Standards Administration	20, VI
Federal Acquisition Regulation	48, 29
Federal Contract Compliance Programs, Office of	41, 60
Federal Procurement Regulations System	41, 50
Labor-Management Standards, Office of	29, II, IV
Mine Safety and Health Administration	30, I
Occupational Safety and Health Administration	29, XVII
Pension and Welfare Benefits Administration	29, XXV
Public Contracts	41, 50
Secretary of Labor, Office of	29, Subtitle A
Veterans' Employment and Training, Office of the Assistant Secretary for	41, 61; 20, IX
Wage and Hour Division	29, V
Workers' Compensation Programs, Office of	20, I
Labor-Management Standards, Office of	29, II, IV
Land Management, Bureau of	43, II
Legal Services Corporation	45, XVI
Library of Congress	36, VII
Copyright Office	37, II
Management and Budget, Office of	5, III, LXXVII; 48, 99
Marine Mammal Commission	50, V
Maritime Administration	46, II
Merit Systems Protection Board	5, II
Micronesian Status Negotiations, Office for	32, XXVII

Agency	CFR Title, Subtitle or Chapter
Mine Safety and Health Administration	30, I
Minerals Management Service	30, II
Mines, Bureau of	30, VI
Minority Business Development Agency	15, XIV
Miscellaneous Agencies	1, IV
Monetary Offices	31, I
National Aeronautics and Space Administration	5, LIX; 14, V
Federal Acquisition Regulation	48, 18
National Agricultural Library	7, XLI
National Agricultural Statistics Service	7, XXXVI
National Archives and Records Administration	5, LXVI; 36, XII
Information Security Oversight Office	32, XX
National Bureau of Standards	15, II
National Capital Planning Commission	1, IV
National Commission for Employment Policy	1, IV
National Commission on Libraries and Information Science	45, XVII
National and Community Service, Corporation for	45, XXV
National Council on Disability	34, XII
National Credit Union Administration	12, VII
National Drug Control Policy, Office of	21, III
National Foundation on the Arts and the Humanities	45, XI
National Highway Traffic Safety Administration	23, II, III; 49, V
National Indian Gaming Commission	25, III
National Institute for Literacy	34, XI
National Institute of Standards and Technology	15, II
National Labor Relations Board	5, LXI; 29, I
National Marine Fisheries Service	50, II, IV
National Mediation Board	29, X
National Oceanic and Atmospheric Administration	15, IX; 50, II, III, IV, VI
National Park Service	36, I
National Railroad Adjustment Board	29, III
National Railroad Passenger Corporation (AMTRAK)	49, VII
National Science Foundation	5, XLIII; 45, VI
Federal Acquisition Regulation	48, 25
National Security Council	32, XXI
National Security Council and Office of Science and Technology Policy	47, II
National Telecommunications and Information Administration	15, XXIII; 47, III
National Transportation Safety Board	49, VIII
National Weather Service	15, IX
Natural Resources Conservation Service	7, VI
Navajo and Hopi Indian Relocation, Office of	25, IV
Navy Department	32, VI
Federal Acquisition Regulation	48, 52
Neighborhood Reinvestment Corporation	24, XXV
Northeast Dairy Compact Commission	7, XIII
Nuclear Regulatory Commission	5, XLVIII; 10, I
Federal Acquisition Regulation	48, 20
Occupational Safety and Health Administration	29, XVII
Occupational Safety and Health Review Commission	29, XX
Offices of Independent Counsel	28, VI
Operations Office	7, XXVIII
Overseas Private Investment Corporation	5, XXXIII; 22, VII
Panama Canal Commission	48, 35
Panama Canal Regulations	35, I
Patent and Trademark Office	37, I
Payment From a Non-Federal Source for Travel Expenses	41, 304
Payment of Expenses Connected With the Death of Certain Employees	41, 303
Peace Corps	22, III
Pennsylvania Avenue Development Corporation	36, IX
Pension and Welfare Benefits Administration	29, XXV
Pension Benefit Guaranty Corporation	29, XL
Personnel Management, Office of	5, I, XXXV; 45, VIII
Federal Acquisition Regulation	48, 17
Federal Employees Group Life Insurance Federal Acquisition Regulation	48, 21

Agency	CFR Title, Subtitle or Chapter
Federal Employees Health Benefits Acquisition Regulation	48, 16
Postal Rate Commission	5, XLVI; 39, III
Postal Service, United States	5, LX; 39, I
Postsecondary Education, Office of	34, VI
President's Commission on White House Fellowships	1, IV
Presidential Commission on the Assignment of Women in the Armed Forces	32, XXIX
Presidential Documents	3
Prisons, Bureau of	28, V
Productivity, Technology and Innovation, Assistant Secretary	37, IV
Public Contracts, Department of Labor	41, 50
Public and Indian Housing, Office of Assistant Secretary for	24, IX
Public Health Service	42, I
Railroad Retirement Board	20, II
Reclamation, Bureau of	43, I
Refugee Resettlement, Office of	45, IV
Regional Action Planning Commissions	13, V
Relocation Allowances	41, 302
Research and Special Programs Administration	49, I
Rural Business-Cooperative Service	7, XVIII, XLII
Rural Development Administration	7, XLII
Rural Housing Service	7, XVIII, XXXV
Rural Telephone Bank	7, XVI
Rural Utilities Service	7, XVII, XVIII, XLII
Saint Lawrence Seaway Development Corporation	33, IV
Science and Technology Policy, Office of	32, XXIV
Science and Technology Policy, Office of, and National Security Council	47, II
Secret Service	31, IV
Securities and Exchange Commission	17, II
Selective Service System	32, XVI
Small Business Administration	13, I
Smithsonian Institution	36, V
Social Security Administration	20, III; 48, 23
Soldiers' and Airmen's Home, United States	5, XI
Special Counsel, Office of	5, VIII
Special Education and Rehabilitative Services, Office of	34, III
State Department	22, I
Federal Acquisition Regulation	48, 6
Surface Mining and Reclamation Appeals, Board of	30, III
Surface Mining Reclamation and Enforcement, Office of	30, VII
Surface Transportation Board	49, X
Susquehanna River Basin Commission	18, VIII
Technology Administration	15, XI
Technology Policy, Assistant Secretary for	37, IV
Technology, Under Secretary for	37, V
Tennessee Valley Authority	5, LXIX; 18, XIII
Thrift Depositor Protection Oversight Board	12, XV
Thrift Supervision Office, Department of the Treasury	12, V
Trade Representative, United States, Office of	15, XX
Transportation, Department of	5, L
Coast Guard	33, I; 46, I; 49, IV
Commercial Space Transportation	14, III
Contract Appeals, Board of	48, 63
Emergency Management and Assistance	44, IV
Federal Acquisition Regulation	48, 12
Federal Aviation Administration	14, I
Federal Highway Administration	23, I, II; 49, III
Federal Railroad Administration	49, II
Federal Transit Administration	49, VI
Maritime Administration	46, II
National Highway Traffic Safety Administration	23, II, III; 49, V
Research and Special Programs Administration	49, I
Saint Lawrence Seaway Development Corporation	33, IV
Secretary of Transportation, Office of	14, II; 49, Subtitle A
Surface Transportation Board	49, X

Agency	CFR Title, Subtitle or Chapter
Transportation, Office of	7, XXXIII
Travel Allowances	41, 301
Treasury Department	5, XXI; 17, IV
Alcohol, Tobacco and Firearms, Bureau of	27, I
Community Development Financial Institutions Fund	12, XVIII
Comptroller of the Currency	12, I
Customs Service, United States	19, I
Engraving and Printing, Bureau of	31, VI
Federal Acquisition Regulation	48, 10
Federal Law Enforcement Training Center	31, VII
Fiscal Service	31, II
Foreign Assets Control, Office of	31, V
Internal Revenue Service	26, I
International Investment, Office of	31, VIII
Monetary Offices	31, I
Secret Service	31, IV
Secretary of the Treasury, Office of	31, Subtitle A
Thrift Supervision, Office of	12, V
Truman, Harry S. Scholarship Foundation	45, XVIII
United States and Canada, International Joint Commission	22, IV
United States and Mexico, International Boundary and Water Commission, United States Section	22, XI
United States Enrichment Corporation	10, XI
Utah Reclamation Mitigation and Conservation Commission	43, III
Veterans Affairs Department	38, I
Federal Acquisition Regulation	48, 8
Veterans' Employment and Training, Office of the Assistant Secretary for	41, 61; 20, IX
Vice President of the United States, Office of	32, XXVIII
Vocational and Adult Education, Office of	34, IV
Wage and Hour Division	29, V
Water Resources Council	18, VI
Workers' Compensation Programs, Office of	20, I
World Agricultural Outlook Board	7, XXXVIII

List of CFR Sections Affected

All changes in this volume of the Code of Federal Regulations which were made by documents published in the FEDERAL REGISTER since January 1, 1986, are enumerated in the following list. Entries indicate the nature of the changes effected. Page numbers refer to FEDERAL REGISTER pages. The user should consult the entries for chapters and parts as well as sections for revisions.

For the period before January 1, 1986, see the "List of CFR Sections Affected, 1949-1963, 1964-1972, and 1973-1985," published in seven separate volumes.

1986		47 CFR—Continued	
47 CFR	51 FR Page		51 FR Page
Chapter I		Chapter I—Continued	
Chapter I Report and order	4918	0.243 Heading and (a) through (e)	
Policy statement	9794, 20975	amended	12615
Procedural changes	16688	(a) revised	41106
Petitions granted in part	17631	0.247 Amended	12615
Petition for clarification granted	18792	0.284 (a)(7), (8), (9), and (10) amended	12615
Rates of return; eff. 10-17-86	32920	0.291 (b)(1) and (2) amended; (b)(3) added	13230
Petition denied	44478	0.303 Amended	12615
0.5 (a)(2) amended	12615	0.314 (e)(3) added; (o) removed	20290
0.21 (i) amended	12615	(e)(1) and (o) amended; eff. 10-2-86	31304
0.31-0.32 Undesignated center heading revised	12615	0.332 (g), (h), and (j) amended	12615
0.31 Introductory text and (a) revised	12615	(i) added	20290
0.32 Revised	12615	0.408 (b) table amended (OMB numbers)	12157, 34619
0.41 Amended	12615	0.411 (b)(2) revised	7444
0.91 (i) amended	12615	0.415 (b) amended; eff. 10-2-86	31304
0.131 (d) amended	12615	0.416 Revised	7444, 45889
(g) added; eff. 10-22-86	14995	0.431 Amended	12615
0.186 (b)(3) amended; (b)(10) removed; (b) (11) through (14) redesignated as (b) (10) through (13)	12615	0.432 Removed	32088
0.211 (d) revised	23550	0.433 Amended	12615
0.231 (f) revised	23550	0.434 (a)(3) removed	32088
(j) added	25527	0.445 (b), (c), and (d) revised	7444
0.241-0.247 Undesignated center heading revised	12615, 41106	(a), (b), (d), (e), and (f) revised	45889
0.241 Heading and introductory text revised	12615	0.455 (a) amended	12616
Revised	41106	0.457 (d)(2) introductory text amended; eff. 10-2-86	31304

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

51 FR
Page

Chapter I—Continued

0.465 (a) introductory text and (d)(3) amended; (c)(1), (2), (3), and (4) redesignated as (e), (c)(1), (2), and (3); (a) Note, (b), new (c)(1), and (d)(1) revised; new (c)(3) amended; (d)(4) added.....	34982
0.487 Removed; eff. 10–2–86.....	31304
1 Decision.....	17969
1.4 (b) clarification	23059
1.14 Revised.....	45890
1.21 (c) amended.....	12616
1.49 (b), (c), and (d) revised.....	16322
1.201 (b) Note revised.....	32088
1.221 (b) revised.....	19347
1.223 (b) and (c) revised.....	19347
1.229 (b) revised.....	19347
1.412 (a)(1) revised	7445
1.420 (h) added.....	15629
(g) revised.....	20291
1.430 Revised.....	7445
1.713 Amended	16039
1.716 Revised	16039
1.717 Revised	16039
1.718 Revised	16040
1.741 Nomenclature change; eff. 10–2–86.....	31304
1.761 Nomenclature change; eff. 10–2–86.....	31304
1.912 (b) added; eff. 10–22–86.....	14995
1.924 (b)(2)(ii) revised.....	2703
Effective date corrected.....	4596
1.925 (a) revised; eff. 10–2–86.....	31304
1.926 (a)(2) amended; eff. 10–2–86.....	31304
1.951 (a)(2) revised; eff. 10–2–86.....	31304
1.953 (b) removed.....	2703
Effective date corrected.....	4596
1.962 (g) revised	2703
Effective date corrected.....	4596
1.972 (a)(1) and (c) amended; eff. 10–2–86.....	31304
1.1205 (e) amended.....	12616
1.1209 (f) amended	12616
1.1301 Revised.....	15000
1.1302 Added	15000
1.1303 Revised.....	15000
1.1304 Added	15000
1.1305 Revised.....	15000
1.1306 Added	15000
Note 3 correctly added.....	18889
1.1307 Added	15000
1.1308 Added	15001
(d) corrected	18889

47 CFR—Continued

51 FR
Page

Chapter I—Continued

1.1309 Added	15001
1.1311 Added	15001
(b) correctly added	18889
1.1312 Added	15002
1.1313 Revised.....	15002
1.1314 Added	15002
1.1315 Revised.....	15002
1.1317 Revised.....	15003
1.1319 Revised.....	15003
2 Authority citation revised	39534
2.1 Amended	37399
2.106 Table amended.....	4167, 37399
Table corrected; Footnote US308 correctly revised	39662
Table amended; footnote NG66 revised	4361
Footnote US81 amended	12616
Petitions granted in part; clarification.....	16847
Table amended; eff. 10–2–86	31304
2.933 (a) revised.....	39535
2.936 (b) and (c) revised.....	39535
2.939 (a)(1) revised.....	39535
2.941 (a) amended	12616
2.947 (a)(1) amended	12616
2.967 (c) revised.....	39535
2.977 (c)(1) revised	2706
(d) added.....	41628
Effective date corrected	44478
2.983 (j) revised.....	2706
2.995 (a)(2) amended; eff. 10–2–86.....	31304
2.1001 (g) revised.....	2707
(d) revised; authority citation removed.....	39535
(l) added.....	41628
Effective date corrected	44478
2.1035 (a) and (c)(1) revised.....	39535
13.61 Amended; eff. 10–2–86.....	31305
15 Authority citation re-vised.....	4366, 39535
15.38 Note amended.....	12616
15.46 (a) and (b) revised; authority citation removed.....	39535
15.48 (a), (b), and (c) introductory text and (1) revised.....	39535
15.63 (a) introductory text re-vised.....	37400
15.69 (a) revised.....	37400
15.72 (b) introductory text re-vised.....	37400
15.79 Introductory text re-vised.....	37400
15.111 Nomenclature change.....	4366
15.113 Nomenclature change.....	4366

List of CFR Sections Affected

47 CFR—Continued

51 FR
Page

Chapter I—Continued	
15.114 Redesignated as 15.115; new	
15.114 added	4366
15.115 Removed; new 15.115 redesignated from 15.114	4366
15.132 (d) added	4366
15.141 (a) revised; (d) added	4366
15.142 Table revised	4366
15.143 (a) revised	39535
15.305 (c) revised	4366
15.321 Removed	4366
15.323 Removed	4366
15.801—15.840 (Subpart J) Clarification	30362
18 Authority citation revised	43745
18.121 Added	43745
18.205 (c) Note amended	12616
18.213 Introductory text revised	17970
18.305 (b) and Notes 1 and 2 revised	17970
18.309 (a) revised	17971
19 Authority citation revised	37022
19.735–204 (e)(3) revised	37022

1987

47 CFR

52 FR
Page

Chapter I	
Chapter I Motions granted and denied	
Policy statement	2226
Determination	16386
Adjudication ruling	27348
0.5 (a)(13) and (b)(7) revised; (a)(14) and (b)(8) added	31768
0.11 (b) revised	42438
0.15–0.16 Undesignated center heading revised	10227
0.15 Introductory text revised; (j) removed	42438
0.16 Revised	42438
0.17 Undesignated center heading and section added	42438
0.231 (c) revised; (h) removed; (i) redesignated as (h)	5288
(k) added; authority citation amended	12383
0.284 (a)(3) removed; (a) (4) through (11) redesignated as (a) (3) through (10)	5288
0.291 (b) (2) and (3) amended; (b)(4) added; eff. 11–12–87	35918
0.332 (c) removed; (d) through (j) redesignated as (c) through (i)	5288

47 CFR—Continued

52 FR
Page

Chapter I—Continued	
0.401 Revised	10227
0.403 Revised	10228
0.406 (b)(2) revised	5288
0.408 (b) table amended (OMB numbers)	35918
0.453 (d) revised; (e) through (l) added	38764
0.455 (a)(3) revised	10228
(b)(1) revised	21685
Revised	38765
(b)(2) corrected	40020
0.465 (d)(3) revised	36477, 36774
0.482 Revised	10229
1.4 (c) and (d) revised	10229
Revised	49159
1.80 (h) revised	5288
1.87 Revised	22654
1.221 (f), (g), and Note added	5288
1.227 (b)(4) revised	10229
1.415 (d) Note amended	37460
1.420 (h) Note added	8260
Effective date corrected	11473
Heading, (a) and (b) revised	25866
1.429 (e) and (f) revised	49161
1.742 Revised	5289
Revised	10229
1.762 Revised	5289
1.764 (a) revised	5289
1.766 (a) revised	5289
1.767 (a) revised	5289
1.772 Revised	5289
1.773 (a)(1)(iii) added; eff. 1–1–88	26682
1.786 Revised	1630
1.795 Added	274
1.912 (b), (d), and (e) revised	10229
1.931 (a) revised	10229
1.959 Revised	10230
1.1101–1.1116 (Subpart G) Revised	5289
1.1108 (b)(1) introductory text, (i) through (iv), (2), and (3) correctly designated	38232
1.1109 Revised	10230
1.1200–1.1216 (Subpart H) Revised	21052
Table of Contents corrected	37459
1.1202 (c) Note added; (d) amended; (f) (i), (ii), and (iii) correctly designated as (f) (1), (2), and (3); new (f)(1) revised	37459
1.1203 (c) and Note following (c) added	37459
1.1204 (a)(3) Note and (6) and (b)(7) Note amended	37460

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

52 FR
Page

Chapter I—Continued

1.1206 (a)(3) Note and (5) and (b)(10) and Note following (b)(10) added.....	37460
1.1208 (c)(1) (i), (ii), and (iii) and (4) redesignated as (c)(1)(ii) (A), (B), and (C) and (5); (c)(1)(iv) introductory text, (A), (B), and (C) redesignated as (c)(1)(i) introductory text, (A), (B), and (C); new (c)(1)(i) introductory text revised; new (c)(1)(ii) introductory text and (D) and (4) added; new (c)(1)(ii)(A) amended.....	37460
(c)(1)(iv) introductory text correctly redesignated as (c)(1)(i) introductory text; (c)(1)(ii)(D) correctly designated.....	38042
1.1210 Undesignated center heading and section amended.....	37460
1.1212 (h) added.....	37460
1.1307 (b) Note revised.....	13241
1.1402 (d) and (e) revised (effective date pending).....	31770
1.1404 (a), (d) (1) and (2), (g) (2), (4), (5), (9) and (10), (h) and (i) revised (effective date pending).....	31770
1.1409 (b) revised (effective date pending).....	31770
1.1502 Revised.....	11653
1.1503 (a) revised.....	11653
1.1504 (b) (1), (2), and (5), (c) and (f) revised.....	11653
1.1505 (a) revised.....	11653
1.1511 (b) revised.....	11653
1.1526 (a) revised.....	11653
1.1801—1.1870 (Subpart N) Added.....	16258
1 Appendix B removed.....	5294
2 Extension of time for oppositions and replies.....	1458
2.1 Petition comment time extended.....	4016
(c) amended.....	7417
2.106 Table corrected.....	417
Table amended; Footnote G105 removed.....	1331
Petition comment time extended.....	4016
Table amended; Footnote NG149 added.....	6154
Table amended.....	7139
Table amended; Footnote NG148 added.....	7417

47 CFR—Continued

52 FR
Page

Chapter I—Continued

Footnotes US7 and US228 amended.....	8906
Footnote NG149 correctly designated.....	20087
Footnote US234 removed.....	21686
Petitions denied.....	43588
Footnote US308 revised.....	44986
2.901—2.1065 (Subpart J) Authority citation revised.....	21687
2.909 (f) added.....	5294
2.925 (b)(4) added; authority citation removed.....	21687
2.926 (e) revised; authority citation removed.....	21687
2.983 (j) revised.....	10570
(j) correctly revised.....	15725
15 Extension of time for oppositions and replies.....	1458
Authority citation revised.....	22460
15.4 (j)(2) revised.....	9297
(u) revised.....	22460
15.45 (e) amended.....	37618
15.63 Petition comment time extended.....	4016
15.64 Added.....	45962
15.69 Petition comment time extended.....	4016
(b) table amended.....	21687
15.72 Petition comment time extended.....	4016
15.79 Petition comment time extended.....	4016
15.305 (d) revised.....	9297
15.310 Revised.....	9297
15.312 (b) revised; (c) added.....	9298
15.324 (b) and (c) revised; (d) removed; (e) redesignated as (d); new (e) added.....	9298
(b) corrected.....	13241
15.602 (b) revised; (c) added.....	22460
15.606 (c) added.....	22460
Heading revised; (d) added.....	45962
15.616 (a) and (c) text revised; (d) added.....	22460
Heading revised; (e) added.....	45963
15.618 Heading and (c) revised.....	22460
15.622 Existing text designated as (a); (b) added.....	45963
15.623 Added.....	22460
18.305 (b) table amended.....	43198
18.307 Notes revised.....	43198
19.735–202 (b)(2) revised; (b)(5) added.....	7578

List of CFR Sections Affected

1988		47 CFR—Continued	
47 CFR	53 FR Page		53 FR Page
Chapter I		Chapter I—Continued	
Chapter I Order	502	0.467 Removed; new 0.467 redesignated from 0.466 and new (a) through (e) revised, new (h) and (j) removed, new (i) redesignated as (h)	39093
Policy statements	13270, 15557	0.468—0.470 Added	39094
0 Petition granted	11849	1 Recommendations	17039
Authority citation revised	29054	1.4 (b)(1) Example 3, (d) Examples 10 and 11, and (h) Example 13 corrected; (b)(4) Example 7 correctly revised	44196
0.1 Revised	29054	1.47 (b) amended	11852
0.5 (b) revised	29054	1.713 Removed	11852
0.6 Removed	29054	1.720 Added	11852
0.11 (b) revised	29054	1.721 Revised	11853
0.11 (a)(10) revised	47536	1.722 Revised	11853
0.12 Removed	29054	1.723 Revised	11853
0.16 Removed	29054	1.724 Revised	11853
0.32 Removed	29054	1.725 Revised	11854
0.42 Removed	29054	1.726 Revised	11854
0.62 Removed	29054	1.727 Revised	11854
0.91 (l) added	47536	1.728 Revised	11854
0.92 Removed	29054	1.729 Revised	11854
0.112 Removed	29054	1.730 Revised	11854
0.121 Revised	29054	1.731 Revised	11855
0.132 Removed	29055	1.732 Revised	11855
0.152 Removed	29055	1.733 Revised	11855
0.176 Removed	29055	1.734 Revised	11855
0.183 Revised	29055	1.735 Removed	11855
0.186 Revised	29055	1.743 (b) revised	17193
0.231 (l) added	29055	1.786 Removed	44197
0.284 (a)(4) revised	29055	1.823 (a) amended	52425
0.314 (g) revised	29055	1.962 (a)(5) revised	28940
0.314 (g) revised	47536	1.1102 Revised	40886
0.335 Added	1023	1.1103 Revised	40887
0.381—0.387 Undesignated center heading revised	29055	1.1104 Revised	40887
0.383 Heading and (a) revised	29055	1.1105 Revised	40887
0.387 (a) revised	29055	1.1107 (b) revised	40888
0.401 (b)(2) (i) and (ii) revised; (b)(2) (iii) and (iv) added	18564	1.1108 (b)(4) and (d) added	40888
0.401 (b)(1)(iii) added	40886	1.1111 (b) and (c) added	40889
0.408 (b) table amended (OMB numbers)	5184	1.1112 (a) and (e) revised	40889
(b) table corrected (OMB numbers)	6916	1.1114 (a) revised	40889
0.409 Added	27861	1.1116 Existing text designated as (a); (b) added	40889
0.434 Heading, introductory text, (a), (b), (e), and (f) revised	4412	1.1202 (a) Note added	26597
0.460 (e) revised	39093	1.1203 (c) correctly revised	44196
0.461 (b)(2) revised; (f)(6) added	39093	1.1204 (a) introductory text, (1), and (3) amended; (a)(3) Note redesignated as (a)(2) Note and amended; (a) (7) through (11) and Note added	26597
0.465 (a), note, and (c)(2) revised; (c)(4) and (f) added	39093	1.1306 (b) (1) and (2) and Note 1 revised	28393
0.466 Redesignated as 0.467 and new (a) through (e) revised, new (h) and (j) removed, new (i) redesignated as (h); new 0.466 added	39093	Technical correction	32394, 34538
		1.1307 (b) Note revised; eff. 11-17-88	28224

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

53 FR
Page

Chapter I—Continued	
(a) (3), (4), (5), and (6) redesignated as (a) (4), (6), (7), and (8) and revised; new (a) (3) and (5) added	28393
Technical correction	32394, 34538
1.1307 (b) Note correctly revised	41169
1.1308 (b) Note added; (c) and (d) revised	28394
Technical correction	32394, 34538
1.1311 (a)(6) added	28394
Technical correction	32394, 34538
1.1314 (d) Note removed	28394
Technical correction	32394, 34538
2.106 Table amended; Footnote NG31 added	3211
Petition for reconsideration extension of time	4624
Comment time extended	8459
Table amended; Footnotes NG133 and 569 removed	10879
Footnote NG120 revised	11856
Table amended	36288
Footnote 649 revised; eff. 10–24–88	37307
2.106 Table amended; footnote NG151 added	52175
2.901–2.1065 (Subpart J) Clarification	5980
13.12 (b) (2) and (3) revised	46454
15 Authority citation revised	11862,
15 Authority citation revised	46616
28226	
15.4 (w) added	28226
15.4 (u) revised; (x) added	46616
15.64 Effective date deferred	3894
Revised	28226
15.122 (a) Note revised	11862
15.184 Introductory text revised	11862
15.201–15.215 Authority citation removed	11862
15.205 (a) Note removed; (a) introductory text and (b) Note revised; (a) (1) and (2) and (f) added	11862
15.231 Heading revised; section amended	1782
Technical correction	32051
15.232 Heading revised; section amended	1782
Technical correction	32051
15.233 (a), (b), and (d) amended	1782
Technical correction	32051

47 CFR—Continued

53 FR
Page

Chapter I—Continued	
15.602–15.650 (Subpart H) Revised	46616
15.606 Effective date deferred	3894
(d) revised	28226
15.616 Effective date deferred	3894
Heading and (e) revised	28226
15.622 Effective date deferred	3894
(b) revised	28226
15.628 Added	28226
19.735–202 (a)(5) and (b) Note added; (b)(2) amended	28227

1989

47 CFR

54 FR
Page

Chapter I	
Chapter I Petition granted in part	
Aeronautical Services via Inmarsat system provisions	33224
0.5 (a) revised	15194
0.11 Effective date corrected	152
0.13 Undesignated heading and section added	15194
0.91 (l) and effective date corrected	152
0.181 Reserved undesignated center heading removed	15195
0.231 (h) revised	15195
0.314 Effective date corrected	152
0.331 (a)(1) revised	1177
0.387 Heading revised	15195
0.401 (a)(5) added	12453
0.408 (b) amended; OMB numbers	3038
(b) table amended (OMB numbers)	35650
1 Inquiry	19373
Clarification of effective date	39182
Policy statement	43062
1.13 Added	12453
1.45 Introductory text republished; (a) and (b) revised	31032
(d) amended	37682
1.49 (e) added	31032
1.51 (b) revised	29037
(c) (1) and (2) revised	31032
1.115 (d) and (f) revised	40392
1.419 (b) revised	29037
1.420 (h) note revised	16366
(i) added	26201
1.773 (a)(1)(iv) added	19840
1.922 Table amended	50238

List of CFR Sections Affected

47 CFR—Continued

54 FR
Page

Chapter I—Continued	
1.925 (i) redesignated as (j); new (i) added.....	50238
(i) correctly redesignated as (j)	51550
1.958 (a)(4) revised.....	38995
1.962 (a)(1) revised; (i) added	10327
Effective date corrected	24905
1.1202 (b) concluding text re-vised.....	29038
1.1203 (b) amended	29038
1.1204 (b)(5) amended.....	29038
1.1206 (a) (1), (2), and (3) Note 1 revised; (a)(3) Note 2 and (4) Notes 1 and 2 added.....	29038
1.1307 (b) Note revised.....	1178
(b) Note correctly revised	30548
1.1901—1.1952 (Subpart O) Added	403
2 Authority citation revised.....	1698
Petition denied	33898, 34995
2.1 (c) amended	49980
2.104 (c)(3) revised	49981
2.106 Table amended; footnote US310 added	9996
Table amended; footnote US311 added	17710
Table amended	25460, 30041
Table amended; footnote US312 added	43294
Waiver granted	41974
Table, International footnotes, and US footnotes amended; footnotes 458, 473, 583, 590, 680, 681, 698, 699, 728, 774, 775, 776, US39, US232, US241, US248, US280, and US288 removed	49981
2.302 Table amended	50239
2.801—2.815 (Subpart I) Authority citation removed	1698
2.801 (b) revised.....	17711
2.805 Revised	17711
2.806 Revised	17712
2.901—2.1065 (Subpart J) Authority citation removed	1698
2.909 Redesignated as 2.911; new 2.909 added	17712
2.910 Added	1698
Redesignated as 2.913	17712
2.911 Redesignated from 2.909	17712
2.913 Redesignated from 2.910	17712
2.924 Added	1698
2.925 (a) and (b)(1) revised	1698
2.926 (a) through (d) revised	1698
2.929 (b)(3) removed	1699
2.934 Revised	1699

47 CFR—Continued

54 FR
Page

Chapter I—Continued	
2.946 Added	1699
2.948 Added	17712
2.954 Revised	1699
2.955 (a) (3) and (4) added	17713
2.975 (a)(5) revised; (a)(7), (f), and (g) added	17713
2.1033 (b) and (c) revised	17713
2.1035 Removed	1699
2.1043 (b) and (d) revised.....	1699
(a) and (c) revised; (b)(3) added	17714
(b) introductory text and (3) re-published; (b) (1) and (2) cor-rectly added.....	32339
2.1201—2.1219 (Subpart K) Au-thority citation removed	1698
2.1201 (c) added.....	17714
2.1300 Revised	1699
15 Petition denied	9996
Revised	17714
Compliance clarification	46729
15.37 Correctly revised.....	32339
15.113 (f) correctly revised.....	32339
15.115 (b)(3) note correctly added.....	32339
15.209 (a) correctly revised	32339
15.231 (b) (2) and (3) correctly re-vised.....	32340
15.233 (b), (d), and (e) correctly revised	32340
15.239 (d) introductory text cor-rectly revised	32340
15.251 (f) correctly revised.....	32340
19.735—105 (a)(1) revised	15195
19.735—107 (c) redesignated as (d); new (c) added	15195
19.735—410 Revised	15195

1990

47 CFR

55 FR
Page

Chapter I	
Chapter I Policy decision.....	39275
0.5 (a)(13) revised.....	1676
(d) amended.....	6797
0.51 Undesignated center heading and section added	1676
0.291 (b) revised.....	30461
0.401 Introductory text and (b) re-vised.....	19154
0.408 (b) table amended (OMB numbers).....	39277
0.459 9g) revised.....	8951
0.461 (h)(1), (4), and (i) re-vised	8951

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

55 FR
Page

Chapter I—Continued	
(g) introductory text revised	9445
0.482 Revised	19154
1 Policy statement	23082
1.17 Added	23084
1.65 (c) added	23084
1.80 (a)(4) amended; (b)(1), (2), and (j) revised; (b)(3) redesignated as (b)(4); new (b)(3) added	25605
1.115 (e)(1) amended	36641
1.221 (f), (g), and note revised	19154
1.227 (b)(4) revised	9728, 46008
Technical correction	12360
(b)(4) effective date corrected	46514
1.245 (b)(3), (4), (5) and (6) revised	36641
1.301 (a)(3) added	36641
1.420 (j) added; eff. 10–04–90	28914
1.791 Revised	30461
1.792 Removed	30461
1.801 Removed	30461
1.804 Removed	30461
1.812 Removed	30461
1.931 (a) revised	19154
1.962 (i) removed	10462
1.1101–1.1117 (Subpart G) Authority citation revised	19155
1.1101 Revised	19155
1.1102 Revised	19155
1.1103 Revised	19157
1.1104 Revised	19158
1.1105 Revised	19162
1.1107 (a) and (b) revised	19171
1.1108 (b) revised; (c) and (d) redesignated as (e) and (f); new (c) and (d) added	19171
1.1109 Revised	19171
1.1110 (a) introductory text and (b) introductory text revised; (c) added	19171
1.1112 (b) and (d) revised	19172
1.1113 (a) revised	19172
1.1114 (a)(2) revised	19172
1.1115 (c)(1) and (2) removed; new (e) added	19172
(e) correctly designated	38065
1.1117 Added	19172
1.1303 Revised	20396
1.1307 (b) note removed; (b) notes 1, 2, and 3 added	2381
(b) Note 1 revised	46008
(b) Note 1 effective date corrected	46514

47 CFR—Continued

55 FR
Page

Chapter I—Continued	
(b) Note 1 revised	50692
1.1312 Revised	20396
2.1 (c) amended	28761
2.106 Footnote US276 revised	4175
Table amended; footnote US316 added	6393
Table corrected; footnote US316 correctly designated	11195
Table amended	25841
Footnote US244 revised	28627
2.1033 (b)(11) amended	28762
5.51 (c) added	20396
5.53 (b) revised	19172
13 Memorandum and order	7898
15 Reconsideration petition	7494, 13907, 14285, 50181, 52172
Authority citation revised	28762
15.3 (q) revised	18340
15.37 (d) added	25095
15.203 Amended	28762
15.205 (b) and (c) revised; (e) added	46791
15.209 (g) revised	18340
15.229 (b) and (c) redesignated as (c) and (d); new (b) added	33910
15.245 (b) revised	46792
15.247 (a)(1), (b), and (c) revised; (d), (e), and (f) added	28762
15.249 (e) added	25095

1991

47 CFR

56 FR
Page

Chapter I	
Chapter I Order	964
Interpretation	1931
Policy statements	56937
0 Authority citation revised	36730
0.91 (m) added	36731
0.251 (f)(12) added	792
0.331 (a)(1) amended	6583
Designation corrected	9752, 43649
0.341 (d) and (e) added	792
0.401 (a)(3)(i) revised	64714
0.408 (b) table amended (OMB numbers)	49417
0.481 Revised	64714
0.482 Amended	64714
0.491 Revised	64714
1 Policy statement	37665
Authority citation revised	57598
1.4 (b) introductory text note removed; (b)(1) through (5) amended; eff. 10–15–91	40567

List of CFR Sections Affected

47 CFR—Continued

56 FR
Page

Chapter I—Continued

(c), (d) and (g) through (j) amended; eff. 10–15–91	40568
1.18 Added	51178
1.65 (c) revised	25635
(c) suspended	44009
1.80 (g)(3) added	25638
1.221 (f), (g), and Note removed; (c)(1) added	792
(c)(1) removed; (f) and (g) added	25638
1.229 (a) and (b) revised; (e) and (f) added	792
(e) revised	25639
1.244 Added	793
1.248 (d)(4) added	793
1.277 (c) revised	793
1.311 (c) revised	794
1.313 Introductory text re- vised	794
1.315 (e) added	794
1.325 (a) revised; (c) added	794
(c) introductory text, (1) intro- ductory text, (2) introductory text and (3) revised	25639
1.402 Added	24013
1.403 Revised	24014
1.823 (b)(3) added	58506
1.824 Heading, (a) and (b) re- vised	57815
1.912 (a), (b)(1) and (e) amended; (b)(3) and (d) revised	64714
1.922 Table amended	64715
1.926 (a)(2) revised	64715
(c) added	65858
1.931 (a) amended	64715
1.962 (g) amended	64715
1.1101–1.1117 (Subpart G) Au- thority citation removed	57598
1.1102 Amended	19599
Table amended	56602, 65858
Amended	63662, 64715
1.1105 Amended	57598
Amended	63663
1.1111 (c) revised	795
(b) and (c) introductory text through (5) redesignated as (a)(6) and (b) introductory text through (5); new (b) intro- ductory text, (3) and (4) re- vised; new (c) added	56602
1.1112 (g) added	56602
1.1306 (b) Note 1 revised	13414
1.1307 Regulation at 55 FR 50692 suspended to 6–1–91	23024
1.1312 (d) redesignated as (e) and revised; new (d) added	13414

47 CFR—Continued

56 FR
Page

Chapter I—Continued

2 Memorandum and order	6991
Authority citation revised	26619
2.1 (c) amended	42703
2.106 Table amended	3782, 9883
Table amended	42703
Table amended	51656
Footnote NG47 revised	57815
Table amended (effective date pending)	64855
2.806 (c)(2) revised	13082
2.995 (a)(2) revised	11682
2.1201 (b) Note and (c) removed; (b) revised	26619
Regulation at 56 FR 26619 com- ment period extended to 10–24– 91	51178
2.1202 Revised	26619
Regulation at 56 FR 26619 com- ment period extended to 10–24– 91	51178
2.1203 Revised	26619
(d) corrected	32474
Regulation at 56 FR 26619 com- ment period extended to 10–24– 91	51178
2.1204 Added	26619
Regulation at 56 FR 26619 com- ment period extended to 10–24– 91	51178
2.1205 Revised	26619
Regulation at 56 FR 26619 com- ment period extended to 10–24– 91	51178
2.1207 Revised	26620
Regulation at 56 FR 26620 com- ment period extended to 10–24– 91	51178
2.1209 Removed	26620
Regulation at 56 FR 26620 com- ment period extended to 10–24– 91	51178
2.1211 Removed	26620
Regulation at 56 FR 26620 com- ment period extended to 10–24– 91	51178
2.1213 Removed	26620
Regulation at 56 FR 26620 com- ment period extended to 10–24– 91	51178
2.1215 Removed	26620
Regulation at 56 FR 26620 com- ment period extended to 10–24– 91	51178
2.1219 Removed	26620

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

56 FR
Page

Chapter I—Continued	
Regulation at 56 FR 26620 comment period extended to 10–24–91	51178
2.1501–2.1517 (Subpart N) Added	11683
5.207 Added	24014
13.5 (d) added	56602
15 Reconsideration of petitions	48442, 57823
15.31 (f)(1) and (3) revised; (p) added	13083
15.35 Heading revised	13038
15.37 (e) added	3785
15.109 (e) revised	373
15.119 Added	27201
15.205 (a) table amended	6288
15.207 (b) revised	373
15.214 Added	3785
15.221 Revised	373
15.233 (h) through (k) removed; new(h) added	3785
(b) and (d) revised; (e) republished	5659

1992

47 CFR

57 FR
Page

Chapter I	
Chapter I Memorandum Opinion	
and Order	6481
Order	33275
0.231 (h) revised	38444
0.241 (a)(8) revised	18088
0.243 Removed	18088
0.251 (f)(12) revised	19387
0.283 (c)(3) revised	18088
0.291 (h) revised	8579
(f) revised	18088
(f) correctly revised	22181
0.311 (d) revised	18088
0.331 (a)(9) revised	18089
0.408 (b) table amended (OMB numbers)	45747
(c) table added (OMB numbers)	45748
1 Authority citation revised	187
Order	3133
Policy statements	24986
Technical correction	43406
1.18 Existing text designated as (a); (b) added	32181
1.23 (a) revised	38285
1.24 (b) revised; (c) added	38285
1.65 (c) revised	47412

47 CFR—Continued

57 FR
Page

Chapter I—Continued	
Regulation at 57 FR 47412 effective date corrected to 1–14–93	49218
1.80 (h) revised	23161
(d) introductory text revised	47006
(f)(2) amended	48333
1.115 (e)(1) amended	19387
1.402 Revised	7882
1.403 Revised	7882
1.790 Revised	8579
1.926 (a)(1) revised	8274
1.951 (a) revised; (c) removed; (d) redesignated as (c)	8274
1.952 (b) amended	8274
1.972 (a)(1) amended; (c) revised	8274
1.1102 Amended	8275
1.1104 Amended	23160
1.1105 Amended	23161
1.2001–1.2003 (Subpart P) Added	187
1.2003 Amended	48333
2 Authority citation revised	38286
2.106 Table amended; Footnote US317 added	8275
Regulation at 56 FR 64855 eff. 4–19–92	11689
Technical Correction	43290
2.106 Table amended	49021, 60133
2.948 (b)(8) revised	24990
2.1201 (c) added	38286
2.1204 (a)(3) and (4) revised	38286
5.207 Revised	7882
13.2 (b)(7) added	9065
13.21 (a)(7) added	9065
13.22 (b)(6) added	9065
15.3 (f) amended	33448
15.31 (a) revised	24990
(h) amended	33448
15.107 (c) revised	33448
15.115 (b)(3) revised	33448
15.119 (a) note added; (f)(1)(iii) and (3)(ii) removed; (f)(1)(iv) through (xi) and (3)(ii) through (v) redesignated as (f)(1)(iii) through (x) and (3)(i) through (iv) (d), (i)(4) and (5) table amended, (e)(1)(i), (ii), (f) introductory text, (1)(iii), (x), (2)(i), (ii), (iii), (3)(iii), (h)(1) introductory text, (l) and (n)(6) revised	19094
15.205 (a) revised	13048
15.207 (b) revised	33448

List of CFR Sections Affected

47 CFR—Continued

Chapter I—Continued
15.237 Heading revised 13048

1993

47 CFR

	58 FR Page
Chapter I	
Chapter I Memorandum opinion and order	14161
Waiver	63086
0.61 (j) through (n) added	29752
Regulation at 58 FR 29752 effec- tive date delayed to 10-1-93	33560
Regulation at 58 FR 29752 and 33560 effective date corrected to 9-1-93.....	41042
Regulation at 58 FR 29752 and 33560 effective date pending	43816
0.111 (b) through (l) redesignated as (d) through (n); new (b) and new (c) added; introductory text, (a) and new (d) re- vised.....	13020
0.131 (h) and (i) added	9124
(j) added.....	13020
(k) added.....	30717
0.311 (a)(1) revised.....	13020
(f) added.....	68053
0.314 (a), (d), (f), (p), (q), (r), (v) and (w) removed.....	13020
0.331 (a)(1) revised; (c) added.....	13020
(d) added.....	30717
0.401 (a)(3)(i) and (b)(1) re- vised.....	13020
0.406 (b) introductory text amended.....	13021
0.408 (b) and (c) tables amended (OMB numbers)	55023
0.453 (l) revised	13021
Introductory text, (d), (g) and (l) revised	19772
0.455 (d) removed.....	13021
(a)(11) and (12) added.....	29752
Regulation at 58 FR 29752 effec- tive date delayed to 10-1-93	33560
Regulation at 58 FR 29752 and 33560 effective date corrected to 9-1-93.....	41042

47 CFR—Continued

	58 FR Page
Chapter I—Continued	
Regulation at 58 FR 29752 and 33560 effective date pending	43816
0.484 Revised	13021
0.485 Revised	9124
0.486 Added	30717
0.561 (f) and (g) added.....	11549
1 Reconsideration petition	14328, 37867
Authority citation revised	27473
Policy statements	44767
1.4 (g) introductory text re- vised.....	17529
1.19 Added	44893
1.49 (a) amended.....	44893, 63087
1.61 (a), (b), (c) and (f) re- vised.....	13021
1.80 (a) introductory text, (3), (4), concluding text, (c)(1) and (h) revised	6896
(d) amended	27473
1.83 (b) revised	13021
1.85 Amended.....	13021
1.420 (g) Note 1 added; (h) note redesignated as Note 2.....	38535
1.423 Revised	66300
1.720 (i) added.....	25572
1.724 (e) added	25572
1.726 Revised	25572
1.727 (e) revised; (f) added	25572
1.729 (a) and (d) revised; (c) amended; (e) added.....	25572
1.730 (c) revised; (d) added.....	25572
1.731 Redesignated as 1.732; new 1.731 added	25573
1.732 Redesignated as 1.733; new 1.732 redesignated from 1.731; (a) amended; (b) redesignated as (g); (b) through (f) added.....	25573
1.733 Redesignated as 1.734; new 1.733 redesignated from 1.732; (a)(5) and (b) revised; (c) and (d) redesignated as (d) and (e); new (c) added	25573
1.734 Redesignated as 1.735; new 1.734 redesignated from 1.733.....	25573
1.735 Redesignated from 1.734	25573
(b) revised.....	25574

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

58 FR
Page

Chapter I—Continued

1.773 (a)(1)(i) and (2) introductory text amended; (a)(2)(i), (ii) and (iii) redesignated as (a)(2)(ii), (iii) and (iv), (b)(1)(i) through (iv) redesignated as (b)(1)(ii) through (v) and (c) redesignated as (b)(3); (a)(2)(i), (4) and (b)(1)(i) added; (a)(1) introductory text, new (2)(ii), (iii), (iv), new (b)(1)(ii) through (v), (b)(2) and new (3) revised	17529
(a)(4) and (b)(3) revised	51247
1.785 (a) revised; eff. 10–4–93	36143
1.793 Removed; eff. 10–4–93	36143
1.794 Removed; eff. 10–4–93	36143
1.815 (c) added	42249
1.901 Revised	13021
1.912 (a) revised	30717
1.913 (a) revised; (e) added	21406
1.1102 Table amended	68541
1.1103 Table amended	9129
1.1104 Table amended	19772
1.1105 Table amended	9129, 19773
1.1117 (a) amended	68541
1.2002 (c) revised	8701
2.1 Amended	68058
2.106 Table amended	11796, 16361, 27949, 34921, 42684, 59176
Footnotes 723B, 726C, 726D, 730B, 730C and US315 added; Footnote 726 removed; Footnotes 724, 726A and 726B revised	34923
Footnotes 747–750 removed; Footnotes 735A, 740A, 746A, 746B, 746C, 747A, 750A and US331 added; Footnote NG 153 revised	59179
Footnotes 700A, 700B and US330 added	42685
Table amended; eff. 12–20–93	49222
2.948 (b)(8) revised	37430
(b)(2) amended	44893
2.975 (a)(8) added	25575
(a)(5) amended	44893
2.1033 (b)(12) added	25575
(b)(7) amended	44893
5 Reconsideration petition	14328
13 Revised	9124
13.7 (c)(2) correctly revised	12632
15.31 (a) revised	37430
(a)(6)(iii) note added	51249
15.37 (b) amended; (f) added	25575
15.107 (d) redesignated as (f); new (d) and (e) added	51249
15.109 (e) amended, (g) added	51249

47 CFR—Continued

58 FR
Page

Chapter I—Continued

15.119 (a) amended	44893
15.121 Added	25575
(a) corrected	29454
15.205 (a) revised	33774
15.207 (b) and (c) redesignated as (c) and (d), new (b) added	51249
15.301–15.323 (Subpart D) Added	59180
18.205 (b)(2) revised	44894

1994

47 CFR

59 FR
Page

Chapter I

Chapter Periodic review of regulations	3633
Report	35631
0 Technical correction	25825
0.5 (a)(14) added	32132
0.11 (a)(10) removed; (a)(11) and (12) redesignated as (a)(10) and (11)	26971
0.61 (a) revised; (h) and (j) through (n) removed; (i) redesignated as (h)	32132
(a) revised	38374
0.91 (n) added	26747
(l) revised	26971
Introductory text revised	38374
0.101 Added	32132
0.111 (o) added	26971
0.131 (k) removed	543
(k) added	24957
0.182 Heading revised	26971
Heading and (d) revised	67092
0.183 Revised	26971, 67092
0.185 Introductory text, (a) and (b) revised	26971
0.231 (a), (b) and (i) removed; (c) through (h), (j), (k) and (l) redesignated as (a) through (f), (g), (h) and (i)	26971
(a) revised	30998
(h) removed	39703
0.251 (a) added	39703
0.284 (a)(4) revised	26971
(a)(10) removed	32132
(a)(4) removed; (a)(5) through (10) redesignated as (a)(4) through (9)	67092
0.291 (j) added	66487
0.311 (g) and (h) revised	26971, 67092
0.321 Undesignated center heading and section added	32132
0.325 Added	32132

List of CFR Sections Affected

47 CFR—Continued

59 FR
Page

Chapter I—Continued	
0.331 (d) removed.....	543
0.332 (d) revised.....	26971
0.406 (b)(2) revised.....	30998
(b) table and (c) table amended (OMB numbers).....	50168
0.408 (b) table and (c) table amended (OMB numbers)	50168
0.453 (g) revised.....	38374
(a) introductory text, (1) and (4) revised; (a)(5) through (7) added	32132
0.455 (a) introductory text, (1) and (5) revised; (a)(6), (11) and (12) removed; (a)(7) through (10) re- designated as (a)(6) through (9); (d) added	32133
0.467 (a) redesignated in part as (a)(1) and (2); heading, (a) table and new (a)(2) revised	21946
0.486 Removed	543
1 Report and order.....	8413
Report	53363
Authority citation revised	22985
Technical correction	25825
1.7 Added.....	44340
1.49 (a) revised	37721
1.50 Revised.....	37721
1.402 (g) added.....	42528
1.420 Heading, (a) and (b) re- vised.....	59503
1.742 Revised	30998
Introductory text amended	59503
Corrected.....	64856
1.743 (a) revised; (e) added.....	59503
1.821 Introductory text re- vised.....	38375
1.821 Revised	59503
1.823 Heading, (b)(1), (2) heading and (3) heading revised	59503
(b)(2) removed.....	59949
1.901 Revised	59949
1.912 (a) revised.....	543
(e) redesignated as (f); new (e) added	24957
1.922 Table amended	24957
Revised	59949
1.924 (d) added	9101
(b)(2)(i) heading and (vi) revised; (b)(2)(vii) added	59949
1.925 (g) and (h) amended	59949
1.972 (a)(1) and (c) amended	24957
1.1102 Revised	31009
Table corrected	32489
1.1103 Revised.....	31014
1.1104 Revised.....	31015

47 CFR—Continued

59 FR
Page

Chapter I—Continued	
Amended (OMB number pend- ing).....	63051
1.1105 Revised.....	31018
Table amended	59504, 59950
1.1106 Redesignated as 1.1107	30998
New 1.1106 added	31029
1.1107 Redesignated as 1.1108; new 1.1107 redesignated from 1.1106 and amended.....	30998
1.1108 Redesignated as 1.1109; new 1.1108 redesignated from 1.1107; (a) through (d) revised.....	30998
1.1109 Redesignated as 1.1110; new 1.1109 redesignated from 1.1108	30998
(a), (d) and (f) revised	30999
1.1110 Redesignated as 1.1111; new 1.1110 redesignated from 1.1109	30998
(a) revised.....	30999
1.1111 Redesignated as 1.1112; new 1.1111 redesignated from 1.1110	30998
1.1112 Redesignated as 1.1113; new 1.1112 redesignated from 1.1111	30998
1.1113 Redesignated as 1.1114; new 1.1113 redesignated from 1.1112; introductory text, (d), (e) in- troductory text and (3) amend- ed	30998
1.1114 Redesignated as 1.1115; new 1.1114 redesignated from 1.1113; (a) amended	30998
1.1115 Redesignated as 1.1116; new 1.1115 redesignated from 1.1114; (a) amended	30998
1.1116 Redesignated as 1.1117; new 1.1116 redesignated from 1.1115; (e) amended	30998
Heading and (c) revised.....	30999
1.1117 Redesignated as 1.1118; new 1.1117 redesignated from 1.1116	30998
1.1118 Redesignated from 1.1117; (b) amended	30998
1.1151 Added	30999
1.1152 Added	31000
1.1153 Added	31000
1.1154 Added	31000
1.1155 Added	31001
1.1156 Added	31001
1.1157 Added	31001
1.1158 Added	31002
1.1159 Added	31002

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

	59 FR Page
Chapter I—Continued	
1.1160 Added	31002
1.1161 Added	31003
1.1162 Added	31003
1.1163 Added	31004
1.1164 Added	31004
1.1165 Added	31004
1.1166 Added	31005
1.1204 (b)(8) added	53759
1.2003 Amended (OMB number pending)	63051
1.2101—1.2111 (Subpart Q) Added	22985
Revised	44293
1.2105 (c) revised	64162
1.3000—1.3004 (Subpart R) Added	38128
2 Authority citation revised	32851
Petition reconsideration	37439
Memorandum opinion and order	61284
Reconsideration petition	66254
2.106 Table amended; Footnotes 731A through 731D, 753E, 877, 878, 890 and 891 removed; Foot- notes 733A, 733E, 734, 753, 753C, 882E, 882F, 882G and US-319 re- vised; Footnotes 731E, 731F, 753F, 881A and 881B added	9415
Table corrected	15266, 40835, 44456
Table amended; Footnotes US331 and NG153 revised	32851
Table amended; Footnotes 873 and 883 revised, footnotes 873A, 873B, 873C, 873D, 873E, 882A, 882B, 882C, and 882D added	40474
Table amended	55373, 60562
Table amended; Footnote US243 removed; Footnote 471 cor- rected	66253
5 Memorandum opinion and order	61284
11 Added	67092
13.9 (c) and (d) revised	3795
13.13 (c) revised	3795
13.201 (c) removed	3795
13.205 Removed	3795
15 Authority citation revised	25340
Petition reconsideration	37439, 66254
Comment request	42528
15.3 (aa) added	25340
15.19 (d) added	25341
15.115 (c)(1)(i) revised; (h) and (i) added	25341
15.117 (h) revised	25341

47 CFR—Continued

	59 FR Page
Chapter I—Continued	
15.118 Added	25341
15.301 Revised	32852
15.303 (g) and (j) revised	32852
15.307 (a) introductory text, (d) and (e) revised	32852
15.311 Revised	32852
15.319 (a) and (i) revised	32852
(a) corrected	40835
15.321 (a), (c)(5), (d) and (f) cor- rected	15269
Redesignated as 15.323; new 15.321 redesignated from 15.323	32852
(g) removed; heading, (a), (b), (c)(1), (4), (6), (d) and (e) re- vised	32853
(d) corrected	40835
15.323 (a) corrected	15269
Redesignated as 15.321; new 15.323 redesignated from 15.321	32852
Heading, (a), (b), (c)(1), (4), (6), (8), (d) and (f) revised; (c)(10), (11) and (12) added	32853
(c)(1), (5), (d) and (e) corrected	40835
(c)(1), (5) and (e) revised	55373
18.107 (j) added	39472
18.121 Revised	39472

1995

47 CFR

	60 FR Page
Chapter I	
0.5 (a)(13) revised	5323
(a)(12) revised	35504
0.11 (a)(11) removed	5323
0.21 (h) amended; (i) removed; (j) redesignated as (i)	5323
0.31 (b) revised; (f) amended	5323
0.41 (c) removed; (d) through (p) redesignated as (c) through (o); new (i) revised	5323
(f) amended; (j) removed; (k) through (o) redesignated as (j) through (n); (g), new (m) and new (n) revised	34901
0.51 Undesignated center heading and section revised	5323
(p) and (q) revised; (r) added	35504
0.61 (b) removed; (c) through (h) redesignated as (b) through (g)	5323
(a) revised; (h) added	35504

List of CFR Sections Affected

47 CFR—Continued

60 FR
Page

Chapter I—Continued	
0.91 Introductory text amended.....	5323
(b), (d) and (k) removed; (c), (e) through (j), (l), (m) and (n) redesignated as (b) through (k); new (i) revised.....	5324
Introductory text, (a), (c), (i) and (j) revised.....	35504
0.111 (e) revised.....	5324
0.131 (b) removed; (c) through (k) redesignated as (b) through (j).....	5324
Undesignated center heading and section revised.....	35505
0.241 (a)(6) removed; (a)(7), (8) and (9) redesignated as (a)(6), (7) and (8).....	5324
(f) added.....	32119
0.251 (b) revised; (c), (d) and (e) removed.....	34902
0.261 Undesignated center heading and section added.....	5324
(a)(4), (10), (b)(5) and (6) revised.....	35506
0.262 Added.....	5324
0.291 (d) removed; (e) through (i) redesignated as (d) through (h); new (d), new (g) and new (h) revised.....	5324
(a)(1), (d) and (e) revised; (h) removed; (j) redesignated as (h).....	35506
0.301 Removed.....	35506
0.302 Revised.....	35506
0.311 Undesignated center heading and (f) revised.....	31256
(f) revised.....	35506
(g) revised.....	55998
(f) amended.....	61662
0.321 (a)(7) added.....	35506
0.331 Undesignated center heading and section revised.....	35506
0.332 (b) removed; (c) through (i) redesignated as (b) through (h); new (f) revised.....	5325
Introductory text revised; (g) removed; (h) redesignated as (g).....	35507
0.333 Removed.....	35507
0.335 Removed.....	35507
0.337 Removed.....	35507
0.401 (b)(1) revised; (b)(2) amended.....	5325
(a)(3)(i) revised; (b)(1) amended.....	35507

47 CFR—Continued

60 FR
Page

Chapter I—Continued	
0.406 (b) introductory text and (2) amended.....	35507
0.408 Revised.....	50470
0.453 (d)(1) and (g)(3) removed; (d)(2) and (3) redesignated as (d)(1) and (2); (g)(2) revised; (m) added.....	5325
(a)(4) through (7) removed; (m)(1) revised; (n) added.....	35507
0.455 (b)(12) revised; (b)(14) removed; (b)(15) and (16) redesignated as (b)(14) and (15); (g) added.....	5325
0.467 (a)(1) table and (2) revised.....	30002
1 Policy statement.....	38738
Clarification.....	39656
Report.....	64348
1.7 Revised.....	16055
1.24 (d) added.....	53277
1.402 (a) amended; (b) removed; (c), (d), (e), (f), (g) and (h) redesignated as (b), (c), (d), (e), (f) and (j); new (c) and new (f) revised; new (g), new (h), (i) and (k) added.....	32119
(c), (d), (e) and (g) revised; (f) redesignated as (h); new (f) added.....	13636
1.403 Revised.....	13637
1.1104 Table amended.....	5325
Regulation at 59 FR 63051 eff. date confirmed as 12–20–94.....	10511
1.1105 Table amended.....	5325
1.1107 Redesignated as 1.1108; new 1.1107 added.....	5326
1.1108 Redesignated as 1.1109; new 1.1108 redesignated from 1.1107.....	5326
1.1109 Redesignated as 1.1110; new 1.1109 redesignated from 1.1108.....	5326
1.1110 Redesignated as 1.1111; new 1.1110 redesignated from 1.1109.....	5326
1.1111 Redesignated as 1.1112; new 1.1111 redesignated from 1.1110.....	5326
1.1112 Redesignated as 1.1113; new 1.1112 redesignated from 1.1111.....	5326
1.1113 Redesignated as 1.1114; new 1.1113 redesignated from 1.1112.....	5326

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

60 FR
Page

Chapter I—Continued

1.1114 Redesignated as 1.1115; new 1.1114 redesignated from 1.1113.....	5326
1.1115 Redesignated as 1.1116; new 1.1115 redesignated from 1.1114.....	5326
1.1116 Redesignated as 1.1117; new 1.1116 redesignated from 1.1115.....	5326
1.1117 Redesignated as 1.1118; new 1.1117 redesignated from 1.1116.....	5326
1.1118 Redesignated as 1.1119; new 1.1118 redesignated from 1.1117.....	5326
1.1119 Redesignated from 1.1118.....	5326
1.1152 Revised.....	34029
1.1153 Amended.....	5332
Revised.....	34030
1.1154 Revised.....	5332, 34031
Corrected.....	36737
1.1155 Revised.....	34031
1.1156 Redesignated as 1.1158; new 1.1156 added.....	5333
Redesignated as 1.1157; new 1.1167 added.....	34031
1.1157 Redesignated as 1.1159; new 1.1157 added.....	5333
Redesignated as 1.1158; new 1.1157 redesignated from 1.1156 and revised.....	34031
1.1158 Redesignated as 1.1160; new 1.1158 redesignated from 1.1156.....	5333
Redesignated as 1.1159; new 1.1158 redesignated from 1.1157 and revised.....	34031
1.1159 Redesignated as 1.1161; new 1.1159 redesignated from 1.1157.....	5333
Redesignated as 1.1160; new 1.1159 redesignated from 1.1158	34031
Revised.....	34032
1.1160 Redesignated as 1.1162; new 1.1160 redesignated from 1.1158.....	5333
Redesignated as 1.1161; new 1.1160 redesignated from 1.1159	34031
Revised.....	34032
1.1161 Redesignated as 1.1163; new 1.1161 redesignated from 1.1159.....	5333

47 CFR—Continued

60 FR
Page

Chapter I—Continued

Redesignated as 1.1162; new 1.1161 redesignated from 1.1160	34031
Revised.....	34032
1.1162 Redesignated as 1.1164; new 1.1162 redesignated from 1.1160.....	5333
Redesignated as 1.1163; new 1.1162 redesignated from 1.1161	34031
Revised.....	34033
(c) revised.....	34904
1.1163 Redesignated as 1.1165; new 1.1163 redesignated from 1.1161.....	5333
Redesignated as 1.1164; new 1.1163 redesignated from 1.1162	34031
Revised.....	34033
1.1164 Redesignated as 1.1166; new 1.1164 redesignated from 1.1162.....	5333
Redesignated as 1.1165; new 1.1164 redesignated from 1.1163	34031
Revised.....	34034
1.1165 Redesignated as 1.1167; new 1.1165 redesignated from 1.1163.....	5333
Redesignated as 1.1166; new 1.1165 redesignated from 1.1164	34031
Revised.....	34034
1.1166 Redesignated as 1.1168; new 1.1166 redesignated from 1.1164.....	5333
Redesignated as 1.1167; new 1.1166 redesignated from 1.1165	34031
Revised.....	34034
1.1167 Redesignated from 1.1165.....	5333
Removed; new 1.1167 redesignated from 1.1166.....	34031
Revised.....	34035
1.1168 Redesignated from 1.1166.....	5333
Removed.....	34031
1.1181 Added.....	38280
1.1182 Added.....	38280
1.2001 Revised.....	39269
1.2002 (a) revised.....	39269
1.2003 Regulation at 59 FR 63051 eff. date confirmed as 12–20– 94.....	10511

List of CFR Sections Affected

47 CFR—Continued

60 FR
Page

Chapter I—Continued	
1.2102 (a)(8) added	40718
1.2110 (b)(4)(x)(C), (D) and (E) re-designated as (c), (d) and (e).....	52865
2 Report and order	18778, 35507
Waiver	18999
2.106 Table amended; Footnotes 599A, 599B, 608A, 608B, 608C, 609B, 647A and 647B added; Footnotes US318, US319, US320, US322, US323, US324, US325 and US326 revised	20911
Table amended; Footnote 743A removed; Footnotes 750B, 751A, 751B, US327 and US328 added	8311
Table amended.....	13072, 21049, 39658
Footnote G2 revised; Footnote G12 added	13073
Table amended; Footnotes US218 and US275 revised	15251
Table amended; Footnote NG152 added	15687
Footnotes 731E, 731F, 753F, 881A, 881B, 882E, 882F and 882G added; Footnotes 733A, 733E, 734, 753, 753C, US319 and NG147 revised.....	21051
Table amended; Footnote NG154 added	35509
Table amended; Footnote US78 revised.....	37829
Table amended; Footnote US334 added; Footnote G117 revised	48905
2.947 Reinstated; CFR correction	37596
2.948 Reinstated in part; CFR correction	37596
2.1515 (b) corrected.....	47302
5.207 Revised	13637
11.11 (a) and (b) revised.....	55998
11.12 Revised	55999
11.21 Introductory text revised.....	55999
11.31 (a)(1), (b) and (c) revised.....	55999
11.33 (a)(3)(i), (ii), (5) introductory text, (ii), (9), (11) and (b)(2) revised	55999
11.34 (c) revised.....	56000
11.47 Added	56000

47 CFR—Continued

60 FR
Page

Chapter I—Continued	
11.51 (a) and (b) amended; (c) revised; (f) and (i) removed; (g), (h) and (j) through (n) redesignated as (f), (g) and (h) through (l)	56000
11.52 (a) revised.....	56000
11.61 (a)(1)(i), (2)(i) and (ii)(A) revised.....	56000
13.9 (d) and (e) redesignated as (e) and (f); new (d) added	27699
13.13 (d) and (e) redesignated as (e) and (f); new (d) added	27699
13.19 (b)(3) and (c) revised	27700
15 Interpretation.....	16055
Order	40760
15.205 (a) table amended	28068
15.233 Heading, (b) and (d) revised.....	21985
15.301 Revised	13073
15.303 (g) revised	13073
15.307 (a) revised	27425
15.311 Revised.....	13073
15.319 (a) amended	13073
15.321 Heading, (a) and (b) revised; (e) amended	13073
15.323 (e) corrected	3303
18.121 Correctly revised	47302

1996

47 CFR

61 FR
Page

Chapter I	
Chapter I Policy statement	11163
Order	14672, 26466, 30531, 35964, 39359, 40155
Petition denial	45903
0.5 (a)(15) added	8476
0.15 (i) amended.....	8477
0.81 Undesignated center heading and section added	2727
0.91 (i) amended.....	8477
0.111 Undesignated center heading and section revised	8476
0.121 (a) amended.....	8477
0.131 (j) revised	4361
0.151 Revised	10689
0.185 Introductory text, (a) and (b) revised	8476
0.241 (f) revised.....	4918
(g) added	31045
0.251 (j) added.....	26464
(c), (d) and (e) added; (f), (g) and (h) removed; (i) and (j) redesignated as (f) and (g)	29311
0.283 (a)(9)(i) revised	10689

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

61 FR
Page

Chapter I—Continued	
0.284 (a)(3) and (4) revised.....	8477
0.291 (h) revised.....	16230
0.311 Amended.....	8477
(i) added.....	25805
0.314 (l) revised.....	25805
0.317 Amended.....	8477
0.331 (d) revised.....	26465
0.332 (b) and (c) amended.....	8477
0.387 (b) amended.....	8477
0.391 Undesignated center heading and section added.....	2728
0.401 (a)(4) amended.....	8477
0.408 Revised (OMB numbers).....	51023
0.431 Amended.....	8477
0.445 (g) amended.....	8477
0.467 (a)(1) table and (2) revised.....	14500
1 Authority citation revised.....	45618, 46561, 52899
Technical correction.....	63758
Reconsideration petitions.....	66931
1.4 (h) introductory text revised; Examples 12 and 13 redesignated as Examples 13 and 14; new Example 12 added.....	11749
1.61 (c), (d), (e) and (f) removed; (g) redesignated as (c); (a), (b) and new (c) introductory text revised.....	4361
1.77 (i) added.....	26670
1.227 (b)(6) revised.....	18291
1.402 (h) and (i) revised.....	4918
1.420 (f) revised.....	43472
1.741 Revised.....	26670
1.761 Revised.....	26671
1.767 (a) revised; (e) and (f) added (effective date pending).....	15726
1.825 (b) revised.....	26671
1.901 Revised.....	26671
1.924 (b)(2)(ii) revised.....	26671
1.926 (a)(6) revised.....	26671
1.962 (a)(1) removed; (a)(2) through (7) redesignated as (a)(1) through (6).....	26671
1.972 (a)(1) and (c) revised.....	26671
1.1102 Revised.....	41967
1.1103 Revised.....	41974
1.1104 Revised.....	41975
1.1105 Revised.....	41979
Table corrected.....	44176
1.1106 Revised.....	41979
1.1107 Revised.....	41980
Table corrected.....	44176
1.1152 Revised.....	36639
1.1153 Revised.....	36641

47 CFR—Continued

61 FR
Page

Chapter I—Continued	
1.1154 Revised.....	36641
1.1155 Revised.....	36641
1.1156 Revised.....	36642
1.1307 (b) revised; (e) added.....	41014
1.1310 Added.....	41016
1.1401 Revised.....	43024, 45618
1.1402 (a), (b), (d), (e) and (f) revised; (h) added.....	43024
(d) revised.....	45618
1.1403 Revised.....	43025, 45618
1.1404 (a), (d) introductory text and (2) revised.....	43025
(b) and (c) revised; (k) added.....	45619
1.1409 (e) added.....	43025
(b) and (d) revised.....	45619
1.1416 Added.....	43025
Heading and (b) revised.....	45619
1.1501 Amended.....	39898
1.1502 Revised.....	39898
1.1504 (b)(5) amended; (b)(6) added.....	39898
1.1505 Revised.....	39899
1.1506 (b) amended.....	39899
1.1507 (a) amended.....	39899
1.1508 Amended.....	39899
1.1511 (a) and (b) introductory text revised.....	39899
1.1513 Amended.....	39899
1.1514 (a) and (c) revised.....	39899
1.1524 Amended.....	39899
1.1526 (a) revised.....	39899
1.1527 Revised.....	39900
1.1528 Amended.....	39900
1.2107 (c) revised; eff. 11–18–96.....	49075
1.4000 (Subpart S) Added (OMB number pending).....	46561
1.5000–1.5007 (Subpart T) Added.....	52899
Correctly designated; nomenclature corrected.....	57335
1.5000 Correctly designated.....	57335
1.5001 Correctly designated.....	57335
1.5002 Correctly designated.....	57335
1.5003 Correctly designated.....	57335
1.5004 Correctly designated.....	57335
1.5005 Correctly designated.....	57335
1.5006 Correctly designated.....	57335
1.5007 Correctly designated.....	57335
2 Technical correction.....	63758
2.104 (a) revised.....	15384
2.106 Table amended.....	14501, 52303

List of CFR Sections Affected

47 CFR—Continued

61 FR
Page

Chapter I—Continued	
Table amended; Footnotes 621, 622, 627 and 635 revised; Footnotes 633 and 634 removed; Footnote 641A added.....	15384
Table amended; Footnotes 551, 612, 614, 682, 708, US330 and US331 removed; Footnotes 672, 675, 676, 678, 697 and 703 revised; eff. 10–28–96	45342
2.805 Revised	31045
2.901 Revised	31045
2.906 Added	31045
2.909 Introductory text revised; (c) added	31045
2.913 Revised	31045
2.927 Undesignated center heading revised	31046
2.937 Revised	31046
2.945 Revised	31046
2.946 (a) and (b) revised	31046
2.948 (a)(3) and (d) added	31046
2.995 (a)(2) revised	26671
2.997 Revised	14502
2.1071 Undesignated center heading and section added	31046
2.1072 Added	31046
2.1073 Added	31046
2.1074 Added	31047
2.1075 Added	31047
2.1076 Added	31047
2.1077 Added	31048
2.1091 Undesignated center heading and section added	41017
2.1093 Added	41017
2.1204 (a)(4) amended	8477
2.1302 Amended; eff. 11–13–96	42386
3 Added	20165
5.67 (d)(2) amended	8477
11.31 (c) revised	54952
15 Reconsideration petition	3600
Authority citation revised	18509, 29689
Technical correction	63758
15.3 (r) revised; (bb) added	31048
15.19 (d) revised	18509
(b) and (c) redesignated as (a)(4) and (5); new (a)(4) and new (5) revised; new (b) and new (c) added	31048
15.31 (f)(1) revised	14502
15.32 Added	31049
15.33 (a) revised	14502
15.35 (b) revised	14502
15.37 (g) added	31049
15.101 (a) table and (c) through (f) revised	31050

47 CFR—Continued

61 FR
Page

Chapter I—Continued	
15.102 Added	31050
15.115 (i) revised	18509
15.117 (g)(3) removed	30532
15.118 (b), (c)(1) through (5) and (d) revised	18509
15.205 (d)(4) added	14503
15.245 (b)(1) introductory text correctly revised	42558
15.253 Added	14503
(f) revised	41018
15.255 Added; stayed	14503
(g) revised	41018
15.307 (a), (f) and (g) revised	29689
15.319 (i) revised	41018
15.321 (g) added	55926
17.1 Revised	4362
17.2 (a) revised; (c) and (d) added	4362
17.4 Revised	4362
17.5 Added	4362
17.6 Added	4363
17.7–17.17 (Subpart B) Heading revised	4363
17.10 Introductory text revised	4363
17.14 (a) amended	4363
17.17 (a) revised	4363
17.22 Amended	4363
17.23 Revised	4363
17.24 Removed	4363
17.25 Removed	4363
17.26 Removed	4363
17.27 Removed	4363
17.28 Removed	4363
17.29 Removed	4363
17.30 Removed	4363
17.31 Removed	4363
17.32 Removed	4363
17.33 Removed	4363
17.34 Removed	4363
17.35 Removed	4363
17.36 Removed	4363
17.37 Removed	4363
17.38 Removed	4363
17.39 Removed	4363
17.40 Removed	4363
17.41 Removed	4363
17.42 Removed	4363
17.43 Removed	4363
17.47 Revised	4363
17.48 Introductory text revised; (a) amended	4364
17.49 Heading, introductory text and (c) revised; (d) added	4364
17.50 Revised	4364

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

Chapter I—Continued	61 FR Page
17.51 (b) revised	4364
17.57 Revised	4364
19 Revised	56112

1997

(Regulations published from January 1, 1997, through October 1, 1997)

47 CFR

Chapter I	62 FR Page
Chapter I Clarification and interpretation	7690
Interpretation	16093
Policy statement	34648
Order	36216
0.5 (a)(8) removed; (a)(9) through (15) redesignated as (a)(8) through (14); (b) and (c) amended	4170
0.11 (a)(9) revised	15853
(a)(9) removed	51052
0.31 (m) amended	4170
0.41 (h) amended	4170
(o) added	15853
0.61 (c) amended	4170
(g) removed	45172
0.91 (d) amended	4170
Introductory text revised; (h) removed; (i), (j) and (k) redesignated as (h), (i) and (j)	8401
0.101 (g) amended	4170
Revised	8401
0.131 (p) added	17567
0.161 Removed	4170
0.201 (a) introductory text and (3) amended; (a)(2) revised	4170
0.204 (c)(1) removed; (c)(2) through (6) redesignated as (c)(1) through (5)	4170
0.231 (c) and (f) removed	51052
0.241 (f) removed; (g) redesignated as (f)	48952
0.251 (h) added	15853
(a) revised	24055
(i) added	51052
0.321 Revised	8401
0.331 (d) revised	40285
0.341 (c) revised	4170
0.361 Removed	4170
0.362 Removed	4170
0.363 Removed	4170
0.365 Removed	4170
0.367 Removed	4170

47 CFR—Continued

Chapter I—Continued	62 FR Page
0.408 Table amended (OMB numbers)	45172
0.467 (a)(1) table and (2) revised	42929
1 Reconsideration petitions	12959
Authority citation revised	37422
Orders	38475, 39450
Technical correction	48774
1.4 (b) introductory text amended	4170
(g), (j) and (k) revised (OMB number pending)	26238
OMB number	38029
1.25 Removed	51052
1.28 (c)(3)(ii) amended	4170
Removed	51052
1.29 Removed	51052
1.51 (a)(2) removed; (a)(3) and (4) redesignated as (a)(2) and (3)	4170
1.77 (i) revised	23162
1.80 (a) introductory text, (4), concluding text, (b)(1), (2) and (3) revised; (b)(5) added	4918
(b)(4) note added; eff. 10–14–97	43475
1.101 Amended	4170
1.102 (a)(1) amended	4170
1.104 (a) amended	4170
1.106 (a)(1) amended	4170
1.115 (b)(5) removed; (d), (e)(3) and (f) revised; (e)(1) amended	4170
1.209 Amended	4171
1.229 (f) amended	4171
1.244 (c)(4) amended; (d) revised	4171
1.245 (b)(4), (5) and (6) amended	4171
1.271 Revised	4171
1.273 Amended	4171
1.277 (f) amended	4171
1.291 (a)(2) removed; (a)(3), (4) and (5) redesignated as (a)(2), (3) and (4); new (a)(4), (d) and authority citation revised; (c)(3) amended	4171
1.296 Authority citation revised	4171
1.301 (c)(6) amended	4171
1.302 (b) amended; (f) revised	4171
1.311 (d) amended	4171
1.402 Removed	48952
1.767 Regulation at 60 FR 15726 eff. 6–13–96	51378

List of CFR Sections Affected

47 CFR—Continued

62 FR
Page

Chapter I—Continued

1.773 (a)(2)(i) through (iv) and (b)(1)(i) through (v) redesignated as (a)(2)(ii) through (v) and (b)(1)(ii) through (vi); new (a)(2)(i) and new (b)(1)(i) added; (a)(4) and (b)(3) revised.....	5777
1.825 (a) designation and (b) removed	24581
1.952 (b) revised; eff. 10-17-97.....	18843
1.1104 Table amended; eff. 12-1-97	51058
1.1152 Revised	37422
1.1153 Revised	37423
1.1154 Revised	37423
1.1155 Revised	37423
1.1156 Revised	37423
1.1200 Revised	15853
1.1202 Revised	15854
1.1203 Revised	15855
1.1204 Revised	15855
1.1206 Revised	15856
1.1208 Revised	15857
1.1210 Revised	15857
1.1212 Revised	15857
1.1214 Revised	15858
1.1216 Revised	15858
1.1307 (b)(4) introductory text revised	3240
(b)(2) revised	4655
(b)(1) introductory text revised; (b)(1) table and (b)(2) amended	9654
Heading revised; (b)(1) table amended	23162
(b)(1), (2), (3) and (4) introductory text revised; (b)(5) added; eff. 10-15-97	47965
1.1319 (a)(2) amended	4171
1.1701-1.1712 (Subpart M) Removed	45172
1.2102 (a)(9) added	23163
1.2103 (a) and (b) revised	13542
1.2105 (a)(2) revised	13543
1.2106 (b) revised	13543
1.2107 (b) and (c) revised	13543
1.2109 (a) and (b) revised	13544
1.2110 (b)(2), (e)(1), (2) and (3) introductory text revised.....	13544
2 Reconsideration petitions.....	12959
Authority citation revised	26711
Order	43316
2.1 (c) amended	26242
2.106 Table amended 9655, 15991, 19512, 23163, 24581, 26711, 40285	
2.803 Revised	10468

47 CFR—Continued

62 FR
Page

Chapter I—Continued

2.805 Removed	10470
2.806 Removed	10470
2.807 Introductory text revised.....	10470
2.809 Removed	10470
2.811 Revised	10470
2.813 Revised	10470
2.815 (d) and (e) revised.....	10470
2.901 (a) and (b) amended	10470
2.903 Removed	10470
2.909 (a) and (b) amended; (c)(3) and (d) added.....	10470
(c)(3) redesignated as (c)(4); new (c)(3) added	41880
2.913 (a) revised.....	10470
2.915 (a) introductory text and (c) amended.....	10470
2.917 (d) removed.....	10470
2.924 Revised	10470
2.925 (b)(4), (d) introductory text and (f) revised; (g) removed	10470
2.926 (e) amended	10471
2.927 (a) and (b) revised; (d) removed	10471
2.929 (b)(1) revised.....	10471
2.931 Revised	10471
2.932 (f) added.....	10471
2.933 (a), (b)(7) and (c) revised.....	10471
2.934 Amended	10471
2.936 Revised	10471
2.938 Revised	10471
2.941 Revised	10472
2.948 (d) note removed; (d)(1), (2) and (3) added.....	41880
2.953 Heading, (a), (b) and (d) revised.....	10472
2.954 Revised	10472
2.955 (a) introductory text and (3) revised	10472
2.956 Revised	10472
2.957 Removed	10472
2.961-2.969 Undesignated center heading removed	10472
2.961 Removed	10472
2.963 Removed	10472
2.965 Removed	10472
2.967 Removed	10472
2.969 Removed	10472
2.975 (b) and (g) revised.....	10473
2.979 Removed	10473
2.983 (h) removed; (i) amended	10473
2.1003 Removed.....	10473

47 CFR Ch. I (10–1–97 Edition)

47 CFR—Continued

62 FR
Page

Chapter I—Continued	
2.1005 (a), (c) introductory text, (4) and (d) revised	10473
2.1033 (b)(10) removed; (b)(11) amended	10473
2.1045 Removed	10473
2.1077 (b)(1) through (4) redesign- ated as (b)(2) through (5); new (b)(1) added	41880
2.1091 (c) and (d) introductory text revised	4655
(c) amended	9658
Heading, (b), (c) and (d)(3) re- vised; (d)(4) added; eff. 10–15– 97	47966
2.1093 (c) revised	4655
(c) amended	9658
(b), (c) and (d) introductory text revised; eff. 10–15–97	47967
2.1300 Revised	10473
5.207 Removed	48952
11.11 Note added	33753
15 Waiver request	35106

47 CFR—Continued

62 FR
Page

Chapter I—Continued	
Order	43316
15.3 (cc) added	26242
15.17 (a) revised	4655
15.19 (b)(1)(ii) revised; (b)(2) and (3) redesignated as (b)(3) and (4); new (b)(2) added	41881
15.31 (a)(6) amended; (b) re- vised	41881
(f)(1) revised	45333
15.32 (a)(1) and (2) revised	41881
15.37 Regulation at 61 FR 31049 eff. date delayed to 9–17– 97	33368
15.101 (a) table revised	41881
15.204 Added	26242
15.205 (a) table amended	4655
15.215 (a) revised	45333
15.247 (a)(1)(i) and (b) through (e) revised; (g) and (h) added	26242
15.255 (a) and (b) revised	45333
15.401–15.407 (Subpart E) Added	4656

