AUTHENTICATED
U.S. GOVERNMENT
INFORMATION
GPO

CODE OF FEDERAL REGULATIONS

Title 40
Protection of Environment

Part 63 (§§ 63.6580 to 63.8830)

Revised as of July 1, 2024

Containing a codification of documents
of general applicability and future effect

As of July 1, 2024

Published by the Office of the Federal Register
National Archives and Records Administration
as a Special Edition of the Federal Register

U.S. GOVERNMENT OFFICIAL EDITION NOTICE

Legal Status and Use of Seals and Logos

The seal of the National Archives and Records Administration (NARA) authenticates the Code of Federal Regulations (CFR) as the official codification of Federal regulations established under the Federal Register Act. Under the provisions of 44 U.S.C. 1507, the contents of the CFR, a special edition of the Federal Register, shall be judicially noticed. The CFR is prima facie evidence of the original documents published in the Federal Register (44 U.S.C. 1510).

It is prohibited to use NARA's official seal and the stylized Code of Federal Regulations logo on any republication of this material without the express, written permission of the Archivist of the United States or the Archivist's designee. Any person using NARA's official seals and logos in a manner inconsistent with the provisions of 36 CFR part 1200 is subject to the penalties specified in 18 U.S.C. 506, 701, and 1017.

Use of ISBN Prefix

This is the Official U.S. Government edition of this publication and is herein identified to certify its authenticity. Use of the 0–16 ISBN prefix is for U.S. Government Publishing Office Official Editions only. The Superintendent of Documents of the U.S. Government Publishing Office requests that any reprinted edition clearly be labeled as a copy of the authentic work with a new ISBN.

GPO U.S. GOVERNMENT PUBLISHING OFFICE

U.S. Superintendent of Documents • Washington, DC 20402–0001

http://bookstore.gpo.gov

Phone: toll-free (866) 512-1800; DC area (202) 512-1800

Table of Contents

	Page
Explanation	v
Title 40:	
Chapter I—Environmental Protection Agency (Continued)	3
Finding Aids:	
Table of CFR Titles and Chapters	589
Alphabetical List of Agencies Appearing in the CFR	609
List of CFR Sections Affected	619

Cite this Code: CFR

To cite the regulations in this volume use title, part and section number. Thus, 40 CFR 63.6580 *refers to title 40, part 63, section 6580.*

Explanation

The Code of Federal Regulations is a codification of the general and permanent rules published in the Federal Register by the Executive departments and agencies of the Federal Government. The Code is divided into 50 titles which represent broad areas subject to Federal regulation. Each title is divided into chapters which usually bear the name of the issuing agency. Each chapter is further subdivided into parts covering specific regulatory areas.

Each volume of the Code is revised at least once each calendar year and issued on a quarterly basis approximately as follows:

Title 1 through Title 16.....as of January 1
Title 17 through Title 27.....as of April 1
Title 28 through Title 41.....as of July 1
Title 42 through Title 50.....as of October 1

The appropriate revision date is printed on the cover of each volume.

LEGAL STATUS

The contents of the Federal Register are required to be judicially noticed (44 U.S.C. 1507). The Code of Federal Regulations is prima facie evidence of the text of the original documents (44 U.S.C. 1510).

HOW TO USE THE CODE OF FEDERAL REGULATIONS

The Code of Federal Regulations is kept up to date by the individual issues of the Federal Register. These two publications must be used together to determine the latest version of any given rule.

To determine whether a Code volume has been amended since its revision date (in this case, July 1, 2024), consult the ''List of CFR Sections Affected (LSA),'' which is issued monthly, and the ''Cumulative List of Parts Affected,'' which appears in the Reader Aids section of the daily Federal Register. These two lists will identify the Federal Register page number of the latest amendment of any given rule.

EFFECTIVE AND EXPIRATION DATES

Each volume of the Code contains amendments published in the Federal Register since the last revision of that volume of the Code. Source citations for the regulations are referred to by volume number and page number of the Federal Register and date of publication. Publication dates and effective dates are usually not the same and care must be exercised by the user in determining the actual effective date. In instances where the effective date is beyond the cut-off date for the Code a note has been inserted to reflect the future effective date. In those instances where a regulation published in the Federal Register states a date certain for expiration, an appropriate note will be inserted following the text.

OMB CONTROL NUMBERS

The Paperwork Reduction Act of 1980 (Pub. L. 96–511) requires Federal agencies to display an OMB control number with their information collection request.

Many agencies have begun publishing numerous OMB control numbers as amendments to existing regulations in the CFR. These OMB numbers are placed as close as possible to the applicable recordkeeping or reporting requirements.

PAST PROVISIONS OF THE CODE

Provisions of the Code that are no longer in force and effect as of the revision date stated on the cover of each volume are not carried. Code users may find the text of provisions in effect on any given date in the past by using the appropriate List of CFR Sections Affected (LSA). For the convenience of the reader, a ''List of CFR Sections Affected'' is published at the end of each CFR volume. For changes to the Code prior to the LSA listings at the end of the volume, consult previous annual editions of the LSA. For changes to the Code prior to 2001, consult the List of CFR Sections Affected compilations, published for 1949-1963, 1964-1972, 1973-1985, and 1986-2000.

''[RESERVED]'' TERMINOLOGY

The term ''[Reserved]'' is used as a place holder within the Code of Federal Regulations. An agency may add regulatory information at a ''[Reserved]'' location at any time. Occasionally ''[Reserved]'' is used editorially to indicate that a portion of the CFR was left vacant and not dropped in error.

INCORPORATION BY REFERENCE

What is incorporation by reference? Incorporation by reference was established by statute and allows Federal agencies to meet the requirement to publish regulations in the Federal Register by referring to materials already published elsewhere. For an incorporation to be valid, the Director of the Federal Register must approve it. The legal effect of incorporation by reference is that the material is treated as if it were published in full in the Federal Register (5 U.S.C. 552(a)). This material, like any other properly issued regulation, has the force of law.

What is a proper incorporation by reference? The Director of the Federal Register will approve an incorporation by reference only when the requirements of 1 CFR part 51 are met. Some of the elements on which approval is based are:

(a) The incorporation will substantially reduce the volume of material published in the Federal Register.

(b) The matter incorporated is in fact available to the extent necessary to afford fairness and uniformity in the administrative process.

(c) The incorporating document is drafted and submitted for publication in accordance with 1 CFR part 51.

What if the material incorporated by reference cannot be found? If you have any problem locating or obtaining a copy of material listed as an approved incorporation by reference, please contact the agency that issued the regulation containing that incorporation. If, after contacting the agency, you find the material is not available, please notify the Director of the Federal Register, National Archives and Records Administration, 8601 Adelphi Road, College Park, MD 20740-6001, or call 202-741-6010.

CFR INDEXES AND TABULAR GUIDES

A subject index to the Code of Federal Regulations is contained in a separate volume, revised annually as of January 1, entitled CFR INDEX AND FINDING AIDS. This volume contains the Parallel Table of Authorities and Rules. A list of CFR titles, chapters, subchapters, and parts and an alphabetical list of agencies publishing in the CFR are also included in this volume.

An index to the text of ''Title 3—The President'' is carried within that volume.

The Federal Register Index is issued monthly in cumulative form. This index is based on a consolidation of the ''Contents'' entries in the daily Federal Register.

A List of CFR Sections Affected (LSA) is published monthly, keyed to the revision dates of the 50 CFR titles.

REPUBLICATION OF MATERIAL

There are no restrictions on the republication of material appearing in the Code of Federal Regulations.

INQUIRIES

For a legal interpretation or explanation of any regulation in this volume, contact the issuing agency. The issuing agency's name appears at the top of odd-numbered pages.

For inquiries concerning CFR reference assistance, call 202–741–6000 or write to the Director, Office of the Federal Register, National Archives and Records Administration, 8601 Adelphi Road, College Park, MD 20740-6001 or e-mail *fedreg.info@nara.gov*.

SALES

The Government Publishing Office (GPO) processes all sales and distribution of the CFR. For payment by credit card, call toll-free, 866-512-1800, or DC area, 202-512-1800, M-F 8 a.m. to 4 p.m. e.s.t. or fax your order to 202-512-2104, 24 hours a day. For payment by check, write to: U.S. Government Publishing Office Superintendent of Documents, P.O. Box 37082, Washington, DC 20013–7082.

ELECTRONIC SERVICES

The full text of the Code of Federal Regulations, the LSA (List of CFR Sections Affected), The United States Government Manual, the Federal Register, Public Laws, Compilation of Presidential Documents and the Privacy Act Compilation are available in electronic format via *www.govinfo.gov*. For more information, contact the GPO Customer Contact Center, U.S. Government Publishing Office. Phone 202-512-1800, or 866-512-1800 (toll-free). E-mail, *ContactCenter@gpo.gov*.

The Office of the Federal Register also offers a free service on the National Archives and Records Administration's (NARA) website for public law numbers, Federal Register finding aids, and related information. Connect to NARA's website at *www.archives.gov/federal-register*.

The eCFR is a regularly updated, unofficial editorial compilation of CFR material and Federal Register amendments, produced by the Office of the Federal Register and the Government Publishing Office. It is available at *www.ecfr.gov*.

OLIVER A. POTTS,
Director,
Office of the Federal Register
July 1, 2024.

THIS TITLE

Title 40—PROTECTION OF ENVIRONMENT is composed of thirty-seven volumes. The parts in these volumes are arranged in the following order: Parts 1–49, parts 50–51, part 52 (52.01–52.1018), part 52 (52.1019–52.2019), part 52 (52.2020–end of part 52), parts 53–59, part 60 (60.1–60.499), part 60 (60.500–end of part 60, sections), part 60 (Appendices), parts 61–62, part 63 (63.1–63.599), part 63 (63.600–63.1199), part 63 (63.1200–63.1439), part 63 (63.1440–63.6175), part 63 (63.6580–63.8830), part 63 (63.8980–end of part 63), parts 64–71, parts 72–78, parts 79–80, part 81, parts 82–84, parts 85–96, parts 97–99, parts 100–135, parts 136–149, parts 150–189, parts 190–259, parts 260–265, parts 266–299, parts 300–399, parts 400–424, parts 425–699, parts 700–722, parts 723–789, parts 790–999, parts 1000–1059, and part 1060 to end. The contents of these volumes represent all current regulations codified under this title of the CFR as of July 1, 2024.

Chapter I—Environmental Protection Agency appears in all thirty-seven volumes. OMB control numbers for title 40 appear in §9.1 of this chapter.

Chapters IV–IX—Regulations issued by the Environmental Protection Agency and Department of Justice, Council on Environmental Quality, Chemical Safety and Hazard Investigation Board, Environmental Protection Agency and Department of Defense; Uniform National Discharge Standards for Vessels of the Armed Forces, Gulf Coast Ecosystem Restoration Council, and the Federal Permitting Improvement Steering Council appear in volume thirty-seven.

For this volume, Susannah C. Hurley was Chief Editor. The Code of Federal Regulations publication program is under the direction of John Hyrum Martinez, assisted by Stephen J. Frattini.

Title 40—Protection of Environment

(This book contains part 63, §§ 63.6580 to 63.8830)

Part

CHAPTER I—Environmental Protection Agency (Continued) 63

CHAPTER I—ENVIRONMENTAL PROTECTION AGENCY (CONTINUED)

EDITORIAL NOTE: Nomenclature changes to chapter I appear at 65 FR 47324, 47325, Aug. 2, 2000.

SUBCHAPTER C—AIR PROGRAMS (CONTINUED)

Part		*Page*
63	National emission standards for hazardous air pollutants for source categories (Continued)	5

SUBCHAPTER C—AIR PROGRAMS (CONTINUED)

PART 63—NATIONAL EMISSION STANDARDS FOR HAZARDOUS AIR POLLUTANTS FOR SOURCE CATEGORIES (CONTINUED)

Subpart ZZZZ—National Emission Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines

WHAT THIS SUBPART COVERS

Sec.
63.6580 What is the purpose of subpart ZZZZ?
63.6585 Am I subject to this subpart?
63.6590 What parts of my plant does this subpart cover?
63.6595 When do I have to comply with this subpart?

EMISSION LIMITATIONS

63.6600 What emission limitations and operating limitations must I meet if I own or operate a stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions?
63.6601 What emission limitations must I meet if I own or operate a new or reconstructed 4SLB stationary RICE with a site rating of greater than or equal to 250 brake HP and less than or equal to 500 brake HP located at a major source of HAP emissions?
63.6602 What emission limitations and other requirements must I meet if I own or operate an existing stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions?
63.6603 What emission limitations, operating limitations, and other requirements must I meet if I own or operate an existing stationary RICE located at an area source of HAP emissions?
63.6604 What fuel requirements must I meet if I own or operate a stationary CI RICE?

GENERAL COMPLIANCE REQUIREMENTS

63.6605 What are my general requirements for complying with this subpart?

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

63.6610 By what date must I conduct the initial performance tests or other initial compliance demonstrations if I own or operate a stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions?
63.6611 By what date must I conduct the initial performance tests or other initial compliance demonstrations if I own or operate a new or reconstructed 4SLB SI stationary RICE with a site rating of greater than or equal to 250 and less than or equal to 500 brake HP located at a major source of HAP emissions?
63.6612 By what date must I conduct the initial performance tests or other initial compliance demonstrations if I own or operate an existing stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions or an existing stationary RICE located at an area source of HAP emissions?
63.6615 When must I conduct subsequent performance tests?
63.6620 What performance tests and other procedures must I use?
63.6625 What are my monitoring, installation, collection, operation, and maintenance requirements?
63.6630 How do I demonstrate initial compliance with the emission limitations, operating limitations, and other requirements?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.6635 How do I monitor and collect data to demonstrate continuous compliance?
63.6640 How do I demonstrate continuous compliance with the emission limitations, operating limitations, and other requirements?

NOTIFICATION, REPORTS, AND RECORDS

63.6645 What notifications must I submit and when?
63.6650 What reports must I submit and when?
63.6655 What records must I keep?
63.6660 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.6665 What parts of the General Provisions apply to me?
63.6670 Who implements and enforces this subpart?
63.6675 What definitions apply to this subpart?
TABLE 1A TO SUBPART ZZZZ OF PART 63—EMISSION LIMITATIONS FOR EXISTING, NEW, AND RECONSTRUCTED SPARK IGNITION, 4SRB STATIONARY RICE >500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS
TABLE 1B TO SUBPART ZZZZ OF PART 63—OPERATING LIMITATIONS FOR EXISTING, NEW, AND RECONSTRUCTED SI 4SRB STATIONARY

RICE >500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS
TABLE 2A TO SUBPART ZZZZ OF PART 63—EMISSION LIMITATIONS FOR NEW AND RECONSTRUCTED 2SLB AND COMPRESSION IGNITION STATIONARY RICE >500 HP AND NEW AND RECONSTRUCTED 4SLB STATIONARY RICE ≥250 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS
TABLE 2B TO SUBPART ZZZZ OF PART 63—OPERATING LIMITATIONS FOR NEW AND RECONSTRUCTED 2SLB AND CI STATIONARY RICE >500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS, NEW AND RECONSTRUCTED 4SLB STATIONARY RICE ≥250 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS, EXISTING CI STATIONARY RICE >500 HP
TABLE 2C TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR EXISTING COMPRESSION IGNITION STATIONARY RICE LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS AND EXISTING SPARK IGNITION STATIONARY RICE ≤500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS
TABLE 2D TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR EXISTING STATIONARY RICE LOCATED AT AREA SOURCES OF HAP EMISSIONS
TABLE 3 TO SUBPART ZZZZ OF PART 63—SUBSEQUENT PERFORMANCE TESTS
TABLE 4 TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS
TABLE 5 TO SUBPART ZZZZ OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS, OPERATING LIMITATIONS, AND OTHER REQUIREMENTS
TABLE 6 TO SUBPART ZZZZ OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS, AND OTHER REQUIREMENTS
TABLE 7 TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 8 TO SUBPART ZZZZ OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART ZZZZ
APPENDIX A TO SUBPART ZZZZ OF PART 63—PROTOCOL FOR USING AN ELECTROCHEMICAL ANALYZER TO DETERMINE OXYGEN AND CARBON MONOXIDE CONCENTRATIONS FROM CERTAIN ENGINES

Subpart AAAAA—National Emission Standards for Hazardous Air Pollutants for Lime Manufacturing Plants

WHAT THIS SUBPART COVERS

63.7080 What is the purpose of this subpart?
63.7081 Am I subject to this subpart?
63.7082 What parts of my plant does this subpart cover?
63.7083 When do I have to comply with this subpart?

EMISSION LIMITATIONS

63.7090 What emission limitations must I meet?

GENERAL COMPLIANCE REQUIREMENTS

63.7100 What are my general requirements for complying with this subpart?

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

63.7110 By what date must I conduct performance tests and other initial compliance demonstrations?
63.7111 When must I conduct subsequent performance tests?
63.7112 What performance tests, design evaluations, and other procedures must I use?
63.7113 What are my monitoring installation, operation, and maintenance requirements?
63.7114 How do I demonstrate initial compliance with the emission limitations standard?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.7120 How do I monitor and collect data to demonstrate continuous compliance?
63.7121 How do I demonstrate continuous compliance with the emission limitations standard?

NOTIFICATIONS, REPORTS, AND RECORDS

63.7130 What notifications must I submit and when?
63.7131 What reports must I submit and when?
63.7132 What records must I keep?
63.7133 In what form and for how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7140 What parts of the General Provisions apply to me?
63.7141 Who implements and enforces this subpart?
63.7142 What are the requirements for claiming area source status?
63.7143 What definitions apply to this subpart?

TABLE 1 TO SUBPART AAAAA OF PART 63—EMISSION LIMITS
TABLE 2 TO SUBPART AAAAA OF PART 63—STARTUP AND SHUTDOWN EMISSION LIMITS FOR KILNS AND COOLERS
TABLE 3 TO SUBPART AAAAA OF PART 63—OPERATING LIMITS
TABLE 4 TO SUBPART AAAAA OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITS
TABLE 5 TO SUBPART AAAAA OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS
TABLE 6 TO SUBPART AAAAA OF PART 63—CONTINUOUS COMPLIANCE WITH OPERATING LIMITS
TABLE 7 TO SUBPART AAAAA OF PART 63—PERIODIC MONITORING FOR COMPLIANCE WITH OPACITY AND VISIBLE EMISSIONS LIMITS

TABLE 8 TO SUBPART AAAAA OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 9 TO SUBPART AAAAA OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART AAAAA

Subpart BBBBB—National Emission Standards for Hazardous Air Pollutants for Semiconductor Manufacturing

WHAT THIS SUBPART COVERS

63.7180 What is the purpose of this subpart?
63.7181 Am I subject to this subpart?
63.7182 What parts of my facility does this subpart cover?
63.7183 When do I have to comply with this subpart?

EMISSION STANDARDS

63.7184 What emission limitations, operating limits, and work practice standards must I meet?

COMPLIANCE REQUIREMENTS

63.7185 What are my general requirements for complying with this subpart?
63.7186 By what date must I conduct performance tests or other initial compliance demonstrations?
63.7187 What performance tests and other compliance procedures must I use?
63.7188 What are my monitoring installation, operation, and maintenance requirements?

APPLICATIONS, NOTIFICATIONS, REPORTS, AND RECORDS

63.7189 What applications and notifications must I submit and when?
63.7190 What reports must I submit and when?
63.7191 What records must I keep?
63.7192 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7193 What parts of the General Provisions apply to me?
63.7194 Who implements and enforces this subpart?
63.7195 What definitions apply to this subpart?
TABLE 1 TO SUBPART BBBBB OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS
TABLE 2 TO SUBPART BBBBB OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART BBBBB

Subpart CCCCC—National Emission Standards for Hazardous Air Pollutants for Coke Ovens: Pushing, Quenching, and Battery Stacks

WHAT THIS SUBPART COVERS

63.7280 What is the purpose of this subpart?
63.7281 Am I subject to this subpart?
63.7282 What parts of my plant does this subpart cover?
63.7283 When do I have to comply with this subpart?

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

63.7290 What emission limitations must I meet for capture systems and control devices applied to pushing emissions?
63.7291 What work practice standards must I meet for fugitive pushing emissions if I have a by-product coke oven battery with vertical flues?
63.7292 What work practice standards must I meet for fugitive pushing emissions if I have a by-product coke oven battery with horizontal flues?
63.7293 What work practice standards must I meet for fugitive pushing emissions if I have a non-recovery coke oven battery?
63.7294 What work practice standard must I meet for soaking?
63.7295 What requirements must I meet for quenching?
63.7296 What emission limitations must I meet for battery stacks?

OPERATION AND MAINTENANCE REQUIREMENTS

63.7300 What are my operation and maintenance requirements?

GENERAL COMPLIANCE REQUIREMENTS

63.7310 What are my general requirements for complying with this subpart?

INITIAL COMPLIANCE REQUIREMENTS

63.7320 By what date must I conduct performance tests or other initial compliance demonstrations?
63.7321 When must I conduct subsequent performance tests?
63.7322 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits for particulate matter?
63.7323 What procedures must I use to establish operating limits?
63.7324 What procedures must I use to demonstrate initial compliance with the opacity limits?
63.7325 What test methods and other procedures must I use to demonstrate initial compliance with the TDS or constituent limits for quench water?
63.7326 How do I demonstrate initial compliance with the emission limitations that apply to me?
63.7327 How do I demonstrate initial compliance with the work practice standards that apply to me?
63.7328 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.7330 What are my monitoring requirements?
63.7331 What are the installation, operation, and maintenance requirements for my monitors?
63.7332 How do I monitor and collect data to demonstrate continuous compliance?
63.7333 How do I demonstrate continuous compliance with the emission limitations that apply to me?
63.7334 How do I demonstrate continuous compliance with the work practice standards that apply to me?
63.7335 How do I demonstrate continuous compliance with the operation and maintenance requirements that apply to me?
63.7336 What other requirements must I meet to demonstrate continuous compliance?

NOTIFICATIONS, REPORTS, AND RECORDS

63.7340 What notifications must I submit and when?
63.7341 What reports must I submit and when?
63.7342 What records must I keep?
63.7343 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7350 What parts of the General Provisions apply to me?
63.7351 Who implements and enforces this subpart?
63.7352 What definitions apply to this subpart?

TABLE 1 TO SUBPART CCCCC OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART CCCCC

Subpart DDDDD—National Emission Standards for Hazardous Air Pollutants for Major Sources: Industrial, Commercial, and Institutional Boilers and Process Heaters

WHAT THIS SUBPART COVERS

63.7480 What is the purpose of this subpart?
63.7485 Am I subject to this subpart?
63.7490 What is the affected source of this subpart?
63.7491 Are any boilers or process heaters not subject to this subpart?
63.7495 When do I have to comply with this subpart?

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

63.7499 What are the subcategories of boilers and process heaters?
63.7500 What emission limitations, work practice standards, and operating limits must I meet?
63.7501 [Reserved]

GENERAL COMPLIANCE REQUIREMENTS

63.7505 What are my general requirements for complying with this subpart?

TESTING, FUEL ANALYSES, AND INITIAL COMPLIANCE REQUIREMENTS

63.7510 What are my initial compliance requirements and by what date must I conduct them?
63.7515 When must I conduct subsequent performance tests, fuel analyses, or tune-ups?
63.7520 What stack tests and procedures must I use?
63.7521 What fuel analyses, fuel specification, and procedures must I use?
63.7522 Can I use emissions averaging to comply with this subpart?
63.7525 What are my monitoring, installation, operation, and maintenance requirements?
63.7530 How do I demonstrate initial compliance with the emission limitations, fuel specifications and work practice standards?
63.7533 Can I use efficiency credits earned from implementation of energy conservation measures to comply with this subpart?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.7535 Is there a minimum amount of monitoring data I must obtain?
63.7540 How do I demonstrate continuous compliance with the emission limitations, fuel specifications and work practice standards?
63.7541 How do I demonstrate continuous compliance under the emissions averaging provision?

NOTIFICATION, REPORTS, AND RECORDS

63.7545 What notifications must I submit and when?
63.7550 What reports must I submit and when?
63.7555 What records must I keep?
63.7560 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7565 What parts of the General Provisions apply to me?
63.7570 Who implements and enforces this subpart?
63.7575 What definitions apply to this subpart?

TABLES TO SUBPART DDDDD OF PART 63

TABLE 1 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]

TABLE 2 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR EXISTING BOILERS AND PROCESS HEATERS [d]
TABLE 3 TO SUBPART DDDDD OF PART 63—WORK PRACTICE STANDARDS
TABLE 4 TO SUBPART DDDDD OF PART 63—OPERATING LIMITS FOR BOILERS AND PROCESS HEATERS
TABLE 5 TO SUBPART DDDDD OF PART 63—PERFORMANCE TESTING REQUIREMENTS
TABLE 6 TO SUBPART DDDDD OF PART 63—FUEL ANALYSIS REQUIREMENTS
TABLE 7 TO SUBPART DDDDD OF PART 63—ESTABLISHING OPERATING LIMIT
TABLE 8 TO SUBPART DDDDD OF PART 63—DEMONSTRATING CONTINUOUS COMPLIANCE
TABLE 9 TO SUBPART DDDDD OF PART 63—REPORTING REQUIREMENTS
TABLE 10 TO SUBPART DDDDD OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART DDDDD
TABLE 11 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS THAT COMMENCED CONSTRUCTION OR RECONSTRUCTION AFTER JUNE 4, 2010, AND BEFORE MAY 20, 2011
TABLE 12 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS THAT COMMENCED CONSTRUCTION OR RECONSTRUCTION AFTER MAY 20, 2011, AND BEFORE DECEMBER 23, 2011
TABLE 13 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS THAT COMMENCED CONSTRUCTION OR RECONSTRUCTION AFTER DECEMBER 23, 2011, AND BEFORE APRIL 1, 2013
TABLE 14 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]
TABLE 15 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR EXISTING BOILERS AND PROCESS HEATERS [D]

Subpart EEEEE—National Emission Standards for Hazardous Air Pollutants for Iron and Steel Foundries

WHAT THIS SUBPART COVERS

63.7680 What is the purpose of this subpart?
63.7681 Am I subject to this subpart?
63.7682 What parts of my foundry does this subpart cover?
63.7683 When do I have to comply with this subpart?

EMISSIONS LIMITATIONS

63.7690 What emissions limitations must I meet?

WORK PRACTICE STANDARDS

63.7700 What work practice standards must I meet?

OPERATION AND MAINTENANCE REQUIREMENTS

63.7710 What are my operation and maintenance requirements?

GENERAL COMPLIANCE REQUIREMENTS

63.7720 What are my general requirements for complying with this subpart?

INITIAL COMPLIFANCE REQUIREMENTS

63.7730 By what date must I conduct performance tests or other initial compliance demonstrations?
63.7731 When must I conduct subsequent performance tests?
63.7732 What test methods and other procedures must I use to demonstrate initial compliance with the emissions limitations?
63.7733 What procedures must I use to establish operating limits?
63.7734 How do I demonstrate initial compliance with the emissions limitations that apply to me?
63.7735 How do I demonstrate initial compliance with the work practice standards that apply to me?
63.7736 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.7740 What are my monitoring requirements?
63.7741 What are the installation, operation, and maintenance requirements for my monitors?
63.7742 How do I monitor and collect data to demonstrate continuous compliance?
63.7743 How do I demonstrate continuous compliance with the emissions limitations that apply to me?
63.7744 How do I demonstrate continuous compliance with the work practice standards that apply to me?
63.7745 How do I demonstrate continuous compliance with the operation and maintenance requirements that apply to me?
63.7746 What other requirements must I meet to demonstrate continuous compliance?
63.7747 How do I apply for alternative monitoring requirements for a continuous emissions monitoring system?

NOTIFICATIONS, REPORTS, AND RECORDS

63.7750 What notifications must I submit and when?
63.7751 What reports must I submit and when?
63.7752 What records must I keep?
63.7753 In what form and for how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7760 What parts of the General Provisions apply to me?
63.7761 Who implements and enforces this subpart?

DEFINITIONS

63.7765 What definitions apply to this subpart?

TABLE 1 TO SUBPART EEEEE OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART

Subpart FFFFF—National Emission Standards for Hazardous Air Pollutants for Integrated Iron and Steel Manufacturing Facilities

WHAT THIS SUBPART COVERS

63.7780 What is the purpose of this subpart?
63.7781 Am I subject to this subpart?
63.7782 What parts of my plant does this subpart cover?
63.7783 When do I have to comply with this subpart?

EMISSION LIMITATIONS AND STANDARDS

63.7790 What emission limitations must I meet?
63.7791 How do I comply with the requirements for the control of mercury from BOPF Groups?
63.7792 What fenceline monitoring requirements must I meet?
63.7793 What work practice standards must I meet?

OPERATION AND MAINTENANCE REQUIREMENTS

63.7800 What are my operation and maintenance requirements?

GENERAL COMPLIANCE REQUIREMENTS

63.7810 What are my general requirements for complying with this subpart?

INITIAL COMPLIANCE REQUIREMENTS

63.7820 By what date must I conduct performance tests or other initial compliance demonstrations?
63.7821 When must I conduct subsequent performance tests?
63.7822 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits for particulate matter?
63.7823 What test methods and other procedures must I use to demonstrate initial compliance with the opacity limits?
63.7824 What test methods and other procedures must I use to establish and demonstrate initial compliance with the operating limits?
63.7825 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits for hazardous air pollutants?
63.7826 How do I demonstrate initial compliance with the emission limitations that apply to me?
63.7827 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.7830 What are my monitoring requirements?
63.7831 What are the installation, operation, and maintenance requirements for my monitors?
63.7832 How do I monitor and collect data to demonstrate continuous compliance?
63.7833 How do I demonstrate continuous compliance with the emission limitations that apply to me?
63.7834 How do I demonstrate continuous compliance with the operation and maintenance requirements that apply to me?
63.7835 What other requirements must I meet to demonstrate continuous compliance?

NOTIFICATIONS, REPORTS, AND RECORDS

63.7840 What notifications must I submit and when?
63.7841 What reports must I submit and when?
63.7842 What records must I keep?
63.7843 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7850 What parts of the General Provisions apply to me?
63.7851 Who implements and enforces this subpart?
63.7852 What definitions apply to this subpart?

TABLE 1 TO SUBPART FFFFF OF PART 63—EMISSION, OPACITY, AND WORK PRACTICE LIMITS

TABLE 2 TO SUBPART FFFFF OF PART 63—INITIAL COMPLIANCE WITH EMISSION AND OPACITY LIMITS

TABLE 3 TO SUBPART FFFFF OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION AND OPACITY LIMITS

TABLE 4 TO SUBPART FFFFF OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART FFFFF

TABLE 5 TO SUBPART FFFFF OF PART 63—TOXIC EQUIVALENCY FACTORS

TABLE 6 TO SUBPART FFFFF OF PART 63—LIST OF POLYCYCLIC AROMATIC HYDROCARBONS

Subpart GGGGG—National Emission Standards for Hazardous Air Pollutants: Site Remediation

WHAT THIS SUBPART COVERS

63.7880 What is the purpose of this subpart?
63.7881 Am I subject to this subpart?
63.7882 What site remediation sources at my facility does this subpart affect?
63.7883 When do I have to comply with this subpart?

GENERAL STANDARDS

63.7884 What are the general standards I must meet for each site remediation with affected sources?
63.7885 What are the general standards I must meet for my affected process vents?
63.7886 What are the general standards I must meet for my affected remediation material management units?
63.7887 What are the general standards I must meet for my affected equipment leak sources?
63.7888 How do I implement this rule at my facility using the cross-referenced requirements in other subparts?

PROCESS VENTS

63.7890 What emissions limitations and work practice standards must I meet for process vents?
63.7891 How do I demonstrate initial compliance with the emissions limitations and work practice standards for process vents?
63.7892 What are my inspection and monitoring requirements for process vents?
63.7893 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for process vents?

TANKS

63.7895 What emissions limitations and work practice standards must I meet for tanks?
63.7896 How do I demonstrate initial compliance with the emissions limitations and work practice standards for tanks?
63.7897 What are my inspection and monitoring requirements for tanks?
63.7898 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for tanks?

CONTAINERS

63.7900 What emissions limitations and work practice standards must I meet for containers?
63.7901 How do I demonstrate initial compliance with the emissions limitations and work practice standards for containers?
63.7902 What are my inspection and monitoring requirements for containers?
63.7903 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for containers?

SURFACE IMPOUNDMENTS

63.7905 What emissions limitations and work practice standards must I meet for surface impoundments?
63.7906 How do I demonstrate initial compliance with the emissions limitations and work practice standards for surface impoundments?
63.7907 What are my inspection and monitoring requirements for surface impoundments?
63.7908 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for surface impoundments?

SEPARATORS

63.7910 What emissions limitations and work practice standards must I meet for separators?
63.7911 How do I demonstrate initial compliance with the emissions limitations and work practice standards for separators?
63.7912 What are my inspection and monitoring requirements for separators?
63.7913 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for separators?

TRANSFER SYSTEMS

63.7915 What emissions limitations and work practice standards must I meet for transfer systems?
63.7916 How do I demonstrate initial compliance with the emissions limitations and work practice standards for transfer systems?
63.7917 What are my inspection and monitoring requirements for transfer systems?
63.7918 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for transfer systems?

EQUIPMENT LEAKS AND PRESSURE RELIEF DEVICES

63.7920 What emissions limitations and work practice standards must I meet for equipment leaks?
63.7921 How do I demonstrate initial compliance with the emissions limitations and work practice standards for equipment leaks?
63.7922 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for equipment leaks?

63.7923 What monitoring and work practice standards must I meet for pressure relief devices?

CLOSED VENT SYSTEMS AND CONTROL DEVICES

63.7925 What emissions limitations and work practice standards must I meet for closed vent systems and control devices?
63.7926 How do I demonstrate initial compliance with the emissions limitations and work practice standards for closed vent systems and control devices?
63.7927 What are my inspection and monitoring requirements for closed vent systems and control devices?
63.7928 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for closed vent systems and control devices?

GENERAL COMPLIANCE REQUIREMENTS

63.7935 What are my general requirements for complying with this subpart?
63.7936 What requirements must I meet if I transfer remediation material off-site to another facility?
63.7937 How do I demonstrate initial compliance with the general standards?
63.7938 How do I demonstrate continuous compliance with the general standards?

PERFORMANCE TESTS

63.7940 By what date must I conduct performance tests or other initial compliance demonstrations?
63.7941 How do I conduct a performance test, design evaluation, or other type of initial compliance demonstration?
63.7942 When must I conduct subsequent performance tests?
63.7943 How do I determine the average VOHAP concentration of my remediation material?
63.7944 How do I determine the maximum HAP vapor pressure of my remediation material?

CONTINUOUS MONITORING SYSTEMS

63.7945 What are my monitoring installation, operation, and maintenance requirements?
63.7946 How do I monitor and collect data to demonstrate continuous compliance?
63.7947 What are my monitoring alternatives?

NOTIFICATIONS, REPORTS, AND RECORDS

63.7950 What notifications must I submit and when?
63.7951 What reports must I submit and when?
63.7952 What records must I keep?
63.7953 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.7955 What parts of the General Provisions apply to me?
63.7956 Who implements and enforces this subpart?
63.7957 What definitions apply to this subpart?

TABLE 1 TO SUBPART GGGGG OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS

TABLE 2 TO SUBPART GGGGG OF PART 63—CONTROL LEVELS AS REQUIRED BY §63.7895(a) FOR TANKS MANAGING REMEDIATION MATERIAL WITH A MAXIMUM HAP VAPOR PRESSURE LESS THAN 76.6 KPA

TABLE 3 TO SUBPART GGGGG OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART GGGGG

Subpart HHHHH—National Emission Standards for Hazardous Air Pollutants: Miscellaneous Coating Manufacturing

WHAT THIS SUBPART COVERS

63.7980 What is the purpose of this subpart?
63.7985 Am I subject to the requirements in this subpart?
63.7990 What parts of my plant does this subpart cover?

COMPLIANCE DATES

63.7995 When do I have to comply with this subpart?

EMISSION LIMITS, WORK PRACTICE STANDARDS, AND COMPLIANCE REQUIREMENTS

63.8000 What are my general requirements for complying with this subpart?
63.8005 What requirements apply to my process vessels?
63.8010 What requirements apply to my storage tanks?
63.8015 What requirements apply to my equipment leaks?
63.8020 What requirements apply to my wastewater streams?
63.8025 What requirements apply to my transfer operations?
63.8030 What requirements apply to my heat exchange systems?

ALTERNATIVE MEANS OF COMPLIANCE

63.8050 How do I comply with emissions averaging for stationary process vessels at existing sources?
63.8055 How do I comply with a weight percent HAP limit in coating products?

NOTIFICATIONS, REPORTS, AND RECORDS

63.8070 What notifications must I submit and when?
63.8075 What reports must I submit and when?
63.8080 What records must I keep?

OTHER REQUIREMENTS AND INFORMATION

63.8090 What compliance options do I have if part of my plant is subject to both this subpart and another subpart?
63.8095 What parts of the General Provisions apply to me?
63.8100 Who implements and enforces this subpart?
63.8105 What definitions apply to this subpart?
TABLE 1 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR PROCESS VESSELS
TABLE 2 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR STORAGE TANKS
TABLE 3 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR EQUIPMENT LEAKS
TABLE 4 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR WASTEWATER STREAMS
TABLE 5 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR TRANSFER OPERATIONS
TABLE 6 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR HEAT EXCHANGE SYSTEMS
TABLE 7 TO SUBPART HHHHH OF PART 63—PARTIALLY SOLUBLE HAZARDOUS AIR POLLUTANTS
TABLE 8 TO SUBPART HHHHH OF PART 63—SOLUBLE HAZARDOUS AIR POLLUTANTS
TABLE 9 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 10 TO SUBPART HHHHH OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART
TABLE 11 TO SUBPART HHHHH OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS THAT MUST BE COUNTED TOWARD TOTAL ORGANIC HAP CONTENT IF PRESENT AT 0.1 PERCENT OR MORE BY MASS

Subpart IIIII—National Emission Standards for Hazardous Air Pollutants for Mercury Cell Chlor-Alkali Plants

WHAT THIS SUBPART COVERS

63.8180 What is the purpose of this subpart?
63.8182 Am I subject to this subpart?
63.8184 What parts of my plant does this subpart cover?
63.8186 When do I have to comply with this subpart?

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

63.8190 What emission limitations must I meet?
63.8192 What work practice standards must I meet?

OPERATION AND MAINTENANCE REQUIREMENTS

63.8222 What are my operation and maintenance requirements?

GENERAL COMPLIANCE REQUIREMENTS

63.8226 What are my general requirements for complying with this subpart?

INITIAL COMPLIANCE REQUIREMENTS

63.8230 By what date must I conduct performance tests or other initial compliance demonstrations?
63.8232 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits?
63.8234 What equations and procedures must I use for the initial compliance demonstration?
63.8236 How do I demonstrate initial compliance with the emission limitations and work practice standards?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.8240 What are my monitoring requirements?
63.8242 What are the installation, operation, and maintenance requirements for my continuous mercury monitoring systems?
63.8243 What equations and procedures must I use to demonstrate continuous compliance?
63.8244 How do I monitor and collect data to demonstrate continuous compliance?
63.8246 How do I demonstrate continuous compliance with the emission limitations and work practice standards?
63.8248 What other requirements must I meet?

NOTIFICATIONS, REPORTS, AND RECORDS

63.8252 What notifications must I submit and when?
63.8254 What reports must I submit and when?
63.8256 What records must I keep?
63.8258 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.8262 What parts of the General Provisions apply to me?
63.8264 Who implements and enforces this subpart?
63.8266 What definitions apply to this subpart?
TABLE 1 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—DESIGN, OPERATION, AND MAINTENANCE REQUIREMENTS
TABLE 2 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—REQUIRED INSPECTIONS
TABLE 3 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—REQUIRED ACTIONS FOR LIQUID MERCURY SPILLS AND ACCUMULATIONS AND HYDROGEN AND MERCURY VAPOR LEAKS

TABLE 4 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—REQUIREMENTS FOR MERCURY LIQUID COLLECTION
TABLE 5 TO SUBPART IIIII OF PART 63—REQUIRED ELEMENTS OF FLOOR-LEVEL MERCURY VAPOR MEASUREMENT AND CELL ROOM MONITORING PLANS
TABLE 6 TO SUBPART IIIII OF PART 63—EXAMPLES OF TECHNIQUES FOR EQUIPMENT PROBLEM IDENTIFICATION, LEAK DETECTION AND MERCURY VAPOR MEASUREMENTS
TABLE 7 TO SUBPART IIIII OF PART 63—REQUIRED ELEMENTS OF WASHDOWN PLANS
TABLE 8 TO SUBPART IIIII OF PART 63—REQUIREMENTS FOR CELL ROOM MONITORING PROGRAM
TABLE 9 TO SUBPART IIIII OF PART 63—REQUIRED RECORDS FOR WORK PRACTICE STANDARDS
TABLE 10 TO SUBPART IIIII OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART IIIII

Subpart JJJJJ—National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing

WHAT THIS SUBPART COVERS

63.8380 What is the purpose of this subpart?
63.8385 Am I subject to this subpart?
63.8390 What parts of my plant does this subpart cover?
63.8395 When do I have to comply with this subpart?

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

63.8405 What emission limitations and work practice standards must I meet?
63.8410 What are my options for meeting the emission limitations and work practice standards?

GENERAL COMPLIANCE REQUIREMENTS

63.8420 What are my general requirements for complying with this subpart?
63.8425 What do I need to know about operation, maintenance, and monitoring plans?

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

63.8435 By what date must I conduct performance tests?
63.8440 When must I conduct subsequent performance tests?
63.8445 How do I conduct performance tests and establish operating limits?
63.8450 What are my monitoring installation, operation, and maintenance requirements?
63.8455 How do I demonstrate initial compliance with the emission limitations and work practice standards?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.8465 How do I monitor and collect data to demonstrate continuous compliance?
63.8470 How do I demonstrate continuous compliance with the emission limitations and work practice standards?

NOTIFICATIONS, REPORTS, AND RECORDS

63.8480 What notifications must I submit and when?
63.8485 What reports must I submit and when?
63.8490 What records must I keep?
63.8495 In what form and for how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.8505 What parts of the General Provisions apply to me?
63.8510 Who implements and enforces this subpart?
63.8515 What definitions apply to this subpart?

TABLES TO SUBPART JJJJJ OF PART 63
TABLE 1 TO SUBPART JJJJJ OF PART 63—EMISSION LIMITS
TABLE 2 TO SUBPART JJJJJ OF PART 63—OPERATING LIMITS
TABLE 3 TO SUBPART JJJJJ OF PART 63—WORK PRACTICE STANDARDS
TABLE 4 TO SUBPART JJJJJ OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS
TABLE 5 TO SUBPART JJJJJ OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS
TABLE 6 TO SUBPART JJJJJ OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS
TABLE 7 TO SUBPART JJJJJ OF PART 63—COMPLIANCE DATES
TABLE 8 TO SUBPART JJJJJ OF PART 63—REQUIREMENTS FOR NOTIFICATIONS
TABLE 9 TO SUBPART JJJJJ OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 10 TO SUBPART JJJJJ OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART JJJJJ

Subpart KKKKK—National Emission Standards for Hazardous Air Pollutants for Clay Ceramics Manufacturing

WHAT THIS SUBPART COVERS

63.8530 What is the purpose of this subpart?
63.8535 Am I subject to this subpart?
63.8540 What parts of my plant does this subpart cover?
63.8545 When do I have to comply with this subpart?

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

63.8555 What emission limitations and work practice standards must I meet?

63.8560 What are my options for meeting the emission limitations and work practice standards?

GENERAL COMPLIANCE REQUIREMENTS

63.8570 What are my general requirements for complying with this subpart?
63.8575 What do I need to know about operation, maintenance, and monitoring plans?

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

63.8585 By what date must I conduct performance tests?
63.8590 When must I conduct subsequent performance tests?
63.8595 How do I conduct performance tests and establish operating limits?
63.8600 What are my monitoring installation, operation, and maintenance requirements?
63.8605 How do I demonstrate initial compliance with the emission limitations and work practice standards?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.8615 How do I monitor and collect data to demonstrate continuous compliance?
63.8620 How do I demonstrate continuous compliance with the emission limitations and work practice standards?

NOTIFICATIONS, REPORTS, AND RECORDS

63.8630 What notifications must I submit and when?
63.8635 What reports must I submit and when?
63.8640 What records must I keep?
63.8645 In what form and for how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.8655 What parts of the General Provisions apply to me?
63.8660 Who implements and enforces this subpart?
63.8665 What definitions apply to this subpart?

TABLES TO SUBPART KKKKK OF PART 63

TABLE 1 TO SUBPART KKKKK OF PART 63—EMISSION LIMITS
TABLE 2 TO SUBPART KKKKK OF PART 63—OPERATING LIMITS
TABLE 3 TO SUBPART KKKKK OF PART 63—WORK PRACTICE STANDARDS
TABLE 4 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS
TABLE 5 TO SUBPART KKKKK OF PART 63—TOXIC EQUIVALENCY FACTORS
TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS
TABLE 7 TO SUBPART KKKKK OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS
TABLE 8 TO SUBPART KKKKK OF PART 63—COMPLIANCE DATES
TABLE 9 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR NOTIFICATIONS
TABLE 10 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 11 TO SUBPART KKKKK OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART KKKKK

Subpart LLLLL—National Emission Standards for Hazardous Air Pollutants: Asphalt Processing and Asphalt Roofing Manufacturing

WHAT THIS SUBPART COVERS

63.8680 What is the purpose of this subpart?
63.8681 Am I subject to this subpart?
63.8682 What parts of my plant does this subpart cover?
63.8683 When must I comply with this subpart?

EMISSION LIMITATIONS

63.8684 What emission limitations and operating limits must I meet?

GENERAL COMPLIANCE REQUIREMENTS

63.8685 What are my general requirements for complying with this subpart?

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

63.8686 By what date must I conduct initial performance tests or other initial compliance demonstrations?
63.8687 What performance tests, design evaluations, and other procedures must I use?
63.8688 What are my monitoring installation, operation, and maintenance requirements?
63.8689 How do I demonstrate initial compliance with the emission limitations?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.8690 How do I monitor and collect data to demonstrate continuous compliance?
63.8691 How do I conduct periodic performance tests and demonstrate continuous compliance with the emission limitations and operating limits?

NOTIFICATIONS, REPORTS, AND RECORDS

63.8692 What notifications must I submit and when?
63.8693 What reports must I submit and when?
63.8694 What records must I keep?
63.8695 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.8696 What parts of the General Provisions apply to me?
63.8697 Who implements and enforces this subpart?
63.8698 What definitions apply to this subpart?
TABLE 1 TO SUBPART LLLLL OF PART 63—EMISSION LIMITATIONS
TABLE 2 TO SUBPART LLLLL OF PART 63—OPERATING LIMITS
TABLE 3 TO SUBPART LLLLL OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS
TABLE 4 TO SUBPART LLLLL OF PART 63—INITIAL AND CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS
TABLE 5 TO SUBPART LLLLL OF PART 63—CONTINUOUS COMPLIANCE WITH OPERATING LIMITS
TABLE 6 TO SUBPART LLLLL OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 7 TO SUBPART LLLLL OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART LLLLL

Subpart MMMMM—National Emission Standards for Hazardous Air Pollutants: Flexible Polyurethane Foam Fabrication Operations

WHAT THIS SUBPART COVERS

63.8780 What is the purpose of this subpart?
63.8782 Am I subject to this subpart?
63.8784 What parts of my plant does this subpart cover?
63.8786 When do I have to comply with this subpart?

EMISSION LIMITATIONS

63.8790 What emission limitations must I meet?

GENERAL COMPLIANCE REQUIREMENTS

63.8794 What are my general requirements for complying with this subpart?

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

63.8798 By what date must I conduct performance tests or other initial compliance demonstrations?
63.8800 What performance tests and other procedures must I use to demonstrate compliance with the emission limit for flame lamination?
63.8802 What methods must I use to demonstrate compliance with the emission limitation for loop slitter adhesive use?
63.8806 How do I demonstrate initial compliance with the emission limitations?

CONTINUOUS COMPLIANCE REQUIREMENTS

63.8810 How do I monitor and collect data to demonstrate continuous compliance?
63.8812 How do I demonstrate continuous compliance with the emission limitations?

NOTIFICATIONS, REPORTS, AND RECORDS

63.8816 What notifications must I submit and when?
63.8818 What reports must I submit and when?
63.8820 What records must I keep?
63.8822 In what form and how long must I keep my records?

OTHER REQUIREMENTS AND INFORMATION

63.8826 What parts of the General Provisions apply to me?
63.8828 Who implements and enforces this subpart?
63.8830 What definitions apply to this subpart?
TABLE 1 TO SUBPART MMMMM OF PART 63—EMISSION LIMITS
TABLE 2 TO SUBPART MMMMM OF PART 63—OPERATING LIMITS FOR EXISTING, NEW, OR RECONSTRUCTED FLAME LAMINATION AFFECTED SOURCES
TABLE 3 TO SUBPART MMMMM OF PART 63—PERFORMANCE TEST REQUIREMENTS FOR EXISTING, NEW, OR RECONSTRUCTED FLAME LAMINATION AFFECTED SOURCES
TABLE 4 TO SUBPART MMMMM OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITS
TABLE 5 TO SUBPART MMMMM OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITS AND OPERATING LIMITS
TABLE 6 TO SUBPART MMMMM OF PART 63—REQUIREMENTS FOR REPORTS
TABLE 7 TO SUBPART MMMMM OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART MMMMM
TABLE 8 TO SUBPART MMMMM OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS THAT MUST BE COUNTED TOWARD TOTAL HAP CONTENT IF PRESENT AT 0.1 PERCENT OR MORE BY WEIGHT

AUTHORITY: 42 U.S.C. 7401 *et seq.*

SOURCE: 57 FR 61992, Dec. 29, 1992, unless otherwise noted.

Subpart ZZZZ—National Emissions Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines

SOURCE: 69 FR 33506, June 15, 2004, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.6580 What is the purpose of subpart ZZZZ?

Subpart ZZZZ establishes national emission limitations and operating limitations for hazardous air pollutants (HAP) emitted from stationary reciprocating internal combustion engines (RICE) located at major and area sources of HAP emissions. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations and operating limitations.

[73 FR 3603, Jan. 18, 2008]

§ 63.6585 Am I subject to this subpart?

You are subject to this subpart if you own or operate a stationary RICE at a major or area source of HAP emissions, except if the stationary RICE is being tested at a stationary RICE test cell/stand.

(a) A stationary RICE is any internal combustion engine which uses reciprocating motion to convert heat energy into mechanical work and which is not mobile. Stationary RICE differ from mobile RICE in that a stationary RICE is not a non-road engine as defined at 40 CFR 1068.30, and is not used to propel a motor vehicle or a vehicle used solely for competition.

(b) A major source of HAP emissions is a plant site that emits or has the potential to emit any single HAP at a rate of 10 tons (9.07 megagrams) or more per year or any combination of HAP at a rate of 25 tons (22.68 megagrams) or more per year, except that for oil and gas production facilities, a major source of HAP emissions is determined for each surface site.

(c) An area source of HAP emissions is a source that is not a major source.

(d) If you are an owner or operator of an area source subject to this subpart, your status as an entity subject to a standard or other requirements under this subpart does not subject you to the obligation to obtain a permit under 40 CFR part 70 or 71, provided you are not required to obtain a permit under 40 CFR 70.3(a) or 40 CFR 71.3(a) for a reason other than your status as an area source under this subpart. Notwithstanding the previous sentence, you must continue to comply with the provisions of this subpart as applicable.

(e) If you are an owner or operator of a stationary RICE used for national security purposes, you may be eligible to request an exemption from the requirements of this subpart as described in 40 CFR part 1068, subpart C.

(f) The emergency stationary RICE listed in paragraphs (f)(1) through (3) of this section are not subject to this subpart. The stationary RICE must meet the definition of an emergency stationary RICE in §63.6675, which includes operating according to the provisions specified in §63.6640(f).

(1) Existing residential emergency stationary RICE located at an area source of HAP emissions that do not operate for the purpose specified in §63.6640(f)(4)(ii).

(2) Existing commercial emergency stationary RICE located at an area source of HAP emissions that do not operate for the purpose specified in §63.6640(f)(4)(ii).

(3) Existing institutional emergency stationary RICE located at an area source of HAP emissions that do not operate for the purpose specified in §63.6640(f)(4)(ii).

[69 FR 33506, June 15, 2004, as amended at 73 FR 3603, Jan. 18, 2008; 78 FR 6700, Jan. 30, 2013; 87 FR 48607, Aug. 10, 2022]

§ 63.6590 What parts of my plant does this subpart cover?

This subpart applies to each affected source.

(a) *Affected source.* An affected source is any existing, new, or reconstructed stationary RICE located at a major or area source of HAP emissions, excluding stationary RICE being tested at a stationary RICE test cell/stand.

(1) *Existing stationary RICE.*

(i) For stationary RICE with a site rating of more than 500 brake horsepower (HP) located at a major source of HAP emissions, a stationary RICE is existing if you commenced construction or reconstruction of the stationary RICE before December 19, 2002.

(ii) For stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions, a stationary RICE is existing if you commenced construction or

reconstruction of the stationary RICE before June 12, 2006.

(iii) For stationary RICE located at an area source of HAP emissions, a stationary RICE is existing if you commenced construction or reconstruction of the stationary RICE before June 12, 2006.

(iv) A change in ownership of an existing stationary RICE does not make that stationary RICE a new or reconstructed stationary RICE.

(2) *New stationary RICE.* (i) A stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions is new if you commenced construction of the stationary RICE on or after December 19, 2002.

(ii) A stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions is new if you commenced construction of the stationary RICE on or after June 12, 2006.

(iii) A stationary RICE located at an area source of HAP emissions is new if you commenced construction of the stationary RICE on or after June 12, 2006.

(3) *Reconstructed stationary RICE.* (i) A stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions is reconstructed if you meet the definition of reconstruction in §63.2 and reconstruction is commenced on or after December 19, 2002.

(ii) A stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions is reconstructed if you meet the definition of reconstruction in §63.2 and reconstruction is commenced on or after June 12, 2006.

(iii) A stationary RICE located at an area source of HAP emissions is reconstructed if you meet the definition of reconstruction in §63.2 and reconstruction is commenced on or after June 12, 2006.

(b) *Stationary RICE subject to limited requirements.* (1) An affected source which meets either of the criteria in paragraphs (b)(1)(i) through (ii) of this section does not have to meet the requirements of this subpart and of subpart A of this part except for the initial notification requirements of §63.6645(f).

(i) The stationary RICE is a new or reconstructed emergency stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions.

(ii) The stationary RICE is a new or reconstructed limited use stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions.

(2) A new or reconstructed stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions which combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis must meet the initial notification requirements of §63.6645(f) and the requirements of §§63.6625(c), 63.6650(g), and 63.6655(c). These stationary RICE do not have to meet the emission limitations and operating limitations of this subpart.

(3) The following stationary RICE do not have to meet the requirements of this subpart and of subpart A of this part, including initial notification requirements:

(i) Existing spark ignition 2 stroke lean burn (2SLB) stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions;

(ii) Existing spark ignition 4 stroke lean burn (4SLB) stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions;

(iii) Existing emergency stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions.

(iv) Existing limited use stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions;

(v) Existing stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions that combusts landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis;

(c) *Stationary RICE subject to Regulations under 40 CFR Part 60.* An affected source that meets any of the criteria in paragraphs (c)(1) through (7) of this

section must meet the requirements of this part by meeting the requirements of 40 CFR part 60 subpart IIII, for compression ignition engines or 40 CFR part 60 subpart JJJJ, for spark ignition engines. No further requirements apply for such engines under this part.

(1) A new or reconstructed stationary RICE located at an area source;

(2) A new or reconstructed 2SLB stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions;

(3) A new or reconstructed 4SLB stationary RICE with a site rating of less than 250 brake HP located at a major source of HAP emissions;

(4) A new or reconstructed spark ignition 4 stroke rich burn (4SRB) stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions;

(5) A new or reconstructed stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions which combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis;

(6) A new or reconstructed emergency or limited use stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions;

(7) A new or reconstructed compression ignition (CI) stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions.

[69 FR 33506, June 15, 2004, as amended at 73 FR 3604, Jan. 18, 2008; 75 FR 9674, Mar. 3, 2010; 75 FR 37733, June 30, 2010; 75 FR 51588, Aug. 20, 2010; 78 FR 6700, Jan. 30, 2013; 87 FR 48607, Aug. 10, 2022]

§ 63.6595 When do I have to comply with this subpart?

(a) *Affected sources.* (1) If you have an existing stationary RICE, excluding existing non-emergency CI stationary RICE, with a site rating of more than 500 brake HP located at a major source of HAP emissions, you must comply with the applicable emission limitations, operating limitations and other requirements no later than June 15, 2007. If you have an existing non-emergency CI stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, an existing stationary CI RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions, or an existing stationary CI RICE located at an area source of HAP emissions, you must comply with the applicable emission limitations, operating limitations, and other requirements no later than May 3, 2013. If you have an existing stationary SI RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions, or an existing stationary SI RICE located at an area source of HAP emissions, you must comply with the applicable emission limitations, operating limitations, and other requirements no later than October 19, 2013.

(2) If you start up your new or reconstructed stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions before August 16, 2004, you must comply with the applicable emission limitations and operating limitations in this subpart no later than August 16, 2004.

(3) If you start up your new or reconstructed stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions after August 16, 2004, you must comply with the applicable emission limitations and operating limitations in this subpart upon startup of your affected source.

(4) If you start up your new or reconstructed stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions before January 18, 2008, you must comply with the applicable emission limitations and operating limitations in this subpart no later than January 18, 2008.

(5) If you start up your new or reconstructed stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions after January 18, 2008, you must comply with the applicable emission limitations and operating limitations in this subpart upon startup of your affected source.

(6) If you start up your new or reconstructed stationary RICE located at an area source of HAP emissions before

January 18, 2008, you must comply with the applicable emission limitations and operating limitations in this subpart no later than January 18, 2008.

(7) If you start up your new or reconstructed stationary RICE located at an area source of HAP emissions after January 18, 2008, you must comply with the applicable emission limitations and operating limitations in this subpart upon startup of your affected source.

(b) *Area sources that become major sources.* If you have an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP, the compliance dates in paragraphs (b)(1) and (2) of this section apply to you.

(1) Any stationary RICE for which construction or reconstruction is commenced after the date when your area source becomes a major source of HAP must be in compliance with this subpart upon startup of your affected source.

(2) Any stationary RICE for which construction or reconstruction is commenced before your area source becomes a major source of HAP must be in compliance with the provisions of this subpart that are applicable to RICE located at major sources within 3 years after your area source becomes a major source of HAP.

(c) If you own or operate an affected source, you must meet the applicable notification requirements in §63.6645 and in 40 CFR part 63, subpart A.

[69 FR 33506, June 15, 2004, as amended at 73 FR 3604, Jan. 18, 2008; 75 FR 9675, Mar. 3, 2010; 75 FR 51589, Aug. 20, 2010; 78 FR 6701, Jan. 30, 2013]

EMISSION AND OPERATING LIMITATIONS

§63.6600 What emission limitations and operating limitations must I meet if I own or operate a stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions?

Compliance with the numerical emission limitations established in this subpart is based on the results of testing the average of three 1-hour runs using the testing requirements and procedures in §63.6620 and Table 4 to this subpart.

(a) If you own or operate an existing, new, or reconstructed spark ignition 4SRB stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you must comply with the emission limitations in Table 1a to this subpart and the operating limitations in Table 1b to this subpart which apply to you.

(b) If you own or operate a new or reconstructed 2SLB stationary RICE with a site rating of more than 500 brake HP located at major source of HAP emissions, a new or reconstructed 4SLB stationary RICE with a site rating of more than 500 brake HP located at major source of HAP emissions, or a new or reconstructed CI stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you must comply with the emission limitations in Table 2a to this subpart and the operating limitations in Table 2b to this subpart which apply to you.

(c) If you own or operate any of the following stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you do not need to comply with the emission limitations in Tables 1a, 2a, 2c, and 2d to this subpart or operating limitations in Tables 1b and 2b to this subpart: an existing 2SLB stationary RICE; an existing 4SLB stationary RICE; a stationary RICE that combusts landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis; an emergency stationary RICE; or a limited use stationary RICE.

(d) If you own or operate an existing non-emergency stationary CI RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you must comply with the emission limitations in Table 2c to this subpart and the operating limitations in Table 2b to this subpart which apply to you.

[73 FR 3605, Jan. 18, 2008, as amended at 75 FR 9675, Mar. 3, 2010]

§ 63.6601 What emission limitations must I meet if I own or operate a new or reconstructed 4SLB stationary RICE with a site rating of greater than or equal to 250 brake HP and less than or equal to 500 brake HP located at a major source of HAP emissions?

Compliance with the numerical emission limitations established in this subpart is based on the results of testing the average of three 1-hour runs using the testing requirements and procedures in § 63.6620 and Table 4 to this subpart. If you own or operate a new or reconstructed 4SLB stationary RICE with a site rating of greater than or equal to 250 and less than or equal to 500 brake HP located at major source of HAP emissions manufactured on or after January 1, 2008, you must comply with the emission limitations in Table 2a to this subpart and the operating limitations in Table 2b to this subpart which apply to you.

[73 FR 3605, Jan. 18, 2008, as amended at 75 FR 9675, Mar. 3, 2010; 75 FR 51589, Aug. 20, 2010]

§ 63.6602 What emission limitations and other requirements must I meet if I own or operate an existing stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions?

If you own or operate an existing stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions, you must comply with the emission limitations and other requirements in Table 2c to this subpart which apply to you. Compliance with the numerical emission limitations established in this subpart is based on the results of testing the average of three 1-hour runs using the testing requirements and procedures in § 63.6620 and Table 4 to this subpart.

[78 FR 6701, Jan. 30, 2013]

§ 63.6603 What emission limitations, operating limitations, and other requirements must I meet if I own or operate an existing stationary RICE located at an area source of HAP emissions?

Compliance with the numerical emission limitations established in this subpart is based on the results of testing the average of three 1-hour runs using the testing requirements and procedures in § 63.6620 and Table 4 to this subpart.

(a) If you own or operate an existing stationary RICE located at an area source of HAP emissions, you must comply with the requirements in Table 2d to this subpart and the operating limitations in Table 2b to this subpart that apply to you.

(b) If you own or operate an existing stationary non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP that meets either paragraph (b)(1) or (2) of this section, you do not have to meet the numerical CO emission limitations specified in Table 2d of this subpart. Existing stationary non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP that meet either paragraph (b)(1) or (2) of this section must meet the management practices that are shown for stationary non-emergency CI RICE with a site rating of less than or equal to 300 HP in Table 2d of this subpart.

(1) The area source is located in an area of Alaska that is not accessible by the Federal Aid Highway System (FAHS).

(2) The stationary RICE is located at an area source that meets paragraphs (b)(2)(i), (ii), and (iii) of this section.

(i) The only connection to the FAHS is through the Alaska Marine Highway System (AMHS), or the stationary RICE operation is within an isolated grid in Alaska that is not connected to the statewide electrical grid referred to as the Alaska Railbelt Grid.

(ii) At least 10 percent of the power generated by the stationary RICE on an annual basis is used for residential purposes.

(iii) The generating capacity of the area source is less than 12 megawatts, or the stationary RICE is used exclusively for backup power for renewable energy.

(c) If you own or operate an existing stationary non-emergency CI RICE with a site rating of more than 300 HP located on an offshore vessel that is an area source of HAP and is a nonroad vehicle that is an Outer Continental Shelf (OCS) source as defined in 40 CFR

55.2, you do not have to meet the numerical CO emission limitations specified in Table 2d of this subpart. You must meet all of the following management practices:

(1) Change oil every 1,000 hours of operation or annually, whichever comes first. Sources have the option to utilize an oil analysis program as described in § 63.6625(i) in order to extend the specified oil change requirement.

(2) Inspect and clean air filters every 750 hours of operation or annually, whichever comes first, and replace as necessary.

(3) Inspect fuel filters and belts, if installed, every 750 hours of operation or annually, whichever comes first, and replace as necessary.

(4) Inspect all flexible hoses every 1,000 hours of operation or annually, whichever comes first, and replace as necessary.

(d) If you own or operate an existing non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP emissions that is certified to the Tier 1 or Tier 2 emission standards in Table 1 of 40 CFR 89.112 and that is subject to an enforceable state or local standard that requires the engine to be replaced no later than June 1, 2018, you may until January 1, 2015, or 12 years after the installation date of the engine (whichever is later), but not later than June 1, 2018, choose to comply with the management practices that are shown for stationary non-emergency CI RICE with a site rating of less than or equal to 300 HP in Table 2d of this subpart instead of the applicable emission limitations in Table 2d, operating limitations in Table 2b, and crankcase ventilation system requirements in § 63.6625(g). You must comply with the emission limitations in Table 2d and operating limitations in Table 2b that apply for non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP emissions by January 1, 2015, or 12 years after the installation date of the engine (whichever is later), but not later than June 1, 2018. You must also comply with the crankcase ventilation system requirements in § 63.6625(g) by January 1, 2015, or 12 years after the installation date of the engine (whichever is later), but not later than June 1, 2018.

(e) If you own or operate an existing non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP emissions that is certified to the Tier 3 (Tier 2 for engines above 560 kilowatt (kW)) emission standards in Table 1 of 40 CFR 89.112, you may comply with the requirements under this part by meeting the requirements for Tier 3 engines (Tier 2 for engines above 560 kW) in 40 CFR part 60 subpart IIII instead of the emission limitations and other requirements that would otherwise apply under this part for existing non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP emissions.

(f) An existing non-emergency SI 4SLB and 4SRB stationary RICE with a site rating of more than 500 HP located at area sources of HAP must meet the definition of remote stationary RICE in § 63.6675 on the initial compliance date for the engine, October 19, 2013, in order to be considered a remote stationary RICE under this subpart. Owners and operators of existing non-emergency SI 4SLB and 4SRB stationary RICE with a site rating of more than 500 HP located at area sources of HAP that meet the definition of remote stationary RICE in § 63.6675 of this subpart as of October 19, 2013 must evaluate the status of their stationary RICE every 12 months. Owners and operators must keep records of the initial and annual evaluation of the status of the engine. If the evaluation indicates that the stationary RICE no longer meets the definition of remote stationary RICE in § 63.6675 of this subpart, the owner or operator must comply with all of the requirements for existing non-emergency SI 4SLB and 4SRB stationary RICE with a site rating of more than 500 HP located at area sources of HAP that are not remote stationary RICE within 1 year of the evaluation.

[75 FR 9675, Mar. 3, 2010, as amended at 75 FR 51589, Aug. 20, 2010; 76 FR 12866, Mar. 9, 2011; 78 FR 6701, Jan. 30, 2013]

§ 63.6604 What fuel requirements must I meet if I own or operate a stationary CI RICE?

(a) If you own or operate an existing non-emergency, non-black start CI stationary RICE with a site rating of more than 300 brake HP with a displacement of less than 30 liters per cylinder that uses diesel fuel, you must use diesel fuel that meets the requirements in 40 CFR 1090.305 for nonroad diesel fuel.

(b) Beginning January 1, 2015, if you own or operate an existing emergency CI stationary RICE with a site rating of more than 100 brake HP and a displacement of less than 30 liters per cylinder that uses diesel fuel and operates for the purpose specified in § 63.6640(f)(4)(ii), you must use diesel fuel that meets the requirements in 40 CFR 1090.305 for nonroad diesel fuel, except that any existing diesel fuel purchased (or otherwise obtained) prior to January 1, 2015, may be used until depleted.

(c) [Reserved]

(d) Existing CI stationary RICE located in Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, at area sources in areas of Alaska that meet either § 63.6603(b)(1) or § 63.6603(b)(2), or are on offshore vessels that meet § 63.6603(c) are exempt from the requirements of this section.

[78 FR 6702, Jan. 30, 2013, as amended at 85 FR 78463, Dec. 4, 2020; 87 FR 48607, Aug. 10, 2022]

General Compliance Requirements

§ 63.6605 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the emission limitations, operating limitations, and other requirements in this subpart that apply to you at all times.

(b) At all times you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by this standard have been achieved. Determination of whether such operation and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

[75 FR 9675, Mar. 3, 2010, as amended at 78 FR 6702, Jan. 30, 2013]

Testing and Initial Compliance Requirements

§ 63.6610 By what date must I conduct the initial performance tests or other initial compliance demonstrations if I own or operate a stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions?

If you own or operate a stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions you are subject to the requirements of this section.

(a) You must conduct the initial performance test or other initial compliance demonstrations in Table 4 to this subpart that apply to you within 180 days after the compliance date that is specified for your stationary RICE in § 63.6595 and according to the provisions in § 63.7(a)(2).

(b) If you commenced construction or reconstruction between December 19, 2002 and June 15, 2004 and own or operate stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you must demonstrate initial compliance with either the proposed emission limitations or the promulgated emission limitations no later than February 10, 2005 or no later than 180 days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

(c) If you commenced construction or reconstruction between December 19, 2002 and June 15, 2004 and own or operate stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, and you chose to comply with the proposed emission limitations when demonstrating initial compliance, you must conduct a second performance test to demonstrate compliance with

the promulgated emission limitations by December 13, 2007 or after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

(d) An owner or operator is not required to conduct an initial performance test on units for which a performance test has been previously conducted, but the test must meet all of the conditions described in paragraphs (d)(1) through (5) of this section.

(1) The test must have been conducted using the same methods specified in this subpart, and these methods must have been followed correctly.

(2) The test must not be older than 2 years.

(3) The test must be reviewed and accepted by the Administrator.

(4) Either no process or equipment changes must have been made since the test was performed, or the owner or operator must be able to demonstrate that the results of the performance test, with or without adjustments, reliably demonstrate compliance despite process or equipment changes.

(5) The test must be conducted at any load condition within plus or minus 10 percent of 100 percent load.

[69 FR 33506, June 15, 2004, as amended at 73 FR 3605, Jan. 18, 2008]

§ 63.6611 By what date must I conduct the initial performance tests or other initial compliance demonstrations if I own or operate a new or reconstructed 4SLB SI stationary RICE with a site rating of greater than or equal to 250 and less than or equal to 500 brake HP located at a major source of HAP emissions?

If you own or operate a new or reconstructed 4SLB stationary RICE with a site rating of greater than or equal to 250 and less than or equal to 500 brake HP located at a major source of HAP emissions, you must conduct an initial performance test within 240 days after the compliance date that is specified for your stationary RICE in § 63.6595 and according to the provisions specified in Table 4 to this subpart, as appropriate.

[73 FR 3605, Jan. 18, 2008, as amended at 75 FR 51589, Aug. 20, 2010]

§ 63.6612 By what date must I conduct the initial performance tests or other initial compliance demonstrations if I own or operate an existing stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions or an existing stationary RICE located at an area source of HAP emissions?

If you own or operate an existing stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions or an existing stationary RICE located at an area source of HAP emissions you are subject to the requirements of this section.

(a) You must conduct any initial performance test or other initial compliance demonstration according to Tables 4 and 5 to this subpart that apply to you within 180 days after the compliance date that is specified for your stationary RICE in § 63.6595 and according to the provisions in § 63.7(a)(2).

(b) An owner or operator is not required to conduct an initial performance test on a unit for which a performance test has been previously conducted, but the test must meet all of the conditions described in paragraphs (b)(1) through (4) of this section.

(1) The test must have been conducted using the same methods specified in this subpart, and these methods must have been followed correctly.

(2) The test must not be older than 2 years.

(3) The test must be reviewed and accepted by the Administrator.

(4) Either no process or equipment changes must have been made since the test was performed, or the owner or operator must be able to demonstrate that the results of the performance test, with or without adjustments, reliably demonstrate compliance despite process or equipment changes.

[75 FR 9676, Mar. 3, 2010, as amended at 75 FR 51589, Aug. 20, 2010]

§ 63.6615 When must I conduct subsequent performance tests?

If you must comply with the emission limitations and operating limitations, you must conduct subsequent performance tests as specified in Table 3 of this subpart.

§ 63.6620 What performance tests and other procedures must I use?

(a) You must conduct each performance test in Tables 3 and 4 of this subpart that applies to you.

(b) Each performance test must be conducted according to the requirements that this subpart specifies in Table 4 to this subpart. If you own or operate a non-operational stationary RICE that is subject to performance testing, you do not need to start up the engine solely to conduct the performance test. Owners and operators of a non-operational engine can conduct the performance test when the engine is started up again. The test must be conducted at any load condition within plus or minus 10 percent of 100 percent load for the stationary RICE listed in paragraphs (b)(1) through (4) of this section.

(1) Non-emergency 4SRB stationary RICE with a site rating of greater than 500 brake HP located at a major source of HAP emissions.

(2) New non-emergency 4SLB stationary RICE with a site rating of greater than or equal to 250 brake HP located at a major source of HAP emissions.

(3) New non-emergency 2SLB stationary RICE with a site rating of greater than 500 brake HP located at a major source of HAP emissions.

(4) New non-emergency CI stationary RICE with a site rating of greater than 500 brake HP located at a major source of HAP emissions.

(c) [Reserved]

(d) You must conduct three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour, unless otherwise specified in this subpart.

(e)(1) You must use Equation 1 of this section to determine compliance with the percent reduction requirement:

$$\frac{C_i - C_o}{C_i} \times 100 = R \quad (Eq.\ 1)$$

Where:

C_i = concentration of carbon monoxide (CO), total hydrocarbons (THC), or formaldehyde at the control device inlet,

C_o = concentration of CO, THC, or formaldehyde at the control device outlet, and

R = percent reduction of CO, THC, or formaldehyde emissions.

(2) You must normalize the CO, THC, or formaldehyde concentrations at the inlet and outlet of the control device to a dry basis and to 15 percent oxygen, or an equivalent percent carbon dioxide (CO_2). If pollutant concentrations are to be corrected to 15 percent oxygen and CO_2 concentration is measured in lieu of oxygen concentration measurement, a CO_2 correction factor is needed. Calculate the CO_2 correction factor as described in paragraphs (e)(2)(i) through (iii) of this section.

(i) Calculate the fuel-specific F_o value for the fuel burned during the test using values obtained from Method 19, Section 5.2, and the following equation:

$$F_o = \frac{0.209\ F_d}{F_c} \quad (Eq.\ 2)$$

Where:

F_o = Fuel factor based on the ratio of oxygen volume to the ultimate CO_2 volume produced by the fuel at zero percent excess air.

0.209 = Fraction of air that is oxygen, percent/100.

F_d = Ratio of the volume of dry effluent gas to the gross calorific value of the fuel from Method 19, dsm^3/J ($dscf/10^6$ Btu).

F_c = Ratio of the volume of CO_2 produced to the gross calorific value of the fuel from Method 19, dsm^3/J ($dscf/10^6$ Btu)

(ii) Calculate the CO_2 correction factor for correcting measurement data to 15 percent O_2, as follows:

$$X_{CO2} = \frac{5.9}{F_O} \quad (Eq. 3)$$

Where:

X_{CO2} = CO_2 correction factor, percent.

5.9 = 20.9 percent O_2—15 percent O_2, the defined O_2 correction value, percent.

(iii) Calculate the CO, THC, and formaldehyde gas concentrations adjusted to 15 percent O_2 using CO_2 as follows:

$$C_{adj} = C_d \frac{X_{CO2}}{\%CO_2} \quad (Eq. 4)$$

Where:

C_{adj} = Calculated concentration of CO, THC, or formaldehyde adjusted to 15 percent O_2.

C_d = Measured concentration of CO, THC, or formaldehyde, uncorrected.

X_{CO2} = CO_2 correction factor, percent.

$\%CO_2$ = Measured CO_2 concentration measured, dry basis, percent.

(f) If you comply with the emission limitation to reduce CO and you are not using an oxidation catalyst, if you comply with the emission limitation to reduce formaldehyde and you are not using NSCR, or if you comply with the emission limitation to limit the concentration of formaldehyde in the stationary RICE exhaust and you are not using an oxidation catalyst or NSCR, you must petition the Administrator for operating limitations to be established during the initial performance test and continuously monitored thereafter; or for approval of no operating limitations. You must not conduct the initial performance test until after the petition has been approved by the Administrator.

(g) If you petition the Administrator for approval of operating limitations, your petition must include the information described in paragraphs (g)(1) through (5) of this section.

(1) Identification of the specific parameters you propose to use as operating limitations;

(2) A discussion of the relationship between these parameters and HAP emissions, identifying how HAP emissions change with changes in these parameters, and how limitations on these parameters will serve to limit HAP emissions;

(3) A discussion of how you will establish the upper and/or lower values for these parameters which will establish the limits on these parameters in the operating limitations;

(4) A discussion identifying the methods you will use to measure and the instruments you will use to monitor these parameters, as well as the relative accuracy and precision of these methods and instruments; and

(5) A discussion identifying the frequency and methods for recalibrating the instruments you will use for monitoring these parameters.

(h) If you petition the Administrator for approval of no operating limitations, your petition must include the information described in paragraphs (h)(1) through (7) of this section.

(1) Identification of the parameters associated with operation of the stationary RICE and any emission control device which could change intentionally (*e.g.*, operator adjustment, automatic controller adjustment, etc.) or unintentionally (*e.g.*, wear and tear, error, etc.) on a routine basis or over time;

(2) A discussion of the relationship, if any, between changes in the parameters and changes in HAP emissions;

(3) For the parameters which could change in such a way as to increase HAP emissions, a discussion of whether establishing limitations on the parameters would serve to limit HAP emissions;

(4) For the parameters which could change in such a way as to increase HAP emissions, a discussion of how you could establish upper and/or lower values for the parameters which would establish limits on the parameters in operating limitations;

(5) For the parameters, a discussion identifying the methods you could use to measure them and the instruments you could use to monitor them, as well as the relative accuracy and precision of the methods and instruments;

(6) For the parameters, a discussion identifying the frequency and methods for recalibrating the instruments you could use to monitor them; and

(7) A discussion of why, from your point of view, it is infeasible or unreasonable to adopt the parameters as operating limitations.

(i) The engine percent load during a performance test must be determined by documenting the calculations, assumptions, and measurement devices used to measure or estimate the percent load in a specific application. A written report of the average percent load determination must be included in the notification of compliance status. The following information must be included in the written report: the engine model number, the engine manufacturer, the year of purchase, the manufacturer's site-rated brake horsepower, the ambient temperature, pressure, and humidity during the performance test, and all assumptions that were made to estimate or calculate percent load during the performance test must be clearly explained. If measurement devices such as flow meters, kilowatt meters, beta analyzers, stain gauges, etc. are used, the model number of the measurement device, and an estimate of its accurate in percentage of true value must be provided.

[69 FR 33506, June 15, 2004, as amended at 75 FR 9676, Mar. 3, 2010; 78 FR 6702, Jan. 30, 2013]

§ 63.6625 What are my monitoring, installation, collection, operation, and maintenance requirements?

(a) If you elect to install a CEMS as specified in Table 5 of this subpart, you must install, operate, and maintain a CEMS to monitor CO and either O_2 or CO_2 according to the requirements in paragraphs (a)(1) through (4) of this section. If you are meeting a requirement to reduce CO emissions, the CEMS must be installed at both the inlet and outlet of the control device. If you are meeting a requirement to limit the concentration of CO, the CEMS must be installed at the outlet of the control device.

(1) Each CEMS must be installed, operated, and maintained according to the applicable performance specifications of 40 CFR part 60, appendix B.

(2) You must conduct an initial performance evaluation and an annual relative accuracy test audit (RATA) of each CEMS according to the requirements in § 63.8 and according to the applicable performance specifications of 40 CFR part 60, appendix B as well as daily and periodic data quality checks in accordance with 40 CFR part 60, appendix F, procedure 1.

(3) As specified in § 63.8(c)(4)(ii), each CEMS must complete a minimum of one cycle of operation (sampling, analyzing, and data recording) for each successive 15-minute period. You must have at least two data points, with each representing a different 15-minute period, to have a valid hour of data.

(4) The CEMS data must be reduced as specified in § 63.8(g)(2) and recorded in parts per million or parts per billion (as appropriate for the applicable limitation) at 15 percent oxygen or the equivalent CO_2 concentration.

(b) If you are required to install a continuous parameter monitoring system (CPMS) as specified in Table 5 of this subpart, you must install, operate, and maintain each CPMS according to the requirements in paragraphs (b)(1) through (6) of this section. For an affected source that is complying with the emission limitations and operating limitations on March 9, 2011, the requirements in paragraph (b) of this section are applicable September 6, 2011.

(1) You must prepare a site-specific monitoring plan that addresses the

monitoring system design, data collection, and the quality assurance and quality control elements outlined in paragraphs (b)(1)(i) through (v) of this section and in § 63.8(d). As specified in § 63.8(f)(4), you may request approval of monitoring system quality assurance and quality control procedures alternative to those specified in paragraphs (b)(1) through (5) of this section in your site-specific monitoring plan.

(i) The performance criteria and design specifications for the monitoring system equipment, including the sample interface, detector signal analyzer, and data acquisition and calculations;

(ii) Sampling interface (*e.g.*, thermocouple) location such that the monitoring system will provide representative measurements;

(iii) Equipment performance evaluations, system accuracy audits, or other audit procedures;

(iv) Ongoing operation and maintenance procedures in accordance with provisions in § 63.8(c)(1)(ii) and (c)(3); and

(v) Ongoing reporting and recordkeeping procedures in accordance with provisions in § 63.10(c), (e)(1), and (e)(2)(i).

(2) You must install, operate, and maintain each CPMS in continuous operation according to the procedures in your site-specific monitoring plan.

(3) The CPMS must collect data at least once every 15 minutes (see also § 63.6635).

(4) For a CPMS for measuring temperature range, the temperature sensor must have a minimum tolerance of 2.8 degrees Celsius (5 degrees Fahrenheit) or 1 percent of the measurement range, whichever is larger.

(5) You must conduct the CPMS equipment performance evaluation, system accuracy audits, or other audit procedures specified in your site-specific monitoring plan at least annually.

(6) You must conduct a performance evaluation of each CPMS in accordance with your site-specific monitoring plan.

(c) If you are operating a new or reconstructed stationary RICE which fires landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, you must monitor and record your fuel usage daily with separate fuel meters to measure the volumetric flow rate of each fuel. In addition, you must operate your stationary RICE in a manner which reasonably minimizes HAP emissions.

(d) If you are operating a new or reconstructed emergency 4SLB stationary RICE with a site rating of greater than or equal to 250 and less than or equal to 500 brake HP located at a major source of HAP emissions, you must install a non-resettable hour meter prior to the startup of the engine.

(e) If you own or operate any of the following stationary RICE, you must operate and maintain the stationary RICE and after-treatment control device (if any) according to the manufacturer's emission-related written instructions or develop your own maintenance plan which must provide to the extent practicable for the maintenance and operation of the engine in a manner consistent with good air pollution control practice for minimizing emissions:

(1) An existing stationary RICE with a site rating of less than 100 HP located at a major source of HAP emissions;

(2) An existing emergency or black start stationary RICE with a site rating of less than or equal to 500 HP located at a major source of HAP emissions;

(3) An existing emergency or black start stationary RICE located at an area source of HAP emissions;

(4) An existing non-emergency, non-black start stationary CI RICE with a site rating less than or equal to 300 HP located at an area source of HAP emissions;

(5) An existing non-emergency, non-black start 2SLB stationary RICE located at an area source of HAP emissions;

(6) An existing non-emergency, non-black start stationary RICE located at an area source of HAP emissions which combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis.

(7) An existing non-emergency, non-black start 4SLB stationary RICE with a site rating less than or equal to 500 HP located at an area source of HAP emissions;

(8) An existing non-emergency, non-black start 4SRB stationary RICE with a site rating less than or equal to 500 HP located at an area source of HAP emissions;

(9) An existing, non-emergency, non-black start 4SLB stationary RICE with a site rating greater than 500 HP located at an area source of HAP emissions that is operated 24 hours or less per calendar year; and

(10) An existing, non-emergency, non-black start 4SRB stationary RICE with a site rating greater than 500 HP located at an area source of HAP emissions that is operated 24 hours or less per calendar year.

(f) If you own or operate an existing emergency stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions or an existing emergency stationary RICE located at an area source of HAP emissions, you must install a non-resettable hour meter if one is not already installed.

(g) If you own or operate an existing non-emergency, non-black start CI engine greater than or equal to 300 HP that is not equipped with a closed crankcase ventilation system, you must comply with either paragraph (g)(1) or paragraph (2) of this section. Owners and operators must follow the manufacturer's specified maintenance requirements for operating and maintaining the open or closed crankcase ventilation systems and replacing the crankcase filters, or can request the Administrator to approve different maintenance requirements that are as protective as manufacturer requirements. Existing CI engines located at area sources in areas of Alaska that meet either § 63.6603(b)(1) or § 63.6603(b)(2) do not have to meet the requirements of this paragraph (g). Existing CI engines located on offshore vessels that meet § 63.6603(c) do not have to meet the requirements of this paragraph (g).

(1) Install a closed crankcase ventilation system that prevents crankcase emissions from being emitted to the atmosphere, or

(2) Install an open crankcase filtration emission control system that reduces emissions from the crankcase by filtering the exhaust stream to remove oil mist, particulates and metals.

(h) If you operate a new, reconstructed, or existing stationary engine, you must minimize the engine's time spent at idle during startup and minimize the engine's startup time to a period needed for appropriate and safe loading of the engine, not to exceed 30 minutes, after which time the emission standards applicable to all times other than startup in Tables 1a, 2a, 2c, and 2d to this subpart apply.

(i) If you own or operate a stationary CI engine that is subject to the work, operation or management practices in items 1 or 2 of Table 2c to this subpart or in items 1 or 4 of Table 2d to this subpart, you have the option of utilizing an oil analysis program in order to extend the specified oil change requirement in Tables 2c and 2d to this subpart. The oil analysis must be performed at the same frequency specified for changing the oil in Table 2c or 2d to this subpart. The analysis program must at a minimum analyze the following three parameters: Total Base Number, viscosity, and percent water content. The condemning limits for these parameters are as follows: Total Base Number is less than 30 percent of the Total Base Number of the oil when new; viscosity of the oil has changed by more than 20 percent from the viscosity of the oil when new; or percent water content (by volume) is greater than 0.5. If all of these condemning limits are not exceeded, the engine owner or operator is not required to change the oil. If any of the limits are exceeded, the engine owner or operator must change the oil within 2 business days of receiving the results of the analysis; if the engine is not in operation when the results of the analysis are received, the engine owner or operator must change the oil within 2 business days or before commencing operation, whichever is later. The owner or operator must keep records of the parameters that are analyzed as part of the program, the results of the analysis, and the oil changes for the engine. The analysis program must be part of the maintenance plan for the engine.

(j) If you own or operate a stationary SI engine that is subject to the work, operation or management practices in

items 6, 7, or 8 of Table 2c to this subpart or in items 5, 6, 7, 9, or 11 of Table 2d to this subpart, you have the option of utilizing an oil analysis program in order to extend the specified oil change requirement in Tables 2c and 2d to this subpart. The oil analysis must be performed at the same frequency specified for changing the oil in Table 2c or 2d to this subpart. The analysis program must at a minimum analyze the following three parameters: Total Acid Number, viscosity, and percent water content. The condemning limits for these parameters are as follows: Total Acid Number increases by more than 3.0 milligrams of potassium hydroxide (KOH) per gram from Total Acid Number of the oil when new; viscosity of the oil has changed by more than 20 percent from the viscosity of the oil when new; or percent water content (by volume) is greater than 0.5. If all of these condemning limits are not exceeded, the engine owner or operator is not required to change the oil. If any of the limits are exceeded, the engine owner or operator must change the oil within 2 business days of receiving the results of the analysis; if the engine is not in operation when the results of the analysis are received, the engine owner or operator must change the oil within 2 business days or before commencing operation, whichever is later. The owner or operator must keep records of the parameters that are analyzed as part of the program, the results of the analysis, and the oil changes for the engine. The analysis program must be part of the maintenance plan for the engine.

[69 FR 33506, June 15, 2004, as amended at 73 FR 3606, Jan. 18, 2008; 75 FR 9676, Mar. 3, 2010; 75 FR 51589, Aug. 20, 2010; 76 FR 12866, Mar. 9, 2011; 78 FR 6703, Jan. 30, 2013]

§ 63.6630 How do I demonstrate initial compliance with the emission limitations, operating limitations, and other requirements?

(a) You must demonstrate initial compliance with each emission limitation, operating limitation, and other requirement that applies to you according to Table 5 of this subpart.

(b) During the initial performance test, you must establish each operating limitation in Tables 1b and 2b of this subpart that applies to you.

(c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.6645.

(d) Non-emergency 4SRB stationary RICE complying with the requirement to reduce formaldehyde emissions by 76 percent or more can demonstrate initial compliance with the formaldehyde emission limit by testing for THC instead of formaldehyde. The testing must be conducted according to the requirements in Table 4 of this subpart. The average reduction of emissions of THC determined from the performance test must be equal to or greater than 30 percent.

(e) The initial compliance demonstration required for existing non-emergency 4SLB and 4SRB stationary RICE with a site rating of more than 500 HP located at an area source of HAP that are not remote stationary RICE and that are operated more than 24 hours per calendar year must be conducted according to the following requirements:

(1) The compliance demonstration must consist of at least three test runs.

(2) Each test run must be of at least 15 minute duration, except that each test conducted using the method in appendix A to this subpart must consist of at least one measurement cycle and include at least 2 minutes of test data phase measurement.

(3) If you are demonstrating compliance with the CO concentration or CO percent reduction requirement, you must measure CO emissions using one of the CO measurement methods specified in Table 4 of this subpart, or using appendix A to this subpart.

(4) If you are demonstrating compliance with the THC percent reduction requirement, you must measure THC emissions using Method 25A, reported as propane, of 40 CFR part 60, appendix A.

(5) You must measure O_2 using one of the O_2 measurement methods specified in Table 4 of this subpart. Measurements to determine O_2 concentration must be made at the same time as the measurements for CO or THC concentration.

(6) If you are demonstrating compliance with the CO or THC percent reduction requirement, you must measure CO or THC emissions and O_2 emissions simultaneously at the inlet and outlet of the control device.

[69 FR 33506, June 15, 2004, as amended at 78 FR 6704, Jan. 30, 2013]

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.6635 How do I monitor and collect data to demonstrate continuous compliance?

(a) If you must comply with emission and operating limitations, you must monitor and collect data according to this section.

(b) Except for monitor malfunctions, associated repairs, required performance evaluations, and required quality assurance or control activities, you must monitor continuously at all times that the stationary RICE is operating. A monitoring malfunction is any sudden, infrequent, not reasonably preventable failure of the monitoring to provide valid data. Monitoring failures that are caused in part by poor maintenance or careless operation are not malfunctions.

(c) You may not use data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities in data averages and calculations used to report emission or operating levels. You must, however, use all the valid data collected during all other periods.

[69 FR 33506, June 15, 2004, as amended at 76 FR 12867, Mar. 9, 2011]

§ 63.6640 How do I demonstrate continuous compliance with the emission limitations, operating limitations, and other requirements?

(a) You must demonstrate continuous compliance with each emission limitation, operating limitation, and other requirements in Tables 1a and 1b, Tables 2a and 2b, Table 2c, and Table 2d to this subpart that apply to you according to methods specified in Table 6 to this subpart.

(b) You must report each instance in which you did not meet each emission limitation or operating limitation in Tables 1a and 1b, Tables 2a and 2b, Table 2c, and Table 2d to this subpart that apply to you. These instances are deviations from the emission and operating limitations in this subpart. These deviations must be reported according to the requirements in § 63.6650. If you change your catalyst, you must reestablish the values of the operating parameters measured during the initial performance test. When you reestablish the values of your operating parameters, you must also conduct a performance test to demonstrate that you are meeting the required emission limitation applicable to your stationary RICE.

(c) The annual compliance demonstration required for existing non-emergency 4SLB and 4SRB stationary RICE with a site rating of more than 500 HP located at an area source of HAP that are not remote stationary RICE and that are operated more than 24 hours per calendar year must be conducted according to the following requirements:

(1) The compliance demonstration must consist of at least one test run.

(2) Each test run must be of at least 15 minute duration, except that each test conducted using the method in appendix A to this subpart must consist of at least one measurement cycle and include at least 2 minutes of test data phase measurement.

(3) If you are demonstrating compliance with the CO concentration or CO percent reduction requirement, you must measure CO emissions using one of the CO measurement methods specified in Table 4 of this subpart, or using appendix A to this subpart.

(4) If you are demonstrating compliance with the THC percent reduction requirement, you must measure THC emissions using Method 25A, reported as propane, of 40 CFR part 60, appendix A.

(5) You must measure O_2 using one of the O_2 measurement methods specified in Table 4 of this subpart. Measurements to determine O_2 concentration must be made at the same time as the measurements for CO or THC concentration.

(6) If you are demonstrating compliance with the CO or THC percent reduction requirement, you must measure CO or THC emissions and O_2 emissions simultaneously at the inlet and outlet of the control device.

(7) If the results of the annual compliance demonstration show that the emissions exceed the levels specified in Table 6 of this subpart, the stationary RICE must be shut down as soon as safely possible, and appropriate corrective action must be taken (e.g., repairs, catalyst cleaning, catalyst replacement). The stationary RICE must be retested within 7 days of being restarted and the emissions must meet the levels specified in Table 6 of this subpart. If the retest shows that the emissions continue to exceed the specified levels, the stationary RICE must again be shut down as soon as safely possible, and the stationary RICE may not operate, except for purposes of startup and testing, until the owner/operator demonstrates through testing that the emissions do not exceed the levels specified in Table 6 of this subpart.

(d) For new, reconstructed, and rebuilt stationary RICE, deviations from the emission or operating limitations that occur during the first 200 hours of operation from engine startup (engine burn-in period) are not violations. Rebuilt stationary RICE means a stationary RICE that has been rebuilt as that term is defined in 40 CFR 94.11(a).

(e) You must also report each instance in which you did not meet the requirements in Table 8 to this subpart that apply to you. If you own or operate a new or reconstructed stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions (except new or reconstructed 4SLB engines greater than or equal to 250 and less than or equal to 500 brake HP), a new or reconstructed stationary RICE located at an area source of HAP emissions, or any of the following RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you do not need to comply with the requirements in Table 8 to this subpart: An existing 2SLB stationary RICE, an existing 4SLB stationary RICE, an existing emergency stationary RICE, an existing limited use stationary RICE, or an existing stationary RICE which fires landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis. If you own or operate any of the following RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you do not need to comply with the requirements in Table 8 to this subpart, except for the initial notification requirements: a new or reconstructed stationary RICE that combusts landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, a new or reconstructed emergency stationary RICE, or a new or reconstructed limited use stationary RICE.

(f) If you own or operate an emergency stationary RICE, you must operate the emergency stationary RICE according to the requirements in paragraphs (f)(1) through (4) of this section. In order for the engine to be considered an emergency stationary RICE under this subpart, any operation other than emergency operation, maintenance and testing, and operation in non-emergency situations for 50 hours per year, as described in paragraphs (f)(1) through (4), is prohibited. If you do not operate the engine according to the requirements in paragraphs (f)(1) through (4), the engine will not be considered an emergency engine under this subpart and must meet all requirements for non-emergency engines.

(1) There is no time limit on the use of emergency stationary RICE in emergency situations.

(2) You may operate your emergency stationary RICE for the purpose specified in paragraph (f)(2)(i) of this section for a maximum of 100 hours per calendar year. Any operation for non-emergency situations as allowed by paragraphs (f)(3) and (4) of this section counts as part of the 100 hours per calendar year allowed by this paragraph (f)(2).

(i) Emergency stationary RICE may be operated for maintenance checks and readiness testing, provided that the tests are recommended by federal, state or local government, the manufacturer, the vendor, the regional

transmission organization or equivalent balancing authority and transmission operator, or the insurance company associated with the engine. The owner or operator may petition the Administrator for approval of additional hours to be used for maintenance checks and readiness testing, but a petition is not required if the owner or operator maintains records indicating that federal, state, or local standards require maintenance and testing of emergency RICE beyond 100 hours per calendar year.

(ii)–(iii) [Reserved]

(3) Emergency stationary RICE located at major sources of HAP may be operated for up to 50 hours per calendar year in non-emergency situations. The 50 hours of operation in non-emergency situations are counted as part of the 100 hours per calendar year for maintenance and testing provided in paragraph (f)(2) of this section. The 50 hours per year for non-emergency situations cannot be used for peak shaving or non-emergency demand response, or to generate income for a facility to supply power to an electric grid or otherwise supply power as part of a financial arrangement with another entity.

(4) Emergency stationary RICE located at area sources of HAP may be operated for up to 50 hours per calendar year in non-emergency situations. The 50 hours of operation in non-emergency situations are counted as part of the 100 hours per calendar year for maintenance and testing provided in paragraph (f)(2) of this section. Except as provided in paragraphs (f)(4)(i) and (ii) of this section, the 50 hours per year for non-emergency situations cannot be used for peak shaving or non-emergency demand response, or to generate income for a facility to an electric grid or otherwise supply power as part of a financial arrangement with another entity.

(i) Prior to May 3, 2014, the 50 hours per year for non-emergency situations can be used for peak shaving or non-emergency demand response to generate income for a facility, or to otherwise supply power as part of a financial arrangement with another entity if the engine is operated as part of a peak shaving (load management program) with the local distribution system operator and the power is provided only to the facility itself or to support the local distribution system.

(ii) The 50 hours per year for non-emergency situations can be used to supply power as part of a financial arrangement with another entity if all of the following conditions are met:

(A) The engine is dispatched by the local balancing authority or local transmission and distribution system operator.

(B) The dispatch is intended to mitigate local transmission and/or distribution limitations so as to avert potential voltage collapse or line overloads that could lead to the interruption of power supply in a local area or region.

(C) The dispatch follows reliability, emergency operation or similar protocols that follow specific NERC, regional, state, public utility commission or local standards or guidelines.

(D) The power is provided only to the facility itself or to support the local transmission and distribution system.

(E) The owner or operator identifies and records the entity that dispatches the engine and the specific NERC, regional, state, public utility commission or local standards or guidelines that are being followed for dispatching the engine. The local balancing authority or local transmission and distribution system operator may keep these records on behalf of the engine owner or operator.

[69 FR 33506, June 15, 2004, as amended at 71 FR 20467, Apr. 20, 2006; 73 FR 3606, Jan. 18, 2008; 75 FR 9676, Mar. 3, 2010; 75 FR 51591, Aug. 20, 2010; 78 FR 6704, Jan. 30, 2013; 87 FR 48607, Aug. 10, 2022]

NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.6645 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(e), (f)(4) and (f)(6), 63.9(b) through (e), and (g) and (h) that apply to you by the dates specified if you own or operate any of the following;

(1) An existing stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions.

(2) An existing stationary RICE located at an area source of HAP emissions.

(3) A stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions.

(4) A new or reconstructed 4SLB stationary RICE with a site rating of greater than or equal to 250 HP located at a major source of HAP emissions.

(5) This requirement does not apply if you own or operate an existing stationary RICE less than 100 HP, an existing stationary emergency RICE, or an existing stationary RICE that is not subject to any numerical emission standards.

(b) As specified in § 63.9(b)(2), if you start up your stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions before the effective date of this subpart, you must submit an Initial Notification not later than December 13, 2004, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) If you start up your new or reconstructed stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions on or after August 16, 2004, you must submit an Initial Notification not later than 120 days after you become subject to this subpart.

(d) As specified in § 63.9(b)(2), if you start up your stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions before the effective date of this subpart and you are required to submit an initial notification, you must submit an Initial Notification not later than July 16, 2008, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(e) If you start up your new or reconstructed stationary RICE with a site rating of equal to or less than 500 brake HP located at a major source of HAP emissions on or after March 18, 2008 and you are required to submit an initial notification, you must submit an Initial Notification not later than 120 days after you become subject to this subpart.

(f) If you are required to submit an Initial Notification but are otherwise not affected by the requirements of this subpart, in accordance with § 63.6590(b), your notification should include the information in § 63.9(b)(2)(i) through (v), and a statement that your stationary RICE has no additional requirements and explain the basis of the exclusion (for example, that it operates exclusively as an emergency stationary RICE if it has a site rating of more than 500 brake HP located at a major source of HAP emissions).

(g) If you are required to conduct a performance test, you must submit a Notification of Intent to conduct a performance test at least 60 days before the performance test is scheduled to begin as required in § 63.7(b)(1).

(h) If you are required to conduct a performance test or other initial compliance demonstration as specified in Tables 4 and 5 to this subpart, you must submit a Notification of Compliance Status according to § 63.9(h)(2)(ii).

(1) For each initial compliance demonstration required in Table 5 to this subpart that does not include a performance test, you must submit the Notification of Compliance Status before the close of business on the 30th day following the completion of the initial compliance demonstration.

(2) For each initial compliance demonstration required in Table 5 to this subpart that includes a performance test conducted according to the requirements in Table 3 to this subpart, you must submit the Notification of Compliance Status, including the performance test results, before the close of business on the 60th day following the completion of the performance test according to § 63.10(d)(2).

(i) If you own or operate an existing non-emergency CI RICE with a site rating of more than 300 HP located at an area source of HAP emissions that is certified to the Tier 1 or Tier 2 emission standards in Table 1 of 40 CFR 89.112 and subject to an enforceable state or local standard requiring engine replacement and you intend to meet management practices rather than emission limits, as specified in § 63.6603(d), you must submit a notification by March 3, 2013, stating that you intend to use the provision in § 63.6603(d) and identifying the state or

local regulation that the engine is subject to.

[73 FR 3606, Jan. 18, 2008, as amended at 75 FR 9677, Mar. 3, 2010; 75 FR 51591, Aug. 20, 2010; 78 FR 6705, Jan. 30, 2013; 85 FR 73912, Nov. 19, 2020]

§ 63.6650 What reports must I submit and when?

(a) You must submit each report in Table 7 of this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report by the date in Table 7 of this subpart and according to the requirements in paragraphs (b)(1) through (b)(9) of this section.

(1) For semiannual Compliance reports, the first Compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.6595 and ending on June 30 or December 31, whichever date is the first date following the end of the first calendar half after the compliance date that is specified for your source in § 63.6595.

(2) For semiannual Compliance reports, the first Compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date follows the end of the first calendar half after the compliance date that is specified for your affected source in § 63.6595.

(3) For semiannual Compliance reports, each subsequent Compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) For semiannual Compliance reports, each subsequent Compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date is the first date following the end of the semiannual reporting period.

(5) For each stationary RICE that is subject to permitting regulations pursuant to 40 CFR part 70 or 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6 (a)(3)(iii)(A), you may submit the first and subsequent Compliance reports according to the dates the permitting authority has established instead of according to the dates in paragraphs (b)(1) through (b)(4) of this section.

(6) For annual Compliance reports, the first Compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.6595 and ending on December 31.

(7) For annual Compliance reports, the first Compliance report must be postmarked or delivered no later than January 31 following the end of the first calendar year after the compliance date that is specified for your affected source in § 63.6595.

(8) For annual Compliance reports, each subsequent Compliance report must cover the annual reporting period from January 1 through December 31.

(9) For annual Compliance reports, each subsequent Compliance report must be postmarked or delivered no later than January 31.

(c) The Compliance report must contain the information in paragraphs (c)(1) through (6) of this section.

(1) Company name and address.

(2) Statement by a responsible official, with that official's name, title, and signature, certifying the accuracy of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) If you had a malfunction during the reporting period, the compliance report must include the number, duration, and a brief description for each type of malfunction which occurred during the reporting period and which caused or may have caused any applicable emission limitation to be exceeded. The report must also include a description of actions taken by an owner or operator during a malfunction of an affected source to minimize emissions in accordance with § 63.6605(b), including actions taken to correct a malfunction.

(5) If there are no deviations from any emission or operating limitations that apply to you, a statement that there were no deviations from the emission or operating limitations during the reporting period.

(6) If there were no periods during which the continuous monitoring system (CMS), including CEMS and CPMS, was out-of-control, as specified in §63.8(c)(7), a statement that there were no periods during which the CMS was out-of-control during the reporting period.

(d) For each deviation from an emission or operating limitation that occurs for a stationary RICE where you are not using a CMS to comply with the emission or operating limitations in this subpart, the Compliance report must contain the information in paragraphs (c)(1) through (4) of this section and the information in paragraphs (d)(1) and (2) of this section.

(1) The total operating time of the stationary RICE at which the deviation occurred during the reporting period.

(2) Information on the number, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(e) For each deviation from an emission or operating limitation occurring for a stationary RICE where you are using a CMS to comply with the emission and operating limitations in this subpart, you must include information in paragraphs (c)(1) through (4) and (e)(1) through (12) of this section.

(1) The date and time that each malfunction started and stopped.

(2) The date, time, and duration that each CMS was inoperative, except for zero (low-level) and high-level checks.

(3) The date, time, and duration that each CMS was out-of-control, including the information in §63.8(c)(8).

(4) The date and time that each deviation started and stopped, and whether each deviation occurred during a period of malfunction or during another period.

(5) A summary of the total duration of the deviation during the reporting period, and the total duration as a percent of the total source operating time during that reporting period.

(6) A breakdown of the total duration of the deviations during the reporting period into those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(7) A summary of the total duration of CMS downtime during the reporting period, and the total duration of CMS downtime as a percent of the total operating time of the stationary RICE at which the CMS downtime occurred during that reporting period.

(8) An identification of each parameter and pollutant (CO or formaldehyde) that was monitored at the stationary RICE.

(9) A brief description of the stationary RICE.

(10) A brief description of the CMS.

(11) The date of the latest CMS certification or audit.

(12) A description of any changes in CMS, processes, or controls since the last reporting period.

(f) Each affected source that has obtained a title V operating permit pursuant to 40 CFR part 70 or 71 must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6 (a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If an affected source submits a Compliance report pursuant to Table 7 of this subpart along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the Compliance report includes all required information concerning deviations from any emission or operating limitation in this subpart, submission of the Compliance report shall be deemed to satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submission of a Compliance report shall not otherwise affect any obligation the affected source may have to report deviations from permit requirements to the permit authority.

(g) If you are operating as a new or reconstructed stationary RICE which fires landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, you must submit an annual report according to Table 7 of this subpart by the date specified unless the Administrator has approved a different schedule, according to the information described in paragraphs (b)(1) through (b)(5) of this section. You must report the data specified in (g)(1) through (g)(3) of this section.

(1) Fuel flow rate of each fuel and the heating values that were used in your

calculations. You must also demonstrate that the percentage of heat input provided by landfill gas or digester gas is equivalent to 10 percent or more of the total fuel consumption on an annual basis.

(2) The operating limits provided in your federally enforceable permit, and any deviations from these limits.

(3) Any problems or errors suspected with the meters.

(h) If you own or operate an emergency stationary RICE with a site rating of more than 100 brake HP that operates for the purpose specified in § 63.6640(f)(4)(ii), you must submit an annual report according to the requirements in paragraphs (h)(1) through (3) of this section.

(1) The report must contain the following information:

(i) Company name and address where the engine is located.

(ii) Date of the report and beginning and ending dates of the reporting period.

(iii) Engine site rating and model year.

(iv) Latitude and longitude of the engine in decimal degrees reported to the fifth decimal place.

(v)–(vi) [Reserved]

(vii) Hours spent for operation for the purpose specified in § 63.6640(f)(4)(ii), including the date, start time, and end time for engine operation for the purposes specified in § 63.6640(f)(4)(ii). The report must also identify the entity that dispatched the engine and the situation that necessitated the dispatch of the engine.

(viii) If there were no deviations from the fuel requirements in § 63.6604 that apply to the engine (if any), a statement that there were no deviations from the fuel requirements during the reporting period.

(ix) If there were deviations from the fuel requirements in § 63.6604 that apply to the engine (if any), information on the number, duration, and cause of deviations, and the corrective action taken.

(2) The first annual report must cover the calendar year 2015 and must be submitted no later than March 31, 2016. Subsequent annual reports for each calendar year must be submitted no later than March 31 of the following calendar year.

(3) The annual report must be submitted electronically using the subpart specific reporting form in the Compliance and Emissions Data Reporting Interface (CEDRI) that is accessed through EPA's Central Data Exchange (CDX) (*www.epa.gov/cdx*). However, if the reporting form specific to this subpart is not available in CEDRI at the time that the report is due, the written report must be submitted to the Administrator at the appropriate address listed in § 63.13.

[69 FR 33506, June 15, 2004, as amended at 75 FR 9677, Mar. 3, 2010; 78 FR 6705, Jan. 30, 2013; 87 FR 48607, Aug. 10, 2022]

§ 63.6655 What records must I keep?

(a) If you must comply with the emission and operating limitations, you must keep the records described in paragraphs (a)(1) through (a)(5), (b)(1) through (b)(3) and (c) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirement in § 63.10(b)(2)(xiv).

(2) Records of the occurrence and duration of each malfunction of operation (*i.e.*, process equipment) or the air pollution control and monitoring equipment.

(3) Records of performance tests and performance evaluations as required in § 63.10(b)(2)(viii).

(4) Records of all required maintenance performed on the air pollution control and monitoring equipment.

(5) Records of actions taken during periods of malfunction to minimize emissions in accordance with § 63.6605(b), including corrective actions to restore malfunctioning process and air pollution control and monitoring equipment to its normal or usual manner of operation.

(b) For each CEMS or CPMS, you must keep the records listed in paragraphs (b)(1) through (3) of this section.

(1) Records described in § 63.10(b)(2)(vi) through (xi).

(2) Previous (*i.e.*, superseded) versions of the performance evaluation plan as required in § 63.8(d)(3).

(3) Requests for alternatives to the relative accuracy test for CEMS or CPMS as required in §63.8(f)(6)(i), if applicable.

(c) If you are operating a new or reconstructed stationary RICE which fires landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, you must keep the records of your daily fuel usage monitors.

(d) You must keep the records required in Table 6 of this subpart to show continuous compliance with each emission or operating limitation that applies to you.

(e) You must keep records of the maintenance conducted on the stationary RICE in order to demonstrate that you operated and maintained the stationary RICE and after-treatment control device (if any) according to your own maintenance plan if you own or operate any of the following stationary RICE;

(1) An existing stationary RICE with a site rating of less than 100 brake HP located at a major source of HAP emissions.

(2) An existing stationary emergency RICE.

(3) An existing stationary RICE located at an area source of HAP emissions subject to management practices as shown in Table 2d to this subpart.

(f) If you own or operate any of the stationary RICE in paragraphs (f)(1) through (2) of this section, you must keep records of the hours of operation of the engine that is recorded through the non-resettable hour meter. The owner or operator must document how many hours are spent for emergency operation, including what classified the operation as emergency and how many hours are spent for non-emergency operation. If the engine is used for the purpose specified in §63.6640(f)(4)(ii), the owner or operator must keep records of the notification of the emergency situation, and the date, start time, and end time of engine operation for these purposes.

(1) An existing emergency stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions that does not meet the standards applicable to non-emergency engines.

(2) An existing emergency stationary RICE located at an area source of HAP emissions that does not meet the standards applicable to non-emergency engines.

[69 FR 33506, June 15, 2004, as amended at 75 FR 9678, Mar. 3, 2010; 75 FR 51592, Aug. 20, 2010; 78 FR 6706, Jan. 30, 2013; 87 FR 48607, Aug. 10, 2022]

§63.6660 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review according to §63.10(b)(1).

(b) As specified in §63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record readily accessible in hard copy or electronic form for at least 5 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to §63.10(b)(1).

[69 FR 33506, June 15, 2004, as amended at 75 FR 9678, Mar. 3, 2010]

OTHER REQUIREMENTS AND INFORMATION

§63.6665 What parts of the General Provisions apply to me?

Table 8 to this subpart shows which parts of the General Provisions in §§63.1 through 63.15 apply to you. If you own or operate a new or reconstructed stationary RICE with a site rating of less than or equal to 500 brake HP located at a major source of HAP emissions (except new or reconstructed 4SLB engines greater than or equal to 250 and less than or equal to 500 brake HP), a new or reconstructed stationary RICE located at an area source of HAP emissions, or any of the following RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you do not need to comply with any of the requirements of the General Provisions specified in Table 8: An existing 2SLB stationary RICE, an existing 4SLB stationary RICE, an existing stationary RICE that combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, an existing emergency stationary RICE, or an

existing limited use stationary RICE. If you own or operate any of the following RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, you do not need to comply with the requirements in the General Provisions specified in Table 8 except for the initial notification requirements: A new stationary RICE that combusts landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, a new emergency stationary RICE, or a new limited use stationary RICE.

[75 FR 9678, Mar. 3, 2010]

§ 63.6670 Who implements and enforces this subpart?

(a) This subpart is implemented and enforced by the U.S. EPA, or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency (as well as the U.S. EPA) has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out whether this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under 40 CFR part 63, subpart E, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities that will not be delegated to State, local, or tribal agencies are:

(1) Approval of alternatives to the non-opacity emission limitations and operating limitations in § 63.6600 under § 63.6(g).

(2) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(5) Approval of a performance test which was conducted prior to the effective date of the rule, as specified in § 63.6610(b).

§ 63.6675 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act (CAA); in 40 CFR 63.2, the General Provisions of this part; and in this section as follows:

Alaska Railbelt Grid means the service areas of the six regulated public utilities that extend from Fairbanks to Anchorage and the Kenai Peninsula. These utilities are Golden Valley Electric Association; Chugach Electric Association; Matanuska Electric Association; Homer Electric Association; Anchorage Municipal Light & Power; and the City of Seward Electric System.

Area source means any stationary source of HAP that is not a major source as defined in part 63.

Associated equipment as used in this subpart and as referred to in section 112(n)(4) of the CAA, means equipment associated with an oil or natural gas exploration or production well, and includes all equipment from the well bore to the point of custody transfer, except glycol dehydration units, storage vessels with potential for flash emissions, combustion turbines, and stationary RICE.

Backup power for renewable energy means an engine that provides backup power to a facility that generates electricity from renewable energy resources, as that term is defined in Alaska Statute 42.45.045(l)(5) (incorporated by reference, see § 63.14).

Black start engine means an engine whose only purpose is to start up a combustion turbine.

CAA means the Clean Air Act (42 U.S.C. 7401 *et seq.*, as amended by Public Law 101–549, 104 Stat. 2399).

Commercial emergency stationary RICE means an emergency stationary RICE used in commercial establishments such as office buildings, hotels, stores, telecommunications facilities, restaurants, financial institutions such as banks, doctor's offices, and sports and performing arts facilities.

Compression ignition means relating to a type of stationary internal combustion engine that is not a spark ignition engine.

Custody transfer means the transfer of hydrocarbon liquids or natural gas: After processing and/or treatment in the producing operations, or from storage vessels or automatic transfer facilities or other such equipment, including product loading racks, to pipelines or any other forms of transportation. For the purposes of this subpart, the point at which such liquids or natural gas enters a natural gas processing plant is a point of custody transfer.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart, including but not limited to any emission limitation or operating limitation;

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Fails to meet any emission limitation or operating limitation in this subpart during malfunction, regardless or whether or not such failure is permitted by this subpart.

(4) Fails to satisfy the general duty to minimize emissions established by §63.6(e)(1)(i).

Diesel engine means any stationary RICE in which a high boiling point liquid fuel injected into the combustion chamber ignites when the air charge has been compressed to a temperature sufficiently high for auto-ignition. This process is also known as compression ignition.

Diesel fuel means any liquid obtained from the distillation of petroleum with a boiling point of approximately 150 to 360 degrees Celsius. One commonly used form is fuel oil number 2. Diesel fuel also includes any non-distillate fuel with comparable physical and chemical properties (*e.g.* biodiesel) that is suitable for use in compression ignition engines.

Digester gas means any gaseous byproduct of wastewater treatment typically formed through the anaerobic decomposition of organic waste materials and composed principally of methane and CO_2.

Dual-fuel engine means any stationary RICE in which a liquid fuel (typically diesel fuel) is used for compression ignition and gaseous fuel (typically natural gas) is used as the primary fuel.

Emergency stationary RICE means any stationary reciprocating internal combustion engine that meets all of the criteria in paragraphs (1) through (3) of this definition. All emergency stationary RICE must comply with the requirements specified in §63.6640(f) in order to be considered emergency stationary RICE. If the engine does not comply with the requirements specified in §63.6640(f), then it is not considered to be an emergency stationary RICE under this subpart.

(1) The stationary RICE is operated to provide electrical power or mechanical work during an emergency situation. Examples include stationary RICE used to produce power for critical networks or equipment (including power supplied to portions of a facility) when electric power from the local utility (or the normal power source, if the facility runs on its own power production) is interrupted, or stationary RICE used to pump water in the case of fire or flood, etc.

(2) The stationary RICE is operated under limited circumstances for situations not included in paragraph (1) of this definition, as specified in §63.6640(f).

(3) The stationary RICE operates as part of a financial arrangement with another entity in situations not included in paragraph (1) of this definition only as allowed in §63.6640(f)(4)(i) or (ii).

Engine startup means the time from initial start until applied load and engine and associated equipment reaches steady state or normal operation. For stationary engine with catalytic controls, engine startup means the time from initial start until applied load and engine and associated equipment, including the catalyst, reaches steady state or normal operation.

Four-stroke engine means any type of engine which completes the power cycle in two crankshaft revolutions, with intake and compression strokes in

the first revolution and power and exhaust strokes in the second revolution.

Gaseous fuel means a material used for combustion which is in the gaseous state at standard atmospheric temperature and pressure conditions.

Gasoline means any fuel sold in any State for use in motor vehicles and motor vehicle engines, or nonroad or stationary engines, and commonly or commercially known or sold as gasoline.

Glycol dehydration unit means a device in which a liquid glycol (including, but not limited to, ethylene glycol, diethylene glycol, or triethylene glycol) absorbent directly contacts a natural gas stream and absorbs water in a contact tower or absorption column (absorber). The glycol contacts and absorbs water vapor and other gas stream constituents from the natural gas and becomes ''rich'' glycol. This glycol is then regenerated in the glycol dehydration unit reboiler. The ''lean'' glycol is then recycled.

Hazardous air pollutants (HAP) means any air pollutants listed in or pursuant to section 112(b) of the CAA.

Institutional emergency stationary RICE means an emergency stationary RICE used in institutional establishments such as medical centers, nursing homes, research centers, institutions of higher education, correctional facilities, elementary and secondary schools, libraries, religious establishments, police stations, and fire stations.

ISO standard day conditions means 288 degrees Kelvin (15 degrees Celsius), 60 percent relative humidity and 101.3 kilopascals pressure.

Landfill gas means a gaseous by-product of the land application of municipal refuse typically formed through the anaerobic decomposition of waste materials and composed principally of methane and CO_2.

Lean burn engine means any two-stroke or four-stroke spark ignited engine that does not meet the definition of a rich burn engine.

Limited use stationary RICE means any stationary RICE that operates less than 100 hours per year.

Liquefied petroleum gas means any liquefied hydrocarbon gas obtained as a by-product in petroleum refining of natural gas production.

Liquid fuel means any fuel in liquid form at standard temperature and pressure, including but not limited to diesel, residual/crude oil, kerosene/naphtha (jet fuel), and gasoline.

Major Source, as used in this subpart, shall have the same meaning as in § 63.2, except that:

(1) Emissions from any oil or gas exploration or production well (with its associated equipment (as defined in this section)) and emissions from any pipeline compressor station or pump station shall not be aggregated with emissions from other similar units, to determine whether such emission points or stations are major sources, even when emission points are in a contiguous area or under common control;

(2) For oil and gas production facilities, emissions from processes, operations, or equipment that are not part of the same oil and gas production facility, as defined in § 63.1271 of subpart HHH of this part, shall not be aggregated;

(3) For production field facilities, only HAP emissions from glycol dehydration units, storage vessel with the potential for flash emissions, combustion turbines and reciprocating internal combustion engines shall be aggregated for a major source determination; and

(4) Emissions from processes, operations, and equipment that are not part of the same natural gas transmission and storage facility, as defined in § 63.1271 of subpart HHH of this part, shall not be aggregated.

Malfunction means any sudden, infrequent, and not reasonably preventable failure of air pollution control equipment, process equipment, or a process to operate in a normal or usual manner which causes, or has the potential to cause, the emission limitations in an applicable standard to be exceeded. Failures that are caused in part by poor maintenance or careless operation are not malfunctions.

Natural gas means a naturally occurring mixture of hydrocarbon and nonhydrocarbon gases found in geologic formations beneath the Earth's surface, of which the principal constituent

is methane. Natural gas may be field or pipeline quality.

Non-selective catalytic reduction (NSCR) means an add-on catalytic nitrogen oxides (NO_X) control device for rich burn engines that, in a two-step reaction, promotes the conversion of excess oxygen, NO_X, CO, and volatile organic compounds (VOC) into CO_2, nitrogen, and water.

Oil and gas production facility as used in this subpart means any grouping of equipment where hydrocarbon liquids are processed, upgraded (*i.e.,* remove impurities or other constituents to meet contract specifications), or stored prior to the point of custody transfer; or where natural gas is processed, upgraded, or stored prior to entering the natural gas transmission and storage source category. For purposes of a major source determination, facility (including a building, structure, or installation) means oil and natural gas production and processing equipment that is located within the boundaries of an individual surface site as defined in this section. Equipment that is part of a facility will typically be located within close proximity to other equipment located at the same facility. Pieces of production equipment or groupings of equipment located on different oil and gas leases, mineral fee tracts, lease tracts, subsurface or surface unit areas, surface fee tracts, surface lease tracts, or separate surface sites, whether or not connected by a road, waterway, power line or pipeline, shall not be considered part of the same facility. Examples of facilities in the oil and natural gas production source category include, but are not limited to, well sites, satellite tank batteries, central tank batteries, a compressor station that transports natural gas to a natural gas processing plant, and natural gas processing plants.

Oxidation catalyst means an add-on catalytic control device that controls CO and VOC by oxidation.

Peaking unit or engine means any standby engine intended for use during periods of high demand that are not emergencies.

Percent load means the fractional power of an engine compared to its maximum manufacturer's design capacity at engine site conditions. Percent load may range between 0 percent to above 100 percent.

Potential to emit means the maximum capacity of a stationary source to emit a pollutant under its physical and operational design. Any physical or operational limitation on the capacity of the stationary source to emit a pollutant, including air pollution control equipment and restrictions on hours of operation or on the type or amount of material combusted, stored, or processed, shall be treated as part of its design if the limitation or the effect it would have on emissions is federally enforceable. For oil and natural gas production facilities subject to subpart HH of this part, the potential to emit provisions in §63.760(a) may be used. For natural gas transmission and storage facilities subject to subpart HHH of this part, the maximum annual facility gas throughput for storage facilities may be determined according to §63.1270(a)(1) and the maximum annual throughput for transmission facilities may be determined according to §63.1270(a)(2).

Production field facility means those oil and gas production facilities located prior to the point of custody transfer.

Production well means any hole drilled in the earth from which crude oil, condensate, or field natural gas is extracted.

Propane means a colorless gas derived from petroleum and natural gas, with the molecular structure C_3H_8.

Remote stationary RICE means stationary RICE meeting any of the following criteria:

(1) Stationary RICE located in an offshore area that is beyond the line of ordinary low water along that portion of the coast of the United States that is in direct contact with the open seas and beyond the line marking the seaward limit of inland waters.

(2) Stationary RICE located on a pipeline segment that meets both of the criteria in paragraphs (2)(i) and (ii) of this definition.

(i) A pipeline segment with 10 or fewer buildings intended for human occupancy and no buildings with four or more stories within 220 yards (200 meters) on either side of the centerline of

any continuous 1-mile (1.6 kilometers) length of pipeline. Each separate dwelling unit in a multiple dwelling unit building is counted as a separate building intended for human occupancy.

(ii) The pipeline segment does not lie within 100 yards (91 meters) of either a building or a small, well-defined outside area (such as a playground, recreation area, outdoor theater, or other place of public assembly) that is occupied by 20 or more persons on at least 5 days a week for 10 weeks in any 12-month period. The days and weeks need not be consecutive. The building or area is considered occupied for a full day if it is occupied for any portion of the day.

(iii) For purposes of this paragraph (2), the term pipeline segment means all parts of those physical facilities through which gas moves in transportation, including but not limited to pipe, valves, and other appurtenance attached to pipe, compressor units, metering stations, regulator stations, delivery stations, holders, and fabricated assemblies. Stationary RICE located within 50 yards (46 meters) of the pipeline segment providing power for equipment on a pipeline segment are part of the pipeline segment. Transportation of gas means the gathering, transmission, or distribution of gas by pipeline, or the storage of gas. A building is intended for human occupancy if its primary use is for a purpose involving the presence of humans.

(3) Stationary RICE that are not located on gas pipelines and that have 5 or fewer buildings intended for human occupancy and no buildings with four or more stories within a 0.25 mile radius around the engine. A building is intended for human occupancy if its primary use is for a purpose involving the presence of humans.

Residential emergency stationary RICE means an emergency stationary RICE used in residential establishments such as homes or apartment buildings.

Responsible official means responsible official as defined in 40 CFR 70.2.

Rich burn engine means any four-stroke spark ignited engine where the manufacturer's recommended operating air/fuel ratio divided by the stoichiometric air/fuel ratio at full load conditions is less than or equal to 1.1. Engines originally manufactured as rich burn engines, but modified prior to December 19, 2002 with passive emission control technology for NO_X (such as pre-combustion chambers) will be considered lean burn engines. Also, existing engines where there are no manufacturer's recommendations regarding air/fuel ratio will be considered a rich burn engine if the excess oxygen content of the exhaust at full load conditions is less than or equal to 2 percent.

Site-rated HP means the maximum manufacturer's design capacity at engine site conditions.

Spark ignition means relating to either: A gasoline-fueled engine; or any other type of engine with a spark plug (or other sparking device) and with operating characteristics significantly similar to the theoretical Otto combustion cycle. Spark ignition engines usually use a throttle to regulate intake air flow to control power during normal operation. Dual-fuel engines in which a liquid fuel (typically diesel fuel) is used for CI and gaseous fuel (typically natural gas) is used as the primary fuel at an annual average ratio of less than 2 parts diesel fuel to 100 parts total fuel on an energy equivalent basis are spark ignition engines.

Stationary reciprocating internal combustion engine (RICE) means any reciprocating internal combustion engine which uses reciprocating motion to convert heat energy into mechanical work and which is not mobile. Stationary RICE differ from mobile RICE in that a stationary RICE is not a nonroad engine as defined at 40 CFR 1068.30, and is not used to propel a motor vehicle or a vehicle used solely for competition.

Stationary RICE test cell/stand means an engine test cell/stand, as defined in subpart PPPPP of this part, that tests stationary RICE.

Stoichiometric means the theoretical air-to-fuel ratio required for complete combustion.

Storage vessel with the potential for flash emissions means any storage vessel that contains a hydrocarbon liquid with a stock tank gas-to-oil ratio equal to or greater than 0.31 cubic meters per liter and an American Petroleum Institute gravity equal to or greater than 40 degrees and an actual annual average

hydrocarbon liquid throughput equal to or greater than 79,500 liters per day. Flash emissions occur when dissolved hydrocarbons in the fluid evolve from solution when the fluid pressure is reduced.

Subpart means 40 CFR part 63, subpart ZZZZ.

Surface site means any combination of one or more graded pad sites, gravel pad sites, foundations, platforms, or the immediate physical location upon which equipment is physically affixed.

Two-stroke engine means a type of engine which completes the power cycle in single crankshaft revolution by combining the intake and compression operations into one stroke and the power and exhaust operations into a second stroke. This system requires auxiliary scavenging and inherently runs lean of stoichiometric.

[69 FR 33506, June 15, 2004, as amended at 71 FR 20467, Apr. 20, 2006; 73 FR 3607, Jan. 18, 2008; 75 FR 9679, Mar. 3, 2010; 75 FR 51592, Aug. 20, 2010; 76 FR 12867, Mar. 9, 2011; 78 FR 6706, Jan. 30, 2013; 87 FR 48608, Aug. 10, 2022]

TABLE 1a TO SUBPART ZZZZ OF PART 63—EMISSION LIMITATIONS FOR EXISTING, NEW, AND RECONSTRUCTED SPARK IGNITION, 4SRB STATIONARY RICE >500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS

As stated in §§ 63.6600 and 63.6640, you must comply with the following emission limitations at 100 percent load plus or minus 10 percent for existing, new and reconstructed 4SRB stationary RICE >500 HP located at a major source of HAP emissions:

For each . . .	You must meet the following emission limitation, except during periods of startup . . .	During periods of startup you must . . .
1. 4SRB stationary RICE	a. Reduce formaldehyde emissions by 76 percent or more. If you commenced construction or reconstruction between December 19, 2002 and June 15, 2004, you may reduce formaldehyde emissions by 75 percent or more until June 15, 2007 or. b. Limit the concentration of formaldehyde in the stationary RICE exhaust to 350 ppbvd or less at 15 percent O_2.	Minimize the engine's time spent at idle and minimize the engine's startup time at startup to a period needed for appropriate and safe loading of the engine, not to exceed 30 minutes, after which time the non-startup emission limitations apply.[1]

[1] Sources can petition the Administrator pursuant to the requirements of 40 CFR 63.6(g) for alternative work practices.

[75 FR 9679, Mar. 3, 2010, as amended at 75 FR 51592, Aug. 20, 2010]

TABLE 1b TO SUBPART ZZZZ OF PART 63—OPERATING LIMITATIONS FOR EXISTING, NEW, AND RECONSTRUCTED SI 4SRB STATIONARY RICE >500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS

As stated in §§ 63.6600, 63.6603, 63.6630 and 63.6640, you must comply with the following operating limitations for existing, new and reconstructed 4SRB stationary RICE >500 HP located at a major source of HAP emissions:

For each . . .	You must meet the following operating limitation, except during periods of startup . . .
1. existing, new and reconstructed 4SRB stationary RICE >500 HP located at a major source of HAP emissions complying with the requirement to reduce formaldehyde emissions by 76 percent or more (or by 75 percent or more, if applicable) and using NSCR; or existing, new and reconstructed 4SRB stationary RICE >500 HP located at a major source of HAP emissions complying with the requirement to limit the concentration of formaldehyde in the stationary RICE exhaust to 350 ppbvd or less at 15 percent O_2 and using NSCR;	a. maintain your catalyst so that the pressure drop across the catalyst does not change by more than 2 inches of water at 100 percent load plus or minus 10 percent from the pressure drop across the catalyst measured during the initial performance test; and b. maintain the temperature of your stationary RICE exhaust so that the catalyst inlet temperature is greater than or equal to 750 °F and less than or equal to 1250 °F.[1]
2. existing, new and reconstructed 4SRB stationary RICE >500 HP located at a major source of HAP emissions complying with the requirement to reduce formaldehyde emissions by 76 percent or more (or by 75 percent or more, if applicable) and not using NSCR; or	Comply with any operating limitations approved by the Administrator.

For each . . .	You must meet the following operating limitation, except during periods of startup . . .
existing, new and reconstructed 4SRB stationary RICE >500 HP located at a major source of HAP emissions complying with the requirement to limit the concentration of formaldehyde in the stationary RICE exhaust to 350 ppbvd or less at 15 percent O_2 and not using NSCR.	

[1] Sources can petition the Administrator pursuant to the requirements of 40 CFR 63.8(f) for a different temperature range.

[78 FR 6706, Jan. 30, 2013]

TABLE 2a TO SUBPART ZZZZ OF PART 63—EMISSION LIMITATIONS FOR NEW AND RECONSTRUCTED 2SLB AND COMPRESSION IGNITION STATIONARY RICE >500 HP AND NEW AND RECONSTRUCTED 4SLB STATIONARY RICE ≥250 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS

As stated in §§63.6600 and 63.6640, you must comply with the following emission limitations for new and reconstructed lean burn and new and reconstructed compression ignition stationary RICE at 100 percent load plus or minus 10 percent:

For each . . .	You must meet the following emission limitation, except during periods of startup . . .	During periods of startup you must . . .
1. 2SLB stationary RICE	a. Reduce CO emissions by 58 percent or more; or b. Limit concentration of formaldehyde in the stationary RICE exhaust to 12 ppmvd or less at 15 percent O_2. If you commenced construction or reconstruction between December 19, 2002 and June 15, 2004, you may limit concentration of formaldehyde to 17 ppmvd or less at 15 percent O_2 until June 15, 2007.	Minimize the engine's time spent at idle and minimize the engine's startup time at startup to a period needed for appropriate and safe loading of the engine, not to exceed 30 minutes, after which time the non-startup emission limitations apply.[1]
2. 4SLB stationary RICE	a. Reduce CO emissions by 93 percent or more; or b. Limit concentration of formaldehyde in the stationary RICE exhaust to 14 ppmvd or less at 15 percent O_2.	
3. CI stationary RICE	a. Reduce CO emissions by 70 percent or more; or b. Limit concentration of formaldehyde in the stationary RICE exhaust to 580 ppbvd or less at 15 percent O_2.	

[1] Sources can petition the Administrator pursuant to the requirements of 40 CFR 63.6(g) for alternative work practices.

[75 FR 9680, Mar. 3, 2010]

TABLE 2b TO SUBPART ZZZZ OF PART 63—OPERATING LIMITATIONS FOR NEW AND RECONSTRUCTED 2SLB AND CI STATIONARY RICE >500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS, NEW AND RECONSTRUCTED 4SLB STATIONARY RICE ≥250 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS, EXISTING CI STATIONARY RICE >500 HP

As stated in §§63.6600, 63.6601, 63.6603, 63.6630, and 63.6640, you must comply with the following operating limitations for new and reconstructed 2SLB and CI stationary RICE >500 HP located at a major source of HAP emissions; new and reconstructed 4SLB stationary RICE ≥250 HP located at a major source of HAP emissions; and existing CI stationary RICE >500 HP:

For each . . .	You must meet the following operating limitation, except during periods of startup . . .
1. New and reconstructed 2SLB and CI stationary RICE >500 HP located at a major source of HAP emissions and new and reconstructed 4SLB stationary RICE ≥250 HP located at a major source of HAP emissions complying with the requirement to reduce CO emissions and using an oxidation catalyst; and New and reconstructed 2SLB and CI stationary RICE >500 HP located at a major source of HAP emissions and new and reconstructed 4SLB stationary RICE ≥250 HP located at a major source of HAP emissions complying with the requirement to limit the concentration of formaldehyde in the stationary RICE exhaust and using an oxidation catalyst.	a. maintain your catalyst so that the pressure drop across the catalyst does not change by more than 2 inches of water at 100 percent load plus or minus 10 percent from the pressure drop across the catalyst that was measured during the initial performance test; and b. maintain the temperature of your stationary RICE exhaust so that the catalyst inlet temperature is greater than or equal to 450 °F and less than or equal to 1350 °F.[1]
2. Existing CI stationary RICE >500 HP complying with the requirement to limit or reduce the concentration of CO in the stationary RICE exhaust and using an oxidation catalyst.	a. maintain your catalyst so that the pressure drop across the catalyst does not change by more than 2 inches of water from the pressure drop across the catalyst that was measured during the initial performance test; and b. maintain the temperature of your stationary RICE exhaust so that the catalyst inlet temperature is greater than or equal to 450 °F and less than or equal to 1350 °F.[1]
3. New and reconstructed 2SLB and CI stationary RICE >500 HP located at a major source of HAP emissions and new and reconstructed 4SLB stationary RICE ≥250 HP located at a major source of HAP emissions complying with the requirement to reduce CO emissions and not using an oxidation catalyst; and New and reconstructed 2SLB and CI stationary RICE >500 HP located at a major source of HAP emissions and new and reconstructed 4SLB stationary RICE ≥250 HP located at a major source of HAP emissions complying with the requirement to limit the concentration of formaldehyde in the stationary RICE exhaust and not using an oxidation catalyst; and existing CI stationary RICE >500 HP complying with the requirement to limit or reduce the concentration of CO in the stationary RICE exhaust and not using an oxidation catalyst.	Comply with any operating limitations approved by the Administrator.

[1] Sources can petition the Administrator pursuant to the requirements of 40 CFR 63.8(f) for a different temperature range.

[78 FR 6707, Jan. 30, 2013]

TABLE 2c TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR EXISTING COMPRESSION IGNITION STATIONARY RICE LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS AND EXISTING SPARK IGNITION STATIONARY RICE ≤500 HP LOCATED AT A MAJOR SOURCE OF HAP EMISSIONS

As stated in §§ 63.6600, 63.6602, and 63.6640, you must comply with the following requirements for existing compression ignition stationary RICE located at a major source of HAP emissions and existing spark ignition stationary RICE ≤500 HP located at a major source of HAP emissions:

For each . . .	You must meet the following requirement, except during periods of startup . . .	During periods of startup you must . . .
1. Emergency stationary CI RICE and black start stationary CI RICE [1].	a. Change oil and filter every 500 hours of operation or annually, whichever comes first.[2] b. Inspect air cleaner every 1,000 hours of operation or annually, whichever comes first, and replace as necessary; c. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.[3]	Minimize the engine's time spent at idle and minimize the engine's startup time at startup to a period needed for appropriate and safe loading of the engine, not to exceed 30 minutes, after which time the non-startup emission limitations apply.[3]

For each . . .	You must meet the following requirement, except during periods of startup . . .	During periods of startup you must . . .
2. Non-Emergency, non-black start stationary CI RICE <100 HP.	a. Change oil and filter every 1,000 hours of operation or annually, whichever comes first.[2] b. Inspect air cleaner every 1,000 hours of operation or annually, whichever comes first, and replace as necessary; c. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.[3]	
3. Non-Emergency, non-black start CI stationary RICE 100≤HP≤300 HP.	Limit concentration of CO in the stationary RICE exhaust to 230 ppmvd or less at 15 percent O_2.	
4. Non-Emergency, non-black start CI stationary RICE 300<HP≤500.	a. Limit concentration of CO in the stationary RICE exhaust to 49 ppmvd or less at 15 percent O_2; or b. Reduce CO emissions by 70 percent or more.	
5. Non-Emergency, non-black start stationary CI RICE >500 HP.	a. Limit concentration of CO in the stationary RICE exhaust to 23 ppmvd or less at 15 percent O_2; or b. Reduce CO emissions by 70 percent or more.	
6. Emergency stationary SI RICE and black start stationary SI RICE.[1]	a. Change oil and filter every 500 hours of operation or annually, whichever comes first;[2] b. Inspect spark plugs every 1,000 hours of operation or annually, whichever comes first, and replace as necessary; c. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.[3]	
7. Non-Emergency, non-black start stationary SI RICE <100 HP that are not 2SLB stationary RICE.	a. Change oil and filter every 1,440 hours of operation or annually, whichever comes first;[2] b. Inspect spark plugs every 1,440 hours of operation or annually, whichever comes first, and replace as necessary; c. Inspect all hoses and belts every 1,440 hours of operation or annually, whichever comes first, and replace as necessary.[3]	
8. Non-Emergency, non-black start 2SLB stationary SI RICE <100 HP.	a. Change oil and filter every 4,320 hours of operation or annually, whichever comes first;[2] b. Inspect spark plugs every 4,320 hours of operation or annually, whichever comes first, and replace as necessary; c. Inspect all hoses and belts every 4,320 hours of operation or annually, whichever comes first, and replace as necessary.[3]	
9. Non-emergency, non-black start 2SLB stationary RICE 100≤HP≤500.	Limit concentration of CO in the stationary RICE exhaust to 225 ppmvd or less at 15 percent O_2.	
10. Non-emergency, non-black start 4SLB stationary RICE 100≤HP≤500.	Limit concentration of CO in the stationary RICE exhaust to 47 ppmvd or less at 15 percent O_2.	
11. Non-emergency, non-black start 4SRB stationary RICE 100≤HP≤500.	Limit concentration of formaldehyde in the stationary RICE exhaust to 10.3 ppmvd or less at 15 percent O_2.	

For each . . .	You must meet the following requirement, except during periods of startup . . .	During periods of startup you must . . .
12. Non-emergency, non-black start stationary RICE 100≤HP≤500 which combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis.	Limit concentration of CO in the stationary RICE exhaust to 177 ppmvd or less at 15 percent O_2.	

[1] If an emergency engine is operating during an emergency and it is not possible to shut down the engine in order to perform the work practice requirements on the schedule required in Table 2c of this subpart, or if performing the work practice on the required schedule would otherwise pose an unacceptable risk under federal, state, or local law, the work practice can be delayed until the emergency is over or the unacceptable risk under federal, state, or local law has abated. The work practice should be performed as soon as practicable after the emergency has ended or the unacceptable risk under federal, state, or local law has abated. Sources must report any failure to perform the work practice on the schedule required and the federal, state or local law under which the risk was deemed unacceptable.

[2] Sources have the option to utilize an oil analysis program as described in §63.6625(i) or (j) in order to extend the specified oil change requirement in Table 2c of this subpart.

[3] Sources can petition the Administrator pursuant to the requirements of 40 CFR 63.6(g) for alternative work practices.

[78 FR 6708, Jan. 30, 2013, as amended at 78 FR 14457, Mar. 6, 2013]

TABLE 2d TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR EXISTING STATIONARY RICE LOCATED AT AREA SOURCES OF HAP EMISSIONS

As stated in §§63.6603 and 63.6640, you must comply with the following requirements for existing stationary RICE located at area sources of HAP emissions:

For each . . .	You must meet the following requirement, except during periods of startup . . .	During periods of startup you must . . .
1. Non-Emergency, non-black start CI stationary RICE ≤300 HP.	a. Change oil and filter every 1,000 hours of operation or annually, whichever comes first;[1] b. Inspect air cleaner every 1,000 hours of operation or annually, whichever comes first, and replace as necessary; c. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.	Minimize the engine's time spent at idle and minimize the engine's startup time at startup to a period needed for appropriate and safe loading of the engine, not to exceed 30 minutes, after which time the non-startup emission limitations apply.
2. Non-Emergency, non-black start CI stationary RICE 300<HP≤500.	a. Limit concentration of CO in the stationary RICE exhaust to 49 ppmvd at 15 percent O_2; or b. Reduce CO emissions by 70 percent or more.	
3. Non-Emergency, non-black start CI stationary RICE >500 HP.	a. Limit concentration of CO in the stationary RICE exhaust to 23 ppmvd at 15 percent O_2; or b. Reduce CO emissions by 70 percent or more.	
4. Emergency stationary CI RICE and black start stationary CI RICE.[2]	a. Change oil and filter every 500 hours of operation or annually, whichever comes first;[1] b. Inspect air cleaner every 1,000 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.	
5. Emergency stationary SI RICE; black start stationary SI RICE; non-emergency, non-black start 4SLB stationary RICE >500 HP that operate 24 hours or less per calendar year; non-emergency, non-black start 4SRB stationary RICE >500 HP that operate 24 hours or less per calendar year.[2]	a. Change oil and filter every 500 hours of operation or annually, whichever comes first;[1]; b. Inspect spark plugs every 1,000 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 500 hours of operation or annually, whichever comes first, and replace as necessary.	

For each . . .	You must meet the following requirement, except during periods of startup . . .	During periods of startup you must . . .
6. Non-emergency, non-black start 2SLB stationary RICE.	a. Change oil and filter every 4,320 hours of operation or annually, whichever comes first;[1] b. Inspect spark plugs every 4,320 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 4,320 hours of operation or annually, whichever comes first, and replace as necessary.	
7. Non-emergency, non-black start 4SLB stationary RICE ≤500 HP.	a. Change oil and filter every 1,440 hours of operation or annually, whichever comes first;[1] b. Inspect spark plugs every 1,440 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 1,440 hours of operation or annually, whichever comes first, and replace as necessary.	
8. Non-emergency, non-black start 4SLB remote stationary RICE >500 HP.	a. Change oil and filter every 2,160 hours of operation or annually, whichever comes first;[1] b. Inspect spark plugs every 2,160 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 2,160 hours of operation or annually, whichever comes first, and replace as necessary.	
9. Non-emergency, non-black start 4SLB stationary RICE >500 HP that are not remote stationary RICE and that operate more than 24 hours per calendar year.	Install an oxidation catalyst to reduce HAP emissions from the stationary RICE.	
10. Non-emergency, non-black start 4SRB stationary RICE ≤500 HP.	a. Change oil and filter every 1,440 hours of operation or annually, whichever comes first;[1] b. Inspect spark plugs every 1,440 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 1,440 hours of operation or annually, whichever comes first, and replace as necessary.	
11. Non-emergency, non-black start 4SRB remote stationary RICE >500 HP.	a. Change oil and filter every 2,160 hours of operation or annually, whichever comes first;[1] b. Inspect spark plugs every 2,160 hours of operation or annually, whichever comes first, and replace as necessary; and c. Inspect all hoses and belts every 2,160 hours of operation or annually, whichever comes first, and replace as necessary.	
12. Non-emergency, non-black start 4SRB stationary RICE >500 HP that are not remote stationary RICE and that operate more than 24 hours per calendar year.	Install NSCR to reduce HAP emissions from the stationary RICE.	
13. Non-emergency, non-black start stationary RICE which combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis.	a. Change oil and filter every 1,440 hours of operation or annually, whichever comes first;[1] b. Inspect spark plugs every 1,440 hours of operation or annually, whichever comes first, and replace as necessary; and	

For each . . .	You must meet the following requirement, except during periods of startup . . .	During periods of startup you must . . .
	c. Inspect all hoses and belts every 1,440 hours of operation or annually, whichever comes first, and replace as necessary.	

[1] Sources have the option to utilize an oil analysis program as described in §63.6625(i) or (j) in order to extend the specified oil change requirement in Table 2d of this subpart.

[2] If an emergency engine is operating during an emergency and it is not possible to shut down the engine in order to perform the management practice requirements on the schedule required in Table 2d of this subpart, or if performing the management practice on the required schedule would otherwise pose an unacceptable risk under federal, state, or local law, the management practice can be delayed until the emergency is over or the unacceptable risk under federal, state, or local law has abated. The management practice should be performed as soon as practicable after the emergency has ended or the unacceptable risk under federal, state, or local law has abated. Sources must report any failure to perform the management practice on the schedule required and the federal, state or local law under which the risk was deemed unacceptable.

[78 FR 6709, Jan. 30, 2013]

TABLE 3 TO SUBPART ZZZZ OF PART 63—SUBSEQUENT PERFORMANCE TESTS

As stated in §§63.6615 and 63.6620, you must comply with the following subsequent performance test requirements:

For each . . .	Complying with the requirement to . . .	You must . . .
1. New or reconstructed 2SLB stationary RICE >500 HP located at major sources; new or reconstructed 4SLB stationary RICE ≥250 HP located at major sources; and new or reconstructed CI stationary RICE >500 HP located at major sources.	Reduce CO emissions and not using a CEMS.	Conduct subsequent performance tests semiannually.[1]
2. 4SRB stationary RICE ≥5,000 HP located at major sources.	Reduce formaldehyde emissions	Conduct subsequent performance tests semiannually.[1]
3. Stationary RICE >500 HP located at major sources and new or reconstructed 4SLB stationary RICE 250≤HP≤500 located at major sources.	Limit the concentration of formaldehyde in the stationary RICE exhaust.	Conduct subsequent performance tests semiannually.[1]
4. Existing non-emergency, non-black start CI stationary RICE >500 HP that are not limited use stationary RICE.	Limit or reduce CO emissions and not using a CEMS.	Conduct subsequent performance tests every 8,760 hours or 3 years, whichever comes first.
5. Existing non-emergency, non-black start CI stationary RICE >500 HP that are limited use stationary RICE.	Limit or reduce CO emissions and not using a CEMS.	Conduct subsequent performance tests every 8,760 hours or 5 years, whichever comes first.

[1] After you have demonstrated compliance for two consecutive tests, you may reduce the frequency of subsequent performance tests to annually. If the results of any subsequent annual performance test indicate the stationary RICE is not in compliance with the CO or formaldehyde emission limitation, or you deviate from any of your operating limitations, you must resume semiannual performance tests.

[78 FR 6711, Jan. 30, 2013]

TABLE 4 TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS

As stated in §§63.6610, 63.6611, 63.6620, and 63.6640, you must comply with the following requirements for performance tests for stationary RICE:

For each . . .	Complying with the requirement to . . .	You must . . .	Using . . .	According to the following requirements . . .
1. 2SLB, 4SLB, and CI stationary RICE.	a. Reduce CO emissions.	i. Select the sampling port location and the number/location of traverse points at the inlet and outlet of the control device; and	.....	(a) For CO, O_2, and moisture measurement, ducts ≤6 inches in diameter may be sampled at a single point located at the duct centroid and ducts >6 and ≤12 inches in diameter may be sampled at 3 traverse points located at 16.7, 50.0, and 83.3% of the measurement line ('3-point long line'). If the duct is >12 inches in diameter *and* the sampling port location meets the two and half-diameter criterion of section 11.1.1 of method 1 of 40 CFR part 60, appendix A–1, the duct may be sampled at '3-point long line'; otherwise, conduct the stratification testing and select sampling points according to section 8.1.2 of method 7E of 40 CFR part 60, appendix A–4.
		ii. Measure the O_2 at the inlet and outlet of the control device; and	(1) Method 3 or 3A or 3B of 40 CFR part 60, appendix A–2, or ASTM D6522–00 (Reapproved 2005)[1 3] (heated probe not necessary).	(b) Measurements to determine O_2 must be made at the same time as the measurements for CO concentration.
		iii. Measure the CO at the inlet and the outlet of the control device; and	(2) ASTM D6522–00 (Reapproved 2005)[1 2 3] (heated probe not necessary) or method 10 of 40 CFR part 60, appendix A–4.	(c) The CO concentration must be at 15 percent O_2, dry basis.
		iv. Measure moisture content at the inlet and outlet of the control device as needed to determine CO and O_2 concentrations on a dry basis.	(3) Method 4 of 40 CFR part 60, appendix A–3, or method 320 of 40 CFR part 63, appendix A, or ASTM D6348–03[1 3].	(d) Measurements to determine moisture content must be made at the same time and location as the measurements for CO concentration.
2. 4SRB stationary RICE.	a. Reduce formaldehyde or THC emissions.	i. Select the sampling port location and the number/location of traverse points at the inlet and outlet of the control device; and	.....	(a) For formaldehyde, THC, O_2, and moisture measurement, ducts ≤6 inches in diameter may be sampled at a single point located at the duct centroid and ducts >6 and ≤12 inches in diameter may be sampled at 3 traverse points located at 16.7, 50.0, and 83.3% of the measurement line ('3-point long line'). If the duct is >12 inches in diameter *and* the sampling port location meets the two and half-diameter criterion of section 11.1.1 of method 1 of 40 CFR part 60, appendix A, the duct may be sampled at '3-point long line'; otherwise, conduct the stratification testing and select sampling points according to section 8.1.2 of method 7E of 40 CFR part 60, appendix A.

For each . . .	Complying with the requirement to . . .	You must . . .	Using . . .	According to the following requirements . . .
		ii. Measure O_2 at the inlet and outlet of the control device; and	(1) Method 3 or 3A or 3B of 40 CFR part 60, appendix A–2, or ASTM D6522–00 (Reapproved 2005)[1 3] (heated probe not necessary).	(b) Measurements to determine O_2 concentration must be made at the same time as the measurements for formaldehyde or THC concentration.
		iii. Measure moisture content at the inlet and outlet of the control device as needed to determine formaldehyde or THC and O_2 concentrations on a dry basis; and	(2) Method 4 of 40 CFR part 60, appendix A–3, or method 320 of 40 CFR part 63, appendix A, or ASTM D6348–03[1 3].	(c) Measurements to determine moisture content must be made at the same time and location as the measurements for formaldehyde or THC concentration.
		iv. If demonstrating compliance with the formaldehyde percent reduction requirement, measure formaldehyde at the inlet and the outlet of the control device.	(3) Method 320 or 323 of 40 CFR part 63, appendix A; or ASTM D6348–03,[1 3] provided in ASTM D6348–03 Annex A5 (Analyte Spiking Technique), the percent R must be greater than or equal to 70 and less than or equal to 130.	(d) Formaldehyde concentration must be at 15 percent O_2, dry basis. Results of this test consist of the average of the three 1-hour or longer runs.
		v. If demonstrating compliance with the THC percent reduction requirement, measure THC at the inlet and the outlet of the control device.	(4) (1) Method 25A, reported as propane, of 40 CFR part 60, appendix A–7.	(e) THC concentration must be at 15 percent O_2, dry basis. Results of this test consist of the average of the three 1-hour or longer runs.
3. Stationary RICE	a. Limit the concentration of formaldehyde or CO in the stationary RICE exhaust.	i. Select the sampling port location and the number/location of traverse points at the exhaust of the stationary RICE; and	.....	(a) For formaldehyde, CO, O_2, and moisture measurement, ducts ≤6 inches in diameter may be sampled at a single point located at the duct centroid and ducts >6 and ≤12 inches in diameter may be sampled at 3 traverse points located at 16.7, 50.0, and 83.3% of the measurement line ('3-point long line'). If the duct is >12 inches in diameter *and* the sampling port location meets the two and half-diameter criterion of section 11.1.1 of method 1 of 40 CFR part 60, appendix A, the duct may be sampled at '3-point long line'; otherwise, conduct the stratification testing and select sampling points according to section 8.1.2 of method 7E of 40 CFR part 60, appendix A. If using a control device, the sampling site must be located at the outlet of the control device.

For each . . .	Complying with the requirement to . . .	You must . . .	Using . . .	According to the following requirements . . .
		ii. Determine the O_2 concentration of the stationary RICE exhaust at the sampling port location; and	(1) Method 3 or 3A or 3B of 40 CFR part 60, appendix A–2, or ASTM D6522–00 (Reapproved 2005) [1] [3] (heated probe not necessary).	(b) Measurements to determine O_2 concentration must be made at the same time and location as the measurements for formaldehyde or CO concentration.
		iii. Measure moisture content of the stationary RICE exhaust at the sampling port location as needed to determine formaldehyde or CO and O_2 concentrations on a dry basis; and	(2) Method 4 of 40 CFR part 60, appendix A–3, or method 320 of 40 CFR part 63, appendix A, or ASTM D6348–03 [1] [3].	(c) Measurements to determine moisture content must be made at the same time and location as the measurements for formaldehyde or CO concentration.
		iv. Measure formaldehyde at the exhaust of the stationary RICE; or	(3) Method 320 or 323 of 40 CFR part 63, appendix A; or ASTM D6348–03,[1] [3] provided in ASTM D6348–03 Annex A5 (Analyte Spiking Technique), the percent R must be greater than or equal to 70 and less than or equal to 130.	(d) Formaldehyde concentration must be at 15 percent O_2, dry basis. Results of this test consist of the average of the three 1-hour or longer runs.
		v. Measure CO at the exhaust of the stationary RICE.	(4) Method 10 of 40 CFR part 60, appendix A–4, ASTM D6522–00 (2005),[1] [3] method 320 of 40 CFR part 63, appendix A, or ASTM D6348–03 [1] [3].	(e) CO concentration must be at 15 percent O_2, dry basis. Results of this test consist of the average of the three 1-hour or longer runs.

[1] You may also use methods 3A and 10 as options to ASTM–D6522–00 (2005).
[2] You may obtain a copy of ASTM–D6348–03 from at least one of the following addresses: American Society for Testing and Materials, 100 Barr Harbor Drive, West Conshohocken, PA 19428–2959, or University Microfilms International, 300 North Zeeb Road, Ann Arbor, MI 48106.
[3] Incorporated by reference, see § 63.14.

[88 FR 18413, Mar. 29, 2023]

TABLE 5 TO SUBPART ZZZZ OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS, OPERATING LIMITATIONS, AND OTHER REQUIREMENTS

As stated in §§ 63.6612, 63.6625 and 63.6630, you must initially comply with the emission and operating limitations as required by the following:

For each . . .	Complying with the requirement to . . .	You have demonstrated initial compliance if . . .
1. New or reconstructed non-emergency 2SLB stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE ≥250 HP located at a major source of HAP, non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP located at an area source of HAP.	a. Reduce CO emissions and using oxidation catalyst, and using a CPMS.	i. The average reduction of emissions of CO determined from the initial performance test achieves the required CO percent reduction; and ii. You have installed a CPMS to continuously monitor catalyst inlet temperature according to the requirements in § 63.6625(b); and iii. You have recorded the catalyst pressure drop and catalyst inlet temperature during the initial performance test.

For each . . .	Complying with the requirement to . . .	You have demonstrated initial compliance if . . .
2. Non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP located at an area source of HAP.	a. Limit the concentration of CO, using oxidation catalyst, and using a CPMS.	i. The average CO concentration determined from the initial performance test is less than or equal to the CO emission limitation; and ii. You have installed a CPMS to continuously monitor catalyst inlet temperature according to the requirements in §63.6625(b); and iii. You have recorded the catalyst pressure drop and catalyst inlet temperature during the initial performance test.
3. New or reconstructed non-emergency 2SLB stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE ≥250 HP located at a major source of HAP, non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP located at an area source of HAP.	a. Reduce CO emissions and not using oxidation catalyst.	i. The average reduction of emissions of CO determined from the initial performance test achieves the required CO percent reduction; and ii. You have installed a CPMS to continuously monitor operating parameters approved by the Administrator (if any) according to the requirements in §63.6625(b); and iii. You have recorded the approved operating parameters (if any) during the initial performance test.
4. Non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP located at an area source of HAP.	a. Limit the concentration of CO, and not using oxidation catalyst.	i. The average CO concentration determined from the initial performance test is less than or equal to the CO emission limitation; and ii. You have installed a CPMS to continuously monitor operating parameters approved by the Administrator (if any) according to the requirements in §63.6625(b); and iii. You have recorded the approved operating parameters (if any) during the initial performance test.
5. New or reconstructed non-emergency 2SLB stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE ≥250 HP located at a major source of HAP, non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP located at an area source of HAP.	a. Reduce CO emissions, and using a CEMS.	i. You have installed a CEMS to continuously monitor CO and either O_2 or CO_2 at both the inlet and outlet of the oxidation catalyst according to the requirements in §63.6625(a); and ii. You have conducted a performance evaluation of your CEMS using PS 3 and 4A of 40 CFR part 60, appendix B; and iii. The average reduction of CO calculated using §63.6620 equals or exceeds the required percent reduction. The initial test comprises the first 4-hour period after successful validation of the CEMS. Compliance is based on the average percent reduction achieved during the 4-hour period.
6. Non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP located at an area source of HAP.	a. Limit the concentration of CO, and using a CEMS.	i. You have installed a CEMS to continuously monitor CO and either O_2 or CO_2 at the outlet of the oxidation catalyst according to the requirements in §63.6625(a); and ii. You have conducted a performance evaluation of your CEMS using PS 3 and 4A of 40 CFR part 60, appendix B; and iii. The average concentration of CO calculated using §63.6620 is less than or equal to the CO emission limitation. The initial test comprises the first 4-hour period after successful validation of the CEMS. Compliance is based on the average concentration measured during the 4-hour period.

For each . . .	Complying with the requirement to . . .	You have demonstrated initial compliance if . . .
7. Non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP.	a. Reduce formaldehyde emissions and using NSCR.	i. The average reduction of emissions of formaldehyde determined from the initial performance test is equal to or greater than the required formaldehyde percent reduction, or the average reduction of emissions of THC determined from the initial performance test is equal to or greater than 30 percent; and ii. You have installed a CPMS to continuously monitor catalyst inlet temperature according to the requirements in §63.6625(b); and iii. You have recorded the catalyst pressure drop and catalyst inlet temperature during the initial performance test.
8. Non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP.	a. Reduce formaldehyde emissions and not using NSCR.	i. The average reduction of emissions of formaldehyde determined from the initial performance test is equal to or greater than the required formaldehyde percent reduction or the average reduction of emissions of THC determined from the initial performance test is equal to or greater than 30 percent; and ii. You have installed a CPMS to continuously monitor operating parameters approved by the Administrator (if any) according to the requirements in §63.6625(b); and iii. You have recorded the approved operating parameters (if any) during the initial performance test.
9. New or reconstructed non-emergency stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE 250≤HP≤500 located at a major source of HAP, and existing non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP.	a. Limit the concentration of formaldehyde in the stationary RICE exhaust and using oxidation catalyst or NSCR.	i. The average formaldehyde concentration, corrected to 15 percent O_2, dry basis, from the three test runs is less than or equal to the formaldehyde emission limitation; and ii. You have installed a CPMS to continuously monitor catalyst inlet temperature according to the requirements in §63.6625(b); and iii. You have recorded the catalyst pressure drop and catalyst inlet temperature during the initial performance test.
10. New or reconstructed non-emergency stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE 250≤HP≤500 located at a major source of HAP, and existing non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP.	a. Limit the concentration of formaldehyde in the stationary RICE exhaust and not using oxidation catalyst or NSCR.	i. The average formaldehyde concentration, corrected to 15 percent O_2, dry basis, from the three test runs is less than or equal to the formaldehyde emission limitation; and ii. You have installed a CPMS to continuously monitor operating parameters approved by the Administrator (if any) according to the requirements in §63.6625(b); and iii. You have recorded the approved operating parameters (if any) during the initial performance test.
11. Existing non-emergency stationary RICE 100≤HP≤500 located at a major source of HAP, and existing non-emergency stationary CI RICE 300<HP≤500 located at an area source of HAP.	a. Reduce CO emissions	i. The average reduction of emissions of CO or formaldehyde, as applicable determined from the initial performance test is equal to or greater than the required CO or formaldehyde, as applicable, percent reduction.
12. Existing non-emergency stationary RICE 100≤HP≤500 located at a major source of HAP, and existing non-emergency stationary CI RICE 300<HP≤500 located at an area source of HAP.	a. Limit the concentration of formaldehyde or CO in the stationary RICE exhaust.	i. The average formaldehyde or CO concentration, as applicable, corrected to 15 percent O_2, dry basis, from the three test runs is less than or equal to the formaldehyde or CO emission limitation, as applicable.

For each . . .	Complying with the requirement to . . .	You have demonstrated initial compliance if . . .
13. Existing non-emergency 4SLB stationary RICE >500 HP located at an area source of HAP that are not remote stationary RICE and that are operated more than 24 hours per calendar year.	a. Install an oxidation catalyst	i. You have conducted an initial compliance demonstration as specified in §63.6630(e) to show that the average reduction of emissions of CO is 93 percent or more, or the average CO concentration is less than or equal to 47 ppmvd at 15 percent O_2; ii. You have installed a CPMS to continuously monitor catalyst inlet temperature according to the requirements in §63.6625(b), or you have installed equipment to automatically shut down the engine if the catalyst inlet temperature exceeds 1350 °F.
14. Existing non-emergency 4SRB stationary RICE >500 HP located at an area source of HAP that are not remote stationary RICE and that are operated more than 24 hours per calendar year.	a. Install NSCR	i. You have conducted an initial compliance demonstration as specified in §63.6630(e) to show that the average reduction of emissions of CO is 75 percent or more, the average CO concentration is less than or equal to 270 ppmvd at 15 percent O_2, or the average reduction of emissions of THC is 30 percent or more; ii. You have installed a CPMS to continuously monitor catalyst inlet temperature according to the requirements in §63.6625(b), or you have installed equipment to automatically shut down the engine if the catalyst inlet temperature exceeds 1250 °F.

[78 FR 6712, Jan. 30, 2013]

TABLE 6 TO SUBPART ZZZZ OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS, AND OTHER REQUIREMENTS

As stated in §63.6640, you must continuously comply with the emissions and operating limitations and work or management practices as required by the following:

For each . . .	Complying with the requirement to . . .	You must demonstrate continuous compliance by . . .
1. New or reconstructed non-emergency 2SLB stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE ≥250 HP located at a major source of HAP, and new or reconstructed non-emergency CI stationary RICE >500 HP located at a major source of HAP.	a. Reduce CO emissions and using an oxidation catalyst, and using a CPMS.	i. Conducting semiannual performance tests for CO to demonstrate that the required CO percent reduction is achieved[a]; and ii. Collecting the catalyst inlet temperature data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the catalyst inlet temperature; and v. Measuring the pressure drop across the catalyst once per month and demonstrating that the pressure drop across the catalyst is within the operating limitation established during the performance test.
2. New or reconstructed non-emergency 2SLB stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE ≥250 HP located at a major source of HAP, and new or reconstructed non-emergency CI stationary RICE >500 HP located at a major source of HAP.	a. Reduce CO emissions and not using an oxidation catalyst, and using a CPMS.	i. Conducting semiannual performance tests for CO to demonstrate that the required CO percent reduction is achieved[a]; and ii. Collecting the approved operating parameter (if any) data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and

For each . . .	Complying with the requirement to . . .	You must demonstrate continuous compliance by . . .
		iv. Maintaining the 4-hour rolling averages within the operating limitations for the operating parameters established during the performance test.
3. New or reconstructed non-emergency 2SLB stationary RICE >500 HP located at a major source of HAP, new or reconstructed non-emergency 4SLB stationary RICE ≥250 HP located at a major source of HAP, new or reconstructed non-emergency stationary CI RICE >500 HP located at a major source of HAP, and existing non-emergency stationary CI RICE >500 HP.	a. Reduce CO emissions or limit the concentration of CO in the stationary RICE exhaust, and using a CEMS.	i. Collecting the monitoring data according to §63.6625(a), reducing the measurements to 1-hour averages, calculating the percent reduction or concentration of CO emissions according to §63.6620; and ii. Demonstrating that the catalyst achieves the required percent reduction of CO emissions over the 4-hour averaging period, or that the emission remain at or below the CO concentration limit; and iii. Conducting an annual RATA of your CEMS using PS 3 and 4A of 40 CFR part 60, appendix B, as well as daily and periodic data quality checks in accordance with 40 CFR part 60, appendix F, procedure 1.
4. Non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP.	a. Reduce formaldehyde emissions and using NSCR.	i. Collecting the catalyst inlet temperature data according to §63.6625(b); and ii. Reducing these data to 4-hour rolling averages; and iii. Maintaining the 4-hour rolling averages within the operating limitations for the catalyst inlet temperature; and iv. Measuring the pressure drop across the catalyst once per month and demonstrating that the pressure drop across the catalyst is within the operating limitation established during the performance test.
5. Non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP.	a. Reduce formaldehyde emissions and not using NSCR.	i. Collecting the approved operating parameter (if any) data according to §63.6625(b); and ii. Reducing these data to 4-hour rolling averages; and iii. Maintaining the 4-hour rolling averages within the operating limitations for the operating parameters established during the performance test.
6. Non-emergency 4SRB stationary RICE with a brake HP ≥5,000 located at a major source of HAP.	a. Reduce formaldehyde emissions	Conducting semiannual performance tests for formaldehyde to demonstrate that the required formaldehyde percent reduction is achieved, or to demonstrate that the average reduction of emissions of THC determined from the performance test is equal to or greater than 30 percent.[a]
7. New or reconstructed non-emergency stationary RICE >500 HP located at a major source of HAP and new or reconstructed non-emergency 4SLB stationary RICE 250≤HP≤500 located at a major source of HAP.	a. Limit the concentration of formaldehyde in the stationary RICE exhaust and using oxidation catalyst or NSCR.	i. Conducting semiannual performance tests for formaldehyde to demonstrate that your emissions remain at or below the formaldehyde concentration limit[a]; and ii. Collecting the catalyst inlet temperature data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the catalyst inlet temperature; and v. Measuring the pressure drop across the catalyst once per month and demonstrating that the pressure drop across the catalyst is within the operating limitation established during the performance test.

For each . . .	Complying with the requirement to . . .	You must demonstrate continuous compliance by . . .
8. New or reconstructed non-emergency stationary RICE >500 HP located at a major source of HAP and new or reconstructed non-emergency 4SLB stationary RICE 250≤HP≤500 located at a major source of HAP.	a. Limit the concentration of formaldehyde in the stationary RICE exhaust and not using oxidation catalyst or NSCR.	i. Conducting semiannual performance tests for formaldehyde to demonstrate that your emissions remain at or below the formaldehyde concentration limit [a]; and ii. Collecting the approved operating parameter (if any) data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the operating parameters established during the performance test.
9. Existing emergency and black start stationary RICE ≤500 HP located at a major source of HAP, existing non-emergency stationary RICE <100 HP located at a major source of HAP, existing emergency and black start stationary RICE located at an area source of HAP, existing non-emergency stationary CI RICE ≤300 HP located at an area source of HAP, existing non-emergency 2SLB stationary RICE located at an area source of HAP, existing non-emergency stationary SI RICE located at an area source of HAP which combusts landfill or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis, existing non-emergency 4SLB and 4SRB stationary RICE ≤500 HP located at an area source of HAP, existing non-emergency 4SLB and 4SRB stationary RICE >500 HP located at an area source of HAP that operate 24 hours or less per calendar year, and existing non-emergency 4SLB and 4SRB stationary RICE >500 HP located at an area source of HAP that are remote stationary RICE.	a. Work or Management practices	i. Operating and maintaining the stationary RICE according to the manufacturer's emission-related operation and maintenance instructions; or ii. Develop and follow your own maintenance plan which must provide to the extent practicable for the maintenance and operation of the engine in a manner consistent with good air pollution control practice for minimizing emissions.
10. Existing stationary CI RICE >500 HP that are not limited use stationary RICE.	a. Reduce CO emissions, or limit the concentration of CO in the stationary RICE exhaust, and using oxidation catalyst.	i. Conducting performance tests every 8,760 hours or 3 years, whichever comes first, for CO or formaldehyde, as appropriate, to demonstrate that the required CO or formaldehyde, as appropriate, percent reduction is achieved or that your emissions remain at or below the CO or formaldehyde concentration limit; and ii. Collecting the catalyst inlet temperature data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the catalyst inlet temperature; and v. Measuring the pressure drop across the catalyst once per month and demonstrating that the pressure drop across the catalyst is within the operating limitation established during the performance test.
11. Existing stationary CI RICE >500 HP that are not limited use stationary RICE.	a. Reduce CO emissions, or limit the concentration of CO in the stationary RICE exhaust, and not using oxidation catalyst.	i. Conducting performance tests every 8,760 hours or 3 years, whichever comes first, for CO or formaldehyde, as appropriate, to demonstrate that the required CO or formaldehyde, as appropriate, percent reduction is achieved or that your emissions remain at or below the CO or formaldehyde concentration limit; and

For each . . .	Complying with the requirement to . . .	You must demonstrate continuous compliance by . . .
		ii. Collecting the approved operating parameter (if any) data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the operating parameters established during the performance test.
12. Existing limited use CI stationary RICE >500 HP.	a. Reduce CO emissions or limit the concentration of CO in the stationary RICE exhaust, and using an oxidation catalyst.	i. Conducting performance tests every 8,760 hours or 5 years, whichever comes first, for CO or formaldehyde, as appropriate, to demonstrate that the required CO or formaldehyde, as appropriate, percent reduction is achieved or that your emissions remain at or below the CO or formaldehyde concentration limit; and ii. Collecting the catalyst inlet temperature data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the catalyst inlet temperature; and v. Measuring the pressure drop across the catalyst once per month and demonstrating that the pressure drop across the catalyst is within the operating limitation established during the performance test.
13. Existing limited use CI stationary RICE >500 HP.	a. Reduce CO emissions or limit the concentration of CO in the stationary RICE exhaust, and not using an oxidation catalyst.	i. Conducting performance tests every 8,760 hours or 5 years, whichever comes first, for CO or formaldehyde, as appropriate, to demonstrate that the required CO or formaldehyde, as appropriate, percent reduction is achieved or that your emissions remain at or below the CO or formaldehyde concentration limit; and ii. Collecting the approved operating parameter (if any) data according to §63.6625(b); and iii. Reducing these data to 4-hour rolling averages; and iv. Maintaining the 4-hour rolling averages within the operating limitations for the operating parameters established during the performance test.
14. Existing non-emergency 4SLB stationary RICE >500 HP located at an area source of HAP that are not remote stationary RICE and that are operated more than 24 hours per calendar year.	a. Install an oxidation catalyst	i. Conducting annual compliance demonstrations as specified in §63.6640(c) to show that the average reduction of emissions of CO is 93 percent or more, or the average CO concentration is less than or equal to 47 ppmvd at 15 percent O_2; and either ii. Collecting the catalyst inlet temperature data according to §63.6625(b), reducing these data to 4-hour rolling averages; and maintaining the 4-hour rolling averages within the limitation of greater than 450 °F and less than or equal to 1350 °F for the catalyst inlet temperature; or iii. Immediately shutting down the engine if the catalyst inlet temperature exceeds 1350 °F.

For each . . .	Complying with the requirement to . . .	You must demonstrate continuous compliance by . . .
15. Existing non-emergency 4SRB stationary RICE >500 HP located at an area source of HAP that are not remote stationary RICE and that are operated more than 24 hours per calendar year.	a. Install NSCR	i. Conducting annual compliance demonstrations as specified in §63.6640(c) to show that the average reduction of emissions of CO is 75 percent or more, the average CO concentration is less than or equal to 270 ppmvd at 15 percent O_2, or the average reduction of emissions of THC is 30 percent or more; and either ii. Collecting the catalyst inlet temperature data according to §63.6625(b), reducing these data to 4-hour rolling averages; and maintaining the 4-hour rolling averages within the limitation of greater than or equal to 750 °F and less than or equal to 1250 °F for the catalyst inlet temperature; or iii. Immediately shutting down the engine if the catalyst inlet temperature exceeds 1250 °F.

[a] After you have demonstrated compliance for two consecutive tests, you may reduce the frequency of subsequent performance tests to annually. If the results of any subsequent annual performance test indicate the stationary RICE is not in compliance with the CO or formaldehyde emission limitation, or you deviate from any of your operating limitations, you must resume semiannual performance tests.

[78 FR 6715, Jan. 30, 2013]

TABLE 7 TO SUBPART ZZZZ OF PART 63—REQUIREMENTS FOR REPORTS

As stated in §63.6650, you must comply with the following requirements for reports:

For each . . .	You must submit a . . .	The report must contain . . .	You must submit the report . . .
1. Existing non-emergency, non-black start stationary RICE 100≤HP≤500 located at a major source of HAP; existing non-emergency, non-black start stationary CI RICE >500 HP located at a major source of HAP; existing non-emergency 4SRB stationary RICE >500 HP located at a major source of HAP; existing non-emergency, non-black start stationary CI RICE >300 HP located at an area source of HAP; new or reconstructed non-emergency stationary RICE >500 HP located at a major source of HAP; and new or reconstructed non-emergency 4SLB stationary RICE 250≤HP≤500 located at a major source of HAP.	Compliance report	a. If there are no deviations from any emission limitations or operating limitations that apply to you, a statement that there were no deviations from the emission limitations or operating limitations during the reporting period. If there were no periods during which the CMS, including CEMS and CPMS, was out-of-control, as specified in §63.8(c)(7), a statement that there were not periods during which the CMS was out-of-control during the reporting period; or	i. Semiannually according to the requirements in §63.6650(b)(1)–(5) for engines that are not limited use stationary RICE subject to numerical emission limitations; and ii. Annually according to the requirements in §63.6650(b)(6)–(9) for engines that are limited use stationary RICE subject to numerical emission limitations.
		b. If you had a deviation from any emission limitation or operating limitation during the reporting period, the information in §63.6650(d). If there were periods during which the CMS, including CEMS and CPMS, was out-of-control, as specified in §63.8(c)(7), the information in §63.6650(e); or	i. Semiannually according to the requirements in §63.6650(b).
		c. If you had a malfunction during the reporting period, the information in §63.6650(c)(4)	i. Semiannually according to the requirements in §63.6650(b).

For each . . .	You must submit a . . .	The report must contain . . .	You must submit the report . . .
2. New or reconstructed non-emergency stationary RICE that combusts landfill gas or digester gas equivalent to 10 percent or more of the gross heat input on an annual basis.	Report	a. The fuel flow rate of each fuel and the heating values that were used in your calculations, and you must demonstrate that the percentage of heat input provided by landfill gas or digester gas, is equivalent to 10 percent or more of the gross heat input on an annual basis; and	i. Annually, according to the requirements in § 63.6650.
		b. The operating limits provided in your federally enforceable permit, and any deviations from these limits; and	i. See item 2.a.i.
		c. Any problems or errors suspected with the meters.	i. See item 2.a.i.
3. Existing non-emergency, non-black start 4SLB and 4SRB stationary RICE >500 HP located at an area source of HAP that are not remote stationary RICE and that operate more than 24 hours per calendar year.	Compliance report	a. The results of the annual compliance demonstration, if conducted during the reporting period.	i. Semiannually according to the requirements in § 63.6650(b)(1)–(5).
4. Emergency stationary RICE that operate for the purposes specified in § 63.6640(f)(4)(ii).	Report	a. The information in § 63.6650(h)(1).	i. annually according to the requirements in § 63.6650(h)(2)–(3).

[87 FR 48608, Aug. 10, 2022]

Table 8 to Subpart ZZZZ of Part 63—Applicability of General Provisions to Subpart ZZZZ.

As stated in § 63.6665, you must comply with the following applicable general provisions.

General provisions citation	Subject of citation	Applies to subpart	Explanation
§ 63.1	General applicability of the General Provisions.	Yes.	
§ 63.2	Definitions	Yes	Additional terms defined in § 63.6675.
§ 63.3	Units and abbreviations	Yes.	
§ 63.4	Prohibited activities and circumvention.	Yes.	
§ 63.5	Construction and reconstruction	Yes.	
§ 63.6(a)	Applicability	Yes.	
§ 63.6(b)(1)–(4)	Compliance dates for new and reconstructed sources.	Yes.	
§ 63.6(b)(5)	Notification	Yes.	
§ 63.6(b)(6)	[Reserved]		
§ 63.6(b)(7)	Compliance dates for new and reconstructed area sources that become major sources.	Yes.	
§ 63.6(c)(1)–(2)	Compliance dates for existing sources.	Yes.	
§ 63.6(c)(3)–(4)	[Reserved]		
§ 63.6(c)(5)	Compliance dates for existing area sources that become major sources.	Yes.	
§ 63.6(d)	[Reserved]		
§ 63.6(e)	Operation and maintenance	No.	
§ 63.6(f)(1)	Applicability of standards	No.	
§ 63.6(f)(2)	Methods for determining compliance	Yes.	
§ 63.6(f)(3)	Finding of compliance	Yes.	
§ 63.6(g)(1)–(3)	Use of alternate standard	Yes.	
§ 63.6(h)	Opacity and visible emission standards.	No	Subpart ZZZZ does not contain opacity or visible emission standards.
§ 63.6(i)	Compliance extension procedures and criteria.	Yes.	
§ 63.6(j)	Presidential compliance exemption	Yes.	

General provisions citation	Subject of citation	Applies to subpart	Explanation
§63.7(a)(1)–(2)	Performance test dates	Yes	Subpart ZZZZ contains performance test dates at §§63.6610, 63.6611, and 63.6612.
§63.7(a)(3)	CAA section 114 authority	Yes.	
§63.7(b)(1)	Notification of performance test	Yes	Except that §63.7(b)(1) only applies as specified in §63.6645.
§63.7(b)(2)	Notification of rescheduling	Yes	Except that §63.7(b)(2) only applies as specified in §63.6645.
§63.7(c)	Quality assurance/test plan	Yes	Except that §63.7(c) only applies as specified in §63.6645.
§63.7(d)	Testing facilities	Yes.	
§63.7(e)(1)	Conditions for conducting performance tests.	No.	Subpart ZZZZ specifies conditions for conducting performance tests at §63.6620.
§63.7(e)(2)	Conduct of performance tests and reduction of data.	Yes	Subpart ZZZZ specifies test methods at §63.6620.
§63.7(e)(3)	Test run duration	Yes.	
§63.7(e)(4)	Administrator may require other testing under section 114 of the CAA.	Yes.	
§63.7(f)	Alternative test method provisions	Yes.	
§63.7(g)	Performance test data analysis, recordkeeping, and reporting.	Yes.	
§63.7(h)	Waiver of tests	Yes.	
§63.8(a)(1)	Applicability of monitoring requirements.	Yes	Subpart ZZZZ contains specific requirements for monitoring at §63.6625.
§63.8(a)(2)	Performance specifications	Yes.	
§63.8(a)(3)	[Reserved]		
§63.8(a)(4)	Monitoring for control devices	No.	
§63.8(b)(1)	Monitoring	Yes.	
§63.8(b)(2)–(3)	Multiple effluents and multiple monitoring systems.	Yes.	
§63.8(c)(1)	Monitoring system operation and maintenance.	Yes.	
§63.8(c)(1)(i)	Routine and predictable SSM	No.	
§63.8(c)(1)(ii)	SSM not in Startup Shutdown Malfunction Plan.	Yes.	
§63.8(c)(1)(iii)	Compliance with operation and maintenance requirements.	No.	
§63.8(c)(2)–(3)	Monitoring system installation	Yes.	
§63.8(c)(4)	Continuous monitoring system (CMS) requirements.	Yes	Except that subpart ZZZZ does not require Continuous Opacity Monitoring System (COMS).
§63.8(c)(5)	COMS minimum procedures	No	Subpart ZZZZ does not require COMS.
§63.8(c)(6)–(8)	CMS requirements	Yes	Except that subpart ZZZZ does not require COMS.
§63.8(d)	CMS quality control	Yes.	
§63.8(e)	CMS performance evaluation	Yes Except that §63.8(e) only applies as specified in §63.6645.	Except for §63.8(e)(5)(ii), which applies to COMS.
§63.8(f)(1)–(5)	Alternative monitoring method	Yes	Except that §63.8(f)(4) only applies as specified in §63.6645.
§63.8(f)(6)	Alternative to relative accuracy test	Yes	Except that §63.8(f)(6) only applies as specified in §63.6645.
§63.8(g)	Data reduction	Yes	Except that provisions for COMS are not applicable. Averaging periods for demonstrating compliance are specified at §§63.6635 and 63.6640.
§63.9(a)	Applicability and State delegation of notification requirements.	Yes.	
§63.9(b)(1)–(5)	Initial notifications	Yes Except that §63.9(b) only applies as specified in §63.6645.	Except that §63.9(b)(3) is reserved.

General provisions citation	Subject of citation	Applies to subpart	Explanation
§ 63.9(c)	Request for compliance extension	Yes	Except that § 63.9(c) only applies as specified in § 63.6645.
§ 63.9(d)	Notification of special compliance requirements for new sources.	Yes	Except that § 63.9(d) only applies as specified in § 63.6645.
§ 63.9(e)	Notification of performance test	Yes	Except that § 63.9(e) only applies as specified in § 63.6645.
§ 63.9(f)	Notification of visible emission (VE)/opacity test.	No	Subpart ZZZZ does not contain opacity or VE standards.
§ 63.9(g)(1)	Notification of performance evaluation	Yes	Except that § 63.9(g) only applies as specified in § 63.6645.
§ 63.9(g)(2)	Notification of use of COMS data	No	Subpart ZZZZ does not contain opacity or VE standards.
§ 63.9(g)(3)	Notification that criterion for alternative to RATA is exceeded.	Yes Except that § 63.9(g) only applies as specified in § 63.6645.	If alternative is in use.
§ 63.9(h)(1)–(6)	Notification of compliance status	Yes	Except that notifications for sources using a CEMS are due 30 days after completion of performance evaluations. § 63.9(h)(4) is reserved. Except that § 63.9(h) only applies as specified in § 63.6645.
§ 63.9(i)	Adjustment of submittal deadlines	Yes.	
§ 63.9(j)	Change in previous information	Yes.	
§ 63.9(k)	Electronic reporting procedures	Yes	Only as specified in § 63.9(j).
§ 63.10(a)	Administrative provisions for recordkeeping/reporting.	Yes.	
§ 63.10(b)(1)	Record retention	Yes	Except that the most recent 2 years of data do not have to be retained on site.
§ 63.10(b)(2)(i)–(v)	Records related to SSM	No.	
§ 63.10(b)(2)(vi)–(xi)	Records	Yes.	
§ 63.10(b)(2)(xii)	Record when under waiver	Yes.	
§ 63.10(b)(2)(xiii)	Records when using alternative to RATA.	Yes	For CO standard if using RATA alternative.
§ 63.10(b)(2)(xiv)	Records of supporting documentation	Yes.	
§ 63.10(b)(3)	Records of applicability determination	Yes.	
§ 63.10(c)	Additional records for sources using CEMS.	Yes	Except that § 63.10(c)(2)–(4) and (9) are reserved.
§ 63.10(d)(1)	General reporting requirements	Yes.	
§ 63.10(d)(2)	Report of performance test results	Yes.	
§ 63.10(d)(3)	Reporting opacity or VE observations	No	Subpart ZZZZ does not contain opacity or VE standards.
§ 63.10(d)(4)	Progress reports	Yes.	
§ 63.10(d)(5)	Startup, shutdown, and malfunction reports.	No.	
§ 63.10(e)(1) and (2)(i)	Additional CMS Reports	Yes.	
§ 63.10(e)(2)(ii)	COMS-related report	No	Subpart ZZZZ does not require COMS.
§ 63.10(e)(3)	Excess emission and parameter exceedances reports.	Yes.	Except that § 63.10(e)(3)(i) (C) is reserved.
§ 63.10(e)(4)	Reporting COMS data	No	Subpart ZZZZ does not require COMS.
§ 63.10(f)	Waiver for recordkeeping/reporting	Yes.	
§ 63.11	Flares	No.	
§ 63.12	State authority and delegations	Yes.	
§ 63.13	Addresses	Yes.	
§ 63.14	Incorporation by reference	Yes.	
§ 63.15	Availability of information	Yes.	

[75 FR 9688, Mar. 3, 2010, as amended at 78 FR 6720, Jan. 30, 2013; 85 FR 73912, Nov. 19, 2020]

APPENDIX A TO SUBPART ZZZZ OF PART 63—PROTOCOL FOR USING AN ELECTROCHEMICAL ANALYZER TO DETERMINE OXYGEN AND CARBON MONOXIDE CONCENTRATIONS FROM CERTAIN ENGINES

1.0 SCOPE AND APPLICATION. WHAT IS THIS PROTOCOL?

This protocol is a procedure for using portable electrochemical (EC) cells for measuring carbon monoxide (CO) and oxygen (O_2) concentrations in controlled and uncontrolled emissions from existing stationary 4-stroke lean burn and 4-stroke rich burn reciprocating internal combustion engines as specified in the applicable rule.

1.1 Analytes. What does this protocol determine?

This protocol measures the engine exhaust gas concentrations of carbon monoxide (CO) and oxygen (O_2).

Analyte	CAS No.	Sensitivity
Carbon monoxide (CO)	630–08–0	Minimum detectable limit should be 2 percent of the nominal range or 1 ppm, whichever is less restrictive.
Oxygen (O_2)	7782–44–7	

1.2 Applicability. When is this protocol acceptable?

This protocol is applicable to 40 CFR part 63, subpart ZZZZ. Because of inherent cross sensitivities of EC cells, you must not apply this protocol to other emissions sources without specific instruction to that effect.

1.3 Data Quality Objectives. How good must my collected data be?

Refer to Section 13 to verify and document acceptable analyzer performance.

1.4 Range. What is the targeted analytical range for this protocol?

The measurement system and EC cell design(s) conforming to this protocol will determine the analytical range for each gas component. The nominal ranges are defined by choosing up-scale calibration gas concentrations near the maximum anticipated flue gas concentrations for CO and O_2, or no more than twice the permitted CO level.

1.5 Sensitivity. What minimum detectable limit will this protocol yield for a particular gas component?

The minimum detectable limit depends on the nominal range and resolution of the specific EC cell used, and the signal to noise ratio of the measurement system. The minimum detectable limit should be 2 percent of the nominal range or 1 ppm, whichever is less restrictive.

2.0 SUMMARY OF PROTOCOL

In this protocol, a gas sample is extracted from an engine exhaust system and then conveyed to a portable EC analyzer for measurement of CO and O_2 gas concentrations. This method provides measurement system performance specifications and sampling protocols to ensure reliable data. You may use additions to, or modifications of vendor supplied measurement systems (e.g., heated or unheated sample lines, thermocouples, flow meters, selective gas scrubbers, etc.) to meet the design specifications of this protocol. Do not make changes to the measurement system from the as-verified configuration (Section 3.12).

3.0 DEFINITIONS

3.1 Measurement System. The total equipment required for the measurement of CO and O_2 concentrations. The measurement system consists of the following major subsystems:

3.1.1 Data Recorder. A strip chart recorder, computer or digital recorder for logging measurement data from the analyzer output. You may record measurement data from the digital data display manually or electronically.

3.1.2 Electrochemical (EC) Cell. A device, similar to a fuel cell, used to sense the presence of a specific analyte and generate an electrical current output proportional to the analyte concentration.

3.1.3 Interference Gas Scrubber. A device used to remove or neutralize chemical compounds that may interfere with the selective operation of an EC cell.

3.1.4 Moisture Removal System. Any device used to reduce the concentration of moisture in the sample stream so as to protect the EC cells from the damaging effects of condensation and to minimize errors in measurements caused by the scrubbing of soluble gases.

3.1.5 Sample Interface. The portion of the system used for one or more of the following: sample acquisition; sample transport; sample conditioning or protection of the EC cell from any degrading effects of the engine exhaust effluent; removal of particulate matter and condensed moisture.

3.2 Nominal Range. The range of analyte concentrations over which each EC cell is operated (normally 25 percent to 150 percent of up-scale calibration gas value). Several

nominal ranges can be used for any given cell so long as the calibration and repeatability checks for that range remain within specifications.

3.3 Calibration Gas. A vendor certified concentration of a specific analyte in an appropriate balance gas.

3.4 Zero Calibration Error. The analyte concentration output exhibited by the EC cell in response to zero-level calibration gas.

3.5 Up-Scale Calibration Error. The mean of the difference between the analyte concentration exhibited by the EC cell and the certified concentration of the up-scale calibration gas.

3.6 Interference Check. A procedure for quantifying analytical interference from components in the engine exhaust gas other than the targeted analytes.

3.7 Repeatability Check. A protocol for demonstrating that an EC cell operated over a given nominal analyte concentration range provides a stable and consistent response and is not significantly affected by repeated exposure to that gas.

3.8 Sample Flow Rate. The flow rate of the gas sample as it passes through the EC cell. In some situations, EC cells can experience drift with changes in flow rate. The flow rate must be monitored and documented during all phases of a sampling run.

3.9 Sampling Run. A timed three-phase event whereby an EC cell's response rises and plateaus in a sample conditioning phase, remains relatively constant during a measurement data phase, then declines during a refresh phase. The sample conditioning phase exposes the EC cell to the gas sample for a length of time sufficient to reach a constant response. The measurement data phase is the time interval during which gas sample measurements can be made that meet the acceptance criteria of this protocol. The refresh phase then purges the EC cells with CO-free air. The refresh phase replenishes requisite O_2 and moisture in the electrolyte reserve and provides a mechanism to de-gas or desorb any interference gas scrubbers or filters so as to enable a stable CO EC cell response. There are four primary types of sampling runs: pre- sampling calibrations; stack gas sampling; post-sampling calibration checks; and measurement system repeatability checks. Stack gas sampling runs can be chained together for extended evaluations, providing all other procedural specifications are met.

3.10 Sampling Day. A time not to exceed twelve hours from the time of the pre-sampling calibration to the post-sampling calibration check. During this time, stack gas sampling runs can be repeated without repeated recalibrations, providing all other sampling specifications have been met.

3.11 Pre-Sampling Calibration/Post-Sampling Calibration Check. The protocols executed at the beginning and end of each sampling day to bracket measurement readings with controlled performance checks.

3.12 Performance-Established Configuration. The EC cell and sampling system configuration that existed at the time that it initially met the performance requirements of this protocol.

4.0 Interferences.

When present in sufficient concentrations, NO and NO_2 are two gas species that have been reported to interfere with CO concentration measurements. In the likelihood of this occurrence, it is the protocol user's responsibility to employ and properly maintain an appropriate CO EC cell filter or scrubber for removal of these gases, as described in Section 6.2.12.

5.0 Safety. [Reserved]

6.0 Equipment and Supplies.

6.1 What equipment do I need for the measurement system?

The system must maintain the gas sample at conditions that will prevent moisture condensation in the sample transport lines, both before and as the sample gas contacts the EC cells. The essential components of the measurement system are described below.

6.2 Measurement System Components.

6.2.1 Sample Probe. A single extraction-point probe constructed of glass, stainless steel or other non-reactive material, and of length sufficient to reach any designated sampling point. The sample probe must be designed to prevent plugging due to condensation or particulate matter.

6.2.2 Sample Line. Non-reactive tubing to transport the effluent from the sample probe to the EC cell.

6.2.3 Calibration Assembly (optional). A three-way valve assembly or equivalent to introduce calibration gases at ambient pressure at the exit end of the sample probe during calibration checks. The assembly must be designed such that only stack gas or calibration gas flows in the sample line and all gases flow through any gas path filters.

6.2.4 Particulate Filter (optional). Filters before the inlet of the EC cell to prevent accumulation of particulate material in the measurement system and extend the useful life of the components. All filters must be fabricated of materials that are non-reactive to the gas mixtures being sampled.

6.2.5 Sample Pump. A leak-free pump to provide undiluted sample gas to the system at a flow rate sufficient to minimize the response time of the measurement system. If located upstream of the EC cells, the pump must be constructed of a material that is non-reactive to the gas mixtures being sampled.

6.2.8 Sample Flow Rate Monitoring. An adjustable rotameter or equivalent device used

to adjust and maintain the sample flow rate through the analyzer as prescribed.

6.2.9 Sample Gas Manifold (optional). A manifold to divert a portion of the sample gas stream to the analyzer and the remainder to a by-pass discharge vent. The sample gas manifold may also include provisions for introducing calibration gases directly to the analyzer. The manifold must be constructed of a material that is non-reactive to the gas mixtures being sampled.

6.2.10 EC cell. A device containing one or more EC cells to determine the CO and O_2 concentrations in the sample gas stream. The EC cell(s) must meet the applicable performance specifications of Section 13 of this protocol.

6.2.11 Data Recorder. A strip chart recorder, computer or digital recorder to make a record of analyzer output data. The data recorder resolution (i.e., readability) must be no greater than 1 ppm for CO; 0.1 percent for O_2; and one degree (either °C or °F) for temperature. Alternatively, you may use a digital or analog meter having the same resolution to observe and manually record the analyzer responses.

6.2.12 Interference Gas Filter or Scrubber. A device to remove interfering compounds upstream of the CO EC cell. Specific interference gas filters or scrubbers used in the performance-established configuration of the analyzer must continue to be used. Such a filter or scrubber must have a means to determine when the removal agent is exhausted. Periodically replace or replenish it in accordance with the manufacturer's recommendations.

7.0 Reagents and Standards. What calibration gases are needed?

7.1 Calibration Gases. CO calibration gases for the EC cell must be CO in nitrogen or CO in a mixture of nitrogen and O_2. Use CO calibration gases with labeled concentration values certified by the manufacturer to be within ±5 percent of the label value. Dry ambient air (20.9 percent O_2) is acceptable for calibration of the O_2 cell. If needed, any lower percentage O_2 calibration gas must be a mixture of O_2 in nitrogen.

7.1.1 Up-Scale CO Calibration Gas Concentration. Choose one or more up-scale gas concentrations such that the average of the stack gas measurements for each stack gas sampling run are between 25 and 150 percent of those concentrations. Alternatively, choose an up-scale gas that does not exceed twice the concentration of the applicable outlet standard. If a measured gas value exceeds 150 percent of the up-scale CO calibration gas value at any time during the stack gas sampling run, the run must be discarded and repeated.

7.1.2 Up-Scale O_2 Calibration Gas Concentration.

Select an O_2 gas concentration such that the difference between the gas concentration and the average stack gas measurement or reading for each sample run is less than 15 percent O_2. When the average exhaust gas O_2 readings are above 6 percent, you may use dry ambient air (20.9 percent O_2) for the up-scale O_2 calibration gas.

7.1.3 Zero Gas. Use an inert gas that contains less than 0.25 percent of the up-scale CO calibration gas concentration. You may use dry air that is free from ambient CO and other combustion gas products (e.g., CO_2).

8.0 Sample Collection and Analysis

8.1 Selection of Sampling Sites.

8.1.1 Control Device Inlet. Select a sampling site sufficiently downstream of the engine so that the combustion gases should be well mixed. Use a single sampling extraction point near the center of the duct (e.g., within the 10 percent centroidal area), unless instructed otherwise.

8.1.2 Exhaust Gas Outlet. Select a sampling site located at least two stack diameters downstream of any disturbance (e.g., turbocharger exhaust, crossover junction or recirculation take-off) and at least one-half stack diameter upstream of the gas discharge to the atmosphere. Use a single sampling extraction point near the center of the duct (e.g., within the 10 percent centroidal area), unless instructed otherwise.

8.2 Stack Gas Collection and Analysis. Prior to the first stack gas sampling run, conduct that the pre-sampling calibration in accordance with Section 10.1. Use Figure 1 to record all data. Zero the analyzer with zero gas. Confirm and record that the scrubber media color is correct and not exhausted. Then position the probe at the sampling point and begin the sampling run at the same flow rate used during the up-scale calibration. Record the start time. Record all EC cell output responses and the flow rate during the ''sample conditioning phase'' once per minute until constant readings are obtained. Then begin the ''measurement data phase'' and record readings every 15 seconds for at least two minutes (or eight readings), or as otherwise required to achieve two continuous minutes of data that meet the specification given in Section 13.1. Finally, perform the ''refresh phase'' by introducing dry air, free from CO and other combustion gases, until several minute-to-minute readings of consistent value have been obtained. For each run use the ''measurement data phase'' readings to calculate the average stack gas CO and O_2 concentrations.

8.3 EC Cell Rate. Maintain the EC cell sample flow rate so that it does not vary by more than ±10 percent throughout the pre-sampling calibration, stack gas sampling and post-sampling calibration check. Alternatively, the EC cell sample flow rate can be maintained within a tolerance range that

does not affect the gas concentration readings by more than ±3 percent, as instructed by the EC cell manufacturer.

9.0 QUALITY CONTROL (RESERVED)

10.0 CALIBRATION AND STANDARDIZATION

10.1 Pre-Sampling Calibration. Conduct the following protocol once for each nominal range to be used on each EC cell before performing a stack gas sampling run on each field sampling day. Repeat the calibration if you replace an EC cell before completing all of the sampling runs. There is no prescribed order for calibration of the EC cells; however, each cell must complete the measurement data phase during calibration. Assemble the measurement system by following the manufacturer's recommended protocols including for preparing and preconditioning the EC cell. Assure the measurement system has no leaks and verify the gas scrubbing agent is not depleted. Use Figure 1 to record all data.

10.1.1 Zero Calibration. For both the O_2 and CO cells, introduce zero gas to the measurement system (e.g., at the calibration assembly) and record the concentration reading every minute until readings are constant for at least two consecutive minutes. Include the time and sample flow rate. Repeat the steps in this section at least once to verify the zero calibration for each component gas.

10.1.2 Zero Calibration Tolerance. For each zero gas introduction, the zero level output must be less than or equal to ±3 percent of the up-scale gas value or ±1 ppm, whichever is less restrictive, for the CO channel and less than or equal to ±0.3 percent O_2 for the O_2 channel.

10.1.3 Up-Scale Calibration. Individually introduce each calibration gas to the measurement system (e.g., at the calibration assembly) and record the start time. Record all EC cell output responses and the flow rate during this ''sample conditioning phase'' once per minute until readings are constant for at least two minutes. Then begin the ''measurement data phase'' and record readings every 15 seconds for a total of two minutes, or as otherwise required. Finally, perform the ''refresh phase'' by introducing dry air, free from CO and other combustion gases, until readings are constant for at least two consecutive minutes. Then repeat the steps in this section at least once to verify the calibration for each component gas. Introduce all gases to flow through the entire sample handling system (i.e., at the exit end of the sampling probe or the calibration assembly).

10.1.4 Up-Scale Calibration Error. The mean of the difference of the ''measurement data phase'' readings from the reported standard gas value must be less than or equal to ±5 percent or ±1 ppm for CO or ±0.5 percent O_2, whichever is less restrictive, respectively. The maximum allowable deviation from the mean measured value of any single ''measurement data phase'' reading must be less than or equal to ±2 percent or ±1 ppm for CO or ±0.5 percent O_2, whichever is less restrictive, respectively.

10.2 Post-Sampling Calibration Check. Conduct a stack gas post-sampling calibration check after the stack gas sampling run or set of runs and within 12 hours of the initial calibration. Conduct up-scale and zero calibration checks using the protocol in Section 10.1. Make no changes to the sampling system or EC cell calibration until all post-sampling calibration checks have been recorded. If either the zero or up-scale calibration error exceeds the respective specification in Sections 10.1.2 and 10.1.4 then all measurement data collected since the previous successful calibrations are invalid and re-calibration and re-sampling are required. If the sampling system is disassembled or the EC cell calibration is adjusted, repeat the calibration check before conducting the next analyzer sampling run.

11.0 ANALYTICAL PROCEDURE

The analytical procedure is fully discussed in Section 8.

12.0 CALCULATIONS AND DATA ANALYSIS

Determine the CO and O_2 concentrations for each stack gas sampling run by calculating the mean gas concentrations of the data recorded during the ''measurement data phase''.

13.0 PROTOCOL PERFORMANCE

Use the following protocols to verify consistent analyzer performance during each field sampling day.

13.1 Measurement Data Phase Performance Check. Calculate the mean of the readings from the ''measurement data phase''. The maximum allowable deviation from the mean for each of the individual readings is ±2 percent, or ±1 ppm, whichever is less restrictive. Record the mean value and maximum deviation for each gas monitored. Data must conform to Section 10.1.4. The EC cell flow rate must conform to the specification in Section 8.3.

Example: A measurement data phase is invalid if the maximum deviation of any single reading comprising that mean is greater than ±2 percent *or* ±1 ppm (the default criteria). For example, if the mean = 30 ppm, single readings of below 29 ppm and above 31 ppm are disallowed).

13.2 Interference Check. Before the initial use of the EC cell and interference gas scrubber in the field, and semi-annually thereafter, challenge the interference gas scrubber with NO and NO_2 gas standards that are

generally recognized as representative of diesel-fueled engine NO and NO_2 emission values. Record the responses displayed by the CO EC cell and other pertinent data on Figure 1 or a similar form.

13.2.1 Interference Response. The combined NO and NO_2 interference response should be less than or equal to ±5 percent of the up-scale CO calibration gas concentration.

13.3 Repeatability Check. Conduct the following check once for each nominal range that is to be used on the CO EC cell within 5 days prior to each field sampling program. If a field sampling program lasts longer than 5 days, repeat this check every 5 days. Immediately repeat the check if the EC cell is replaced or if the EC cell is exposed to gas concentrations greater than 150 percent of the highest up-scale gas concentration.

13.3.1 Repeatability Check Procedure. Perform a complete EC cell sampling run (all three phases) by introducing the CO calibration gas to the measurement system and record the response. Follow Section 10.1.3. Use Figure 1 to record all data. Repeat the run three times for a total of four complete runs. During the four repeatability check runs, do not adjust the system except where necessary to achieve the correct calibration gas flow rate at the analyzer.

13.3.2 Repeatability Check Calculations. Determine the highest and lowest average ''measurement data phase'' CO concentrations from the four repeatability check runs and record the results on Figure 1 or a similar form. The absolute value of the difference between the maximum and minimum average values recorded must not vary more than ±3 percent or ±1 ppm of the up-scale gas value, whichever is less restrictive.

14.0 Pollution Prevention (Reserved)

15.0 Waste Management (Reserved)

16.0 Alternative Procedures (Reserved)

17.0 References

(1) ''Development of an Electrochemical Cell Emission Analyzer Test Protocol'', Topical Report, Phil Juneau, Emission Monitoring, Inc., July 1997.

(2) ''Determination of Nitrogen Oxides, Carbon Monoxide, and Oxygen Emissions from Natural Gas-Fired Engines, Boilers, and Process Heaters Using Portable Analyzers'', EMC Conditional Test Protocol 30 (CTM–30), Gas Research Institute Protocol GRI–96/0008, Revision 7, October 13, 1997.

(3) ''ICAC Test Protocol for Periodic Monitoring'', EMC Conditional Test Protocol 34 (CTM–034), The Institute of Clean Air Companies, September 8, 1999.

(4) ''Code of Federal Regulations'', Protection of Environment, 40 CFR, Part 60, Appendix A, Methods 1–4; 10.

TABLE 1: APPENDIX A—SAMPLING RUN DATA.

Facility_____ Engine I.D._____ Date_____

Run Type: .....

(X) .....

	Pre-Sample Calibration			Stack Gas Sample				Post-Sample Cal. Check			Repeatability Check	
	( )	( )		( )				( )				
	1 O_2	1 CO	2 O_2	2 CO	3 O_2	3 CO	4 O_2	4 CO	Time	Scrub. OK	Flow- Rate
Run #											
Gas											
.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Sample Cond.											
Phase	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Measurement											
Data Phase	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Mean	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Refresh											
Phase	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
"	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....

[78 FR 6721, Jan. 30, 2013]

Subpart AAAAA—National Emission Standards for Hazardous Air Pollutants for Lime Manufacturing Plants

SOURCE: 69 FR 416, Jan. 5, 2004, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7080 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for lime manufacturing plants. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations.

§ 63.7081 Am I subject to this subpart?

(a) You are subject to this subpart if you own or operate a lime manufacturing plant (LMP) that is a major source, or that is located at, or is part of, a major source of hazardous air pollutant (HAP) emissions, unless the LMP is located at a kraft pulp mill, soda pulp mill, sulfite pulp mill, beet sugar manufacturing plant, or only processes sludge containing calcium carbonate from water softening processes.

(1) An LMP is an establishment engaged in the manufacture of lime product (calcium oxide, calcium oxide with magnesium oxide, or dead burned dolomite) by calcination of limestone, dolomite, shells or other calcareous substances.

(2) A major source of HAP is a plant site that emits or has the potential to emit any single HAP at a rate of 9.07 megagrams (10 tons) or more per year or any combination of HAP at a rate of 22.68 megagrams (25 tons) or more per year from all emission sources at the plant site.

(b) [Reserved]

§ 63.7082 What parts of my plant does this subpart cover?

(a) This subpart applies to each existing or new lime kiln(s) and their associated cooler(s), and processed stone handling (PSH) operations system(s) located at an LMP that is a major source.

(b) A new lime kiln is a lime kiln, and (if applicable) its associated lime cooler, for which construction or reconstruction began after December 20, 2002, if you met the applicability criteria in § 63.7081 at the time you began construction or reconstruction.

(c) A new PSH operations system is the equipment in paragraph (g) of this section, for which construction or reconstruction began after December 20, 2002, if you met the applicability criteria in § 63.7081 at the time you began construction or reconstruction.

(d) A lime kiln or PSH operations system is reconstructed if it meets the criteria for reconstruction defined in § 63.2.

(e) An existing lime kiln is any lime kiln, and (if applicable) its associated lime cooler, that does not meet the definition of a new kiln of paragraph (b) of this section.

(f) An existing PSH operations system is any PHS operations system that does not meet the definition of a new PSH operations system in paragraph (c) of this section.

(g) A PSH operations system includes all equipment associated with PSH operations beginning at the processed stone storage bin(s) or open storage pile(s) and ending where the processed stone is fed into the kiln. It includes man-made processed stone storage bins (but not open processed stone storage piles), conveying system transfer points, bulk loading or unloading systems, screening operations, surge bins, bucket elevators, and belt conveyors. No other materials processing operations are subject to this subpart.

(h) Nuisance dust collectors on lime coolers are part of the lime materials processing operations and are not covered by this subpart.

(i) Lime hydrators are not subject to this subpart.

(j) Open material storage piles are not subject to this subpart.

§ 63.7083 When do I have to comply with this subpart?

(a) If you have a new affected source, you must comply with this subpart according to paragraphs (a)(1) and (2) of this section.

(1) If you start up your affected source before January 5, 2004, you must comply with the emission limitations no later than January 5, 2004, and you must have completed all applicable performance tests no later than July 5, 2004, except as noted in paragraphs (e)(1) and (2) of this section.

(2) If you start up your affected source after January 5, 2004, then you must comply with the emission limitations for new affected sources upon startup of your affected source and you must have completed all applicable performance tests no later than 180 days after startup, except as noted in paragraphs (e)(1) and (2) of this section.

(b) If you have an existing affected source, you must comply with the applicable emission limitations for the existing affected source, and you must have completed all applicable performance tests no later than January 5, 2007, except as noted in paragraphs (e)(1) and (2) of this section.

(c) If you have an LMP that is an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP, the deadlines specified in paragraphs (c)(1) and (2) of this section apply.

(1) New affected sources at your LMP you must be in compliance with this subpart upon startup.

(2) Existing affected sources at your LMP must be in compliance with this subpart within 3 years after your source becomes a major source of HAP.

(d) You must meet the notification requirements in §63.7130 according to the schedule in §63.7130 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

(e)(1) If your affected source commenced construction or reconstruction on or before September, 16, 2019, then the compliance date for the revised requirements promulgated at §§63.7090, 63.7100, 63.7112, 63.7113, 63.7121, 63.7130, 63.7131, 63.7132, 63.7140, 63.7141, 63.7142, and 63.7143 and Tables 2, 3, 4, 5, 7, 8 and 9 (except changes to the cross references to 63.6(f)(1) and (h)(1)) of 40 CFR 63, subpart AAAAA, published on July 24, 2020 is January 20, 2021.

(2) If your affected source commenced construction or reconstruction after September 16, 2019, then the compliance date for the revised requirements promulgated at §§63.7090, 63.7100, 63.7112, 63.7113, 63.7121, 63.7130, 63.7131, 63.7132, 63.7140, 63.7141, 63.7142, and 63.7143 and Tables 2, 3, 4, 5, 7, 8 and 9 to this subpart, published on July 24, 2020 is July 24, 2020 or the date of initial startup, whichever is later.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44977, July 24, 2020]

Emission Limitations

§ 63.7090 What emission limitations must I meet?

(a) You must meet each emission limit in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit in Table 3 to this subpart that applies to you.

(c) On or after the relevant compliance date for your source as specified in §§63.7083(e), you must meet each startup and shutdown period emission limit in Table 2 to this subpart that applies to you.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44977, July 24, 2020]

General Compliance Requirements

§ 63.7100 What are my general requirements for complying with this subpart?

(a) Prior to the relevant compliance date for your source as specified in §63.7083(e), you must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods of startup, shutdown, and malfunction. On and after the relevant compliance date for your source as specified in §63.7083(e), you must be in compliance with the applicable emission limitations (including operating limits) at all times.

(b) Prior to the relevant compliance date for your source as specified in §63.7083(e), you must be in compliance with the opacity and visible emission (VE) limits in this subpart at all times, except during periods of startup, shutdown, and malfunction. On and after the relevant compliance date for your source as specified in §63.7083(e), you

must be in compliance with the applicable opacity and VE limits at all times.

(c) Prior to the relevant compliance date for your source as specified in § 63.7083(e), you must always operate and maintain your affected source, including air pollution control and monitoring equipment, according to the provisions in § 63.6(e)(1)(i). On and after the relevant compliance date for your source as specified in § 63.7083(e), you must always operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require the owner or operator to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether such operation and maintenance procedures are being used will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

(d) You must prepare and implement for each LMP, a written operations, maintenance, and monitoring (OM&M) plan. You must submit the plan to the applicable permitting authority for review and approval as part of the application for a 40 CFR part 70 or 40 CFR part 71 permit. Any subsequent changes to the plan must be submitted to the applicable permitting authority for review and approval. Pending approval by the applicable permitting authority of an initial or amended plan, you must comply with the provisions of the submitted plan. Each plan must contain the following information:

(1) Process and control device parameters to be monitored to determine compliance, along with established operating limits or ranges, as applicable, for each emission unit.

(2) A monitoring schedule for each emission unit.

(3) Procedures for the proper operation and maintenance of each emission unit and each air pollution control device used to meet the applicable emission limitations and operating limits in Tables 1, 2 and 3 to this subpart, respectively. On and after the relevant compliance date for your source as specified in § 63.7083(e), your OM&M plan must address periods of startup and shutdown.

(4) Procedures for the proper installation, operation, and maintenance of monitoring devices or systems used to determine compliance, including:

(i) Calibration and certification of accuracy of each monitoring device;

(ii) Performance and equipment specifications for the sample interface, parametric signal analyzer, and the data collection and reduction systems;

(iii) Prior to the relevant compliance date for your source as specified in § 63.7083(e), ongoing operation and maintenance procedures in accordance with the general requirements of §§ 63.8(c)(1)(i) and (ii), (3), and (4)(ii). On and after the relevant compliance date for your source as specified in § 63.7083(e), ongoing operation and maintenance procedures in accordance with the general requirements of paragraph (c) of this section and §§ 63.8(c)(1)(ii), (3), and (4)(ii); and

(iv) Ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d).

(5) Procedures for monitoring process and control device parameters.

(6) Corrective actions to be taken when process or operating parameters or add-on control device parameters deviate from the operating limits specified in Table 3 to this subpart, including:

(i) Procedures to determine and record the cause of a deviation or excursion, and the time the deviation or excursion began and ended; and

(ii) Procedures for recording the corrective action taken, the time corrective action was initiated, and the time and date the corrective action was completed.

(7) A maintenance schedule for each emission unit and control device that is consistent with the manufacturer's instructions and recommendations for routine and long-term maintenance.

(e) Prior to the relevant compliance date for your source as specified in § 63.7083(e), you must develop a written

startup, shutdown, and malfunction plan (SSMP) according to the provisions in § 63.6(e)(3).

[69 FR 416, Jan. 5, 2004, as amended at 71 FR 20467, Apr. 20, 2006; 85 FR 44977, July 24, 2020]

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.7110 By what date must I conduct performance tests and other initial compliance demonstrations?

(a) If you have an existing affected source, you must complete all applicable performance tests within January 5, 2007, according to the provisions in §§ 63.7(a)(2) and 63.7114.

(b) If you have a new affected source, and commenced construction or reconstruction between December 20, 2002, and January 5, 2004, you must demonstrate initial compliance with either the proposed emission limitation or the promulgated emission limitation no later than 180 calendar days after January 5, 2004 or within 180 calendar days after startup of the source, whichever is later, according to §§ 63.7(a)(2)(ix) and 63.7114.

(c) If you commenced construction or reconstruction between December 20, 2002, and January 5, 2004, and you chose to comply with the proposed emission limitation when demonstrating initial compliance, you must conduct a demonstration of compliance with the promulgated emission limitation within January 5, 2007 or after startup of the source, whichever is later, according to §§ 63.7(a)(2)(ix) and 63.7114.

(d) For each initial compliance requirement in Table 4 to this subpart that applies to you where the monitoring averaging period is 3 hours, the 3-hour period for demonstrating continuous compliance for emission units within existing affected sources at LMP begins at 12:01 a.m. on the compliance date for existing affected sources, that is, the day following completion of the initial compliance demonstration, and ends at 3:01 a.m. on the same day.

(e) For each initial compliance requirement in Table 4 to this subpart that applies to you where the monitoring averaging period is 3 hours, the 3-hour period for demonstrating continuous compliance for emission units within new or reconstructed affected sources at LMP begins at 12:01 a.m. on the day following completion of the initial compliance demonstration, as required in paragraphs (b) and (c) of this section, and ends at 3:01 a.m. on the same day.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44977, July 24, 2020]

§ 63.7111 When must I conduct subsequent performance tests?

You must conduct a performance test within 5 years following the initial performance test and within 5 years following each subsequent performance test thereafter.

§ 63.7112 What performance tests, design evaluations, and other procedures must I use?

(a) You must conduct each performance test in Table 5 to this subpart that applies to you.

(b) Prior to the relevant compliance date for your source as specified in § 63.7083(e), each performance test must be conducted according to the requirements in § 63.7(e)(1) and under the specific conditions specified in Table 5 to this subpart. On and after the relevant compliance date for your source as specified in § 63.7083(e), each performance test must be conducted based on representative performance (*i.e.*, performance based on normal operating conditions) of the affected source and under the specific conditions in Table 5 to this subpart. Representative conditions exclude periods of startup and shutdown. The owner or operator may not conduct performance tests during periods of malfunction. The owner or operator must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, the owner or operator shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(c) Prior to the relevant compliance date for your source as specified in

§ 63.7083(e), you may not conduct performance tests during periods of startup, shutdown, or malfunction, as specified in § 63.7(e)(1). On and after the relevant compliance date for your source as specified in § 63.7083(e), you may not conduct performance tests during periods of startup, shutdown, or malfunction, as specified in paragraph (b) of this section.

(d) Except for opacity and VE observations, you must conduct three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.

(e) The emission rate of particulate matter (PM) from each lime kiln (and each lime cooler if there is a separate exhaust to the atmosphere from the lime cooler) must be computed for each run using Equation 1 of this section:

$$E = \left(C_k Q_k + C_c Q_c\right)/PK \qquad \text{(Eq. 1)}$$

Where:

E = Emission rate of PM, pounds per ton (lb/ton) of stone feed.

C_k = Concentration of PM in the kiln effluent, grain/dry standard cubic feet (gr/dscf).

Q_k = Volumetric flow rate of kiln effluent gas, dry standard cubic feet per hour (dscf/hr).

C_c = Concentration of PM in the cooler effluent, grain/dscf. This value is zero if there is not a separate cooler exhaust to the atmosphere.

Q_c = Volumetric flow rate of cooler effluent gas, dscf/hr. This value is zero if there is not a separate cooler exhaust to the atmosphere.

P = Stone feed rate, tons per hour (ton/hr).

K = Conversion factor, 7000 grains per pound (grains/lb).

(f)(1) If you choose to meet a weighted average emission limit as specified in item 4 of Table 1 to this subpart, you must calculate a combined particulate emission rate from all kilns and coolers within your LMP using Equation 2 of this section:

$$E_T = \sum_{i=1}^{n} E_i P_i / \sum_{i=1}^{n} P_i \qquad \text{(Eq. 2)}$$

Where:

E_T = Emission rate of PM from all kilns and coolers, lb/ton of stone feed.

E_i = Emission rate of PM from kiln i, or from kiln/cooler combination i, lb/ton of stone feed.

P_i = Stone feed rate to kiln i, ton/hr.

n = Number of kilns you wish to include in averaging.

(2) You do not have to include every kiln in this calculation, only include kilns you wish to average. Kilns that have a PM emission limit of 0.60 lb/tsf are ineligible for any averaging.

(g) The weighted average PM emission limit from all kilns and coolers for which you are averaging must be calculated using Equation 3 of this section:

$$E_{TN} = \sum_{j=1}^{m} E_j P_j / \sum_{j=1}^{m} P_j \qquad \text{(Eq. 3)}$$

Where:

E_{TN} = Weighted average PM emission limit for all kilns and coolers being included in averaging at the LMP, lb/ton of stone feed.

E_j = PM emission limit (0.10 or 0.12) for kiln j, or for kiln/cooler combination j, lb/ton of stone feed.

P_j = Stone feed rate to kiln j, ton/hr.

m = Number of kilns and kiln/cooler combinations you are averaging at your LMP. You must include the same kilns in the calculation of E_T and E_{TN}. Kilns that have a PM emission limit of 0.60 lb/tsf are ineligible for any averaging.

(h) Performance test results must be documented in complete test reports that contain the information required by paragraphs (h)(1) through (10) of this section, as well as all other relevant information. The plan to be followed during testing must be made available to the Administrator at least 60 days prior to testing.

(1) A brief description of the process and the air pollution control system;

(2) Sampling location description(s);

(3) A description of sampling and analytical procedures and any modifications to standard procedures;

(4) Test results, including opacity;

(5) Quality assurance procedures and results;

(6) Records of operating conditions during the test, preparation of standards, and calibration procedures;

(7) Raw data sheets for field sampling and field and laboratory analyses;

(8) Documentation of calculations;

(9) All data recorded and used to establish operating limits; and

(10) Any other information required by the test method.

(i) [Reserved]

(j) You must establish any applicable 3-hour block average operating limit indicated in Table 3 to this subpart according to the applicable requirements in Table 4 to this subpart and paragraphs (j)(1) through (4) of this section.

(1) Continuously record the parameter during the PM performance test and include the parameter record(s) in the performance test report.

(2) Determine the average parameter value for each 15-minute period of each test run.

(3) Calculate the test run average for the parameter by taking the average of all the 15-minute parameter values for the run.

(4) Calculate the 3-hour operating limit by taking the average of the three test run averages.

(k) For each building enclosing any PSH operations that is subject to a VE limit, you must conduct a VE check according to item 18 in Table 5 to this subpart, and in accordance with paragraphs (k)(1) through (3) of this section.

(1) Conduct visual inspections that consist of a visual survey of the building over the test period to identify if there are VE, other than condensed water vapor.

(2) Select a position at least 15 but not more 1,320 feet from each side of the building with the sun or other light source generally at your back.

(3) The observer conducting the VE checks need not be certified to conduct EPA Method 9 in appendix A–4 to part 60 of this chapter. However, the observer must meet the training requirements as described in EPA Method 22 in appendix A–7 to part 60 of this chapter.

(l) When determining compliance with the opacity standards for fugitive emissions from PSH operations in item 8 of Table 1 to this subpart, you must conduct EPA Method 9 in appendix A–4 to part 60 of this chapter according to item 17 in Table 5 to this subpart, and in accordance with paragraphs (l)(1) through (3) of this section.

(1) The minimum distance between the observer and the emission source shall be 4.57 meters (15 feet).

(2) The observer shall, when possible, select a position that minimizes interference from other fugitive emission sources (*e.g.*, road dust). The required observer position relative to the sun must be followed.

(3) If you use wet dust suppression to control PM from PSH operations, a visible mist is sometimes generated by the spray. The water mist must not be confused with particulate matter emissions and is not to be considered VE. When a water mist of this nature is present, you must observe emissions at a point in the plume where the mist is no longer visible.

(m) On and after the relevant compliance date for your source as specified in § 63.7083(e), during startup, kilns must be tested hourly to determine when lime product meets the definition of on-specification lime product.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44977, July 24, 2020]

§ 63.7113 What are my monitoring installation, operation, and maintenance requirements?

(a) You must install, operate, and maintain each continuous parameter monitoring system (CPMS) according to your OM&M plan required by § 63.7100(d) and paragraphs (a)(1) through (5) of this section, and you must install, operate, and maintain each continuous opacity monitoring system (COMS) as required by paragraph (g) of this section

(1) The CPMS must complete a minimum of one cycle of operation for each successive 15-minute period.

(2) To calculate a valid hourly value, you must have at least four equally spaced data values (or at least two, if that condition is included to allow for periodic calibration checks) for that hour from a CPMS that is not out of control according your OM&M plan, and use all valid data.

(3) To calculate the average for each 3-hour block averaging period, you must use all valid data, and you must have at least 66 percent of the hourly averages for that period using only hourly average values that are based

on valid data (*i.e.*, not from out-of-control periods).

(4) You must conduct a performance evaluation of each CPMS in accordance with your OM&M plan.

(5) You must continuously operate and maintain the CPMS according to the OM&M plan, including, but not limited to, maintaining necessary parts for routine repairs of the monitoring equipment.

(b) For each flow measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and (b)(1) through (4) of this section.

(1) Use a flow sensor with a minimum tolerance of 2 percent of the flow rate.

(2) Reduce swirling flow or abnormal velocity distributions due to upstream and downstream disturbances.

(3) Conduct a flow sensor calibration check at least semiannually.

(4) At least monthly, inspect all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(c) For each pressure measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and (c)(1) through (7) of this section.

(1) Locate the pressure sensor(s) in or as close to as possible a position that provides a representative measurement of the pressure.

(2) Minimize or eliminate pulsating pressure, vibration, and internal and external corrosion.

(3) Use a gauge with a minimum tolerance of 0.5 inch of water or a transducer with a minimum tolerance of 1 percent of the pressure range.

(4) Check pressure tap pluggage daily.

(5) Using a manometer, check gauge calibration quarterly and transducer calibration monthly.

(6) Conduct calibration checks any time the sensor exceeds the manufacturer's specified maximum operating pressure range or install a new pressure sensor.

(7) At least monthly, inspect all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(d) For each bag leak detection system (BLDS), you must meet any applicable requirements in paragraphs (a)(1) through (5) and (d)(1) through (10) of this section.

(1) The BLDS must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The sensor on the BLDS must provide output of relative PM emissions.

(3) The BLDS must be equipped with a device to continuously record the output signal from the sensor.

(4) The BLDS must have an alarm that will sound automatically when it detects an increase in relative PM emissions greater than a preset level.

(5) The alarm must be located in an area where appropriate plant personnel will be able to hear it.

(6) For a positive-pressure fabric filter (FF), each compartment or cell must have a bag leak detector (BLD). For a negative-pressure or induced-air FF, the BLD must be installed downstream of the FF. If multiple BLD are required (for either type of FF), the detectors may share the system instrumentation and alarm.

(7) Each triboelectric BLDS must be installed, calibrated, operated, and maintained according to EPA–454/R–98–015, ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference—see § 63.14). Other types of bag leak detection systems must be installed, operated, calibrated, and maintained according to the manufacturer's written specifications and recommendations. Standard operating procedures must be incorporated into the OM&M plan.

(8) At a minimum, initial adjustment of the system must consist of establishing the baseline output in both of the following ways, according to section 5.0 of the EPA–454/R–98–015, ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference—see § 63.14):

(i) Adjust the range and the averaging period of the device.

(ii) Establish the alarm set points and the alarm delay time.

(9) After initial adjustment, the sensitivity or range, averaging period, alarm set points, or alarm delay time may not be adjusted except as specified in the OM&M plan required by

§ 63.7100(d). In no event may the range be increased by more than 100 percent or decreased by more than 50 percent over a 365-day period unless such adjustment follows a complete FF inspection that demonstrates that the FF is in good operating condition, as defined in section 5.2 of the ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference—see § 63.14). Record each adjustment.

(10) Record the results of each inspection, calibration, and validation check.

(e) For each PM detector, you must meet any applicable requirements in paragraphs (a)(1) through (5) and (e)(1) through (8) of this section.

(1) The PM detector must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The sensor on the PM detector must provide output of relative PM emissions.

(3) The PM detector must have an alarm that will sound automatically when it detects an increase in relative PM emissions greater than a preset level.

(4) The alarm must be located in an area where appropriate plant personnel will be able to hear it.

(5) For a positive-pressure electrostatic precipitator (ESP), each compartment must have a PM detector. For a negative-pressure or induced-air ESP, the PM detector must be installed downstream of the ESP. If multiple PM detectors are required (for either type of ESP), the detectors may share the system instrumentation and alarm.

(6) Particulate matter detectors must be installed, operated, adjusted, and maintained according to the manufacturer's written specifications and recommendations. Standard operating procedures must be incorporated into the OM&M plan.

(7) At a minimum, initial adjustment of the system must consist of establishing the baseline output in both of the following ways:

(i) Adjust the range and the averaging period of the device.

(ii) Establish the alarm set points and the alarm delay time.

(8) After initial adjustment, the range, averaging period, alarm set points, or alarm delay time may not be adjusted except as specified in the OM&M plan required by § 63.7100(d). In no event may the range be increased by more than 100 percent or decreased by more than 50 percent over a 365-day period unless a responsible official as defined in § 63.2 certifies in writing to the Administrator that the ESP has been inspected and found to be in good operating condition.

(f) For each emission unit equipped with an add-on air pollution control device, you must inspect each capture/collection and closed vent system at least once each calendar year to ensure that each system is operating in accordance with the operating requirements in item 6 of Table 3 to this subpart and record the results of each inspection.

(g) For each COMS used to monitor an add-on air pollution control device, you must meet the requirements in paragraphs (g)(1) and (2) of this section.

(1) Install the COMS at the outlet of the control device.

(2) Install, maintain, calibrate, and operate the COMS as required by 40 CFR part 63, subpart A, General Provisions and according to Performance Specification (PS)–1 of appendix B to part 60 of this chapter. Facilities that operate COMS installed on or before February 6, 2001, may continue to meet the requirements in effect at the time of COMS installation unless specifically required to re-certify the COMS by their permitting authority.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44978, July 24, 2020]

§ 63.7114 How do I demonstrate initial compliance with the emission limitations standard?

(a) You must demonstrate initial compliance with each emission limit in Table 1 to this subpart that applies to you, according to Table 4 to this subpart. For existing lime kilns and their associated coolers, you may perform VE measurements in accordance with EPA Method 9 of appendix A to part 60 in lieu of installing a COMS or PM detector if any of the conditions in paragraphs (a)(1) through (3) of this section exist:

(1) You use a FF for PM control, and the FF is under positive pressure and has multiple stacks; or

(2) The control device exhausts through a monovent; or

(3) The installation of a COMS in accordance with PS–1 of appendix B to part 60 is infeasible.

(b) You must establish each site-specific operating limit in Table 3 to this subpart that applies to you according to the requirements in §63.7112(j) and Table 5 to this subpart. Alternative parameters may be monitored if approval is obtained according to the procedures in §63.8(f).

(c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in §63.7130(e).

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44979, July 24, 2020]

CONTINUOUS COMPLIANCE REQUIREMENTS

§63.7120 How do I monitor and collect data to demonstrate continuous compliance?

(a) You must monitor and collect data according to this section.

(b) Except for monitor malfunctions, associated repairs, required quality assurance or control activities (including, as applicable, calibration checks and required zero adjustments), and except for PSH operations subject to monthly VE testing, you must monitor continuously (or collect data at all required intervals) at all times that the emission unit is operating.

(c) Data recorded during the conditions described in paragraphs (c)(1) and (2) of this section may not be used either in data averages or calculations of emission or operating limits; or in fulfilling a minimum data availability requirement. You must use all the data collected during all other periods in assessing the operation of the control device and associated control system.

(1) Monitoring system breakdowns, repairs, preventive maintenance, calibration checks, and zero (low-level) and high-level adjustments;

(2) Periods of non-operation of the process unit (or portion thereof), resulting in cessation of the emissions to which the monitoring applies; and

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44979, July 24, 2020]

§63.7121 How do I demonstrate continuous compliance with the emission limitations standard?

(a) You must demonstrate continuous compliance with each emission limitation in Tables 1 and 3 to this subpart that applies to you according to the methods specified in Tables 6 and 7 to this subpart.

(b) You must report each instance in which you did not meet each operating limit, opacity limit, and VE limit in Tables 2, 3 and 7 to this subpart that applies to you. These deviations must be reported according to the requirements in §63.7131.

(c) [Reserved]

(d) Prior to the relevant compliance date for your source as specified in §63.7083(e), consistent with §§63.6(e) and 63.7(e)(1), deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with §63.6(e)(1). The Administrator will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in §63.6(e).

(e) For each PSH operation subject to an opacity limit as specified in Table 1 to this subpart, and any vents from buildings subject to an opacity limit, you must conduct a VE check according to item 1 in Table 7 to this subpart, and as follows:

(1) Conduct visual inspections that consist of a visual survey of each stack or process emission point over the test period to identify if there are VE, other than condensed water vapor.

(2) Select a position at least 15 but not more 1,320 feet from the affected emission point with the sun or other light source generally at your back.

(3) The observer conducting the VE checks need not be certified to conduct EPA Method 9 in appendix A–4 to part 60 of this chapter but must meet the training requirements as described in EPA Method 22 of appendix A–7 to part 60 of this chapter.

(f) For existing lime kilns and their associated coolers, you may perform VE measurements in accordance with EPA Method 9 of appendix A to part 60 in lieu of installing a COMS or PM detector if any of the conditions in paragraphs (f)(1) or (3) of this section exist:

(1) You use a FF for PM control, and the FF is under positive pressure and has multiple stacks; or

(2) The control device exhausts through a monovent; or

(3) The installation of a COMS in accordance with PS–1 of appendix B to part 60 is infeasible.

[69 FR 416, Jan. 5, 2004, as amended at 71 FR 20467, Apr. 20, 2006; 85 FR 44979, July 24, 2020]

NOTIFICATION, REPORTS, AND RECORDS

§ 63.7130 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.6(h)(4) and (5); 63.7(b) and (c); 63.8(e); (f)(4) and (6); and 63.9 (a) through (j) that apply to you, by the dates specified.

(b) As specified in § 63.9(b)(2), if you start up your affected source before January 5, 2004, you must submit an initial notification not later than 120 calendar days after January 5, 2004, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) If you startup your new or reconstructed affected source on or after January 5, 2004, you must submit an initial notification not later than 120 calendar days after you start up your affected source, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin, as required in § 63.7(b)(1).

(e) If you are required to conduct a performance test, design evaluation, opacity observation, VE observation, or other initial compliance demonstration as specified in Table 4 or 5 to this subpart, you must submit a Notification of Compliance Status according to § 63.9(h)(2)(ii). Beginning on the relevant compliance date for your source as specified in § 63.7083(e), submit all subsequent Notification of Compliance Status following the procedure specified in § 63.7131(h).

(1) For each initial compliance demonstration required in Table 4 to this subpart that does not include a performance test, you must submit the Notification of Compliance Status before the close of business on the 30th calendar day following the completion of the initial compliance demonstration.

(2) For each compliance demonstration required in Table 6 to this subpart that includes a performance test conducted according to the requirements in Table 5 to this subpart, you must submit the Notification of Compliance Status, including the performance test results, before the close of business on the 60th calendar day following the completion of the performance test according to § 63.10(d)(2).

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44979, July 24, 2020; 85 FR 73912, Nov. 19, 2020]

§ 63.7131 What reports must I submit and when?

(a) You must submit each report listed in Table 8 to this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report by the date specified in Table 8 to this subpart and according to the requirements in paragraphs (b)(1) through (6) of this section:

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.7083 and ending on June 30 or December 31, whichever date is the first date following the end of the first half calendar year after the compliance date that is specified for your source in § 63.7083.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date follows the end of the first half calendar year after the compliance date that is specified for your affected source in § 63.7083.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting

period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date is the first date following the end of the semiannual reporting period.

(5) For each affected source that is subject to permitting regulations pursuant to part 70 or part 71 of this chapter, if the permitting authority has established dates for submitting semiannual reports pursuant to §§ 70.6(a)(3)(iii)(A) or 71.6(a)(3)(iii)(A) of this chapter, you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of according to the dates specified in paragraphs (b)(1) through (4) of this section.

(6) Beginning on the relevant compliance date for your source as specified in § 63.7083(e), submit all subsequent compliance reports following the procedure specified in paragraph (h) of this section.

(c) The compliance report must contain the information specified in paragraphs (c)(1) through (6) of this section.

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) Prior to the relevant compliance date for your source as specified in § 63.7083(e), if you had a startup, shutdown or malfunction during the reporting period and you took actions consistent with your SSMP, the compliance report must include the information in § 63.10(d)(5)(i).

(5) If there were no deviations from any emission limitations (emission limit, operating limit, opacity limit, and VE limit) that apply to you, the compliance report must include a statement that there were no deviations from the emission limitations during the reporting period.

(6) If there were no periods during which the continuous monitoring systems (CMS) were out-of-control as specified in § 63.8(c)(7), a statement that there were no periods during which the CMS were out-of-control during the reporting period.

(d) For each deviation from an emission limitation (emission limit, operating limit, opacity limit, and VE limit) that occurs at an affected source where you are not using a CMS to comply with the emission limitations in this subpart, the compliance report must contain the information specified in paragraphs (c)(1) through (4) and (d)(1) and (2) of this section. The deviations must be reported in accordance with the requirements in § 63.10(d) prior to the relevant compliance date for your source as specified in § 63.7083(e) and the requirements in § 63.10(d)(1)–(4) beginning on the relevant compliance date for your source as specified in § 63.7083(e).

(1) The total operating time of each emission unit during the reporting period.

(2) Information on the number, duration, and cause of deviations (including unknown cause, if applicable), and the corrective action taken.

(3) An estimate of the quantity of each regulated pollutant emitted over a particulate matter emission limit, and a description of the method used to estimate the emissions.

(e) For each deviation from an emission limitation (emission limit, operating limit, opacity limit, and VE limit) occurring at an affected source where you are using a CMS to comply with the emission limitation in this subpart, you must include the information specified in paragraphs (c)(1) through (4) and (e)(1) through (11) of this section, except that beginning on the relevant compliance date for your source as specified in 63.7083(e), the semiannual compliance report must also include the information included in paragraph (e)(12) of this section. This includes periods of startup, shutdown, and malfunction.

(1) The date and time that each malfunction started and stopped.

(2) The date, time, and duration that each CMS was inoperative, except for zero (low-level) and high-level checks.

(3) The date, time and duration that each CMS was out-of-control, including the information in § 63.8(c)(8).

(4) The date and time that each deviation started and stopped, and whether

each deviation occurred during a period of startup, shutdown, or malfunction or during another period.

(5) A summary of the total duration of the deviations during the reporting period and the total duration as a percent of the total affected source operating time during that reporting period.

(6) A breakdown of the total duration of the deviations during the reporting period into those that are due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes.

(7) A summary of the total duration of CMS downtime during the reporting period and the total duration of CMS downtime as a percent of the total emission unit operating time during that reporting period.

(8) A brief description of the process units.

(9) A brief description of the CMS.

(10) The date of the latest CMS certification or audit.

(11) A description of any changes in CMS, processes, or controls since the last reporting period.

(12) An estimate of the quantity of each regulated pollutant emitted over a particulate matter emission limit, and a description of the method used to estimate the emissions.

(f) Each facility that has obtained a title V operating permit pursuant to part 70 or part 71 of this chapter must report all deviations as defined in this subpart in the semiannual monitoring report required by §70.6(a)(3)(iii)(A) or 71.6(a)(3)(iii)(A) of this chapter. If you submit a compliance report specified in Table 8 to this subpart along with, or as part of, the semiannual monitoring report required by §70.6(a)(3)(iii)(A) or 71.6(a)(3)(iii)(A) of this chapter, and the compliance report includes all required information concerning deviations from any emission limitation (including any operating limit), submission of the compliance report shall be deemed to satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report shall not otherwise affect any obligation you may have to report deviations from permit requirements to the permit authority.

(g) If you are required to submit reports following the procedure specified in this paragraph, you must submit reports to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). You must use the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/compliance-and-emissions-data-reporting-interface-cedri*) for this subpart. The date report templates become available will be listed on the CEDRI website. The report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. If you claim some of the information required to be submitted via CEDRI is confidential business information (CBI), submit a complete report, including information claimed to be CBI, to the EPA. The report must be generated using the appropriate form on the CEDRI website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph.

(h) Within 60 days after the date of completing each performance test required by this subpart, you must submit the results of the performance test following the procedures specified in paragraphs (h)(1) through (3) of this section.

(1) *Data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test to the EPA via CEDRI, which can be accessed through the EPA's CDX (*https://cdx.epa.gov/*). The data must be submitted in a file format generated

through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the extensible markup language (XML) schema listed on the EPA's ERT website.

(2) *Data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the test.* The results of the performance test must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *Confidential business information (CBI).* If you claim some of the information submitted under paragraph (i) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to the EPA. The file must be generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described in paragraph (i) of this section.

(i) If you are required to electronically submit a report or notification through CEDRI in the EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement. To assert a claim of EPA system outage, you must meet the requirements outlined in paragraphs (i)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either the EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning five business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(j) If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of force majeure for failure to timely comply with the reporting requirement. To assert a claim of force majeure, you must meet the requirements outlined in paragraphs (j)(1) through (5) of this section.

(1) You may submit a claim if a force majeure event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For the purposes of this section, a force majeure event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (*e.g.,* hurricanes, earthquakes, or floods), acts of war or terrorism, or

equipment failure or safety hazard beyond the control of the affected facility (*e.g.*, large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the force majeure event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the force majeure event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of force majeure and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the force majeure event occurs.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44979, July 24, 2020]

§ 63.7132 What records must I keep?

(a) You must keep the records specified in paragraphs (a)(1) through (3) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) Prior to the relevant compliance date for your source as specified in § 63.7083(e), the records in § 63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunction. On and after the relevant compliance date for your source as specified in § 63.7083(e), the records in paragraphs (a)(2)(i) and (ii) of this section.

(i) You must keep records for each startup period of the date, the time startup began, the time began producing on-specification lime product, and the time discharge from the kiln began for any affected source that is subject to a standard during startup that differs from the standard applicable at other times.

(ii) You must keep records of the date, time, cause and duration of each malfunction (as defined in 40 CFR 63.2) that causes an affected source to fail to meet an applicable standard; if there was also a monitoring malfunction, the date, time, cause, and duration of the monitoring malfunction; the record must list the affected source or equipment; if there was a failure to meet a particulate matter emissions limit, an estimate of the volume of each regulated pollutant emitted over the limit, and a description of the method used to estimate the emissions.

(3) Records of performance tests, performance evaluations, and opacity and VE observations as required in § 63.10(b)(2)(viii).

(b) You must keep the records in § 63.6(h)(6) for VE observations.

(c) You must keep the records required by Tables 6 and 7 to this subpart to show continuous compliance with each emission limitation that applies to you.

(d) You must keep the records which document the basis for the initial applicability determination as required under § 63.7081.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44981, July 24, 2020]

§ 63.7133 In what form and for how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record onsite for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You may keep the records offsite for the remaining 3 years.

(d) Any records required to be maintained by this part that are submitted electronically via the EPA's CEDRI

may be maintained in electronic format. This ability to maintain electronic copies does not affect the requirement for facilities to make records, data, and reports available upon request to a delegated air agency or the EPA as part of an on-site compliance evaluation.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44981, July 24, 2020]

OTHER REQUIREMENTS AND INFORMATION

§ 63.7140 What parts of the General Provisions apply to me?

Table 9 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.16 apply to you. When there is overlap between subpart A and subpart AAAAA, as indicated in the ''Explanations'' column in Table 8, subpart AAAAA takes precedence.

[85 FR 44981, July 24, 2020]

§ 63.7141 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. EPA, or by a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency (as well as the U.S. EPA) has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities that will not be delegated to State, local, or tribal agencies are as specified in paragraphs (c)(1) through (7) of this section.

(1) Approval of alternatives to the non-opacity emission limitations in § 63.7090(a).

(2) Approval of alternative opacity emission limitations in § 63.7090(a) and (c).

(3) Approval of alternatives to the operating limits in § 63.7090(b).

(4) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(5) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(6) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(7) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44981, July 24, 2020]

§ 63.7142 What are the requirements for claiming area source status?

(a) If you wish to claim that your LMP is an area source, you must measure the emissions of hydrogen chloride from all lime kilns, except as provided in paragraph (c) of this section, at your plant using either:

(1) EPA Method 320 of appendix A to this part, or

(2) As an alternative to Method 320 of Appendix A, ASTM D6348–03 (Reapproved 2010) including Annexes A1 through A8 (incorporated by reference—see § 63.14). ASTM D6348–12e1 (incorporated by reference—see § 63.14) is an acceptable alternative to EPA Method 320 of appendix A, provided that the provisions of paragraphs (a)(2)(i) and (ii) of this section are followed:

(i) The test plan preparation and implementation in the Annexes to ASTM D6348–03 (Reapproved 2010), Sections A1 through A8 are mandatory.

(ii) In ASTM D6348–03 (Reapproved 2010) Annex A5 (Analyte Spiking Technique), the percent recovery (%R) must be determined for each target analyte (Equation A5.5). In order for the test data to be acceptable for a compound, %R must be greater than or equal to 70 percent and less than or equal to 130 percent. If the %R value does not meet this criterion for a target compound, the test data are not acceptable for that compound and the test must be repeated for that analyte (*i.e.*, the sampling and/or analytical procedure should be adjusted before a retest). The %R value for each compound must be reported in the test report, and all field

measurements must be corrected with the calculated %R value for that compound by using the following equation: Reported Results = ((Measured Concentration in the Stack))/(%R) × 100; or

(3) EPA Method 321 of appendix A to this part, or

(4) As an alternative to EPA Method 321, ASTM Method D6735–01 (Reapproved 2009), (incorporated by reference—see §63.14), provided that the provisions in paragraphs (a)(3)(i) through (vi) of this section are followed.

(i) A test must include three or more runs in which a pair of samples is obtained simultaneously for each run according to section 11.2.6 of ASTM Method D6735–01 (Reapproved 2009).

(ii) You must calculate the test run standard deviation of each set of paired samples to quantify data precision, according to Equation 1 of this section:

$$RSD_a = (100)\ \text{Absolute Value}\left[\frac{C1_a - C2_a}{C1_a + C2_a}\right] \qquad \text{(Eq. 1)}$$

Where:

RSD_a = The test run relative standard deviation of sample pair a, percent.

$C1_a$ and $C2_a$ = The HCl concentrations, milligram/dry standard cubic meter(mg/dscm), from the paired samples.

(iii) You must calculate the test average relative standard deviation according to Equation 2 of this section:

$$RSD_{TA} = \frac{\sum_{a=1}^{p} RSD_a}{p} \qquad \text{(Eq. 2)}$$

Where:

RSD_{TA} = The test average relative standard deviation, percent.

RSD_a = The test run relative standard deviation for sample pair a.

p = The number of test runs, ≥3.

(iv) If RSD^{TA} is greater than 20 percent, the data are invalid and the test must be repeated.

(v) The post-test analyte spike procedure of section 11.2.7 of ASTM Method D6735–01 (Reapproved 2009) is conducted, and the percent recovery is calculated according to section 12.6 of ASTM Method D6735–01 (Reapproved 2009).

(vi) If the percent recovery is between 70 percent and 130 percent, inclusive, the test is valid. If the percent recovery is outside of this range, the data are considered invalid, and the test must be repeated.

(b) If you conduct tests to determine the rates of emission of specific organic HAP from lime kilns at LMP for use in applicability determinations under §63.7081, you may use either:

(1) Method 320 of appendix A to this part, or

(2) As an alternative to Method 320 of Appendix A, ASTM D6348–03 (Reapproved 2010) including Annexes A1 through A8 (incorporated by reference—see §63.14). ASTM D6348–12e1 (incorporated by reference—see §63.14) is an acceptable alternative to EPA Method 320 of appendix A, provided that the provisions of paragraphs (b)(2)(i) and (ii) of this section are followed:

(i) The test plan preparation and implementation in the Annexes to ASTM D6348–03 (Reapproved 2010), Sections A1 through A8 are mandatory.

(ii) In ASTM D6348–03 (Reapproved 2010) Annex A5 (Analyte Spiking Technique), the percent recovery (%R) must be determined for each target analyte (Equation A5.5). In order for the test data to be acceptable for a compound, %R must be greater than or equal to 70 percent and less than or equal to 130 percent. If the %R value does not meet this criterion for a target compound, the test data are not acceptable for that compound and the test must be repeated for that analyte (*i.e.*, the sampling and/or analytical procedure should be adjusted before a retest). The %R value for each compound must be reported in the test report, and all field measurements must be corrected with

the calculated %R value for that compound by using the following equation: Reported Results = ((Measured Concentration in the Stack))/(%R) × 100; or

(3) Method 18 of appendix A–6 to part 60 of this chapter; or

(4) As an alternative to Method 18, ASTM D6420–99 (Reapproved 2010), (incorporated by reference—see § 63.14), provided that the provisions of paragraphs (b)(3)(i) through (iv) of this section are followed:

(i) The target compound(s) are those listed in section 1.1 of ASTM D6420–99 (Reapproved 2010) as measurable;

(ii) This ASTM should not be used for methane and ethane because their atomic mass is less than 35 and

(iii) ASTM D6420–99 (Reapproved 2010) should never be specified as a total VOC method.

(c) It is left to the discretion of the permitting authority whether or not idled kilns must be tested for (HCl) to claim area source status. If the facility has kilns that use common feed materials and fuel, are essentially identical in design, and use essentially identical emission controls, the permitting authority may also determine if one kiln can be tested, and the HCl emissions for the other essentially identical kilns be estimated from that test.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44981, July 24, 2020]

§ 63.7143 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in § 63.2, and in this section as follows:

Bag leak detector system (BLDS) is a type of PM detector used on FF to identify an increase in PM emissions resulting from a broken filter bag or other malfunction and sound an alarm.

Belt conveyor means a conveying device that transports *processed stone* from one location to another by means of an endless belt that is carried on a series of idlers and routed around a pulley at each end.

Bucket elevator means a *processed stone* conveying device consisting of a head and foot assembly which supports and drives an endless single or double strand chain or belt to which buckets are attached.

Building means any frame structure with a roof.

Capture system means the equipment (including enclosures, hoods, ducts, fans, dampers, etc.) used to capture and transport PM to a control device.

Control device means the air pollution control equipment used to reduce PM emissions released to the atmosphere from one or more process operations at an LMP.

Conveying system means a device for transporting *processed stone* from one piece of equipment or location to another location within a plant. Conveying systems include but are not limited to feeders, belt conveyors, bucket elevators and pneumatic systems.

Deviation means any instance in which an affected source, subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart, including but not limited to any emission limitation (including any operating limit);

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Prior to the relevant compliance date for your source as specified in § 63.7083(e), fails to meet any emission limitation (including any operating limit) in this subpart during startup, shutdown, or malfunction, regardless of whether or not such failure is allowed by this subpart.

Emission limitation means any emission limit, opacity limit, operating limit, or VE limit.

Emission unit means a lime kiln, lime cooler, storage bin, conveying system transfer point, bulk loading or unloading operation, bucket elevator or belt conveyor at an LMP.

Fugitive emission means PM that is not collected by a capture system.

Hydrator means the device used to produce hydrated lime or calcium hydroxide via the chemical reaction of the lime product with water.

Lime cooler means the device external to the lime kiln (or part of the lime

kiln itself) used to reduce the temperature of the lime produced by the kiln.

Lime kiln means the device, including any associated preheater, used to produce a lime product from stone feed by calcination. Kiln types include, but are not limited to, rotary kiln, vertical kiln, rotary hearth kiln, double-shaft vertical kiln, and fluidized bed kiln.

Lime manufacturing plant (LMP) means any plant which uses a lime kiln to produce lime product from limestone or other calcareous material by calcination.

Lime product means the product of the lime kiln calcination process including, calcitic lime, dolomitic lime, and dead-burned dolomite.

Limestone means the material comprised primarily of calcium carbonate (referred to sometimes as calcitic or high calcium limestone), magnesium carbonate, and/or the double carbonate of both calcium and magnesium (referred to sometimes as dolomitic limestone or dolomite).

Monovent means an exhaust configuration of a building or emission control device (*e.g.*, positive pressure FF) that extends the length of the structure and has a width very small in relation to its length (*i.e.*, length-to-width ratio is typically greater than 5:1). The exhaust may be an open vent with or without a roof, louvered vents, or a combination of such features.

On-specification Lime Product means lime product that has been sufficiently calcined to meet end use requirements.

Particulate matter (PM) detector means a system that is continuously capable of monitoring PM loading in the exhaust of FF or ESP in order to detect bag leaks, upset conditions, or control device malfunctions and sounds an alarm at a preset level. A PM detector system includes, but is not limited to, an instrument that operates on triboelectric, light scattering, light transmittance, or other effects to continuously monitor relative particulate loadings. A BLDS is a type of PM detector.

Positive pressure FF or ESP means a FF or ESP with the fan(s) on the upstream side of the control device.

Process stone handling operations means the equipment and transfer points between the equipment used to transport *processed stone*, and includes, storage bins, conveying system transfer points, bulk loading or unloading systems, screening operations, bucket elevators, and belt conveyors.

Processed stone means limestone or other calcareous material that has been processed to a size suitable for feeding into a lime kiln.

Screening operation means a device for separating material according to size by passing undersize material through one or more mesh surfaces (screens) in series and retaining oversize material on the mesh surfaces (screens).

Shutdown means the cessation of kiln operation. Shutdown begins when feed to the kiln is reduced below planned production quantities and ends when stone feed is halted and fuel combustion from the main burner ceases.

Stack emissions means the PM that is released to the atmosphere from a capture system or control device.

Startup means the beginning of kiln operation. Startup begins when a shutdown kiln begins firing fuel in the main burner. Startup ends when the lime kiln first generates on-specification lime product or 12 hours following first discharge from the kiln, whichever is earlier.

Storage bin means a manmade enclosure for storage (including surge bins) of *processed stone* prior to the lime kiln.

Transfer point means a point in a conveying operation where the material is transferred to or from a belt conveyor.

Vent means an opening through which there is mechanically induced air flow for the purpose of exhausting from a building air carrying PM emissions from one or more emission units.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44982, July 24, 2020]

TABLE 1 TO SUBPART AAAAA OF PART 63—EMISSION LIMITS

As required in §63.7090(a), you must meet each emission limit in the following table that applies to you, except for kilns and coolers during startup and shutdown (See Table 2 for emission limits for kilns and coolers during startup and shutdown).

For . . .	You must meet the following emission limit
1. Existing lime kilns and their associated lime coolers that did not have a wet scrubber installed and operating prior to January 5, 2004.	PM emissions must not exceed 0.12 pounds per ton of stone feed (lb/tsf).
2. Existing lime kilns and their associated lime coolers that have a wet scrubber, where the scrubber itself was installed and operating prior to January 5, 2004.	PM emissions must not exceed 0.60 lb/tsf. If at any time after January 5, 2004 the kiln changes to a dry control system, then the PM emission limit in item 1 of this Table 1 applies, and the kiln is hereafter ineligible for the PM emission limit in item 2 of this Table 1 regardless of the method of PM control.
3. New lime kilns and their associated lime coolers	PM emissions must not exceed 0.10 lb/tsf.
4. All existing and new lime kilns and their associated coolers at your LMP, and you choose to average PM emissions, except that any kiln that is allowed to meet the 0.60 lb/tsf PM emission limit is ineligible for averaging.	Weighted average PM emissions calculated according to Eq. 2 in §63.7112 must not exceed 0.12 lb/tsf (if you are averaging only existing kilns) or 0.10 lb/tsf (if you are averaging only new kilns). If you are averaging existing and new kilns, your weighted average PM emissions must not exceed the weighted average emission limit calculated according to Eq. 3 in §63.7112, except that no new kiln and its associated cooler considered alone may exceed an average PM emissions limit of 0.10 lb/tsf.
5. Stack emissions from all PSH operations at a new or existing affected source.	PM emissions must not exceed 0.05 grams per dry standard cubic meter (g/dscm).
6. Stack emissions from all PSH operations at a new or existing affected source, unless the stack emissions are discharged through a wet scrubber control device.	Emissions must not exceed 7 percent opacity.
7. Fugitive emissions from all PSH operations at a new or existing affected source, except as provided by item 8 of this Table 1.	Emissions must not exceed 10 percent opacity.
8. All PSH operations at a new or existing affected source enclosed in a building.	All of the individually affected PSH operations must comply with the applicable PM and opacity emission limitations in items 5 through 7 of this Table 1, or the building must comply with the following: There must be no VE from the building, except from a vent; and vent emissions must not exceed the stack emissions limitations in items 5 and 6 of this Table 1.
9. Each FF that controls emissions from only an individual, enclosed storage bin.	Emissions must not exceed 7 percent opacity.
10. Each set of multiple storage bins at a new or existing affected source, with combined stack emissions.	You must comply with the emission limits in items 5 and 6 of this Table 1.

[69 FR 416, Jan. 5, 2004, as amended at 85 FR 44982, July 24, 2020]

TABLE 2 TO SUBPART AAAAA OF PART 63—STARTUP AND SHUTDOWN EMISSION LIMITS FOR KILNS AND COOLERS

As required in §63.7090(b), on and after the relevant compliance date for your source as specified in §63.7083(e), you must meet each emission limit in the following table that applies to you.

TABLE 2 TO SUBPART AAAAA OF PART 63—STARTUP AND SHUTDOWN EMISSION LIMITS FOR KILNS AND COOLERS

For . . .	You must meet the following emission limit	You have demonstrated compliance, if after following the requirements in §63.7112 . . .
1. All new and existing lime kilns and their associated coolers equipped with an FF or an ESP during each startup.	Emissions must not exceed 15 percent opacity (based on startup period block average).	i. Installed, maintained, calibrated and operated a COMS as required by 40 CFR part 63, subpart A, General Provisions and according to PS–1 of appendix B to part 60 of this chapter, except as specified in §63.7113(g)(2); ii. Collected the COMS data at a frequency of at least once every 15 seconds, determining block averages for each startup period and demonstrating for each startup block period the average opacity does not exceed 15 percent.
2. All existing lime kilns and their associated coolers that have a wet scrubber during each startup.	See item 2.b of Table 3 of subpart AAAAA for emission limit.	See item 1 of Table 6 of subpart AAAAA for requirements for demonstrating compliance.

TABLE 2 TO SUBPART AAAAA OF PART 63—STARTUP AND SHUTDOWN EMISSION LIMITS FOR KILNS AND COOLERS—Continued

For . . .	You must meet the following emission limit	You have demonstrated compliance, if after following the requirements in §63.7112 . . .
3. All new and existing lime kilns and their associated coolers equipped with an FF or an ESP during shutdown.	Emissions must not exceed 15 percent opacity (based on 6-minute average opacity for any 6-minute block period does not exceed 15 percent).	i. Installed, maintained, calibrated and operated a COMS as required by 40 CFR part 63, subpart A, General Provisions and according to PS–1 of appendix B to part 60 of this chapter, except as specified in §63.7113(g)(2); ii. Collecting the COMS data at a frequency of at least once every 15 seconds, determining block averages for each 6-minute period and demonstrating for each 6-minute block period the average opacity does not exceed 15 percent.
4. All existing lime kilns and their associated coolers that have a wet scrubber during shutdown.	See item 2.b of Table 3 of subpart AAAAA for emission limit.	See item 1 of Table 6 of subpart AAAAA for requirements for demonstrating compliance.

[85 FR 44982, July 24, 2020]

TABLE 3 TO SUBPART AAAAA OF PART 63—OPERATING LIMITS

As required in §63.7090(b), you must meet each operating limit in the following table that applies to you, except for kilns and coolers during startup and shutdown (See Table 2 for operating limits during startup and shutdown).

For . . .	You must . . .
1. Each lime kiln and each lime cooler (if there is a separate exhaust to the atmosphere from the associated lime cooler) equipped with an FF.	Maintain and operate the FF such that the BLDS or PM detector alarm condition does not exist for more than 5 percent of the total operating time in a 6-month period; and comply with the requirements in §63.7113(d) through (f) and Table 6 to this subpart. In lieu of a BLDS or PM detector maintain the FF such that the 6-minute average opacity for any 6-minute block period does not exceed 15 percent; and comply with the requirements in §63.7113(f) and (g) and Table 6 to this subpart.
2. Each lime kiln equipped with a wet scrubber	a. Maintain the 3-hour block exhaust gas stream pressure drop across the wet scrubber greater than or equal to the pressure drop operating limit established during the most recent PM performance test; and b. Maintain the 3-hour block scrubbing liquid flow rate greater than the flow rate operating limit established during the most recent performance test.
3. Each lime kiln equipped with an electrostatic precipitator	Install a PM detector and maintain and operate the ESP such that the PM detector alarm is not activated and alarm condition does not exist for more than 5 percent of the total operating time in a 6-month period, and comply with §63.7113(e); or, maintain the ESP such that the 6-minute average opacity for any 6-minute block period does not exceed 15 percent, and comply with the requirements in §63.7113(g); and comply with the requirements in §63.7113(f) and Table 6 to this subpart.
4. Each PSH operation subject to a PM limit which uses a wet scrubber.	Maintain the 3-hour block average exhaust gas stream pressure drop across the wet scrubber greater than or equal to the pressure drop operating limit established during the PM performance test; and maintain the 3-hour block average scrubbing liquid flow rate greater than or equal to the flow rate operating limit established during the performance test.
5. All affected sources	Prepare a written OM&M plan; the plan must include the items listed in §63.7100(d) and the corrective actions to be taken when required in Table 6 to this subpart.
6. Each emission unit equipped with an add-on air pollution control device.	a. Vent captured emissions through a closed system, except that dilution air may be added to emission streams for the purpose of controlling temperature at the inlet to an FF; and b. Operate each capture/collection system according to the procedures and requirements in the OM&M plan.

[85 FR 44983, July 24, 2020]

TABLE 4 TO SUBPART AAAAA OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITS

As required in §63.7114, you must demonstrate initial compliance with each emission limitation that applies to you, according to the following table.

For . . .	For the following emission limit . . .	You have demonstrated initial compliance, if after following the requirements in §63.7112 . . .
1. All new or existing lime kilns and their associated lime coolers (kilns/coolers).	PM emissions must not exceed 0.12 lb/tsf for all existing kilns/coolers with dry controls, 0.60 lb/tsf for existing kilns/coolers with wet scrubbers, 0.10 lb/tsf for all new kilns/coolers, or a weighted average calculated according to Eq. 3 in §63.7112.	The kiln outlet PM emissions (and if applicable, summed with the separate cooler PM emissions), based on the PM emissions measured using Method 5 in appendix A to part 60 of this chapter and the stone feed rate measurement over the period of initial performance test, do not exceed the emission limit; if the lime kiln is controlled by an FF or ESP and you are opting to monitor PM emissions with a BLDS or PM detector, you have installed and are operating the monitoring device according to the requirements in §63.7113(d) or (e), respectively; and if the lime kiln is controlled by an FF or ESP and you are opting to monitor PM emissions using a COMS, you have installed and are operating the COMS according to the requirements in §63.7113(g).
2. Stack emissions from all PHS operations at a new or existing affected source.	PM emissions must not exceed 0.05 g/dscm.	The outlet PM emissions, based on Method 5 or Method 17 in appendix A to part 60 of this chapter, over the period of the initial performance test do not exceed 0.05 g/dscm; and if the emission unit is controlled with a wet scrubber, you have a record of the scrubber's pressure drop and liquid flow rate operating parameters over the 3-hour performance test during which emissions did not exceed the emissions limitation.
3. Stack emissions from all PSH operations at a new or existing affected source, unless the stack emissions are discharged through a wet scrubber control device.	Emissions must not exceed 7 percent opacity.	Each of the thirty 6-minute opacity averages during the initial compliance period, using Method 9 in appendix A to part 60 of this chapter, does not exceed the 7 percent opacity limit. At least thirty 6-minute averages must be obtained.
4. Fugitive emissions from all PSH operations at a new or existing affected source.	Emissions must not exceed 10 percent opacity.	Each of the 6-minute opacity averages during the initial compliance period, using Method 9 in appendix A to part 60 of this chapter, does not exceed the 10 percent opacity limit.
5. All PSH operations at a new or existing affected source, enclosed in building.	All of the individually affected PSH operations must comply with the applicable PM and opacity emission limitations for items 2 through 4 of this Table 4, or the building must comply with the following: There must be no VE from the building, except from a vent, and vent emissions must not exceed the emission limitations in items 2 and 3 of this Table 4.	All the PSH operations enclosed in the building have demonstrated initial compliance according to the applicable requirements for items 2 through 4 of this Table 4; or if you are complying with the building emission limitations, there are no VE from the building according to item 18 of Table 5 to this subpart and §63.7112(k), and you demonstrate initial compliance with applicable building vent emissions limitations according to the requirements in items 2 and 3 of this Table 4.
6. Each FF that controls emissions from only an individual storage bin.	Emissions must not exceed 7 percent opacity.	Each of the ten 6-minute averages during the 1-hour initial compliance period, using Method 9 in appendix A to part 60 of this chapter, does not exceed the 7 percent opacity limit.

For . . .	For the following emission limit . . .	You have demonstrated initial compliance, if after following the requirements in § 63.7112 . . .
7. Each set of multiple storage bins with combined stack emissions.	You must comply with emission limitations in items 2 and 3 of this Table 4.	You demonstrate initial compliance according to the requirements in items 2 and 3 of this Table 4.

[85 FR 44983, July 24, 2020]

TABLE 5 TO SUBPART AAAAA OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS

As required in § 63.7112, you must conduct each performance test in the following table that applies to you.

For . . .	You must . . .	Using . . .	According to the following requirements . . .
1. Each lime kiln and each associated lime cooler, if there is a separate exhaust to the atmosphere from the associated lime cooler.	Select the location of the sampling port and the number of traverse ports.	Method 1 or 1A of appendix A to part 60 of this chapter; and § 63.6(d)(1)(i).	Sampling sites must be located at the outlet of the control device(s) and prior to any releases to the atmosphere.
2. Each lime kiln and each associated lime cooler, if there is a separate exhaust to the atmosphere from the associated lime cooler.	Determine velocity and volumetric flow rate.	Method 2, 2A, 2C, 2D, 2F, or 2G in appendix A to part 60 of this chapter.	Not applicable.
3. Each lime kiln and each associated lime cooler, if there is a separate exhaust to the atmosphere from the associated lime cooler.	Conduct gas molecular weight analysis.	Method 3, 3A, or 3B in appendix A to part 60 of this chapter.	You may use ASME PTC 19.10–1981—Part 10 (available for purchase from Three Park Avenue, New York, NY 10016–5990) as an alternative to using the manual procedures (but not instrumental procedures) in Method 3B.
4. Each lime kiln and each associated lime cooler, if there is a separate exhaust to the atmosphere from the associated lime cooler.	Measure moisture content of the stack gas.	Method 4 in appendix A to part 60 of this chapter.	Not applicable.
5. Each lime kiln and each associated lime cooler, if there is a separate exhaust to the atmosphere from the associated lime cooler, and which uses a negative pressure PM control device.	Measure PM emissions	Method 5 in appendix A to part 60 of this chapter.	Conduct the test(s) when the source is operating at representative operating conditions in accordance with § 63.7(e) before the relevant compliance date for your source as specified in § 63.7083(e) and § 63.7112(b) on and after the relevant compliance date for your source as specified in § 63.7083(e); the minimum sampling volume must be 0.85 dry standard cubic meter (dscm) (30 dry standard cubic foot (dscf)); if there is a separate lime cooler exhaust to the atmosphere, you must conduct the Method 5 test of the cooler exhaust concurrently with the kiln exhaust test.

For . . .	You must . . .	Using . . .	According to the following requirements . . .
6. Each lime kiln and each associated lime cooler, if there is a separate exhaust to the atmosphere from the associated lime cooler, and which uses a positive pressure FF or ESP.	Measure PM emissions	Method 5D in appendix A to part 60 of this chapter.	Conduct the test(s) when the source is operating at representative operating conditions in accordance with § 63.7(e) before the relevant compliance date for your source as specified in § 63.7083(e) and § 63.7112(b) on and after the relevant compliance date for your source as specified in § 63.7083(e); if there is a separate lime cooler exhaust to the atmosphere, you must conduct the Method 5 test of the separate cooler exhaust concurrently with the kiln exhaust test.
7. Each lime kiln	Determine the mass rate of stone feed to the kiln during the kiln PM emissions test.	Any suitable device	Calibrate and maintain the device according to manufacturer's instructions; the measuring device used must be accurate to within ±5 percent of the mass rate of stone feed over its operating range.
8. Each lime kiln equipped with a wet scrubber.	Establish the operating limit for the average gas stream pressure drop across the wet scrubber.	Data for the gas stream pressure drop measurement device during the kiln PM performance test.	The continuous pressure drop measurement device must be accurate within plus or minus 1 percent; you must collect the pressure drop data during the period of the performance test and determine the operating limit according to § 63.7112(j).
9. Each lime kiln equipped with a wet scrubber.	Establish the operating limit for the average liquid flow rate to the scrubber.	Data from the liquid flow rate measurement device during the kiln PM performance test.	The continuous scrubbing liquid flow rate measuring device must be accurate within plus or minus 1 percent; you must collect the flow rate data during the period of the performance test and determine the operating limit according to § 63.7112(j).
10. Each lime kiln equipped with a FF or ESP that is monitored with a PM detector.	Have installed and have operating the BLDS or PM detector prior to the performance test.	Standard operating procedures incorporated into the OM&M plan.	According to the requirements in § 63.7113(d) or (e), respectively.
11. Each lime kiln equipped with a FF or ESP that is monitored with a COMS.	Have installed and have operating the COMS prior to the performance test.	Standard operating procedures incorporated into the OM&M plan and as required by 40 CFR part 63, subpart A, General Provisions and according to PS–1 of appendix B to part 60 of this chapter, except as specified in § 63.7113(g)(2).	According to the requirements in § 63.7113(g).

For . . .	You must . . .	Using . . .	According to the following requirements . . .
12. Each stack emission from a PSH operation, vent from a building enclosing a PSH operation, or set of multiple storage bins with combined stack emissions, which is subject to a PM emission limit.	Measure PM emissions	Method 5 or Method 17 in appendix A to part 60 of this chapter.	The sample volume must be at least 1.70 dscm (60 dscf); for Method 5, if the gas stream being sampled is at ambient temperature, the sampling probe and filter may be operated without heaters; and if the gas stream is above ambient temperature, the sampling probe and filter may be operated at a temperature high enough, but no higher than 121 °C (250 °F), to prevent water condensation on the filter (Method 17 may be used only with exhaust gas temperatures of not more than 250 °F).
13. Each stack emission from a PSH operation, vent from a building enclosing a PSH operation, or set of multiple storage bins with combined stack emissions, which is subject to an opacity limit.	Conduct opacity observations	Method 9 in appendix A to part 60 of this chapter.	The test duration must be for at least 3 hours and you must obtain at least thirty, 6-minute averages.
14. Each stack emissions source from a PSH operation subject to a PM or opacity limit, which uses a wet scrubber.	Establish the average gas stream pressure drop across the wet scrubber.	Data for the gas stream pressure drop measurement device during the PSH operation stack PM performance test.	The pressure drop measurement device must be accurate within plus or minus 1 percent; you must collect the pressure drop data during the period of the performance test and determine the operating limit according to § 63.7112(j).
15. Each stack emissions source from a PSH operation subject to a PM or opacity limit, which uses a wet scrubber.	Establish the operating limit for the average liquid flow rate to the scrubber.	Data from the liquid flow rate measurement device during the PSH operation stack PM performance test.	The continuous scrubbing liquid flow rate measuring device must be accurate within plus or minus 1 percent; you must collect the flow rate data during the period of the performance test and determine the operating limit according to § 63.7112(j).
16. Each FF that controls emissions from only an individual, enclosed, new or existing storage bin.	Conduct opacity observations	Method 9 in appendix A to part 60 of this chapter.	The test duration must be for at least 1 hour and you must obtain ten 6-minute averages.
17. Fugitive emissions from any PSH operation subject to an opacity limit.	Conduct opacity observations	Method 9 in appendix A to part 60 of this chapter.	The test duration must be for at least 3 hours, but the 3-hour test may be reduced to 1 hour if, during the first 1-hour period, there are no individual readings greater than 10 percent opacity and there are no more than three readings of 10 percent during the first 1-hour period.
18. Each building enclosing any PSH operation, that is subject to a VE limit.	Conduct VE check	The specifications in § 63.7112(k).	The performance test must be conducted while all affected PSH operations within the building are operating; the performance test for each affected building must be at least 75 minutes, with each side of the building and roof being observed for at least 15 minutes.

[85 FR 44984, July 24, 2020]

TABLE 6 TO SUBPART AAAAA OF PART 63—CONTINUOUS COMPLIANCE WITH OPERATING LIMITS

As required in §63.7121, you must demonstrate continuous compliance with each operating limit listed in Table 3 to subpart AAAAA that applies to you, according to the following table:

For . . .	For the following operating limit . . .	You must demonstrate continuous compliance by . . .
1. Each lime kiln controlled by a wet scrubber.	Maintain the 3-hour block average exhaust gas stream pressure drop across the wet scrubber greater than or equal to the pressure drop operating limit established during the PM performance test; and maintain the 3-hour block average scrubbing liquid flow rate greater than or equal to the flow rate operating limit established during the performance test.	Collecting the wet scrubber operating data according to all applicable requirements in §63.7113 and reducing the data according to §63.7113(a); maintaining the 3-hour block average exhaust gas stream pressure drop across the wet scrubber greater than or equal to the pressure drop operating limit established during the PM performance test; and maintaining the 3-hour block average scrubbing liquid flow rate greater than or equal to the flow rate operating limit established during the performance test (the continuous scrubbing liquid flow rate measuring device must be accurate within ±1% and the continuous pressure drop measurement device must be accurate within ±1%).
2. Each lime kiln or lime cooler equipped with a FF and using a BLDS, and each lime kiln equipped with an ESP or FF using a PM detector.	a. Maintain and operate the FF or ESP such that the bag leak or PM detector alarm, is not activated and alarm condition does not exist for more than 5 percent of the total operating time in each 6-month period.	(i) Operating the FF or ESP so that the alarm on the bag leak or PM detection system is not activated and an alarm condition does not exist for more than 5 percent of the total operating time in each 6-month reporting period; and continuously recording the output from the BLD or PM detection system; and (ii) Each time the alarm sounds and the owner or operator initiates corrective actions within 1 hour of the alarm, 1 hour of alarm time will be counted (if the owner or operator takes longer than 1 hour to initiate corrective actions, alarm time will be counted as the actual amount of time taken by the owner or operator to initiate corrective actions); if inspection of the FF or ESP system demonstrates that no corrective actions are necessary, no alarm time will be counted.
3. Each stack emissions source from a PSH operation subject to an opacity limit, which is controlled by a wet scrubber.	Maintain the 3-hour block average exhaust gas stream pressure drop across the wet scrubber greater than or equal to the pressure drop operating limit established during the PM performance test; and maintain the 3-hour block average scrubbing liquid flow rate greater than or equal to the flow rate operating limit established during the performance test.	Collecting the wet scrubber operating data according to all applicable requirements in §63.7113 and reducing the data according to §63.7113(a); maintaining the 3-hour block average exhaust gas stream pressure drop across the wet scrubber greater than or equal to the pressure drop operating limit established during the PM performance test; and maintaining the 3-hour block average scrubbing liquid flow rate greater than or equal to the flow rate operating limit established during the performance test (the continuous scrubbing liquid flow rate measuring device must be accurate within ±1% and the continuous pressure drop measurement device must be accurate within ±1%).

For . . .	For the following operating limit . . .	You must demonstrate continuous compliance by . . .
4. For each lime kiln or lime cooler equipped with a FF or an ESP that uses a COMS as the monitoring device.	a. Maintain and operate the FF or ESP such that the average opacity for any 6-minute block period does not exceed 15 percent.	i. Installing, maintaining, calibrating and operating a COMS as required by 40 CFR part 63, subpart A, General Provisions and according to PS–1 of appendix B to part 60 of this chapter, except as specified in §63.7113(g)(2); and ii. Collecting the COMS data at a frequency of at least once every 15 seconds, determining block averages for each 6-minute period and demonstrating for each 6-minute block period the average opacity does not exceed 15 percent.

[69 FR 416, Jan. 5, 2004. Redesignated and amended at 85 FR 44982, 44986, July 24, 2020]

TABLE 7 TO SUBPART AAAAA OF PART 63—PERIODIC MONITORING FOR COMPLIANCE WITH OPACITY AND VISIBLE EMISSIONS LIMITS

As required in §63.7121 you must periodically demonstrate compliance with each opacity and VE limit that applies to you, according to the following table:

For . . .	For the following emission limitation . . .	You must demonstrate ongoing compliance . . .
1. Each PSH operation subject to an opacity limitation as required in Table 1 to this subpart, or any vents from buildings subject to an opacity limitation.	a. 7–10 percent opacity, depending on the PSH operation, as required in Table 1 to this subpart.	(i) Conducting a monthly 1-minute VE check of each emission unit in accordance with §63.7121(e); the check must be conducted while the affected source is in operation; (ii) If no VE are observed in 6 consecutive monthly checks for any emission unit, you may decrease the frequency of VE checking from monthly to semiannually for that emission unit; if VE are observed during any semiannual check, you must resume VE checking of that emission unit on a monthly basis and maintain that schedule until no VE are observed in 6 consecutive monthly checks; (iii) If no VE are observed during the semiannual check for any emission unit, you may decrease the frequency of VE checking from semi-annually to annually for that emission unit; if VE are observed during any annual check, you must resume VE checking of that emission unit on a monthly basis and maintain that schedule until no VE are observed in 6 consecutive monthly checks; and (iv) If VE are observed during any VE check, you must conduct a 6-minute test of opacity in accordance with Method 9 of appendix A to part 60 of this chapter; you must begin the Method 9 test within 1 hour of any observation of VE and the 6-minute opacity reading must not exceed the applicable opacity limit.
2. Any building subject to a VE limit, according to item 8 of Table 1 to this subpart.	a. No VE	(i) Conducting a monthly VE check of the building, in accordance with the specifications in §63.7112(k); the check must be conducted while all the enclosed PSH operations are operating; (ii) The check for each affected building must be at least 5 minutes, with each side of the building and roof being observed for at least 1 minute;

For . . .	For the following emission limitation . . .	You must demonstrate ongoing compliance . . .
		(iii) If no VE are observed in 6 consecutive monthly checks of the building, you may decrease the frequency of checking from monthly to semi-annually for that affected source; if VE are observed during any semi-annual check, you must resume checking on a monthly basis and maintain that schedule until no VE are observed in 6 consecutive monthly checks; and (iv) If no VE are observed during the semi-annual check, you may decrease the frequency of checking from semi-annually to annually for that affected source; and if VE are observed during any annual check, you must resume checking of that emission unit on a monthly basis and maintain that schedule until no VE are observed in 6 consecutive monthly checks (the source is in compliance if no VE are observed during any of these checks).

[85 FR 44986, July 24, 2020]

TABLE 8 TO SUBPART AAAAA OF PART 63—REQUIREMENTS FOR REPORTS

As required in §63.7131, you must submit each report in this table that applies to you.

You must submit a . . .	The report must contain . . .	You must submit the report . . .
1. Compliance report	a. If there are no deviations from any emission limitations (emission limit, operating limit, opacity limit, and VE limit) that applies to you, a statement that there were no deviations from the emission limitations during the reporting period;	Semiannually according to the requirements in §63.7131(b).
	b. If there were no periods during which the CMS, including any operating parameter monitoring system, was out-of-control as specified in §63.8(c)(7), a statement that there were no periods during which the CMS was out-of-control during the reporting period;	Semiannually according to the requirements in §63.7131(b).
	c. If you have a deviation from any emission limitation (emission limit, operating limit, opacity limit, and VE limit) during the reporting period, the report must contain the information in §63.7131(d);	Semiannually according to the requirements in §63.7131(b).
	d. If there were periods during which the CMS, including any operating parameter monitoring system, was out-of-control, as specified in §63.8(c)(7), the report must contain the information in §63.7131(e); and	Semiannually according to the requirements in §63.7131(b).

You must submit a . . .	The report must contain . . .	You must submit the report . . .
	e. Before the relevant compliance date for your source as specified in §63.7083(e), if you had a startup, shutdown or malfunction during the reporting period and you took actions consistent with your SSMP, the compliance report must include the information in §63.10(d)(5)(i). On and after the relevant compliance date for your source as specified in §63.7083(e), if you had a startup, shutdown or malfunction during the reporting period and you failed to meet an applicable standard, the compliance report must include the information in §63.7131(c)(3).	Semiannually according to the requirements in §63.7131(b).
2. Before the relevant compliance date for your source as specified in §63.7083(e), an immediate startup, shutdown, and malfunction report if you had a startup, shutdown, or malfunction during the reporting period that is not consistent with your SSMP.	Actions taken for the event	By fax or telephone within 2 working days after starting actions inconsistent with the SSMP.
3. Before the relevant compliance date for your source as specified in §63.7083(e), an immediate startup, shutdown, and malfunction report if you had a startup, shutdown, or malfunction during the reporting period that is not consistent with your SSMP.	The information in §63.10(d)(5)(ii)	By letter within 7 working days after the end of the event unless you have made alternative arrangements with the permitting authority. See §63.10(d)(5)(ii).
(4) Performance Test Report	The information required in §63.7(g)	According to the requirements of §63.7131.

[85 FR 44987, July 24, 2020]

Table 9 to Subpart AAAAA of Part 63—Applicability of General Provisions to Subpart AAAAA

As required in §63.7140, you must comply with the applicable General Provisions requirements according to the following table:

Citation	Summary of requirement	Am I subject to this requirement?	Explanations
§63.1(a)(1)–(4)	Applicability	Yes.	
§63.1(a)(5)		No.	
§63.1(a)(6)	Applicability	Yes.	
§63.1(a)(7)–(a)(9)		No.	
§63.1(a)(10)–(a)(14)	Applicability	Yes.	
§63.1(b)(1)	Initial Applicability Determination.	Yes	§§63.7081 and 63.7142 specify additional applicability determination requirements.
§63.1(b)(2)		No.	
§63.1(b)(3)	Initial Applicability Determination.	Yes.	
§63.1(c)(1)	Applicability After Standard Established.	Yes.	
§63.1(c)(2)	Permit Requirements	No	Area sources not subject to subpart AAAAA, except all sources must make initial applicability determination.
§63.1(c)(3)–(4)		No.	
§63.1(c)(5)	Area Source Becomes Major	Yes.	
§63.1(c)(6)	Reclassification	Yes.	
§63.1(d)		No.	
§63.1(e)	Applicability of Permit Program.	Yes.	
§63.2	Definitions	Yes	Additional definitions in §63.7143.
§63.3(a)–(c)	Units and Abbreviations	Yes.	
§63.4(a)(1)–(a)(2)	Prohibited Activities	Yes.	

Citation	Summary of requirement	Am I subject to this requirement?	Explanations
§63.4(a)(3)–(a)(5)	.....	No.	
§63.4(b)–(c)	Circumvention, Severability ...	Yes.	
§63.5(a)(1)–(2)	Construction/Reconstruction ..	Yes.	
§63.5(b)(1)	Compliance Dates	Yes.	
§63.5(b)(2)	.....	No.	
§63.5(b)(3)–(4)	Construction Approval, Applicability.	Yes.	
§63.5(b)(5)	.....	No.	
§63.5(b)(6)	Applicability	Yes.	
§63.5(c)	.....	No.	
§63.5(d)(1)–(4)	Approval of Construction/Reconstruction.	Yes.	
§63.5(e)	Approval of Construction/Reconstruction.	Yes.	
§63.5(f)(1)–(2)	Approval of Construction/Reconstruction.	Yes.	
§63.6(a)	Compliance for Standards and Maintenance.	Yes.	
§63.6(b)(1)–(5)	Compliance Dates	Yes.	
§63.6(b)(6)	.....	No.	
§63.6(b)(7)	Compliance Dates	Yes.	
§63.6(c)(1)–(2)	Compliance Dates	Yes.	
§63.6(c)(3)–(c)(4)	.....	No.	
§63.6(c)(5)	Compliance Dates	Yes.	
§63.6(d)	.....	No.	
§63.6(e)(1)(i)	General Duty to Minimize Emissions.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), see §63.7100 for general duty requirement.
§63.6(e)(1)(ii)	Requirement to Correct Malfunctions ASAP.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	
§63.6(e)(1)(iii)	Operation and Maintenance Requirements.	Yes.	
§63.6(e)(2)	.....	No	[Reserved].
§63.6(e)(3)	Startup, Shutdown Malfunction Plan.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), the OM&M plan must address periods of startup and shutdown. See §63.7100(d).
§63.6(f)(1)	SSM exemption	No	See §63.7100. For periods of startup and shutdown, see §63.7090(c).
§63.6(f)(2)–(3)	Methods for Determining Compliance.	Yes.	
§63.6(g)(1)–(g)(3)	Alternative Standard	Yes.	
§63.6(h)(1)	SSM exemption	No	See §63.7100. For periods of startup and shutdown, see §63.7090(c).
§63.6(h)(2)	Methods for Determining Compliance.	Yes.	
§63.6(h)(3)	.....	No.	
§63.6(h)(4)–(h)(5)(i)	Opacity/VE Standards	Yes	This requirement only applies to opacity and VE performance checks required in Table 4 to subpart AAAAA.
§63.6(h)(5) (ii)–(iii)	Opacity/VE Standards	No	Test durations are specified in subpart AAAAA; subpart AAAAA takes precedence.
§63.6(h)(5)(iv)	Opacity/VE Standards	No.	
§63.6(h)(5)(v)	Opacity/VE Standards	Yes.	
§63.6(h)(6)	Opacity/VE Standards	Yes.	
§63.6(h)(7)	COM Use	Yes.	

Citation	Summary of requirement	Am I subject to this requirement?	Explanations
§63.6(h)(8)	Compliance with Opacity and VE.	Yes.	
§63.6(h)(9)	Adjustment of Opacity Limit	Yes.	
§63.6(i)(1)–(i)(14)	Extension of Compliance	Yes.	
§63.6(i)(15)		No.	
§63.6(i)(16)	Extension of Compliance	Yes.	
§63.6(j)	Exemption from Compliance	Yes.	
§63.7(a)(1)–(a)(3)	Performance Testing Requirements.	Yes	§63.7110 specifies deadlines; §63.7112 has additional specific requirements.
§63.7(b)	Notification	Yes.	
§63.7(c)	Quality Assurance/Test Plan	Yes.	
§63.7(d)	Testing Facilities	Yes.	
§63.7(e)(1)	Conduct of Tests	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), see §63.7112(b).
§63.7(e)(2)–(4)	Conduct of Tests	Yes.	
§63.7(f)	Alternative Test Method	Yes.	
§63.7(g)	Data Analysis	Yes.	
§63.7(h)	Waiver of Tests	Yes.	
§63.8(a)(1)	Monitoring Requirements	Yes	See §63.7113.
§63.8(a)(2)	Monitoring	Yes.	
§63.8(a)(3)		No.	
§63.8(a)(4)	Monitoring	No	Flares not applicable.
§63.8(b)(1)–(3)	Conduct of Monitoring	Yes.	
§63.8(c)(1)(i)	CMS Operation/Maintenance	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), see §63.7100 for OM&M requirements.
§63.8(c)(1)(ii)	CMS Spare Parts	Yes.	
§63.8(c)(1)(iii)	Requirement to Develop SSM Plan for CMS.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), no longer required.
§63.8(c)(2)–(3)	CMS Operation/Maintenance	Yes.	
§63.8(c)(4)	CMS Requirements	No	See §63.7121.
§63.8(c)(4)(i)–(ii)	Cycle Time for COM and CEMS.	Yes	No CEMS are required under subpart AAAAA; see §63.7113 for CPMS requirements.
§63.8(c)(5)	Minimum COM procedures	Yes	COM not required.
§63.8(c)(6)	CMS Requirements	No	See §63.7113.
§63.8(c)(7)–(8)	CMS Requirements	Yes.	
§63.8(d)(1)–(2)	Quality Control	Yes	See also §63.7113.
§63.8(d)(3)	Quality Control	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	
§63.8(e)	Performance Evaluation for CMS.	Yes	See also §63.7113.
§63.8(f)(1)–(f)(5)	Alternative Monitoring Method	Yes.	
§63.8(f)(6)	Alternative to Relative Accuracy Test for CEMS.	No	No CEMS required in subpart AAAAA.
§63.8(g)(1)–(g)(5)	Data Reduction; Data That Cannot Be Used.	No	See data reduction requirements in §§63.7120 and 63.7121.
§63.9(a)	Notification Requirements	Yes	See §63.7130.
§63.9(b)	Initial Notifications	Yes.	
§63.9(c)	Request for Compliance Extension.	Yes.	

Citation	Summary of requirement	Am I subject to this requirement?	Explanations
§63.9(d)	New Source Notification for Special Compliance Requirements.	Yes.	
§63.9(e)	Notification of Performance Test.	Yes.	
§63.9(f)	Notification of VE/Opacity Test.	Yes	This requirement only applies to opacity and VE performance tests required in Table 5 to subpart AAAAA. Notification not required for VE/opacity test under Table 7 to subpart AAAAA.
§63.9(g)	Additional CMS Notifications	No	Not required for operating parameter monitoring.
§63.9(h)(1)–(h)(3)	Notification of Compliance Status.	Yes.	
§63.9(h)(4)		No.	
§63.9(h)(5)–(h)(6)	Notification of Compliance Status.	Yes.	
§63.9(i)	Adjustment of Deadlines	Yes.	
§63.9(j)	Change in Previous Information.	Yes.	
§63.9(k)	Electronic reporting procedures.	Yes	Only as specified in §63.9(j).
§63.10(a)	Recordkeeping/Reporting General Requirements.	Yes	See §§63.7131 through 63.7133.
§63.10(b)(1)	Records	Yes.	
§63.10(b)(2)(i)	Recordkeeping of Occurrence and Duration of Startups and Shutdowns.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	
§63.10(b)(2)(ii)	Recordkeeping of Failures to Meet a Standard.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), see §63.7132 for recordkeeping of (1) date, time and duration; (2) listing of affected source or equipment, and an estimate of the quantity of each regulated pollutant emitted over the standard; and (3) actions to minimize emissions and correct the failure.
§63.10(b)(2)(iii)	Maintenance Records	Yes.	
§63.10(b)(2)(iv)–(v)	Actions Taken to Minimize Emissions During SSM.	Yes before the relevant compliance date for your source as specified in §63.7083(e). No on and after the relevant compliance date for your source as specified in §63.7083(e).	On and after the relevant compliance date for your source as specified in §63.7083(e), see §63.7100 for OM&M requirements.
§63.10(b)(2)(vi)–(xii)	Recordkeeping for CMS	Yes.	
§63.10(b)(2)(xiii)	Records for Relative Accuracy Test.	No.	
§63.10(b)(2)(xiv)	Records for Notification	Yes.	
§63.10(b)(3)	Applicability Determinations	Yes.	
§63.10(c)	Additional CMS Recordkeeping.	No	See §63.7132.
§63.10(d)(1)	General Reporting Requirements.	Yes.	
§63.10(d)(2)	Performance Test Results	Yes.	
§63.10(d)(3)	Opacity or VE Observations	Yes	For the periodic monitoring requirements in Table 7 to subpart AAAAA, report according to §63.10(d)(3) only if VE observed and subsequent visual opacity test is required.

Citation	Summary of requirement	Am I subject to this requirement?	Explanations
§ 63.10(d)(4)	Progress Reports	Yes.	
§ 63.10(d)(5)(i)	Periodic Startup, Shutdown, Malfunction Reports.	Yes before the relevant compliance date for your source as specified in § 63.7083(e). No on and after the relevant compliance date for your source as specified in § 63.7083(e).	On and after the relevant compliance date for your source as specified in § 63.7083(e), see § 63.7131 for malfunction reporting requirements.
§ 63.10(d)(5)(ii)	Immediate Startup, Shutdown, Malfunction Reports.	Yes before the relevant compliance date for your source as specified in § 63.7083(e). No on and after the relevant compliance date for your source as specified in § 63.7083(e).	
§ 63.10(e)	Additional CMS Reports	No	See specific requirements in subpart AAAAA, see § 63.7131.
§ 63.10(f)	Waiver for Recordkeeping/Reporting.	Yes.	
§ 63.11(a)–(b)	Control Device and Work Practice Requirements.	No	Flares not applicable.
§ 63.12(a)–(c)	State Authority and Delegations.	Yes.	
§ 63.13(a)–(c)	State/Regional Addresses	Yes.	
§ 63.14(a)–(b)	Incorporation by Reference	No.	
§ 63.15(a)–(b)	Availability of Information and Confidentiality.	Yes.	
§ 63.16	Performance Track Provisions	Yes.	

[85 FR 44988, July 24, 2020, as amended at 85 FR 73912, Nov. 19, 2020; 85 FR 84262, Dec. 28, 2020]

Subpart BBBBB—National Emission Standards for Hazardous Air Pollutants for Semiconductor Manufacturing

SOURCE: 68 FR 27925, May 22, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7180 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for semiconductor manufacturing facilities. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission standards.

§ 63.7181 Am I subject to this subpart?

(a) You are subject to this subpart if you own or operate a semiconductor manufacturing process unit that is a major source of hazardous air pollutants (HAP) emissions or that is located at, or is part of, a major source of HAP emissions.

(b) A major source of HAP emissions is any stationary source or group of stationary sources located within a contiguous area and under common control that emits or has the potential to emit, considering controls, in the aggregate, any single HAP at a rate of 10 tons per year (tpy) or more or any combination of HAP at a rate of 25 tpy or more.

§ 63.7182 What parts of my facility does this subpart cover?

(a) This subpart applies to each new, reconstructed, or existing affected source that you own or operate that manufactures semiconductors.

(b) An affected source subject to this subpart is the collection of all semiconductor manufacturing process units used to manufacture p-type and n-type semiconductors and active solid-state devices from a wafer substrate, including research and development activities integrated into a semiconductor manufacturing process unit. A semiconductor manufacturing process unit includes the equipment assembled and connected by ductwork or hard-piping including furnaces and associated unit

operations; associated wet and dry work benches; associated recovery devices; feed, intermediate, and product storage tanks; product transfer racks and connected ducts and piping; pumps, compressors, agitators, pressure-relief devices, sampling connecting systems, open-ended valves or lines, valves, connectors, and instrumentation systems; and control devices.

(c) Your affected source is a new affected source if you commence construction of the affected source after May 8, 2002, and you meet the applicability criteria in § 63.7181 at the time you commence construction.

(d) Your affected source is a reconstructed affected source if you meet the criteria for ''reconstruction,'' as defined in § 63.2.

(e) Your source is an existing affected source if it is not a new or reconstructed affected source.

§ 63.7183 When do I have to comply with this subpart?

(a) If you have a new or reconstructed affected source, you must comply with this subpart according to paragraphs (a)(1) and (2) of this section.

(1) If you start up your affected source before May 22, 2003, then you must comply with the emission standards for new and reconstructed sources in this subpart no later than May 22, 2003.

(2) If you start up your affected source after May 22, 2003, then you must comply with the emission standards for new and reconstructed sources in this subpart upon startup of your affected source.

(b) If you have an existing affected source, you must comply with the emission standards for existing sources no later than 3 years from May 22, 2003.

(c) If you have an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP and an affected source subject to this subpart, paragraphs (c)(1) and (2) of this section apply.

(1) Any portion of your existing facility that is a new affected source as specified at § 63.7182(c), or a reconstructed affected source as specified at § 63.7182(d), must be in compliance with this subpart upon startup.

(2) Any portion of your facility that is an existing affected source, as specified at § 63.7182(e), must be in compliance with this subpart by not later than 3 years after it becomes a major source.

(d) You must meet the notification requirements in § 63.7189 and in subpart A of this part. You must submit some of the notifications (*e.g.*, Initial Notification) before the date you are required to comply with the emission limitations in this subpart.

EMISSION STANDARDS

§ 63.7184 What emission limitations, operating limits, and work practice standards must I meet?

(a) If you have a new, reconstructed, or existing affected source, as defined in § 63.7182(b), you must comply with all applicable emission limitations in this section on and after the compliance dates specified in § 63.7183.

(b) *Process vents—organic HAP emissions.* For each organic HAP process vent, other than process vents from storage tanks, you must limit organic HAP emissions to the level specified in paragraph (b)(1) or (2) of this section. These limitations can be met by venting emissions from your process vent through a closed vent system to any combination of control devices meeting the requirements of § 63.982(a)(2).

(1) Reduce the emissions of organic HAP from the process vent stream by 98 percent by weight.

(2) Reduce or maintain the concentration of emitted organic HAP from the process vent to less than or equal to 20 parts per million by volume (ppmv).

(c) *Process vents—inorganic HAP emissions.* For each inorganic HAP process vent, other than process vents from storage tanks, you must limit inorganic HAP emissions to the level specified in paragraph (c)(1) or (2) of this section. These limitations can be met by venting emissions from your process vent through a closed vent system to a halogen scrubber meeting the requirements of §§ 63.983 (closed vent system requirements) and § 63.994 (halogen scrubber requirements); the applicable general monitoring requirements of § 63.996; the applicable performance test

requirements; and the monitoring, recordkeeping and reporting requirements referenced therein.

(1) Reduce the emissions of inorganic HAP from the process vent stream by 95 percent by weight.

(2) Reduce or maintain the concentration of emitted inorganic HAP from the process vent to less than or equal to 0.42 ppmv.

(d) *Storage tanks.* For each storage tank, 1,500 gallons or larger, you must limit total HAP emissions to the level specified in paragraph (d)(1) or (2) of this section if the emissions from the storage tank vent contains greater than 0.42 ppmv inorganic HAP. These limitations can be met by venting emissions from your storage tank through a closed vent system to a halogen scrubber meeting the requirements of §§ 63.983 (closed vent system requirements) and 63.994 (halogen scrubber requirements); the applicable general monitoring requirements of § 63.996; the applicable performance test requirements; and the monitoring, recordkeeping and reporting requirements referenced therein.

(1) Reduce the emissions of inorganic HAP from each storage tank by 95 percent by weight.

(2) Reduce or maintain the concentration of emitted inorganic HAP from the process vent to less than or equal to 0.42 ppmv.

(e) You must comply with the applicable work practice standards and operating limits contained in § 63.982(a)(1) and (2). The closed vent system inspection requirements of § 63.983(c), as referenced by § 63.982(a)(1) and (2), do not apply.

(f) *Process vents—combined HAP emissions.* For each combined HAP process vent, other than process vents from storage tanks, you must reduce or maintain the concentration of emitted HAP from the process vent to less than or equal to 14.22 ppmv. These limitations can be met by venting emissions from your process vent through a closed vent system to any combination of control devices meeting the requirements of § 63.982(a)(2).

[68 FR 27925, May 22, 2003, as amended at 73 FR 42532, July 22, 2008]

COMPLIANCE REQUIREMENTS

§ 63.7185 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the requirements of § 63.7184 at all times, except during periods of startup, shutdown, or malfunction.

(b) You must always operate and maintain your affected source, including air pollution control and monitoring equipment, according to the provisions in § 63.6(e)(1)(i).

(c) You must develop a written startup, shutdown, and malfunction plan (SSMP). Your SSMP must be prepared in accordance with the provisions in § 63.6(e)(3).

(d) You must perform all the items listed in paragraphs (d)(1) through (3) of this section:

(1) Submit the necessary notifications in accordance with § 63.7189.

(2) Submit the necessary reports in accordance with § 63.7190.

(3) Maintain all necessary records you have used to demonstrate compliance with this subpart in accordance with § 63.7191.

[68 FR 27925, May 22, 2003, as amended at 71 FR 20467, Apr. 20, 2006]

§ 63.7186 By what date must I conduct performance tests or other initial compliance demonstrations?

For each process vent or storage tank vent emission limitation in § 63.7184 for which initial compliance is demonstrated by meeting a percent by weight HAP emissions reduction, or a HAP concentration limitation, you must conduct performance tests or an initial compliance demonstration within 180 days after the compliance date that is specified for your source in § 63.7183 and according to the provisions in § 63.7(a)(2).

§ 63.7187 What performance tests and other compliance procedures must I use?

(a) You must conduct each performance test in Table 1 to this subpart that applies to you as specified for process vents in § 63.982(a)(2) and storage tanks in § 63.982(a)(1). Performance tests must be conducted under maximum operating conditions or HAP

emissions potential. Section 63.982(a)(1) and (2) only includes methods to measure the total organic regulated material or total organic carbon (TOC) concentration. The EPA Methods 26 and 26A are included in Table 1 to this subpart in addition to the test methods contained within §63.982(a)(1) and (2). The EPA Method 26 or 26A must be used for testing regulated material containing inorganic HAP. Method 320 of 40 CFR part 63, appendix A, must be used to measure total vapor phase organic and inorganic HAP concentrations.

(b) If, without the use of a control device, your process vent stream has an organic HAP concentration of 20 ppmv or less or an inorganic HAP concentration of 0.42 ppmv or less, or your storage tank vent stream has an inorganic HAP concentration of 0.42 ppmv or less, you may demonstrate that the vent stream is compliant by engineering assessments and calculations or by conducting the applicable performance test requirements specified in Table 1 to this subpart. Your engineering assessments and calculations, as with performance tests (as specified in §63.982(a)(1) and (2)), must represent your maximum operating conditions or HAP emissions potential and must be approved by the Administrator. You must demonstrate continuous compliance by certifying that your operations will not exceed the maximum operating conditions or HAP emissions potential represented by your engineering assessments, calculations, or performance test.

(c) If you are using a control device to comply with the emission limitations in §63.7184 and the inlet concentration of HAP to the control device is 20 ppmv or less, then you may demonstrate that the control device meets the percent by weight HAP emission reduction limitation in §63.7184(c)(1) or (d)(1) by conducting a design evaluation as specified in paragraph (i) of this section. Your design evaluation must represent your maximum operating conditions or HAP emissions potential and must be approved by the Administrator. You must demonstrate continuous compliance by certifying that your operations will not exceed the maximum operating conditions or HAP emissions potential represented by your design evaluation.

(d) [Reserved]

(e) For each monitoring system required in this section, you must develop and submit for approval a site-specific monitoring plan that addresses the criteria specified in paragraphs (e)(1) through (3) of this section.

(1) Installation of the continuous monitoring system (CMS) sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last control device);

(2) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system; and

(3) Performance evaluation procedures and acceptance criteria (*e.g.*, calibrations).

(f) In your site-specific monitoring plan, you must also address the procedural processes in paragraphs (f)(1) through (3) of this section.

(1) Ongoing operation and maintenance procedures in accordance with the general requirements of §63.8(c)(1), (3), (4)(ii), (7), and (8);

(2) Ongoing data quality assurance procedures in accordance with the general requirements of §63.8(d); and

(3) Ongoing recordkeeping and reporting procedures in accordance with the general requirements of §63.10(c), (e)(1), and (e)(2)(i).

(g) You must conduct a performance evaluation of each CMS in accordance with your site-specific monitoring plan.

(h) You must operate and maintain the CMS in continuous operation according to the site-specific monitoring plan.

(i) *Design evaluation.* To demonstrate that a control device meets the required percent by weight inorganic HAP emission reduction limitation in §63.7184(c)(1) or (d)(1), a design evaluation must address the composition of the inorganic HAP concentration of the vent stream entering the control device. A design evaluation also must

address other vent stream characteristics and control device operating parameters as specified in any one of paragraphs (i)(1) through (5) of this section, depending on the type of control device that is used. If the vent stream is not the only inlet to the control device, the efficiency demonstration must also consider all other vapors, gases, and liquids, other than fuels, received by the control device.

(1) For a condenser, the design evaluation shall consider the vent stream flow rate, relative humidity, and temperature and shall establish the design outlet organic HAP compound concentration level, design average temperature of the condenser exhaust vent stream, and the design average temperatures of the coolant fluid at the condenser inlet and outlet. The temperature of the gas stream exiting the condenser must be measured and used to establish the outlet organic HAP concentration.

(2) For a carbon adsorption system that regenerates the carbon bed directly onsite in the control device such as a fixed-bed adsorber, the design evaluation shall consider the vent stream flow rate, relative humidity, and temperature and shall establish the design exhaust vent stream organic compound concentration level, adsorption cycle time, number and capacity of carbon beds, type and working capacity of activated carbon used for carbon beds, design total regeneration stream mass or volumetric flow over the period of each complete carbon bed regeneration cycle, design carbon bed temperature after regeneration, design carbon bed regeneration time, and design service life of carbon. For vacuum desorption, the pressure drop shall be included.

(3) For a carbon adsorption system that does not regenerate the carbon bed directly onsite in the control device such as a carbon canister, the design evaluation shall consider the vent stream mass or volumetric flow rate, relative humidity, and temperature and shall establish the design exhaust vent stream organic compound concentration level, capacity of carbon bed, type and working capacity of activated carbon used for carbon bed, and design carbon replacement interval based on the total carbon working capacity of the control device and source operating schedule.

(4) For a scrubber, the design evaluation shall consider the vent stream composition, constituent concentrations, liquid-to-vapor ratio, scrubbing liquid flow rate and concentration, temperature, and the reaction kinetics of the constituents with the scrubbing liquid. The design evaluation shall establish the design exhaust vent stream organic compound concentration level and will include the additional information in paragraphs (i)(5)(i) and (ii) of this section for trays and a packed column scrubber.

(i) Type and total number of theoretical and actual trays;

(ii) Type and total surface area of packing for entire column, and for individual packed sections if column contains more than one packed section.

[68 FR 27925, May 22, 2003, as amended at 71 FR 20467, Apr. 20, 2006]

§ 63.7188 What are my monitoring installation, operation, and maintenance requirements?

If you comply with the emission limitations of § 63.7184 by venting the emissions of your semiconductor process vent through a closed vent system to a control device, you must comply with the requirements of paragraphs (a) and (b) of this section.

(a) You must meet the applicable general monitoring, installation, operation, and maintenance requirements specified in § 63.996.

(b) You must meet the monitoring, installation, operation, and maintenance requirements specified for closed vent systems and applicable control devices in §§ 63.983 through 63.995. If you used the design evaluation procedure in § 63.7187(i) to demonstrate compliance, you must use the information from the design evaluation to establish the operating parameter level for monitoring of the control device.

APPLICATIONS, NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.7189 What applications and notifications must I submit and when?

(a) You must submit all of the applications and notifications in §§ 63.7(b)

and (c); 63.8(e), (f)(4) and (f)(6); and 63.9(b) through (e), (g) and (h) that apply to you by the dates specified.

(b) As specified in §63.9(b)(2), if you start up your affected source before May 22, 2003, you must submit an Initial Notification not later than 120 calendar days after May 22, 2003, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) As specified in §63.9(b)(3), if you start up your new or reconstructed affected source on or after May 22, 2003. you must submit an Initial Notification not later than 120 calendar days after you become subject to this subpart.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required in §63.7(b)(1).

(e) If you are required to conduct a performance test or other initial compliance demonstration, you must submit a Notification of Compliance Status according to §63.9(h)(2)(ii) and according to paragraphs (e)(1) and (2) of this section.

(1) For each initial compliance demonstration that does not include a performance test, you must submit the Notification of Compliance Status before the close of business on the 30th calendar day following the completion of the initial compliance demonstration. If you used the design evaluation procedure in §63.7187(i) to demonstrate compliance, you must include the results of the design evaluation in the Notification of Compliance Status.

(2) For each initial compliance demonstration required that includes a performance test conducted according to the requirements in Table 1 to this subpart, you must submit a notification of the date of the performance evaluation at least 60 days prior to the date the performance evaluation is scheduled to begin as required in §63.8(e)(2).

[68 FR 27925, May 22, 2003, as amended at 85 FR 73913, Nov. 19, 2020]

§63.7190 What reports must I submit and when?

(a) You must submit each of the following reports that apply to you.

(1) *Periodic compliance reports.* You must submit a periodic compliance report that contains the information required under paragraphs (c) through (e) of this section, and any requirements specified to be reported for process vents in §63.982(a)(2) and storage tanks in §63.982(a)(1).

(2) *Immediate startup, shutdown, and malfunction report.* You must submit an Immediate Startup, Shutdown, and Malfunction Report if you had a startup, shutdown, or malfunction during the reporting period that is not consistent with your SSMP. Your report must contain actions taken during the event. You must submit this report by fax or telephone within 2 working days after starting actions inconsistent with you SSMP. You are required to follow up this report with a report specifying the information in §63.10(d)(5)(ii) by letter within 7 working days after the end of the event unless you have made alternative arrangements with your permitting authority.

(b) Unless the Administrator has approved a different schedule for submission of reports under §63.10(a), you must submit each report by the date according to paragraphs (b)(1) through (5) of this section.

(1) The first periodic compliance report must cover the period beginning on the compliance date that is specified for your affected source in §63.7183 and ending on June 30 or December 31, whichever date is the first date following the end of the first 12 calendar months after the compliance date that is specified for your source in §63.7183.

(2) The first periodic compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date follows the end of the first 12 calendar months after the compliance date that is specified for your affected source in §63.7183.

(3) Each subsequent periodic compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent periodic compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date is the first date

following the end of the semiannual reporting period.

(5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent periodic compliance reports according to the dates the permitting authority has established instead of according to the dates in paragraphs (b)(1) through (4) of this section.

(c) The periodic compliance report must contain the information specified in paragraphs (c)(1) through (5) of this section.

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) If there are no deviations from any emission limitations that apply to you, a statement that there were no deviations from the emission limitations during the reporting period and that no CMS was inoperative, inactive, malfunctioning, out-of-control, repaired, or adjusted.

(5) If you had a startup, shutdown, or malfunction during the reporting period and you took actions consistent with your SSMP, your periodic compliance report must include the information in §63.10(d)(5) for each startup, shutdown, and malfunction.

(d) For each deviation from an emission limitation that occurs at an affected source where you are not using a CMS to comply with the emission limitations, the periodic compliance report must contain the information in paragraphs (d)(1) through (2) of this section.

(1) The total operating time of each affected source during the reporting period.

(2) Information on the number, duration, and cause of deviations (including unknown cause), if applicable.

(e) For each deviation from an emission limitation occurring at an affected source where you are using a CMS to demonstrate compliance with the emission limitation, you must include the information in paragraphs (e)(1) through (8) of this section.

(1) The date and time that each malfunction started and stopped, and the reason it was inoperative.

(2) The date and time that each CMS was inoperative, except for calibration checks.

(3) The date and time that each CMS was out-of-control, including the information in §63.8(c)(8).

(4) The date and time that each deviation started and stopped, and whether each deviation occurred during a period of startup, shutdown, or malfunction or during another period, and the cause of the deviation.

(5) A summary of the total duration of the deviation during the reporting period, and the total duration as a percent of the total source operating time during that reporting period.

(6) A summary of the total duration of CMS downtime during the reporting period, and the total duration of CMS downtime as a percent of the total source operating time during the reporting period.

(7) An identification of each HAP that was monitored at the affected source.

(8) The date of the latest CMS certification or audit.

§63.7191 What records must I keep?

(a) You must keep the records listed in paragraphs (a)(1) through (3) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Notification of Compliance Status and periodic report of compliance that you submitted, according to the requirements in §63.10(b)(2)(xiv).

(2) The records in §63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunctions.

(3) Records of performance tests and performance evaluations as required in §63.10(b)(2)(viii).

(b) For each CMS, you must keep the records listed in paragraphs (b)(1) through (5) of this section.

(1) Records described in §63.10(b)(2)(vi) through (xi).

(2) All required measurements needed to demonstrate compliance with a relevant standard (*e.g.*, 30-minute averages of CMS data, raw performance testing measurements, raw performance evaluation measurements).

(3) All required CMS measurements (including monitoring data recorded during unavoidable CMS breakdowns and out-of-control periods).

(4) Records of the date and time that each deviation started and stopped, and whether the deviation occurred during a period of startup, shutdown, or malfunction or during another period.

(5) Records for process vents according to the requirements specified in § 63.982(a)(2) and storage tank vents according to the requirements specified in § 63.982(a)(1).

§ 63.7192 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You can keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.7193 What parts of the General Provisions apply to me?

Table 2 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.13 apply to you.

§ 63.7194 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. Environmental Protection Agency (EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under 40 CFR part 63, subpart E, the authorities contained in paragraph (c) of this section are retained by the U.S. EPA Administrator and are not transferred to the State, local, or tribal agency.

(c) The authorities that will not be delegated to State, local, or tribal agencies are as listed in paragraphs (c)(1) through (4) of this section.

(1) Approval of alternatives to the non-opacity emission limitations in § 63.7184 under § 63.6(g).

(2) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

§ 63.7195 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in §§ 63.2 and 63.981, the General Provisions of this part (40 CFR part 63, subpart A), and in this section as follows:

Combined HAP process vent means a *process vent* that emits both inorganic and organic HAP to the atmosphere.

Control device means a combustion device, recovery device, recapture device, or any combination of these devices used for the primary purpose of reducing emissions to comply with this subpart. Devices that are inherent to a process or are integral to the operation of a process are not considered control devices for the purposes of this subpart, even though these devices may have the secondary effect of reducing emissions.

Inorganic HAP process vent means a *process vent* that emits only inorganic HAP to the atmosphere.

Organic HAP process vent means a *process vent* that emits only organic HAP to the atmosphere.

Process vent means the point at which HAP emissions are released to the atmosphere from a semiconductor manufacturing process unit or storage tank by means of a stack, chimney, vent, or other functionally equivalent opening. The HAP emission points originating from wastewater treatment equipment, other than storage tanks, are not considered to be a process vent, unless the wastewater treatment equipment emission points are connected to a common vent or exhaust plenum with other process vents.

Semiconductor manufacturing means the collection of semiconductor manufacturing process units used to manufacture p-type and n-type semiconductors or active solid state devices from a wafer substrate, including processing from crystal growth through wafer fabrication, and testing and assembly. Examples of semiconductor or related solid state devices include semiconductor diodes, semiconductor stacks, rectifiers, integrated circuits, and transistors.

Semiconductor manufacturing process unit means the collection of equipment used to carry out a discrete operation in the semiconductor manufacturing process. These operations include, but are not limited to, crystal growing; solvent stations used to prepare and clean materials for subsequent processing or for parts cleaning; wet chemical stations used for cleaning (other than solvent cleaning); photoresist application, developing, and stripping; etching; gaseous operation stations used for stripping, cleaning, doping, etching, and layering; separation; encapsulation; and testing. Research and development operations associated with semiconductor manufacturing and conducted at a semiconductor manufacturing facility are considered to be semiconductor manufacturing process units.

Storage tank means a stationary unit that is constructed primarily from nonearthen materials (such as wood, concrete, steel, fiberglass, or plastic) which provides structural support and is designed to hold an accumulation of liquids or other materials used in or generated by a semiconductor manufacturing process unit. The following are not storage tanks for the purposes of this subpart:

(1) Tanks permanently attached to motor vehicles such as trucks, railcars, barges, or ships;

(2) Flow-through tanks where wastewater undergoes treatment (such as pH adjustment) before discharge, and are not used to accumulate wastewater;

(3) Bottoms receiver tanks; and

(4) Surge control tanks.

[68 FR 27925, May 22, 2003, as amended at 73 FR 42532, 73 FR 42532, July 22, 2008]

TABLE 1 TO SUBPART BBBBB OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS

As stated in §63.7187, you must comply with the requirements for performance tests in the following table:

For . . .	You must . . .	Using . . .	According to the following requirements . . .
1. Process or storage tank vent streams.	a. Select sampling port's location and the number of traverse ports.	Method 1 or 1A of 40 CFR part 60, appendix A.	Sampling sites must be located at the inlet (if emission reduction or destruction efficiency testing is required) and outlet of the control device and prior to any releases to the atmosphere.
	b. Determine velocity and volumetric flow rate.	Method 2, 2A, 2C, 2D, 2F, or 2G of 40 CFR part 60, appendix A.	For HAP reduction efficiency testing only; not necessary for determining compliance with a ppmv concentration limit.
	c. Conduct gas molecular weight analysis.	i. Method 3, 3A, or 3B of 40 CFR part 60, appendix A.	For flow rate determination only.
		ii. ASME PTC 19.10–1981–Part 10.	You may use ASME PTC 19.10–1981–Part 10 (available for purchase from Three Park Avenue, New York, NY 10016–5990) as an alternative to EPA Method 3B.
	d. Measure moisture content of the stack gas.	Method 4 of 40 CFR part 60, appendix A.	For flow rate determination and correction to dry basis, if necessary.

For . . .	You must . . .	Using . . .	According to the following requirements . . .
2. Process vent stream ...	a. Measure organic and inorganic HAP concentration (two method option).	i. Method 18, 25, or 25A of 40 CFR part 60, appendix A, AND ii. Method 26 or 26A of 40 CFR part 60, appendix A.	(1) To determine compliance with the percent by weight emission reduction limit, conduct simultaneous sampling at inlet and outlet of control device and analyze for same organic and inorganic HAP at both inlet and outlet; and (2) If you use Method 25A to determine the TOC concentration for compliance with the 20 ppmv emission limitation, the instrument must be calibrated on methane or the predominant HAP. If you calibrate on the predominant HAP, you must comply with each of the following: —The organic HAP used as the calibration gas must be the single organic HAP representing the largest percent of emissions by volume. —The results are acceptable if the response from the high level calibration gas is at least 20 times the standard deviation of the response from the zero calibration gas when the instrument is zeroed on its most sensitive scale. —The span value of the analyzer must be less than 100 ppmv. To determine compliance with 98 percent reduction limit, conduct simultaneous sampling at inlet and outlet of control device and analyze for same organic and inorganic HAP at both inlet and outlet.
	c. Measure organic and inorganic HAP simultaneously (one method option).	Method 320 of 40 CFR part 63, appendix A.	To determine compliance with the percent by weight emission reduction limit, conduct simultaneous sampling at inlet and outlet of control device and analyze for same organic and inorganic HAP at both inlet and outlet.
3. Storage tank vent stream.	Measure inorganic HAP concentration.	Method 26 or 26A of 40 CFR part 60, appendix A, or Method 320 of 40 CFR part 63, appendix A.	To determine compliance with percent by weight emission reduction limit, conduct simultaneous sampling at inlet and outlet of control device and analyze for same inorganic HAP at both inlet and outlet.

TABLE 2 TO SUBPART BBBBB OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART BBBBB

As stated in §63.7193, you must comply with the applicable General Provisions requirements according to the following table:

Citation	Subject	Applicable to Subpart BBBBB?
§63.1	Applicability	Yes.
§63.2	Definitions	Yes.
§63.3	Units and Abbreviations	Yes.
§63.4	Prohibited Activities and Circumvention	Yes.
§63.5	Construction and Reconstruction	Yes.
§63.6	Compliance with Standards and Maintenance	Yes.
§63.7	Performance Testing Requirements	Yes, with the exception of §63.7(e)(1). The requirements of §63.7(e)(1) do not apply. Performance testing requirements that apply are specified in this subpart, and in §63.982(a)(1) and (2).
§63.8	Monitoring Requirements	Monitoring requirements are specified in this subpart and in §63.982(a)(1) and (2). The closed vent system inspection requirements of §63.983(c), as referenced by §63.982(a)(1) and (2), do not apply.
§63.9	Notification Requirements	Yes.
§63.10	Recordkeeping and Reporting Requirements	Yes, with the exception of §63.10(e). The requirements of §63.10(e) do not apply. In addition, the recordkeeping and reporting requirements specified in this subpart apply.
§63.11	Flares	Yes.

Citation	Subject	Applicable to Subpart BBBBB?
§ 63.12	Delegation	Yes.
§ 63.13	Addresses	Yes.
§ 63.14	Incorporation by Reference	Yes.
§ 63.15	Availability of Information	Yes.

Subpart CCCCC—National Emission Standards for Hazardous Air Pollutants for Coke Ovens: Pushing, Quenching, and Battery Stacks

SOURCE: 68 FR 18025, Apr. 14, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7280 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for pushing, soaking, quenching, and battery stacks at coke oven batteries. This subpart also establishes requirements to demonstrate initial and continuous compliance with all applicable emission limitations, work practice standards, and operation and maintenance requirements in this subpart.

§ 63.7281 Am I subject to this subpart?

You are subject to this subpart if you own or operate a coke oven battery at a coke plant that is (or is part of) a major source of hazardous air pollutant (HAP) emissions. A major source of HAP is a plant site that emits or has the potential to emit any single HAP at a rate of 10 tons or more per year or any combination of HAP at a rate of 25 tons or more per year.

§ 63.7282 What parts of my plant does this subpart cover?

(a) This subpart applies to each new or existing affected source at your coke plant. The affected source is each coke oven battery.

(b) This subpart covers emissions from pushing, soaking, quenching, and battery stacks from each affected source.

(c) An affected source at your coke plant is existing if you commenced construction or reconstruction of the affected source before July 3, 2001.

(d) An affected source at your coke plant is new if you commenced construction or reconstruction of the affected source on or after July 3, 2001. An affected source is reconstructed if it meets the definition of ''reconstruction'' in § 63.2.

§ 63.7283 When do I have to comply with this subpart?

(a) If you have an existing affected source, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you no later than April 14, 2006.

(b) If you have a new affected source and its initial startup date is on or before April 14, 2003, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you by April 14, 2003.

(c) If you have a new affected source and its initial startup date is after April 14, 2003, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you upon initial startup.

(d) You must meet the notification and schedule requirements in § 63.7340. Several of these notifications must be submitted before the compliance date for your affected source.

[68 FR 18025, Apr. 14, 2003; 68 FR 19885, Apr. 22, 2003]

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

§ 63.7290 What emission limitations must I meet for capture systems and control devices applied to pushing emissions?

(a) You must not discharge to the atmosphere emissions of particulate matter from a control device applied to

pushing emissions from a new or existing coke oven battery that exceed the applicable limit in paragraphs (a)(1) through (4) of this section:

(1) 0.01 grain per dry standard cubic foot (gr/dscf) if a cokeside shed is used to capture emissions;

(2) 0.02 pound per ton (lb/ton) of coke if a moveable hood vented to a stationary control device is used to capture emissions;

(3) If a mobile scrubber car that does not capture emissions during travel is used:

(i) 0.03 lb/ton of coke for a control device applied to pushing emissions from a short battery, or

(ii) 0.01 lb/ton of coke for a control device applied to pushing emissions from a tall battery; and

(4) 0.04 lb/ton of coke if a mobile control device that captures emissions during travel is used.

(b) You must meet each operating limit in paragraphs (b)(1) through (4) of this section that applies to you for a new or existing coke oven battery.

(1) For each venturi scrubber applied to pushing emissions, you must maintain the daily average pressure drop and scrubber water flow rate at or above the minimum levels established during the initial performance test.

(2) For each hot water scrubber applied to pushing emissions, you must maintain the daily average water pressure and water temperature at or above the minimum levels established during the initial performance test.

(3) For each capture system applied to pushing emissions, you must maintain the daily average volumetric flow rate at the inlet of the control device at or above the minimum level established during the initial performance test; or

(i) For each capture system that uses an electric motor to drive the fan, you must maintain the daily average fan motor amperes at or above the minimum level established during the initial performance test; and

(ii) For each capture system that does not use a fan driven by an electric motor, you must maintain the daily average static pressure at the inlet to the control device at an equal or greater vacuum than the level established during the initial performance test or maintain the daily average fan revolutions per minute (RPM) at or above the minimum level established during the initial performance test.

(4) For each multicyclone, you must maintain the daily average pressure drop at or below the minimum level established during the initial performance test.

[68 FR 18025, Apr. 14, 2003, as amended at 69 FR 60818, Oct. 13, 2004]

§ 63.7291 What work practice standards must I meet for fugitive pushing emissions if I have a by-product coke oven battery with vertical flues?

(a) You must meet each requirement in paragraphs (a)(1) through (7) of this section for each new or existing by-product coke oven battery with vertical flues.

(1) Observe and record the opacity of fugitive pushing emissions from each oven at least once every 90 days. If an oven cannot be observed during a 90-day period due to circumstances that were not reasonably avoidable, you must observe the opacity of the first push of that oven following the close of the 90-day period that is capable of being observed in accordance with the procedures in § 63.7334(a), and you must document why the oven was not observed within a 90-day period. All opacity observations of fugitive pushing emissions for batteries with vertical flues must be made using the procedures in § 63.7334(a).

(2) If two or more batteries are served by the same pushing equipment and total no more than 90 ovens, the batteries as a unit can be considered a single battery.

(3) Observe and record the opacity of fugitive pushing emissions for at least four consecutive pushes per battery each day. Exclude any push during which the observer's view is obstructed or obscured by interferences and observe the next available push to complete the set of four pushes. If necessary due to circumstances that were not reasonably avoidable, you may observe fewer than four consecutive pushes in a day; however, you must observe and record as many consecutive pushes as possible and document why four consecutive pushes could not be

observed. You may observe and record one or more non-consecutive pushes in addition to any consecutive pushes observed in a day.

(4) Do not alter the pushing schedule to change the sequence of consecutive pushes to be observed on any day. Keep records indicating the legitimate operational reason for any change in your pushing schedule which results in a change in the sequence of consecutive pushes observed on any day.

(5) If the average opacity for any individual push exceeds 30 percent opacity for any short battery or 35 percent opacity for any tall battery, you must take corrective action and/or increase coking time for that oven. You must complete corrective action or increase coking time within either 10 calendar days or the number of days determined using Equation 1 of this section, whichever is greater:

$$X = 0.55 * Y \quad \text{(Eq. 1)}$$

Where:

X = Number of calendar days allowed to complete corrective action or increase coking time; and

Y = Current coking time for the oven, hours.

For the purpose of determining the number of calendar days allowed under Equation 1 of this section, day one is the first day following the day you observed an opacity in excess of 30 percent for any short battery or 35 percent for any tall battery. Any fraction produced by Equation 1 of this section must be counted as a whole day. Days during which the oven is removed from service are not included in the number of days allowed to complete corrective action.

(6)(i) You must demonstrate that the corrective action and/or increased coking time was successful. After a period of time no longer than the number of days allowed in paragraph (a)(5) of this section, observe and record the opacity of the first two pushes for the oven capable of being observed using the procedures in §63.7334(a). The corrective action and/or increased coking time was successful if the average opacity for each of the two pushes is 30 percent or less for a short battery or 35 percent or less for a tall battery. If the corrective action and/or increased coking time was successful, you may return the oven to the 90-day reading rotation described in paragraph (a)(1) of this section. If the average opacity of either push exceeds 30 percent for a short battery or 35 percent for a tall battery, the corrective action and/or increased coking time was unsuccessful, and you must complete additional corrective action and/or increase coking time for that oven within the number of days allowed in paragraph (a)(5) of this section.

(ii) After implementing any additional corrective action and/or increased coking time required under paragraph (a)(6)(i) or (a)(7)(ii) of this section, you must demonstrate that corrective action and/or increased coking time was successful. After a period of time no longer than the number of days allowed in paragraph (a)(5) of this section, you must observe and record the opacity of the first two pushes for the oven capable of being observed using the procedures in §63.7334(a). The corrective action and/or increased coking time was successful if the average opacity for each of the two pushes is 30 percent or less for a short battery or 35 percent or less for a tall battery. If the corrective action and/or increased coking time was successful, you may return the oven to the 90-day reading rotation described in paragraph (a)(1) of this section. If the average opacity of either push exceeds 30 percent for a short battery or 35 percent for a tall battery, the corrective action and/or increased coking time was unsuccessful, and you must follow the procedures in paragraph (a)(6)(iii) of this section.

(iii) If the corrective action and/or increased coking time was unsuccessful as described in paragraph (a)(6)(ii) of this section, you must repeat the procedures in paragraph (a)(6)(ii) of this section until the corrective action and/or increased coking time is successful. You must report to the permitting authority as a deviation each unsuccessful attempt at corrective action and/or increased coking time under paragraph (a)(6)(ii) of this section.

(7)(i) If at any time you place an oven on increased coking time as a result of fugitive pushing emissions that exceed 30 percent for a short battery or 35 percent for a tall battery, you must keep the oven on the increased coking time

until the oven qualifies for decreased coking time using the procedures in paragraph (a)(7)(ii) or (a)(7)(iii) of this section.

(ii) To qualify for a decreased coking time for an oven placed on increased coking time in accordance with paragraph (a)(5) or (6) of this section, you must operate the oven on the decreased coking time. After no more than two coking cycles on the decreased coking time, you must observe and record the opacity of the first two pushes that are capable of being observed using the procedures in §63.7334(a). If the average opacity for each of the two pushes is 30 percent or less for a short battery or 35 percent or less for a tall battery, you may keep the oven on the decreased coking time and return the oven to the 90-day reading rotation described in paragraph (a)(1) of this section. If the average opacity of either push exceeds 30 percent for a short battery or 35 percent for a tall battery, the attempt to qualify for a decreased coking time was unsuccessful. You must then return the oven to the previously established increased coking time, or implement other corrective action(s) and/or increased coking time. If you implement other corrective action and/or a coking time that is shorter than the previously established increased coking time, you must follow the procedures in paragraph (a)(6)(ii) of this section to confirm that the corrective action(s) and/or increased coking time was successful.

(iii) If the attempt to qualify for decreased coking time was unsuccessful as described in paragraph (a)(7)(ii) of this section, you may again attempt to qualify for decreased coking time for the oven. To do this, you must operate the oven on the decreased coking time. After no more than two coking cycles on the decreased coking time, you must observe and record the opacity of the first two pushes that are capable of being observed using the procedures in §63.7334(a). If the average opacity for each of the two pushes is 30 percent or less for a short battery or 35 percent or less for a tall battery, you may keep the oven on the decreased coking time and return the oven to the 90-day reading rotation described in paragraph (a)(1) of this section. If the average opacity of either push exceeds 30 percent for a short battery or 35 percent for a tall battery, the attempt to qualify for a decreased coking time was unsuccessful. You must then return the oven to the previously established increased coking time, or implement other corrective action(s) and/or increased coking time. If you implement other corrective action and/or a coking time that is shorter than the previously established increased coking time, you must follow the procedures in paragraph (a)(6)(ii) of this section to confirm that the corrective action(s) and/or increased coking time was successful.

(iv) You must report to the permitting authority as a deviation the second and any subsequent consecutive unsuccessful attempts on the same oven to qualify for decreased coking time as described in paragraph (a)(7)(iii) of this section.

(b) As provided in §63.6(g), you may request to use an alternative to the work practice standards in paragraph (a) of this section.

§63.7292 What work practice standards must I meet for fugitive pushing emissions if I have a by-product coke oven battery with horizontal flues?

(a) You must comply with each of the requirements in paragraphs (a)(1) through (4) of this section.

(1) Prepare and operate by a written plan that will eliminate or minimize incomplete coking for each by-product coke oven battery with horizontal flues. You must submit the plan and supporting documentation to the Administrator (or delegated authority) for approval no later than 90 days after completing all observations and measurements required for the study in paragraph (a)(3) of this section or April 14, 2004, whichever is earlier. You must begin operating by the plan requirements by the compliance date that is specified in §63.7283. The written plan must identify minimum flue temperatures for different coking times and a battery-wide minimum acceptable flue temperature for any oven at any coking time.

(2) Submit the written plan and supporting documentation to the Administrator (or delegated authority) for review and approval. Include all data collected during the study described in paragraph (a)(3) of this section. If the Administrator (or delegated authority) disapproves the plan, you must revise the plan as directed by the Administrator (or delegated authority) and submit the amended plan for approval. The Administrator (or delegated authority) may require you to collect and submit additional data. You must operate according to your submitted plan (or submitted amended plan, if any) until the Administrator (or delegated authority) approves your plan.

(3) You must base your written plan on a study that you conduct that meets each of the requirements listed in paragraphs (a)(3)(i) through (x) of this section.

(i) Initiate the study by July 14, 2003. Notify the Administrator (or delegated authority) at least 7 days prior to initiating the study according to the requirements in § 63.7340(f).

(ii) Conduct the study under representative operating conditions, including but not limited to the range of moisture content and volatile matter in the coal that is charged.

(iii) Include every oven in the study and observe at least two pushes from each oven.

(iv) For each push observed, measure and record the temperature of every flue within 2 hours before the scheduled pushing time. Document the oven number, date, and time the oven was charged and pushed, and calculate the net coking time.

(v) For each push observed, document the factors to be used to identify pushes that are incompletely coked. These factors must include (but are not limited to): average opacity during the push, average opacity during travel to the quench tower, average of six highest consecutive observations during both push and travel, highest single opacity reading, color of the emissions (especially noting any yellow or brown emissions), presence of excessive smoke during travel to the quench tower, percent volatile matter in the coke, percent volatile matter and percent moisture in the coal that is charged, and the date the oven was last rebuilt or completely relined. Additional documentation may be provided in the form of pictures or videotape of emissions during the push and travel. All opacity observations must be conducted in accordance with the procedures in § 63.7334(a)(3) through (7).

(vi) Inspect the inside walls of the oven after each observed push for cool spots as indicated by a flue that is darker than others (the oven walls should be red hot) and record the results.

(vii) For each push observed, note where incomplete coking occurs if possible (*e.g.*, coke side end, pusher side end, top, or center of the coke mass). For any push with incomplete coking, investigate and document the probable cause.

(viii) Use the documented factors in paragraph (a)(3)(v) of this section to identify pushes that were completely coked and those that were not completely coked. Provide a rationale for the determination based on the documentation of factors observed during the study.

(ix) Use only the flue temperature and coking time data for pushes that were completely coked to identify minimum flue temperatures for various coking times. Submit the criteria used to determine complete coking, as well as a table of coking times and corresponding temperatures for complete coking as part of your plan.

(x) Determine the battery-wide minimum acceptable flue temperature for any oven. This temperature will be equal to the lowest temperature that provided complete coking as determined in paragraph (a)(3)(ix) of this section.

(4) You must operate according to the coking times and temperatures in your approved plan and the requirements in paragraphs (a)(4)(i) through (viii) of this section.

(i) Measure and record the percent volatile matter in the coal that is charged.

(ii) Measure and record the temperature of all flues on two ovens per day within 2 hours before the scheduled pushing time for each oven. Measure and record the temperature of all flues on each oven at least once each month.

(iii) For each oven observed in accordance with paragraph (a)(4)(ii) of this section, record the time each oven is charged and pushed and calculate and record the net coking time. If any measured flue temperature for an oven is below the minimum flue temperature for an oven's scheduled coking time as established in the written plan, increase the coking time for the oven to the coking time in the written plan for the observed flue temperature before pushing the oven.

(iv) If you increased the coking time for any oven in accordance with paragraph (a)(4)(iii) of this section, you must investigate the cause of the low flue temperature and take corrective action to fix the problem. You must continue to measure and record the temperature of all flues for the oven within 2 hours before each scheduled pushing time until the measurements meet the minimum temperature requirements for the increased coking time for two consecutive pushes. If any measured flue temperature for an oven on increased coking time falls below the minimum flue temperature for the increased coking time, as established in the written plan, you must increase the coking time for the oven to the coking time specified in the written plan for the observed flue temperature before pushing the oven. The oven must continue to operate at this coking time (or at a longer coking time if the temperature falls below the minimum allowed for the increased coking time) until the problem has been corrected, and you have confirmed that the corrective action was successful as required by paragraph (a)(4)(v) of this section.

(v) Once the heating problem has been corrected, the oven may be returned to the battery's normal coking schedule. You must then measure and record the flue temperatures for the oven within 2 hours before the scheduled pushing time for the next two consecutive pushes. If any flue temperature measurement is below the minimum flue temperature for that coking time established in the written plan, repeat the procedures in paragraphs (a)(4)(iii) and (iv) of this section.

(vi) If any flue temperature measurement is below the battery-wide minimum acceptable temperature for complete coking established in the written plan for any oven at any coking time, you must remove the oven from service for repairs.

(vii) For an oven that has been repaired and returned to service after being removed from service in accordance with paragraph (a)(4)(vi) of this section, you must measure and record the temperatures of all flues for the oven within 2 hours before the first scheduled pushing time. If any flue temperature measurement is below the minimum flue temperature for the scheduled coking time, as established in the written plan, you must repeat the procedures described in paragraphs (a)(4)(iii) and (iv) of this section.

(viii) For an oven that has been repaired and returned to service after removal from service in accordance with paragraph (a)(4)(vi) of this section, you must report as a deviation to the permitting authority any flue temperature measurement made during the initial coking cycle after return to service that is below the lowest acceptable minimum flue temperature.

(b) As provided in § 63.6(g), you may request to use an alternative to the work practice standards in paragraph (a) of this section.

§ 63.7293 What work practice standards must I meet for fugitive pushing emissions if I have a non-recovery coke oven battery?

(a) You must meet the requirements in paragraphs (a)(1) and (2) of this section for each new and existing non-recovery coke oven battery.

(1) You must visually inspect each oven prior to pushing by opening the door damper and observing the bed of coke.

(2) Do not push the oven unless the visual inspection indicates that there is no smoke in the open space above the coke bed and that there is an unobstructed view of the door on the opposite side of the oven.

(b) As provided in § 63.6(g), you may request to use an alternative to the work practice standard in paragraph (a) of this section.

§ 63.7294 What work practice standard must I meet for soaking?

(a) For each new and existing by-product coke oven battery, you must prepare and operate at all times according to a written work practice plan for soaking. Each plan must include measures and procedures to:

(1) Train topside workers to identify soaking emissions that require corrective actions.

(2) Damper the oven off the collecting main prior to opening the standpipe cap.

(3) Determine the cause of soaking emissions that do not ignite automatically, including emissions that result from raw coke oven gas leaking from the collecting main through the damper, and emissions that result from incomplete coking.

(4) If soaking emissions are caused by leaks from the collecting main, take corrective actions to eliminate the soaking emissions. Corrective actions may include, but are not limited to, reseating the damper, cleaning the flushing liquor piping, using aspiration, putting the oven back on the collecting main, or igniting the emissions.

(5) If soaking emissions are not caused by leaks from the collecting main, notify a designated responsible party. The responsible party must determine whether the soaking emissions are due to incomplete coking. If incomplete coking is the cause of the soaking emissions, you must put the oven back on the collecting main until it is completely coked or you must ignite the emissions.

(b) As provided in § 63.6(g), you may request to use an alternative to the work practice standard in paragraph (a) of this section.

§ 63.7295 What requirements must I meet for quenching?

(a) You must meet the requirements in paragraphs (a)(1) and (2) of this section for each quench tower and backup quench station at a new or existing coke oven battery.

(1) For the quenching of hot coke, you must meet the requirements in paragraph (a)(1)(i) or (ii) of this section.

(i) The concentration of total dissolved solids (TDS) in the water used for quenching must not exceed 1,100 milligrams per liter (mg/L); or

(ii) The sum of the concentrations of benzene, benzo(a)pyrene, and naphthalene in the water used for quenching must not exceed the applicable site-specific limit approved by the permitting authority.

(2) You must use acceptable makeup water, as defined in § 63.7352, as makeup water for quenching.

(b) For each quench tower at a new or existing coke oven battery and each backup quench station at a new coke oven battery, you must meet each of the requirements in paragraphs (b)(1) through (4) of this section.

(1) You must equip each quench tower with baffles such that no more than 5 percent of the cross sectional area of the tower may be uncovered or open to the sky.

(2) You must wash the baffles in each quench tower once each day that the tower is used to quench coke, except as specified in paragraphs (b)(2)(i) and (ii) of this section.

(i) You are not required to wash the baffles in a quench tower if the highest measured ambient temperature remains less than 30 degrees Fahrenheit throughout that day (24-hour period). If the measured ambient temperature rises to 30 degrees Fahrenheit or more during the day, you must resume daily washing according to the schedule in your operation and maintenance plan.

(ii) You must continuously record the ambient temperature on days that the baffles were not washed.

(3) You must inspect each quench tower monthly for damaged or missing baffles and blockage.

(4) You must initiate repair or replacement of damaged or missing baffles within 30 days and complete as soon as practicable.

(c) As provided in § 63.6(g), you may request to use an alternative to the work practice standards in paragraph (b) of this section.

§ 63.7296 What emission limitations must I meet for battery stacks?

You must not discharge to the atmosphere any emissions from any battery stack at a new or existing by-product coke oven battery that exhibit an opacity greater than the applicable

limit in paragraphs (a) and (b) of this section.

(a) Daily average of 15 percent opacity for a battery on a normal coking cycle.

(b) Daily average of 20 percent opacity for a battery on batterywide extended coking.

OPERATION AND MAINTENANCE REQUIREMENTS

§ 63.7300 What are my operation and maintenance requirements?

(a) As required by § 63.6(e)(1)(i), you must always operate and maintain your affected source, including air pollution control and monitoring equipment, in a manner consistent with good air pollution control practices for minimizing emissions at least to the levels required by this subpart.

(b) You must prepare and operate at all times according to a written operation and maintenance plan for the general operation and maintenance of new or existing by-product coke oven batteries. Each plan must address, at a minimum, the elements listed in paragraphs (b)(1) through (6) of this section.

(1) Frequency and method of recording underfiring gas parameters.

(2) Frequency and method of recording battery operating temperature, including measurement of individual flue and cross-wall temperatures.

(3) Procedures to prevent pushing an oven before it is fully coked.

(4) Procedures to prevent overcharging and undercharging of ovens, including measurement of coal moisture, coal bulk density, and procedures for determining volume of coal charged.

(5) Frequency and procedures for inspecting flues, burners, and nozzles.

(6) Schedule and procedures for the daily washing of baffles.

(c) You must prepare and operate at all times according to a written operation and maintenance plan for each capture system and control device applied to pushing emissions from a new or existing coke oven battery. Each plan must address at a minimum the elements in paragraphs (c)(1) through (3) of this section.

(1) Monthly inspections of the equipment that are important to the performance of the total capture system (*e.g.*, pressure sensors, dampers, and damper switches). This inspection must include observations of the physical appearance of the equipment (*e.g.*, presence of holes in ductwork or hoods, flow constrictions caused by dents or accumulated dust in ductwork, and fan erosion). In the event a defect or deficiency is found in the capture system (during a monthly inspection or between inspections), you must complete repairs within 30 days after the date that the defect or deficiency is discovered. If you determine that the repairs cannot be completed within 30 days, you must submit a written request for an extension of time to complete the repairs that must be received by the permitting authority not more than 20 days after the date that the defect or deficiency is discovered. The request must contain a description of the defect or deficiency, the steps needed and taken to correct the problem, the interim steps being taken to mitigate the emissions impact of the defect or deficiency, and a proposed schedule for completing the repairs. The request shall be deemed approved unless and until such time as the permitting authority notifies you that it objects to the request. The permitting authority may consider all relevant factors in deciding whether to approve or deny the request (including feasibility and safety). Each approved schedule must provide for completion of repairs as expeditiously as practicable, and the permitting authority may request modifications to the proposed schedule as part of the approval process.

(2) Preventative maintenance for each control device, including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

(3) Corrective action for all baghouses applied to pushing emissions. In the event a bag leak detection system alarm is triggered, you must initiate corrective action to determine the cause of the alarm within 1 hour of the alarm, initiate corrective action to correct the cause of the problem within 24 hours of the alarm, and complete the corrective action as soon as practicable. Actions may include, but are not limited to:

(i) Inspecting the baghouse for air leaks, torn or broken bags or filter media, or any other condition that may cause an increase in emissions.

(ii) Sealing off defective bags or filter media.

(iii) Replacing defective bags or filter media or otherwise repairing the control device.

(iv) Sealing off a defective baghouse compartment.

(v) Cleaning the bag leak detection system probe, or otherwise repairing the bag leak detection system.

(vi) Shutting down the process producing the particulate emissions.

[68 FR 18025, Apr. 14, 2003, as amended at 70 FR 44289, Aug. 2, 2005]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7310 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the emission limitations, work practice standards, and operation and maintenance requirements in this subpart at all times, except during periods of startup, shutdown, and malfunction as defined in § 63.2.

(b) During the period between the compliance date specified for your affected source in § 63.7283 and the date upon which continuous monitoring systems have been installed and certified and any applicable operating limits have been set, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.

(c) You must develop a written startup, shutdown, and malfunction plan according to the provisions in § 63.6(e)(3).

[68 FR 18025, Apr. 14, 2003, as amended at 71 FR 20467, Apr. 20, 2006]

INITIAL COMPLIANCE REQUIREMENTS

§ 63.7320 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) As required in § 63.7(a)(2), you must conduct a performance test to demonstrate compliance with each limit in § 63.7290(a) for emissions of particulate matter from a control device applied to pushing emissions that applies to you within 180 calendar days after the compliance date that is specified in § 63.7283.

(b) You must conduct performance tests to demonstrate compliance with the TDS limit or constituent limit for quench water in § 63.7295(a)(1) and each opacity limit in § 63.7297(a) for a by-product coke oven battery stack by the compliance date that is specified in § 63.7283.

(c) For each work practice standard and operation and maintenance requirement that applies to you, you must demonstrate initial compliance within 30 calendar days after the compliance date that is specified in § 63.7283.

(d) If you commenced construction or reconstruction between July 3, 2001 and April 14, 2003, you must demonstrate initial compliance with either the proposed emission limit or the promulgated emission limit no later than October 14, 2003, or no later than 180 calendar days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

(e) If you commenced construction or reconstruction between July 3, 2001 and April 14, 2003, and you chose to comply with the proposed emission limit when demonstrating initial compliance, you must conduct a second performance test to demonstrate compliance with the promulgated emission limit by October 11, 2006, or after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

§ 63.7321 When must I conduct subsequent performance tests?

For each control device subject to an emission limit for particulate matter in § 63.7290(a), you must conduct subsequent performance tests no less frequently than twice (at mid-term and renewal) during each term of your title V operating permit.

§ 63.7322 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits for particulate matter?

(a) You must conduct each performance test that applies to your affected source according to the requirements in paragraph (b) of this section.

(b) To determine compliance with the emission limit for particulate matter

from a control device applied to pushing emissions where a cokeside shed is the capture system, follow the test methods and procedures in paragraphs (b)(1) and (2) of this section. To determine compliance with a process-weighted mass rate of particulate matter (lb/ton of coke) from a control device applied to pushing emissions where a cokeside shed is not used, follow the test methods and procedures in paragraphs (b)(1) through (4) of this section.

(1) Determine the concentration of particulate matter according to the following test methods in appendix A to 40 CFR part 60.

(i) Method 1 to select sampling port locations and the number of traverse points. Sampling sites must be located at the outlet of the control device and prior to any releases to the atmosphere.

(ii) Method 2, 2F, or 2G to determine the volumetric flow rate of the stack gas.

(iii) Method 3, 3A, or 3B to determine the dry molecular weight of the stack gas.

(iv) Method 4 to determine the moisture content of the stack gas.

(v) Method 5 or 5D, as applicable, to determine the concentration of front half particulate matter in the stack gas.

(2) During each particulate matter test run, sample only during periods of actual pushing when the capture system fan and control device are engaged. Collect a minimum sample volume of 30 dry standard cubic feet of gas during each test run. Three valid test runs are needed to comprise a performance test. Each run must start at the beginning of a push and finish at the end of a push (*i.e.*, sample for an integral number of pushes).

(3) Determine the total combined weight in tons of coke pushed during the duration of each test run according to the procedures in your source test plan for calculating coke yield from the quantity of coal charged to an individual oven.

(4) Compute the process-weighted mass emissions (E_p) for each test run using Equation 1 of this section as follows:

$$E_p = \frac{C \times Q \times T}{P \times K} \qquad \text{(Eq. 1)}$$

Where:

E_p = Process weighted mass emissions of particulate matter, lb/ton;

C = Concentration of particulate matter, gr/dscf;

Q = Volumetric flow rate of stack gas, dscf/hr;

T = Total time during a run that a sample is withdrawn from the stack during pushing, hr;

P = Total amount of coke pushed during the test run, tons; and

K = Conversion factor, 7,000 gr/lb.

[68 FR 18025, Apr. 14, 2003, as amended at 70 FR 44289, Aug. 2, 2005]

§ 63.7323 What procedures must I use to establish operating limits?

(a) For a venturi scrubber applied to pushing emissions from a coke oven battery, you must establish site-specific operating limits for pressure drop and scrubber water flow rate according to the procedures in paragraphs (a)(1) and (2) of this section.

(1) Using the continuous parameter monitoring systems (CPMS) required in § 63.7330(b), measure and record the pressure drop and scrubber water flow rate for each particulate matter test run during periods of pushing. A minimum of one pressure drop measurement and one scrubber water flow rate measurement must be obtained for each push.

(2) Compute and record the average pressure drop and scrubber water flow rate for each test run. Your operating limits are the lowest average pressure drop and scrubber water flow rate values recorded during any of the three runs that meet the applicable emission limit.

(b) For a hot water scrubber applied to pushing emissions from a coke oven battery, you must establish site-specific operating limits for water pressure and water temperature according to the procedures in paragraphs (b)(1) and (2) of this section.

(1) Using the CPMS required in § 63.7330(c), measure and record the hot water pressure and temperature for each particulate matter test run during periods of pushing. A minimum of one pressure measurement and one temperature measurement must be

made just prior to each push by monitoring the hot water holding tank on the mobile scrubber car.

(2) Compute and record the average water pressure and temperature for each test run. Your operating limits are the lowest pressure and temperature values recorded during any of the three runs that meet the applicable emission limit.

(c) For a capture system applied to pushing emissions from a coke oven battery, you must establish a site-specific operating limit according to the procedures in paragraphs (c)(1), (2), or (3) of this section.

(1) If you elect the operating limit in § 63.7290(b)(3) for volumetric flow rate, measure and record the total volumetric flow rate at the inlet of the control device during each push sampled for each particulate matter test run. Your operating limit is the lowest volumetric flow rate recorded during any of the three runs that meet the emission limit.

(2) If you elect the operating limit in § 63.7290(b)(3)(i) for fan motor amperes, measure and record the fan motor amperes during each push sampled for each particulate matter test run. Your operating limit is the lowest fan motor amperes recorded during any of the three runs that meet the emission limit.

(3) If you elect the operating limit in § 63.7290(b)(3)(ii) for static pressure or fan RPM, measure and record the static pressure at the inlet of the control device or fan RPM during each push sampled for each particulate matter test run. Your operating limit for static pressure is the minimum vacuum recorded during any of the three runs that meets the emission limit. Your operating limit for fan RPM is the lowest fan RPM recorded during any of the three runs that meets the emission limit.

(d) For a multicyclone applied to pushing emissions from a coke oven battery, you must establish a site-specific operating limit for pressure drop according to the procedures in paragraphs (d)(1) and (2) of this section.

(1) Using the CPMS required in § 63.7330(f), measure and record the pressure drop for each particulate matter test run during periods of pushing. A minimum of one pressure drop measurement must be obtained for each push.

(2) Compute and record the average pressure drop for each test run. Your operating limit is the highest average pressure drop value recorded during any of the three runs that meet the emission limit.

(e) You may change the operating limit for a venturi scrubber, capture system, or mobile control device that captures emissions during pushing if you meet the requirements in paragraphs (e)(1) through (3) of this section.

(1) Submit a written notification to the Administrator of your request to conduct a new performance test to revise the operating limit.

(2) Conduct a performance test to demonstrate that emissions of particulate matter from the control device do not exceed the applicable limit in § 63.7290(a).

(3) Establish revised operating limits according to the applicable procedures in paragraphs (a) through (d) of this section.

[68 FR 18025, Apr. 14, 2003, as amended at 69 FR 60818, Oct. 13, 2004]

§ 63.7324 What procedures must I use to demonstrate initial compliance with the opacity limits?

(a) You must conduct each performance test that applies to your affected source according to the requirements in paragraph (b) of this section.

(b) To determine compliance with the daily average opacity limit for stacks of 15 percent for a by-product coke oven battery on a normal coking cycle or 20 percent for a by-product coke oven battery on batterywide extended coking, follow the test methods and procedures in paragraphs (b)(1) through (3) of this section.

(1) Using the continuous opacity monitoring system (COMS) required in § 63.7330(e), measure and record the opacity of emissions from each battery stack for a 24-hour period.

(2) Reduce the monitoring data to hourly averages as specified in § 63.8(g)(2).

(3) Compute and record the 24-hour (daily) average of the COMS data.

§ 63.7325 What test methods and other procedures must I use to demonstrate initial compliance with the TDS or constituent limits for quench water?

(a) If you elect the TDS limit for quench water in § 63.7295(a)(1)(i), you must conduct each performance test that applies to your affected source according to the conditions in paragraphs (a)(1) and (2) of this section.

(1) Take the quench water sample from a location that provides a representative sample of the quench water as applied to the coke (*e.g.*, from the header that feeds water to the quench tower reservoirs). Conduct sampling under normal and representative operating conditions.

(2) Determine the TDS concentration of the sample using Method 160.1 in 40 CFR part 136.3 (see ''residue—filterable''), except that you must dry the total filterable residue at 103 to 105 °C (degrees Centigrade) instead of 180 °C.

(b) If at any time you elect to meet the alternative requirements for quench water in § 63.7295(a)(1)(ii), you must establish a site-specific constituent limit according to the procedures in paragraphs (b)(1) through (4) of this section.

(1) Take a minimum of nine quench water samples from a location that provides a representative sample of the quench water as applied to the coke (*e.g.*, from the header that feeds water to the quench tower reservoirs). Conduct sampling under normal and representative operating conditions.

(2) For each sample, determine the TDS concentration according to the requirements in paragraph (a)(2) of this section and the concentration of benzene, benzo(a)pyrene, and naphthalene using the applicable methods in 40 CFR part 136 or an approved alternative method.

(3) Determine and record the highest sum of the concentrations of benzene, benzo(a)pyrene, and naphthalene in any sample that has a TDS concentration less than or equal to the TDS limit of 1,100 mg/L. This concentration is the site-specific constituent limit.

(4) Submit the site-specific limit, sampling results, and all supporting data and calculations to your permitting authority for review and approval.

(c) If you elect the constituent limit for quench water in § 63.7295(a)(1)(ii), you must conduct each performance test that applies to your affected source according to the conditions in paragraphs (c)(1) and (2) of this section.

(1) Take a quench water sample from a location that provides a representative sample of the quench water as applied to the coke (*e.g.*, from the header that feeds water to the quench tower reservoirs). Conduct sampling under normal and representative operating conditions.

(2) Determine the sum of the concentration of benzene, benzo(a)pyrene, and naphthalene in the sample using the applicable methods in 40 CFR part 136 or an approved alternative method.

§ 63.7326 How do I demonstrate initial compliance with the emission limitations that apply to me?

(a) For each coke oven battery subject to the emission limit for particulate matter from a control device applied to pushing emissions, you have demonstrated initial compliance if you meet the requirements in paragraphs (a)(1) through (4) of this section that apply to you.

(1) The concentration of particulate matter, measured in accordance with the performance test procedures in § 63.7322(b)(1) and (2), did not exceed 0.01 gr/dscf for a control device where a cokeside shed is used to capture pushing emissions or the process-weighted mass rate of particulate matter (lb/ton of coke), measured in accordance with the performance test procedures in § 63.7322(b)(1) through (4), did not exceed:

(i) 0.02 lb/ton of coke if a moveable hood vented to a stationary control device is used to capture emissions;

(ii) If a mobile scrubber car that does not capture emissions during travel is used, 0.03 lb/ton of coke from a control device applied to pushing emissions from a short coke oven battery or 0.01 lb/ton of coke from a control device applied to pushing emissions from a tall coke oven battery; and

(iii) 0.04 lb/ton of coke if a mobile control device that captures emissions during travel is used.

(2) For each venturi scrubber applied to pushing emissions, you have established appropriate site-specific operating limits and have a record of the pressure drop and scrubber water flow rate measured during the performance test in accordance with § 63.7323(a).

(3) For each hot water scrubber applied to pushing emissions, you have established appropriate site-specific operating limits and have a record of the water pressure and temperature measured during the performance test in accordance with § 63.7323(b).

(4) For each capture system applied to pushing emissions, you have established an appropriate site-specific operating limit, and:

(i) If you elect the operating limit in § 63.7290(b)(3) for volumetric flow rate, you have a record of the total volumetric flow rate at the inlet of the control device measured during the performance test in accordance with § 63.7323(c)(1); or

(ii) If you elect the operating limit in § 63.7290(b)(3)(i) for fan motor amperes, you have a record of the fan motor amperes during the performance test in accordance with § 63.7323(c)(2); or

(iii) If you elect the operating limit in § 63.7290(b)(3)(ii) for static pressure or fan RPM, you have a record of the static pressure at the inlet of the control device or fan RPM measured during the performance test in accordance with § 63.7323(c)(3).

(5) For each multicyclone applied to pushing emissions, you have established an appropriate site-specific operating limit and have a record of the pressure drop measured during the performance test in accordance with § 63.7323(d).

(b) For each new or existing by-product coke oven battery subject to the opacity limit for stacks in § 63.7296(a), you have demonstrated initial compliance if the daily average opacity, as measured according to the performance test procedures in § 63.7324(b), is no more than 15 percent for a battery on a normal coking cycle or 20 percent for a battery on batterywide extended coking.

(c) For each new or existing by-product coke oven battery subject to the TDS limit or constituent limits for quench water in § 63.7295(a)(1),

(1) You have demonstrated initial compliance with the TDS limit in § 63.7295(a)(1)(i) if the TDS concentration, as measured according to the performance test procedures in § 63.7325(a), does not exceed 1,100 mg/L.

(2) You have demonstrated initial compliance with the constituent limit in § 63.7295(a)(1)(ii) if:

(i) You have established a site-specific constituent limit according to the procedures in § 63.7325(b); and

(ii) The sum of the constituent concentrations, as measured according to the performance test procedures in § 63.7325(c), is less than or equal to the site-specific limit.

(d) For each by-product coke oven battery stack subject to an opacity limit in § 63.7296(a) and each by-product coke oven battery subject to the requirements for quench water in § 63.7295(a)(1), you must submit a notification of compliance status containing the results of the COMS performance test for battery stacks and the quench water performance test (TDS or constituent limit) according to § 63.7340(e)(1). For each particulate matter emission limitation that applies to you, you must submit a notification of compliance status containing the results of the performance test according to § 63.7340(e)(2).

[68 FR 18025, Apr. 14, 2003, as amended at 69 FR 60819, Oct. 13, 2004]

§ 63.7327 How do I demonstrate initial compliance with the work practice standards that apply to me?

(a) For each by-product coke oven battery with vertical flues subject to the work practice standards for fugitive pushing emissions in § 63.7291(a), you have demonstrated initial compliance if you certify in your notification of compliance status that you will meet each of the work practice requirements beginning no later than the compliance date that is specified in § 63.7283.

(b) For each by-product coke oven battery with horizontal flues subject to the work practice standards for fugitive pushing emissions in § 63.7292(a), you have demonstrated initial compliance if you have met the requirements of paragraphs (b)(1) and (2) of this section:

(1) You have prepared and submitted a written plan and supporting documentation establishing appropriate minimum flue temperatures for different coking times and the lowest acceptable temperature to the Administrator (or delegated authority) for review and approval; and

(2) You certify in your notification of compliance status that you will meet each of the work practice requirements beginning no later than the compliance date that is specified in § 63.7283.

(c) For each non-recovery coke oven battery subject to the work practice standards for fugitive pushing emissions in § 63.7293(a), you have demonstrated initial compliance if you certify in your notification of compliance status that you will meet each of the work practice requirements beginning no later than the compliance date that is specified in § 63.7283.

(d) For each by-product coke oven battery subject to the work practice standards for soaking in § 63.7294, you have demonstrated initial compliance if you have met the requirements of paragraphs (d)(1) and (2) of this section:

(1) You have prepared and submitted a written work practice plan in accordance with § 63.7294(a); and

(2) You certify in your notification of compliance status that you will meet each of the work practice requirements beginning no later than the compliance date that is specified in § 63.7283.

(e) For each coke oven battery, you have demonstrated initial compliance with the work practice standards for quenching in § 63.7295(b) if you certify in your notification of compliance status that you have met the requirements of paragraphs (e)(1) and (2) of this section:

(1) You have installed the required equipment in each quench tower; and

(2) You will meet each of the work practice requirements beginning no later than the compliance date that is specified in § 63.7283.

(f) For each work practice standard that applies to you, you must submit a notification of compliance status according to the requirements in § 63.7340(e)(1).

§ 63.7328 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

You have demonstrated initial compliance if you certify in your notification of compliance status that you have met the requirements of paragraphs (a) through (d) of this section:

(a) You have prepared the operation and maintenance plans according to the requirements in § 63.7300(b) and (c);

(b) You will operate each by-product coke oven battery and each capture system and control device applied to pushing emissions from a coke oven battery according to the procedures in the plans beginning no later than the compliance date that is specified in § 63.7283;

(c) You have prepared a site-specific monitoring plan according to the requirements in § 63.7331(b); and

(d) You submit a notification of compliance status according to the requirements in § 63.7340(e).

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.7330 What are my monitoring requirements?

(a) For each baghouse applied to pushing emissions from a coke oven battery, you must at all times monitor the relative change in particulate matter loadings using a bag leak detection system according to the requirements in § 63.7331(a) and conduct inspections at their specified frequency according to the requirements in paragraphs (a)(1) through (8) of this section.

(1) Monitor the pressure drop across each baghouse cell each day to ensure pressure drop is within the normal operating range identified in the manual;

(2) Confirm that dust is being removed from hoppers through weekly visual inspections or equivalent means of ensuring the proper functioning of removal mechanisms;

(3) Check the compressed air supply for pulse-jet baghouses each day;

(4) Monitor cleaning cycles to ensure proper operation using an appropriate methodology;

(5) Check bag cleaning mechanisms for proper functioning through monthly visual inspection or equivalent means;

(6) Make monthly visual checks of bag tension on reverse air and shaker-type baghouses to ensure that bags are not kinked (kneed or bent) or laying on their sides. You do not have to make this check for shaker-type baghouses using self-tensioning (spring-loaded) devices;

(7) Confirm the physical integrity of the baghouse through quarterly visual inspections of the baghouse interior for air leaks; and

(8) Inspect fans for wear, material buildup, and corrosion through quarterly visual inspections, vibration detectors, or equivalent means.

(b) For each venturi scrubber applied to pushing emissions, you must at all times monitor the pressure drop and water flow rate using a CPMS according to the requirements in § 63.7331(e).

(c) For each hot water scrubber applied to pushing emissions, you must at all times monitor the water pressure and temperature using a CPMS according to the requirements in § 63.7331(f).

(d) For each capture system applied to pushing emissions, you must at all times monitor the volumetric flow rate according to the requirements in § 63.7331(g), the fan motor amperes according to the requirements in § 63.7331(h), or the static pressure or the fan RPM according to the requirements in § 63.7331(i).

(e) For each by-product coke oven battery, you must monitor at all times the opacity of emissions exiting each stack using a COMS according to the requirements in § 63.7331(j).

(f) For each multicyclone applied to pushing emissions, you must monitor at all times the pressure drop using a CPMS according to the requirements in § 63.7331(k).

[68 FR 18025, Apr. 14, 2003, as amended at 69 FR 60819, Oct. 13, 2004]

§ 63.7331 What are the installation, operation, and maintenance requirements for my monitors?

(a) For each baghouse applied to pushing emissions, you must install, operate, and maintain each bag leak detection system according to the requirements in paragraphs (a)(1) through (7) of this section.

(1) The system must be certified by the manufacturer to be capable of detecting emissions of particulate matter at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less;

(2) The system must provide output of relative changes in particulate matter loadings;

(3) The system must be equipped with an alarm that will sound when an increase in relative particulate loadings is detected over a preset level. The alarm must be located such that it can be heard by the appropriate plant personnel;

(4) Each system that works based on the triboelectric effect must be installed, operated, and maintained in a manner consistent with the guidance document, ''Fabric Filter Bag Leak Detection Guidance'' (EPA–454/R–98–015, September 1997). You may install, operate, and maintain other types of bag leak detection systems in a manner consistent with the manufacturer's written specifications and recommendations;

(5) To make the initial adjustment of the system, establish the baseline output by adjusting the sensitivity (range) and the averaging period of the device. Then, establish the alarm set points and the alarm delay time;

(6) Following the initial adjustment, do not adjust the sensitivity or range, averaging period, alarm set points, or alarm delay time, except as detailed in your operation and maintenance plan. Do not increase the sensitivity by more than 100 percent or decrease the sensitivity by more than 50 percent over a 365-day period unless a responsible official certifies, in writing, that the baghouse has been inspected and found to be in good operating condition; and

(7) Where multiple detectors are required, the system's instrumentation and alarm may be shared among detectors.

(b) For each CPMS required in § 63.7330, you must develop and make available for inspection upon request by the permitting authority a site-specific monitoring plan that addresses the requirements in paragraphs (b)(1) through (6) of this section.

(1) Installation of the CPMS sampling probe or other interface at a measurement location relative to each affected process unit such that the

measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last control device);

(2) Performance and equipment specifications for the sample interface, the parametric signal analyzer, and the data collection and reduction system;

(3) Performance evaluation procedures and acceptance criteria (*e.g.*, calibrations);

(4) Ongoing operation and maintenance procedures in accordance with the general requirements of §§ 63.8(c)(1), (3), (4)(ii), (7), and (8);

(5) Ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d); and

(6) Ongoing recordkeeping and reporting procedures in accordance the general requirements of §§ 63.10(c), (e)(1), and (e)(2)(i).

(c) You must conduct a performance evaluation of each CPMS in accordance with your site-specific monitoring plan.

(d) You must operate and maintain the CPMS in continuous operation according to the site-specific monitoring plan.

(e) For each venturi scrubber applied to pushing emissions, you must install, operate, and maintain CPMS to measure and record the pressure drop across the scrubber and scrubber water flow rate during each push according to the requirements in paragraphs (b) through (d) of this section except as specified in paragraphs (e)(1) through (3) of this section.

(1) Each CPMS must complete a measurement at least once per push;

(2) Each CPMS must produce valid data for all pushes; and

(3) Each CPMS must determine and record the daily (24-hour) average of all recorded readings.

(f) For each hot water scrubber applied to pushing emissions, you must install, operate, and maintain CPMS to measure and record the water pressure and temperature during each push according to the requirements in paragraphs (b) through (d) of this section, except as specified in paragraphs (e)(1) through (3) of this section.

(g) If you elect the operating limit in § 63.7290(b)(3) for a capture system applied to pushing emissions, you must install, operate, and maintain a device to measure the total volumetric flow rate at the inlet of the control device.

(h) If you elect the operating limit in § 63.7290(b)(3)(i) for a capture system applied to pushing emissions, you must install, operate, and maintain a device to measure the fan motor amperes.

(i) If you elect the operating limit in § 63.7290(b)(3)(ii) for a capture system applied to pushing emissions, you must install, operate and maintain a device to measure static pressure at the inlet of the control device or the fan RPM.

(j) For each by-product coke oven battery, you must install, operate, and maintain a COMS to measure and record the opacity of emissions exiting each stack according to the requirements in paragraphs (j)(1) through (5) of this section.

(1) You must install, operate, and maintain each COMS according to the requirements in § 63.8(e) and Performance Specification 1 in 40 CFR part 60, appendix B. Identify periods the COMS is out-of-control, including any periods that the COMS fails to pass a daily calibration drift assessment, quarterly performance audit, or annual zero alignment audit.

(2) You must conduct a performance evaluation of each COMS according to the requirements in § 63.8 and Performance Specification 1 in appendix B to 40 CFR part 60;

(3) You must develop and implement a quality control program for operating and maintaining each COMS according to the requirements in § 63.8(d). At minimum, the quality control program must include a daily calibration drift assessment, quarterly performance audit, and an annual zero alignment audit of each COMS;

(4) Each COMS must complete a minimum of one cycle of sampling and analyzing for each successive 10-second period and one cycle of data recording for each successive 6-minute period. You must reduce the COMS data as specified in § 63.8(g)(2).

(5) You must determine and record the hourly and daily (24-hour) average opacity according to the procedures in § 63.7324(b) using all the 6-minute averages collected for periods during which the COMS is not out-of-control.

(k) For each multicyclone applied to pushing emissions, you must install, operate, and maintain CPMS to measure and record the pressure drop across each multicyclone during each push according to the requirements in paragraphs (b) through (d) of this section except as specified in paragraphs (e)(1) through (3) of this section.

[68 FR 18025, Apr. 14, 2003, as amended at 69 FR 60819, Oct. 13, 2004]

§ 63.7332 How do I monitor and collect data to demonstrate continuous compliance?

(a) Except for monitor malfunctions, associated repairs, and required quality assurance or control activities (including as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times the affected source is operating.

(b) You may not use data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities in data averages and calculations used to report emission or operating levels, or in fulfilling a minimum data availability requirement, if applicable. You must use all the data collected during all other periods in assessing compliance. A monitoring malfunction is any sudden, infrequent, not reasonably preventable failure of the monitor to provide valid data. Monitoring failures that are caused in part by poor maintenance or careless operation are not malfunctions.

§ 63.7333 How do I demonstrate continuous compliance with the emission limitations that apply to me?

(a) For each control device applied to pushing emissions and subject to the emission limit in § 63.7290(a), you must demonstrate continuous compliance by meeting the requirements in paragraphs (a)(1) and (2) of this section:

(1) Maintaining emissions of particulate matter at or below the applicable limits in paragraphs § 63.7290(a)(1) through (4); and

(2) Conducting subsequent performance tests to demonstrate continuous compliance no less frequently than twice during each term of your title V operating permit (at mid-term and renewal).

(b) For each venturi scrubber applied to pushing emissions and subject to the operating limits in § 63.7290(b)(1), you must demonstrate continuous compliance by meeting the requirements in paragraphs (b)(1) through (3) of this section.

(1) Maintaining the daily average pressure drop and scrubber water flow rate at levels no lower than those established during the initial or subsequent performance test.

(2) Operating and maintaining each CPMS according to § 63.7331(b) and recording all information needed to document conformance with these requirements.

(3) Collecting and reducing monitoring data for pressure drop and scrubber water flow rate according to § 63.7331(e)(1) through (3).

(c) For each hot water scrubber applied to pushing emissions and subject to the operating limits in § 63.7290(b)(2), you must demonstrate continuous compliance by meeting the requirements in paragraphs (c)(1) through (3) of this section.

(1) Maintaining the daily average water pressure and temperature at levels no lower than those established during the initial or subsequent performance test.

(2) Operating and maintaining each CPMS according to § 63.7331(b) and recording all information needed to document conformance with these requirements.

(3) Collecting and reducing monitoring data for water pressure and temperature according to § 63.7331(f).

(d) For each capture system applied to pushing emissions and subject to the operating limit in § 63.7290(b)(3), you must demonstrate continuous compliance by meeting the requirements in paragraph (d)(1), (2), or (3) of this section:

(1) If you elect the operating limit for volumetric flow rate in § 63.7290(b)(3):

(i) Maintaining the daily average volumetric flow rate at the inlet of the control device at or above the minimum level established during the initial or subsequent performance test; and

(ii) Checking the volumetric flow rate at least every 8 hours to verify the daily average is at or above the minimum level established during the initial or subsequent performance test and recording the results of each check.

(2) If you elect the operating limit for fan motor amperes in § 63.7290(b)(3)(i):

(i) Maintaining the daily average fan motor amperages at or above the minimum level established during the initial or subsequent performance test; and

(ii) Checking the fan motor amperage at least every 8 hours to verify the daily average is at or above the minimum level established during the initial or subsequent performance test and recording the results of each check.

(3) If you elect the operating limit for static pressure or fan RPM in § 63.7290(b)(3)(ii):

(i) Maintaining the daily average static pressure at the inlet to the control device at an equal or greater vacuum than established during the initial or subsequent performance test or the daily average fan RPM at or above the minimum level established during the initial or subsequent performance test; and

(ii) Checking the static pressure or fan RPM at least every 8 hours to verify the daily average static pressure at the inlet to the control device is at an equal or greater vacuum than established during the initial or subsequent performance test or the daily average fan RPM is at or above the minimum level established during the initial or subsequent performance test and recording the results of each check.

(e) Beginning on the first day compliance is required under § 63.7283, you must demonstrate continuous compliance for each by-product coke oven battery subject to the opacity limit for stacks in § 63.7296(a) by meeting the requirements in paragraphs (e)(1) and (2) of this section:

(1) Maintaining the daily average opacity at or below 15 percent for a battery on a normal coking cycle or 20 percent for a battery on batterywide extended coking; and

(2) Operating and maintaining a COMS and collecting and reducing the COMS data according to § 63.7331(j).

(f) Beginning on the first day compliance is required under § 63.7283, you must demonstrate continuous compliance with the TDS limit for quenching in § 63.7295(a)(1)(i) by meeting the requirements in paragraphs (f)(1) and (2) of this section:

(1) Maintaining the TDS content of the water used to quench hot coke at 1,100 mg/L or less; and

(2) Determining the TDS content of the quench water at least weekly according to the requirements in § 63.7325(a) and recording the sample results.

(g) Beginning on the first day compliance is required under § 63.7283, you must demonstrate continuous compliance with the constituent limit for quenching in § 63.7295(a)(1)(ii) by meeting the requirements in paragraphs (g)(1) and (2) of this section:

(1) Maintaining the sum of the concentrations of benzene, benzo(a)pyrene, and naphthalene in the water used to quench hot coke at levels less than or equal to the site-specific limit approved by the permitting authority; and

(2) Determining the sum of the constituent concentrations at least monthly according to the requirements in § 63.7325(c) and recording the sample results.

(h) For each multicyclone applied to pushing emissions and subject to the operating limit in § 63.7290(b)(4), you must demonstrate compliance by meeting the requirements in paragraphs (h)(1) through (3) of this section.

(1) Maintaining the daily average pressure drop at a level at or below the level established during the initial or subsequent performance test.

(2) Operating and maintaining each CPMS according to § 63.7331(k) and recording all information needed to document conformance with these requirements.

(3) Collecting and reducing monitoring data for pressure drop according to § 63.7331(e)(1) through (3).

[68 FR 18025, Apr. 14, 2003, as amended at 69 FR 60819, Oct. 13, 2004]

§ 63.7334 How do I demonstrate continuous compliance with the work practice standards that apply to me?

(a) For each by-product coke oven battery with vertical flues subject to the work practice standards for fugitive pushing emissions in § 63.7291(a), you must demonstrate continuous compliance according to the requirements of paragraphs (a)(1) through (8) of this section:

(1) Observe and record the opacity of fugitive emissions for four consecutive pushes per operating day, except you may make fewer or non-consecutive observations as permitted by § 63.7291(a)(3). Maintain records of the pushing schedule for each oven and records indicating the legitimate operational reason for any change in the pushing schedule according to § 63.7291(a)(4).

(2) Observe and record the opacity of fugitive emissions from each oven in a battery at least once every 90 days. If an oven cannot be observed during a 90-day period, observe and record the opacity of the first push of that oven following the close of the 90-day period that can be read in accordance with the procedures in paragraphs (a)(1) through (8) of this section.

(3) Make all observations and calculations for opacity observations of fugitive pushing emissions in accordance with Method 9 in appendix A to 40 CFR part 60 using a Method 9 certified observer unless you have an approved alternative procedure under paragraph (a)(7) of this section.

(4) Record pushing opacity observations at 15-second intervals as required in section 2.4 of Method 9 (appendix A to 40 CFR part 60). The requirement in section 2.4 of Method 9 for a minimum of 24 observations does not apply, and the data reduction requirements in section 2.5 of Method 9 do not apply. The requirement in § 63.6(h)(5)(ii)(B) for obtaining at least 3 hours of observations (thirty 6-minute averages) to demonstrate initial compliance does not apply.

(5) If fewer than six but at least four 15-second observations can be made, use the average of the total number of observations to calculate average opacity for the push. Missing one or more observations during the push (*e.g.*, as the quench car passes behind a building) does not invalidate the observations before or after the interference for that push. However, a minimum of four 15-second readings must be made for a valid observation.

(6) Begin observations for a push at the first detectable movement of the coke mass. End observations of a push when the quench car enters the quench tower.

(i) For a battery without a cokeside shed, observe fugitive pushing emissions from a position at least 10 meters from the quench car that provides an unobstructed view and avoids interferences from the topside of the battery. This may require the observer to be positioned at an angle to the quench car rather than perpendicular to it. Typical interferences to avoid include emissions from open standpipes and charging. Observe the opacity of emissions above the battery top with the sky as the background where possible. Record the oven number of any push not observed because of obstructions or interferences.

(ii) For a battery with a cokeside shed, the observer must be in a position that provides an unobstructed view and avoids interferences from the topside of the battery. Typical interferences to avoid include emissions from open standpipes and charging. Observations must include any fugitive emissions that escape from the top of the shed, from the ends of the shed, or from the area where the shed is joined to the battery. If the observer does not have a clear view to identify when a push starts or ends, a second person can be positioned to signal the start or end of the push and notify the observer when to start or end the observations. Radio communications with other plant personnel (*e.g.*, pushing ram operator or quench car operator) may also serve to notify the observer of the start or end of a push. Record the oven number of any push not observed because of obstructions or interferences.

(iii) You may reposition after the push to observe emissions during travel if necessary.

(7) If it is infeasible to implement the procedures in paragraphs (a)(1) through (6) of this section for an oven due to

physical obstructions, nighttime pushes, or other reasons, you may apply to your permitting authority for permission to use an alternative procedure. The application must provide a detailed explanation of why it is infeasible to use the procedures in paragraphs (a)(1) through (6) of this section, identify the oven and battery numbers, and describe the alternative procedure. An alternative procedure must identify whether the coke in that oven is not completely coked, either before, during, or after an oven is pushed.

(8) For each oven observed that exceeds an opacity of 30 percent for any short battery or 35 percent for any tall battery, you must take corrective action and/or increase the coking time in accordance with §63.7291(a). Maintain records documenting conformance with the requirements in §63.7291(a).

(b) For each by-product coke oven battery with horizontal flues subject to the work practice standards for fugitive pushing emissions in §63.7292(a), you must demonstrate continuous compliance by having met the requirements of paragraphs (b)(1) through (3) of this section:

(1) Measuring and recording the temperature of all flues on two ovens per day within 2 hours before the oven's scheduled pushing time and ensuring that the temperature of each oven is measured and recorded at least once every month;

(2) Recording the time each oven is charged and pushed and calculating and recording the net coking time for each oven; and

(3) Increasing the coking time for each oven that falls below the minimum flue temperature trigger established for that oven's coking time in the written plan required in §63.7292(a)(1), assigning the oven to the oven-directed program, and recording all relevant information according to the requirements in §63.7292(a)(4) including, but not limited to, daily pushing schedules, diagnostic procedures, corrective actions, and oven repairs.

(c) For each non-recovery coke oven battery subject to the work practice standards in §63.7293(a), you must demonstrate continuous compliance by maintaining records that document each visual inspection of an oven prior to pushing and that the oven was not pushed unless there was no smoke in the open space above the coke bed and there was an unobstructed view of the door on the opposite side of the oven.

(d) For each by-product coke oven battery subject to the work practice standard for soaking in §63.7294(a), you must demonstrate continuous compliance by maintaining records that document conformance with requirements in §63.7294(a)(1) through (5).

(e) For each coke oven battery subject to the work practice standard for quenching in §63.7295(b), you must demonstrate continuous compliance according to the requirements of paragraphs (e)(1) through (3) of this section:

(1) Maintaining baffles in each quench tower such that no more than 5 percent of the cross-sectional area of the tower is uncovered or open to the sky as required in §63.7295(b)(1);

(2) Maintaining records that document conformance with the washing, inspection, and repair requirements in §63.7295(b)(2), including records of the ambient temperature on any day that the baffles were not washed; and

(3) Maintaining records of the source of makeup water to document conformance with the requirement for acceptable makeup water in §63.7295(a)(2).

§63.7335 How do I demonstrate continuous compliance with the operation and maintenance requirements that apply to me?

(a) For each by-product coke oven battery, you must demonstrate continuous compliance with the operation and maintenance requirements in §63.7300(b) by adhering at all times to the plan requirements and recording all information needed to document conformance.

(b) For each coke oven battery with a capture system or control device applied to pushing emissions, you must demonstrate continuous compliance with the operation and maintenance requirements in §63.7300(c) by meeting the requirements of paragraphs (b)(1) through (3) of this section:

(1) Making monthly inspections of capture systems according to §63.7300(c)(1) and recording all information needed to document conformance with these requirements;

(2) Performing preventative maintenance for each control device according to § 63.7300(c)(2) and recording all information needed to document conformance with these requirements; and

(3) Initiating and completing corrective action for a bag leak detection system alarm according to § 63.7300(c)(3) and recording all information needed to document conformance with these requirements. This includes records of the times the bag leak detection system alarm sounds, and for each valid alarm, the time you initiated corrective action, the corrective action(s) taken, and the date on which corrective action is completed.

(c) To demonstrate continuous compliance with the operation and maintenance requirements for a baghouse applied to pushing emissions from a coke oven battery in § 63.7331(a), you must inspect and maintain each baghouse according to the requirements in § 63.7331(a)(1) through (8) and record all information needed to document conformance with these requirements. If you increase or decrease the sensitivity of the bag leak detection system beyond the limits specified in § 63.7331(a)(6), you must include a copy of the required written certification by a responsible official in the next semiannual compliance report.

(d) You must maintain a current copy of the operation and maintenance plans required in § 63.7300(b) and (c) onsite and available for inspection upon request. You must keep the plans for the life of the affected source or until the affected source is no longer subject to the requirements of this subpart.

§ 63.7336 What other requirements must I meet to demonstrate continuous compliance?

(a) *Deviations.* You must report each instance in which you did not meet each emission limitation in this subpart that applies to you. This includes periods of startup, shutdown, and malfunction. You must also report each instance in which you did not meet each work practice standard or operation and maintenance requirement in this subpart that applies to you. These instances are deviations from the emission limitations (including operating limits), work practice standards, and operation and maintenance requirements in this subpart. These deviations must be reported according to the requirements in § 63.7341.

(b) *Startup, shutdowns, and malfunctions.* (1) Consistent with §§ 63.6(e) and 63.7(e)(1), deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with § 63.6(e)(1).

(2) The Administrator will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in § 63.6(e).

[68 FR 18025, Apr. 14, 2003, as amended at 71 FR 20467, Apr. 20, 2006]

NOTIFICATION, REPORTS, AND RECORDS

§ 63.7340 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.6(h)(4) and (5), 63.7(b) and (c), 63.8(e) and (f)(4), and 63.9(b) through (h) that apply to you by the specified dates.

(b) As specified in § 63.9(b)(2), if you startup your affected source before April 14, 2003, you must submit your initial notification no later than August 12, 2003, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) As specified in § 63.9(b)(3), if you startup your new affected source on or after April 14, 2003, you must submit your initial notification no later than 120 calendar days after you become subject to this subpart.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required in § 63.7(b)(1).

(e) If you are required to conduct a performance test, opacity observation, or other initial compliance demonstration, you must submit a notification of compliance status according to § 63.9(h)(2)(ii).

(1) For each initial compliance demonstration that does not include a performance test, you must submit the notification of compliance status before the close of business on the 30th

calendar day following the completion of the initial compliance demonstration.

(2) For each initial compliance demonstration that does include a performance test, you must submit the notification of compliance status, including the performance test results, before the close of business on the 60th calendar day following completion of the performance test according to § 63.10(d)(2).

(f) For each by-product coke oven battery with horizontal flues, you must notify the Administrator (or delegated authority) of the date on which the study of flue temperatures required by § 63.7292(a)(3) will be initiated. You must submit this notification no later than 7 days prior to the date you initiate the study.

[68 FR 18025, Apr. 14, 2003, as amended at 85 FR 73913, Nov. 19, 2020]

§ 63.7341 What reports must I submit and when?

(a) *Compliance report due dates.* Unless the Administrator has approved a different schedule, you must submit quarterly compliance reports for battery stacks and semiannual compliance reports for all other affected sources to your permitting authority according to the requirements in paragraphs (a)(1) through (4) of this section.

(1) The first quarterly compliance report for battery stacks must cover the period beginning on the compliance date that is specified for your affected source in § 63.7283 and ending on the last date of the third calendar month. Each subsequent compliance report must cover the next calendar quarter.

(2) The first semiannual compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.7283 and ending on June 30 or December 31, whichever date comes first after the compliance date that is specified for your affected source. Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(3) All quarterly compliance reports for battery stacks must be postmarked or delivered no later than one calendar month following the end of the quarterly reporting period. All semiannual compliance reports must be postmarked or delivered no later than July 31 or January 31, whichever date is the first date following the end of the semiannual reporting period.

(4) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of according to the dates in paragraphs (a)(1) through (3) of this section.

(b) *Quarterly compliance report contents.* Each quarterly report must provide information on compliance with the emission limitations for battery stacks in § 63.7296. The reports must include the information in paragraphs (c)(1) through (3), and as applicable, paragraphs (c)(4) through (8) of this section.

(c) *Semiannual compliance report contents.* Each compliance report must provide information on compliance with the emission limitations, work practice standards, and operation and maintenance requirements for all affected sources except battery stacks. The reports must include the information in paragraphs (c)(1) through (3) of this section, and as applicable, paragraphs (c)(4) through (8) of this section.

(1) Company name and address.

(2) Statement by a responsible official, with the official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) If you had a startup, shutdown, or malfunction during the reporting period and you took actions consistent with your startup, shutdown, and malfunction plan, the compliance report must include the information in § 63.10(d)(5)(i).

(5) If there were no deviations from the continuous compliance requirements in § 63.7333(e) for battery stacks, a statement that there were no deviations from the emission limitations

during the reporting period. If there were no deviations from the continuous compliance requirements in §§ 63.7333 through 63.7335 that apply to you (for all affected sources other than battery stacks), a statement that there were no deviations from the emission limitations, work practice standards, or operation and maintenance requirements during the reporting period.

(6) If there were no periods during which a continuous monitoring system (including COMS, continuous emission monitoring system (CEMS), or CPMS) was out-of-control as specified in § 63.8(c)(7), a statement that there were no periods during which a continuous monitoring system was out-of-control during the reporting period.

(7) For each deviation from an emission limitation in this subpart (including quench water limits) and for each deviation from the requirements for work practice standards in this subpart that occurs at an affected source where you are not using a continuous monitoring system (including a COMS, CEMS, or CPMS) to comply with the emission limitations in this subpart, the compliance report must contain the information in paragraphs (c)(4) and (7)(i) and (ii) of this section. This includes periods of startup, shutdown, and malfunction.

(i) The total operating time of each affected source during the reporting period.

(ii) Information on the number, duration, and cause of deviations (including unknown cause, if applicable) as applicable and the corrective action taken.

(8) For each deviation from an emission limitation occurring at an affected source where you are using a continuous monitoring system (including COMS, CEMS, or CPMS) to comply with the emission limitation in this subpart, you must include the information in paragraphs (c)(4) and (8)(i) through (xii) of this section. This includes periods of startup, shutdown, and malfunction.

(i) The date and time that each malfunction started and stopped.

(ii) The date and time that each continuous monitoring system (including COMS, CEMS, or CPMS) was inoperative, except for zero (low-level) and high-level checks.

(iii) The date, time, and duration that each continuous monitoring system (including COMS, CEMS, or CPMS) was out-of-control, including the information in § 63.8(c)(8).

(iv) The date and time that each deviation started and stopped, and whether each deviation occurred during a period of startup, shutdown, or malfunction or during another period.

(v) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.

(vi) A breakdown of the total duration of the deviations during the reporting period into those that are due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes.

(vii) A summary of the total duration of continuous monitoring system downtime during the reporting period and the total duration of continuous monitoring system downtime as a percent of the total source operating time during the reporting period.

(viii) An identification of each HAP that was monitored at the affected source.

(ix) A brief description of the process units.

(x) A brief description of the continuous monitoring system.

(xi) The date of the latest continuous monitoring system certification or audit.

(xii) A description of any changes in continuous monitoring systems, processes, or controls since the last reporting period.

(d) *Immediate startup, shutdown, and malfunction report.* If you had a startup, shutdown, or malfunction during the semiannual reporting period that was not consistent with your startup, shutdown, and malfunction plan, you must submit an immediate startup, shutdown, and malfunction report according to the requirements in § 63.10(d)(5)(ii).

(e) *Part 70 monitoring report.* If you have obtained a title V operating permit for an affected source pursuant to 40 CFR part 70 or 40 CFR part 71, you must report all deviations as defined in

this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If you submit a compliance report for an affected source along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all the required information concerning deviations from any emission limitation or work practice standard in this subpart, submission of the compliance report satisfies any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report does not otherwise affect any obligation you may have to report deviations from permit requirements to your permitting authority.

§ 63.7342 What records must I keep?

(a) You must keep the records specified in paragraphs (a)(1) through (3) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any initial notification or notification of compliance status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) The records in § 63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunction.

(3) Records of performance tests, performance evaluations, and opacity observations as required in § 63.10(b)(2)(viii).

(b) For each COMS or CEMS, you must keep the records specified in paragraphs (b)(1) through (4) of this section.

(1) Records described in § 63.10(b)(2)(vi) through (xi).

(2) Monitoring data for COMS during a performance evaluation as required in § 63.6(h)(7)(i) and (ii).

(3) Previous (that is, superceded) versions of the performance evaluation plan as required in § 63.8(d)(3).

(4) Records of the date and time that each deviation started and stopped, and whether the deviation occurred during a period of startup, shutdown, or malfunction or during another period.

(c) You must keep the records in § 63.6(h)(6) for visual observations.

(d) You must keep the records required in §§ 63.7333 through 63.7335 to show continuous compliance with each emission limitation, work practice standard, and operation and maintenance requirement that applies to you.

§ 63.7343 In what form and how long must I keep my records?

(a) You must keep your records in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You can keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.7350 What parts of the General Provisions apply to me?

Table 1 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.15 apply to you.

§ 63.7351 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the United States Environmental Protection Agency (U.S. EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities in paragraphs (c)(1) through (6) of this section will not be delegated to State, local, or tribal agencies.

(1) Approval of alternatives to work practice standards for fugitive pushing emissions in § 63.7291(a) for a by-product coke oven battery with vertical flues, fugitive pushing emissions in § 63.7292(a) for a by-product coke oven battery with horizontal flues, fugitive pushing emissions in § 63.7293 for a non-recovery coke oven battery, soaking for a by-product coke oven battery in § 63.7294(a), and quenching for a coke oven battery in § 63.7295(b) under § 63.6(g).

(2) Approval of alternative opacity emission limitations for a by-product coke oven battery under § 63.6(h)(9).

(3) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90, except for alternative procedures in § 63.7334(a)(7).

(4) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(5) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(6) Approval of the work practice plan for by-product coke oven batteries with horizontal flues submitted under § 63.7292(a)(1).

§ 63.7352 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act (CAA), in § 63.2, and in this section as follows:

Acceptable makeup water means surface water from a river, lake, or stream; water meeting drinking water standards; storm water runoff and production area clean up water except for water from the by-product recovery plant area; process wastewater treated to meet effluent limitations guidelines in 40 CFR part 420; water from any of these sources that has been used only for non-contact cooling or in water seals; or water from scrubbers used to control pushing emissions.

Backup quench station means a quenching device that is used for less than 5 percent of the quenches from any single coke oven battery in the 12-month period from July 1 to June 30.

Baffles means an apparatus comprised of obstructions for checking or deflecting the flow of gases. Baffles are installed in a quench tower to remove droplets of water and particles from the rising vapors by providing a point of impact. Baffles may be installed either inside or on top of quench towers and are typically constructed of treated wood, steel, or plastic.

Battery stack means the stack that is the point of discharge to the atmosphere of the combustion gases from a battery's underfiring system.

Batterywide extended coking means increasing the average coking time for all ovens in the coke oven battery by 25 percent or more over the manufacturer's specified design rate.

By-product coke oven battery means a group of ovens connected by common walls, where coal undergoes destructive distillation under positive pressure to produce coke and coke oven gas from which by-products are recovered.

By-product recovery plant area means that area of the coke plant where process units subject to subpart L in part 61 are located.

Coke oven battery means a group of ovens connected by common walls, where coal undergoes destructive distillation to produce coke. A coke oven battery includes by-product and non-recovery processes.

Coke plant means a facility that produces coke from coal in either a by-product coke oven battery or a non-recovery coke oven battery.

Cokeside shed means a structure used to capture pushing emissions that encloses the cokeside of the battery and ventilates the emissions to a control device.

Coking time means the time interval that starts when an oven is charged with coal and ends when the oven is pushed.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limitation (including operating limits) or work practice standard;

(2) Fails to meet any term or condition that is adopted to implement an

applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Fails to meet any emission limitation or work practice standard in this subpart during startup, shutdown, or malfunction, regardless of whether or not such failure is permitted by this subpart.

Emission limitation means any emission limit, opacity limit, or operating limit.

Four consecutive pushes means four pushes observed successively.

Fugitive pushing emissions means emissions from pushing that are not collected by a capture system.

Horizontal flue means a type of coke oven heating system used on Semet-Solvay batteries where the heating flues run horizontally from one end of the oven to the other end, and the flues are not shared with adjacent ovens.

Hot water scrubber means a mobile scrubber used to control pushing emissions through the creation of an induced draft formed by the expansion of pressurized hot water through a nozzle.

Increased coking time means increasing the charge-to-push time for an individual oven.

Non-recovery coke oven battery means a group of ovens connected by common walls and operated as a unit, where coal undergoes destructive distillation under negative pressure to produce coke, and which is designed for the combustion of the coke oven gas from which by-products are not recovered.

Oven means a chamber in the coke oven battery in which coal undergoes destructive distillation to produce coke.

Pushing means the process of removing the coke from the oven. Pushing begins with the first detectable movement of the coke mass and ends when the quench car enters the quench tower.

Quenching means the wet process of cooling (wet quenching) the hot incandescent coke by direct contact with water that begins when the quench car enters the quench tower and ends when the quench car exits the quench tower.

Quench tower means the structure in which hot incandescent coke in the quench car is deluged or quenched with water.

Remove from service means that an oven is not charged with coal and is not used for coking. When removed from service, the oven may remain at the operating temperature or it may be cooled down for repairs.

Responsible official means responsible official as defined in §63.2.

Short battery means a by-product coke oven battery with ovens less than five meters in height.

Soaking means that period in the coking cycle that starts when an oven is dampered off the collecting main and vented to the atmosphere through an open standpipe prior to pushing and ends when the coke begins to be pushed from the oven.

Soaking emissions means the discharge from an open standpipe during soaking of visible emissions due to either incomplete coking or leakage into the standpipe from the collecting main.

Standpipe means an apparatus on the oven that provides a passage for gases from an oven to the atmosphere when the oven is dampered off the collecting main and the standpipe cap is opened. This includes mini-standpipes that are not connected to the collecting main.

Tall battery means a by-product coke oven battery with ovens five meters or more in height.

Vertical flue means a type of coke oven heating system in which the heating flues run vertically from the bottom to the top of the oven, and flues are shared between adjacent ovens.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the CAA.

TABLE 1 TO SUBPART CCCCC OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART CCCCC

As required in §63.7350, you must comply with each applicable requirement of the NESHAP General Provisions (40 CFR part 63, subpart A) as shown in the following table:

Citation	Subject	Applies to Subpart CCCCC?	Explanation
§ 63.1	Applicability	Yes.	
§ 63.2	Definitions	Yes.	
§ 63.3	Units and Abbreviations	Yes.	
§ 63.4	Prohibited Activities	Yes.	
§ 63.5	Construction/Reconstruction	Yes.	
§ 63.6(a), (b), (c), (d), (e), (f), (g), (h)(2)–(8).	Compliance with Standards and Maintenance Requirements.	Yes.	
§ 63.6(h)(9)	Adjustment to an Opacity Emission Standard.	Yes.	
§ 63.7(a)(3), (b), (c)–(h)	Performance Testing Requirements	Yes.	
§ 63.7(a)(1)–(2)	Applicability and Performance Test Dates.	No	Subpart CCCCC specifies applicability and dates.
§ 63.8(a)(1)–(3), (b), (c)(1)–(3), (c)(4)(i)–(ii), (c)(5)–(8), (d), (e), (f)(1)–(5), (g)(1)–(4).	Monitoring Requirements	Yes	CMS requirements in § 63.8(c)(4)(i)–(ii), (c)(5), and (c)(6) apply only to COMS for battery stacks.
§ 63.8(a)(4)	Additional Monitoring Requirements for Control Devices in § 63.11.	No	Flares are not a control device for Subpart CCCCC affected sources.
§ 63.8(c)(4)	Continuous Monitoring System (CMS) Requirements.	No	Subpart CCCCC specifies requirements for operation of CMS.
§ 63.8(e)(4)–(5)	Performance Evaluations	Yes	Except COMS performance evaluation must be conducted before the compliance date.
§ 63.8(f)(6)	RATA Alternative	No	Subpart CCCCC does not require CEMS.
§ 63.8(g)(5)	Data Reduction	No	Subpart CCCCC specifies data that can't be used in computing averages for COMS.
§ 63.9	Notification Requirements	Yes	Additional notifications for CMS in § 63.9(g) apply only to COMS for battery stacks.
§ 63.10(a), (b)(1)–(b)(2)(xii), (b)(2)(xiv), (b)(3), (c)(1)–(6), (c)(9)–(15), (d), (e)(1)–(2), (e)(4), (f).	Recordkeeping and Reporting Requirements.	Yes.	Additional records for CMS in § 63.10(c)(1)–(6), (9)–(15), and reports in § 63.10(d)(1)–(2) apply only to COMS for battery stacks.
§ 63.10(b)(2) (xi)–(xii)	CMS Records for RATA Alternative	No	Subpart CCCCC doesn't require CEMS.
§ 63.10(c)(7)–(8)	Records of Excess Emissions and Parameter Monitoring Exceedances for CMS.	No	Subpart CCCCC specifies record requirements.
§ 63.10(e)(3)	Excess Emission Reports	No	Subpart CCCCC specifies reporting requirements.
§ 63.11	Control Device Requirements	No	Subpart CCCCC does not require flares.
§ 63.12	State Authority and Delegations.	Yes.	
§§ 63.13–63.15	Addresses, Incorporation by Reference, Availability of Information.	Yes.	

Subpart DDDDD—National Emission Standards for Hazardous Air Pollutants for Major Sources: Industrial, Commercial, and Institutional Boilers and Process Heaters

SOURCE: 76 FR 15664, Mar. 21, 2011, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7480 What is the purpose of this subpart?

This subpart establishes national emission limitations and work practice standards for hazardous air pollutants (HAP) emitted from industrial, commercial, and institutional boilers and process heaters located at major sources of HAP. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations and work practice standards.

§ 63.7485 Am I subject to this subpart?

You are subject to this subpart if you own or operate an industrial, commercial, or institutional boiler or process heater as defined in § 63.7575 that is located at, or is part of, a major source of HAP, except as specified in § 63.7491. For purposes of this subpart, a major source of HAP is as defined in § 63.2, except that for oil and natural gas production facilities, a major source of HAP is as defined in § 63.7575.

[78 FR 7162, Jan. 31, 2013]

§ 63.7490 What is the affected source of this subpart?

(a) This subpart applies to new, reconstructed, and existing affected sources as described in paragraphs (a)(1) and (2) of this section.

(1) The affected source of this subpart is the collection at a major source of all existing industrial, commercial, and institutional boilers and process heaters within a subcategory as defined in § 63.7575.

(2) The affected source of this subpart is each new or reconstructed industrial, commercial, or institutional boiler or process heater, as defined in § 63.7575, located at a major source.

(b) A boiler or process heater is new if you commence construction of the boiler or process heater after June 4, 2010, and you meet the applicability criteria at the time you commence construction.

(c) A boiler or process heater is reconstructed if you meet the reconstruction criteria as defined in § 63.2, you commence reconstruction after June 4, 2010, and you meet the applicability criteria at the time you commence reconstruction.

(d) A boiler or process heater is existing if it is not new or reconstructed.

(e) An existing electric utility steam generating unit (EGU) that meets the applicability requirements of this subpart after the effective date of this final rule due to a change (e.g., fuel switch) is considered to be an existing source under this subpart.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7162, Jan. 31, 2013]

§ 63.7491 Are any boilers or process heaters not subject to this subpart?

The types of boilers and process heaters listed in paragraphs (a) through (n) of this section are not subject to this subpart.

(a) An electric utility steam generating unit (EGU) covered by subpart UUUUU of this part or a natural gas-fired EGU as defined in subpart UUUUU of this part firing at least 85 percent natural gas on an annual heat input basis.

(b) A recovery boiler or furnace covered by subpart MM of this part.

(c) A boiler or process heater that is used specifically for research and development, including test steam boilers used to provide steam for testing the propulsion systems on military vessels. This does not include units that provide heat or steam to a process at a research and development facility.

(d) A hot water heater as defined in this subpart.

(e) A refining kettle covered by subpart X of this part.

(f) An ethylene cracking furnace covered by subpart YY of this part.

(g) Blast furnace stoves as described in EPA–453/R–01–005 (incorporated by reference, see § 63.14).

(h) Any boiler or process heater that is part of the affected source subject to another subpart of this part, such as boilers and process heaters used as control devices to comply with subparts JJJ, OOO, PPP, and U of this part.

(i) Any boiler or process heater that is used as a control device to comply with another subpart of this part, or part 60, part 61, or part 65 of this chapter provided that at least 50 percent of the average annual heat input during any 3 consecutive calendar years to the boiler or process heater is provided by regulated gas streams that are subject to another standard.

(j) Temporary boilers and process heaters as defined in this subpart.

(k) Blast furnace gas fuel-fired boilers and process heaters as defined in this subpart.

(l) Any boiler or process heater specifically listed as an affected source in any standard(s) established under section 129 of the Clean Air Act.

(m) A unit that burns hazardous waste covered by Subpart EEE of this

part. A unit that is exempt from Subpart EEE as specified in § 63.1200(b) is not covered by Subpart EEE.

(n) Residential boilers as defined in this subpart.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7162, Jan. 31, 2013; 80 FR 72806, Nov. 20, 2015]

§ 63.7495 When do I have to comply with this subpart?

(a) If you have a new or reconstructed boiler or process heater, you must comply with this subpart by April 1, 2013, or upon startup of your boiler or process heater, whichever is later.

(b) If you have an existing boiler or process heater, you must comply with this subpart no later than January 31, 2016, except as provided in § 63.6(i).

(c) If you have an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP, paragraphs (c)(1) and (2) of this section apply to you.

(1) Any new or reconstructed boiler or process heater at the existing source must be in compliance with this subpart upon startup.

(2) Any existing boiler or process heater at the existing source must be in compliance with this subpart within 3 years after the source becomes a major source.

(d) You must meet the notification requirements in § 63.7545 according to the schedule in § 63.7545 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission limits and work practice standards in this subpart.

(e) If you own or operate an industrial, commercial, or institutional boiler or process heater and would be subject to this subpart except for the exemption in § 63.7491(l) for commercial and industrial solid waste incineration units covered by part 60, subpart CCCC or subpart DDDD, and you cease combusting solid waste, you must be in compliance with this subpart and are no longer subject to part 60, subparts CCCC or DDDD beginning on the effective date of the switch as identified under the provisions of § 60.2145(a)(2) and (3) or § 60.2710(a)(2) and (3).

(f) If you own or operate an existing EGU that becomes subject to this subpart after January 31, 2016, you must be in compliance with the applicable existing source provisions of this subpart on the effective date such unit becomes subject to this subpart.

(g) If you own or operate an existing industrial, commercial, or institutional boiler or process heater and would be subject to this subpart except for a exemption in § 63.7491(i) that becomes subject to this subpart after January 31, 2013, you must be in compliance with the applicable existing source provisions of this subpart within 3 years after such unit becomes subject to this subpart.

(h) If you own or operate an existing industrial, commercial, or institutional boiler or process heater and have switched fuels or made a physical change to the boiler or process heater that resulted in the applicability of a different subcategory after the compliance date of this subpart, you must be in compliance with the applicable existing source provisions of this subpart on the effective date of the fuel switch or physical change.

(i) If you own or operate a new industrial, commercial, or institutional boiler or process heater and have switched fuels or made a physical change to the boiler or process heater that resulted in the applicability of a different subcategory, you must be in compliance with the applicable new source provisions of this subpart on the effective date of the fuel switch or physical change.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7162, Jan. 31, 2013; 80 FR 72807, Nov. 20, 2015]

Emission Limitations and Work Practice Standards

§ 63.7499 What are the subcategories of boilers and process heaters?

The subcategories of boilers and process heaters, as defined in § 63.7575 are:

(a) Pulverized coal/solid fossil fuel units.

(b) Stokers designed to burn coal/solid fossil fuel.

(c) Fluidized bed units designed to burn coal/solid fossil fuel.

(d) Stokers/sloped grate/other units designed to burn kiln dried biomass/bio-based solid.

(e) Fluidized bed units designed to burn biomass/bio-based solid.

(f) Suspension burners designed to burn biomass/bio-based solid.

(g) Fuel cells designed to burn biomass/bio-based solid.

(h) Hybrid suspension/grate burners designed to burn wet biomass/bio-based solid.

(i) Stokers/sloped grate/other units designed to burn wet biomass/bio-based solid.

(j) Dutch ovens/pile burners designed to burn biomass/bio-based solid.

(k) Units designed to burn liquid fuel that are non-continental units.

(l) Units designed to burn gas 1 fuels.

(m) Units designed to burn gas 2 (other) gases.

(n) Metal process furnaces.

(o) Limited-use boilers and process heaters.

(p) Units designed to burn solid fuel.

(q) Units designed to burn liquid fuel.

(r) Units designed to burn coal/solid fossil fuel.

(s) Fluidized bed units with an integrated fluidized bed heat exchanger designed to burn coal/solid fossil fuel.

(t) Units designed to burn heavy liquid fuel.

(u) Units designed to burn light liquid fuel.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7163, Jan. 31, 2013]

§ 63.7500 What emission limitations, work practice standards, and operating limits must I meet?

(a) You must meet the requirements in paragraphs (a)(1) through (3) of this section, except as provided in paragraphs (b) through (e) of this section. You must meet these requirements at all times the affected unit is operating, except as provided in paragraph (f) of this section.

(1) You must meet each emission limit and work practice standard in Tables 1 through 3 and 11 through 15 to this subpart that applies to your boiler or process heater, for each boiler or process heater at your source, except as provided under § 63.7522. The output-based emission limits, in units of pounds per million Btu of steam output, in Table 1 or 2 to this subpart are an alternative applicable only to boilers and process heaters that generate either steam, cogenerate steam with electricity, or both. The output-based emission limits, in units of pounds per megawatt-hour, in Table 1 or 2 to this subpart are an alternative applicable only to boilers that generate only electricity. Boilers that perform multiple functions (cogeneration and electricity generation) or supply steam to common headers would calculate a total steam energy output using Equation 1 of § 63.7575 to demonstrate compliance with the output-based emission limits, in units of pounds per million Btu of steam output, in Table 1 or 2 to this subpart. If you operate a new boiler or process heater, you can choose to comply with alternative limits as discussed in paragraphs (a)(1)(i) through (iv) of this section, but on or after October 6, 2025, you must comply with the emission limits in Table 1 to this subpart. If you operate an existing boiler or process heater, you can choose to comply with alternative limits as discussed in paragraph (a)(1)(v) of this section, but on or after October 6, 2025 you must comply with the emission limits in Table 2 to this subpart.

(i) If your boiler or process heater commenced construction or reconstruction after June 4, 2010, and before May 20, 2011, you may comply with the emission limits in Table 11 or 14 to this subpart until January 31, 2016.

(ii) If your boiler or process heater commenced construction or reconstruction on or after May 20, 2011, and before December 23, 2011, you may comply with the emission limits in Table 12 or 14 to this subpart until January 31, 2016.

(iii) If your boiler or process heater commenced construction or reconstruction on or after December 23, 2011, and before April 1, 2013, you may comply with the emission limits in Table 13 or 14 to this subpart until January 31, 2016.

(iv) If you operate a new boiler or process heater, you must comply with either the emission limits in Table 1 to this subpart or the emission limits in Table 14 to this subpart until you must comply with the emission limits in Table 1.

(v) If you operate an existing boiler or process heater, you must comply with either the emission limits in Table 2 to this subpart or the emission limits in Table 15 to this subpart until you must comply with the emission limits in Table 2.

(2) You must meet each operating limit in Table 4 to this subpart that applies to your boiler or process heater. If you use a control device or combination of control devices not covered in Table 4 to this subpart, or you wish to establish and monitor an alternative operating limit or an alternative monitoring parameter, you must apply to the EPA Administrator for approval of alternative monitoring under § 63.8(f).

(3) At all times, you must operate and maintain any affected source (as defined in § 63.7490), including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. Determination of whether such operation and maintenance procedures are being used will be based on information available to the Administrator that may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

(b) As provided in § 63.6(g), EPA may approve use of an alternative to the work practice standards in this section.

(c) Limited-use boilers and process heaters must complete a tune-up every 5 years as specified in § 63.7540. They are not subject to the emission limits in Tables 1 and 2 or Tables 11 through 15 to this subpart, the annual tune-up, or the energy assessment requirements in Table 3 to this subpart, or the operating limits in Table 4 to this subpart.

(d) Boilers and process heaters with a heat input capacity of less than or equal to 5 million Btu per hour in the units designed to burn gas 2 (other) fuels subcategory or units designed to burn light liquid fuels subcategory must complete a tune-up every 5 years as specified in § 63.7540.

(e) Boilers and process heaters in the units designed to burn gas 1 fuels subcategory with a heat input capacity of less than or equal to 5 million Btu per hour must complete a tune-up every 5 years as specified in § 63.7540. Boilers and process heaters in the units designed to burn gas 1 fuels subcategory with a heat input capacity greater than 5 million Btu per hour and less than 10 million Btu per hour must complete a tune-up every 2 years as specified in § 63.7540. Boilers and process heaters in the units designed to burn gas 1 fuels subcategory are not subject to the emission limits in Tables 1 and 2 or Tables 11 through 15 to this subpart, or the operating limits in Table 4 to this subpart.

(f) These standards apply at all times the affected unit is operating, except during periods of startup and shutdown during which time you must comply only with items 5 and 6 of Table 3 to this subpart.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7163, Jan. 31, 2013; 80 FR 72807, Nov. 20, 2015; 87 FR 60840, Oct. 6, 2022]

§ 63.7501 [Reserved]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7505 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the emission limits, work practice standards, and operating limits in this subpart. These emission and operating limits apply to you at all times the affected unit is operating except for the periods noted in § 63.7500(f).

(b) [Reserved]

(c) You must demonstrate compliance with all applicable emission limits using performance stack testing, fuel analysis, or continuous monitoring systems (CMS), including a continuous emission monitoring system (CEMS), continuous opacity monitoring system (COMS), continuous parameter monitoring system (CPMS), or particulate matter continuous parameter monitoring system (PM CPMS), where applicable. You may demonstrate compliance with the applicable emission limit for hydrogen chloride (HCl), mercury, or total selected metals (TSM) using fuel analysis if the emission rate calculated according to § 63.7530(c) is less than the applicable emission limit. For gaseous fuels, you may not use fuel

analyses to comply with the TSM alternative standard or the HCl standard. Otherwise, you must demonstrate compliance for HCl, mercury, or TSM using performance stack testing, if subject to an applicable emission limit listed in Table 1 or 2 or Tables 11 through 15 to this subpart.

(d) If you demonstrate compliance with any applicable emission limit through performance testing and subsequent compliance with operating limits through the use of CPMS, or with a CEMS or COMS, you must develop a site-specific monitoring plan according to the requirements in paragraphs (d)(1) through (4) of this section for the use of any CEMS, COMS, or CPMS. This requirement also applies to you if you petition the EPA Administrator for alternative monitoring parameters under § 63.8(f).

(1) For each CMS required in this section (including CEMS, COMS, or CPMS), you must develop, and submit to the Administrator for approval upon request, a site-specific monitoring plan that addresses design, data collection, and the quality assurance and quality control elements outlined in § 63.8(d) and the elements described in paragraphs (d)(1)(i) through (iii) of this section. You must submit this site-specific monitoring plan, if requested, at least 60 days before your initial performance evaluation of your CMS. This requirement to develop and submit a site specific monitoring plan does not apply to affected sources with existing CEMS or COMS operated according to the performance specifications under appendix B to part 60 of this chapter and that meet the requirements of § 63.7525. Using the process described in § 63.8(f)(4), you may request approval of alternative monitoring system quality assurance and quality control procedures in place of those specified in this paragraph and, if approved, include the alternatives in your site-specific monitoring plan.

(i) Installation of the CMS sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (e.g., on or downstream of the last control device);

(ii) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction systems; and

(iii) Performance evaluation procedures and acceptance criteria (e.g., calibrations, accuracy audits, analytical drift).

(2) In your site-specific monitoring plan, you must also address paragraphs (d)(2)(i) through (iii) of this section.

(i) Ongoing operation and maintenance procedures in accordance with the general requirements of § 63.8(c)(1)(ii), (c)(3), and (c)(4)(ii);

(ii) Ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d); and

(iii) Ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c) (as applicable in Table 10 to this subpart), (e)(1), and (e)(2)(i).

(3) You must conduct a performance evaluation of each CMS in accordance with your site-specific monitoring plan.

(4) You must operate and maintain the CMS in continuous operation according to the site-specific monitoring plan.

(e) If you have an applicable emission limit, and you choose to comply using definition (2) of ''startup'' in § 63.7575, you must develop and implement a written startup and shutdown plan (SSP) according to the requirements in Table 3 to this subpart. The SSP must be maintained onsite and available upon request for public inspection.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7164, Jan. 31, 2013; 80 FR 72807, Nov. 20, 2015; 87 FR 60841, Oct. 6, 2022]

TESTING, FUEL ANALYSES, AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.7510 What are my initial compliance requirements and by what date must I conduct them?

(a) For each boiler or process heater that is required or that you elect to demonstrate compliance with any of the applicable emission limits in Table 1 or 2 or Tables 11 through 15 to this subpart through performance (stack) testing, your initial compliance requirements include all the following:

(1) Conduct performance tests according to § 63.7520 and Table 5 to this subpart.

(2) Conduct a fuel analysis for each type of fuel burned in your boiler or process heater according to § 63.7521 and Table 6 to this subpart, except as specified in paragraphs (a)(2)(i) through (iii) of this section.

(i) For each boiler or process heater that burns a single type of fuel, you are not required to conduct a fuel analysis for each type of fuel burned in your boiler or process heater according to § 63.7521 and Table 6 to this subpart. For purposes of this subpart, units that use a supplemental fuel only for start-up, unit shutdown, and transient flame stability purposes still qualify as units that burn a single type of fuel, and the supplemental fuel is not subject to the fuel analysis requirements under § 63.7521 and Table 6 to this subpart.

(ii) When natural gas, refinery gas, or other gas 1 fuels are co-fired with other fuels, you are not required to conduct a fuel analysis of those Gas 1 fuels according to § 63.7521 and Table 6 to this subpart. If gaseous fuels other than natural gas, refinery gas, or other gas 1 fuels are co-fired with other fuels and those non-Gas 1 gaseous fuels are subject to another subpart of this part, part 60, part 61, or part 65, you are not required to conduct a fuel analysis of those non-Gas 1 fuels according to § 63.7521 and Table 6 to this subpart.

(iii) You are not required to conduct a chlorine fuel analysis for any gaseous fuels. You must conduct a fuel analysis for mercury on gaseous fuels unless the fuel is exempted in paragraphs (a)(2)(i) and (ii) of this section.

(3) Establish operating limits according to § 63.7530 and Table 7 to this subpart.

(4) Conduct CMS performance evaluations according to § 63.7525.

(b) For each boiler or process heater that you elect to demonstrate compliance with the applicable emission limits in Table 1 or 2 or Tables 11 through 15 to this subpart for HCl, mercury, or TSM through fuel analysis, your initial compliance requirement is to conduct a fuel analysis for each type of fuel burned in your boiler or process heater according to § 63.7521 and Table 6 to this subpart and establish operating limits according to § 63.7530 and Table 8 to this subpart. The fuels described in paragraphs (a)(2)(i) and (ii) of this section are exempt from these fuel analysis and operating limit requirements. The fuels described in paragraph (a)(2)(ii) of this section are exempt from the chloride fuel analysis and operating limit requirements. Boilers and process heaters that use a CEMS for mercury or HCl are exempt from the performance testing and operating limit requirements specified in paragraph (a) of this section for the HAP for which CEMS are used.

(c) If your boiler or process heater is subject to a carbon monoxide (CO) limit, your initial compliance demonstration for CO is to conduct a performance test for CO according to Table 5 to this subpart or conduct a performance evaluation of your continuous CO monitor, if applicable, according to § 63.7525(a). Boilers and process heaters that use a CO CEMS to comply with the applicable alternative CO CEMS emission standard listed in Table 1 or 2 or Tables 11 through 15 to this subpart, as specified in § 63.7525(a), are exempt from the initial CO performance testing and oxygen concentration operating limit requirements specified in paragraph (a) of this section.

(d) If your boiler or process heater is subject to a PM limit, your initial compliance demonstration for PM is to conduct a performance test in accordance with § 63.7520 and Table 5 to this subpart.

(e) For existing affected sources (as defined in § 63.7490), you must complete the initial compliance demonstrations, as specified in paragraphs (a) through (d) of this section, no later than 180 days after the compliance date that is specified for your source in § 63.7495 and according to the applicable provisions in § 63.7(a)(2) as cited in Table 10 to this subpart, except as specified in paragraph (j) of this section. You must complete an initial tune-up by following the procedures described in § 63.7540(a)(10)(i) through (vi) no later than the compliance date specified in § 63.7495, except as specified in paragraph (j) of this section. You must

complete the one-time energy assessment specified in Table 3 to this subpart no later than the compliance date specified in § 63.7495.

(f) For new or reconstructed affected sources (as defined in § 63.7490), you must complete the initial compliance demonstration with the emission limits no later than July 30, 2013, or within 180 days after startup of the source, whichever is later.

(1) If you are demonstrating compliance with an emission limit in Tables 11 through 13 to this subpart that is less stringent than the applicable emission limit in Table 14 to this subpart, you must demonstrate compliance with the applicable emission limit in Table 14 no later than July 29, 2016.

(2) If you are demonstrating compliance with an emission limit in Table 14 to this subpart that is less stringent than the applicable emission limit in Table 1 to this subpart, you must demonstrate compliance with the applicable emission limit in Table 1 no later than October 6, 2025.

(g) For new or reconstructed affected sources (as defined in § 63.7490), you must demonstrate initial compliance with the applicable work practice standards in Table 3 to this subpart within the applicable annual, biennial, or 5-year schedule as specified in § 63.7515(d) following the initial compliance date specified in § 63.7495(a). Thereafter, you are required to complete the applicable annual, biennial, or 5-year tune-up as specified in § 63.7515(d).

(h) For affected sources (as defined in § 63.7490) that ceased burning solid waste consistent with § 63.7495(e) and for which the initial compliance date has passed, you must demonstrate compliance within 60 days of the effective date of the waste-to-fuel switch. If you have not conducted your compliance demonstration for this subpart within the previous 12 months, you must complete all compliance demonstrations for this subpart before you commence or recommence combustion of solid waste.

(i) For an existing EGU that becomes subject after January 31, 2016, you must demonstrate compliance within 180 days after becoming an affected source.

(j) For existing affected sources (as defined in § 63.7490) that have not operated between the effective date of the rule and the compliance date that is specified for your source in § 63.7495, you must complete the initial compliance demonstration, if subject to the emission limits in Table 2 or 14 to this subpart, as applicable, as specified in paragraphs (a) through (d) of this section, no later than 180 days after the re-start of the affected source and according to the applicable provisions in § 63.7(a)(2) as cited in Table 10 to this subpart. You must complete an initial tune-up by following the procedures described in § 63.7540(a)(10)(i) through (vi) no later than 30 days after the re-start of the affected source and, if applicable, complete the one-time energy assessment specified in Table 3 to this subpart, no later than the compliance date specified in § 63.7495.

(k) For affected sources, as defined in § 63.7490, that switch subcategories consistent with § 63.7545(h) after the initial compliance date, you must demonstrate compliance within 60 days of the effective date of the switch, unless you had previously conducted your compliance demonstration for this subcategory within the previous 12 months.

[78 FR 7164, Jan. 31, 2013, as amended at 80 FR 72808, Nov. 20, 2015; 87 FR 60841, Oct. 6, 2022]

§ 63.7515 When must I conduct subsequent performance tests, fuel analyses, or tune-ups?

(a) You must conduct all applicable performance tests according to § 63.7520 on an annual basis, except as specified in paragraphs (b) through (e), (g), and (h) of this section. Annual performance tests must be completed no more than 13 months after the previous performance test, except as specified in paragraphs (b) through (e), (g), and (h) of this section.

(b) If your performance tests for a given pollutant for at least 2 consecutive years show that your emissions are at or below 75 percent of the emission limit (or, in limited instances as specified in Tables 1 and 2 or 11 through 15 to this subpart, at or below the emission limit) for the pollutant,

and if there are no changes in the operation of the individual boiler or process heater or air pollution control equipment that could increase emissions, you may choose to conduct performance tests for the pollutant every third year. Each such performance test must be conducted no more than 37 months after the previous performance test. If you elect to demonstrate compliance using emission averaging under §63.7522, you must continue to conduct performance tests annually. The requirement to test at maximum chloride input level is waived unless the stack test is conducted for HCl. The requirement to test at maximum mercury input level is waived unless the stack test is conducted for mercury. The requirement to test at maximum TSM input level is waived unless the stack test is conducted for TSM.

(c) If a performance test shows emissions exceeded the emission limit or 75 percent of the emission limit (as specified in Tables 1 and 2 or 11 through 15 to this subpart) for a pollutant, you must conduct annual performance tests for that pollutant until all performance tests over a consecutive 2-year period meet the required level (at or below 75 percent of the emission limit, as specified in Tables 1 and 2 or 11 through 15).

(d) If you are required to meet an applicable tune-up work practice standard, you must conduct an annual, biennial, or 5-year performance tune-up according to §63.7540(a)(10), (11), or (12), respectively. Each annual tune-up specified in §63.7540(a)(10) must be no more than 13 months after the previous tune-up. Each biennial tune-up specified in §63.7540(a)(11) must be conducted no more than 25 months after the previous tune-up. Each 5-year tune-up specified in §63.7540(a)(12) must be conducted no more than 61 months after the previous tune-up. For a new or reconstructed affected source (as defined in §63.7490), the first annual, biennial, or 5-year tune-up must be no later than 13 months, 25 months, or 61 months, respectively, after April 1, 2013 or the initial startup of the new or reconstructed affected source, whichever is later.

(e) If you demonstrate compliance with the mercury, HCl, or TSM based on fuel analysis, you must conduct a monthly fuel analysis according to §63.7521 for each type of fuel burned that is subject to an emission limit in Table 1 or 2 or Tables 11 through 15 to this subpart. You may comply with this monthly requirement by completing the fuel analysis any time within the calendar month as long as the analysis is separated from the previous analysis by at least 14 calendar days. If you burn a new type of fuel, you must conduct a fuel analysis before burning the new type of fuel in your boiler or process heater. You must still meet all applicable continuous compliance requirements in §63.7540. If each of 12 consecutive monthly fuel analyses demonstrates 75 percent or less of the compliance level, you may decrease the fuel analysis frequency to quarterly for that fuel. If any quarterly sample exceeds 75 percent of the compliance level or you begin burning a new type of fuel, you must return to monthly monitoring for that fuel, until 12 months of fuel analyses are again less than 75 percent of the compliance level. If sampling is conducted on 1 day per month, samples should be no less than 14 days apart, but if multiple samples are taken per month, the 14-day restriction does not apply.

(f) You must report the results of performance tests and the associated fuel analyses within 60 days after the completion of the performance tests. This report must also verify that the operating limits for each boiler or process heater have not changed or provide documentation of revised operating limits established according to §63.7530 and Table 7 to this subpart, as applicable. The reports for all subsequent performance tests must include all applicable information required in §63.7550.

(g) For affected sources (as defined in §63.7490) that have not operated since the previous compliance demonstration and more than 1 year has passed since the previous compliance demonstration, you must complete the subsequent compliance demonstration, if subject to the emission limits in Table 1 or 2 or Tables 11 through 15 to this subpart, no later than 180 days after the re-start of the affected source and

according to the applicable provisions in § 63.7(a)(2) as cited in Table 10 to this subpart. You must complete a subsequent tune-up by following the procedures described in § 63.7540(a)(10)(i) through (vi) and the schedule described in § 63.7540(a)(13) for units that are not operating at the time of their scheduled tune-up.

(h) If your affected boiler or process heater is in the unit designed to burn light liquid subcategory and you combust ultra-low sulfur liquid fuel, you do not need to conduct further performance tests (stack tests or fuel analyses) if the pollutants measured during the initial compliance performance tests meet the emission limits in Tables 1 or 2 of this subpart providing you demonstrate ongoing compliance with the emissions limits by monitoring and recording the type of fuel combusted on a monthly basis. If you intend to use a fuel other than ultra-low sulfur liquid fuel, natural gas, refinery gas, or other gas 1 fuel, you must conduct new performance tests within 60 days of burning the new fuel type.

(i) If you operate a CO CEMS that meets the Performance Specifications outlined in § 63.7525(a)(3) to demonstrate compliance with the applicable alternative CO CEMS emission standard listed in Table 1 or 2 or Tables 11 through 15 to this subpart, you are not required to conduct CO performance tests and are not subject to the oxygen concentration operating limit requirement specified in § 63.7510(a).

[78 FR 7165, Jan. 31, 2013, as amended at 80 FR 72808, Nov. 20, 2015; 87 FR 60842, Oct. 6, 2022]

§ 63.7520 What stack tests and procedures must I use?

(a) You must conduct all performance tests according to § 63.7(c), (d), (f), and (h). You must also develop a site-specific stack test plan according to the requirements in § 63.7(c). You shall conduct all performance tests under such conditions as the Administrator specifies to you based on the representative performance of each boiler or process heater for the period being tested. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of the performance tests.

(b) You must conduct each performance test according to the requirements in Table 5 to this subpart.

(c) You must conduct each performance test under the specific conditions listed in Tables 5 and 7 to this subpart. You must conduct performance tests at representative operating load conditions while burning the type of fuel or mixture of fuels that has the highest content of chlorine and mercury, and TSM if you are opting to comply with the TSM alternative standard and you must demonstrate initial compliance and establish your operating limits based on these performance tests. These requirements could result in the need to conduct more than one performance test. Following each performance test and until the next performance test, you must comply with the operating limit for operating load conditions specified in Table 4 to this subpart.

(d) You must conduct a minimum of three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must comply with the minimum applicable sampling times or volumes specified in Tables 1 and 2 or 11 through 15 to this subpart.

(e) To determine compliance with the emission limits, you must use the F-Factor methodology and equations in sections 12.2 and 12.3 of EPA Method 19 at 40 CFR part 60, appendix A–7 of this chapter to convert the measured particulate matter (PM) concentrations, the measured HCl concentrations, the measured mercury concentrations, and the measured TSM concentrations that result from the performance test to pounds per million Btu heat input emission rates.

(f) Except for a 30-day rolling average based on CEMS (or sorbent trap monitoring system) data, if measurement results for any pollutant are reported as below the method detection level (e.g., laboratory analytical results for one or more sample components are below the method defined analytical detection level), you must use the method detection level as the measured emissions level for that pollutant

in calculating compliance. The measured result for a multiple component analysis (e.g., analytical values for multiple Method 29 fractions both for individual HAP metals and for total HAP metals) may include a combination of method detection level data and analytical data reported above the method detection level.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7166, Jan. 31, 2013; 87 FR 60842, Oct. 6, 2022]

§ 63.7521 What fuel analyses, fuel specification, and procedures must I use?

(a) For solid and liquid fuels, you must conduct fuel analyses for chloride and mercury according to the procedures in paragraphs (b) through (e) of this section and Table 6 to this subpart, as applicable. For solid fuels and liquid fuels, you must also conduct fuel analyses for TSM if you are opting to comply with the TSM alternative standard. For gas 2 (other) fuels, you must conduct fuel analyses for mercury according to the procedures in paragraphs (b) through (e) of this section and Table 6 to this subpart, as applicable. For gaseous fuels, you may not use fuel analyses to comply with the TSM alternative standard or the HCl standard. For purposes of complying with this section, a fuel gas system that consists of multiple gaseous fuels collected and mixed with each other is considered a single fuel type and sampling and analysis is only required on the combined fuel gas system that will feed the boiler or process heater. Sampling and analysis of the individual gaseous streams prior to combining is not required. You are not required to conduct fuel analyses for fuels used for only startup, unit shutdown, and transient flame stability purposes. You are required to conduct fuel analyses only for fuels and units that are subject to emission limits for mercury, HCl, or TSM in Tables 1 and 2 or 11 through 15 to this subpart. Gaseous and liquid fuels are exempt from the sampling requirements in paragraphs (c) and (d) of this section.

(b) You must develop a site-specific fuel monitoring plan according to the following procedures and requirements in paragraphs (b)(1) and (2) of this section, if you are required to conduct fuel analyses as specified in § 63.7510.

(1) If you intend to use an alternative analytical method other than those required by Table 6 to this subpart, you must submit the fuel analysis plan to the Administrator for review and approval no later than 60 days before the date that you intend to conduct the initial compliance demonstration described in § 63.7510.

(2) You must include the information contained in paragraphs (b)(2)(i) through (vi) of this section in your fuel analysis plan.

(i) The identification of all fuel types anticipated to be burned in each boiler or process heater.

(ii) For each anticipated fuel type, the notification of whether you or a fuel supplier will be conducting the fuel analysis.

(iii) For each anticipated fuel type, a detailed description of the sample location and specific procedures to be used for collecting and preparing the composite samples if your procedures are different from paragraph (c) or (d) of this section. Samples should be collected at a location that most accurately represents the fuel type, where possible, at a point prior to mixing with other dissimilar fuel types.

(iv) For each anticipated fuel type, the analytical methods from Table 6, with the expected minimum detection levels, to be used for the measurement of chlorine or mercury.

(v) If you request to use an alternative analytical method other than those required by Table 6 to this subpart, you must also include a detailed description of the methods and procedures that you are proposing to use. Methods in Table 6 shall be used until the requested alternative is approved.

(vi) If you will be using fuel analysis from a fuel supplier in lieu of site-specific sampling and analysis, the fuel supplier must use the analytical methods required by Table 6 to this subpart.

(c) You must obtain composite fuel samples for each fuel type according to the procedures in paragraph (c)(1) or (2) of this section, or the methods listed in Table 6 to this subpart, or use an automated sampling mechanism that provides representative composite fuel

samples for each fuel type that includes both coarse and fine material. At a minimum, for demonstrating initial compliance by fuel analysis, you must obtain three composite samples. For monthly fuel analyses, at a minimum, you must obtain a single composite sample. For fuel analyses as part of a performance stack test, as specified in §63.7510(a), you must obtain a composite fuel sample during each performance test run.

(1) If sampling from a belt (or screw) feeder, collect fuel samples according to paragraphs (c)(1)(i) and (ii) of this section.

(i) Stop the belt and withdraw a 6-inch wide sample from the full cross-section of the stopped belt to obtain a minimum two pounds of sample. You must collect all the material (fines and coarse) in the full cross-section. You must transfer the sample to a clean plastic bag.

(ii) Each composite sample will consist of a minimum of three samples collected at approximately equal intervals during the testing period for sampling during performance stack testing.

(2) If sampling from a fuel pile or truck, you must collect fuel samples according to paragraphs (c)(2)(i) through (iii) of this section.

(i) For each composite sample, you must select a minimum of five sampling locations uniformly spaced over the surface of the pile.

(ii) At each sampling site, you must dig into the pile to a uniform depth of approximately 18 inches. You must insert a clean shovel into the hole and withdraw a sample, making sure that large pieces do not fall off during sampling; use the same shovel to collect all samples.

(iii) You must transfer all samples to a clean plastic bag for further processing.

(d) You must prepare each composite sample according to the procedures in paragraphs (d)(1) through (7) of this section.

(1) You must thoroughly mix and pour the entire composite sample over a clean plastic sheet.

(2) You must break large sample pieces (e.g., larger than 3 inches) into smaller sizes.

(3) You must make a pie shape with the entire composite sample and subdivide it into four equal parts.

(4) You must separate one of the quarter samples as the first subset.

(5) If this subset is too large for grinding, you must repeat the procedure in paragraph (d)(3) of this section with the quarter sample and obtain a one-quarter subset from this sample.

(6) You must grind the sample in a mill.

(7) You must use the procedure in paragraph (d)(3) of this section to obtain a one-quarter subsample for analysis. If the quarter sample is too large, subdivide it further using the same procedure.

(e) You must determine the concentration of pollutants in the fuel (mercury and/or chlorine and/or TSM) in units of pounds per million Btu of each composite sample for each fuel type according to the procedures in Table 6 to this subpart, for use in Equations 7, 8, and 9 of this subpart.

(f) To demonstrate that a gaseous fuel other than natural gas or refinery gas qualifies as an other gas 1 fuel, as defined in §63.7575, you must conduct a fuel specification analyses for mercury according to the procedures in paragraphs (g) through (i) of this section and Table 6 to this subpart, as applicable, except as specified in paragraph (f)(1) through (4) of this section, or as an alternative where fuel specification analysis is not practical, you must measure mercury concentration in the exhaust gas when firing only the gaseous fuel to be demonstrated as an other gas 1 fuel in the boiler or process heater according to the procedures in Table 6 to this subpart.

(1) You are not required to conduct the fuel specification analyses in paragraphs (g) through (i) of this section for natural gas or refinery gas.

(2) You are not required to conduct the fuel specification analyses in paragraphs (g) through (i) of this section for gaseous fuels that are subject to another subpart of this part, part 60, part 61, or part 65.

(3) You are not required to conduct the fuel specification analyses in paragraphs (g) through (i) of this section on

gaseous fuels for units that are complying with the limits for units designed to burn gas 2 (other) fuels.

(4) You are not required to conduct the fuel specification analyses in paragraphs (g) through (i) of this section for gas streams directly derived from natural gas at natural gas production sites or natural gas plants.

(g) You must develop a site-specific fuel analysis plan for other gas 1 fuels according to the following procedures and requirements in paragraphs (g)(1) and (2) of this section.

(1) If you intend to use an alternative analytical method other than those required by Table 6 to this subpart, you must submit the fuel analysis plan to the Administrator for review and approval no later than 60 days before the date that you intend to conduct the initial compliance demonstration described in § 63.7510.

(2) You must include the information contained in paragraphs (g)(2)(i) through (vi) of this section in your fuel analysis plan.

(i) The identification of all gaseous fuel types other than those exempted from fuel specification analysis under (f)(1) through (3) of this section anticipated to be burned in each boiler or process heater.

(ii) For each anticipated fuel type, the identification of whether you or a fuel supplier will be conducting the fuel specification analysis.

(iii) For each anticipated fuel type, a detailed description of the sample location and specific procedures to be used for collecting and preparing the samples if your procedures are different from the sampling methods contained in Table 6 to this subpart. Samples should be collected at a location that most accurately represents the fuel type, where possible, at a point prior to mixing with other dissimilar fuel types. If multiple boilers or process heaters are fueled by a common fuel stream it is permissible to conduct a single gas specification at the common point of gas distribution.

(iv) For each anticipated fuel type, the analytical methods from Table 6 to this subpart, with the expected minimum detection levels, to be used for the measurement of mercury.

(v) If you request to use an alternative analytical method other than those required by Table 6 to this subpart, you must also include a detailed description of the methods and procedures that you are proposing to use. Methods in Table 6 to this subpart shall be used until the requested alternative is approved.

(vi) If you will be using fuel analysis from a fuel supplier in lieu of site-specific sampling and analysis, the fuel supplier must use the analytical methods required by Table 6 to this subpart. When using a fuel supplier's fuel analysis, the owner or operator is not required to submit the information in § 63.7521(g)(2)(iii).

(h) You must obtain a single fuel sample for each fuel type for fuel specification of gaseous fuels.

(i) You must determine the concentration in the fuel of mercury, in units of microgram per cubic meter, dry basis, of each sample for each other gas 1 fuel type according to the procedures in Table 6 to this subpart.

[78 FR 7167, Jan. 31, 2013, as amended at 80 FR 72808, Nov. 20, 2015; 87 FR 60842, Oct. 6, 2022]

§ 63.7522 Can I use emissions averaging to comply with this subpart?

(a) As an alternative to meeting the requirements of § 63.7500 for PM (or TSM), HCl, or mercury on a boiler or process heater-specific basis, if you have more than one existing boiler or process heater in any subcategories located at your facility, you may demonstrate compliance by emissions averaging, if your averaged emissions are not more than 90 percent of the applicable emission limit, according to the procedures in this section. You may not include new boilers or process heaters in an emissions average.

(b) For a group of two or more existing boilers or process heaters in the same subcategory that each vent to a separate stack, you may average PM (or TSM), HCl, or mercury emissions among existing units to demonstrate compliance with the limits in Table 2 or 15 to this subpart as specified in paragraphs (b)(1) through (3) of this section, if you satisfy the requirements in paragraphs (c) through (g) of this section.

(1) You may average units using a CEMS or PM CPMS for demonstrating compliance.

(2) For mercury and HCl, averaging is allowed as follows:

(i) You may average among units in any of the solid fuel subcategories.

(ii) You may average among units in any of the liquid fuel subcategories.

(iii) You may average among units in a subcategory of units designed to burn gas 2 (other) fuels.

(iv) You may not average across the units designed to burn liquid, units designed to burn solid fuel, and units designed to burn gas 2 (other) subcategories.

(3) For PM (or TSM), averaging is only allowed between units within each of the following subcategories and you may not average across subcategories:

(i) Units designed to burn coal/solid fossil fuel.

(ii) Stokers/sloped grate/other units designed to burn kiln dried biomass/bio-based solids.

(iii) Stokers/sloped grate/other units designed to burn wet biomass/bio-based solids.

(iv) Fluidized bed units designed to burn biomass/bio-based solid.

(v) Suspension burners designed to burn biomass/bio-based solid.

(vi) Dutch ovens/pile burners designed to burn biomass/bio-based solid.

(vii) Fuel Cells designed to burn biomass/bio-based solid.

(viii) Hybrid suspension/grate burners designed to burn wet biomass/bio-based solid.

(ix) Units designed to burn heavy liquid fuel.

(x) Units designed to burn light liquid fuel.

(xi) Units designed to burn liquid fuel that are non-continental units.

(xii) Units designed to burn gas 2 (other) gases.

(c) For each existing boiler or process heater in the averaging group, the emission rate achieved during the initial compliance test for the HAP being averaged must not exceed the emission level that was being achieved on April 1, 2013 or the control technology employed during the initial compliance test must not be less effective for the HAP being averaged than the control technology employed on April 1, 2013.

(d) The averaged emissions rate from the existing boilers and process heaters participating in the emissions averaging option must not exceed 90 percent of the limits in Table 2 or 15 to this subpart at all times the affected units are subject to numeric emission limits following the compliance date specified in § 63.7495.

(e) You must demonstrate initial compliance according to paragraph (e)(1) or (2) of this section using the maximum rated heat input capacity or maximum steam generation capacity of each unit and the results of the initial performance tests or fuel analysis.

(1) You must use Equation 1a or 1b or 1c to this paragraph (e)(1) to demonstrate that the PM (or TSM), HCl, or mercury emissions from all existing units participating in the emissions averaging option for that pollutant do not exceed the emission limits in Table 2 or 15 to this subpart. Use Equation 1a if you are complying with the emission limits on a heat input basis, use Equation 1b if you are complying with the emission limits on a steam generation (output) basis, and use Equation 1c if you are complying with the emission limits on a electric generation (output) basis.

Equation 1a to paragraph (e)(1)

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times Hm) \div \sum_{i=1}^{n} Hm \qquad \text{(Eq. 1a)}$$

Where:

AveWeightedEmissions = Average weighted emissions for PM (or TSM), HCl, or mercury, in units of pounds per million Btu of heat input.

Er = Emission rate (as determined during the initial compliance demonstration) of PM

(or TSM), HCl, or mercury from unit, i, in units of pounds per million Btu of heat input. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM using the applicable equation in § 63.7530(c).

Hm = Maximum rated heat input capacity of unit, i, in units of million Btu per hour.

n = Number of units participating in the emissions averaging option.

1.1 = Required discount factor.

Equation 1b to paragraph (e)(1)

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times So) \div \sum_{i=1}^{n} So \qquad \text{(Eq. 1b)}$$

Where:

AveWeightedEmissions = Average weighted emissions for PM (or TSM), HCl, or mercury, in units of pounds per million Btu of steam output.

Er = Emission rate (as determined during the initial compliance demonstration) of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per million Btu of steam output. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM using the applicable equation in § 63.7530(c). If you are taking credit for energy conservation measures from a unit according to § 63.7533, use the adjusted emission level for that unit, Eadj, determined according to § 63.7533 for that unit.

So = Maximum steam output capacity of unit, i, in units of million Btu per hour, as defined in § 63.7575.

n = Number of units participating in the emissions averaging option.

1.1 = Required discount factor.

Equation 1c to paragraph (e)(1)

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times Eo) \div \sum_{i=1}^{n} Eo \qquad \text{(Eq. 1c)}$$

Where:

AveWeightedEmissions = Average weighted emissions for PM (or TSM), HCl, or mercury, in units of pounds per megawatt hour.

Er = Emission rate (as determined during the initial compliance demonstration) of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per megawatt hour. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM using the applicable equation in § 63.7530(c). If you are taking credit for energy conservation measures from a unit according to § 63.7533, use the adjusted emission level for that unit, Eadj, determined according to § 63.7533 for that unit.

Eo = Maximum electric generating output capacity of unit, i, in units of megawatt hour, as defined in § 63.7575.

n = Number of units participating in the emissions averaging option.

1.1 = Required discount factor.

(2) If you are not capable of determining the maximum rated heat input capacity of one or more boilers that generate steam, you may use Equation 2 to this paragraph (e)(2) as an alternative to using Equation 1a of paragraph (e)(1) of this section to demonstrate that the PM (or TSM), HCl, or mercury emissions from all existing units participating in the emissions averaging option do not exceed the emission limits for that pollutant in Table 2 or 15 to this subpart that are in pounds per million Btu of heat input.

Equation 2 to paragraph (e)(2)

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times Sm \times Cfi) \div \sum_{i=1}^{n} (Sm \times Cfi) \quad \text{(Eq. 2)}$$

Where:

AveWeightedEmissions = Average weighted emission level for PM (or TSM), HCl, or mercury, in units of pounds per million Btu of heat input.

Er = Emission rate (as determined during the most recent compliance demonstration) of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per million Btu of heat input. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM using the applicable equation in § 63.7530(c).

Sm = Maximum steam generation capacity by unit, i, in units of pounds per hour.

Cfi = Conversion factor, calculated from the most recent compliance test, in units of million Btu of heat input per pounds of steam generated for unit, i.

1.1 = Required discount factor.

(f) After the initial compliance demonstration described in paragraph (e) of this section, you must demonstrate compliance on a monthly basis determined at the end of every month (12 times per year) according to paragraphs (f)(1) through (3) of this section. The first monthly period begins on the compliance date specified in § 63.7495. If the affected source elects to collect monthly data for up the 11 months preceding the first monthly period, these additional data points can be used to compute the 12-month rolling average in paragraph (f)(3) of this section.

(1) For each calendar month, you must use Equation 3a or 3b or 3c of this section to calculate the average weighted emission rate for that month. Use Equation 3a and the actual heat input for the month for each existing unit participating in the emissions averaging option if you are complying with emission limits on a heat input basis. Use Equation 3b and the actual steam generation for the month if you are complying with the emission limits on a steam generation (output) basis. Use Equation 3c and the actual electrical generation for the month if you are complying with the emission limits on an electrical generation (output) basis.

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times Hb) \div \sum_{i=1}^{n} Hb \quad \text{(Eq. 3a)}$$

Where:

AveWeightedEmissions = Average weighted emission level for PM (or TSM), HCl, or mercury, in units of pounds per million Btu of heat input, for that calendar month.

Er = Emission rate (as determined during the most recent compliance demonstration) of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per million Btu of heat input. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM according to Table 6 to this subpart.

Hb = The heat input for that calendar month to unit, i, in units of million Btu.

n = Number of units participating in the emissions averaging option.

1.1 = Required discount factor.

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times So) \div \sum_{i=1}^{n} So \quad \text{(Eq. 3b)}$$

Where:
AveWeightedEmissions = Average weighted emission level for PM (or TSM), HCl, or mercury, in units of pounds per million Btu of steam output, for that calendar month.
Er = Emission rate (as determined during the most recent compliance demonstration) of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per million Btu of steam output. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM according to Table 6 to this subpart. If you are taking credit for energy conservation measures from a unit according to §63.7533, use the adjusted emission level for that unit, E_{adj}, determined according to §63.7533 for that unit.
So = The steam output for that calendar month from unit, i, in units of million Btu, as defined in §63.7575.
n = Number of units participating in the emissions averaging option.
1.1 = Required discount factor.

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times Eo) \div \sum_{i=1}^{n} Eo \quad \text{(Eq. 3c)}$$

Where:
AveWeightedEmissions = Average weighted emission level for PM (or TSM), HCl, or mercury, in units of pounds per megawatt hour, for that calendar month.
Er = Emission rate (as determined during the most recent compliance demonstration) of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per megawatt hour. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM according to Table 6 to this subpart. If you are taking credit for energy conservation measures from a unit according to §63.7533, use the adjusted emission level for that unit, E_{adj}, determined according to §63.7533 for that unit.
Eo = The electric generating output for that calendar month from unit, i, in units of megawatt hour, as defined in §63.7575.
n = Number of units participating in the emissions averaging option.
1.1 = Required discount factor.

(2) If you are not capable of monitoring heat input, you may use Equation 4 of this section as an alternative to using Equation 3a of this section to calculate the average weighted emission rate using the actual steam generation from the boilers participating in the emissions averaging option.

$$AveWeightedEmissions = 1.1 \times \sum_{i=1}^{n} (Er \times Sa \times Cfi) \div \sum_{i=1}^{n} (Sa \times Cfi) \quad \text{(Eq. 4)}$$

Where:
AveWeightedEmissions = average weighted emission level for PM (or TSM), HCl, or mercury, in units of pounds per million Btu of heat input for that calendar month.
Er = Emission rate (as determined during the most recent compliance demonstration of PM (or TSM), HCl, or mercury from unit, i, in units of pounds per million Btu of heat input. Determine the emission rate for PM (or TSM), HCl, or mercury by performance testing according to Table 5 to this subpart, or by fuel analysis for HCl or mercury or TSM according to Table 6 to this subpart.
Sa = Actual steam generation for that calendar month by boiler, i, in units of pounds.
Cfi = Conversion factor, as calculated during the most recent compliance test, in units of million Btu of heat input per pounds of steam generated for boiler, i.
1.1 = Required discount factor.

(3) Until 12 monthly weighted average emission rates have been accumulated, calculate and report only the average weighted emission rate determined under paragraph (f)(1) or (2) of this section for each calendar month. After 12 monthly weighted average emission rates have been accumulated,

for each subsequent calendar month, use Equation 5 of this section to calculate the 12-month rolling average of the monthly weighted average emission rates for the current calendar month and the previous 11 calendar months.

$$Eavg = \sum_{i=1}^{n} ERi \div 12 \quad \text{(Eq. 5)}$$

Where:

Eavg = 12-month rolling average emission rate, (pounds per million Btu heat input)

ERi = Monthly weighted average, for calendar month ''i'' (pounds per million Btu heat input), as calculated by paragraph (f)(1) or (2) of this section.

(g) You must develop, and submit upon request to the applicable Administrator for review and approval, an implementation plan for emission averaging according to the following procedures and requirements in paragraphs (g)(1) through (4) of this section.

(1) If requested, you must submit the implementation plan no later than 180 days before the date that the facility intends to demonstrate compliance using the emission averaging option.

(2) You must include the information contained in paragraphs (g)(2)(i) through (vii) of this section in your implementation plan for all emission sources included in an emissions average:

(i) The identification of all existing boilers and process heaters in the averaging group, including for each either the applicable HAP emission level or the control technology installed as of January 31, 2013 and the date on which you are requesting emission averaging to commence;

(ii) The process parameter (heat input or steam generated) that will be monitored for each averaging group;

(iii) The specific control technology or pollution prevention measure to be used for each emission boiler or process heater in the averaging group and the date of its installation or application. If the pollution prevention measure reduces or eliminates emissions from multiple boilers or process heaters, the owner or operator must identify each boiler or process heater;

(iv) The test plan for the measurement of PM (or TSM), HCl, or mercury emissions in accordance with the requirements in § 63.7520;

(v) The operating parameters to be monitored for each control system or device consistent with § 63.7500 and Table 4, and a description of how the operating limits will be determined;

(vi) If you request to monitor an alternative operating parameter pursuant to § 63.7525, you must also include:

(A) A description of the parameter(s) to be monitored and an explanation of the criteria used to select the parameter(s); and

(B) A description of the methods and procedures that will be used to demonstrate that the parameter indicates proper operation of the control device; the frequency and content of monitoring, reporting, and recordkeeping requirements; and a demonstration, to the satisfaction of the Administrator, that the proposed monitoring frequency is sufficient to represent control device operating conditions; and

(vii) A demonstration that compliance with each of the applicable emission limit(s) will be achieved under representative operating load conditions. Following each compliance demonstration and until the next compliance demonstration, you must comply with the operating limit for operating load conditions specified in Table 4 to this subpart.

(3) If submitted upon request, the Administrator shall review and approve or disapprove the plan according to the following criteria:

(i) Whether the content of the plan includes all of the information specified in paragraph (g)(2) of this section; and

(ii) Whether the plan presents sufficient information to determine that compliance will be achieved and maintained.

(4) The applicable Administrator shall not approve an emission averaging implementation plan containing any of the following provisions:

(i) Any averaging between emissions of differing pollutants or between differing sources; or

(ii) The inclusion of any emission source other than an existing unit in the same subcategories.

(h) For a group of two or more existing affected units, each of which vents through a single common stack, you may average PM (or TSM), HCl, or mercury emissions to demonstrate compliance with the limits for that pollutant in Table 2 or 15 to this subpart if you satisfy the requirements in paragraph (i) or (j) of this section.

(i) For a group of two or more existing units in the same subcategory, each of which vents through a common emissions control system to a common stack, that does not receive emissions from units in other subcategories or categories, you may treat such averaging group as a single existing unit for purposes of this subpart and comply with the requirements of this subpart as if the group were a single unit.

(j) For all other groups of units subject to the common stack requirements of paragraph (h) of this section, including situations where the exhaust of affected units are each individually controlled and then sent to a common stack, the owner or operator may elect to:

(1) Conduct performance tests according to procedures specified in §63.7520 in the common stack if affected units from other subcategories vent to the common stack. The emission limits that the group must comply with are determined by the use of Equation 6 to this paragraph (j)(1).

Equation 6 to paragraph (j)(1)

$$En = \sum_{i=1}^{n} (ELi \times Hi) \div \sum_{i=1}^{n} Hi \qquad \text{(Eq. 6)}$$

Where:

En = HAP emission limit, pounds per million British thermal units (lb/MMBtu) or parts per million (ppm).

ELi = Appropriate emission limit from Table 2 or 15 to this subpart for unit i, in units of lb/MMBtu or ppm.

Hi = Heat input from unit i, MMBtu.

(2) Conduct performance tests according to procedures specified in §63.7520 in the common stack. If affected units and non-affected units vent to the common stack, the non-affected units must be shut down or vented to a different stack during the performance test unless the facility determines to demonstrate compliance with the non-affected units venting to the stack; and

(3) Meet the applicable operating limit specified in §63.7540 and Table 8 to this subpart for each emissions control system (except that, if each unit venting to the common stack has an applicable opacity operating limit, then a single continuous opacity monitoring system may be located in the common stack instead of in each duct to the common stack).

(k) The common stack of a group of two or more existing boilers or process heaters in the same subcategories subject to paragraph (h) of this section may be treated as a separate stack for purposes of paragraph (b) of this section and included in an emissions averaging group subject to paragraph (b) of this section.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7168, Jan. 31, 2013; 80 FR 72809, Nov. 20, 2015; 87 FR 60843, Oct. 6, 2022]

§63.7525 What are my monitoring, installation, operation, and maintenance requirements?

(a) If your boiler or process heater is subject to a CO emission limit in Table 1 or 2 or Tables 11 through 15 to this subpart, you must install, operate, and maintain an oxygen analyzer system, as defined in §63.7575, or install, certify, operate and maintain continuous emission monitoring systems for CO

and oxygen (O_2) (or carbon dioxide (CO_2)) according to the procedures in paragraphs (a)(1) through (6) of this section.

(1) Install the CO CEMS including an O_2 (or CO_2) analyzer by the compliance date specified in § 63.7495. The CO and O_2 (or CO_2) levels shall be monitored at the same location at the outlet of the boiler or process heater. An owner or operator may determine compliance with the CO emissions limit using a CO_2 analyzer as the diluent monitor. If a CO_2 analyzer is used as the diluent monitor, EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, for the fuel type(s) being burned in the unit and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to calculate the emissions corrected to 3 percent O_2 using the measured CO_2 percentage, and must also take into account that the 3 percent oxygen correction is to be done on a dry basis. The equations used to calculate the emissions, must also account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. The methodology used to calculate the CO emissions and the methodology used to account for any CO_2 being added to, or removed from the emissions gas stream shall be detailed and approved in the site-specific monitoring plan developed according to § 63.7505(d).

(2) To demonstrate compliance with the applicable alternative CO CEMS emission standard listed in Table 1 or 2 or Tables 11 through 15 to this subpart, you must install, certify, operate, and maintain a CO CEMS and an oxygen analyzer according to the applicable procedures under Performance Specification 4, 4A, or 4B at 40 CFR part 60, appendix B; part 75 of this chapter (if an CO_2 analyzer is used); the site-specific monitoring plan developed according to § 63.7505(d); and the requirements in § 63.7540(a)(8) and this paragraph (a). Any boiler or process heater that has a CO CEMS that is compliant with Performance Specification 4, 4A, or 4B at 40 CFR part 60, appendix B, a site-specific monitoring plan developed according to § 63.7505(d), and the requirements in § 63.7540(a)(8) and this paragraph (a) must use the CO CEMS to comply with the applicable alternative CO CEMS emission standard listed in Table 1 or 2 or Tables 11 through 15 to this subpart.

(i) You must conduct a performance evaluation of each CO CEMS according to the requirements in § 63.8(e) and according to Performance Specification 4, 4A, or 4B at 40 CFR part 60, appendix B.

(ii) During each relative accuracy test run of the CO CEMS, you must collect emission data for CO concurrently using both the CO CEMS and Method 10, 10A, or 10B at 40 CFR part 60, appendix A–4. The relative accuracy testing must be conducted at representative operating conditions.

(iii) You must follow the quality assurance procedures (e.g., quarterly accuracy determinations and daily calibration drift tests) of Procedure 1 of appendix F to part 60. The measurement span value of the CO CEMS must be two times the applicable CO emission limit, expressed as a concentration.

(iv) Any CO CEMS that does not comply with this paragraph (a) cannot be used to meet any requirement in this subpart to demonstrate compliance with a CO emission limit listed in Table 1 or 2 or Tables 11 through 15 to this subpart.

(v) For a new unit, complete the initial performance evaluation no later than July 30, 2013, or 180 days after the date of initial startup, whichever is later. For an existing unit, complete the initial performance evaluation no later than July 29, 2016.

(vi) When CO_2 is used to correct CO emissions and CO_2 is measured on a wet basis, if needed, correct for moisture as follows: Install, operate, maintain, and quality assure a continuous moisture monitoring system for measuring and recording the moisture content of the flue gases, in order to correct the measured hourly volumetric flow rates for moisture when calculating CO concentrations. The following continuous moisture monitoring systems are acceptable: a continuous moisture sensor; an oxygen analyzer (or analyzers) capable of measuring O_2 both on a wet basis and on a dry basis; or a stack temperature sensor and a moisture look-up table, *i.e.,* a psychrometric chart (for saturated gas streams following wet

scrubbers or other demonstrably saturated gas streams, only). The moisture monitoring system shall include as a component the automated data acquisition and handling system (DAHS) for recording and reporting both the raw data (e.g., hourly average wet-and dry-basis O_2 values) and the hourly average values of the stack gas moisture content derived from those data. When a moisture look-up table is used, the moisture monitoring system shall be represented as a single component, the certified DAHS, in the monitoring plan for the unit or common stack.

(3) Complete a minimum of one cycle of CO and oxygen (or CO_2) CEMS operation (sampling, analyzing, and data recording) for each successive 15-minute period. Collect CO and oxygen (or CO_2) data concurrently. Collect at least four CO and oxygen (or CO_2) CEMS data values representing the four 15-minute periods in an hour, or at least two 15-minute data values during an hour when CEMS calibration, quality assurance, or maintenance activities are being performed.

(4) Reduce the CO CEMS data as specified in §63.8(g)(2).

(5) Calculate one-hour arithmetic averages, corrected to 3 percent oxygen (or corrected to an CO_2 percentage determined to be equivalent to 3 percent oxygen) from each hour of CO CEMS data in parts per million CO concentration. The one-hour arithmetic averages required shall be used to calculate the 30-day or 10-day rolling average emissions. Use Equation 19–19 in section 12.4.1 of Method 19 of 40 CFR part 60, appendix A–7 for calculating the average CO concentration from the hourly values.

(6) For purposes of collecting CO data, operate the CO CEMS as specified in §63.7535(b). You must use all the data collected during all periods in calculating data averages and assessing compliance, except that you must exclude certain data as specified in §63.7535(c). Periods when CO data are unavailable may constitute monitoring deviations as specified in §63.7535(d).

(7) Operate an oxygen trim system with the oxygen level set no lower than the lowest hourly average oxygen concentration measured during the most recent CO performance test as the operating limit for oxygen according to Table 7 to this subpart.

(b) If your boiler or process heater is in the unit designed to burn coal/solid fossil fuel subcategory or the unit designed to burn heavy liquid subcategory and has an average annual heat input rate greater than 250 MMBtu per hour from solid fossil fuel and/or heavy liquid, and you demonstrate compliance with the PM limit instead of the alternative TSM limit, you must install, maintain, and operate a PM CPMS monitoring emissions discharged to the atmosphere and record the output of the system as specified in paragraphs (b)(1) through (4) of this section. As an alternative to use of a PM CPMS to demonstrate compliance with the PM limit, you may choose to use a PM CEMS. If you choose to use a PM CEMS to demonstrate compliance with the PM limit instead of the alternative TSM limit, you must install, certify, maintain, and operate a PM CEMS monitoring emissions discharged to the atmosphere and record the output of the system as specified in paragraph (b)(5) through (8) of this section. For other boilers or process heaters, you may elect to use a PM CPMS or PM CEMS operated in accordance with this section in lieu of using other CMS for monitoring PM compliance (*e.g.,* bag leak detectors, ESP secondary power, and PM scrubber pressure). Owners of boilers and process heaters who elect to comply with the alternative TSM limit are not required to install a PM CPMS.

(1) Install, operate, and maintain your PM CPMS according to the procedures in your approved site-specific monitoring plan developed in accordance with §63.7505(d), the requirements in §63.7540(a)(9), and paragraphs (b)(1)(i) through (iii) of this section.

(i) The operating principle of the PM CPMS must be based on in-stack or extractive light scatter, light scintillation, beta attenuation, or mass accumulation detection of PM in the exhaust gas or representative exhaust gas sample. The reportable measurement output from the PM CPMS must be expressed as milliamps.

(ii) The PM CPMS must have a cycle time (i.e., period required to complete

sampling, measurement, and reporting for each measurement) no longer than 60 minutes.

(iii) The PM CPMS must have a documented detection limit of 0.5 milligram per actual cubic meter, or less.

(2) For a new unit, complete the initial performance evaluation no later than July 30, 2013, or 180 days after the date of initial startup, whichever is later. For an existing unit, complete the initial performance evaluation no later than July 29, 2016.

(3) Collect PM CPMS hourly average output data for all boiler or process heater operating hours except as indicated in §63.7535(a) through (d). Express the PM CPMS output as milliamps.

(4) Calculate the arithmetic 30-day rolling average of all of the hourly average PM CPMS output data collected during all boiler or process heater operating hours (milliamps).

(5) Install, certify, operate, and maintain your PM CEMS according to the procedures in your approved site-specific monitoring plan developed in accordance with §63.7505(d), the requirements in §63.7540(a)(9), and paragraphs (b)(5)(i) through (iv) of this section.

(i) You shall conduct a performance evaluation of the PM CEMS according to the applicable requirements of §60.8(e), and Performance Specification 11 at 40 CFR part 60, appendix B of this chapter.

(ii) During each PM correlation testing run of the CEMS required by Performance Specification 11 at 40 CFR part 60, appendix B of this chapter, you shall collect PM and oxygen (or carbon dioxide) data concurrently (or within a 30-to 60-minute period) by both the CEMS and conducting performance tests using Method 5 at 40 CFR part 60, appendix A–3 or Method 17 at 40 CFR part 60, appendix A–6 of this chapter.

(iii) You shall perform quarterly accuracy determinations and daily calibration drift tests in accordance with Procedure 2 at 40 CFR part 60, appendix F of this chapter. You must perform Relative Response Audits annually and perform Response Correlation Audits every 3 years.

(iv) Within 60 days after the date of completing each CEMS relative accuracy test audit or performance test conducted to demonstrate compliance with this subpart, you must submit the relative accuracy test audit data and performance test data to the EPA by successfully submitting the data electronically into the EPA's Central Data Exchange by using the Electronic Reporting Tool (see *http://www.epa.gov/ttn/chief/ert/erttool.html/*).

(6) For a new unit, complete the initial performance evaluation no later than July 30, 2013, or 180 days after the date of initial startup, whichever is later. For an existing unit, complete the initial performance evaluation no later than July 29, 2016.

(7) Collect PM CEMS hourly average output data for all boiler or process heater operating hours except as indicated in §63.7535(a) through (d).

(8) Calculate the arithmetic 30-day rolling average of all of the hourly average PM CEMS output data collected during all boiler or process heater operating hours.

(c) If you have an applicable opacity operating limit in this rule, and are not otherwise required or elect to install and operate a PM CPMS, PM CEMS, or a bag leak detection system, you must install, operate, certify and maintain each COMS according to the procedures in paragraphs (c)(1) through (7) of this section by the compliance date specified in §63.7495.

(1) Each COMS must be installed, operated, and maintained according to Performance Specification 1 at appendix B to part 60 of this chapter.

(2) You must conduct a performance evaluation of each COMS according to the requirements in §63.8(e) and according to Performance Specification 1 at appendix B to part 60 of this chapter.

(3) As specified in §63.8(c)(4)(i), each COMS must complete a minimum of one cycle of sampling and analyzing for each successive 10-second period and one cycle of data recording for each successive 6-minute period.

(4) The COMS data must be reduced as specified in §63.8(g)(2).

(5) You must include in your site-specific monitoring plan procedures and acceptance criteria for operating and maintaining each COMS according to

the requirements in § 63.8(d). At a minimum, the monitoring plan must include a daily calibration drift assessment, a quarterly performance audit, and an annual zero alignment audit of each COMS.

(6) You must operate and maintain each COMS according to the requirements in the monitoring plan and the requirements of § 63.8(e). You must identify periods the COMS is out of control including any periods that the COMS fails to pass a daily calibration drift assessment, a quarterly performance audit, or an annual zero alignment audit. Any 6-minute period for which the monitoring system is out of control and data are not available for a required calculation constitutes a deviation from the monitoring requirements.

(7) You must determine and record all the 6-minute averages (and daily block averages as applicable) collected for periods during which the COMS is not out of control.

(d) If you have an operating limit that requires the use of a CMS other than a PM CPMS or COMS, you must install, operate, and maintain each CMS according to the procedures in paragraphs (d)(1) through (5) of this section by the compliance date specified in § 63.7495.

(1) The CPMS must complete a minimum of one cycle of operation every 15-minutes. You must have a minimum of four successive cycles of operation, one representing each of the four 15-minute periods in an hour, to have a valid hour of data.

(2) You must operate the monitoring system as specified in § 63.7535(b), and comply with the data calculation requirements specified in § 63.7535(c).

(3) Any 15-minute period for which the monitoring system is out-of-control and data are not available for a required calculation constitutes a deviation from the monitoring requirements. Other situations that constitute a monitoring deviation are specified in § 63.7535(d).

(4) You must determine the 30-day rolling average of all recorded readings, except as provided in § 63.7535(c).

(5) You must record the results of each inspection, calibration, and validation check.

(e) If you have an operating limit that requires the use of a flow monitoring system, you must meet the requirements in paragraphs (d) and (e)(1) through (4) of this section.

(1) You must install the flow sensor and other necessary equipment in a position that provides a representative flow.

(2) You must use a flow sensor with a measurement sensitivity of no greater than 2 percent of the design flow rate.

(3) You must minimize, consistent with good engineering practices, the effects of swirling flow or abnormal velocity distributions due to upstream and downstream disturbances.

(4) You must conduct a flow monitoring system performance evaluation in accordance with your monitoring plan at the time of each performance test but no less frequently than annually.

(f) If you have an operating limit that requires the use of a pressure monitoring system, you must meet the requirements in paragraphs (d) and (f)(1) through (6) of this section.

(1) Install the pressure sensor(s) in a position that provides a representative measurement of the pressure (*e.g.*, PM scrubber pressure drop).

(2) Minimize or eliminate pulsating pressure, vibration, and internal and external corrosion consistent with good engineering practices.

(3) Use a pressure sensor with a minimum tolerance of 1.27 centimeters of water or a minimum tolerance of 1 percent of the pressure monitoring system operating range, whichever is less.

(4) Perform checks at least once each process operating day to ensure pressure measurements are not obstructed (*e.g.*, check for pressure tap pluggage daily).

(5) Conduct a performance evaluation of the pressure monitoring system in accordance with your monitoring plan at the time of each performance test but no less frequently than annually.

(6) If at any time the measured pressure exceeds the manufacturer's specified maximum operating pressure range, conduct a performance evaluation of the pressure monitoring system in accordance with your monitoring plan and confirm that the pressure monitoring system continues to meet

the performance requirements in you monitoring plan. Alternatively, install and verify the operation of a new pressure sensor.

(g) If you have an operating limit that requires a pH monitoring system, you must meet the requirements in paragraphs (d) and (g)(1) through (4) of this section.

(1) Install the pH sensor in a position that provides a representative measurement of scrubber effluent pH.

(2) Ensure the sample is properly mixed and representative of the fluid to be measured.

(3) Calibrate the pH monitoring system in accordance with your monitoring plan and according to the manufacturer's instructions. Clean the pH probe at least once each process operating day. Maintain on-site documentation that your calibration frequency is sufficient to maintain the specified accuracy of your device.

(4) Conduct a performance evaluation (including a two-point calibration with one of the two buffer solutions having a pH within 1 of the pH of the operating limit) of the pH monitoring system in accordance with your monitoring plan at the time of each performance test but no less frequently than annually.

(h) If you have an operating limit that requires a secondary electric power monitoring system for an electrostatic precipitator (ESP) operated with a wet scrubber, you must meet the requirements in paragraphs (h)(1) and (2) of this section.

(1) Install sensors to measure (secondary) voltage and current to the precipitator collection plates.

(2) Conduct a performance evaluation of the electric power monitoring system in accordance with your monitoring plan at the time of each performance test but no less frequently than annually.

(i) If you have an operating limit that requires the use of a monitoring system to measure sorbent injection rate (e.g., weigh belt, weigh hopper, or hopper flow measurement device), you must meet the requirements in paragraphs (d) and (i)(1) through (2) of this section.

(1) Install the system in a position(s) that provides a representative measurement of the total sorbent injection rate.

(2) Conduct a performance evaluation of the sorbent injection rate monitoring system in accordance with your monitoring plan at the time of each performance test but no less frequently than annually.

(j) If you are not required to use a PM CPMS and elect to use a fabric filter bag leak detection system to comply with the requirements of this subpart, you must install, calibrate, maintain, and continuously operate the bag leak detection system as specified in paragraphs (j)(1) through (6) of this section.

(1) You must install a bag leak detection sensor(s) in a position(s) that will be representative of the relative or absolute PM loadings for each exhaust stack, roof vent, or compartment (e.g., for a positive pressure fabric filter) of the fabric filter.

(2) Conduct a performance evaluation of the bag leak detection system in accordance with your monitoring plan and consistent with the guidance provided in EPA–454/R–98–015 (incorporated by reference, see § 63.14).

(3) Use a bag leak detection system certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter or less.

(4) Use a bag leak detection system equipped with a device to record continuously the output signal from the sensor.

(5) Use a bag leak detection system equipped with a system that will alert plant operating personnel when an increase in relative PM emissions over a preset level is detected. The alert must easily recognizable (e.g., heard or seen) by plant operating personnel.

(6) Where multiple bag leak detectors are required, the system's instrumentation and alert may be shared among detectors.

(k) For each unit that meets the definition of limited-use boiler or process heater, you must keep fuel use records for the days the boiler or process heater was operating.

(l) For each unit for which you decide to demonstrate compliance with the mercury or HCl emissions limits in Table 1 or 2 or Tables 11 through 15 to

this subpart by use of a CEMS for mercury or HCl, you must install, certify, maintain, and operate a CEMS measuring emissions discharged to the atmosphere and record the output of the system as specified in paragraphs (l)(1) through (8) of this section. For HCl, this option for an affected unit takes effect on the date of approval of a site-specific monitoring plan.

(1) Notify the Administrator one month before starting use of the CEMS, and notify the Administrator one month before stopping use of the CEMS.

(2) Each CEMS shall be installed, certified, operated, and maintained according to the requirements in § 63.7540(a)(14) for a mercury CEMS and § 63.7540(a)(15) for a HCl CEMS.

(3) For a new unit, you must complete the initial performance evaluation of the CEMS by the latest of the dates specified in paragraph (l)(3)(i) through (iii) of this section.

(i) No later than July 30, 2013.

(ii) No later 180 days after the date of initial startup.

(iii) No later 180 days after notifying the Administrator before starting to use the CEMS in place of performance testing or fuel analysis to demonstrate compliance.

(4) For an existing unit, you must complete the initial performance evaluation by the latter of the two dates specified in paragraph (l)(4)(i) and (ii) of this section.

(i) No later than July 29, 2016.

(ii) No later 180 days after notifying the Administrator before starting to use the CEMS in place of performance testing or fuel analysis to demonstrate compliance.

(5) Compliance with the applicable emissions limit shall be determined based on the 30-day rolling average of the hourly arithmetic average emissions rates using the continuous monitoring system outlet data. The 30-day rolling arithmetic average emission rate (lb/MMBtu) shall be calculated using the equations in EPA Reference Method 19 at 40 CFR part 60, appendix A–7, but substituting the mercury or HCl concentration for the pollutant concentrations normally used in Method 19.

(6) Collect CEMS hourly averages for all operating hours on a 30-day rolling average basis. Collect at least four CMS data values representing the four 15-minute periods in an hour, or at least two 15-minute data values during an hour when CMS calibration, quality assurance, or maintenance activities are being performed.

(7) The one-hour arithmetic averages required shall be expressed in lb/MMBtu and shall be used to calculate the boiler 30-day and 10-day rolling average emissions.

(8) You are allowed to substitute the use of the PM, mercury or HCl CEMS for the applicable fuel analysis, annual performance test, and operating limits specified in Table 4 to this subpart to demonstrate compliance with the PM, mercury or HCl emissions limit, and if you are using an acid gas wet scrubber or dry sorbent injection control technology to comply with the HCl emission limit, you are allowed to substitute the use of a sulfur dioxide (SO_2) CEMS for the applicable fuel analysis, annual performance test, and operating limits specified in Table 4 to this subpart to demonstrate compliance with HCl emissions limit.

(m) If your unit is subject to a HCl emission limit in Table 1 or 2 or Tables 11 through 15 to this subpart and you have an acid gas wet scrubber or dry sorbent injection control technology and you elect to use an SO_2 CEMS to demonstrate continuous compliance with the HCl emission limit, you must install the monitor at the outlet of the boiler or process heater, downstream of all emission control devices, and you must install, certify, operate, and maintain the CEMS according to either part 60 or part 75 of this chapter.

(1) The SO_2 CEMS must be installed by the compliance date specified in § 63.7495.

(2) For on-going quality assurance (QA), the SO_2 CEMS must meet either the applicable daily and quarterly requirements in Procedure 1 of appendix F of part 60 or the applicable daily, quarterly, and semiannual or annual requirements in sections 2.1 through 2.3 of appendix B to part 75 of this chapter, with the following addition: You must perform the linearity checks required in section 2.2 of appendix B to part 75

of this chapter if the SO_2 CEMS has a span value of 30 ppm or less.

(3) For a new unit, the initial performance evaluation shall be completed no later than July 30, 2013, or 180 days after the date of initial startup, whichever is later. For an existing unit, the initial performance evaluation shall be completed no later than July 29, 2016.

(4) For purposes of collecting SO_2 data, you must operate the SO_2 CEMS as specified in §63.7535(b). You must use all the data collected during all periods in calculating data averages and assessing compliance, except that you must exclude certain data as specified in §63.7535(c). Periods when SO_2 data are unavailable may constitute monitoring deviations as specified in §63.7535(d).

(5) Collect CEMS hourly averages for all operating hours on a 30-day rolling average basis.

(6) Use only unadjusted, quality-assured SO_2 concentration values in the emissions calculations; do not apply bias adjustment factors to the part 75 SO_2 data and do not use part 75 substitute data values.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7171, Jan. 31, 2013; 80 FR 72810, Nov. 20, 2015; 87 FR 60844, Oct. 6, 2022]

§63.7530 How do I demonstrate initial compliance with the emission limitations, fuel specifications and work practice standards?

(a) You must demonstrate initial compliance with each emission limit that applies to you by conducting initial performance tests and fuel analyses and establishing operating limits, as applicable, according to §63.7520, paragraphs (b) and (c) of this section, and Tables 5 and 7 to this subpart. The requirement to conduct a fuel analysis is not applicable for units that burn a single type of fuel, as specified by §63.7510(a)(2). If applicable, you must also install, operate, and maintain all applicable CMS (including CEMS, COMS, and CPMS) according to §63.7525.

(b) If you demonstrate compliance through performance stack testing, you must establish each site-specific operating limit in Table 4 to this subpart that applies to you according to the requirements in §63.7520, Table 7 to this subpart, and paragraph (b)(4) of this section, as applicable. You must also conduct fuel analyses according to §63.7521 and establish maximum fuel pollutant input levels according to paragraphs (b)(1) through (3) of this section, as applicable, and as specified in §63.7510(a)(2). (Note that §63.7510(a)(2) exempts certain fuels from the fuel analysis requirements.) However, if you switch fuel(s) and cannot show that the new fuel(s) does (do) not increase the chlorine, mercury, or TSM input into the unit through the results of fuel analysis, then you must repeat the performance test to demonstrate compliance while burning the new fuel(s).

(1) You must establish the maximum chlorine fuel input (Clinput) during the initial fuel analysis according to the procedures in paragraphs (b)(1)(i) through (iii) of this section.

(i) You must determine the fuel type or fuel mixture that you could burn in your boiler or process heater that has the highest content of chlorine.

(ii) During the fuel analysis for hydrogen chloride, you must determine the fraction of the total heat input for each fuel type burned (Qi) based on the fuel mixture that has the highest content of chlorine, and the average chlorine concentration of each fuel type burned (Ci).

(iii) You must establish a maximum chlorine input level using Equation 7 of this section.

$$Clinput = \sum_{i=1}^{n} (Ci \times Qi) \quad \text{(Eq. 7)}$$

Where:

Clinput = Maximum amount of chlorine entering the boiler or process heater

through fuels burned in units of pounds per million Btu.

Ci = Arithmetic average concentration of chlorine in fuel type, i, analyzed according to §63.7521, in units of pounds per million Btu.

Qi = Fraction of total heat input from fuel type, i, based on the fuel mixture that has the highest content of chlorine during the initial compliance test. If you do not burn multiple fuel types during the performance testing, it is not necessary to determine the value of this term. Insert a value of ''1'' for Qi. For continuous compliance demonstration, the actual fraction of the fuel burned during the month should be used.

n = Number of different fuel types burned in your boiler or process heater for the mixture that has the highest content of chlorine.

(2) You must establish the maximum mercury fuel input level (Mercuryinput) during the initial fuel analysis using the procedures in paragraphs (b)(2)(i) through (iii) of this section.

(i) You must determine the fuel type or fuel mixture that you could burn in your boiler or process heater that has the highest content of mercury.

(ii) During the compliance demonstration for mercury, you must determine the fraction of total heat input for each fuel burned (Qi) based on the fuel mixture that has the highest content of mercury, and the average mercury concentration of each fuel type burned (HGi).

(iii) You must establish a maximum mercury input level using Equation 8 of this section.

$$Mercuryinput = \sum_{i=1}^{n} (HGi \times Qi) \qquad \text{(Eq. 8)}$$

Where:

Mercuryinput = Maximum amount of mercury entering the boiler or process heater through fuels burned in units of pounds per million Btu.

HGi = Arithmetic average concentration of mercury in fuel type, i, analyzed according to §63.7521, in units of pounds per million Btu.

Qi = Fraction of total heat input from fuel type, i, based on the fuel mixture that has the highest mercury content during the initial compliance test. If you do not burn multiple fuel types during the performance test, it is not necessary to determine the value of this term. Insert a value of ''1'' for Qi. For continuous compliance demonstration, the actual fraction of the fuel burned during the month should be used.

n = Number of different fuel types burned in your boiler or process heater for the mixture that has the highest content of mercury.

(3) If you opt to comply with the alternative TSM limit, you must establish the maximum TSM fuel input (TSMinput) for solid or liquid fuels during the initial fuel analysis according to the procedures in paragraphs (b)(3)(i) through (iii) of this section.

(i) You must determine the fuel type or fuel mixture that you could burn in your boiler or process heater that has the highest content of TSM.

(ii) During the fuel analysis for TSM, you must determine the fraction of the total heat input for each fuel type burned (Qi) based on the fuel mixture that has the highest content of TSM, and the average TSM concentration of each fuel type burned (TSMi).

(iii) You must establish a maximum TSM input level using Equation 9 of this section.

$$TSMinput = \sum_{i=1}^{n} (TSMi \times Qi) \qquad \text{(Eq. 9)}$$

Where:

TSMinput = Maximum amount of TSM entering the boiler or process heater through fuels burned in units of pounds per million Btu.

TSMi = Arithmetic average concentration of TSM in fuel type, i, analyzed according to § 63.7521, in units of pounds per million Btu.

Qi = Fraction of total heat input from fuel type, i, based on the fuel mixture that has the highest content of TSM during the initial compliance test. If you do not burn multiple fuel types during the performance testing, it is not necessary to determine the value of this term. Insert a value of ''1'' for Qi. For continuous compliance demonstration, the actual fraction of the fuel burned during the month should be used.

n = Number of different fuel types burned in your boiler or process heater for the mixture that has the highest content of TSM.

(4) You must establish parameter operating limits according to paragraphs (b)(4)(i) through (ix) of this section. As indicated in Table 4 to this subpart, you are not required to establish and comply with the operating parameter limits when you are using a CEMS to monitor and demonstrate compliance with the applicable emission limit for that control device parameter.

(i) For a wet acid gas scrubber, you must establish the minimum scrubber effluent pH and liquid flow rate as defined in § 63.7575, as your operating limits during the performance test during which you demonstrate compliance with your applicable limit. If you use a wet scrubber and you conduct separate performance tests for HCl and mercury emissions, you must establish one set of minimum scrubber effluent pH, liquid flow rate, and pressure drop operating limits. The minimum scrubber effluent pH operating limit must be established during the HCl performance test. If you conduct multiple performance tests, you must set the minimum liquid flow rate operating limit at the higher of the minimum values established during the performance tests.

(ii) For any particulate control device (e.g., ESP, particulate wet scrubber, fabric filter) for which you use a PM CPMS, you must establish your PM CPMS operating limit and determine compliance with it according to paragraphs (b)(4)(ii)(A) through (F) of this section.

(A) Determine your operating limit as the average PM CPMS output value recorded during the most recent performance test run demonstrating compliance with the filterable PM emission limit or at the PM CPMS output value corresponding to 75 percent of the emission limit if your PM performance test demonstrates compliance below 75 percent of the emission limit. You must verify an existing or establish a new operating limit after each repeated performance test. You must repeat the performance test annually and reassess and adjust the site-specific operating limit in accordance with the results of the performance test.

(*1*) Your PM CPMS must provide a 4–20 milliamp output and the establishment of its relationship to manual reference method measurements must be determined in units of milliamps.

(*2*) Your PM CPMS operating range must be capable of reading PM concentrations from zero to a level equivalent to at least two times your allowable emission limit. If your PM CPMS is an auto-ranging instrument capable of multiple scales, the primary range of the instrument must be capable of reading PM concentration from zero to a level equivalent to two times your allowable emission limit.

(*3*) During the initial performance test or any such subsequent performance test that demonstrates compliance with the PM limit, record and average all milliamp output values from the PM CPMS for the periods corresponding to the compliance test runs (e.g., average all your PM CPMS output values for three corresponding 2-hour Method 5I test runs).

(B) If the average of your three PM performance test runs are below 75 percent of your PM emission limit, you must calculate an operating limit by establishing a relationship of PM CPMS signal to PM concentration using the PM CPMS instrument zero, the average PM CPMS values corresponding to the three compliance test runs, and the average PM concentration from the Method 5 or performance test with the procedures in paragraphs (b)(4)(ii)(B)(*1*) through (*4*) of this section.

(*1*) Determine your instrument zero output with one of the following procedures:

(*i*) Zero point data for *in-situ* instruments should be obtained by removing the instrument from the stack and monitoring ambient air on a test bench.

(*ii*) Zero point data for *extractive* instruments should be obtained by removing the extractive probe from the stack and drawing in clean ambient air.

(*iii*) The zero point may also be established by performing manual reference method measurements when the flue gas is free of PM emissions or contains very low PM concentrations (e.g., when your process is not operating, but the fans are operating or your source is combusting only natural gas) and plotting these with the compliance data to find the zero intercept.

(*iv*) If none of the steps in paragraphs (b)(4)(ii)(B)(*1*)(*i*) through (*iii*) of this section are possible, you must use a zero output value provided by the manufacturer.

(*2*) Determine your PM CPMS instrument average in milliamps, and the average of your corresponding three PM compliance test runs, using equation 10.

$$\bar{x} = \frac{1}{n}\sum_{i=1}^{n} X_1 \; , \bar{y} = \frac{1}{n}\sum_{i=1}^{n} Y_1 \qquad \text{(Eq. 10)}$$

Where:

X_1 = the PM CPMS data points for the three runs constituting the performance test,

Y_1 = the PM concentration value for the three runs constituting the performance test, and

n = the number of data points.

(*3*) With your instrument zero expressed in milliamps, your three run average PM CPMS milliamp value, and your three run average PM concentration from your three compliance tests, determine a relationship of lb/MMBtu per milliamp with equation 11.

$$\mathrm{R} = \frac{Y_1}{\left(X_1 - z\right)} \qquad \text{(Eq. 11)}$$

Where:

R = the relative lb/MMBtu per milliamp for your PM CPMS,

Y_1 = the three run average lb/MMBtu PM concentration,

X_1 = the three run average milliamp output from you PM CPMS, and

z = the milliamp equivalent of your instrument zero determined from (B)(i).

(*4*) Determine your source specific 30-day rolling average operating limit using the lb/MMBtu per milliamp value from Equation 11 in equation 12, below. This sets your operating limit at the PM CPMS output value corresponding to 75 percent of your emission limit.

$$O_1 = z + \frac{0.75(L)}{R} \qquad \text{(Eq. 12)}$$

Where:

O_1 = the operating limit for your PM CPMS on a 30-day rolling average, in milliamps.

L = your source emission limit expressed in lb/MMBtu,

z = your instrument zero in milliamps, determined from (B)(i), and

R = the relative lb/MMBtu per milliamp for your PM CPMS, from Equation 11.

(C) If the average of your three PM compliance test runs is at or above 75 percent of your PM emission limit you must determine your 30-day rolling average operating limit by averaging the PM CPMS milliamp output corresponding to your three PM performance test runs that demonstrate compliance with the emission limit using equation 13 and you must submit all compliance test and PM CPMS data according to the reporting requirements in paragraph (b)(4)(ii)(F) of this section.

$$O_h = \frac{1}{n}\sum_{i=1}^{n} X_1 \qquad \text{(Eq. 13)}$$

Where:

X_1 = the PM CPMS data points for all runs i,
n = the number of data points, and
O_h = your site specific operating limit, in milliamps.

(D) To determine continuous compliance, you must record the PM CPMS output data for all periods when the process is operating and the PM CPMS is not out-of-control. You must demonstrate continuous compliance by using all quality-assured hourly average data collected by the PM CPMS for all operating hours to calculate the arithmetic average operating parameter in units of the operating limit (milliamps) on a 30-day rolling average basis, updated at the end of each new operating hour. Use Equation 14 to determine the 30-day rolling average.

$$30-\text{day} = \frac{\sum_{i=1}^{n} Hpv_i}{n} \qquad \text{(Eq. 14)}$$

Where:

30-day = 30-day average.
Hpvi = is the hourly parameter value for hour i
n = is the number of valid hourly parameter values collected over the previous 30 operating days.

(E) Use EPA Method 5 of appendix A to part 60 of this chapter to determine PM emissions. For each performance test, conduct three separate runs under the conditions that exist when the affected source is operating at the highest load or capacity level reasonably expected to occur. Conduct each test run to collect a minimum sample volume specified in Table 1 or 2 or Tables 11 through 15 to this subpart, as applicable, for determining compliance with a new source limit or an existing source limit. Calculate the average of the results from three runs to determine compliance. You need not determine the PM collected in the impingers (''back half'') of the Method 5 particulate sampling train to demonstrate compliance with the PM standards in this subpart. This shall not preclude the permitting authority from requiring a determination of the ''back half'' for other purposes.

(F) For PM performance test reports used to set a PM CPMS operating limit, the electronic submission of the test report must also include the make and model of the PM CPMS instrument, serial number of the instrument, analytical principle of the instrument (*e.g.* beta attenuation), span of the instruments primary analytical range, milliamp value equivalent to the instrument zero output, technique by which this zero value was determined,

and the average milliamp signals corresponding to each PM compliance test run.

(iii) For a particulate wet scrubber, you must establish the minimum pressure drop and liquid flow rate as defined in §63.7575, as your operating limits during the three-run performance test during which you demonstrate compliance with your applicable limit. If you use a wet scrubber and you conduct separate performance tests for PM and TSM emissions, you must establish one set of minimum scrubber liquid flow rate and pressure drop operating limits. If you conduct multiple performance tests, you must set the minimum liquid flow rate and pressure drop operating limits at the higher of the minimum values established during the performance tests.

(iv) For an electrostatic precipitator (ESP) operated with a wet scrubber, you must establish the minimum total secondary electric power input, as defined in §63.7575, as your operating limit during the three-run performance test during which you demonstrate compliance with your applicable limit. (These operating limits do not apply to ESP that are operated as dry controls without a wet scrubber.)

(v) For a dry scrubber, you must establish the minimum sorbent injection rate for each sorbent, as defined in §63.7575, as your operating limit during the three-run performance test during which you demonstrate compliance with your applicable limit.

(vi) For activated carbon injection, you must establish the minimum activated carbon injection rate, as defined in §63.7575, as your operating limit during the three-run performance test during which you demonstrate compliance with your applicable limit.

(vii) The operating limit for boilers or process heaters with fabric filters that demonstrate continuous compliance through bag leak detection systems is that a bag leak detection system be installed according to the requirements in §63.7525, and that each fabric filter must be operated such that the bag leak detection system alert is not activated more than 5 percent of the operating time during a 6-month period.

(viii) For a minimum oxygen level, if you conduct multiple performance tests, you must set the minimum oxygen level at the lower of the minimum values established during the performance tests.

(ix) The operating limit for boilers or process heaters that demonstrate continuous compliance with the HCl emission limit using a SO_2 CEMS is to install and operate the SO_2 according to the requirements in §63.7525(m) establish a maximum SO_2 emission rate equal to the highest hourly average SO_2 measurement during the most recent three-run performance test for HCl.

(c) If you elect to demonstrate compliance with an applicable emission limit through fuel analysis, you must conduct fuel analyses according to §63.7521 and follow the procedures in paragraphs (c)(1) through (5) of this section.

(1) If you burn more than one fuel type, you must determine the fuel mixture you could burn in your boiler or process heater that would result in the maximum emission rates of the pollutants that you elect to demonstrate compliance through fuel analysis.

(2) You must determine the 90th percentile confidence level fuel pollutant concentration of the composite samples analyzed for each fuel type using the one-sided t-statistic test described in Equation 15 of this section.

$$P90 = mean + (SD \times t) \quad \text{(Eq. 15)}$$

Where:

P90 = 90th percentile confidence level pollutant concentration, in pounds per million Btu.

Mean = Arithmetic average of the fuel pollutant concentration in the fuel samples analyzed according to §63.7521, in units of pounds per million Btu.

SD = Standard deviation of the mean of pollutant concentration in the fuel samples

analyzed according to § 63.7521, in units of pounds per million Btu. SD is calculated as the sample standard deviation divided by the square root of the number of samples.

t = t distribution critical value for 90th percentile ($t_{0.1}$) probability for the appropriate degrees of freedom (number of samples minus one) as obtained from a t-Distribution Critical Value Table.

(3) To demonstrate compliance with the applicable emission limit for HCl, the HCl emission rate that you calculate for your boiler or process heater using Equation 16 of this section must not exceed the applicable emission limit for HCl.

$$HCl = \sum_{i=1}^{n} \left(Ci90 \times Qi \times 1.028 \right) \qquad \text{(Eq. 16)}$$

Where:

HCl = HCl emission rate from the boiler or process heater in units of pounds per million Btu.

Ci90 = 90th percentile confidence level concentration of chlorine in fuel type, i, in units of pounds per million Btu as calculated according to Equation 15 of this section.

Qi = Fraction of total heat input from fuel type, i, based on the fuel mixture that has the highest content of chlorine. If you do not burn multiple fuel types, it is not necessary to determine the value of this term. Insert a value of ''1'' for Qi. For continuous compliance demonstration, the actual fraction of the fuel burned during the month should be used.

n = Number of different fuel types burned in your boiler or process heater for the mixture that has the highest content of chlorine.

1.028 = Molecular weight ratio of HCl to chlorine.

(4) To demonstrate compliance with the applicable emission limit for mercury, the mercury emission rate that you calculate for your boiler or process heater using Equation 17 of this section must not exceed the applicable emission limit for mercury.

$$Mercury = \sum_{i=1}^{n} \left(Hgi90 \times Qi \right) \qquad \text{(Eq. 17)}$$

Where:

Mercury = Mercury emission rate from the boiler or process heater in units of pounds per million Btu.

Hgi90 = 90th percentile confidence level concentration of mercury in fuel, i, in units of pounds per million Btu as calculated according to Equation 15 of this section.

Qi = Fraction of total heat input from fuel type, i, based on the fuel mixture that has the highest mercury content. If you do not burn multiple fuel types, it is not necessary to determine the value of this term. Insert a value of ''1'' for Qi. For continuous compliance demonstration, the actual fraction of the fuel burned during the month should be used.

n = Number of different fuel types burned in your boiler or process heater for the mixture that has the highest mercury content.

(5) To demonstrate compliance with the applicable emission limit for TSM for solid or liquid fuels, the TSM emission rate that you calculate for your boiler or process heater from solid fuels using Equation 18 of this section must not exceed the applicable emission limit for TSM.

$$Metals = \sum_{i=1}^{n} (TSM90i \times Qi) \qquad \text{(Eq. 18)}$$

Where:

Metals = TSM emission rate from the boiler or process heater in units of pounds per million Btu.

TSMi90 = 90th percentile confidence level concentration of TSM in fuel, i, in units of pounds per million Btu as calculated according to Equation 15 of this section.

Qi = Fraction of total heat input from fuel type, i, based on the fuel mixture that has the highest TSM content. If you do not burn multiple fuel types, it is not necessary to determine the value of this term. Insert a value of ''1'' for Qi. For continuous compliance demonstration, the actual fraction of the fuel burned during the month should be used.

n = Number of different fuel types burned in your boiler or process heater for the mixture that has the highest TSM content.

(d)[Reserved]

(e) You must include with the Notification of Compliance Status a signed certification that either the energy assessment was completed according to Table 3 to this subpart, and that the assessment is an accurate depiction of your facility at the time of the assessment, or that the maximum number of on-site technical hours specified in the definition of energy assessment applicable to the facility has been expended.

(f) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in §63.7545(e).

(g) If you elect to demonstrate that a gaseous fuel meets the specifications of another gas 1 fuel as defined in §63.7575, you must conduct an initial fuel specification analyses according to §63.7521(f) through (i) and according to the frequency listed in §63.7540(c) and maintain records of the results of the testing as outlined in §63.7555(g). For samples where the initial mercury specification has not been exceeded, you will include a signed certification with the Notification of Compliance Status that the initial fuel specification test meets the gas specification outlined in the definition of other gas 1 fuels.

(h) If you own or operate a unit subject to emission limits in Table 1 or 2 or Tables 11 through 15 to this subpart, you must meet the work practice standard according to Table 3 to this subpart. During startup and shutdown, you must only follow the work practice standards according to items 5 and 6 of Table 3 to this subpart.

(i) If you opt to comply with the alternative SO_2 CEMS operating limit in Tables 4 and 8 to this subpart, you may do so only if your affected boiler or process heater:

(1) Has a system using wet scrubber or dry sorbent injection and SO_2 CEMS installed on the unit; and

(2) At all times, you operate the wet scrubber or dry sorbent injection for acid gas control on the unit consistent with §63.7500(a)(3); and

(3) You establish a unit-specific maximum SO_2 operating limit by collecting the maximum hourly SO_2 emission rate on the SO_2 CEMS during the paired 3-run test for HCl. The maximum SO_2 operating limit is equal to the highest hourly average SO_2 concentration measured during the HCl performance test.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7174, Jan. 31, 2013; 80 FR 72811, Nov. 20, 2015; 87 FR 60845, Oct. 6, 2022]

§63.7533 Can I use efficiency credits earned from implementation of energy conservation measures to comply with this subpart?

(a) If you elect to comply with the alternative equivalent output-based emission limits, instead of the heat input-based limits listed in Table 2 or 15 to this subpart, and you want to take credit for implementing energy conservation measures identified in an energy assessment, you may demonstrate compliance using efficiency credits according to the procedures in this section. You may use this compliance approach for an existing affected boiler for demonstrating initial compliance according to §63.7522(e) and for

demonstrating monthly compliance according to § 63.7522(f). Owners or operators using this compliance approach must establish an emissions benchmark, calculate and document the efficiency credits, develop an Implementation Plan, comply with the general reporting requirements, and apply the efficiency credit according to the procedures in paragraphs (b) through (f) of this section. You cannot use this compliance approach for a new or reconstructed affected boiler. Additional guidance from the Department of Energy on efficiency credits is available at *https://www.epa.gov/ttn/atw/boiler/boilerpg.html*.

(b) For each existing affected boiler for which you intend to apply emissions credits, establish a benchmark from which emission reduction credits may be generated by determining the actual annual fuel heat input to the affected boiler before initiation of an energy conservation activity to reduce energy demand (*i.e.*, fuel usage) according to paragraphs (b)(1) through (4) of this section. The benchmark shall be expressed in trillion Btu per year heat input.

(1) The benchmark from which efficiency credits may be generated shall be determined by using the most representative, accurate, and reliable process available for the source. The benchmark shall be established for a one-year period before the date that an energy demand reduction occurs, unless it can be demonstrated that a different time period is more representative of historical operations.

(2) Determine the starting point from which to measure progress. Inventory all fuel purchased and generated onsite (off-gases, residues) in physical units (MMBtu, million cubic feet, etc.).

(3) Document all uses of energy from the affected boiler. Use the most recent data available.

(4) Collect non-energy related facility and operational data to normalize, if necessary, the benchmark to current operations, such as building size, operating hours, etc. If possible, use actual data that are current and timely rather than estimated data.

(c) Efficiency credits can be generated if the energy conservation measures were implemented after January 1, 2008 and if sufficient information is available to determine the appropriate value of credits.

(1) The following emission points cannot be used to generate efficiency credits:

(i) Energy conservation measures implemented on or before January 1, 2008, unless the level of energy demand reduction is increased after January 1, 2008, in which case credit will be allowed only for change in demand reduction achieved after January 1, 2008.

(ii) Efficiency credits on shut-down boilers. Boilers that are shut down cannot be used to generate credits unless the facility provides documentation linking the permanent shutdown to energy conservation measures identified in the energy assessment. In this case, the bench established for the affected boiler to which the credits from the shutdown will be applied must be revised to include the benchmark established for the shutdown boiler.

(2) For all points included in calculating emissions credits, the owner or operator shall:

(i) Calculate annual credits for all energy demand points. Use Equation 19 to calculate credits. Energy conservation measures that meet the criteria of paragraph (c)(1) of this section shall not be included, except as specified in paragraph (c)(1)(i) of this section.

(3) Credits are generated by the difference between the benchmark that is established for each affected boiler, and the actual energy demand reductions from energy conservation measures implemented after January 1, 2008. Credits shall be calculated using Equation 19 of this section as follows:

(i) The overall equation for calculating credits is:

$$ECredits = \left(\sum_{i=1}^{n} EIS_{iactual} \right) \div EI_{baseline} \qquad \text{(Eq. 19)}$$

Where:

ECredits = Energy Input Savings for all energy conservation measures implemented for an affected boiler, expressed as a decimal fraction of the baseline energy input.

$EIS_{iactual}$ = Energy Input Savings for each energy conservation measure, i, implemented for an affected boiler, million Btu per year.

$EI_{baseline}$ = Energy Input baseline for the affected boiler, million Btu per year.

n = Number of energy conservation measures included in the efficiency credit for the affected boiler.

(ii) [Reserved]

(d) The owner or operator shall develop, and submit for approval upon request by the Administrator, an Implementation Plan containing all of the information required in this paragraph for all boilers to be included in an efficiency credit approach. The Implementation Plan shall identify all existing affected boilers to be included in applying the efficiency credits. The Implementation Plan shall include a description of the energy conservation measures implemented and the energy savings generated from each measure and an explanation of the criteria used for determining that savings. If requested, you must submit the implementation plan for efficiency credits to the Administrator for review and approval no later than 180 days before the date on which the facility intends to demonstrate compliance using the efficiency credit approach.

(e) The emissions rate as calculated using Equation 20 in paragraph (f) of this section from each existing boiler participating in the efficiency credit option must be in compliance with the limits in Table 2 or 15 to this subpart at all times the affected unit is subject to numeric emission limits, following the compliance date specified in § 63.7495.

(f) You must use Equation 20 of this paragraph (f) to demonstrate initial compliance by demonstrating that the emissions from the affected boiler participating in the efficiency credit compliance approach do not exceed the emission limits in Table 2 or 15 to this subpart.

Equation 20 to paragraph (f)

$$E_{adj} = E_m \times (1 - ECredits) \quad \text{(Eq. 20)}$$

Where:

E_{adj} = Emission level adjusted by applying the efficiency credits earned, lb per million Btu steam output (or lb per MWh) for the affected boiler.

E_m = Emissions measured during the performance test, lb per million Btu steam output (or lb per MWh) for the affected boiler.

ECredits = Efficiency credits from Equation 19 to paragraph (c)(3)(i) of this section for the affected boiler.

(g) As part of each compliance report submitted as required under § 63.7550, you must include documentation that the energy conservation measures implemented continue to generate the credit for use in demonstrating compliance with the emission limits.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7178, Jan. 31, 2013; 80 FR 72812, Nov. 20, 2015; 87 FR 60845, Oct. 6, 2022]

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.7535 Is there a minimum amount of monitoring data I must obtain?

(a) You must monitor and collect data according to this section and the site-specific monitoring plan required by § 63.7505(d).

(b) You must operate the monitoring system and collect data at all required intervals at all times that each boiler or process heater is operating and compliance is required, except for periods of monitoring system malfunctions or

out of control periods (see § 63.8(c)(7) of this part), and required monitoring system quality assurance or control activities, including, as applicable, calibration checks, required zero and span adjustments, and scheduled CMS maintenance as defined in your site-specific monitoring plan. A monitoring system malfunction is any sudden, infrequent, not reasonably preventable failure of the monitoring system to provide valid data. Monitoring system failures that are caused in part by poor maintenance or careless operation are not malfunctions. You are required to complete monitoring system repairs in response to monitoring system malfunctions or out-of-control periods and to return the monitoring system to operation as expeditiously as practicable.

(c) You may not use data recorded during periods of startup and shutdown, monitoring system malfunctions or out-of-control periods, repairs associated with monitoring system malfunctions or out-of-control periods, or required monitoring system quality assurance or control activities in data averages and calculations used to report emissions or operating levels. You must record and make available upon request results of CMS performance audits and dates and duration of periods when the CMS is out of control to completion of the corrective actions necessary to return the CMS to operation consistent with your site-specific monitoring plan. You must use all the data collected during all other periods in assessing compliance and the operation of the control device and associated control system.

(d) Except for periods of monitoring system malfunctions, repairs associated with monitoring system malfunctions, and required monitoring system quality assurance or quality control activities (including, as applicable, system accuracy audits, calibration checks, and required zero and span adjustments), failure to collect required data is a deviation of the monitoring requirements. In calculating monitoring results, do not use any data collected during periods of startup and shutdown, when the monitoring system is out of control as specified in your site-specific monitoring plan, while conducting repairs associated with periods when the monitoring system is out of control, or while conducting required monitoring system quality assurance or quality control activities. You must calculate monitoring results using all other monitoring data collected while the process is operating. You must report all periods when the monitoring system is out of control in your semi-annual report.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7179, Jan. 31, 2013; 80 FR 72812, Nov. 20, 2015]

§ 63.7540 How do I demonstrate continuous compliance with the emission limitations, fuel specifications and work practice standards?

(a) You must demonstrate continuous compliance with each emission limit in Tables 1 and 2 or 11 through 15 to this subpart, the work practice standards in Table 3 to this subpart, and the operating limits in Table 4 to this subpart that applies to you according to the methods specified in Table 8 to this subpart and paragraphs (a)(1) through (19) of this section.

(1) Following the date on which the initial compliance demonstration is completed or is required to be completed under §§ 63.7 and 63.7510, whichever date comes first, operation above the established maximum or below the established minimum operating limits shall constitute a deviation of established operating limits listed in Table 4 of this subpart except during performance tests conducted to determine compliance with the emission limits or to establish new operating limits. Operating limits must be confirmed or reestablished during performance tests.

(2) As specified in § 63.7555(d), you must keep records of the type and amount of all fuels burned in each boiler or process heater during the reporting period to demonstrate that all fuel types and mixtures of fuels burned would result in either of the following:

(i) Equal to or lower emissions of HCl, mercury, and TSM than the applicable emission limit for each pollutant, if you demonstrate compliance through fuel analysis.

(ii) Equal to or lower fuel input of chlorine, mercury, and TSM than the maximum values calculated during the

last performance test, if you demonstrate compliance through performance testing.

(3) If you demonstrate compliance with an applicable HCl emission limit through fuel analysis for a solid or liquid fuel and you plan to burn a new type of solid or liquid fuel, you must recalculate the HCl emission rate using Equation 16 of § 63.7530 according to paragraphs (a)(3)(i) through (iii) of this section. You are not required to conduct fuel analyses for the fuels described in § 63.7510(a)(2)(i) through (iii). You may exclude the fuels described in § 63.7510(a)(2)(i) through (iii) when recalculating the HCl emission rate.

(i) You must determine the chlorine concentration for any new fuel type in units of pounds per million Btu, based on supplier data or your own fuel analysis, according to the provisions in your site-specific fuel analysis plan developed according to § 63.7521(b).

(ii) You must determine the new mixture of fuels that will have the highest content of chlorine.

(iii) Recalculate the HCl emission rate from your boiler or process heater under these new conditions using Equation 16 of § 63.7530. The recalculated HCl emission rate must be less than the applicable emission limit.

(4) If you demonstrate compliance with an applicable HCl emission limit through performance testing and you plan to burn a new type of fuel or a new mixture of fuels, you must recalculate the maximum chlorine input using Equation 7 of § 63.7530. If the results of recalculating the maximum chlorine input using Equation 7 of § 63.7530 are greater than the maximum chlorine input level established during the previous performance test, then you must conduct a new performance test within 60 days of burning the new fuel type or fuel mixture according to the procedures in § 63.7520 to demonstrate that the HCl emissions do not exceed the emission limit. You must also establish new operating limits based on this performance test according to the procedures in § 63.7530(b). In recalculating the maximum chlorine input and establishing the new operating limits, you are not required to conduct fuel analyses for and include the fuels described in § 63.7510(a)(2)(i) through (iii).

(5) If you demonstrate compliance with an applicable mercury emission limit through fuel analysis, and you plan to burn a new type of fuel, you must recalculate the mercury emission rate using Equation 17 of § 63.7530 according to the procedures specified in paragraphs (a)(5)(i) through (iii) of this section. You are not required to conduct fuel analyses for the fuels described in § 63.7510(a)(2)(i) through (iii). You may exclude the fuels described in § 63.7510(a)(2)(i) through (iii) when recalculating the mercury emission rate.

(i) You must determine the mercury concentration for any new fuel type in units of pounds per million Btu, based on supplier data or your own fuel analysis, according to the provisions in your site-specific fuel analysis plan developed according to § 63.7521(b).

(ii) You must determine the new mixture of fuels that will have the highest content of mercury.

(iii) Recalculate the mercury emission rate from your boiler or process heater under these new conditions using Equation 17 of § 63.7530. The recalculated mercury emission rate must be less than the applicable emission limit.

(6) If you demonstrate compliance with an applicable mercury emission limit through performance testing, and you plan to burn a new type of fuel or a new mixture of fuels, you must recalculate the maximum mercury input using Equation 8 of § 63.7530. If the results of recalculating the maximum mercury input using Equation 8 of § 63.7530 are higher than the maximum mercury input level established during the previous performance test, then you must conduct a new performance test within 60 days of burning the new fuel type or fuel mixture according to the procedures in § 63.7520 to demonstrate that the mercury emissions do not exceed the emission limit. You must also establish new operating limits based on this performance test according to the procedures in § 63.7530(b). You are not required to conduct fuel analyses for the fuels described in § 63.7510(a)(2)(i) through (iii). You may exclude the fuels described in § 63.7510(a)(2)(i) through (iii) when recalculating the mercury emission rate.

(7) If your unit is controlled with a fabric filter, and you demonstrate continuous compliance using a bag leak detection system, you must initiate corrective action within 1 hour of a bag leak detection system alert and complete corrective actions as soon as practical, and operate and maintain the fabric filter system such that the periods which would cause an alert are no more than 5 percent of the operating time during a 6-month period. You must also keep records of the date, time, and duration of each alert, the time corrective action was initiated and completed, and a brief description of the cause of the alert and the corrective action taken. You must also record the percent of the operating time during each 6-month period that the conditions exist for an alert. In calculating this operating time percentage, if inspection of the fabric filter demonstrates that no corrective action is required, no alert time is counted. If corrective action is required, each alert shall be counted as a minimum of 1 hour. If you take longer than 1 hour to initiate corrective action, the alert time shall be counted as the actual amount of time taken to initiate corrective action.

(8) To demonstrate compliance with the applicable alternative CO CEMS emission limit listed in Table 1 or 2 or Tables 11 through 15 to this subpart, you must meet the requirements in paragraphs (a)(8)(i) through (iv) of this section.

(i) Continuously monitor CO according to §§ 63.7525(a) and 63.7535.

(ii) Maintain a CO emission level below or at your applicable alternative CO CEMS-based standard in Table 1 or 2 or Tables 11 through 15 to this subpart at all times the affected unit is subject to numeric emission limits.

(iii) Keep records of CO levels according to § 63.7555(b).

(iv) You must record and make available upon request results of CO CEMS performance audits, dates and duration of periods when the CO CEMS is out of control to completion of the corrective actions necessary to return the CO CEMS to operation consistent with your site-specific monitoring plan.

(9) The owner or operator of a boiler or process heater using a PM CPMS or a PM CEMS to meet requirements of this subpart shall install, certify (PM CEMS only), operate, and maintain the PM CPMS or PM CEMS in accordance with your site-specific monitoring plan as required in § 63.7505(d).

(10) If your boiler or process heater has a heat input capacity of 10 million Btu per hour or greater, you must conduct an annual tune-up of the boiler or process heater to demonstrate continuous compliance as specified in paragraphs (a)(10)(i) through (vi) of this section. You must conduct the tune-up while burning the type of fuel (or fuels in case of units that routinely burn a mixture) that provided the majority of the heat input to the boiler or process heater over the 12 months prior to the tune-up. This frequency does not apply to limited-use boilers and process heaters, as defined in § 63.7575, or units with continuous oxygen trim systems that maintain an optimum air to fuel ratio.

(i) As applicable, inspect the burner, and clean or replace any components of the burner as necessary (you may perform the burner inspection any time prior to the tune-up or delay the burner inspection until the next scheduled unit shutdown). Units that produce electricity for sale may delay the burner inspection until the first outage, not to exceed 36 months from the previous inspection. At units where entry into a piece of process equipment or into a storage vessel is required to complete the tune-up inspections, inspections are required only during planned entries into the storage vessel or process equipment;

(ii) Inspect the flame pattern, as applicable, and adjust the burner as necessary to optimize the flame pattern. The adjustment should be consistent with the manufacturer's specifications, if available;

(iii) Inspect the system controlling the air-to-fuel ratio, as applicable, and ensure that it is correctly calibrated and functioning properly (you may delay the inspection until the next scheduled unit shutdown). Units that produce electricity for sale may delay the inspection until the first outage, not to exceed 36 months from the previous inspection;

(iv) Optimize total emissions of CO. This optimization should be consistent

with the manufacturer's specifications, if available, and with any NO_X requirement to which the unit is subject;

(v) Measure the concentrations in the effluent stream of CO in parts per million, by volume, and oxygen in volume percent, before and after the adjustments are made (measurements may be either on a dry or wet basis, as long as it is the same basis before and after the adjustments are made). Measurements may be taken using a portable CO analyzer; and

(vi) Maintain on-site and submit, if requested by the Administrator, a report containing the information in paragraphs (a)(10)(vi)(A) through (C) of this section,

(A) The concentrations of CO in the effluent stream in parts per million by volume, and oxygen in volume percent, measured at high fire or typical operating load, before and after the tune-up of the boiler or process heater;

(B) A description of any corrective actions taken as a part of the tune-up; and

(C) The type and amount of fuel used over the 12 months prior to the tune-up, but only if the unit was physically and legally capable of using more than one type of fuel during that period. Units sharing a fuel meter may estimate the fuel used by each unit.

(11) If your boiler or process heater has a heat input capacity of less than 10 million Btu per hour (except as specified in paragraph (a)(12) of this section), you must conduct a biennial tune-up of the boiler or process heater as specified in paragraphs (a)(10)(i) through (vi) of this section to demonstrate continuous compliance.

(12) If your boiler or process heater has a continuous oxygen trim system that maintains an optimum air to fuel ratio, or a heat input capacity of less than or equal to 5 million Btu per hour and the unit is in the units designed to burn gas 1; units designed to burn gas 2 (other); or units designed to burn light liquid subcategories, or meets the definition of limited-use boiler or process heater in § 63.7575, you must conduct a tune-up of the boiler or process heater every 5 years as specified in paragraphs (a)(10)(i) through (vi) of this section to demonstrate continuous compliance. You may delay the burner inspection specified in paragraph (a)(10)(i) of this section until the next scheduled or unscheduled unit shutdown, but you must inspect each burner at least once every 72 months. If an oxygen trim system is utilized on a unit without emission standards to reduce the tune-up frequency to once every 5 years, set the oxygen level no lower than the oxygen concentration measured during the most recent tune-up.

(13) If the unit is not operating on the required date for a tune-up, the tune-up must be conducted within 30 calendar days of startup.

(14) If you are using a CEMS measuring mercury emissions to meet requirements of this subpart you must install, certify, operate, and maintain the mercury CEMS as specified in paragraphs (a)(14)(i) and (ii) of this section.

(i) Operate the mercury CEMS in accordance with performance specification 12A of 40 CFR part 60, appendix B or operate a sorbent trap based integrated monitor in accordance with performance specification 12B of 40 CFR part 60, appendix B. The duration of the performance test must be 30 operating days if you specified a 30 operating day basis in § 63.7545(e)(2)(iii) for mercury CEMS or it must be 720 hours if you specified a 720 hour basis in § 63.7545(e)(2)(iii) for mercury CEMS. For each day in which the unit operates, you must obtain hourly mercury concentration data, and stack gas volumetric flow rate data.

(ii) If you are using a mercury CEMS, you must install, operate, calibrate, and maintain an instrument for continuously measuring and recording the mercury mass emissions rate to the atmosphere according to the requirements of performance specifications 6 and 12A of 40 CFR part 60, appendix B, and quality assurance procedure 6 of 40 CFR part 60, appendix F.

(15) If you are using a CEMS to measure HCl emissions to meet requirements of this subpart, you must install, certify, operate, and maintain the HCl CEMS as specified in paragraphs (a)(15)(i) and (ii) of this section. This option for an affected unit takes effect on the date of approval of a site-specific monitoring plan.

(i) Operate the continuous emissions monitoring system in accordance with the applicable performance specification in 40 CFR part 60, appendix B. The duration of the performance test must be 30 operating days if you specified a 30 operating day basis in §63.7545(e)(2)(iii) for HCl CEMS or it must be 720 hours if you specified a 720 hour basis in §63.7545(e)(2)(iii) for HCl CEMS. For each day in which the unit operates, you must obtain hourly HCl concentration data, and stack gas volumetric flow rate data.

(ii) If you are using a HCl CEMS, you must install, operate, calibrate, and maintain an instrument for continuously measuring and recording the HCl mass emissions rate to the atmosphere according to the requirements of the applicable performance specification of 40 CFR part 60, appendix B, and the quality assurance procedures of 40 CFR part 60, appendix F.

(16) If you demonstrate compliance with an applicable TSM emission limit through performance testing, and you plan to burn a new type of fuel or a new mixture of fuels, you must recalculate the maximum TSM input using Equation 9 of §63.7530. If the results of recalculating the maximum TSM input using Equation 9 of §63.7530 are higher than the maximum total selected input level established during the previous performance test, then you must conduct a new performance test within 60 days of burning the new fuel type or fuel mixture according to the procedures in §63.7520 to demonstrate that the TSM emissions do not exceed the emission limit. You must also establish new operating limits based on this performance test according to the procedures in §63.7530(b). You are not required to conduct fuel analyses for the fuels described in §63.7510(a)(2)(i) through (iii). You may exclude the fuels described in §63.7510(a)(2)(i) through (iii) when recalculating the TSM emission rate.

(17) If you demonstrate compliance with an applicable TSM emission limit through fuel analysis for solid or liquid fuels, and you plan to burn a new type of fuel, you must recalculate the TSM emission rate using Equation 18 of §63.7530 according to the procedures specified in paragraphs (a)(5)(i) through (iii) of this section. You are not required to conduct fuel analyses for the fuels described in §63.7510(a)(2)(i) through (iii). You may exclude the fuels described in §63.7510(a)(2)(i) through (iii) when recalculating the TSM emission rate.

(i) You must determine the TSM concentration for any new fuel type in units of pounds per million Btu, based on supplier data or your own fuel analysis, according to the provisions in your site-specific fuel analysis plan developed according to §63.7521(b).

(ii) You must determine the new mixture of fuels that will have the highest content of TSM.

(iii) Recalculate the TSM emission rate from your boiler or process heater under these new conditions using Equation 18 of §63.7530. The recalculated TSM emission rate must be less than the applicable emission limit.

(18) If you demonstrate continuous PM emissions compliance with a PM CPMS you will use a PM CPMS to establish a site-specific operating limit corresponding to the results of the performance test demonstrating compliance with the PM limit. You will conduct your performance test using the test method criteria in Table 5 of this subpart. You will use the PM CPMS to demonstrate continuous compliance with this operating limit. You must repeat the performance test annually and reassess and adjust the site-specific operating limit in accordance with the results of the performance test.

(i) To determine continuous compliance, you must record the PM CPMS output data for all periods when the process is operating and the PM CPMS is not out-of-control. You must demonstrate continuous compliance by using all quality-assured hourly average data collected by the PM CPMS for all operating hours to calculate the arithmetic average operating parameter in units of the operating limit (milliamps) on a 30-day rolling average basis.

(ii) For any deviation of the 30-day rolling PM CPMS average value from the established operating parameter limit, you must:

(A) Within 48 hours of the deviation, visually inspect the air pollution control device (APCD);

(B) If inspection of the APCD identifies the cause of the deviation, take corrective action as soon as possible and return the PM CPMS measurement to within the established value; and

(C) Within 30 days of the deviation or at the time of the annual compliance test, whichever comes first, conduct a PM emissions compliance test to determine compliance with the PM emissions limit and to verify or re-establish the CPMS operating limit. You are not required to conduct additional testing for any deviations that occur between the time of the original deviation and the PM emissions compliance test required under this paragraph.

(iii) PM CPMS deviations from the operating limit leading to more than four required performance tests in a 12-month operating period constitute a separate violation of this subpart.

(19) If you choose to comply with the PM filterable emissions limit by using PM CEMS you must install, certify, operate, and maintain a PM CEMS and record the output of the PM CEMS as specified in paragraphs (a)(19)(i) through (vii) of this section. The compliance limit will be expressed as a 30-day rolling average of the numerical emissions limit value applicable for your unit in Table 1 or 2 or Tables 11 through 15 to this subpart.

(i) Install and certify your PM CEMS according to the procedures and requirements in Performance Specification 11—Specifications and Test Procedures for Particulate Matter Continuous Emission Monitoring Systems at Stationary Sources in Appendix B to part 60 of this chapter, using test criteria outlined in Table V of this rule. The reportable measurement output from the PM CEMS must be expressed in units of the applicable emissions limit (e.g., lb/MMBtu, lb/MWh).

(ii) Operate and maintain your PM CEMS according to the procedures and requirements in Procedure 2— Quality Assurance Requirements for Particulate Matter Continuous Emission Monitoring Systems at Stationary Sources in Appendix F to part 60 of this chapter.

(A) You must conduct the relative response audit (RRA) for your PM CEMS at least once annually.

(B) You must conduct the relative correlation audit (RCA) for your PM CEMS at least once every 3 years.

(iii) Collect PM CEMS hourly average output data for all boiler operating hours except as indicated in paragraph (v) of this section.

(iv) Calculate the arithmetic 30-day rolling average of all of the hourly average PM CEMS output data collected during all nonexempt boiler or process heater operating hours.

(v) You must collect data using the PM CEMS at all times the unit is operating and at the intervals specified this paragraph (a), except for periods of monitoring system malfunctions, repairs associated with monitoring system malfunctions, and required monitoring system quality assurance or quality control activities.

(vi) You must use all the data collected during all boiler or process heater operating hours in assessing the compliance with your operating limit except:

(A) Any data collected during monitoring system malfunctions, repairs associated with monitoring system malfunctions, or required monitoring system quality assurance or control activities conducted during monitoring system malfunctions in calculations and report any such periods in your annual deviation report;

(B) Any data collected during periods when the monitoring system is out of control as specified in your site-specific monitoring plan, repairs associated with periods when the monitoring system is out of control, or required monitoring system quality assurance or control activities conducted during out of control periods in calculations used to report emissions or operating levels and report any such periods in your annual deviation report;

(C) Any data recorded during periods of startup or shutdown.

(vii) You must record and make available upon request results of PM CEMS system performance audits, dates and duration of periods when the PM CEMS is out of control to completion of the corrective actions necessary to return the PM CEMS to operation consistent with your site-specific monitoring plan.

(b) You must report each instance in which you did not meet each emission limit and operating limit in Tables 1 through 4 or 11 through 15 to this subpart that apply to you. These instances are deviations from the emission limits or operating limits, respectively, in this subpart. These deviations must be reported according to the requirements in § 63.7550.

(c) If you elected to demonstrate that the unit meets the specification for mercury for the unit designed to burn gas 1 subcategory, you must follow the sampling frequency specified in paragraphs (c)(1) through (4) of this section and conduct this sampling according to the procedures in § 63.7521(f) through (i).

(1) If the initial mercury constituents in the gaseous fuels are measured to be equal to or less than half of the mercury specification as defined in § 63.7575, you do not need to conduct further sampling.

(2) If the initial mercury constituents are greater than half but equal to or less than 75 percent of the mercury specification as defined in § 63.7575, you will conduct semi-annual sampling. If 6 consecutive semi-annual fuel analyses demonstrate 50 percent or less of the mercury specification, you do not need to conduct further sampling. If any semi-annual sample exceeds 75 percent of the mercury specification, you must return to monthly sampling for that fuel, until 12 months of fuel analyses again are less than 75 percent of the compliance level.

(3) If the initial mercury constituents are greater than 75 percent of the mercury specification as defined in § 63.7575, you will conduct monthly sampling. If 12 consecutive monthly fuel analyses demonstrate 75 percent or less of the mercury specification, you may decrease the fuel analysis frequency to semi-annual for that fuel.

(4) If the initial sample exceeds the mercury specification as defined in § 63.7575, each affected boiler or process heater combusting this fuel is not part of the unit designed to burn gas 1 subcategory and must be in compliance with the emission and operating limits for the appropriate subcategory. You may elect to conduct additional monthly sampling while complying with these emissions and operating limits to demonstrate that the fuel qualifies as another gas 1 fuel. If 12 consecutive monthly fuel analyses samples are at or below the mercury specification as defined in § 63.7575, each affected boiler or process heater combusting the fuel can elect to switch back into the unit designed to burn gas 1 subcategory until the mercury specification is exceeded.

(d) For startup and shutdown, you must meet the work practice standards according to items 5 and 6 of Table 3 of this subpart.

[78 FR 7179, Jan. 31, 2013, as amended at 80 FR 72813, Nov. 20, 2015; 87 FR 60846, Oct. 6, 2022]

§ 63.7541 How do I demonstrate continuous compliance under the emissions averaging provision?

(a) Following the compliance date, the owner or operator must demonstrate compliance with this subpart on a continuous basis by meeting the requirements of paragraphs (a)(1) through (5) of this section.

(1) For each calendar month, demonstrate compliance with the average weighted emissions limit for the existing units participating in the emissions averaging option as determined in § 63.7522(f) and (g).

(2) You must maintain the applicable opacity limit according to paragraphs (a)(2)(i) and (ii) of this section.

(i) For each existing unit participating in the emissions averaging option that is equipped with a dry control system and not vented to a common stack, maintain opacity at or below the applicable limit.

(ii) For each group of units participating in the emissions averaging option where each unit in the group is equipped with a dry control system and vented to a common stack that does not receive emissions from non-affected units, maintain opacity at or below the applicable limit at the common stack.

(3) For each existing unit participating in the emissions averaging option that is equipped with a wet scrubber, maintain the 30-day rolling average parameter values at or above the operating limits established during the most recent performance test.

(4) For each existing unit participating in the emissions averaging option that has an approved alternative operating parameter, maintain the 30-day rolling average parameter values consistent with the approved monitoring plan.

(5) For each existing unit participating in the emissions averaging option venting to a common stack configuration containing affected units from other subcategories, maintain the appropriate operating limit for each unit as specified in Table 4 to this subpart that applies.

(b) Any instance where the owner or operator fails to comply with the continuous monitoring requirements in paragraphs (a)(1) through (5) of this section is a deviation.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7182, Jan. 31, 2013]

NOTIFICATION, REPORTS, AND RECORDS

§ 63.7545 What notifications must I submit and when?

(a) You must submit to the Administrator all of the notifications in §§ 63.7(b) and (c), 63.8(e), (f)(4) and (6), and 63.9(b) through (h) that apply to you by the dates specified.

(b) As specified in § 63.9(b)(2), if you startup your affected source before January 31, 2013, you must submit an Initial Notification not later than 120 days after January 31, 2013, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) As specified in § 63.9(b)(4) and (5), if you startup your new or reconstructed affected source on or after January 31, 2013, you must submit an Initial Notification not later than 15 days after the actual date of startup of the affected source. For a new or reconstructed affected source that has reclassified to major source status, you must submit an Initial Notification not later 120 days after the source becomes subject to this subpart.

(d) If you are required to conduct a performance test you must submit a Notification of Intent to conduct a performance test at least 60 days before the performance test is scheduled to begin.

(e) If you are required to conduct an initial compliance demonstration as specified in § 63.7530, you must submit a Notification of Compliance Status according to § 63.9(h)(2)(ii). For the initial compliance demonstration for each boiler or process heater, you must submit the Notification of Compliance Status, including all performance test results and fuel analyses, before the close of business on the 60th day following the completion of all performance test and/or other initial compliance demonstrations for all boiler or process heaters at the facility according to § 63.10(d)(2). The Notification of Compliance Status report must contain all the information specified in paragraphs (e)(1) through (8) of this section, as applicable. If you are not required to conduct an initial compliance demonstration as specified in § 63.7530(a), the Notification of Compliance Status must only contain the information specified in paragraphs (e)(1) and (8) of this section and must be submitted within 60 days of the compliance date specified at § 63.7495(b).

(1) A description of the affected unit(s) including identification of which subcategories the unit is in, the design heat input capacity of the unit, a description of the add-on controls used on the unit to comply with this subpart, description of the fuel(s) burned, including whether the fuel(s) were a secondary material determined by you or the EPA through a petition process to be a non-waste under § 241.3 of this chapter, whether the fuel(s) were a secondary material processed from discarded non-hazardous secondary materials within the meaning of § 241.3 of this chapter, and justification for the selection of fuel(s) burned during the compliance demonstration.

(2) Summary of the results of all performance tests and fuel analyses, and calculations conducted to demonstrate initial compliance including all established operating limits, and including:

(i) Identification of whether you are complying with the PM emission limit or the alternative TSM emission limit.

(ii) Identification of whether you are complying with the output-based emission limits or the heat input-based (i.e., lb/MMBtu or ppm) emission limits,

(iii) Identification of whether you are complying the arithmetic mean of all valid hours of data from the previous 30 operating days or of the previous 720 hours. This identification shall be specified separately for each operating parameter.

(3) A summary of the maximum CO emission levels recorded during the performance test to show that you have met any applicable emission standard in Table 1 or 2 or Tables 11 through 15 to this subpart, if you are not using a CO CEMS to demonstrate compliance.

(4) Identification of whether you plan to demonstrate compliance with each applicable emission limit through performance testing, a CEMS, or fuel analysis.

(5) Identification of whether you plan to demonstrate compliance by emissions averaging and identification of whether you plan to demonstrate compliance by using efficiency credits through energy conservation:

(i) If you plan to demonstrate compliance by emission averaging, report the emission level that was being achieved or the control technology employed on January 31, 2013.

(ii) [Reserved]

(6) A signed certification that you have met all applicable emission limits and work practice standards.

(7) If you had a deviation from any emission limit, work practice standard, or operating limit, you must also submit a description of the deviation, the duration of the deviation, and the corrective action taken in the Notification of Compliance Status report.

(8) In addition to the information required in §63.9(h)(2), your notification of compliance status must include the following certification(s) of compliance, as applicable, and signed by a responsible official:

(i) ''This facility completed the required initial tune-up for all of the boilers and process heaters covered by 40 CFR part 63 subpart DDDDD at this site according to the procedures in §63.7540(a)(10)(i) through (vi).''

(ii) ''This facility has had an energy assessment performed according to §63.7530(e).''

(iii) Except for units that burn only natural gas, refinery gas, or other gas 1 fuel, or units that qualify for a statutory exemption as provided in section 129(g)(1) of the Clean Air Act, include the following: ''No secondary materials that are solid waste were combusted in any affected unit.''

(f) If you operate a unit designed to burn natural gas, refinery gas, or other gas 1 fuels that is subject to this subpart, and you intend to use a fuel other than natural gas, refinery gas, gaseous fuel subject to another subpart of this part, part 60, 61, or 65, or other gas 1 fuel to fire the affected unit during a period of natural gas curtailment or supply interruption, as defined in §63.7575, you must submit a notification of alternative fuel use within 48 hours of the declaration of each period of natural gas curtailment or supply interruption, as defined in §63.7575. The notification must include the information specified in paragraphs (f)(1) through (5) of this section.

(1) Company name and address.

(2) Identification of the affected unit.

(3) Reason you are unable to use natural gas or equivalent fuel, including the date when the natural gas curtailment was declared or the natural gas supply interruption began.

(4) Type of alternative fuel that you intend to use.

(5) Dates when the alternative fuel use is expected to begin and end.

(g) If you intend to commence or recommence combustion of solid waste, you must provide 30 days prior notice of the date upon which you will commence or recommence combustion of solid waste. The notification must identify:

(1) The name of the owner or operator of the affected source, as defined in §63.7490, the location of the source, the boiler(s) or process heater(s) that will commence burning solid waste, and the date of the notice.

(2) The currently applicable subcategories under this subpart.

(3) The date on which you became subject to the currently applicable emission limits.

(4) The date upon which you will commence combusting solid waste.

(h) If you have switched fuels or made a physical change to the boiler or process heater and the fuel switch or

physical change resulted in the applicability of a different subcategory, you must provide notice of the date upon which you switched fuels or made the physical change within 30 days of the switch/change. The notification must identify:

(1) The name of the owner or operator of the affected source, as defined in § 63.7490, the location of the source, the boiler(s) and process heater(s) that have switched fuels, were physically changed, and the date of the notice.

(2) The currently applicable subcategory under this subpart.

(3) The date upon which the fuel switch or physical change occurred.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7183, Jan. 31, 2013; 80 FR 72814, Nov. 20, 2015; 85 FR 73913, Nov. 19, 2020; 85 FR 84262, Dec. 28, 2020; 87 FR 60846, Oct. 6, 2022]

§ 63.7550 What reports must I submit and when?

(a) You must submit each report in Table 9 to this subpart that applies to you.

(b) Unless the EPA Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report, according to paragraph (h) of this section, by the date in Table 9 to this subpart and according to the requirements in paragraphs (b)(1) through (4) of this section. For units that are subject only to a requirement to conduct subsequent annual, biennial, or 5-year tune-up according to § 63.7540(a)(10), (11), or (12), respectively, and not subject to emission limits or Table 4 operating limits, you may submit only an annual, biennial, or 5-year compliance report, as applicable, as specified in paragraphs (b)(1) through (4) of this section, instead of a semi-annual compliance report.

(1) The first semi-annual compliance report must cover the period beginning on the compliance date that is specified for each boiler or process heater in § 63.7495 and ending on June 30 or December 31, whichever date is the first date that occurs at least 180 days after the compliance date that is specified for your source in § 63.7495. If submitting an annual, biennial, or 5-year compliance report, the first compliance report must cover the period beginning on the compliance date that is specified for each boiler or process heater in § 63.7495 and ending on December 31 within 1, 2, or 5 years, as applicable, after the compliance date that is specified for your source in § 63.7495.

(2) The first semi-annual compliance report must be postmarked or submitted no later than July 31 or January 31, whichever date is the first date following the end of the first calendar half after the compliance date that is specified for each boiler or process heater in § 63.7495. The first annual, biennial, or 5-year compliance report must be postmarked or submitted no later than January 31.

(3) Each subsequent semi-annual compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31. Annual, biennial, and 5-year compliance reports must cover the applicable 1-, 2-, or 5-year periods from January 1 to December 31.

(4) Each subsequent semi-annual compliance report must be postmarked or submitted no later than July 31 or January 31, whichever date is the first date following the end of the semiannual reporting period. Annual, biennial, and 5-year compliance reports must be postmarked or submitted no later than January 31.

(5) For each affected source that is subject to permitting regulations pursuant to part 70 or part 71 of this chapter, and if the permitting authority has established dates for submitting semiannual reports pursuant to 70.6(a)(3)(iii)(A) or 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established in the permit instead of according to the dates in paragraphs (b)(1) through (4) of this section.

(c) A compliance report must contain the following information depending on how the facility chooses to comply with the limits set in this rule.

(1) If the facility is subject to the requirements of a tune up you must submit a compliance report with the information in paragraphs (c)(5)(i) through (iii) of this section, (xiv) and (xvii) of this section, and paragraph (c)(5)(iv) of

this section for limited-use boiler or process heater.

(2) If you are complying with the fuel analysis you must submit a compliance report with the information in paragraphs (c)(5)(i) through (iii), (vi), (x), (xi), (xiii), (xv), (xvii), (xviii) and paragraph (d) of this section.

(3) If you are complying with the applicable emissions limit with performance testing you must submit a compliance report with the information in (c)(5)(i) through (iii), (vi), (vii), (viii), (ix), (xi), (xiii), (xv), (xvii), (xviii) and paragraph (d) of this section.

(4) If you are complying with an emissions limit using a CMS the compliance report must contain the information required in paragraphs (c)(5)(i) through (iii), (v), (vi), (xi) through (xiii), (xv) through (xviii), and paragraph (e) of this section.

(5)(i) Company and Facility name and address.

(ii) Process unit information, emissions limitations, and operating parameter limitations.

(iii) Date of report and beginning and ending dates of the reporting period.

(iv) The total operating time during the reporting period.

(v) If you use a CMS, including CEMS, COMS, or CPMS, you must include the monitoring equipment manufacturer(s) and model numbers and the date of the last CMS certification or audit.

(vi) The total fuel use by each individual boiler or process heater subject to an emission limit within the reporting period, including, but not limited to, a description of the fuel, whether the fuel has received a non-waste determination by the EPA or your basis for concluding that the fuel is not a waste, and the total fuel usage amount with units of measure.

(vii) If you are conducting performance tests once every 3 years consistent with §63.7515(b) or (c), the date of the last 2 performance tests and a statement as to whether there have been any operational changes since the last performance test that could increase emissions.

(viii) A statement indicating that you burned no new types of fuel in an individual boiler or process heater subject to an emission limit. Or, if you did burn a new type of fuel and are subject to a HCl emission limit, you must submit the calculation of chlorine input, using Equation 7 of §63.7530, that demonstrates that your source is still within its maximum chlorine input level established during the previous performance testing (for sources that demonstrate compliance through performance testing) or you must submit the calculation of HCl emission rate using Equation 16 of §63.7530 that demonstrates that your source is still meeting the emission limit for HCl emissions (for boilers or process heaters that demonstrate compliance through fuel analysis). If you burned a new type of fuel and are subject to a mercury emission limit, you must submit the calculation of mercury input, using Equation 8 of §63.7530, that demonstrates that your source is still within its maximum mercury input level established during the previous performance testing (for sources that demonstrate compliance through performance testing), or you must submit the calculation of mercury emission rate using Equation 17 of §63.7530 that demonstrates that your source is still meeting the emission limit for mercury emissions (for boilers or process heaters that demonstrate compliance through fuel analysis). If you burned a new type of fuel and are subject to a TSM emission limit, you must submit the calculation of TSM input, using Equation 9 of §63.7530, that demonstrates that your source is still within its maximum TSM input level established during the previous performance testing (for sources that demonstrate compliance through performance testing), or you must submit the calculation of TSM emission rate, using Equation 18 of §63.7530, that demonstrates that your source is still meeting the emission limit for TSM emissions (for boilers or process heaters that demonstrate compliance through fuel analysis).

(ix) If you wish to burn a new type of fuel in an individual boiler or process heater subject to an emission limit and you cannot demonstrate compliance with the maximum chlorine input operating limit using Equation 7 of §63.7530 or the maximum mercury input operating limit using Equation 8 of §63.7530,

or the maximum TSM input operating limit using Equation 9 of § 63.7530 you must include in the compliance report a statement indicating the intent to conduct a new performance test within 60 days of starting to burn the new fuel.

(x) A summary of any monthly fuel analyses conducted to demonstrate compliance according to §§ 63.7521 and 63.7530 for individual boilers or process heaters subject to emission limits, and any fuel specification analyses conducted according to §§ 63.7521(f) and 63.7530(g).

(xi) If there are no deviations from any emission limits or operating limits in this subpart that apply to you, a statement that there were no deviations from the emission limits or operating limits during the reporting period.

(xii) If there were no deviations from the monitoring requirements including no periods during which the CMSs, including CEMS, COMS, and CPMS, were out of control as specified in § 63.8(c)(7), a statement that there were no deviations and no periods during which the CMS were out of control during the reporting period.

(xiii) If a malfunction occurred during the reporting period, the report must include the number, duration, and a brief description for each type of malfunction which occurred during the reporting period and which caused or may have caused any applicable emission limitation to be exceeded. The report must also include a description of actions taken by you during a malfunction of a boiler, process heater, or associated air pollution control device or CMS to minimize emissions in accordance with § 63.7500(a)(3), including actions taken to correct the malfunction.

(xiv) Include the date of the most recent tune-up for each unit subject to only the requirement to conduct an annual, biennial, or 5-year tune-up according to § 63.7540(a)(10), (11), or (12) respectively. Include the date of the most recent burner inspection if it was not done annually, biennially, or on a 5-year period and was delayed until the next scheduled or unscheduled unit shutdown.

(xv) If you plan to demonstrate compliance by emission averaging, certify the emission level achieved or the control technology employed is no less stringent than the level or control technology contained in the notification of compliance status in § 63.7545(e)(5)(i).

(xvi) For each reporting period, the compliance reports must include all of the calculated 30 day rolling average values for CEMS (CO, HCl, SO_2, and mercury), 10 day rolling average values for CO CEMS when the limit is expressed as a 10 day instead of 30 day rolling average, and the PM CPMS data.

(xvii) Statement by a responsible official with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(xviii) For each instance of startup or shutdown include the information required to be monitored, collected, or recorded according to the requirements of § 63.7555(d).

(d) For each deviation from an emission limit or operating limit in this subpart that occurs at an individual boiler or process heater where you are not using a CMS to comply with that emission limit or operating limit, or from the work practice standards for periods if startup and shutdown, the compliance report must additionally contain the information required in paragraphs (d)(1) through (3) of this section.

(1) A description of the deviation and which emission limit, operating limit, or work practice standard from which you deviated.

(2) Information on the number, duration, and cause of deviations (including unknown cause), as applicable, and the corrective action taken.

(3) If the deviation occurred during an annual performance test, provide the date the annual performance test was completed.

(e) For each deviation from an emission limit, operating limit, and monitoring requirement in this subpart occurring at an individual boiler or process heater where you are using a CMS to comply with that emission limit or operating limit, the compliance report must additionally contain the information required in paragraphs (e)(1)

through (9) of this section. This includes any deviations from your site-specific monitoring plan as required in § 63.7505(d).

(1) The date and time that each deviation started and stopped and description of the nature of the deviation (i.e., what you deviated from).

(2) The date and time that each CMS was inoperative, except for zero (low-level) and high-level checks.

(3) The date, time, and duration that each CMS was out of control, including the information in § 63.8(c)(8).

(4) The date and time that each deviation started and stopped.

(5) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.

(6) A characterization of the total duration of the deviations during the reporting period into those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(7) A summary of the total duration of CMS's downtime during the reporting period and the total duration of CMS downtime as a percent of the total source operating time during that reporting period.

(8) A brief description of the source for which there was a deviation.

(9) A description of any changes in CMSs, processes, or controls since the last reporting period for the source for which there was a deviation.

(f)–(g) [Reserved]

(h) You must submit the reports according to the procedures specified in paragraphs (h)(1) through (3) of this section.

(1) Within 60 days after the date of completing each performance test (as defined in § 63.2) required by this subpart, you must submit the results of the performance tests, including any fuel analyses, following the procedure specified in either paragraph (h)(1)(i) or (ii) of this section.

(i) For data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT Web site (*http://www.epa.gov/ttn/chief/ert/index.html*), you must submit the results of the performance test to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI). (CEDRI can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*).) Performance test data must be submitted in a file format generated through use of the EPA's ERT or an electronic file format consistent with the extensible markup language (XML) schema listed on the EPA's ERT Web site. If you claim that some of the performance test information being submitted is confidential business information (CBI), you must submit a complete file generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT Web site, including information claimed to be CBI, on a compact disc, flash drive, or other commonly used electronic storage media to the EPA. The electronic media must be clearly marked as CBI and mailed to U.S. EPA/OAPQS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same ERT or alternate file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph.

(ii) For data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT Web site at the time of the test, you must submit the results of the performance test to the Administrator at the appropriate address listed in § 63.13.

(2) Within 60 days after the date of completing each CEMS performance evaluation (as defined in 63.2), you must submit the results of the performance evaluation following the procedure specified in either paragraph (h)(2)(i) or (ii) of this section.

(i) For performance evaluations of continuous monitoring systems measuring relative accuracy test audit (RATA) pollutants that are supported by the EPA's ERT as listed on the EPA's ERT Web site at the time of the evaluation, you must submit the results of the performance evaluation to the EPA via the CEDRI. (CEDRI can be accessed through the EPA's CDX.) Performance evaluation data must be submitted in a file format generated through the use of the EPA's ERT or an alternate file format consistent

with the XML schema listed on the EPA's ERT Web site. If you claim that some of the performance evaluation information being transmitted is CBI, you must submit a complete file generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT Web site, including information claimed to be CBI, on a compact disc, flash drive, or other commonly used electronic storage media to the EPA. The electronic media must be clearly marked as CBI and mailed to U.S. EPA/OAPQS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same ERT or alternate file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph.

(ii) For any performance evaluations of continuous monitoring systems measuring RATA pollutants that are not supported by the EPA's ERT as listed on the ERT Web site at the time of the evaluation, you must submit the results of the performance evaluation to the Administrator at the appropriate address listed in § 63.13.

(3) You must submit all reports required by Table 9 of this subpart electronically to the EPA via the CEDRI. (CEDRI can be accessed through the EPA's CDX.) You must use the appropriate electronic report in CEDRI for this subpart. Instead of using the electronic report in CEDRI for this subpart, you may submit an alternate electronic file consistent with the XML schema listed on the CEDRI Web site (*http://www.epa.gov/ttn/chief/cedri/index.html*), once the XML schema is available. If the reporting form specific to this subpart is not available in CEDRI at the time that the report is due, you must submit the report to the Administrator at the appropriate address listed in § 63.13. You must begin submitting reports via CEDRI no later than 90 days after the form becomes available in CEDRI.

[78 FR 7183, Jan. 31, 2013, as amended at 80 FR 72814, Nov. 20, 2015]

§ 63.7555 What records must I keep?

(a) You must keep records according to paragraphs (a)(1) and (2) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status or semiannual compliance report that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) Records of performance tests, fuel analyses, or other compliance demonstrations and performance evaluations as required in § 63.10(b)(2)(viii).

(3) For units in the limited use subcategory, you must keep a copy of the federally enforceable permit that limits the annual capacity factor to less than or equal to 10 percent and fuel use records for the days the boiler or process heater was operating.

(b) For each CEMS, COMS, and continuous monitoring system you must keep records according to paragraphs (b)(1) through (5) of this section.

(1) Records described in § 63.10(b)(2)(vii) through (xi).

(2) Monitoring data for continuous opacity monitoring system during a performance evaluation as required in § 63.6(h)(7)(i) and (ii).

(3) Previous (*i.e.*, superseded) versions of the performance evaluation plan as required in § 63.8(d)(3).

(4) Request for alternatives to relative accuracy test for CEMS as required in § 63.8(f)(6)(i).

(5) Records of the date and time that each deviation started and stopped.

(c) You must keep the records required in Table 8 to this subpart including records of all monitoring data and calculated averages for applicable operating limits, such as opacity, pressure drop, pH, and operating load, to show continuous compliance with each emission limit and operating limit that applies to you.

(d) For each boiler or process heater subject to an emission limit in Table 1 or 2 or Tables 11 through 15 to this subpart, you must also keep the applicable records in paragraphs (d)(1) through (11) of this section.

(1) You must keep records of monthly fuel use by each boiler or process heater, including the type(s) of fuel and amount(s) used.

(2) If you combust non-hazardous secondary materials that have been determined not to be solid waste pursuant to §241.3(b)(1) and (2) of this chapter, you must keep a record that documents how the secondary material meets each of the legitimacy criteria under §241.3(d)(1) of this chapter. If you combust a fuel that has been processed from a discarded non-hazardous secondary material pursuant to §241.3(b)(4) of this chapter, you must keep records as to how the operations that produced the fuel satisfy the definition of processing in §241.2 of this chapter. If the fuel received a non-waste determination pursuant to the petition process submitted under §241.3(c) of this chapter, you must keep a record that documents how the fuel satisfies the requirements of the petition process. For operating units that combust non-hazardous secondary materials as fuel per §241.4 of this chapter, you must keep records documenting that the material is listed as a non-waste under §241.4(a) of this chapter. Units exempt from the incinerator standards under section 129(g)(1) of the Clean Air Act because they are qualifying facilities burning a homogeneous waste stream do not need to maintain the records described in this paragraph (d)(2).

(3) A copy of all calculations and supporting documentation of maximum chlorine fuel input, using Equation 7 of §63.7530, that were done to demonstrate continuous compliance with the HCl emission limit, for sources that demonstrate compliance through performance testing. For sources that demonstrate compliance through fuel analysis, a copy of all calculations and supporting documentation of HCl emission rates, using Equation 16 of §63.7530, that were done to demonstrate compliance with the HCl emission limit. Supporting documentation should include results of any fuel analyses and basis for the estimates of maximum chlorine fuel input or HCl emission rates. You can use the results from one fuel analysis for multiple boilers and process heaters provided they are all burning the same fuel type. However, you must calculate chlorine fuel input, or HCl emission rate, for each boiler and process heater.

(4) A copy of all calculations and supporting documentation of maximum mercury fuel input, using Equation 8 of §63.7530, that were done to demonstrate continuous compliance with the mercury emission limit for sources that demonstrate compliance through performance testing. For sources that demonstrate compliance through fuel analysis, a copy of all calculations and supporting documentation of mercury emission rates, using Equation 17 of §63.7530, that were done to demonstrate compliance with the mercury emission limit. Supporting documentation should include results of any fuel analyses and basis for the estimates of maximum mercury fuel input or mercury emission rates. You can use the results from one fuel analysis for multiple boilers and process heaters provided they are all burning the same fuel type. However, you must calculate mercury fuel input, or mercury emission rates, for each boiler and process heater.

(5) If, consistent with §63.7515(b), you choose to stack test less frequently than annually, you must keep a record that documents that your emissions in the previous stack test(s) were less than 75 percent of the applicable emission limit (or, in specific instances noted in Tables 1 and 2 or 11 through 15 to this subpart, less than the applicable emission limit), and document that there was no change in source operations including fuel composition and operation of air pollution control equipment that would cause emissions of the relevant pollutant to increase within the past year.

(6) Records of the occurrence and duration of each malfunction of the boiler or process heater, or of the associated air pollution control and monitoring equipment.

(7) Records of actions taken during periods of malfunction to minimize emissions in accordance with the general duty to minimize emissions in §63.7500(a)(3), including corrective actions to restore the malfunctioning boiler or process heater, air pollution control, or monitoring equipment to

its normal or usual manner of operation.

(8) A copy of all calculations and supporting documentation of maximum TSM fuel input, using Equation 9 of § 63.7530, that were done to demonstrate continuous compliance with the TSM emission limit for sources that demonstrate compliance through performance testing. For sources that demonstrate compliance through fuel analysis, a copy of all calculations and supporting documentation of TSM emission rates, using Equation 18 of § 63.7530, that were done to demonstrate compliance with the TSM emission limit. Supporting documentation should include results of any fuel analyses and basis for the estimates of maximum TSM fuel input or TSM emission rates. You can use the results from one fuel analysis for multiple boilers and process heaters provided they are all burning the same fuel type. However, you must calculate TSM fuel input, or TSM emission rates, for each boiler and process heater.

(9) You must maintain records of the calendar date, time, occurrence and duration of each startup and shutdown.

(10) You must maintain records of the type(s) and amount(s) of fuels used during each startup and shutdown.

(11) For each startup period, for units selecting paragraph (2) of the definition of ''startup'' in § 63.7575 you must maintain records of the time that clean fuel combustion begins; the time when you start feeding fuels that are not clean fuels; the time when useful thermal energy is first supplied; and the time when the PM controls are engaged.

(12) If you choose to rely on paragraph (2) of the definition of ''startup'' in § 63.7575, for each startup period, you must maintain records of the hourly steam temperature, hourly steam pressure, hourly steam flow, hourly flue gas temperature, and all hourly average CMS data (*e.g.*, CEMS, PM CPMS, COMS, ESP total secondary electric power input, scrubber pressure drop, scrubber liquid flow rate) collected during each startup period to confirm that the control devices are engaged. In addition, if compliance with the PM emission limit is demonstrated using a PM control device, you must maintain records as specified in paragraphs (d)(12)(i) through (iii) of this section.

(i) For a boiler or process heater with an electrostatic precipitator, record the number of fields in service, as well as each field's secondary voltage and secondary current during each hour of startup.

(ii) For a boiler or process heater with a fabric filter, record the number of compartments in service, as well as the differential pressure across the baghouse during each hour of startup.

(iii) For a boiler or process heater with a wet scrubber needed for filterable PM control, record the scrubber's liquid flow rate and the pressure drop during each hour of startup.

(13) If you choose to use paragraph (2) of the definition of ''startup'' in § 63.7575 and you find that you are unable to safely engage and operate your PM control(s) within 1 hour of first firing of non-clean fuels, you may choose to rely on paragraph (1) of definition of ''startup'' in § 63.7575 or you may submit to the delegated permitting authority a request for a variance with the PM controls requirement, as described below.

(i) The request shall provide evidence of a documented manufacturer-identified safety issue.

(ii) The request shall provide information to document that the PM control device is adequately designed and sized to meet the applicable PM emission limit.

(iii) In addition, the request shall contain documentation that:

(A) The unit is using clean fuels to the maximum extent possible to bring the unit and PM control device up to the temperature necessary to alleviate or prevent the identified safety issues prior to the combustion of primary fuel;

(B) The unit has explicitly followed the manufacturer's procedures to alleviate or prevent the identified safety issue; and

(C) Identifies with specificity the details of the manufacturer's statement of concern.

(iv) You must comply with all other work practice requirements, including but not limited to data collection, recordkeeping, and reporting requirements.

(e) If you elect to average emissions consistent with § 63.7522, you must additionally keep a copy of the emission averaging implementation plan required in § 63.7522(g), all calculations required under § 63.7522, including monthly records of heat input or steam generation, as applicable, and monitoring records consistent with § 63.7541.

(f) If you elect to use efficiency credits from energy conservation measures to demonstrate compliance according to § 63.7533, you must keep a copy of the Implementation Plan required in § 63.7533(d) and copies of all data and calculations used to establish credits according to § 63.7533(b), (c), and (f).

(g) If you elected to demonstrate that the unit meets the specification for mercury for the unit designed to burn gas 1 subcategory, you must maintain monthly records (or at the frequency required by § 63.7540(c)) of the calculations and results of the fuel specification for mercury in Table 6.

(h) If you operate a unit in the unit designed to burn gas 1 subcategory that is subject to this subpart, and you use an alternative fuel other than natural gas, refinery gas, gaseous fuel subject to another subpart under this part, other gas 1 fuel, or gaseous fuel subject to another subpart of this part or part 60, 61, or 65, you must keep records of the total hours per calendar year that alternative fuel is burned and the total hours per calendar year that the unit operated during periods of gas curtailment or gas supply emergencies.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7185, Jan. 31, 2013; 80 FR 72816, Nov. 20, 2015; 87 FR 60846, Oct. 6, 2022]

§ 63.7560 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site, or they must be accessible from on site (for example, through a computer network), for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You can keep the records off site for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.7565 What parts of the General Provisions apply to me?

Table 10 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.15 apply to you.

§ 63.7570 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by the EPA, or an Administrator such as your state, local, or tribal agency. If the EPA Administrator has delegated authority to your state, local, or tribal agency, then that agency (as well as the EPA) has the authority to implement and enforce this subpart. You should contact your EPA Regional Office to find out if this subpart is delegated to your state, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a state, local, or tribal agency under 40 CFR part 63, subpart E, the authorities listed in paragraphs (b)(1) through (4) of this section are retained by the EPA Administrator and are not transferred to the state, local, or tribal agency, however, the EPA retains oversight of this subpart and can take enforcement actions, as appropriate.

(1) Approval of alternatives to the emission limits and work practice standards in § 63.7500(a) and (b) under § 63.6(g), except as specified in § 63.7555(d)(13).

(2) Approval of major change to test methods in Table 5 to this subpart under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90, and alternative analytical methods requested under § 63.7521(b)(2).

(3) Approval of major change to monitoring under § 63.8(f) and as defined in § 63.90, and approval of alternative operating parameters under §§ 63.7500(a)(2) and 63.7522(g)(2).

(4) Approval of major change to recordkeeping and reporting under § 63.10(e) and as defined in § 63.90.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7186, Jan. 31, 2013; 80 FR 72817, Nov. 20, 2015]

§ 63.7575 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in § 63.2 (the General Provisions), and in this section as follows:

10-day rolling average means the arithmetic mean of the previous 240 hours of valid operating data. Valid data excludes hours during startup and shutdown, data collected during periods when the monitoring system is out of control as specified in your site-specific monitoring plan, while conducting repairs associated with periods when the monitoring system is out of control, or while conducting required monitoring system quality assurance or quality control activities, and periods when this unit is not operating. The 240 hours should be consecutive, but not necessarily continuous if operations were intermittent.

12-month rolling average means the arithmetic mean of the previous 12 months of valid fuel analysis data. The 12 months should be consecutive, but not necessarily continuous if operations were intermittent.

30-day rolling average means the arithmetic mean of the previous 720 hours of valid CO CEMS data. The 720 hours should be consecutive, but not necessarily continuous if operations were intermittent. For parameters other than CO, 30-day rolling average means either the arithmetic mean of all valid hours of data from 30 successive operating days or the arithmetic mean of the previous 720 hours of valid operating data. Valid data excludes hours during startup and shutdown, data collected during periods when the monitoring system is out of control as specified in your site-specific monitoring plan, while conducting repairs associated with periods when the monitoring system is out of control, or while conducting required monitoring system quality assurance or quality control activities, and periods when this unit is not operating.

Annual capacity factor means the ratio between the actual heat input to a boiler or process heater from the fuels burned during a calendar year and the potential heat input to the boiler or process heater had it been operated for 8,760 hours during a year at the maximum steady state design heat input capacity.

Annual heat input means the heat input for the 12 months preceding the compliance demonstration.

Average annual heat input rate means total heat input divided by the hours of operation for the 12 months preceding the compliance demonstration.

Bag leak detection system means a group of instruments that are capable of monitoring particulate matter loadings in the exhaust of a fabric filter (*i.e.,* baghouse) in order to detect bag failures. A bag leak detection system includes, but is not limited to, an instrument that operates on electrodynamic, triboelectric, light scattering, light transmittance, or other principle to monitor relative particulate matter loadings.

Benchmark means the fuel heat input for a boiler or process heater for the one-year period before the date that an energy demand reduction occurs, unless it can be demonstrated that a different time period is more representative of historical operations.

Biodiesel means a mono-alkyl ester derived from biomass and conforming to ASTM D6751–11b, Standard Specification for Biodiesel Fuel Blend Stock (B100) for Middle Distillate Fuels (incorporated by reference, see § 63.14).

Biomass or bio-based solid fuel means any biomass-based solid fuel that is not a solid waste. This includes, but is not limited to, wood residue; wood products (*e.g.,* trees, tree stumps, tree limbs, bark, lumber, sawdust, sander dust, chips, scraps, slabs, millings, and shavings); animal manure, including litter and other bedding materials; vegetative agricultural and silvicultural materials, such as logging residues (slash), nut and grain hulls and chaff (*e.g.,* almond, walnut, peanut, rice, and wheat), bagasse, orchard prunings, corn stalks, coffee bean hulls and grounds. This definition of biomass is not intended to suggest that these materials are or are not solid waste.

Blast furnace gas fuel-fired boiler or process heater means an industrial/commercial/institutional boiler or process heater that receives 90 percent or more of its total annual gas volume from blast furnace gas.

Boiler means an enclosed device using controlled flame combustion and having the primary purpose of recovering thermal energy in the form of steam or hot water. Controlled flame combustion refers to a steady-state, or near steady-state, process wherein fuel and/or oxidizer feed rates are controlled. A device combusting solid waste, as defined in § 241.3 of this chapter, is not a boiler unless the device is exempt from the definition of a solid waste incineration unit as provided in section 129(g)(1) of the Clean Air Act. Waste heat boilers are excluded from this definition.

Boiler system means the boiler and associated components, such as, the feed water system, the combustion air system, the fuel system (including burners), blowdown system, combustion control systems, steam systems, and condensate return systems.

Calendar year means the period between January 1 and December 31, inclusive, for a given year.

Clean dry biomass means any biomass-based solid fuel that have not been painted, pigment-stained, or pressure treated, does not contain contaminants at concentrations not normally associated with virgin biomass materials and has a moisture content of less than 20 percent and is not a solid waste.

Coal means all solid fuels classifiable as anthracite, bituminous, sub-bituminous, or lignite by ASTM D388 (incorporated by reference, see § 63.14), coal refuse, and petroleum coke. For the purposes of this subpart, this definition of ''coal'' includes synthetic fuels derived from coal, including but not limited to, solvent-refined coal, coal-oil mixtures, and coal-water mixtures. Coal derived gases are excluded from this definition.

Coal refuse means any by-product of coal mining or coal cleaning operations with an ash content greater than 50 percent (by weight) and a heating value less than 13,900 kilojoules per kilogram (6,000 Btu per pound) on a dry basis.

Commercial/institutional boiler means a boiler used in commercial establishments or institutional establishments such as medical centers, nursing homes, research centers, institutions of higher education, elementary and secondary schools, libraries, religious establishments, governmental buildings, hotels, restaurants, and laundries to provide electricity, steam, and/or hot water.

Common stack means the exhaust of emissions from two or more affected units through a single flue. Affected units with a common stack may each have separate air pollution control systems located before the common stack, or may have a single air pollution control system located after the exhausts come together in a single flue.

Cost-effective energy conservation measure means a measure that is implemented to improve the energy efficiency of the boiler or facility that has a payback (return of investment) period of 2 years or less.

Daily block average means the arithmetic mean of all valid emission concentrations or parameter levels recorded when a unit is operating measured over the 24-hour period from 12 a.m. (midnight) to 12 a.m. (midnight), except for periods of startup and shutdown or downtime.

Deviation. (1) *Deviation* means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(i) Fails to meet any applicable requirement or obligation established by this subpart including, but not limited to, any emission limit, operating limit, or work practice standard; or

(ii) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit.

(2) A deviation is not always a violation.

Dioxins/furans means tetra- through octa-chlorinated dibenzo-p-dioxins and dibenzofurans.

Distillate oil means fuel oils that contain 0.05 weight percent nitrogen or less and comply with the specifications for fuel oil numbers 1 and 2, as defined by the American Society of Testing

and Materials in ASTM D396 (incorporated by reference, see §63.14) or diesel fuel oil numbers 1 and 2, as defined by the American Society for Testing and Materials in ASTM D975 (incorporated by reference, see §63.14), kerosene, and biodiesel as defined by the American Society of Testing and Materials in ASTM D6751–11b (incorporated by reference, see §60.14).

Dry scrubber means an add-on air pollution control system that injects dry alkaline sorbent (dry injection) or sprays an alkaline sorbent (spray dryer) to react with and neutralize acid gas in the exhaust stream forming a dry powder material. Sorbent injection systems used as control devices in fluidized bed boilers and process heaters are included in this definition. A dry scrubber is a dry control system.

Dutch oven means a unit having a refractory-walled cell connected to a conventional boiler setting. Fuel materials are introduced through an opening in the roof of the dutch oven and burn in a pile on its floor. Fluidized bed boilers are not part of the dutch oven design category.

Efficiency credit means emission reductions above those required by this subpart. Efficiency credits generated may be used to comply with the emissions limits. Credits may come from pollution prevention projects that result in reduced fuel use by affected units. Boilers that are shut down cannot be used to generate credits unless the facility provides documentation linking the permanent shutdown to implementation of the energy conservation measures identified in the energy assessment.

Electric utility steam generating unit (EGU) means a fossil fuel-fired combustion unit of more than 25 megawatts electric (MWe) that serves a generator that produces electricity for sale. A fossil fuel-fired unit that cogenerates steam and electricity and supplies more than one-third of its potential electric output capacity and more than 25 MWe output to any utility power distribution system for sale is considered an electric utility steam generating unit. To be ''capable of combusting'' fossil fuels, an EGU would need to have these fuels allowed in their operating permits and have the appropriate fuel handling facilities onsite or otherwise available (e.g., coal handling equipment, including coal storage area, belts and conveyers, pulverizers, etc.; oil storage facilities). In addition, fossil fuel-fired EGU means any EGU that fired fossil fuel for more than 10.0 percent of the average annual heat input in any 3 consecutive calendar years or for more than 15.0 percent of the annual heat input during any one calendar year after April 16, 2012.

Electrostatic precipitator (ESP) means an add-on air pollution control device used to capture particulate matter by charging the particles using an electrostatic field, collecting the particles using a grounded collecting surface, and transporting the particles into a hopper. An electrostatic precipitator is usually a dry control system.

Energy assessment means the following for the emission units covered by this subpart:

(1) The energy assessment for facilities with affected boilers and process heaters with a combined heat input capacity of less than 0.3 trillion Btu (TBtu) per year will be 8 on-site technical labor hours in length maximum, but may be longer at the discretion of the owner or operator of the affected source. The boiler system(s), process heater(s), and any on-site energy use system(s) accounting for at least 50 percent of the affected boiler(s) energy (*e.g.*, steam, hot water, process heat, or electricity) production, as applicable, will be evaluated to identify energy savings opportunities, within the limit of performing an 8-hour on-site energy assessment.

(2) The energy assessment for facilities with affected boilers and process heaters with a combined heat input capacity of 0.3 to 1.0 TBtu/year will be 24 on-site technical labor hours in length maximum, but may be longer at the discretion of the owner or operator of the affected source. The boiler system(s), process heater(s), and any on-site energy use system(s) accounting for at least 33 percent of the energy (*e.g.*, steam, hot water, process heat, or electricity) production, as applicable, will be evaluated to identify energy savings opportunities, within the limit

of performing a 24-hour on-site energy assessment.

(3) The energy assessment for facilities with affected boilers and process heaters with a combined heat input capacity greater than 1.0 TBtu/year will be up to 24 on-site technical labor hours in length for the first TBtu/yr plus 8 on-site technical labor hours for every additional 1.0 TBtu/yr not to exceed 160 on-site technical hours, but may be longer at the discretion of the owner or operator of the affected source. The boiler system(s), process heater(s), and any on-site energy use system(s) accounting for at least 20 percent of the energy (*e.g.*, steam, process heat, hot water, or electricity) production, as applicable, will be evaluated to identify energy savings opportunities.

(4) The on-site energy use systems serving as the basis for the percent of affected boiler(s) and process heater(s) energy production in paragraphs (1), (2), and (3) of this definition may be segmented by production area or energy use area as most logical and applicable to the specific facility being assessed (*e.g.*, product X manufacturing area; product Y drying area; Building Z).

Energy management practices means the set of practices and procedures designed to manage energy use that are demonstrated by the facility's energy policies, a facility energy manager and other staffing responsibilities, energy performance measurement and tracking methods, an energy saving goal, action plans, operating procedures, internal reporting requirements, and periodic review intervals used at the facility.

Energy management program means a program that includes a set of practices and procedures designed to manage energy use that are demonstrated by the facility's energy policies, a facility energy manager and other staffing responsibilities, energy performance measurement and tracking methods, an energy saving goal, action plans, operating procedures, internal reporting requirements, and periodic review intervals used at the facility. Facilities may establish their program through energy management systems compatible with ISO 50001.

Energy use system includes the following systems located on-site that use energy (steam, hot water, or electricity) provided by the affected boiler or process heater: process heating; compressed air systems; machine drive (motors, pumps, fans); process cooling; facility heating, ventilation, and air-conditioning systems; hot water systems; building envelop; and lighting; or other systems that use steam, hot water, process heat, or electricity provided by the affected boiler or process heater. Energy use systems are only those systems using energy clearly produced by affected boilers and process heaters.

Equivalent means the following only as this term is used in Table 6 to this subpart:

(1) An equivalent sample collection procedure means a published voluntary consensus standard or practice (VCS) or EPA method that includes collection of a minimum of three composite fuel samples, with each composite consisting of a minimum of three increments collected at approximately equal intervals over the test period.

(2) An equivalent sample compositing procedure means a published VCS or EPA method to systematically mix and obtain a representative subsample (part) of the composite sample.

(3) An equivalent sample preparation procedure means a published VCS or EPA method that: Clearly states that the standard, practice or method is appropriate for the pollutant and the fuel matrix; or is cited as an appropriate sample preparation standard, practice or method for the pollutant in the chosen VCS or EPA determinative or analytical method.

(4) An equivalent procedure for determining heat content means a published VCS or EPA method to obtain gross calorific (or higher heating) value.

(5) An equivalent procedure for determining fuel moisture content means a published VCS or EPA method to obtain moisture content. If the sample analysis plan calls for determining metals (especially the mercury, selenium, or arsenic) using an aliquot of the dried sample, then the drying temperature must be modified to prevent vaporizing these metals. On the other hand, if metals analysis is done on an

''as received'' basis, a separate aliquot can be dried to determine moisture content and the metals concentration mathematically adjusted to a dry basis.

(6) An equivalent pollutant (mercury, HCl) determinative or analytical procedure means a published VCS or EPA method that clearly states that the standard, practice, or method is appropriate for the pollutant and the fuel matrix and has a published detection limit equal or lower than the methods listed in Table 6 to this subpart for the same purpose.

Fabric filter means an add-on air pollution control device used to capture particulate matter by filtering gas streams through filter media, also known as a baghouse. A fabric filter is a dry control system.

Federally enforceable means all limitations and conditions that are enforceable by the EPA Administrator, including, but not limited to, the requirements of 40 CFR parts 60, 61, 63, and 65, requirements within any applicable state implementation plan, and any permit requirements established under 40 CFR 52.21 or under 40 CFR 51.18 and 40 CFR 51.24.

Fluidized bed boiler means a boiler utilizing a fluidized bed combustion process that is not a pulverized coal boiler.

Fluidized bed boiler with an integrated fluidized bed heat exchanger means a boiler utilizing a fluidized bed combustion where the entire tube surface area is located outside of the furnace section at the exit of the cyclone section and exposed to the flue gas stream for conductive heat transfer. This design applies only to boilers in the unit designed to burn coal/solid fossil fuel subcategory that fire coal refuse.

Fluidized bed combustion means a process where a fuel is burned in a bed of granulated particles, which are maintained in a mobile suspension by the forward flow of air and combustion products.

Fossil fuel means natural gas, oil, coal, and any form of solid, liquid, or gaseous fuel derived from such material.

Fuel cell means a boiler type in which the fuel is dropped onto suspended fixed grates and is fired in a pile. The refractory-lined fuel cell uses combustion air preheating and positioning of secondary and tertiary air injection ports to improve boiler efficiency. Fluidized bed, dutch oven, pile burner, hybrid suspension grate, and suspension burners are not part of the fuel cell subcategory.

Fuel type means each category of fuels that share a common name or classification. Examples include, but are not limited to, bituminous coal, sub-bituminous coal, lignite, anthracite, biomass, distillate oil, residual oil. Individual fuel types received from different suppliers are not considered new fuel types.

Gaseous fuel includes, but is not limited to, natural gas, process gas, landfill gas, coal derived gas, refinery gas, and biogas. Blast furnace gas and process gases that are regulated under another subpart of this part, or part 60, part 61, or part 65 of this chapter, are exempted from this definition.

Heat input means heat derived from combustion of fuel in a boiler or process heater and does not include the heat input from preheated combustion air, recirculated flue gases, returned condensate, or exhaust gases from other sources such as gas turbines, internal combustion engines, kilns, etc.

Heavy liquid includes residual oil and any other liquid fuel not classified as a light liquid.

Hourly average means the arithmetic average of at least four CMS data values representing the four 15-minute periods in an hour, or at least two 15-minute data values during an hour when CMS calibration, quality assurance, or maintenance activities are being performed.

Hot water heater means a closed vessel with a capacity of no more than 120 U.S. gallons in which water is heated by combustion of gaseous, liquid, or biomass/bio-based solid fuel and is withdrawn for use external to the vessel. Hot water boilers (i.e., not generating steam) combusting gaseous, liquid, or biomass fuel with a heat input capacity of less than 1.6 million Btu per hour are included in this definition. The 120 U.S. gallon capacity threshold to be considered a hot water heater is independent of the 1.6 MMBtu/hr heat input capacity threshold for hot water

boilers. Hot water heater also means a tankless unit that provides on demand hot water.

Hybrid suspension grate boiler means a boiler designed with air distributors to spread the fuel material over the entire width and depth of the boiler combustion zone. The biomass fuel combusted in these units exceeds a moisture content of 40 percent on an as-fired annual heat input basis as demonstrated by monthly fuel analysis. The drying and much of the combustion of the fuel takes place in suspension, and the combustion is completed on the grate or floor of the boiler. Fluidized bed, dutch oven, and pile burner designs are not part of the hybrid suspension grate boiler design category.

Industrial boiler means a boiler used in manufacturing, processing, mining, and refining or any other industry to provide steam, hot water, and/or electricity.

Light liquid includes distillate oil, biodiesel, or vegetable oil.

Limited-use boiler or process heater means any boiler or process heater that burns any amount of solid, liquid, or gaseous fuels and has a federally enforceable annual capacity factor of no more than 10 percent.

Liquid fuel includes, but is not limited to, light liquid, heavy liquid, any form of liquid fuel derived from petroleum, used oil, liquid biofuels, biodiesel, and vegetable oil.

Load fraction means the actual heat input of a boiler or process heater divided by heat input during the performance test that established the minimum sorbent injection rate or minimum activated carbon injection rate, expressed as a fraction (*e.g.*, for 50 percent load the load fraction is 0.5). For boilers and process heaters that cofire natural gas or refinery gas with a solid or liquid fuel, the load fraction is determined by the actual heat input of the solid or liquid fuel divided by heat input of the solid or liquid fuel fired during the performance test (*e.g.*, if the performance test was conducted at 100 percent solid fuel firing, for 100 percent load firing 50 percent solid fuel and 50 percent natural gas the load fraction is 0.5).

Major source for oil and natural gas production facilities, as used in this subpart, shall have the same meaning as in § 63.2, except that:

(1) Emissions from any oil or gas exploration or production well (with its associated equipment, as defined in this section), and emissions from any pipeline compressor station or pump station shall not be aggregated with emissions from other similar units to determine whether such emission points or stations are major sources, even when emission points are in a contiguous area or under common control;

(2) Emissions from processes, operations, or equipment that are not part of the same facility, as defined in this section, shall not be aggregated; and

(3) For facilities that are production field facilities, only HAP emissions from glycol dehydration units and storage vessels with the potential for flash emissions shall be aggregated for a major source determination. For facilities that are not production field facilities, HAP emissions from all HAP emission units shall be aggregated for a major source determination.

Metal process furnaces are a subcategory of process heaters, as defined in this subpart, which include natural gas-fired annealing furnaces, preheat furnaces, reheat furnaces, aging furnaces, heat treat furnaces, and homogenizing furnaces.

Million Btu (MMBtu) means one million British thermal units.

Minimum activated carbon injection rate means load fraction multiplied by the lowest hourly average activated carbon injection rate measured according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable emission limit.

Minimum oxygen level means the lowest hourly average oxygen level measured according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable emission limit.

Minimum pressure drop means the lowest hourly average pressure drop measured according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable emission limit.

Minimum scrubber effluent pH means the lowest hourly average sorbent liquid pH measured at the inlet to the wet

scrubber according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable hydrogen chloride emission limit.

Minimum scrubber liquid flow rate means the lowest hourly average liquid flow rate (e.g., to the PM scrubber or to the acid gas scrubber) measured according to Table 7 to this subpart during the most recent performance stack test demonstrating compliance with the applicable emission limit.

Minimum scrubber pressure drop means the lowest hourly average scrubber pressure drop measured according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable emission limit.

Minimum sorbent injection rate means:

(1) The load fraction multiplied by the lowest hourly average sorbent injection rate for each sorbent measured according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable emission limits; or

(2) For fluidized bed combustion not using an acid gas wet scrubber or dry sorbent injection control technology to comply with the HCl emission limit, the lowest average ratio of sorbent to sulfur measured during the most recent performance test.

Minimum total secondary electric power means the lowest hourly average total secondary electric power determined from the values of secondary voltage and secondary current to the electrostatic precipitator measured according to Table 7 to this subpart during the most recent performance test demonstrating compliance with the applicable emission limits.

Natural gas means:

(1) A naturally occurring mixture of hydrocarbon and nonhydrocarbon gases found in geologic formations beneath the earth's surface, of which the principal constituent is methane; or

(2) Liquefied petroleum gas, as defined in ASTM D1835 (incorporated by reference, see § 63.14); or

(3) A mixture of hydrocarbons that maintains a gaseous state at ISO conditions. Additionally, natural gas must either be composed of at least 70 percent methane by volume or have a gross calorific value between 35 and 41 megajoules (MJ) per dry standard cubic meter (950 and 1,100 Btu per dry standard cubic foot); or

(4) Propane or propane derived synthetic natural gas. Propane means a colorless gas derived from petroleum and natural gas, with the molecular structure C_3H_8.

Opacity means the degree to which emissions reduce the transmission of light and obscure the view of an object in the background.

Operating day means a 24-hour period between 12 midnight and the following midnight during which any fuel is combusted at any time in the boiler or process heater unit. It is not necessary for fuel to be combusted for the entire 24-hour period. For calculating rolling average emissions, an operating day does not include the hours of operation during startup or shutdown.

Other combustor means a unit designed to burn solid fuel that is not classified as a dutch oven, fluidized bed, fuel cell, hybrid suspension grate boiler, pulverized coal boiler, stoker, sloped grate, or suspension boiler as defined in this subpart.

Other gas 1 fuel means a gaseous fuel that is not natural gas or refinery gas and does not exceed a maximum mercury concentration of 40 micrograms/cubic meters of gas.

Oxygen analyzer system means all equipment required to determine the oxygen content of a gas stream and used to monitor oxygen in the boiler or process heater flue gas, boiler or process heater, firebox, or other appropriate location. This definition includes oxygen trim systems. The source owner or operator must install, calibrate, maintain, and operate the oxygen analyzer system in accordance with the manufacturer's recommendations.

Oxygen trim system means a system of monitors that is used to maintain excess air at the desired level in a combustion device over its operating load range. A typical system consists of a flue gas oxygen and/or CO monitor that automatically provides a feedback signal to the combustion air controller or draft controller.

Particulate matter (PM) means any finely divided solid or liquid material,

other than uncombined water, as measured by the test methods specified under this subpart, or an approved alternative method.

Period of gas curtailment or supply interruption means a period of time during which the supply of gaseous fuel to an affected boiler or process heater is restricted or halted for reasons beyond the control of the facility. The act of entering into a contractual agreement with a supplier of natural gas established for curtailment purposes does not constitute a reason that is under the control of a facility for the purposes of this definition. An increase in the cost or unit price of natural gas due to normal market fluctuations not during periods of supplier delivery restriction does not constitute a period of natural gas curtailment or supply interruption. On-site gaseous fuel system emergencies or equipment failures qualify as periods of supply interruption when the emergency or failure is beyond the control of the facility.

Pile burner means a boiler design incorporating a design where the anticipated biomass fuel has a high relative moisture content. Grates serve to support the fuel, and underfire air flowing up through the grates provides oxygen for combustion, cools the grates, promotes turbulence in the fuel bed, and fires the fuel. The most common form of pile burning is the dutch oven.

Process heater means an enclosed device using controlled flame, and the unit's primary purpose is to transfer heat indirectly to a process material (liquid, gas, or solid) or to a heat transfer material (e.g., glycol or a mixture of glycol and water) for use in a process unit, instead of generating steam. Process heaters are devices in which the combustion gases do not come into direct contact with process materials. A device combusting solid waste, as defined in § 241.3 of this chapter, is not a process heater unless the device is exempt from the definition of a solid waste incineration unit as provided in section 129(g)(1) of the Clean Air Act. Process heaters do not include units used for comfort heat or space heat, food preparation for on-site consumption, or autoclaves. Waste heat process heaters are excluded from this definition.

Pulverized coal boiler means a boiler in which pulverized coal or other solid fossil fuel is introduced into an air stream that carries the coal to the combustion chamber of the boiler where it is fired in suspension.

Qualified energy assessor means:

(1) Someone who has demonstrated capabilities to evaluate energy savings opportunities for steam generation and major energy using systems, including, but not limited to:

(i) Boiler combustion management.

(ii) Boiler thermal energy recovery, including

(A) Conventional feed water economizer,

(B) Conventional combustion air preheater, and

(C) Condensing economizer.

(iii) Boiler blowdown thermal energy recovery.

(iv) Primary energy resource selection, including

(A) Fuel (primary energy source) switching, and

(B) Applied steam energy versus direct-fired energy versus electricity.

(v) Insulation issues.

(vi) Steam trap and steam leak management.

(vi) Condensate recovery.

(viii) Steam end-use management.

(2) Capabilities and knowledge includes, but is not limited to:

(i) Background, experience, and recognized abilities to perform the assessment activities, data analysis, and report preparation.

(ii) Familiarity with operating and maintenance practices for steam or process heating systems.

(iii) Additional potential steam system improvement opportunities including improving steam turbine operations and reducing steam demand.

(iv) Additional process heating system opportunities including effective utilization of waste heat and use of proper process heating methods.

(v) Boiler-steam turbine cogeneration systems.

(vi) Industry specific steam end-use systems.

Refinery gas means any gas that is generated at a petroleum refinery and is combusted. Refinery gas includes natural gas when the natural gas is

combined and combusted in any proportion with a gas generated at a refinery. Refinery gas includes gases generated from other facilities when that gas is combined and combusted in any proportion with gas generated at a refinery.

Regulated gas stream means an offgas stream that is routed to a boiler or process heater for the purpose of achieving compliance with a standard under another subpart of this part or part 60, part 61, or part 65 of this chapter.

Residential boiler means a boiler used to provide heat and/or hot water and/or as part of a residential combined heat and power system. This definition includes boilers located at an institutional facility (e.g., university campus, military base, church grounds) or commercial/industrial facility (e.g., farm) used primarily to provide heat and/or hot water for:

(1) A dwelling containing four or fewer families; or

(2) A single unit residence dwelling that has since been converted or subdivided into condominiums or apartments.

Residual oil means crude oil, fuel oil that does not comply with the specifications under the definition of distillate oil, and all fuel oil numbers 4, 5, and 6, as defined by the American Society of Testing and Materials in ASTM D396–10 (incorporated by reference, *see* § 63.14(b)).

Responsible official means responsible official as defined in § 70.2.

Rolling average means the average of all data collected during the applicable averaging period. For demonstration of compliance with a CO CEMS-based emission limit based on CO concentration a 30-day (10-day) rolling average is comprised of the average of all the hourly average concentrations over the previous 720 (240) operating hours calculated each operating day. To demonstrate compliance on a 30-day rolling average basis for parameters other than CO, you must indicate the basis of the 30-day rolling average period you are using for compliance, as discussed in § 63.7545(e)(2)(iii). If you indicate the 30 operating day basis, you must calculate a new average value each operating day and shall include the measured hourly values for the preceding 30 operating days. If you select the 720 operating hours basis, you must average of all the hourly average concentrations over the previous 720 operating hours calculated each operating day.

Secondary material means the material as defined in § 241.2 of this chapter.

Shutdown means the period in which cessation of operation of a boiler or process heater is initiated for any purpose. Shutdown begins when the boiler or process heater no longer supplies useful thermal energy (such as heat or steam) for heating, cooling, or process purposes and/or generates electricity or when no fuel is being fed to the boiler or process heater, whichever is earlier. Shutdown ends when the boiler or process heater no longer supplies useful thermal energy (such as steam or heat) for heating, cooling, or process purposes and/or generates electricity, and no fuel is being combusted in the boiler or process heater.

Sloped grate means a unit where the solid fuel is fed to the top of the grate from where it slides downwards; while sliding the fuel first dries and then ignites and burns. The ash is deposited at the bottom of the grate. Fluidized bed, dutch oven, pile burner, hybrid suspension grate, suspension burners, and fuel cells are not considered to be a sloped grate design.

Solid fossil fuel includes, but is not limited to, coal, coke, petroleum coke, and tire derived fuel.

Solid fuel means any solid fossil fuel or biomass or bio-based solid fuel.

Startup means:

(1) Either the first-ever firing of fuel in a boiler or process heater for the purpose of supplying useful thermal energy for heating and/or producing electricity, or for any other purpose, or the firing of fuel in a boiler after a shutdown event for any purpose. Startup ends when any of the useful thermal energy from the boiler or process heater is supplied for heating, and/or producing electricity, or for any other purpose, or

(2) The period in which operation of a boiler or process heater is initiated for any purpose. Startup begins with either the first-ever firing of fuel in a boiler or process heater for the purpose of supplying useful thermal energy

(such as steam or heat) for heating, cooling or process purposes, or producing electricity, or the firing of fuel in a boiler or process heater for any purpose after a shutdown event. Start-up ends four hours after when the boiler or process heater supplies useful thermal energy (such as heat or steam) for heating, cooling, or process purposes, or generates electricity, whichever is earlier.

Steam output means:

(1) For a boiler that produces steam for process or heating only (no power generation), the energy content in terms of MMBtu of the boiler steam output,

(2) For a boiler that cogenerates process steam and electricity (also known as combined heat and power), the total energy output, which is the sum of the energy content of the steam exiting the turbine and sent to process in MMBtu and the energy of the electricity generated converted to MMBtu at a rate of 10,000 Btu per kilowatt-hour generated (10 MMBtu per megawatt-hour), and

(3) For a boiler that generates only electricity, the alternate output-based emission limits would be the appropriate emission limit from Table 1, 2, 14, or 15 to this subpart in units of pounds per million Btu heat input (lb per MWh).

(4) For a boiler that performs multiple functions and produces steam to be used for any combination of paragraphs (1), (2), and (3) of this definition that includes electricity generation of paragraph (3) of this definition, the total energy output, in terms of MMBtu of steam output, is the sum of the energy content of steam sent directly to the process and/or used for heating (S_1), the energy content of turbine steam sent to process plus energy in electricity according to paragraph (2) of this definition (S_2), and the energy content of electricity generated by a electricity only turbine as paragraph (3) of this definition (MW_3) and would be calculated using Equation 1 to this definition. In the case of boilers supplying steam to one or more common headers, S_1, S_2, and $MW_{(3)}$ for each boiler would be calculated based on its (steam energy) contribution (fraction of total steam energy) to the common header.

Equation 1 to the definition *Steam Output*

$$SO_M = S_1 + S_2 + (MW_{(3)}\ x\ CFn) \qquad \text{(Eq. 1)}$$

Where:

SO_M = Total steam output for multi-function boiler, MMBtu.

S_1 = Energy content of steam sent directly to the process and/or used for heating, MMBtu.

S_2 = Energy content of turbine steam sent to the process plus energy in electricity according to paragraph (2) of this definition, MMBtu.

$MW_{(3)}$ = Electricity generated according to paragraph (3) of this definition, MWh.

CFn = Conversion factor for the appropriate subcategory for converting electricity generated according to paragraph (3) of this definition to equivalent steam energy, MMBtu/MWh.

CFn for emission limits for boilers in the unit designed to burn solid fuel subcategory = 10.8.

CFn PM and CO emission limits for boilers in one of the subcategories of units designed to burn coal = 11.7.

CFn PM and CO emission limits for boilers in one of the subcategories of units designed to burn biomass = 12.1.

CFn for emission limits for boilers in one of the subcategories of units designed to burn liquid fuel = 11.2.

CFn for emission limits for boilers in the unit designed to burn gas 2 (other) subcategory = 6.2.

Stoker means a unit consisting of a mechanically operated fuel feeding mechanism, a stationary or moving grate to support the burning of fuel and admit under-grate air to the fuel, an overfire air system to complete combustion, and an ash discharge system. This definition of stoker includes

air swept stokers. There are two general types of stokers: Underfeed and overfeed. Overfeed stokers include mass feed and spreader stokers. Fluidized bed, dutch oven, pile burner, hybrid suspension grate, suspension burners, and fuel cells are not considered to be a stoker design.

Stoker/sloped grate/other unit designed to burn kiln dried biomass means the unit is in the units designed to burn biomass/bio-based solid subcategory that is either a stoker, sloped grate, or other combustor design and is not in the stoker/sloped grate/other units designed to burn wet biomass subcategory.

Stoker/sloped grate/other unit designed to burn wet biomass means the unit is in the units designed to burn biomass/biobased solid subcategory that is either a stoker, sloped grate, or other combustor design and any of the biomass/bio-based solid fuel combusted in the unit exceeds 20 percent moisture on an annual heat input basis.

Suspension burner means a unit designed to fire dry biomass/biobased solid particles in suspension that are conveyed in an airstream to the furnace like pulverized coal. The combustion of the fuel material is completed on a grate or floor below. The biomass/biobased fuel combusted in the unit shall not exceed 20 percent moisture on an annual heat input basis. Fluidized bed, dutch oven, pile burner, and hybrid suspension grate units are not part of the suspension burner subcategory.

Temporary boiler means any gaseous or liquid fuel boiler or process heater that is designed to, and is capable of, being carried or moved from one location to another by means of, for example, wheels, skids, carrying handles, dollies, trailers, or platforms. A boiler or process heater is not a temporary boiler or process heater if any one of the following conditions exists:

(1) The equipment is attached to a foundation.

(2) The boiler or process heater or a replacement remains at a location within the facility and performs the same or similar function for more than 12 consecutive months, unless the regulatory agency approves an extension. An extension may be granted by the regulating agency upon petition by the owner or operator of a unit specifying the basis for such a request. Any temporary boiler or process heater that replaces a temporary boiler or process heater at a location and performs the same or similar function will be included in calculating the consecutive time period.

(3) The equipment is located at a seasonal facility and operates during the full annual operating period of the seasonal facility, remains at the facility for at least 2 years, and operates at that facility for at least 3 months each year.

(4) The equipment is moved from one location to another within the facility but continues to perform the same or similar function and serve the same electricity, process heat, steam, and/or hot water system in an attempt to circumvent the residence time requirements of this definition.

Total selected metals (TSM) means the sum of the following metallic hazardous air pollutants: arsenic, beryllium, cadmium, chromium, lead, manganese, nickel and selenium.

Traditional fuel means the fuel as defined in §241.2 of this chapter.

Tune-up means adjustments made to a boiler or process heater in accordance with the procedures outlined in §63.7540(a)(10).

Ultra low sulfur liquid fuel means a distillate oil that has less than or equal to 15 ppm sulfur.

Unit designed to burn biomass/bio-based solid subcategory includes any boiler or process heater that burns at least 10 percent biomass or bio-based solids on an annual heat input basis in combination with solid fossil fuels, liquid fuels, or gaseous fuels.

Unit designed to burn coal/solid fossil fuel subcategory includes any boiler or process heater that burns any coal or other solid fossil fuel alone or at least 10 percent coal or other solid fossil fuel on an annual heat input basis in combination with liquid fuels, gaseous fuels, or less than 10 percent biomass and bio-based solids on an annual heat input basis.

Unit designed to burn gas 1 subcategory includes any boiler or process heater that burns only natural gas, refinery gas, and/or other gas 1 fuels. Gaseous

fuel boilers and process heaters that burn liquid fuel for periodic testing of liquid fuel, maintenance, or operator training, not to exceed a combined total of 48 hours during any calendar year, are included in this definition. Gaseous fuel boilers and process heaters that burn liquid fuel during periods of gas curtailment or gas supply interruptions of any duration are also included in this definition.

Unit designed to burn gas 2 (other) subcategory includes any boiler or process heater that is not in the unit designed to burn gas 1 subcategory and burns any gaseous fuels either alone or in combination with less than 10 percent coal/solid fossil fuel, and less than 10 percent biomass/bio-based solid fuel on an annual heat input basis, and no liquid fuels. Gaseous fuel boilers and process heaters that are not in the unit designed to burn gas 1 subcategory and that burn liquid fuel for periodic testing of liquid fuel, maintenance, or operator training, not to exceed a combined total of 48 hours during any calendar year, are included in this definition. Gaseous fuel boilers and process heaters that are not in the unit designed to burn gas 1 subcategory and that burn liquid fuel during periods of gas curtailment or gas supply interruption of any duration are also included in this definition.

Unit designed to burn heavy liquid subcategory means a unit in the unit designed to burn liquid subcategory where at least 10 percent of the heat input from liquid fuels on an annual heat input basis comes from heavy liquids.

Unit designed to burn light liquid subcategory means a unit in the unit designed to burn liquid subcategory that is not part of the unit designed to burn heavy liquid subcategory.

Unit designed to burn liquid subcategory includes any boiler or process heater that burns any liquid fuel, but less than 10 percent coal/solid fossil fuel and less than 10 percent biomass/bio-based solid fuel on an annual heat input basis, either alone or in combination with gaseous fuels. Units in the unit design to burn gas 1 or unit designed to burn gas 2 (other) subcategories that burn liquid fuel for periodic testing of liquid fuel, maintenance, or operator training, not to exceed a combined total of 48 hours during any calendar year are not included in this definition. Units in the unit design to burn gas 1 or unit designed to burn gas 2 (other) subcategories during periods of gas curtailment or gas supply interruption of any duration are also not included in this definition.

Unit designed to burn liquid fuel that is a non-continental unit means an industrial, commercial, or institutional boiler or process heater meeting the definition of the unit designed to burn liquid subcategory located in the State of Hawaii, the Virgin Islands, Guam, American Samoa, the Commonwealth of Puerto Rico, or the Northern Mariana Islands.

Unit designed to burn solid fuel subcategory means any boiler or process heater that burns only solid fuels or at least 10 percent solid fuel on an annual heat input basis in combination with liquid fuels or gaseous fuels.

Useful thermal energy means energy (*i.e.*, steam, hot water, or process heat) that meets the minimum operating temperature, flow, and/or pressure required by any energy use system that uses energy provided by the affected boiler or process heater.

Vegetable oil means oils extracted from vegetation.

Voluntary Consensus Standards or VCS mean technical standards (*e.g.*, materials specifications, test methods, sampling procedures, business practices) developed or adopted by one or more voluntary consensus bodies. EPA/Office of Air Quality Planning and Standards, by precedent, has only used VCS that are written in English. Examples of VCS bodies are: American Society of Testing and Materials (ASTM 100 Barr Harbor Drive, P.O. Box CB700, West Conshohocken, Pennsylvania 19428–B2959, (800) 262–1373, *http://www.astm.org*), American Society of Mechanical Engineers (ASME ASME, Three Park Avenue, New York, NY 10016–5990, (800) 843–2763, *http://www.asme.org*), International Standards Organization (ISO 1, ch. de la Voie-Creuse, Case postale 56, CH–1211 Geneva 20, Switzerland, + 41 22 749 01 11,

http://www.iso.org/iso/home.htm), Standards Australia (AS Level 10, The Exchange Centre, 20 Bridge Street, Sydney, GPO Box 476, Sydney NSW 2001, + 61 2 9237 6171 *http://www.stadards.org.au*), British Standards Institution (BSI, 389 Chiswick High Road, London, W4 4AL, United Kingdom, + 44 (0)20 8996 9001, *http://www.bsigroup.com*), Canadian Standards Association (CSA 5060 Spectrum Way, Suite 100, Mississauga, Ontario L4W 5N6, Canada, 800–463–6727, *http://www.csa.ca*), European Committee for Standardization (CEN CENELEC Management Centre Avenue Marnix 17 B–1000 Brussels, Belgium + 32 2 550 08 11, *http://www.cen.eu/cen*), and German Engineering Standards (VDI VDI Guidelines Department, P.O. Box 10 11 39 40002, Duesseldorf, Germany, + 49 211 6214–230, *http://www.vdi.eu*). The types of standards that are not considered VCS are standards developed by: The United States, *e.g.*, California (CARB) and Texas (TCEQ); industry groups, such as American Petroleum Institute (API), Gas Processors Association (GPA), and Gas Research Institute (GRI); and other branches of the U.S. government, *e.g.*, Department of Defense (DOD) and Department of Transportation (DOT). This does not preclude EPA from using standards developed by groups that are not VCS bodies within their rule. When this occurs, EPA has done searches and reviews for VCS equivalent to these non-EPA methods.

Waste heat boiler means a device that recovers normally unused energy (i.e., hot exhaust gas) and converts it to usable heat. Waste heat boilers are also referred to as heat recovery steam generators. Waste heat boilers are heat exchangers generating steam from incoming hot exhaust gas from an industrial (e.g., thermal oxidizer, kiln, furnace) or power (e.g., combustion turbine, engine) equipment. Duct burners are sometimes used to increase the temperature of the incoming hot exhaust gas.

Waste heat process heater means an enclosed device that recovers normally unused energy (i.e., hot exhaust gas) and converts it to usable heat. Waste heat process heaters are also referred to as recuperative process heaters. This definition includes both fired and unfired waste heat process heaters.

Wet scrubber means any add-on air pollution control device that mixes an aqueous stream or slurry with the exhaust gases from a boiler or process heater to control emissions of particulate matter or to absorb and neutralize acid gases, such as hydrogen chloride. A wet scrubber creates an aqueous stream or slurry as a byproduct of the emissions control process.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the Clean Air Act.

[78 FR 15664, Mar. 21, 2011, as amended at 78 FR 7163, Jan. 31, 2013; 80 FR 72817, Nov. 20, 2015; 87 FR 60846, Oct. 6, 2022]

TABLE 1 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS[c]

As stated in §63.7500, you must comply with the following applicable emission limits:

TABLE 1 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling
1. Units in all subcategories designed to burn solid fuel.	a. HCl	2.1E–04 [a] lb per MMBtu of heat input.	2.9E–04 [a] lb per MMBtu of steam output or 2.7E–03 [a] lb per MWh.	For M26A, collect a minimum of 1 dscm per run; for M26 collect a minimum of 120 liters per run.
	b. Mercury	8.0E–07 [a] lb per MMBtu of heat input.	8.7E–07 [a] lb per MMBtu of steam output or 1.1E–05 [a] lb per MWh.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 4 dscm.
2. Units designed to burn coal/solid fossil fuel.	a. Filterable PM (or TSM).	1.1E–03 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	1.1E–03 lb per MMBtu of steam output or 1.4E–02 lb per MWh; or (2.7E–05 lb per MMBtu of steam output or 2.9E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
3. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. Carbon monoxide (CO) (or CEMS).	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3-percent oxygen, [d] 30-day rolling average).	0.11 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
4. Stokers/others designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3-percent oxygen [d], 30-day rolling average).	0.12 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
5. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3-percent oxygen, [d] 30-day rolling average).	0.11 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
6. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	140 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3-percent oxygen, [d] 30-day rolling average).	1.2E–01 lb per MMBtu of steam output or 1.5 lb per MWh; 3-run average.	1 hr minimum sampling time.

TABLE 1 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]—Continued

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling
7. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS)	590 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (390 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	6.1E–01 lb per MMBtu of steam output or 6.5 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.3E–02 lb per MMBtu of heat input; or (2.6E–05 lb per MMBtu of heat input).	1.4E–02 lb per MMBtu of steam output or 1.9E–01 lb per MWh; or (2.7E–05 lb per MMBtu of steam output or 3.7E–04 lb per MWh).	Collect a minimum of 2 dscm per run.
8. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	460 ppm by volume on a dry basis corrected to 3-percent oxygen.	4.3E–01 lb per MMBtu of steam output or 5.1 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (5.0E–03 lb per MMBtu of heat input).	3.5E–02 lb per MMBtu of steam output or 4.2E–01 lb per MWh; or (5.2E–03 lb per MMBtu of steam output or 7.0E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
9. Fluidized bed units designed to burn biomass/bio-based solids.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	1.3E–01 lb per MMBtu of steam output or 1.5 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	4.1E–03 lb per MMBtu of heat input; or (8.4E–06 [a] lb per MMBtu of heat input).	5.0E–03 lb per MMBtu of steam output or 5.8E–02 lb per MWh; or (1.1E–05 [a] lb per MMBtu of steam output or 1.2E–04 [a] lb per MWh).	Collect a minimum of 3 dscm per run.
10. Suspension burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	220 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 10-day rolling average).	0.18 lb per MMBtu of steam output or 2.5 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (8.0E–03 lb per MMBtu of heat input).	3.1E–02 lb per MMBtu of steam output or 4.2E–01 lb per MWh; or (8.1E–03 lb per MMBtu of steam output or 1.2E–01 lb per MWh).	Collect a minimum of 2 dscm per run.

TABLE 1 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]—Continued

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling
11. Dutch Ovens/Pile burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	330 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 10-day rolling average).	3.5E–01 lb per MMBtu of steam output or 3.6 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.5E–03 lb per MMBtu of heat input; or (3.9E–05 lb per MMBtu of heat input).	3.4E–03 lb per MMBtu of steam output or 3.5E–02 lb per MWh; or (5.2E–05 lb per MMBtu of steam output or 5.5E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
12. Fuel cell units designed to burn biomass/bio-based solids.	a. CO	910 ppm by volume on a dry basis corrected to 3-percent oxygen.	1.1 lb per MMBtu of steam output or 1.0E+01 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.1E–02 lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	2.0E–02 lb per MMBtu of steam output or 1.6E–01 lb per MWh; or (5.1E–05 lb per MMBtu of steam output or 4.1E–04 lb per MWh).	Collect a minimum of 2 dscm per run.
13. Hybrid suspension grate boiler designed to burn biomass/bio-based solids.	a. CO (or CEMS)	180 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3-percent oxygen[d], 30-day rolling average).	0.22 lb per MMBtu of steam output or 2.0 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.6E–02 lb per MMBtu of heat input; or (4.4E–04 lb per MMBtu of heat input).	3.3E–02 lb per MMBtu of steam output or 3.7E–01 lb per MWh; or (5.5E–04 lb per MMBtu of steam output or 6.2E–03 lb per MWh).	Collect a minimum of 3 dscm per run.
14. Units designed to burn liquid fuel.	a. HCl	1.5E–04[a] lb per MMBtu of heat input.	1.7E–04[a] lb per MMBtu of steam output or 2.1E–03[a] lb per MWh.	For M26A: Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	b. Mercury	4.8E–07[a] lb per MMBtu of heat input.	5.3E–07[a] lb per MMBtu of steam output or 6.7E–06[a] lb per MWh.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784[b] collect a minimum of 4 dscm.
15. Units designed to burn heavy liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.

TABLE 1 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]—Continued

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling
	b. Filterable PM (or TSM).	1.9E–03 lb per MMBtu of heat input; or (6.1E–06 [a] lb per MMBtu of heat input).	2.1E–03 lb per MMBtu of steam output or 2.7E–02 lb per MWh; or (6.7E–6 [a] lb per MMBtu of steam output or 8.5E–5 [a] lb per MWh).	Collect a minimum of 3 dscm per run.
16. Units designed to burn light liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.1E–03 [a] lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	1.2E–03 [a] lb per MMBtu of steam output or 1.6E–02 [a] lb per MWh; or (3.2E–05 lb per MMBtu of steam output or 4.0E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
17. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average based on stack test.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.3E–02 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	2.5E–02 lb per MMBtu of steam output or 3.2E–01 lb per MWh; or (9.4E–04 lb per MMBtu of steam output or 1.2E–02 lb per MWh).	Collect a minimum of 4 dscm per run.
18. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.16 lb per MMBtu of steam output or 1.0 lb per MWh.	1 hr minimum sampling time.
	b. HCl	1.7E–03 lb per MMBtu of heat input.	2.9E–03 lb per MMBtu of steam output or 1.8E–02 lb per MWh.	For M26A, collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input.	1.4E–05 lb per MMBtu of steam output or 8.3E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 3 dscm.
	d. Filterable PM (or TSM).	7.3E–03 lb per MMBtu of heat input; or (2.1E–04 lb per MMBtu of heat input).	1.3E–02 lb per MMBtu of steam output or 7.6E–02 lb per MWh; or (3.5E–04 lb per MMBtu of steam output or 2.2E–03 lb per MWh).	Collect a minimum of 3 dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit, you can skip testing according to §63.7515 if all of the other provisions of §63.7515 are met. For all other pollutants that do not contain a footnote "a", your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see §63.14.

[c] If your affected source is a new or reconstructed affected source that commenced construction or reconstruction after June 4, 2010, and before April 1, 2013, you may comply with the emission limits in Table 11, 12, or 13 to this subpart until January 31, 2016. On and after January 31, 2016, but before October 6, 2025 you may comply with the emission limits in Table 14 to this subpart. On and after October 6, 2025 you must comply with the emission limits in this Table 1.

[d] An owner or operator may determine compliance with the carbon monoxide emissions limit using CO_2 as a diluent correction in place of oxygen as described in §63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit and must also take into account that the 3-percent oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to §63.7505(d).

[87 FR 60847, Oct. 6, 2022]

TABLE 2 TO SUBPART DDDDD OF PART 63—EMISSION LIMITS FOR EXISTING BOILERS AND PROCESS HEATERS [d]

As stated in §63.7500, you must comply with the following applicable emission limits:

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
1. Units in all subcategories designed to burn solid fuel.	a. HCl	2.0E–02 lb per MMBtu of heat input.	2.3E–02 lb per MMBtu of steam output or 0.26 lb per MWh.	For M26A, collect a minimum of 1 dscm per run; for M26, collect a minimum of 120 liters per run.
	b. Mercury	5.4E–06 lb per MMBtu of heat input.	6.2E–06 lb per MMBtu of steam output or 6.9E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 3 dscm.
2. Units design to burn coal/solid fossil fuel.	a. Filterable PM (or TSM).	3.9E–02 lb per MMBtu of heat input; or (5.3E–05 lb per MMBtu of heat input).	4.1E–02 lb per MMBtu of steam output or 4.8E–01 lb per MWh; or (5.6E–05 lb per MMBtu of steam output or 6.5E–04 lb per MWh).	Collect a minimum of 2 dscm per run.
3. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	0.11 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
4. Stokers/others designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	150 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	0.14 lb per MMBtu of steam output or 1.6 lb per MWh; 3-run average.	1 hr minimum sampling time.
5. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	0.12 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
6. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	140 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	1.3E–01 lb per MMBtu of steam output or 1.5 lb per MWh; 3-run average.	1 hr minimum sampling time.
7. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS)	1,100 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (720 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	1.1 lb per MMBtu of steam output or 13 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.4E–02 lb per MMBtu of heat input; or (2.0E–04 lb per MMBtu of heat input).	4.0E–02 lb per MMBtu of steam output or 4.8E–01 lb per MWh; or (2.4E–04 lb per MMBtu of steam output or 2.8E–03 lb per MWh).	Collect a minimum of 2 dscm per run.
8. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	460 ppm by volume on a dry basis corrected to 3-percent oxygen.	4.2E–01 lb per MMBtu of steam output or 5.1 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.2E–01 lb per MMBtu of heat input; or (5.0E–03 lb per MMBtu of heat input).	3.7E–01 lb per MMBtu of steam output or 4.5 lb per MWh; or (5.9E–03 lb per MMBtu of steam output or 7.0E–02 lb per MWh).	Collect a minimum of 1 dscm per run.
9. Fluidized bed units designed to burn biomass/bio-based solid.	a. CO (or CEMS)	210 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	2.1E–01 lb per MMBtu of steam output or 2.3 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	7.4E–03 lb per MMBtu of heat input; or (6.4E–05 lb per MMBtu of heat input).	9.2E–03 lb per MMBtu of steam output or 0.11 lb per MWh; or (8.0E–05 lb per MMBtu of steam output or 9.0E–04 lb per MWh).	Collect a minimum of 1 dscm per run.
10. Suspension burners designed to burn biomass/bio-based solid.	a. CO (or CEMS)	2,400 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 10-day rolling average).	1.9 lb per MMBtu of steam output or 27 lb per MWh; 3-run average.	1 hr minimum sampling time.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	b. Filterable PM (or TSM).	4.1E–02 lb per MMBtu of heat input; or (8.0E–03 lb per MMBtu of heat input).	4.2E–02 lb per MMBtu of steam output or 5.8E–01 lb per MWh; or (8.1E–03 lb per MMBtu of steam output or 0.12 lb per MWh).	Collect a minimum of 2 dscm per run.
11. Dutch Ovens/Pile burners designed to burn biomass/bio-based solid.	a. CO (or CEMS)	770 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 10-day rolling average).	8.4E–01 lb per MMBtu of steam output or 8.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.8E–01 lb per MMBtu of heat input; or (2.0E–03 lb per MMBtu of heat input).	2.5E–01 lb per MMBtu of steam output or 2.6 lb per MWh; or (2.8E–03 lb per MMBtu of steam output or 2.8E–02 lb per MWh).	Collect a minimum of 1 dscm per run.
12. Fuel cell units designed to burn biomass/bio-based solid.	a. CO	1,100 ppm by volume on a dry basis corrected to 3-percent oxygen.	2.4 lb per MMBtu of steam output or 12 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.0E–02 lb per MMBtu of heat input; or (5.8E–03 lb per MMBtu of heat input).	5.5E–02 lb per MMBtu of steam output or 2.8E–01 lb per MWh; or (1.6E–02 lb per MMBtu of steam output or 8.1E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
13. Hybrid suspension grate units designed to burn biomass/bio-based solid.	a. CO (or CEMS)	3,500 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	3.5 lb per MMBtu of steam output or 39 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	4.4E–01 lb per MMBtu of heat input; or (4.5E–04 lb per MMBtu of heat input).	5.5E–01 lb per MMBtu of steam output or 6.2 lb per MWh; or (5.7E–04 lb per MMBtu of steam output or 6.3E–03 lb per MWh).	Collect a minimum of 1 dscm per run.
14. Units designed to burn liquid fuel.	a. HCl	1.1E–03 lb per MMBtu of heat input.	1.4E–03 lb per MMBtu of steam output or 1.6E–02 lb per MWh.	For M26A, collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	b. Mercury	7.3E–07 lb per MMBtu of heat input.	8.8E–07 lb per MMBtu of steam output or 1.1E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B collect a minimum sample as specified in the method, for ASTM D6784[b] collect a minimum of 2 dscm.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
15. Units designed to burn heavy liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	5.9E–02 lb per MMBtu of heat input; or (2.0E–04 lb per MMBtu of heat input).	7.2E–02 lb per MMBtu of steam output or 8.2E–01 lb per MWh; or (2.5E–04 lb per MMBtu of steam output or 2.8E–03 lb per MWh).	Collect a minimum of 1 dscm per run.
16. Units designed to burn light liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	7.9E–03 lb per MMBtu of heat input; or (6.2E–05 lb per MMBtu of heat input).	9.6E–03 lb per MMBtu of steam output or 1.1E–01 lb per MWh; or (7.5E–05 lb per MMBtu of steam output or 8.6E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
17. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average based on stack test.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.2E–01 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	2.7E–01 lb per MMBtu of steam output or 3.1 lb per MWh; or (1.1E–03 lb per MMBtu of steam output or 1.2E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
18. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.16 lb per MMBtu of steam output or 1.0 lb per MWh.	1 hr minimum sampling time.
.....	b. HCl	1.7E–03 lb per MMBtu of heat input.	2.9E–03 lb per MMBtu of steam output or 1.8E–02 lb per MWh.	For M26A, collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input.	1.4E–05 lb per MMBtu of steam output or 8.3E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 2 dscm.
	d. Filterable PM (or TSM).	7.3E–03 lb per MMBtu of heat input or (2.1E–04 lb per MMBtu of heat input).	1.3E–02 lb per MMBtu of steam output or 7.6E–02 lb per MWh; or (3.5E–04 lb per MMBtu of steam output or 2.2E–03 lb per MWh).	Collect a minimum of 3 dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit, you can skip testing according to §63.7515 if all of the other provisions of §63.7515 are met. For all other pollutants that do not contain a footnote a, your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see §63.14.

[c] An owner or operator may determine compliance with the carbon monoxide emissions limit be determined using CO_2 as a diluent correction in place of oxygen as described in §63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit and must also take into account that the 3-percent oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to §63.7505(d).

[d] Before October 6, 2025 you may comply with the emission limits in Table 15 to this subpart. On and after October 6, 2025], you must comply with the emission limits in this Table 2.

[87 FR 60849, Oct. 6, 2022]

TABLE 3 TO SUBPART DDDDD OF PART 63—WORK PRACTICE STANDARDS

As stated in §63.7500, you must comply with the following applicable work practice standards:

If your unit is . . .	You must meet the following . . .
1. A new or existing boiler or process heater with a continuous oxygen trim system that maintains an optimum air to fuel ratio, or a heat input capacity of less than or equal to 5 million Btu per hour in any of the following subcategories: unit designed to burn gas 1; unit designed to burn gas 2 (other); or unit designed to burn light liquid, or a limited use boiler or process heater.	Conduct a tune-up of the boiler or process heater every 5 years as specified in §63.7540.
2. A new or existing boiler or process heater without a continuous oxygen trim system and with heat input capacity of less than 10 million Btu per hour in the unit designed to burn heavy liquid or unit designed to burn solid fuel subcategories; or a new or existing boiler or process heater with heat input capacity of less than 10 million Btu per hour, but greater than 5 million Btu per hour, in any of the following subcategories: unit designed to burn gas 1; unit designed to burn gas 2 (other); or unit designed to burn light liquid.	Conduct a tune-up of the boiler or process heater biennially as specified in §63.7540.
3. A new or existing boiler or process heater without a continuous oxygen trim system and with heat input capacity of 10 million Btu per hour or greater.	Conduct a tune-up of the boiler or process heater annually as specified in §63.7540. Units in either the Gas 1 or Metal Process Furnace subcategories will conduct this tune-up as a work practice for all regulated emissions under this subpart. Units in all other subcategories will conduct this tune-up as a work practice for dioxins/furans.
4. An existing boiler or process heater located at a major source facility, not including limited use units.	Must have a one-time energy assessment performed by a qualified energy assessor. An energy assessment completed on or after January 1, 2008, that meets or is amended to meet the energy assessment requirements in this table, satisfies the energy assessment requirement. A facility that operated under an energy management program developed according to the ENERGY STAR guidelines for energy management or compatible with ISO 50001 for at least one year between January 1, 2008 and the compliance date specified in §63.7495 that includes the affected units also satisfies the energy assessment requirement. The energy assessment must include the following with extent of the evaluation for items a. to e. appropriate for the on-site technical hours listed in §63.7575: a. A visual inspection of the boiler or process heater system. b. An evaluation of operating characteristics of the boiler or process heater systems, specifications of energy using systems, operating and maintenance procedures, and unusual operating constraints. c. An inventory of major energy use systems consuming energy from affected boilers and process heaters and which are under the control of the boiler/process heater owner/operator. d. A review of available architectural and engineering plans, facility operation and maintenance procedures and logs, and fuel usage. e. A review of the facility's energy management program and provide recommendations for improvements consistent with the definition of energy management program, if identified. f. A list of cost-effective energy conservation measures that are within the facility's control. g. A list of the energy savings potential of the energy conservation measures identified.

If your unit is . . .	You must meet the following . . .
	h. A comprehensive report detailing the ways to improve efficiency, the cost of specific improvements, benefits, and the time frame for recouping those investments.
5. An existing or new boiler or process heater subject to emission limits in Table 1 or 2 or 11 through 15 to this subpart during startup.	a. You must operate all CMS during startup. b. For startup of a boiler or process heater, you must use one or a combination of the following clean fuels: natural gas, synthetic natural gas, propane, other Gas 1 fuels, distillate oil, syngas, ultra-low sulfur diesel, fuel oil-soaked rags, kerosene, hydrogen, paper, cardboard, refinery gas, liquefied petroleum gas, clean dry biomass, and any fuels meeting the appropriate HCl, mercury and TSM emission standards by fuel analysis. c. You have the option of complying using either of the following work practice standards. (1) If you choose to comply using paragraph (1) of the definition of ''startup'' in § 63.7575, once you start firing fuels that are not clean fuels you must vent emissions to the main stack(s) and engage all of the applicable control devices except limestone injection in fluidized bed combustion (FBC) boilers, dry scrubber, fabric filter, and selective catalytic reduction (SCR). You must start your limestone injection in FBC boilers, dry scrubber, fabric filter, and SCR systems as expeditiously as possible. Startup ends when steam or heat is supplied for any purpose, OR (2) If you choose to comply using paragraph (2) of the definition of ''startup'' in § 63.7575, once you start to feed fuels that are not clean fuels, you must vent emissions to the main stack(s) and engage all of the applicable control devices so as to comply with the emission limits within 4 hours of start of supplying useful thermal energy. You must engage and operate PM control within one hour of first feeding fuels that are not clean fuels[a]. You must start all applicable control devices as expeditiously as possible, but, in any case, when necessary to comply with other standards applicable to the source by a permit limit or a rule other than this subpart that require operation of the control devices. You must develop and implement a written startup and shutdown plan, as specified in § 63.7505(e). d. You must comply with all applicable emission limits at all times except during startup and shutdown periods at which time you must meet this work practice. You must collect monitoring data during periods of startup, as specified in § 63.7535(b). You must keep records during periods of startup. You must provide reports concerning activities and periods of startup, as specified in § 63.7555.
6. An existing or new boiler or process heater subject to emission limits in Table 1 or 2 or Tables 11 through 15 to this subpart during shutdown.	You must operate all CMS during shutdown. While firing fuels that are not clean fuels during shutdown, you must vent emissions to the main stack(s) and operate all applicable control devices, except limestone injection in FBC boilers, dry scrubber, fabric filter, and SCR but, in any case, when necessary to comply with other standards applicable to the source that require operation of the control device. If, in addition to the fuel used prior to initiation of shutdown, another fuel must be used to support the shutdown process, that additional fuel must be one or a combination of the following clean fuels: Natural gas, synthetic natural gas, propane, other Gas 1 fuels, distillate oil, syngas, ultra-low sulfur diesel, refinery gas, and liquefied petroleum gas. You must comply with all applicable emissions limits at all times except for startup or shutdown periods conforming with this work practice. You must collect monitoring data during periods of shutdown, as specified in § 63.7535(b). You must keep records during periods of shutdown. You must provide reports concerning activities and periods of shutdown, as specified in § 63.7555.

[a] As specified in § 63.7555(d)(13), the source may request an alternative timeframe with the PM controls requirement to the permitting authority (state, local, or tribal agency) that has been delegated authority for this subpart by EPA. The source must provide evidence that (1) it is unable to safely engage and operate the PM control(s) to meet the ''fuel firing + 1 hour'' requirement and (2) the PM control device is appropriately designed and sized to meet the filterable PM emission limit. It is acknowledged that there may be another control device that has been installed other than ESP that provides additional PM control (e.g., scrubber).

[87 FR 60852, Oct. 6, 2022]

TABLE 4 TO SUBPART DDDDD OF PART 63—OPERATING LIMITS FOR BOILERS AND PROCESS HEATERS

As stated in §63.7500, you must comply with the applicable operating limits:

TABLE 4 TO SUBPART DDDDD OF PART 63—OPERATING LIMITS FOR BOILERS AND PROCESS HEATERS

When complying with a numerical emission limit under Table 1, 2, 11, 12, 13, 14, or 15 of this subpart using . . .	You must meet these operating limits. . .
1. Wet PM scrubber control on a boiler or process heater not using a PM CPMS.	Maintain the 30-day rolling average pressure drop and the 30-day rolling average liquid flow rate at or above the lowest one-hour average pressure drop and the lowest one-hour average liquid flow rate, respectively, measured during the performance test demonstrating compliance with the PM emission limitation according to §63.7530(b) and Table 7 to this subpart.
2. Wet acid gas (HCl) scrubber[a] control on a boiler or process heater not using a HCl CEMS.	Maintain the 30-day rolling average effluent pH at or above the lowest one-hour average pH and the 30-day rolling average liquid flow rate at or above the lowest one-hour average liquid flow rate measured during the performance test demonstrating compliance with the HCl emission limitation according to §63.7530(b) and Table 7 to this subpart.
3. Fabric filter control on a boiler or process heater not using a PM CPMS.	a. Maintain opacity to less than or equal to 10 percent opacity or the highest hourly average opacity reading measured during the performance test run demonstrating compliance with the PM (or TSM) emission limitation (daily block average); or b. Install and operate a bag leak detection system according to §63.7525 and operate the fabric filter such that the bag leak detection system alert is not activated more than 5 percent of the operating time during each 6-month period.
4. Electrostatic precipitator control on a boiler or process heater not using a PM CPMS.	a. This option is for boilers and process heaters that operate dry control systems (*i.e.*, an ESP without a wet scrubber). Existing and new boilers and process heaters must maintain opacity to less than or equal to 10 percent opacity or the highest hourly average opacity reading measured during the performance test run demonstrating compliance with the PM (or TSM) emission limitation (daily block average). b. This option is only for boilers and process heaters not subject to PM CPMS or continuous compliance with an opacity limit (*i.e.*, dry ESP). Maintain the 30-day rolling average total secondary electric power input of the electrostatic precipitator at or above the operating limits established during the performance test according to §63.7530(b) and Table 7 to this subpart.
5. Dry scrubber or carbon injection control on a boiler or process heater not using a mercury CEMS.	Maintain the minimum sorbent or carbon injection rate as defined in §63.7575 of this subpart.
6. Any other add-on air pollution control type on a boiler or process heater not using a PM CPMS.	This option is for boilers and process heaters that operate dry control systems. Existing and new boilers and process heaters must maintain opacity to less than or equal to 10 percent opacity or the highest hourly average opacity reading measured during the performance test run demonstrating compliance with the PM (or TSM) emission limitation (daily block average).
7. Performance testing	For boilers and process heaters that demonstrate compliance with a performance test, maintain the 30-day rolling average operating load of each unit such that it does not exceed 110 percent of the highest hourly average operating load recorded during the performance test.
8. Oxygen analyzer system	For boilers and process heaters subject to a CO emission limit that demonstrate compliance with an O_2 analyzer system as specified in §63.7525(a), maintain the 30-day rolling average oxygen content at or above the lowest hourly average oxygen concentration measured during the CO performance test, as specified in Table 8. This requirement does not apply to units that install an oxygen trim system since these units will set the trim system to the level specified in §63.7525(a).
9. SO_2 CEMS	For boilers or process heaters subject to an HCl emission limit that demonstrate compliance with an SO_2 CEMS, maintain the 30-day rolling average SO_2 emission rate at or below the highest hourly average SO_2 concentration measured during the HCl performance test, as specified in Table 8.

[a] A wet acid gas scrubber is a control device that removes acid gases by contacting the combustion gas with an alkaline slurry or solution. Alkaline reagents include, but not limited to, lime, limestone and sodium.

[80 FR 72874, Nov. 20, 2015, as amended at 87 FR 60853, Oct. 6, 2022]

TABLE 5 TO SUBPART DDDDD OF PART 63—PERFORMANCE TESTING REQUIREMENTS

As stated in §63.7520, you must comply with the following requirements for performance testing for existing, new or reconstructed affected sources:

To conduct a performance test for the following pollutant . . .	You must. . .	Using, as appropriate . . .
1. Filterable PM	a. Select sampling ports location and the number of traverse points.	Method 1 at 40 CFR part 60, appendix A–1 of this chapter.
	b. Determine velocity and volumetric flowrate of the stack gas.	Method 2, 2F, or 2G at 40 CFR part 60, appendix A–1 or A–2 to part 60 of this chapter.
	c. Determine oxygen or carbon dioxide concentration of the stack gas.	Method 3A or 3B at 40 CFR part 60, appendix A–2 to part 60 of this chapter, or ANSI/ASME PTC 19.10–1981.[a]
	d. Measure the moisture content of the stack gas.	Method 4 at 40 CFR part 60, appendix A–3 of this chapter.
	e. Measure the PM emission concentration	Method 5 or 17 (positive pressure fabric filters must use Method 5D) at 40 CFR part 60, appendix A–3 or A–6 of this chapter.
	f. Convert emissions concentration to lb per MMBtu emission rates.	Method 19 F-factor methodology at 40 CFR part 60, appendix A–7 of this chapter.
2. TSM	a. Select sampling ports location and the number of traverse points.	Method 1 at 40 CFR part 60, appendix A–1 of this chapter.
	b. Determine velocity and volumetric flowrate of the stack gas.	Method 2, 2F, or 2G at 40 CFR part 60, appendix A–1 or A–2 of this chapter.
	c. Determine oxygen or carbon dioxide concentration of the stack gas.	Method 3A or 3B at 40 CFR part 60, appendix A–1 of this chapter, or ANSI/ASME PTC 19.10–1981.[a]
	d. Measure the moisture content of the stack gas.	Method 4 at 40 CFR part 60, appendix A–3 of this chapter.
	e. Measure the TSM emission concentration.	Method 29 at 40 CFR part 60, appendix A–8 of this chapter
	f. Convert emissions concentration to lb per MMBtu emission rates.	Method 19 F-factor methodology at 40 CFR part 60, appendix A–7 of this chapter.
3. Hydrogen chloride	a. Select sampling ports location and the number of traverse points.	Method 1 at 40 CFR part 60, appendix A–1 of this chapter.
	b. Determine velocity and volumetric flowrate of the stack gas.	Method 2, 2F, or 2G at 40 CFR part 60, appendix A–2 of this chapter.
	c. Determine oxygen or carbon dioxide concentration of the stack gas.	Method 3A or 3B at 40 CFR part 60, appendix A–2 of this chapter, or ANSI/ASME PTC 19.10–1981.[a]
	d. Measure the moisture content of the stack gas.	Method 4 at 40 CFR part 60, appendix A–3 of this chapter.
	e. Measure the hydrogen chloride emission concentration.	Method 26 or 26A (M26 or M26A) at 40 CFR part 60, appendix A–8 of this chapter.
	f. Convert emissions concentration to lb per MMBtu emission rates.	Method 19 F-factor methodology at 40 CFR part 60, appendix A–7 of this chapter.
4. Mercury	a. Select sampling ports location and the number of traverse points.	Method 1 at 40 CFR part 60, appendix A–1 of this chapter.
	b. Determine velocity and volumetric flowrate of the stack gas.	Method 2, 2F, or 2G at 40 CFR part 60, appendix A–1 or A–2 of this chapter.
	c. Determine oxygen or carbon dioxide concentration of the stack gas.	Method 3A or 3B at 40 CFR part 60, appendix A–1 of this chapter, or ANSI/ASME PTC 19.10–1981.[a]
	d. Measure the moisture content of the stack gas.	Method 4 at 40 CFR part 60, appendix A–3 of this chapter.
	e. Measure the mercury emission concentration.	Method 29, 30A, or 30B (M29, M30A, or M30B) at 40 CFR part 60, appendix A–8 of this chapter or Method 101A at 40 CFR part 61, appendix B of this chapter, or ASTM Method D6784.[a]
	f. Convert emissions concentration to lb per MMBtu emission rates.	Method 19 F-factor methodology at 40 CFR part 60, appendix A–7 of this chapter.
5. CO	a. Select the sampling ports location and the number of traverse points.	Method 1 at 40 CFR part 60, appendix A–1 of this chapter.

To conduct a performance test for the following pollutant . . .	You must. . .	Using, as appropriate . . .
	b. Determine oxygen concentration of the stack gas.	Method 3A or 3B at 40 CFR part 60, appendix A–3 of this chapter, or ASTM D6522–00 (Reapproved 2005), or ANSI/ASME PTC 19.10–1981.[a]
	c. Measure the moisture content of the stack gas.	Method 4 at 40 CFR part 60, appendix A–3 of this chapter.
	d. Measure the CO emission concentration	Method 10 at 40 CFR part 60, appendix A–4 of this chapter. Use a measurement span value of 2 times the concentration of the applicable emission limit.

[a] Incorporated by reference, see §63.14.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7200, Jan. 31, 2013; 80 FR 72825, Nov. 20, 2015]

TABLE 6 TO SUBPART DDDDD OF PART 63—FUEL ANALYSIS REQUIREMENTS

As stated in §63.7521, you must comply with the following requirements for fuel analysis testing for existing, new or reconstructed affected sources. However, equivalent methods (as defined in §63.7575) may be used in lieu of the prescribed methods at the discretion of the source owner or operator:

To conduct a fuel analysis for the following pollutant . . .	You must . . .	Using . . .
1. Mercury	a. Collect fuel samples	Procedure in §63.7521(c) or ASTM D5192[a], or ASTM D7430[a], or ASTM D6883[a], or ASTM D2234/D2234M[a] (for coal) or EPA 1631 or EPA 1631E or ASTM D6323[a] (for solid), or EPA 821–R–01–013 (for liquid or solid), or ASTM D4177[a] (for liquid), or ASTM D4057[a] (for liquid), or equivalent.
	b. Composite fuel samples	Procedure in §63.7521(d) or equivalent.
	c. Prepare composited fuel samples.	EPA SW–846–3050B[a] (for solid samples), ASTM D2013/D2013M[a] (for coal), ASTM D5198[a] (for biomass), or EPA 3050[a] (for solid fuel), or EPA 821–R–01–013[a] (for liquid or solid), or equivalent.
	d. Determine heat content of the fuel type.	ASTM D5865[a] (for coal) or ASTM E711[a] (for biomass), or ASTM D5864[a] for liquids and other solids, or ASTM D240[a] or equivalent.
	e. Determine moisture content of the fuel type.	ASTM D3173[a], ASTM E871[a], or ASTM D5864[a], or ASTM D240[a], or ASTM D95[a] (for liquid fuels), or ASTM D4006[a] (for liquid fuels), or equivalent.
	f. Measure mercury concentration in fuel sample.	ASTM D6722[a] (for coal), EPA SW–846–7471B[a] or EPA 1631 or EPA 1631E[a] (for solid samples), or EPA SW–846–7470A[a] or EPA SW–846–7471B[a] (for liquid samples), or EPA 821–R–01–013[a] (for liquid or solid), or equivalent.
	g. Convert concentration into units of pounds of mercury per MMBtu of heat content.	For fuel mixtures use Equation 8 in §63.7530.
2. HCl	a. Collect fuel samples	Procedure in §63.7521(c) or ASTM D5192[a], or ASTM D7430[a], or ASTM D6883[a], or ASTM D2234/D2234M[a] (for coal) or ASTM D6323[a] (for coal or biomass), ASTM D4177[a] (for liquid fuels) or ASTM D4057[a] (for liquid fuels), or equivalent.
	b. Composite fuel samples	Procedure in §63.7521(d) or equivalent.
	c. Prepare composited fuel samples.	EPA SW–846–3050B[a] (for solid samples), ASTM D2013/D2013M[a] (for coal), or ASTM D5198[a] (for biomass), or EPA 3050[a] or equivalent.
	d. Determine heat content of the fuel type.	ASTM D5865[a] (for coal) or ASTM E711[a] (for biomass), ASTM D5864[a], ASTM D240[a] or equivalent.
	e. Determine moisture content of the fuel type.	ASTM D3173[a] or ASTM E871[a], or D5864[a], or ASTM D240[a], or ASTM D95[a] (for liquid fuels), or ASTM D4006[a] (for liquid fuels), or equivalent.
	f. Measure chlorine concentration in fuel sample.	EPA SW–846–9250[a], ASTM D6721[a], ASTM D4208[a] (for coal), or EPA SW–846–5050[a] or ASTM E776[a] (for solid fuel), or EPA SW–846–9056[a] or SW–846–9076[a] (for solids or liquids) or equivalent.
	g. Convert concentrations into units of pounds of HCl per MMBtu of heat content.	For fuel mixtures use Equation 7 in §63.7530 and convert from chlorine to HCl by multiplying by 1.028.

To conduct a fuel analysis for the following pollutant . . .	You must . . .	Using . . .
3. Mercury Fuel Specification for other gas 1 fuels.	a. Measure mercury concentration in the fuel sample and convert to units of micrograms per cubic meter, or.	Method 30B (M30B) at 40 CFR part 60, appendix A–8 of this chapter or ASTM D5954[a], ASTM D6350[a], ISO 6978–1:2003(E)[a], or ISO 6978–2:2003(E)[a], or EPA–1631[a] or equivalent.
	b. Measure mercury concentration in the exhaust gas when firing only the other gas 1 fuel is fired in the boiler or process heater.	Method 29, 30A, or 30B (M29, M30A, or M30B) at 40 CFR part 60, appendix A–8 of this chapter or Method 101A or Method 102 at 40 CFR part 61, appendix B of this chapter, or ASTM Method D6784[a] or equivalent.
4. TSM	a. Collect fuel samples	Procedure in §63.7521(c) or ASTM D5192[a], or ASTM D7430[a], or ASTM D6883[a], or ASTM D2234/D2234M[a] (for coal) or ASTM D6323[a] (for coal or biomass), or ASTM D4177[a], (for liquid fuels), or ASTM D4057[a] (for liquid fuels), or equivalent.
	b. Composite fuel samples	Procedure in §63.7521(d) or equivalent.
	c. Prepare composited fuel samples.	EPA SW–846–3050B[a] (for solid samples), ASTM D2013/D2013M[a] (for coal), ASTM D5198[a] or TAPPI T266[a] (for biomass), or EPA 3050[a] or equivalent.
	d. Determine heat content of the fuel type.	ASTM D5865[a] (for coal) or ASTM E711[a] (for biomass), or ASTM D5864[a] for liquids and other solids, or ASTM D240[a] or equivalent.
	e. Determine moisture content of the fuel type.	ASTM D3173[a] or ASTM E871[a], or D5864[a], or ASTM D240[a], or ASTM D95[a] (for liquid fuels), or ASTM D4006[a] (for liquid fuels), or ASTM D4177[a] (for liquid fuels) or ASTM D4057[a] (for liquid fuels), or equivalent.
	f. Measure TSM concentration in fuel sample.	ASTM D3683[a], or ASTM D4606[a], or ASTM D6357[a] or EPA 200.8[a] or EPA SW–846–6020[a], or EPA SW–846–6020A[a], or EPA SW–846–6010C[a], EPA 7060[a] or EPA 7060A[a] (for arsenic only), or EPA SW–846–7740[a] (for selenium only).
	g. Convert concentrations into units of pounds of TSM per MMBtu of heat content.	For fuel mixtures use Equation 9 in §63.7530.

[a] Incorporated by reference, see §63.14.

[83 FR 56725, Nov. 14, 2018]

TABLE 7 TO SUBPART DDDDD OF PART 63—ESTABLISHING OPERATING LIMITS [a b]

As stated in §63.7520, you must comply with the following requirements for establishing operating limits:

TABLE 7 TO SUBPART DDDDD OF PART 63—ESTABLISHING OPERATING LIMITS [a b]

If you have an applicable emission limit for . . .	And your operating limits are based on . . .	You must . . .	Using . . .	According to the following requirements
1. PM, TSM, or mercury.	a. Wet scrubber operating parameters.	i. Establish a site-specific minimum scrubber pressure drop and minimum flow rate operating limit according to §63.7530(b).	(1) Data from the scrubber pressure drop and liquid flow rate monitors and the PM, TSM, or mercury performance test.	(a) You must collect scrubber pressure drop and liquid flow rate data every 15 minutes during the entire period of the performance tests. (b) Determine the lowest hourly average scrubber pressure drop and liquid flow rate by computing the hourly averages using all of the 15-minute readings taken during each performance test.

TABLE 7 TO SUBPART DDDDD OF PART 63—ESTABLISHING OPERATING LIMITS [a] [b]—Continued

If you have an applicable emission limit for . . .	And your operating limits are based on . . .	You must . . .	Using . . .	According to the following requirements
	b. Electrostatic precipitator operating parameters (option only for units that operate wet scrubbers).	i. Establish a site-specific minimum total secondary electric power input according to §63.7530(b).	(1) Data from the voltage and secondary amperage monitors during the PM or mercury performance test.	(a) You must collect secondary voltage and secondary amperage for each ESP cell and calculate total secondary electric power input data every 15 minutes during the entire period of the performance tests. (b) Determine the average total secondary electric power input by computing the hourly averages using all of the 15-minute readings taken during each performance test.
	c. Opacity	i. Establish a site-specific maximum opacity level.	(1) Data from the opacity monitoring system during the PM performance test.	(a) You must collect opacity readings every 15 minutes during the entire period of the performance tests. (b) Determine the average hourly opacity reading by computing the hourly averages using all of the 15-minute readings taken during each performance test. (c) Determine the highest hourly average opacity reading measured during the test run demonstrating compliance with the PM (or TSM) emission limitation.
2. HCl	a. Wet scrubber operating parameters.	i. Establish site-specific minimum effluent pH and flow rate operating limits according to §63.7530(b).	(1) Data from the pH and liquid flow-rate monitors and the HCl performance test.	(a) You must collect pH and liquid flow-rate data every 15 minutes during the entire period of the performance tests. (b) Determine the hourly average pH and liquid flow rate by computing the hourly averages using all of the 15-minute readings taken during each performance test.

TABLE 7 TO SUBPART DDDDD OF PART 63—ESTABLISHING OPERATING LIMITS [a] [b]—Continued

If you have an applicable emission limit for . . .	And your operating limits are based on . . .	You must . . .	Using . . .	According to the following requirements
	b. Dry scrubber operating parameters.	i. Establish a site-specific minimum sorbent injection rate operating limit according to §63.7530(b). If different acid gas sorbents are used during the HCl performance test, the average value for each sorbent becomes the site-specific operating limit for that sorbent.	(1) Data from the sorbent injection rate monitors and HCl or mercury performance test.	(a) You must collect sorbent injection rate data every 15 minutes during the entire period of the performance tests. (b) Determine the hourly average sorbent injection rate by computing the hourly averages using all of the 15-minute readings taken during each performance test. (c) Determine the lowest hourly average of the three test run averages established during the performance test as your operating limit. When your unit operates at lower loads, multiply your sorbent injection rate by the load fraction, as defined in §63.7575, to determine the required injection rate.
	c. Alternative Maximum SO_2 emission rate.	i. Establish a site-specific maximum SO_2 emission rate operating limit according to §63.7530(b).	(1) Data from SO_2 CEMS and the HCl performance test.	(a) You must collect the SO_2 emissions data according to §63.7525(m) during the most recent HCl performance tests. (b) The maximum SO_2 emission rate is equal to the highest hourly average SO_2 emission rate measured during the most recent HCl performance tests.
3. Mercury	a. Activated carbon injection.	i. Establish a site-specific minimum activated carbon injection rate operating limit according to §63.7530(b).	(1) Data from the activated carbon rate monitors and mercury performance test.	(a) You must collect activated carbon injection rate data every 15 minutes during the entire period of the performance tests. (b) Determine the hourly average activated carbon injection rate by computing the hourly averages using all of the 15-minute readings taken during each performance test.

TABLE 7 TO SUBPART DDDDD OF PART 63—ESTABLISHING OPERATING LIMITS [a] [b]—Continued

If you have an applicable emission limit for . . .	And your operating limits are based on . . .	You must . . .	Using . . .	According to the following requirements
				(c) Determine the lowest hourly average established during the performance test as your operating limit. When your unit operates at lower loads, multiply your activated carbon injection rate by the load fraction, as defined in §63.7575, to determine the required injection rate.
4. Carbon monoxide for which compliance is demonstrated by a performance test.	a. Oxygen	i. Establish a unit-specific limit for minimum oxygen level according to §63.7530(b).	(1) Data from the oxygen analyzer system specified in §63.7525(a).	(a) You must collect oxygen data every 15 minutes during the entire period of the performance tests. (b) Determine the hourly average oxygen concentration by computing the hourly averages using all of the 15-minute readings taken during each performance test. (c) Determine the lowest hourly average established during the performance test as your minimum operating limit.
5. Any pollutant for which compliance is demonstrated by a performance test.	a. Boiler or process heater operating load.	i. Establish a unit specific limit for maximum operating load according to §63.7520(c).	(1) Data from the operating load monitors or from steam generation monitors.	(a) You must collect operating load or steam generation data every 15 minutes during the entire period of the performance test. (b) Determine the average operating load by computing the hourly averages using all of the 15-minute readings taken during each performance test. (c) Determine the highest hourly average of the three test run averages during the performance test, and multiply this by 1.1 (110 percent) as your operating limit.

[a] Operating limits must be confirmed or reestablished during performance tests.

[b] If you conduct multiple performance tests, you must set the minimum liquid flow rate and pressure drop operating limits at the higher of the minimum values established during the performance tests. For a minimum oxygen level, if you conduct multiple performance tests, you must set the minimum oxygen level at the lower of the minimum values established during the performance tests. For maximum operating load, if you conduct multiple performance tests, you must set the maximum operating load at the lower of the maximum values established during the performance tests.

[87 FR 60853, Oct. 6, 2022]

TABLE 8 TO SUBPART DDDDD OF PART 63—DEMONSTRATING CONTINUOUS COMPLIANCE

As stated in §63.7540, you must show continuous compliance with the emission limitations for each boiler or process heater according to the following:

If you must meet the following operating limits or work practice standards . . .	You must demonstrate continuous compliance by . . .
1. Opacity	a. Collecting the opacity monitoring system data according to §63.7525(c) and §63.7535; and b. Reducing the opacity monitoring data to 6-minute averages; and c. Maintaining daily block average opacity to less than or equal to 10 percent or the highest hourly average opacity reading measured during the performance test run demonstrating compliance with the PM (or TSM) emission limitation.
2. PM CPMS	a. Collecting the PM CPMS output data according to §63.7525; b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average PM CPMS output data to less than the operating limit established during the performance test according to §63.7530(b)(4).
3. Fabric Filter Bag Leak Detection Operation.	Installing and operating a bag leak detection system according to §63.7525 and operating the fabric filter such that the requirements in §63.7540(a)(7) are met.
4. Wet Scrubber Pressure Drop and Liquid Flow-rate.	a. Collecting the pressure drop and liquid flow rate monitoring system data according to §§63.7525 and 63.7535; and b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average pressure drop and liquid flow-rate at or above the operating limits established during the performance test according to §63.7530(b).
5. Wet Scrubber pH	a. Collecting the pH monitoring system data according to §§63.7525 and 63.7535; and b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average pH at or above the operating limit established during the performance test according to §63.7530(b).
6. Dry Scrubber Sorbent or Carbon Injection Rate.	a. Collecting the sorbent or carbon injection rate monitoring system data for the dry scrubber according to §§63.7525 and 63.7535; and b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average sorbent or carbon injection rate at or above the minimum sorbent or carbon injection rate as defined in §63.7575.
7. Electrostatic Precipitator Total Secondary Electric Power Input.	a. Collecting the total secondary electric power input monitoring system data for the electrostatic precipitator according to §§63.7525 and 63.7535; and b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average total secondary electric power input at or above the operating limits established during the performance test according to §63.7530(b).
8. Emission limits using fuel analysis	a. Conduct monthly fuel analysis for HCl or mercury or TSM according to Table 6 to this subpart; and b. Reduce the data to 12-month rolling averages; and c. Maintain the 12-month rolling average at or below the applicable emission limit for HCl or mercury or TSM in Tables 1 and 2 or 11 through 15 to this subpart. d. Calculate the HCl, mercury, and/or TSM emission rate from the boiler or process heater in units of lb/MMBtu using Equation 15 and Equations 16, 17, and/or 18 in §63.7530.
9. Oxygen content	a. Continuously monitor the oxygen content using an oxygen analyzer system according to §63.7525(a). This requirement does not apply to units that install an oxygen trim system since these units will set the trim system to the level specified in §63.7525(a)(7). b. Reducing the data to 30-day rolling averages; and c. Maintain the 30-day rolling average oxygen content at or above the lowest hourly average oxygen level measured during the CO performance test.
10. Boiler or process heater operating load	a. Collecting operating load data or steam generation data every 15 minutes. b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average operating load such that it does not exceed 110 percent of the highest hourly average operating load recorded during the performance test according to §63.7520(c).
11. SO_2 emissions using SO_2 CEMS	a. Collecting the SO_2 CEMS output data according to §63.7525; b. Reducing the data to 30-day rolling averages; and c. Maintaining the 30-day rolling average SO_2 CEMS emission rate to a level at or below the highest hourly SO_2 rate measured during the HCl performance test according to §63.7530.

[78 FR 7204, Jan. 31, 2013, as amended at 80 FR 72829, Nov. 20, 2015; 87 FR 60855, Oct. 6, 2022]

TABLE 9 TO SUBPART DDDDD OF PART 63—REPORTING REQUIREMENTS

As stated in §63.7550, you must comply with the following requirements for reports:

You must submit a(n)	The report must contain . . .	You must submit the report . . .
1. Compliance report	a. Information required in §63.7550(c)(1) through (5); and b. If there are no deviations from any emission limitation (emission limit and operating limit) that applies to you and there are no deviations from the requirements for work practice standards for periods of startup and shutdown in Table 3 to this subpart that apply to you, a statement that there were no deviations from the emission limitations and work practice standards during the reporting period. If there were no periods during which the CMSs, including continuous emissions monitoring system, continuous opacity monitoring system, and operating parameter monitoring systems, were out-of-control as specified in §63.8(c)(7), a statement that there were no periods during which the CMSs were out-of-control during the reporting period; and c. If you have a deviation from any emission limitation (emission limit and operating limit) where you are not using a CMS to comply with that emission limit or operating limit, or a deviation from a work practice standard for periods of startup and shutdown, during the reporting period, the report must contain the information in §63.7550(d); and d. If there were periods during which the CMSs, including continuous emissions monitoring system, continuous opacity monitoring system, and operating parameter monitoring systems, were out-of-control as specified in §63.8(c)(7), or otherwise not operating, the report must contain the information in §63.7550(e).	Semiannually, annually, biennially, or every 5 years according to the requirements in §63.7550(b).

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7205, Jan. 31, 2013; 80 FR 72830, Nov. 20, 2015]

TABLE 10 TO SUBPART DDDDD OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART DDDDD

As stated in §63.7565, you must comply with the applicable General Provisions according to the following:

Citation	Subject	Applies to subpart DDDDD
§63.1	Applicability	Yes.
§63.2	Definitions	Yes. Additional terms defined in §63.7575
§63.3	Units and Abbreviations	Yes.
§63.4	Prohibited Activities and Circumvention	Yes.
§63.5	Preconstruction Review and Notification Requirements	Yes.
§63.6(a), (b)(1)–(b)(5), (b)(7), (c).	Compliance with Standards and Maintenance Requirements	Yes.
§63.6(e)(1)(i)	General duty to minimize emissions.	No. See §63.7500(a)(3) for the general duty requirement.
§63.6(e)(1)(ii)	Requirement to correct malfunctions as soon as practicable.	No.
§63.6(e)(3)	Startup, shutdown, and malfunction plan requirements.	No.
§63.6(f)(1)	Startup, shutdown, and malfunction exemptions for compliance with non-opacity emission standards..	No.
§63.6(f)(2) and (3)	Compliance with non-opacity emission standards.	Yes.
§63.6(g)	Use of alternative standards	Yes, except §63.7555(d)(13) specifies the procedure for application and approval of an alternative timeframe with the PM controls requirement in the startup work practice (2).
§63.6(h)(1)	Startup, shutdown, and malfunction exemptions to opacity standards..	No. See §63.7500(a).
§63.6(h)(2) to (h)(9)	Determining compliance with opacity emission standards	No. Subpart DDDDD specifies opacity as an operating limit not an emission standard.

Citation	Subject	Applies to subpart DDDDD
§63.6(i)	Extension of compliance	Yes. Note: Facilities may also request extensions of compliance for the installation of combined heat and power, waste heat recovery, or gas pipeline or fuel feeding infrastructure as a means of complying with this subpart.
§63.6(j)	Presidential exemption.	Yes.
§63.7(a), (b), (c), and (d)	Performance Testing Requirements	Yes.
§63.7(e)(1)	Conditions for conducting performance tests	No. Subpart DDDDD specifies conditions for conducting performance tests at §63.7520(a) to (c).
§63.7(e)(2)–(e)(9), (f), (g), and (h).	Performance Testing Requirements	Yes.
§63.8(a) and (b)	Applicability and Conduct of Monitoring	Yes.
§63.8(c)(1)	Operation and maintenance of CMS	Yes.
§63.8(c)(1)(i)	General duty to minimize emissions and CMS operation	No. See §63.7500(a)(3).
§63.8(c)(1)(ii)	Operation and maintenance of CMS	Yes.
§63.8(c)(1)(iii)	Startup, shutdown, and malfunction plans for CMS	No.
§63.8(c)(2) to (c)(9)	Operation and maintenance of CMS	Yes.
§63.8(d)(1) and (2)	Monitoring Requirements, Quality Control Program	Yes.
§63.8(d)(3)	Written procedures for CMS	Yes, except for the last sentence, which refers to a startup, shutdown, and malfunction plan. Startup, shutdown, and malfunction plans are not required.
§63.8(e)	Performance evaluation of a CMS	Yes.
§63.8(f)	Use of an alternative monitoring method.	Yes.
§63.8(g)	Reduction of monitoring data	Yes.
§63.9	Notification Requirements	Yes.
§63.10(a), (b)(1)	Recordkeeping and Reporting Requirements	Yes.
§63.10(b)(2)(i)	Recordkeeping of occurrence and duration of startups or shutdowns.	Yes.
§63.10(b)(2)(ii)	Recordkeeping of malfunctions	No. See §63.7555(d)(7) for recordkeeping of occurrence and duration and §63.7555(d)(8) for actions taken during malfunctions.
§63.10(b)(2)(iii)	Maintenance records	Yes.
§63.10(b)(2)(iv) and (v)	Actions taken to minimize emissions during startup, shutdown, or malfunction.	No.
§63.10(b)(2)(vi)	Recordkeeping for CMS malfunctions	Yes.
§63.10(b)(2)(vii) to (xiv)	Other CMS requirements	Yes.
§63.10(b)(3)	Recordkeeping requirements for applicability determinations	No.
§63.10(c)(1) to (9)	Recordkeeping for sources with CMS	Yes.
§63.10(c)(10) and (11)	Recording nature and cause of malfunctions, and corrective actions.	No. See §63.7555(d)(7) for recordkeeping of occurrence and duration and §63.7555(d)(8) for actions taken during malfunctions.
§63.10(c)(12) and (13)	Recordkeeping for sources with CMS	Yes.
§63.10(c)(15)	Use of startup, shutdown, and malfunction plan	No.
§63.10(d)(1) and (2)	General reporting requirements	Yes.
§63.10(d)(3)	Reporting opacity or visible emission observation results	No.
§63.10(d)(4)	Progress reports under an extension of compliance	Yes.
§63.10(d)(5)	Startup, shutdown, and malfunction reports	No. See §63.7550(c)(11) for malfunction reporting requirements.
§63.10(e)	Additional reporting requirements for sources with CMS	Yes.
§63.10(f)	Waiver of recordkeeping or reporting requirements	Yes.
§63.11	Control Device Requirements	No.
§63.12	State Authority and Delegation	Yes.
§63.13–63.16	Addresses, Incorporation by Reference, Availability of Information, Performance Track Provisions.	Yes.
§63.1(a)(5),(a)(7)–(a)(9), (b)(2), (c)(3)-(4), (d), 63.6(b)(6), (c)(3), (c)(4), (d), (e)(2), (e)(3)(ii), (h)(3), (h)(5)(iv), 63.8(a)(3), 63.9(b)(3), (h)(4), 63.10(c)(2)–(4), (c)(9)..	Reserved	No.

[76 FR 15664, Mar. 21, 2011, as amended at 78 FR 7205, Jan. 31, 2013; 80 FR 72830, Nov. 20, 2015]

TABLE 11 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS THAT COMMENCED CONSTRUCTION OR RECONSTRUCTION AFTER JUNE 4, 2010, AND BEFORE MAY 20, 2011

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
1. Units in all subcategories designed to burn solid fuel.	a. HCl	0.022 lb per MMBtu of heat input.	For M26A, collect a minimum of 1 dscm per run; for M26 collect a minimum of 120 liters per run.
2. Units in all subcategories designed to burn solid fuel that combust at least 10 percent biomass/bio-based solids on an annual heat input basis and less than 10 percent coal/solid fossil fuels on an annual heat input basis.	a. Mercury	8.0E–07 [a] lb per MMBtu of heat input.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 4 dscm.
3. Units in all subcategories designed to burn solid fuel that combust at least 10 percent coal/solid fossil fuels on an annual heat input basis and less than 10 percent biomass/bio-based solids on an annual heat input basis.	a. Mercury	2.0E–06 lb per MMBtu of heat input.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 4 dscm.
4. Units design to burn coal/solid fossil fuel.	a. Filterable PM (or TSM).	1.1E–03 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
5. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. Carbon monoxide (CO) (or CEMS).	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
6. Stokers designed to burn coal/solid fossil fuel.	a. CO (or CEMS).	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3 percent oxygen ,[c] 10-day rolling average).	1 hr minimum sampling time.
7. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
8. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	140 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
9. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS)	620 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (390 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (2.6E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
10. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	560 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (4.0E–03 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run
11. Fluidized bed units designed to burn biomass/bio-based solids.	a. CO (or CEMS)	230 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	9.8E–03 lb per MMBtu of heat input; or (8.3E–05 [a] lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run
12. Suspension burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	2,400 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3 percent oxygen [c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (6.5E–03 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
13. Dutch Ovens/Pile burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	1,010 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3 percent oxygen [c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	8.0E–03 lb per MMBtu of heat input; or (3.9E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
14. Fuel cell units designed to burn biomass/bio-based solids.	a. CO	910 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.0E–02 lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
15. Hybrid suspension grate boiler designed to burn biomass/bio-based solids.	a. CO (or CEMS)	1,100 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.6E–02 lb per MMBtu of heat input; or (4.4E–04 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run
16. Units designed to burn liquid fuel.	a. HCl	4.4E–04 lb per MMBtu of heat input.	For M26A: Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run
	b. Mercury.	4.8E–07[a] lb per MMBtu of heat input.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784[b] collect a minimum of 4 dscm.
17. Units designed to burn heavy liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.3E–02 lb per MMBtu of heat input; or (7.5E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
18. Units designed to burn light liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.0E–03[a] lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run
19. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average based on stack test.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.3E–02 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	Collect a minimum of 4 dscm per run
20. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. HCl	1.7E–03 lb per MMBtu of heat input.	For M26A, Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784[b] collect a minimum of 3 dscm.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	d. Filterable PM (or TSM).	6.7E–03 lb per MMBtu of heat input; or (2.1E–04 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit, you can skip testing according to §63.7515 if all of the other provision of §63.7515 are met. For all other pollutants that do not contain a footnote "a", your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see §63.14.

[c] An owner or operator may determine compliance with the carbon monoxide emissions limit using carbon dioxide as a diluent correction in place of oxygen as described in §63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit, and must also take into account that the 3% oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to §63.7505(d).

[87 FR 60855, Oct. 6, 2022]

Table 12 to Subpart DDDDD of Part 63—Alternative Emission Limits for New or Reconstructed Boilers and Process Heaters That Commenced Construction or Reconstruction After May 20, 2011, and Before December 23, 2011

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
1. Units in all subcategories designed to burn solid fuel.	a. HCl	0.022 lb per MMBtu of heat input	For M26A, collect a minimum of 1 dscm per run; for M26 collect a minimum of 120 liters per run.
	b. Mercury	3.5E–06 [a] lb per MMBtu of heat input ...	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 3 dscm.
2. Units design to burn coal/solid fossil fuel.	a. Filterable PM (or TSM).	1.1E–03 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
3. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. Carbon monoxide (CO) (or CEMS).	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
4. Stokers designed to burn coal/solid fossil fuel.	a. CO (or CEMS) ...	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
5. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS) ...	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
6. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS) ...	140 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
7. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS) ...	620 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (390 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (2.6E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
8. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	460 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (4.0E–03 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
9. Fluidized bed units designed to burn biomass/bio-based solids.	a. CO (or CEMS)	260 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	9.8E–03 lb per MMBtu of heat input; or (8.3E–05[a] lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
10. Suspension burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	2,400 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (6.5E–03 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
11. Dutch Ovens/Pile burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	470 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.2E–03 lb per MMBtu of heat input; or (3.9E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
12. Fuel cell units designed to burn biomass/bio-based solids.	a. CO	910 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.0E–02 lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
13. Hybrid suspension grate boiler designed to burn biomass/bio-based solids.	a. CO (or CEMS)	1,500 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.6E–02 lb per MMBtu of heat input; or (4.4E–04 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
14. Units designed to burn liquid fuel.	a. HCl	4.4E–04 lb per MMBtu of heat input	For M26A: Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	b. Mercury	4.8E–07[a] lb per MMBtu of heat input	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784[b] collect a minimum of 4 dscm.
15. Units designed to burn heavy liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.3E–02 lb per MMBtu of heat input; or (7.5E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
16. Units designed to burn light liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.3E–03[a] lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
17. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average based on stack test.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.3E–02 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	Collect a minimum of 4 dscm per run.
18. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	b. HCl	1.7E–03 lb per MMBtu of heat input	For M26A, Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 3 dscm.
	d. Filterable PM (or TSM).	6.7E–03 lb per MMBtu of heat input; or (2.1E–04 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit, you can skip testing according to §63.7515 if all of the other provision of §63.7515 are met. For all other pollutants that do not contain a footnote "a", your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see §63.14.

[c] An owner or operator may determine compliance with the carbon monoxide emissions limit using carbon dioxide as a diluent correction in place of oxygen as described in §63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit, and must also take into account that the 3% oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to §63.7505(d).

[87 FR 60857, Oct. 6, 2022]

Table 13 to Subpart DDDDD of Part 63—Alternative Emission Limits for New or Reconstructed Boilers and Process Heaters That Commenced Construction or Reconstruction After December 23, 2011, and Before April 1, 2013

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
1. Units in all subcategories designed to burn solid fuel.	a. HCl	0.022 lb per MMBtu of heat input.	For M26A, collect a minimum of 1 dscm per run; for M26 collect a minimum of 120 liters per run.
	b. Mercury	8.6E–07 [a] lb per MMBtu of heat input.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 4 dscm.
2. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. Carbon monoxide (CO) (or CEMS).	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	1.1E–03 lb per MMBtu of heat input; or (2.8E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
3. Stokers designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	2.8E–02 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
4. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	1.1E–03 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
5. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	140 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	1.1E–03 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
6. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS)	620 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (410 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	3.0E–02 lb per MMBtu of heat input; or (2.6E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
7. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	460 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	3.2E–01 lb per MMBtu of heat input; or (4.0E–03 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
8. Fluidized bed units designed to burn biomass/bio-based solids.	a. CO (or CEMS)	230 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	9.8E–03 lb per MMBtu of heat input; or (8.3E–05[a] lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
9. Suspension burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	2,400 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	5.1E–02 lb per MMBtu of heat input; or (6.5E–03 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
10. Dutch Ovens/Pile burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	810 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	3.6E–02 lb per MMBtu of heat input; or (3.9E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
11. Fuel cell units designed to burn biomass/bio-based solids.	a. CO	910 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	b. Filterable PM (or TSM)	2.0E–02 lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
12. Hybrid suspension grate boiler designed to burn biomass/bio-based solids.	a. CO (or CEMS)	1,500 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 30-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	2.6E–02 lb per MMBtu of heat input; or (4.4E–04 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
13. Units designed to burn liquid fuel.	a. HCl	1.2E–03 lb per MMBtu of heat input.	For M26A: Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	b. Mercury	4.9E–07 [a] lb per MMBtu of heat input.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b]collect a minimum of 4 dscm.
14. Units designed to burn heavy liquid fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average; or (18 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 10-day rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	1.3E–03 lb per MMBtu of heat input; or (7.5E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
15. Units designed to burn light liquid fuel.	a. CO (or CEMS)	130 [a] ppm by volume on a dry basis corrected to 3 percent oxygen; or (60 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 1-day block average)..	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	1.1E–03 [a] lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.
16. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen, 3-run average based on stack test; or (91 ppm by volume on a dry basis corrected to 3 percent oxygen,[c] 3-hour rolling average).	1 hr minimum sampling time.
	b. Filterable PM (or TSM)	2.3E–02 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	Collect a minimum of 2 dscm per run.
17. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3 percent oxygen.	1 hr minimum sampling time.
	b. HCl	1.7E–03 lb per MMBtu of heat input.	For M26A, Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b]collect a minimum of 3 dscm.

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during periods of startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	d. Filterable PM (or TSM)	6.7E–03 lb per MMBtu of heat input; or (2.1E–04 lb per MMBtu of heat input).	Collect a minimum of 3 dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit and you are not required to conduct testing for CEMS or CPMS monitor certification, you can skip testing according to §63.7515 if all of the other provision of §63.7515 are met. For all other pollutants that do not contain a footnote ''a'', your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see §63.14.

[c] An owner or operator may determine compliance with the carbon monoxide emissions limit using carbon dioxide as a diluent correction in place of oxygen as described in §63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit, and must also take into account that the 3% oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to §63.7505(d).

[87 FR 60859, Oct. 6, 2022]

TABLE 14 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR NEW OR RECONSTRUCTED BOILERS AND PROCESS HEATERS [c]

As stated in §63.7500, you may continue to comply with the following applicable emission limits until October 6, 2025:

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
1. Units in all subcategories designed to burn solid fuel..	a. HCl	2.2E–02 lb per MMBtu of heat input.	2.5E–02 lb per MMBtu of steam output or 0.28 lb per MWh.	For M26A, collect a minimum of 1 dscm per run; for M26 collect a minimum of 120 liters per run.
	b. Mercury	8.0E–07 [a] lb per MMBtu of heat input.	8.7E–07 [a] lb per MMBtu of steam output or 1.1E–05 [a] lb per MWh.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 4 dscm.
2. Units designed to burn coal/solid fossil fuel.	a. Filterable PM (or TSM).	1.1E–03 lb per MMBtu of heat input; or (2.3E–05 lb per MMBtu of heat input).	1.1E–03 lb per MMBtu of steam output or 1.4E–02 lb per MWh; or (2.7E–05 lb per MMBtu of steam output or 2.9E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
3. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. Carbon monoxide (CO) (or CEMS).	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3-percent oxygen, [d] 30-day rolling average).	0.11 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
4. Stokers/others designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	0.12 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
5. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	0.11 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
6. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	140 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3- percent oxygen,[d] 30-day rolling average).	1.2E–01 lb per MMBtu of steam output or 1.5 lb per MWh; 3-run average.	1 hr minimum sampling time.
7. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS)	620 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (390 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	5.8E–01 lb per MMBtu of steam output or 6.8 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (2.6E–05 lb per MMBtu of heat input).	3.5E–02 lb per MMBtu of steam output or 4.2E–01 lb per MWh; or (2.7E–05 lb per MMBtu of steam output or 3.7E–04 lb per MWh).	Collect a minimum of 2 dscm per run.
8. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	460 ppm by volume on a dry basis corrected to 3-percent oxygen.	4.2E–01 lb per MMBtu of steam output or 5.1 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (4.0E–03 lb per MMBtu of heat input).	3.5E–02 lb per MMBtu of steam output or 4.2E–01 lb per MWh; or (4.2E–03 lb per MMBtu of steam output or 5.6E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
9. Fluidized bed units designed to burn biomass/bio-based solids.	a. CO (or CEMS)	230 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	2.2E–01 lb per MMBtu of steam output or 2.6 lb per MWh; 3-run average.	1 hr minimum sampling time.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	b. Filterable PM (or TSM).	9.8E–03 lb per MMBtu of heat input; or (8.3E–05 [a] lb per MMBtu of heat input).	1.2E–02 lb per MMBtu of steam output or 0.14 lb per MWh; or (1.1E–04 [a] lb per MMBtu of steam output or 1.2E–03 [a] lb per MWh).	Collect a minimum of 3 dscm per run.
10. Suspension burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	2,400 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 10-day rolling average).	1.9 lb per MMBtu of steam output or 27 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.0E–02 lb per MMBtu of heat input; or (6.5E–03 lb per MMBtu of heat input).	3.1E–02 lb per MMBtu of steam output or 4.2E–01 lb per MWh; or (6.6E–03 lb per MMBtu of steam output or 9.1E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
11. Dutch Ovens/Pile burners designed to burn biomass/bio-based solids.	a. CO (or CEMS)	330 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 10-day rolling average).	3.5E–01 lb per MMBtu of steam output or 3.6 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.2E–03 lb per MMBtu of heat input; or (3.9E–05 lb per MMBtu of heat input).	4.3E–03 lb per MMBtu of steam output or 4.5E–02 lb per MWh; or (5.2E–05 lb per MMBtu of steam output or 5.5E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
12. Fuel cell units designed to burn biomass/bio-based solids.	a. CO	910 ppm by volume on a dry basis corrected to 3-percent oxygen.	1.1 lb per MMBtu of steam output or 1.0E+01 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.0E–02 lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	3.0E–02 lb per MMBtu of steam output or 2.8E–01 lb per MWh; or (5.1E–05 lb per MMBtu of steam output or 4.1E–04 lb per MWh).	Collect a minimum of 2 dscm per run.
13. Hybrid suspension grate boiler designed to burn biomass/bio-based solids.	a. CO (or CEMS)	1,100 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3-percent oxygen,[d] 30-day rolling average).	1.4 lb per MMBtu of steam output or 12 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.6E–02 lb per MMBtu of heat input; or (4.4E–04 lb per MMBtu of heat input).	3.3E–02 lb per MMBtu of steam output or 3.7E–01 lb per MWh; or (5.5E–04 lb per MMBtu of steam output or 6.2E–03 lb per MWh).	Collect a minimum of 3 dscm per run.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
14. Units designed to burn liquid fuel.	a. HCl	4.4E–04 lb per MMBtu of heat input.	4.8E–04 lb per MMBtu of steam output or 6.1E–03 lb per MWh.	For M26A: Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	b. Mercury	4.8E–07 [a] lb per MMBtu of heat input.	5.3E–07 [a] lb per MMBtu of steam output or 6.7E–06 [a] lb per MWh.	For M29, collect a minimum of 4 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 4 dscm.
15. Units designed to burn heavy liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.3E–02 lb per MMBtu of heat input; or (7.5E–05 [a] lb per MMBtu of heat input).	1.5E–02 lb per MMBtu of steam output or 1.8E–01 lb per MWh; or (8.2E–05 [a] lb per MMBtu of steam output or 1.1E–03 [a] lb per MWh).	Collect a minimum of 3 dscm per run.
16. Units designed to burn light liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.1E–03 [a] lb per MMBtu of heat input; or (2.9E–05 lb per MMBtu of heat input).	1.2E–03 [a] lb per MMBtu of steam output or 1.6E–02 [a] lb per MWh; or (3.2E–05 lb per MMBtu of steam output or 4.0E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
17. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average based on stack test.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.3E–02 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	2.5E–02 lb per MMBtu of steam output or 3.2E–01 lb per MWh; or (9.4E–04 lb per MMBtu of steam output or 1.2E–02 lb per MWh).	Collect a minimum of 4 dscm per run.
18. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.16 lb per MMBtu of steam output or 1.0 lb per MWh.	1 hr minimum sampling time.
	b. HCl	1.7E–03 lb per MMBtu of heat input.	2.9E–03 lb per MMBtu of steam output or 1.8E–02 lb per MWh.	For M26A, Collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input.	1.4E–05 lb per MMBtu of steam output or 8.3E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 3 dscm.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	Or the emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	d. Filterable PM (or TSM).	6.7E–03 lb per MMBtu of heat input; or (2.1E–04 lb per MMBtu of heat input).	1.2E–02 lb per MMBtu of steam output or 7.0E–02 lb per MWh; or (3.5E–04 lb per MMBtu of steam output or 2.2E–03 lb per MWh).	Collect a minimum of 3 dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit, you can skip testing according to §63.7515 if all of the other provisions of §63.7515 are met. For all other pollutants that do not contain a footnote "a", your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see §63.14.

[c] If your affected source is a new or reconstructed affected source that commenced construction or reconstruction after June 4, 2010, and before April 1, 2013, you may comply with the emission limits in Table 11, 12, or 13 to this subpart until January 31, 2016. On and after January 31, 2016, but before October 6, 2025 you may comply with the emission limits in this Table 14. On and after October 6, 2025, you must comply with the emission limits in Table 1 to this subpart.

[d] An owner or operator may determine compliance with the carbon monoxide emissions limit using carbon dioxide as a diluent correction in place of oxygen as described in §63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit, and must also take into account that the 3% oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to §63.7505(d).

[87 FR 60860, Oct. 6, 2022]

TABLE 15 TO SUBPART DDDDD OF PART 63—ALTERNATIVE EMISSION LIMITS FOR EXISTING BOILERS AND PROCESS HEATERS [D]

As stated in §63.7500, you may continue to comply with following emission limits until October 6, 2025:

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
1. Units in all subcategories designed to burn solid fuel.	a. HCl	2.2E–02 lb per MMBtu of heat input.	2.5E–02 lb per MMBtu of steam output or 0.27 lb per MWh.	For M26A, Collect a minimum of 1 dscm per run; for M26, collect a minimum of 120 liters per run.
	b. Mercury	5.7E–06 lb per MMBtu of heat input.	6.4E–06 lb per MMBtu of steam output or 7.3E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 3 dscm.
2. Units design to burn coal/solid fossil fuel.	a. Filterable PM (or TSM).	4.0E–02 lb per MMBtu of heat input; or (5.3E–05 lb per MMBtu of heat input).	4.2E–02 lb per MMBtu of steam output or 4.9E–01 lb per MWh; or (5.6E–05 lb per MMBtu of steam output or 6.5E–04 lb per MWh).	Collect a minimum of 2 dscm per run.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
3. Pulverized coal boilers designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (320 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	0.11 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
4. Stokers/others designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	160 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (340 ppm by volume on a dry basis corrected to 3- percent oxygen,[c] 30-day rolling average).	0.14 lb per MMBtu of steam output or 1.7 lb per MWh; 3-run average.	1 hr minimum sampling time.
5. Fluidized bed units designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (230 ppm by volume on a dry basis corrected to 3- percent oxygen,[c] 30-day rolling average).	0.12 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
6. Fluidized bed units with an integrated heat exchanger designed to burn coal/solid fossil fuel.	a. CO (or CEMS)	140 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (150 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	1.3E–01 lb per MMBtu of steam output or 1.5 lb per MWh; 3-run average.	1 hr minimum sampling time.
7. Stokers/sloped grate/others designed to burn wet biomass fuel.	a. CO (or CEMS)	1,500 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (720 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	1.4 lb per MMBtu of steam output or 17 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.7E–02 lb per MMBtu of heat input; or (2.4E–04 lb per MMBtu of heat input).	4.3E–02 lb per MMBtu of steam output or 5.2E–01 lb per MWh; or (2.8E–04 lb per MMBtu of steam output or 3.4E–04 lb per MWh).	Collect a minimum of 2 dscm per run.
8. Stokers/sloped grate/others designed to burn kiln-dried biomass fuel.	a. CO	460 ppm by volume on a dry basis corrected to 3-percent oxygen.	4.2E–01 lb per MMBtu of steam output or 5.1 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	3.2E–01 lb per MMBtu of heat input; or (4.0E–03 lb per MMBtu of heat input).	3.7E–01 lb per MMBtu of steam output or 4.5 lb per MWh; or (4.6E–03 lb per MMBtu of steam output or 5.6E–02 lb per MWh).	Collect a minimum of 1 dscm per run.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
9. Fluidized bed units designed to burn biomass/bio-based solid.	a. CO (or CEMS)	470 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (310 ppm by volume on a dry basis corrected to 3- percent oxygen,[c] 30-day rolling average).	4.6E–01 lb per MMBtu of steam output or 5.2 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	1.1E–01 lb per MMBtu of heat input; or (1.2E–03 lb per MMBtu of heat input).	1.4E–01 lb per MMBtu of steam output or 1.6 lb per MWh; or (1.5E–03 lb per MMBtu of steam output or 1.7E–02 lb per MWh).	Collect a minimum of 1 dscm per run.
10. Suspension burners designed to burn biomass/bio-based solid.	a. CO (or CEMS)	2,400 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (2,000 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 10-day rolling average).	1.9 lb per MMBtu of steam output or 27 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	5.1E–02 lb per MMBtu of heat input; or (6.5E–03 lb per MMBtu of heat input).	5.2E–02 lb per MMBtu of steam output or 7.1E–01 lb per MWh; or (6.6E–03 lb per MMBtu of steam output or 9.1E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
11. Dutch Ovens/Pile burners designed to burn biomass/bio-based solid.	a. CO (or CEMS)	770 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (520 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 10-day rolling average).	8.4E–01 lb per MMBtu of steam output or 8.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.8E–01 lb per MMBtu of heat input; or (2.0E–03 lb per MMBtu of heat input).	3.9E–01 lb per MMBtu of steam output or 3.9 lb per MWh; or (2.8E–03 lb per MMBtu of steam output or 2.8E–02 lb per MWh).	Collect a minimum of 1 dscm per run.
12. Fuel cell units designed to burn biomass/bio-based solid.	a. CO	1,100 ppm by volume on a dry basis corrected to 3-percent oxygen.	2.4 lb per MMBtu of steam output or 12 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.0E–02 lb per MMBtu of heat input; or (5.8E–03 lb per MMBtu of heat input).	5.5E–02 lb per MMBtu of steam output or 2.8E–01 lb per MWh; or (1.6E–02 lb per MMBtu of steam output or 8.1E–02 lb per MWh).	Collect a minimum of 2 dscm per run.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
13. Hybrid suspension grate units designed to burn biomass/bio-based solid.	a. CO (or CEMS)	3,500 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average; or (900 ppm by volume on a dry basis corrected to 3-percent oxygen,[c] 30-day rolling average).	3.5 lb per MMBtu of steam output or 39 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	4.4E–01 lb per MMBtu of heat input; or (4.5E–04 lb per MMBtu of heat input).	5.5E–01 lb per MMBtu of steam output or 6.2 lb per MWh; or (5.7E–04 lb per MMBtu of steam output or 6.3E–03 lb per MWh).	Collect a minimum of 1 dscm per run.
14. Units designed to burn liquid fuel.	a. HCl	1.1E–03 lb per MMBtu of heat input.	1.4E–03 lb per MMBtu of steam output or 1.6E–02 lb per MWh.	For M26A, collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	b. Mercury	2.0E–06 lb per MMBtu of heat input.	2.5E–06 lb per MMBtu of steam output or 2.8E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B collect a minimum sample as specified in the method, for ASTM D6784 [b] collect a minimum of 2 dscm.
15. Units designed to burn heavy liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	6.2E–02 lb per MMBtu of heat input; or (2.0E–04 lb per MMBtu of heat input).	7.5E–02 lb per MMBtu of steam output or 8.6E–01 lb per MWh; or (2.5E–04 lb per MMBtu of steam output or 2.8E–03 lb per MWh).	Collect a minimum of 1 dscm per run.
16. Units designed to burn light liquid fuel.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	7.9E–03 lb per MMBtu of heat input; or (6.2E–05 lb per MMBtu of heat input).	9.6E–03 lb per MMBtu of steam output or 1.1E–01 lb per MWh; or (7.5E–05 lb per MMBtu of steam output or 8.6E–04 lb per MWh).	Collect a minimum of 3 dscm per run.
17. Units designed to burn liquid fuel that are non-continental units.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen, 3-run average based on stack test.	0.13 lb per MMBtu of steam output or 1.4 lb per MWh; 3-run average.	1 hr minimum sampling time.
	b. Filterable PM (or TSM).	2.7E–01 lb per MMBtu of heat input; or (8.6E–04 lb per MMBtu of heat input).	3.3E–01 lb per MMBtu of steam output or 3.8 lb per MWh; or (1.1E–03 lb per MMBtu of steam output or 1.2E–02 lb per MWh).	Collect a minimum of 2 dscm per run.
18. Units designed to burn gas 2 (other) gases.	a. CO	130 ppm by volume on a dry basis corrected to 3-percent oxygen.	0.16 lb per MMBtu of steam output or 1.0 lb per MWh.	1 hr minimum sampling time.

[Units with heat input capacity of 10 million Btu per hour or greater]

If your boiler or process heater is in this subcategory . . .	For the following pollutants . . .	The emissions must not exceed the following emission limits, except during startup and shutdown . . .	The emissions must not exceed the following alternative output-based limits, except during startup and shutdown . . .	Using this specified sampling volume or test run duration . . .
	b. HCl	1.7E–03 lb per MMBtu of heat input.	2.9E–03 lb per MMBtu of steam output or 1.8E–02 lb per MWh.	For M26A, collect a minimum of 2 dscm per run; for M26, collect a minimum of 240 liters per run.
	c. Mercury	7.9E–06 lb per MMBtu of heat input.	1.4E–05 lb per MMBtu of steam output or 8.3E–05 lb per MWh.	For M29, collect a minimum of 3 dscm per run; for M30A or M30B, collect a minimum sample as specified in the method; for ASTM D6784 [b] collect a minimum of 2 dscm.
	d. Filterable PM (or TSM).	6.7E–03 lb per MMBtu of heat input or (2.1E–04 lb per MMBtu of heat input).	1.2E–02 lb per MMBtu of steam output or 7.0E–02 lb per MWh; or (3.5E–04 lb per MMBtu of steam output or 2.2E–03 lb per MWh).	Collect a minimum of three dscm per run.

[a] If you are conducting stack tests to demonstrate compliance and your performance tests for this pollutant for at least 2 consecutive years show that your emissions are at or below this limit, you can skip testing according to § 63.7515 if all of the other provisions of § 63.7515 are met. For all other pollutants that do not contain a footnote a, your performance tests for this pollutant for at least 2 consecutive years must show that your emissions are at or below 75 percent of this limit in order to qualify for skip testing.

[b] Incorporated by reference, see § 63.14.

[c] An owner or operator may determine compliance with the carbon monoxide emissions limit using carbon dioxide as a diluent correction in place of oxygen as described in § 63.7525(a)(1). EPA Method 19 F-factors in 40 CFR part 60, appendix A–7, and EPA Method 19 equations in 40 CFR part 60, appendix A–7, must be used to generate the appropriate CO_2 correction percentage for the fuel type burned in the unit, and must also take into account that the 3% oxygen correction is to be done on a dry basis. The methodology must account for any CO_2 being added to, or removed from, the emissions gas stream as a result of limestone injection, scrubber media, etc. This methodology must be detailed in the site-specific monitoring plan developed according to § 63.7505(d).

[d] Before October 6, 2025 you may comply with the emission limits in this Table 15. On and after October 6, 2025, you must comply with the emission limits in Table 2 to this subpart.

[87 FR 60863, Oct. 6, 2022]

Subpart EEEEE—National Emission Standards for Hazardous Air Pollutants for Iron and Steel Foundries

SOURCE: 69 FR 21923, Apr. 22, 2004, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7680 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for iron and steel foundries. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emissions limitations, work practice standards, and operation and maintenance requirements in this subpart.

§ 63.7681 Am I subject to this subpart?

You are subject to this subpart if you own or operate an iron and steel foundry that is (or is part of) a major source of hazardous air pollutant (HAP) emissions. Your iron and steel foundry is a major source of HAP for purposes of this subpart if it emits or has the potential to emit any single HAP at a rate of 10 tons or more per year or any combination of HAP at a rate of 25 tons or more per year or if it is located at a facility that emits or has the potential to emit any single HAP at a rate of 10 tons or more per year or any combination of HAP at a rate of 25 tons or more per year as defined in § 63.2.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7218, Feb. 7, 2008]

§ 63.7682 What parts of my foundry does this subpart cover?

(a) The affected source is each new or existing iron and steel foundry.

(b) This subpart covers emissions from metal melting furnaces, scrap preheaters, pouring areas, pouring stations, automated conveyor and pallet cooling lines, automated shakeout lines, and mold and core making lines. This subpart also covers fugitive emissions from foundry operations.

(c) An affected source is existing if you commenced construction or reconstruction of the affected source before December 23, 2002.

(d) An affected source is new if you commenced construction or reconstruction of the affected source on or after December 23, 2002. An affected source is reconstructed if it meets the definition of ''reconstruction'' in § 63.2.

§ 63.7683 When do I have to comply with this subpart?

(a) Except as specified in paragraph (b) of this section, if you have an existing affected source, you must comply with each emissions limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you no later than April 23, 2007. Major source status for existing affected sources must be determined no later than April 23, 2007.

(b) If you have an existing affected source, you must comply with the work practice standards in § 63.7700(b) or (c), as applicable, no later than April 22, 2005.

(c) If you have a new affected source for which the initial startup date is on or before April 22, 2004, you must comply with each emissions limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you by April 22, 2004.

(d) If you have a new affected source for which the initial startup date is after April 22, 2004, you must comply with each emissions limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you upon initial startup.

(e) If your iron and steel foundry is an area source that becomes a major source of HAP, you must meet the requirements of § 63.6(c)(5).

(f) You must meet the notification and schedule requirements in § 63.7750. Note that several of these notifications must be submitted before the compliance date for your affected source.

EMISSIONS LIMITATIONS

§ 63.7690 What emissions limitations must I meet?

(a) You must meet the emissions limits or standards in paragraphs (a)(1) through (11) of this section that apply to you. When alternative emissions limitations are provided for a given emissions source, you are not restricted in the selection of which applicable alternative emissions limitation is used to demonstrate compliance.

(1) For each electric arc metal melting furnace, electric induction metal melting furnace, or scrap preheater at an existing iron and steel foundry, you must not discharge emissions through a conveyance to the atmosphere that exceed either the limit for particulate matter (PM) in paragraph (a)(1)(i) of this section or, alternatively the limit for total metal HAP in paragraph (a)(1)(ii) of this section:

(i) 0.005 grains of PM per dry standard cubic foot (gr/dscf), or

(ii) 0.0004 gr/dscf of total metal HAP.

(2) For each cupola metal melting furnace at an existing iron and steel foundry, you must not discharge emissions through a conveyance to the atmosphere that exceed either the limit for PM in paragraph (a)(2)(i) or (ii) of this section or, alternatively the limit for total metal HAP in paragraph (a)(2)(iii) or (iv) of this section:

(i) 0.006 gr/dscf of PM; or

(ii) 0.10 pound of PM per ton (lb/ton) of metal charged, or

(iii) 0.0005 gr/dscf of total metal HAP; or

(iv) 0.008 pound of total metal HAP per ton (lb/ton) of metal charged.

(3) For each cupola metal melting furnace or electric arc metal melting furnace at a new iron and steel foundry, you must not discharge emissions through a conveyance to the atmosphere that exceed either the limit for PM in paragraph (a)(3)(i) of this section or, alternatively the limit for total

metal HAP in paragraph (a)(3)(ii) of this section:

(i) 0.002 gr/dscf of PM, or

(ii) 0.0002 gr/dscf of total metal HAP.

(4) For each electric induction metal melting furnace or scrap preheater at a new iron and steel foundry, you must not discharge emissions through a conveyance to the atmosphere that exceed either the limit for PM in paragraph (a)(4)(i) of this section or, alternatively the limit for total metal HAP in paragraph (a)(4)(ii) of this section:

(i) 0.001 gr/dscf of PM, or

(ii) 0.00008 gr/dscf of total metal HAP.

(5) For each pouring station at an existing iron and steel foundry, you must not discharge emissions through a conveyance to the atmosphere that exceed either the limit for PM in paragraph (a)(5)(i) of this section or, alternatively the limit for total metal HAP in paragraph (a)(5)(ii) of this section:

(i) 0.010 gr/dscf of PM, or

(ii) 0.0008 gr/dscf of total metal HAP.

(6) For each pouring area or pouring station at a new iron and steel foundry, you must not discharge emissions through a conveyance to the atmosphere that exceed either the limit for PM in paragraph (a)(6)(i) of this section or, alternatively the limit for total metal HAP in paragraph (a)(6)(ii) of this section:

(i) 0.002 gr/dscf of PM, or

(ii) 0.0002 gr/dscf of total metal HAP.

(7) For each building or structure housing any iron and steel foundry emissions source at the iron and steel foundry, you must not discharge any fugitive emissions to the atmosphere from foundry operations that exhibit opacity greater than 20 percent (6-minute average), except for one 6-minute average per hour that does not exceed 27 percent opacity.

(8) For each cupola metal melting furnace at a new or existing iron and steel foundry, you must not discharge emissions of volatile organic hazardous air pollutants (VOHAP) through a conveyance to the atmosphere that exceed 20 parts per million by volume (ppmv) corrected to 10-percent oxygen while on blast.

(9) As an alternative to the work practice standard in §63.7700(e) for a scrap preheater at an existing iron and steel foundry or in §63.7700(f) for a scrap preheater at a new iron and steel foundry, you must not discharge emissions of VOHAP through a conveyance to the atmosphere that exceed 20 ppmv.

(10) For one or more automated conveyor and pallet cooling lines that use a sand mold system or automated shakeout lines that use a sand mold system at a new iron and steel foundry, you must not discharge emissions of VOHAP through a conveyance to the atmosphere that exceed a flow-weighted average of 20 ppmv.

(11) For each triethylamine (TEA) cold box mold or core making line at a new or existing iron and steel foundry, you must meet either the emissions limit in paragraph (a)(11)(i) of this section or, alternatively the emissions standard in paragraph (a)(11)(ii) of this section:

(i) You must not discharge emissions of TEA through a conveyance to the atmosphere that exceed 1 ppmv, as determined according to the performance test procedures in §63.7732(g); or

(ii) You must reduce emissions of TEA from each TEA cold box mold or core making line by at least 99 percent, as determined according to the performance test procedures in §63.7732(g).

(b) You must meet each operating limit in paragraphs (b)(1) through (5) of this section that applies to you.

(1) You must install, operate, and maintain a capture and collection system for all emissions sources subject to an emissions limit for VOHAP or TEA in paragraphs (a)(8) through (11) of this section.

(i) Each capture and collection system must meet accepted engineering standards, such as those published by the American Conference of Governmental Industrial Hygienists.

(ii) You must operate each capture system at or above the lowest value or settings established as operating limits in your operation and maintenance plan.

(2) You must operate each wet scrubber applied to emissions from a metal melting furnace, scrap preheater, pouring area, or pouring station subject to an emissions limit for PM or total metal HAP in paragraphs (a)(1) through (6) of this section such that the 3-hour average pressure drop and scrubber water flow rate does not fall

below the minimum levels established during the initial or subsequent performance test.

(3) You must operate each combustion device applied to emissions from a cupola metal melting furnace subject to the emissions limit for VOHAP in paragraph (a)(8) of this section, such that the 15-minute average combustion zone temperature does not fall below 1,300 degrees Fahrenheit (°F). Periods when the cupola is off blast and for 15 minutes after going on blast from an off blast condition are not included in the 15-minute average.

(4) You must operate each combustion device applied to emissions from a scrap preheater subject to the emissions limit for VOHAP in paragraph (a)(9) of this section or from a TEA cold box mold or core making line subject to the emissions limit for TEA in paragraph (a)(11) of this section, such that the 3-hour average combustion zone temperature does not fall below the minimum level established during the initial or subsequent performance test.

(5) You must operate each wet acid scrubber applied to emissions from a TEA cold box mold or core making line subject to the emissions limit for TEA in paragraph (a)(11) of this section such that:

(i) The 3-hour average scrubbing liquid flow rate does not fall below the minimum level established during the initial or subsequent performance test; and

(ii) The 3-hour average pH of the scrubber blowdown, as measured by a continuous parameter monitoring system (CPMS), does not exceed 4.5 or the pH of the scrubber blowdown, as measured once every 8 hours during process operations, does not exceed 4.5.

(c) If you use a control device other than a baghouse, wet scrubber, wet acid scrubber, or combustion device, you must prepare and submit a monitoring plan containing the information listed in paragraphs (c)(1) through (5) of this section. The monitoring plan is subject to approval by the Administrator.

(1) A description of the device;

(2) Test results collected in accordance with §63.7732 verifying the performance of the device for reducing emissions of PM, total metal HAP, VOHAP, or TEA to the levels required by this subpart;

(3) A copy of the operation and maintenance plan required by §63.7710(b);

(4) A list of appropriate operating parameters that will be monitored to maintain continuous compliance with the applicable emissions limitation(s); and

(5) Operating parameter limits based on monitoring data collected during the performance test.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7218, Feb. 7, 2008; 85 FR 56095, Sept. 10, 2020]

Work Practice Standards

§ 63.7700 What work practice standards must I meet?

(a) For each segregated scrap storage area, bin or pile, you must either comply with the certification requirements in paragraph (b) of this section, or prepare and implement a plan for the selection and inspection of scrap according to the requirements in paragraph (c) of this section. You may have certain scrap subject to paragraph (b) of this section and other scrap subject to paragraph (c) of this section at your facility provided the scrap remains segregated until charge make-up.

(b) You must prepare and operate at all times according to a written certification that the foundry purchases and uses only metal ingots, pig iron, slitter, or other materials that do not include post-consumer automotive body scrap, post-consumer engine blocks, post-consumer oil filters, oily turnings, lead components, mercury switches, plastics, or free organic liquids. For the purpose of this paragraph (b), ''free organic liquids'' is defined as material that fails the paint filter test by EPA Method 9095A, ''Paint Filter Liquids Test'' (Revision 1, December 1996), as published in EPA Publication SW–846 ''Test Methods for Evaluating Solid Waste, Physical/Chemical Methods'' (incorporated by reference—see §63.14). Any post-consumer engine blocks, post-consumer oil filters, or oily turnings that are processed and/or cleaned to the extent practicable such that the materials do not include lead components, mercury switches,

chlorinated plastics, or free organic liquids can be included in this certification.

(c) You must prepare and operate at all times according to a written plan for the selection and inspection of iron and steel scrap to minimize, to the extent practicable, the amount of organics and HAP metals in the charge materials used by the iron and steel foundry. This scrap selection and inspection plan is subject to approval by the Administrator. You must keep a copy of the plan onsite and readily available to all plant personnel with materials acquisition or inspection duties. You must provide a copy of the material specifications to each of your scrap vendors. Each plan must include the information specified in paragraphs (c)(1) through (3) of this section.

(1) A materials acquisition program to limit organic contaminants according to the requirements in paragraph (c)(1)(i) or (ii) of this section, as applicable.

(i) For scrap charged to a scrap preheater, electric arc metal melting furnace, or electric induction metal melting furnace, specifications for scrap materials to be depleted (to the extent practicable) of the presence of used oil filters, chlorinated plastic parts, organic liquids, and a program to ensure the scrap materials are drained of free liquids; or

(ii) For scrap charged to a cupola metal melting furnace, specifications for scrap materials to be depleted (to the extent practicable) of the presence of chlorinated plastic, and a program to ensure the scrap materials are drained of free liquids.

(2) A materials acquisition program specifying that the scrap supplier remove accessible mercury switches from the trunks and hoods of any automotive bodies contained in the scrap and remove accessible lead components such as batteries and wheel weights. You must either obtain and maintain onsite a copy of the procedures used by the scrap supplier for either removing accessible mercury switches or for purchasing automobile bodies that have had mercury switches removed, as applicable, or document your attempts to obtain a copy of these procedures from the scrap suppliers servicing your area.

(3) Procedures for visual inspection of a representative portion, but not less than 10 percent, of all incoming scrap shipments to ensure the materials meet the specifications.

(i) The inspection procedures must identify the location(s) where inspections are to be performed for each type of shipment. Inspections may be performed at the scrap supplier's facility. The selected location(s) must provide a reasonable vantage point, considering worker safety, for visual inspection.

(ii) The inspection procedures must include recordkeeping requirements that document each visual inspection and the results.

(iii) The inspection procedures must include provisions for rejecting or returning entire or partial scrap shipments that do not meet specifications and limiting purchases from vendors whose shipments fail to meet specifications for more than three inspections in one calendar year.

(iv) If the inspections are performed at the scrap supplier's facility, the inspection procedures must include an explanation of how the periodic inspections ensure that not less than 10 percent of scrap purchased from each supplier is subject to inspection.

(d) For each furan warm box mold or core making line in a new or existing iron and steel foundry, you must use a binder chemical formulation that does not contain methanol as a specific ingredient of the catalyst formulation as determined by the Material Safety Data Sheet. This requirement does not apply to the resin portion of the binder system.

(e) For each scrap preheater at an existing iron and steel foundry, you must meet either the requirement in paragraph (e)(1) or (2) of this section. As an alternative to the requirement in paragraph (e)(1) or (2) of this section, you must meet the VOHAP emissions limit in § 63.7690(a)(9).

(1) You must operate and maintain a gas-fired preheater where the flame directly contacts the scrap charged; or

(2) You must charge only material that is subject to and in compliance with the scrap certification requirement in paragraph (b) of this section.

(f) For each scrap preheater at a new iron and steel foundry, you must

charge only material that is subject to and in compliance with the scrap certification requirement in paragraph (b) of this section. As an alternative to this requirement, you must meet the VOHAP emissions limit in § 63.7690(a)(9).

(g) For each cupola at a new or existing iron and steel foundry, you must reduce VOHAP emissions to the extent practicable during periods of off blast, as defined in § 63.7765, by meeting the applicable requirements in paragraph (g)(1) or (2) of this section.

(1) On and before March 9, 2021, you must comply with the requirements in § 63.7710 and the requirements specified in the startup, shutdown, and malfunction plan required at § 63.7720(c).

(2) After March 9, 2021, you must comply with the applicable requirements in paragraphs (g)(2)(i) through (iii) of this section.

(i) Except as provided in paragraphs (g)(2)(ii) and (iii) of this section, you must operate an afterburner or other thermal combustion control device with a flame present at all times while the cupola is off blast. This includes the latter portion of coke bed preparation step and the initial metallics charging step during cupola startup, the slag and residual metal removal step during cupola shutdown, and idling conditions when the blast air is turned off or down to the point that the cupola does not produce additional molten metal.

(ii) During cupola startup steps of refractory curing and cupola bed preparation and during the cupola shutdown steps of cupola cooling and banking or bottom drop, you must comply with the requirements in § 63.7710 and the opacity limit in § 63.7690(a)(7).

(iii) You must light the cupola afterburner or other thermal combustion control device as soon as practicable during the cupola startup step of coke bed preparation following the procedures included in the operation and maintenance plan required at § 63.7710(b), but no later than 30 minutes after the blast air is started to begin the coke bed burn-in.

[69 FR 21923, Apr. 22, 2004, as amended at 70 FR 29404, May 20, 2005; 73 FR 7218, Feb. 7, 2008; 85 FR 56095, Sept. 10, 2020]

OPERATION AND MAINTENANCE REQUIREMENTS

§ 63.7710 What are my operation and maintenance requirements?

(a) You must always operate and maintain your iron and steel foundry, including air pollution control and monitoring equipment, in a manner consistent with good air pollution control practices for minimizing emissions at least to the levels required by this subpart.

(b) You must prepare and operate at all times according to a written operation and maintenance plan for each capture and collection system and control device for an emissions source subject to a PM, metal HAP, TEA, or VOHAP emissions limit in § 63.7690(a) or the work practice standards in § 63.7700(g). Your operation and maintenance plan also must include procedures for igniting gases from mold vents in pouring areas and pouring stations that use a sand mold system. This operation and maintenance plan is subject to approval by the Administrator. Each plan must contain the elements described in paragraphs (b)(1) through (6) of this section.

(1) Monthly inspections of the equipment that is important to the performance of the total capture system (*i.e.*, pressure sensors, dampers, and damper switches). This inspection must include observations of the physical appearance of the equipment (*e.g.*, presence of holes in the ductwork or hoods, flow constrictions caused by dents or accumulated dust in the ductwork, and fan erosion). The operation and maintenance plan must also include requirements to repair the defect or deficiency as soon as practicable.

(2) Operating limits for each capture system for an emissions source subject to an emissions limit or standard for VOHAP or TEA in § 63.7690(a)(8) through (11). You must establish the operating according to the requirements in paragraphs (b)(2)(i) through (iii) of this section.

(i) Select operating limit parameters appropriate for the capture system design that are representative and reliable indicators of the performance of the capture system. At a minimum, you must use appropriate operating

limit parameters that indicate the level of the ventilation draft and damper position settings for the capture system when operating to collect emissions, including revised settings for seasonal variations. Appropriate operating limit parameters for ventilation draft include, but are not limited to: volumetric flow rate through each separately ducted hood, total volumetric flow rate at the inlet to the control device to which the capture system is vented, fan motor amperage, or static pressure. Any parameter for damper position setting may be used that indicates the duct damper position related to the fully open setting.

(ii) For each operating limit parameter selected in paragraph (b)(2)(i) of this section, designate the value or setting for the parameter at which the capture system operates during the process operation. If your operation allows for more than one process to be operating simultaneously, designate the value or setting for the parameter at which the capture system operates during each possible configuration that you may operate (*i.e.*, the operating limits with one furnace melting, two melting, as applicable to your plant).

(iii) Include documentation in your plan to support your selection of the operating limits established for your capture system. This documentation must include a description of the capture system design, a description of the capture system operating during production, a description of each selected operating limit parameter, a rationale for why you chose the parameter, a description of the method used to monitor the parameter according to the requirements of § 63.7740(a), and the data used to set the value or setting for the parameter for each of your process configurations.

(3) Preventative maintenance plan for each control device, including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

(4) A site-specific monitoring plan for each bag leak detection system. For each bag leak detection system that operates on the triboelectric effect, the monitoring plan must be consistent with the recommendations contained in the U.S. Environmental Protection Agency guidance document ''Fabric Filter Bag Leak Detection Guidance'' (EPA–454/R–98–015). This baghouse monitoring plan is subject to approval by the Administrator. The owner or operator shall operate and maintain the bag leak detection system according to the site-specific monitoring plan at all times. The plan must address all of the items identified in paragraphs (b)(4)(i) through (v) of this section.

(i) Installation of the bag leak detection system.

(ii) Initial and periodic adjustment of the bag leak detection system including how the alarm set-point will be established.

(iii) Operation of the bag leak detection system including quality assurance procedures.

(iv) How the bag leak detection system will be maintained including a routine maintenance schedule and spare parts inventory list.

(v) How the bag leak detection system output will be recorded and stored.

(5) Corrective action plan for each baghouse. The plan must include the requirement that, in the event a bag leak detection system alarm is triggered, you must initiate corrective action to determine the cause of the alarm within 1 hour of the alarm, initiate corrective action to correct the cause of the problem within 24 hours of the alarm, and complete the corrective action as soon as practicable. Corrective actions taken may include, but are not limited to:

(i) Inspecting the baghouse for air leaks, torn or broken bags or filter media, or any other condition that may cause an increase in emissions.

(ii) Sealing off defective bags or filter media.

(iii) Replacing defective bags or filter media or otherwise repairing the control device.

(iv) Sealing off a defective baghouse compartment.

(v) Cleaning the bag leak detection system probe or otherwise repairing the bag leak detection system.

(vi) Making process changes.

(vii) Shutting down the process producing the PM emissions.

(6) Procedures for providing an ignition source to mold vents of sand mold

systems in each pouring area and pouring station unless you determine the mold vent gases either are not ignitable, ignite automatically, or cannot be ignited due to accessibility or safety issues. You must document and maintain records of this determination. The determination of ignitability, accessibility, and safety may encompass multiple casting patterns provided the castings utilize similar sand-to-metal ratios, binder formulations, and coating materials. The determination of ignitability must be based on observations of the mold vents within 5 minutes of pouring, and the flame must be present for at least 15 seconds for the mold vent to be considered ignited. For the purpose of this determination:

(i) Mold vents that ignite more than 75 percent of the time without the presence of an auxiliary ignition source are considered to ignite automatically; and

(ii) Mold vents that do not ignite automatically and cannot be ignited in the presence of an auxiliary ignition source more than 25 percent of the time are considered to be not ignitable.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7218, Feb. 7, 2008; 85 FR 56096, Sept. 10, 2020]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7720 What are my general requirements for complying with this subpart?

(a) On and before March 9, 2021, for affected sources that commenced construction or reconstruction on or before September 10, 2020, you must be in compliance with the emissions limitations, work practice standards, and operation and maintenance requirements in this subpart at all times, except during periods of startup and shutdown. After March 9, 2021, for affected sources that commenced construction or reconstruction on or before September 10, 2020, and upon startup for affected sources that commenced construction or reconstruction after September 10, 2020, you must be in compliance with the emissions limitations, work practice standards, and operation and maintenance requirements in this subpart at all times.

(b) During the period between the compliance date specified for your iron and steel foundry in § 63.7683 and the date when applicable operating limits have been established during the initial performance test, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.

(c) On and before March 9, 2021, for affected sources that commenced construction or reconstruction on or before March 9, 2021, you must develop a written startup, shutdown, and malfunction plan according to the provisions in § 63.6(e)(3). The startup, shutdown, and malfunction plan also must specify what constitutes a shutdown of a cupola and how to determine that operating conditions are normal following startup of a cupola. After March 9, 2021, for affected sources that commenced construction or reconstruction on or before September 10, 2020, and upon startup for affected sources that commenced construction or reconstruction after September 10, 2020, the startup, shutdown, and malfunction plan requirements no longer apply.

[69 FR 21923, Apr. 22, 2004, as amended at 71 FR 20468, Apr. 20, 2006; 85 FR 56096, Sept. 10, 2020]

INITIAL COMPLIANCE REQUIREMENTS

§ 63.7730 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) As required by § 63.7(a)(2), you must conduct a performance test no later than 180 calendar days after the compliance date that is specified in § 63.7683 for your iron and steel foundry to demonstrate initial compliance with each emissions limitation in § 63.7690 that applies to you.

(b) For each work practice standard in § 63.7700 and each operation and maintenance requirement in § 63.7710 that applies to you where initial compliance is not demonstrated using a performance test, you must demonstrate initial compliance no later than 30 calendar days after the compliance date that is specified for your iron and steel foundry in § 63.7683.

(c) If you commenced construction or reconstruction between December 23, 2002 and April 22, 2004, you must demonstrate initial compliance with either the proposed emissions limit or the

promulgated emissions limit no later than October 19, 2004 or no later than 180 calendar days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

(d) If you commenced construction or reconstruction between December 23, 2002 and April 22, 2004, and you chose to comply with the proposed emissions limit when demonstrating initial compliance, you must conduct a second performance test to demonstrate compliance with the promulgated emissions limit by October 19, 2007 or after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

§ 63.7731 When must I conduct subsequent performance tests?

(a) You must conduct subsequent performance tests to demonstrate compliance with all applicable PM or total metal HAP, VOHAP, and TEA emissions limitations in § 63.7690 for your iron and steel foundry no less frequently than every 5 years and each time you elect to change an operating limit or to comply with a different alternative emissions limit, if applicable. The requirement to conduct performance tests every 5 years does not apply to an emissions source for which a continuous emissions monitoring system (CEMS) is used to demonstrate continuous compliance.

(b) You must conduct subsequent performance tests to demonstrate compliance with the opacity limit in § 63.7690(a)(7) for your iron and steel foundry no less frequently than once every 6 months.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7219, Feb. 7, 2008]

§ 63.7732 What test methods and other procedures must I use to demonstrate initial compliance with the emissions limitations?

(a) You must conduct each performance test that applies to your iron and steel foundry based on your selected compliance alternative, if applicable, according to the requirements in paragraphs (b) through (i) of this section. Each performance test must be conducted under conditions representative of normal operations. Normal operating conditions exclude periods of startup and shutdown. You may not conduct performance tests during periods of malfunction. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(b) To determine compliance with the applicable emissions limit for PM in § 63.7690(a)(1) through (6) for a metal melting furnace, scrap preheater, pouring station, or pouring area, follow the test methods and procedures in paragraphs (b)(1) through (6) of this section.

(1) Determine the concentration of PM according to the test methods in 40 CFR part 60, appendix A that are specified in paragraphs (b)(1)(i) through (v) of this section.

(i) Method 1 or 1A to select sampling port locations and the number of traverse points in each stack or duct. Sampling sites must be located at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(ii) Method 2, 2A, 2C, 2D, 2F, or 2G to determine the volumetric flow rate of the stack gas.

(iii) Method 3, 3A, or 3B to determine the dry molecular weight of the stack gas.

(iv) Method 4 to determine the moisture content of the stack gas.

(v) Method 5, 5B, 5D, 5F, or 5I, as applicable, to determine the PM concentration. The PM concentration is determined using only the front-half (probe rinse and filter) of the PM catch.

(2) Collect a minimum sample volume of 60 dscf of gas during each PM sampling run. A minimum of three valid test runs are needed to comprise a performance test.

(3) For cupola metal melting furnaces, sample only during times when the cupola is on blast.

(4) For electric arc and electric induction metal melting furnaces, sample only during normal production conditions, which may include, but are not

limited to the following cycles: Charging, melting, alloying, refining, slagging, and tapping.

(5) For scrap preheaters, sample only during normal production conditions, which may include, but are not limited to the following cycles: Charging, heating, and discharging.

(6) Determine the total mass of metal charged to the furnace or scrap preheater. For a cupola metal melting furnace at an existing iron and steel foundry that is subject to the PM emissions limit in §63.7690(a)(ii), calculate the PM emissions rate in pounds of PM per ton (lb/ton) of metal charged using Equation 1 of this section:

$$EF_{PM} = C_{PM} \times \left(\frac{Q}{M_{charge}} \right) \times \left(\frac{t_{test}}{7{,}000} \right) \qquad \text{(Eq. 1)}$$

Where:

EF_{PM} = Mass emissions rate of PM, pounds of PM per ton (lb/ton) of metal charged;

C_{PM} = Concentration of PM measured during performance test run, gr/dscf;

Q = Volumetric flow rate of exhaust gas, dry standard cubic feet per minute (dscfm);

M_{charge} = Mass of metal charged during performance test run, tons;

t_{test} = Duration of performance test run, minutes; and

7,000 = Unit conversion factor, grains per pound (gr/lb).

(c) To determine compliance with the applicable emissions limit for total metal HAP in §63.7690(a)(1) through (6) for a metal melting furnace, scrap preheater, pouring station, or pouring area, follow the test methods and procedures in paragraphs (c)(1) through (6) of this section.

(1) Determine the concentration of total metal HAP according to the test methods in 40 CFR part 60, appendix A that are specified in paragraphs (c)(1)(i) through (v) of this section.

(i) Method 1 or 1A to select sampling port locations and the number of traverse points in each stack or duct. Sampling sites must be located at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(ii) Method 2, 2A, 2C, 2D, 2F, or 2G to determine the volumetric flow rate of the stack gas.

(iii) Method 3, 3A, or 3B to determine the dry molecular weight of the stack gas.

(iv) Method 4 to determine the moisture content of the stack gas.

(v) Method 29 to determine the total metal HAP concentration.

(2) A minimum of three valid test runs are needed to comprise a performance test.

(3) For cupola metal melting furnaces, sample only during times when the cupola is on blast.

(4) For electric arc and electric induction metal melting furnaces, sample only during normal production conditions, which may include, but are not limited to the following cycles: Charging, melting, alloying, refining, slagging, and tapping.

(5) For scrap preheaters, sample only during normal production conditions, which may include, but are not limited to the following cycles: Charging, heating, and discharging.

(6) Determine the total mass of metal charged to the furnace or scrap preheater during each performance test run and calculate the total metal HAP emissions rate (pounds of total metal HAP per ton (lb/ton) of metal charged) using Equation 2 of this section:

$$EF_{TMHAP} = C_{TMHAP} \times \left(\frac{Q}{M_{charge}} \right) \times \left(\frac{t_{test}}{7{,}000} \right) \qquad \text{(Eq. 2)}$$

Where:

EF_{TMHAP} = Emissions rate of total metal HAP, pounds of total metal HAP per ton (lb/ton) of metal charged;

C_{TMHAP} = Concentration of total metal HAP measured during performance test run, gr/dscf;

Q = Volumetric flow rate of exhaust gas, dscfm;

M_{charge} = Mass of metal charged during performance test run, tons;

t_{test} = Duration of performance test run, minutes; and

7,000 = Unit conversion factor, gr/lb.

(d) To determine compliance with the opacity limit in §63.7690(a)(7) for fugitive emissions from buildings or structures housing any iron and steel foundry emissions source at the iron and steel foundry, follow the procedures in paragraphs (d)(1) and (2) of this section.

(1) Using a certified observer, conduct each opacity test according to the requirements in EPA Method 9 (40 CFR part 60, appendix A) and §63.6(h)(5). The certified observer may identify a limited number of openings or vents that appear to have the highest opacities and perform opacity observations on the identified openings or vents in lieu of performing observations for each opening or vent from the building or structure. Alternatively, a single opacity observation for the entire building or structure may be performed, if the fugitive release points afford such an observation.

(2) During testing intervals when PM performance tests, if applicable, are being conducted, conduct the opacity test such the opacity observations are recorded during the PM performance tests.

(e) To determine compliance with the applicable VOHAP emissions limit in §63.7690(a)(8) for a cupola metal melting furnace or in §63.7690(a)(9) for a scrap preheater, follow the test methods and procedures in paragraphs (e)(1) through (4) of this section.

(1) Determine the VOHAP concentration for each test run according to the test methods in 40 CFR part 60, appendix A, that are specified in paragraphs (e)(1)(i) through (v) of this section.

(i) Method 1 or 1A to select sampling port locations and the number of traverse points in each stack or duct. Sampling sites must be located at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(ii) Method 2, 2A, 2C, 2D, 2F, or 2G to determine the volumetric flow rate of the stack gas.

(iii) Method 3, 3A, or 3B to determine the dry molecular weight of the stack gas.

(iv) Method 4 to determine the moisture content of the stack gas.

(v) Method 18 to determine the VOHAP concentration. Alternatively, you may use Method 25 to determine the concentration of total gaseous nonmethane organics (TGNMO) or Method 25A to determine the concentration of total organic compounds (TOC), using hexane as the calibration gas.

(2) Determine the average VOHAP, TGNMO, or TOC concentration using a minimum of three valid test runs. Each test run must include a minimum of 60 continuous operating minutes.

(3) For a cupola metal melting furnace, correct the measured concentration of VOHAP, TGNMO, or TOC for oxygen content in the gas stream using Equation 3 of this section:

$$C_{VOHAP,\ 10\%O_2} = C_{VOHAP}\left(\frac{10.9\%}{20.9\% - \%O_2}\right) \qquad \text{(Eq. 3)}$$

Where:

C_{VOHAP} = Concentration of VOHAP in ppmv as measured by Method 18 in 40 CFR part 60, appendix A or the concentration of TGNMO or TOC in ppmv as hexane as measured by Method 25 or 25A in 40 CFR part 60, appendix A; and

$\%O_2$ = Oxygen concentration in gas stream, percent by volume (dry basis).

(4) For a cupola metal melting furnace, measure the combustion zone temperature of the combustion device with the CPMS required in §63.7740(d)

during each sampling run in 15-minute intervals. Determine and record the 15-minute average of the three runs.

(f) Follow the applicable procedures in paragraphs (f)(1) through (3) of this section to determine compliance with the VOHAP emissions limit in §63.7690(a)(10) for automated pallet cooling lines or automated shakeout lines.

(1) Follow these procedures to demonstrate compliance by direct measurement of total hydrocarbons (a surrogate for VOHAP) using a volatile organic compound (VOC) CEMS.

(i) Using the VOC CEMS required in §63.7740(g), measure and record the concentration of total hydrocarbons (as hexane) for 180 continuous operating minutes. You must measure emissions at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(ii) Reduce the monitoring data to hourly averages as specified in §63.8(g)(2).

(iii) Compute and record the 3-hour average of the monitoring data.

(2) As an alternative to the procedures in paragraph (f)(1) of this section, you may demonstrate compliance with the VOHAP emissions limit in §63.7690(a)(10) by establishing a site-specific TOC emissions limit that is correlated to the VOHAP emissions limit according to the procedures in paragraph (f)(2)(i) through (ix) of this section.

(i) Determine the VOHAP concentration for each test run according to the test methods in 40 CFR part 60, appendix A that are specified in paragraph (f)(2)(ii) through (vi) of this section.

(ii) Method 1 or 1A to select sampling port locations and the number of traverse points in each stack or duct. Sampling sites must be located at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(iii) Method 2, 2A, 2C, 2D, 2F, or 2G to determine the volumetric flow rate of the stack gas.

(iv) Method 3, 3A, or 3B to determine the dry molecular weight of the stack gas.

(v) Method 4 to determine the moisture content of the stack gas.

(vi) Method 18 to determine the VOHAP concentration. Alternatively, you may use Method 25 to determine the concentration of TGNMO using hexane as the calibration gas.

(vii) Using the CEMS required in §63.7740(g), measure and record the concentration of total hydrocarbons (as hexane) during each of the Method 18 (or Method 25) sampling runs. You must measure emissions at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(viii) Calculate the average VOHAP (or TGNMO) concentration for the source test as the arithmetic average of the concentrations measured for the individual test runs, and determine the average concentration of total hydrocarbon (as hexane) as measured by the CEMS during all test runs.

(ix) Calculate the site-specific VOC emissions limit using Equation 4 of this section:

$$VOC_{limit} = 20 \times \frac{C_{VOHAP,\,avg}}{C_{CEM}} \qquad \text{(Eq. 4)}$$

Where:

$C_{VOHAP,avg}$ = Average concentration of VOHAP for the source test in ppmv as measured by Method 18 in 40 CFR part 60, appendix A or the average concentration of TGNMO for the source test in ppmv as hexane as measured by Method 25 in 40 CFR part 60, appendix A; and

C_{CEM} = Average concentration of total hydrocarbons in ppmv as hexane as measured using the CEMS during the source test.

(3) For two or more exhaust streams from one or more automated conveyor and pallet cooling lines or automated shakeout lines, compute the flow-weighted average concentration of VOHAP emissions for each combination of exhaust streams using Equation 5 of this section:

$$C_W = \frac{\sum_{i=1}^{n} C_i Q_i}{\sum_{i=1}^{n} Q_i} \qquad \text{(Eq. 5)}$$

Where:

C_w = Flow-weighted concentration of VOHAP or VOC, ppmv (as hexane);
C_i = Concentration of VOHAP or VOC from exhaust stream ''i'', ppmv (as hexane);
n = Number of exhaust streams sampled; and
Q_i = Volumetric flow rate of effluent gas from exhaust stream ''i,'', dscfm.

(g) To determine compliance with the emissions limit or standard in §63.7690(a)(11) for a TEA cold box mold or core making line, follow the test methods in 40 CFR part 60, appendix A, specified in paragraphs (g)(1) through (4) of this section.

(1) Determine the TEA concentration for each test run according to the test methods in 40 CFR part 60, appendix A that are specified in paragraphs (g)(1)(i) through (v) of this section.

(i) Method 1 or 1A to select sampling port locations and the number of traverse points in each stack or duct. If you elect to meet the 99 percent reduction standard, sampling sites must be located both at the inlet to the control device and at the outlet of the control device prior to any releases to the atmosphere. If you elect to meet the concentration limit, the sampling site must be located at the outlet of the control device (or at the outlet of the emissions source if no control device is present) prior to any releases to the atmosphere.

(ii) Method 2, 2A, 2C, 2D, 2F, or 2G to determine the volumetric flow rate of the stack gas.

(iii) Method 3, 3A, or 3B to determine the dry molecular weight of the stack gas.

(iv) Method 4 to determine the moisture content of the stack gas.

(v) Method 18 to determine the TEA concentration. Alternatively, you may use NIOSH Method 2010 (incorporated by reference—see §63.14) to determine the TEA concentration provided the performance requirements outlined in section 13.1 of EPA Method 18 are satisfied. The sampling option and time must be sufficiently long such that either the TEA concentration in the field sample is at least 5 times the limit of detection for the analytical method or the test results calculated using the laboratory's reported analytical detection limit for the specific field samples are less than ⅕ of the applicable emissions limit. When using Method 18, the adsorbent tube approach, as described in section 8.2.4 of Method 18, may be required to achieve the necessary analytical detection limits. The sampling time must be at least 1 hour in all cases.

(2) If you use a wet acid scrubber, conduct the test as soon as practicable after adding fresh acid solution and the system has reached normal operating conditions.

(3) If you use a wet acid scrubber that is subject to the operating limit in §63.7690(b)(5)(ii) for pH level, determine the pH of the scrubber blowdown using the procedures in paragraph (g)(3)(i) or (ii) of this section.

(i) Measure the pH of the scrubber blowdown with the CPMS required in §63.7740(f)(2) during each TEA sampling run in intervals of no more than 15 minutes. Determine and record the 3-hour average; or

(ii) Measure and record the pH level using the probe and meter required in §63.7740(f)(2) once each sampling run. Determine and record the average pH level for the three runs.

(4) If you are subject to the 99 percent reduction standard, calculate the mass emissions reduction using Equation 6 of this section:

$$\%\,\text{reduction} = \frac{E_i - E_o}{E_i} \times 100\% \qquad \text{(Eq. 6)}$$

Where:

E_i = Mass emissions rate of TEA at control device inlet, kilograms per hour (kg/hr); and
E_o = Mass emissions rate of TEA at control device outlet, kg/hr.

(h) To determine compliance with the PM or total metal HAP emissions limits in §63.7690(a)(1) through (6) when one or more regulated emissions sources are combined with either another regulated emissions source subject to a different emissions limit or other non-regulated emissions sources, you may demonstrate compliance using one of the procedures in paragraphs (h)(1) through (3) of this section.

(1) Meet the most stringent applicable emissions limit for the regulated emissions sources included in the combined emissions stream for the combined emissions stream.

(2) Use the procedures in paragraphs (h)(2)(i) through (iii) of this section.

(i) Determine the volumetric flow rate of the individual regulated streams for which emissions limits apply.

(ii) Calculate the flow-weighted average emissions limit, considering only the regulated streams, using Equation 5 of this section, except C_w is the flow-weighted average emissions limit for PM or total metal HAP in the exhaust stream, gr/dscf; and C_i is the concentration of PM or total metal HAP in exhaust stream ''i'', gr/dscf.

(iii) Meet the calculated flow-weighted average emissions limit for the regulated emissions sources included in the combined emissions stream for the combined emissions stream.

(3) Use the procedures in paragraphs (h)(3)(i) through (iii) of this section.

(i) Determine the PM or total metal HAP concentration of each of the regulated streams prior to the combination with other exhaust streams or control device.

(ii) Measure the flow rate and PM or total metal HAP concentration of the combined exhaust stream both before and after the control device and calculate the mass removal efficiency of the control device using Equation 6 of this section, except E_i is the mass emissions rate of PM or total metal HAP at the control device inlet, lb/hr and E_o is the mass emissions rate of PM or total metal HAP at the control device outlet, lb/hr.

(iii) Meet the applicable emissions limit based on the calculated PM or total metal HAP concentration for the regulated emissions sources using Equation 7 of this section:

$$C_{released} = C_i \times \left(1 - \frac{\%\,reduction}{100}\right) \qquad \text{(Eq. 7)}$$

Where:

$C_{released}$ = Calculated concentration of PM (or total metal HAP) predicted to be released to the atmosphere from the regulated emissions source, gr/dscf; and

C_i = Concentration of PM (or total metal HAP) in the uncontrolled regulated exhaust stream, gr/dscf.

(i) To determine compliance with an emissions limit for situations when multiple sources are controlled by a single control device, but only one source operates at a time, or other situations that are not expressly considered in paragraphs (b) through (h) of this section, a site-specific test plan should be submitted to the Administrator for approval according to the requirements in § 63.7(c)(2) and (3).

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7219, Feb. 7, 2008; 85 FR 56096, Sept. 10, 2020]

§ 63.7733 What procedures must I use to establish operating limits?

(a) For each capture system subject to operating limits in § 63.7690(b)(1)(ii), you must establish site-specific operating limits in your operation and maintenance plan according to the procedures in paragraphs (a)(1) through (3) of this section.

(1) Concurrent with applicable emissions and opacity tests, measure and record values for each of the operating limit parameters in your capture system operation and maintenance plan according to the monitoring requirements in § 63.7740(a).

(2) For any dampers that are manually set and remain at the same position at all times the capture system is operating, the damper position must be visually checked and recorded at the beginning and end of each run.

(3) Review and record the monitoring data. Identify and explain any times the capture system operated outside the applicable operating limits.

(b) For each wet scrubber subject to the operating limits in § 63.7690(b)(2) for pressure drop and scrubber water flow rate, you must establish site-specific operating limits according to the procedures specified in paragraphs (b)(1) and (2) of this section.

(1) Using the CPMS required in § 63.7740(c), measure and record the

pressure drop and scrubber water flow rate in intervals of no more than 15 minutes during each PM test run.

(2) Compute and record the average pressure drop and average scrubber water flow rate for each valid sampling run in which the applicable emissions limit is met.

(c) For each combustion device applied to emissions from a scrap preheater or TEA cold box mold or core making line subject to the operating limit in § 63.7690(b)(4) for combustion zone temperature, you must establish a site-specific operating limit according to the procedures specified in paragraphs (c)(1) and (2) of this section.

(1) Using the CPMS required in § 63.7740(e), measure and record the combustion zone temperature during each sampling run in intervals of no more than 15 minutes.

(2) Compute and record the average combustion zone temperature for each valid sampling run in which the applicable emissions limit is met.

(d) For each acid wet scrubber subject to the operating limit in § 63.7690(b)(5), you must establish a site-specific operating limit for scrubbing liquid flow rate according to the procedures specified in paragraphs (d)(1) and (2) of this section.

(1) Using the CPMS required in § 63.7740(f), measure and record the scrubbing liquid flow rate during each TEA sampling run in intervals of no more than 15 minutes.

(2) Compute and record the average scrubbing liquid flow rate for each valid sampling run in which the applicable emissions limit is met.

(e) You may change the operating limits for a capture system, wet scrubber, acid wet scrubber, or combustion device if you meet the requirements in paragraphs (e)(1) through (3) of this section.

(1) Submit a written notification to the Administrator of your request to conduct a new performance test to revise the operating limit.

(2) Conduct a performance test to demonstrate compliance with the applicable emissions limitation in § 63.7690.

(3) Establish revised operating limits according to the applicable procedures in paragraphs (a) through (d) of this section.

(f) You may use a previous performance test (conducted since December 22, 2002) to establish an operating limit provided the test meets the requirements of this subpart.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008]

§ 63.7734 How do I demonstrate initial compliance with the emissions limitations that apply to me?

(a) You have demonstrated initial compliance with the emissions limits in § 63.7690(a) by meeting the applicable conditions in paragraphs (a)(1) through (11) of this section. When alternative emissions limitations are provided for a given emissions source, you are not restricted in the selection of which applicable alternative emissions limitation is used to demonstrate compliance.

(1) For each electric arc metal melting furnace, electric induction metal melting furnace, or scrap preheater at an existing iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.005 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0004 gr/dscf.

(2) For each cupola metal melting furnace at an existing iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.006 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0005 gr/dscf; or

(iii) The average PM mass emissions rate, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.10 pound of PM per ton (lb/ton) of metal charged; or

(iv) The average total metal HAP mass emissions rate, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.008 pound of total metal HAP per ton (lb/ton) of metal charged.

(3) For each cupola metal melting furnace or electric arc metal melting furnace at a new iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.002 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0002 gr/dscf.

(4) For each electric induction metal melting furnace or scrap preheater at a new iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.001 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.00008 gr/dscf.

(5) For each pouring station at an existing iron and steel foundry,

(i) The average PM concentration in the exhaust stream, measured according to the performance test procedures in § 63.7732(b), did not exceed 0.010 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0008 gr/dscf.

(6) For each pouring area or pouring station at a new iron and steel foundry,

(i) The average PM concentration in the exhaust stream, measured according to the performance test procedures in § 63.7732(b), did not exceed 0.002 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0002 gr/dscf.

(7) For each building or structure housing any iron and steel foundry emissions source at the iron and steel foundry, the opacity of fugitive emissions from foundry operations discharged to the atmosphere, determined according to the performance test procedures in § 63.7732(d), did not exceed 20 percent (6-minute average), except for one 6-minute average per hour that did not exceed 27 percent opacity.

(8) For each cupola metal melting furnace at a new or existing iron and steel foundry, the average VOHAP concentration, determined according to the performance test procedures in § 63.7732(e), did not exceed 20 ppmv corrected to 10 percent oxygen.

(9) For each scrap preheater at an existing iron and steel foundry that does not meet the work practice standards in § 63.7700(e)(1) or (2) and for each scrap preheater at a new iron and steel foundry that does not meet the work practice standard in § 63.7700(f), the average VOHAP concentration determined according to the performance test procedures in § 63.7732(e), did not exceed 20 ppmv.

(10) For one or more automated conveyor and pallet cooling lines that use a sand mold system or automated shakeout lines that use a sand mold system at a new foundry,

(i) You have reduced the data from the CEMS to 3-hour averages according to the performance test procedures in § 63.7732(f)(1) or (2); and

(ii) The 3-hour flow-weighted average VOHAP concentration, measured according to the performance test procedures in § 63.7332(f)(1) or (2), did not exceed 20 ppmv.

(11) For each TEA cold box mold or core making line in a new or existing iron and steel foundry, the average TEA concentration, determined according to the performance test procedures in § 63.7732(g), did not exceed 1 ppmv or was reduced by 99 percent.

(b) You have demonstrated initial compliance with the operating limits in § 63.7690(b) if:

(1) For each capture system subject to the operating limit in § 63.7690(b)(1)(ii),

(i) You have established appropriate site-specific operating limits in your operation and maintenance plan according to the requirements in § 63.7710(b); and

(ii) You have a record of the operating parameter data measured during the performance test in accordance with § 63.7733(a); and

(2) For each wet scrubber subject to the operating limits in § 63.7690(b)(2) for pressure drop and scrubber water flow rate, you have established appropriate site-specific operating limits and have a record of the pressure drop and scrubber water flow rate measured during the performance test in accordance with § 63.7733(b).

(3) For each combustion device subject to the operating limit in § 63.7690(b)(3) for combustion zone temperature, you have a record of the combustion zone temperature measured during the performance test in accordance with § 63.7732(e)(4).

(4) For each combustion device subject to the operating limit in § 63.7690(b)(4) for combustion zone temperature, you have established appropriate site-specific operating limits and have a record of the combustion zone temperature measured during the performance test in accordance with § 63.7733(c).

(5) For each acid wet scrubber subject to the operating limits in § 63.7690(b)(5) for scrubbing liquid flow rate and scrubber blowdown pH,

(i) You have established appropriate site-specific operating limits for the scrubbing liquid flow rate and have a record of the scrubbing liquid flow rate measured during the performance test in accordance with § 63.7733(d); and

(ii) You have a record of the pH of the scrubbing liquid blowdown measured during the performance test in accordance with § 63.7732(g)(3).

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008]

§ 63.7735 How do I demonstrate initial compliance with the work practice standards that apply to me?

(a) For each iron and steel foundry subject to the certification requirement in § 63.7700(b), you have demonstrated initial compliance if you have certified in your notification of compliance status that: ''At all times, your foundry will purchase and use only metal ingots, pig iron, slitter, or other materials that do not include post-consumer automotive body scrap, post-consumer engine blocks, post-consumer oil filters, oily turnings, lead components, mercury switches, plastics, or free organic liquids.''

(b) For each iron and steel foundry subject to the requirements in § 63.7700(c) for a scrap inspection and selection plan, you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You have submitted a written plan to the Administrator for approval according to the requirements in § 63.7700(c); and

(2) You will operate at all times according to the plan requirements.

(c) For each furan warm box mold or core making line in a new or existing foundry subject to the work practice standard in § 63.7700(d), you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You will meet the no methanol requirement for the catalyst portion of each binder chemical formulation; and

(2) You have records documenting your certification of compliance, such as a material safety data sheet (provided that it contains appropriate information), a certified product data sheet, or a manufacturer's hazardous air pollutant data sheet, onsite and available for inspection.

(d) For each scrap preheater at an existing iron and steel foundry subject to the work practice standard in § 63.7700(e)(1) or (2), you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You have installed a gas-fired preheater where the flame directly contacts the scrap charged, you will operate and maintain each gas-fired scrap preheater such that the flame directly contacts the scrap charged, and you have records documenting your certification of compliance that are onsite and available for inspection; or

(2) You will charge only material that is subject to and in compliance with the scrap certification requirements in § 63.7700(b) and you have records documenting your certification of compliance that are onsite and available for inspection.

(e) For each scrap preheater at a new iron and steel foundry subject to the work practice standard in § 63.7700(f), you have demonstrated initial compliance if you have certified in your notification of compliance status that you will charge only material that is subject to and in compliance with the scrap certification requirements in § 63.7700(b) and you have records documenting your certification of compliance that are onsite and available for inspection.

[69 FR 21923, Apr. 22, 2004, as amended at 70 FR 29404, May 20, 2005]

§ 63.7736 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

(a) For each capture system subject to an operating limit in § 63.7690(b), you have demonstrated initial compliance if you have met the conditions in paragraphs (a)(1) and (2) of this section.

(1) You have certified in your notification of compliance status that:

(i) You have submitted the capture system operation and maintenance plan to the Administrator for approval according to the requirements of § 63.7710(b); and

(ii) You will inspect, operate, and maintain each capture system according to the procedures in the plan.

(2) You have certified in your performance test report that the system operated during the test at the operating limits established in your operation and maintenance plan.

(b) For each control device subject to an operating limit in § 63.7690(b), you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You have submitted the control device operation and maintenance plan to the Administrator for approval according to the requirements of § 63.7710(b); and

(2) You will inspect, operate, and maintain each control device according to the procedures in the plan.

(c) For each bag leak detection system, you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You have submitted the bag leak detection system monitoring information to the Administrator within the written O&M plan for approval according to the requirements of § 63.7710(b);

(2) You will inspect, operate, and maintain each bag leak detection system according to the procedures in the plan; and

(3) You will follow the corrective action procedures for bag leak detection system alarms according to the requirements in the plan.

(d) For each pouring area and pouring station in a new or existing foundry, you have demonstrated initial compliance if you have certified in your notification of compliance status report that:

(1) You have submitted the mold vent ignition plan to the Administrator for approval according to the requirements in § 63.7710(b); and

(2) You will follow the procedures for igniting mold vent gases according to the requirements in the plan.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008]

Continuous Compliance Requirements

§ 63.7740 What are my monitoring requirements?

(a) For each capture system subject to an operating limit in § 63.7690(b)(1), you must install, operate, and maintain a CPMS according to the requirements in § 63.7741(a) and the requirements in paragraphs (a)(1) and (2) of this section.

(1) If you use a flow measurement device to monitor the operating limit parameter, you must at all times monitor the hourly average rate (*e.g.*, the hourly average actual volumetric flow rate through each separately ducted hood or the average hourly total volumetric flow rate at the inlet to the control device).

(2) Dampers that are manually set and remain in the same position are exempt from the requirement to install and operate a CPMS. If dampers are not manually set and remain in the same position, you must make a visual check at least once every 24 hours to verify that each damper for the capture system is in the same position as during the initial performance test.

(b) For each negative pressure baghouse or positive pressure baghouse equipped with a stack that is applied to meet any PM or total metal HAP emissions limitation in this subpart, you must at all times monitor the relative change in PM loadings using a bag leak detection system according to the requirements in § 63.7741(b).

(c) For each baghouse, regardless of type, that is applied to meet any PM or total metal HAP emissions limitation in this subpart, you must conduct inspections at their specified frequencies according to the requirements specified in paragraphs (c)(1) through (8) of this section.

(1) Monitor the pressure drop across each baghouse cell each day to ensure pressure drop is within the normal operating range identified in the manual.

(2) Confirm that dust is being removed from hoppers through weekly visual inspections or other means of ensuring the proper functioning of removal mechanisms.

(3) Check the compressed air supply for pulse-jet baghouses each day.

(4) Monitor cleaning cycles to ensure proper operation using an appropriate methodology.

(5) Check bag cleaning mechanisms for proper functioning through monthly visual inspections or equivalent means.

(6) Make monthly visual checks of bag tension on reverse air and shaker-type baghouses to ensure that bags are not kinked (kneed or bent) or lying on their sides. You do not have to make this check for shaker-type baghouses using self-tensioning (spring-loaded) devices.

(7) Confirm the physical integrity of the baghouse through quarterly visual inspections of the baghouse interior for air leaks.

(8) Inspect fans for wear, material buildup, and corrosion through quarterly visual inspections, vibration detectors, or equivalent means.

(d) For each wet scrubber subject to the operating limits in § 63.7690(b)(2), you must at all times monitor the 3-hour average pressure drop and scrubber water flow rate using CPMS according to the requirements in § 63.7741(c).

(e) For each combustion device subject to the operating limit in § 63.7690(b)(3) or the work practice standard in § 63.7700(g)(2)(i), you must at all times monitor the 15-minute average combustion zone temperature using a CPMS according to the requirements of § 63.7741(d).

(f) For each combustion device subject to the operating limit in § 63.7690(b)(4), you must at all times monitor the 3-hour average combustion zone temperature using CPMS according to the requirements in § 63.7741(d).

(g) For each wet acid scrubber subject to the operating limits in § 63.7690(b)(5),

(1) You must at all times monitor the 3-hour average scrubbing liquid flow rate using CPMS according to the requirements of § 63.7741(e)(1); and

(2) You must at all times monitor the 3-hour average pH of the scrubber blowdown using CPMS according to the requirements in § 63.7741(e)(2) or measure and record the pH of the scrubber blowdown once per production cycle using a pH probe and meter according to the requirements in § 63.7741(e)(3).

(h) For one or more automated conveyor and pallet cooling lines and automated shakeout lines at a new iron and steel foundry subject to the VOHAP emissions limit in § 63.7690(a)(10), you must at all times monitor the 3-hour average VOHAP concentration using a CEMS according to the requirements of § 63.7741(g).

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008; 85 FR 56096, Sept. 10, 2020]

§ 63.7741 What are the installation, operation, and maintenance requirements for my monitors?

(a) For each capture system subject to an operating limit in § 63.7690(b)(1), you must install, operate, and maintain each CPMS according to the requirements in paragraphs (a)(1) through (3) of this section.

(1) If you use a flow measurement device to monitor an operating limit parameter for a capture system, you must meet the requirements in paragraphs (a)(1)(i) through (iv) of this section.

(i) Locate the flow sensor and other necessary equipment such as straightening vanes in a position that provides a representative flow and that reduces swirling flow or abnormal velocity distributions due to upstream and downstream disturbances.

(ii) Use a flow sensor with a minimum measurement sensitivity of 2 percent of the flow rate.

(iii) Conduct a flow sensor calibration check at least semiannually.

(iv) At least monthly, visually inspect all components, including all electrical and mechanical connections, for proper functioning.

(2) If you use a pressure measurement device to monitor the operating limit parameter for a capture system, you must meet the requirements in paragraphs (a)(2)(i) through (vi) of this section.

(i) Locate the pressure sensor(s) in or as close as possible to a position that provides a representative measurement of the pressure and that minimizes or eliminates pulsating pressure, vibration, and internal and external corrosion.

(ii) Use a gauge with a minimum measurement sensitivity of 0.5 inch of water or a transducer with a minimum measurement sensitivity of 1 percent of the pressure range.

(iii) Check the pressure tap for pluggage daily. If a ''non-clogging'' pressure tap is used, check for pluggage monthly.

(iv) Using a manometer or equivalent device such as a magnahelic or other pressure indicating transmitter, check gauge and transducer calibration quarterly.

(v) Conduct calibration checks any time the sensor exceeds the manufacturer's specified maximum operating pressure range, or install a new pressure sensor.

(vi) At least monthly, visually inspect all components, including all electrical and mechanical connections, for proper functioning.

(3) Record the results of each inspection, calibration, and validation check.

(b) For each negative pressure baghouse or positive pressure baghouse equipped with a stack that is applied to meet any PM or total metal HAP emissions limitation in this subpart, you must install, operate, and maintain a bag leak detection system according to the requirements in paragraphs (b)(1) through (7) of this section.

(1) The system must be certified by the manufacturer to be capable of detecting emissions of particulate matter at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The bag leak detection system sensor must provide output of relative particulate matter loadings and the owner or operator shall continuously record the output from the bag leak detection system using electronic or other means (*e.g.*, using a strip chart recorder or a data logger).

(3) The system must be equipped with an alarm that will sound when an increase in relative particulate loadings is detected over the alarm set point established in the operation and maintenance plan, and the alarm must be located such that it can be heard by the appropriate plant personnel.

(4) The initial adjustment of the system must, at minimum, consist of establishing the baseline output by adjusting the sensitivity (range) and the averaging period of the device, and establishing the alarm set points and the alarm delay time (if applicable).

(5) Following the initial adjustment, do not adjust the sensitivity or range, averaging period, alarm set point, or alarm delay time without approval from the Administrator. Except, once per quarter, you may adjust the sensitivity of the bag leak detection system to account for seasonable effects including temperature and humidity according to the procedures in the operation and maintenance plan required by §63.7710(b).

(6) For negative pressure, induced air baghouses, and positive pressure baghouses that are discharged to the atmosphere through a stack, the bag leak detector sensor must be installed downstream of the baghouse and upstream of any wet scrubber.

(7) Where multiple detectors are required, the system's instrumentation and alarm may be shared among detectors.

(c) For each wet scrubber subject to the operating limits in §63.7690(b)(2), you must install and maintain CPMS

to measure and record the pressure drop and scrubber water flow rate according to the requirements in paragraphs (c)(1) and (2) of this section.

(1) For each CPMS for pressure drop you must:

(i) Locate the pressure sensor in or as close as possible to a position that provides a representative measurement of the pressure drop and that minimizes or eliminates pulsating pressure, vibration, and internal and external corrosion.

(ii) Use a gauge with a minimum measurement sensitivity of 0.5 inch of water or a transducer with a minimum measurement sensitivity of 1 percent of the pressure range.

(iii) Check the pressure tap for pluggage daily. If a ''non-clogging'' pressure tap is used, check for pluggage monthly.

(iv) Using a manometer or equivalent device such as a magnahelic or other pressure indicating transmitter, check gauge and transducer calibration quarterly.

(v) Conduct calibration checks any time the sensor exceeds the manufacturer's specified maximum operating pressure range, or install a new pressure sensor.

(vi) At least monthly, visually inspect all components, including all electrical and mechanical connections, for proper functioning.

(2) For each CPMS for scrubber liquid flow rate, you must:

(i) Locate the flow sensor and other necessary equipment in a position that provides a representative flow and that reduces swirling flow or abnormal velocity distributions due to upstream and downstream disturbances.

(ii) Use a flow sensor with a minimum measurement sensitivity of 2 percent of the flow rate.

(iii) Conduct a flow sensor calibration check at least semiannually according to the manufacturer's instructions.

(iv) At least monthly, visually inspect all components, including all electrical and mechanical connections, for proper functioning.

(d) For each combustion device subject to the operating limit in §63.7690(b)(3) or (4) or the work practice standard in §63.7700(g)(2)(i), you must install and maintain a CPMS to measure and record the combustion zone temperature according to the requirements in paragraphs (d)(1) through (8) of this section.

(1) Locate the temperature sensor in a position that provides a representative temperature.

(2) For a noncryogenic temperature range, use a temperature sensor with a minimum tolerance of 2.2 °C or 0.75 percent of the temperature value, whichever is larger.

(3) For a cryogenic temperature range, use a temperature sensor with a minimum tolerance of 2.2 °C or 2 percent of the temperature value, whichever is larger.

(4) Shield the temperature sensor system from electromagnetic interference and chemical contaminants.

(5) If you use a chart recorder, it must have a sensitivity in the minor division of at least 20 °F.

(6) Perform an electronic calibration at least semiannually according to the procedures in the manufacturer's owners manual. Following the electronic calibration, conduct a temperature sensor validation check, in which a second or redundant temperature sensor placed nearby the process temperature sensor must yield a reading within 16.7 °C of the process temperature sensor's reading.

(7) Conduct calibration and validation checks any time the sensor exceeds the manufacturer's specified maximum operating temperature range, or install a new temperature sensor.

(8) At least monthly, visually inspect all components, including all electrical and mechanical connections, for proper functioning.

(e) For each wet acid scrubber subject to the operating limits in §63.7690(b)(5), you must:

(1) Install and maintain CPMS to measure and record the scrubbing liquid flow rate according to the requirements in paragraph (c)(2) of this section; and

(2) Install and maintain CPMS to measure and record the pH of the scrubber blowdown according to the requirements in paragraph (e)(2)(i) through (iv) of this section.

(i) Locate the pH sensor in a position that provides a representative measurement of the pH and that minimizes or eliminates internal and external corrosion.

(ii) Use a gauge with a minimum measurement sensitivity of 0.1 pH or a transducer with a minimum measurement sensitivity of 5 percent of the pH range.

(iii) Check gauge calibration quarterly and transducer calibration monthly using a manual pH gauge.

(iv) At least monthly, visually inspect all components, including all electrical and mechanical connections, for proper functioning.

(3) As an alternative to the CPMS required in paragraph (e)(2) of this section, you may use a pH probe to extract a sample for analysis by a pH meter that meets the requirements in paragraphs (e)(3)(i) through (iii) of this section.

(i) The pH meter must have a range of at least 1 to 5 or more;

(ii) The pH meter must have an accuracy of ±0.1; and

(iii) The pH meter must have a resolution of at least 0.1 pH.

(f) You must operate each CPMS used to meet the requirements of this subpart according to the requirements specified in paragraphs (f)(1) through (3) of this section.

(1) Each CPMS must complete a minimum of one cycle of operation for each successive 15-minute period. You must have a minimum of three of the required four data points to constitute a valid hour of data.

(2) Each CPMS must have valid hourly data for 100 percent of every averaging period.

(3) Each CPMS must determine and record the hourly average of all recorded readings and the 3-hour average of all recorded readings.

(g) For each automated conveyor and pallet cooling line and automated shakeout line at a new iron and steel foundry subject to the VOHAP emissions limit in § 63.7690(a)(10), you must install, operate, and maintain a CEMS to measure and record the concentration of VOHAP emissions according to the requirements in paragraphs (g)(1) through (3) of this section.

(1) You must install, operate, and maintain each CEMS according to Performance Specification 8 in 40 CFR part 60, appendix B.

(2) You must conduct a performance evaluation of each CEMS according to the requirements of § 63.8 and Performance Specification 8 in 40 CFR part 60, appendix B.

(3) You must operate each CEMS according to the requirements specified in paragraph (g)(3)(i) through (iv) of this section.

(i) As specified in § 63.8(c)(4)(ii), each CEMS must complete a minimum of one cycle of operation (sampling, analyzing, and data recording) for each successive 15-minute period.

(ii) You must reduce CEMS data as specified in § 63.8(g)(2).

(iii) Each CEMS must determine and record the 3-hour average emissions using all the hourly averages collected for periods during which the CEMS is not out-of-control.

(iv) Record the results of each inspection, calibration, and validation check.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008; 85 FR 56096, Sept. 10, 2020]

§ 63.7742 How do I monitor and collect data to demonstrate continuous compliance?

(a) Except for monitoring malfunctions, associated repairs, and required quality assurance or control activities (including as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) any time a source of emissions is operating.

(b) You may not use data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities in data averages and calculations used to report emissions or operating levels or to fulfill a minimum data availability requirement, if applicable. You must use all the data collected during all other periods in assessing compliance.

(c) A monitoring malfunction is any sudden, infrequent, not reasonably preventable failure of the monitoring system to provide valid data. Monitoring failures that are caused in part by poor

maintenance or careless operation are not malfunctions.

§ 63.7743 How do I demonstrate continuous compliance with the emissions limitations that apply to me?

(a) You must demonstrate continuous compliance by meeting the applicable conditions in paragraphs (a)(1) through (12) of this section. When alternative emissions limitations are provided for a given emissions source, you must comply with the alternative emissions limitation most recently selected as your compliance alternative.

(1) For each electric arc metal melting furnace, electric induction metal melting furnace, or scrap preheater at an existing iron and steel foundry,

(i) Maintaining the average PM concentration in the exhaust stream at or below 0.005 gr/dscf; or

(ii) Maintaining the average total metal HAP concentration in the exhaust stream at or below 0.0004 gr/dscf.

(2) For each cupola metal melting furnace at an existing iron and steel foundry,

(i) Maintaining the average PM concentration in the exhaust stream at or below 0.006 gr/dscf; or

(ii) Maintaining the average total metal HAP concentration in the exhaust stream at or below 0.0005 gr/dscf; or

(iii) Maintaining the average PM mass emissions rate at or below 0.10 pound of PM per ton (lb/ton) of metal charged; or

(iv) Maintaining the average total metal HAP mass emissions rate at or below 0.008 pound of total metal HAP per ton (lb/ton) of metal charged.

(3) For each cupola metal melting furnace or electric arc metal melting furnace at new iron and steel foundry,

(i) Maintaining the average PM concentration in the exhaust stream at or below 0.002 gr/dscf; or

(ii) Maintaining the average total metal HAP concentration in the exhaust stream at or below 0.0002 gr/dscf.

(4) For each electric induction metal melting furnace or scrap preheater at a new iron and steel foundry,

(i) Maintaining the average PM concentration in the exhaust stream at or below 0.001 gr/dscf; or

(ii) Maintaining the average total metal HAP concentration in the exhaust stream at or below 0.00008 gr/dscf.

(5) For each pouring station at an existing iron and steel foundry,

(i) Maintaining the average PM concentration in the exhaust stream at or below 0.010 gr/dscf; or

(ii) Maintaining the average total metal HAP concentration in the exhaust stream at or below 0.0008 gr/dscf.

(6) For each pouring area or pouring station at a new iron and steel foundry,

(i) Maintaining the average PM concentration in the exhaust stream at or below 0.002 gr/dscf; or

(ii) Maintaining the average total metal HAP concentration in the exhaust stream at or below 0.0002 gr/dscf.

(7) For each building or structure housing any iron and steel foundry emissions source at the iron and steel foundry, maintaining the opacity of any fugitive emissions from foundry operations discharged to the atmosphere at or below 20 percent opacity (6-minute average), except for one 6-minute average per hour that does not exceed 27 percent opacity.

(8) For each cupola metal melting furnace at a new or existing iron and steel foundry, maintaining the average VOHAP concentration in the exhaust stream at or below 20 ppmv corrected to 10 percent oxygen.

(9) For each scrap preheater at an existing new iron and steel foundry that does not comply with the work practice standard in § 63.7700(e)(1) or (2) and for each scrap preheater at a new iron and steel foundry that does not comply with the work practice standard in § 63.7700(f), maintaining the average VOHAP concentration in the exhaust stream at or below 20 ppmv.

(10) For one or more automated conveyor and pallet cooling lines or automated shakeout lines that use a sand mold system at a new iron and steel foundry,

(i) Maintaining the 3-hour flow-weighted average VOHAP concentration in the exhaust stream at or below 20 ppmv;

(ii) Inspecting and maintaining each CEMS according to the requirements of § 63.7741(g) and recording all information needed to document conformance with these requirements; and

(iii) Collecting and reducing monitoring data for according to the requirements of § 63.7741(g) and recording all information needed to document conformance with these requirements.

(11) For each TEA cold box mold or core making line at a new or existing iron and steel foundry, maintaining a 99 percent reduction in the VOHAP concentration in the exhaust stream or maintaining the average VOHAP concentration in the exhaust stream at or below 1 ppmv.

(12) Conducting subsequent performance tests at least every 5 years for each emissions source subject to an emissions limit for PM, total metal HAP, VOHAP, or TEA in § 63.7690(a) and subsequent performance tests at least every 6 months for each building or structure subject to the opacity limit in § 63.7690(a)(7).

(b) You must demonstrate continuous compliance for each capture system subject to an operating limit in § 63.7690(b)(1) by meeting the requirements in paragraphs (b)(1) and (2) of this section.

(1) Operating the capture system at or above the lowest values or settings established for the operating limits in your operation and maintenance plan; and

(2) Monitoring the capture system according to the requirements in § 63.7740(a) and collecting, reducing, and recording the monitoring data for each of the operating limit parameters according to the applicable requirements in this subpart.

(c) For each baghouse,

(1) Inspecting and maintaining each baghouse according to the requirements of § 63.7740(c)(1) through (8) and recording all information needed to document conformance with these requirements; and

(2) If the baghouse is equipped with a bag leak detection system, maintaining records of the times the bag leak detection system sounded, and for each valid alarm, the time you initiated corrective action, the corrective action taken, and the date on which corrective action was completed.

(d) For each wet scrubber that is subject to the operating limits in § 63.7690(b)(2), you must demonstrate continuous compliance by:

(1) Maintaining the 3-hour average pressure drop and 3-hour average scrubber water flow rate at levels no lower than those established during the initial or subsequent performance test;

(2) Inspecting and maintaining each CPMS according to the requirements of § 63.7741(c) and recording all information needed to document conformance with these requirements; and

(3) Collecting and reducing monitoring data for pressure drop and scrubber water flow rate according to the requirements of § 63.7741(f) and recording all information needed to document conformance with these requirements.

(e) For each combustion device that is subject to the operating limit in § 63.7690(b)(3), you must demonstrate continuous compliance by:

(1) Maintaining the 15-minute average combustion zone temperature at a level no lower than 1,300 °F;

(2) Inspecting and maintaining each CPMS according to the requirements of § 63.7741(d) and recording all information needed to document conformance with these requirements; and

(3) Collecting and reducing monitoring data for combustion zone temperature according to the requirements of § 63.7741(f) and recording all information needed to document conformance with these requirements.

(f) For each combustion device that is subject to the operating limit in § 63.7690(b)(4), you must demonstrate continuous compliance by:

(1) Maintaining the 3-hour average combustion zone temperature at a level no lower that established during the initial or subsequent performance test;

(2) Inspecting and maintaining each CPMS according to the requirements of § 63.7741(d) and recording all information needed to document conformance with these requirements; and

(3) Collecting and reducing monitoring data for combustion zone temperature according to the requirements of § 63.7741(f) and recording all information needed to document conformance with these requirements.

(g) For each acid wet scrubber subject to the operating limits in § 63.7690(b)(5), you must demonstrate continuous compliance by:

(1) Maintaining the 3-hour average scrubbing liquid flow rate at a level no lower than the level established during the initial or subsequent performance test;

(2) Maintaining the 3-hour average pH of the scrubber blowdown at a level no higher than 4.5 (if measured by a CPMS) or maintaining the pH level of the scrubber blowdown during each production shift no higher than 4.5;

(3) Inspecting and maintaining each CPMS according to the requirements of §63.7741(e) and recording all information needed to document conformance with these requirements; and

(4) Collecting and reducing monitoring data for scrubbing liquid flow rate and scrubber blowdown pH according to the requirements of §63.7741(f) and recording all information needed to document conformance with these requirements. If the pH level of the scrubber blowdown is measured by a probe and meter, you must demonstrate continuous compliance by maintaining records that document the date, time, and results of each sample taken for each production shift.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7222, Feb. 7, 2008]

§63.7744 How do I demonstrate continuous compliance with the work practice standards that apply to me?

(a) You must maintain records that document continuous compliance with the certification requirements in §63.7700(b) or with the procedures in your scrap selection and inspection plan required in §63.7700(c). Your records documenting compliance with the scrap selection and inspection plan must include a copy (kept onsite) of the procedures used by the scrap supplier for either removing accessible mercury switches or for purchasing automobile bodies that have had mercury switches removed, as applicable.

(b) You must keep records of the chemical composition of all catalyst binder formulations applied in each furan warm box mold or core making line at a new or existing iron and steel foundry to demonstrate continuous compliance with the requirements in §63.7700(d).

(c) For a scrap preheater at an existing iron and steel foundry, you must operate and maintain each gas-fired preheater such that the flame directly contacts the scrap charged to demonstrate continuous compliance with the requirement §63.7700(e)(1). If you choose to meet the work practice standard in §63.7700(e)(2), you must keep records to document that the scrap preheater charges only material that is subject to and in compliance with the scrap certification requirements in §63.7700(b).

(d) For a scrap preheater at a new iron and steel foundry, you must keep records to document that each scrap preheater charges only material that is subject to and in compliance with the scrap certification requirements in §63.7700(b) to demonstrate continuous compliance with the requirement in §63.7700(f).

(e) For each cupola furnace at a new or existing iron and steel foundry in off blast, you must keep daily records to document the relevant times of off blast, in conjunction with the requirements to monitor and record the combustion zone temperature for the cupola's thermal combustion control device as required in §§63.7740(e) and 63.7741(d), to demonstrate continuous compliance with the requirements in §63.7700(g). The relevant times of off blast include: The time blast air is started to begin the coke bed burn-in, the time the cupola afterburner or other thermal combustion device is lit, and the time metal production starts during cupola startup; the time when metal production ends, the time slag removal is completed, and the time the afterburner or other thermal combustion device is turned off during cupola shutdown; and the times idling starts and stops.

[69 FR 21923, Apr. 22, 2004, as amended at 85 FR 56096, Sept. 10, 2020]

§63.7745 How do I demonstrate continuous compliance with the operation and maintenance requirements that apply to me?

(a) For each capture system and control device for an emissions source subject to an emissions limit in §63.7690(a), you must demonstrate continuous compliance with the operation and

maintenance requirements of § 63.7710 by:

(1) Making monthly inspections of capture systems and initiating corrective action according to § 63.7710(b)(1) and recording all information needed to document conformance with these requirements;

(2) Performing preventative maintenance for each control device according to the preventive maintenance plan required by § 63.7710(b)(3) and recording all information needed to document conformance with these requirements;

(3) Operating and maintaining each bag leak detection system according to the site-specific monitoring plan required by § 63.7710(b)(4) and recording all information needed to demonstrate conformance with these requirements;

(4) Initiating and completing corrective action for a bag leak detection system alarm according to the corrective action plan required by § 63.7710(b)(5) and recording all information needed to document conformance with these requirements; and

(5) Igniting gases from mold vents according to the procedures in the plan required by § 63.7710(b)(6). (Any instance where you fail to follow the procedures is a deviation that must be included in your semiannual compliance report.)

(b) You must maintain a current copy of the operation and maintenance plans required by § 63.7710(b) onsite and available for inspection upon request. You must keep the plans for the life of the iron and steel foundry or until the iron and steel foundry is no longer subject to the requirements of this subpart.

§ 63.7746 What other requirements must I meet to demonstrate continuous compliance?

(a) *Deviations.* You must report each instance in which you did not meet each emissions limitation in § 63.7690 (including each operating limit) that applies to you. This requirement includes periods of startup, shutdown, and malfunction. You also must report each instance in which you did not meet each work practice standard in § 63.7700 and each operation and maintenance requirement of § 63.7710 that applies to you. These instances are deviations from the emissions limitations, work practice standards, and operation and maintenance requirements in this subpart. These deviations must be reported according to the requirements of § 63.7751.

(b) [Reserved]

[69 FR 21923, Apr. 22, 2004, as amended at 71 FR 20468, Apr. 20, 2006; 85 FR 56097, Sept. 10, 2020]

§ 63.7747 How do I apply for alternative monitoring requirements for a continuous emissions monitoring system?

(a) You may request an alternative monitoring method to demonstrate compliance with the VOHAP emissions limits in § 63.7690(a)(10) for automated pallet cooling lines or automated shakeout lines at a new iron and steel foundry according to the procedures in this section.

(b) You can request approval to use an alternative monitoring method in the notification of construction or reconstruction for new sources, or at any time.

(c) You must submit a monitoring plan that includes a description of the control technique or pollution prevention technique, a description of the continuous monitoring system or method including appropriate operating parameters that will be monitored, test results demonstrating compliance with the emissions limit, operating limit(s) (if applicable) determined according to the test results, and the frequency of measuring and recording to establish continuous compliance. If applicable, you must also include operation and maintenance requirements for the monitors.

(d) The monitoring plan is subject to approval by the Administrator. Use of the alternative monitoring method must not begin until approval is granted by the Administrator.

NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.7750 What notifications must I submit and when?

(a) You must submit all of the notifications required by §§ 63.6(h)(4) and (5), 63.7(b) and (c); 63.8(e); 63.8(f)(4) and (6); 63.9(b) through (h) that apply to you by the specified dates.

(b) As specified in § 63.9(b)(2), if you start up your iron and steel foundry before April 22, 2004, you must submit your initial notification no later than August 20, 2004, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) If you start up your new iron and steel foundry on or after April 22, 2004, you must submit your initial notification no later than 120 calendar days after you become subject to this subpart.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required by § 63.7(b)(1).

(e) If you are required to conduct a performance test or other initial compliance demonstration, you must submit a notification of compliance status according to the requirements of § 63.9(h)(2)(ii). For opacity performance tests, the notification of compliance status may be submitted with the semiannual compliance report in § 63.7751(a) and (b) or the semiannual part 70 monitoring report in § 63.7551(d).

(1) For each initial compliance demonstration that does not include a performance test, you must submit the notification of compliance status before the close of business on the 30th calendar day following completion of the initial compliance demonstration.

(2) For each initial compliance demonstration that does include a performance test, you must submit the notification of compliance status, including the performance test results, before the close of business on the 60th calendar day following the completion of the performance test according to the requirement specified in § 63.10(d)(2).

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7222, Feb. 7, 2008; 85 FR 73913, Nov. 19, 2020]

§ 63.7751 What reports must I submit and when?

(a) *Compliance report due dates.* Unless the Administrator has approved a different schedule, you must submit a semiannual compliance report to your permitting authority according to the requirements specified in paragraphs (a)(1) through (5) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your iron and steel foundry by § 63.7683 and ending on June 30 or December 31, whichever date comes first after the compliance date that is specified for your iron and steel foundry.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after your first compliance report is due.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after the end of the semiannual reporting period.

(5) For each iron and steel foundry that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of the dates specified in paragraphs (a)(1) through (4) of this section.

(b) *Compliance report contents.* Each compliance report must include the information specified in paragraphs (b)(1) through (3) of this section and, as applicable, paragraphs (b)(4) through (8) of this section.

(1) Company name and address.

(2) Statement by a responsible official, with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) [Reserved]

(5) If there were no deviations from any emissions limitations (including operating limit), work practice standards, or operation and maintenance requirements, a statement that there were no deviations from the emissions limitations, work practice standards,

or operation and maintenance requirements during the reporting period.

(6) If there were no periods during which a continuous monitoring system (including a CPMS or CEMS) was inoperable or out-of-control as specified by §63.8(c)(7), a statement that there were no periods during which the CPMS was inoperable or out-of-control during the reporting period.

(7) For each affected source or equipment for which there was a deviation from an emissions limitation (including an operating limit, work practice standard, or operation and maintenance requirement) that occurs at an iron and steel foundry during the reporting period, the compliance report must contain the information specified in paragraphs (b)(7)(i) through (iii) of this section. The requirement in this paragraph (b)(7) includes periods of startup, shutdown, and malfunction.

(i) A list of the affected source or equipment and the total operating time of each emissions source during the reporting period.

(ii) For each deviation from an emissions limitation (including an operating limit, work practice standard, or operation and maintenance requirement) that occurs at an iron and steel foundry during the reporting period, report:

(A) The date, start time, duration (in hours), and cause of each deviation (characterized as either startup, shutdown, control equipment problem, process problem, other known cause, or unknown cause, as applicable) and the corrective action taken; and

(B) An estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(iii) A summary of the total duration (in hours) of the deviations that occurred during the reporting period by cause (characterized as startup, shutdown, control equipment problems, process problems, other known causes, and unknown causes) and the cumulative duration of deviations during the reporting period across all causes both in hours and as a percent of the total source operating time during the reporting period.

(8) For each continuous monitoring system (including a CPMS or CEMS) used to comply with the emissions limitation or work practice standard in this subpart that was inoperable or out-of-control during any portion of the reporting period, you must include the information specified in paragraphs (b)(8)(i) through (vi) of this section. The requirement in this paragraph (b)(8) includes periods of startup, shutdown, and malfunction.

(i) A brief description of the continuous monitoring system, including manufacturer and model number.

(ii) The date of the latest continuous monitoring system certification or audit.

(iii) A brief description and the total operating time of the affected source or equipment that is monitored by the continuous monitoring system during the reporting period.

(iv) A description of any changes in continuous monitoring systems, processes, or controls since the last reporting period.

(v) For each period for which the continuous monitoring system was inoperable or out-of-control during the reporting period, report:

(A) The date, start time, and duration (in hours) of the deviation;

(B) The type of deviation (inoperable or out-of-control); and

(C) The cause of deviation (characterized as monitoring system malfunctions, non-monitoring equipment malfunctions, quality assurance/quality control calibrations, other known causes, and unknown causes, as applicable) and the corrective action taken.

(vi) A summary of the total duration (in hours) of the deviations that occurred during the reporting period by cause (characterized as monitoring system malfunctions, non-monitoring equipment malfunctions, quality assurance/quality control calibrations, other known causes, and unknown causes) and the cumulative duration of deviations during the reporting period across all causes both in hours and as a percent of the total source operating time during the reporting period.

(c) [Reserved]

(d) *Part 70 monitoring report.* If you have obtained a title V operating permit for an iron and steel foundry pursuant to 40 CFR part 70 or 40 CFR part 71, you must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If you submit a compliance report for an iron and steel foundry along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all the required information concerning deviations from any emissions limitation or operation and maintenance requirement in this subpart, submission of the compliance report satisfies any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report does not otherwise affect any obligation you may have to report deviations from permit requirements for an iron and steel foundry to your permitting authority.

(e) *Compliance report submission requirements.* Prior to March 9, 2021, you must submit semiannual compliance reports to the Administrator as specified in §63.13. Beginning on March 9, 2021, you must submit all subsequent semiannual compliance reports to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). The EPA will make all the information submitted through CEDRI available to the public without further notice to you. Do not use CEDRI to submit information you claim as confidential business information (CBI). Anything submitted using CEDRI cannot later be claimed to be CBI. You must use the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/cedri*) for this subpart. The date report templates become available will be listed on the CEDRI website. The report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. If you claim some of the information required to be submitted via CEDRI is CBI, submit a complete report, including information claimed to be CBI, to the EPA. The report must be generated using the appropriate form on the CEDRI website or an alternate electronic file consistent with the extensible markup language (XML) schema listed on the CEDRI website. Although we do not expect persons to assert a claim of CBI, if persons wish to assert a CBI, submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph (e). All CBI claims must be asserted at the time of submission. Furthermore, under CAA section 114(c) emissions data is not entitled to confidential treatment and requires EPA to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

(f) *Performance test results submission requirements.* Within 60 days after the date of completing each performance test required by this subpart, you must submit the results of the performance test following the procedures specified in paragraphs (f)(1) through (3) of this section.

(1) *Data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test to the EPA via the CEDRI, which can be accessed through the EPA's CDX (*https://cdx.epa.gov/*). The data must be submitted in a file format generated through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on the EPA's ERT website.

(2) *Data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT website at the*

time of the test. The results of the performance test must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *Confidential business information*. The EPA will make all the information submitted through CEDRI available to the public without further notice to you. Do not use CEDRI to submit information you claim as CBI. Anything submitted using CEDRI cannot later be claimed to be CBI. Although we do not expect persons to assert a claim of CBI, if you claim some of the information submitted under paragraph (f)(1) or (2) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to the EPA. The file must be generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described in paragraph (f)(1) of this section. All CBI claims must be asserted at the time of submission. Furthermore, under CAA section 114(c) emissions data is not entitled to confidential treatment and requires EPA to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

(g) *Performance evaluation results submission requirements*. Within 60 days after the date of completing each continuous monitoring system (CMS) performance evaluation (as defined in §63.2), you must submit the results of the performance evaluation following the procedures specified in paragraphs (g)(1) through (3) of this section.

(1) *Performance evaluations of CMS measuring relative accuracy test audit (RATA) pollutants that are supported by the EPA's ERT as listed on the EPA's ERT website at the time of the evaluation*. Submit the results of the performance evaluation to the EPA via CEDRI, which can be accessed through the EPA's CDX. The data must be submitted in a file format generated through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on the EPA's ERT website.

(2) *Performance evaluations of CMS measuring RATA pollutants that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the evaluation*. The results of the performance evaluation must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *Confidential business information*. The EPA will make all the information submitted through CEDRI available to the public without further notice to you. Do not use CEDRI to submit information you claim as CBI. Anything submitted using CEDRI cannot later be claimed to be CBI. Although we do not expect persons to assert a claim of CBI, if you claim some of the information submitted under paragraph (g)(1) or (2) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to the EPA. The file must be generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described in paragraph (g)(1) of this section. All CBI claims must be asserted at the time of submission. Furthermore, under CAA section 114(c) emissions data is not entitled to confidential treatment and requires EPA to

make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

(h) *Claims of EPA system outage.* If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement. To assert a claim of EPA system outage, you must meet the requirements outlined in paragraphs (h)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either the EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning five business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(i) *Claims of force majeure.* If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of force majeure for failure to timely comply with the reporting requirement. To assert a claim of force majeure, you must meet the requirements outlined in paragraphs (i)(1) through (5) of this section.

(1) You may submit a claim if a force majeure event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For the purposes of this section, a force majeure event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (*e.g.*, hurricanes, earthquakes, or floods), acts of war or terrorism, or equipment failure or safety hazard beyond the control of the affected facility (*e.g.*, large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the force majeure event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the force majeure event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of force majeure and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the force majeure event occurs.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7222, Feb. 7, 2008; 85 FR 56097, Sept. 10, 2020]

§ 63.7752 What records must I keep?

(a) You must keep the records specified in paragraphs (a)(1) through (4) of this section:

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any initial notification or notification of compliance status that you submitted, according to the requirements of § 63.10(b)(2)(xiv).

(2) Records of required maintenance performed on the air pollution control and monitoring equipment as required by § 63.10(b)(2)(iii).

(3) Records of performance tests and performance evaluations as required by § 63.10(b)(2)(viii).

(4) Records of the annual quantity of each chemical binder or coating material used to coat or make molds and cores, the Material Data Safety Sheet or other documentation that provides the chemical composition of each component, and the annual quantity of HAP used in these chemical binder or coating materials at the foundry as calculated from the recorded quantities and chemical compositions (from Material Data Safety Sheets or other documentation).

(b) You must keep the following records for each CEMS.

(1) Records described in § 63.10(b)(2)(vi) through (xi).

(2) Records of the site-specific performance evaluation test plan required under § 63.8(d)(2) for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan is revised, you shall keep previous (*i.e.*, superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action should be included in the plan as required under § 63.8(d)(2)(vi).

(3) Request for alternatives to relative accuracy tests for CEMS as required in § 63.8(f)(6)(i).

(4) Records of the date and time that each deviation started and stopped.

(c) You must keep the records required by §§ 63.7743, 63.7744, and 63.7745 to show continuous compliance with each emissions limitation, work practice standard, and operation and maintenance requirement that applies to you.

(d) You must keep the following records for each failure to meet an emissions limitation (including operating limit), work practice standard, or operation and maintenance requirement in this subpart.

(1) Date, start time, and duration of each failure.

(2) List of the affected sources or equipment for each failure, an estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(3) Actions taken to minimize emissions in accordance with § 63.7710(a), and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(e) Any records required to be maintained by this part that are submitted electronically via the EPA's CEDRI may be maintained in electronic format. This ability to maintain electronic copies does not affect the requirement for facilities to make records, data, and reports available upon request to a delegated air agency or the EPA as part of an on-site compliance evaluation.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7222, Feb. 7, 2008; 85 FR 56099, Sept. 10, 2020]

§ 63.7753 In what form and for how long must I keep my records?

(a) You must keep your records in a form suitable and readily available for expeditious review, according to the requirements of § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record onsite for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record according to the requirements in § 63.10(b)(1). You can keep the records for the previous 3 years offsite.

OTHER REQUIREMENTS AND INFORMATION

§ 63.7760 What parts of the General Provisions apply to me?

Table 1 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.15 apply to you.

§ 63.7761 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. Environmental Protection Agency (EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if implementation and enforcement of this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under 40 CFR part 63, subpart E, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities that cannot be delegated to state, local, or tribal agencies are specified in paragraphs (c)(1) through (5) of this section.

(1) Approval of alternatives to nonopacity emissions limitations in § 63.7690 and work practice standards in § 63.7700 under § 63.6(g).

(2) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(5) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

[69 FR 21923, Apr. 22, 2004, as amended at 85 FR 56099, Sept. 10, 2020]

DEFINITIONS

§ 63.7765 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act (CAA), in § 63.2, and in this section.

Automated conveyor and pallet cooling line means any dedicated conveyor line or area used for cooling molds received from pouring stations.

Automated shakeout line means any mechanical process unit designed for and dedicated to separating a casting from a mold. These mechanical processes include, but are not limited to, shaker decks, rotary separators, and high-frequency vibration units. Automated shakeout lines do not include manual processes for separating a casting from a mold, such as personnel using a hammer, chisel, pick ax, sledge hammer, or jackhammer.

Bag leak detection system means a system that is capable of continuously monitoring relative particulate matter (dust) loadings in the exhaust of a baghouse to detect bag leaks and other upset conditions. A bag leak detection system includes, but is not limited to, an instrument that operates on triboelectric, electrodynamic, light scattering, light transmittance, or other effect to continuously monitor relative particulate matter loadings.

Binder chemical means a component of a system of chemicals used to bind sand together into molds, mold sections, and cores through chemical reaction as opposed to pressure.

Capture system means the collection of components used to capture gases and fumes released from one or more emissions points and then convey the captured gas stream to a control device or to the atmosphere. A capture system may include, but is not limited to, the following components as applicable to a given capture system design: duct intake devices, hoods, enclosures, ductwork, dampers, manifolds, plenums, and fans.

Cold box mold or core making line means a mold or core making line in which the formed aggregate is hardened by catalysis with a gas.

Combustion device means an afterburner, thermal incinerator, or scrap preheater.

Conveyance means the system of equipment that is designed to capture pollutants at the source, convey them through ductwork, and exhaust them using forced ventilation. A conveyance may, but does not necessarily include, control equipment designed to reduce emissions of the pollutants. Emissions that are released through windows, vents, or other general building ventilation or exhaust systems are not considered to be discharged through a conveyance.

Cooling means the process of molten metal solidification within the mold and subsequent temperature reduction prior to shakeout.

Cupola means a vertical cylindrical shaft furnace that uses coke and forms of iron and steel such as scrap and foundry returns as the primary charge components and melts the iron and steel through combustion of the coke by a forced upward flow of heated air.

Cupola shutdown means the period beginning when the last of the molten metal is tapped from the cupola's primary tap hole and ending when the cupola is cooled and the cupola is either banked or the bottom contents are removed (''bottom drop''). *Cupola shutdown* includes the following steps: slag and residual metal removal from secondary tap; cupola cooling; and cupola banking or bottom drop.

Cupola startup means the commencement of activities needed to take a banked cupola or a cupola that has had the bottom dropped back into melt production. *Cupola startup* includes the following steps: refractory curing, if needed; cupola bed preparation (during which the sand bed is preheated), if needed; coke bed preparation (during which coke is added to the cupola and lit); and initial metallics charging.

Deviation means any instance in which an affected source or an owner or operator of such an affected source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emissions limitation (including operating imits), work practice standard, or operation and maintenance requirement; or

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any iron and steel foundry required to obtain such a permit.

(3) A deviation is not always a violation. The determination of whether a deviation constitutes a violation of the standard is up to the discretion of the entity responsible for enforcement of the standards.

Electric arc furnace means a vessel in which forms of iron and steel such as scrap and foundry returns are melted through resistance heating by an electric current flowing through the arcs formed between the electrodes and the surface of the metal and also flowing through the metal between the arc paths.

Electric induction furnace means a vessel in which forms of iron and steel such as scrap and foundry returns are melted though resistance heating by an electric current that is induced in the metal by passing an alternating current through a coil surrounding the metal charge or surrounding a pool of molten metal at the bottom of the vessel.

Emissions limitation means any emissions limit or operating limit.

Exhaust stream means gases emitted from a process through a conveyance as defined in this subpart.

Free organic liquids means material that fails the paint filter test by EPA Method 9095A (incorporated by reference—see § 63.14). That is, if any portion of the material passes through and drops from the filter within the 5-minute test period, the material contains free liquids.

Fresh acid solution means a sulfuric acid solution used for the control of triethylamine emissions that has a pH of 2.0 or less.

Fugitive emissions means any pollutant released to the atmosphere that is not discharged through a *conveyance* as defined in this subpart.

Furan warm box mold or core making line means a mold or core making line in which the binder chemical system used is that system commonly designated as a furan warm box system by the foundry industry.

Hazardous air pollutant means any substance on the list originally established in 112(b)(1) of the CAA and subsequently amended as published in the *Code of Federal Regulations*.

Iron and steel foundry means a facility or portion of a facility that melts scrap, ingot, and/or other forms of iron and/or steel and pours the resulting molten metal into molds to produce final or near final shape products for introduction into commerce. Research and development facilities and operations that only produce non-commercial castings are not included in this definition.

Metal melting furnace means a cupola, electric arc furnace, or electric induction furnace that converts scrap, foundry returns, and/or other solid forms of iron and/or steel to a liquid state. This definition does not include a holding furnace, an argon oxygen decarburization vessel, or ladle that receives molten metal from a metal melting furnace, to which metal ingots or other material may be added to adjust the metal chemistry.

Mold or core making line means the collection of equipment that is used to mix an aggregate of sand and binder chemicals, form the aggregate into final shape, and harden the formed aggregate. This definition does not include a line for making green sand molds or cores.

Mold vent means an intentional opening in a mold through which gases containing pyrolysis products of organic mold and core constituents produced by contact with or proximity to molten metal normally escape the mold during and after metal pouring.

Off blast means those periods of cupola operation when the cupola is not actively being used to produce molten metal. *Off blast* conditions include cupola startup and cupola shutdown. *Off blast* conditions also include idling conditions when the blast air is turned off or down to the point that the cupola does not produce additional molten metal.

On blast means those periods of cupola operation when combustion (blast) air is introduced to the cupola furnace and the furnace is capable of producing molten metal. On blast conditions are characterized by both blast air introduction and molten metal production.

Pouring area means an area, generally associated with floor and pit molding operations, in which molten metal is brought to each individual mold. Pouring areas include all pouring operations that do not meet the definition of a pouring station.

Pouring station means the fixed location to which molds are brought in a continuous or semicontinuous manner to receive molten metal, after which the molds are moved to a cooling area.

Responsible official means responsible official as defined in § 63.2.

Scrap preheater means a vessel or other piece of equipment in which metal scrap that is to be used as melting furnace feed is heated to a temperature high enough to eliminate volatile impurities or other tramp materials by direct flame heating or similar means of heating. Scrap dryers, which solely remove moisture from metal scrap, are not considered to be scrap preheaters for purposes of this subpart.

Scrubber blowdown means liquor or slurry discharged from a wet scrubber that is either removed as a waste stream or processed to remove impurities or adjust its composition or pH before being returned to the scrubber.

Total metal HAP means, for the purposes of this subpart, the sum of the concentrations of antimony, arsenic, beryllium, cadmium, chromium, cobalt, lead, manganese, mercury, nickel, and selenium as measured by EPA Method 29 (40 CFR part 60, appendix A). Only the measured concentration of the listed analytes that are present at concentrations exceeding one-half the quantitation limit of the analytical method are to be used in the sum. If any of the analytes are not detected or are detected at concentrations less than one-half the quantitation limit of the analytical method, the concentration of those analytes will be assumed to be zero for the purposes of calculating the total metal HAP for this subpart.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the CAA.

[69 FR 21923, Apr. 22, 2004, as amended at 70 FR 29404, May 20, 2005; 73 FR 7222, Feb. 7, 2008; 85 FR 56099, Sept. 10, 2020]

TABLE 1 TO SUBPART EEEEE OF PART 63— APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART

TABLE 1 TO SUBPART EEEEE OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART

[As stated in § 63.7760, you must meet each requirement in the following table that applies to you]

Citation	Subject	Applies to this subpart?	Explanation
63.1	Applicability	Yes.	
63.2	Definitions	Yes.	
63.3	Units and abbreviations	Yes.	
63.4	Prohibited activities	Yes.	
63.5	Construction/reconstruction	Yes.	
63.6(a) through (d)	Compliance applicability and dates	Yes.	
63.6(e)	Operating and maintenance requirements.	No	This subpart specifies operating and maintenance requirements.
63.6(f)(1)	Applicability of non-opacity emission standards.	No	This subpart specifies applicability of non-opacity emission standards.
63.6(f)(2) through (3)	Methods and finding of compliance with non-opacity emission standards.	Yes.	
63.6(g)	Use of an alternative nonopacity emission standard.	Yes.	
63.6(h)(1)	Applicability of opacity and visible emissions standards.	No	This subpart specifies applicability of opacity and visible emission standards.
63.6(h)(2) through (9)	Methods and other requirements for opacity and visible emissions standards.	Yes.	
63.6(i) through (j)	Compliance extension and Presidential compliance exemption.	Yes.	
63.7(a)(1) through (2)	Applicability and performance test dates.	No	This subpart specifies applicability and performance test dates.
63.7(a)(3) through (4)	Administrators rights to require a performance test and force majeure provisions.	Yes.	
63.7(b) through (d)	Notification of performance test, quality assurance program, and testing facilities.	Yes.	
63.7(e)(1)	Performance test conditions	No	This subpart specifies performance test conditions.
63.7(e)(2) through (4), (f) through (h).	Other performance testing requirements.	Yes.	
63.8(a)(1) through (3), (b), (c)(1)(ii), (c)(2) through (3), (c)(6) through (8), (d)(1) through (2).	Monitoring requirements	Yes.	
63.8(a)(4)	Additional monitoring requirements for control devices in § 63.11.	No	This subpart does not require flares.
63.8(c)(1)(i), (c)(1)(iii)	Operation and maintenance of continuous monitoring systems.	No	Not necessary in light of other requirements of § 63.8 that apply.
63.8(c)(4)	CMS requirements	No	This subpart specifies requirements for operation of CMS and CEMS.
63.8(c)(5)	Continuous opacity monitoring system (COMS) Minimum Procedures.	No	This subpart does not require COMS.
63.8(d)(3)	Quality control program	No	This subpart specifies records that must be kept associated with site-specific performance evaluation test plan.
63.8(e), (f)(1) through (6), (g)(1) through (4).	Performance evaluations and alternative monitoring.	Yes	This subpart specifies requirements for alternative monitoring systems.
63.8(g)(5)	Data reduction	No	This subpart specifies data reduction requirements.
63.9	Notification requirements	Yes	Except: for opacity performance tests, this subpart allows the notification of compliance status to be submitted with the semiannual compliance report or the semiannual part 70 of this chapter monitoring report.

TABLE 1 TO SUBPART EEEEE OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART—Continued

[As stated in § 63.7760, you must meet each requirement in the following table that applies to you]

Citation	Subject	Applies to this subpart?	Explanation
63.10(a),(b)(1), (b)(2)(iii) and (vi) through (xiv), (b)(3), (c)(1) through (6), (c)(9) through (14), (d)(1) through (4), (e)(1) through (2), (f).	Recordkeeping and reporting requirements.	Yes	Additional records for CMS in § 63.10(c)(1)-(6), (9)-(15) apply only to CEMS.
63.10(b)(2)(i), (ii), (iv) and (v)	Recordkeeping for startup, shutdown, and malfunction events.	No.	
63.10(c)(7), (8) and (15)	Records of excess emissions and parameter monitoring exceedances for CMS.	No	This subpart specifies records requirements.
63.10(d)(5)	Periodic startup, shutdown, and malfunction reports.	No.	
63.10(e)(3)	Excess emissions reports	No	This subpart specifies reporting requirements.
63.10(e)(4)	Reporting COMS data	No	This subpart data does not require COMS.
63.11	Control device requirements	No	This subpart does not require flares.
63.12	State authority and delegations	Yes.	
63.13(a)	Reporting to EPA regional offices	Yes	Except: reports and notifications required to be submitted to CEDRI meet this obligation through electronic reporting.
63.13(b) through 63.15	Addresses of state air pollution control agencies. Incorporation by reference. Availability of information and confidentiality.	Yes	

[85 FR 56100, Sept. 10, 2020]

Subpart FFFFF—National Emission Standards for Hazardous Air Pollutants for Integrated Iron and Steel Manufacturing Facilities

SOURCE: 68 FR 27663, May 20, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7780 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for integrated iron and steel manufacturing facilities. This subpart also establishes requirements to demonstrate initial and continuous compliance with all applicable emission limitations and operation and maintenance requirements in this subpart.

§ 63.7781 Am I subject to this subpart?

You are subject to this subpart if you own or operate an integrated iron and steel manufacturing facility that is (or is part of) a major source of hazardous air pollutants (HAP) emissions. Your integrated iron and steel manufacturing facility is a major source of HAP if it emits or has the potential to emit any single HAP at a rate of 10 tons or more per year or any combination of HAP at a rate of 25 tons or more per year.

§ 63.7782 What parts of my plant does this subpart cover?

(a) This subpart applies to each new and existing affected source at your integrated iron and steel manufacturing facility.

(b) The affected sources are each new or existing sinter plant, blast furnace, and basic oxygen process furnace (BOPF) shop at your integrated iron and steel manufacturing facility.

(c) This subpart covers emissions from the sinter plant windbox exhaust,

discharge end, and sinter cooler; the blast furnace casthouse; the blast furnace stove; and the BOPF shop including each individual BOPF and shop ancillary operations (hot metal transfer, hot metal desulfurization, slag skimming, and ladle metallurgy). This subpart also covers fugitive and intermittent particulate emissions from blast furnace unplanned bleeder valve openings, blast furnace planned bleeder valve openings, blast furnace and BOPF slag processing, handling, and storage, blast furnace bell leaks, beaching of iron from blast furnaces, blast furnace casthouse fugitives, and BOPF shop fugitives.

(d) A sinter plant, blast furnace, blast furnace stove, or BOPF shop at your integrated iron and steel manufacturing facility is existing if you commenced construction or reconstruction of the affected source before July 13, 2001.

(e) A sinter plant, blast furnace, blast furnace stove, or BOPF shop at your integrated iron and steel manufacturing facility is new if you commence construction or reconstruction of the affected source on or after July 13, 2001. An affected source is reconstructed if it meets the definition of reconstruction in § 63.2.

[68 FR 27663, May 20, 2003, as amended at 89 FR 23319, Apr. 3, 2024]

§ 63.7783 When do I have to comply with this subpart?

(a) If you have an existing affected source, you must comply with each emission limitation, standard, and operation and maintenance requirement in this subpart that applies to you by the dates specified in paragraphs (a)(1) and (2) of this section. This paragraph does not apply to the emission limitations for BOPF group: mercury (Hg); sinter plant windbox: Hg, hydrochloric acid (HCl), carbonyl sulfide (COS); Blast Furnace casthouse: HCl, total hydrocarbon (THC); Blast Furnace stove: HCl and total hydrocarbon (THC); primary emission control system for a BOPF: 2,3,7,8-tetrachlorodibenzo-p-dioxin (2,3,7,8–TCDD) toxic equivalent (TEQ), HCl, THC; fugitive and intermittent particulate sources.

(1) No later than May 22, 2006 for all emissions sources at an existing affected source except for a sinter cooler at an existing sinter plant.

(2) No later than January 13, 2007 for a sinter cooler at an existing sinter plant.

(b) If you have a new affected source and its initial startup date is on or before May 20, 2003, then you must comply with each emission limitation, standard, and operation and maintenance requirement in this subpart that applies to you by May 20, 2003. This paragraph does not apply to the emission limitations for mercury.

(c) If you have a new affected source and its initial startup date is after May 20, 2003, you must comply with each emission limitation, standard, and operation and maintenance requirement in this subpart that applies to you upon initial startup. This paragraph does not apply to the emission limitations for mercury.

(d) If your integrated iron and steel manufacturing facility is not a major source and becomes a major source of HAP, the following compliance dates apply to you.

(1) Any portion of the existing integrated iron and steel manufacturing facility that becomes a new affected source or a new reconstructed source must be in compliance with this subpart upon startup.

(2) All other parts of the integrated iron and steel manufacturing facility must be in compliance with this subpart no later than 2 years after it becomes a major source.

(e) You must meet the notification and schedule requirements in § 63.7840. Several of these notifications must be submitted before the compliance date for your affected source.

(f) With regard to the mercury emission limitations, if you have a new or existing affected source, you must comply with each emission limitation for mercury that applies to you by the deadlines set forth in § 63.7791.

(g) If you have an existing affected source or a new or reconstructed affected source for which construction or reconstruction commenced on or before July 31, 2023, each sinter plant windbox, BF casthouse, BF stove, primary emission control system for a BOPF, and fugitive and intermittent particulate source at your facility

must be in compliance with the applicable emission limits in table 1 of this subpart through performance testing under § 63.7825, April 3, 2025, except for the following:

(1) All affected sinter plant windbox sources that commence construction or reconstruction on or before July 31, 2023, must be in compliance with Hg, HCl, COS, TEQ, and PAH emissions limits in table 1 to this subpart through performance testing by April 3, 2027.

(2) All affected BF and BOPF sources that commence construction or reconstruction on or before July 31, 2023, must be in compliance with HCl, THC, and TEQ emissions limits in table 1 to this subpart through performance testing by April 3, 2027.

(3) All affected sources that commence construction or reconstruction on or before July 31, 2023 must be in compliance with work practices and limits for unplanned openings, work practices for beaching, and the opacity limit for slag processing in table 1 to this subpart through performance testing (or through reporting of number of unplanned openings for limits applicable to unplanned openings shown in table 1) by April 3, 2026.

(4) All affected sources that commence construction or reconstruction after July 31, 2023, must be in compliance with all new and revised provisions in table 1 to this subpart through performance testing by April 3, 2024 or upon startup, whichever is later.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39585, July 13, 2006; 85 FR 42114, July 13, 2020; 89 FR 23319, Apr. 3, 2024]

EMISSION LIMITATIONS AND STANDARDS

§ 63.7790 What emission limitations must I meet?

(a) You must meet each emission limit and opacity limit in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit for capture systems and control devices in paragraphs (b)(1) through (3) of this section that applies to you.

(1) You must operate each capture system applied to emissions from a sinter plant discharge end or blast furnace casthouse or to secondary emissions from a BOPF at or above the lowest value or settings established for the operating limits in your operation and maintenance plan;

(2) For each venturi scrubber applied to meet any particulate emission limit in Table 1 to this subpart, you must maintain the hourly average pressure drop and scrubber water flow rate at or above the minimum levels established during the initial performance test.

(3) For each electrostatic precipitator applied to emissions from a BOPF, you must maintain the hourly average opacity of emissions exiting the control device at or below 10 percent.

(c) An owner or operator who uses an air pollution control device other than a baghouse, venturi scrubber, or electrostatic precipitator must submit a description of the device; test results collected in accordance with § 63.7822 verifying the performance of the device for reducing emissions of particulate matter to the atmosphere to the levels required by this subpart; a copy of the operation and maintenance plan required in § 63.7800(b); and appropriate operating parameters that will be monitored to maintain continuous compliance with the applicable emission limitation(s). The monitoring plan identifying the operating parameters to be monitored is subject to approval by the Administrator.

(d) For each sinter plant, you must either:

(1) Maintain the 30-day rolling average oil content of the feedstock at or below 0.02 percent; or

(2) Maintain the 30-day rolling average of volatile organic compound emissions from the windbox exhaust stream at or below 0.2 lb/ton of sinter.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39585, July 13, 2006]

§ 63.7791 How do I comply with the requirements for the control of mercury from BOPF Groups?

(a) *Compliance deadlines.* (1) If you have an existing affected source or a new or reconstructed affected source for which construction or reconstruction commenced on or before August 16, 2019, each BOPF Group at your facility must be in compliance with the applicable mercury emission limit in

Table 1 of this subpart through performance testing under §§ 63.7825 and 63.7833, or through procurement of steel scrap pursuant to the compliance options in § 63.7791(c), (d), or (e) beginning July 13, 2021.

(2) If you have a new or reconstructed affected source for which construction or reconstruction commenced after August 16, 2019, each BOPF Group at that source must be in compliance with the applicable mercury emission limit in Table 1 of this subpart beginning July 13, 2020 or upon initial startup of your affected source, whichever is later.

(b) *Alternative compliance demonstration.* (1) As an alternative to demonstrating compliance with the emission limits in Table 1 by conducting performance tests pursuant to §§ 63.7825 and 63.7833(h), you may demonstrate compliance with the emission limits in Table 1 by procuring scrap pursuant to the requirements in paragraph (c), (d), or (e) of this section for each scrap provider, contract, or shipment. It is not necessary to use the same BOPF scrap compliance provision for all scrap providers, contracts, or shipments. You may procure some scrap through providers, contracts, or shipments pursuant to one BOPF scrap compliance provision and other scrap through providers, contracts, or shipments pursuant to other BOPF scrap compliance provisions.

(2) To utilize the alternative compliance options established in paragraph (b)(1) of this section, you must submit an initial certification of compliance and semiannual compliance reports consistent with the requirements of §§ 63.7840(f) and 63.7841(b)(9) through (11), and (13), and comply with the recordkeeping requirements in § 63.7842(e) and all other applicable provisions related to demonstrating compliance through participating in an approved mercury program or through the use of scrap that does not contain mercury switches.

(3) For any facility that initially elects to utilize the alternative compliance options established in paragraph (b)(1) of this section, but subsequently stops using scrap that meets the requirements of paragraph (c), (d), or (e) of this section for each scrap provider, contract, or shipment, within 180 days of the change you must, for that BOPF Group, demonstrate compliance through performance testing pursuant to the requirements of §§ 63.7825 and 63.7833(h), and submit a revised notice of compliance status in your next semiannual compliance report described in this section. You must also comply with the requirements for conducting subsequent performance tests in §§ 63.7821(e) and 63.7840(g), and all other applicable requirements related to demonstrating compliance with the emission limits through performance testing.

(c) *Participation in the NVMSRP.* (1) You must obtain all post-consumer scrap that contains motor vehicle scrap from scrap providers who participate in the NVMSRP. The NVMSRP is an EPA-approved program under this section unless and until the Administrator disapproves the program (in part or in whole);

(2) You must certify in your initial notification of compliance status required by § 63.7840(f) and semiannual compliance report required by § 63.7841(a) that you purchased post-consumer steel scrap containing motor vehicle scrap according to paragraph (c)(1) of this section, and identify all your scrap providers in your semiannual compliance report;

(3) If you purchase scrap from a broker, you must certify that all scrap received from that broker was obtained from other scrap providers who participate in the NVMSRP and identify all scrap providers used by all your scrap brokers in your semiannual compliance report; and

(4) You must conduct periodic inspections or provide other means of corroboration to ensure that scrap providers and brokers participate in the NVMSRP and, therefore, are aware of the need for and are implementing appropriate steps to minimize the presence of mercury in scrap from end-of-life vehicles.

(d) *Use of scrap that does not contain mercury switches.* For BOPF scrap not complying with the requirements in paragraph (c) or (e) of this section, you must certify in your initial notification of compliance report required by § 63.7840(f) and semiannual compliance

report required by § 63.7841(a) and maintain records of documentation required by § 63.7842(e) establishing that the scrap does not contain mercury switches. You may satisfy this requirement by certifying and documenting that:

(1) The scrap does not contain motor vehicle scrap; or

(2) The scrap does not contain shredded motor vehicle scrap; or

(3) The only materials from motor vehicles in the scrap are materials recovered for their specialty alloy content (including, but not limited to, chromium, nickel, molybdenum, or other alloys); therefore, based on the type of the scrap and purchase specifications, the scrap does not contain mercury switches.

(e) *Use of an EPA-approved mercury removal program.* (1) You must obtain all post-consumer scrap containing motor vehicle scrap from scrap providers who participate in a program for the removal of mercury switches that has been approved by the Administrator;

(2) You must certify in your initial notification of compliance status required by § 63.7840(f) and semiannual compliance report required by § 63.7841(a) that you purchase post-consumer steel scrap containing motor vehicle scrap according to paragraph (e)(1) of this section and identify all your scrap providers in your semiannual compliance report;

(3) If you purchase scrap from a broker, you must certify that all scrap received from that broker was obtained from other scrap providers who participate in a program for the removal of mercury switches that has been approved by the Administrator and identify all scrap providers used by all your scrap brokers in your semiannual compliance report; and

(4) You must conduct periodic inspections or provide other means of corroboration to ensure that scrap providers and brokers are complying with the approved mercury removal program and, therefore, are aware of the need for and are implementing appropriate steps to minimize the presence of mercury in scrap from end-of-life vehicles.

[85 FR 42115, July 13, 2020, as amended at 89 FR 23320, Apr. 3, 2024]

§ 63.7792 What fenceline monitoring requirements must I meet?

The owner or operator must conduct sampling along the facility property boundary and analyze the samples in accordance with paragraphs (a) through (g) of this section.

(a) Beginning either 1 year after promulgation of the test method for fenceline sampling of metals applicable to this subpart or April 3, 2026 whichever is later, the owner or operator must conduct sampling along the facility property boundary and analyze the samples in accordance with the method and paragraphs (a)(1) through (3) of this section.

(1) The owner or operator must monitor for total chromium.

(2) The owner or operator must use a sampling period and sampling frequency as specified in paragraphs (a)(2)(i) through (iii) of this section.

(i) *Sampling period.* A 24-hour sampling period must be used. A sampling period is defined as the period during active collection of a sample and does not include the time required to analyze the sample.

(ii) *Sampling frequency.* The frequency of sample collection must be samples at least every 6 calendar days, such that the beginning of each sampling period begins no greater than approximately 144 hours (±12 hours) from the end of the previous sample.

(iii) *Sunset provision.* When the annual rolling average Δc remains less than 0.05 $\mu g/m^3$ for 24 months in succession, a test waiver may be requested from the Administrator to remove or reduce fenceline sampling requirements. If the annual rolling average Δc exceeds 0.05$\mu g/m^3$, the determination of 24 consecutive annual average Δc months restarts.

(3) The owner or operator must determine sample locations in accordance with paragraphs (b)(3)(i) through (v) of this section.

(i) The monitoring perimeter must be located between the property boundary and the process unit(s), such that the monitoring perimeter encompasses all potential sources of the target analyte(s) specified in paragraph (a)(1) of this section.

(ii) The owner or operator must place a minimum of 4 samplers around the monitoring perimeter.

(iii) To determine sampling locations, measure the length of the monitoring perimeter.

(A) Locate the point downwind of the prevailing wind direction.

(B) Divide the monitoring perimeter equally into 4 evenly spaced sampling points, with one located in accordance with paragraph (a)(3)(iii)(A) of this section.

(4) The owner or operator must follow the procedures in of the fenceline metals test method to determine the detection limit of the target analyte(s) and requirements for quality assurance samples.

(b) The owner or operator must collect and record meteorological data according to the applicable requirements in paragraphs (b)(1) through (3) of this section.

(1) If monitoring is conducted under paragraph (b) of this section, if a near-field source correction is used as provided in paragraph (f)(2) of this section, or if an alternative test method is used that provides time-resolved measurements, the owner or operator must use an on-site meteorological station in accordance with the metals fenceline test method applicable to this subpart. Collect and record hourly average meteorological data, including temperature, barometric pressure, wind speed and wind direction and calculate daily unit vector wind direction and daily sigma theta.

(2) For cases other than those specified in paragraph (c)(1) of this section, the owner or operator must collect and record sampling period average temperature and barometric pressure using either an on-site meteorological station in accordance with the metals fenceline test method of this part or, alternatively, using data from a National Weather Service (NWS) meteorological station provided the NWS meteorological station is within 40 kilometers (25 miles) of the facility.

(3) If an on-site meteorological station is used, the owner or operator must follow the calibration and standardization procedures for meteorological measurements in EPA–454/B–08–002 (incorporated by reference, see § 63.14).

(c) Within 45 days of completion of each sampling period, the owner or operator must determine whether the results are above or below the action level as follows.

(1) The owner or operator must determine the facility impact on the concentration (Δc) for each sampling period according to either paragraph (d)(1)(i) or (ii) of this section, as applicable.

(i) Except when near-field source correction is used as provided in paragraph (d)(1)(ii) of this section, the owner or operator must determine the highest and lowest sample results individually from the sample pool and calculate the Δc as the difference in these concentrations. Co-located samples must be averaged together for the purposes of determining the concentration at a particular sampling location, and, if applicable, for determining Δc. The owner or operator must adhere to the following procedures when one or more samples for the sampling period are below the method detection limit for a particular compound:

(A) If the lowest detected value is below detection, the owner or operator must use zero as the lowest sample result when calculating Δc.

(B) If all sample results are below the method detection limit, the owner or operator must use the highest method detection limit for the sample set as the highest sample result and zero as the lowest sample result when calculating Δc.

(ii) When near-field source correction is used as provided in paragraph (g) of this section, the owner or operator must determine Δc using the calculation protocols outlined in the approved site-specific monitoring plan and in paragraph (g) of this section.

(2) The owner or operator must calculate the annual average Δc based on the average of the Δc values for the 61 most recent sampling periods. The owner or operator must update this annual average value after receiving the results of each subsequent sampling period.

(3) The action level for chromium is 0.1 $\mu g/m^3$. If the annual average Δc value (rounded to 1 significant figure) is greater than the action level, the concentration is above the action level,

and the owner or operator must conduct a root cause analysis and corrective action in accordance with paragraph (d) of this section.

(d) Once any action level in paragraph (c)(3) of this section has been exceeded, the owner or operator must take the following actions to bring the annual average Δc back below the action level(s).

(1) Within 5 days of updating the annual average value as required in (c)(2) and determining that any action level in paragraph (c)(3) of this section has been exceeded (*i.e.*, in no case longer than 50 days after completion of the sampling period), the owner or operator must initiate a root cause analysis to determine appropriate corrective action. A root cause analysis is an assessment conducted through a process of investigation to determine the primary underlying cause and all other contributing causes to an exceedance of the action level(s) set forth in paragraph (c)(3).

(2) The initial root cause analysis may include, but is not limited to:

(i) Visual inspection to determine the cause of the high emissions.

(ii) Operator knowledge of process changes (*e.g.*, a malfunction or release event).

(3) If the initial root cause cannot be identified using the type of techniques described in paragraph (d)(2) of this section, the owner or operator must employ more frequent sampling and analysis to determine the root cause of the exceedance.

(i) The owner or operator may first employ additional monitoring points or more frequent sampling to determine the root cause of the exceedance.

(ii) If the owner or operator has not determined the root cause of the exceedance within 30 days of determining that the action level has been exceeded, the owner or operator must employ the appropriate more time resolute sampling techniques (*e.g.*, continuous multi metals monitors) to locate the cause of the exceedance. If the root cause is not identified after 28 days, either the more time resolute monitor must be relocated or an additional more time resolute monitor must be added. Relocation or addition of extra monitors must continue after each 28-day period of nonidentification until the owner or operator can identify the root cause of the exceedance.

(4) If the underlying primary and other contributing causes of the exceedance are deemed to be under the control of the owner or operator, the owner or operator must take appropriate corrective action as expeditiously as possible to bring annual average fenceline concentrations back below the action level(s) set forth in paragraph (c)(2)(3) of this section. At a minimum, the corrective actions taken must address the underlying primary and other contributing cause(s) determined in the root cause analysis to prevent future exceedances from the same underlying cause(s).

(5) The root cause analysis must be completed and initial corrective actions taken no later than 45 days after determining there is an exceedance of an action level.

(e) An owner or operator must develop a corrective action plan if the conditions in either paragraph (e)(1) or (2) of this section are met. The corrective action plan must describe the corrective action(s) completed to date, additional measures that the owner or operator proposes to employ to expeditiously reduce annual average fenceline concentrations below the action level set forth in paragraph (c)(3) of this section, and a schedule for completion of these measures. The corrective action plan must identify actions to address the underlying primary and other contributing cause(s) determined in the root cause analysis to prevent future exceedances from the same underlying cause(s). The corrective action plan does not need to be approved by the Administrator. However, if upon review, the Administrator disagrees with the additional measures outlined in the plan, the owner or operator must revise and resubmit the plan within 7 calendar days of receiving comments from the Administrator.

(1) The owner or operator must develop a corrective action plan if, upon completion of the root cause analysis and initial corrective actions required in paragraph (d) of this section, the Δc value for the next sampling period, for which the sampling start time begins

after the completion of the initial corrective actions, is greater than 0.1 μg/m³. The owner or operator must submit the corrective action plan to the Administrator within 60 days after receiving the analytical results indicating that the Δc value for the sampling period following the completion of the initial corrective action is greater than 0.1 μg/m³.

(2) The owner or operator must develop a corrective action plan if complete implementation of all corrective measures identified in the root cause analysis required by paragraph (d) of this section will require more than 45 days. The owner or operator must submit the corrective action plan to the Administrator no later than 60 days following the completion of the root cause analysis required in paragraph (d) of this section.

(f) An owner or operator may request approval from the Administrator for a site-specific monitoring plan to account for offsite upwind sources according to the requirements in paragraphs (f)(1) through (4) of this section.

(1) The owner or operator must prepare and submit a site-specific monitoring plan and receive approval of the site-specific monitoring plan prior to using the near-field source alternative calculation for determining Δc provided in paragraph (f)(2) of this section. The site-specific monitoring plan must include, at a minimum, the elements specified in paragraphs (f)(1)(i) through (v) of this section. The procedures in section 12 of Method 325A of appendix A of this part are not required, but may be used, if applicable, when determining near-field source contributions.

(i) Identification of the near-field source or sources.

(ii) Location of the additional monitoring stations that must be used to determine the uniform background concentration and the near-field source concentration contribution. Modeling may not be used in lieu of monitoring to identify uniform background concentration and near-field sources.

(iii) Identification of the fenceline monitoring locations impacted by the near-field source. If more than one near-field source is present, identify the near-field source or sources that are expected to contribute to the concentration at that monitoring location.

(iv) A description of (including sample calculations illustrating) the planned data reduction including the treatment of invalid data, data below detection limits, and data collected during calm wind periods; and calculations to determine the near-field source concentration contribution for each monitoring location.

(v) A detailed description of the measurement technique, measurement location(s), the standard operation procedure, measurement frequency, recording frequency, measurement detection limit, and data quality indicators to ensure accuracy, precision, and validity of the data.

(2) When an approved site-specific monitoring plan is used, the owner or operator must determine Δc for comparison with the action level using the requirements specified in paragraphs (f)(2)(i) through (iii) of this section.

(i) For each monitoring location, calculate Δc_i using the following equation.

Equation 1 to paragraph (f)(1)(i)

$$\Delta c_i = MFC_i - NFS_i$$

Where:

Δc_i = The fenceline concentration, corrected for background, at measurement location i, micrograms per cubic meter (μg/m³).

MFC_i = The measured fenceline concentration at measurement location i, μg/m³.

NFS_i = The near-field source contributing concentration at measurement location i determined using the additional measurements and calculation procedures included in the site-specific monitoring plan, μg/m³. For monitoring locations that are not included in the site-specific monitoring plan as impacted by a near-field source, use $NFS_i = 0$ μg/m³.

(ii) When one or more samples for the sampling period are below the method detection limit, adhere to the following procedures:

(A) If the concentration at the monitoring location(s) used to determine the near-field source contributing concentration is below the method detection limit, the owner or operator must use zero for the monitoring location concentration when calculating NFS_i for that monitoring period.

(B) If a fenceline monitoring location sample result is below the method detection limit, the owner or operator must use the method detection limit as the sample result.

(iii) Determine Δc for the monitoring period as the maximum value of Δc_i from all of the fenceline monitoring locations for that monitoring period.

(3) The site-specific monitoring plan must be submitted and approved as described in paragraphs (f)(3)(i) through (iv) of this section.

(i) The site-specific monitoring plan must be submitted to the Administrator for approval.

(ii) The site-specific monitoring plan must also be submitted to the following address: U.S. Environmental Protection Agency, Office of Air Quality Planning and Standards, Sector Policies and Programs Division, U.S. EPA Mailroom (E143–01), Attention: Integrated Iron and Steel Sector Lead, 109 T.W. Alexander Drive, Research Triangle Park, NC 27711. Electronic copies in lieu of hard copies may also be submitted to *fencelineplan@epa.gov*.

(iii) The Administrator will approve or disapprove the plan in 90 days. The plan is considered approved if the Administrator either approves the plan in writing or fails to disapprove the plan in writing. The 90-day period begins when the Administrator receives the plan.

(iv) If the Administrator finds any deficiencies in the site-specific monitoring plan and disapproves the plan in writing, the owner or operator may revise and resubmit the site-specific monitoring plan following the requirements in paragraphs (f)(3)(i) and (ii) of this section. The 90-day period starts over with the resubmission of the revised monitoring plan.

(4) The approval by the Administrator of a site-specific monitoring plan will be based on the completeness, accuracy, and reasonableness of the request for a site-specific monitoring plan. Factors that the Administrator will consider in reviewing the request for a site-specific monitoring plan include, but are not limited to, those described in paragraphs (f)(4)(i) through (v) of this section.

(i) The identification of the near-field source or sources and evidence of how the sources impact the fenceline concentrations.

(ii) The monitoring location selected to determine the uniform background concentration or an indication that no uniform background concentration monitor will be used.

(iii) The location(s) selected for additional monitoring to determine the near-field source concentration contribution.

(iv) The identification of the fenceline monitoring locations impacted by the near-field source or sources.

(v) The appropriateness of the planned data reduction and calculations to determine the near-field source concentration contribution for each monitoring location, including the handling of invalid data, data below the detection limit, and data during calm periods.

(vi) If more frequent monitoring is proposed, the adequacy of the description of and rationale for the measurement technique, measurement location(s), the standard operation procedure, measurement frequency, recording frequency, measurement detection limit, and data quality indicators to ensure accuracy, precision, and validity of the data.

(g) The owner or operator must comply with the applicable recordkeeping and reporting requirements in § 63.7841 and § 63.7842.

(1) As outlined in § 63.7(f), the owner or operator may submit a request for an alternative test method. At a minimum, the request must follow the requirements outlined in paragraphs (f)(1)(i) through (vi) of this section.

(i) The alternative method may be used in lieu of all or a partial number

of the sampling locations required under paragraph (a) of this section.

(ii) The alternative method must be validated according to Method 301 in appendix A of this part or contain performance-based procedures and indicators to ensure self-validation.

(iii) The method detection limit must nominally be at least three times below the action level. The alternate test method must describe the procedures used to provide field verification of the detection limit.

(iv) If the alternative test method will be used to replace some or all samplers required under paragraph (a) of this section, the spatial coverage must be equal to or better than the spatial coverage provided under paragraph (a).

(v) For alternative test methods capable of real time measurements (less than a 5-minute sampling and analysis cycle), the alternative test method may allow for elimination of data points corresponding to outside emission sources for purpose of calculation of the high point for the two week average. The alternative test method approach must have wind speed, direction, and stability class of the same time resolution and within the footprint of the instrument.

(vi) For purposes of averaging data points to determine the Δc for the individual sampling period, all results measured under the method detection limit must use the method detection limit. For purposes of averaging data points for the individual sampling period low sample result, all results measured under the method detection limit must use zero.

[89 FR 23320, Apr. 3, 2024]

§ 63.7793 What work practice standards must I meet?

(a) You must meet each work practice limit in table 1 to this subpart that applies to you.

(b) For unplanned bleeder valve openings on a new and existing blast furnace, you must meet each work practice standard listed in paragraphs (b)(1) through (3) of this section.

(1) Develop and operate according to a ''Slip Avoidance Plan'' to minimize slips and submit it to EPA for approval;

(2) Install devices to continuously measure/monitor material levels in the furnace (*i.e.*, stockline), at a minimum of three locations, with alarms to inform operators of static (*i.e.*, not moving) stockline conditions which increase the likelihood of slips; and

(3) Install and use instruments on the furnace to monitor temperature and pressure to help determine when a slip is likely to occur.

(c) For each large bell on a new and existing blast furnace, you must meet each work practice standard listed in paragraphs (c)(1) and (2) of this section.

(1) Maintain metal seats to minimize wear on seals and emissions; and

(2) Replace or repair large bell seals according to § 63.7833(j).

(d) For each small bell on a new and existing blast furnace, you must meet each work practice standard listed in paragraphs (d)(1) and (2) of this section.

(1) Maintain metal seats to minimize wear on seals; and

(2) You must repair or replace small bell seals prior to the time period or metal throughput limit that has been proven and documented to produce no opacity from the small bell.

(e) For each iron beaching operation, you must meet each work practice standard listed in paragraphs (e)(1) and (2) of this section.

(1) Minimize the drop height of molten metal to the ground, the slope or grade of the area where beaching occurs, and the rate at which molten metal is poured onto the ground; and

(2) Use carbon dioxide shielding during beaching event; and/or use full or partial (hoods) enclosures around beached iron.

(f) For each BOPF at a new or existing shop, you must develop and operate according to a ''BOPF Shop Operating Plan'' to minimize fugitive emissions and detect openings and leaks and submit it to EPA for approval. Your BOPF Shop Operating Plan may include, but is not limited to, any of the items listed in paragraphs (f)(1) through (8) of this section.

(1) List all events that generate VE, including slopping and other steps company will take to reduce incidence

rate. State the specific actions that operators will take when slag foaming approaches the mouth of the vessel in order to prevent slopping;

(2) Minimize hot iron pour/charge rate (minutes) and set a maximum pour rate in tons/second;

(3) Schedule of regular inspections of BOPF shop structure for openings and leaks to the atmosphere;

(4) Optimize positioning of hot metal ladles with respect to hood face and furnace mouth;

(5) Optimize furnace tilt angle during charging and set a maximum tilt angle during charging;

(6) Keep all openings, except roof monitors, closed, especially during transfer, to extent feasible and safe. All openings shall be closed unless the opening was in the original design of the Shop;

(7) Use higher draft velocities to capture more fugitives at a given distance from hood, if possible; and

(8) Monitor opacity periodically (*e.g.*, once per month) from all openings with EPA Method Alt-082 (camera) or with EPA Method 9 in appendix A–4 to part 60 of this chapter.

[89 FR 23322, Apr. 3, 2024]

OPERATION AND MAINTENANCE REQUIREMENTS

§ 63.7800 What are my operation and maintenance requirements?

(a) You must always operate and maintain your affected source, including air pollution control and monitoring equipment, according to the requirements in § 63.7810(d).

(b) You must prepare and operate at all times according to a written operation and maintenance plan for each capture system or control device subject to an operating limit in § 63.7790(b). Each plan must address the elements in paragraphs (b)(1) through (9) of this section.

(1) Monthly inspections of the equipment that is important to the performance of the total capture system (*e.g.*, pressure sensors, dampers, and damper switches). This inspection must include observations of the physical appearance of the equipment (*e.g.*, presence of holes in ductwork or hoods, flow constrictions caused by dents or accumulated dust in the ductwork, and fan erosion). The operation and maintenance plan also must include requirements to repair any defect or deficiency in the capture system before the next scheduled inspection.

(2) Preventative maintenance for each control device, including a preventative maintenance schedule that is consistent with the manufacturer's instructions for routine and long-term maintenance.

(3) Operating limits for each capture system applied to emissions from a sinter plant discharge end or blast furnace casthouse, or to secondary emissions from a BOPF. You must establish the operating limits according to the requirements in paragraphs (b)(3)(i) through (iii) of this section.

(i) Select operating limit parameters appropriate for the capture system design that are representative and reliable indicators of the performance of the capture system. At a minimum, you must use appropriate operating limit parameters that indicate the level of the ventilation draft and the damper position settings for the capture system when operating to collect emissions, including revised settings for seasonal variations. Appropriate operating limit parameters for ventilation draft include, but are not limited to, volumetric flow rate through each separately ducted hood, total volumetric flow rate at the inlet to the control device to which the capture system is vented, fan motor amperage, or static pressure.

(ii) For each operating limit parameter selected in paragraph (b)(3)(i) of this section, designate the value or setting for the parameter at which the capture system operates during the process operation. If your operation allows for more than one process to be operating simultaneously, designate the value or setting for the parameter at which the capture system operates during each possible configuration that you may operate.

(iii) Include documentation in your plan to support your selection of the operating limits established for the capture system. This documentation must include a description of the capture system design, a description of the

capture system operating during production, a description of each selected operating limit parameter, a rationale for why you chose the parameter, a description of the method used to monitor the parameter according to the requirements of § 63.7830(a), and the data used to set the value or setting for the parameter for each of your process configurations.

(4) Corrective action procedures for baghouses equipped with bag leak detection systems or continuous opacity monitoring systems (COMS). In the event a bag leak detection system alarm is triggered or emissions from a baghouse equipped with a COMS exceed an hourly average opacity of 5 percent, you must initiate corrective action to determine the cause of the alarm within 1 hour of the alarm, initiate corrective action to correct the cause of the problem within 24 hours of the alarm, and complete the corrective action as soon as practicable. Corrective actions may include, but are not limited to:

(i) Inspecting the baghouse for air leaks, torn or broken bags or filter media, or any other condition that may cause an increase in emissions.

(ii) Sealing off defective bags or filter media.

(iii) Replacing defective bags or filter media or otherwise repairing the control device.

(iv) Sealing off a defective baghouse compartment.

(v) Cleaning the bag leak detection system probe, or otherwise repair the bag leak detection system.

(vi) Shutting down the process producing the particulate emissions.

(5) Corrective action procedures for venturi scrubbers equipped with continuous parameter monitoring systems (CPMS). In the event a venturi scrubber exceeds the operating limit in § 63.7790(b)(2), you must take corrective actions consistent with your site-specific monitoring plan in accordance with § 63.7831(a).

(6) Corrective action procedures for electrostatic precipitators equipped with COMS. In the event an electrostatic precipitator exceeds the operating limit in § 63.7790(b)(3), you must take corrective actions consistent with your site-specific monitoring plan in accordance with § 63.7831(a).

(7) Procedures for determining and recording the daily sinter plant production rate in tons per hour.

(8) Small Bell repair or replacement period, in weeks, or mass of material throughput, in tons, and the specific begin date and end date for the chosen repair or replacement period or throughput over which there were no visible emissions observed.

(9) Building drawings of the BF Casthouse and BOPF shop that show and list by number the openings, including doors and vents, that are part of the original design of the building.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39585, July 13, 2006; 85 FR 42116, July 13, 2020; 89 FR 23323, Apr. 3, 2024]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7810 What are my general requirements for complying with this subpart?

(a) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, you must be in compliance with the emission limitations, standards, and operation and maintenance requirements in this subpart at all times, except during periods of startup, shutdown, and malfunction. After January 11, 2021, for each such source you must be in compliance with the emission limitations in this subpart at all times. For new and reconstructed sources for which construction or reconstruction commenced after August 16, 2019, you must be in compliance with the emission limitations in this subpart at all times.

(b) During the period between the compliance date specified for your affected source in § 63.7783 and the date upon which continuous monitoring systems have been installed and certified and any applicable operating limits have been set, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.

(c) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, you must develop a written startup, shutdown,

and malfunction plan according to the provisions in § 63.6(e)(3). For each such source, a startup, shutdown, and malfunction plan is not required after January 11, 2021. No startup, shutdown, and malfunction plan is required for any new or reconstructed source for which construction or reconstruction commenced after August 16, 2019.

(d) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, you must always operate and maintain your affected source, including air pollution control and monitoring equipment, according to the provisions in § 63.6(e)(1)(i). After January 11, 2021for each such source, and after July 13, 2020 for new and reconstructed sources for which construction or reconstruction commenced after August 16, 2019, at all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

[68 FR 27663, May 20, 2003, as amended at 71 FR 20468, Apr. 20, 2006; 85 FR 42116, July 13, 2020]

INITIAL COMPLIANCE REQUIREMENTS

§ 63.7820 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) You must conduct a performance test to demonstrate initial compliance with each emission and opacity limit in Table 1 to this subpart that applies to you. You must also conduct a performance test to demonstrate initial compliance with the 30-day rolling average operating limit for the oil content of the sinter plant feedstock in § 63.7790(d)(1) or alternative limit for volatile organic compound emissions from the sinter plant windbox exhaust stream in § 63.7790(d)(2). You must conduct the performance tests within 180 calendar days after the compliance date that is specified in § 63.7783 for your affected source and report the results in your notification of compliance status.

(b) For each operation and maintenance requirement that applies to you where initial compliance is not demonstrated using a performance test or opacity observation, you must demonstrate initial compliance within 30 calendar days after the compliance date that is specified for your affected source in § 63.7783.

(c) If you commenced construction or reconstruction between July 13, 2001 and May 20, 2003, you must demonstrate initial compliance with either the proposed emission limit or the promulgated emission limit no later than November 17, 2003 or no later than 180 days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

(d) If you commenced construction or reconstruction between July 13, 2001 and May 20, 2003, and you chose to comply with the proposed emission limit when demonstrating initial compliance, you must conduct a second performance test to demonstrate compliance with the promulgated emission limit by November 17, 2006, or no later than 180 days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).

(e) Notwithstanding the deadlines in this section, existing and new affected sources must comply with the deadlines for making the initial compliance demonstrations for the BOPF Group mercury emission limit set forth in paragraphs (e)(1) through (4) in this section.

(1) If you have an existing affected BOPF Group or a new or reconstructed affected source for which construction

or reconstruction commenced on or before August 16, 2019, and you are demonstrating compliance with the emission limit in Table 1 through performance testing, you must conduct the initial performance test at your BOPF Group to demonstrate compliance with the mercury emission limit in Table 1 no later than July 13, 2021.

(2) If you have a new or reconstructed affected BOPF Group for which construction or reconstruction commenced after August 16, 2019, and you are demonstrating compliance with the emission limit in Table 1 through performance testing, you must conduct the initial performance test at your BOPF Group to demonstrate compliance with the mercury emission limit in Table 1 within 180 days of July 13, 2020 or within 180 days of initial startup of your affected source, whichever is later.

(3) If you have an existing affected BOPF Group or a new or reconstructed affected source for which construction or reconstruction commenced on or before August 16, 2019, and you are demonstrating compliance with the mercury emission limit in Table 1 through the requirements in § 63.7791(c) through (e), you must certify compliance in accordance with § 63.7840(f) in your notification of compliance and in accordance with § 63.7841(b)(11) in your first semiannual compliance report after July 13, 2021.

(4) If you have a new affected BOPF Group or a new or reconstructed affected source for which construction or reconstruction commenced after August 16, 2019, and you are demonstrating compliance with the mercury emission limit in Table 1 through the requirements in § 63.7791(b) through (d), you must certify compliance in accordance with § 63.7840(f) in your initial notification of compliance and in accordance with § 63.7841(b)(11) in your first semiannual compliance report after July 13, 2021 or after initial startup of your BOPF Group, whichever is later.

[68 FR 27663, May 20, 2003, as amended at 85 FR 42116, July 13, 2020; 89 FR 23323, Apr. 3, 2024]

§ 63.7821 When must I conduct subsequent performance tests?

(a) You must conduct subsequent performance tests to demonstrate compliance with all applicable emission and opacity limits in table 1 to this subpart at the frequencies specified in paragraphs (b) through (m) of this section.

(b) For each sinter cooler at an existing sinter plant and each emissions unit equipped with a control device other than a baghouse, you must conduct subsequent particulate matter and opacity performance tests no less frequently than twice (at mid-term and renewal) during each term of your title V operating permit.

(c) For each emissions unit equipped with a baghouse, you must conduct subsequent particulate matter and opacity performance tests no less frequently than once during each term of your title V operating permit.

(d) For sources without a title V operating permit, you must conduct subsequent particulate matter and opacity performance tests every 2.5 years.

(e) For each BOPF Group, if demonstrating compliance with the mercury emission limit in table 1 to this subpart through performance testing under §§ 63.7825 and 63.7833, you must conduct subsequent performance tests twice per permit cycle (*i.e.*, mid-term and initial/final) for sources with title V operating permits, and every 2.5 years for sources without a title V operating permit, at the outlet of the control devices for the BOPF Group.

(f) For each sinter plant windbox, you must conduct subsequent mercury, hydrogen chloride, carbonyl sulfide, dioxin/furan, and polycyclic aromatic hydrocarbon performance tests every 5 years.

(g) For each blast furnace stove and BOPF shop primary emission control device, you must conduct subsequent hydrogen chloride and total hydrocarbon testing every 5 years. For the BOPF shop primary emission control device, you must also conduct subsequent dioxin/furan testing every 5 years.

(h) For each blast furnace casthouse and BOPF shop, you must conduct subsequent opacity tests two times per month during a cast, or during a full heat cycle, as appropriate.

(i) For planned bleeder valve openings on each blast furnace, you must conduct opacity tests according to § 63.7823(f) for each planned opening.

(j) For slag processing, handling, and storage operations for each blast furnace or BOPF, you must conduct subsequent opacity tests once per week for a minimum of 18 minutes for each: BF pit filling; BOPF slag pit filling; BF pit digging; BOPF slag pit digging; and one slag handling (either truck loading or dumping slag to slag piles).

(k) For large bells on each blast furnace, you must conduct visible emissions testing on the interbell relief valve according to EPA Method 22 in appendix A–7 to part 60 of this chapter, unless specified in paragraphs (k)(1) through (3) of this section. Testing must be conducted monthly, for 15 minutes.

(1) If visible emissions are detected for a large bell during the monthly visible emissions testing, you must conduct EPA Method 9 (in appendix A–4 to part 60 of this chapter) opacity tests in place of EPA Method 22 testing on that bell once per month, taking 3-minute averages for 15 minutes, until the large bell seal is repaired or replaced.

(2) If the average of 3 instantaneous visible emission readings taken while the interbell relief valve is exhausting exceeds 20 percent, you must initiate corrective action within five business days.

(3) Ten business days after the initial opacity exceedance of 20 percent, you must conduct an EPA Method 9 opacity test, taking 3-minute averages for 15 minutes. If the average of 3 instantaneous visible emissions readings from this test exceeds 20 percent, you must repair or replace that bell seal within 4 months.

(l) For small bells on each blast furnace, you must conduct visible emissions testing according to EPA Method 22 in appendix A–7 to part 60 of this chapter. Testing must be conducted monthly for 15 minutes. If visible emissions are observed, you must compare the period between the visible emissions being present and the most recent bell seal repair or replacement. If this time period or throughput is shorter or lower than the period or throughput stated in the O&M plan required by 63.7800, this new shorter period or lower limit shall be placed in the O&M plan as the work practice limit.

(m) For each blast furnace casthouse, you must conduct subsequent hydrogen chloride and total hydrocarbon testing every 5 years.

[89 FR 23323, Apr. 3, 2024]

§ 63.7822 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits for particulate matter?

(a) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, you must conduct each performance test that applies to your affected source based on representative performance (*i.e.*, performance based on normal operating conditions) of the affected source for the period being tested, according to the conditions detailed in paragraphs (b) through (i) of this section. After January 11, 2021 for each such source, and after July 13, 2020 for new and reconstructed sources for which construction or reconstruction commenced after August 16, 2019, you must conduct each performance test under conditions representative of normal operations. The owner or operator must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, the owner or operator shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests. Representative conditions exclude periods of startup and shutdown. You shall not conduct performance tests during periods of malfunction. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may

be necessary to determine the conditions of performance tests.

(b) To determine compliance with the applicable emission limit for particulate matter in Table 1 to this subpart, follow the test methods and procedures in paragraphs (b)(1) and (2) of this section.

(1) Determine the concentration of particulate matter according to the following test methods:

(i) EPA Method 1 in appendix A–1 to part 60 of this chapter to select sampling port locations and the number of traverse points. Sampling ports must be located at the outlet of the control device and prior to any releases to the atmosphere.

(ii) EPA Method 2 or 2F in appendix A–1 to part 60 of this chapter or EPA Method 2G in appendix A–2 to part 60 of this chapter to determine the volumetric flow rate of the stack gas.

(iii) EPA Method 3, 3A, or 3B in appendix A–2 to part 60 of this chapter to determine the dry molecular weight of the stack gas. The manual procedures (but not instrumental procedures) of voluntary consensus standard ANSI/ASME PTC 19.10–1981—Part 10 (incorporated by reference—see §63.14) may be used as an alternative to EPA Method 3B.

(iv) EPA Method 4 in appendix A–3 to part 60 of this chapter to determine the moisture content of the stack gas.

(v) EPA Method 5 or 5D in appendix A–3 to part 60 of this chapter or EPA Method 17 in appendix A–6 to part 60 of this chapter, as applicable, to determine the concentration of particulate matter (front half filterable catch only).

(2) Collect a minimum sample volume of 60 dry standard cubic feet (dscf) of gas during each particulate matter test run. Three valid test runs are needed to comprise a performance test.

(c) For each sinter plant windbox exhaust stream, you must complete the requirements of paragraphs (c)(1) and (2) of this section:

(1) Follow the procedures in your operation and maintenance plan for measuring and recording the sinter production rate for each test run in tons per hour; and

(2) Compute the process-weighted mass emissions (E_p) for each test run using Equation 1 of this section as follows:

$$E_p = \frac{C \times Q}{P \times K} \qquad \text{(Eq. 1)}$$

Where:

E_p = Process-weighted mass emissions of particulate matter, lb/ton;

C = Concentration of particulate matter, grains per dry standard cubic foot (gr/dscf);

Q = Volumetric flow rate of stack gas, dry standard cubic foot per hour (dscf/hr);

P = Production rate of sinter during the test run, tons/hr; and

K = Conversion factor, 7,000 grains per pound (gr/lb).

(d) If you apply two or more control devices in parallel to emissions from a sinter plant discharge end or a BOPF, compute the average flow-weighted concentration for each test run using Equation 2 of this section as follows:

$$C_W = \frac{\sum_{i=1}^{n} C_i Q_i}{\sum_{i=1}^{n} Q_i} \qquad \text{(Eq. 2)}$$

Where:

C_w = Flow-weighted concentration, gr/dscf;

C_i = Concentration of particulate matter from exhaust stream ''i'', gr/dscf; and

Q_i = Volumetric flow rate of effluent gas from exhaust stream ''i'', dry standard cubic foot per minute (dscfm).

(e) For a control device applied to emissions from a blast furnace casthouse, sample for an integral number of furnace tapping operations sufficient to obtain at least 1 hour of sampling for each test run.

(f) For a primary emission control device applied to emissions from a BOPF with a closed hood system, sample only during the primary oxygen blow and do not sample during any subsequent reblows. Continue sampling for each run for an integral number of primary oxygen blows.

(g) For a primary emission control system applied to emissions from a BOPF with an open hood system and for a control device applied solely to secondary emissions from a BOPF, you must complete the requirements of paragraphs (g)(1) and (2) of this section:

(1) Sample only during the steel production cycle. Conduct sampling under conditions that are representative of normal operation. Record the start and end time of each steel production cycle and each period of abnormal operation; and

(2) Sample for an integral number of steel production cycles. The steel production cycle begins when the scrap is charged to the furnace and ends 3 minutes after the slag is emptied from the vessel into the slag pot.

(h) For a control device applied to emissions from BOPF shop ancillary operations (hot metal transfer, skimming, desulfurization, or ladle metallurgy), sample only when the operation(s) is being conducted.

(i) Subject to approval by the permitting authority, you may conduct representative sampling of stacks when there are more than three stacks associated with a process.

[68 FR 27663, May 20, 2003, as amended at 85 FR 42116, July 13, 2020]

§ 63.7823 What test methods and other procedures must I use to demonstrate initial compliance with the opacity limits?

(a) For each discharge end of a sinter plant, sinter plant cooler, blast furnace casthouse, BOPF shop, and large bell on a blast furnace, you must conduct each performance test that applies to your affected source based on representative performance (*i.e.,* performance based on normal operating conditions) of the affected source for the period being tested, according to the conditions detailed in paragraphs (b) through (d) of this section. Representative conditions exclude periods of startup and shutdown. You shall not conduct performance tests during periods of malfunction. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(b) You must conduct each visible emissions performance test such that the opacity observations overlap with the performance test for particulate matter.

(c) To determine compliance with the applicable opacity limit in Table 1 to this subpart for a sinter plant discharge end or a blast furnace casthouse:

(1) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter. Alternatively, ASTM D7520–16, (incorporated by reference, see § 63.14) may be used with the following conditions:

(i) During the digital camera opacity technique (DCOT) certification procedure outlined in Section 9.2 of ASTM D7520–16 (incorporated by reference, see § 63.14), the owner or operator or the DCOT vendor must present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand).

(ii) The owner or operator must also have standard operating procedures in place including daily or other frequency quality checks to ensure the equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16 (incorporated by reference, see § 63.14).

(iii) The owner or operator must follow the recordkeeping procedures outlined in § 63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination.

(iv) The owner or operator or the DCOT vendor must have a minimum of four independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15-percent opacity of anyone reading and the average error must not exceed 7.5-percent opacity.

(v) Use of this approved alternative does not provide or imply a certification or validation of any vendor's hardware or software. The onus to maintain and verify the certification and/or training of the DCOT camera, software, and operator in accordance

with ASTM D7520–16 (incorporated by reference, see § 63.14) and these requirements is on the facility, DCOT operator, and DCOT vendor.

(2) Obtain a minimum of 30 6-minute block averages. For a blast furnace casthouse, make observations during tapping of the furnace. Tapping begins when the furnace is opened, usually by creating a hole near the bottom of the furnace, and ends when the hole is plugged.

(3) For the blast furnace casthouse, make observations at each opening:

(i) If EPA Method 9 is used, observations should be made separately at each opening.

(ii) If ASTM D7520–16 (incorporated by reference, see § 63.14) is used, observations may be read for more than one opening at the same time.

(d) To determine compliance with the applicable opacity limit in Table 1 to this subpart for BOPF shops:

(1) For an existing BOPF shop:

(i) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter except as specified in paragraphs (d)(1)(ii) and (iii) of this section. Alternatively, ASTM D7520–16 (incorporated by reference, see § 63.14) may be used with the following conditions:

(A) During the DCOT certification procedure outlined in Section 9.2 of ASTM D7520–16 (incorporated by reference, see § 63.14), the owner or operator or the DCOT vendor must present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand).

(B) The owner or operator must also have standard operating procedures in place including daily or other frequency quality checks to ensure the equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16 (incorporated by reference, see § 63.14).

(C) The owner or operator must follow the recordkeeping procedures outlined in § 63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination.

(D) The owner or operator or the DCOT vendor must have a minimum of four independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15-percent opacity of anyone reading and the average error must not exceed 7.5-percent opacity.

(E) Use of this approved alternative does not provide or imply a certification or validation of any vendor's hardware or software. The onus to maintain and verify the certification and/or training of the DCOT camera, software, and operator in accordance with ASTM D7520–16 (incorporated by reference, see § 63.14) and these requirements is on the facility, DCOT operator, and DCOT vendor.

(ii) Instead of procedures in section 2.4 of Method 9 in appendix A to part 60 of this chapter, record observations to the nearest 5 percent at 15-second intervals for at least three steel production cycles.

(iii) Instead of procedures in section 2.5 of Method 9 in appendix A to part 60 of this chapter, determine the 3-minute block average opacity from the average of 12 consecutive observations recorded at 15-second intervals.

(2) For a new BOPF shop housing a bottom-blown BOPF:

(i) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter. Alternatively, ASTM D7520–16 (incorporated by reference, see § 63.14) may be used with the following conditions:

(A) During the DCOT certification procedure outlined in Section 9.2 of ASTM D7520–16 (incorporated by reference, see § 63.14), the owner or operator or the DCOT vendor must present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand).

(B) The owner or operator must also have standard operating procedures in place including daily or other frequency quality checks to ensure the

equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16 (incorporated by reference, see § 63.14).

(C) The owner or operator must follow the recordkeeping procedures outlined in § 63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination.

(D) The owner or operator or the DCOT vendor must have a minimum of four independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15-percent opacity of anyone reading and the average error must not exceed 7.5-percent opacity.

(E) Use of this approved alternative does not provide or imply a certification or validation of any vendor's hardware or software. The onus to maintain and verify the certification and/or training of the DCOT camera, software, and operator in accordance with ASTM D7520–16 (incorporated by reference, see § 63.14) and these requirements is on the facility, DCOT operator, and DCOT vendor.

(ii) Determine the highest and second highest sets of 6-minute block average opacities for each steel production cycle.

(3) For a new BOPF shop housing a top-blown BOPF:

(i) Determine the opacity of emissions according to the requirements for an existing BOPF shop in paragraphs (d)(1)(i) through (iii) of this section.

(ii) Determine the highest and second highest sets of 3-minute block average opacities for each steel production cycle.

(4) Opacity observations must cover the entire steel production cycle and must be made for at least three cycles. The steel production cycle begins when the scrap is charged to the furnace and ends 3 minutes after the slag is emptied from the vessel into the slag pot.

(5) Determine and record the starting and stopping times of the steel production cycle.

(6) Make observations at each opening:

(i) If EPA Method 9 in appendix A–4 to part 60 of this chapter is used, observations should be made separately at each opening.

(ii) If ASTM D7520–16 (incorporated by reference, see § 63.14) is used, observations may be read for more than one opening at the same time.

(e) To determine compliance with the applicable opacity limit in Table 1 to this subpart for a sinter cooler at an existing sinter plant:

(1) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter. Alternatively, ASTM D7520–16 (incorporated by reference, see § 63.14) may be used with the following conditions:

(i) During the DCOT certification procedure outlined in Section 9.2 of ASTM D7520–16 (incorporated by reference, see § 63.14), the owner or operator or the DCOT vendor must present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand).

(ii) The owner or operator must also have standard operating procedures in place including daily or other frequency quality checks to ensure the equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16 (incorporated by reference, see § 63.14).

(iii) The owner or operator must follow the recordkeeping procedures outlined in § 63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination.

(iv) The owner or operator or the DCOT vendor must have a minimum of four independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15-percent opacity of anyone reading and the average error must not exceed 7.5-percent opacity.

(v) Use of this approved alternative does not provide or imply a certification or validation of any vendor's hardware or software. The onus to

maintain and verify the certification and/or training of the DCOT camera, software, and operator in accordance with ASTM D7520–16 (incorporated by reference, see § 63.14) and these requirements is on the facility, DCOT operator, and DCOT vendor.

(2) Obtain a minimum of 30 6-minute block averages.

(3) Make visible emission observations of uncovered portions of sinter plant coolers with the line of sight generally in the direction of the center of the cooler.

(f) To determine compliance with the applicable opacity limit in table 1 to this subpart for planned bleeder valve openings at a blast furnace:

(1) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter. Alternatively, ASTM D7520–16 (incorporated by reference, see § 63.14) may be used with the following conditions:

(i) During the DCOT certification procedure outlined in Section 9.2 of ASTM D7520–16 (incorporated by reference, see § 63.14), the owner or operator or the DCOT vendor must be present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand).

(ii) The owner or operator must also have standard operating procedures in place including daily or other frequency quality checks to ensure the equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16 (incorporated by reference, see § 63.14).

(iii) The owner or operator must follow the recordkeeping procedures outlined in § 63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination.

(iv) The owner or operator or the DCOT vendor must have a minimum of four independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15-percent opacity of any one reading and the average error must not exceed 7.5-percent opacity.

(v) Use of this approved alternative does not provide or imply a certification or validation of any vendor's hardware or software. The onus to maintain and verify the certification and/or training of the DCOT camera, software, and operator in accordance with ASTM D7520–16 (incorporated by reference, see § 63.14) and these requirements is on the facility, DCOT operator, and DCOT vendor.

(2) Conduct opacity observations in 6-minute block averages starting as soon as event begins or sunrise whichever is later and ending either when the bleeder valve closes, sunset, or after the first 6-minute block average where all readings are zero percent opacity, but in no case shall the opacity observation period be less than 6 minutes.

(g) To determine compliance with the applicable opacity limit in table 1 to this subpart for slag processing, handling, and storage operations for a blast furnace or BOPF:

(1) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter.

(2) Conduct opacity observations in 6-minute blocks for 30 minutes at each: slag dumping to BF pit; BOPF slag dumping to pit; BF pit digging, BOPF pit digging; slag dumping to a pile, slag dumping to a piece of slag handling equipment such as crusher.

(h) To determine compliance with the work practice trigger for large bells on a blast furnace:

(1) Using a certified observer, determine the opacity of emissions according to EPA Method 9 in appendix A–4 to part 60 of this chapter.

(2) Conduct opacity observations of 15 instantaneous interbell relief valve emissions.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006; 85 FR 42117, July 13, 2020; 89 FR 23324, Apr. 3, 2024]

§ 63.7824 What test methods and other procedures must I use to establish and demonstrate initial compliance with operating limits?

(a) For each capture system subject to an operating limit in § 63.7790(b)(1),

you must certify that the system operated during the performance test at the site-specific operating limits established in your operation and maintenance plan using the procedures in paragraphs (a)(1) through (4) of this section.

(1) Concurrent with all opacity observations, measure and record values for each of the operating limit parameters in your capture system operation and maintenance plan according to the monitoring requirements specified in § 63.7830(a).

(2) For any dampers that are manually set and remain at the same position at all times the capture system is operating, the damper position must be visually checked and recorded at the beginning and end of each opacity observation period segment.

(3) Review and record the monitoring data. Identify and explain any times the capture system operated outside the applicable operating limits.

(4) Certify in your performance test report that during all observation period segments, the capture system was operating at the values or settings established in your capture system operation and maintenance plan.

(b) For a venturi scrubber subject to operating limits for pressure drop and scrubber water flow rate in § 63.7790(b)(2), you must establish site-specific operating limits according to the procedures in paragraphs (b)(1) and (2) of this section. You may establish the parametric monitoring limit during the initial performance test or during any other performance test run that meets the emission limit.

(1) Using the CPMS required in § 63.7830(c), measure and record the pressure drop and scrubber water flow rate during each run of the particulate matter performance test.

(2) Compute and record the hourly average pressure drop and scrubber water flow rate for each individual test run. Your operating limits are the lowest average pressure drop and scrubber water flow rate value in any of the three runs that meet the applicable emission limit.

(c) You may change the operating limits for a capture system or venturi scrubber if you meet the requirements in paragraphs (c)(1) through (3) of this section.

(1) Submit a written notification to the Administrator of your request to conduct a new performance test to revise the operating limit.

(2) Conduct a performance test to demonstrate compliance with the applicable emission limitation in Table 1 to this subpart.

(3) Establish revised operating limits according to the applicable procedures in paragraphs (a) and (b) of this section for a control device or capture system.

(d) For each sinter plant subject to the operating limit for the oil content of the sinter plant feedstock in § 63.7790(d)(1), you must demonstrate initial compliance according to the procedures in paragraphs (d)(1) through (3) of this section.

(1) Sample the feedstock at least three times a day (once every 8 hours), composite the three samples each day, and analyze the composited samples using Method 9071B, ''n-Hexane Extractable Material(HEM) for Sludge, Sediment, and Solid Samples,'' (Revision 2, April 1998). Method 9071B is incorporated by reference (see § 63.14) and is published in EPA Publication SW–846 ''Test Methods for Evaluating Solid Waste, Physical/Chemical Methods.'' Record the sampling date and time, oil content values, and sinter produced (tons/day).

(2) Continue the sampling and analysis procedure for 30 consecutive days.

(3) Each day, compute and record the 30-day rolling average using that day's value and the 29 previous daily values.

(e) To demonstrate initial compliance with the alternative operating limit for volatile organic compound emissions from the sinter plant windbox exhaust stream in § 63.7790(d)(2), follow the test methods and procedures in paragraphs (e)(1) through (5) of this section. You must conduct each performance test that applies to your affected source based on representative performance (*i.e.*, performance based on normal operating conditions) of the affected source for the period being tested. Representative conditions exclude periods of startup and shutdown. You shall not conduct performance tests during periods of malfunction. You must record the

process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(1) Determine the volatile organic compound emissions according to the following test methods:

(i) EPA Method 1 in appendix A–1 to part 60 of this chapter to select sampling port locations and the number of traverse points. Sampling ports must be located at the outlet of the control device and prior to any releases to the atmosphere.

(ii) EPA Method 2 or 2F in appendix A–1 to part 60 of this chapter or EPA Method 2G in appendix A–2 to part 60 of this chapter to determine the volumetric flow rate of the stack gas.

(iii) EPA Method 3, 3A, or 3B in appendix A–2 to part 60 of this chapter to determine the dry molecular weight of the stack gas. The manual procedures (but not instrumental procedures) of voluntary consensus standard ANSI/ASME PTC 19.10–1981—Part 10 (incorporated by reference—see §63.14) may be used as an alternative to EPA Method 3B.

(iv) EPA Method 4 in appendix A–3 to part 60 of this chapter to determine the moisture content of the stack gas.

(v) EPA Method 25 in appendix A–7 to part 60 of this chapter to determine the mass concentration of volatile organic compound emissions (total gaseous nonmethane organics as carbon) from the sinter plant windbox exhaust stream stack.

(2) Determine volatile organic compound (VOC) emissions every 24 hours (from at least three samples taken at 8-hour intervals) using EPA Method 25 in appendix A–7 to part 60 of this chapter. Record the sampling date and time, sampling results, and sinter produced (tons/day).

(3) Compute the process-weighted mass emissions (E_v) each day using Equation 1 of this section as follows:

$$E_v = \frac{M_C \times Q}{35.31 \times 454{,}000 \times K} \qquad \text{(Eq. 1)}$$

Where:

E_v = Process-weighted mass emissions of volatile organic compounds, lb/ton;

M_c = Average concentration of total gaseous nonmethane organics as carbon by EPA Method 25 in appendix A–7 to part 60 of this chapter, milligrams per dry standard cubic meters (mg/dscm) for each day;

Q = Volumetric flow rate of stack gas, dscf/hr;

35.31 = Conversion factor (dscf/dscm);

454,000 = Conversion factor (mg/lb); and

K = Daily production rate of sinter, tons/hr.

(4) Continue the sampling and analysis procedures in paragraphs (e)(1) through (3) of this section for 30 consecutive days.

(5) Compute and record the 30-day rolling average of VOC emissions for each operating day.

(f) You may use an alternative test method to determine the oil content of the sinter plant feedstock or the volatile organic compound emissions from the sinter plant windbox exhaust stack if you have already demonstrated the equivalency of the alternative method for a specific plant and have received previous approval from the applicable permitting authority.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006; 85 FR 42118, July 13, 2020]

§ 63.7825 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits for hazardous air pollutants?

(a) If demonstrating compliance with the emission limits in Table 1 to this subpart through performance testing, you must conduct a performance test to demonstrate initial compliance with the emission limit. If demonstrating compliance with the emission limit through performance testing, you must conduct each performance test that applies to your affected source based on representative performance (*i.e.*, performance based on normal operating conditions) of the affected source for the period being tested, according to the conditions detailed in paragraphs (b) through (k) of this section. Representative conditions exclude periods of startup and shutdown. You shall not conduct performance tests during periods of malfunction. Initial compliance

tests must be conducted by the deadlines in § 63.7820(e).

(1) You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(2) For sources with multiple emission units ducted to a common control device and stack, compliance testing must be performed either by conducting a single compliance test with all affected emissions units in operation or by conducting a separate compliance test on each emissions unit. Alternatively, the owner or operator may request approval from the permit authority for an alternative testing approach. If the units are tested separately, any emissions unit that is not tested initially must be tested as soon as is practicable.

(b) To demonstrate compliance with the emission limit for mercury in Table 1 to this subpart through performance testing, follow the test methods and procedures in paragraphs (b)(1) and (2) of this section.

(1) Determine the concentration of mercury according to the following test methods:

(i) EPA Method 1 in appendix A–1 to part 60 of this chapter to select sampling port locations and the number of traverse points. Sampling ports must be located at the outlet of the control device and prior to any releases to the atmosphere.

(ii) EPA Method 2 or 2F in appendix A–1 to part 60 of this chapter or EPA Method 2G in appendix A–2 to part 60 of this chapter to determine the volumetric flow rate of the stack gas.

(iii) EPA Method 3, 3A, or 3B in appendix A–2 to part 60 of this chapter to determine the dry molecular weight of the stack gas. The manual procedures (but not instrumental procedures) of voluntary consensus standard ANSI/ASME PTC 19.10–1981—Part 10 (incorporated by reference—see § 63.14) may be used as an alternative to EPA Method 3B.

(iv) EPA Method 4 in appendix A–3 to part 60 of this chapter to determine the moisture content of the stack gas.

(v) EPA Method 29 or 30B in appendix A–8 to part 60 of this chapter to determine the concentration of mercury from the exhaust stream stack of each unit. If performing measurements using EPA Method 29, you must collect a minimum sample volume of 1.7 dscm (60 dscf). Alternative test methods may be considered on a case-by-case basis per § 63.7(f).

(2) Three valid test runs are needed to comprise a performance test of each unit in table 1 to this subpart as applicable. If the performance testing results for any of the emission points yields a non-detect value, then the method detection limit (MDL) must be used to calculate the mass emissions (lb) for that emission unit and, in turn, for calculating the sum of the emissions (in units of pounds of mercury per ton of steel scrap or pounds of mercury per ton of product sinter) for all units subject to the emission standard for determining compliance. If the resulting mercury emissions are greater than the MACT emission standard, the owner or operator may use procedures that produce lower MDL results and repeat the mercury performance testing one additional time for any emission point for which the measured result was below the MDL. If this additional testing is performed, the results from that testing must be used to determine compliance (*i.e.*, there are no additional opportunities allowed to lower the MDL).

(3) For a primary emission control device applied to emissions from a BOPF with a closed hood system, sample only during the primary oxygen blow and do not sample during any subsequent reblows. Continue sampling for each run for an integral number of primary oxygen blows.

(4) For a primary emission control system applied to emissions from a BOPF with an open hood system and for a control device applied solely to secondary emissions from a BOPF, you must complete the requirements of paragraphs (b)(4)(i) and (ii) of this section:

(i) Sample only during the steel production cycle. Conduct sampling under

conditions that are representative of normal operation. Record the start and end time of each steel production cycle and each period of abnormal operation; and

(ii) Sample for an integral number of steel production cycles. The steel production cycle begins when the scrap is charged to the furnace and ends 3 minutes after the slag is emptied from the vessel into the slag pot.

(5) For a control device applied to emissions from BOPF shop ancillary operations (hot metal transfer, skimming, desulfurization, or ladle metallurgy), sample only when the operation(s) is being conducted.

(c) Calculate the mass emissions, based on the average of three test run values, for each BOPF Group unit (or combination of units that are ducted to a common stack and are tested when all affected sources are operating pursuant to paragraph (a) of this section) using equation 1 to this paragraph (c) as follows:

Equation 1 to paragraph (c)

$$E = \frac{C_s \times Q \times t}{454{,}000 \times 35.31} \quad \text{(Eq. 1)}$$

Where:

E = Mass emissions of pollutant, pounds (lb);
C_s = Concentration of pollutant in stack gas, mg/dscm;
454,000 = Conversion factor (mg/lb);
Q = Volumetric flow rate of stack gas, dscf/min;
35.31 = Conversion factor (dscf/dscm); and
t = Duration of test, minutes.

(d) You must install, calibrate, maintain, and operate an appropriate weight measurement device, to measure the tons of steel scrap input to the BOPF cycle simultaneous with each BOPF Group unit's stack test.

(e) You must maintain the systems for measuring weight within ±5 percent accuracy. You must describe the specific equipment used to make measurements at your facility and how that equipment is periodically calibrated. You must also explain, document, and maintain written procedures for determining the accuracy of the measurements and make these written procedures available to your permitting authority upon request. You must determine, record, and maintain a record of the accuracy of the measuring systems before the beginning of your initial compliance test and during each subsequent quarter of affected source operation.

(f) Calculate the emissions from each new and existing affected source in pounds of mercury per ton of steel scrap to determine initial compliance with the mercury emission limit in Table 1. Sum the mercury mass emissions (in pounds) from all BOPF Group units calculated using Equation 1 of this section. Divide that sum by the sum of the total amount of steel scrap charged to the BOPFs (in tons).

(g) To demonstrate compliance with the emission limit for hydrogen chloride in table 1 to this subpart through performance testing, follow the test methods and procedures in paragraphs (g)(1) through (3) of this section.

(1) Determine the concentration of hydrogen chloride according to the following test methods:

(i) The methods specified in paragraphs (b)(1)(i) through (iv) of this section, and

(ii) EPA Method 26A in appendix A–8 to part 60 of this chapter to determine the concentration of hydrogen chloride from the exhaust stream stack of each unit, with the following conditions; or

(A) Collect a minimum sample volume of 70 dscf (2 dscm) of gas during each run.

(B) [Reserved]

(iii) EPA Method 320 in appendix A to this part to determine the concentration of hydrogen chloride and hydrogen fluoride from the exhaust stream stack of each unit. Alternatively, ASTM

D6348–12(R2020), (incorporated by reference, see § 63.14) may be used with the following conditions:

(A) The test plan preparation and implementation in the Annexes to ASTM D 6348–12(R2020), Annexes A1 through A8 are mandatory; and

(B) In ASTM D6348–12(R2020) Annex A5 (Analyte Spiking Technique), the percent (%) R must be determined for each target analyte (Equation A5.5). In order for the test data to be acceptable for a compound, %R must be 70% ≥ R ≤ 130%. If the %R value does not meet this criterion for a target compound, the test data is not acceptable for that compound and the test must be repeated for that analyte (*i.e.*, the sampling and/or analytical procedure should be adjusted before a retest). The %R value for each compound must be reported in the test report, and all field measurements must be corrected with the calculated %R value for that compound by using the equation 2 o to this paragraph (g)(1)(iii)(B) as follows:

Equation 2 to paragraph (g)(1)(iii)(B)

$$Reported\ Results = \frac{C_S}{\%R} \times 100 \quad \text{(Eq. 2)}$$

Where

c_s = measured concentration in stack.

(2) At least three valid test runs are needed to comprise a performance test of each unit in table 1 to this subpart. If the performance testing results for any of the emission points yields a non-detect value, then the MDL must be used to calculate the mass emissions (lb) for that unit and, in turn, for calculating the emissions rate (lb/ton of product sinter, lb/ton of iron, or lb/ton of steel).

(3) Calculate the emissions from each new and existing affected source in pounds of hydrogen chloride per ton of throughput processed or unit of energy (tons of product sinter, tons of iron, tons of steel, or MMBtu) to determine initial compliance with the emission limits in table 1 to this subpart.

(h) To demonstrate compliance with the emission limit for carbonyl sulfide in table 1 to this subpart through performance testing, follow the test methods and procedures in paragraphs (h)(1) through (3) of this section.

(1) Determine the concentration of carbonyl sulfide according to the following test methods:

(i) The methods specified in paragraphs (b)(1)(i) through (iv) of this section, and

(ii) EPA Method 15 in appendix A–5 to part 60 of this chapter to determine the concentration of carbonyl sulfide from the exhaust stream stack of each unit; or

(iii) EPA Method 320 in appendix A to this part to determine the concentration of carbon disulfide and carbonyl sulfide from the exhaust stream stack of each unit. Alternatively, ASTM D6348–12 (R2020), (incorporated by reference, see § 63.14) may be used with the following conditions:

(A) The test plan preparation and implementation in the Annexes to ASTM D 6348–12 (R2020), Annexes A1 through A8 are mandatory; and

(B) In ASTM D6348–12 (R2020) Annex A5 (Analyte Spiking Technique), the percent (%) R must be determined for each target analyte (Equation A5.5). In order for the test data to be acceptable for a compound, %R must be 70% ≥ R ≤ 130%. If the %R value does not meet this criterion for a target compound, the test data is not acceptable for that compound and the test must be repeated for that analyte (*i.e.*, the sampling and/or analytical procedure should be adjusted before a retest). The %R value for each compound must be reported in the test report, and all field measurements must be corrected with the calculated %R value for that compound by using the Equation 2 of this section.

(2) Three valid test runs at least one hour in duration are needed to comprise a performance test of each unit in

table 1 to this subpart. If the performance testing results for any of the emission points yields a non-detect value, then the MDL must be used to calculate the mass emissions (lb) for that unit and, in turn, for calculating the emissions rate (lb/ton of product sinter).

(3) Calculate the emissions from each new and existing affected source in pounds of carbonyl sulfide per ton of product sinter to determine initial compliance with the emission limits in table 1 to this subpart .

(i) To demonstrate compliance with the emission limit for total hydrocarbons in table 1 to this subpart through performance testing, follow the test methods and procedures in paragraphs (i)(1) through (5) of this section.

(1) Determine the concentration of total hydrocarbons according to the following test methods:

(i) The methods specified in paragraphs (b)(1)(i) through (iv) of this section, and

(ii) EPA Method 25A in appendix A–7 to part 60 of this chapter to determine the concentration of total hydrocarbons as propane from the exhaust stream stack of each unit.

(2) Three valid test runs at least one hour in duration are needed to comprise a performance test of each unit in table 1 to this subpart. If the performance testing results for any of the emission points yields a non-detect value, then the MDL must be used to calculate the mass emissions (lb) for that unit and, in turn, for calculating the emissions rate (lb/ton of iron or lb/ton of steel).

(3) For BOPF tests, the test runs must include at least one full production cycle (from scrap charge to 3 minutes after slag is emptied from the vessel) for each run, except for BOPF with closed hood systems, where sampling should be performed only during the primary oxygen blow and only for 20 heat cycles.

(4) For blast furnaces, each test run duration must be a minimum of 1 hour.

(5) Calculate the emissions from each new and existing affected source in pounds of total hydrocarbons as propane per ton of throughput processed or unit of energy (tons of iron, tons of steel, or MMBtu) to determine initial compliance with the emission limits in table 1 to this subpart.

(j) To demonstrate compliance with the emission limit for D/F TEQ in table 1 to this subpart through performance testing, follow the test methods and procedures in paragraphs (j)(1) through (4) of this section.

(1) Determine the concentration of each dioxin and furan listed in table 5 to this subpart according to the following test methods:

(i) The methods specified in paragraphs (b)(1)(i) through (iv) of this section, and

(ii) EPA Method 23 in appendix A–7 to part 60 of this chapter to determine the concentration of each dioxin and furan listed in table 5 to this subpart from the exhaust stream stack of each unit. You must collect a minimum sample volume of 105 dscf (3 dscm) of gas during each test run.

(2) Three valid test runs are needed to comprise a performance test of each unit in table 1 to this subpart. For determination of TEQ, zero may be used in subsequent calculations for values less than the estimated detection limit (EDL). For estimated maximum pollutant concentration (EMPC) results, when the value is greater than the EDL, the EMPC value must be used in determination of TEQ, when the EMPC is less than the EDL, zero may be used.

(3) For BOPF tests, the test runs must include at least one full production cycle (from scrap charge to 3 minutes after slag is emptied from the vessel) for each run, except for BOPF with closed hood systems, where sampling should be performed only during the primary oxygen blow and only for 20 heat cycles or the collection of 105 dscf (3 dscm) sample volume, whichever is less.

(4) Calculate the sum of the D/F TEQ per ton of throughput processed (tons of product sinter or tons of steel) to determine initial compliance with the emission limits in table 1 using equation 3 to this paragraph (j)(4) as follows:

Equation 3 to paragraph (j)(4)

$$TEQ = \frac{\sum_{i=1}^{n}(M_i \times TEF_i)}{T_r \times P} \text{ (Eq. 3)}$$

Where:

TEQ = sum of the 2,3,7,8-TCDD TEQs, lb/ton of throughput processed

M_i = mass of dioxin or furan cogener i during performance test run, lbs

TEF_i = 2,3,7,8-TCDD toxic equivalency factor (TEF) for cogener i, as provided in Table 5 of this subpart

n = number of cogeners included in TEQ

T_r = time of performance test run, hours

P = production rate during performance test run, tons of throughput processed per hour.

(k) To demonstrate compliance with the emission limit for polycyclic aromatic hydrocarbons in table 1 to this subpart through performance testing, follow the test methods and procedures in paragraphs (k)(1) through (3) of this section.

(1) Determine the concentration of each polycyclic aromatic hydrocarbon listed in table 6 to this subpart according to the following test methods:

(i) The methods specified in paragraphs (b)(1)(i) through (iv) of this section, and

(ii) EPA Method 23 in appendix A–7 to part 60 of this chapter to determine the concentration of each polycyclic aromatic hydrocarbon listed in table 6 to this subpart from the exhaust stream stack of each unit. You must collect a minimum sample volume of 105 dscf (3 dscm) of gas during each test run.

(2) Three valid test runs are needed to comprise a performance test of each unit in table 1 to this subpart. If the performance testing results for any of the emission points yields a non-detect value, then the EDL must be used to calculate the mass emissions (lb) for that unit and, in turn, for calculating the emissions rate (lb/ton of product sinter).

(3) Calculate the sum of polycyclic aromatic hydrocarbons per ton of product sinter to determine initial compliance with the emission limits in table 1 to this subpart using equation 4 to this paragraph (k)(3) as follows:

Equation 4 to paragraph (k)(3)

$$E = \frac{\sum_{i=1}^{n} M_i}{T_r \times P} \text{ (Eq. 4)}$$

Where:

E = emission rate of polycyclic aromatic hydrocarbons, lb/ton of sinter

M_i = mass of polycyclic aromatic hydrocarbon i, as provided in Table 6 to this subpart, during performance test run, lbs

n = number of polycyclic aromatic hydrocarbons included in emissions

T_r = time of performance test run, hours

P = production rate during performance test run, tons of product sinter per hour.

[85 FR 42119, July 13, 2020, as amended at 89 FR 23325, Apr. 3, 2024]

§ 63.7826 How do I demonstrate initial compliance with the emission limitations that apply to me?

(a) For each affected source subject to an emission or opacity limit in Table 1 to this subpart, you have demonstrated initial compliance if:

(1) You meet the conditions in Table 2 to this subpart; and

(2) For each capture system subject to the operating limit in § 63.7790(b)(1), you have established appropriate site-specific operating limit(s) and have a record of the operating parameter data

measured during the performance test in accordance with § 63.7824(a)(1); and

(3) For each venturi scrubber subject to the operating limits for pressure drop and scrubber water flow rate in § 63.7790(b)(2), you have established appropriate site-specific operating limits and have a record of the pressure drop and scrubber water flow rate measured during the performance test in accordance with § 63.7824(b).

(b) For each existing or new sinter plant subject to the operating limit in § 63.7790(d)(1), you have demonstrated initial compliance if the 30-day rolling average of the oil content of the feedstock, measured during the initial performance test in accordance with § 63.7824(d) is no more than 0.02 percent. For each existing or new sinter plant subject to the alternative operating limit in § 63.7790(d)(2), you have demonstrated initial compliance if the 30-day rolling average of the volatile organic compound emissions from the sinter plant windbox exhaust stream, measured during the initial performance test in accordance with § 63.7824(e) is no more than 0.2 lb/ton of sinter produced.

(c) For each emission limitation that applies to you, you must submit a notification of compliance status according to § 63.7840(e).

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006. Redesignated at 85 FR 42119, July 13, 2020]

§ 63.7827 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

(a) For a capture system applied to emissions from a sinter plant discharge end or blast furnace casthouse or to secondary emissions from a BOPF, you have demonstrated initial compliance if you meet all of the conditions in paragraphs (a)(1) through (4) of this section.

(1) Prepared the capture system operation and maintenance plan according to the requirements of § 63.7800(b), including monthly inspection procedures and detailed descriptions of the operating parameter(s) selected to monitor the capture system;

(2) Certified in your performance test report that the system operated during the test at the operating limits established in your operation and maintenance plan;

(3) Submitted a notification of compliance status according to the requirements in § 63.7840(e), including a copy of the capture system operation and maintenance plan and your certification that you will operate the capture system at the values or settings established for the operating limits in that plan; and

(4) Prepared a site-specific monitoring plan according to the requirements in § 63.7831(a).

(b) For each control device subject to operating limits in § 63.7790(b)(2) or (3), you have demonstrated initial compliance if you meet all the conditions in paragraphs (b)(1) through (3) of this section.

(1) Prepared the control device operation and maintenance plan according to the requirements of § 63.7800(b), including a preventative maintenance schedule and, as applicable, detailed descriptions of the corrective action procedures for baghouses and other control devices;

(2) Submitted a notification of compliance status according to the requirements in § 63.7840(e), including a copy of the operation and maintenance plan; and

(3) Prepared a site-specific monitoring plan according to the requirements in § 63.7831(a).

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006. Redesignated at 85 FR 42119, July 13, 2020]

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.7830 What are my monitoring requirements?

(a) For each capture system subject to an operating limit in § 63.7790(b)(1) established in your capture system operation and maintenance plan, you must install, operate, and maintain a CPMS according to the requirements in § 63.7831(e) and the requirements in paragraphs (a)(1) through (3) of this section.

(1) Dampers that are manually set and remain in the same position are exempt from the requirement to install and operate a CPMS. If dampers are not manually set and remain in the

same position, you must make a visual check at least once every 24 hours to verify that each damper for the capture system is in the same position as during the initial performance test.

(2) If you use a flow measurement device to monitor the operating limit parameter for a sinter plant discharge end or blast furnace casthouse, you must monitor the hourly average rate (*e.g.*, the hourly average actual volumetric flow rate through each separately ducted hood, the average hourly total volumetric flow rate at the inlet to the control device) according to the requirements in § 63.7832.

(3) If you use a flow measurement device to monitor the operating limit parameter for a capture system applied to secondary emissions from a BOPF, you must monitor the average rate for each steel production cycle (*e.g.*, the average actual volumetric flow rate through each separately ducted hood for each steel production cycle, the average total volumetric flow rate at the inlet to the control device for each steel production cycle) according to the requirements in § 63.7832.

(b) Except as provided in paragraph (b)(3) of this section, you must meet the requirements in paragraph (b)(1) or (2) of this section for each baghouse applied to meet any particulate emission limit in Table 1 to this subpart. You must conduct inspections of each baghouse according to the requirements in paragraph (b)(4) of this section.

(1) Install, operate, and maintain a bag leak detection system according to § 63.7831(f) and monitor the relative change in particulate matter loadings according to the requirements in § 63.7832; or

(2) If you do not install and operate a bag leak detection system, you must install, operate, and maintain a COMS according to the requirements in § 63.7831(h) and monitor the hourly average opacity of emissions exiting each control device stack according to the requirements in § 63.7832.

(3) A bag leak detection system and COMS are not required for a baghouse that meets the requirements in paragraphs (b)(3)(i) and (ii) of this section.

(i) The baghouse is a positive pressure baghouse and is not equipped with exhaust gas stacks; and

(ii) The baghouse was installed before August 30, 2005.

(4) You must conduct inspections of each baghouse at the specified frequencies according to the requirements in paragraphs (b)(4)(i) through (viii) of this section.

(i) Monitor the pressure drop across each baghouse cell each day to ensure pressure drop is within the normal operating range identified in the manual.

(ii) Confirm that dust is being removed from hoppers through weekly visual inspections or other means of ensuring the proper functioning of removal mechanisms.

(iii) Check the compressed air supply for pulse-jet baghouses each day.

(iv) Monitor cleaning cycles to ensure proper operation using an appropriate methodology.

(v) Check bag cleaning mechanisms for proper functioning through monthly visual inspection or equivalent means.

(vi) Make monthly visual checks of bag tension on reverse air and shaker-type baghouses to ensure that bags are not kinked (kneed or bent) or laying on their sides. You do not have to make this check for shaker-type baghouses using self-tensioning (spring-loaded) devices.

(vii) Confirm the physical integrity of the baghouse through quarterly visual inspections of the baghouse interior for air leaks.

(viii) Inspect fans for wear, material buildup, and corrosion through quarterly visual inspections, vibration detectors, or equivalent means.

(c) For each venturi scrubber subject to the operating limits for pressure drop and scrubber water flow rate in § 63.7790(b)(2), you must install, operate, and maintain CPMS according to the requirements in § 63.7831(g) and monitor the hourly average pressure drop and water flow rate according to the requirements in § 63.7832.

(d) For each electrostatic precipitator subject to the opacity operating limit in § 63.7790(b)(3), you must install, operate, and maintain a COMS according to the requirements in § 63.7831(h)

and monitor the hourly average opacity of emissions exiting each control device stack according to the requirements in § 63.7832.

(e) For each sinter plant subject to the operating limit in § 63.7790(d), you must either:

(1) Compute and record the 30-day rolling average of the oil content of the feedstock for each operating day using the procedures in § 63.7824(d); or

(2) Compute and record the 30-day rolling average of the volatile organic compound emissions (lbs/ton of sinter) for each operating day using the procedures in § 63.7824(e).

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006; 89 FR 23327, Apr. 3, 2024]

§ 63.7831 What are the installation, operation, and maintenance requirements for my monitors?

(a) For each CPMS required in § 63.7830, you must develop and make available for inspection upon request by the permitting authority a site-specific monitoring plan that addresses the requirements in paragraphs (a)(1) through (8) of this section.

(1) Installation of the CPMS sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last control device);

(2) Performance and equipment specifications for the sample interface, the parametric signal analyzer, and the data collection and reduction system;

(3) Performance evaluation procedures and acceptance criteria (*e.g.*, calibrations);

(4) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, ongoing operation and maintenance procedures in accordance with the general requirements of § 63.8(c)(1)(ii), (c)(3), (c)(4)(ii), and (c)(7) and (8). After January 11, 2021 for each such source, and after July 13, 2020 for new and reconstructed sources for which construction or reconstruction commenced after August 16, ongoing operation and maintenance procedures in accordance with the general requirements of § 63.8(c)(1)(ii), (c)(3), (c)(4)(ii), and (c)(7) and (8);

(5) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d). After January 11, 2021 for each such source, and after July 13, 2020 for new and reconstructed sources for which construction or reconstruction commenced after August 16, 2019, ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d) except for the requirements related to startup, shutdown, and malfunction plans referenced in § 63.8(d)(3). The owner or operator shall keep these written procedures on record for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan is revised, the owner or operator shall keep previous (*i.e.*, superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action should be included in the plan required under § 63.8(d)(2);

(6) On or before January 11, 2021, for each existing source, and for each new or reconstructed source for which construction or reconstruction commenced on or before August 16, 2019, ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c)(1) through (14), (e)(1), and (e)(2)(i). After January 11, 2021 for each such source, and after July 13, 2020 for new and reconstructed sources for which construction or reconstruction commenced after August 16, 2019, ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c)(1) through (14), (e)(1), and (e)(2)(i);

(7) Corrective action procedures you will follow in the event a venturi scrubber exceeds the operating limit in § 63.7790(b)(2); and

(8) Corrective action procedures you will follow in the event an electrostatic precipitator exceeds the operating limit in § 63.7790(b)(3).

(b) Unless otherwise specified, each CPMS must:

(1) Complete a minimum of one cycle of operation for each successive 15-minute period and collect a minimum of three of the required four data points to constitute a valid hour of data;

(2) Provide valid hourly data for at least 95 percent of every averaging period; and

(3) Determine and record the hourly average of all recorded readings.

(c) You must conduct a performance evaluation of each CPMS in accordance with your site-specific monitoring plan.

(d) You must operate and maintain the CPMS in continuous operation according to the site-specific monitoring plan.

(e) For each capture system subject to an operating limit in § 63.7790(b)(1), you must install, operate, and maintain each CPMS according to the requirements in paragraphs (a) through (d) of this section.

(f) For each baghouse equipped with a bag leak detection system according to § 63.7830(b)(1), you must install, operate, and maintain the bag leak detection system according to the requirements in paragraphs (f)(1) through (7) of this section.

(1) The system must be certified by the manufacturer to be capable of detecting emissions of particulate matter at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The system must provide output of relative changes in particulate matter loadings.

(3) The system must be equipped with an alarm that will sound when an increase in relative particulate loadings is detected over a preset level. The alarm must be located such that it can be heard by the appropriate plant personnel.

(4) Each system that works based on the triboelectric effect must be installed, operated, and maintained in a manner consistent with the guidance document, ''Fabric Filter Bag Leak Detection Guidance,'' EPA–454/R–98–015 (incorporated by reference, see § 63.14). You may install, operate, and maintain other types of bag leak detection systems in a manner consistent with the manufacturer's written specifications and recommendations.

(5) To make the initial adjustment of the system, establish the baseline output by adjusting the sensitivity (range) and the averaging period of the device. Then, establish the alarm set points and the alarm delay time.

(6) Following the initial adjustment, do not adjust the sensitivity or range, averaging period, alarm set points, or alarm delay time, except as detailed in your operation and maintenance plan. Do not increase the sensitivity by more than 100 percent or decrease the sensitivity by more than 50 percent over a 365-day period unless a responsible official certifies, in writing, that the baghouse has been inspected and found to be in good operating condition.

(7) Where multiple detectors are required, the system's instrumentation and alarm may be shared among detectors.

(g) For each venturi scrubber subject to operating limits in § 63.7790(b)(2) for pressure drop and scrubber water flow rate, you must install, operate, and maintain each CPMS according to the requirements in paragraphs (a) through (d) of this section.

(h) For each electrostatic precipitator subject to the opacity operating limit in § 63.7790(b)(3) and each baghouse equipped with a COMS according to § 63.7830(b)(2), you must install, operate, and maintain each COMS according to the requirements in paragraphs (h)(1) through (4) of this section.

(1) You must install, operate, and maintain each COMS according to Performance Specification 1 in 40 CFR part 60, appendix B.

(2) You must conduct a performance evaluation of each COMS according to § 63.8 and Performance Specification 1 in appendix B to 40 CFR part 60.

(3) Each COMS must complete a minimum of one cycle of sampling and analyzing for each successive 10-second period and one cycle of data recording for each successive 6-minute period.

(4) COMS data must be reduced to 6-minute averages as specified in §63.8(g)(2) and to hourly averages where required by this subpart.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39587, July 13, 2006; 85 FR 42120, July 13, 2020]

EDITORIAL NOTE: At 85 FR 44992, July 24, 2020, the amendment to §63.7831(f)(4) could not be incorporated due to an inaccurate instruction.

§63.7832 How do I monitor and collect data to demonstrate continuous compliance?

(a) Except for monitoring malfunctions, out-of-control periods as specified in §63.8(c)(7), associated repairs, and required quality assurance or control activities (including as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times an affected source is operating.

(b) You may not use data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities in data averages and calculations used to report emission or operating levels or to fulfill a minimum data availability requirement, if applicable. You must use all the data collected during all other periods in assessing compliance.

(c) A monitoring malfunction is any sudden, infrequent, not reasonably preventable failure of the monitoring to provide valid data. Monitoring failures that are caused in part by poor maintenance or careless operation are not malfunctions.

§63.7833 How do I demonstrate continuous compliance with the emission limitations that apply to me?

(a) You must demonstrate continuous compliance for each affected source subject to an emission or opacity limit in §63.7790(a) by meeting the requirements in Table 3 to this subpart.

(b) You must demonstrate continuous compliance for each capture system subject to an operating limit in §63.7790(b)(1) by meeting the requirements in paragraphs (b)(1) and (2) of this section.

(1) Operate the capture system at or above the lowest values or settings established for the operating limits in your operation and maintenance plan; and

(2) Monitor the capture system according to the requirements in §63.7830(a) and collect, reduce, and record the monitoring data for each of the operating limit parameters according to the applicable requirements of this subpart;

(c) For each baghouse applied to meet any particulate emission limit in Table 1 to this subpart, you must demonstrate continuous compliance by meeting the requirements in paragraph (c)(1) or (2) of this section as applicable, and paragraphs (c)(3) and (4) of this section:

(1) For a baghouse equipped with a bag leak detection system, operating and maintaining each bag leak detection system according to §63.7831(f) and recording all information needed to document conformance with these requirements. If you increase or decrease the sensitivity of the bag leak detection system beyond the limits specified in §63.7831(f)(6), you must include a copy of the required written certification by a responsible official in the next semiannual compliance report.

(2) For a baghouse equipped with a COMS, operating and maintaining each COMS and reducing the COMS data according to §63.7831(h).

(3) Inspecting each baghouse according to the requirements in §63.7830(b)(4) and maintaining all records needed to document conformance with these requirements.

(4) Maintaining records of the time you initiated corrective action in the event of a bag leak detection system alarm or when the hourly average opacity exceeded 5 percent, the corrective action(s) taken, and the date on which corrective action was completed.

(d) For each venturi scrubber subject to the operating limits for pressure drop and scrubber water flow rate in §63.7790(b)(2), you must demonstrate continuous compliance by meeting the requirements of paragraphs (d)(1) through (4) of this section:

(1) Maintaining the hourly average pressure drop and scrubber water flow

rate at levels no lower than those established during the initial or subsequent performance test;

(2) Operating and maintaining each venturi scrubber CPMS according to § 63.7831(g) and recording all information needed to document conformance with these requirements; and

(3) Collecting and reducing monitoring data for pressure drop and scrubber water flow rate according to § 63.7831(b) and recording all information needed to document conformance with these requirements.

(4) If the hourly average pressure drop or scrubber water flow rate is below the operating limits, you must follow the corrective action procedures in paragraph (g) of this section.

(e) For each electrostatic precipitator subject to the opacity operating limit in § 63.7790(b)(3), you must demonstrate continuous compliance by meeting the requirements of paragraphs (e)(1) through (3) of this section:

(1) Maintaining the hourly average opacity of emissions no higher than 10 percent; and

(2) Operating and maintaining each COMS and reducing the COMS data according to § 63.7831(h).

(3) If the hourly average opacity of emissions exceeds 10 percent, you must follow the corrective action procedures in paragraph (g) of this section.

(f) For each new or existing sinter plant subject to the operating limit in § 63.7790(d), you must demonstrate continuous compliance by either:

(1) For the sinter plant feedstock oil content operating limit in § 63.7790(d)(1),

(i) Computing and recording the 30-day rolling average of the percent oil content for each operating day according to the performance test procedures in § 63.7824(d);

(ii) Recording the sampling date and time, oil content values, and sinter produced (tons/day); and

(iii) Maintaining the 30-day rolling average oil content of the feedstock no higher than 0.02 percent.

(2) For the volatile organic compound operating limit in § 63.7790(d)(2),

(i) Computing and recording the 30-day rolling average of the volatile organic compound emissions for each operating day according to the performance test procedures in § 63.7824(e);

(ii) Recording the sampling date and time, sampling values, and sinter produced (tons/day); and

(iii) Maintaining the 30-day rolling average of volatile organic compound emissions no higher than 0.2 lb/ton of sinter produced.

(g) If the hourly average pressure drop or water flow rate for a venturi scrubber or hourly average opacity for an electrostatic precipitator exceeds the operating limit, you must follow the procedures in paragraphs (g)(1) through (4) of this section.

(1) You must initiate corrective action to determine the cause of the exceedance within 1 hour. During any period of corrective action, you must continue to monitor and record all required operating parameters for equipment that remains in operation. Within 24 hours of the exceedance, you must measure and record the hourly average operating parameter value for the emission unit on which corrective action was taken. If the hourly average parameter value meets the applicable operating limit, then the corrective action was successful and the emission unit is in compliance with the applicable operating limit.

(2) If the initial corrective action required in paragraph (g)(1) of this section was not successful, you must complete additional corrective action within the next 24 hours (48 hours from the time of the exceedance). During any period of corrective action, you must continue to monitor and record all required operating parameters for equipment that remains in operation. After this second 24-hour period, you must again measure and record the hourly average operating parameter value for the emission unit on which corrective action was taken. If the hourly average parameter value meets the applicable operating limit, then the corrective action was successful and the emission unit is in compliance with the applicable operating limit.

(3) For purposes of paragraphs (g)(1) and (2) of this section, in the case of an exceedance of the hourly average opacity operating limit for an electrostatic precipitator, measurements of the hourly average opacity based on visible

emission observations in accordance with EPA Method 9 (in appendix A–4 to part 60) may be taken to evaluate the effectiveness of corrective action. ASTM D7520–16 (incorporated by reference, see § 63.14) may be used with the following conditions:

(i) During the DCOT certification procedure outlined in Section 9.2 of ASTM D7520–16 (incorporated by reference, see § 63.14), the owner or operator or the DCOT vendor must present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand).

(ii) The owner or operator must also have standard operating procedures in place including daily or other frequency quality checks to ensure the equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16 (incorporated by reference, see § 63.14).

(iii) The owner or operator must follow the recordkeeping procedures outlined in § 63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination.

(iv) The owner or operator or the DCOT vendor must have a minimum of four independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15-percent opacity of anyone reading and the average error must not exceed 7.5-percent opacity.

(v) Use of this approved alternative does not provide or imply a certification or validation of any vendor's hardware or software. The onus to maintain and verify the certification and/or training of the DCOT camera, software, and operator in accordance with ASTM D7520–16 (incorporated by reference, see § 63.14) and these requirements is on the facility, DCOT operator, and DCOT vendor.

(4) If the second attempt at corrective action required in paragraph (g)(2) of this section was not successful, you must report the exceedance as a deviation in your next semiannual compliance report according to § 63.7841(b).

(h) If you are demonstrating compliance with the mercury emission limits in Table 1 of this section for your BOPF Groups through performance testing, you must conduct mercury performance tests in accordance with §§ 63.7821(e) and 63.7825 and calculate the emissions from each new and existing affected source in pounds of mercury per ton of steel scrap to determine compliance with the mercury emission limits in Table 1. Sum the mercury mass emissions (in pounds) from all BOPF Group units calculated using Equation 1 of § 63.7825. Divide that sum by the sum of the total amount of steel scrap charged to the BOPFs (in tons).

(i) If you are demonstrating compliance with the mercury emission limits in Table 1 of this section for your BOPF Groups by certifying participation in the NVMSRP or another EPA-approved mercury program, or by using scrap that does not contain mercury switches, you must obtain and certify your use of steel scrap per § 63.7791(c), (d), or (e), as applicable, and § 63.7841(b)(11) to demonstrate continuous compliance with the standard.

(j) For large bells on each blast furnace, you must demonstrate continuous compliance by following the requirements specified in paragraphs (j)(1) and (2) of this section if a bell seal exceeds a 20 percent average of 3 instantaneous opacity readings of the interbell relief valve emissions.

(1) Initiate corrective action within five business days.

(2) Ten business days after the initial opacity exceedance of 20 percent, if the average of 3 instantaneous visible emissions readings from this test exceeds 20 percent, you must repair or replace that bell seal within 4 months.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39587, July 13, 2006; 85 FR 42120, July 13, 2020; 89 FR 23327, Apr. 3, 2024]

§ 63.7834 How do I demonstrate continuous compliance with the operation and maintenance requirements that apply to me?

(a) For each capture system and control device subject to an operating limit in § 63.7790(b), you must demonstrate continuous compliance with

the operation and maintenance requirements in § 63.7800(b) by meeting the requirements of paragraphs (a)(1) through (4) of this section:

(1) Making monthly inspections of capture systems and initiating corrective action according to § 63.7800(b)(1) and recording all information needed to document conformance with these requirements;

(2) Performing preventative maintenance according to § 63.7800(b)(2) and recording all information needed to document conformance with these requirements;

(3) Initiating and completing corrective action for a baghouse equipped with a bag leak detection system or COMS according to § 63.7800(b)(4) and recording all information needed to document conformance with these requirements, including the time you initiated corrective action, the corrective action(s) taken, and date on which corrective action was completed.

(4) Initiating and completing corrective action for a venturi scrubber equipped with a CPMS or an electrostatic precipitator equipped with a COMS according to § 63.7833(g) and recording all information needed to document conformance with these requirements, including the time you initiated corrective action, the corrective action(s) taken within the first 24 hours according to § 63.7833(g)(1) and whether they were successful, the corrective action(s) taken within the second 24 hours according to § 63.7833(g)(2) and whether they were successful, and the date on which corrective action was completed.

(b) You must maintain a current copy of the operation and maintenance plan required in § 63.7800(b) onsite and available for inspection upon request. You must keep the plans for the life of the affected source or until the affected source is no longer subject to the requirements of this subpart.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39588, July 13, 2006]

§ 63.7835 What other requirements must I meet to demonstrate continuous compliance?

Except as provided in § 63.7833(g), you must report each instance in which you did not meet each emission limitation in § 63.7790 that applies to you. This includes periods of startup, shutdown, and malfunction. You also must report each instance in which you did not meet each operation and maintenance requirement in § 63.7800 that applies to you. These instances are deviations from the emission limitations and operation and maintenance requirements in this subpart. These deviations must be reported according to the requirements in § 63.7841.

(a) In the event that an affected unit fails to meet an applicable standard, record the date, time, and duration of each failure.

(b) For each failure to meet an applicable standard, record and retain a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(c) Record actions taken to minimize emissions in accordance with § 63.7810(d), and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(d) For existing sources and for new or reconstructed sources which commenced construction or reconstruction on or before August 16, 2019, before January 11, 2021, consistent with §§ 63.6(e) and 63.7(e)(1), deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with § 63.6(e)(1). The Administrator will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in § 63.6(e). After January 11, 2021 for such sources, and after July 13, 2020 for new and reconstructed sources which commence construction or reconstruction after August 16, 2019, the exemptions for periods of startup, shutdown, and malfunction in § 63.6(e) no longer apply.

[85 FR 42121, July 13, 2020]

NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.7840 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.6(h)(4) and (5), 63.7(b)

and (c), 63.8(e) and (f)(4), and 63.9(b) through (h) that apply to you by the specified dates.

(b) As specified in § 63.9(b)(2), if you startup your affected source before May 20, 2003, you must submit your initial notification no later than September 17, 2003, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) As specified in § 63.9(b)(3), if you start your new affected source on or after May 20, 2003, you must submit your initial notification no later than 120 calendar days after you become subject to this subpart.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required in § 63.7(b)(1). For the first mercury compliance test in the BOPF Group for anyone sequence of tests, you must include a schedule of all subsequent tests in the BOPF Group in the test series.

(e) If you are required to conduct a performance test, opacity observation, or other initial compliance demonstration, you must submit a notification of compliance according to § 63.9(h)(2)(ii), except that for the purposes of submitting the notification of compliance status for BOPF Group mercury testing, the performance test shall be considered complete when the final unit or control device in the BOPF Group in the sequence is tested.

(1) For each initial compliance demonstration that does not include a performance test, you must submit the notification of compliance status before the close of business on the 30th calendar day following completion of the initial compliance demonstration.

(2) For each initial compliance demonstration that includes a performance test, you must submit the notification of compliance status, including the summary of performance test results, before the close of business on the 60th calendar day following the completion of the performance test according to § 63.10(d)(2).

(f) The notification of compliance status required by §§ 63.9(b) and (h) and 63.7826(c) must include each applicable certification of compliance, signed by a responsible official, in paragraphs (f)(1) and (2) of this section, regarding the mercury requirements, as applicable, in § 63.7791(c) through (e).

(1) ''This facility participates in and purchases scrap only from scrap providers who participate in a program for removal of mercury switches that has been approved by the EPA Administrator, in accordance with § 63.7791(c) or (e)''; or

(2) ''This facility complies with the requirements for scrap that does not contain mercury switches, in accordance with § 63.7791(d).''

(g) Within 60 calendar days after the date of completing each performance test required by this subpart, you must submit the results of the performance test following the procedures specified in paragraphs (g)(1) through (3) of this section. Where applicable, you may assert a claim of EPA system outage, in accordance with § 63.7841(e), or force majeure, in accordance with § 63.7841(f), for failure to timely comply with this requirement.

(1) Data collected using test methods supported by EPA's Electronic Reporting Tool (ERT) as listed on EPA's ERT website (*https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert*) at the time of the test. Submit the results of the performance test to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). The data must be submitted in a file format generated through the use of EPA's ERT. Alternatively, you may submit an electronic file consistent with the extensible markup language (XML) schema listed on EPA's ERT website.

(2) Data collected using test methods that are not supported by EPA's ERT as listed on EPA's ERT website at the time of the test. The results of the performance test must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) [Reserved]

(h) Within 60 calendar days after the date of completing each continuous monitoring system (CMS) performance

evaluation (as defined in § 63.2), you must submit the results of the performance evaluation following the procedures specified in paragraphs (h)(1) through (3) of this section. Where applicable, you may assert a claim of EPA system outage, in accordance with § 63.7841(e), or force majeure, in accordance with § 63.7841(f), for failure to timely comply with this requirement.

(1) Performance evaluations of CMS measuring relative accuracy test audit (RATA) pollutants that are supported by EPA's ERT as listed on EPA's ERT website at the time of the evaluation. Submit the results of the performance evaluation to the EPA via CEDRI, which can be accessed through EPA's CDX. The data must be submitted in a file format generated through the use of EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on EPA's ERT website.

(2) Performance evaluations of CMS measuring RATA pollutants that are not supported by EPA's ERT as listed on EPA's ERT website at the time of the evaluation. The results of the performance evaluation must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) [Reserved]

(i) Confidential business information (CBI): For notifications and reports required to be submitted to CEDRI:

(1) The EPA will make all the information submitted through CEDRI available to the public without further notice to you. Do not use CEDRI to submit information you claim as CBI. Although we do not expect persons to assert a claim of CBI, if you wish to assert a CBI claim for some of the information submitted under paragraph (h) of this section, you must submit a complete file, including information claimed to be CBI, to the EPA.

(2) The file must be generated using the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website.

(3) Clearly mark the part or all of the information that you claim to be CBI. Information not marked as CBI may be authorized for public release without prior notice. Information marked as CBI will not be disclosed except in accordance with procedures set forth in 40 CFR part 2.

(4) The preferred method to receive CBI is for it to be transmitted electronically using email attachments, File Transfer Protocol, or other online file sharing services. Electronic submissions must be transmitted directly to the OAQPS CBI Office at the email address *oaqpscbi@epa.gov*, and as described above, should include clear CBI markings and be flagged to the attention of the Group Leader, Measurement Policy Group. If assistance is needed with submitting large electronic files that exceed the file size limit for email attachments, and if you do not have your own file sharing service, please email *oaqpscbi@epa.gov* to request a file transfer link.

(5) If you cannot transmit the file electronically, you may send CBI information through the postal service to the following address: OAQPS Document Control Officer (C404–02), OAQPS, U.S. Environmental Protection Agency, Research Triangle Park, North Carolina 27711, Attention Group Leader, Measurement Policy Group. The mailed CBI material should be double wrapped and clearly marked. Any CBI markings should not show through the outer envelope.

(6) All CBI claims must be asserted at the time of submission. Anything submitted using CEDRI cannot later be claimed CBI. Furthermore, under CAA section 114(c), emissions data is not entitled to confidential treatment, and the EPA is required to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

(7) You must submit the same file submitted to the CBI office with the CBI omitted to the EPA via the EPA's CDX as described in paragraphs (g) or (h) of this section.

[68 FR 27663, May 20, 2003, as amended at 85 FR 42121, July 13, 2020; 85 FR 73913, Nov. 19, 2020; 89 FR 23327, Apr. 3, 2024]

§ 63.7841 What reports must I submit and when?

(a) *Compliance report due dates.* Unless the Administrator has approved a different schedule, you must submit a semiannual compliance report to your permitting authority according to the requirements in paragraphs (a)(1) through (5) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.7783 and ending on June 30 or December 31, whichever date comes first after the compliance date that is specified for your source in § 63.7783.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after your first compliance report is due.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after the end of the semiannual reporting period.

(5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of according to the dates in paragraphs (a)(1) through (4) of this section.

(b) *Compliance report contents.* Each compliance report must include the information in paragraphs (b)(1) through (3) of this section and, as applicable, paragraphs (b)(4) through (13) of this section.

(1) Company name and address.

(2) Statement by a responsible official, with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) For existing sources and for new or reconstructed sources for which construction or reconstruction commenced on or before August 16, 2019, before January 11, 2021, if you had a startup, shutdown, or malfunction during the reporting period and you took actions consistent with your startup, shutdown, and malfunction plan, the compliance report must include the information in § 63.10(d)(5)(i). A startup, shutdown, and malfunction plan and the information in § 63.10(d)(5)(i) is not required after January 11, 2021.

(5) If there were no deviations from the continuous compliance requirements in §§ 63.7833 and 63.7834 that apply to you, a statement that there were no deviations from the emission limitations or operation and maintenance requirements during the reporting period.

(6) If there were no periods during which a continuous monitoring system (including a CPMS, COMS, or continuous emission monitoring system (CEMS) was out-of-control as specified in § 63.8(c)(7), a statement that there were no periods during which the CPMS was out-of-control during the reporting period.

(7) For each deviation from an emission limitation in § 63.7790 that occurs at an affected source where you are not using a continuous monitoring system (including a CPMS, COMS, or CEMS) to comply with an emission limitation in this subpart, the compliance report must contain the information in paragraphs (b)(1) through (4) of this section, the information in paragraphs (b)(7)(i) and (ii) of this section, and the information in (b)(13) of this section. This includes periods of startup, shutdown, and malfunction.

(i) The total operating time of each affected source during the reporting period.

(ii) Information on the duration and cause of deviations (including unknown cause, if applicable) as applicable and the corrective action taken.

(8) For each deviation from an emission limitation occurring at an affected source where you are using a continuous monitoring system (including a CPMS or COMS) to comply with

the emission limitation in this subpart, you must include the information in paragraphs (b)(1) through (4) of this section, the information in paragraphs (b)(8)(i) through (xi) of this section, and the information in (b)(13) of this section. This includes periods of malfunction.

(i) The date and time that each malfunction started and stopped.

(ii) The date, time, and duration that each continuous monitoring was inoperative, except for zero (low-level) and high-level checks.

(iii) The date, time, and duration that each continuous monitoring system was out-of-control as specified in §63.8(c)(7), including the information in §63.8(c)(8).

(iv) The date and time that each deviation started and stopped, and whether each deviation occurred during a malfunction or during another period.

(v) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.

(vi) A breakdown of the total duration of the deviations during the reporting period including those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(vii) A summary of the total duration of continuous monitoring system downtime during the reporting period and the total duration of continuous monitoring system downtime as a percent of the total source operating time during the reporting period.

(viii) A brief description of the process units.

(ix) A brief description of the continuous monitoring system.

(x) The date of the latest continuous monitoring system certification or audit.

(xi) A description of any changes in continuous monitoring systems, processes, or controls since the last reporting period.

(9) Any deviation from the requirements in §63.7791 and the corrective action taken. For each deviation, you must include the information in (b)(13) of this section.

(10) If there were no deviations from the requirements in §63.7791, a statement that there were no deviations from the requirements during the reporting period.

(11) If the facility demonstrates compliance with the mercury emission limits in Table 1 through the compliance options in §63.7791(c), (d), or (e), the report must contain the applicable statement in paragraphs (b)(11)(i) and (ii) of this section, as applicable.

(i) ''This facility participates in and purchases scrap only from scrap providers who participate in a program for removal of mercury switches that has been approved by the EPA Administrator, in accordance with §63.7791(c) or (e)''; or

(ii) ''This facility complies with the requirements for scrap that does not contain mercury switches, in accordance with §63.7791(d).''

(12) For existing sources and for new or reconstructed sources which commenced construction or reconstruction on or before August 16, 2019, before January 11, 2021, for each startup, shutdown, or malfunction during the reporting period that is not consistent with your startup, shutdown, and malfunction plan you must submit an immediate startup, shutdown and malfunction report. Unless the Administrator has approved a different schedule for submission of reports under §63.10(a), you must submit each report according to paragraphs (f)(1) and (2) of this section. An immediate startup, shutdown, and malfunction report is not required after January 11, 2021.

(13) Beginning on January 11, 2021 if you failed to meet an applicable standard, the compliance report must include the start date, start time, and duration of each failure. For each failure, the compliance report must include a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, and a description of the method used to estimate the emissions.

(14) For each unplanned bleeder valve opening for each blast furnace, you must include the information in paragraphs (b)(14)(i) through (iii) of this section.

(i) The date and time of the event.

(ii) The duration of the event.

(iii) Any corrective actions taken in response to the event.

(c) *Use of CEDRI template.* Beginning on January 11, 2021 or 180 days after the date the reporting template becomes available in CEDRI, whichever is later, submit all subsequent reports following the procedure specified in paragraph (d) of this section.

(d) *CEDRI submission.* If you are required to submit reports following the procedure specified in this paragraph, you must submit reports to the EPA via CEDRI, which can be accessed through EPA's CDX (*https://cdx.epa.gov/*). You must use the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/compliance-and-emissions-data-reporting-interface-cedri*) for this subpart. The date report templates become available will be listed on the CEDRI website. The report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. Do not use CEDRI to submit information you claim as CBI. Although we do not expect persons to assert a claim of CBI, if you wish to assert a CBI claim for some of the information in the report, you must submit a complete file, including information claimed to be CBI, to the EPA following the procedures in paragraphs (d)(1) and (2) of this section. Clearly mark the part or all of the information that you claim to be CBI. Information not marked as CBI may be authorized for public release without prior notice. Information marked as CBI will not be disclosed except in accordance with procedures set forth in 40 CFR part 2. All CBI claims must be asserted at the time of submission. Anything submitted using CEDRI cannot later be claimed CBI. Furthermore, under CAA section 114(c), emissions data is not entitled to confidential treatment, and the EPA is required to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available. You must submit the same file submitted to the CBI office with the CBI omitted to the EPA via the EPA's CDX as described earlier in this paragraph.

(1) The preferred method to receive CBI is for it to be transmitted electronically using email attachments, File Transfer Protocol, or other online file sharing services. Electronic submissions must be transmitted directly to the OAQPS CBI Office at the email address *oaqpscbi@epa.gov*, and as described above, should include clear CBI markings and be flagged to the attention of the Integrated Iron and Steel Sector Lead. If assistance is needed with submitting large electronic files that exceed the file size limit for email attachments, and if you do not have your own file sharing service, please email *oaqpscbi@epa.gov* to request a file transfer link.

(2) If you cannot transmit the file electronically, you may send CBI information through the postal service to the following address: OAQPS Document Control Officer (C404–02), OAQPS, U.S. Environmental Protection Agency, Research Triangle Park, North Carolina 27711, Attention Integrated Iron and Steel Sector Lead. The mailed CBI material should be double wrapped and clearly marked. Any CBI markings should not show through the outer envelope.

(e) *CDX outage.* If you are required to electronically submit a report through CEDRI in EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement. To assert a claim of EPA system outage, you must meet the requirements outlined in paragraphs (e)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning five business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(f) *Claim of force majeure.* If you are required to electronically submit a report through CEDRI in EPA's CDX, you may assert a claim of force majeure for failure to timely comply with the reporting requirement. To assert a claim of force majeure, you must meet the requirements outlined in paragraphs (f)(1) through (5) of this section.

(1) You may submit a claim if a force majeure event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For the purposes of this section, a force majeure event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (*e.g.,* hurricanes, earthquakes, or floods), acts of war or terrorism, or equipment failure or safety hazard beyond the control of the affected facility (*e.g.,* large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the force majeure event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the force majeure event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of force majeure and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the force majeure event occurs.

(g) *Part 70 monitoring report.* If you have obtained a title V operating permit for an affected source pursuant to part 70 or 71 of this chapter, you must report all deviations as defined in this subpart in the semiannual monitoring report required by §70.6(a)(3)(iii)(A) or §71.6(a)(3)(iii)(A) of this chapter. If you submit a compliance report for an affected source along with, or as part of, the semiannual monitoring report required by §70.6(a)(3)(iii)(A) or §71.6(a)(3)(iii)(A) of this chapter, and the compliance report includes all the required information concerning deviations from any emission limitation, standard, or operation and maintenance requirement in this subpart, submission of the compliance report satisfies any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report does not otherwise affect any obligation you may have to report deviations from permit requirements for an affected source to your permitting authority.

(h) *Fenceline monitoring reports.* For fenceline monitoring systems subject to §63.7792, each owner or operator must submit Fenceline Monitoring Reports on a quarterly basis using the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/*

electronic-reporting-air-emissions/cedri) for this subpart and following the procedure specified in paragraph (d) of this section. The first quarterly report must be submitted once the owner or operator has obtained 12 months of data. The first quarterly report must cover the period beginning on the date one year after the promulgation of the metals fenceline method and ending on March 31, June 30, September 30 or December 31, whichever date is the first date that occurs after the owner or operator has obtained 12 months of data (*i.e.*, the first quarterly report will contain between 12 and 15 months of data). Each subsequent quarterly report must cover one of the following reporting periods: Quarter 1 from January 1 through March 31; Quarter 2 from April 1 through June 30; Quarter 3 from July 1 through September 30; and Quarter 4 from October 1 through December 31. Each quarterly report must be electronically submitted no later than 45 calendar days following the end of the reporting period.

(1) Facility name and address.

(2) Year and reporting quarter (*i.e.*, Quarter 1, Quarter 2, Quarter 3, or Quarter 4).

(3) For each sampler: The latitude and longitude location coordinates; the sampler name; and identification of the type of sampler (*e.g.*, regular monitor, extra monitor, duplicate, field blank, inactive). Coordinates shall be in decimal degrees with at least five decimal places.

(4) The beginning and ending dates for each sampling period.

(5) Individual sample results for each monitored compound, reported in units of $\mu g/m^3$, for each monitor for each sampling period that ends during the reporting period. Results below the method detection limit shall be flagged as below the detection limit and reported at the method detection limit.

(6) Data flags for each outlier determined in accordance with the fenceline metals method. For each outlier, the owner or operator must submit the individual sample result of the outlier, as well as the evidence used to conclude that the result is an outlier.

(7) The biweekly concentration difference (Δc) for each sampling period and the annual average Δc for each sampling period.

(8) Indication of whether the owner or operator was required to develop a corrective action plan under § 63.7792(e).

[68 FR 27663, May 20, 2003, as amended at 85 FR 42122, July 13, 2020; 89 FR 23328, Apr. 3, 2024]

§ 63.7842 What records must I keep?

(a) You must keep the following records:

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any initial notification or notification of compliance status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) For existing sources and for new or reconstructed sources which commenced construction or reconstruction on or before August 16, 2019, before January 11, 2021, the records in § 63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunction for a period of five years. A startup, shutdown, and malfunction plan is not required after January 11, 2021.

(3) For each failure to meet an applicable standard, a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, and a description of the method used to estimate the emissions.

(4) Records of the actions taken to minimize emissions in accordance with § 63.7810(d), and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(5) Records of performance tests, performance evaluations, and opacity observations as required in § 63.10(b)(2)(viii).

(b) For each COMS, you must keep the records specified in paragraphs (b)(1) through (4) of this section.

(1) Records described in § 63.10(b)(2)(vi) through (xi).

(2) Monitoring data for a performance evaluation as required in § 63.6(h)(7)(i) and (ii).

(3) Previous (that is, superseded) versions of the performance evaluation plan required under § 63.8(d)(2), with the program of corrective action included in the plan.

(4) Records of the date and time that each deviation started and stopped, and whether the deviation occurred during a period of startup, shutdown, or malfunction or during another period.

(c) You must keep the records required in § 63.6(h)(6) for visual observations.

(d) You must keep the records required in §§ 63.7823, 63.7833, and 63.7834 to show continuous compliance with each emission limitation and operation and maintenance requirement that applies to you. This includes a record of each large and small bell repair and replacement, a record of the date on which the large bell opacity has exceeded 20 percent, and the most current time period or throughput over which no opacity was observed from the small bell.

(e) If you are demonstrating compliance with the mercury emission limit in Table 1 through § 63.7791(c), you must keep records to demonstrate compliance with the requirements for mercury in § 63.7791(c) as applicable. If you are demonstrating compliance with the mercury emission limit in Table 1 through § 63.7791(d), you must keep records documenting compliance with § 63.7791(d) for scrap that does not contain mercury switches. If you are demonstrating compliance with the mercury emission limit in Table 1 through § 63.7791(e), you must maintain records identifying each scrap provider and documenting the scrap provider's participation in an approved mercury switch removal program. If you purchase scrap from a broker, you must maintain records identifying each broker and documentation that all scrap provided by the broker was obtained from other scrap providers who participate in an approved mercury switch removal program.

(f) For fenceline monitoring systems subject to § 63.7792 of this subpart, each owner or operator must keep the records specified in paragraphs (f)(1) through (11) of this section.

(1) Coordinates of samplers, including co-located samplers and field blanks, and if applicable, the meteorological station. The owner or operator shall determine the coordinates using an instrument with an accuracy of at least 3 meters. The coordinates shall be in decimal degrees with at least five decimal places.

(2) The start and stop times and dates for each sample, as well as the sample identifying information.

(3) Sampling period average temperature and barometric pressure measurements.

(4) For each outlier determined in accordance with the procedures specified in the fenceline metals method, the sampler location and the concentration of the outlier and the evidence used to conclude that the result is an outlier.

(5) For samples that will be adjusted for uniform background, the location of and the concentration measured simultaneously by the background sampler, and the perimeter samplers to which it applies.

(6) Individual sample results, the calculated Δc for each sampling period and the two samples used to determine it, whether background correction was used, and the annual average Δc calculated after each sampling period.

(7) Method detection limit for each sample, including co-located samples and blanks.

(8) Documentation of the root cause analysis and any resulting corrective action taken each time an action level is exceeded, including the dates the root cause analysis was initiated and the resulting correction action(s) were taken.

(9) Any corrective action plan developed under § 63.7792(e).

(10) Other records as required by the sampling method.

(11) If a near-field source correction is used as provided in § 63.7792(f), or if an alternative test method is used that provides time-resolved measurements, records of hourly meteorological data, including temperature, barometric pressure, wind speed and wind direction, calculated daily unit vector wind direction, and daily sigma theta, and other records specified in the site-specific monitoring plan.

(g) For each unplanned bleeder valve opening for each blast furnace, you must keep the records specified in paragraphs (g)(1) through (3) of this section.

(1) The start date and start time of the event.

(2) The duration of the event in minutes.

(3) Any corrective actions taken in response to the event.

[68 FR 27663, May 20, 2003, as amended at 85 FR 42123, July 13, 2020; 89 FR 23328, Apr. 3, 2024]

§ 63.7843 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record according to § 63.10(b)(1). You can keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.7850 What parts of the General Provisions apply to me?

Table 4 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.15 apply to you.

§ 63.7851 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the United States Environmental Protection Agency (U.S. EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities that will not be delegated to State, local, or tribal agencies are specified in paragraphs (c)(1) through (5) of this section.

(1) Approval of alternative opacity emission limits in Table 1 to this subpart under § 63.6(h)(9).

(2) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90, except for approval of an alternative method for the oil content of the sinter plant feedstock or volatile organic compound measurements for the sinter plant windbox exhaust stream stack as provided in § 63.7824(f).

(3) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(5) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39588, July 13, 2006; 85 FR 42124, July 13, 2020]

§ 63.7852 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in § 63.2, and in this section as follows.

Bag leak detection system means a system that is capable of continuously monitoring relative particulate matter (dust) loadings in the exhaust of a baghouse to detect bag leaks and other upset conditions. A bag leak detection system includes, but is not limited to, an instrument that operates on tribroelectric, light scattering, light transmittance, or other effect to continuously monitor relative particulate matter loadings.

Basic oxygen process furnace means any refractory-lined vessel in which high-purity oxygen is blown under pressure through a bath of molten iron, scrap metal, and fluxes to produce steel. This definition includes both top and bottom blown furnaces, but does not include argon oxygen decarburization furnaces.

Basic oxygen process furnace group means the collection of BOPF shop steelmaking operating units and their control devices including the BOPF

primary emission control system, BOPF secondary control system, ladle metallurgy units, and hot metal transfer, desulfurization and slag skimming units that are operating at the time of each mercury test sequence. In the case of duplicate units in the BOPF Group, the BOPF Group for purposes of this rule means only those units operating at the time of the test sequence. See related definitions in this section for ''primary emissions,'' ''primary emission control system,'' ''secondary emissions,'' and ''secondary emission control system.''

Basic oxygen process furnace shop means the place where steelmaking operations that begin with the transfer of molten iron (hot metal) from the torpedo car and end prior to casting the molten steel, including hot metal transfer, desulfurization, slag skimming, refining in a basic oxygen process furnace, and ladle metallurgy occur.

Basic oxygen process furnace shop ancillary operations means the processes where hot metal transfer, hot metal desulfurization, slag skimming, and ladle metallurgy occur.

Blast furnace means a furnace used for the production of molten iron from iron ore and other iron bearing materials.

Bottom-blown furnace means any basic oxygen process furnace in which oxygen and other combustion gases are introduced into the bath of molten iron through tuyeres in the bottom of the vessel or through tuyeres in the bottom and sides of the vessel.

Casthouse means the building or structure that encloses the bottom portion of a blast furnace where the hot metal and slag are tapped from the furnace.

Certified observer means a visible emission observer certified to perform EPA Method 9 opacity observations.

Desulfurization means the process in which reagents such as magnesium, soda ash, and lime are injected into the hot metal, usually with dry air or nitrogen, to remove sulfur.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart, including but not limited to any emission limitation (including operating limits), standard, or operation and maintenance requirement;

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Fails to meet any emission limitation in this subpart during startup, shutdown, or malfunction, regardless of whether or not such failure is permitted by this subpart.

Discharge end means the place where those operations conducted within the sinter plant starting at the discharge of the sintering machine's traveling grate including (but not limited to) hot sinter crushing, screening, and transfer operations occur.

Emission limitation means any emission limit, opacity limit, or operating limit.

Hot metal transfer station means the location in a basic oxygen process furnace shop where molten iron (hot metal) is transferred from a torpedo car or hot metal car used to transport hot metal from the blast furnace casthouse to a holding vessel or ladle in the basic oxygen process furnace shop. This location also is known as the reladling station or ladle transfer station.

Integrated iron and steel manufacturing facility means an establishment engaged in the production of steel from iron ore.

Iron beaching operation means pouring hot molten iron from a torpedo car onto the ground when the iron from the blast furnace cannot be charged to the basic oxygen process furnace.

Ladle metallurgy means a secondary steelmaking process that is performed typically in a ladle after initial refining in a basic oxygen process furnace to adjust or amend the chemical and/or mechanical properties of steel. This definition does not include vacuum degassing.

Large blast furnace means a blast furnace with a working volume of greater than 2,500 m^3.

Mercury switch means each mercury-containing capsule or switch assembly that is part of a convenience light switch mechanism installed in a motor vehicle.

Motor vehicle means an automotive vehicle not operated on rails and usually operated with rubber tires for use on roads and highways.

Motor vehicle scrap means post-consumer scrap from discarded automotive vehicles, in whole or in part, including automobile body hulks that have been processed through a shredder. Motor vehicle scrap does not include automobile manufacturing bundles or miscellaneous vehicle parts, such as wheels and bumpers, which do not contain mercury switches.

Opening means any roof monitor, vent, door, window, hole, crack or other conduit that allows gas to escape to the atmosphere from a blast furnace casthouse or BOPF shop.

Planned bleeder valve opening means the opening of a blast furnace pressure relief safety valve that is initiated by an operator.

Post-consumer steel scrap means steel scrap that is composed of materials made of steel that were purchased by households or by commercial, industrial, and institutional facilities in their role as end-users of the product and which can no longer be used for its intended purpose.

Pre-consumer steel scrap means steel scrap that is left over from industrial or manufacturing processes and which is subsequently recycled as scrap. Other terms used to describe this scrap are new, home, run-around, prompt-industrial, and return scrap.

Primary emissions means particulate matter emissions from the basic oxygen process furnace generated during the steel production cycle which are captured and treated in the furnace's primary emission control system.

Primary emission control system means the combination of equipment used for the capture and collection of primary emissions (*e.g.*, an open hood capture system used in conjunction with an electrostatic precipitator or a closed hood system used in conjunction with a scrubber).

Primary oxygen blow means the period in the steel production cycle of a basic oxygen process furnace during which oxygen is blown through the molten iron bath by means of a lance inserted from the top of the vessel (top-blown) or through tuyeres in the bottom and/or sides of the vessel (bottom-blown).

Responsible official means responsible official as defined in § 63.2.

Scrap provider means the company or person (including a broker) who contracts directly with an integrated iron and steel manufacturing facility to provide steel scrap. Scrap processors, such as shredder operators or vehicle dismantlers, who do not sell scrap directly to an integrated iron and steel manufacturing facility are not scrap providers.

Secondary emissions means particulate matter emissions that are not controlled by a primary emission control system, including emissions that escape from open and closed hoods, lance hole openings, and gaps or tears in ductwork to the primary emission control system.

Secondary emission control system means the combination of equipment used for the capture and collection of secondary emissions from a basic oxygen process furnace.

Shredded motor vehicle scrap means post-consumer scrap from discarded automotive vehicles that has been processed through a shredder.

Sinter cooler means the apparatus used to cool the hot sinter product that is transferred from the discharge end through contact with large volumes of induced or forced draft air.

Sinter plant means the machine used to produce a fused clinker-like aggregate or sinter of fine iron-bearing materials suited for use in a blast furnace. The machine is composed of a continuous traveling grate that conveys a bed of ore fines and other finely divided iron-bearing material and fuel (typically coke breeze), a burner at the feed end of the grate for ignition, and a series of downdraft windboxes along the length of the strand to support downdraft combustion and heat sufficient to produce a fused sinter product.

Skimming station means the locations inside a basic oxygen process furnace shop where slag is removed from the top of the molten metal bath.

Slip means when raw materials loaded in the top of the furnace fail to descend smoothly in the furnace and bind together to form a ''bridge'' which than ''hangs'' (*i.e.*, accumulates) in one position in the furnace. When a ''hang'' eventually falls, or ''slips,'' it creates a pressure surge that may open the bleeder valves, releasing emissions in the form of a large dust cloud.

Small blast furnace means a blast furnace with a working volume of less than 2,500 m^3.

Specialty metal scrap means scrap where the only materials from motor vehicles in the scrap are materials (such as certain exhaust systems) recovered for their specialty alloy content (including, but not limited to, chromium, nickel, molybdenum, or other alloys), and, based on the nature of the scrap and purchase specifications, the scrap is not expected to contain mercury switches.

Steel production cycle means the operations conducted within the basic oxygen process furnace shop that are required to produce each batch of steel. The following operations are included: scrap charging, preheating (when done), hot metal charging, primary oxygen blowing, sampling, (vessel turndown and turnup), additional oxygen blowing (when done), tapping, and deslagging. The steel production cycle begins when the scrap is charged to the furnace and ends after the slag is emptied from the vessel Into the slag pot.

Steel scrap means pre-consumer and post-consumer discarded steel that is processed by scrap providers for resale (post-consumer) or used on-site (pre-consumer or run-around scrap from within a facility or company). Post-consumer steel scrap may or may not contain motor vehicle scrap, depending on the type of scrap.

Top-blown furnace means any basic oxygen process furnace in which oxygen is introduced into the bath of molten iron by means of an oxygen lance inserted from the top of the vessel.

Total hydrocarbons (THC) means the sum of organic compounds measured as carbon using EPA Method 25A (appendix A–7 to part 60 of this chapter).

Unplanned bleeder valve opening means the opening of a blast furnace pressure relief safety valve that is not a planned bleeder valve opening.

Windboxes means the compartments that provide for a controlled distribution of downdraft combustion air as it is drawn through the sinter bed of a sinter plant to make the fused sinter product.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39588, July 13, 2006; 85 FR 42124, July 13, 2020; 89 FR 23329, Apr. 3, 2024]

TABLE 1 TO SUBPART FFFFF OF PART 63—EMISSION, OPACITY, AND WORK PRACTICE LIMITS

TABLE 1 TO SUBPART FFFFF OF PART 63—EMISSION, OPACITY, AND WORK PRACTICE LIMITS

As required in §63.7790(a), you must comply with each applicable emission, opacity, and work practice limit in the following table:

For . . .	You must comply with each of the following . . .
1. Each windbox exhaust stream at an existing sinter plant.	a. You must not cause to be discharged to the atmosphere any gases that contain particulate matter in excess of 0.4 lb/ton of product sinter; b. You must not cause to be discharged to the atmosphere any gases that contain mercury in excess of 0.000018 lb/ton of product sinter; c. You must not cause to be discharged to the atmosphere any gases that contain hydrogen chloride in excess of 0.025 lb/ton of product sinter; d. You must not cause to be discharged to the atmosphere any gases that contain carbonyl sulfide in excess of 0.064 lb/ton of product sinter; e. You must not cause to be discharged to the atmosphere any gases that contain D/F TEQs in excess of 1.1E–08 lb/ton of product sinter; and f. You must not cause to be discharged to the atmosphere any gases that contain polycyclic aromatic hydrocarbons in excess of 0.0018 lb/ton of product sinter.

For . . .	You must comply with each of the following . . .
2. Each windbox exhaust stream at a new sinter plant.	a. You must not cause to be discharged to the atmosphere any gases that contain particulate matter in excess of 0.3 lb/ton of product sinter; b. You must not cause to be discharged to the atmosphere any gases that contain mercury in excess of 0.000012 lb/ton of product sinter; c. You must not cause to be discharged to the atmosphere any gases that contain hydrogen chloride in excess of 0.0012 lb/ton of product sinter; d. You must not cause to be discharged to the atmosphere any gases that contain carbonyl sulfide in excess of 0.030 lb/ton of product sinter; e. You must not cause to be discharged to the atmosphere any gases that contain D/F TEQs in excess of 1.1E–08 lb/ton of product sinter; and f. You must not cause to be discharged to the atmosphere any gases that contain polycyclic aromatic hydrocarbons in excess of 0.0015 lb/ton of product sinter.
3. Each discharge end at an existing sinter plant.	a. You must not cause to be discharged to the atmosphere any gases that exit from one or more control devices that contain, on a flow-weighted basis, particulate matter in excess of 0.02 gr/dscf; [1] [2] and b. You must not cause to be discharged to the atmosphere any secondary emissions that exit any opening in the building or structure housing the discharge end that exhibit opacity greater than 20 percent (6-minute average).
4. Each discharge end at a new sinter plant.	a. You must not cause to be discharged to the atmosphere any gases that exit from one or more control devices that contain, on a flow weighted basis, particulate matter in excess of 0.01 gr/dscf; and b. You must not cause to be discharged to the atmosphere any secondary emissions that exit any opening in the building or structure housing the discharge end that exhibit opacity greater than 10 percent (6-minute average).
5. Each sinter cooler at an existing sinter plant.	You must not cause to be discharged to the atmosphere any emissions that exhibit opacity greater than 10 percent (6-minute average).
6. Each sinter cooler at a new sinter plant.	You must not cause to be discharged to the atmosphere any gases that contain particulate matter in excess of 0.01 gr/dscf.
7. Each casthouse at an existing blast furnace.	a. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain particulate matter in excess of 0.01 gr/dscf; [2] b. You must not cause to be discharged to the atmosphere any secondary emissions that exit all openings in the casthouse or structure housing the blast furnace that exhibit opacity greater than 20 percent (6-minute average); c. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain hydrogen chloride in excess of 0.0056 lb/ton of iron; d. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain total hydrocarbons as propane in excess of 0.48 lb/ton of iron; and e. You must not cause unplanned bleeder valve openings in excess of 4 events per year for large blast furnaces or 15 events per year for small blast furnaces.
8. Each casthouse at a new blast furnace.	a. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain particulate matter in excess of 0.003 gr/dscf; and b. You must not cause to be discharged to the atmosphere any secondary emissions that exit all openings in the casthouse or structure housing the blast furnace that exhibit opacity greater than 15 percent (6-minute average); c. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain hydrogen chloride in excess of 0.00059 lb/ton of iron; d. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain total hydrocarbons as propane in excess of 0.035 lb/ton of iron; and e. You must not cause unplanned bleeder valve openings in excess of zero events per year.
9. Each BOPF at a new or existing shop.	a. You must not cause to be discharged to the atmosphere any gases that exit from a primary emission control system for a BOPF with a closed hood system at a new or existing BOPF shop that contain, on a flow-weighted basis, particulate matter in excess of 0.03 gr/dscf during the primary oxygen blow; [2] [3]

For . . .	You must comply with each of the following . . .
	b. You must not cause to be discharged to the atmosphere any gases that exit from a primary emission control system for a BOPF with an open hood system that contain, on a flow-weighted basis, particulate matter in excess of 0.02 gr/dscf during the steel production cycle for an existing BOPF shop[2] [3] or 0.01 gr/dscf during the steel production cycle for a new BOPF shop;[3] c. You must not cause to be discharged to the atmosphere any gases that exit from a control device used solely for the collection of secondary emissions from the BOPF that contain particulate matter in excess of 0.01 gr/dscf for an existing BOPF shop[2] or 0.0052 gr/dscf for a new BOPF shop; d. You must not cause to be discharged to the atmosphere any gases that exit from a primary emission control system for a BOPF that contain hydrogen chloride in excess of 0.058 lb/ton of steel for existing sources and 2.8E–04 lb/ton steel for new sources; e. You must not cause to be discharged to the atmosphere any gases that exit from a primary emission control system for a BOPF that contain THC as propane in excess of 0.04 lb/ton of steel for existing sources and 0.0017 lb/ton of steel for new sources; and f. You must not cause to be discharged to the atmosphere any gases that exit from a primary emission control system for a BOPF that contain D/F TEQs in excess of 9.2E–10 lb/ton of steel.
10. Each hot metal transfer, skimming, and desulfurization operation at a new or existing BOPF shop.	You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain particulate matter in excess of 0.01 gr/dscf for an existing BOPF shop[2] or 0.003 gr/dscf for a new BOPF shop.
11. Each ladle metallurgy operation at a new or existing BOPF shop.	You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain particulate matter in excess of 0.01 gr/dscf for an existing BOPF shop[2] or 0.004 gr/dscf for a new BOPF shop.
12. Each existing BOPF shop.	You must not cause to be discharged to the atmosphere any secondary emissions that exit any opening in the BOPF shop or any other building housing the BOPF or BOPF shop operation that exhibit opacity greater than 20 percent (3-minute average).
13. Each new BOPF shop	a. You must not cause to be discharged to the atmosphere any secondary emissions that exit any opening in the BOPF shop or other building housing a bottom-blown BOPF or BOPF shop operations that exhibit opacity (for any set of 6-minute averages) greater than 10 percent, except that one 6-minute period not to exceed 20 percent may occur once per steel production cycle; or b. You must not cause to be discharged to the atmosphere any secondary emissions that exit any opening in the BOPF shop or other building housing a top-blown BOPF or BOPF shop operations that exhibit opacity (for any set of 3-minute averages) greater than 10 percent, except that one 3-minute period greater than 10 percent but less than 20 percent may occur once per steel production cycle.
14. Each BOPF Group at an existing BOPF shop.	You must not cause to be discharged to the atmosphere any gases that exit from the collection of BOPF Group control devices that contain mercury in excess of 0.00026 lb/ton of steel scrap input to the BOPF.
15. Each BOPF Group at a new BOPF shop.	You must not cause to be discharged to the atmosphere any gases that exit from the collection of BOPF Group control devices that contain mercury in excess of 0.000081 lb/ton of steel scrap input to the BOPF.
16. Each planned bleeder valve opening at a new or existing blast furnace.	You must not cause to be discharged to the atmosphere any emissions that exhibit opacity greater than 8 percent (6-minute average).
17. Each slag processing, handling and storage operation for a new or existing blast furnace or BOPF.	You must not cause to be discharged to the atmosphere any emissions that exhibit opacity greater than 10 percent (6-minute average).
18. Each existing blast furnace stove.	a. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain HCl in excess of 0.0012 lb/MMBtu; and b. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain THC in excess of 0.12 lb/MMBtu.
19. Each new blast furnace stove.	a. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain HCl in excess of 4.2e–4 lb/MMBtu; and

For . . .	You must comply with each of the following . . .
	b. You must not cause to be discharged to the atmosphere any gases that exit from a control device that contain THC in excess of 0.0054 lb/MMBtu.

[1] This limit applies if the cooler is vented to the same control device as the discharge end.
[2] This concentration limit (gr/dscf) for a control device does not apply to discharges inside a building or structure housing the discharge end at an existing sinter plant, inside a casthouse at an existing blast furnace, or inside an existing BOPF shop if the control device was installed before August 30, 2005.
[3] This limit applies to control devices operated in parallel for a single BOPF during the oxygen blow.

[89 FR 23329, Apr. 3, 2024]

TABLE 2 TO SUBPART FFFFF OF PART 63—INITIAL COMPLIANCE WITH EMISSION AND OPACITY LIMITS

As required in §63.7826(a)(1), you must demonstrate initial compliance with the emission and opacity limits according to the following table:

For . . .	You have demonstrated initial compliance if . . .
1. Each windbox exhaust stream at an existing sinter plant.	a. The process-weighted mass rate of particulate matter from a windbox exhaust stream, measured according to the performance test procedures in §63.7822(c), did not exceed 0.4 lb/ton of product sinter; b. The process-weighted mass rate of mercury from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.000018 lb/ton of product sinter; c. The process-weighted mass rate of hydrogen chloride from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.025 lb/ton of product sinter; d. The process-weighted mass rate of carbonyl sulfide from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.064 lb/ton of product sinter; e. The process-weighted mass rate of D/F TEQs from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 1.1E–08 lb/ton of product sinter; and f. The process-weighted mass rate of polycyclic aromatic hydrocarbons from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.0018 lb/ton of product sinter.
2. Each windbox exhaust stream at a new sinter plant.	a. The process-weighted mass rate of particulate matter from a windbox exhaust stream, measured according to the performance test procedures in §63.7822(c), did not exceed 0.3 lb/ton of product sinter; b. The process-weighted mass rate of mercury from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.000012 lb/ton of product sinter; c. The process-weighted mass rate of hydrogen chloride from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.0012 lb/ton of product sinter; d. The process-weighted mass rate of carbonyl sulfide from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.030 lb/ton of product sinter; e. The process-weighted mass rate of D/F TEQs from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 1.1E–08 lb/ton of product sinter; and f. The process-weighted mass rate of polycyclic aromatic hydrocarbons from a windbox exhaust stream, measured according to the performance test procedures in §63.7825, did not exceed 0.0015 lb/ton of product sinter.
3. Each discharge end at an existing sinter plant.	a. The flow-weighted average concentration of particulate matter from one or more control devices applied to emissions from a discharge end, measured according to the performance test procedures in §63.7822(d), did not exceed 0.02 gr/dscf; and b. The opacity of secondary emissions from each discharge end, determined according to the performance test procedures in §63.7823(c), did not exceed 20 percent (6-minute average).

For . . .	You have demonstrated initial compliance if . . .
4. Each discharge end at a new sinter plant.	a. The flow-weighted average concentration of particulate matter from one or more control devices applied to emissions from a discharge end, measured according to the performance test procedures in § 63.7822(d), did not exceed 0.01 gr/dscf; and b. The opacity of secondary emissions from each discharge end, determined according to the performance test procedures in § 63.7823(c), did not exceed 10 percent (6-minute average).
5. Each sinter cooler at an existing sinter plant.	The opacity of emissions, determined according to the performance test procedures in § 63.7823(e), did not exceed 10 percent (6-minute average).
6. Each sinter cooler at a new sinter plant.	The average concentration of particulate matter, measured according to the performance test procedures in § 63.7822(b), did not exceed 0.01 gr/dscf.
7. Each casthouse at an existing blast furnace.	a. The average concentration of particulate matter from a control device applied to emissions from a casthouse, measured according to the performance test procedures in § 63.7822(e), did not exceed 0.01 gr/dscf; b. The opacity of secondary emissions from each casthouse, determined according to the performance test procedures in § 63.7823(c), did not exceed 20 percent (6-minute average); c. The process-weighted mass rate of hydrogen chloride from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.0056 lb/ton of iron; d. The process-weighted mass rate of total hydrocarbons from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.48 lb/ton of iron; and e. The number of unplanned bleeder valve openings in one year, as reported according to the specifications in § 63.7841(b)(14), did not exceed 4 events for large blast furnaces or 15 events for small blast furnaces.
8. Each casthouse at a new blast furnace.	a. The average concentration of particulate matter from a control device applied to emissions from a casthouse, measured according to the performance test procedures in § 63.7822(e), did not exceed 0.003 gr/dscf; and b. The opacity of secondary emissions from each casthouse, determined according to the performance test procedures in § 63.7823(c), did not exceed 15 percent (6-minute average); c. The process-weighted mass rate of hydrogen chloride from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.00059 lb/ton of iron; d. The process-weighted mass rate of total hydrocarbons from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.035 lb/ton of iron; and e. The number of unplanned bleeder valve openings in one year, as reported according to the specifications in § 63.7841(b)(14), did not exceed zero events.
9. Each BOPF at a new or existing BOPF shop.	a. The average concentration of particulate matter from a primary emission control system applied to emissions from a BOPF with a closed hood system, measured according to the performance test procedures in § 63.7822(f), did not exceed 0.03 gr/dscf for a new or existing BOPF shop; b. The average concentration of particulate matter from a primary emission control system applied to emissions from a BOPF with an open hood system, measured according to the performance test procedures in § 63.7822(g), did not exceed 0.02 gr/dscf for an existing BOPF shop or 0.01 gr/dscf for a new BOPF shop; c. The average concentration of particulate matter from a control device applied solely to secondary emissions from a BOPF, measured according to the performance test procedures in § 63.7822(g), did not exceed 0.01 gr/dscf for an existing BOPF shop or 0.0052 gr/dscf for a new BOPF shop; d. The process-weighted mass rate of hydrogen chloride from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.058 lb/ton of steel for an existing BOPF shop or 0.00028 lb/ton of steel for a new BOPF shop; e. The process-weighted mass rate of total hydrocarbons from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.04 lb/ton of steel for an existing BOPF shop or 0.0017 lb/ton of steel for a new BOPF shop; and

For . . .	You have demonstrated initial compliance if . . .
	f. The process-weighted mass rate of D/F TEQs from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 9.2e–10 lb/ton of steel.
10. Each hot metal transfer skimming, and desulfurization at a new or existing BOPF shop.	The average concentration of particulate matter from a control device applied to emissions from hot metal transfer, skimming, or desulfurization, measured according to the performance test procedures in § 63.7822(h), did not exceed 0.01 gr/dscf for an existing BOPF shop or 0.003 gr/dscf for a new BOPF shop.
11. Each ladle metallurgy operation at a new or existing BOPF shop.	The average concentration of particulate matter from a control device applied to emissions from a ladle metallurgy operation, measured according to the performance test procedures in § 63.7822(h), did not exceed 0.01 gr/dscf for an existing BOPF shop or 0.004 gr/dscf for a new BOPF shop.
12. Each existing BOPF shop.	The opacity of secondary emissions from each BOPF shop, determined according to the performance test procedures in § 63.7823(d), did not exceed 20 percent (3-minute average).
13. Each new BOPF shop	a. The opacity of the highest set of 6-minute averages from each BOPF shop housing a bottom-blown BOPF, determined according to the performance test procedures in § 63.7823(d), did not exceed 20 percent and the second highest set of 6-minute averages did not exceed 10 percent; or b. The opacity of the highest set of 3-minute averages from each BOPF shop housing a top-blown BOPF, determined according to the performance test procedures in § 63.7823(d), did not exceed 20 percent and the second highest set of 3-minute averages did not exceed 10 percent.
14. Each BOPF Group at an existing BOPF shop.	If demonstrating compliance through performance testing, the average emissions of mercury from the collection of BOPF Group control devices applied to the emissions from the BOPF Group, measured according to the performance test procedures in § 63.7825, did not exceed 0.00026 lb/ton steel scrap input to the BOPF.
15. Each BOPF Group at a new BOPF shop.	If demonstrating compliance through performance testing, the average emissions of mercury from the collection of BOPF Group control devices applied to the emissions from the BOPF Group, measured according to the performance test procedures in § 63.7825, did not exceed 0.000081 lb/ton steel scrap input to the BOPF.
16. Each planned bleeder valve opening at a new or existing blast furnace.	The opacity of emissions, determined according to the performance test procedures in § 63.7823(f), did not exceed 8 percent (6-minute average).
17. Each slag processing, handling and storage operation for a new or existing blast furnace or BOPF.	The opacity of emissions, determined according to the performance test procedures in § 63.7823(g), did not exceed 10 percent (6-minute average).
18. Each existing blast furnace stove.	a. The process-weighted mass rate of HCl from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.0012 lb/MMBtu; and b. The process-weighted mass rate of THC from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.12 lb/MMBtu.
19. Each new blast furnace stove.	a. The process-weighted mass rate of HCl from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 4.2e–4 lb/MMBtu; and b. The process-weighted mass rate of THC from a windbox exhaust stream, measured according to the performance test procedures in § 63.7825, did not exceed 0.0054 lb/MMBtu.

[89 FR 23329, Apr. 3, 2024]

Table 3 to Subpart FFFFF of Part 63—Continuous Compliance With Emission and Opacity Limits

As required in § 63.7833(a), you must demonstrate continuous compliance with the emission and opacity limits according to the following table:

For . . .	You must demonstrate continuous compliance by . . .
1. Each windbox exhaust stream at an existing sinter plant.	a. Maintaining emissions of particulate matter at or below 0.4 lb/ton of product sinter; b. Conducting subsequent performance tests at the frequencies specified in §63.7821; c. Maintaining emissions of mercury at or below 0.000018 lb/ton of product sinter; d. Maintaining emissions of hydrogen chloride at or below 0.025 lb/ton of product sinter; e. Maintaining emissions of carbonyl sulfide at or below 0.064 lb/ton of product sinter; f. Maintaining emissions of D/F TEQs at or below 1.1E–08 lb/ton of product sinter; and g. Maintaining emissions of polycyclic aromatic hydrocarbons at or below 0.0018 lb/ton of product sinter.
2. Each windbox exhaust stream at a new sinter plant.	a. Maintaining emissions of particulate matter at or below 0.3 lb/ton of product sinter; b. Conducting subsequent performance tests at the frequencies specified in §63.7821; c. Maintaining emissions of mercury at or below 0.000012 lb/ton of product sinter; d. Maintaining emissions of hydrogen chloride at or below 0.0012 lb/ton of product sinter; e. Maintaining emissions of carbonyl sulfide at or below 0.030 lb/ton of product sinter; f. Maintaining emissions of D/F TEQs at or below 1.1E–08 lb/ton of product sinter; and g. Maintaining emissions of polycyclic aromatic hydrocarbons at or below 0.0015 lb/ton of product sinter.
3. Each discharge end at an existing sinter plant.	a. Maintaining emissions of particulate matter from one or more control devices at or below 0.02 gr/dscf; and b. Maintaining the opacity of secondary emissions that exit any opening in the building or structure housing the discharge end at or below 20 percent (6-minute average); and c. Conducting subsequent performance tests at the frequencies specified in §63.7821.
4. Each discharge end at a new sinter plant.	a. Maintaining emissions of particulate matter from one or more control devices at or below 0.01 gr/dscf; and b. Maintaining the opacity of secondary emissions that exit any opening in the building or structure housing the discharge end at or below 10 percent (6-minute average); and c. Conducting subsequent performance tests at the frequencies specified in §63.7821.
5. Each sinter cooler at an existing sinter plant.	a. Maintaining the opacity of emissions that exit any sinter cooler at or below 10 percent (6-minute average); and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
6. Each sinter cooler at a new sinter plant.	a. Maintaining emissions of particulate matter at or below 0.1 gr/dscf; and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
7. Each casthouse at an existing blast furnace.	a. Maintaining emissions of particulate matter from a control device at or below 0.01 gr/dscf; b. Maintaining the opacity of secondary emissions that exit all openings in the casthouse or structure housing the casthouse at or below 20 percent (6-minute average); c. Conducting subsequent performance tests at the frequencies specified in §63.7821; d. Maintaining emissions of hydrogen chloride at or below 0.0056 lb/ton of iron; e. Maintaining emissions of total hydrocarbons at or below 0.48 lb/ton of iron; and f. Maintaining unplanned bleeder valve openings at or below 4 events per year for large blast furnaces or 15 events per year for small blast furnaces.

For . . .	You must demonstrate continuous compliance by . . .
8. Each casthouse at a new blast furnace.	a. Maintaining emissions of particulate matter from a control device at or below 0.003 gr/dscf; b. Maintaining the opacity of secondary emissions that exit all openings in the casthouse or structure housing the casthouse at or below 15 percent (6-minute average); c. Conducting subsequent performance tests at the frequencies specified in §63.7821; d. Maintaining emissions of hydrogen chloride at or below 0.00059 lb/ton of iron; e. Maintaining emissions of total hydrocarbons at or below 0.035 lb/ton of iron; and f. Maintaining unplanned bleeder valve openings at zero events per year.
9. Each BOPF at a new or existing BOPF shop.	a. Maintaining emissions of particulate matter from the primary control system for a BOPF with a closed hood system at or below 0.03 gr/dscf; b. Maintaining emissions of particulate matter from the primary control system for a BOPF with an open hood system at or below 0.02 gr/dscf for an existing BOPF shop or 0.01 gr/dscf for a new BOPF shop; c. Maintaining emissions of particulate matter from a control device applied solely to secondary emissions from a BOPF at or below 0.01 gr/dscf for an existing BOPF shop or 0.0052 gr/dscf for a new BOPF shop; d. Conducting subsequent performance tests at the frequencies specified in §63.7821; e. Maintaining emissions of hydrogen chloride from a primary emission control system for a BOPF at or below 0.058 lb/ton of steel for existing sources and 2.8E–04 lb/ton steel for new sources; f. Maintaining emissions of THC from a primary emission control system for a BOPF at or below 0.04 lb/ton of steel for existing sources and 0.0017 lb/ton of steel for new sources; and g. Maintaining emissions of D/F TEQs from a primary emission control system for a BOPF at or below 9.2E–10 lb/ton of steel.
10. Each hot metal transfer, skimming, and desulfurization operation at a new or existing BOPF shop.	a. Maintaining emissions of particulate matter from a control device at or below 0.01 gr/dscf at an existing BOPF or 0.003 gr/dscf for a new BOPF; and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
11. Each ladle metallurgy operation at a new or existing BOPF shop.	a. Maintaining emissions of particulate matter from a control device at or below 0.01 gr/dscf at an existing BOPF shop or 0.004 gr/dscf for a new BOPF shop; and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
12. Each existing BOPF shop.	a. Maintaining the opacity of secondary emissions that exit any opening in the BOPF shop or other building housing the BOPF shop or shop operation at or below 20 percent (3-minute average); and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
13. Each new BOPF shop	a. Maintaining the opacity (for any set of 6-minute averages) of secondary emissions that exit any opening in the BOPF shop or other building housing a bottom-blown BOPF or shop operation at or below 10 percent, except that one 6-minute period greater than 10 percent but no more than 20 percent may occur once per steel production cycle; b. Maintaining the opacity (for any set of 3-minute averages) of secondary emissions that exit any opening in the BOPF shop or other building housing a top-blown BOPF or shop operation at or below 10 percent, except that one 3-minute period greater than 10 percent but less than 20 percent may occur once per steel production cycle; and c. Conducting subsequent performance tests at the frequencies specified in §63.7821.
14. Each BOPF Group at an existing BOPF shop.	a. Maintaining emissions of mercury from the collection of BOPF Group control devices at or below 0.00026 lb/ton steel scrap input to the BOPF; and b. If demonstrating compliance through performance testing, conducting subsequent performance tests at the frequencies specified in §63.7821; and c. If demonstrating compliance through §63.7791(c), (d), or (e), maintaining records pursuant to §63.7842(e).
15. Each BOPF Group at a new BOPF shop.	a. Maintaining emissions of mercury from the collection of BOPF Group control devices at or below 0.000081 lb/ton steel scrap input to the BOPF; and

For . . .	You must demonstrate continuous compliance by . . .
	b. If demonstrating compliance through performance testing, conducting subsequent performance tests at the frequencies specified in §63.7821; and c. If demonstrating compliance through §63.7791(c), (d), or (e), maintaining records pursuant to §63.7842(e).
16. Each planned bleeder valve opening at a new or existing blast furnace.	a. Maintaining the opacity of emissions that exit any bleeder valve as a result of a planned opening at or below 8 percent (6-minute average); and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
17. Each slag processing, handling and storage operation for a new or existing blast furnace or BOPF.	a. Maintaining the opacity of emissions that exit any slag processing, handling, or storage operation at or below 10 percent (6-minute average); and b. Conducting subsequent performance tests at the frequencies specified in §63.7821.
18. Each existing blast furnace stove.	a. Maintaining emissions of HCl at or below 0.0012 lb/MMBtu; b. Maintaining emissions of THC at or below 0.12 lb/MMBtu; and c. Conducting subsequent performance tests at the frequencies specified in §63.7821.
19. Each new blast furnace stove.	a. Maintaining emissions of HCl at or below 4.2e–4 lb/MMBtu; b. Maintaining emissions of THC at or below 0.0054 lb/MMBtu; and c. Conducting subsequent performance tests at the frequencies specified in §63.7821.

[89 FR 23329, Apr. 3, 2024]

TABLE 4 TO SUBPART FFFFF OF PART 63— APPLICABILITY OF GENERAL PROVISIONS TO SUBPART FFFFF

As required in §63.7850, you must comply with the requirements of the NESHAP General Provisions (subpart A of this part) shown in the following table:

Citation	Subject	Applies to subpart FFFFF	Explanation
§63.1	Applicability	Yes.	
§63.2	Definitions	Yes.	
§63.3	Units and Abbreviations	Yes.	
§63.4	Prohibited Activities	Yes.	
§63.5	Construction/Reconstruction.	Yes.	
§63.6(a), (b), (c), (d), (e)(1)(iii), (f)(2)–(3), (g), (h)(2)(ii)–(h)(9).	Compliance with Standards and Maintenance Requirements.	Yes.	
§63.6(e)(1)(i)	General Duty to Minimize Emissions.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See §63.7810(d) for general duty requirement.
§63.6(e)(1)(ii)	Requirement to Correct Malfunctions ASAP.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes, on or before January 11, 2021, and No thereafter.	

Citation	Subject	Applies to subpart FFFFF	Explanation
§ 63.6(e)(3)	SSM Plan Requirements	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See § 63.7810(c).
§ 63.6(f)(1)	Compliance except during SSM.	No	See § 63.7810(a).
§ 63.6(h)(1)	Compliance except during SSM.	No	See § 63.7810(a).
§ 63.6(h)(2)(i)	Determining Compliance with Opacity and VE Standards.	No	Subpart FFFFF specifies methods and procedures for determining compliance with opacity emission and operating limits.
§ 63.6(i)	Extension of Compliance with Emission Standards.	Yes.	
§ 63.6(j)	Exemption from Compliance with Emission Standards.	Yes.	
§ 63.7(a)(1)–(2)	Applicability and Performance Test Dates.	No	Subpart FFFFF and specifies performance test applicability and dates.
§ 63.7(a)(3), (b)–(d), (e)(2)–(4), (f)–(h).	Performance Testing Requirements.	Yes.	
§ 63.7(e)(1)	Performance Testing	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See §§ 63.7822(a), 63.7823(a), and 63.7825(a).
§ 63.8(a)(1)–(3), (b), (c)(1)(ii), (c)(2)–(3), (c)(4)(i)–(ii), (c)(5)–(6), (c)(7)–(8), (d)(1)–(2), (e), (f)(1)–(5), (g)(1)–(4).	Monitoring Requirements	Yes	CMS requirements in § 63.8(c)(4)(i)–(ii), (c)(5)–(6), (d)(1)–(2), and (e) apply only to COMS.
§ 63.8(a)(4)	Additional Monitoring Requirements for Control Devices in § 63.11.	No	Subpart FFFFF does not require flares.
§ 63.8(c)(1)(i)	General Duty to Minimize Emissions and CMS Operation.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	

Citation	Subject	Applies to subpart FFFFF	Explanation
§ 63.8(c)(1)(iii)	Requirement to Develop SSM Plan for CMS.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	
§ 63.8(c)(4)	Continuous Monitoring System Requirements.	No	Subpart FFFFF specifies requirements for operation of CMS.
§ 63.8(d)(3)	Written procedures for CMS.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See § 63.7842(b)(3).
§ 63.8(f)(6)	RATA Alternative	No.	
§ 63.8(g)(5)	Data Reduction	No	Subpart FFFFF specifies data reduction requirements.
§ 63.9	Notification Requirements	Yes	Additional notifications for CMS in § 63.9(g) apply only to COMS.
§ 63.10(a), (b)(1), (b)(2)(x), (b)(2)(xiv), (b)(3), (c)(1)–(6), (c)(9)–(14), (d)(1)–(4), (e)(1)–(2), (e)(4), (f).	Recordkeeping and Reporting Requirements.	Yes	Additional records for CMS in § 63.10(c)(1)–(6), (9)–(14), and reports in § 63.10(d)(1)–(2) apply only to COMS.
§ 63.10(b)(2)(i)	Recordkeeping of Occurrence and Duration of Startups and Shutdowns.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	
§ 63.10(b)(2)(ii)	Recordkeeping of Failures to Meet a Standard.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See § 63.7842(a)(2)–(4) for recordkeeping of (1) date, time, and duration of failure to meet the standard; (2) listing of affected source or equipment, and an estimate of the quantity of each regulated pollutant emitted over the standard; and (3) actions to minimize emissions and correct the failure.
§ 63.10(b)(2)(iii)	Maintenance Records	Yes.	

Citation	Subject	Applies to subpart FFFFF	Explanation
§ 63.10(b)(2)(iv)	Actions Taken to Minimize Emissions During SSM.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See § 63.7842(a)(4) for records of actions taken to minimize emissions.
§ 63.10(b)(2)(v)	Actions Taken to Minimize Emissions During SSM.	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See § 63.7842(a)(4) for records of actions taken to minimize emissions.
§ 63.10(b)(2)(vi)	Recordkeeping for CMS Malfunctions.	Yes.	
§ 63.10(b)(2)(vii)–(ix)	Other CMS Requirements.	Yes.	
§ 63.10(b)(2)(xiii)	CMS Records for RATA Alternative.	No.	
§ 63.10(c)(7)–(8)	Records of Excess Emissions and Parameter Monitoring Exceedances for CMS.	No	Subpart FFFFF specifies record requirements; see § 63.7842.
§ 63.10(c)(15)	Use of SSM Plan	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	
§ 63.10(d)(5)(i)	Periodic SSM Reports	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	See § 63.7841(b)(4) for malfunction reporting requirements.
§ 63.10(d)(5)(ii)	Immediate SSM Reports	No, for new or reconstructed sources which commenced construction or reconstruction after August 16, 2019. For all other affected sources, Yes on or before January 11, 2021, and No thereafter.	
§ 63.10(e)(3)	Excess Emission Reports	No	Subpart FFFFF specifies reporting requirements; see § 63.7841.
§ 63.11	Control Device Requirements.	No	Subpart FFFFF does not require flares.
§ 63.12	State Authority and Delegations.	Yes.	

Citation	Subject	Applies to subpart FFFFF	Explanation
§ 63.13–§ 63.16	Addresses, Incorporations by Reference, Availability of Information and Confidentiality, Performance Track Provisions.	Yes.	

[89 FR 23329, Apr. 3, 2024]

TABLE 5 TO SUBPART FFFFF OF PART 63—TOXIC EQUIVALENCY FACTORS

As stated in § 63.7825(u), you must demonstrate compliance with each dioxin/furan emission limit that applies to you by calculating the sum of the 2,3,7,8-TCDD TEQs using the 2005 World Health Organization (WHO) toxicity equivalence factors (TEF) presented in the following table:

For each dioxin/furan congener . . .	You must calculate its 2,3,7,8-TCDD TEQ using the following TEF . . .
2,3,7,8-tetrachlorodibenzo-p-dioxin	1
1,2,3,7,8-pentachlorodibenzo-p-dioxin	1
1,2,3,4,7,8-hexachlorodibenzo-p-dioxin	0.1
1,2,3,7,8,9-hexachlorodibenzo-p-dioxin	0.1
1,2,3,6,7,8-hexachlorodibenzo-p-dioxin	0.1
1,2,3,4,6,7,8-heptachlorodibenzo-p-dioxin	0.01
Octachlorodibenzo-p-dioxin	0.0003
2,3,7,8-tetrachlorodibenzofuran	0.1
1,2,3,7,8-pentachlorodibenzofuran	0.03
2,3,4,7,8-pentachlorodibenzofuran	0.3
1,2,3,4,7,8-hexachlorodibenzofuran	0.1
1,2,3,6,7,8-hexachlorodibenzofuran	0.1
1,2,3,7,8,9-hexachlorodibenzofuran	0.1
2,3,4,6,7,8-hexachlorodibenzofuran	0.1
1,2,3,4,6,7,8-heptachlorodibenzofuran	0.01
1,2,3,4,7,8,9-heptachlorodibenzofuran	0.01
Octachlorodibenzofuran	0.0003

[89 FR 23335, Apr. 3, 2024]

TABLE 6 TO SUBPART FFFFF OF PART 63—LIST OF POLYCYCLIC AROMATIC HYDROCARBONS

As stated in § 63.7825(x), you must demonstrate compliance with each polycyclic aromatic hydrocarbon emission limit that applies to you by calculating the sum of the emissions of each polycyclic aromatic hydrocarbon in the following table:

Pollutant name	CAS No.
Acenaphthene	83–32–9
Acenaphthylene	208–96–8
Anthracene	120–12–7
Benz[a]anthracene	56–55–3
Benzo[a]pyrene	50–32–8
Benzo[b]fluoranthene	205–99–2
Benzo[g,h,i]perylene	191–24–2
Benzo[k]fluoranthene	207–08–9
Chrysene	218–01–9
Dibenz[a,h]anthracene	53–70–3
Fluoranthene	206–44–0
Fluorene	86–73–7
Indeno (1,2,3-cd) pyrene	193–39–5
Naphthalene	91–20–3
Phenanthrene	85–01–8
Perylene	198–55–0
Pyrene	129–00–0

[89 FR 23335, Apr. 3, 2024]

Subpart GGGGG—National Emission Standards for Hazardous Air Pollutants: Site Remediation

SOURCE: 68 FR 58190, Oct. 8, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7880 What is the purpose of this subpart?

This subpart establishes national emissions limitations and work practice standards for hazardous air pollutants (HAP) emitted from site remediation activities. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emissions limitations and work practice standards.

§ 63.7881 Am I subject to this subpart?

(a) This subpart applies to you if you own or operate a facility at which you conduct a site remediation, as defined in § 63.7957; and this site remediation, unless exempted under paragraph (b) or (c) of this section, meets all three of the following conditions specified in paragraphs (a)(1) through (3) of this section.

(1) Your site remediation cleans up a remediation material, as defined in § 63.7957.

(2) Your site remediation is co-located at your facility with one or more other stationary sources that emit HAP and meet an affected source definition specified for a source category that is regulated by another subpart under 40 CFR part 63. This condition applies regardless whether or not the affected stationary source(s) at your facility is subject to the standards under the applicable subpart(s).

(3) Your facility is a major source of HAP as defined in § 63.2, except as specified in paragraph (a)(3)(i) or (ii) of this section. A major source emits or has the potential to emit any single HAP at the rate of 10 tons (9.07 megagrams) or more per year or any combination of HAP at a rate of 25 tons (22.68 megagrams) or more per year.

(i) For production field facilities, as defined in § 63.761, only the HAP emissions from the glycol dehydration units and storage vessels with the potential for flash emissions (both as defined in § 63.761) shall be aggregated with the HAP emissions from the site remediation activities at the facility for a major source determination.

(ii) For natural gas transmission and storage facilities, HAP emissions shall be aggregated in accordance with the definition of major source in § 63.1271 for a major source determination.

(b) You are not subject to this subpart if your site remediation qualifies for any of one of the exemptions listed in paragraphs (b)(1) through (6) of this section.

(1) Your site remediation is not subject to this subpart if the site remediation only cleans up material that does not contain any of the HAP listed in Table 1 of this subpart.

(2)–(3) [Reserved]

(4) Your site remediation is not subject to this subpart if the site remediation is conducted at a gasoline service station to clean up remediation material from a leaking underground storage tank.

(5) Your site remediation is not subject to this subpart if the site remediation is conducted at a farm or residential site.

(6) Your site remediation is not subject to this subpart if the site remediation is conducted at a research and development facility that meets the requirements under Clean Air Act (CAA) section 112(c)(7).

(c) Your site remediation activities are not subject to the requirements of this subpart, except for the recordkeeping requirements in this paragraph, provided that you meet the requirements specified in paragraphs (c)(1) through (c)(3) of this section.

(1) You determine that the total quantity of the HAP listed in Table 1 to this subpart that is contained in the remediation material excavated, extracted, pumped, or otherwise removed during all of the site remediations conducted at your facility is less than 1 megagram (Mg) annually. This exemption applies the 1 Mg limit on a facility-wide, annual basis, and there is no restriction to the number of site remediations that can be conducted during this period.

(2) You must prepare and maintain at your facility written documentation to

support your determination that the total HAP quantity in your remediation materials for the year is less than 1 Mg. The documentation must include a description of your methodology and data used for determining the total HAP content of the remediation material.

(3) Your Title V permit does not have to be reopened or revised solely to include the recordkeeping requirement specified in paragraph (c)(2) of this section. However, the requirement must be included in your permit the next time the permit is renewed, reopened, or revised for another reason.

(d) Your site remediation is not subject to the requirements of this subpart if all remediation activities at your facility subject to this subpart are completed and you have notified the Administrator in writing that all remediation activities subject to this subpart are completed. You must maintain records of compliance, in accordance with § 63.7953, for each remediation activity that was subject to this subpart. All future remediation activity meeting the applicability criteria in this section must comply with the requirements of this subpart.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69016, Nov. 29, 2006; 87 FR 78558, Dec. 22, 2022]

§ 63.7882 What site remediation sources at my facility does this subpart affect?

(a) This subpart applies to each new, reconstructed, or existing affected source for your Site Remediation as designated by paragraphs (a)(1) through (4) of this section.

(1) *Process vents.* The affected source is the entire group of process vents associated with the in-situ and ex-situ remediation processes used at your site to remove, destroy, degrade, transform, or immobilize hazardous substances in the remediation material subject to remediation. Examples of such in-situ remediation processes include, but are not limited to, soil vapor extraction and bioremediation processes. Examples of such ex-situ remediation processes include but are not limited to, thermal desorption, bioremediation, and air stripping processes.

(2) *Remediation material management units.* Remediation material management unit means a tank, surface impoundment, container, oil-water separator, organic-water separator, or transfer system, as defined in § 63.7957, and is used at your site to manage remediation material. The affected source is the entire group of remediation material management units used for the site remediations at your site. For the purpose of this subpart, a tank or container that is also equipped with a vent that serves as a process vent, as defined in § 63.7957, is not a remediation material management unit, but instead this unit is considered to be a process vent affected source under paragraph (a)(1) of this section.

(3) *Equipment leaks.* The affected source is the entire group of equipment components (pumps, valves, etc.) used to manage remediation materials and meeting both of the conditions specified in paragraphs (a)(3)(i) and (ii) of this section. If either of these conditions do not apply to an equipment component, then that component is not part of the affected source for equipment leaks.

(i) The equipment component contains or contacts remediation material having a concentration of total HAP listed in Table 1 of this subpart equal to or greater than 10 percent by weight.

(ii) The equipment component is intended to operate for 300 hours or more during a calendar year in remediation material service, as defined in § 63.7957.

(4) *Pressure relief devices.* The affected source is any pressure relief device in remediation material service, as defined in § 63.7957. Pressure relief devices meeting the specifications of paragraph (a)(3) of this section are also part of an equipment leaks affected source.

(b) Each affected source for your site is existing if you commenced construction or reconstruction of the affected source before July 30, 2002.

(c) Each affected source for your site is new if you commenced construction or reconstruction of the affected source on or after July 30, 2002. An affected source is reconstructed if it meets the definition of reconstruction in § 63.2.

(d) Notwithstanding paragraphs (b) and (c) of this section:

(1) Each affected source for your site is considered an existing source if your

site remediation commenced construction or reconstruction under the authority of the Comprehensive Environmental Response and Compensation Liability Act (CERCLA) as a remedial action or a non-time-critical removal action on or before May 13, 2016.

(2) Each affected source for your site is considered an existing source if your site remediation commenced construction or reconstruction under a Resource Conservation and Recovery Act (RCRA) corrective action conducted at a treatment, storage, and disposal facility (TSDF) that is either required by your permit issued by either the U.S. Environmental Protection Agency (EPA) or a state program authorized by the EPA under RCRA section 3006; required by orders authorized under RCRA; or required by orders authorized under RCRA section 7003 on or before May 13, 2016.

(3) Each affected source for your site is considered a new source if your site remediation commenced construction or reconstruction under the authority of CERCLA as a remedial action or a non-time-critical removal action after May 13, 2016.

(4) Each affected source for your site is considered a new source if your site remediation commenced construction or reconstruction under a RCRA corrective action conducted at a TSDF that is either required by your permit issued by either the U.S. Environmental Protection Agency (EPA) or a State program authorized by the EPA under RCRA section 3006; required by orders authorized under RCRA; or required by orders authorized under RCRA section 7003 after May 13, 2016.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41702, July 10, 2020; 87 FR 78558, Dec. 22, 2022]

§ 63.7883 When do I have to comply with this subpart?

(a) If you have an existing affected source, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you no later than October 9, 2006, except as provided in paragraph (f) of this section.

(b) If you have a new affected source that manages remediation material other than a radioactive mixed waste as defined in § 63.7957, then you must meet the compliance date specified in paragraph (b)(1) or (2) of this section, as applicable to your affected source, except as provided in paragraph (f) of this section.

(1) If the affected source's initial startup date is on or before October 8, 2003, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you by October 8, 2003.

(2) If the affected source's initial startup date is after October 8, 2003, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you upon initial startup.

(c) If you have a new affected source that manages remediation material that is a radioactive mixed waste as defined in § 63.7957, then you must meet the compliance date specified in paragraph (c)(1) or (2) of this section, as applicable to your affected source, except as provided in paragraph (f) of this section.

(1) If the affected source's initial startup date is on or before October 8, 2003, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you no later than October 9, 2006.

(2) If the affected source's initial startup date is after October 8, 2003, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you upon initial startup.

(d) If your facility is an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP as defined in § 63.2, then you must meet the compliance dates specified in paragraphs (d)(1) and (2) of this section, except as provided in paragraph (f) of this section.

(1) For each source at your facility that is a new affected source subject to this subpart, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart

that applies to you upon initial startup.

(2) For all other affected sources subject to this subpart, you must comply with each emission limitation, work practice standard, and operation and maintenance requirement in this subpart that applies to you no later than 3 years after your facility becomes a major source.

(e) You must meet the notification requirements, according to the schedule applicable to your facility, as specified in §63.7950 and in 40 CFR part 63, subpart A. Some of the notifications must be submitted before you are required to comply with the emissions limitations and work practice standards in this subpart.

(f) If the affected source's initial startup date is on or before September 3, 2019, you must comply with the requirements specified in paragraphs (f)(1) through (5) of this section by the dates specified in those paragraphs. If the affected source's initial startup date is after September 3, 2019, you must comply with all of the applicable requirements of this subpart upon initial startup or July 10, 2020, whichever is later.

(1) You must comply with the equipment leak requirements of §63.7920(b)(3), (d), and (e) on or before July 10, 2021.

(2) You must comply with the pressure relief device requirements of §63.7923(a) on or before January 6, 2021.

(3) You must comply with the pressure relief device requirements of §63.7923(b) through (f) on or before January 10, 2022.

(4) You must comply with the pressure tank closure device reporting and recordkeeping requirements of §§63.7951(b)(11) and 63.7952(a)(7) on or before January 6, 2021.

(5) You must comply with the electronic reporting requirements of §63.7951(e) through (h) on or before January 6, 2021.

(g) Notwithstanding paragraphs (a) through (f) of this section, the following dates for compliance apply to sources identified in §63.7882(d):

(1) Site remediations identified in §63.7882(d)(1) and (2) must comply with the requirements of this subpart that apply to you no later than June 24, 2024.

(2) Site remediations identified in §63.7882(d)(3) and (4) must comply with the requirements of this subpart that apply to you no later than December 22, 2022, or upon initial startup, whichever is later.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41703, July 10, 2020; 87 FR 78558, Dec. 22, 2022]

GENERAL STANDARDS

§63.7884 What are the general standards I must meet for each site remediation with affected sources?

(a) For each site remediation with an affected source designated under §63.7882, you must meet the standards specified in §§63.7885 through 63.7955, as applicable to your affected source, unless your site remediation meets the requirements for an exemption under paragraph (b) of this section.

(b) A site remediation that is completed within 30 consecutive calendar days according to the conditions in paragraphs (b)(1) through (3) of this section is not subject to the standards under paragraph (a) of this section. This exemption cannot be used for a site remediation involving the staged or intermittent cleanup of remediation material whereby the remediation activities at the site are started, stopped, and then re-started in a series of intervals, with durations less than 30-days per interval, when the time period from the beginning of the first interval to the end of the last interval exceeds 30 days.

(1) The 30 consecutive calendar day period for a site remediation that qualifies for this exemption is determined according to actions taken by you as defined in paragraphs (b)(1)(i) through (iii) of this section.

(i) The first day of the 30-day period is defined as the day on which you initiate any action that removes, destroys, degrades, transforms, immobilizes, or otherwise manages the remediation materials. The following activities, when completed before beginning this initial action, are not counted as part of the 30-day period: Activities to characterize the type and extent of the contamination by collecting and analyzing samples; activities to obtain

permits from Federal, State, or local authorities to conduct the site remediation; activities to schedule workers and necessary equipment; and activities to arrange for contractor or third party assistance in performing the site remediation.

(ii) The last day of the 30-day period is defined as the day on which treatment or disposal of all of the remediation materials generated by the cleanup is completed such that the organic constituents in these materials no longer have a reasonable potential for volatilizing and being released to the atmosphere.

(iii) If treatment or disposal of the remediation materials is conducted at an off-site facility where the final treatment or disposal of the material cannot, or may not, be completed within the 30-day exemption period, then the shipment of all of the remediation material generated from your cleanup that is transferred to another party, or shipped to another facility, within the 30-day period, must be performed according to the applicable requirements specified in § 63.7936.

(2) For the purpose of complying with paragraph (b)(1) of this section, if you ship or otherwise transfer the remediation material off-site you must include in the applicable shipping documentation, in addition to any notifications and certifications required under § 63.7936, a statement that the shipped material was generated by a site remediation activity subject to the conditions of this exemption. The statement must include the date on which you initiated the site remediation activity generating the shipped remediation materials, as specified in paragraph (b)(1)(i) of this section, and the date 30 calendar days following your initiation date.

(3) You must prepare and maintain at your facility written documentation describing the exempted site remediation, and listing the initiation and completion dates for the site remediation.

[71 FR 69016, Nov. 29, 2006]

§ 63.7885 What are the general standards I must meet for my affected process vents?

(a) For the process vents that comprise the affected source designated under § 63.7882, you must select and meet the requirements under one of the options specified in paragraph (b) of this section.

(b) For each affected process vent, except as exempted under paragraph (c) of this section, you must meet one of the options in paragraphs (b)(1) through (3) of this section.

(1) You control HAP emissions from the affected process vents according to the standards specified in §§ 63.7890 through 63.7893.

(2) You determine for the remediation material treated or managed by the process vented through the affected process vents that the average total volatile organic hazardous air pollutant (VOHAP) concentration, as defined in § 63.7957, of this material is less than 10 parts per million by weight (ppmw). Determination of the VOHAP concentration is made using the procedures specified in § 63.7943.

(3) If the process vent is also subject to another subpart under 40 CFR part 61 or 40 CFR part 63, you control emissions of the HAP listed in Table 1 of this subpart from the affected process vent in compliance with the standards specified in the applicable subpart. This means you are complying with all applicable emissions limitations and work practice standards under the other subpart (*e.g.*, you install and operate the required air pollution controls or have implemented the required work practice to reduce HAP emissions to levels specified by the applicable subpart). This provision does not apply to any exemption of the affected source from the emissions limitations and work practice standards allowed by the other applicable subpart.

(c) A process vent that meets the exemption requirements in paragraphs (c)(1) and (2) of this section is exempted from the requirements in paragraph (b) of this section.

(1) The process vent stream exiting the process vent meets the conditions in either paragraph (c)(1)(i) or (ii) of this section.

(i) The process vent stream flow rate is less than 0.005 cubic meters per minute (m^3/min) at standard conditions (as defined in 40 CFR 63.2); or

(ii) The process vent stream flow rate is less than 6.0 m^3/min at standard conditions (as defined in 40 CFR 63.2) and the total concentration of HAP listed in Table 1 of this subpart is less than 20 parts per million by volume (ppmv).

(2) You must demonstrate that the process vent stream meets the applicable exemption conditions in paragraph (c)(1) of this section using the procedures specified in § 63.694(m). You must prepare and maintain documentation at your facility to support your determination of the process vent stream flow rate. This documentation must include identification of each process vent exempted under this paragraph and the test results used to determine the process vent stream flow rate and total HAP concentration, as applicable to the exemption conditions for your process vent. You must perform a new determination of the process vent stream flow rate and total HAP concentration, as applicable to the exemption conditions for your process vent, whenever changes to operation of the unit on which the process vent is used could cause the process vent stream conditions to exceed the maximum limits of the exemption.

§ 63.7886 What are the general standards I must meet for my affected remediation material management units?

(a) For each remediation material management unit that is part of an affected source designated by § 63.7882, you must select and meet the requirements under one of the options specified in paragraph (b) of this section except for those remediation material management units exempted under paragraph (c) or (d) of this section.

(b) For each affected remediation material management unit, you must meet one of the options in paragraphs (b)(1) through (4) of this section.

(1) You control HAP emissions from the affected remediation material management unit according to the standards specified in paragraphs (b)(1)(i) through (v) of this section, as applicable to the unit.

(i) If the remediation material management unit is a tank, then you control HAP emissions according to the standards specified in §§ 63.7895 through 63.7898.

(ii) If the remediation material management unit is a container, then you control HAP emissions according to the standards specified in §§ 63.7900 through 63.7903.

(iii) If the remediation material management unit is a surface impoundment, then you control HAP emissions according to the standards specified in §§ 63.7905 through 63.7908.

(iv) If the remediation material management unit is an oil-water or organic-water separator, then you control HAP emissions according to the standards specified in §§ 63.7910 through 63.7913.

(v) If the remediation material management unit is a transfer system, then you control HAP emissions according to the standards specified in §§ 63.7915 through 63.7918.

(2) You determine that the average total VOHAP concentration, as defined in § 63.7957, of the remediation material managed in the remediation material management unit material is less than 500 ppmw. You must follow the requirements in § 63.7943 to demonstrate that the VOHAP concentration of the remediation material is less than 500 ppmw. Once the VOHAP concentration for a remediation material has been determined to be less than 500 ppmw, all remediation material management units downstream from the point of determination managing this material meet the requirements of this paragraph unless a remediation process is used that concentrates all, or part of, the remediation material being managed in the unit such that the VOHAP concentration of the material could increase. Any free product returned to the manufacturing process (*e.g.*, recovered oil returned to a storage tank at a refinery) is no longer subject to this subpart.

(3) If the remediation material management unit is also subject to another subpart under 40 CFR part 61 or 40 CFR part 63, you control emissions of the HAP listed in Table 1 of this subpart from the affected remediation material management unit in compliance with

the standards specified in the applicable subpart. This means you are complying with all applicable emissions limitations and work practice standards under the other subpart (*e.g.*, you install and operate the required air pollution controls or have implemented the required work practice to reduce HAP emissions to levels specified by the applicable subpart). This provision does not apply to any exemption of the affected source from the emissions limitations and work practice standards allowed by the other applicable subpart.

(4) If the remediation material management unit is an open tank or surface impoundment used for a biological treatment process, you meet the requirements as specified in paragraphs (b)(4)(i) and (ii) of this section.

(i) You demonstrate that the biological treatment process conducted in the open tank or surface impoundment meets the performance levels specified in either § 63.684(b)(4)(i) or (ii).

(ii) You monitor the biological treatment process conducted in the open tank or surface impoundment according to the requirements in § 63.684(e)(4).

(c) A remediation material management unit is exempted from the requirements in paragraph (b) of this section if this unit is used for cleanup of radioactive mixed waste, as defined in § 63.7957, that is subject to applicable regulations, directives, and other requirements under the Atomic Energy Act, the Nuclear Waste Policy Act, or the Waste Isolation Pilot Plant Land Withdrawal Act.

(d) One or a combination of remediation material management units may be exempted at your discretion from the requirements in paragraph (b) of this section provided that the total annual quantity of HAP listed in Table 1 of this subpart contained in the remediation material placed in all of the remediation material management units exempted under this paragraph is less than 1 Mg/yr. For each remediation material management unit you select to be exempted under this provision, you must meet the requirements in paragraphs (d)(1) and (2) of this section.

(1) You must designate each of the remediation material management units you are selecting to be exempted under this paragraph by either submitting to the Administrator a written notification identifying the exempt units or permanently marking the exempt units at the faculty site. If you choose to prepare and submit a written notification, this notification must include a site plan, process diagram, or other appropriate documentation identifying each of the exempt units. If you choose to permanently mark the exempt units, each exempt unit must be marked in such a manner that it can be readily identified as an exempt unit from the other remediation material management units located at the site.

(2) You must prepare an initial determination of the total annual HAP quantity in the remediation material placed in the units exempted under this paragraph. This determination is based on the total quantity of the HAP listed in Table 1 of this subpart as determined at the point where the remediation material is placed in each exempted unit. You must perform a new determination whenever the extent of changes to the quantity or composition of the remediation material placed in the exempted units could cause the total annual HAP content in the remediation material to exceed 1 Mg/yr. You must maintain documentation to support the most recent determination of the total annual HAP quantity. This documentation must include the basis and data used for determining the organic HAP content of the remediation material.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69017, Nov. 29, 2006]

§ 63.7887 What are the general standards I must meet for my affected equipment leak sources?

(a) You must control HAP emissions from equipment leaks from each equipment component that is part of the affected source by implementing leak detection and control measures according to the standards specified in §§ 63.7920 through 63.7922 unless you elect to meet the requirements in paragraph (b) of this section.

(b) If the affected equipment leak source is also subject to another subpart in 40 CFR part 61 or 40 CFR part 63, you may control emissions of the HAP listed in Table 1 to this subpart

from the affected equipment leak source in compliance with the standards specified in the other applicable subpart. This means you are complying with all applicable emissions limitations and work practice standards under the other subpart (*e.g.*, you implement leak detection and control measures to reduce HAP emissions as specified by the applicable subpart). This provision does not apply to any exemption of the affected source from the emissions limitations and work practice standards allowed by the other applicable subpart.

[71 FR 69017, Nov. 29, 2006]

§ 63.7888 How do I implement this rule at my facility using the cross-referenced requirements in other subparts?

(a) For the purposes of this subpart, when you read the term ''HAP listed in Table 1 of this subpart'' in a cross-referenced section under 40 CFR part 63, subpart DD—National Emission Standards for Hazardous Air Pollutants from Off-Site Waste and Recovery Operations, you should refer to Table 1 of this subpart.

(b) For the purposes of this subpart, when you read the term off-site material in a cross-referenced section under 40 CFR part 63, subpart DD—National Emission Standards for Hazardous Air Pollutants from Off-Site Waste and Recovery Operations you should substitute the term remediation material, as defined in § 63.7957.

(c) For the purposes of this subpart, when you read the term regulated material in a cross-referenced section under 40 CFR part 63, subparts OO, PP, QQ, RR, TT, UU, WW, and VV you should substitute the term remediation material, as defined in § 63.7957.

PROCESS VENTS

§ 63.7890 What emissions limitations and work practice standards must I meet for process vents?

(a) You must control HAP emissions from each new and existing process vent subject to § 63.7885(b)(1) according to emissions limitations and work practice standards in this section that apply to your affected process vents.

(b) For your affected process vents, you must meet one of the facility-wide emission limit options specified in paragraphs (b)(1) through (4) of this section. If you have multiple affected process vent streams, you may comply with this paragraph using a combination of controlled and uncontrolled process vent streams that achieve the facility-wide emission limit that applies to you.

(1) Reduce from all affected process vents the total emissions of the HAP listed in Table 1 of this subpart to a level less than 1.4 kilograms per hour (kg/hr) and 2.8 Mg/yr (3.0 pounds per hour (lb/hr) and 3.1 tpy); or

(2) Reduce from all affected process vents the emissions of total organic compounds (TOC) (minus methane and ethane) to a level below 1.4 kg/hr and 2.8 Mg/yr (3.0 lb/hr and 3.1 tpy); or

(3) Reduce from all affected process vents the total emissions of the HAP listed in Table 1 of this subpart by 95 percent by weight or more; or

(4) Reduce from all affected process vents the emissions of TOC (minus methane and ethane) by 95 percent by weight or more.

(c) For each closed vent system and control device you use to comply with paragraph (b) of this section, you must meet the operating limit requirements and work practice standards in § 63.7925(c) through (j) that apply to your closed vent system and control device.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69017, Nov. 29, 2006]

§ 63.7891 How do I demonstrate initial compliance with the emissions limitations and work practice standards for process vents?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7890(b) applicable to your affected process vents by meeting the requirements in paragraphs (b) through (d) of this section.

(b) You have measured or determined using the procedures for performance tests and design evaluations in § 63.7941 that emission levels from all of your affected process vents meet the facility-wide emission limits in § 63.7890(b)

that apply to you, as follows in paragraphs (b)(1) through (4) of this section.

(1) If you elect to meet § 63.7890(b)(1), you demonstrate that the total emissions of the HAP listed in Table 1 of this subpart from all affected process vents at your facility are less than 1.4 kg/hr and 2.8 Mg/yr (3.0 lb/hr and 3.1 tpy).

(2) If you elect to meet § 63.7890(b)(2), you demonstrate that emissions of TOC (minus methane and ethane) from all affected process vents at your facility are less than 1.4 kg/hr and 2.8 Mg/yr (3.0 lb/hr and 3.1 tpy).

(3) If you elect to meet § 63.7890(b)(3), you demonstrate that the total emissions of the HAP listed in Table 1 of this subpart from all affected process vents are reduced by 95 percent by weight or more.

(4) If you elect to meet § 63.7890(b)(4), you demonstrate that the emissions of TOC (minus methane and ethane) from all affected process vents are reduced by 95 percent by weight or more.

(c) For each closed vent system and control device you use to comply with § 63.7890(b), you have met each requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

(d) You have submitted a notification of compliance status according to the requirements in § 63.7950.

§ 63.7892 What are my inspection and monitoring requirements for process vents?

For each closed vent system and control device you use to comply with § 63.7890(b), you must monitor and inspect the closed vent system and control device according to the requirements in § 63.7927 that apply to you.

§ 63.7893 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for process vents?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in § 63.7890 applicable to your affected process vents by meeting the requirements in paragraphs (b) through (d) of this section.

(b) You must maintain emission levels from all of your affected process vents to meet the facilitywide emission limits in § 63.7890(b) that apply to you, as specified in paragraphs (b)(1) through (4) of this section.

(1) If you elect to meet § 63.7890(b)(1), you maintain the total emissions of the HAP listed in Table 1 of this subpart from all affected process vents at your facility are less than 1.4 kg/hr and 2.8 Mg/yr (3.0 lb/hr and 3.1 tpy).

(2) If you elect to meet § 63.7890(b)(2), you maintain emissions of TOC (minus methane and ethane) from all affected process vents at your facility are less than 1.4 kg/hr and 2.8 Mg/yr (3.0 lb/hr and 3.1 tpy).

(3) If you elect to meet § 63.7890(b)(3), you maintain the total emissions of the HAP listed in Table 1 of this subpart from all affected process vents are reduced by 95 percent by weight or more.

(4) If you elect to meet § 63.7890(b)(4), you maintain that the emissions of TOC (minus methane and ethane) from all affected process vents are reduced by 95 percent by weight or more.

(c) For each closed vent system and control device you use to comply with § 63.7890(b), you have met each requirement for demonstrating continuous compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7928.

(d) Keeping records to document continuous compliance with the requirements of this subpart according to the requirements in § 63.7952.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69017, Nov. 29, 2006]

TANKS

§ 63.7895 What emissions limitations and work practice standards must I meet for tanks?

(a) You must control HAP emissions from each new and existing tank subject to § 63.7886(b)(1)(i) according to emissions limitations and work practice standards in this section that apply to your affected tanks.

(b) For each affected tank, you must install and operate air pollution controls that meet the requirements in

paragraphs (b)(1) through (4) of this section that apply to your tank.

(1) Unless your tank is used for a waste stabilization process, as defined in § 63.7957, you must determine the maximum HAP vapor pressure (expressed in kilopascals (kPa)) of the remediation material placed in your tank using the procedures specified in § 63.7944.

(2) If the maximum HAP vapor pressure of the remediation material you place in your tank is less than 76.6 kPa, then you must determine which tank level controls (*i.e.*, Tank Level 1 or Tank Level 2) apply to your tank as shown in Table 2 of this subpart, and based on your tank's design capacity (expressed in cubic meters (m^3)) and the maximum HAP vapor pressure of the remediation material you place in this tank. If your tank is required by Table 2 of this subpart to use Tank Level 1 controls, then you must meet the requirements in paragraph (c) of this section. If your tank is required by Table 2 of this subpart to use Tank Level 2 controls, then you must meet the requirements in paragraph (d) of this section

(3) If maximum HAP vapor pressure of the remediation material you place in your tank is 76.6 kPa or greater, then the tank must use one of the Tank Level 2 controls specified in paragraphs (d)(3) through (5) of this section. Use of floating roofs under paragraph (d)(1) or (2) of this section is not allowed for tanks managing these remediation materials.

(4) A tank used for a waste stabilization process, as defined in § 63.7957, must use one of Tank Level 2 controls, as specified in paragraph (d) of this section, that is appropriate for your waste stabilization process.

(c) If you use Tank Level 1 controls, you must install and operate a fixed roof according to the requirements in § 63.902, with the exceptions specified in paragraphs (c)(1) and (2) of this section. As an alternative to using this fixed roof, you may choose to use one of Tank Level 2 controls in paragraph (d) of this section.

(1) Where § 63.902(c)(2) provides an exception for a spring-loaded pressure-vacuum relief valve, conservation vent, or similar type of pressure relief device which vents to the atmosphere, for any source for the purposes of this subpart, only a conservation vent is eligible for the exception after January 6, 2021. If your initial startup date is after September 3, 2019, the exception for a spring-loaded pressure-vacuum relief valve, conservation vent, or similar type of pressure relief device does not apply, with the exception of a conservation vent, for the purposes of this subpart after July 10, 2020.

(2) The provisions of § 63.902(c)(3) do not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; for any source the provisions of § 63.902(c)(3) do not apply for the purposes of this subpart after January 6, 2021.

(d) If you use Tank Level 2 controls, you must meet the requirements of one of the options in paragraphs (d)(1) through (5) of this section.

(1) Install and operate a fixed roof with an internal floating roof according to the requirements in § 63.1063(a)(1)(i), (a)(2), and (b); or

(2) Install and operate an external floating roof according to the requirements in § 63.1063(a)(1)(ii), (a)(2), and (b); or

(3) Install and operate a fixed roof vented through a closed vent system to a control device according to the requirements in § 63.685(g). You must meet the emissions limitations and work practice standards in § 63.7925 that apply to your closed vent system and control device; or

(4) Install and operate a pressure tank according to the requirements in § 63.685(h); or

(5) Locate the tank inside a permanent total enclosure and vent emissions from the enclosure through a closed vent system to a control device that is an enclosed combustion device according to the requirements in § 63.685(i). You must meet the emissions limitations and work practice standards in § 63.7925 that apply to your closed vent system and control device.

(e) As provided in § 63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your tanks. If you request for permission to use an alternative to the work

practice standards, you must submit the information described in § 63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41703, July 10, 2020]

§ 63.7896 How do I demonstrate initial compliance with the emissions limitations and work practice standards for tanks?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7895 that apply to your affected tanks by meeting the requirements in paragraphs (b) through (h) of this section, as applicable to your containers.

(b) You have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(1) and (2) of this section.

(1) You have determined the applicable tank control levels specified in § 63.7895(b) for the tanks to be used for your site remediation.

(2) You have determined, according to the procedures in § 63.7944, and recorded the maximum HAP vapor pressure of the remediation material placed in each affected tank subject to § 63.7886(b)(1)(i) that does not use Tank Level 2 controls.

(c) You must demonstrate initial compliance of each tank determined under paragraph (b) of this section to require Tank Level 1 controls if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (c)(1) through (3) of this section.

(1) Each tank using Tank Level 1 controls is equipped with a fixed roof and closure devices according to the requirements in § 63.902(b) and (c), with the exceptions specified in § 63.7895(c)(1) and (2), and you have records documenting the design.

(2) You have performed an initial visual inspection of the fixed roof and closure devices for defects according to the requirements in § 63.906(a) and you have records documenting the inspection results.

(3) You will operate the fixed roof and closure devices according to the requirements in § 63.902, with the exceptions specified in § 63.7895(c)(1) and (2).

(d) You must demonstrate initial compliance of each tank determined under paragraph (b) of this section to require Tank Level 2 controls and using a fixed roof with an internal floating roof according to § 63.7895(d)(1) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (d)(1) through (3) of this section.

(1) Each tank is equipped with an internal floating roof that meets the requirements in § 63.1063(a) and you have records documenting the design.

(2) You will operate the internal floating roof according to the requirements in § 63.1063(b).

(3) You have performed an initial visual inspection according to the requirements in § 63.1063(d)(1) and you have a record of the inspection results.

(e) You must demonstrate initial compliance of each tank determined under paragraph (b) of this section to require Tank Level 2 controls and using an external floating roof according to § 63.7895(d)(2) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (e)(1) through (3) of this section.

(1) Each tank is equipped with an external floating roof that meets the requirements in § 63.1063(a) and you have records documenting the design.

(2) You will operate the external floating roof according to the requirements in § 63.1063(b).

(3) You have performed an initial seal gap measurement inspection according to the requirements in § 63.1063(d)(3) and you have records of the measurement results.

(f) You must demonstrate initial compliance of each tank determined under paragraph (b) of this section to require Tank Level 2 controls and using a fixed roof vented to a control device according to § 63.7895(d)(3) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (f)(1) through (4) of this section.

(1) Each tank is equipped with a fixed roof and closure devices according to

the requirements in § 63.685(g), with the exceptions specified in § 63.7895(c)(1) and (2), and you have records documenting the design.

(2) You have performed an initial visual inspection of fixed roof and closure devices for defects according to the requirements in § 63.695(b)(3) and you have records documenting the inspection results.

(3) You will operate the fixed roof and closure devices according to the requirements in § 63.685(g).

(4) You have met each applicable requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

(g) You must demonstrate initial compliance of each tank determined under paragraph (b) of this section to require Tank Level 2 controls and operates as a pressure tank according to § 63.7895(d)(4) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (g)(1) and (2) of this section.

(1) Each tank is designed to operate as a pressure tank according to the requirements in § 63.685(h), and you have records documenting the design.

(2) You will operate the pressure tank and according to the requirements in § 63.685(h).

(h) You must demonstrate initial compliance of each tank determined under paragraph (b) of this section to require Tank Level 2 controls and using a permanent total enclosure vented to an enclosed combustion device according to § 63.7895(d)(5) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (h)(1) and (2) of this section.

(1) You have submitted as part of your notification of compliance status a signed statement that you have performed the verification procedure according to the requirements in § 63.685(i), and you have records of the supporting calculations and measurements.

(2) You have met each applicable requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69017, Nov. 29, 2006; 85 FR 41703, July 10, 2020]

§ 63.7897 What are my inspection and monitoring requirements for tanks?

(a) You must visually inspect each of your tanks using Tank Level 1 controls for defects at least annually according to the requirements in § 63.906(a).

(b) You must inspect and monitor each of your tanks using Tank Level 2 controls according to the requirements in paragraphs (b)(1) through (5), as applicable to your tanks.

(1) If you use a fixed roof with an internal floating roof according to § 63.7895(d)(1), you must visually inspect the fixed roof and internal floating roof according to the requirements in § 63.1063(d)(1) and (2).

(2) If you use an external floating roof according to § 63.7895(d)(2), you must visually inspect the external floating roof according to the requirements in § 63.1063(d)(1) and inspect the seals according to the requirements in § 63.1063(d)(2) and (3).

(3) If you use a fixed roof vented to a control device according to § 63.7895(d)(3), you must meet requirements in paragraphs (b)(3)(i) and (ii) of this section.

(i) You must visually inspect the fixed roof and closure devices for defects according to the requirements in § 63.695(b)(3).

(ii) You must monitor and inspect the closed vent system and control device according to the requirements in § 63.7927 that apply to you.

(4) If you use a pressure tank according to § 63.7895(d)(4), you must visually inspect the tank and its closure devices for defects at least annually to ensure they are operating according to the design requirements in § 63.685(h).

(5) If you use a permanent total enclosure vented to an enclosed combustion device according to § 63.7895(d)(5), you must meet requirements in paragraphs (b)(5)(i) and (ii) of this section.

(i) You must perform the verification procedure for the permanent total enclosure at least annually according to the requirements in § 63.685(i).

(ii) You must monitor and inspect the closed vent system and control device according to the requirements in § 63.7927 that apply to you.

§ 63.7898 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for tanks?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in § 63.7895 applicable to your affected tanks by meeting the requirements in paragraphs (b) through (d) of this section.

(b) You must demonstrate continuous compliance with the requirement to determine the applicable tank control level specified in § 63.7895(b) for each affected tank by meeting the requirements in paragraphs (b)(1) through (3) of this section.

(1) Keeping records of the tank design capacity according to the requirements in § 63.1065(a).

(2) For tanks subject to § 63.7886(b)(1)(ii) and not using Tank Level 2 controls, meeting the requirements in paragraphs (b)(2)(i) and (ii) of this section.

(i) Keeping records of the maximum HAP vapor pressure determined according to the procedures in § 63.7944 for the remediation material placed in each affected tank.

(ii) Performing a new determination of the maximum HAP vapor pressure whenever changes to the remediation material managed in the tank could potentially cause the maximum HAP vapor pressure to increase to a level that is equal to or greater than the maximum HAP vapor pressure for the tank design capacity specified in Table 2. You must keep records of each determination.

(3) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(c) You must demonstrate continuous compliance for each tank determined to require Tank Level 1 controls by meeting the requirements in paragraphs (c)(1) through (5) of this section.

(1) Operating and maintaining the fixed roof and closure devices according to the requirements in § 63.902(c), with the exceptions specified in § 63.7895(c)(1) and (2).

(2) Visually inspecting the fixed roof and closure devices for defects at least annually according to the requirements in § 63.906(a).

(3) Repairing defects according to the requirements in § 63.63.906(b).

(4) Recording the information specified in § 63.907(a)(3) and (b).

(5) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(d) You must demonstrate continuous compliance for each tank determined to require Tank Level 2 controls and using a fixed roof with an internal floating roof according to § 63.7895(d)(1) by meeting the requirements in paragraphs (d)(1) through (5) of this section.

(1) Operating and maintaining the internal floating roof according to the requirements in § 63.1063(b).

(2) Visually inspecting the internal floating roof according to the requirements in § 63.1063(d)(1) and (2).

(3) Repairing defects according to the requirements in § 63.1063(e).

(4) Recording the information specified in § 63.1065(b) through (d).

(5) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(e) You must demonstrate continuous compliance for each tank determined to require Tank Level 2 controls and using an external floating roof according to § 63.7895(d)(2) by meeting the requirements in paragraphs (e)(1) through (5) of this section.

(1) Operating and maintaining the external floating roof according to the requirements in § 63.1063(b).

(2) Visually inspecting the external floating roof according to the requirements in § 63.1063(d)(1) and inspecting the seals according to the requirements in § 63.1063(d)(2) and (3).

(3) Repairing defects according to the requirements in § 63.1063(e).

(4) Recording the information specified in § 63.1065(b) through (d).

(5) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(f) You must demonstrate continuous compliance for each tank determined to require Tank Level 2 controls and using a fixed roof vented to a control device according to §63.7895(d)(3) by meeting the requirements in paragraphs (f)(1) through (6) of this section.

(1) Operating and maintaining the fixed roof and closure devices according to the requirements in §63.685(g).

(2) Visually inspecting the fixed roof and closure devices for defects at least annually according to the requirements in §63.695(b)(3)(i).

(3) Repairing defects according to the requirements in §63.695(b)(4).

(4) Recording the information specified in §63.696(e).

(5) Meeting each applicable requirement for demonstrating continuous compliance with the emission limitations and work practice standards for a closed vent system and control device in §63.7928.

(6) Keeping records to document compliance with the requirements of this subpart according to the requirements in §63.7952.

(g) You must demonstrate continuous compliance for each tank determined to require Tank Level 2 controls and operated as a pressure tank according to §63.7895(d)(4) by meeting the requirements in paragraphs (g)(1) through (3) of this section.

(1) Operating and maintaining the pressure tank and closure devices according to the requirements in §63.685(h).

(2) Visually inspecting each pressurized tank and closure devices for defects at least annually to ensure they are operating according to the design requirements in §63.685(h), and recording the results of each inspection.

(3) Keeping records to document compliance with the requirements of this subpart according to the requirements in §63.7952.

(h) You must demonstrate continuous compliance for each tank determined to require Tank Level 2 controls and using a permanent total enclosure vented to an enclosed combustion device according to §63.7895(d)(5) by meeting the requirements in paragraphs (h)(1) through (4) of this section.

(1) Performing the verification procedure for the enclosure annually according to the requirements in §63.685(i).

(2) Recording the information specified in §63.696(f).

(3) Meeting each applicable requirement for demonstrating continuous compliance with the emissions limitations and work practice standards for a closed vent system and control device in §63.7928.

(4) Keeping records to document compliance with the requirements of this subpart according to the requirements in §63.7952.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69017, Nov. 29, 2006; 85 FR 41703, July 10, 2020]

CONTAINERS

§63.7900 What emissions limitations and work practice standards must I meet for containers?

(a) You must control HAP emissions from each new and existing container subject to §63.7886(b)(1)(ii) according to emissions limitations and work practice standards in this section that apply to your affected containers.

(b) For each container having a design capacity greater than 0.1 m^3 you must meet the requirements in paragraph (b)(1) or (2) of this section that apply to your container except at the times the container is used for treatment of remediation material by a waste stabilization process, as defined in §63.7957. As an alternative for any container subject to this paragraph, you may choose to meet the requirements in paragraph (d) of this section.

(1) If the design capacity of your container is less than or equal to 0.46 m^3, then you must use controls according to the standards for Container Level 1 controls as specified in §63.922. As an alternative, you may choose to use controls according to either of the standards for Container Level 2 controls as specified in §63.923. §63.922(d)(4) and (5) do not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; §63.922(d)(4) and (5) do not apply for the purposes of this subpart for any source after January 6, 2021.

(2) If the design capacity of your container is greater than 0.46 m3, then you must use controls according to the

standards for Container Level 2 controls as specified in § 63.923 except as provided for in paragraph (b)(3) of this section. § 63.923(d)(4) and (5) do not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.923(d)(4) and (5) do not apply for the purposes of this subpart for any source after January 6, 2021.

(3) As an alternative to meeting the standards in paragraph (b)(2) of this section for containers with a capacity greater than 0.46 m3, if you determine that either of the conditions in paragraph (b)(3)(i) or (ii) apply to the remediation material placed in your container, then you may use controls according to the standards for Container Level 1 controls as specified in § 63.922. § 63.922(d)(4) and (5) do not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.922(d)(4) and (5) do not apply for the purposes of this subpart for any source after January 6, 2021.

(c) At times when a container having a design capacity greater than 0.1 m3 is used for treatment of a remediation material by a waste stabilization process as defined in § 63.7957, you must control air emissions from the container during the process whenever the remediation material in the container is exposed to the atmosphere according to the standards for Container Level 3 controls as specified in § 63.924. You must meet the emissions limitations and work practice standards in § 63.7925 that apply to your closed vent system and control device. § 63.924(d) does not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.924(d) does not apply for the purposes of this subpart for any source after January 6, 2021.

(d) As an alternative to meeting the requirements in paragraph (b) of this section, you may choose to use controls on your container according to the standards for Container Level 3 controls as specified in § 63.924. You must meet the emissions limitations and work practice standards in § 63.7925 that apply to your closed vent system and control device. § 63.924(d) does not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.924(d) does not apply for the purposes of this subpart for any source after January 6, 2021.

(e) As provided in § 63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your containers. If you request for permission to use an alternative to the work practice standards, you must submit the information described in § 63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41703, July 10, 2020]

§ 63.7901 How do I demonstrate initial compliance with the emissions limitations and work practice standards for containers?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7900 that apply to your affected containers by meeting the requirements in paragraphs (b) through (e) of this section, as applicable to your containers.

(b) You have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(1) and (2) of this section.

(1) You have determined the applicable container control levels specified in § 63.7900 for the containers to be used for your Site Remediation.

(2) You have determined and recorded the maximum vapor pressure or total organic concentration for the remediation material placed in containers with a design capacity greater than 0.46 m^3, and do not use Container Level 2 or Level 3 controls.

(c) You must demonstrate initial compliance of each container determined under paragraph (b) of this section to require Container Level 1 controls if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (c)(1) and (2) of this section.

(1) Each container using Container Level 1 controls will be one of the containers specified in § 63.922(b).

(2) You will operate each container cover and closure device according to the requirements in § 63.922(d), with the exceptions specified in § 63.7900(b)(1).

(d) You must demonstrate initial compliance of each container determined under paragraph (b) of this section to require Container Level 2 controls if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (d)(1) through (4) of this section.

(1) Each container using Container Level 2 controls will be one of the containers specified in § 63.923(b).

(2) You will transfer remediation materials into and out of each container according to the procedures in § 63.923(d).

(3) You will operate and maintain the container covers and closure devices according to the requirements in § 63.923(d), with the exceptions specified in § 63.7900(b)(2).

(4) You have records that the container meets the applicable U.S. Department of Transportation regulations, or you have conducted an initial test of each container for no detectable organic emissions using the procedures in § 63.925(a), and have records documenting the test results, or you have demonstrated within the last 12 months that each container is vapor-tight according to the procedures in § 63.925(a) and have records documenting the test results.

(e) You must demonstrate initial compliance of each container determined under paragraph (b) of this section to require Container Level 3 controls if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (e)(1) and (2) of this section.

(1) For each permanent total enclosure you use to comply with § 63.7900, you have performed the verification procedure according to the requirements in § 63.924(c)(1), and prepare records of the supporting calculations and measurements.

(2) You have met each applicable requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41704, July 10, 2020]

§ 63.7902 What are my inspection and monitoring requirements for containers?

(a) You must inspect each container using Container Level 1 or Container Level 2 controls according to the requirements in § 63.926(a).

(b) If you use Container Level 3 controls, you must meet requirements in paragraphs (b)(1) and (2) of this section, as applicable to your site remediation.

(1) You must perform the verification procedure for each permanent total enclosure annually according to the requirements in § 63.924(c)(1).

(2) You must monitor and inspect each closed vent system and control device according to the requirements in § 63.7927 that apply to you.

§ 63.7903 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for containers?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in § 63.7900 applicable to your affected containers by meeting the requirements in paragraphs (b) through (e) of this section.

(b) You must demonstrate continuous compliance with the requirement to determine the applicable container control level specified in § 63.7900(b) for each affected tank by meeting the requirements in paragraphs (b)(1) through (3) of this section.

(1) Keeping records of the quantity and design capacity for each type of container used for your site remediation and subject to § 63.7886(b)(1)(ii).

(2) For containers subject to § 63.7886(b)(1)(ii) with a design capacity greater than 0.46 m^3 and not using Container Level 2 or Container Level 3 controls, meeting the requirements in paragraphs (b)(2)(i) and (ii) of this section.

(i) Keeping records of the maximum vapor pressure or total organic concentration for the remediation material placed in the containers, as applicable to the conditions in § 63.7900(b)(3)(i) or (ii) for which your containers qualify to use Container Level 1 controls.

(ii) Performing a new determination whenever changes to the remediation

material placed in the containers could potentially cause the maximum vapor pressure or total organic concentration to increase to a level that is equal to or greater than the conditions specified in § 63.7900(b)(3)(i) or (ii), as applicable to your containers. You must keep records of each determination.

(3) Keeping records to document compliance with the requirements according to the requirements in § 63.7952.

(c) You must demonstrate continuous compliance for each container determined to require Container Level 1 controls by meeting the requirements in paragraphs (c)(1) through (5) of this section.

(1) Operating and maintaining covers for each container according to the requirements in § 63.922(d), with the exceptions specified in § 63.7900(b)(1).

(2) Inspecting each container annually according to the requirements in § 63.926(a)(2).

(3) Emptying or repairing each container according to the requirements in § 63.926(a)(3).

(4) Keeping records of an inspection that includes the information in paragraphs (a)(4)(i) and (ii) of this section.

(i) Date of each inspection; and

(ii) If a defect is detected during an inspection, the location of the defect, a description of the defect, the date of detection, the corrective action taken to repair the defect, and if repair is delayed, the reason for any delay and the date completion of the repair is expected.

(5) Keeping records to document compliance with the requirements according to the requirements in § 63.7952.

(d) You must demonstrate continuous compliance for each container determined to require Container Level 2 controls by meeting the requirements in paragraphs (d)(1) through (6) of this section.

(1) Transferring remediation material in and out of the container according to the requirements in § 63.923(c).

(2) Operating and maintaining container covers according to the requirements in § 63.923(d), with the exceptions specified in § 63.7900(b)(2).

(3) Inspecting each container annually according to the requirements in § 63.926(a)(2).

(4) Emptying or repairing containers according to the requirements in § 63.926(a)(3).

(5) Keeping records of each inspection that include the information in paragraphs (d)(5)(i) and (ii) of this section.

(i) Date of each inspection; and

(ii) If a defect is detected during an inspection, the location of the defect, a description of the defect, the date of detection, the corrective action taken to repair the defect, and if repair is delayed, the reason for any delay and the date completion of the repair is expected.

(6) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(e) You must demonstrate continuous compliance for each container determined to require Container Level 3 controls by meeting the requirements in paragraphs (e)(1) through (4) of this section.

(1) Performing the verification procedure for the enclosure annually according to the requirements in § 63.685(i).

(2) Recording the information specified in § 63.696(f).

(3) Meeting each applicable requirement for demonstrating continuous compliance with the emissions limitations and work practice standards for a closed vent system and control device in § 63.7928.

(4) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41704, July 10, 2020]

SURFACE IMPOUNDMENTS

§ 63.7905 What emissions limitations or work practice standards must I meet for surface impoundments?

(a) You must control HAP emissions from each new and existing surface impoundment subject to § 63.7886(b)(1)(iii) according to emissions limitations and work practice standards in this section that apply to your affected surface impoundments.

(b) For each affected surface impoundment, you must install and operate air pollution controls that meet either of the options in paragraphs (b)(1) or (2) of this section.

(1) Install and operate a floating membrane cover according to the requirements in § 63.942. § 63.942(c)(2) and (3) do not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.942(c)(2) and (3) do not apply for the purposes of this subpart for any source after January 6, 2021; or

(2) Install and operate a cover vented through a closed vent system to a control device according to the requirements in § 63.943. You must meet the emissions limitations and work practice standards in § 63.7925 that apply to your closed vent system and control device. § 63.943(c)(2) does not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.943(c)(2) does not apply for the purposes of this subpart for any source after January 6, 2021.

(c) As provided in § 63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your surface impoundments. If you request for permission to use an alternative to the work practice standards, you must submit the information described in § 63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41704, July 10, 2020]

§ 63.7906 How do I demonstrate initial compliance with the emissions limitations or work practice standards for surface impoundments?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7905 that apply to your affected surface impoundments by meeting the requirements in paragraphs (b) and (c) of this section, as applicable to your surface impoundments.

(b) You must demonstrate initial compliance of each surface impoundment using a floating membrane cover according to § 63.7905(b)(1) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(1) through (3) of this section.

(1) You have installed a floating membrane cover and closure devices that meet the requirements in § 63.942(b), and you have records documenting the design and installation.

(2) You will operate the cover and closure devices according to the requirements in § 63.942(c), with the exceptions specified in § 63.7905(b)(1).

(3) You have performed an initial visual inspection of each surface impoundment and closure devices according to the requirements in § 63.946(a), and you have records documenting the inspection results.

(c) You must demonstrate initial compliance of each surface impoundment using a cover vented to a control device according to § 63.7905(b)(2) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (c)(1) through (4) of this section.

(1) You have installed a cover and closure devices that meet the requirements in § 63.943(b), and have records documenting the design and installation.

(2) You will operate the cover and closure devices according to the requirements in § 63.943(c), with the exceptions specified in § 63.7905(b)(2).

(3) You have performed an initial visual inspection of each cover and closure devices according to the requirements in § 63.946(b), and have records documenting the inspection results.

(4) You have met each applicable requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41704, July 10, 2020]

§ 63.7907 What are my inspection and monitoring requirements for surface impoundments?

(a) If you use a floating membrane cover according to § 63.7905(b)(1), you must visually inspect the floating membrane cover and its closure devices at least annually according to the requirements in § 63.946(a).

(b) If you use a cover vented to a control device according to §63.7905(b)(2), you must meet requirements in paragraphs (b)(1) and (2) of this section.

(1) You must visually inspect the cover and its closure devices for defects according to the requirements in §63.946(b).

(2) You must monitor and inspect the closed vent system and control device according to the requirements in §63.7927 that apply to you.

§63.7908 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for surface impoundments?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in §63.7905 applicable to your affected surface impoundments by meeting the requirements in paragraphs (b) and (c) of this section as applicable to your surface impoundments.

(b) You must demonstrate continuous compliance for each surface impoundment using a floating membrane cover according to §63.7905(b)(1) by meeting the requirements in paragraphs (b)(1) through (5) of this section.

(1) Operating and maintaining the floating membrane cover and closure devices according to the requirements in §63.942(c), with the exceptions specified in §63.7905(b)(1).

(2) Visually inspecting the floating membrane cover and closure devices for defects at least annually according to the requirements in §63.946(a).

(3) Repairing defects according to the requirements in §63.946(c).

(4) Recording the information specified in §63.947(a)(2) and (a)(3).

(5) Keeping records to document compliance with the requirements according to the requirements in §63.7952.

(c) You must demonstrate continuous compliance for each surface impoundment using a cover vented to a control device according to §63.7905(b)(2) by meeting the requirements in paragraphs (c)(1) through (6) of this section.

(1) Operating and maintaining the floating membrane cover and closure devices according to the requirements in §63.943(c), with the exceptions specified in §63.7905(b)(2).

(2) Visually inspecting the cover and its closure devices for defects at least annually according to the requirements in §63.946(b).

(3) Repairing defects according to the requirements in §63.946(c).

(4) Recording the information specified in §63.947(a)(2) and (a)(3).

(5) Meeting each applicable requirement for demonstrating continuous compliance with the emission limitations and work practice standards for a closed vent system and control device in §63.7928.

(6) Keeping records to document compliance with the requirements according to the requirements in §63.7952.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41704, July 10, 2020]

SEPARATORS

§63.7910 What emissions limitations and work practice standards must I meet for separators?

(a) You must control HAP emissions from each new and existing oil-water separator and organic-water separator subject to §63.7886(b)(1)(iv) according to emissions limitations and work practice standards in this section that apply to your affected separators.

(b) For each affected separator, you must install and operate air pollution controls that meet one of the options in paragraphs (b)(1) through (3) of this section.

(1) Install and operate a floating roof according to the requirements in §63.1043. For portions of the separator where it is infeasible to install and operate a floating roof, such as over a weir mechanism, you must comply with the requirements specified in paragraph (b)(2) of this section. §63.1043(c)(2) does not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; §63.1043(c)(2) does not apply for the purposes of this subpart for any source after January 6, 2021.

(2) Install and operate a fixed roof vented through a closed vent system to a control device according to the requirements in §63.1044. You must meet the emissions limitations and work practice standards in §63.7925 that apply to your closed vent system and control device. §63.1044(c)(2) does not

apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.1044(c)(2) does not apply for the purposes of this subpart for any source after January 6, 2021.

(3) Install and operate a pressurized separator according to the requirements in § 63.1045. § 63.1045(b)(3)(i) does not apply for the purposes of this subpart if your initial startup date is after September 3, 2019; § 63.1045(b)(3)(i) does not apply for the purposes of this subpart for any source after January 6, 2021.

(c) As provided in § 63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your separators. If you request for permission to use an alternative to the work practice standards, you must submit the information described in § 63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41705, July 10, 2020]

§ 63.7911 How do I demonstrate initial compliance with the emissions limitations and work practice standards for separators?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7910 that apply to your affected separators by meeting the requirements in paragraphs (b) through (d) of this section, as applicable to your separators.

(b) You must demonstrate initial compliance of each separator using a floating roof according to § 63.7910(b)(1) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(1) through (4) of this section.

(1) You have installed a floating roof and closure devices that meet the requirements in § 63.1043(b), and you have records documenting the design and installation.

(2) You will operate the floating roof and closure devices according to the requirements in § 63.1043(c), with the exceptions specified in § 63.7910(b)(1).

(3) You have performed an initial seal gap measurement inspection using the procedures in § 63.1046(b), and you have records documenting the measurement results.

(4) You have performed an initial visual inspection of the floating roof and closure devices for defects according to the requirements in § 63.1047(b)(2), and you have records documenting the inspection results.

(5) For any portions of the separator using a fixed roof vented to a control device according to § 63.7910(b)(1), you have met the requirements in paragraphs (c)(1) through (4) of this section.

(c) You must demonstrate initial compliance of each separator using a fixed roof vented to a control device according to § 63.7910(b)(2) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (c)(1) through (4) of this section.

(1) You have installed a fixed roof and closure devices that meet the requirements in § 63.1042(b), and you have records documenting the design and installation.

(2) You will operate the fixed roof and its closure devices according to the requirements in § 63.1042(c). § 63.1042(c)(3) does not apply for the purposes of this subpart if your initial date is after September 3, 2019; § 63.1042(c)(3) does not apply for the purposes of this subpart for any source after January 6, 2021.

(3) You have performed an initial visual inspection of the fixed roof and closure devices for defects according to the requirements in § 63.1047(a).

(4) You have met each applicable requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

(d) You must demonstrate initial compliance of each pressurized separator that operates as a closed system according to § 63.7910(b)(3) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (d)(1) and (2) of this section.

(1) You have installed a pressurized separator that operates as a closed system according to the requirements in

§ 63.1045(b)(1) and (b)(2), and you have records of the design and installation.

(2) You will operate the pressurized separator as a closed system according to the requirements in § 63.1045(b)(3), with the exceptions specified in § 63.7910(b)(3).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41705, July 10, 2020]

§ 63.7912 What are my inspection and monitoring requirements for separators?

(a) If you use a floating roof according to § 63.7910(b)(1), you must meet requirements in paragraphs (a)(1) and (2) of this section.

(1) Measure the seal gaps at least annually according to the requirements in § 63.1047(b)(1).

(2) Visually inspect the floating roof at least annually according to the requirements in § 63.1047(b)(2).

(b) If you use a cover vented to a control device according to § 63.7910(b)(1) or (2), you must meet requirements in paragraphs (b)(1) and (2) of this section.

(1) You must visually inspect the cover and its closure devices for defects according to the requirements in § 63.1047(c).

(2) You must monitor and inspect the closed vent system and control device according to the requirements in § 63.7927 that apply to you.

(c) If you use a pressurized separator that operates as a closed system according to § 63.7910(b)(3), you must visually inspect each pressurized separator and closure devices for defects at least annually to ensure they are operating according to the design requirements in § 63.1045(b), with the exceptions specified in § 63.7910(b)(3).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41705, July 10, 2020]

§ 63.7913 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for separators?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in § 63.7910 applicable to your affected separators by meeting the requirements in paragraphs (b) through (d) of this section as applicable to your surface impoundments.

(b) You must demonstrate continuous compliance for each separator using a floating roof according to § 63.7910(b)(1) by meeting the requirements in paragraphs (b)(1) through (6) of this section.

(1) Operating and maintaining the floating roof according to the requirements in § 63.1043(b).

(2) Performing seal gap measurement inspections at least annually according to the requirements in § 63.1047(b)(1).

(3) Visually inspecting the floating roof at least annually according to the requirements in § 63.1047(b)(2).

(4) Repairing defects according to the requirements in § 63.1047(d).

(5) Recording the information specified in § 63.1048(a) and (b).

(6) Keeping records to document compliance with the requirements according to the requirements in § 63.7952.

(c) You must demonstrate continuous compliance for each separator using a fixed roof vented through a closed vent system to a control device according to § 63.7910(b)(2) by meeting the requirements in paragraphs (c)(1) through (6) of this section.

(1) Operating and maintaining the fixed roof and its closure devices according to the requirements in § 63.1042, with the exceptions specified in § 63.7911(c)(2).

(2) Performing visual inspections of the fixed roof and its closure devices for defects at least annually according to the requirements in § 63.1047(a).

(3) Repairing defects according to the requirements in § 63.1047(d).

(4) Recording the information specified in § 63.1048(a).

(5) Meeting each applicable requirement for demonstrating continuous compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7928.

(6) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(d) You must demonstrate continuous compliance for each pressurized separator operated as a closed system according to § 63.7910(b)(3) by meeting the requirements in paragraphs (d)(1) and (2) of this section.

(1) Operating the pressurized separator at all times according to the requirements in § 63.1045, with the exceptions specified in § 63.7910(b)(3).

(2) Visually inspecting each pressurized tank and closure devices for defects at least annually to ensure they are operating according to the design requirements in § 63.1045(b), and recording the results of each inspection.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69017, Nov. 29, 2006; 85 FR 41705, July 10, 2020]

TRANSFER SYSTEMS

§ 63.7915 What emissions limitations and work practice standards must I meet for transfer systems?

(a) You must control HAP emissions from each new and existing transfer system subject to § 63.7886(b)(1)(v) according to emissions limitations and work practice standards in this section that apply to your affected transfer systems.

(b) For each affected transfer system that is an individual drain system as defined in § 63.7957, you must install and operate controls according to the requirements in § 63.962.

(c) For each affected transfer system that is not an individual drain system as defined in § 63.7957, you must use one of the transfer systems specified in paragraphs (c)(1) through (3) of this section.

(1) A transfer system that uses covers according to the requirements in § 63.689(d).

(2) A transfer system that consists of continuous hard piping. All joints or seams between the pipe sections must be permanently or semi-permanently sealed (*e.g.*, a welded joint between two sections of metal pipe or a bolted and gasketed flange).

(3) A transfer system that is enclosed and vented through a closed vent system to a control device according to the requirements specified in paragraphs (c)(3)(i) and (ii) of this section.

(i) The transfer system is designed and operated such that an internal pressure in the vapor headspace in the enclosure is maintained at a level less than atmospheric pressure when the control device is operating, and

(ii) The closed vent system and control device are designed and operated to meet the emissions limitations and work practice standards in § 63.7925 that apply to your closed vent system and control device.

(d) As provided in § 63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your transfer systems. If you request for permission to use an alternative to the work practice standards, you must submit the information described in § 63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

§ 63.7916 How do I demonstrate initial compliance with the emissions limitations and work practice standards for transfer systems?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7915 that apply to your affected transfer systems by meeting the requirements in paragraphs (b) through (e) of this section, as applicable to your transfer systems.

(b) You must demonstrate initial compliance of each individual drain system using controls according to § 63.7915(b) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(1) through (3) of this section.

(1) You have installed air emission controls for each individual drain system and junction box according to the requirements in § 63.962(a) and (b), and you have records documenting the installation and design.

(2) You will operate the air emission controls according to the requirements in § 63.962(b)(5).

(3) You have performed an initial visual inspection of each individual drain system according to the requirements in § 63.964(a), and you have records documenting the inspection results.

(c) You must demonstrate initial compliance of each transfer system using covers according to § 63.7915(c)(1) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in

paragraphs (c)(1) through (3) of this section.

(1) Each transfer system is equipped with covers and closure devices according to the requirements in § 63.689(d)(1) through (4), and you have records documenting the design and installation.

(2) You have performed an initial inspection of each cover and its closure devices for defects according to the requirements in § 63.695(d)(1) through (5), and you have records documenting the inspection results.

(3) You will operate each cover and its closure devices according to the requirements in § 63.689(5).

(d) You must demonstrate initial compliance of each transfer system that consists of hard piping according to § 63.7915(c)(2) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (d)(1) and (2) of this section.

(1) You have installed a transfer system that consists entirely of hard piping and meets the requirements in § 63.7915(c)(2), and you have records documenting the design and installation.

(2) You have performed an initial inspection of the entire transfer system to verify that all joints or seams between the pipe sections are permanently or semi-permanently sealed (*e.g.*, a welded joint between two sections of metal pipe or a bolted and gasketed flange), and you have records documenting the inspection results.

(e) You must demonstrate initial compliance of each transfer system that is enclosed and vented to a control device according to § 63.7915(e)(3) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (e)(1) and (2) of this section.

(1) You have installed a transfer system that is designed and operated such that an internal pressure in the vapor headspace in the enclosure is maintained at a level less than atmospheric pressure when the control device is operating, and you have records documenting the design and installation.

(2) You have met each applicable requirement for demonstrating initial compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7926.

§ 63.7917 What are my inspection and monitoring requirements for transfer systems?

(a) If you operate an individual drain system as a transfer system according to § 63.7915(b), you must visually inspect each individual drain system at least annually according to the requirements in § 63.964(a).

(b) If you operate a transfer system using covers according to § 63.7915(c)(1), you must inspect each cover and its closure devices for defects according to the requirements in § 63.695(d)(1) through (5).

(c) If you operate a transfer system consisting of hard piping according to § 63.7915(c)(2), you must annually inspect the unburied portion of pipeline and all joints for leaks and other defects. In the event that a defect is detected, you must repair the leak or defect according to the requirements of paragraph (e) of this section.

(d) If you operate a transfer system that is enclosed and vented to a control device according to § 63.7915(c)(3), you must meet requirements in paragraphs (d)(1) and (2) of this section.

(1) You must annually inspect all enclosure components (e.g., enclosure sections, closure devices, fans) for defects that would prevent an internal pressure in the vapor headspace in the enclosure from continuously being maintained at a level less than atmospheric pressure when the control device is operating. In the event that a defect is detected, you must repair the defect according to the requirements of paragraph (e) of this section.

(2) You must monitor and inspect the closed vent system and control device according to the requirements in § 63.7927 that apply to you.

(e) If you are subject to paragraph (c) or (d) of this section, you must repair all detected defects as specified in paragraphs (e)(1) through (3) of this section.

(1) You must make first efforts at repair of the defect no later than 5 calendar days after detection and repair shall be completed as soon as possible but no later than 45 calendar days after

detection except as provided in paragraph (e)(2) of this section.

(2) Repair of a defect may be delayed beyond 45 calendar days if you determine that repair of the defect requires emptying or temporary removal from service of the transfer system and no alternative transfer system is available at the site to accept the material normally handled by the system. In this case, you must repair the defect the next time the process or unit that is generating the material handled by the transfer system stops operation. Repair of the defect must be completed before the process or unit resumes operation.

(3) You must maintain a record of the defect repair according to the requirements specified in § 63.7952.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

§ 63.7918 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for transfer systems?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in § 63.7915 applicable to your affected transfer system by meeting the requirements in paragraphs (b) through (e) of this section as applicable to your transfer systems.

(b) You must demonstrate continuous compliance for each individual drain system using controls according to § 63.7915(b) by meeting the requirements in paragraphs (b)(1) through (5) of this section.

(1) Operating and maintaining the air emission controls for individual drain systems according to the requirements in § 63.962.

(2) Visually inspecting each individual drain system at least annually according to the requirements in § 63.964(a).

(3) Repairing defects according to the requirements in § 63.964(b).

(4) Recording the information specified in § 63.965(a).

(5) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(c) You must demonstrate continuous compliance for each transfer system using covers according to § 63.7915(c)(1) by meeting the requirements in paragraphs (c)(1) through (4) of this section.

(1) Operating and maintaining each cover and its closure devices according to the requirements in § 63.689(d)(1) through (5).

(2) Performing inspections of each cover and its closure devices for defects at least annually according to the requirements in § 63.695(d)(1) through (5).

(3) Repairing defects according to the requirements in § 63.695(5)

(4) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(d) You must demonstrate continuous compliance for each transfer system that consists of hard piping according to § 63.7915(c)(2) by meeting the requirements in paragraphs (d)(1) through (4) of this section.

(1) Operating and maintaining the pipeline to ensure that all joints or seams between the pipe sections remain permanently or semi-permanently sealed (*e.g.*, a welded joint between two sections of metal pipe or a bolted and gasketed flange).

(2) Inspecting the pipeline for defects at least annually according to the requirements in § 63.7917(c).

(3) Repairing defects according to the requirements in § 63.7917(e).

(4) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(e) You must demonstrate continuous compliance for each transfer system that is enclosed and vented to a control device according to § 63.7915(c)(3) by meeting the requirements in paragraphs (e)(1) through (5) of this section.

(1) Operating and maintaining the enclosure to ensure that the internal pressure in the vapor headspace in the enclosure is maintained continuously at a level less than atmospheric pressure when the control device is operating.

(2) Inspecting the enclosure and its closure devices for defects at least annually according to the requirements in § 63.7918(d).

(3) Repairing defects according to the requirements in § 63.7918(e).

(4) Meeting each applicable requirement for demonstrating continuous

compliance with the emission limitations and work practice standards for a closed vent system and control device in § 63.7928.

(5) Keeping records to document compliance with the requirements according to the requirements in § 63.7952.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

EQUIPMENT LEAKS AND PRESSURE RELIEF DEVICES

§ 63.7920 What emissions limitations and work practice standards must I meet for equipment leaks?

(a) You must control HAP emissions from each new and existing equipment subject to § 63.7887 according to emissions limitations and work practice standards in this section that apply to your affected equipment.

(b) For your affected equipment, you must meet the requirements in either paragraph (b)(1) or (2) of this section.

(1) Control equipment leaks according to all applicable requirements under 40 CFR part 63, subpart TT—National Emission Standards for Equipment Leaks—Control Level 1, with the differences noted in paragraph (b)(3) of this section for the purposes of this subpart; or

(2) Control equipment leaks according to all applicable requirements under 40 CFR part 63, subpart UU—National Emission Standards for Equipment Leaks—Control Level 2.

(3)(i) For the purpose of complying with the requirements of § 63.1006(b)(2), the instrument reading that defines a leak is 500 parts per million or greater.

(ii) For the purpose of complying with the requirements of § 63.1007(b)(2), the instrument reading that defines a leak is 5,000 parts per million or greater for pumps handling polymerizing monomers; 2,000 parts per million or greater for pumps in food/medical service; and 1,000 parts per million or greater for all other pumps.

(c) If you use a closed vent system and control device to comply with this section, as an alternative to meeting the standards in § 63.1015 or § 63.1034 for closed vent systems and control devices, you may elect to meet the requirements in §§ 63.7925 through 63.7928 that apply to your closed vent system and control device.

(d) For the purposes of this subpart, the requirements of § 63.7920(e) of this subpart apply rather than those of § 63.1030 or of § 63.1011, as applicable, for pressure relief devices in gas and vapor service. The requirements of § 63.7920(e) of this subpart apply rather than those of § 63.1029 or of § 63.1010, as applicable, for pressure relief devices in liquid service.

(e) Operate each pressure relief device under normal operating conditions, as indicated by an instrument reading of less than 500 ppm above the background level as detected by the method specified in § 63.1004(b) or § 63.1023(b), as applicable.

(f) As provided in § 63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your equipment. If you request for permission to use an alternative to the work practice standards, you must submit the information described in § 63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41705, July 10, 2020]

§ 63.7921 How do I demonstrate initial compliance with the emissions limitations and work practice standards for equipment leaks?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in § 63.7920 that apply to your affected equipment by meeting the requirements in paragraphs (b) and (c) of this section, as applicable to your affected sources.

(b) If you control equipment leaks according to the requirements under § 63.7920(b)(1), you must demonstrate initial compliance if you have met the requirements in paragraphs (b)(1) and (2) of this section.

(1) You include the information required in § 63.1018(a)(1) in your notification of compliance status report.

(2) You have submitted as part of your notification of compliance status a signed statement that:

(i) You will meet the requirements in §§ 63.1002 through 63.1016 that apply to your affected equipment.

(ii) You have identified the equipment subject to control according to the requirements in § 63.1003, including equipment designated as unsafe to monitor, and have records supporting the determinations with a written plan for monitoring the equipment according to the requirements in § 63.1003(c)(4).

(c) If you control equipment leaks according to the requirements under § 63.7920(b)(2), you must demonstrate initial compliance if you have met the requirements in paragraphs (c)(1) and (2) of this section.

(1) You have included the information required in § 63.1039(a) in your notification of compliance status report.

(2) You have submitted as part of your notification of compliance status a signed statement that:

(i) You will meet the requirements in §§ 63.1021 through 63.1037 that apply to your affected equipment.

(ii) You have identified the equipment subject to control according to the requirements in § 63.1022, including equipment designated as unsafe to monitor, and have records supporting the determinations with a written plan for monitoring the equipment according to the requirements in § 63.1022(c)(4).

§ 63.7922 How do I demonstrate continuous compliance with the work practice standards for equipment leaks?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in § 63.7920 applicable to your affected equipment by meeting the requirements in paragraphs (b) through (d) of this section that apply to you.

(b) If you control equipment leaks according to the requirements under § 63.7920(b)(1), you must demonstrate continuous compliance by inspecting, monitoring, repairing, and maintaining records according to the requirements in §§ 63.1002 through 63.1018 that apply to your affected equipment.

(c) If you control equipment leaks according to the requirements under § 63.7920(b)(2), you must demonstrate continuous compliance by inspecting, monitoring, repairing, and maintaining records according to the requirements in §§ 63.1021 through 63.1039 that apply to your affected equipment.

(d) You must keep records to demonstrate compliance with the requirements according to the requirements in § 63.7952.

§ 63.7923 What monitoring and work practice standards must I meet for pressure relief devices?

(a) For each pressure relief device in remediation material service, you must comply with either paragraph (a)(1) or (2) of this section following a pressure release actuation event, as applicable.

(1) If the pressure relief device does not consist of or include a rupture disk, return the pressure relief device to the normal operating conditions specified in § 63.7920(e) as soon as practicable and conduct instrument monitoring by the method specified in § 63.1004(b) or § 63.1023(b), as applicable, no later than 5 calendar days after the pressure release device returns to remediation material service following a pressure release actuation event, except as provided in § 63.1024(d) or of § 63.1005(c), as applicable.

(2) If the pressure relief device consists of or includes a rupture disk, except as provided in § 63.1024(d) or § 63.1005(c), as applicable, install a replacement disk as soon as practicable but no later than 5 calendar days after the pressure release actuation event.

(b) Except for the pressure relief devices described in paragraph (e) of this section, you must comply with the requirements of paragraphs (c) and (d) of this section for each pressure relief device in remediation material service.

(c) Equip each pressure relief device in remediation material service with a device(s) or use a monitoring system sufficient to indicate a pressure release to the atmosphere. The device or monitoring system may be either specific to the pressure release device itself or may be associated with the process system or piping. Examples of these types of devices or monitoring systems include, but are not limited to, a rupture disk indicator, magnetic sensor, motion detector on the pressure relief valve stem, flow monitor, pressure

monitor, or parametric monitoring system. The device(s) or monitoring systems must be capable of meeting the requirements specified in paragraphs (c)(1) through (3) of this section.

(1) Identifying the pressure release;

(2) Recording the time and duration of each pressure release; and

(3) Notifying operators immediately that a pressure release is occurring.

(d) If any pressure relief device in remediation material service releases directly to the atmosphere as a result of a pressure release actuation event, follow the requirements of paragraphs (d)(1) through (6) of this section.

(1) Calculate the quantity of HAP listed in Table 1 of this subpart released during each pressure release actuation event. Calculations may be based on data from the pressure relief device monitoring alone or in combination with process parameter monitoring data and process knowledge.

(2) Determine the total number of pressure release actuation events that occurred during the calendar year for each pressure relief device.

(3) Determine the total number of pressure release actuation events for each pressure relief device for which the analysis conducted as required by paragraph (d)(4) of this section concluded that the pressure release was due to a force majeure event, as defined in § 63.7957.

(4) Complete an analysis to determine the source, nature and cause of each pressure release actuation event as soon as practicable, but no later than 45 days after a pressure release actuation event.

(5) Identify corrective measures to prevent future such pressure release actuation events as soon as practicable, but no later than 45 days after a pressure release actuation event.

(6) Implement the corrective measure(s) identified as required by paragraph (d)(5) of this section within 45 days of the pressure release actuation event or as soon thereafter as practicable. For corrective measures that cannot be fully implemented within 45 days following the pressure release actuation event, you must record the corrective measure(s) completed to date, and, for measure(s) not already completed, a schedule for implementation, including proposed commencement and completion dates, no later than 45 days following the pressure release actuation event.

(e) The pressure relief devices listed in paragraphs (e)(1) through (6) are not subject to the requirements in paragraph (c) or (d) of this section.

(1) Pressure relief devices designed and operated to route all pressure releases through a closed vent system to a drain system meeting the requirements of §§ 63.7915–63.7918, or to a fuel gas system, process or control device meeting the requirements of §§ 63.7925 through 63.7928.

(2) Pressure relief devices in heavy liquid service, as defined in § 63.1001 or § 63.1020, as applicable.

(3) Thermal expansion relief valves.

(4) Pilot-operated pressure relief devices where the primary release valve is routed through a closed vent system to a control device or back into the process, to the fuel gas system, or to a drain system.

(5) Balanced bellows pressure relief devices where the primary release valve is routed through a closed vent system to a control device or back into the process, to the fuel gas system, or to a drain system.

(6) Pressure relief devices on containers, as defined in § 63.7957.

(f) Except for the pressure relief devices described in paragraph (e) of this section, it is a violation of the requirements of paragraphs (c) and (d) of this section for any pressure relief device in remediation material service to release directly to the atmosphere as a result of a pressure release actuation event(s) described in paragraphs (f)(1) through (3) of this section.

(1) Any pressure release actuation event for which the cause of the event determined as required by paragraph (d)(4) of this section was determined to be operator error or poor maintenance.

(2) A second pressure release actuation event, not including force majeure events, from a single pressure relief device in a 3 calendar-year period for the same cause for the same equipment.

(3) A third pressure release actuation event, not including force majeure

events, from a single pressure relief device in a 3 calendar-year period for any reason.

[85 FR 41705, July 10, 2020]

CLOSED VENT SYSTEMS AND CONTROL DEVICES

§ 63.7925 What emissions limitations and work practice standards must I meet for closed vent systems and control devices?

(a) For each closed-vent system and control device you use to comply with requirements in §§ 63.7890 through 63.7922, as applicable to your affected sources, you must meet the emissions limitations and work practice standards in this section.

(b) You must comply with paragraph (b)(2) of this section, and paragraph (b)(1) of this section does not apply, if your initial startup date is after September 3, 2019. If your initial startup date was on or before September 3, 2019, you must comply with paragraph (b)(1) or (2) of this section until January 7, 2021, and after that date, you must comply with paragraph (b)(2) of this section, and paragraph (b)(1) of this section does not apply.

(1) Whenever gases or vapors containing HAP are vented through the closed-vent system to the control device, the control device must be operating except at those times listed in either paragraph (b)(1)(i) or (ii) of this section.

(i) The control device may be bypassed for the purpose of performing planned routine maintenance of the closed-vent system or control device in situations when the routine maintenance cannot be performed during periods that the emission point vented to the control device is shutdown. On an annual basis, the total time that the closed-vent system or control device is bypassed to perform routine maintenance must not exceed 240 hours per each calendar year.

(ii) The control device may be bypassed for the purpose of correcting a malfunction of the closed-vent system or control device. You must perform the adjustments or repairs necessary to correct the malfunction as soon as practicable after the malfunction is detected.

(2) Whenever gases or vapors containing HAP are vented through the closed-vent system to the control device, the control device must be operating, except that the control device on a tank may be bypassed for the purpose of performing planned routine maintenance of the control device. When the tank control device is bypassed, the owner or operator must comply with paragraphs (b)(2)(i) through (iii) of this section.

(i) The control device may only be bypassed when the planned routine maintenance cannot be performed during periods that tank emissions are vented to the control device.

(ii) On an annual basis, the total time that the closed-vent system or control device is bypassed to perform routine maintenance must not exceed 240 hours per each calendar year.

(iii) The level of material in the tank must not be increased during periods that the closed-vent system or control device is bypassed to perform planned routine maintenance.

(c) For each closed vent system, you must meet the work practice standards in § 63.693(c).

(d) For each control device other than a flare or a control device used to comply with the facility-wide process vent emission limits in § 63.7890(b), you must control HAP emissions to meet either of the emissions limits in paragraphs (d)(1) or (2) of this section except as provided for in paragraph (f) of this section.

(1) Reduce emissions of total HAP listed in Table 1 of this subpart or TOC (minus methane and ethane) from each control device by 95 percent by weight; or

(2) Limit the concentration of total HAP listed in Table 1 of this subpart or TOC (minus methane and ethane) from each combustion control device (a thermal incinerator, catalytic incinerator, boiler, or process heater) to 20 ppmv or less on a dry basis corrected to 3 percent oxygen.

(e) If you use a flare for your control device, then you must meet the requirements for flares in § 63.11(b).

(f) If you use a process heater or boiler for your control device, then as alternative to meeting the emissions limits in paragraph (d) of this section

you may choose to comply with one of the work practice standards in paragraphs (f)(1) through (3) of this section.

(1) Introduce the vent stream into the flame zone of the boiler or process heater and maintain the conditions in the combustion chamber at a residence time of 0.5 seconds or longer and at a temperature of 760 °C or higher; or

(2) Introduce the vent stream with the fuel that provides the predominate heat input to the boiler or process heater (*i.e.*, the primary fuel); or

(3) Introduce the vent stream to a boiler or process heater for which you either have been issued a final permit under 40 CFR part 270 and complies with the requirements of 40 CFR part 266, subpart H—Hazardous Waste Burned in Boilers and Industrial Furnaces; or has certified compliance with the interim status requirements of 40 CFR part 266, subpart H.

(g) For each control device other than a flare, you must meet each operating limit in paragraphs (g)(1) through (6) of this section that applies to your control device.

(1) If you use a regenerable carbon adsorption system, you must:

(i) Maintain the hourly average total regeneration stream mass flow during the adsorption bed regeneration cycle greater than or equal to the stream mass flow established in the design evaluation or performance test.

(ii) Maintain the hourly average temperature of the adsorption bed during regeneration (except during the cooling cycle) greater than or equal to the temperature established during the design evaluation or performance test.

(iii) Maintain the hourly average temperature of the adsorption bed after regeneration (and within 15 minutes after completing any cooling cycle) less than or equal to the temperature established during the design evaluation.

(iv) Maintain the frequency of regeneration greater than or equal to the frequency established during the design evaluation.

(2) If you use a nonregenerable carbon adsorption system, you must maintain the hourly average temperature of the adsorption bed less than or equal to the temperature established during the design evaluation or performance test.

(3) If you use a condenser, you must maintain the daily average condenser exit temperature less than or equal to the temperature established during the design evaluation or performance test.

(4) If you use a thermal incinerator, you must maintain the daily average firebox temperature greater than or equal to the temperature established in the design evaluation or during the performance test.

(5) If you use a catalytic incinerator, you must maintain the daily average temperature difference across the catalyst bed greater than or equal to the minimum temperature difference established during the performance test or design evaluation.

(6) If you use a boiler or process heater to comply with an emission limit in paragraph (d) of this section, you must maintain the daily average firebox temperature within the operating level established during the design evaluation or performance test.

(h) If you use a carbon adsorption system as your control, you must meet each work practice standard in paragraphs (h)(1) through (3) of this section that applies to your control device.

(1) If you use a regenerable carbon adsorption system, you must:

(i) Replace the existing adsorbent in each segment of the bed with an adsorbent that meets the replacement specifications established during the design evaluation before the age of the adsorbent exceeds the maximum allowable age established during the design evaluation.

(ii) Follow the disposal requirements for spent carbon in § 63.693(d)(4).

(2) If you use a nonregenerable carbon adsorption system, you must:

(i) Replace the existing adsorbent in each segment of the bed with an adsorbent that meets the replacement specifications established during the design evaluation before the age of the adsorbent exceeds the maximum allowable age established during the design evaluation.

(ii) Meet the disposal requirements for spent carbon in § 63.693(d)(4)(ii).

(3) If you use a nonregenerative carbon adsorption system, you may choose to comply with the requirements in paragraphs (h)(3)(i) and (ii) of

this section as an alternative to the requirements in paragraph (h)(2) of this section. You must:

(i) Immediately replace the carbon canister or carbon in the control device when the monitoring device indicates breakthrough has occurred according to the requirements in §63.693(d)(4)(iii)(A), or replace the carbon canister or carbon in the control device at regular intervals according to the requirements in §63.693(d)(4)(iii)(B).

(ii) Follow the disposal requirements for spent carbon in §63.693(d)(4)(ii).

(i) If you use a catalytic incinerator, you must replace the existing catalyst bed with a bed that meets the replacement specifications before the age of the bed exceeds the maximum allowable age established in the design evaluation or during the performance test.

(j) As provided in §63.6(g), you may request approval from the EPA to use an alternative to the work practice standards in this section that apply to your closed vent systems and control devices. If you request for permission to use an alternative to the work practice standards, you must submit the information described in §63.6(g)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41706, July 10, 2020]

§63.7926 How do I demonstrate initial compliance with the emission limitations and work practice standards for closed vent systems and control devices?

(a) You must demonstrate initial compliance with the emissions limitations and work practice standards in this subpart applicable to your closed vent system and control device by meeting the requirements in paragraphs (b) through (h) of this section that apply to your closed vent system and control device.

(b) You must demonstrate initial compliance with the closed vent system work practice standards in §63.7925(c) if you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (b)(1) and (2) of this section.

(1) You have installed a closed vent system that meets the requirements in §63.695(c)(1) and (2), and you have records documenting the equipment design and installation.

(2) You have performed the initial inspection of the closed vent system according to the requirements in §63.695(c)(1)(i) or (ii), and you have records documenting the inspection results.

(c) You must demonstrate initial compliance of each control device subject to the emissions limits in §63.7925(d) with the applicable emissions limit in §63.7925(d) if you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (c)(1) and (2) of this section that apply to you.

(1) For the emissions limit in §63.7925(d)(1), the emissions of total HAP listed in Table 1 of this subpart or TOC (minus methane and ethane) from the control device, measured or determined according to the procedures for performance tests and design evaluations in §63.7941, are reduced by at least 95 percent by weight.

(2) For the emissions limit in §63.7925(d)(2), the concentration of total HAP listed in Table 1 of this subpart or TOC (minus methane and ethane) from the combustion control device, measured by a performance test or determined by a design evaluation according to the procedures in §63.7941, do not exceed 20 ppmv on a dry basis corrected to 3 percent oxygen.

(d) You must demonstrate initial compliance of each control device subject to operating limits in §63.7925(g) with the applicable limits if you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (d)(1) and (2) of this section.

(1) You have established an appropriate operating limit(s) for each of the operating parameter applicable to your control device as specified in §63.7925(g)(1) through (6).

(2) You have a record of the applicable operating parameter data during the performance test or design evaluation during which the emissions met the applicable limit.

(e) You must demonstrate initial compliance with the spent carbon replacement and disposal work practice standards for carbon adsorption systems in § 63.7925(h) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you will comply with each work practice standard that applies to your carbon adsorption system.

(f) You must demonstrate initial compliance with the catalyst replacement work practice standards for catalytic incinerators in § 63.7925(i) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you will comply with the specified work practice standard.

(g) You must demonstrate initial compliance of each flare with the work practice standards in § 63.7925(e) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (g)(1) through (3) of this section.

(1) Each flare meets the requirements in § 63.11(b).

(2) You have performed a visible emissions test, determined the net heating value of gas being combusted, and determined the flare exit velocity as required in § 63.693(h)(2).

(3) You will operate each flare according to the requirements in § 63.11(b).

(h) You must demonstrate initial compliance of each boiler or process heater with the work practice standards in § 63.7925(f) if you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (h)(1) through (3) of this section.

(1) For the work practice standards in § 63.7925(f)(1), you have records documenting that the boiler or process heater is designed to operate at a residence time of 0.5 seconds or greater and maintain the combustion zone temperature at 760 °C or greater.

(2) For the work practice standard in § 63.7925(f)(2), you have records documenting that the vent stream is introduced with the fuel according to the requirements in § 63.693(g)(1)(iv), or that the vent stream is introduced to a boiler or process heater that meets the requirements in § 63.693(g)(1)(v).

(3) For the work practice standard in § 63.7925(f)(3), you have records documenting you either have been issued a final permit under 40 CFR part 270 and your boiler or process heater complies with the requirements of 40 CFR part 266, subpart H—Hazardous Waste Burned in Boilers and Industrial Furnaces; or has been certified in compliance with the interim status requirements of 40 CFR part 266, subpart H.

§ 63.7927 What are my inspection and monitoring requirements for closed vent systems and control devices?

(a) You must comply with the requirements in paragraphs (a)(1) and (2) of this section for each closed vent system.

(1) You must monitor and inspect each closed vent system according to the requirements in either paragraph (a)(1)(i) or (ii) of this section.

(i) You must monitor, inspect, and repair defects according to the requirements in § 63.695(c)(1)(ii) through (c)(3); or

(ii) You must monitor and inspect the closed vent system according to the requirements in § 63.172(f) through (j) and record the information in § 63.181.

(2) If your closed vent system includes a bypass device, you must meet the requirements in either paragraph (a)(2)(i) or (ii) of this section.

(i) Use a flow indicator to determine if the presence of flow according to the requirements in § 63.693(c)(2)(i); or

(ii) Use a seal or locking device and make monthly inspections as required by § 63.693(c)(2)(ii).

(b) If you use a regenerable carbon adsorption system, you must meet the requirements in paragraphs (b)(1) through (3) of this section.

(1) Use a continuous parameter monitoring system (CPMS) to measure and record the hourly average total regeneration stream mass flow during each carbon adsorption cycle.

(2) Use a CPMS to measure and record the hourly average temperature of the adsorption bed during regeneration (except during the cooling cycle).

(3) Use a CPMS to measure and record the hourly average temperature of the adsorption bed after regeneration (and within 15 minutes after completing any cooling cycle).

(c) If you use a nonregenerable carbon adsorption system, you must use a CPMS to measure and record the hourly average temperature of the adsorption bed or you must monitor the concentration of organic compounds in the exhaust vent stream according to the requirements in § 63.693(d)(4)(iii)(A).

(d) If you use a condenser, you must use a CPMS to measure and record the hourly average condenser exit temperature and determine and record the daily average condenser exit temperature.

(e) If you use a thermal incinerator, you must use a CPMS to measure and record the hourly average firebox temperature and determine and record the daily average firebox temperature.

(f) If you use a catalytic incinerator, you must use a CPMS with two temperature sensors to measure and record the hourly average temperature at the inlet of the catalyst bed, the hourly average temperature at the outlet of the catalyst bed, the hourly average temperature difference across the catalyst bed, and to determine and record the daily average temperature difference across the catalyst bed.

(g) If you use a boiler or process heater to meet an emission limitation, you must use a CPMS to measure and record the hourly average firebox temperature and determine and record the daily average firebox temperature.

(h) If you use a flare, you must monitor the operation of the flare using a heat sensing monitoring device according to the requirements in § 63.693(h)(3).

(i) If you introduce the vent stream into the flame zone of a boiler or process heater according to the requirements in § 63.7925(f)(1), you must use a CPMS to measure and record the combustion zone temperature.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

§ 63.7928 How do I demonstrate continuous compliance with the emissions limitations and work practice standards for closed vent systems and control devices?

(a) You must demonstrate continuous compliance with the emissions limitations and work practice standards in this subpart applicable to your closed vent system and control device by meeting the requirements in paragraphs (b) through (j) of this section as applicable to your closed vent system and control device.

(b) You must demonstrate continuous compliance with the closed vent system work practice standards in § 63.7925(c) by meeting the requirements in paragraphs (b)(1) through (7) of this section.

(1) For a closed vent system designed to operate with no detectable organic emissions, visually inspecting the closed vent system at least annually, monitoring after a repair or replacement using the procedures in § 63.694(k), and monitoring at least annually according to the requirements in § 63.695(c)(1)(ii).

(2) For a closed vent system designed to operate below atmospheric pressure, visually inspecting the closed vent system at least annually according to the requirements in § 63.695(c)(2)(ii).

(3) Repairing defects according to the requirements in § 63.695(c)(3).

(4) Keeping records of each inspection that include the information in paragraphs (b)(4)(i) through (iii) of this section:

(i) A closed vent system identification number (or other unique identification description you select).

(ii) Date of each inspection.

(iii) If a defect is detected during an inspection, the location of the defect, a description of the defect, the date of detection, the corrective action taken to repair the defect, and if repair is delayed, the reason for any delay and the date completion of the repair is expected.

(5) If you elect to monitor the closed vent system according to the requirements in § 63.172(f) through (j), recording the information in § 63.181.

(6) If the closed vent system is equipped with a flow indicator, recording the information in § 63.693(c)(2)(i).

(7) If the closed vent system is equipped with a seal or locking device, visually inspecting the seal or closure mechanism at least monthly according to the requirements in § 63.693(c)(2)(ii), and recording the results of each inspection.

(c) You must demonstrate continuous compliance of each control device subject to the emissions limits in § 63.7925(d) with the applicable emissions limit in § 63.7925(d) by meeting the requirements in paragraph (c)(1) or (2) of this section.

(1) For the emission limit in § 63.7925(d)(1), maintaining the reduction in emissions of total HAP listed in Table 1 of this subpart or TOC (minus methane and ethane) from the control device at 95 percent by weight or greater.

(2) For the emission limit in § 63.7925(d)(2), maintaining the concentration of total HAP listed in Table 1 of this subpart or TOC (minus methane and ethane) from the control device at 20 ppmv or less.

(d) You must demonstrate continuous compliance of each control device subject to operating limits in § 63.7925(g) with the applicable limits by meeting the requirements in paragraphs (d)(1) through (4) of this section.

(1) Maintaining each operating limit according to the requirements in § 63.7925(g) as applicable to the control device.

(2) Monitoring and inspecting each control device according to the requirements in § 63.7927(b) through (i) as applicable to the control device.

(3) Operating and maintaining each continuous monitoring system according to the requirements in § 63.7945, and collecting and reducing data according to the requirements in § 63.7946.

(4) Keeping records to document compliance with the requirements of this subpart according to the requirements in § 63.7952.

(e) You must demonstrate continuous compliance with the spent carbon replacement and disposal work practice standards for regenerable carbon adsorption systems in § 63.7925(h)(1) by meeting the requirements in paragraphs (e)(1) through (3) of this section.

(1) Replacing the adsorbent as required by § 63.7925(h)(1)(i).

(2) Following the disposal requirements for spent carbon in § 63.693(d)(4)(ii).

(3) Keeping records to document compliance with the requirements of the work practice standards.

(f) You must demonstrate continuous compliance with the spent carbon replacement and disposal work practice standards for nonregenerable carbon adsorption systems in § 63.7925(h)(2) by meeting the requirements in paragraphs (f)(1) through (3) of this section.

(1) Replacing the adsorbent as required by the work practice standard in § 63.7925(h)(2)(i).

(2) Following the disposal requirements for spent carbon in § 63.693(d)(4)(ii).

(3) Keeping records to document compliance with the requirements of the work practice standards.

(g) You must demonstrate continuous compliance with the spent carbon replacement and disposal work practice standards for nonregenerable carbon adsorption systems in § 63.7925(h)(3) by meeting the requirements in paragraphs (g)(1) through (3) of this section.

(1) Monitoring the concentration level of the organic compounds in the exhaust vent for the carbon adsorption system as required in § 63.7927(c), immediately replacing the carbon canister or carbon in the control device when breakthrough is indicated by the monitoring device, and recording the date of breakthrough and carbon replacement. Or, you must replace the carbon canister or carbon in the control device at regular intervals and record the date of carbon replacement.

(2) Following the disposal requirements for spent carbon in § 63.693(d)(4)(ii).

(3) Keeping records to document compliance with the requirements of the work practice standards.

(h) You must demonstrate continuous compliance with the catalyst replacement work practice standards for catalytic incinerators in § 63.7925(i) by meeting the requirements in paragraphs (h)(1) and (2) of this section.

(1) Replacing the existing catalyst bed as required in § 63.7925(i).

(2) Keeping records to document compliance with the requirements of the work practice standards.

(i) You must demonstrate continuous compliance of each flare with the work practice standards in § 63.7925(e) by meeting the requirements in paragraphs (i)(1) through (5) of this section.

(1) Operating the flare with no visible emissions except for up to 5 minutes in any 2 consecutive hours according to the requirements in § 63.11(b)(4).

(2) Monitoring the presence of a pilot flare according to the requirements in § 63.7927(h) and maintaining a pilot flame and flare flame at all times that emissions are not vented to the flare according to the requirements in § 63.11(b)(5).

(3) Operating the flare with an exit velocity according to the requirements in § 63.11(b)(6) through (8).

(4) Operating the flare with a net heating value of the gas being combusted according to the requirements in § 63.11(b)(6)(ii).

(5) Keeping records to document compliance with the requirements of the work practice standards.

(j) You must demonstrate continuous compliance of each boiler or process heater with the work practice standards in § 63.7925(f) by meeting the requirements in paragraphs (j)(1) through (3) of this section.

(1) For the work practice standards in § 63.7925(f)(1), you must demonstrate continuous compliance by meeting the requirements in paragraphs (j)(1)(i) through (iv).

(i) Maintaining conditions in the combustion chamber at a residence time of 0.5 seconds or longer and at a combustion zone temperature at 760 °C or greater whenever the vent stream is introduced to the flame zone of the boiler or process heater.

(ii) Monitoring each boiler or process heater according to the requirements in § 63.7927(i).

(iii) Operating and maintaining each continuous monitoring system according to the requirements in § 63.7945, and collecting and reducing data according to the requirements in § 63.7946.

(iv) Keeping records to document compliance with residence time design requirement.

(2) For the work practice standards in § 63.7925(f)(2), you maintain the boiler or process heater operations such that the vent stream is introduced with the fuel according to the requirements in § 63.693(g)(1)(iv), or that the vent stream is introduced to a boiler or process heater that meets the requirements in § 63.693(g)(1)(v).

(3) For the work practice standard in § 63.7925(f)(3), you remain in compliance with all terms and conditions of the final permit under 40 CFR part 270 and your boiler or process heater complies with the requirements of 40 CFR part 266, subpart H—Hazardous Waste Burned in Boilers and Industrial Furnaces; or in compliance with the interim status requirements of 40 CFR part 266, subpart H, as applicable to your boiler or process heater.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7935 What are my general requirements for complying with this subpart?

(a) If your initial startup was on or before September 3, 2019, you must be in compliance with the emissions limitations (including operating limits) and the work practice standards in this subpart at all times, except, until January 6, 2021, during periods of startup, shutdown, and malfunction. If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources, after January 6, 2021, you must be in compliance with the emission limitations (including operating limits) and the work practice standards in this subpart at all times.

(b) If your initial startup was on or before September 3, 2019, then until January 6, 2021, you must operate and maintain your affected source, including air pollution control and monitoring equipment, according to the provisions in § 63.6(e)(1)(i). If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, at all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require

you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

(c) If your initial startup date was on or before September 3, 2019, then until January 6, 2021, you must develop a written startup, shutdown, and malfunction plan (SSMP) according to the provisions in § 63.6(e)(3), and a SSMP is not required after January 6, 2021. No SSMP is required for any source for which the initial startup date is after September 3, 2019.

(d) [Reserved]

(e) You must report each instance in which you did not meet each emissions limitation and each operating limit that applies to you. You must also report each instance in which you did not meet the requirements for work practice standards that apply to you. These instances are deviations from the emissions limitations and work practice standards in this subpart. These deviations must be reported according to the requirements in § 63.7951.

(f) If your initial start date was on or before September 3, 2019, consistent with §§ 63.6(e) and 63.7(e)(1), then until January 6, 2021, deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with § 63.6(e)(1). We will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in § 63.6(e). If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, you must be in compliance with the emission limitations in this subpart at all times (unless a longer timeframe for compliance is expressly provided in this subpart), and we will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations according to the provisions in § 63.7935(a) and (b).

(g) For each monitoring system required in this section, you must develop and make available for inspection by the permitting authority, upon request, a site-specific monitoring plan that addresses the following:

(1) Installation of the continuous monitoring system sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last control device).

(2) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system.

(3) Performance evaluation procedures and acceptance criteria (*e.g.*, calibrations).

(4) Continuous monitoring system (CMS) operation and maintenance requirements in accordance with § 63.7945.

(5) CMS data collection in accordance with § 63.7946.

(h) In your site-specific monitoring plan, you must also address the following:

(1) If your initial startup was on or before September 3, 2019, then until January 6, 2021, you must address ongoing operation and maintenance (O&M) procedures in accordance with the general requirements of § 63.8(c)(1), (3), (4)(ii), (7), and (8). If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, you must address ongoing O&M procedures in accordance with the general requirements of § 63.8(c)(1)(ii), (c)(3), (c)(4)(ii), and (c)(7) and (8).

(2) If your initial startup was on or before September 3, 2019, then until January 6, 2021, you must address ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d). If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, you must address ongoing data quality assurance procedures

in accordance with the general requirements of § 63.8(d) except for the requirements related to startup, shutdown, and malfunction plans referenced in § 63.8(d)(3). The owner or operator shall keep these written procedures on record for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan is revised, the owner or operator shall keep previous (*i.e.,* superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action should be included in the plan required under § 63.8(d)(2).

(3) If your initial startup was on or before September 3, 2019, then until January 6, 2021, you must address ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c), (e)(1), and (e)(2)(i). If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, you must address ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c)(1) through (14), (e)(1), and (e)(2)(i).

(i) You must operate and maintain the continuous monitoring system according to the site-specific monitoring plan.

(j) You must conduct a performance evaluation of each continuous monitoring according to your site-specific monitoring plan.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 20468, Apr. 20, 2006; 71 FR 69018, Nov. 29, 2006; 85 FR 41707, July 10, 2020]

§ 63.7936 What requirements must I meet if I transfer remediation material off-site to another facility?

(a) If you transfer to another facility a remediation material generated by your remediation activities and having an average total VOHAP concentration equal to or greater than 10 ppmw (as determined using the procedures specified in § 63.7943), then you must transfer the remediation material to a facility that meets the requirements in paragraph (b) of this section. You must record the name, street address, and telephone number of the facility where you send this remediation material.

(b) You may elect to transfer the remediation material to one of the following facilities:

(1) A facility where your remediation material will be directly disposed in a landfill or other land disposal unit according to all applicable Federal and State requirements.

(2) A facility subject to 40 CFR part 63, subpart DD where the exemption under § 63.680(b)(2)(iii) is waived and air emissions from the management of your remediation material at the facility are controlled according to all applicable requirements in the subpart for an off-site material. Prior to sending your remediation material, you must obtain a written statement from the owner or operator of the facility to which you send your remediation material acknowledging that the exemption under § 63.680(b)(2)(iii) will be waived for all remediation material received at the facility from you and your material will be managed as an off-site material at the facility according to all applicable requirements. This statement must be signed by the responsible official of the receiving facility, provide the name and address of the receiving facility, and a copy sent to the appropriate EPA Regional Office at the addresses listed in 40 CFR 63.13.

(3) A facility where your remediation material will be managed according to all applicable requirements under this Subpart.

(i) You must prepare and include a notice with each shipment or transport of remediation material from your site. This notice must state that the remediation material contains organic HAP that are to be treated according to the provisions of this subpart. When the transport is continuous or ongoing (for example, discharge to a publicly owned treatment works), the notice must be submitted to the receiving facility owner or operator initially and whenever there is a change in the required treatment.

(ii) You may not transfer the remediation material unless the owner or operator of the facility receiving your remediation material has submitted to the EPA a written certification that he or she will manage remediation material received from you according to the requirements of §§ 63.7885 through 63.7957. The receiving facility owner or operator may revoke the written certification by sending a written statement to the EPA and to you providing at least 90 days notice that they rescind acceptance of responsibility for compliance with the regulatory provisions listed in this section. Upon expiration of the notice period, you may not transfer your remediation material to the facility.

(iii) By providing the written certification to the EPA, the receiving facility owner or operator accepts responsibility for compliance with the regulatory provisions listed in paragraph (b)(3) of this section with respect to any shipment of remediation material covered by the written certification. Failure to abide by any of those provisions with respect to such shipments may result in enforcement action by the EPA against the certifying entity according to the enforcement provisions applicable to violations of these provisions by owners or operators of sources.

(iv) Written certifications and revocation statements to the EPA from the receiving facility owner or operator must be signed by the responsible official of the receiving facility, provide the name and address of the receiving facility, and a copy sent to the appropriate EPA Regional Office at the addresses listed in 40 CFR 63.13. Such written certifications are not transferable.

(c) Acceptance by a facility owner or operator of remediation material from a site remediation subject to this Subpart does not, by itself, require the facility owner or operator to obtain a title V permit under 40 CFR 70.3 or 40 CFR 71.3.

§ 63.7937 How do I demonstrate initial compliance with the general standards?

(a) You must demonstrate initial compliance with the general standards in §§ 63.7884 through 63.7887 that apply to your affected sources by meeting the requirements in paragraphs (b) through (d) of this section, as applicable to you.

(b) You must demonstrate initial compliance with the general standards in § 63.7885 that apply to your affected process vents by meeting the requirements in paragraphs (b)(1) through (4) of this section, as applicable to your process vents.

(1) If HAP emissions are controlled from the affected process vents according to the emission limitations and work practice standards specified in § 63.7885(b)(1), you have met the initial compliance requirements in § 63.7891.

(2) If the remediation material treated or managed by the process vented through the affected process vents has an average total VOHAP less than 10 ppmw according to § 63.7885(b)(2), you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have determined, according to the procedures § 63.7943, and recorded the average VOHAP concentration of the remediation material placed in the affected remediation material management unit.

(3) If HAP emissions are controlled from the affected process vents to meet standards in another subpart under 40 CFR part 61 or 40 CFR part 63 according to § 63.7885(b)(3), you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(3)(i) and (ii) of this section.

(i) You include in your statement the citations for the specific emission limitations and work practice standards that apply to the process vents under the subpart in 40 CFR part 61 or 40 CFR part 63 that the vents are also subject.

(ii) You are complying with all applicable emissions limitations and work practice standards specified by the applicable subpart.

(4) For each process vent exempted according to § 63.7885(c), you have submitted as part of your notification of compliance status, specified in § 63.7950, a signed statement that you have met the requirements in paragraphs (b)(4)(i) and (ii) of this section.

(i) You identify in your statement each process vent that qualifies for an exemption and the exemption conditions in §63.7885(c)(1)(i) or (ii) that apply to each exempted process vent.

(ii) You have performed the measurements and prepared the documentation required in §63.7885(c)(2) that demonstrates that each exempted process vent stream meets the applicable exemption conditions in §63.7885(c)(1).

(c) You must demonstrate initial compliance with the general standards in §63.7886 that apply to your affected remediation material management units by meeting the requirements in paragraphs (c)(1) through (6) of this section, as applicable to your remediation material management units.

(1) If the remediation material management unit uses air pollution controls according to the standards specified in §63.7886(b)(1), you have met the initial compliance requirements applicable to the remediation material management unit in §§63.7896, 63.7901, 63.7906, 63.7911, or 63.7816.

(2) If the remediation material managed in the affected remediation material management unit has an average total VOHAP concentration less than 500 ppmw according to §63.7886(b)(2), you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have determined, according to the procedures in §63.7943, and recorded the average VOHAP concentration of the remediation material placed in the affected remediation material management unit.

(3) If HAP emissions are controlled from the affected remediation material management units to meet standards in another subpart under 40 CFR part 61 or 40 CFR part 63 according to §63.7886(b)(3), you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (c)(3)(i) and (ii) of this section.

(i) You include in your statement the citations for the specific emission limitations and work practice standards that apply to the remediation material management units under the subpart in 40 CFR part 61 or 40 CFR part 63 that the units are also subject.

(ii) You are complying with all applicable emissions limitations and work practice standards specified by the applicable subpart.

(4) If HAP emissions are controlled from the affected remediation material management unit that is an open tank or surface impoundment used for a biological treatment process according to §63.7886(b)(4), you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (c)(4)(i) and (ii) of this section.

(i) You have performed the measurements and prepared the documentation required in §63.7886(b)(4)(i) that demonstrates that each unit meets the applicable performance levels.

(ii) You will monitor the biological treatment process conducted in each unit according to the requirements in §63.684(e)(4).

(5) For each remediation material management unit used for cleanup of radioactive mixed waste and exempted according to §63.7886(c), you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (c)(5)(i) and (ii) of this section.

(i) You include in your statement the citations for the specific requirements that apply to the remediation material management units under regulations, directives, and other requirements under the Atomic Energy Act, the Nuclear Waste Policy Act, or the Waste Isolation Pilot Plant Land Withdrawal Act.

(ii) You are complying with all requirements that apply to the remediation material management units under the applicable regulations or directives.

(6) For each remediation material management unit exempted according to §63.7886(d), you have submitted as part of your notification of compliance status, specified in §63.7950, a signed statement that you have met the requirements in paragraphs (c)(6)(i) and (ii) of this section.

(i) You have designated according to the requirements in §63.7886(d)(1) each

of the remediation material management units you are selecting to be exempted.

(ii) You have performed an initial determination and prepared the documentation required in § 63.7886(d)(2) that demonstrates that the total annual HAP quantity (based on the HAP listed in Table 1 of this subpart) in the remediation material placed in all of the designated exempted remediation material management units will be less than 1 Mg/yr.

(d) You must demonstrate initial compliance with the general standards in § 63.7887 that apply to your affected equipment leak sources by meeting the requirements in § 63.7921.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

§ 63.7938 How do I demonstrate continuous compliance with the general standards?

(a) You must demonstrate continuous compliance with the general standards in §§ 63.7884 through 63.7887 that apply to your affected sources by meeting the requirements in paragraphs (b) through (d) of this section, as applicable to you.

(b) You have demonstrated continuous compliance with the general standards in § 63.7885 that apply to your affected process vents by meeting the requirements in paragraphs (b)(1) through (4) of this section, as applicable to your process vents.

(1) If HAP emissions are controlled from the affected process vents according to the emission limitations and work practice standards specified in § 63.7885(b)(1), you must demonstrate continuous compliance by meeting the requirements in § 63.7893.

(2) If the remediation material treated or managed by the process vented through the affected process vents has an average total VOHAP less than 10 ppmw according to § 63.7885(c)(1), you must demonstrate continuous compliance by performing a new determination and preparing new documentation as required in § 63.7885(c)(2) to show that the total VOHAP concentration of the remediation material remains less than 10 ppmw.

(3) If HAP emissions are controlled from the affected process vents to meet standards in another subpart under 40 CFR part 61 or 40 CFR part 63 according to § 63.7885(b)(3), you must demonstrate continuous compliance by complying with all applicable emissions limitations and work practice standards specified by the applicable subpart.

(4) For each process vent exempted according to § 63.7885(c), you must demonstrate continuous compliance by performing new measurements and preparing new documentation as required in § 63.7885(c)(2) that demonstrates that each exempted process vent stream meets the applicable exemption conditions in § 63.7885(c)(1).

(c) You must demonstrate continuous compliance with the general standards in § 63.7886 that apply to your affected remediation material management units by meeting the requirements in paragraphs (c)(1) through (6) of this section, as applicable to your remediation material management units.

(1) If the remediation material management unit uses air pollution controls according to the standards specified in § 63.7886(b)(1), you must demonstrate continuous compliance by meeting the requirements applicable to the remediation material management unit in §§ 63.7898, 63.7903, 63.7908, 63.7913, or 63.7818.

(2) If the remediation material managed in the affected remediation material managements has an average total VOHAP concentration less than 500 ppmw according to § 63.7886(b)(2), you must demonstrate continuous compliance by performing a new determination and preparing new documentation as required in § 63.7886(c)(2) to show that the total VOHAP concentration of the remediation material remains less than 500 ppmw.

(3) If HAP emissions are controlled from the affected remediation material management units to meet standards in another subpart under 40 CFR part 61 or 40 CFR part 63 according to § 63.7886(b)(3), you must demonstrate continuous compliance by meeting all applicable emissions limitations and work practice standards specified by the applicable subpart.

(4) If HAP emissions are controlled from the affected remediation material management unit that is an open tank

or surface impoundment used for a biological treatment process according to §63.7886(b)(4), you must demonstrate continuous compliance by meeting the requirements in paragraphs (c)(4)(i) and (ii) of this section.

(i) Performing new measurements and preparing new documentation as required in §63.7886(4)(i) that demonstrates that each unit meets the applicable performance levels.

(ii) Monitoring the biological treatment process conducted in each unit according to the requirements in §63.7886(4)(i).

(5) For each remediation material management unit used for cleanup of radioactive mixed waste and exempted according to §63.7886(c), you must demonstrate continuous compliance by meeting all requirements that apply to the remediation material management units under the applicable regulations or directives.

(6) For each remediation material management unit exempted according to §63.7886(d), you must demonstrate continuous compliance by performing new measurements and preparing new documentation as required in §63.7886(d)(2) to show that the total annual HAP quantity (based on the HAP listed in Table 1 of this subpart) in the remediation material placed in all of the designated exempted remediation material management units remains less than 1 Mg/yr.

(d) You have demonstrated continuous compliance with the general standards in §63.7887 that apply to your affected equipment leak sources by meeting the requirements in §63.7923.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69018, Nov. 29, 2006]

PERFORMANCE TESTS

§63.7940 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) You must conduct a performance test or design evaluation for each existing affected source within 180 calendar days after the compliance date that is specified in §63.7883.

(b) For each work practice standard that applies to you where initial compliance is not demonstrated using a performance test or design evaluation, you must demonstrate initial compliance within 30 calendar days after the compliance date that is specified in §63.7883 for your affected source.

(c) For new sources, you must conduct initial performance tests and other initial compliance demonstrations according to the provisions in §63.7(a)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69019, Nov. 29, 2006]

§63.7941 How do I conduct a performance test, design evaluation, or other type of initial compliance demonstration?

(a) You must conduct a performance test or design evaluation to demonstrate initial compliance for each new or existing affected source that is subject to an emission limit in this subpart. You must report the results of the performance test or design evaluation according to the requirements in §63.7950(e)(1).

(b) If you choose to conduct a performance test to demonstrate initial compliance, you must conduct the test according to the requirements in §63.7(e)(1) and paragraphs (b) (1) through (5) of this section.

(1) You must conduct three separate test runs for each performance test required in this section, as specified in §63.7(e)(3). Each test run must last at least 1 hour.

(2) If your initial startup date was on or before September 3, 2019, then until January 6, 2021, you must conduct each performance test under representative conditions according to the requirements in §63.7(e)(1). If your initial startup date is after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, you must conduct each performance test under conditions representative of normal operations. You may not conduct performance tests during periods of startup, shutdown, or malfunction. The owner or operator must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, the owner or operator

shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(3) You must conduct each performance test using the test methods and procedures in §63.694(l).

(4) Follow the procedures in paragraphs (b)(4)(i) through (iii) of this section to determine compliance with the facility-wide total organic mass emissions rate in §63.7890(b).

(i) Determine compliance with the total organic mass flow rate using Equation 1 of this section as follows:

$$E_h = \left(0.0416 \times 10^{-6}\right) Q_{sd} \sum_{i=1}^{n} \left(C_i \times MW_i\right) \qquad \text{(Eq. 1)}$$

Where:

E_h = Total organic mass flow rate, kg/h;

Q_{sd} = Volumetric flow rate of gases entering or exiting control device (or exiting the process vent if no control device is used), as determined by Method 2 of 40 CFR part 60, appendix A, dscm/h;

n = Number of organic compounds in the vent gas;

C_i = Organic concentration in ppm, dry basis, of compound i in the vent gas, as determined by Method 18 of 40 CFR part 60, appendix A;

MW_i = Molecular weight of organic compound i in the vent gas,kg/kg-mol;

(ii) Determine compliance with the annual total organic emissions rate using Equation 2 of this section as follows:

$$E_A = E_h \times H \qquad \text{(Eq. 2)}$$

Where:

E_A = Total organic mass emissions rate, kilograms per year;

E_h = Total organic mass flow rate for the process vent, kg/h;

H = Total annual hours of operation for the affected unit, h.

(iii) Determine compliance with the total organic emissions limit from all affected process vents at the facility by summing the total hourly organic mass emissions rates (E_h as determined in Equation 1 of this section) and summing the total annual organic mass emissions rates (E_A, as determined in Equation 2 of this section) for all affected process vents at the facility.

(5) Determine compliance with the 95 percent reduction limit in §63.7890(a)(2)(i) for the combination of all affected process vents at the facility using Equations 3 and 4 of this section to calculate control device inlet and outlet concentrations and Equation 5 of this section to calculate control device emission reductions for process vents as follows:

$$E_i = K_2 \left(\sum_{j=1}^{n} C_{ij} M_{ij} \right) Q_i \qquad \text{(Eq. 3)}$$

$$E_o = K_2 \left(\sum_{j=1}^{n} C_{oj} M_{oj} \right) Q_o \qquad \text{(Eq. 4)}$$

Where:

C_{ij}, C_{oj} = Concentration of sample component j of the gas stream at the inlet and outlet of the control device, dry basis, parts per million by volume. For uncontrolled vents, $C_{ij} = C_{oj}$ and equal the concentration exiting the vent;

E_i, E_o = Mass rate of total organic compounds (TOC) (minus methane and ethane) or total HAP, from Table 1 of this subpart, at the inlet and outlet of the control device, respectively, dry basis, kilogram per hour. For uncontrolled vents, $E_i = E_o$ and equal the concentration exiting the vent;

M_{ij}, M_{oj} = Molecular weight of sample component j of the gas stream at the inlet and outlet of the control device, respectively, gram/gram-mole. For uncontrolled vents, $M_{ij} = M_{oj}$ and equal the gas stream molecular weight exiting the vent;

Q_i, Q_o = Flowrate of gas stream at the inlet and outlet of the control device, respectively, dry standard cubic meters per minute (dscm/min). For uncontrolled vents, $Q_i = Q_o$ and equals the flowrate exiting the vent;

K_2 = Constant, 2.494×10^{-6} (parts per million)$^{-1}$ (gram-mole per standard cubic meter) (kilogram/gram)(minute/hour, where standard temperature (gram-mole per standard cubic meter) is 20 °C);

n = the number of components in the sample.

$$R_v = \frac{\sum_{j=1}^{n} E_i - \sum_{j=1}^{n} E_o}{\sum_{j=1}^{n} E_i} \times 100 \qquad \text{(Eq. 5)}$$

Where:

R_v = Overall emissions reduction for all affected process vents, percent

E_i = Mass rate of TOC (minus methane and ethane) or total HAP, from Table 1 of this subpart, at the inlet to the control device, or exiting the vent for uncontrolled vents, as calculated in this section, kilograms TOC per hour or kilograms HAP per hour;

E_o = Mass rate of TOC (minus methane and ethane) or total HAP, from Table 1 of this subpart, at the outlet to the control device, or exiting the vent for uncontrolled vents, as calculated in this section, kilograms TOC per hour or kilograms HAP per hour. For vents without a control device, $E_o = E_i$;

n = number of affected source process vents.

(c) If you use a carbon adsorption system, condenser, vapor incinerator, boiler, or process heater to meet an emission limit in this subpart, you may choose to perform a design evaluation to demonstrate initial compliance instead of a performance test. You must perform a design evaluation according to the general requirements in §63.693(b)(8) and the specific requirements in §63.693(d)(2)(ii) for a carbon adsorption system (including establishing carbon replacement schedules and associated requirements), §63.693(e)(2)(ii) for a condenser, §63.693(f)(2)(ii) for a vapor incinerator, or §63.693(g)(2)(i)(B) for a boiler or process heater.

(d) During the performance test or design evaluation, you must collect the appropriate operating parameter monitoring system data, average the operating parameter data over each test run, and set operating limits, whether a minimum or maximum value, based on the average of values for each of the three test runs. If you use a control device design analysis to demonstrate control device performance, then the minimum or maximum operating parameter value must be established based on the control device design analysis and supplemented, as necessary, by the control device manufacturer recommendations or other applicable information.

(e) If you control air emissions from an affected source by introducing the vent stream into the flame zone of a boiler or process heater according to the requirements in §63.693(g)(1)(iii), you must conduct a performance test or design evaluation to demonstrate that the boiler or process heater meets the applicable emission limit while operating at a residence time of 0.5 seconds or greater and at a combustion zone temperature of 760 °C or higher.

(f) You must conduct a performance evaluation for each continuous monitoring system according to the requirements in §63.8(e).

(g) If you are required to conduct a visual inspection of an affected source, you must conduct the inspection according to the procedures in §63.906(a)(1) for Tank Level 1 controls, §63.1063(d) for Tank Level 2 controls, §63.926(a) for Container Level 1 controls, §63.946(a) for a surface impoundment equipped with a floating membrane cover, §63.946(b) for a surface impoundment equipped with a cover and vented to a control device, §63.1047(a) for a separator with a fixed roof, §63.1047(c) for a separator equipped with a fixed roof and vented to a control device, §63.695(c)(1)(i) or (c)(2)(i) for a closed vent system, and §63.964(a) for individual drain systems.

(h) [Reserved]

(i) If you use Container Level 2 controls, you must conduct a test to demonstrate that the container operates with no detectable organic emissions or that the container is vapor-tight. You must conduct the test using Method 21 (40 CFR part 60, appendix A) and the procedures in §63.925(a) to demonstrate that the container operates with no detectable organic emissions or Method 27 (40 CFR part 60, appendix A) and the procedures in §63.925(b) to demonstrate that the container is vapor-tight.

(j) If you locate an affected source inside a permanent total enclosure that is vented to a control device, you must demonstrate that the enclosure meets the verification criteria in section 5 of Procedure T in 40 CFR 52.741, appendix B.

(k) If you use a fixed roof or a floating roof to control air emissions from a separator, you must conduct a test to demonstrate that the roof operates with no detectable organic emissions using Method 21 (40 CFR part 60, appendix A) and the procedures in § 63.1046(a). If you use a floating roof, you also must measure the seal gaps according to the procedures in § 63.1046(b).

(l) If you use a flare to control air emissions, you must conduct a visible emissions test using Method 22 in 40 CFR part 60, appendix A, and the procedures in § 63.11(b)(4).

(m) For each initial compliance demonstration that requires a performance test or design evaluation, you must report the results in your notification of compliance status according to the requirements in § 63.7950(e)(1). For each initial compliance demonstration that does not require a performance test or design evaluation, you must submit a notification of compliance status according to the requirements in § 63.7950(e)(2).

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69019, Nov. 29, 2006; 85 FR 41708, July 10, 2020]

§ 63.7942 When must I conduct subsequent performance tests?

For non-flare control devices, you must conduct performance tests at any time the EPA requires you to according to § 63.7(a)(3).

[85 FR 41708, July 10, 2020]

§ 63.7943 How do I determine the average VOHAP concentration of my remediation material?

(a) General requirements. You must determine the average total VOHAP concentration of a remediation material using either direct measurement as specified in paragraph (b) of this section or by knowledge as specified in paragraph (c) of this section. These methods may be used to determine the average VOHAP concentration of any material listed in (a)(1) through (3) of this section.

(1) A single remediation material stream; or

(2) Two or more remediation material streams that are combined prior to, or within, a remediation material management unit or treatment process; or

(3) Remediation material that is combined with one or more non-remediation material streams prior to, or within, a remediation material management unit or treatment process.

(b) Direct measurement. To determine the average total VOHAP concentration of a remediation material using direct measurement, you must use the procedures in paragraphs (b)(1) through (3) of this section.

(1) Sampling. Samples of each material stream must be collected from the container, pipeline, or other device used to deliver each material stream prior to entering the remediation material management unit or treatment process in a manner such that volatilization of organics contained in the sample is minimized and an adequately representative sample is collected and maintained for analysis by the selected method.

(i) The averaging period to be used for determining the average total VOHAP concentration for the material stream on a mass-weighted average basis must be designated and recorded. The averaging period can represent any time interval that you determine is appropriate for the material stream but must not exceed 1 year. For streams that are combined, an averaging period representative for all streams must be selected.

(ii) No less than four samples must be collected to represent the complete range of HAP compositions and HAP quantities that occur in each material stream during the entire averaging period due to normal variations in the material stream(s). Examples of such normal variations are variation of the HAP concentration within a contamination area.

(iii) All samples must be collected and handled according to written procedures you prepare and document in a site sampling plan. This plan must describe the procedure by which representative samples of the material stream(s) are collected such that a minimum loss of organics occurs throughout the sample collection and handling process and by which sample integrity is maintained. A copy of the written sampling plan must be maintained on site in the facility operating records. An example of an acceptable

sampling plan includes a plan incorporating sample collection and handling procedures according to the guidance found in ''Test Methods for Evaluating Solid Waste, Physical/Chemical Methods,'' EPA Publication No. SW–846 or Method 25D in 40 CFR part 60, appendix A.

(2) Analysis. Each collected sample must be prepared and analyzed according to either one of the methods listed in §63.694(b)(2)(ii), or any current EPA Contracts Lab Program method (or future revisions) capable of identifying all the HAP in Table 1 of this subpart.

(3) Calculations. The average total VOHAP concentration ($\bar{C}$) on a mass-weighted basis must be calculated by using the results for all samples analyzed according to paragraph (b)(2) of this section and Equation 1 of this section as follows:

$$\bar{C} = \frac{1}{Q_T} \times \sum_{i=1}^{n} \left(Q_i \times C_i \right) \qquad \text{(Eq. 1)}$$

Where:

$\bar{C}$ = Average VOHAP concentration of the material on a mass-weighted basis, ppmw.

i = Individual sample ''i'' of the material.

n = Total number of samples of the material collected (at least 4 per stream) for the averaging period (not to exceed 1 year).

Q_i = Mass quantity of material stream represented by C_i, kilograms per hour (kg/hr).

Q_T = Total mass quantity of all material during the averaging period, kg/hr.

C_i = Measured VOHAP concentration of sample ''i'' as determined according to the requirements of paragraph (b)(2) of this section, ppmw.

(c) Knowledge of the material. To determine the average total VOHAP concentration of a remediation material using knowledge, you must use the procedures in paragraphs (c)(1) through (3) of this section.

(1) Documentation must be prepared that presents the information used as the basis for your knowledge of the material stream's average VOHAP concentration. Examples of information that may be used as the basis for knowledge include: material balances for the source(s) generating each material stream; species-specific chemical test data for the material stream from previous testing that are still applicable to the current material stream; test data for material from the contamination area(s) being remediated.

(2) If test data are used as the basis for knowledge, then you must document the test method, sampling protocol, and the means by which sampling variability and analytical variability are accounted for in the determination of the average VOHAP concentration. For example, you may use HAP concentration test data for the material stream that are validated according to Method 301 in 40 CFR part 63, appendix A as the basis for knowledge of the material. This information must be provided for each material stream where streams are combined.

(3) If you use species-specific chemical concentration test data as the basis for knowledge of the material, you may adjust the test data to the corresponding average VOHAP concentration value which would be obtained had the material samples been analyzed using Method 305. To adjust these data, the measured concentration for each individual HAP chemical species contained in the material is multiplied by the appropriate species-specific adjustment factor (f_{m305}) listed in Table 1 of this subpart.

(d) In the event that you and we disagree on a determination using knowledge of the average total VOHAP concentration for a remediation material, then the results from a determination of VOHAP concentration using direct measurement by EPA Method 305 in 40 CFR part 60, appendix A, as specified in paragraph (b) of this section, will be used to determine compliance with the applicable requirements of this subpart. We may perform or require that you perform this determination using direct measurement.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69019, Nov. 29, 2006; 85 FR 41708, July 10, 2020]

§ 63.7944 How do I determine the maximum HAP vapor pressure of my remediation material?

(a) You must determine the maximum HAP vapor pressure of your remediation material using either direct measurement as specified in paragraph (b) of this section or by knowledge as specified in paragraph (c) of this section.

(b) Direct measurement to determine the maximum HAP vapor pressure.

(1) Sampling. A sufficient number of samples must be collected to be representative of the remediation material contained in the tank. All samples must be collected and handled according to written procedures prepared by you and documented in a site sampling plan. This plan must describe the procedure by which representative samples of the remediation material are collected such that a minimum loss of organics occurs throughout the sample collection and handling process and by which sample integrity is maintained. A copy of the written sampling plan must be maintained on site in the facility site operating records. An example of an acceptable sampling plan includes a plan incorporating sample collection and handling procedures according to the guidance found in ''Test Methods for Evaluating Solid Waste, Physical/Chemical Methods,'' EPA Publication No. SW–846 or Method 25D in 40 CFR part 60, appendix A.

(2) Analysis. Any one of the following methods may be used to analyze the samples and compute the maximum HAP vapor pressure of the remediation material:

(i) Method 25E in 40 CFR part 60 appendix A;

(ii) Methods described in American Petroleum Institute Bulletin 2517, ''Evaporation Loss from External Floating Roof Tanks,'' (incorporated by reference, see § 63.14);

(iii) Methods obtained from standard reference texts;

(iv) ASTM D2879–83 (incorporated by reference, see § 63.14); or

(v) Any other method approved by the Administrator.

(c) Use of knowledge to determine the maximum HAP vapor pressure. Documentation must be prepared and recorded that presents the information used as the basis for your knowledge that the maximum HAP vapor pressure of the remediation material is less than the maximum vapor pressure limit listed in Table 2 of this subpart for the applicable tank design capacity category.

(d) In the event that you and us disagree on a determination using knowledge of the maximum HAP vapor pressure of the remediation material, then the results from a determination of maximum HAP vapor pressure using direct measurement by EPA Method 25E in 40 CFR part 60, appendix A, as specified in paragraph (b) of this section, will be used to determine compliance with the applicable requirements of this subpart. We may perform or require that you perform this determination using direct measurement.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41708, July 10, 2020]

CONTINUOUS MONITORING SYSTEMS

§ 63.7945 What are my monitoring installation, operation, and maintenance requirements?

(a) Each CPMS must meet the requirements in paragraphs (a)(1) through (4) of this section.

(1) Complete a minimum of one cycle of operation for each successive 15-minute period.

(2) To calculate a valid hourly value, you must have at least three of four equally spaced data values (or at least two, if that condition is included to allow for periodic calibration checks) for that hour from a CPMS that is not out of control according to the monitoring plan referenced in § 63.7935.

(3) To calculate the average emissions for each averaging period, you must have at least 75 percent of the hourly averages for that period using only block hourly average values that are based on valid data (*i.e.*, not from out-of-control periods).

(4) Unless otherwise specified, each CPMS must determine the hourly average of all recorded readings and daily average, if required.

(b) You must record the results of each inspection, calibration, and validation check.

(c) You must conduct a performance evaluation for each CPMS according to the requirements in § 63.8(e) and your site-specific monitoring plan.

(d) Failure to meet the requirements of paragraphs (a)(1) through (4) of this section is a deviation and must be reported according to the requirements in § 63.7951(b)(7).

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41708, July 10, 2020]

§ 63.7946 How do I monitor and collect data to demonstrate continuous compliance?

(a) You must monitor and collect data according to this section and your site-specific monitoring plan required in § 63.7935.

(b) Except for monitor malfunctions, associated repairs, and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times that the affected source is operating.

(c) You may not use data recorded during monitoring malfunctions, associated repairs, out of control periods and required quality assurance or control activities in data averages and calculations used to report emissions or operating levels, nor may such data be used in fulfilling a minimum data availability requirement, if applicable. You must use all the data collected during all other periods in assessing the operation of the control device and associated control system.

§ 63.7947 What are my monitoring alternatives?

(a) As an alternative to the parametric monitoring required in this subpart, you may install, calibrate, and operate a continuous emission monitoring system (CEMS) to measure the control device outlet total organic emissions or organic HAP emissions concentration.

(1) The CEMS used on combustion control devices must include a diluent gas monitoring system (for O_2 or CO_2) with the pollutant monitoring system in order to correct for dilution (*e.g.*, to 0 percent excess air).

(2) Each CEMS must complete a minimum of one cycle of operation (sampling, analyzing, and data recording) for each successive 15-minute period. Data must be reduced as specified in § 63.8(g)(2).

(3) You must conduct a performance evaluation of the CEMS according to the requirements in § 63.8 and Performance Specification 8 (for a total organic emissions CEMS) or Performance Specification 9 (for a HAP emissions CEMS) and Performance Specification 3 (for an O_2 or CO_2 CEMS) of 40 CFR part 60, appendix B. The relative accuracy provision of Performance Specification 8, sections 2.4 and 3 need not be conducted.

(4) You must prepare a site-specific monitoring plan for operating, calibrating, and verifying the operation of your CEMS according to the requirements in §§ 63.8(c), (d), and (e).

(5) You must establish the emissions concentration operating limit according to paragraphs (a)(5)(i) and (ii) of this section.

(i) During the performance test, you must monitor and record the total organic or HAP emissions concentration at least once every 15 minutes during each of the three test runs.

(ii) Use the data collected during the performance test to calculate and record the average total organic or HAP emissions concentration maintained during the performance test. The average total organic or HAP emissions concentration, corrected for dilution as appropriate, is the maximum operating limit for your control device.

(b) You must maintain the daily (24-hour) average total organic or HAP emissions concentration in the exhaust vent stream of the control device outlet less than or equal to the site-specific operating limit established during the performance test.

NOTIFICATION, REPORTS, AND RECORDS

§ 63.7950 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(e), 63.8(f)(4) and (6), and 63.9(b) through (h) that apply to you.

(b) As specified in § 63.9(b)(2), if you start up your affected source before October 8, 2003, you must submit an Initial Notification not later than 120 calendar days after October 8, 2003, or no later than 120 calendar days after the source becomes subject to this subpart, whichever is later.

(c) As specified in § 63.9(b)(3), if you start up your new or reconstructed affected source on or after the effective date, you must submit an Initial Notification no later than 120 calendar days after initial startup, or no later than

120 calendar days after the source becomes subject to this subpart, whichever is later.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required in § 63.7(b)(1).

(e) If you are required to conduct a performance test, design evaluation, or other initial compliance demonstration, you must submit a Notification of Compliance Status according to § 63.9(h)(2)(ii).

(1) For each initial compliance demonstration that includes a performance test or design evaluation, you must submit the Notification of Compliance Status, including the performance test results, before the close of business on the 60th calendar day following the completion of the performance test according to § 63.10(d)(2). You must submit the complete design evaluation and supporting documentation.

(2) For each initial compliance demonstration that does not include a performance test, you must submit the Notification of Compliance Status before the close of business on the 30th calendar day following the completion of the initial compliance demonstration.

(f) You must provide written notification to the Administrator of the alternative standard selected under § 63.1006(b)(5) or (6) before implementing either of the provisions.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69019, Nov. 29, 2006; 85 FR 73913, Nov. 19, 2020]

§ 63.7951 What reports must I submit and when?

(a) Compliance report due dates. Unless the Administrator has approved a different schedule, you must submit a semiannual compliance report to your permitting authority according to the requirements specified in paragraphs (a)(1) through (5) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.7883 and ending on June 30 or December 31, whichever date comes first after the compliance date that is specified for your affected source.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after your first compliance report is due.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after the end of the semiannual reporting period.

(5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of the dates specified in paragraphs (a)(1) through (4) of this section.

(6) For pressure relief devices in remediation material service subject to the requirements of § 63.7923, submit a description of the device or monitoring system to be implemented, including the pressure relief devices and process parameters to be monitored, and a description of the alarms or other methods by which operators will be notified of a pressure release. If your initial startup date was on or before September 3, 2019, then this information must be submitted with the next semiannual periodic compliance report. If your initial startup date is after September 3, 2019, this information must be submitted in the first periodic compliance report. The information must be updated in subsequent reports if changes are made.

(7) Semi-annual compliance reports must be submitted according to paragraph (f) of this section.

(b) Compliance report contents. Each compliance report must include the information specified in paragraphs (b)(1) through (3) of this section and, as applicable, paragraphs (b)(4) through (9) of this section.

(1) Company name and address.

(2) Statement by a responsible official, with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) If your initial startup date was on or before September 3, 2019, then until January 6, 2021, if you had a startup, shutdown, or malfunction during the reporting period and you took actions consistent with your SSMP, the compliance report must include the information in §63.10(d)(5)(i). If your initial startup date is after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, an SSMP and the information in §63.10(d)(5)(i) is not required.

(5) If there were no deviations from any emissions limitations (including operating limit), work practice standards, or operation and maintenance requirements, a statement that there were no deviations from the emissions limitations, work practice standards, or operation and maintenance requirements during the reporting period.

(6) If there were no periods during which a continuous monitoring system (including a CPMS or CEMS) was out-of-control as specified by §63.8(c)(7), a statement that there were no periods during which the CPMS was out-of-control during the reporting period.

(7) For each deviation from an emissions limitation (including an operating limit) that occurs at an affected source for which you are not using a continuous monitoring system (including a CPMS or CEMS) to comply with an emissions limitation or work practice standard required in this subpart, the compliance report must contain the information specified in paragraphs (b)(1) through (3) and (b)(7)(i) and (ii) of this section.

(i) The total operating time of each affected source during the reporting period.

(ii) Information on the number of deviations. For each deviation, include the date, time, and duration, a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, a description of the method used to estimate the emissions, the actions taken to minimize emissions, the cause of the deviation (including unknown cause), as applicable, and the corrective actions taken to return the affected unit to its normal or usual manner of operation.

(8) For each deviation from an emissions limitation (including an operating limit) or work practice standard occurring at an affected source where you are using a continuous monitoring system (including a CPMS or CEMS) to comply with the emissions limitations or work practice standard in this subpart, you must include the information specified in paragraphs (b)(1) through (3) and (b)(8)(i) through (xi) of this section.

(i) Information on the number of deviations. For each deviation, include the date, time, and duration, a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, a description of the method used to estimate the emissions, the actions taken to minimize emissions, the cause of the deviation (including unknown cause), as applicable, and the corrective actions taken to return the affected unit to its normal or usual manner of operation.

(ii) The date and time that each continuous monitoring system was inoperative, except for zero (low-level) and high-level checks.

(iii) The date, time, and duration that each continuous monitoring system was out-of-control, including the information in §63.8(c)(8).

(iv) For each deviation caused when the daily average value of a monitored operating parameter is less than the minimum operating parameter limit (or, if applicable, greater than the maximum operating parameter limit), the report must include the daily average values of the monitored parameter, the applicable operating parameter limit, and the date and duration of the period that the deviation occurred. For each deviation caused by lack of monitoring data, the report must include the date and duration of period when the monitoring data were not collected and the reason why the data were not collected.

(v) A summary of the total duration of the deviations during the reporting

period and the total duration as a percent of the total source operating time during that reporting period.

(vi) A breakdown of the total duration of the deviations during the reporting period into those that are due to control equipment problems, process problems, other known causes, and unknown causes.

(vii) A summary of the total duration of continuous monitoring system downtime during the reporting period and the total duration of continuous monitoring system downtime as a percent of the total source operating time during the reporting period.

(viii) A brief description of the process units.

(ix) A brief description of the continuous monitoring system.

(x) The date of the latest continuous monitoring system certification or audit.

(xi) A description of any changes in continuous monitoring systems, processes, or controls since the last reporting period.

(9) You must include the information on equipment leaks required in periodic reports by §63.1018(a) or §63.1039(b).

(10) For pressure relief devices in remediation material service, compliance reports must include the information specified in paragraphs (b)(10)(i) through (iii) of this section.

(i) For pressure relief devices in remediation material service subject to §63.7920(e), report the number of occurrences of an instrument reading of 500 ppm above the background level or greater, if detected more than 5 days after a pressure release.

(ii) For pressure relief devices in remediation service subject to §63.7923(c), report confirmation, yes or no, that the monitoring required to show compliance was conducted during the reporting period.

(iii) For pressure relief devices in remediation material service subject to §63.7923(d), report each pressure release to the atmosphere, including the following information:

(A) The date, time, and duration of the pressure release actuation event.

(B) An estimate of the mass quantity of total HAP listed in Table 1 of this subpart emitted during the pressure release actuation event and the method used for determining this quantity.

(C) The source, nature and cause of the pressure release actuation event.

(D) The actions taken to prevent this pressure release actuation event.

(E) The measures implemented during the reporting period to prevent future such pressure release actuation events, and, if applicable, the implementation schedule for planned corrective actions to be implemented subsequent to the reporting period.

(11) Pressure tank closure device or bypass deviation information. Compliance reports must include the information specified in paragraph (b)(11)(iv) of this section when any of the conditions in paragraphs (b)(11)(i) through (iii) of this section are met.

(i) Any pressure tank closure device, as specified in specified in §63.7895(d)(4), has released to the atmosphere.

(ii) Any closed vent system that includes bypass devices that could divert a vent a stream away from the control device and into the atmosphere, as specified in §63.7927(a)(2), has released directly to the atmosphere.

(iii) Any open-ended valve or line in an emergency shutdown system which is designed to open automatically in the event of a process upset, as specified in §63.1014(c) or §63.1033(c), has released directly to the atmosphere.

(iv) The compliance report must include the information specified in paragraphs (b)(11)(iv)(A) through (E) of this section.

(A) The source, nature and cause of the release.

(B) The date, time and duration of the discharge.

(C) An estimate of the quantity of total HAP listed in Table 1 of this subpart emitted during the release and the method used for determining this quantity.

(D) The actions taken to prevent this release.

(E) The measures adopted to prevent future such releases.

(c) *Immediate startup, shutdown, and malfunction report.* If your initial startup was on or before September 3, 2019, then until January 6, 2021, if you had a startup, shutdown, or malfunction during the semiannual reporting period

that was not consistent with your SSMP, you must submit an immediate startup, shutdown and malfunction report according to the requirements of § 63.10(d)(5)(ii). If your initial startup date is after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, an immediate startup, shutdown, and malfunction report is not required.

(d) Part 70 monitoring report. If you have obtained a title V operating permit for an affected source pursuant to 40 CFR part 70 or 40 CFR part 71, you must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If you submit a compliance report for an affected source along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all the required information concerning deviations from any emissions limitation or operation and maintenance requirement in this subpart, submission of the compliance report satisfies any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report does not otherwise affect any obligation you may have to report deviations from permit requirements for an affected source to your permitting authority.

(e) *Performance Test and CMS Performance Evaluation Reports.* Within 60 days after the date of completing each performance test or continuous monitoring system (CMS) performance evaluation (as defined in § 63.2) required by this subpart, the owner or operator must submit the results of the performance test or performance evaluation according to the manner specified by either paragraph (e)(1) or (2) of this section.

(1) *Data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test or the performance evaluation of CMS measuring relative accuracy test audit (RATA) pollutants to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). The data must be submitted in a file format generated through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the extensible markup language (XML) schema listed on the EPA's ERT website.

(2) *Data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the test.* The results of the performance test or the performance evaluation of CMS measuring RATA pollutants by methods that are not supported by the ERT must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. The results of the performance test or the performance evaluation of CMS measuring RATA pollutants by methods that are not supported by the ERT, must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(f) *Submitting reports electronically.* If you are required to submit reports following the procedure specified in this paragraph, you must submit reports to the EPA via CEDRI, which can be accessed through the EPA's CDX (*https://cdx.epa.gov/*). You must use the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/compliance-and-emissions-data-reporting-interface-cedri*) for this subpart. The report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. If you claim some of the information required to be submitted via CEDRI is confidential business information (CBI), submit a complete report, including information claimed to be CBI, to the EPA. The report must be generated using the appropriate form on the CEDRI website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly

mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph.

(g) *Claims of EPA system outage*. If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement. To assert a claim of EPA system outage, you must meet the requirements outlined in paragraphs (g)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either the EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning five business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(h) *Claims of force majeure*. If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of force majeure for failure to timely comply with the reporting requirement. To assert a claim of force majuere, you must meet the requirements outlined in paragraphs (h)(1) through (5) of this section.

(1) You may submit a claim if a force majeure event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For the purposes of this section, a force majeure event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (*e.g.*, hurricanes, earthquakes, or floods), acts of war or terrorism, or equipment failure or safety hazard beyond the control of the affected facility (*e.g.*, large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the force majeure event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the force majeure event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of force majeure and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the force majeure event occurs.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41708, July 10, 2020]

§ 63.7952 What records must I keep?

(a) You must keep the records specified in paragraphs (a)(1) through (4) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63.10(b)(1) and (b)(2)(xiv).

(2) If your initial startup date is on or before September 3, 2019, you must continue to keep any records specified in § 63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunction.

(3) If your initial startup was after September 3, 2019, then as of July 10, 2020, and for all sources after January 6, 2021, for each deviation from an emissions limitation (including an operating limit) or work practice standard occurring at an affected source, you must record information on the number of deviations. For each deviation, include the date, time, and duration, a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, a description of the method used to estimate the emissions, the actions taken to minimize emissions, the cause of the deviation (including unknown cause), as applicable, and the corrective actions taken to return the affected unit to its normal or usual manner of operation.

(4) For pressure relief devices in remediation material service, keep records of the information specified in paragraphs (a)(4)(i) through (iii) of this section, as applicable.

(i) A list of identification numbers for pressure relief devices that are not subject to the requirements of § 63.7923(c) and (d) under the provisions of § 63.7923(e).

(ii) A list of identification numbers for pressure relief devices subject to the requirements of § 63.7923(a), (c), and (d) that do not consist of or include a rupture disk.

(iii) A list of identification numbers for pressure relief devices subject to the requirements of § 63.7923(a), (c), and (d) equipped with rupture disks.

(5) For pressure relief devices in remediation material service subject to § 63.7923(d), keep records of each pressure release event to the atmosphere as specified in paragraphs (a)(5)(i) through (viii) of this section.

(i) The date, time, and duration of the pressure release event.

(ii) The dates and results of the EPA Method 21 of 40 CFR part 60, appendix A, monitoring following a pressure release event, if applicable. The results of each monitoring event shall include the measured background level and the maximum instrument reading measured at each pressure relief device.

(iii) The dates replacement rupture disks were installed following a pressure release event, if applicable.

(iv) An estimate of the mass quantity of total HAP listed in Table 1 of this subpart emitted during the pressure release event and the method used for determining this quantity.

(v) The source, nature and cause of the pressure release event, including an identification of the affected pressure relief device(s) and a statement noting whether the event resulted from the same cause(s) identified following a previous pressure release event.

(vi) The corrective measures identified to prevent future such pressure release events, or an explanation of why corrective measures are not necessary.

(vii) The actions taken to prevent this pressure release event.

(viii) Records of the corrective measures implemented, including a description of the corrective measure(s) completed within the first 45 days following a pressure release event, and, if applicable, the implementation schedule for planned corrective measures to be implemented subsequent to the first 45 days following the pressure release event, including proposed commencement and completion dates.

(6) Records of the number of pressure release events during each calendar year and the number of those events for which the cause was determined to be a force majeure event. Keep these records for the current calendar year and the past 5 calendar years.

(7)(i) For pressure tank closure devices, as specified in § 63.7895(d)(4), keep records of each release to the atmosphere, including the information specified in paragraphs (a)(7)(iii)(A) through (G) of this section.

(ii) For each closed vent system that includes bypass devices that could divert a stream away from the control device and into the atmosphere, as specified in § 63.7927(a)(2), and each open-ended valve or line in an emergency shutdown system which is designed to open automatically in the event of a process upset, as specified in § 63.1014(c) or § 63.1033(c), keep records of each release to the atmosphere, including the information specified in paragraphs (a)(7)(iii)(A) though (G) of this section.

(iii)(A) The source, nature, and cause of the release.

(B) The date, time, and duration of the release.

(C) An estimate of the quantity of HAP listed in Table 1 of this subpart emitted during the release and the calculations used for determining this quantity.

(D) The actions taken to prevent this release.

(E) The measures adopted to prevent future such release.

(F) Hourly records of whether the bypass flow indicator specified under § 63.7927(a)(2)(i) was operating and whether a diversion was detected at any time during the hour, as well as records of the times of all periods when the vent stream is diverted from the control device or the flow indicator is not operating.

(G) Where a seal mechanism is used to comply with § 63.7927(a)(2)(ii), hourly records of flow are not required. In such cases, you must record that the monthly visual inspection of the seals or closure mechanism has been done and record the duration of all periods when the seal mechanism is broken, the bypass line valve position has changed, or the key for a lock-and-key type lock has been checked out, and records of any car-seal that has broken.

(8) A record of the fluid level at the beginning and end of each maintenance period during which the tank is subject to § 63.7925(b)(3).

(9) Results of performance tests and performance evaluations as required by § 63.10(b)(2)(viii).

(10) The records of initial and ongoing determinations for affected sources that are exempt from control requirements under this subpart.

(b) For each continuous monitoring system, you must keep the records as described in paragraphs (b)(1) and (2) of this section.

(1) Records described in § 63.10(b)(2)(vi) through (xi) that apply to your continuous monitoring system.

(2) Performance evaluation plans, including previous (i.e., superseded) versions of the plan as required in § 63.8(d)(3).

(c) You must keep the records required by this subpart to show continuous compliance with each emissions limitation, work practice standard, and operation and maintenance requirement that applies to you.

(d) You must record, on a semiannual basis, the information in § 63.696(g) for planned routine maintenance of a control device for emissions from process vents.

(e) Any records required to be maintained by this part that are submitted electronically via the EPA's CEDRI may be maintained in electronic format. This ability to maintain electronic copies does not affect the requirement for facilities to make records, data, and reports available upon request to a delegated air agency or the EPA as part of an on-site compliance evaluation.

[68 FR 58190, Oct. 8, 2003, as amended at 85 FR 41710, July 10, 2020]

§ 63.7953 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep your files of all information (including all reports and notifications) for 5 years following the date of each occurrence, measurement, maintenance, action taken to correct the cause of a deviation, report, or record.

(c) You must keep each record on site for at least 2 years after the date of

each occurrence, measurement, maintenance, corrective action, report, or record, according to §63.10(b)(1). You can keep the records off-site for the remaining 3 years.

(d) If, after the remediation activity is completed, there is no other remediation activity at the facility, and you are no longer the owner of the facility, you may keep all records for the completed remediation activity at an off-site location provided you notify the Administrator in writing of the name, address and contact person for the off-site location.

OTHER REQUIREMENTS AND INFORMATION

§ 63.7955 What parts of the General Provisions apply to me?

Table 3 of this subpart shows which parts of the General Provisions in §§63.1 through 63.15 apply to you.

§ 63.7956 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the EPA, or a delegated authority such as your State, local, or tribal agency. If the EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency, in addition to the EPA, has the authority to implement and enforce this subpart. You should contact your EPA Regional Office (see list in §63.13) to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under section 40 CFR part 63, subpart E, the authorities contained in paragraph (c) of this section are retained by the Administrator of EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities that cannot be delegated to State, local, or tribal agencies are listed in paragraphs (c)(1) through (4) of this section.

(1) Approval of alternatives to the non-opacity emissions limitations and work practice standards in this subpart under §63.6(g).

(2) Approval of major changes to test methods under §63.7(e)(2)(ii) and (f) and as defined in §63.90.

(3) Approval of major changes to monitoring under §63.8(f) and as defined in §63.90.

(4) Approval of major changes to recordkeeping and reporting under §63.10(f) and as defined in §63.90.

(5) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69019, Nov. 29, 2006; 85 FR 41711, July 10, 2020]

§ 63.7957 What definitions apply to this subpart?

Terms used in this subpart are defined in the CAA, in §63.2, and in this section. If a term is defined both in this section and in another subpart cross-referenced by this subpart, then the term will have the meaning given in this section for purposes of this subpart.

Boiler means an enclosed combustion device that extracts useful energy in the form of steam and is not an incinerator or a process heater.

Bypass means diverting a process vent or closed vent system stream to the atmosphere such that it does not first pass through an emission control device.

Closed vent system means a system that is not open to the atmosphere and is composed of hard-piping, ductwork, connections, and, if necessary, fans, blowers, or other flow-inducing device that conveys gas or vapor from an emissions point to a control device.

Closure device means a cap, hatch, lid, plug, seal, valve, or other type of fitting that prevents or reduces air pollutant emissions to the atmosphere by blocking an opening in a cover when the device is secured in the closed position. Closure devices include devices that are detachable from the cover (*e.g.*, a sampling port cap), manually operated (*e.g.*, a hinged access lid or hatch), or automatically operated (*e.g.*, a spring-loaded pressure relief valve).

Container means a portable unit used to hold material. Examples of containers include, but are not limited to drums, dumpsters, roll-off boxes, bulk cargo containers commonly known as portable tanks or totes, cargo tank trucks, dump trucks, and rail cars. For the purpose of this subpart, a front-end loader, excavator, backhoe, or other

type of self-propelled excavation equipment is not a container.

Continuous record means documentation of data values measured at least once every 15 minutes and recorded at the frequency specified in this subpart.

Continuous recorder means a data recording device that either records an instantaneous data value at least once every 15 minutes or records 15-minutes or more frequent block averages.

Control device means equipment used recovering, removing, oxidizing, or destroying organic vapors. Examples of such equipment include but are not limited to carbon adsorbers, condensers, vapor incinerators, flares, boilers, and process heaters.

Cover means a device that prevents or reduces air pollutant emissions to the atmosphere by forming a continuous barrier over the remediation material managed in a unit. A cover may have openings (such as access hatches, sampling ports, gauge wells) that are necessary for operation, inspection, maintenance, and repair of the unit on which the cover is used. A cover may be a separate piece of equipment which can be detached and removed from the unit (such as a tarp) or a cover may be formed by structural features permanently integrated into the design of the unit.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart, including but not limited to any emissions limitation (including any operating limit), or work practice standard;

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Fails to meet any emissions limitation, (including any operating limit), or work practice standard in this subpart regardless of whether or not such failure is permitted by this subpart.

Emissions limitation means any emissions limit, opacity limit, operating limit, or visible emissions limit.

Emissions point means an individual tank, surface impoundment, container, oil-water, organic-water separator, transfer system, vent, or enclosure.

Enclosure means a structure that surrounds a tank or container, captures organic vapors emitted from the tank or container, and vents the captured vapor through a closed vent system to a control device.

Equipment means each pump, pressure relief device, sampling connection system, valve, and connector used in remediation material service at a facility.

External floating roof means a pontoon-type or double-deck type cover that rests on the liquid surface in a tank with no fixed roof.

Facility means all contiguous or adjoining property that is under common control including properties that are separated only by a road or other public right-of-way. Common control includes properties that are owned, leased, or operated by the same entity, parent entity, subsidiary, or any combination thereof. A unit or group of units within a contiguous property that are not under common control (*e.g.*, a wastewater treatment unit located at the facility but is owned by a different company) is a different facility.

Fixed roof means a cover that is mounted on a unit in a stationary position and does not move with fluctuations in the level of the liquid managed in the unit.

Flame zone means the portion of the combustion chamber in a boiler or process heater occupied by the flame envelope.

Floating roof means a cover consisting of a double deck, pontoon single deck, or internal floating cover which rests upon and is supported by the liquid being contained, and is equipped with a continuous seal.

Flow indicator means a device that indicates whether gas is flowing, or whether the valve position would allow gas to flow in a bypass line.

Force majeure event means a release of HAP directly to the atmosphere from a pressure relief device that is demonstrated to the satisfaction of the Administrator to result from an event beyond the owner or operator's control, such as natural disasters; acts of war or terrorism; loss of a utility external

to the Site Remediation unit (*e.g.*, external power curtailment), excluding power curtailment due to an interruptible service agreement; and fire or explosion originating at a near or adjoining facility outside of the Site Remediation affected source that impacts the Site Remediation affected source's ability to operate.

Hard-piping means pipe or tubing that is manufactured and properly installed according to relevant standards and good engineering practices.

Individual drain system means a stationary system used to convey wastewater streams or residuals to a remediation material management unit or to discharge or disposal. The term includes hard-piping, all drains and junction boxes, together with their associated sewer lines and other junction boxes (*e.g.*, manholes, sumps, and lift stations) conveying wastewater streams or residuals. For the purpose of this subpart, an individual drain system is not a drain and collection system that is designed and operated for the sole purpose of collecting rainfall runoff (*e.g.*, stormwater sewer system) and is segregated from all other individual drain systems.

Internal floating roof means a cover that rests or floats on the liquid surface (but not necessarily in complete contact with it inside a tank that has a fixed roof).

Maximum HAP vapor pressure means the sum of the individual HAP equilibrium partial pressure exerted by remediation material at the temperature equal to either: the monthly average temperature as reported by the National Weather Service when the remediation material is stored or treated at ambient temperature; or the highest calendar-month average temperature of the remediation material when the remediation material is stored at temperatures above the ambient temperature or when the remediation material is stored or treated at temperatures below the ambient temperature. For the purpose of this subpart, maximum HAP vapor pressure is determined using the procedures specified in § 63.7944.

No detectable organic emissions means no escape of organics to the atmosphere as determined using the procedure specified in § 63.694(k).

Oil-water separator means a separator as defined for this subpart that is used to separate oil from water.

Operating parameter value means a minimum or maximum value established for a control device or treatment process parameter which, if achieved by itself or in combination with one or more other operating parameter values, determines that an owner or operator has complied with an applicable emissions limitation or standard.

Organic-water separator means a separator as defined for this subpart that is used to separate organics from water.

Pressure release actuation event means the emission of materials resulting from the system pressure being greater than the set pressure of the pressure relief device. This release can be one release or a series of releases over a short time period.

Pressure relief device or valve means a safety device used to prevent operating pressures from exceeding the maximum allowable working pressure of the process equipment. A common pressure relief device is a spring-loaded pressure relief valve. Devices that are actuated either by a pressure of less than or equal to 2.5 pounds per square inch gauge or by a vacuum are not pressure relief devices.

Process heater means an enclosed combustion device that transfers heat released by burning fuel directly to process streams or to heat transfer liquids other than water.

Process vent means any open-ended pipe, stack, duct, or other opening intended to allow the passage of gases, vapors, or fumes to the atmosphere and this passage is caused by mechanical means (such as compressors, vacuum-producing systems or fans) or by process-related means (such as volatilization produced by heating). For the purposes of this subpart, a process vent is neither a pressure relief device (as defined in this section) nor a stack, duct or other opening used to exhaust combustion products from a boiler, furnace, heater, incinerator, or other combustion device.

Radioactive mixed waste means a material that contains both hazardous

waste subject to RCRA and source, special nuclear, or by-product material subject to the Atomic Energy Act of 1954.

Remediation material means a material that contains one or more of the HAP listed in Table 1 of this subpart, and this material is one of the following:

(1) A material found in naturally occurring media such as soil, groundwater, surface water, sediments, or a mixture of such materials with liquids, sludges, or solids which is inseparable by simple mechanical removal processes and is made up primarily of media. This material does not include debris as defined in 40 CFR 268.2.

(2) A material found in intact or substantially intact containers, tanks, storage piles, or other storage units that requires clean up because this material poses a reasonable potential threat to contaminating media. Examples of these materials include, but are not limited to, solvents, oils, paints, and other volatile or semi-volatile organic liquids found in buried drums, cans, or other containers; gasoline, fuel oil, or other fuels in leaking underground storage tanks; and solid materials containing volatile or semi-volatile organics in unused or abandoned piles. Remediation material is not a waste or residue generated by routine equipment maintenance activities performed at a facility such as, but not limited to, tank bottoms and sludges removed during tank cleanouts; sludges and sediments removed from active wastewater treatment tanks, surface impoundments, or lagoons; spent catalyst removed from process equipment; residues removed from air pollution control equipment; and debris removed during heat exchanger and pipeline cleanouts.

Remediation material management unit means a tank, container, surface impoundment, oil-water separator, organic-water separator, or transfer system used to remove, destroy, degrade, transform, immobilize, or otherwise manage remediation material.

Remediation material service means any time when a pump, compressor, agitator, pressure relief device, sampling connection system, open-ended valve or line, valve, connector, or instrumentation system contains or contacts remediation material.

Responsible official means responsible official as defined in 40 CFR 70.2.

Separator means a remediation material management unit, generally a tank, used to separate oil or organics from water. A separator consists of not only the separation unit but also the forebay and other separator basins, skimmers, weirs, grit chambers, sludge hoppers, and bar screens that are located directly after the individual drain system and prior to any additional treatment units such as an air flotation unit clarifier or biological treatment unit. Examples of a separator include, but are not limited to, an API separator, parallel-plate interceptor, and corrugated-plate interceptor with the associated ancillary equipment.

Site remediation means one or more activities or processes used to remove, destroy, degrade, transform, immobilize, or otherwise manage remediation material. The monitoring or measuring of contamination levels in environmental media using wells or by sampling is not considered to be a site remediation.

Sludge means sludge as defined in § 260.10 of this chapter.

Soil means unconsolidated earth material composing the superficial geologic strata (material overlying bedrock), consisting of clay, silt, sand, or gravel size particles (sizes as classified by the U.S. Soil Conservation Service), or a mixture of such materials with liquids, sludges, or solids which is inseparable by simple mechanical removal processes and is made up primarily of soil.

Stabilization process means any physical or chemical process used to either reduce the mobility of contaminants in media or eliminate free liquids as determined by Test Method 9095—Paint Filter Liquids Test in ''Test Methods for Evaluating Solid Waste, Physical/Chemical Methods,'' EPA Publication No. SW–846, Third Edition, September 1986, as amended by Update I, November 15, 1992. (As an alternative, you may use any more recent, updated version of Method 9095 approved by the EPA). A stabilization process includes mixing remediation material with

binders or other materials, and curing the resulting remediation material and binder mixture. Other synonymous terms used to refer to this process are fixation or solidification. A stabilization process does not include the adding of absorbent materials to the surface of remediation material, without mixing, agitation, or subsequent curing, to absorb free liquid.

Surface impoundment means a unit that is a natural topographical depression, man-made excavation, or diked area formed primarily of earthen materials (although it may be lined with man-made materials), which is designed to hold an accumulation of liquids. Examples of surface impoundments include holding, storage, settling, and aeration pits, ponds, and lagoons.

Tank means a stationary unit that is constructed primarily of nonearthen materials (such as wood, concrete, steel, fiberglass, or plastic) which provide structural support and is designed to hold an accumulation of liquids or other materials.

Temperature monitoring device means a piece of equipment used to monitor temperature and having an accuracy of ±1 percent of the temperature being monitored expressed in degrees Celsius (°C) or ±1.2 degrees °C, whichever value is greater.

Transfer system means a stationary system for which the predominant function is to convey liquids or solid materials from one point to another point within a waste management operation or recovery operation. For the purpose of this subpart, the conveyance of material using a container (as defined for this subpart) or a self-propelled vehicle (*e.g.*, a front-end loader) is not a transfer system. Examples of a transfer system include but are not limited to a pipeline, an individual drain system, a gravity-operated conveyor (such as a chute), and a mechanically-powered conveyor (such as a belt or screw conveyor).

Treatment process means a process in which remediation material is physically, chemically, thermally, or biologically treated to destroy, degrade, or remove hazardous air pollutants contained in the material. A treatment process can be composed of a single unit (*e.g.*, a steam stripper) or a series of units (*e.g.*, a wastewater treatment system). A treatment process can be used to treat one or more remediation material streams at the same time.

Volatile organic hazardous air pollutant (VOHAP) concentration means the fraction by weight of the HAP listed in Table 1 of this subpart that are contained in the remediation material as measured using Method 305, 40 CFR part 63, appendix A and expressed in terms of parts per million (ppm). As an alternative to using Method 305, 40 CFR part 63, appendix A, you may determine the HAP concentration of the remediation material using any one of the other test methods specified in §63.694(b)(2)(ii). When a test method specified in §63.694(b)(2)(ii) other than Method 305 in 40 CFR part 63, appendix A is used to determine the speciated HAP concentration of the contaminated material, the individual compound concentration may be adjusted by the corresponding f_{m305} listed in Table 1 of this subpart to determine a VOHAP concentration.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the CAA.

[68 FR 58190, Oct. 8, 2003, as amended at 71 FR 69019, Nov. 29, 2006; 85 FR 41711, July 10, 2020]

TABLE 1 TO SUBPART GGGGG OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS

CAS No.[a]	Compound name	$F_{m\ 305}$
75070	Acetaldehyde	1.000
75058	Acetonitrile	0.989
98862	Acetophenone	0.314
98862	Acetophenone	0.314
107028	Acrolein	1.000
107131	Acrylonitrile	0.999
107051	Allyl chloride	1.000
71432	Benzene (includes benzene in gasoline)	1.000

CAS No.[a]	Compound name	$F_{m\ 305}$
98077	Benzotrichloride (isomers and mixture)	0.958
100447	Benzyl chloride	1.000
92524	Biphenyl	0.864
542881	Bis(chloromethyl)ether[b]	0.999
75252	Bromoform	0.998
106990	1,3-Butadiene	1.000
75150	Carbon disulfide	1.000
56235	Carbon Tetrachloride	1.000
43581	Carbonyl sulfide	1.000
133904	Chloramben	0.633
108907	Chlorobenzene	1.000
67663	Chloroform	1.000
107302	Chloromethyl methyl ether[b]	1.000
126998	Chloroprene	1.000
98828	Cumene	1.000
94757	2,4-D, salts and esters	0.167
334883	Diazomethane[c]	0.999
132649	Dibenzofurans	0.967
96128	B1,2-Dibromo-3-chloropropane	1.000
106467	1,4-Dichlorobenzene(p)	1.000
107062	Dichloroethane (Ethylene dichloride)	1.000
111444	Dichloroethyl ether (Bis(2-chloroethylether)	0.757
542756	1,3-Dichloropropene	1.000
64675	Diethyl sulfate	0.0025
79447	Dimethyl carbamoyl chloride[c]	0.150
77781	Dimethyl sulfate	0.086
121697	N,N-Dimethylaniline	0.0008
51285	2,4-Dinitrophenol	0.0077
121142	2,4-Dinitrotoluene	0.0848
123911	1,4-Dioxane (1,4-Diethyleneoxide)	0.869
106898	Epichlorohydrin (1-Chloro-2,3-epoxypropane)	0.939
106887	1,2-Epoxybutane	1.000
140885	Ethyl acrylate	1.000
100414	Ethyl benzene	1.000
75003	Ethyl chloride (Chloroethane)	1.000
106934	Ethylene dibromide (Dibromoethane)	0.999
107062	Ethylene dichloride (1,2-Dichloroethane)	1.000
151564	Ethylene imine (Aziridine)	0.867
75218	Ethylene oxide	1.000
75343	Ethylidene dichloride (1,1-Dichloroethane)	1.000
	Glycol ethers[d] that have a Henry's Law Constant value equal to or greater than 0.01 Y/X(1.8×10^{-6} atm/gm-mole/m^3) at 25 °C.	[e]
118741	Hexachlorobenzene	0.97
87683	Hexachlorobutadiene	0.88
67721	Hexachloroethane	0.499
110543	Hexane	1.000
78591	Isophorone	0.506
58899	Lindane (all isomers)	1.000
67561	Methanol	0.855
74839	Methyl bromide (Bromomethane)	1.000
74873	Methyl chloride (Choromethane)	1.000
71556	Methyl chloroform (1,1,1-Trichloroethane)	1.000
74884	Methyl iodide (Iodomethane)	1.000
108101	Methyl isobutyl ketone (Hexone)	0.979
624839	Methyl isocyanate	1.000
80626	Methyl methacrylate	0.999
1634044	Methyl tert butyl ether	1.000
75092	Methylene chloride (Dichloromethane)	1.000
91203	Naphthalene	0.994
98953	Nitrobenzene	0.394
79469	2-Nitropropane	0.989
82688	Pentachloronitrobenzene (Quintobenzene)	0.839
87865	Pentachlorophenol	0.0898
75445	Phosgene[c]	1.000
123386	Propionaldehyde	0.999
78875	Propylene dichloride (1,2-Dichloropropane)	1.000
75569	Propylene oxide	1.000
75558	1,2-Propylenimine (2-Methyl aziridine)	0.945
100425	Styrene	1.000
96093	Styrene oxide	0.830
79345	1,1,2,2-Tetrachloroethane	0.999
127184	Tetrachloroethylene (Perchloroethylene)	1.000
108883	Toluene	1.000

CAS No.[a]	Compound name	$F_{m\ 305}$
95534	o-Toluidine	0.152
120821	1,2,4-Trichlorobenzene	1.000
71556	1,1,1-Trichloroethane (Methyl chlorform)	1.000
79005	1,1,2-Trichloroethane (Vinyltrichloride)	1.000
79016	Trichloroethylene	1.000
95954	2,4,5-Trichlorophenol	0.0108
88062	2,4,6-Trichlorophenol	0.0132
121448	Triethylamine	1.000
540841	2,2,4-Trimethylpentane	1.000
108054	Vinyl acetate	1.000
593602	Vinyl bromide	1.000
75014	Vinyl chloride	1.000
75354	Vinylidene chloride (1,1-Dichloroethylene)	1.000
1330207	Xylenes (isomers and mixture)	1.000
95476	o-Xylenes	1.000
108383	m-Xylenes	1.000
106423	p-Xylenes	1.000

Notes:
$F_{m\ 305}$ Fraction measure factor in Method 305, 40 CFR 305 part 63, appendix A.
[a] CAS numbers refer to the Chemical Abstracts Services registry number assigned to specific compounds, isomers, or mixtures of compounds.
[b] Denotes a HAP that hydrolyzes quickly in water, but the hydrolysis products are also HAP chemicals.
[c] Denotes a HAP that may react violently with water.
[d] Denotes a HAP that hydrolyzes slowly in water.
[e] The $F_{m\ 305}$ factors for some of the more common glycol 305 ethers can be obtained by contacting the Waste and Chemical Processes Group, Office of Air Quality Planning and Standards, Research Triangle Park, NC 27711.

[71 FR 69020, Nov. 29, 2006]

TABLE 2 TO SUBPART GGGGG OF PART 63—CONTROL LEVELS AS REQUIRED BY §63.7895(a) FOR TANKS MANAGING REMEDIATION MATERIAL WITH A MAXIMUM HAP VAPOR PRESSURE LESS THAN 76.6 kPa

If your tank design capacity is . . .	And the maximum HAP vapor pressure of the remediation material placed in your tank is . . .	Then your tank must use . . .
1. Less than 38 m^3	Less than 76.6 kPa	Tank Level 1 controls under §63.7895(b).
2. At least 38 m^3 but less than 151 m^3	Less than 13.1 kPa	Tank Level 1 controls under §63.7895(b).
3. 151 m^3 or greater	Less than 0.7 kPa	Tank Level 1 controls under §63.7895(b).
4. at least 38 m^3 but less than 151 m^3	13.1 kPa or greater	Tank Level 2 controls under §63.7895(c).
5. 151 m^3 or greater	0.7 kPa or greater	Tank Level 2 controls under §63.7895(c)

TABLE 3 TO SUBPART GGGGG OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART GGGGG

As stated in §63.7940, you must comply with the applicable General Provisions requirements according to the following table:

Citation	Subject	Brief description	Applies to subpart GGGGG
§63.1	Applicability	Initial Applicability Determination; Applicability After Standard Established; Permit Requirements; Extensions, Notifications.	Yes.
§63.2	Definitions	Definitions for part 63 standards	Yes.
§63.3	Units and Abbreviations.	Units and abbreviations for part 63 standards.	Yes.
§63.4	Prohibited Activities.	Prohibited Activities; Compliance date; Circumvention, Severability.	Yes.
§63.5	Construction/Reconstruction.	Applicability; applications; approvals	Yes.

Citation	Subject	Brief description	Applies to subpart GGGGG
§ 63.6(a)	Applicability	General Provisions (GP) apply unless compliance extension GP apply to area sources that become major.	Yes.
§ 63.6(b)(1)–(4)	Compliance Dates for New and Reconstructed sources.	Standards apply at effective date; 3 years after effective date; upon startup; 10 years after construction or reconstruction commences for 112(f).	Yes.
§ 63.6(b)(5)	Notification	Must notify if commenced construction or reconstruction after proposal.	Yes.
§ 63.6(b)(6)	[Reserved].		
§ 63.6(b)(7)	Compliance Dates for New and Reconstructed Area Sources That Become Major.	Area sources that become major must comply with major source standards immediately upon becoming major, regardless of whether required to comply when they were an area source.	Yes.
§ 63.6(c)(1)–(2)	Compliance Dates for Existing Sources.	Comply according to date in subpart, which must be no later than 3 years after effective date. For 112(f) standards, comply within 90 days of effective date unless compliance extension.	Yes.
§ 63.6(c)(3)–(4)	[Reserved].		
§ 63.6(c)(5)	Compliance Dates for Existing Area Sources That Become Major.	Area sources that become major must comply with major source standards by date indicated in subpart or by equivalent time period (for example, 3 years).	Yes.
§ 63.6(d)	[Reserved].		
§ 63.6(e)(1)–(2)	Operation & Maintenance.		No, see § 63.7935(b).
§ 63.6(e)(3)	Startup, Shutdown, and Malfunction Plan (SSMP).		No, see § 63.7935(c).
§ 63.6(f)(1)	Compliance Except During SSM.		No, see § 63.7935(b).
§ 63.6(f)(2)–(3)	Methods for Determining Compliance.	Compliance based on performance test, operation and maintenance plans, records, inspection.	Yes.
§ 63.6(g)(1)–(3)	Alternative Standard.	Procedures for getting an alternative standard.	Yes.
§ 63.6(h)	Opacity/Visible Emissions (VE) Standards.	Requirements for opacity and visible emissions limits.	No. No opacity standards.
§ 63.6(i)(1)–(14)	Compliance Extension.	Procedures and criteria for Administrator to grant compliance extension.	Yes.
§ 63.6(j)	Presidential Compliance Exemption.	President may exempt source category from requirement to comply with final rule.	Yes.
§ 63.7(a)(1)–(2)	Performance Test Dates.	Dates for Conducting Initial Performance Testing and Other Compliance Demonstrations. Must conduct 180 days after first subject to final rule.	Yes.
§ 63.7(a)(3)	CAA Section 114 Authority.	Administrator may require a performance test under CAA section 114 at any time.	Yes.
§ 63.7(b)(1)	Notification of Performance Test.	Must notify Administrator 60 days before the test.	Yes.

Citation	Subject	Brief description	Applies to subpart GGGGG
§ 63.7(b)(2)	Notification of Rescheduling.	If rescheduling a performance test is necessary, must notify Administrator 5 days before scheduled date of rescheduled date.	Yes.
§ 63.7(c)	Quality Assurance/ Test Plan.	Requirement to submit site-specific test plan 60 days before the test or on date Administrator agrees with: Test plan approval procedures; performance audit requirements; internal and external QA procedures for testing.	Yes.
§ 63.7(d)	Testing Facilities	Requirements for testing facilities	Yes.
§ 63.7(e)(1)	Conditions for Conducting Performance Tests.	Performance tests must be conducted under representative conditions. Cannot conduct performance tests during SSM. Not a violation to exceed standard during SSM.	No, see § 63.7941(b)(2).
§ 63.7(e)(2)	Conditions for Conducting Performance Tests.	Must conduct according to rule and EPA test methods unless Administrator approves alternative.	Yes.
§ 63.7(e)(3)	Test Run Duration	Must have three test runs of at least one hour each. Compliance is based on arithmetic mean of three runs. Conditions when data from an additional test run can be used.	Yes.
§ 63.7(f)	Alternative Test Method.	Procedures by which Administrator can grant approval to use an alternative test method.	Yes.
§ 63.7(g)	Performance Test Data Analysis.	Must include raw data in performance test report. Must submit performance test data 60 days after end of test with the Notification of Compliance Status. Keep data for 5 years.	Yes.
§ 63.7(h)	Waiver of Tests	Procedures for Administrator to waive performance test.	Yes.
§ 63.8(a)(1)	Applicability of Monitoring Requirements.	Subject to all monitoring requirements in standard.	Yes.
§ 63.8(a)(2)	Performance Specifications.	Performance Specifications in appendix B of part 60 apply.	Yes.
§ 63.8(a)(3)	[Reserved].		
§ 63.8(a)(4)	Monitoring with Flares.	Unless your rule says otherwise, the requirements for flares in 63.11 apply.	Yes.
§ 63.8(b)(1)	Monitoring	Must conduct monitoring according to standard unless Administrator approves alternative.	Yes.
§ 63.8(b)(2)–(3)	Multiple Effluents and Multiple Monitoring Systems.	Specific requirements for installing monitoring systems. Must install on each effluent before it is combined and before it is released to the atmosphere unless Administrator approves otherwise. If more than one monitoring system on an emissions point, must report all monitoring system results, unless one monitoring system is a backup.	Yes.
§ 63.8(c)(1)	Monitoring System Operation and Maintenance.	Maintain monitoring system in a manner consistent with good air pollution control practices.	Yes.
§ 63.8(c)(1)(i)	Monitoring System Operation.	Operate and maintain system as specified in § 63.6(e)(1).	No, see § 63.7935(b).

Citation	Subject	Brief description	Applies to subpart GGGGG
§ 63.8(c)(1)(ii)	Monitoring System Repair.	Keep part for routine repairs available	Yes.
§ 63.8(c)(1)(iii)	Monitoring System SSM Plan.	Develop an SSM Plan for the monitoring system.	No, see § 63.7935(h)(1).
§ 63.8(c)(2)–(3)	Monitoring System Installation.	Must install to get representative emissions and parameter measurements. Must verify operational status before or at performance test.	Yes.
§ 63.8(c)(4)	Continuous Monitoring System (CMS) Requirements.	CMS must be operating except during breakdown, out-of-control, repair, maintenance, and high-level calibration drifts.	No.
§ 63.8(c)(4)(i)–(ii)	Continuous Monitoring System (CMS) Requirements.	COMS must have a minimum of one cycle of sampling and analysis for each successive 10-second period and one cycle of data recording for each successive 6-minute period. CEMS must have a minimum of one cycle of operation for each successive 15-minute period.	Yes. However, COMS are not applicable. Requirements for CPMS are listed in §§ 63.7900 and 63.7913.
§ 63.8(c)(5)	COMS Minimum Procedures.	COMS minimum procedures	No.
§ 63.8(c)(6)	CMS Requirements.	Zero and High level calibration check requirements.	Yes. However requirements for CPMS are addressed in § 63.7927.
§ 63.8(c)(7)–(8)	CMS Requirements.	Out-of-control periods, including reporting.	Yes.
§ 63.8(d)	CMS Quality Control.	Requirements for CMS quality control, including calibration, etc. Must keep quality control plan on record for 5 years. Keep old versions for 5 years after revisions.	Yes.
§ 63.8(e)	CMS Performance Evaluation.	Notification, performance evaluation test plan, reports.	Yes.
§ 63.8(f)(1)–(5)	Alternative Monitoring Method.	Procedures for Administrator to approve alternative monitoring.	Yes.
§ 63.8(f)(6)	Alternative to Relative Accuracy Test.	Procedures for Administrator to approve alternative relative accuracy tests for CEMS.	No.
§ 63.8(g)(1)–(4)	Data Reduction	COMS 6-minute averages calculated over at least 36 evenly spaced data points. CEMS 1-hour averages computed over at least four equally spaced data points.	Yes. However, COMS are not applicable. Requirements for CPMS are addressed in §§ 63.7900 and 63.7913.
§ 63.8(g)(5)	Data Reduction	Data that cannot be used in computing averages for CEMS and COMS.	No.
§ 63.9(a)	Notification Requirements.	Applicability and State Delegation	Yes.
§ 63.9(b)(1)–(5)	Initial Notifications.	Submit notification 120 days after effective date. Notification of intent to construct/reconstruct; Notification of commencement of construct/reconstruct; Notification of startup. Contents of each.	Yes.
§ 63.9(c)	Request for Compliance Extension.	Can request if cannot comply by date or if installed BACT/LAER.	Yes.

Citation	Subject	Brief description	Applies to subpart GGGGG
§ 63.9(d)	Notification of Special Compliance Requirements for New Source.	For sources that commence construction between proposal and promulgation and want to comply 3 years after effective date.	Yes.
§ 63.9(e)	Notification of Performance Test.	Notify Administrator 60 days prior	Yes.
§ 63.9(f)	Notification of VE/Opacity Test.	Notify Administrator 30 days prior	No.
§ 63.9(g)	Additional Notifications When Using CMS.	Notification of performance evaluation. Notification using COMS data. Notification that exceeded criterion for relative accuracy.	Yes. However, there are no opacity standards.
§ 63.9(h)(1)–(6)	Notification of Compliance Status.	Contents. Due 60 days after end of performance test or other initial compliance demonstration, except for opacity/VE, which are due 30 days after. When to submit to Federal vs. State authority.	Yes.
§ 63.9(i)	Adjustment of Submittal Deadlines.	Procedures for Administrator to approve change in when notifications must be submitted.	Yes.
§ 63.9(j)	Change in Previous Information.	Must submit within 15 days after the change.	Yes.
§ 63.9(k)	Electronic reporting procedures.	Electronic reporting procedures for notifications per § 63.9(j).	Yes.
§ 63.10(a)	Recordkeeping/Reporting.	Applies to all, unless compliance extension. When to submit to Federal vs. State authority. Procedures for owners of more than 1 source.	Yes.
§ 63.10(b)(1)	Recordkeeping/Reporting.	General Requirements. Keep all records readily available. Keep for 5 years.	Yes.
§ 63.10(b)(2)(i) and (ii)	Records related to SSM.	Exceedance of emission limit during startup, shutdown or malfunction.	No, for new sources for which initial startup is after September 3, 2019. Yes, for all other affected sources before January 7, 2021, and No thereafter.
§ 63.10(b)(2)(iii)	Maintenance Records.	Maintenance on air pollution control equipment..	Yes.
§ 63.10(b)(2)(iv) and (v)	Records related to SSM.	Actions during SSM.	No, for new sources for which initial startup is after September 3, 2019. Yes, for all other affected sources before January 7, 2021, and No thereafter.
§ 63.10(b)(2)(vi) and (x-xi)	CMS Records	Malfunctions, inoperative, out-of-control. Calibration checks. Adjustments, maintenance.	Yes.

Citation	Subject	Brief description	Applies to subpart GGGGG
§ 63.10(b)(2)(vii)–(ix)	Records	Measurements to demonstrate compliance with emissions limitations. Performance test, performance evaluation, and visible emissions observation results. Measurements to determine conditions of performance tests and performance evaluations.	Yes.
§ 63.10(b)(2)(xii)	Records	Records when under waiver	Yes.
§ 63.10(b)(2)(xiii)	Records	Records when using alternative to relative accuracy test.	No.
§ 63.10(b)(2)(xiv)	Records	All documentation supporting Initial Notification and Notification of Compliance Status.	Yes.
§ 63.10(b)(3)	Records	Applicability Determinations	Yes.
§ 63.10(c)	Records	Additional Records for CMS	No.
§ 63.10(d)(1)	General Reporting Requirements.	Requirement to report	Yes.
§ 63.10(d)(2)	Report of Performance Test Results.	When to submit to Federal or State authority.	Yes.
§ 63.10(d)(3)	Reporting Opacity or VE Observations.	What to report and when	No.
§ 63.10(d)(4)	Progress Reports	Must submit progress reports on schedule if under compliance extension.	Yes.
§ 63.10(d)(5)	Startup, Shutdown, and Malfunction Reports.	Contents and submission	No, see § 63.7951(b)(4).
§ 63.10(e)(1)–(2)	Additional CMS Reports.	Must report results for each CEM on a unit Written copy of performance evaluation Three copies of COMS performance evaluation.	Yes. However, COMS are not applicable.
§ 63.10(e)(3)	Reports	Excess Emissions Reports	No.
§ 63.10(e)(3)(i–iii)	Reports	Schedule for reporting excess emissions and parameter monitor exceedance (now defined as deviations).	No.
§ 63.10(e)(3)(iv–v)	Excess Emissions Reports.	Requirement to revert to quarterly submission if there is an excess emissions and parameter monitor exceedance (now defined as deviations). Provision to request semiannual reporting after compliance for one year. Submit report by 30th day following end of quarter or calendar half. If there has not been an exceedance or excess emissions (now defined as deviations), report contents is a statement that there have been no deviations.	No.
§ 63.10(e)(3)(iv–v)	Excess Emissions Reports.	Must submit report containing all of the information in §§ 63.10(c)(5–13) and 63.8(c)(7–8).	No.
§ 63.10(e)(3)(vi–viii)	Excess Emissions Report and Summary Report.	Requirements for reporting excess emissions for CMSs (now called deviations). Requires all of the information in §§ 63.10(c)(5–13) and 63.8(c)(7–8).	No.
§ 63.10(e)(4)	Reporting COMS data.	Must submit COMS data with performance test data.	No.

Citation	Subject	Brief description	Applies to subpart GGGGG
§ 63.10(f)	Waiver for Recordkeeping/Reporting.	Procedures for Administrator to waive	Yes.
§ 63.11	Control and work practice requirements.	Requirements for flares and alternative work practice for equipment leaks.	Yes.
§ 63.12	Delegation	State authority to enforce standards ..	Yes.
§ 63.13	Addresses	Addresses where reports, notifications, and requests are sent.	Yes, only applicable to those reports not required to be submitted electronically.
§ 63.14	Incorporation by Reference.	Test methods incorporated by reference.	Yes.
§ 63.15	Availability of Information.	Public and confidential information	Yes.

[85 FR 41712, July 10, 2020, as amended at 85 FR 73913, Nov. 19, 2020]

Subpart HHHHH—National Emission Standards for Hazardous Air Pollutants: Miscellaneous Coating Manufacturing

SOURCE: 68 FR 69185, Dec. 11, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.7980 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for miscellaneous coating manufacturing. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limits, operating limits, and work practice standards.

§ 63.7985 Am I subject to the requirements in this subpart?

(a) You are subject to the requirements in this subpart if you own or operate miscellaneous coating manufacturing operations, as defined in paragraph (b) of this section, that meet the conditions specified in paragraphs (a)(1) through (4) of this section.

(1) Are located at or are part of a major source of hazardous air pollutants (HAP) emissions, as defined in section 112(a) of the Clean Air Act (CAA);

(2) Manufacture coatings as defined in § 63.8105;

(3) Process, use, or produce HAP; and

(4) Are not part of an affected source under another subpart of this part 63.

(b) Miscellaneous coating manufacturing operations include the facility-wide collection of equipment described in paragraphs (b)(1) through (4) of this section that is used to manufacture coatings as defined in § 63.8105. Miscellaneous coating manufacturing operations also include cleaning operations.

(1) Process vessels;

(2) Storage tanks for feedstocks and products;

(3) Components such as pumps, compressors, agitators, pressure relief devices, sampling connection systems, open-ended valves or lines, valves, connectors, and instrumentation systems; and

(4) Wastewater tanks and transfer racks.

(c) If the predominant use of a transfer rack loading arm or storage tank (including storage tanks in series) is associated with miscellaneous coating manufacturing, and the loading arm or storage tank is not part of an affected source under a subpart of this part 63, then you must assign the loading arm or storage tank to the miscellaneous coating manufacturing operations. If the predominant use cannot be determined, and the loading arm or storage

tank is not part of an affected source under a subpart of this part 63, then you must assign the loading arm or storage tank to the miscellaneous coating manufacturing operations. If the use varies from year to year, then you must base the determination on the utilization that occurred during the year preceding December 11, 2003 or, if the loading arm or storage tank was not in operation during that year, you must base the use on the expected use for the first 5-year period after startup. You must include the determination in the notification of compliance status report specified in § 63.8075(d). You must redetermine the predominant use at least once every 5 years after the compliance date.

(d) The requirements for miscellaneous coating manufacturing sources in this subpart do not apply to operations described in paragraphs (d)(1) through (5) of this section.

(1) Research and development facilities, as defined in section 112(c)(7) of the CAA;

(2) The affiliated operations located at an affected source under subparts GG (National Emission Standards for Aerospace Manufacturing and Rework Facilities), KK (National Emission Standards for the Printing and Publishing Industry), JJJJ (NESHAP: Paper and Other Web Coating), MMMM (National Emission Standards for Miscellaneous Metal Parts and Products Surface Coating Operations) and SSSS (NESHAP: Surface Coating of Metal Coil) of this part. Affiliated operations include, but are not limited to, mixing or dissolving of coating ingredients; coating mixing for viscosity adjustment, color tint or additive blending, or pH adjustment; cleaning of coating lines and coating line parts; handling and storage of coatings and solvent; and conveyance and treatment of wastewater;

(3) Ancillary equipment such as boilers and incinerators (only those not used to comply with the emission limits in Tables 1 through 5 to this subpart), chillers and refrigeration systems, and other equipment that is not directly involved in the manufacturing of a coating (*i.e.*, it operates as a closed system, and materials are not combined with materials used to manufacture the coating);

(4) Quality assurance/quality control laboratories; or

(5) Modifying a purchased coating in preparation for application at the purchasing facility.

[68 FR 69185, Dec. 11, 2003, as amended at 71 FR 58503, Oct. 4, 2006; 85 FR 49740, Aug. 14, 2020]

§ 63.7990 What parts of my plant does this subpart cover?

(a) This subpart applies to each miscellaneous coating manufacturing affected source as defined in paragraph (b) of this section.

(b) The miscellaneous coating manufacturing affected source is the miscellaneous coating manufacturing operations as defined in § 63.7985(b).

(c) An affected source is a new affected source if you commenced construction or reconstruction after April 4, 2002, and you met the applicability criteria at the time you commenced construction or reconstruction.

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49741, Aug. 14, 2020]

COMPLIANCE DATES

§ 63.7995 When do I have to comply with this subpart?

Except as specified in § 63.8090, you must comply with this subpart according to the requirements of this section.

(a) Except as specified in paragraphs (e) and (f) of this section, if you have a new affected source, you must comply with this subpart according to the requirements in paragraphs (a)(1) and (2) of this section.

(1) If you start up your new affected source before December 11, 2003, then you must comply with the requirements for new sources in this subpart no later than December 11, 2003.

(2) If you start up your new affected source after December 11, 2003, then you must comply with the requirements for new sources in this subpart upon startup of your affected source.

(b) Except as specified in paragraphs (e) and (f) of this section, if you have an existing affected source on December 11, 2003, then you must comply with the requirements for existing sources

in this subpart no later than December 11, 2006.

(c) [Reserved]

(d) You must meet the notification requirements in §63.8070 according to the schedule in §63.8070 and in 40 CFR part 63, subpart A. Some of the notifications must be submitted before you are required to comply with the emission limits, operating limits, and work practice standards in this subpart.

(e) All affected sources that commenced construction or reconstruction on or after September 4, 2019, must be in compliance with the requirements listed in paragraphs (e)(1) through (5) of this section upon initial startup or no later than August 14, 2020, whichever is later. All affected sources that commenced construction or reconstruction before September 4, 2019, must be in compliance with the requirements listed in paragraphs (e)(1) through (5) of this section no later than August 14, 2023.

(1) The general requirements specified in §§63.8000(a)(2), (b)(2), (d)(8), and (f) and 63.8005(d)(5) and (h).

(2) The reporting requirements specified in §63.8075(e)(5), (e)(6)(ii)(B) and (D), and (e)(6)(iii)(C) and (E).

(3) The recordkeeping requirements specified in §63.8080(c), (e), (f), (h), and (i).

(4) The definitions specified in §63.8105.

(5) The general provisions as specified in Table 10 to this subpart.

(f) All affected sources that commenced construction or reconstruction on or before June 7, 2022, must be in compliance with the requirements listed in paragraphs (f)(1) through (4) of this section upon initial startup or February 22, 2024, whichever is later. All affected sources that commenced construction or reconstruction after June 7, 2022, must be in compliance with the requirements listed in paragraphs (f)(1) through (4) of this section upon initial startup, or February 22, 2023, whichever is later.

(1) The general requirements specified in §63.8005(a)(1)(iii) and (i).

(2) The reporting requirements specified in §63.8075.

(3) The recordkeeping requirements specified in §63.8080(i) and (g).

(4) The general provisions as specified in table 10 to this subpart.

[68 FR 69185, Dec. 11, 2003; 68 FR 75033, Dec. 29, 2003, as amended at 70 FR 25681, May 13, 2005; 71 FR 58503, Oct. 4, 2006; 85 FR 49741, Aug. 14, 2020; 88 FR 10849, Feb. 22, 2023]

EMISSION LIMITS, WORK PRACTICE STANDARDS, AND COMPLIANCE REQUIREMENTS

§63.8000 What are my general requirements for complying with this subpart?

(a) *Applicability*. You must comply with paragraphs (a)(1) and (2) of this section.

(1) Except as specified in paragraph (a)(2) of this section, you must be in compliance with the emission limits and work practice standards in Tables 1 through 5 to this subpart at all times, except during periods of startup, shutdown, and malfunction. You must meet the requirements specified in paragraphs (b) and (c) of this section. You must meet the requirements specified in §§63.8005 through 63.8030 (or the alternative means of compliance in §63.8050), except as specified in paragraph (d) of this section. You must meet the notification, reporting, and recordkeeping requirements specified in §§63.8070, 63.8075, and 63.8080.

(2) Beginning on the compliance dates specified in §63.7995(e), paragraph (a)(1) of this section no longer applies. Instead, beginning no later than the compliance dates specified in §63.7995(e), you must be in compliance with the emission limits and work practice standards in Tables 1 through 5 to this subpart at all times. You must meet the requirements specified in paragraphs (b) and (c) of this section. You must meet the requirements specified in §§63.8005 through 63.8030 (or the alternative means of compliance in §63.8050), except as specified in paragraph (d) of this section. You must meet the notification, reporting, and recordkeeping requirements specified in §§63.8070, 63.8075, and 63.8080.

(b) *General requirements.* (1) If an emission stream contains halogen atoms, and you use a combustion-based control device (excluding a flare) to meet an organic HAP emission limit,

you must determine whether the emission stream meets the definition of a halogenated stream by calculating the concentration of each organic compound that contains halogen atoms using the procedures specified in § 63.115(d)(2)(v), multiplying each concentration by the number of halogen atoms in the organic compound, and summing the resulting halogen atom concentrations for all of the organic compounds in the emission stream. Alternatively, you may elect to designate the emission stream as halogenated.

(2) You must comply with paragraphs (b)(2)(i) and (ii) of this section.

(i) Except as specified in paragraph (b)(2)(ii) of this section, opening of a safety device, as defined in § 63.8105, is allowed at any time conditions require it to avoid unsafe conditions.

(ii) Beginning on the compliance dates specified in § 63.7995(e), paragraph (b)(2)(i) of this section no longer applies. Instead, opening of a safety device, as defined in § 63.8105, is considered a deviation, as defined in § 63.8105, unless it is a bypass of a control for a process vessel and accounted for as specified in § 63.8005(h).

(c) *Compliance requirements for closed vent systems and control devices.* If you use a control device to comply with an emission limit in Table 1, 2, or 5 to this subpart, you must comply with the requirements in subpart SS of 40 CFR part 63 as specified in paragraphs (c)(1) through (3) of this section, except as specified in paragraph (d) of this section.

(1) If you reduce organic HAP emissions by venting emissions through a closed-vent system to any combination of control devices (except a flare), you must meet the requirements of § 63.982(c) and the requirements referenced therein.

(2) If you reduce organic HAP emissions by venting emissions through a closed-vent system to a flare, you must meet the requirements of § 63.982(b) and the requirements referenced therein. You may not use a flare to control halogenated vent streams or hydrogen halide and halogen HAP emissions.

(3) If you use a halogen reduction device to reduce hydrogen halide and halogen HAP emissions that are generated by combusting halogenated vent streams, you must meet the requirements of § 63.994, except as specified in paragraph (f) of this section, and the requirements referenced therein. If you use a halogen reduction device before a combustion device, you must determine the halogen atom emission rate prior to the combustion device according to the procedures in § 63.115(d)(2)(v).

(d) *Exceptions to the requirements specified in other subparts of this part 63*—(1) *Requirements for performance tests.* The requirements specified in paragraphs (d)(1)(i) through (vii) of this section apply instead of or in addition to the requirements for performance testing of control devices as specified in subpart SS of this part.

(i) Conduct gas molecular weight analysis using Method 3, 3A, or 3B in appendix A to 40 CFR part 60. As an alternative to EPA Method 3B for the manual procedures only and not the instrumental procedures, you may use ANSI/ASME PTC 19–10–1981 Part 10 (incorporated by reference, *see* § 63.14) as an acceptable alternative.

(ii) Measure moisture content of the stack gas using Method 4 in appendix A to 40 CFR part 60.

(iii) As an alternative to using Method 18, Method 25/25A, or Method 26/26A of 40 CFR part 60, appendix A, to comply with any of the emission limits specified in Tables 1 through 6 to this subpart you may use the alternatives specified in paragraph (d)(1)(iii)(A) or (B) of this section.

(A) As an alternative to using Method 18, Method 25/25A, or Method 26/26A of 40 CFR part 60, appendix A, you may use Method 320 of appendix A to this part. When using Method 320, you must follow the analyte spiking procedures of section 13 of Method 320, unless you demonstrate that the complete spiking procedure has been conducted at a similar source. As an alternative to Method 320 of appendix A to this part, you may use ASTM Method D6348–12e1 (incorporated by reference, *see* § 63.14), with the caveats that the test plan preparation and implementation in the Annexes to ASTM Method D6348–12e1, Sections A1 through A8 are mandatory; and in ASTM Method D6348–12e1 Annex A5 (Analyte Spiking Technique), the percent (%) R must be determined for each target analyte (Equation A5.5). In

order for the test data to be acceptable for a compound, %R must be 70% ≥ R ≤ 130%. If the %R value does not meet this criterion for a target compound, the test data is not acceptable for that compound and the test must be repeated for that analyte (*i.e.*, the sampling and/or analytical procedure should be adjusted before a retest). The %R value for each compound must be reported in the test report, and all field measurements must be corrected with the calculated %R value for that compound by using the following equation:

Reported Results = (Measured Concentration in the Stack × 100)/% R.

(B) As an alternative to using EPA Method 18, you may also use ASTM D6420–18 (incorporated by reference, *see* § 63.14), but only when the target compounds are all known and the target compounds are all listed in ASTM D6420–18 as measurable; ASTM D6420–18 should not be used for methane and ethane; and ASTM D6420–18 may not be used as a total VOC method.

(iv) Section 63.997(c)(1) does not apply. For the purposes of this subpart, results of all initial compliance demonstrations must be included in the notification of compliance status report, which is due 150 days after the compliance date, as specified in § 63.8075(d)(1).

(v) If you do not have a closed-vent system as defined in § 63.981, you must determine capture efficiency using Method 204 of appendix M to 40 CFR part 51 for all stationary process vessels subject to requirements of Table 1 to this subpart.

(vi) You must conduct periodic performance tests and establish the operating limits required by §§ 63.8005(e), 63.8010(b)(1), and 63.8050(d)(3) within 5 years following the previous performance test. You must conduct the initial or first periodic performance test before August 14, 2023, unless you are already required to complete periodic performance tests as a requirement of renewing your facility's operating permit under 40 CFR part 70 or 71, and have conducted a performance test on or after August 15, 2018. Thereafter you must conduct a performance test no later than 5 years following the previous performance test. Operating limits must be confirmed or reestablished during each performance test.

(vii) You must conduct periodic performance tests and establish the operating limits required by § 63.8005(i) within 5 years following the previous performance test. You must conduct the initial or first periodic performance test before February 22, 2024, unless you are already required to complete a periodic performance test as a requirement of renewing your facility's operating permit under 40 CFR part 70 or 71, and have conducted a performance test on or before February 22, 2024. Thereafter you must conduct a performance test no later than 5 years following the previous performance test. Operating limits must be confirmed or reestablished during each performance test.

(2) [Reserved]

(3) *Periodic verification.* For a control device with total inlet HAP emissions less than 1 ton per year (tpy), you must establish at least one operating limit for a parameter that you will measure and record at least once per averaging period (*i.e.*, daily or block) to verify that the control device is operating properly. You may elect to measure the same parameter that is required for control devices that control inlet HAP emissions equal to or greater than 1 tpy. If the parameter will not be measured continuously, you must request approval of your proposed procedure in the precompliance report. You must identify the operating limit or range and the measurement frequency, and you must provide rationale to support how these measurements demonstrate the control device is operating properly.

(4) *Continuous emissions monitoring systems.* Each continuous emissions monitoring system (CEMS) must be installed, operated, and maintained according to the requirements in § 63.8 and paragraphs (d)(4)(i) through (iv) of this section.

(i) Each CEMS must be installed, operated, and maintained according to the applicable Performance Specification of 40 CFR part 60, appendix B, and according to paragraph (d)(4)(ii) of this section, except as specified in paragraph (d)(4)(i)(A) of this section. For any CEMS meeting Performance Specification 8, you must also comply with

appendix F, procedure 1 of 40 CFR part 60.

(A) If you wish to use a CEMS other than a Fourier Transform Infrared Spectroscopy (FTIR) meeting the requirements of Performance Specification 15 in appendix B to 40 CFR part 60 or a hydrogen chloride (HCl) CEMS meeting the requirements of Performance Specification 18 in appendix B to 40 CFR part 60 and Quality Assurance Procedure 6 in appendix F to 40 CFR part 60 to measure hydrogen halide and halogen HAP before we promulgate a Performance Specification for such CEMS, you must prepare a monitoring plan and submit it for approval in accordance with the procedures specified in § 63.8.

(B) [Reserved]

(ii) You must determine the calibration gases and reporting units for TOC CEMS in accordance with paragraph (d)(4)(ii)(A), (B), or (C) of this section.

(A) For CEMS meeting Performance Specification 9 or 15 requirements, determine the target analyte(s) for calibration using either process knowledge of the control device inlet stream or the screening procedures of Method 18 on the control device inlet stream.

(B) For CEMS meeting Performance Specification 8 used to monitor performance of a combustion device, calibrate the instrument on the predominant organic HAP and report the results as carbon (C_1), and use Method 25A or any approved alternative as the reference method for the relative accuracy tests.

(C) For CEMS meeting Performance Specification 8 used to monitor performance of a noncombustion device, determine the predominant organic HAP using either process knowledge or the screening procedures of Method 18 in appendix A–6 to 40 CFR part 60 on the control device inlet stream, calibrate the monitor on the predominant organic HAP, and report the results as C_1. Use Method 18, ASTM D6420–18 (incorporated by reference, *see* § 63.14), or any approved alternative as the reference method for the relative accuracy tests, and report the results as C_1.

(iii) You must conduct a performance evaluation of each CEMS according to the requirements in 40 CFR 63.8 and according to the applicable Performance Specification of 40 CFR part 60, appendix B, except that the schedule in § 63.8(e)(4) does not apply, and the results of the performance evaluation must be included in the notification of compliance status report.

(iv) The CEMS data must be reduced to operating day or operating block averages computed using valid data, except monitoring data also are sufficient to constitute a valid hour of data if measured values are available for at least two of the 15-minute periods during an hour when calibration, quality assurance, or maintenance activities are being performed. An operating block is a period of time from the beginning to end of batch operations in the manufacturing of a coating. Operating block averages may be used only for process vessel data.

(5) *Continuous parameter monitoring.* The provisions in paragraphs (d)(5)(i) through (iii) of this section apply in addition to the requirements for continuous parameter monitoring system (CPMS) in subpart SS of 40 CFR part 63.

(i) You must record the results of each calibration check and all maintenance performed on the CPMS as specified in § 63.998(c)(1)(ii)(A).

(ii) When subpart SS of 40 CFR part 63 uses the term a range or operating range of a monitored parameter, it means an operating limit for a monitored parameter for the purposes of this subpart.

(iii) As an alternative to measuring pH as specified in § 63.994(c)(1)(i), you may elect to continuously monitor the caustic strength of the scrubber effluent.

(6) *Startup, shutdown, and malfunction.* Sections 63.998(b)(2)(iii) and (b)(6)(i)(A), which apply to the exclusion of monitoring data collected during periods of startup, shutdown, and malfunction (SSM) from daily averages, do not apply for the purposes of this subpart.

(7) *Reporting.* (i) When §§ 63.8005 through 63.8025 reference other subparts in this part 63 that use the term periodic report, it means compliance report for the purposes of this subpart.

(ii) When there are conflicts between this subpart and referenced subparts for the due dates of reports required by

this subpart, reports must be submitted according to the due dates presented in this subpart.

(iii) Excused excursions, as defined in subpart SS of 40 CFR part 63, are not allowed.

(8) *Quality control program.* Beginning no later than the compliance dates specified in § 63.7995(e), in lieu of the requirements specified in § 63.8(d)(3), you must keep the written quality control program procedures required by § 63.8(d)(2) on record for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan is revised, you shall keep previous (*i.e.*, superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action should be included in the plan required under § 63.8(d)(2).

(e) *General duty.* Beginning no later than August 14, 2023, at all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

(f) *Removal of startup, shutdown, and malfunction requirements.* Beginning on the compliance dates specified in § 63.7995(e), the referenced provisions specified in paragraphs (f)(1) through (22) of this section do not apply when demonstrating compliance with this subpart through referenced provisions of subparts SS, UU, and TT of this part.

(1) Section 63.983(a)(5).

(2) The phrase ''except during periods of start-up, shutdown and malfunction as specified in the referencing subpart'' in § 63.984(a).

(3) The phrase ''except during periods of start-up, shutdown and malfunction as specified in the referencing subpart'' in § 63.985(a).

(4) The phrase ''other than start-ups, shutdowns, or malfunctions'' in § 63.994(c)(1)(ii)(D).

(5) Section 63.996(c)(2)(ii).

(6) Section 63.997(e)(1)(i).

(7) The term ''breakdowns'' from § 63.998(b)(2)(i).

(8) Section 63.998(b)(2)(iii).

(9) The phrase ''other than periods of startups, shutdowns, and malfunctions'' from § 63.998(b)(5)(i)(A).

(10) The phrase ''other than periods of startups, shutdowns, and malfunctions'' from § 63.998(b)(5)(i)(C).

(11) The phrase '', except as provided in paragraphs (b)(6)(i)(A) and (B) of this section'' from § 63.998(b)(6)(i).

(12) The second sentence of § 63.998(b)(6)(ii).

(13) Section 63.998(c)(1)(ii)(D), (E), (F), and (G).

(14) Section 63.998(d)(1)(ii).

(15) Section 63.998(d)(3)(i) and (ii).

(16) The phrase ''may be included as part of the startup, shutdown, and malfunction plan, as required by the referencing subpart for the source, or'' from § 63.1005(e)(4)(i).

(17) The phrase ''(except periods of startup, shutdown, or malfunction)'' from § 63.1007(e)(1)(ii)(A).

(18) The phrase ''(except during periods of startup, shutdown, or malfunction)'' from § 63.1009(e)(1)(i)(A).

(19) The phrase ''(except during periods of startup, shutdown, or malfunction)'' from § 63.1012(b)(1).

(20) The phrase ''(except periods of startup, shutdown, or malfunction)'' from § 63.1026(e)(1)(ii)(A).

(21) The phrase ''(except periods of startup, shutdown, or malfunction)'' from § 63.1028(e)(1)(i)(A).

(22) The phrase ''(except periods of startup, shutdown, or malfunction)'' from § 63.1031(b)(1).

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25681, May 13, 2005; 85 FR 49741, Aug. 14, 2020; 85 FR 75235, Nov. 25, 2020; 88 FR 10849, Feb. 22, 2023]

§ 63.8005 What requirements apply to my process vessels?

(a) *General.* (1) You must meet each emission limit and work practice standard in table 1 to this subpart that applies to you, and you must meet each applicable requirement specified in § 63.8000(b), except as specified in paragraphs (a)(1)(i) through (iii) of this section.

(i) Except as provided in paragraph (a)(1)(iii) of this section, you are not required to meet the emission limits and work practice standards in table 1 to this subpart if you comply with § 63.8050 or § 63.8055.

(ii) You must meet the emission limits and work practice standards in Table 1 to this subpart for emissions from automatic cleaning operations. You are not required to meet the emission limits and work practice standards in Table 1 to this subpart for emissions from cleaning operations that are conducted manually.

(iii) You must meet the inorganic HAP emissions limit in table 1 to this subpart during the addition of material containing metal HAP to a process vessel. You are not required to meet this limit for the addition of pigments and other solids that are in paste, slurry, or liquid form.

(2) For each control device used to comply with Table 1 to this subpart, you must comply with subpart SS of this part as specified in § 63.8000(c), except as specified in § 63.8000(d) and (f) and paragraphs (b) through (g) of this section.

(b) When subpart SS of this part 63 refers to process vents, it means process vessel vents for the purposes of this section.

(c) Process condensers, as defined in § 63.1251, are not considered to be control devices for process vessels.

(d) *Initial compliance.* (1) To demonstrate initial compliance with a percent reduction emission limit in table 1 to this subpart, you must conduct the performance test under conditions as specified in § 63.7(e)(1), except as specified in paragraph (d)(5) of this section, and except that the performance test must be conducted under worst-case conditions. Also, the performance test for a control device used to control emissions from process vessels must be conducted according to § 63.1257(b)(8), including the submittal of a site-specific test plan for approval prior to testing. The requirements in § 63.997(e)(1)(i) and (iii) also do not apply for performance tests conducted to determine compliance with the emission limits for process vessels.

(2) For the initial compliance demonstration for condensers, you must determine uncontrolled emissions using the procedures specified in § 63.1257(d)(2), and you must determine controlled emissions using the procedures specified in § 63.1257(d)(3)(i)(B) and (iii).

(3) You must demonstrate that each process condenser is properly operated according to the procedures specified in § 63.1257(d)(2)(i)(C)(*4*)(*ii*) and (d)(3)(iii)(B). The reference in § 63.1257(d)(3)(iii)(B) to the alternative standard in § 63.1254(c) does not apply for the purposes of this subpart. As an alternative to measuring the exhaust gas temperature, as required by § 63.1257(d)(3)(iii)(B), you may elect to measure the liquid temperature in the receiver.

(4) You must conduct a performance test or compliance demonstration equivalent to an initial compliance demonstration within 360 hours of a change in operating conditions that are not considered to be within the previously established worst-case conditions.

(5) Beginning on the compliance dates specified in § 63.7995(e), § 63.7(e)(1) no longer applies and performance tests shall be conducted under such conditions as the Administrator specifies to the owner or operator based on representative performance of the affected source for the period being tested. Representative conditions exclude periods of startup and shutdown unless specified by the Administrator or an applicable subpart. The owner or operator may not conduct performance tests during periods of malfunction.

The owner or operator must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, the owner or operator shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(e) *Establishing operating limits.* You must establish operating limits under the conditions required for your initial compliance demonstration and periodic performance tests, except you may elect to establish operating limit(s) for conditions other than those under which a performance test was conducted as specified in paragraph (e)(1) of this section and, if applicable, paragraph (e)(2) of this section.

(1) The operating limits may be based on the results of the performance test and supplementary information such as engineering assessments and manufacturer's recommendations. These limits may be established for conditions as unique as individual emission episodes. You must provide rationale in the precompliance report for the specific level for each operating limit, including any data and calculations used to develop the limit and a description of why the limit indicates proper operation of the control device. The procedures provided in this paragraph (e)(1) have not been approved by the Administrator and determination of the operating limit using these procedures is subject to review and approval by the Administrator.

(2) If you elect to establish separate operating limits for different emission episodes, you must maintain records as specified in §63.8080(g) of each point at which you change from one operating limit to another, even if the duration of the monitoring for an operating limit is less than 15 minutes.

(f) *Averaging periods.* If you elect to establish separate operating limits for different emission episodes, you may elect to determine operating block averages instead of the daily averages specified in §63.998(b)(3). An operating block is a period of time that is equal to the time from the beginning to end of an emission episode or sequence of emission episodes.

(g) *Flow indicators.* If flow to a control device could be intermittent or bypassed, you must install, calibrate, and operate a flow indicator at the inlet or outlet of the control device to identify periods of no flow, or you must comply with the alternatives requirements of paragraph (g)(1) or (2) of this section. Periods of no flow may not be used in daily or block averages. You must perform a flow meter verification check annually for at least two points: One at the instrument's zero and the other at the instrument's span.

(1) You must use a valve position or bypass damper position indicator that provides a continuous reading and record of the bypass valve or damper position when the control device is in operation. You must inspect the monitoring system semiannually to verify that the monitor will indicate valve position.

(2) You must secure the bypass line valve or bypass damper in the non-diverting position with a car-seal or a lock-and-key type configuration. You must visually inspect the seal or closure mechanism at least once every month to ensure that the valve is maintained in the non-diverting position and that the vent stream is not diverted through the bypass line. You must also record the occurrence of all periods when the seal or closure mechanism is broken, or the key for a lock-and-key type lock has been checked out.

(h) *Bypass.* Beginning no later than the compliance date specified in §63.7995(e), when determining compliance with the percent emission reduction requirements in Table 1 to this subpart, you must account for the time that the control device was bypassed. You must use Equation 1 to this section to determine the allowable total hours of bypass for each semi-annual compliance period. To demonstrate compliance, the actual total hours of bypass must not exceed the allowable total hours of bypass calculated by Equation 1 to this section.

$$T_{byp} = (R - OCE) / R * T_{op} \quad \text{Eq. 1}$$

T_{byp} = Total allowable source operating time (hours) when the control device for stationary process vessels can be bypassed during the semiannual compliance period for any reason.

R = Control efficiency of control device, percent, as determined by Equation 6 in §63.997(e)(2)(iv)(C).

OCE = The applicable percent emission reduction requirement in Table 1 to this subpart.

T_{op} = Total source operating time (hours) for stationary process vessels during the semiannual compliance period.

(i) *Inorganic HAP standards.* You must demonstrate initial compliance with the inorganic HAP limit in table 1 to this subpart and as specified in paragraph (a)(1)(iii) of this section by following the requirements specified in paragraph (i)(1) or (2) of this section. You must demonstrate continuous compliance with the requirements in §63.11583(a) through (e) and (h).

(1) You must follow the requirements specified in paragraphs (a)(1)(i) through (iii) of this section and include the results in your notification of compliance status report in accordance with §63.8070.

(i) You must conduct the tests under conditions that represent normal operation, during which dry materials are added; tests may be conducted whether or not those dry materials contain metal HAP.

(ii) You must perform the test using EPA Method 5 in appendix A to 40 CFR part 60.

(iii) You must conduct a minimum of three separate test runs with a minimum sample volume of 70 dry standard cubic feet (2 dry standard cubic meters) per run for each performance test required in this section, as specified in §63.7(e)(3).

(2) For existing sources only, you may demonstrate initial compliance using the results of an emissions test conducted in the past 5 years provided the test meets the requirements in paragraph (i)(1) of this section.

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25681, May 13, 2005; 85 FR 49743, Aug. 14, 2020; 88 FR 10849, Feb. 22, 2023]

§63.8010 What requirements apply to my storage tanks?

(a) *Introduction.* You must meet each emission limit in Table 2 to this subpart that applies to your storage tanks, and you must meet each applicable requirement specified in §63.8000(b). For each control device used to comply with Table 2 to this subpart, you must comply with subpart SS of this part as specified in §63.8000(c), except as specified in §63.8000(d) and (f) and paragraphs (b) through (d) of this section.

(b) *Exceptions to subparts SS and WW of this part 63.* (1) If you conduct a performance test or design evaluation for a control device used to control emissions only from storage tanks, you must establish operating limits, conduct monitoring, and keep records using the same procedures as required in subpart SS of this part 63 for control devices used to reduce emissions from process vents instead of the procedures specified in §§63.985(c), 63.998(d)(2)(i), and 63.999(b)(2).

(2) When the term storage vessel is used in subparts SS and WW of this part 63, the term storage tank, as defined in §63.8105 applies for the purposes of this subpart.

(c) *Planned routine maintenance.* The emission limits in Table 2 to this subpart for control devices used to control emissions from storage tanks do not apply during periods of planned routine maintenance. Periods of planned routine maintenance of each control device, during which the control device does not meet the emission limit specified in Table 2 to this subpart, must not exceed 240 hours per year (hr/yr). You may submit an application to the Administrator requesting an extension of this time limit to a total of 360 hr/yr. The application must explain why

the extension is needed, it must indicate that no material will be added to the storage tank between the time the 240 hr/yr limit is exceeded and the control device is again operational, and it must be submitted at least 60 days before the 240 hr/yr limit will be exceeded.

(d) *Vapor balancing alternative.* As an alternative to the emission limits specified in Table 2 to this subpart, you may elect to implement vapor balancing in accordance with § 63.1253(f), except as specified in paragraphs (d)(1) and (2) of this section.

(1) To comply with § 63.1253(f)(6)(i), the owner or operator of an offsite cleaning and reloading facility must comply with §§ 63.7995 through 63.8105 instead of complying with § 63.1253(f)(7)(ii).

(2) You may elect to set a pressure relief device to a value less than the 2.5 psig required in § 63.1253(f)(5) if you provide rationale in your notification of compliance status report explaining why the alternative value is sufficient to prevent breathing losses at all times.

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49743, Aug. 14, 2020]

§ 63.8015 What requirements apply to my equipment leaks?

(a) You must meet each requirement in Table 3 to this subpart that applies to your equipment leaks, except as specified in paragraphs (b) through (d) of this section.

(b) *Exceptions to requirements in § 63.424(a).* (1) When § 63.424(a) refers to ''a bulk gasoline terminal or pipeline breakout station subject to the provisions of this subpart,'' the phrase ''a miscellaneous coating manufacturing affected source subject to 40 CFR part 63, subpart HHHHH'' shall apply for the purposes of this subpart.

(2) When § 63.424(a) refers to ''equipment in gasoline service,'' the phrase ''equipment in organic HAP service'' shall apply for the purposes of this subpart.

(3) When § 63.424(a) specifies that ''each piece of equipment shall be inspected during loading of a gasoline cargo tank,'' the phrase ''each piece of equipment must be inspected when it is operating in organic HAP service'' shall apply for the purposes of this subpart.

(4) Equipment in service less than 300 hours per year, equipment in vacuum service, or equipment contacting nonprocess fluids is excluded from this section.

(c) When § 63.1036 refers to batch processes, any part of the miscellaneous coating manufacturing operations applies for the purposes of this subpart.

(d) For the purposes of this subpart, pressure testing for leaks in accordance with § 63.1036(b) is not required after reconfiguration of an equipment train if flexible hose connections are the only disturbed equipment.

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25681, May 13, 2005]

§ 63.8020 What requirements apply to my wastewater streams?

(a) You must meet each requirement in Table 4 to this subpart that applies to your wastewater streams, and you must meet each applicable requirement specified in § 63.8000 and paragraphs (b) through (d) of this section.

(b) For each wastewater stream that you generate, you must either designate the wastewater stream as a Group 1 wastewater stream according to the procedures in paragraph (b)(1) of this section, or you must determine whether the wastewater stream is a Group 1 wastewater stream according to the procedures in paragraph (b)(2) of this section.

(1) You may designate any wastewater stream as a Group 1 wastewater stream. You do not have to determine the concentration for any designated Group 1 wastewater stream.

(2) For wastewater streams that you do not designate as Group 1 wastewater streams, you must use the procedures specified in § 63.144(b) to establish the concentrations, except as specified in paragraphs (b)(2)(i) and (ii) of this section.

(i) References to Table 8 compounds in § 63.144 do not apply for the purposes of this subpart.

(ii) *Alternative test methods.* (A) As an alternative to the test methods specified in § 63.144(b)(5)(i), you may use Method 8260 or 8270 as specified in § 63.1257(b)(10)(iii).

(B) As an alternative to using the methods specified in §63.144(b)(5)(i), you may conduct wastewater analyses using Method 1666 or 1671 of 40 CFR part 136, appendix A, and comply with the sampling protocol requirements specified in §63.144(b)(5)(ii). The validation requirements specified in §63.144(b)(5)(iii) do not apply if you use Method 1666 or 1671 of 40 CFR part 136, appendix A.

(c) For each enhanced biological treatment unit used to comply with the requirements in Table 4 to this subpart, you must monitor total suspended solids (TSS), biological oxygen demand (BOD), and the biomass concentration. In the precompliance report you must identify and provide rationale for proposed operating limits for these parameters, methods for monitoring, the frequency of monitoring, and recordkeeping and reporting procedures that will demonstrate proper operation of the enhanced biological treatment unit. Alternatively, you may use the precompliance report to request to monitor other parameters, and you must include a description of planned reporting and recordkeeping procedures and the basis for the selected monitoring frequencies and the methods that will be used.

(d) If you transfer the wastewater offsite for enhanced biological treatment, you must obtain written certification from the offsite facility stating that the offsite facility will comply with the requirements of this subpart. The certifying entity may revoke the certification by providing 90 days notice. Upon expiration of the notice period, you may not transfer wastewater to that treatment facility.

§63.8025 What requirements apply to my transfer operations?

(a) You must comply with each emission limit and work practice standard in Table 5 to this subpart that applies to your transfer operations, and you must meet all applicable requirements specified in §63.8000(b). For each control device used to comply with Table 5 to this subpart, you must comply with subpart SS of this part as specified in §63.8000(c), except as specified in §63.8000(d) and (f) and paragraph (b) of this section.

(b) If you have Group 1 transfer operations, as defined in §63.8105, then all transfer racks used for bulk loading coatings must meet the requirements for high throughput transfer racks in subpart SS of this part.

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49743, Aug. 14, 2020]

§63.8030 What requirements apply to my heat exchange systems?

(a) You must comply with the requirements specified in Table 6 to this subpart that apply to your heat exchange systems, except as specified in paragraphs (b) through (e) of this section.

(b) The phrase a chemical manufacturing process unit meeting the conditions of §63.100(b)(1) through (b)(3) of this section in §63.104(a) means the miscellaneous coating manufacturing operations defined in §63.7985(b) for the purposes of this subpart.

(c) The reference to §63.100(c) in §63.104(a) does not apply for the purposes of this subpart.

(d) The reference to §63.103(c)(1) in §63.104(f)(1) does not apply. For the purposes of this subpart, records must be retained as specified in §63.10(b)(1).

(e) The reference to the periodic report required by §63.152(c) of subpart G of this part means the compliance report required by §63.8075(e) for the purposes of this subpart.

Alternative Means of Compliance

§63.8050 How do I comply with emissions averaging for stationary process vessels at existing sources?

(a) As an alternative to complying with the requirements in Table 1 to this subpart for each individual stationary process vessel, you may elect to comply with emissions averaging for stationary process vessels greater than or equal to 250 gallons (gal) at your existing affected source as specified in paragraphs (b) through (e) of this section.

(b) *General requirements.* (1) A State may prohibit averaging of HAP emissions and require the owner or operator of an existing affected source to comply with the emission limits and work practice standards in Table 1 to this subpart.

(2) All stationary process vessels in an emissions averaging group must be equipped with a tightly-fitting vented cover.

(c) *Initial compliance.* To demonstrate initial compliance with the emissions averaging alternative, you must comply with the provisions in paragraphs (c)(1) through (4) of this section.

(1) Estimate uncontrolled emissions from each affected stationary process vessel in pounds per batch using the procedures specified in §63.1257(d)(2), except as specified in paragraphs (c)(1)(i) and (ii) of this section. For the purposes of this section, uncontrolled emissions means the emissions from the vessel if it were equipped only with a tightly-fitting vented cover. You must identify the range of typical operating parameters and perform the calculation using the values that result in the highest emissions, and you must document the operating parameters and resulting emissions calculations in the precompliance report.

(i) When you are required to calculate uncontrolled emissions from heating, you may not calculate emissions using Equation 13 of subpart GGG of this part 63.

(ii) The statement in §63.1257(d)(2)(i)(B) that ''the partial pressure of HAP shall be assumed to be 25 percent of the saturated value if the purge flow rate is greater than 100 scfm'' does not apply. For the purposes of this subpart, multiply the HAP partial pressure in Equation 12 of 40 CFR part 63, subpart GGG by a HAP-specific saturation factor determined in accordance with Equations 1 through 3 of this section. Solve equation 1 of this section iteratively beginning with saturation factors (in the right-hand side of the equation) of 1.0 for each condensable compound. Stop iterating when the calculated saturation factors for all compounds are the same to two significant figures for subsequent iterations. Note that for multi-component emission streams, saturation factors must be calculated for all condensable compounds, not just the HAP.

$$S_i = \frac{K_i A}{K_i A + V + \sum_{i=1}^{n} S_i V_i^{sat}} \qquad \text{Eq. 1}$$

$$V_i^{sat} = \frac{VP_i}{\left(P_T - \sum_{i=1}^{n} P_i\right)} \qquad \text{Eq. 2}$$

$$K_i = K_o\left(\frac{M_o}{M_i}\right)^{1/3} \qquad \text{Eq. 3}$$

where:

S_I = saturation factor for individual condensable compounds in the emission stream

P_i = partial pressure of individual condensable compounds in the emission stream calculated using Raoult's Law or other appropriate methods

P_T = pressure of the vessel vapor space

A = surface area of liquid

V = purge flow rate as used in Equation 12 of 40 CFR part 63, subpart GGG

V_i^{sat} = volumetric flowrate of condensable compounds in the emission stream

K_i = mass transfer coefficient of individual condensable compounds in the emission stream

K_o = mass transfer coefficient of a reference compound (e.g., 0.83 cm/s for water)

M_o = molecular weight of reference compound (e.g., 18.02 for water)

M_i = molecular weight of individual condensable compounds in the emission stream

n = number of condensable compounds in the emission stream

(2) Estimate controlled emissions in pounds per batch for each vessel as specified in paragraphs (c)(2)(i) through (iii) of this section.

(i) Except as specified in paragraphs (c)(2)(ii) and (iii) of this section, estimate controlled emissions as if the vessel were controlled in compliance with entry 2.b.i. in Table 1 to this subpart.

(ii) Estimate the controlled emissions using the control level achieved on November 15, 1990 if that value is greater than the applicable control level required by entry 2.b.i in Table 1 to this subpart.

(iii) Estimate the controlled emissions using the control level required to comply with a State or Federal rule other than this subpart if that level is greater than the applicable control level required by entry 2.b.i in Table 1 to this subpart and the other rule was in effect before the date when you request approval to comply with emissions averaging.

(3) Determine actual emissions in pounds per batch for each vessel in accordance with paragraph (c)(3)(i), (ii), or (iii) of this section, as applicable.

(i) If emissions are routed through a closed-vent system to a condenser control device, determine controlled emissions using the procedures specified in § 63.1257(d)(3).

(ii) If emissions are routed through a closed-vent system to any control device other than a condenser, determine actual emissions after determining the efficiency of the control device using the procedures in subpart SS of this part as specified in § 63.8000(c).

(iii) If the vessel is vented to the atmosphere, then actual emissions are equal to the uncontrolled emissions estimated in accordance with paragraph (c)(1) of this section.

(4) Provide rationale in the precompliance report for why the sum of the actual emissions will be less than the sum of emissions from the vessels if they had been controlled in accordance with Table 1 to this subpart. The approved actual emissions calculated according to paragraph (c)(3) of this section are emission limits that must be incorporated into your operating permit.

(d) *Continuous compliance.* (1) Maintain a monthly log of the number of batches produced that can be correlated with the emissions estimates per batch developed in accordance with paragraph (c) of this section.

(2) Sum the actual emissions for all of the process vessels in the emissions averaging group every three months, with the first 3-month period beginning on the compliance date, and compare the resulting total with the total emissions for the vessels calculated in accordance with paragraph (c)(2) of this section. Compliance is demonstrated if the sum of the actual emissions is less than the emissions estimated in accordance with paragraph (c)(2) of this section.

(3) For control devices, establish operating limits and monitor as specified in § 63.8000.

(e) *Recordkeeping and reporting.* Comply with §§ 63.8070, 63.8075, and 63.8080.

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25682, May 13, 2005; 85 FR 49744, Aug. 14, 2020]

§ 63.8055 How do I comply with a weight percent HAP limit in coating products?

(a) As an alternative to complying with the requirements in Table 1 to this subpart for each individual stationary process vessel at an existing source, you may elect to comply with a 5 weight percent HAP limit for process vessels at your affected source that are used to manufacture coatings with a HAP content of less than 0.05 kg per kg product as specified in paragraph (b) of this section.

(b) You may only comply with the alternative during the production of coatings that contain less than 5 weight percent HAP, as determined using any of the procedures specified in paragraphs (b)(1) through (4) of this section.

(1) Method 311 (appendix A to this part). As an alternative to Method 311, you may use California Air Resources Board Method 310, Determination of Volatile Organic Compounds (VOC) in Consumer Products and Reactive Organic Compounds (ROC) in Aerosol Coating Products (incorporated by reference, *see* § 63.14) for use with aerosol cans.

(2) Method 24 (appendix A to 40 CFR part 60). You may use Method 24 to determine the mass fraction of volatile matter and use that value as a substitute for the mass fraction of HAP, or one of the alternatives in paragraphs (b)(2)(i) through (iii) of this section.

(i) ASTM D2369–10 (Reapproved 2015)e1, (incorporated by reference, *see* § 63.14);

(ii) ASTM D2697–03 (Reapproved 2014) (incorporated by reference, *see* § 63.14); or

(iii) ASTM D3960–98 (incorporated by reference, *see* § 63.14).

(3) You may use an alternative test method for determining mass fraction of HAP if you obtain prior approval by the Administrator. You must follow the procedure in § 63.7(f) to submit an alternative test method for approval.

(4) You may rely on formulation data from raw material suppliers if it represents each organic HAP that is present at 0.1 percent by mass or more for the HAP listed in Table 11 to this subpart, and at 1.0 percent by mass or more for other compounds. If the HAP

weight percent estimated based on formulation data conflicts with the results of a test conducted according to paragraphs (b)(1) through (3) of this section, then there is a rebuttal presumption that the test results are accurate unless, after consultation, you demonstrate to the satisfaction of the permitting authority that the test results are not accurate and that the formulation data are more appropriate.

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25682, May 13, 2005; 70 FR 75927, Dec. 21, 2005; 85 FR 49744, Aug. 14, 2020]

NOTIFICATION, REPORTS, AND RECORDS

§ 63.8070 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.6(h)(4) and (5), 63.7(b) and (c), 63.8(e), (f)(4) and (6), 63.9(b) through (h) that apply to you by the dates specified.

(b) *Initial notification.* (1) As specified in § 63.9(b)(2), if you have an existing affected source on December 11, 2003, you must submit an initial notification not later than 120 calendar days after December 11, 2003, or no later than 120 calendar days after the source becomes subject to this subpart, whichever is later.

(2) As specified in § 63.9(b)(3), if you start up your new affected source on or after December 11, 2003, you must submit an initial notification not later than 120 calendar days after you become subject to this subpart.

(c) *Notification of performance test.* If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required in § 63.7(b)(1). For any performance test required as part of the compliance procedures for process vessels in Table 1 to this subpart, you must also submit the test plan required by § 63.7(c) and the emission profile with the notification of the performance test.

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49743, Aug. 14, 2020; 85 FR 73914, Nov. 19, 2020]

§ 63.8075 What reports must I submit and when?

(a) You must submit each report in Table 9 to this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report as specified in Table 9 to this subpart and paragraphs (b)(1) and (2) of this section.

(1) The compliance reports must be submitted semiannually. The first report must be submitted no later than 240 days after the applicable compliance date and shall cover the 6-month period beginning on the compliance date. Each subsequent compliance report must cover the 6-month period following the preceding period.

(2) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of according to the dates in Table 9.

(c) *Precompliance report.* You must submit a precompliance report to request approval of any of the information in paragraphs (c)(1) through (4) of this section. We will either approve or disapprove the report within 90 days after we receive it. If we disapprove the report, you must still be in compliance with the emission limitations and work practice standards in this subpart by the compliance date.

(1) Requests for approval to set operating limits for parameters other than those specified in §§ 63.8005 through 63.8030, including parameters for enhanced biological treatment units. Alternatively, you may make these requests according to § 63.8(f).

(2) Descriptions of daily or per batch demonstrations to verify that control devices subject to § 63.8000(d)(3) are operating as designed.

(3) A description of the test conditions, data, calculations, and other information used to establish operating limits according to § 63.8005(e)(1).

(4) If you comply with emissions averaging in § 63.8050, the data and results of emission calculations as specified in § 63.8050(c)(1) through (3), and rationale for why the sum of actual emissions will be less than the sum of emissions if the process vessels were controlled in accordance with Table 1 to this subpart as specified in § 63.8050(c)(4).

(d) *Notification of compliance status report.* You must submit a notification of compliance status report according to the schedule in paragraph (d)(1) of this section, and the notification of compliance status report must include the information specified in paragraph (d)(2) of this section.

(1) You must submit the notification of compliance status report no later than 150 days after the applicable compliance date specified in § 63.7995. You must submit a separate notification of compliance status report after the applicable compliance date specified in § 63.7995(e) and (f).

(2) The notification of compliance status report must include the information in paragraphs (d)(3)(i) through (vi) of this section.

(i) The results of any applicability determinations (*e.g.*, HAP content of coating products; halogenated vent stream determinations; group determinations for storage tanks, wastewater, and transfer operations; and equipment that is in organic HAP service).

(ii) The results of performance tests, engineering analyses, design evaluations, flare compliance assessments, inspections and repairs, and calculations used to demonstrate compliance according to §§ 63.8005 through 63.8030 and 63.8055. For performance tests, results must include descriptions of sampling and analysis procedures and quality assurance procedures.

(iii) Descriptions of monitoring devices, monitoring frequencies, and the operating limits established during the initial compliance demonstrations, including data and calculations to support the levels you establish.

(iv) Identification of parts of the affected source that are subject to overlapping requirements described in § 63.8090 and the authority under which you will comply.

(v) Identify storage tanks for which you are complying with the vapor balancing alternative in § 63.8010(e).

(vi) If you transfer Group 1 wastewater stream to an offsite facility for treatment, include the name and location of the transferee and a description of the Group 1 wastewater stream that is sent to the treatment facility. If the offsite facility provides enhanced biological treatment, also include the certification required by § 63.8020(d) that the offsite facility will comply with the requirements of this subpart.

(e) *Compliance report.* The compliance report must contain the information specified in paragraphs (e)(1) through (8) of this section.

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying the accuracy of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) Applicable records and information for periodic reports as specified in referenced subparts F, SS, TT, UU, and WW of this part 63.

(5) For each SSM during which excess emissions occur, the compliance report must include the information specified in paragraphs (e)(5)(i) and (ii) of this section. On and after the compliance date specified in § 63.7995(e), this paragraph (e)(5) no longer applies.

(i) Records that the procedures specified in your startup, shutdown, and malfunction plan (SSMP) were followed or documentation of actions taken that are not consistent with the SSMP.

(ii) A description of each malfunction.

(6) The compliance report must contain the information on deviations, as defined in § 63.8105, according to paragraphs (e)(6)(i), (ii), and (iii) of this section.

(i) If there are no deviations from any emission limit, operating limit, or work practice standard specified in this subpart, include a statement that there were no deviations from the emission limits, operating limits, or work practice standards during the reporting period.

(ii) For each deviation from an emission limit, operating limit, and work

practice standard that occurs at an affected source where you are not using a continuous monitoring system (CMS) to comply with the emission limit or work practice standards in this subpart, you must include the information in paragraphs (e)(6)(ii)(A) through (D) of this section.

(A) The total operating time of each affected source during the reporting period.

(B) Before the compliance date specified in §63.7995(e), information on the number, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken. On and after the compliance date specified in §63.7995(e), report the number of failures to meet an applicable standard. For each instance, report the date, time, and duration of each failure. For each failure the report must include a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, a description of the method used to estimate the emissions, and the cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(C) Operating logs for the day(s) during which the deviation occurred, except operating logs are not required for deviations of the work practice standards for equipment leaks.

(D) On and after the compliance date specified in §63.7995(e), report the total bypass hours, as monitored according to the provisions of §63.8080(h).

(iii) For each deviation from an emission limit or operating limit occurring at an affected source where you are using a CMS to comply with the emission limit in this subpart, you must include the information in paragraphs (e)(6)(iii)(A) through (L) of this section. This includes periods of SSM.

(A) The date and time that each CMS was inoperative, except for zero (low-level) and high-level checks.

(B) The date, time, and duration that each CEMS was out-of-control, including the information in §63.8(c)(8).

(C) Before the compliance date specified in §63.7995(e), the date and time that each deviation started and stopped, and whether each deviation occurred during a period of SSM or during another period. On and after the compliance date specified in §63.7995(e), report the number of failures to meet an applicable standard. For each instance, report the date, time, and duration of each failure. For each failure the report must include a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit, a description of the method used to estimate the emissions, and the cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(D) A summary of the total duration of the deviation during the reporting period, and the total duration as a percent of the total source operating time during that reporting period.

(E) Before the compliance date specified in §63.7995(e), a breakdown of the total duration of the deviations during the reporting period into those that are due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes. On and after the compliance date specified in §63.7995(e), a breakdown of the total duration of the deviations during the reporting period into those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(F) A summary of the total duration of CMS downtime during the reporting period, and the total duration of CMS downtime as a percent of the total source operating time during that reporting period.

(G) An identification of each HAP that is known to be in the emission stream or wastewater stream, as applicable.

(H) A description of the product being produced.

(I) Identification of the CMS.

(J) The date of the latest CMS certification or audit.

(K) The operating day or operating block average values of monitored parameters for each day(s) during which the deviation occurred.

(L) A summary of the total duration of CMS data unavailability during the

reporting period, and the total duration as a percent of the total source operating time during that reporting period.

(7) If you use a CEMS, and there were no periods during which it was out-of-control as specified in § 63.8(c)(7), include a statement that there were no periods during which the CEMS was out-of-control during the reporting period.

(8) *Notification of process change.* (i) Except as specified in paragraph (e)(8)(ii) of this section, whenever you change any of the information submitted in either the notification of compliance status report or any previously reported change to the notification of compliance status report, you must document the change in your compliance report. The notification must include all of the information in paragraphs (e)(8)(i)(A) and (B) of this section.

(A) Revisions to any of the information reported in the original notification of compliance status report under paragraph (d) of this section.

(B) Information required by the notification of compliance status report under paragraph (d) of this section for changes involving the addition of processes or equipment at the affected source.

(ii) You must submit a report 60 days before the scheduled implementation date of any of the changes identified in paragraphs (e)(8)(ii)(A), (B), or (C) of this section.

(A) Any change to the information contained in either the precompliance report or any previously reported change to the precompliance report.

(B) [Reserved]

(C) A change in compliance status.

(f) *Performance test report.* On and after August 14, 2023, within 60 days after the date of completing each performance test required by § 63.8000, § 63.8005, or § 63.8010, you must submit the results of the performance test following the procedures specified in paragraphs (f)(1) through (3) of this section. The requirements of this paragraph (f) do not affect the schedule for completing performance tests specified in §§ 63.8000, 63.8005, and 63.8010.

(1) *Data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). The data must be submitted in a file format generated through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the extensible markup language (XML) schema listed on the EPA's ERT website. Submit the results of the performance test to the EPA via CEDRI, which can be accessed through the EPA's CDX (*https://cdx.epa.gov/*). The data must be submitted in a file format generated through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on the EPA's ERT website.

(2) *Data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the test.* The results of the performance test must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *Confidential business information (CBI).* If you claim that some of the performance test information being submitted under paragraph (f) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to the EPA. The file must be generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAPQS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to

the EPA via the EPA's CDX as described in this paragraph (f).

(g) *Performance evaluation report.* On and after August 14, 2023, within 60 days after the date of completing each CMS performance evaluation (as defined in § 63.2), you must submit the results of the performance evaluation following the procedures specified in paragraphs (g)(1) through (3) of this section.

(1) *Performance evaluations of CMS measuring relative accuracy test audit (RATA) pollutants that are supported by the EPA's ERT as listed on the EPA's ERT website at the time of the evaluation.* Submit the results of the performance evaluation to the EPA via CEDRI, which can be accessed through the EPA's CDX. The data must be submitted in a file format generated through the use of the EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on the EPA's ERT website.

(2) *Performance evaluations of CMS measuring RATA pollutants that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the evaluation.* The results of the performance evaluation must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *CBI.* If you claim some of the information submitted under paragraph (g) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to the EPA. The file must be generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described in paragraph (f) of this section.

(h) *Reporting.* You must submit to the Administrator initial compliance reports, notification of compliance status reports, and compliance reports of the following information. Beginning on and after August 14, 2023, submit all subsequent reports following the procedure specified in paragraph (i) of this section.

(i) *CEDRI reports.* If you are required to submit reports following the procedure specified in this paragraph (i), you must submit reports to the EPA via CEDRI, which can be accessed through the EPA's CDX (*https://cdx.epa.gov*).

(1) *Compliance reports.* The requirements of this paragraph (i) do not affect the schedule for submitting the initial notification or the notification of compliance status reports. You must use the appropriate electronic compliance report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/compliance-and-emissions-data-reporting-interface-cedri*) for this subpart. The date report templates become available will be listed on the CEDRI website.

(2) *Initial notification reports and notification of compliance status reports.* You must upload to CEDRI a portable document format (PDF) file of each initial notification and of each notification of compliance status.

(3) *All reports.* The report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. If you claim some of the information required to be submitted via CEDRI is CBI, submit a complete report, including information claimed to be CBI, to the EPA. The report must be generated using the appropriate form on the CEDRI website, where applicable. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted shall be submitted to the EPA via the EPA's CDX as described in this paragraph (i).

(j) *Extensions for CDX/CEDRI outages and force majeure events.* If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement in this section. To assert a claim of EPA system outage, you must meet the requirements outlined in paragraphs (j)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either the EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning 5 business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(k) *Force majeure.* If you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of *force majeure* for failure to timely comply with the reporting requirement in this section. To assert a claim of *force majeure*, you must meet the requirements outlined in paragraphs (k)(1) through (5) of this section.

(1) You may submit a claim if a *force majeure* event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For purposes of this section, a *force majeure* event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (*e.g.*, hurricanes, earthquakes, or floods), acts of war or terrorism, or equipment failure or safety hazard beyond the control of the affected facility (*e.g.*, large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the *force majeure* event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the *force majeure* event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of *force majeure* and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the *force majeure* event occurs.

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49744, Aug. 14, 2020; 88 FR 10849, Feb. 22, 2023]

§ 63.8080 What records must I keep?

You must keep the records specified in paragraphs (a) through (h) of this section.

(a) Each applicable record required by subpart A of this part 63 and in referenced subparts SS, TT, UU, and WW of this part 63.

(b) If complying with emissions averaging, records of the monthly number of batches for each process vessel, the quarterly actual emissions for each process vessel, the quarterly estimated emissions for each process vessel if it had been controlled as specified in Table 1 to this subpart, and comparison of the sums of the quarterly actual and estimated emissions as specified in § 63.8050(d).

(c) Before the compliance date specified in § 63.7995(e), a record of each time a safety device is opened to avoid unsafe conditions in accordance with § 63.8000(b)(2). On and after the compliance date specified in § 63.7995(e), a record of the information in paragraphs (c)(1) through (3) of this section.

(1) The source, nature, and cause of the opening.

(2) The date, time, and duration of the opening.

(3) An estimate of the quantity of total HAP emitted during the opening and the method used for determining this quantity.

(d) Records of the results of each CPMS calibration check and the maintenance performed, as specified in § 63.8000(d)(5).

(e) Before the compliance date specified in § 63.7995(e), for each CEMS, you must keep the records of the date and time that each deviation started and stopped, and whether the deviation occurred during a period of SSM or during another period. On and after the compliance date specified in § 63.7995(e), for each CEMS, you must keep the records of the date and time that each deviation started and stopped, and whether the deviation occurred during a period of SSM or during another period.

(f) Before the compliance date specified in § 63.7995(e), in the SSMP required by § 63.6(e)(3), you are not required to include Group 2 or non-affected emission points. For equipment leaks only, the SSMP requirement is limited to control devices and is optional for other equipment. On and after the compliance date specified in § 63.7995(e), the requirements of this paragraph (f) no longer apply.

(g) If you establish separate operating limits as allowed in § 63.8005(e) or (i), you must maintain a log of operation or a daily schedule indicating the time when you change from one operating limit to another.

(h) On and after the compliance date specified in § 63.7995(e), records of the total source operating time (hours) for stationary process vessels during the semiannual compliance period, and the source operating time (hours) when the control device for stationary process vessels was bypassed during the semiannual compliance period for any reason, as used in determining compliance with the percent emission reduction requirements in Table 1 to this subpart, as specified in § 63.8005(h).

(i) On and after the compliance date specified in § 63.7995(e), for each deviation from an emission limitation reported under § 63.8075(e)(5) or § 63.8005(i), a record of the information specified in paragraphs (i)(1) and (2) of this section, as applicable.

(1) In the event that an affected unit fails to meet an applicable standard, record the number of failures. For each failure record the date, time, and duration of each failure.

(2) For each failure to meet an applicable standard, record and retain a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(j) Any records required to be maintained by this subpart that are submitted electronically via the EPA's CEDRI may be maintained in electronic format. This ability to maintain electronic copies does not affect the requirement for facilities to make records, data, and reports available upon request to a delegated air agency or the EPA as part of an on-site compliance evaluation.

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49746, Aug. 14, 2020; 88 FR 10850, Feb. 22, 2023]

OTHER REQUIREMENTS AND INFORMATION

§ 63.8090 What compliance options do I have if part of my plant is subject to both this subpart and another subpart?

(a) *Compliance with 40 CFR parts 264 and 265, subparts AA, BB, and/or CC.* (1) After the compliance dates specified in § 63.7995, if a control device that you use to comply with this subpart is also subject to monitoring, recordkeeping, and reporting requirements in 40 CFR part 264, subpart AA, BB, or CC; or the monitoring and recordkeeping requirements in 40 CFR part 265, subpart AA, BB, or CC; and you comply with the periodic reporting requirements under 40 CFR part 264, subpart AA, BB, or CC that would apply to the device if your facility had final-permitted status, you may elect to comply either with the monitoring, recordkeeping, and reporting requirements of this subpart; or with the monitoring and recordkeeping requirements in 40 CFR part 264 or 265 and the reporting requirements in 40 CFR part 264, as described in this paragraph (a), which constitute compliance with the monitoring, recordkeeping, and reporting requirements of this subpart. If you elect to comply with the monitoring, recordkeeping, and reporting requirements in 40 CFR parts 264 and/or 265, you must report the information required for the compliance report in § 63.8075(e), and you must identify in the notification of compliance status report required by § 63.8075(d) the monitoring, recordkeeping, and reporting authority under which you will comply.

(2) After the compliance dates specified in this section, if any equipment at an affected source that is subject to this subpart is also subject to 40 CFR part 264, subpart BB or to 40 CFR part 265, subpart BB, then compliance with the recordkeeping and reporting requirements of 40 CFR part 264 and/or 265 may be used to comply with the recordkeeping and reporting requirements of § 63.1255, to the extent that the requirements of 40 CFR part 264 and/or 265 duplicate the requirements of this subpart. You must identify in the notification of compliance status report required by § 63.8075(d) if you will comply with the recordkeeping and reporting authority under 40 CFR part 264 and/or 265.

(b) *Compliance with 40 CFR part 60, subpart Kb.* After the compliance dates specified in § 63.7995, you are in compliance with this subpart for any storage tank that is assigned to miscellaneous coating manufacturing operations and that is both controlled with a floating roof and in compliance with the provisions of 40 CFR part 60, subpart Kb. You are in compliance with this subpart if you have a storage tank with a fixed roof, closed-vent system, and control device in compliance with 40 CFR part 60, subpart Kb, and you are in compliance with the monitoring, recordkeeping, and reporting requirements in this subpart. You must also identify in your notification of compliance status report required by § 63.8075(d) which storage tanks are in compliance with 40 CFR part 60, subpart Kb.

(c) *Compliance with 40 CFR part 63, subpart FFFF.* After the compliance dates specified in § 63.7995, an affected source under this subpart HHHHH that includes equipment that is also part of an affected source under 40 CFR part 63, subpart FFFF is deemed in compliance with this subpart HHHHH if all of the conditions specified in paragraphs (c)(1) through (5) of this section are met.

(1) Equipment used for both miscellaneous coating manufacturing operations and as part of a miscellaneous organic chemical manufacturing process unit (MCPU), as defined in § 63.2435, must be part of a process unit group developed in accordance with the provisions in § 63.2535(l).

(2) For the purposes of complying with § 63.2535(l), a miscellaneous coating manufacturing ''process unit'' consists of all coating manufacturing equipment that is also part of an MCPU in the process unit group. All miscellaneous coating manufacturing operations that are not part of a process unit group must comply with the requirements of this subpart HHHHH.

(3) The primary product for a process unit group that includes miscellaneous coating manufacturing equipment must be organic chemicals as described in § 63.2435(b)(1).

(4) The process unit group must be in compliance with the requirements in 40 CFR part 63, subpart FFFF as specified in §63.2535(l)(3)(i) no later than the applicable compliance dates specified in §63.2445.

(5) You must include in the notification of compliance status report required in §63.8070(d) the records as specified in §63.2535(l)(1) through (3).

[68 FR 69185, Dec. 11, 2003, as amended at 71 FR 58503, Oct. 4, 2006; 85 FR 49747, Aug. 14, 2020]

§63.8095 What parts of the General Provisions apply to me?

Table 10 to this subpart shows which parts of the General Provisions in §§63.1 through 63.15 apply to you.

§63.8100 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. Environmental Protection Agency (U.S. EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency also has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under 40 CFR part 63, subpart E, the authorities contained in paragraphs (b)(1) through (4) of this section are retained by the Administrator of U.S. EPA and are not delegated to the State, local, or tribal agency.

(1) Approval of alternatives to the non-opacity emission limits and work practice standards in §63.8000(a) under §63.6(g).

(2) Approval of major alternatives to test methods under §63.7(e)(2)(ii) and (f) and as defined in §63.90.

(3) Approval of major alternatives to monitoring under §63.8(f) and as defined in §63.90.

(4) Approval of major alternatives to recordkeeping and reporting under §63.10(f) and as defined in §63.90.

§63.8105 What definitions apply to this subpart?

(a) For an affected source complying with the requirements in subpart SS of this part 63, the terms used in this subpart and in subpart SS of this part 63 have the meaning given them in §63.981, except as specified in §§63.8000(d)(5)(ii) and (7), 63.8010(c)(2), 63.8025(b), and paragraph (g) of this section.

(b) For an affected source complying with the requirements in subpart TT of this part 63, the terms used in this subpart and in subpart TT of this part 63 have the meaning given them in §63.1001.

(c) For an affected source complying with the requirements in subpart UU of this part 63, the terms used in this subpart and in subpart UU of this part 63 have the meaning given them in §63.1020.

(d) For an affected source complying with the requirements in subpart WW of this part 63, the terms used in this subpart and subpart WW of this part 63 have the meaning given them in §63.1061, except as specified in §§63.8000(d)(7), 63.8010(c)(2), and paragraph (g) of this section.

(e) For an affected source complying with requirements in §§63.1253, 63.1257, and 63.1258, the terms used in this subpart and in §§63.1253, 63.1257, and 63.1258 have the meaning given them in §63.1251, except as specified in §63.8000(d)(7) and paragraph (g) of this section.

(f) For an affected source complying with the requirements of §63.104, the terms used in this subpart and in §63.104 have the meaning given them in §63.101, except as specified in §63.8000(d)(7) and paragraph (g) of this section.

(g) All other terms used in this subpart are defined in the CAA, in 40 CFR 63.2, and in this paragraph (g). If a term is defined in §63.2, §63.981, §63.1001, §63.1020, §63.1061, or §63.1251 and in this paragraph (g), the definition in this paragraph (g) applies for the purposes of this subpart.

Bag Leak Detection System (BLDS) means a system that is capable of continuously monitoring particulate matter (dust) loadings in the exhaust of a baghouse in order to detect bag leaks

and other upset conditions. A BLDS includes, but is not limited to, an instrument that operates on triboelectric, light scattering, light transmittance, or other effect to continuously monitor relative particulate matter loadings.

Bulk loading means the loading, into a tank truck or rail car, of liquid coating products that contain one or more of the organic HAP, as defined in section 112 of the CAA, from a loading rack. A loading rack is the system used to fill tank trucks and railcars at a single geographic site.

Coating means a material such as paint, ink, or adhesive that is intended to be applied to a substrate and consists of a mixture of resins, pigments, solvents, and/or other additives, where the material is produced by a manufacturing operation where materials are blended, mixed, diluted, or otherwise formulated. Coating does not include materials made in processes where a formulation component is synthesized by chemical reaction or separation activity and then transferred to another vessel where it is formulated to produce a material used as a coating, where the synthesized or separated component is not stored prior to formulation. Typically, coatings include products described by the following North American Industry Classification System (NAICS) codes, code 325510, Paint and Coating Manufacturing, code 325520, Adhesive and Sealant Manufacturing, and code 325910, Ink Manufacturing.

Construction means the onsite fabrication, erection, or installation of an affected source. Addition of new equipment to an affected source does not constitute construction, but it may constitute reconstruction of the affected source if it satisfies the definition of reconstruction in § 63.2.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(i) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limit, operating limit, or work practice standard;

(ii) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(iii) Before the compliance date specified in § 63.7995(e), fails to meet any emission limit, operating limit, or work practice standard in this subpart during SSM, regardless of whether or not such failure is permitted by this subpart. On and after the compliance date specified in § 63.7995(e), this paragraph (iii) no longer applies.

Enhanced biological treatment system means an aerated, thoroughly mixed treatment unit(s) that contains biomass suspended in water followed by a clarifier that removes biomass from the treated water and recycles recovered biomass to the aeration unit. The mixed liquor volatile suspended solids (biomass) is greater than 1 kilogram per cubic meter throughout each aeration unit. The biomass is suspended and aerated in the water of the aeration unit(s) either by submerged air flow or mechanical agitation. A thoroughly mixed treatment unit is a unit that is designed and operated to approach or achieve uniform biomass distribution and organic compound concentration throughout the aeration unit by quickly dispersing the recycled biomass and the wastewater entering the unit.

Excess emissions means emissions greater than those allowed by the emission limit.

Fabric filter means an air collection and control system that utilizes a bag filter to reduce the emissions of metal HAP and other particulate matter.

Group 1a storage tank means a storage tank at an existing source with a capacity greater than or equal to 20,000 gal storing material that has a maximum true vapor pressure of total organic HAP greater than or equal to 1.9 pounds per square inch, absolute (psia). Group 1a storage tank also means a storage tank at a new source with either a capacity greater than or equal to 25,000 gal storing material that has a maximum true vapor pressure of total HAP greater than or equal to 0.1 psia or a capacity greater than or equal to 20,000 gal and less than 25,000 gal storing material that has a maximum true vapor pressure of total HAP greater than or equal to 1.5 psia.

Group 1b storage tank means a storage tank at a new source that has a capacity greater than or equal to 10,000 gal, stores material that has a maximum true vapor pressure of total organic HAP greater than or equal to 0.02 psia, and is not a Group 1a storage tank.

Group 2 storage tank means a storage tank that does not meet the definition of a Group 1a or Group 1b storage tank.

Group 1 transfer operations means all bulk loading of coating products if the coatings contain greater than or equal to 3.0 million gallons per year (gal/yr) of HAP with a weighted average HAP partial pressure greater than or equal to 1.5 psia.

Group 2 transfer operations means bulk loading of coating products that does not meet the definition of Group 1 transfer operations, and all loading of coating products from a loading rack to other types of containers such as cans, drums, and totes.

Group 1 wastewater stream means a wastewater stream that contains total partially soluble and soluble HAP at an annual average concentration greater than or equal to 4,000 parts per million by weight (ppmw) and load greater than or equal to 750 pounds per year (lb/yr) at an existing source or greater than or equal to 1,600 ppmw and any partially soluble and soluble HAP load at a new source.

Group 2 wastewater stream means a wastewater stream that does not meet the definition of a Group 1 wastewater stream.

Halogenated vent stream means a vent stream determined to contain halogen atoms in organic compounds at a concentration greater than or equal to 20 ppmv as determined by the procedures specified in § 63.8000(b).

Hydrogen halide and halogen HAP means hydrogen chloride, chlorine, and hydrogen fluoride.

In organic HAP service means that a piece of equipment either contains or contacts a fluid (liquid or gas) that is at least 5 percent by weight of total organic HAP as determined according to the provisions of § 63.180(d). The provisions of § 63.180(d) also specify how to determine that a piece of equipment is not in organic HAP service.

Large control device means a control device that controls total HAP emissions of greater than or equal to 10 tpy, before control.

Material containing metal HAP means a material containing compounds of manganese, antimony, nickel, lead, cobalt, chromium, cadmium, and arsenic compounds, in amounts greater than or equal to 0.1 percent by weight as shown in formulation data provided by the manufacturer or supplier, such as the Material Safety Data Sheet for the material.

Maximum true vapor pressure means the equilibrium partial pressure exerted by the total organic HAP in the stored or transferred liquid at the temperature equal to the highest calendar-month average of the liquid storage or transfer temperature for liquids stored or transferred above or below the ambient temperature or at the local maximum monthly average temperature as reported by the National Weather Service for liquids stored or transferred at the ambient temperature, as determined:

(1) In accordance with methods described in American Petroleum Institute Publication 2517, Evaporative Loss From External Floating-Roof Tanks (incorporated by reference as specified in § 63.14 of subpart A of this part 63); or

(2) As obtained from standard reference texts; or

(3) As determined by the American Society for Testing and Materials Method D2879–83 (incorporated by reference as specified in § 63.14 of subpart A of this part); or

(4) Any other method approved by the Administrator.

Partially soluble HAP means HAP listed in Table 7 of this subpart.

Point of determination (POD) means each point where process wastewater exits the miscellaneous coating operations.

NOTE TO DEFINITION FOR POINT OF DETERMINATION: The regulation allows determination of the characteristics of a wastewater stream at the point of determination or downstream of the point of determination if corrections are made for changes in flow rate and annual average concentration of partially soluble and soluble HAP compounds as determined in § 63.144. Such changes include losses by air emissions; reduction of annual average concentration or changes in flow rate by mixing with other water or wastewater streams; and reduction in flow rate or

annual average concentration by treating or otherwise handling the wastewater stream to remove or destroy HAP.

Process vessel means any stationary or portable tank or other vessel with a capacity greater than or equal to 250 gal and in which mixing, blending, diluting, dissolving, temporary holding, and other processing steps occur in the manufacturing of a coating.

Process vessel vent means a vent from a process vessel or vents from multiple process vessels that are manifolded together into a common header, through which a HAP-containing gas stream is, or has the potential to be, released to the atmosphere. Emission streams that are undiluted and uncontrolled containing less than 50 ppmv HAP, as determined through process knowledge that no HAP are present in the emission stream or using an engineering assessment as discussed in § 63.1257(d)(2)(ii), test data using Method 18 of 40 CFR part 60, appendix A, or any other test method that has been validated according to the procedures in Method 301 of appendix A of this part, are not considered process vessel vents. Flexible elephant trunk systems when used with closed vent systems and drawing ambient air (*i.e.,* the system is not ducted, piped, or otherwise connected to the unit operations) away from operators when vessels are opened are not process vessel vents. Process vessel vents do not include vents on storage tanks, wastewater emission sources, or pieces of equipment subject to the requirements in Table 3 of this subpart. A gas stream going to a fuel gas system is not a process vessel vent. A gas stream routed to a process for a process purpose is not a process vessel vent.

Recovery device, as used in the wastewater provisions, means an individual unit of equipment used for the purpose of recovering chemicals for fuel value (*i.e.,* net positive heating value), use, reuse, or for sale for fuel value, use, or reuse. Examples of equipment that may be recovery devices include organic removal devices such as decanters, strippers, or thin-film evaporation units. To be a recovery device, a decanter and any other equipment based on the operating principle of gravity separation must receive only multiphase liquid streams. A recovery device is considered part of the miscellaneous coating manufacturing operations.

Responsible official means responsible official as defined in 40 CFR 70.2.

Safety device means a closure device such as a pressure relief valve, frangible disc, fusible plug, or any other type of device which functions exclusively to prevent physical damage or permanent deformation to a unit or its air emission control equipment by venting gases or vapors directly to the atmosphere during unsafe conditions resulting from an unplanned, accidental, or emergency event. For the purposes of this subpart, a safety device is not used for routine venting of gases or vapors from the vapor headspace underneath a cover such as during filling of the unit or to adjust the pressure in response to normal daily diurnal ambient temperature fluctuations. A safety device is designed to remain in a closed position during normal operations and open only when the internal pressure, or another relevant parameter, exceeds the device threshold setting applicable to the air emission control equipment as determined by the owner or operator based on manufacturer recommendations, applicable regulations, fire protection and prevention codes and practices, or other requirements for the safe handling of flammable, combustible, explosive, reactive, or hazardous materials.

Shutdown means the cessation of operation of an affected source, any process vessels within an affected source, or equipment required or used to comply with this subpart if steps taken to cease operation differ from those under routine procedures for removing the vessel or equipment from service. Shutdown also applies to the emptying and degassing of storage tanks.

Soluble HAP means the HAP listed in Table 8 of this subpart.

Startup means the setting in operation of a new affected source. For new equipment added to an affected source, including equipment required or used to comply with this subpart, startup means the first time the equipment is put into operation. Startup includes the setting in operation of equipment any time the steps taken differ from

routine procedures for putting the equipment into operation.

Storage tank means a tank or other vessel that is used to store organic liquids that contain one or more HAP as raw material feedstocks or products. The following are not considered storage tanks for the purposes of this subpart:

(1) Vessels permanently attached to motor vehicles such as trucks, railcars, barges, or ships;

(2) Pressure vessels designed to operate in excess of 204.9 kilopascals and without emissions to the atmosphere;

(3) Vessels storing organic liquids that contain HAP only as impurities;

(4) Wastewater storage tanks; and

(5) Process vessels.

Total organic compounds or (TOC) means the total gaseous organic compounds (minus methane and ethane) in a vent stream.

Wastewater storage tank means a stationary structure that is designed to contain an accumulation of wastewater and is constructed primarily of nonearthen materials (*e.g.*, wood, concrete, steel, plastic) which provide structural support.

Wastewater stream means water that is discarded from miscellaneous coating manufacturing operations through a POD, and that contains an annual average concentration of total partially soluble and soluble HAP compounds of at least 1,600 ppmw at any flow rate. For the purposes of this subpart, noncontact cooling water is not considered a wastewater stream.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the Clean Air Act.

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25682, May 13, 2005; 71 FR 58503, Oct. 4, 2006; 85 FR 49747, Aug. 14, 2020; 88 FR 10850, Feb. 22, 2023]

TABLE 1 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR PROCESS VESSELS

TABLE 1 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR PROCESS VESSELS

[As required in § 63.8005, you must meet each emission limit and work practice standard in the following table that applies to your process vessels.]

For each . . .	You must . . .	And you must . . .
1. Portable process vessel at an existing source.	a. Equip the vessel with a cover or lid that must be in place at all times when the vessel contains a HAP, except for material additions and sampling.	Nonapplicable.
2. Stationary process vessel at an existing source.	a. Equip the vessel with a cover or lid that must be in place at all times when the vessel contains a HAP, except for material additions and sampling; or b. Equip the vessel with a tightly fitting vented cover or lid that must be closed at all times when the vessel contains HAP, except for material additions and sampling. c. As specified in § 63.8005(i), on or before February 22, 2024, during the addition of dry material, route material containing metal HAP to a capture and control system that is maintained and operated according to the provisions of § 63.8005.	i. Considering both capture and any combination of control (except a flare), reduce emissions of organic HAP with a vapor existing pressure ≥0.6 kPa by ≥75 percent by weight, and reduce emissions of organic HAP with a vapor pressure <0.6 kPa by ≥60 percent by weight. i. Reduce emissions of organic HAP with a vapor pressure ≥0.6 kPa by ≥75 percent by weight, and reduce emissions of organic HAP with a vapor pressure <0.6 kPa by ≥60 percent by weight, by venting emissions through a closed-vent system to any combination of control devices (except a flare); or ii. Reduce emissions of total organic HAP by venting emissions from a non-halogenated vent stream through a closed-vent system to a flare; or

TABLE 1 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR PROCESS VESSELS—Continued

[As required in § 63.8005, you must meet each emission limit and work practice standard in the following table that applies to your process vessels.]

For each . . .	You must . . .	And you must . . .
		iii. Reduce emissions of total organic HAP by venting emissions through a closed-vent system to a condenser that reduces the outlet gas temperature to: <10 °C if the process vessel contains HAP with a partial pressure <0.6 kPa, or <2 °C if the process vessel contains HAP with a partial pressure ≥0.6 kPa and <17.2 kPa, or <−5 °C if the process vessel contains HAP with a partial pressure ≥17.2 kPa. i. Reduce emissions of material containing metal HAP to 0.014 gr/dscf or less.
3. Portable and stationary process vessel at a new source.	a. Equip the vessel with a tightly fitting vented cover or lid that must be closed at all times when the vessel contains HAP, except for material additions and sampling. b. As specified in § 63.8005(i), upon startup or February 22, 2023, whichever is later, during the addition of dry material, route material containing metal HAP to a capture and control system that is maintained and operated according to the provisions of § 63.8005.	i. Reduce emissions of total organic HAP by ≥95 percent by weight by venting emissions through a closed-vent system to any combination of control devices (except a flare); or ii. Reduce emissions of total organic HAP by venting emissions from a non-halogenated vent stream through a closed-vent system to a flare; or iii. Reduce emissions of total organic HAP by venting emissions through a closed-vent system to a condenser that reduces the outlet gas temperature to: <−4 °C if the process vessel contains HAP with a partial pressure <0.7 kPa, or <−20 °C if the process vessel contains HAP with a partial pressure ≥0.7 kPa and <17.2 kPa, or <−30 °C if the process vessel contains HAP with a partial pressure ≥17.2 kPa. i. Reduce emissions of material containing metal HAP to 0.0079 gr/dscf or less.
4. Halogenated vent stream from a process vessel subject to the requirements of item 2 or 3 of this table for which you use a combustion control device to control organic HAP emissions.	a. Use a halogen reduction device after the combustion control device; or. b. Use a halogen reduction device before the combustion control device.	i. Reduce overall emissions of hydrogen halide and halogen HAP by ≥95 percent; or ii. Reduce overall emissions of hydrogen halide and halogen HAP to ≤0.45 kilogram per hour (kg/hr). Reduce the halogen atom mass emission rate to ≤0.45 kg/hr.

[88 FR 10850, Feb. 22, 2023]

TABLE 2 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS FOR STORAGE TANKS

As required in § 63.8010, you must meet each emission limit in the following table that applies to your storage tanks.

For each . . .	Then you must . . .
1. Group 1a storage tank	a. Comply with the requirements of subpart WW of this part, except as specified in § 63.8010(b); or b. Reduce total organic HAP emissions from the storage tank by ≥90 percent by weight by venting emissions through a closed-vent system to any combination of control devices (excluding a flare); or c. Reduce total organic HAP emissions from the storage tank by venting emissions from a non-halogenated vent stream through a closed-vent system to a flare.
2. Group 1b storage tank	a. Comply with the requirements of subpart WW of this part, except as specified in § 63.8010(b); or b. Reduce total organic HAP emissions from the storage tank by ≥80 percent by weight by venting emissions through a closed-vent system to any combination of control devices (excluding a flare); or c. Reduce total organic HAP emissions from the storage tank by venting emissions from a non-halogenated vent stream through a closed-vent system to a flare.

TABLE 3 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR EQUIPMENT LEAKS

As required in § 63.8015, you must meet each requirement in the following table that applies to your equipment leaks.

TABLE 3 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR EQUIPMENT LEAKS

For all . . .	You must . . .
1. Equipment that is in organic HAP service at an existing source.	a. Comply with the requirements in §§ 63.424(a) through (d) and 63.428(e), (f), and (h)(4), except as specified in § 63.8015(b); or b. Comply with the requirements of subpart TT of this part, except as specified in § 63.8000(f); or c. Comply with the requirements of subpart UU of this part, except as specified in §§ 63.8000(f) and 63.8015(c) and (d).
2. Equipment that is in organic HAP service at a new source ...	a. Comply with the requirements of subpart TT of this part, except as specified in § 63.8000(f); or b. Comply with the requirements of subpart UU of this part, except as specified in §§ 63.8000(f) and 63.8015(c) and (d).

[85 FR 49747, Aug. 14, 2020]

TABLE 4 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR WASTEWATER STREAMS

As required in § 63.8020, you must meet each emission limit and work practice standard in the following table that applies to your wastewater streams.

For each . . .	You must . . .
1. Wastewater tank used to store a Group 1 wastewater stream.	Maintain a fixed roof, which may have openings necessary for proper venting of the tank, such as pressure/vacuum vent or j-pipe vent.
2. Group 1 wastewater stream.	a. Convey using hard-piping and treat the wastewater as a hazardous waste in accordance with 40 CFR part 264, 265, or 266 either onsite or offsite; or b. If the wastewater contains <50 ppmw of partially soluble HAP, you may elect to treat the wastewater in an enhanced biological treatment system that is located either onsite or offsite.

TABLE 5 TO SUBPART HHHHH OF PART 63—EMISSION LIMITS AND WORK PRACTICE STANDARDS FOR TRANSFER OPERATIONS

As required in § 63.8025, you must meet each emission limit and work practice standard in the following table that applies to your transfer operations.

For each . . .	You must. . . .
1. Group 1 transfer operation vent stream.	a. Reduce emissions of total organic HAP by ≥75 percent by weight by venting emissions through a closed-vent system to any combination of control devices (except a flare); or b. Reduce emissions of total organic HAP by venting emissions from a non-halogenated vent stream through a closed-vent system to a flare; or

For each . . .	You must. . . .
	c. Use a vapor balancing system designed and operated to collect organic HAP vapors displaced from tank trucks and railcars during loading and route the collected HAP vapors to the storage tank from which the liquid being loaded originated or to another storage tank connected by a common header.
2. Halogenated Group 1 transfer operation vent stream for which you use a combustion device to control organic HAP emissions.	a. Use a halogen reduction device after the combustion device to reduce emissions of hydrogen halide and halogen HAP by ≥95 percent by weight or to ≤0.45 kg/hr; or b. Use a halogen reduction device before the combustion device to reduce the halogen atom mass emission rate to ≤0.45 kg/hr.

TABLE 6 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR HEAT EXCHANGE SYSTEMS

As required in § 63.8030, you must meet each requirement in the following table that applies to your heat exchange systems.

For each . . .	You must . . .
Heat exchange system, as defined in § 63.101.	Comply with the requirements in § 63.104, except as specified in § 63.8030.

TABLE 7 TO SUBPART HHHHH OF PART 63—PARTIALLY SOLUBLE HAZARDOUS AIR POLLUTANTS

As specified in § 63.8020, the partially soluble HAP in wastewater that are subject to management and treatment requirements in this subpart are listed in the following table:

TABLE 7 TO SUBPART HHHHH OF PART 63—PARTIALLY SOLUBLE HAZARDOUS AIR POLLUTANTS

Chemical name . . .	CAS No.
1. 1,1,1-Trichloroethane (methyl chloroform)	71556
2. 1,1,2,2-Tetrachloroethane	79345
3. 1,1,2-Trichloroethane	79005
4. 1,1-Dichloroethylene (vinylidene chloride)	75354
5. 1,2-Dibromoethane	106934
6. 1,2-Dichloroethane (ethylene dichloride)	107062
7. 1,2-Dichloropropane	78875
8. 1,3-Dichloropropene	542756
9. 2,4,5-Trichlorophenol	95954
10. 1,4-Dichlorobenzene	106467
11. 2-Nitropropane	79469
12. 4-Methyl-2-pentanone (MIBK)	108101
13. Acetaldehyde	75070
14. Acrolein	107028
15. Acrylonitrile	107131
16. Allyl chloride	107051
17. Benzene	71432
18. Benzyl chloride	100447
19. Biphenyl	92524
20. Bromoform (tribromomethane)	75252
21. Bromomethane	74839
22. Butadiene	106990
23. Carbon disulfide	75150
24. Chlorobenzene	108907
25. Chloroethane (ethyl chloride)	75003
26. Chloroform	67663
27. Chloromethane	74873
28. Chloroprene	126998
29. Cumene	98828
30. Dichloroethyl ether	111444
31. Dinitrophenol	51285
32. Epichlorohydrin	106898
33. Ethyl acrylate	140885
34. Ethylbenzene	100414
35. Ethylene oxide	75218
36. Ethylidene dichloride	75343
37. Hexachlorobenzene	118741
38. Hexachlorobutadiene	87683

TABLE 7 TO SUBPART HHHHH OF PART 63—PARTIALLY SOLUBLE HAZARDOUS AIR POLLUTANTS—Continued

Chemical name . . .	CAS No.
39. Hexachloroethane	67721
40. Methyl methacrylate	80626
41. Methyl-t-butyl ether	1634044
42. Methylene chloride	75092
43. N-hexane	110543
44. N,N-dimethylaniline	121697
45. Naphthalene	91203
46. Phosgene	75445
47. Propionaldehyde	123386
48. Propylene oxide	75569
49. Styrene	100425
50. Tetrachloroethylene (perchloroethylene)	127184
51. Tetrachloromethane (carbon tetrachloride)	56235
52. Toluene	108883
53. Trichlorobenzene (1,2,4-)	120821
54. Trichloroethylene	79016
55. Trimethylpentane	540841
56. Vinyl acetate	108054
57. Vinyl chloride	75014
58. Xylene (m)	108383
59. Xylene (o)	95476
60. Xylene (p)	106423

[85 FR 49748, Aug. 14, 2020]

TABLE 8 TO SUBPART HHHHH OF PART 63—SOLUBLE HAZARDOUS AIR POLLUTANTS

As specified in §63.8020, the soluble HAP in wastewater that are subject to management and treatment requirements of this subpart are listed in the following table:

Chemical name . . .	CAS No.
1. Acetonitrile	75058
2. Acetophenone	98862
3. Diethyl sulfate	64675
4. Dimethyl hydrazine (1,1)	57147
5. Dimethyl sulfate	77781
6. Dinitrotoluene (2,4)	121142
7. Dioxane (1,4)	123911
8. Ethylene glycol dimethyl ether	110714
9. Ethylene glycol monobutyl ether acetate	112072
10. Ethylene glycol monomethyl ether acetate	110496
11. Isophorone	78591
12. Methanol	67561
13. Nitrobenzene	98953
14. Toluidine (o-)	95534
15. Triethylamine	121448

[68 FR 69185, Dec. 11, 2003, as amended at 70 FR 25683, May 13, 2005; 85 FR 49749, Aug. 14, 2020]

TABLE 9 TO SUBPART HHHHH OF PART 63—REQUIREMENTS FOR REPORTS

As required in §63.8075(a) and (b), you must submit each report that applies to you on the schedule shown in the following table:

You must submit a . . .	The report must contain . . .	You must submit the report . . .
1. Precompliance report	The information specified in §63.8075(c)	At least 6 months prior to the compliance date; or for new sources, with the application for approval of construction or reconstruction.
2. Notification of compliance status report	The information specified in §63.8075(d)	No later than 150 days after the compliance date specified in §63.7995.
3. Compliance report	The information specified in §63.8075(e)	Semiannually according to the requirements in §63.8075(b).

You must submit a . . .	The report must contain . . .	You must submit the report . . .
4. Performance test report	The information specified in § 63.8075(f)	Within 60 days after completing each performance test according to the requirements in § 63.8075(f).
5. Performance evaluation report	The information specified in § 63.8075(g)	Within 60 days after completing each CMS performance evaluation according to the requirements in § 63.8075(g).

[68 FR 69185, Dec. 11, 2003, as amended at 85 FR 49749, Aug. 14, 2020]

TABLE 10 TO SUBPART HHHHH OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART

As specified in § 63.8095, the parts of the general provisions that apply to you are shown in the following table:

TABLE 10 TO SUBPART HHHHH OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART

Citation	Subject	Explanation
§ 63.1	Applicability	Yes.
§ 63.2	Definitions	Yes.
§ 63.3	Units and Abbreviations	Yes.
§ 63.4	Prohibited Activities	Yes.
§ 63.5	Construction/Reconstruction	Yes.
§ 63.6(a)	Applicability	Yes.
§ 63.6(b)(1)–(4)	Compliance Dates for New and Reconstructed sources.	Yes.
§ 63.6(b)(5)	Notification	Yes.
§ 63.6(b)(6)	[Reserved].	
§ 63.6(b)(7)	Compliance Dates for New and Reconstructed Area Sources That Become Major.	Yes.
§ 63.6(c)(1)–(2)	Compliance Dates for Existing Sources	Yes.
§ 63.6(c)(3)–(4)	[Reserved].	
§ 63.6(c)(5)	Compliance Dates for Existing Area Sources That Become Major.	Yes.
§ 63.6(d)	[Reserved].	
§ 63.6(e)(1)(i)	General Duty to Minimize Emissions	Yes, before the compliance date specified in § 63.7995(e). No, on and after the compliance date specified in § 63.7995(e). See § 63.8000(e) for the general duty requirement.
§ 63.6(e)(1)(ii)	Requirement to Correct Malfunctions as Soon as Possible.	Yes, before the compliance date specified in § 63.7995(e). No, on and after the compliance date specified in § 63.7995(e).
§ 63.6(e)(1)(iii)–(2)	Operation and Maintenance	Yes.
§ 63.6(e)(3)	SSM Plan	Yes, before the compliance date specified in § 63.7995(e). No, on and after the compliance date specified in § 63.7995(e).
§ 63.6(f)(1)	Compliance with Non-Opacity Standards Except During SSM.	No. See § 63.8000(a).
§ 63.6(f)(2)–(3)	Methods for Determining Compliance	Yes.
§ 63.6(g)(1)–(3)	Alternative Standard	Yes.
§ 63.6(h)(1)	Compliance with Opacity/Visible Emission (VE) Standards Except During SSM.	No. See § 63.8000(a).
§ 63.6(h)(2)–(9)	Opacity/VE Standards	Only for flares for which Method 22 of 40 CFR part 60, appendix A–7, observations are required as part of a flare compliance assessment.
§ 63.6(i)(1)–(14)	Compliance Extension	Yes.

TABLE 10 TO SUBPART HHHHH OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART—Continued

Citation	Subject	Explanation
§ 63.6(j)	Presidential Compliance Exemption	Yes.
§ 63.7(a)(1)–(2)	Performance Test Dates	Yes, except substitute 150 days for 180 days.
§ 63.7(a)(3)–(4)	CAA Section 114 Authority, Force Majeure.	Yes, and these paragraphs also apply to flare compliance assessments as specified under § 63.997(b)(2).
§ 63.7(b)(1)	Notification of Performance Test	Yes.
§ 63.7(b)(2)	Notification of Rescheduling	Yes.
§ 63.7(c)	Quality Assurance/Test Plan	Yes, except the test plan must be submitted with the notification of the performance test if the control device controls process vessels.
§ 63.7(d)	Testing Facilities	Yes.
§ 63.7(e)(1)	Conditions for Conducting Performance Tests.	Yes, before the compliance date specified in § 63.7995(e), except that performance tests for process vessels must be conducted under worst-case conditions as specified in § 63.8005. No, on and after the compliance date specified in § 63.7995(e). See § 63.8005(d).
§ 63.7(e)(2)	Conditions for Conducting Performance Tests.	Yes.
§ 63.7(e)(3)	Test Run Duration	Yes.
§ 63.7(f)	Alternative Test Method	Yes.
§ 63.7(g)	Performance Test Data Analysis	Yes.
§ 63.7(h)	Waiver of Tests	Yes.
§ 63.8(a)(1)	Applicability of Monitoring Requirements.	Yes.
§ 63.8(a)(2)	Performance Specifications	Yes.
§ 63.8(a)(3)	[Reserved].	
§ 63.8(a)(4)	Monitoring with Flares	Yes.
§ 63.8(b)(1)	Monitoring	Yes.
§ 63.8(b)(2)–(3)	Multiple Effluents and Multiple Monitoring Systems.	Yes.
§ 63.8(c)(1)	Monitoring System Operation and Maintenance.	Yes.
§ 63.8(c)(1)(i)	Maintain and operate CMS	Yes, before the compliance date specified in § 63.7995(e). No, on and after the compliance date specified in § 63.7995(e). See § 63.8000(e) for the general duty to maintain and operate each CMS.
§ 63.8(c)(1)(ii)	Routine repairs	Yes.
§ 63.8(c)(1)(iii)	Requirement to develop SSM plan for CMS.	Yes, before the compliance date specified in § 63.7995(e). No, on and after the compliance date specified in § 63.7995(e).
§ 63.8(c)(2)–(3)	Monitoring System Installation	Yes.
§ 63.8(c)(4)	Requirements	Only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part. This subpart does not contain requirements for continuous opacity monitoring systems (COMS).
§ 63.8(c)(4)(i)	CMS Requirements	No. This subpart does not require COMS.
§ 63.8(c)(4)(ii)	CMS requirements	Yes.
§ 63.8(c)(5)	COMS Minimum Procedures	No. This subpart does not contain opacity or VE limits.

TABLE 10 TO SUBPART HHHHH OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART—Continued

Citation	Subject	Explanation
§63.8(c)(6)	CMS Requirements	Only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part.
§63.8(c)(7)–(8)	CMS Requirements	Only for CEMS. Requirements for CPMS are specified in referenced subpart SS of this part.
§63.8(d)(1)–(2)	CMS Quality Control	Only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part.
§63.8(d)(3)	Written procedures for CMS	Yes, before the compliance date specified in §63.7995(e). No, on and after the compliance date specified in §63.7995(e). See §63.8000(d)(8).
§63.8(e)	CMS Performance Evaluation	Section 63.8(e)(6)(ii) does not apply because this subpart does not require COMS. Other sections apply only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part.
§63.8(f)(1)–(5)	Alternative Monitoring Method	Yes, except you may also request approval using the precompliance report.
§63.8(f)(6)	Alternative to Relative Accuracy Test	Only for CEMS.
§63.8(g)(1)–(4)	Data Reduction	Only when using CEMS, except §63.8(g)(2) does not apply because data reduction requirements for CEMS are specified in §63.8000(d)(4)(iv). The requirements for COMS do not apply because this subpart has no opacity or VE limits.
§63.8(g)(5)	Data Reduction	No. Requirements for CEMS are specified in §63.8000(d)(4). Requirements for CPMS are specified in referenced subpart SS of this part.
§63.9(a)	Notification Requirements	Yes.
§63.9(b)(1)–(5)	Initial Notifications	Yes.
§63.9(c)	Request for Compliance Extension	Yes.
§63.9(d)	Notification of Special Compliance Requirements for New Source.	Yes.
§63.9(e)	Notification of Performance Test	Yes.
§63.9(f)	Notification of VE/Opacity Test	No. This subpart does not contain opacity or VE limits.
§63.9(g)	Additional Notifications When Using CMS.	Only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part.
§63.9(h)(1)–(6)	Notification of Compliance Status	Yes, except this subpart has no opacity or VE limits, and §63.9(h)(2) does not apply because §63.8075(d) specifies the required contents and due date of the notification of compliance status report.
§63.9(i)	Adjustment of Submittal Deadlines	Yes.
§63.9(j)	Change in previous information	Yes, for change in major source status, otherwise §63.8075(e)(8) specifies reporting requirements for process changes.
§63.9(k)	Electronic reporting procedures	Yes, as specified in §63.9(j).
§63.10(a)	Recordkeeping/Reporting	Yes.
§63.10(b)(1)	Recordkeeping/Reporting	Yes.

TABLE 10 TO SUBPART HHHHH OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO THIS SUBPART—Continued

Citation	Subject	Explanation
§ 63.10(b)(2)(i)–(ii)	Records related to SSM	No. Before the compliance date specified in § 63.7995(e), see § 63.998(c)(1)(ii)(D) through (G) and (d)(3) for recordkeeping requirements for periods of SSM. On and after the compliance date specified in § 63.7995(e), see § 63.8080(i).
§ 63.10(b)(2)(iii)	Records related to maintenance of air pollution control equipment.	Yes.
§ 63.10(b)(2)(iv)–(v)	Records related to SSM	Yes, before the compliance date specified in § 63.7995(e). No, on and after the compliance date specified in § 63.7995(e).
§ 63.10(b)(2)(vi), (x), and (xi).	CMS Records	Only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part.
§ 63.10(b)(2)(vii)–(ix)	Records	Yes.
§ 63.10(b)(2)(xii)	Records	Yes.
§ 63.10(b)(2)(xiii)	Records	Yes.
§ 63.10(b)(2)(xiv)	Records	Yes.
§ 63.10(b)(3)	Records	Yes.
§ 63.10(c)(1)–(6), (9)–(14)	Records	Only for CEMS; requirements for CPMS are specified in referenced subpart SS of this part.
§ 63.10(c)(7)–(8), (15)	Records	No. Recordkeeping requirements are specified in § 63.8080.
§ 63.10(d)(1)	General Reporting Requirements	Yes.
§ 63.10(d)(2)	Report of Performance Test Results	Yes.
§ 63.10(d)(3)	Reporting Opacity or VE Observations	No. This subpart does not contain opacity or VE limits.
§ 63.10(d)(4)	Progress Reports	Yes.
§ 63.10(d)(5)(i)	SSM Reports	No. Before the compliance date specified in § 63.7995(e), see § 63.8075(e)(5) and (6) for the SSM reporting requirements. On and after the compliance date specified in § 63.7995(e), these requirements no longer apply.
§ 63.10(d)(5)(ii)	Immediate SSM reports	No.
§ 63.10(e)(1)–(2)	Additional CMS Reports	Only for CEMS, but § 63.10(e)(2)(ii) does not apply because this subpart does not require COMS.
§ 63.10(e)(3)	Reports	No. Reporting requirements are specified in § 63.8075.
§ 63.10(e)(3)(i)–(iii)	Reports	No. Reporting requirements are specified in § 63.8075.
§ 63.10(e)(3)(iv)–(v)	Excess Emissions Reports	No. Reporting requirements are specified in § 63.8075.
§ 63.10(e)(3)(vi–viii)	Excess Emissions Report and Summary Report.	No. Reporting requirements are specified in § 63.8075.
§ 63.10(e)(4)	Reporting COMS data	No. This subpart does not contain opacity or VE limits.
§ 63.10(f)	Waiver for Recordkeeping/Reporting	Yes.
§ 63.11	Control and work practice requirements	Yes.
§ 63.12	Delegation	Yes.
§ 63.13	Addresses	Yes.
§ 63.14	Incorporation by Reference	Yes.
§ 63.15	Availability of Information	Yes.

[85 FR 49749, Aug. 14, 2020, as amended at 85 FR 73914, Nov. 19, 2020]

TABLE 11 TO SUBPART HHHHH OF PART 63— LIST OF HAZARDOUS AIR POLLUTANTS THAT MUST BE COUNTED TOWARD TOTAL ORGANIC HAP CONTENT IF PRESENT AT 0.1 PERCENT OR MORE BY MASS

TABLE 11 TO SUBPART HHHHH OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS THAT MUST BE COUNTED TOWARD TOTAL ORGANIC HAP CONTENT IF PRESENT AT 0.1 PERCENT OR MORE BY MASS

Chemical name	CAS No.
1,1,2,2-Tetrachloroethane	79–34–5
1,1,2-Trichloroethane	79–00–5
1,1-Dimethylhydrazine	57–14–7
1,2-Dibromo-3-chloropropane	96–12–8
1,2-Diphenylhydrazine	122–66–7
1,3-Butadiene	106–99–0
1,3-Dichloropropene	542–75–6
1,4-Dioxane	123–91–1
2,4,6-Trichlorophenol	88–06–2
2,4/2,6-Dinitrotoluene (mixture)	25321–14–6
2,4-Dinitrotoluene	121–14–2
2,4-Toluene diamine	95–80–7
2-Nitropropane	79–46–9
3,3′-Dichlorobenzidine	91–94–1
3,3′-Dimethoxybenzidine	119–90–4
3,3′-Dimethylbenzidine	119–93–7
4,4′-Methylene bis(2-chloroaniline)	101–14–4
Acetaldehyde	75–07–0
Acrylamide	79–06–1
Acrylonitrile	107–13–1
Allyl chloride	107–05–1
alpha-Hexachlorocyclohexane (a-HCH)	319–84–6
Aniline	62–53–3
Benzene	71–43–2
Benzidine	92–87–5
Benzotrichloride	98–07–7
Benzyl chloride	100–44–7
beta-Hexachlorocyclohexane (b-HCH)	319–85–7
Bis(2-ethylhexyl)phthalate	117–81–7
Bis(chloromethyl)ether	542–88–1
Bromoform	75–25–2
Captan	133–06–2
Carbon tetrachloride	56–23–5
Chlordane	57–74–9
Chlorobenzilate	510–15–6
Chloroform	67–66–3
Chloroprene	126–99–8
Cresols (mixed)	1319–77–3
DDE	3547–04–4
Dichloroethyl ether	111–44–4
Dichlorvos	62–73–7
Epichlorohydrin	106–89–8
Ethyl acrylate	140–88–5
Ethylene dibromide	106–93–4
Ethylene dichloride	107–06–2
Ethylene oxide	75–21–8
Ethylene thiourea	96–45–7
Ethylidene dichloride (1,1-Dichloroethane)	75–34–3
Formaldehyde	50–00–0
Heptachlor	76–44–8
Hexachlorobenzene	118–74–1
Hexachlorobutadiene	87–68–3
Hexachloroethane	67–72–1
Hydrazine	302–01–2
Isophorone	78–59–1
Lindane (hexachlorocyclohexane, all isomers)	58–89–9
m-Cresol	108–39–4
Methylene chloride	75–09–2
Naphthalene	91–20–3
Nitrobenzene	98–95–3
Nitrosodimethylamine	62–75–9
o-Cresol	95–48–7
o-Toluidine	95–53–4
Parathion	56–38–2
p-Cresol	106–44–5
p-Dichlorobenzene	106–46–7

TABLE 11 TO SUBPART HHHHH OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS THAT MUST BE COUNTED TOWARD TOTAL ORGANIC HAP CONTENT IF PRESENT AT 0.1 PERCENT OR MORE BY MASS—Continued

Chemical name	CAS No.
Pentachloronitrobenzene	82–68–8
Pentachlorophenol	87–86–5
Propoxur	114–26–1
Propylene dichloride	78–87–5
Propylene oxide	75–56–9
Quinoline	91–22–5
Tetrachloroethene	127–18–4
Toxaphene	8001–35–2
Trichloroethylene	79–01–6
Trifluralin	1582–09–8
Vinyl bromide	593–60–2
Vinyl chloride	75–01–4
Vinylidene chloride	75–35–4

[85 FR 49751, Aug. 14, 2020]

Subpart IIIII—National Emission Standards for Hazardous Air Pollutants for Mercury Cell Chlor-Alkali Plants

SOURCE: 68 FR 70928, Dec. 19, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.8180 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for affected sources at mercury cell chlor-alkali plants. This subpart also establishes requirements to demonstrate initial and continuous compliance with all applicable emission limitations and work practice standards in this subpart.

[87 FR 27018, May 6, 2022]

§ 63.8182 Am I subject to this subpart?

(a) You are subject to this subpart if you own or operate a mercury cell chlor-alkali plant.

(b) You are required to obtain a title V permit, whether your affected source is a part of a major source of hazardous air pollutant (HAP) emissions or a part of an area source of HAP emissions. A major source of HAP is a source that emits or has the potential to emit any single HAP at a rate of 10 tons or more per year or any combination of HAP at a rate of 25 tons or more per year. An area source of HAP is a source that has the potential to emit HAP but is not a major source. Nothing in this subpart revises how affected sources are aggregated for purposes of determining whether an affected source is a part of an area, nonmajor, or major source under any provisions of the Clean Air Act (CAA) or EPA's regulations. For information on aggregating affected sources to determine what is a source under title V, see the definition of major source in 40 CFR 70.2, 71.2 and 63.2.

(c) Beginning on December 19, 2006, the provisions of subpart E of 40 CFR part 61 that apply to mercury cell chlor-alkali plants, which are listed in paragraphs (c)(1) through (3) of this section, are no longer applicable.

(1) § 61.52(a);

(2) § 61.53(b) and (c); and

(3) § 61.55(b), (c) and (d).

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27018, May 6, 2022]

§ 63.8184 What parts of my plant does this subpart cover?

(a) This subpart applies to each affected source at a plant site where chlorine and caustic are produced in mercury cells. This subpart applies to two types of affected sources: the mercury cell chlor-alkali production facility, as defined in paragraph (a)(1) of this section; and the mercury recovery facility, as defined in paragraph (a)(2) of this section.

(1) The mercury cell chlor-alkali production facility designates an affected

source consisting of all cell rooms and ancillary operations used in the manufacture of product chlorine, product caustic, and by-product hydrogen at a plant site. This subpart covers mercury emissions from by-product hydrogen streams and end box ventilation system vents, mercury fugitive emissions associated with cell rooms, hydrogen systems, caustic systems, and storage areas for mercury-containing wastes; and chlorine fugitive emissions associated with the mercury cell chlor-alkali production facility.

(2) The mercury recovery facility designates an affected source consisting of all processes and associated operations needed for mercury recovery from wastes at a plant site. This subpart covers mercury emissions from mercury thermal recovery unit vents and fugitive emission sources of mercury associated with storage areas for mercury-containing wastes.

(b) An affected source at your mercury cell chlor-alkali plant is existing if you commenced construction of the affected source before July 3, 2002.

(c) A mercury recovery facility is a new affected source if you commence construction or reconstruction of the affected source after July 3, 2002. An affected source is reconstructed if it meets the definition of ''reconstruction'' in § 63.2.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27018, May 6, 2022]

§ 63.8186 When do I have to comply with this subpart?

(a) If you have an existing affected source, you must comply according to the dates specified in paragraphs (a)(1) through (5) of this section, as applicable.

(1) You must comply with each emission limitation, each work practice standard specified in paragraphs § 63.8192(a) through (f) or each work practice standard in paragraphs § 63.8192(e) through (g), and with each recordkeeping and reporting requirement in this subpart that applies to you by December 19, 2006, except as specified in paragraphs (a)(2) through (5) of this section.

(2) You must comply with each work practice standard in § 63.8192(a) through (c) and (e) through (h) and the electronic reporting requirements in § 63.8232(g), § 63.8252(g), and § 63.8254(e) by November 7, 2022.

(3) Until November 7, 2022, you must comply with the requirements in § 63.8226(a) and the requirements specified in the startup, shutdown, and malfunction plan required at § 63.8226(b).

(4) On and after November 7, 2022, you must comply with the applicable requirements in paragraph § 63.8226(c).

(5) On and after May 6, 2025, you must comply with the emission limitations in § 63.8190(a)(2)(ii) and the notification requirement in § 63.8252(h).

(b) If you have a new or reconstructed mercury recovery facility and its initial startup date is on or before December 19, 2003, you must comply with each emission limitation, work practice standard, and recordkeeping and reporting requirement in this subpart that applies to you by December 19, 2003.

(c) If you have a new or reconstructed mercury recovery facility and its initial startup date is after December 19, 2003, you must comply with each emission limitation, work practice standard, and recordkeeping and reporting requirement in this subpart that applies to you upon initial startup.

(d) You must meet the notification and schedule requirements in § 63.8252. Several of these notifications must be submitted before the compliance date for your affected source(s).

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27019, May 6, 2022]

Emission Limitations and Work Practice Standards

§ 63.8190 What emission limitations must I meet?

(a) *Emission limits.* You must meet each emission limit in paragraphs (a)(1) through (3) of this section that applies to you.

(1) New or reconstructed mercury cell chlor-alkali production facility. Emissions of mercury are prohibited from a new or reconstructed mercury cell chlor-alkali production facility.

(2) Existing mercury cell chlor-alkali production facility. Until the compliance date listed in § 63.8186(a)(5), you must comply with paragraph (a)(2)(i) of

this section. On and after the compliance date listed in § 63.8186(a)(5), you must comply with paragraph (a)(2)(ii) of this section.

(i) During any consecutive 52-week period, you must not discharge to the atmosphere total mercury emissions in excess of the applicable limit in paragraph (a)(2)(i)(A) or (B) of this section calculated using the procedures in § 63.8243(a).

(A) 0.076 grams of mercury per megagram of chlorine produced (1.5×10^{-4} pounds of mercury per ton of chlorine produced) from all by-product hydrogen streams and all end box ventilation system vents when both types of emission points are present.

(B) 0.033 grams of mercury per megagram of chlorine produced (6.59×10^{-5} pounds of mercury per ton of chlorine produced) from all by-product hydrogen streams when end box ventilation systems are not present.

(ii) Emissions of mercury are prohibited from an existing mercury cell chlor-alkali production facility.

(3) New, reconstructed, or existing mercury recovery facility. You must not discharge to the atmosphere mercury emissions in excess of the applicable limit in paragraph (a)(3)(i) or (ii) of this section.

(i) 23 milligrams per dry standard cubic meter from each oven type mercury thermal recovery unit vent.

(ii) 4 milligrams per dry standard cubic meter from each non-oven type mercury thermal recovery unit vent.

(b) [Reserved]

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27019, May 6, 2022]

§ 63.8192 What work practice standards must I meet?

In accordance with the compliance dates specified in § 63.8186(a)(1), you must meet the work practice requirements specified in paragraphs (a) through (f) of this section. As an alternative to the requirements specified in paragraphs (a) through (d) of this section, you may choose to comply with paragraph (g) of this section. On and after the compliance date specified in § 63.8186(a)(2) and until the compliance date specified in § 63.8186(a)(5), you must meet the work practice requirements specified in paragraphs (a) through (c) and (e) through (h) of this section.

(a) You must meet the work practice standards in Tables 1 through 4 to this subpart.

(b) You must adhere to the response intervals specified in Tables 1 through 4 to this subpart at all times. Nonadherence to the intervals in Tables 1 through 4 to this subpart constitutes a deviation and must be documented and reported in the compliance report, as required by § 63.8254(b), with the date and time of the deviation, cause of the deviation, a description of the conditions, and time actual compliance was achieved.

(c) As provided in § 63.6(g), you may request to use an alternative to the work practice standards in Tables 1 through 4 to this subpart.

(d) You must institute a floor-level mercury vapor measurement program to limit the amount of mercury vapor in the cell room environment through periodic measurement of mercury vapor levels and actions to be taken when a floor-level mercury concentration action level is exceeded. The program must meet the requirements listed in paragraphs (d)(1) through (4) of this section. As specified in § 63.8252(e)(1)(i) to implement this program, you must prepare and submit to the Administrator a floor-level mercury vapor measurement plan which must contain the elements listed in Table 5 to this subpart.

(1) You must utilize a mercury measurement device described in of Table 6 to this subpart to measure the level of mercury vapor in the cell room at floor-level.

(2) You must conduct at least one floor-level mercury vapor measurement evaluation each half day. This evaluation must include three measurements of the mercury concentration at locations representative of the entire cell room floor area. The average of these measurements must be recorded as specified in § 63.8156(c)(1). At a minimum, you must measure the level of mercury vapor above mercury-containing cell room equipment, as well as areas around the cells, decomposers, or other mercury-containing equipment.

(3) You must establish a floor-level mercury concentration action level that is no higher than 0.05 milligrams per cubic meter (mg/m^3).

(4) If a mercury concentration greater than the action level is measured during any floor-level mercury vapor measurement evaluation, you must meet the requirements in either paragraph (d)(4)(i) or (ii) of this section.

(i) If you determine that the cause of the elevated mercury concentration is an open electrolyzer, decomposer, or other maintenance activity, you must record the information specified in paragraphs (d)(4)(i)(A) through (C) of this section.

(A) A description of the maintenance activity resulting in elevated mercury concentration;

(B) The time the maintenance activity was initiated and completed; and

(C) A detailed explanation how all the applicable requirements of Table 1 to this subpart were met during the maintenance activity.

(ii) If you determine that the cause of the elevated mercury concentration is not an open electrolyzer, decomposer, or other maintenance activity, you must follow the procedures specified in paragraphs (d)(4)(ii)(A) and (B) of this section until the floor-level mercury concentration falls below the floor-level mercury concentration action level. You must also keep all the associated records for these procedures as specified in Table 9 to this subpart.

(A) Within 1 hour of the time the floor-level mercury concentration action level was exceeded, you must conduct each inspection specified in Table 2 to this subpart in the area where the concentration higher than the floor-level mercury concentration action level was measured, with the exception of the cell room floor and the pillars and beam inspections. (B) You must also inspect all decomposers, hydrogen system piping up to the hydrogen header, and other potential locations of mercury vapor leaks in the area using a technique specified in Table 6 to this subpart. You must correct any problem identified during these inspections according to the requirements in Tables 2 and 3 to this subpart.

(e) You must prepare, submit, and operate according to a written washdown plan designed to minimize fugitive mercury emissions through routine washing of surfaces where liquid mercury could accumulate. The written plan must address the elements contained in Table 7 to this subpart.

(f) You must keep records of the mass of all virgin mercury added to cells on an annual basis.

(g) You must institute a cell room monitoring program to continuously monitor the mercury vapor concentration in the upper portion of each cell room and to take corrective actions as quickly as possible when elevated mercury vapor levels are detected. As specified in § 63.8252(e)(1)(iv), you must prepare and submit to the Administrator, a cell room monitoring plan containing the elements listed in Table 5 to this subpart and meet the requirements in paragraphs (g)(1) through (4) of this section.

(1) You must utilize mercury monitoring systems that meet the requirements of Table 8 to this subpart.

(2) You must establish an action level according to the requirements in paragraphs (g)(2)(i) through (iii) of this section.

(i) Beginning on the compliance date specified for your affected source in § 63.8186, measure and record the mercury concentration for at least 30 days using a system that meets the requirements of paragraph (g)(1) of this section.

(ii) Using the monitoring data collected according to paragraph (g)(1)(i) of this section, establish your action level at the 75th percentile of the data set.

(iii) Submit your action level as part of your Notification of Compliance Status report according to § 63.8252(e)(1).

(3) Beginning on the compliance date specified for your affected source in § 63.8186, you must continuously monitor the mercury concentration in the cell room. Failure to monitor and record the data according to § 63.8256(c)(4)(ii) for 75 percent of the time in any 6-month period constitutes a deviation.

(4) If the average mercury concentration for any 1-hour period exceeds the action level established according to paragraph (g)(2) of this section, you must meet the requirements in either

paragraph (g)(4)(i) or (ii) of this section.

(i) If you determine that the cause of the elevated mercury concentration is an open electrolyzer, decomposer, or other maintenance activity, you must record the information specified in paragraphs (g)(4)(i)(A) through (C) of this section.

(A) A description of the maintenance activity resulting in elevated mercury concentration;

(B) The time the maintenance activity was initiated and completed; and

(C) A detailed explanation how all the applicable requirements of Table 1 to this subpart were met during the maintenance activity.

(ii) If you determine that the cause of the elevated mercury concentration is not an open electrolyzer, decomposer, or other maintenance activity, you must follow the procedures specified in paragraphs (g)(4)(ii)(A) and (B) of this section until the mercury concentration falls below the action level. You must also keep all the associated records for these procedures as specified in Table 9 to this subpart.

(A) Within 1 hour of the time the action level was exceeded, you must conduct each inspection specified in Table 2 to this subpart, with the exception of the cell room floor and the pillars and beam inspections. You must correct any problem identified during these inspections in accordance with the requirements in Table 2 and 3 to this subpart.

(B) If the Table 2 inspections and subsequent corrective actions do not reduce the mercury concentration below the action level, you must inspect all decomposers, hydrogen system piping up to the hydrogen header, and other potential locations of mercury vapor leaks using a technique specified in Table 6 to this subpart. If a mercury vapor leak is identified, you must take the appropriate action specified in Table 3 to this subpart.

(h) You must comply with the requirements specified in paragraphs (h)(1) through (4) of this section to reduce fugitive chlorine emissions in the mercury cell chlor-alkali production facility affected source.

(1) You must identify each piece of equipment located throughout the mercury cell chlor-alkali production facility affected source that contains chlorine gas at a concentration of at least 5 percent by volume. You may identify equipment by a list or on a process or piping diagram. You may exclude equipment that is under negative pressure.

(2) You must install ambient chlorine sensors at the mercury cell chlor-alkali production facility affected source to measure the ambient chlorine concentration.

(i) Ambient chlorine sensors must have a detection limit of 0.5 ppmv or less.

(ii) The sensors must be operated continuously to obtain a measurement at least once each 15 minutes.

(iii) You must identify the location of the sensors by a list or on a process or piping diagram.

(iv) You must operate, calibrate, and maintain these sensors in accordance with manufacturer instructions.

(v) You must keep the necessary parts for routine repairs of the sensors readily available.

(3) You must perform inspections to identify leaks of chlorine using olfactory observations according to the schedules in paragraphs (h)(3)(i) and (ii) of this section. A leak is detected when there is an olfactory observation of a leak. If a leak is detected, you must comply with the repair provisions in paragraph (h)(4) of this section.

(i) At least once each 12 hours, you must inspect each piece of equipment located throughout the mercury cell chlor-alkali production facility affected source that contains chlorine gas at a concentration of greater than 5 percent by volume for chlorine leaks, excluding equipment that is under negative pressure.

(ii) Within 1 hour of detection of a 1-hour average chlorine concentration of 2 ppmv or greater by a sensor installed and operated in accordance with paragraph (h)(2) of this section, you must inspect each piece of equipment located throughout the mercury cell chlor-alkali production facility affected source that contains chlorine gas at a concentration of greater than 5 percent by volume for chlorine leaks, excluding equipment that is under negative pressure.

(4) You must undertake a first attempt at repair no later than 1 hour after the leak is detected, and the leak must be repaired no later than 72 hours after the leak is detected. A leak is repaired when there is no olfactory observation of a leak.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27019, May 6, 2022]

OPERATION AND MAINTENANCE REQUIREMENTS

§ 63.8222 What are my operation and maintenance requirements?

At all times you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standards have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, reports and inspection of the source.

[87 FR 27020, May 6, 2022]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.8226 What are my general requirements for complying with this subpart?

(a) Until November 7, 2022, you must be in compliance with the applicable emission limitations in § 63.8190 and the applicable work practice standards in § 63.8192 at all times, except during periods of startup, shutdown, and malfunction.

(b) Until November 7, 2022, you must develop and operate as specified by a written startup, shutdown, and malfunction plan (SSMP) according to the provisions in § 63.6(e)(3).

(c) On and after November 7, 2022, the provisions of paragraphs (a) and (b) of this section no longer apply, and you must be in compliance with the applicable emission limitations in § 63.8190 and the applicable work practice standards in § 63.8192 at all times.

[87 FR 27020, May 6, 2022]

INITIAL COMPLIANCE REQUIREMENTS

§ 63.8230 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) You must conduct a performance test no later than the compliance date that is specified in § 63.8186 for your affected source to demonstrate initial compliance with the applicable emission limit in § 63.8190(a)(2) for by-product hydrogen streams and end box ventilation system vents and the applicable emission limit in § 63.8190(a)(3) for mercury thermal recovery unit vents.

(b) For the applicable work practice standards in § 63.8192, you must demonstrate initial compliance within 30 calendar days after the compliance date that is specified for your affected source in § 63.8186.

§ 63.8232 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits?

You must conduct a performance test for each by-product hydrogen stream, end box ventilation system vent, and mercury thermal recovery unit vent according to the conditions detailed in paragraphs (a) through (d) of this section.

(a) You must conduct each performance test under conditions representative of normal operations. You may not conduct performance tests during periods of startup, shutdown, or malfunction. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(b) For each performance test, you must develop a site-specific test plan in accordance with § 63.7(c)(2).

(c) You must conduct at least three test runs to comprise a performance

test, as specified in § 63.7(e)(3) and in either paragraph (c)(1) or (2) of this section.

(1) The sampling time and sampling volume for each run must be at least 2 hours and 1.70 dry standard cubic meters (dscm). Mercury results below the analytical laboratory's detection limit must be reported using the reported analytical detection limit to calculate the sample concentration value and, in turn, the emission rate in the units of the standard; or

(2) The sampling time for each test run must be at least 2 hours and the mercury concentration in each field sample analyzed must be at least two times the reported analytical detection limit.

(d) You must use the test methods specified in paragraphs (d)(1) through (4) of this section and the applicable test methods in paragraphs (d)(5) through (7) of this section.

(1) Method 1 or 1A in appendix A of 40 CFR part 60 to determine the sampling port locations and the location and required number of sampling traverse points.

(2) Method 2, 2A, 2C, or 2D in appendix A of 40 CFR part 60 to determine the stack gas velocity and volumetric flow rate.

(3) Method 3, 3A, or 3B in appendix A of 40 CFR part 60 to determine the stack gas molecular weight.

(4) Method 4 in appendix A of 40 CFR part 60 to determine the stack gas moisture content.

(5) For each by-product hydrogen stream, Method 102 in appendix A of 40 CFR part 61 to measure the mercury emission rate after the last control device.

(6) For each end box ventilation system vent, Method 101 or 101A in appendix A of 40 CFR part 61 to measure the mercury emission rate after the last control device.

(7) For each mercury thermal recovery unit vent, Method 101 or 101A in appendix A of 40 CFR part 61 to measure the mercury emission rate after the last control device.

(e) During each test run for a by-product hydrogen stream and each test run for an end box ventilation system vent, you must continuously measure the electric current through the operating mercury cells and record a measurement at least once every 15 minutes.

(f) If the final control device is not a nonregenerable carbon adsorber and if you are demonstrating compliance using periodic monitoring under § 63.8240(b), you must continuously monitor the parameters listed in paragraph (f)(1) of this section and establish your maximum or minimum monitoring value (as appropriate for your control device) using the requirements in paragraph (f)(2) of this section.

(1) During the performance test specified in paragraphs (a) through (d) of this section, you must continuously monitor the control device parameters in paragraphs (f)(1)(i) through (vii) of this section and record a measurement at least once every 15 minutes.

(i) The exit gas temperature from uncontrolled streams;

(ii) The outlet temperature of the gas stream for the final (*i.e.*, the farthest downstream) cooling system when no control devices other than coolers or demisters are used;

(iii) The outlet temperature of the gas stream from the final cooling system when the cooling system is followed by a molecular sieve or regenerative carbon adsorber;

(iv) Outlet concentration of available chlorine, pH, liquid flow rate, and inlet gas temperature of chlorinated brine scrubbers and hypochlorite scrubbers;

(v) The liquid flow rate and exit gas temperature for water scrubbers;

(vi) The inlet gas temperature of regenerative carbon adsorption systems; and

(vii) The temperature during the heating phase of the regeneration cycle for carbon adsorbers or molecular sieves.

(2) To establish a maximum monitoring value or minimum monitoring value, as appropriate for your final control device, you must average the recorded parameters in paragraphs (f)(1)(i) through (vi) of this section over the test period. If your final control device is a regenerative carbon adsorber, you must use the highest temperature reading measured in paragraph (f)(1)(vii) as the reference temperature in § 63.8244(b)(2)(v).

(g) Within 60 days after the date of completing each performance test specified in this section, you must submit the results of the performance test following the procedures specified in paragraphs (g)(1) through (3) of this section.

(1) *Data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). The data must be submitted in a file format generated using the EPA's ERT. Alternatively, you may submit an electronic file consistent with the extensible markup language (XML) schema listed on the EPA's ERT website.

(2) *Data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the test.* The results of the performance test must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *Confidential business information (CBI).* Do not use CEDRI to submit information you claim as CBI. Anything submitted using CEDRI cannot later be claimed CBI. Although we do not expect persons to assert a claim of CBI, if you wish to assert a CBI claim for some of the information submitted under paragraph (g)(1) or (2) of this section, you must submit a complete file, including information claimed to be CBI, to the EPA. The file must be generated using the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described in paragraphs (g)(1) and (2) of this section. All CBI claims must be asserted at the time of submission. Furthermore, under CAA section 114(c), emissions data is not entitled to confidential treatment, and the EPA is required to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27020, May 6, 2022]

§ 63.8234 What equations and procedures must I use for the initial compliance demonstration?

(a) *By-product hydrogen streams and end box ventilation system vents.* You must determine the total grams of mercury per Megagram of chlorine production (g Hg/Mg Cl_2) of chlorine produced from all by-product hydrogen streams and all end box ventilation system vents, if applicable, at a mercury cell chlor-alkali production facility, and you must follow the procedures in paragraphs (a)(1) through (6) of this section.

(1) Determine the mercury emission rate for each test run in grams per day for each by-product hydrogen stream and for each end box ventilation system vent, if applicable, from Method 101, 101A, or 102 (40 CFR part 61, appendix A).

(2) Calculate the average measured electric current through the operating mercury cells during each test run for each by-product hydrogen stream and for each end box ventilation system vent, if applicable, using Equation 1 of this section as follows:

$$CL_{avg,\ run} = \frac{\sum_{i=1}^{n} CL_{i,\ run}}{n} \qquad \text{(Eq. 1)}$$

Where:

$CL_{avg,\ run}$ = Average measured cell line current load during the test run, amperes;

$CL_{i,\ run}$ = Individual cell line current load measurement (*i.e.,* 15 minute reading) during the test run, amperes; and

n = Number of cell line current load measurements taken over the duration of the test run.

(3) Calculate the amount of chlorine produced during each test run for each by-product hydrogen stream and for each end box ventilation system vent, if applicable, using Equation 2 of this section as follows:

$$P_{Cl_2,\,run} = \left(1.3\times10^{-6}\right)\left(CL_{avg,\,run}\right)\left(n_{cells,\,run}\right)\left(t_{run}\right) \qquad \text{(Eq. 2)}$$

Where:

$P_{Cl_2,run}$ = Amount of chlorine produced during the test run, megagrams chlorine (Mg Cl_2);

1.3×10^{-6} = Theoretical chlorine production rate factor, Mg Cl_2 per hour per ampere per cell;

$CL_{avg,run}$ = Average measured cell line current load during test run, amperes, calculated using Equation 1 of this section;

$n_{cell,run}$ = Number of cells on-line during the test run; and

t_{run} = Duration of test run, hours.

(4) Calculate the mercury emission rate in grams of mercury per megagram of chlorine produced for each test run for each by-product hydrogen stream and for each end box ventilation system vent, if applicable, using Equation 3 of this section as follows:

$$E_{Hg,\,run} = \left[\frac{\left(R_{run}\right)\left(t_{run}\right)}{(24)\left(P_{Cl_2,\ run}\right)}\right] \qquad \text{(Eq. 3)}$$

Where:

$E_{Hg,run}$ = Mercury emission rate for the test run, g Hg/Mg Cl_2;

R_{run} = Measured mercury emission rate for the test run from paragraph (a)(1) of this section, grams Hg per day;

t_{run} = Duration of test run, hours;

24 = Conversion factor, hours per day; and

$P_{Cl_2,run}$ = Amount of chlorine produced during the test run, calculated using Equation 2 of this section, Mg Cl_2.

(5) Calculate the average mercury emission rate for each by-product hydrogen stream and for each end box ventilation system vent, if applicable, using Equation 4 of this section as follows:

$$E_{Hg,\,avg} = \frac{\sum_{i=1}^{n} E_{Hg,\,run}}{n} \qquad \text{(Eq. 4)}$$

Where:

$E_{Hg,avg}$ = Average mercury emission rate for the by-product hydrogen stream or the end box ventilation system vent, if applicable, g Hg/Mg Cl_2;

$E_{Hg,run}$ = Mercury emission rate for each test run for the by-product hydrogen stream or the end box ventilation system vent, if applicable, g Hg/Mg Cl_2, calculated using Equation 3 of this section; and

n = Number of test runs conducted for the by-product hydrogen stream or the end box ventilation system vent, if applicable.

(6) Calculate the total mercury emission rate from all by-product hydrogen streams and all end box ventilation system vents, if applicable, at the mercury cell chlor-alkali production facility using Equation 5 of this section as follows:

$$E_{Hg,\,H_2EB} = \sum_{i=1}^{n} E_{Hg,\,avg} \qquad \text{(Eq. 5)}$$

Where:

E_{Hg,H_2EB} = Total mercury emission rate from all by-product hydrogen streams and all end box ventilation system vents, if applicable, at the affected source, g Hg/Mg Cl_2;

$E_{Hg,avg}$ = Average mercury emission rate for each by-product hydrogen stream and each end box ventilation system vent, if applicable, g Hg/Mg Cl_2, determined using Equation 4 of this section; and

n = Total number of by-product hydrogen streams and end box ventilation system vents at the affected source.

(b) *Mercury thermal recovery vents.* You must determine the milligrams of mercury per dscm exhaust discharged from mercury thermal recovery unit vents, using the procedures in paragraphs (b)(1) and (2) of this section.

(1) Calculate the concentration of mercury in milligrams of mercury per dscm of exhaust for each test run for each mercury thermal recovery unit vent using Equation 6 of this section as follows:

$$C_{Hg,\,run} = \left[\frac{\left(m_{Hg}\right)\left(10^{-3}\right)}{\left(V_{m_{(std)}}\right)} \right] \quad \text{(Eq. 6)}$$

Where:

$C_{Hg,run}$ = Mercury concentration for the test run, milligrams of mercury per dry standard cubic meter of exhaust;

m_{Hg} = Mass of mercury in test run sample, from Method 101, 101A, or 102, micrograms;

10-3 = Conversion factor, milligrams per microgram; and

$V_{m(std)}$ = Dry gas sample volume at standard conditions, from Method 101, 101A, or 102, dry standard cubic meters.

(2) Calculate the average concentration of mercury in each mercury thermal recovery unit vent exhaust using Equation 7 of this section as follows:

$$C_{Hg,\,avg} = \frac{\sum_{i=1}^{n} C_{Hg,\,run}}{n} \quad \text{(Eq. 7)}$$

Where:

$C_{Hg,avg}$ = Average mercury concentration for the mercury thermal recovery unit vent, milligrams of mercury per dry standard cubic meter exhaust;

$C_{Hg,run}$ = Mercury concentration for each test run, milligrams of mercury per dry standard cubic meter of exhaust, calculated using Equation 6 of this section; and

n = Number of test runs conducted for the mercury thermal recovery unit vent.

§ 63.8236 How do I demonstrate initial compliance with the emission limitations and work practice standards?

(a) For each mercury cell chlor-alkali production facility, you have demonstrated initial compliance with the applicable emission limit for by-product hydrogen streams and end box ventilation system vents in § 63.8190(a)(2) if you comply with paragraphs (a)(1) and (2) of this section:

(1) Total mercury emission rate from all by-product hydrogen streams and all end box ventilation system vents, if applicable, at the affected source, determined according to §§ 63.8232 and 63.8234(a), did not exceed the applicable emission limit in § 63.8190(a)(2)(i) or (ii); and

(2) If you have chosen the periodic monitoring option specified in § 63.8240(b) and your final control device is not a nonregenerable carbon adsorber, you have established a parameter value according to § 63.8232(f)(2).

(b) For each mercury recovery facility, you have demonstrated initial compliance with the applicable emission limit for mercury thermal recovery unit vents in § 63.8190(a)(3) if you comply with paragraphs (b)(1) and (2) of this section.

(1) Mercury concentration in each mercury thermal recovery unit vent exhaust, determined according to §§ 63.8232 and 63.8234(b), did not exceed the applicable emission limit in § 63.8190(a)(3)(i) or (ii); and

(2) If you have chosen the periodic monitoring option in § 63.8240(b) and have a final control device that is not a nonregenerable carbon adsorber, you have established a maximum or minimum monitoring value, as appropriate for your control device according to § 63.8232(f)(2).

(c) Prior to the compliance date specified in § 63.8186(a)(2), for each affected source, you have demonstrated initial compliance with the applicable work practice standards in § 63.8192 if you comply with paragraphs (c)(1) through (7) of this section.

(1) You certify in your Notification of Compliance Status that you are operating according to the work practice standards in § 63.8192(a) through (d).

(2) You choose the continuous cell room monitoring program option, you certify in your Notification of Compliance Status that you are operating according to the continuous cell room monitoring program under § 63.8192(g) and you have established your action level according to § 63.8192(g)(2).

(3) You certify in your Notification of Compliance Status that you are operating according to your washdown plan.

(4) You have submitted your washdown plan as part of your Notification of Compliance Status.

(5) You have submitted your continuous cell room monitoring plan, if applicable, as part of your Notification of Compliance Status.

(6) You have submitted your floor-level cell room monitoring plan, if applicable, as part of your Notification of Compliance Status.

(7) You have submitted records of the mass of virgin mercury added to cells for the 5 years preceding the applicable compliance date for your affected source as a part of the Notification of Compliance Status.

(d) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8252(e).

(e) On and after the compliance date specified in § 63.8186(a)(2), for each affected source, you have demonstrated initial compliance with the applicable work practice standards for mercury emissions in § 63.8192(a) through (c) and (e) through (g) if you comply with paragraphs (e)(1) through (4) of this section.

(1) You have submitted a Revised Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8252(f).

(2) You certify in your Revised Notification of Compliance Status that you are operating according to the work practice standards for mercury emissions in § 63.8192(a) through (c), (e), and (f).

(3) You have submitted your cell room monitoring plan as part of your Revised Work Practice Notification of Compliance Status and you certify in your Revised Notification of Compliance Status that you are operating according to the continuous cell room monitoring program under § 63.8192(g).

(4) You have re-submitted your washdown plan as part of your Revised Notification of Compliance Status and you re-certify in your Revised Notification of Compliance Status that you are operating according to your washdown plan under § 63.8192(e).

(f) On and after the compliance date specified in § 63.8186(a)(2), for each affected source, you have demonstrated initial compliance with the applicable work practice standards for chlorine emissions in § 63.8192(h) if you meet the requirements of paragraphs (f)(1) through (3) of this section.

(1) You have installed chlorine sensors in accordance with § 63.8192(h)(2).

(2) You have certified in your Revised Notification of Compliance Status that you are operating according to the work practice standards in § 63.8192(h).

(3) You have submitted your Revised Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8252(f).

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27020, May 6, 2022]

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.8240 What are my monitoring requirements?

For each by-product hydrogen stream, each end box ventilation system vent, and each mercury thermal recovery unit vent, you must monitor the mercury emissions using the procedures in paragraph (a) or (b) of this section.

(a) You must continuously monitor the mercury concentration using a mercury continuous emissions monitor according to the requirements in §§ 63.8242(a) and 63.8244(a); or

(b) You must periodically monitor the mercury emissions according to the requirements in §§ 63.8242(b) and 63.8244(b).

§ 63.8242 What are the installation, operation, and maintenance requirements for my continuous mercury monitoring systems?

(a) If you choose the continuous mercury monitoring option under § 63.8240(a), you must install, operate, and maintain each mercury continuous emissions monitor according to paragraphs (a)(1) through (5) of this section.

(1) Each mercury continuous emissions monitor must sample, analyze, and record the concentration of mercury at least once every 15 minutes.

(2) Each mercury continuous emissions monitor analyzer must have a detector with the capability to detect a mercury concentration of either 0.1 μg/m^3 or 0.5 times the mercury concentration level measured during the performance test conducted according to § 63.8232.

(3) In lieu of a promulgated performance specification as required in

§ 63.8(a)(2), you must develop a site-specific monitoring plan that addresses the elements in paragraphs (a)(3)(i) through (vi) of this section.

(i) Installation and measurement location downstream of the final control device for each by-product hydrogen stream, end box ventilation system vent, and mercury thermal recovery unit vent.

(ii) Performance and equipment specifications for the sample interface, the pollutant concentration analyzer, and the data collection and reduction system.

(iii) Performance evaluation procedures and acceptance criteria (*i.e.*, calibrations).

(iv) Ongoing operation and maintenance procedures according to the requirements of § 63.8(c)(1), (3), and (4)(ii).

(v) Ongoing data quality assurance procedures according to the requirements of § 63.8(d)(1) and (2). You shall keep these written procedures on record for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan is revised, you shall keep previous (*i.e.*, superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action shall be included in the plan required under § 63.8(d)(2).

(vi) Ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c), (e)(1), and (e)(2)(i).

(4) You must conduct a performance evaluation of each mercury continuous emissions monitor according to your site-specific monitoring plan.

(5) You must operate and maintain each mercury continuous emissions monitor in continuous operation according to the site-specific monitoring plan.

(b) If you choose the periodic monitoring option and your final control device is not a nonregenerable carbon adsorber, you must install, operate, and maintain a continuous parameter monitoring system (CPMS) for each parameter specified in § 63.8232(f)(1), according to § 63.8(c).

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27021, May 6, 2022]

§ 63.8243 What equations and procedures must I use to demonstrate continuous compliance?

(a) *By-product hydrogen streams and end box ventilation system vents.* For each consecutive 52-week period, you must determine the g Hg/Mg Cl_2 produced from all by-product hydrogen streams and all end box ventilation system vents, if applicable, at a mercury cell chlor-alkali production facility using the procedures in paragraphs (a)(1) through (3) of this section. You must begin collecting data on the compliance date that is specified in § 63.8186 for your affected source and calculate your first 52-week average mercury emission rate at the end of the 52nd week after the compliance date.

(1) Each week, you must determine the weekly mercury emission rate in grams per week for each by-product hydrogen stream and for each end box ventilation system vent, if applicable, using one of the monitoring options in paragraph (a)(1)(i) or (ii) of this section.

(i) Continuous mercury monitoring according to §§ 63.8242 and 63.8244(a).

(ii) Periodic monitoring according to § 63.8244(b).

(2) Each week, you must determine the chlorine production and keep records of the production rate as required under § 63.8256(b)(6).

(3) Beginning 52 weeks after the compliance date specified in § 63.8186 for your affected source, you must calculate the 52-week average mercury emission rate from all by-product hydrogen steam and all end box ventilation system vents, if applicable, using Equation 1 of this section as follows:

$$E_{Hg} = \sum_{i=1}^{52}\left[\frac{\left(R_{week_i}\right)}{\left(P_{Cl_2,week_i}\right)}\right] \quad \text{(Eq. 1)}$$

Where:

E_{Hg} = 52-week average mercury emission rate for $week_i$, g Hg/Mg Cl_2;

$R_{week,\ i}$ = Mercury emission rate for $week_i$ from paragraph (a)(1) of this section, g Hg per week;

$P_{Cl2,\ weeki}$ = Amount of chlorine produced during $week_i$, from paragraph (a)(2) of this section, Mg Cl_2 per week.

(b) *Mercury thermal recovery units.* If you choose the continuous monitoring option in § 63.8240(a), you must demonstrate continuous compliance using paragraph (b)(1) of this section. If you choose the periodic monitoring option in § 63.8240(b), you must demonstrate continuous compliance using paragraph (b)(2) of this section.

(1) You must calculate the daily average mercury concentration using Equation 2 of this section as follows:

$$C_{Hg,\ dailyavg} = \frac{\left(\sum_{i=1}^{n} C_{Hg,\ i}\right)}{n} \quad \text{(Eq. 2)}$$

Where:

$C_{Hg,\ dailyavg}$ = Average mercury concentration for the operating day, milligrams per dry standard cubic meter;

$C_{Hg,i}$ = Concentration of mercury measured at the interval *i* (*i.e.*, 15 minute reading) using a mercury continuous emission monitor, milligrams per dry standard cubic meter; and

n = Number of concentration measurements taken during the operating day.

(2) You must calculate the daily average mercury concentration using the procedures in § 63.8234(b).

§ 63.8244 How do I monitor and collect data to demonstrate continuous compliance?

(a) *Continuous monitoring option.* You must monitor mercury concentration according to § 63.8242(a) at all times that the affected source is operating with the exception of paragraphs (a)(1) and (2) of this section.

(1) Except for monitor malfunctions, associated repairs, and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor mercury emissions continuously (or collect data at all required intervals) at all times that the affected source is operating. A monitoring malfunction is any sudden, infrequent, not reasonably preventable failure of the monitoring to provide valid data. Monitoring failures that are caused in part by poor maintenance or careless operation are not malfunctions.

(2) You may not use data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities in data averages and calculations used to report emission or operating levels or to fulfill a minimum data availability requirement, if applicable. You must use all the data collected during all other periods in assessing compliance.

(b) *Periodic monitoring option.* If you choose the periodic monitoring option under § 63.8240(b), you must monitor according to the procedures in paragraph (b)(1) or (2) of this section.

(1) If your final control device is a nonregenerable carbon adsorber, then you must conduct at least three test runs per week meeting the criteria specified in § 63.8232(c)(1) and (2) to measure mercury emissions using the test methods specified in § 63.8232(d). Alternatively, you may use any other method that has been validated using the applicable procedures in Method 301, 40 CFR part 63, appendix A.

(2) If your final control device is anything other than a nonregenerable carbon adsorber, you must monitor according to the requirements of paragraphs (b)(2)(i) through (v) of this section.

(i) You must conduct at least three test runs per week meeting the criteria specified in § 63.8232(c)(1) and (2) to measure mercury emissions using the test methods specified in § 63.8232(d). Alternatively, you may use any other method that has been validated using the applicable procedures in Method 301, 40 CFR part 63, appendix A.

(ii) Except as specified in paragraph (b)(2)(iii) of this section, you must continuously collect data at least once every 15 minutes using a CPMS installed and operated according to § 63.8242(b) and record each 1-hour average from all measured data values during each 1-hour period for the applicable parameter identified in § 63.8232(f)(1) using the methods specified in § 63.8244(a).

(iii) As appropriate, you must continuously monitor the temperature specified in § 63.8232(f)(1)(vii) during each heating phase of the regeneration cycle of your carbon adsorber.

(iv) If the hourly average monitoring value of any applicable parameter recorded under paragraph (b)(2)(ii) of this section is below the minimum monitoring value or above the maximum monitoring value of that same parameter established under § 63.8232(f)(2) for 24 consecutive hours, your monitoring value is out of range and you must take corrective action as soon as practicable. The hourly average monitoring value must be above the minimum monitoring value or below the maximum monitoring value as appropriate for that parameter, within 48 hours of the period that the monitoring value is out of range.

(v) If your final control device is a regenerative carbon adsorber, when the maximum hourly value of the temperature measured according to paragraph (b)(2)(iii) of this section is below the reference temperature determined according to § 63.8232(f)(2) for three consecutive regeneration cycles, your monitoring value is out of range and you must take corrective action as soon as practicable. During the first regeneration cycle following the period that your monitoring value is out of range, the maximum hourly value must be above the reference temperature recorded according to § 63.8232(f)(2).

§ 63.8246 How do I demonstrate continuous compliance with the emission limitations and work practice standards?

(a) *By-product hydrogen streams and end box ventilation system vents.* (1) For all by-product hydrogen streams and all end box ventilation system vents, if applicable, you must demonstrate continuous compliance with the applicable mercury emission limit by reducing the mercury emissions data to 52-week averages using Equation 1 of § 63.8243 and maintaining the 52-week average mercury emissions no higher than the applicable mercury emissions limit in § 63.8190(a)(2). To obtain the data to calculate these 52-week averages, you must monitor in accordance with paragraph (a)(1)(i) or (ii) of this section.

(i) *Continuous monitoring option.* You must collect mercury emissions data according to § 63.8244(a), representing at least 75 percent of the 15-minute periods in each operating day of the 52-week compliance period (with data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities not counting toward the 75 percent requirement);

(ii) *Periodic monitoring option.* You must conduct at least three test runs per week to collect mercury emissions samples according to § 63.8244(b)(1) and (2)(i) and, if your final control device is not a nonregenerable carbon adsorber, you must collect data for monitoring values according to § 63.8244(b)(2)(ii) through (v).

(2) You must maintain records of mercury emissions and 52-week average values, as required in § 63.8256(b)(3) and (4). If your final control device is not a nonregenerable carbon adsorber, you must maintain records according to § 63.8256(d).

(b) *Mercury thermal recovery unit vents.* (1)(1) For each mercury thermal recovery unit vent, you must demonstrate continuous compliance with the applicable emission limit specified in § 63.8190(a)(3) by maintaining the outlet mercury daily-average concentration no higher than the applicable limit. To determine the outlet mercury concentration, you must monitor according to paragraph (b)(1)(i) or (ii) of this section.

(i) *Continuous monitoring option.* You must collect mercury concentration data according to § 63.8244(a), representing at least 75 percent of the 15-minute periods in the operating day (with data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities not counting toward the 75 percent requirement).

(ii) *Periodic monitoring option.* You must conduct at least three test runs per week to collect mercury emissions samples according to § 63.8244(b)(1) and (2)(i) and, if your final control device is not a nonregenerable carbon adsorber, you must collect data for monitoring values according to § 63.8244(b)(2)(ii) through (v).

(2) You must maintain records of mercury emissions and daily average values as required in § 63.8256(b)(3). If your final control device is not a nonregenerable carbon adsorber, you

must maintain records according to § 63.8256(d).

(c) You must demonstrate continuous compliance with the applicable work practice standards for mercury emissions in § 63.8192 by maintaining records in accordance with § 63.8256(c) and (e).

(d) You must demonstrate continuous compliance with the applicable work practice standards for chlorine emissions in § 63.8192(h) by continuously operating the chlorine sensors required by § 63.8192(h)(2), inspecting equipment in accordance with § 63.8192(h)(3), repairing equipment in accordance with § 63.8192(h)(4) and maintaining records in accordance with § 63.8256(f).

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27021, May 6, 2022]

§ 63.8248 What other requirements must I meet?

(a) *Deviations.* The instances specified in paragraphs (a)(1) through (4) of this section are deviations and must be reported according to the requirements in § 63.8254 and recorded according to the requirements in § 63.8256(a)(2).

(1) You must report each instance in which you did not meet each emission limitation in § 63.8190 that applies to you.

(2) You must report each instance in which you did not meet each work practice standard in § 63.8192 that applies to you.

(3) You must report each instance in which the corrective actions taken according to § 63.8244(b)(2)(iv) did not result in average monitoring values being within range within 48 hours of the period that the monitoring value is out of range.

(4) You must report each instance in which the corrective action taken according to § 63.8244(b)(2)(v) did not result in the maximum hourly temperature being above the reference temperature during the first regeneration cycle following the period that the monitoring value was out of range.

(b) *Startups, shutdowns, and malfunctions.*The provisions of paragraphs (b)(1) through (3) of this section apply until November 7, 2022. On and after November 7, 2022, the provisions of paragraphs (b)(1) through (3) of this section no longer apply. (1) Consistent with §§ 63.6(e) and 63.7(e)(1), deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with § 63.6(e)(1).

(2) The Administrator will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in § 63.6(e).

(3) By-passing the control device for maintenance activities is not considered a startup, shutdown, or malfunction event.

[68 FR 70928, Dec. 19, 2003, as amended at 71 FR 20469, Apr. 20, 2006; 87 FR 27021, May 6, 2022]

NOTIFICATION, REPORTS, AND RECORDS

§ 63.8252 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(e) and (f) and 63.9(b) through (h) that apply to you by the dates specified.

(b) As specified in § 63.9(b)(2), if you start up your affected source before December 19, 2003, you must submit an Initial Notification no later than 120 calendar days after December 19, 2003, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) As specified in § 63.9(b)(3), if you start up your new or reconstructed mercury recovery facility on or after December 19, 2003, you must submit your initial notification not later than 120 days after you become subject to this subpart.

(d) For each performance test that you are required to conduct for by-product hydrogen streams and end box ventilation system vents and for mercury thermal recovery unit vents, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin as required in § 63.7(b)(1).

(e) You must submit a Notification of Compliance Status according to paragraphs (e)(1) and (2) of this section.

(1) For each initial compliance demonstration that does not include a performance test, you must submit the Notification of Compliance Status before the close of business on the 30th calendar day following the completion of the initial compliance demonstration. The Notification of Compliance Status must contain the items in paragraphs (e)(1)(i) through (iv) of this section:

(i) If you choose not to implement a cell room monitoring program according to § 63.8192(g), a certification that you are operating according to the applicable work practice standards for mercury emissions in § 63.8192(a) through (d) and your floor-level mercury vapor measurement plan required by § 63.8192(d).

(ii) The washdown plan, and you must certify that you are operating according to the washdown plan specified in § 63.8192(f).

(iii) The mass of virgin mercury added to cells for the 5 years preceding the compliance date.

(iv) If you choose to implement a cell room monitoring program according to § 63.8192(g), your cell room monitoring plan.

(2) For each initial compliance demonstration that does include a performance test, you must submit the Notification of Compliance Status, including the performance test results, before the close of business on the 60th calendar day following the completion of the performance test according to § 63.10(d)(2). The Notification of Compliance Status must contain the information in § 63.9(h)(2)(ii)(A) through (G). The site-specific monitoring plan required in § 63.8242(a)(3) must also be submitted.

(f) You must submit a Revised Notification of Compliance Status before the close of business on the date 30 days after the compliance date in § 63.8186(a)(2) containing the items in paragraphs (f)(1) through (5) of this section:

(1) A certification that you are operating according to the work practice standards for mercury emissions in § 63.8192(a) through (c) and (e) through (g).

(2) Your cell room monitoring plan, including your initial action level determined in accordance with § 63.8192(g)(2), and a certification that you are operating according to the continuous cell room monitoring program under § 63.8192(g).

(3) Your washdown plan, and a certification that you are operating according to your washdown plan under § 63.8192(e).

(4) Records of the mass of virgin mercury added to cells for every year since 2001.

(5) A certification that you have installed chlorine sensors in accordance with § 63.8192(h)(2) and that you are operating according to the work practice standards for chlorine emissions in § 63.8192(h).

(g) You must submit all subsequent Notification of Compliance Status reports and Revised Notification of Compliance Status reports in PDF format to the EPA via CEDRI, which can be accessed through EPA's CDX (*https://cdx.epa.gov/*).

(h) You must submit a notification of compliance with the prohibition of mercury emissions as specified in paragraphs (e)(1) and (2) of this section.

(1) The notification must include the information specified in paragraph (e)(1)(i) and (ii) of this section.

(i) A certification that the requirement of § 63.8190(a)(2)(ii) has been met.

(ii) A brief explanation of how the requirement of § 63.8190(a)(2)(ii) has been met.

(2) You must submit this notification before the close of business on the 30th calendar day following the date when compliance with § 63.8190(a)(2)(ii) is attained.

[68 FR 70928, Dec. 19, 2003, as amended at 85 FR 73914, Nov. 19, 2020, 85 FR 84262, Dec. 28, 2020; 87 FR 27021, May 6, 2022]

§ 63.8254 What reports must I submit and when?

(a) *Compliance report due dates.* You must submit a semiannual compliance report to your permitting authority according to the requirements in paragraphs (a)(1) through (4) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.8186 and ending on June 30 or December 31, whichever date comes first after the compliance

date that is specified for your affected source in § 63.8186.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after your first compliance reporting period.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date comes first after the end of the semiannual reporting period.

(b) *Compliance report contents.* Each compliance report must contain the information in paragraphs (b)(1) through (3) of this section, and as applicable, paragraphs (b)(5) through (13) of this section.

(1) Company name and address.

(2) Statement by a responsible official, with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) [Reserved]

(5) If there were no deviations from the continuous compliance requirements in § 63.8246 that apply to you, a statement that there were no deviations from the emission limitations, work practice standards, and operation and maintenance standards during the reporting period.

(6) If there were no periods during which the mercury continuous emission monitor or CPMS (if applicable) were out-of-control as specified in § 63.8(c)(7), a statement that there were no periods during the which the mercury continuous emissions monitor or CPMS (if applicable) were out-of-control during the reporting period.

(7) For each deviation from the requirements for work practice standards in § 63.8192, the information in paragraphs (b)(7)(i) and (ii) of this section.

(i) For each deviation from the mercury work practice standards in Tables 1 through 4 to this subpart that occurs at an affected source (including deviations where the response intervals were not adhered to as described in § 63.8192(b)), each deviation from the cell room monitoring program monitoring and data recording requirements in § 63.8192(g)(3), and each deviation from the response intervals required by § 63.8192(g)(4) when an action level is exceeded, the compliance report must contain the information in paragraphs (b)(1) through (3) of this section and the information in paragraphs (b)(7)(i)(A) through (C) of this section.

(A) The total operating time of each affected source during the reporting period.

(B) Information on the number, date, time, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(C) A list of the affected sources or equipment.

(ii) For each deviation from the fugitive chlorine requirements in § 63.8192(h), including periods when the chlorine sensors required by § 63.8192(h)(2) were not operating; instances where the chlorine sensors required by § 63.8192(h)(2) were not calibrated and maintained in accordance with manufacturer instructions or spare parts were not maintained; instances where inspections were not performed in accordance with § 63.8192(h)(3)(i) and (ii); and instances where leak repair intervals in § 63.8192(h)(4) were not met; the compliance report must contain the information in paragraphs (b)(1) through (3) of this section and the information in paragraphs (b)(7)(ii)(A) through (C) of this section.

(A) The total operating time of each affected source during the reporting period.

(B) Information on the number, date, time, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(C) A list of the affected sources or equipment.

(8) For each deviation from an emission limitation occurring at an affected source where you are using a mercury continuous emission monitor, according to the site-specific monitoring plan required in § 63.8242(a)(3), to comply with the emission limitation in

this subpart, you must include the information in paragraphs (b)(1) through (3) of this section and the information in paragraphs (b)(8)(i) through (xv) of this section.

(i) A list of the affected sources and equipment.

(ii) The date and time that each deviation started and stopped.

(iii) For each deviation, the cause of the deviation (including unknown cause, if applicable), as applicable, and corrective action taken.

(iv) For each deviation, an estimate of the quantity of each regulated pollutant emitted over any emission limit.

(v) A description of the method used to estimate the emissions.

(vi) The date and time of each instance in which a continuous monitoring system was inoperative, except for zero (low-level) and high-level checks.

(vii) The date, time, and duration of each instance in which a continuous monitoring system was out-of-control, including the information in § 63.8(c)(8).

(viii) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.

(ix) A breakdown of the total duration of the deviations during the reporting period including those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(x) A summary of the total duration of continuous monitoring system downtime during the reporting period and the total duration of monitoring system downtime as a percent of the total source operating time during the reporting period.

(xi) An identification of each hazardous air pollutant that was monitored at the affected source.

(xii) A brief description of the process units.

(xiii) A brief description of the continuous monitoring system.

(xiv) The date of the latest continuous monitoring system certification or audit.

(xv) A description of any changes in monitoring system, processes, or controls since the last reporting period.

(9) For each deviation from an operation and maintenance standard occurring at an affected source where you are using the periodic monitoring option specified in § 63.8240(b) and your final control device is not a nonregenerable carbon adsorber, the compliance report must include the information in paragraphs (b)(1) through (3) of this section and the information in paragraphs (b)(9)(i) through (xiii) of this section.

(i) A list of the affected sources or equipment.

(ii) The total operating time of each affected source during the reporting period.

(iii) Information on the number, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(iv) For each deviation, an estimate of the quantity of each regulated pollutant emitted over any emission limit.

(v) A description of the method used to estimate the emissions.

(vi) The date and time of each instance in which a CPMS was inoperative, except for zero (low-level) and high-level checks.

(vii) The date, time, and duration of each instance in which a CPMS was out-of-control, including the information specified in § 63.8(c)(8).

(viii) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.

(ix) A breakdown of the total duration of the deviations during the reporting period including those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(x) A summary of the total duration of continuous monitoring system downtime during the reporting period and the total duration of monitoring system downtime as a percent of the total source operating time during the reporting period.

(xi) A brief description of the CPMS.

(xii) The date of the latest CPMS certification or audit.

(xiii) A description of any changes in monitoring system, processes, or controls since the last reporting period.

(10) The compliance report must contain the mass of virgin mercury added to cells for the reporting period.

(11) The compliance report must contain each instance in which corrective actions taken under §63.8244(b)(2)(iv) did not result in average monitoring values being within range within 48 hours of the period that the monitoring value is out of range.

(12) The compliance report must contain each instance in which corrective action taken according to §63.8244(b)(2)(v) did not result in the maximum hourly temperature being above the reference temperature during the first regeneration cycle following the period that the monitoring value was out of range.

(13) The compliance report must contain the information specified in paragraphs (b)(13)(i) through (iii) for each instance where the 1-hour average concentration of chlorine detected by a chlorine sensor required by §63.8192(h)(2) was 2 ppmv or greater.

(i) The date and times a chlorine sensor detected chlorine concentrations of 2 ppmv or greater.

(ii) The location of the sensor.

(iii) The date and time that the sensor returned to a 1-hour average concentration of less than 2 ppmv.

(14) The compliance report must contain the information specified in paragraphs (b)(14)(i) and (ii) for all inspections conducted under either §63.8192(h)(3)(i) or (ii). You must also record the information in paragraphs (b)(14)(iii) through (vii) of this section for each leak identified.

(i) The date of each inspection.

(ii) The reason for each inspection (*i.e.*, a routine inspection conducted each 12 hours or an inspection conducted in response to a 2 ppmv or greater 1-hour average concentration of chlorine, as detected by a sensor).

(iii) Location of the leak.

(iv) Date and time the leak was identified.

(v) Date and time of initial repair attempt.

(vi) Date and time the leak is repaired.

(vii) A description of the repair made to stop the leak.

(c) [Reserved]

(d) *Title V monitoring report.* After your affected source has been issued a title V operating permit pursuant to 40 CFR part 70 or 40 CFR part 71, you must report all deviations from permit requirements and provide reports of any required monitoring in your semiannual monitoring report as required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If you submit a semiannual compliance report for an affected source as required by this subpart as part of the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the semiannual compliance report includes all information required by the 40 CFR part 70 or 40 CFR part 71 semiannual monitoring report for the deviations that are reported in the semiannual compliance report, submission of the semiannual compliance report satisfies your obligation to report the same deviation information in the semiannual monitoring report. However, in such situations, the semiannual monitoring report must cross-reference the semiannual compliance report, and submission of a semiannual compliance report does not otherwise affect any obligation you may have to report deviations from permit requirements for an affected source to your permitting authority under 40 CFR part 70 or 40 CFR part 71.

(e) The owner or operator must submit semiannual compliance reports in PDF formatto the EPA viaCEDRI, which can be accessedthrough EPA's CDX (*https://cdx.epa.gov/*).

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27022, May 6, 2022]

§63.8256 What records must I keep?

(a) *General records.* You must keep the records in paragraphs (a)(1) and (2) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any initial notification or Notification of Compliance Status that you submitted, according to the requirements in §63.10(b)(2)(xiv).

(2) The records specified in paragraphs (a)(2)(i) and (ii) of this section related to deviations.

(i) Record actions taken to minimize emissions in accordance with § 63.8222 and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(ii) Records of the information reported as required in § 63.8254(b)(7) through (9) and (11) through (13).

(b) Records associated with the byproduct hydrogen stream and end box ventilation system vent emission limitations and the mercury thermal recovery unit vent emission limitations. You must keep the records in paragraphs (b)(1) through (5) of this section related to the emission limitations in § 63.8190(a)(2) through (3) and (b).

(1) Records of performance tests as required in § 63.10(b)(2)(viii).

(2) Records of the mercury emissions monitoring conducted during the performance tests.

(3) Records of the continuous or periodic mercury emissions monitoring data.

(4) Records of the 52-week rolling average mercury emissions.

(5) Records associated with your site-specific monitoring plan required in § 63.8242(a)(3) (*i.e.*, results of inspections, calibrations, and validation checks of each mercury concentration continuous monitoring system (CMS)).

(6) Records of chlorine production on a weekly basis.

(c) Records associated with the work practice standards for mercury emissions that must be kept prior to the compliance date in § 63.8186(a)(2).

(1) If you choose not to institute a cell room monitoring program according to § 63.8192(g) of this subpart, you must keep the records specified in paragraphs (c)(1)(i) through (v) of this section.

(i) Records specified in Table 9 to this subpart related to the work practice standards in Tables 1 through 4 of this subpart.

(ii) Your current floor-level mercury vapor measurement plan.

(iii) Records of the average value calculated from at least three measurements taken according to your floor-level mercury vapor measurement plan.

(iv) Records indicated in § 63.8192(d)(4)(i) for maintenance activities that cause the floor-level mercury concentration to exceed the action level.

(v) Records of all inspections and corrective actions taken in response to a non-maintenance related situation in which the mercury vapor concentration exceeds the floor-level mercury concentration action level.

(2) You must maintain a copy of your current washdown plan and records of when each washdown occurs.

(3) You must maintain records of the mass of virgin mercury added to cells for each reporting period.

(4) If you choose to institute a cell room monitoring program according to § 63.8192(g) of this subpart, you must keep your current cell room monitoring plan and the records specified in paragraphs (c)(4)(i) through (v) of this section.

(i) Records of the monitoring conducted in accordance with § 63.8192(g)(2)(i) to establish your action level, and records demonstrating the development of this action level.

(ii) Records of the cell room mercury concentration monitoring data collected.

(iii) Instances when the action level is exceeded.

(iv) Records specified in § 63.8192(g)(4)(i) for maintenance activities that cause the mercury vapor concentration to exceed the action level.

(v) Records of all inspections and corrective actions taken in response to a non-maintenance related situation in which the mercury vapor concentration exceeds the action level.

(d) Records associated with the periodic monitoring option if your final control device is not a nonregenerable carbon adsorber. You must keep the records in paragraph (d)(1) through (3) of this section.

(1) Records of the CPMS data collected during the performance test as specified in § 63.8232(f)(1).

(2) Records documenting the development of the maximum monitoring value or minimum monitoring value, as appropriate, according to § 63.8232(f)(2).

(3) Records of hourly average values of applicable parameters monitored as specified in § 63.8244(b)(2)(ii) or (iii).

(e) Records associated with the work practice standards for mercury emissions that must be kept after the compliance date in § 63.8186(a)(2).

(1) The records specified in Table 9 to this subpart related to the work practice standards in Tables 1 through 4 of this subpart.

(2) You must maintain a copy of your current washdown plan and records of when each washdown occurs.

(3) You must maintain records of the mass of virgin mercury added to cells for each reporting period.

(4) You must keep your current cell room monitoring plan and the records specified in paragraphs (e)(4)(i) through (v) of this section.

(i) Records of the monitoring conducted in accordance with § 63.8192(g)(2)(i) to establish your action level, and records demonstrating the development of this action level.

(ii) Records of the cell room mercury concentration monitoring data collected.

(iii) Instances when the action level is exceeded.

(iv) Records specified in § 63.8192(g)(4)(i) for maintenance activities that cause the mercury vapor concentration to exceed the action level.

(v) Records of all inspections and corrective actions taken in response to a non-maintenance related situation in which the mercury vapor concentration exceeds the action level.

(f) You must keep the records specified in paragraphs (f)(1) through (4) of this section associated with the work practice standards for fugitive chlorine emissions specified in § 63.8192(h) after the compliance date in § 63.8186(a)(2).

(1) Identification of all equipment in the mercury cell chlor-alkali production facility affected source containing chlorine gas at a concentration of greater than 5 percent by volume. You may exclude equipment that is under negative pressure.

(2) Records of the information reported as required in § 63.8254(b)(13) and (14).

(3) You must record the information specified in paragraphs (f)(3)(i) through (iv) of this section for the chlorine sensors required by § 63.8192(h)(2).

(i) The location, manufacturer, and model number of each sensor.

(ii) The manufacturer's instructions for operation, maintenance, and calibration of the chlorine sensors.

(iii) Records of all maintenance and calibration of the chlorine sensors.

(iv) You must record all periods when the chlorine sensors are not operating.

(4) You must maintain records of all chlorine concentration measurements.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27023, May 6, 2022]

§ 63.8258 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious inspection and review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You can keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.8262 What parts of the General Provisions apply to me?

Table 10 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.13 apply to you.

[87 FR 27023, May 6, 2022]

§ 63.8264 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the United States Environmental Protection Agency (U.S. EPA), or a delegated authority such as your State, local, or tribal agency. If the EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency has the authority to implement and enforce this subpart. You should contact your EPA Regional Office to find out if this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the EPA Administrator and are not transferred to the State, local, or tribal agency.

(c) The authorities in paragraphs (c)(1) through (5) of this section will not be delegated to State, local, or tribal agencies.

(1) Approval of alternatives under § 63.6(g) to the non-opacity emission limitations in § 63.8190 and work practice standards in § 63.8192.

(2) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(5) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27023, May 6, 2022]

§ 63.8266 What definitions apply to this subpart?

Terms used in this subpart are defined in the CAA, in § 63.2, and in this section as follows:

Aqueous liquid means a liquid mixture in which water is the predominant component.

Brine means an aqueous solution of alkali metal chloride, as sodium chloride salt solution or potassium chloride salt solution, that is used in the electrolyzer as a raw material.

By-product hydrogen stream means the hydrogen gas from each decomposer that passes through the hydrogen system and is burned as fuel, transferred to another process as raw material, or discharged directly to the atmosphere.

Caustic means an aqueous solution of alkali metal hydroxide, as sodium hydroxide or potassium hydroxide, that is produced in the decomposer.

Caustic basket means a fixture adjacent to the decomposer that contains a serrated funnel over which the caustic from the decomposer passes, breaking into droplets such that electric current is interrupted.

Caustic system means all vessels, piping, and equipment that convey caustic and remove mercury from the caustic stream. The caustic system begins at the decomposer and ends after the primary filters.

Cell room means a building or other structure in which one or more mercury cells are located.

Continuous parameter monitoring system, or CPMS, means the total equipment that may be required to meet the data acquisition and availability requirements of this subpart, used to sample, condition (if applicable), analyze, and provide a record of process of control system parameters.

Control device means a piece of equipment (such as condensers, coolers, chillers, heat exchangers, mist eliminators, absorption units, and adsorption units) that removes mercury from gaseous streams.

Decomposer means the component of a mercury cell in which mercury amalgam and water react in bed of graphite packing (within a cylindrical vessel), producing caustic and hydrogen gas and returning mercury to its elemental form for re-use in the process.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limitation (including any operating limit) or work practice standard (including any monitoring plan);

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the title V operating permit for any affected source required to obtain such a permit; or

(3) Fails to take corrective actions within 48 hours that result in parameter monitoring values being within range.

Electrolyzer means the main component of the mercury cell that consists of an elongated, shallow steel trough that holds a layer of mercury as a flowing cathode. The electrolyzer is enclosed by side panels and a top that suspends metal anodes. In the

electrolyzer, brine is fed between a flowing mercury cathode and metal anodes in the presence of electricity to produce chlorine gas and an alkali metal-mercury amalgam (mercury amalgam).

Emission limitation means any emission limit or operating limit.

End box means a component of a mercury cell for transferring materials between the electrolyzer and the decomposer. The inlet end box collects and combines raw materials at the inlet end of the cell, and the outlet end box separates and directs various materials either into the decomposer or out of the cell.

End box ventilation system means all vessels, piping, and equipment that evacuate the head space of each mercury cell end box (and possibly other vessels and equipment) to the atmosphere. The end box ventilation system begins at the end box (and other vessel or equipment which is being evacuated) and terminates at the end box ventilation system vent. The end box ventilation system includes all control devices.

End box ventilation system vent means the discharge point of the end box ventilation system to the atmosphere after all control devices.

Hydrogen leak means hydrogen gas (containing mercury vapor) that is escaping from the decomposer or hydrogen system.

Hydrogen system means all vessels, piping, and equipment that convey a by-product hydrogen stream. The hydrogen system begins at the decomposer and ends at the point just downstream of the last control device. The hydrogen system includes all control devices.

In liquid mercury service means containing or coming in contact with liquid mercury.

Liquid mercury accumulation means one or more liquid mercury droplets, or a pool of liquid mercury, present on the floor or other surface exposed to the atmosphere.

Liquid mercury leak means the liquid mercury that is dripping or otherwise escaping from process equipment.

Liquid mercury spill means a liquid mercury accumulation resulting from a liquid mercury that leaked from process equipment or that dripped during maintenance or handling.

Mercury cell means a device consisting of an electrolyzer and decomposer, with one or more end boxes, a mercury pump, and other components linking the electrolyzer and decomposer.

Mercury cell amalgam seal pot means a compartment through which mercury amalgam passes from an outlet end box to a decomposer.

Mercury cell chlor-alkali plant means all contiguous or adjoining property that is under common control, where mercury cells are used to manufacture product chlorine, product caustic, and by-product hydrogen and where mercury may be recovered from wastes.

Mercury cell chlor-alkali production facility means an affected source consisting of all cell rooms and ancillary operations used in the manufacture of product chlorine, product caustic, and by-product hydrogen at a mercury cell chlor-alkali plant.

Mercury concentration CMS, or mercury concentration continuous monitoring system, means a CMS, as defined in §63.2, that continuously measures the concentration of mercury.

Mercury-containing wastes means waste materials containing mercury, which are typically classified under Resource Conservation and Recovery Act (RCRA) solid waste designations. K071 wastes are sludges from the brine system. K106 are wastewater treatment sludges. D009 wastes are non-specific mercury-containing wastes, further classified as either debris or nondebris (*i.e.,* cell room sludges and carbon from decomposes).

Mercury pump means a component of a mercury cell for conveying elemental mercury re-created in the decomposer to the beginning of the mercury cell. A mercury pump is typically found either as an in-line mercury pump (near a mercury suction pot or mercury seal pot) or submerged mercury pump (within a mercury pump tank or mercury pump seal).

Mercury recovery facility means an affected source consisting of all processes and associated operations needed for mercury recovery from wastes at a mercury cell chlor-alkali plant.

Mercury thermal recovery unit means the retort(s) where mercury-containing wastes are heated to volatilize mercury and the mercury recovery/control system (control devices and other equipment) where the retort off-gas is cooled, causing mercury to condense and liquid mercury to be recovered.

Mercury thermal recovery unit vent means the discharge point of the mercury thermal recovery unit to the atmosphere after all recovery/control devices. This term encompasses both oven type vents and non-oven type vents.

Mercury vacuum cleaner means a cleanup device used to draw a liquid mercury spill or accumulation (via suction pressure) into a closed compartment.

Non-oven type mercury thermal recovery unit vent means the discharge point to the atmosphere after all recovery/control devices of a mercury thermal recovery unit in which the retort is either a rotary kiln or single hearth retort.

Open-top container means any container that does not have a tight-fitting cover that keeps its contents from being exposed to the atmosphere.

Oven type mercury thermal recovery unit vent means the discharge point to the atmosphere after all recovery/control devices of a mercury thermal recovery unit in which each retort is a batch oven retort.

Responsible official means responsible official as defined in 40 CFR 70.2.

Retort means a furnace where mercury-containing wastes are heated to drive mercury into the gas phase. The types of retorts used as part of mercury thermal recovery units at mercury cell chlor-alkali plants include batch oven retorts, rotary kilns, and single hearth retorts.

Spalling means fragmentation by chipping.

Sump means a large reservoir or pit for wastewaters (primarily washdown waters).

Trench means a narrow channel or depression built into the length of a cell room floor that leads washdown materials to a drain.

Vent hose means a connection for transporting gases from the mercury cell.

Virgin mercury means mercury that has not been processed in an onsite mercury thermal recovery unit or otherwise recovered from mercury-containing wastes onsite.

Washdown means the act of rinsing a floor or surface with a stream of aqueous liquid to cleanse it of a liquid mercury spill or accumulation, generally by driving it into a trench.

Week means any consecutive seven-day period.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the CAA.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27023, May 6, 2022]

TABLE 1 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—DESIGN, OPERATION, AND MAINTENANCE REQUIREMENTS

As stated in §63.8192, you must meet the work practice standards in the following table:

For . . .	You must . . .
1. Cell rooms	a. For new or modified cell rooms, construct each cell room interior using materials that are resistant to absorption of mercury, resistant to corrosion, facilitate the detection of liquid mercury spills or accumulations, and are easy to clean. b. Limit access around and beneath mercury cells in each cell room to prevent liquid mercury from being tracked into other areas. c. Provide adequate lighting in each cell room to facilitate the detection of liquid mercury spills or accumulations. d. Minimize the number of items stored around and beneath cells in each cell room.
2. Mercury cells and electrolyzers.	a. Operate and maintain each electrolyzer, decomposer, end box, and mercury pump to minimize leakage of mercury. b. Prior to opening an electrolyzer for maintenance, do the following: (1) Complete work that can be done before opening the electrolyzer in order to minimize the time required to complete maintenance when the electrolyzer is open; (2) fill the electrolyzer with an aqueous liquid, when possible; (3) allow the electrolyzer to cool before opening; and (4) schedule and staff maintenance of the electrolyzer to minimize the time the electrolyzer is open.

For . . .	You must . . .
	c. When the electrolyzer top is raised and before moving the top and anodes, thoroughly flush all visible mercury from the top and the anodes with an aqueous liquid, when possible. d. While an electrolyzer is open, keep the bottom covered with an aqueous liquid or maintain a continuous flow of aqueous liquid, when possible. e. During an electrolyzer side panel change, take measures to ensure an aqueous liquid covers or flows over the bottom, when possible. f. Each time an electrolyzer is opened, inspect and replace components, as appropriate. g. If you step into an electrolyzer bottom, either remove all visible mercury from your footwear or replace them immediately after stepping out of the electrolyzer. h. If an electrolyzer is disassembled for overhaul maintenance or for any other reason, chemically clean the bed plate or thoroughly flush it with an aqueous liquid. i. Before transporting each electrolyzer part to another work area, remove all visible mercury from the part or contain the part to prevent mercury from dripping during transport. j. After completing maintenance on an electrolyzer, check any mercury piping flanges that were opened for liquid mercury leaks. k. If a liquid mercury spill occurs during any maintenance activity on an electrolyzer, clean it up in accordance with the requirements in Table 3 to this subpart.
3. Vessels in liquid mercury service.	If you replace a vessel containing mercury that is intended to trap and collect mercury after December 19, 2003, replace it with a vessel that has a cone shaped bottom with a drain valve or other design that readily facilitates mercury collection.
4. Piping and process lines in liquid mercury service.	a. To prevent mercury buildup after December 19, 2003, equip each new process line and piping system with smooth interiors and adequate low point drains or mercury knock-out pots to avoid liquid mercury buildup within the pipe and to facilitate mercury collection and recovery.
5. Cell room floors	a. Maintain a coating on cell room floors that is resistant to absorption of mercury and that facilitates the detection of liquid mercury spills or accumulations. b. Maintain cell room floors such that they are smooth and free of cracking and spalling. c. Maintain the cell room floor to prevent mercury accumulation in the corners. d. Maintain a layer of aqueous liquid on liquid mercury contained in trenches or drains and replenish the aqueous layer at least once per day. e. Keep the cell room floor clean and free of debris. f. If you step into a liquid mercury spill or accumulation, either remove all visible mercury from your footwear or replace your footwear immediately.
6. End boxes	a. Either equip each end box with a fixed cover that is leak tight, or route the end box head space to an end box ventilation system. b. For each end box ventilation system: maintain a flow of aqueous liquid over the liquid mercury in the end box and maintain the temperature of the aqueous liquid below its boiling point, maintain a negative pressure in the end box ventilation system, and maintain the end box ventilation system in good condition. c. Maintain each end box cover in good condition and keep the end box closed when the cell is in service and when liquid mercury is flowing down the cell, except when operation or maintenance activities require short-term access. d. Keep all bolts and C-clamps used to hold the covers in place when the cell is in service and when liquid mercury is flowing down the cell. e. Maintain each access port stopper in an end box cover in good sealing condition and keep each end box access port closed when the cell is in service and when liquid mercury is flowing down the cell.
7. Decomposers	a. Maintain each decomposer cover in good condition and keep each decomposer closed and sealed, except when maintenance activities require the cover to be removed. b. Maintain connections between the decomposer and the corresponding cell components, hydrogen system piping, and caustic system piping in good condition and keep the connections closed/tight, except when maintenance activities require opening/loosening these connections. c. Keep each mercury cell amalgam seal pot closed and sealed, except when operation or maintenance activities require short-term access. d. Prior to opening a decomposer, do the following: fill the decomposer with an aqueous liquid or drain the decomposer liquid mercury into a container that meets requirements in Table 1, Item 9 or 10, allow the decomposer to cool before opening, and complete work that can be done before opening the decomposer. e. Take precautions to avoid mercury spills when changing graphite grids or balls in horizontal decomposers or graphite packing in vertical decomposers. If a spill occurs, you must clean it up in accordance with the requirements in Table 3 to this subpart. f. After each maintenance activity, use an appropriate technique (Table 6 to this subpart) to check for hydrogen leaks. g. Before transporting any internal part from the decomposer (such as the graphite basket) to another work area, remove all visible mercury from the part or contain the part to prevent mercury from dripping during transport. h. Store carbon from decomposers in accordance with the requirements in 40 CFR part 265, subparts I and CC, until the carbon is treated or is disposed.
8. Submerged mercury pumps	a. Provide a vapor outlet connection from each submerged pump to an end box ventilation system. The connection must be maintained under negative pressure. b. Keep each mercury pump tank closed, except when maintenance or operation activities require the cover to be removed. c. Maintain a flow of aqueous liquid over the liquid mercury in each mercury pump tank and maintain the aqueous liquid at a temperature below its boiling point.

For . . .	You must . . .
9. Open-top containers holding liquid mercury.	Maintain a layer of aqueous liquid over liquid mercury in each open-top container. Replenish the aqueous layer at least once per day and, when necessitated by operating procedures or observation, collect the liquid mercury from the container in accordance with the requirements in Table 4 to this subpart.
10. Closed containers used to store liquid mercury.	a. Store liquid mercury in containers with tight fitting covers. b. Maintain the seals on the covers in good condition. c. Keep each container securely closed when mercury is not being added to, or removed from, the container.
11. Caustic systems	a. Maintain the seal between each caustic basket cover and caustic basket by using gaskets and other appropriate material. b. Do not allow solids and liquids collected from back-flushing primary caustic filters to contact floors or run into open trenches. c. Collect solids and liquids from back-flushing each primary caustic filter and collect these mercury-containing wastes in process vessels or in accordance with the requirements in 40 CFR part 265, subparts I and CC. d. Keep each caustic basket closed and sealed, except when operation or maintenance activities require short term access.
12. Hydrogen systems	a. Collect drips from each hydrogen seal pot and compressor seal in containers meeting the requirements in this table for open containers. These drips should not be allowed to run on the floor or in open trenches. b. Minimize purging of hydrogen from a decomposer into the cell room by either sweeping the decomposer with an inert gas or by routing the hydrogen to the hydrogen system. c. Maintain hydrogen piping gaskets in good condition. d. After any maintenance activities, use an appropriate technique (Table 6 to this subpart) to check all hydrogen piping flanges that were opened for hydrogen leaks.

Table 2 to Subpart IIIII of Part 63—Work Practice Standards—Required Inspections

As stated in §63.8192, you must meet the work practice standards in the following table:

You must inspect . . .	At least once each . . .	And if you find . . .	You must . . .
1. Each vent hose on each mercury cell.	Half day	A leaking vent hose	Take action immediately to correct the leak.
2. Each open-top container holding liquid mercury.	Half day	Liquid mercury that is not covered by an aqueous liquid.	Take action immediately to cover the liquid mercury with an aqueous liquid.
3. Each end box	Half day	a. An end box cover not securely in place.	Take action immediately to put the end box cover securely in place.
		b. An end box stopper not securely in place.	Take action immediately to put the end box stopper securely in place.
		c. Liquid mercury in an end box that is not covered by an aqueous liquid at a temperature below boiling.	Take action immediately to cover the liquid mercury with an aqueous liquid.
4. Each mercury amalgam seal pot.	Half day	A seal pot cover that is not securely in place.	Take action immediately to put the seal pot cover securely in place.
5. Each mercury seal pot	Half day	A mercury seal pot stopper not securely in place.	Take action immediately to put the mercury seal pot stopper securely in place.
6. Cell room floors	Month	Cracks, spalling, or other deficiencies that could cause liquid mercury to become trapped.	Repair the crack, spalling, or other deficiency within 1 month from the time you identify the deficiency.
7. Pillars and beams	6 months	Cracks, spalling, or other deficiencies that could cause liquid mercury to become trapped.	Repair the crack, spalling, or other deficiency within 1 month from the time you identify the deficiency.
8. Each caustic basket	Half day	A caustic basket cover that is not securely in place.	Take action immediately to put the caustic basket cover securely in place.
9. All equipment and piping in the caustic system.	Day	Equipment that is leaking caustic	Initiate repair of the leaking equipment within 72 hours from the time that you identify the caustic leak.

You must inspect . . .	At least once each . . .	And if you find . . .	You must . . .
10. All floors and other surfaces where liquid mercury could accumulate in cell rooms and other production facilities and in mercury recovery facilities.	Half day	A liquid mercury spill or accumulation.	Take the required action specified in Table 3 to this subpart.
11. Each electrolyzer bottom, electrolyzer side panel, end box, mercury amalgam seal pot, decomposer, mercury pump, and hydrogen cooler, and all other vessels, piping, and equipment in liquid mercury service in the cell room.	Day	Equipment that is leaking liquid mercury.	Take the required action specified in Table 3 to this subpart.
12. Each decomposer and all hydrogen piping up to the hydrogen header.	Half day	Equipment that is leaking hydrogen and/or mercury vapor.	Take the required action specified in Table 3 to this subpart.
13. All equipment in the hydrogen system from the start of the header to the last control device.	3 months	Equipment that is leaking hydrogen and/or mercury vapor.	Take the required action specified in Table 3 to this subpart.

TABLE 3 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—REQUIRED ACTIONS FOR LIQUID MERCURY SPILLS AND ACCUMULATIONS AND HYDROGEN AND MERCURY VAPOR LEAKS

As stated in §63.8192, you must meet the work practice standards in the following table:

During a required inspection or at any other time, If you find . . .	You must . . .
1. A liquid mercury spill or accumulation ...	a. Initiate clean up of the liquid mercury spill or accumulation as soon as possible, but no later than 1 hour from the time you detect it. b. Clean up liquid mercury using a mercury vacuum cleaner or by using an alternative method. If you use an alternative method to clean up liquid mercury, you must submit a description of the method to the Administrator in your Notification of Compliance Status report. c. If you use a mercury vacuum cleaner, the vacuum cleaner must be designed to prevent generation of airborne mercury; you must cap the ends of hoses after each use; and after vacuuming, you must wash down the area. d. Inspect all equipment in liquid mercury service in the surrounding area to identify the source of the liquid mercury within 1 hour from the time you detect the liquid mercury spill or accumulation. e. If you identify leaking equipment as the source of the spill or accumulation, contain the dripping mercury, stop the leak, and repair the leaking equipment as specified below. f. If you cannot identify the source of the liquid mercury spill or accumulation, re-inspect the area within 6 hours of the time you detected the liquid mercury spill or accumulation, or within 6 hours of the last inspection of the area.
2. Equipment that is leaking liquid mercury	a. Contain the liquid mercury dripping from the leaking equipment by placing a container under the leak within 30 minutes from the time you identify the liquid mercury leak. b. The container must meet the requirement for open-top containers in Table 1 to this subpart. c. Make a first attempt at stopping the leak within 1 hour from the time you identify the liquid mercury leak. d. Stop the leak and repair the leaking equipment within 4 hours from the time you identify the liquid mercury leak. e. You can delay repair of equipment leaking liquid mercury if you either isolate the leaking equipment from the process so that it does not remain in mercury service; or determine that you cannot repair the leaking equipment without taking the cell off line, provided that you contain the dripping mercury at all times as described above, and take the cell off line as soon as practicable, but no later than 48 hours from the time you identify the leaking equipment. You cannot place the cell back into service until the leaking equipment is repaired.
3. A decomposer or hydrogen system piping up to the hydrogen header that is leaking hydrogen and/or mercury vapor.	a. Make a first attempt at stopping the leak within 1 hour from the time you identify the hydrogen and/or mercury vapor leak. b. Stop the leak and repair the leaking equipment within 4 hours from the time you identify the hydrogen and/or mercury vapor leak. c. You can delay repair of an equipment leaking hydrogen and/or mercury vapor if you isolate the leaking equipment or take the cell off line until you repair the leaking equipment.

During a required inspection or at any other time, If you find . . .	You must . . .
4. Equipment in the hydrogen system, from the start of the hydrogen header to the last control device, that is leaking hydrogen and/or mercury vapor.	a. Make a first attempt at stopping the leak within 4 hours from the time you identify the hydrogen and/or mercury vapor leak. b. Stop the leak and repair the header within 24 hours from the time you identify the hydrogen and/or mercury vapor leak. c. You can delay repair of equipment leaking hydrogen and/or mercury vapor if you isolate the leaking equipment.

TABLE 4 TO SUBPART IIIII OF PART 63—WORK PRACTICE STANDARDS—REQUIREMENTS FOR MERCURY LIQUID COLLECTION

As stated in §63.8192, you must meet the work practice standards in the following table:

You must collect liquid mercury from . . .	At the following intervals	When collecting the mercury, you must meet these requirements		
1. Open-top containers.	a. At least once each 72 hours.	i. If you spill liquid mercury during collection or transport, you must take the action specified in Table 3 to this subpart for liquid mercury spills and accumulations.	ii. From the time that you collect liquid mercury into a temporary container until the time that you store the liquid mercury, you must keep it covered by an aqueous liquid.	iii. Within 4 hours from the time you collect the liquid mercury, you must transfer it from each temporary container to a storage container that meets the specifications in Table 1 to this subpart.
2. Vessels, low point drains, mercury knockout pots, and other closed mercury collection points.	a. At least once each week.	See 1.a.i through iii above.		
3. All other equipment.	a. Whenever maintenance activities require the opening of the equipment.	See 1.a.i. through iii above.		

TABLE 5 TO SUBPART IIIII OF PART 63—REQUIRED ELEMENTS OF FLOOR-LEVEL MERCURY VAPOR MEASUREMENT AND CELL ROOM MONITORING PLANS

Your Floor-Level Mercury Vapor Measurement Plan required by §63.8192(d) prior to the applicable compliance date specified in §63.8186(a)(2) and Cell Room Monitoring Plan required by §63.8192(g) must contain the elements listed in the following table:

You must specify in your plan . . .	Additional requirements
Floor-Level Mercury Vapor Measurement Plan	
1. Locations in the cell room where you will measure the level of mercury vapor.	The locations must be representative of the entire cell room floor area. At a minimum you must measure the level of mercury vapor above mercury-containing cell room equipment, as well as areas around the cells, decomposes, or other mercury-containing equipment.
2. Equipment or sampling and analytical methods that you will use to measure the level of mercury vapor.	If an instrument or other equipment is used, the plan must include manufacturer specifications and calibration procedures. The plan must also include a description of how you will ensure that the instrument will be calibrated and maintained according to manufacturer specifications.
3. Measurement frequency	Measurements must take place at least once each half day.
4. Number of measurements	At least three readings must be taken at each sample location and the average of these readings must be recorded.
5. A floor-level mercury concentration action level	The action level may not be higher than 0.05 mg/m^3.
Cell Room Monitoring Plan	
1. Details of your mercury monitoring system.	
2. How representative sampling will be conducted	Include some pre-plan measurements to demonstrate the profile of mercury concentration in the cell room and how the selected sampling locations ensure conducted representativeness.
3. Quality assurance/quality control procedures for your mercury monitoring system.	Include a description of how you will keep records or other means to demonstrate that the system is operating properly.
4. Your action level	Include the background data used to establish your level.

[68 FR 70928, Dec. 19, 2003, as amended at 87 FR 27024, May 6, 2022]

TABLE 6 TO SUBPART IIIII OF PART 63—EXAMPLES OF TECHNIQUES FOR EQUIPMENT PROBLEM IDENTIFICATION, LEAK DETECTION AND MERCURY VAPOR

As stated in Tables 1 and 2 of Subpart IIIII, examples of techniques for equipment problem identification, leak detection and mercury vapor measurements can be found in the following table:

To detect . . .	You could use . . .	Principle of detection . . .
1. Leaking vent hoses; liquid mercury that is not covered by an aqueous liquid in open-top containers or end boxes; end box covers or stoppers, amalgam seal pot stoppers, or caustic basket covers not securely in place; cracks or spalling in cell room floors, pillars, or beams; caustic leaks; liquid mercury accumulations or spills; and equipment that is leaking liquid mercury.	Visual inspections	
2. Equipment that is leaking hydrogen and/or mercury vapor during inspections required by Table 2 to this subpart.	a. Auditory and visual inspections	
	b. Portable mercury vapor analyzer—ultraviolet light absorption detector.	A sample of gas is drawn through a detection cell where ultraviolet light at 253.7 nanometers (nm) is directed perpendicularly through the sample toward a photodetector. Elemental mercury absorbs the incident light in proportion to its concentration in the air stream.
	c. Portable mercury vapor analyzer—gold film amalgamation detector.	A sample of gas is drawn through a detection cell containing a gold film detector. Elemental mercury amalgamates with the gold film, changing the resistance of the detector in proportion to the mercury concentration in the air sample.

To detect . . .	You could use . . .	Principle of detection . . .
	d. Portable short-wave ultraviolet light, fluorescent background—visual indication.	Ultraviolet light is directed toward a fluorescent background positioned behind a suspected source of mercury emissions. Elemental mercury vapor absorbs the ultraviolet light, projecting a dark shadow image on the fluorescent background.
	e. Portable combustible gas meter.	
3. Level of mercury vapor in the cell room and other areas.	a. Portable mercury vapor analyzer—ultraviolet light absorption detector.	See Item 2.b.
	b. Portable mercury vapor analyzer—gold film amalgamation detector.	See Item 2.c.
	c. Permanganate impingement	A known volume of gas sample is absorbed in potassium permanganate solution. Elemental mercury in the solution is determined using a cold vapor adsorption analyzer, and the concentration of mercury in the gas sample is calculated.

Table 7 to Subpart IIIII of Part 63—Required Elements of Washdown Plans

As stated in §63.8192, your written washdown plan must address the elements contained in the following table:

For each of the following areas . . .	You must establish the following as part of your plan . . .
1. Center aisles of cell rooms	A description of the manner of washdown of the area, and the washdown frequency for the area.
2. Electrolyzers	
3. End boxes and areas under end boxes	
4. Decomposers and areas under decomposers	
5. Caustic baskets and areas around caustic baskets	
6. Hydrogen system piping	
7. Basement floor of cell rooms	
8. Tanks	
9. Pillars and beams in cell rooms	
10. Mercury cell repair areas	
11. Maintenance shop areas	
12. Work tables	
13. Mercury thermal recovery units	
14. Storage areas for mercury-containing wastes	

Table 8 to Subpart IIIII of Part 63—Requirements for Cell Room Monitoring Program

As stated in §63.8192(g)(1), your mercury monitoring system must meet the requirements contained in the following table:

If you utilize an . . .	Your . . .	Must . . .
1. Extractive cold vapor spectroscopy system.	a. Mercury vapor analyzer	Be capable of continuously monitoring the elemental mercury concentration with a detection level at least two times lower than the baseline mercury concentration in the cell room.
	b. Sampling system	Obtain measurements at three or more locations along the center aisle of the cell room at a height sufficient to ensure that sample is representative of the entire cell room. One sampling location must be above the midpoint of the center aisle, and the other two an equidistance between the midpoint and the end of the cells.
2. Open path differential optical absorption spectroscopy system.	a. Mercury vapor analyzer	Be capable of continuously monitoring the elemental mercury concentration with a detection level at least two times lower than the baseline mercury concentration in the cell room.
	b. Path	Be directed along the center aisle at a height sufficient to ensure that the sample is representative of the entire cell room.

TABLE 9 TO SUBPART IIIII OF PART 63—REQUIRED RECORDS FOR WORK PRACTICE STANDARDS

As stated in §63.8256(c), you must keep the records (related to the work practice standards) specified in the following table:

For each . . .	You must record the following information . . .
1. Inspection required by Table 2 to this subpart	Date and time the inspection was conducted.
2. Situation found during an inspection required by Table 2 to this subpart: leaking vent hose; open-top container where liquid mercury is not covered by an aqueous liquid; end box cover that is not securely in place; end box stopper that is not securely in place; end box where liquid mercury is not covered by an aqueous liquid at a temperature below boiling; seal pot cover that is not securely in place; open or mercury seal pot stopper that is not securely in place; crack, spalling, or other deficiency in a cell room floor, pillar, or beam that could cause liquid mercury to become trapped; or caustic basket that is not securely in place.	a. Description of the condition. b. Location of the condition. c. Date and time you identify the condition. d. Description of the corrective action taken. e. Date and time you successfully complete the corrective action.
3. Caustic leak during an inspection required by Table 2 to this subpart.	a. Location of the leak. b. Date and time you identify the leak. c. Date and time you successfully stop the leak and repair the leaking equipment.
4. Liquid mercury spill or accumulation identified during an inspection required by Table 2 to this subpart or at any other time.	a. Location of the liquid mercury spill or accumulation. b. Estimate of the weight of liquid mercury. c. Date and time you detect the liquid mercury spill or accumulation. d. Method you use to clean up the liquid mercury spill or accumulation. e. Date and time when you clean up the liquid mercury spill or accumulation. f. Source of the liquid mercury spill or accumulation. g. If the source of the liquid mercury spill or accumulation is not identified, the time when you reinspect the area.
5. Liquid mercury leak or hydrogen leak identified during an inspection required by Table 2 to this subpart or at any other time.	a. Location of the leak. b. Date and time you identify the leak. c. If the leak is a liquid mercury leak, the date and time that you successfully contain the dripping liquid mercury. d. Date and time you first attempt to stop the leak. e. Date and time you successfully stop the leak and repair the leaking equipment. f. If you take a cell off line or isolate the leaking equipment, the date and time you take the cell off line or isolate the leaking equipment, and the date and time you put the cell or isolated equipment back into service.
6. Occasion for which it is not possible to perform the design, operation and maintenance procedures required by Item 2 of Table 1 to this subpart.	a. Reason for not being able to perform each procedure determined to be not possible. b. Actions taken to reduce or prevent mercury emissions, in lieu of the requirements in Table 1 to this subpart.

TABLE 10 TO SUBPART IIIII OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART IIIII

As stated in §63.8262, you must comply with the applicable General Provisions requirements according to the following table:

Citation	Subject	Applies to subpart IIIII	Explanation
§63.1	Applicability	Yes.	
§63.2	Definitions	Yes.	
§63.3	Units and Abbreviations	Yes.	
§63.4	Prohibited Activities	Yes.	
§63.5	Construction/Reconstruction	Yes.	
§63.6(a)–(g), (i), (j), except for (e)(1)(i) and (ii), (e)(3), and (f)(1).	Compliance with Standards and Maintenance Requirements.	Yes.	
§63.6(e)(1)(i) and (ii), (e)(3), and (f)(1).	SSM Requirements	Yes	Only applies until the date specified in §63.8186(a)(3).
§63.6(h)	Compliance with Opacity and Visible Emission Standards.	No	Subpart IIIII does not have opacity and visible emission standards.

Citation	Subject	Applies to subpart IIIII	Explanation
§ 63.7(a)–(h), except for (a)(2) and (e)(1).	Performance Testing Requirements.	Yes	Subpart IIIII specifies additional requirements related to site-specific test plans and the conduct of performance tests.
§ 63.7(a)(2)	Applicability and Performance Test Dates.	No	Subpart IIIII requires the performance test to be performed on the compliance date.
§ 63.7(e)(1)	Performance Test Conditions	No	See § 63.8232(a).
§ 63.8(a)(1), (a)(3); (b); (c)(1)(ii), (2)–(4), (6)–(8); (d)(1)–(2); (e); and (f)(1)–(5).	Monitoring Requirements	Yes	Only applies for CEMS, except Subpart IIIII specifies how and when the performance evaluation results are reported.
§ 63.8(a)(2)	Continuous Monitoring System (CMS) Requirements.	No	Subpart IIIII requires a site-specific monitoring plan in lieu of a promulgated performance specification for a mercury concentration CMS.
§ 63.8(a)(4)	Additional Monitoring Requirements for Control Devices in § 63.11.	No	Subpart IIIII does not require flares.
§ 63.8(c)(1)(i) and (iii)	CMS Operation and SSM Plan.	Yes	Only applies until the date specified in § 63.8186(a)(3).
§ 63.8(c)(5)	COMS Minimum Procedures	No	Subpart IIIII does not have opacity and visible emission standards.
§ 63.8(d)(3)	Written Procedures for CMS	No	See § 63.8242(a)(3)(v).
§ 63.8(f)(6)	Alternative to Relative Accuracy Test.	No	Subpart IIIII does not require CEMS.
§ 63.8(g)	Data Reduction	No	Subpart IIIII specifies mercury concentration CMS data reduction requirements.
§ 63.9(a)–(e), (g)–(j)	Notification Requirements	Yes.	
§ 63.9(f)	Notification of VE/Opacity Test.	No	Subpart IIIII does not have opacity and visible emission standards.
§ 63.9(k)	Electronic reporting procedures.	Yes	Only as specified in § 63.9(j).
§ 63.10(a); (b)(1); (b)(2)(vi)–(xii), (xiv); (b)(3); (c)(1)–(14); (d)(1), (4); (e); (f).	Recordkeeping/Reporting	Yes.	
§ 63.10(b)(2)(i)–(v)	Recordkeeping/Reporting Associated with Startup, Shutdown, and Malfunctions.	Yes	Only applies until the date specified in § 63.8186(a)(3).
§ 63.10(b)(2)(xiii)	CMS Records for RATA Alternative.	No	Subpart IIIII does not require CEMS.
§ 63.10(c)(15)	Use of SSM Plan	Yes	Only applies until the date specified in § 63.8186(a)(3).
§ 63.10(d)(2)	Performance Test Results	No	This subpart at 63.8232(g) specifies how and when the performance test results are reported electronically.
§ 63.10(d)(3)	Reporting Opacity or VE Observations.	No	Subpart IIIII does not have opacity and visible emission standards.
§ 63.10(d)(5)	Startup, Shutdown, and Malfunction Reports.	No.	
§ 63.10(e)(2)(i)	CEM Reporting	Yes	Except this subpart specifies how and when the performance evaluation results are reported.
§ 63.11	Flares	No	Subpart IIIII does not require flares.
§ 63.12	Delegation	Yes.	
§ 63.13	Addresses	Yes.	
§ 63.14	Incorporation by Reference	Yes.	
§ 63.15	Availability of Information	Yes.	

[87 FR 27024, May 6, 2022]

Subpart JJJJJ—National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing

SOURCE: 80 FR 65520, Oct. 26, 2015, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.8380 What is the purpose of this subpart?

This subpart establishes national emission limitations for hazardous air pollutants (HAP) emitted from brick and structural clay products (BSCP) manufacturing facilities. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations.

§ 63.8385 Am I subject to this subpart?

You are subject to this subpart if you own or operate a BSCP manufacturing facility that is, is located at, or is part of, a major source of HAP emissions according to the criteria in paragraphs (a) and (b) of this section.

(a) A BSCP manufacturing facility is a plant site that manufactures brick (including, but not limited to, face brick, structural brick, and brick pavers); clay pipe; roof tile; extruded floor and wall tile; and/or other extruded, dimensional clay products. Brick and structural clay products manufacturing facilities typically process raw clay and shale, form the processed materials into bricks or shapes, and dry and fire the bricks or shapes. A plant site that manufactures refractory products, as defined in § 63.9824, or clay ceramics, as defined in § 63.8665, is not a BSCP manufacturing facility.

(b) A major source of HAP emissions is any stationary source or group of stationary sources within a contiguous area under common control that emits or has the potential to emit any single HAP at a rate of 9.07 megagrams (10 tons) or more per year or any combination of HAP at a rate of 22.68 megagrams (25 tons) or more per year.

§ 63.8390 What parts of my plant does this subpart cover?

(a) This subpart applies to each existing, new, or reconstructed affected source at a BSCP manufacturing facility.

(b) For the purposes of this subpart, the affected sources are described in paragraphs (b)(1) and (2) of this section.

(1) All tunnel kilns at a BSCP manufacturing facility are an affected source. For the remainder of this subpart, a tunnel kiln with a design capacity equal to or greater than 9.07 megagrams per hour (Mg/hr) (10 tons per hour (tph)) of fired product will be called a large tunnel kiln, and a tunnel kiln with a design capacity less than 9.07 Mg/hr (10 tph) of fired product will be called a small tunnel kiln.

(2) Each periodic kiln is an affected source.

(c) Process units not subject to the requirements of this subpart are listed in paragraphs (c)(1) through (4) of this section.

(1) Kilns that are used exclusively for setting glazes on previously fired products are not subject to the requirements of this subpart.

(2) Raw material processing and handling.

(3) Dryers.

(4) Sources covered by subparts KKKKK and SSSSS of this part.

(d) A source is a new affected source if construction of the affected source began after December 18, 2014, and you met the applicability criteria at the time you began construction.

(e) An affected source is reconstructed if you meet the criteria as defined in § 63.2.

(f) An affected source is existing if it is not new or reconstructed.

§ 63.8395 When do I have to comply with this subpart?

(a) You must comply with this subpart no later than the compliance dates in Table 7 to this subpart.

(b) You must meet the notification requirements in § 63.8480 according to the schedule in § 63.8480 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

§ 63.8405 What emission limitations and work practice standards must I meet?

(a) You must meet each emission limit in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit in Table 2 to this subpart that applies to you.

(c) You must meet each work practice standard in Table 3 to this subpart that applies to you.

§ 63.8410 What are my options for meeting the emission limitations and work practice standards?

(a) To meet the emission limitations in Tables 1 and 2 to this subpart, you must use one or more of the options listed in paragraphs (a)(1) and (2) of this section.

(1) *Emissions control system*. Use an emissions capture and collection system and an air pollution control device (APCD) and demonstrate that the resulting emissions meet the emission limits in Table 1 to this subpart, and that the capture and collection system and APCD meet the applicable operating limits in Table 2 to this subpart.

(2) *Process changes*. Use low-HAP raw materials or implement manufacturing process changes and demonstrate that the resulting emissions or emissions reductions meet the emission limits in Table 1 to this subpart.

(b) To meet the work practice standards for affected periodic kilns, you must comply with the requirements listed in Table 3 to this subpart.

(c) To meet the work practice standards for dioxins/furans for affected tunnel kilns, you must comply with the requirements listed in Table 3 to this subpart.

(d) To meet the work practice standards for affected tunnel kilns during periods of startup and shutdown, you must comply with the requirements listed in Table 3 to this subpart.

GENERAL COMPLIANCE REQUIREMENTS

§ 63.8420 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods that you are approved for and in compliance with the alternative standard for routine control device maintenance as specified in paragraph (d) of this section, and except during periods of start-up and shutdown, at which time you must comply with the applicable work practice standard specified in Table 3 to this subpart.

(b) At all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source. During the period between the compliance date specified for your affected source in § 63.8395 and the date upon which continuous monitoring systems (CMS) (*e.g.*, continuous parameter monitoring systems) have been installed and verified and any applicable operating limits have been set, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.

(c) For each affected kiln that is subject to the emission limits specified in Table 1 to this subpart, you must prepare and implement a written operation, maintenance, and monitoring (OM&M) plan according to the requirements in § 63.8425.

(d) If you own or operate an affected kiln that is subject to the emission

limits specified in Table 1 to this subpart and must perform routine maintenance on the control device for that kiln, you may bypass the kiln control device and continue operating the kiln subject to the alternative standard established in this paragraph upon approval by the Administrator and provided you satisfy the conditions listed in paragraphs (d)(1) through (5) of this section.

(1) You must request to use the routine control device maintenance alternative standard from the Administrator no later than 120 calendar days before the compliance date specified in § 63.8395. Your request must justify the need for the routine maintenance on the control device and the time required to accomplish the maintenance activities, describe the maintenance activities and the frequency of the maintenance activities, explain why the maintenance cannot be accomplished during kiln shutdowns, provide information stating whether the continued operation of the affected source will result in fewer emissions than shutting the source down while the maintenance is performed, describe how you plan to comply with paragraph (b) of this section during the maintenance, and provide any other documentation required by the Administrator.

(2) The routine control device maintenance must not exceed 4 percent of the annual operating uptime for each kiln.

(3) The request for the routine control device maintenance alternative standard, if approved by the Administrator, must be incorporated by reference in and attached to the affected source's title V permit.

(4) You must minimize HAP emissions during the period when the kiln is operating and the control device is offline by complying with the applicable standard in Table 3 to this subpart.

(5) You must minimize the time period during which the kiln is operating and the control device is offline.

(e) You must be in compliance with the work practice standards in this subpart at all times.

(f) You must be in compliance with the provisions of subpart A of this part, except as noted in Table 10 to this subpart.

§ 63.8425 What do I need to know about operation, maintenance, and monitoring plans?

(a) For each affected kiln that is subject to the emission limits specified in Table 1 to this subpart, you must prepare, implement, and revise as necessary an OM&M plan that includes the information in paragraph (b) of this section. Your OM&M plan must be available for inspection by the delegated authority upon request.

(b) Your OM&M plan must include, as a minimum, the information in paragraphs (b)(1) through (13) of this section.

(1) Each process and APCD to be monitored, the type of monitoring device that will be used, and the operating parameters that will be monitored.

(2) A monitoring schedule that specifies the frequency that the parameter values will be determined and recorded.

(3) The limits for each parameter that represent continuous compliance with the emission limitations in § 63.8405. The limits must be based on values of the monitored parameters recorded during performance tests.

(4) Procedures for the proper operation and routine and long-term maintenance of each APCD, including a maintenance and inspection schedule that is consistent with the manufacturer's recommendations.

(5) Procedures for installing the CMS sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last APCD).

(6) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system.

(7) Continuous monitoring system performance evaluation procedures and acceptance criteria (*e.g.*, calibrations).

(8) Procedures for the proper operation and maintenance of monitoring equipment consistent with the requirements in §§ 63.8450 and 63.8(c)(1), (3), (7), and (8).

(9) Continuous monitoring system data quality assurance procedures consistent with the requirements in § 63.8(d)(1) and (2). The owner or operator shall keep these written procedures on record for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan in § 63.8(d)(2) is revised, the owner or operator shall keep previous (*i.e.*, superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action should be included in the plan required under § 63.8(d)(2).

(10) Continuous monitoring system recordkeeping and reporting procedures consistent with the requirements in §§ 63.8485 and 63.8490.

(11) Procedures for responding to operating parameter deviations, including the procedures in paragraphs (b)(11)(i) through (iii) of this section.

(i) Procedures for determining the cause of the operating parameter deviation.

(ii) Actions necessary for correcting the deviation and returning the operating parameters to the allowable limits.

(iii) Procedures for recording the times that the deviation began and ended and corrective actions were initiated and completed.

(12) Procedures for keeping records to document compliance.

(13) If you operate an affected kiln and you plan to take the kiln control device out of service for routine maintenance, as specified in § 63.8420(d), the procedures specified in paragraphs (b)(13)(i) and (ii) of this section.

(i) Procedures for minimizing HAP emissions from the kiln during periods of routine maintenance of the kiln control device when the kiln is operating and the control device is offline.

(ii) Procedures for minimizing the duration of any period of routine maintenance on the kiln control device when the kiln is operating and the control device is offline.

(c) Changes to the operating limits in your OM&M plan require a new performance test. If you are revising an operating limit parameter value, you must meet the requirements in paragraphs (c)(1) and (2) of this section.

(1) Submit a notification of performance test to the Administrator as specified in § 63.7(b).

(2) After completing the performance tests to demonstrate that compliance with the emission limits can be achieved at the revised operating limit parameter value, you must submit the performance test results and the revised operating limits as part of the Notification of Compliance Status required under § 63.9(h).

(d) If you are revising the inspection and maintenance procedures in your OM&M plan, you do not need to conduct a new performance test.

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.8435 By what date must I conduct performance tests?

For each affected kiln that is subject to the emission limits specified in Table 1 to this subpart, you must conduct performance tests within 180 calendar days after the compliance date that is specified for your source in § 63.8395 and according to the provisions in § 63.7(a)(2).

§ 63.8440 When must I conduct subsequent performance tests?

(a) For each affected kiln that is subject to the emission limits specified in Table 1 to this subpart, you must conduct a performance test before renewing your 40 CFR part 70 operating permit or at least every 5 years following the initial performance test.

(b) You must conduct a performance test when you want to change the parameter value for any operating limit specified in your OM&M plan.

§ 63.8445 How do I conduct performance tests and establish operating limits?

(a) You must conduct each performance test in Table 4 to this subpart that applies to you.

(b) Before conducting the performance test, you must install and calibrate all monitoring equipment.

(c) Each performance test must be conducted according to the requirements in § 63.7 and under the specific conditions in Table 4 to this subpart.

(d) Performance tests shall be conducted under such conditions as the Administrator specifies to you based on representative performance of the affected source for the period being tested. Representative conditions exclude periods of startup and shutdown. You may not conduct performance tests during periods of malfunction. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(e) You must conduct at least three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.

(f) You must use the data gathered during the performance test and the equations in paragraphs (f)(1) and (2) of this section to determine compliance with the emission limitations.

(1) To determine compliance with the production-based particulate matter (PM) and mercury (Hg) emission limits in Table 1 to this subpart, you must calculate your mass emissions per unit of production for each test run using Equation 1:

$$MP = \frac{ER}{P} \qquad \text{(Eq. 1)}$$

Where:

MP = mass per unit of production, kilograms (pounds) of pollutant per megagram (ton) of fired product

ER = mass emission rate of pollutant (PM or Hg) during each performance test run, kilograms (pounds) per hour

P = production rate during each performance test run, megagrams (tons) of fired product per hour.

(2) To determine compliance with the health-based standard for acid gas HAP for BSCP manufacturing facilities in Table 1 to this subpart, you must:

(i) Calculate the HCl-equivalent emissions for HF, HCl, and Cl_2 for each tunnel kiln at your facility using Equation 2:

$$E_i = E_{HCl} + \left[E_{HF} \left(\frac{RfC_{HCl}}{RfC_{HF}} \right) \right] + \left[E_{Cl_2} \left(\frac{RfC_{HCl}}{RfC_{Cl_2}} \right) \right] \qquad \text{(Eq. 2)}$$

Where:

E_i = HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

E_{HCl} = emissions of HCl, kilograms (pounds) per hour

E_{HF} = emissions of HF, kilograms (pounds) per hour

E_{Cl2} = emissions of Cl_2, kilograms (pounds) per hour

RfC_{HCl} = reference concentration for HCl, 20 micrograms per cubic meter

RfC_{HF} = reference concentration for HF, 14 micrograms per cubic meter

RfC_{Cl2} = reference concentration for Cl_2, 0.15 micrograms per cubic meter

(ii) If you have multiple tunnel kilns at your facility, sum the HCl-equivalent values for all tunnel kilns at the facility using Equation 3:

$$E_{total} = \sum_{i=1}^{n} E_i \qquad \text{(Eq. 3)}$$

Where:

E_{total} = HCl-equivalent emissions for total of all kilns at facility, kilograms (pounds) per hour

E_i = HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

n = number of tunnel kilns at facility

(iii) Compare this value to the health-based standard in Table 1 to this subpart.

(g) You must establish each site-specific operating limit in Table 2 to this subpart that applies to you as specified in paragraph (g)(1) of this section and in Table 4 to this subpart.

(1)(i) If you do not have an APCD installed on your kiln, calculate the maximum potential HCl-equivalent emissions for HF, HCl, and Cl_2 for each tunnel kiln at your facility using Equation 4:

$$E_{\max i} = (Cap_i)\left[(MP_{iHCl}) + (MP_{iHF})\left(\frac{RfC_{HCl}}{RfC_{HF}}\right) + (MP_{iCl_2})\left(\frac{RfC_{HCl}}{RfC_{Cl_2}}\right)\right] \qquad \text{(Eq. 4)}$$

Where:

$E_{max\ i}$ = maximum potential HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

Cap_i = design capacity for kiln i, megagrams (tons) of fired product per hour

MP_{iHCl} = mass of HCl per unit of production for kiln i, kilograms (pounds) of HCl per megagram (ton) of fired product

MP_{iHF} = mass of HF per unit of production for kiln i, kilograms (pounds) of HF per megagram (ton) of fired product

MP_{iCl2} = mass of Cl_2 per unit of production for kiln i, kilograms (pounds) of Cl_2 per megagram (ton) of fired product

RfC_{HCl} = reference concentration for HCl, 20 micrograms per cubic meter

RfC_{HF} = reference concentration for HF, 14 micrograms per cubic meter

RfC_{Cl2} = reference concentration for Cl_2, 0.15 micrograms per cubic meter

(ii) If you have multiple tunnel kilns at your facility, sum the maximum potential HCl-equivalent values for all tunnel kilns at the facility using Equation 5:

$$E_{\max total} = \sum_{i=1}^{n} E_{\max i} \qquad \text{(Eq. 5)}$$

Where:

$E_{max\ total}$ = maximum potential HCl-equivalent emissions for total of all kilns at facility, kilograms (pounds) per hour

$E_{max\ i}$ = maximum potential HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

n = number of tunnel kilns at facility

(iii) If you have a single tunnel kiln at your facility and the total facility maximum potential HCl-equivalent emissions ($E_{max\ total}$) are greater than the HCl-equivalent limit in Table 1 to this subpart, determine the maximum process rate for the tunnel kiln using Equation 6 that would ensure the total facility maximum potential HCl-equivalent emissions remain at or below the HCl-equivalent limit. The maximum process rate would become your operating limit for process rate and must be included in your OM&M plan.

$$P_{\max i} = \frac{HCl\text{ - }eq}{\left[\left(MP_{iHCl}\right) + \left(MP_{iHF}\right)\left(\frac{RfC_{HCl}}{RfC_{HF}}\right) + \left(MP_{iCl_2}\right)\left(\frac{RfC_{HCl}}{RfC_{Cl_2}}\right)\right]} \quad \text{(Eq. 6)}$$

Where:

$P_{max\ i}$ = maximum process rate for kiln i, megagrams (tons) per hour

HCl-eq = HCl-equivalent limit in Table 1 to this subpart, 26 kilograms (57 pounds) per hour

MP_{iHCl} = mass of HCl per unit of production for kiln i, kilograms (pounds) of HCl per megagram (ton) of fired product

MP_{iHF} = mass of HF per unit of production for kiln i, kilograms (pounds) of HF per megagram (ton) of fired product

MP_{iCl2} = mass of Cl_2 per unit of production for kiln i, kilograms (pounds) of Cl_2 per megagram (ton) of fired product

RfC_{HCl} = reference concentration for HCl, 20 micrograms per cubic meter

RfC_{HF} = reference concentration for HF, 14 micrograms per cubic meter

RfC_{Cl2} = reference concentration for Cl_2, 0.15 micrograms per cubic meter

(iv) If you have multiple tunnel kilns at your facility and the total facility maximum potential HCl-equivalent emissions ($E_{max\ total}$) are greater than the HCl-equivalent limit in Table 1 to this subpart, determine the combination of maximum process rates that would ensure that total facility maximum potential HCl-equivalent remains at or below the HCl-equivalent limit. The maximum process rates would become your operating limits for process rate and must be included in your OM&M plan.

(2) [Reserved]

(h) For each affected kiln that is subject to the emission limits specified in Table 1 to this subpart and is equipped with an APCD that is not addressed in Table 2 to this subpart or that is using process changes as a means of meeting the emission limits in Table 1 to this subpart, you must meet the requirements in §63.8(f) and paragraphs (h)(1) and (2) of this section.

(1) Submit a request for approval of alternative monitoring procedures to the Administrator no later than the notification of intent to conduct a performance test. The request must contain the information specified in paragraphs (h)(1)(i) through (iv) of this section.

(i) A description of the alternative APCD or process changes.

(ii) The type of monitoring device or procedure that will be used.

(iii) The operating parameters that will be monitored.

(iv) The frequency that the operating parameter values will be determined and recorded to establish continuous compliance with the operating limits.

(2) Establish site-specific operating limits during the performance test based on the information included in the approved alternative monitoring procedures request and, as applicable, as specified in Table 4 to this subpart.

§63.8450 What are my monitoring installation, operation, and maintenance requirements?

(a) You must install, operate, and maintain each CMS according to your OM&M plan and the requirements in paragraphs (a)(1) through (5) of this section.

(1) Conduct a performance evaluation of each CMS according to your OM&M plan.

(2) The CMS must complete a minimum of one cycle of operation for each successive 15-minute period. To have a valid hour of data, you must have at least three of four equally spaced data values (or at least 75 percent if you collect more than four data values per hour) for that hour (not including startup, shutdown, malfunction, out-of-control periods, or periods of routine control device maintenance covered by the routine control device maintenance alternative standard as specified in §63.8420(d)).

(3) Determine and record the 3-hour block averages of all recorded readings, calculated after every 3 hours of operation as the average of the previous 3 operating hours. To calculate the average for each 3-hour average period, you

must have at least 75 percent of the recorded readings for that period (not including startup, shutdown, malfunction, out-of-control periods, or periods of routine control device maintenance covered by the routine control device maintenance alternative standard as specified in § 63.8420(d)).

(4) Record the results of each inspection, calibration, and validation check.

(5) At all times, maintain the monitoring equipment including, but not limited to, maintaining necessary parts for routine repairs of the monitoring equipment.

(b) For each liquid flow measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (b)(1) through (3) of this section.

(1) Locate the flow sensor in a position that provides a representative flowrate.

(2) Use a flow sensor with a minimum measurement sensitivity of 2 percent of the liquid flowrate.

(3) At least semiannually, conduct a flow sensor calibration check.

(c) For each pressure measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (c)(1) through (7) of this section.

(1) Locate the pressure sensor(s) in or as close to a position that provides a representative measurement of the pressure.

(2) Minimize or eliminate pulsating pressure, vibration, and internal and external corrosion.

(3) Use a gauge with a minimum measurement sensitivity of 0.5 inch of water or a transducer with a minimum measurement sensitivity of 1 percent of the pressure range.

(4) Check the pressure tap daily to ensure that it is not plugged.

(5) Using a manometer, check gauge calibration quarterly and transducer calibration monthly.

(6) Any time the sensor exceeds the manufacturer's specified maximum operating pressure range, conduct calibration checks or install a new pressure sensor.

(7) At least monthly, inspect all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(d) For each pH measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (d)(1) through (4) of this section.

(1) Locate the pH sensor in a position that provides a representative measurement of pH.

(2) Ensure the sample is properly mixed and representative of the fluid to be measured.

(3) Check the pH meter's calibration at one point daily.

(4) At least monthly, inspect all components for integrity and all electrical connections for continuity.

(e) For each bag leak detection system, you must meet the requirements in paragraphs (e)(1) through (11) of this section.

(1) Each triboelectric bag leak detection system must be installed, calibrated, operated, and maintained according to EPA–454/R–98–015, ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference, see § 63.14). Other types of bag leak detection systems must be installed, operated, calibrated, and maintained in a manner consistent with the manufacturer's written specifications and recommendations.

(2) The bag leak detection system must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(3) The bag leak detection system sensor must provide an output of relative PM loadings.

(4) The bag leak detection system must be equipped with a device to continuously record the output signal from the sensor.

(5) The bag leak detection system must be equipped with an audible alarm system that will sound automatically when an increase in relative PM emissions over a preset level is detected. The alarm must be located where it is easily heard by plant operating personnel.

(6) For positive pressure fabric filter systems, a bag leak detector must be installed in each baghouse compartment or cell.

(7) For negative pressure or induced air fabric filters, the bag leak detector

must be installed downstream of the fabric filter.

(8) Where multiple detectors are required, the system's instrumentation and alarm may be shared among detectors.

(9) The baseline output must be established by adjusting the range and the averaging period of the device and establishing the alarm set points and the alarm delay time according to section 5.0 of the EPA–454/R–98–015, ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference, see § 63.14).

(10) Following initial adjustment of the system, the sensitivity or range, averaging period, alarm set points, or alarm delay time may not be adjusted except as detailed in your OM&M plan. In no case may the sensitivity be increased by more than 100 percent or decreased more than 50 percent over a 365-day period unless such adjustment follows a complete fabric filter inspection that demonstrates that the fabric filter is in good operating condition, as defined in section 5.2 of the ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference, see § 63.14). Record each adjustment.

(11) Record the results of each inspection, calibration, and validation check.

(f) For each lime, chemical, or carbon feed rate measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (f)(1) and (2) of this section.

(1) Locate the measurement device in a position that provides a representative feed rate measurement.

(2) At least semiannually, conduct a calibration check.

(g) For each limestone feed system on a dry limestone adsorber (DLA), you must meet the requirements in paragraphs (a)(1), (4), and (5) of this section and must ensure on a monthly basis that the feed system replaces limestone at least as frequently as the schedule set during the performance test.

(h) For each temperature measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (h)(1) through (3) of this section.

(1) Locate the measurement device in a position that provides a representative temperature.

(2) Use a measurement device with a minimum sensitivity of 1 percent of the temperature being measured.

(3) At least semiannually, conduct a calibration check.

(i) Requests for approval of alternate monitoring procedures must meet the requirements in §§ 63.8445(h) and 63.8(f).

§ 63.8455 How do I demonstrate initial compliance with the emission limitations and work practice standards?

(a) You must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to Table 5 to this subpart.

(b) You must establish each site-specific operating limit in Table 2 to this subpart that applies to you according to the requirements in § 63.8445 and Table 4 to this subpart.

(c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8480(c).

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.8465 How do I monitor and collect data to demonstrate continuous compliance?

(a) You must monitor and collect data according to this section.

(b) Except for periods of monitor malfunctions, associated repairs, and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times that the affected source is operating. This includes periods of startup, shutdown, malfunction, and routine control device maintenance as specified in § 63.8420(d) when the affected source is operating.

(c) You may not use data recorded during monitoring malfunctions, associated repairs, out-of-control periods, or required quality assurance or control activities for purposes of calculating data averages. You must use all the valid data collected during all

other periods in assessing compliance. Any averaging period for which you do not have valid monitoring data and such data are required constitutes a deviation from the monitoring requirements.

§ 63.8470 How do I demonstrate continuous compliance with the emission limitations and work practice standards?

(a) You must demonstrate continuous compliance with each emission limit, operating limit, and work practice standard in Tables 1, 2, and 3 to this subpart that applies to you according to the methods specified in Table 6 to this subpart.

(b) For each affected kiln that is subject to the emission limits specified in Table 1 to this subpart and is equipped with an APCD that is not addressed in Table 2 to this subpart, or that is using process changes as a means of meeting the emission limits in Table 1 to this subpart, you must demonstrate continuous compliance with each emission limit in Table 1 to this subpart, and each operating limit established as required in § 63.8445(h)(2) according to the methods specified in your approved alternative monitoring procedures request, as described in §§ 63.8445(h)(1) and 63.8(f).

(c) You must report each instance in which you did not meet each emission limit and each operating limit in this subpart that applies to you. These instances are deviations from the emission limitations in this subpart. These deviations must be reported according to the requirements in § 63.8485(c)(9).

(d) [Reserved]

(e)(1) *VE testing.* You must demonstrate continuous compliance with the operating limits in Table 2 to this subpart for visible emissions (VE) from tunnel kilns that are uncontrolled or equipped with DLA, dry lime injection fabric filter (DIFF), dry lime scrubber/fabric filter (DLS/FF), or other dry control device by monitoring VE at each kiln stack according to the requirements in paragraphs (e)(1)(i) through (v) of this section.

(i) Perform daily VE observations of each kiln stack according to the procedures of Method 22 of 40 CFR part 60, appendix A–7. You must conduct the Method 22 test while the affected source is operating under normal conditions. The duration of each Method 22 test must be at least 15 minutes.

(ii) If VE are observed during any daily test conducted using Method 22 of 40 CFR part 60, appendix A–7, you must promptly conduct an opacity test, according to the procedures of Method 9 of 40 CFR part 60, appendix A–4. If opacity greater than 10 percent is observed, you must initiate and complete corrective actions according to your OM&M plan.

(iii) You may decrease the frequency of Method 22 testing from daily to weekly for a kiln stack if one of the conditions in paragraph (e)(1)(iii)(A) or (B) of this section is met.

(A) No VE are observed in 30 consecutive daily Method 22 tests for any kiln stack; or

(B) No opacity greater than 10 percent is observed during any of the Method 9 tests for any kiln stack.

(iv) If VE are observed during any weekly test and opacity greater than 10 percent is observed in the subsequent Method 9 test, you must promptly initiate and complete corrective actions according to your OM&M plan, resume testing of that kiln stack following Method 22 of 40 CFR part 60, appendix A–7, on a daily basis, as described in paragraph (e)(1)(i) of this section, and maintain that schedule until one of the conditions in paragraph (e)(1)(iii)(A) or (B) of this section is met, at which time you may again decrease the frequency of Method 22 testing to a weekly basis.

(v) If greater than 10 percent opacity is observed during any test conducted using Method 9 of 40 CFR part 60, appendix A–4, you must report these deviations by following the requirements in § 63.8485.

(2) *Alternative to VE testing.* In lieu of meeting the requirements under paragraph (e)(1) of this section, you may conduct a PM test at least once every year following the initial performance test, according to the procedures of Method 5 of 40 CFR part 60, appendix A–3, and the provisions of § 63.8445(e) and (f)(1).

NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.8480 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(f)(4), and 63.9(b) through (e), (g)(1), and (h) that apply to you, by the dates specified.

(b) You must submit all of the notifications specified in Table 8 to this subpart that apply to you, by the dates specified.

(c) If you are required to conduct a performance test or other initial compliance demonstration as specified in Tables 4 and 5 to this subpart, your Notification of Compliance Status as specified in Table 8 to this subpart must include the information in paragraphs (c)(1) through (3) of this section.

(1) The requirements in § 63.9(h)(2)(i).

(2) The operating limit parameter values established for each affected source with supporting documentation and a description of the procedure used to establish the values.

(3) For each APCD that includes a fabric filter, if a bag leak detection system is used, analysis and supporting documentation demonstrating conformance with EPA guidance and specifications for bag leak detection systems in § 63.8450(e).

§ 63.8485 What reports must I submit and when?

(a) You must submit each report in Table 9 to this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report by the date in Table 9 to this subpart and as specified in paragraphs (b)(1) through (5) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.8395 and ending on either June 30 or December 31. The first reporting period must be at least 6 months, but less than 12 months. For example, if your compliance date is March 1, then the first semiannual reporting period would begin on March 1 and end on December 31.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31 for compliance periods ending on June 30 and December 31, respectively.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31 for compliance periods ending on June 30 and December 31, respectively.

(5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of the dates in paragraphs (b)(1) through (4) of this section.

(c) The compliance report must contain the information in paragraphs (c)(1) through (8) of this section.

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying that, based on information and belief formed after reasonable inquiry, the statements and information in the report are true, accurate, and complete.

(3) Date of report and beginning and ending dates of the reporting period.

(4) A description of control device maintenance performed while the control device was offline and the kiln controlled by the control device was operating, including the information specified in paragraphs (c)(4)(i) through (iii) of this section.

(i) The date and time when the control device was shut down and restarted.

(ii) Identification of the kiln that was operating and the number of hours that the kiln operated while the control device was offline.

(iii) A statement of whether or not the control device maintenance was included in your approved routine control device maintenance request developed as specified in §63.8420(d). If the control device maintenance was included in your approved routine control device maintenance request, then you must report the information in paragraphs (c)(4)(iii)(A) through (C) of this section.

(A) The total amount of time that the kiln controlled by the control device operated during the current semiannual compliance period and during the previous semiannual compliance period.

(B) The amount of time that each kiln controlled by the control device operated while the control device was offline for maintenance covered under the routine control device maintenance alternative standard during the current semiannual compliance period and during the previous semiannual compliance period.

(C) Based on the information recorded under paragraphs (c)(4)(iii)(A) and (B) of this section, compute the annual percent of kiln operating uptime during which the control device was offline for routine maintenance using Equation 7.

$$RM = \frac{DT_p + DT_c}{KU_p + KU_c}(100) \qquad \text{(Eq. 7)}$$

Where:

RM = Annual percentage of kiln uptime during which control device was offline for routine control device maintenance

DT_p = Control device downtime claimed under the routine control device maintenance alternative standard for the previous semiannual compliance period

DT_c = Control device downtime claimed under the routine control device maintenance alternative standard for the current semiannual compliance period

KU_p = Kiln uptime for the previous semiannual compliance period

KU_c = Kiln uptime for the current semiannual compliance period

(5) A report of the most recent burner tune-up conducted to comply with the dioxin/furan work practice standard in Table 3 to this subpart.

(6) If there are no deviations from any emission limitations (emission limits or operating limits) that apply to you, the compliance report must contain a statement that there were no deviations from the emission limitations during the reporting period.

(7) If there were no periods during which the CMS was out-of-control as specified in your OM&M plan, the compliance report must contain a statement that there were no periods during which the CMS was out-of-control during the reporting period.

(8) The first compliance report must contain the startup push rate for each kiln, the minimum APCD inlet temperature for each APCD, and the temperature profile for each kiln without an APCD.

(9) For each deviation that occurs at an affected source, report such events in the compliance report by including the information in paragraphs (c)(9)(i) through (iii) of this section.

(i) The date, time, and duration of the deviation.

(ii) A list of the affected sources or equipment for which the deviation occurred.

(iii) An estimate of the quantity of each regulated pollutant emitted over any emission limit, and a description of the method used to estimate the emissions.

(d) For each deviation from an emission limitation (emission limit or operating limit) occurring at an affected source where you are using a CMS to comply with the emission limitations in this subpart, you must include the information in paragraphs (c)(1) through (4) and (c)(9), and paragraphs (d)(1) through (11) of this section. This includes periods of startup, shutdown, and routine control device maintenance.

(1) The total operating time of each affected source during the reporting period.

(2) The date and time that each CMS was inoperative, except for zero (low-level) and high-level checks.

(3) The date, time, and duration that each CMS was out-of-control, including the pertinent information in your OM&M plan.

(4) Whether each deviation occurred during routine control device maintenance covered in your approved routine control device maintenance alternative standard or during another period, and the cause of each deviation (including unknown cause, if applicable).

(5) A description of any corrective action taken to return the affected unit to its normal or usual manner of operation.

(6) A breakdown of the total duration of the deviations during the reporting period into those that were due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes.

(7) A summary of the total duration of CMS downtime during the reporting period and the total duration of CMS downtime as a percent of the total source operating time during that reporting period.

(8) A brief description of the process units.

(9) A brief description of the CMS.

(10) The date of the latest CMS certification or audit.

(11) A description of any changes in CMS, processes, or control equipment since the last reporting period.

(e) If you have obtained a title V operating permit according to 40 CFR part 70 or 40 CFR part 71, you must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If you submit a compliance report according to Table 9 to this subpart along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all required information concerning deviations from any emission limitation (including any operating limit), then submitting the compliance report will satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submitting a compliance report will not otherwise affect any obligation you may have to report deviations from permit requirements to the permitting authority.

(f) Within 60 calendar days after the date of completing each performance test (as defined in § 63.2) required by this subpart, you must submit the results of the performance test following the procedure specified in either paragraph (f)(1) or (f)(2) of this section.

(1) For data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT Web site (*http://www.epa.gov/ttn/chief/ert/index.html*) at the time of the test, you must submit the results of the performance test to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI). (CEDRI can be accessed through the EPA's Central Data Exchange (CDX) (*http://cdx.epa.gov/*).) Performance test data must be submitted in a file format generated through the use of the EPA's ERT or an alternate electronic file format consistent with the extensible markup language (XML) schema listed on the EPA's ERT Web site. If you claim that some of the performance test information being submitted is confidential business information (CBI), you must submit a complete file generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT Web site, including information claimed to be CBI, on a compact disc, flash drive, or other commonly used electronic storage media to the EPA. The electronic media must be clearly marked as CBI and mailed to U.S. EPA/OAPQS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same ERT or alternate file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph.

(2) For data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT Web site at the time of the test, you

must submit the results of the performance test to the Administrator at the appropriate address listed in § 63.13.

§ 63.8490 What records must I keep?

(a) You must keep the records listed in paragraphs (a)(1) through (3) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) Records of performance tests as required in § 63.10(b)(2)(viii).

(3) Records relating to control device maintenance and documentation of your approved routine control device maintenance request, if you request to use the alternative standard under § 63.8420(d).

(b) You must keep the records required in Table 6 to this subpart to show continuous compliance with each emission limitation and work practice standard that applies to you.

(c) You must also maintain the records listed in paragraphs (c)(1) through (11) of this section.

(1) For each bag leak detection system, records of each alarm, the time of the alarm, the time corrective action was initiated and completed, and a brief description of the cause of the alarm and the corrective action taken.

(2) For each deviation, record the information in paragraphs (c)(2)(i) through (iv) of this section.

(i) The date, time, and duration of the deviation.

(ii) A list of the affected sources or equipment.

(iii) An estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(iv) Actions taken to minimize emissions in accordance with § 63.8420(b) and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(3) For each affected source, records of production rates on a fired-product basis.

(4) Records for any approved alternative monitoring or test procedures.

(5) Records of maintenance and inspections performed on the APCD.

(6) Current copies of your OM&M plan, including any revisions, with records documenting conformance.

(7) Logs of the information required in paragraphs (c)(7)(i) through (iii) of this section to document proper operation of your periodic kiln.

(i) Records of the firing time and temperature cycle for each product produced in each periodic kiln. If all periodic kilns use the same time and temperature cycles, one copy may be maintained for each kiln. Reference numbers must be assigned to use in log sheets.

(ii) For each periodic kiln, a log that details the type of product fired in each batch, the corresponding time and temperature protocol reference number, and an indication of whether the appropriate time and temperature cycle was fired.

(iii) For each periodic kiln, a log of the actual tonnage of product fired in the periodic kiln and an indication of whether the tonnage was below the maximum tonnage for that specific kiln.

(8) Logs of the maintenance procedures used to demonstrate compliance with the maintenance requirements of the periodic kiln work practice standards specified in Table 3 to this subpart.

(9) Records of burner tune-ups used to comply with the dioxin/furan work practice standard for tunnel kilns.

(10) For periods of startup and shutdown, records of the following information:

(i) The date, time, and duration of each startup and/or shutdown period, recording the periods when the affected source was subject to the standard applicable to startup and shutdown.

(ii) For periods of startup, the kiln push rate and kiln exhaust temperature prior to the time the kiln exhaust reaches the minimum APCD inlet temperature (for a kiln with an APCD) or the kiln temperature profile is attained (for a kiln with no APCD).

(iii) For periods of shutdown, the kiln push rate and kiln exhaust temperature after the time the kiln exhaust falls below the minimum APCD inlet temperature (for a kiln with an APCD)

or the kiln temperature profile is no longer maintained (for a kiln with no APCD).

(11) All site-specific parameters, temperature profiles, and procedures required to be established or developed according to the applicable work practice standards in Table 3 to this subpart.

§ 63.8495 In what form and for how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record onsite for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You may keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.8505 What parts of the General Provisions apply to me?

Table 10 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.16 apply to you.

§ 63.8510 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. EPA, or a delegated authority such as your state, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your state, local, or tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if implementation and enforcement of this subpart is delegated to your state, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a state, local, or tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the state, local, or tribal agency.

(c) The authorities that cannot be delegated to state, local, or tribal agencies are as specified in paragraphs (c)(1) through (6) of this section.

(1) Approval of alternatives to the applicability requirements in §§ 63.8385 and 63.8390, the compliance date requirements in § 63.8395, and the nonopacity emission limitations in § 63.8405.

(2) Approval of major changes to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major changes to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major changes to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(5) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

(6) Approval of a routine control device maintenance request under § 63.8420(d).

§ 63.8515 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in § 63.2, and in this section as follows:

Air pollution control device (APCD) means any equipment that reduces the quantity of a pollutant that is emitted to the air.

Bag leak detection system means an instrument that is capable of monitoring PM loadings in the exhaust of a fabric filter in order to detect bag failures. A bag leak detection system includes, but is not limited to, an instrument that operates on triboelectric, light-scattering, light-transmittance, or other effects to monitor relative PM loadings.

Brick and structural clay products (BSCP) manufacturing facility means a plant site that manufactures brick (including, but not limited to, face brick, structural brick, and brick pavers); clay pipe; roof tile; extruded floor and wall tile; and/or other extruded, dimensional clay products. Brick and structural clay products manufacturing facilities typically process raw clay and shale, form the processed materials into bricks or shapes, and dry and fire

the bricks or shapes. A plant site that manufactures refractory products, as defined in 40 CFR 63.9824, or clay ceramics, as defined in 40 CFR 63.8665, is not a BSCP manufacturing facility.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limitation (including any operating limit) or work practice standard; or

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart for any affected source required to obtain such a permit.

Dry lime injection fabric filter (DIFF) means an APCD that includes continuous injection of hydrated lime or other sorbent into a duct or reaction chamber followed by a fabric filter.

Dry lime scrubber/fabric filter (DLS/FF) means an APCD that includes continuous injection of humidified hydrated lime or other sorbent into a reaction chamber followed by a fabric filter. These systems typically include recirculation of some of the sorbent.

Dry limestone adsorber (DLA) means an APCD that includes a limestone storage bin, a reaction chamber that is essentially a packed tower filled with limestone, and may or may not include a peeling drum that mechanically scrapes reacted limestone to regenerate the stone for reuse.

Emission limitation means any emission limit or operating limit.

Fabric filter means an APCD used to capture PM by filtering a gas stream through filter media; also known as a baghouse.

Initial startup means:

(1) For a new or reconstructed tunnel kiln controlled with a DLA, the time at which the temperature in the kiln first reaches 260 °C (500 °F) and the kiln contains product; or

(2) for a new or reconstructed tunnel kiln controlled with a DIFF, DLS/FF, or wet scrubber (WS), the time at which the kiln first reaches a level of production that is equal to 75 percent of the kiln design capacity or 12 months after the affected source begins firing BSCP, whichever is earlier.

Fired product means brick or structural clay products that have gone through the firing process via kilns.

Kiln exhaust process stream means the portion of the exhaust from a tunnel kiln that exhausts directly to the atmosphere (or to an APCD), rather than to a sawdust dryer.

Large tunnel kiln means a tunnel kiln (existing, new, or reconstructed) with a design capacity equal to or greater than 9.07 Mg/hr (10 tph) of fired product.

Minimum APCD inlet temperature means the minimum temperature that kiln exhaust can be vented to the APCD that ensures the long-term integrity of the APCD.

Particulate matter (PM) means, for purposes of this subpart, emissions of PM that serve as a measure of total particulate emissions, as measured by Method 5 (40 CFR part 60, appendix A–3) or Method 29 (40 CFR part 60, appendix A–8), and as a surrogate for nonmercury metal HAP contained in the particulates including, but not limited to, antimony, arsenic, beryllium, cadmium, chromium, cobalt, lead, manganese, nickel, and selenium.

Periodic kiln means a batch firing kiln.

Plant site means all contiguous or adjoining property that is under common control, including properties that are separated only by a road or other public right-of-way. Common control includes properties that are owned, leased, or operated by the same entity, parent entity, subsidiary, or any combination thereof.

Responsible official means responsible official as defined in 40 CFR 70.2.

Small tunnel kiln means a tunnel kiln (existing, new, or reconstructed) with a design capacity less than 9.07 Mg/hr (10 tph) of fired product.

Startup means the setting in operation of an affected source and starting the production process.

Startup push rate means the kiln push rate required to bring the kiln to the proper operating temperature during startup.

Tunnel kiln means any continuous kiln that is used to fire BSCP. Some tunnel kilns have two process streams,

including a process stream that exhausts directly to the atmosphere or to an APCD, and a process stream in which the kiln exhaust is ducted to a sawdust dryer where it is used to dry sawdust before being emitted to the atmosphere.

Tunnel kiln design capacity means the maximum amount of brick, in Mg (tons), that a kiln is designed to produce in one year divided by the number of hours in a year (8,760 hours), taking into account the void space in the brick, the push rate for the kiln, and the stacking pattern, if applicable. If a kiln is modified to increase the capacity, the design capacity is considered to be the capacity following modifications.

Wet scrubber (WS) means an APCD that uses water, which may include caustic additives or other chemicals, as the sorbent. Wet scrubbers may use any of various design mechanisms to increase the contact between exhaust gases and the sorbent.

Work practice standard means any design, equipment, work practice, operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the Clean Air Act.

Tables to Subpart JJJJJ of Part 63

TABLE 1 TO SUBPART JJJJJ OF PART 63—EMISSION LIMITS

As stated in §63.8405, you must meet each emission limit in the following table that applies to you:

For each . . .	You must meet the following emission limits . . .	Or you must comply with the following . . .
1. Collection of all tunnel kilns at facility, including all process streams.	HF, HCl, and Cl_2 emissions must not exceed 26 kg/hr (57 lb/hr) HCl equivalent, under the health-based standard, as determined using Equations 2 and 3.	Not applicable.
2. Existing large tunnel kiln (design capacity ≥10 tons per hour (tph) of fired product), including all process streams.	a. PM emissions must not exceed 0.018 kg/Mg (0.036 lb/ton) of fired product.	i. PM emissions must not exceed 6.6 mg/dscm (0.0029 gr/dscf) at 17% O_2; or ii. Non-Hg HAP metals emissions must not exceed 0.0026 kg/hr (0.0057 lb/hr).
	b. Hg emissions must not exceed 2.1 E–05 kilogram per megagram (kg/Mg) (4.1 E–05 pound per ton (lb/ton)) of fired product.	i. Hg emissions must not exceed 7.7 micrograms per dry standard cubic meter (μg/dscm) at 17% O_2; or ii. Hg emissions must not exceed 2.5 E–04 kg/hr (5.5 E–04 lb/hr).
3. Existing small tunnel kiln (design capacity <10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product.	i. PM emissions must not exceed 4.8 mg/dscm (0.0021 gr/dscf) at 17% O_2; or ii. Non-Hg HAP metals emissions must not exceed 0.047 kg/hr (0.11 lb/hr).
	b. Hg emissions must not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product.	i. Hg emissions must not exceed 91 μg/dscm at 17% O_2; or ii. Hg emissions must not exceed 8.5 E–04 kg/hr (0.0019 lb/hr).
4. New or reconstructed large tunnel kiln (design capacity ≥10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.0089 kg/Mg (0.018 lb/ton) of fired product..	i. PM emissions must not exceed 3.2 mg/dscm (0.0014 gr/dscf) at 17% O_2; or ii. Non-Hg HAP metals emissions must not exceed 0.0026 kg/hr (0.0057 lb/hr) of fired product.
	b. Hg emissions must not exceed 1.4 E–05 kg/Mg (2.8 E–05 lb/ton) of fired product.	i. Hg emissions must not exceed 6.2 μg/dscm at 17% O_2. ii. Hg emissions must not exceed 1.6 E–04 kg/hr (3.4 E–04 lb/hr).
5. New or reconstructed small tunnel kiln (design capacity <10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.015 kg/Mg (0.030 lb/ton) of fired product.	i. PM emissions must not exceed 4.7 mg/dscm (0.0021 gr/dscf) at 17% O_2; or ii. Non-Hg HAP metals emissions must not exceed 0.047 kg/hr (0.11 lb/hr) of fired product.
	b. Hg emissions must not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product.	i. Hg emissions must not exceed 91 μg/dscm at 17% O_2. ii. Hg emissions must not exceed 8.5 E–04 kg/hr (0.0019 lb/hr).

TABLE 2 TO SUBPART JJJJJ OF PART 63—OPERATING LIMITS

As stated in §63.8405, you must meet each operating limit in the following table that applies to you:

For each . . .	You must . . .
1. Tunnel kiln equipped with a DLA	a. Maintain the average pressure drop across the DLA for each 3-hour block period at or above the average pressure drop established during the HF/HCl/Cl_2 performance test; or, if you are monitoring the bypass stack damper position, initiate corrective action within 1 hour after the bypass damper is opened allowing the kiln exhaust gas to bypass the DLA and complete corrective action in accordance with your OM&M plan; and b. Maintain an adequate amount of limestone in the limestone hopper, storage bin (located at the top of the DLA), and DLA at all times; maintain the limestone feeder setting (on a per ton of fired product basis) at or above the level established during the HF/HCl/Cl_2 performance test in which compliance was demonstrated; and c. Use the same grade of limestone from the same source as was used during the HF/HCl/Cl_2 performance test in which compliance was demonstrated; maintain records of the source and grade of limestone; and d. Maintain no VE from the DLA stack.
2. Tunnel kiln equipped with a DIFF or DLS/FF	a. If you use a bag leak detection system, initiate corrective action within 1 hour of a bag leak detection system alarm and complete corrective actions in accordance with your OM&M plan; operate and maintain the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period; or maintain no VE from the DIFF or DLS/FF stack; and b. Maintain free-flowing lime in the feed hopper or silo and to the APCD at all times for continuous injection systems; maintain the feeder setting (on a per ton of fired product basis) at or above the level established during the HF/HCl/Cl_2 performance test for continuous injection systems in which compliance was demonstrated.
3. Tunnel kiln equipped with a WS	a. Maintain the average scrubber liquid pH for each 3-hour block period at or above the average scrubber liquid pH established during the HF/HCl/Cl_2 performance test in which compliance was demonstrated; and b. Maintain the average scrubber liquid flow rate for each 3-hour block period at or above the highest average scrubber liquid flow rate established during the HF/HCl/Cl_2 and PM/non-Hg HAP metals performance tests in which compliance was demonstrated.
4. Tunnel kiln equipped with an ACI system	Maintain the average carbon flow rate for each 3-hour block period at or above the average carbon flow rate established during the Hg performance test in which compliance was demonstrated.
5. Tunnel kiln with no add-on control	a. Maintain no VE from the stack. b. Maintain the kiln process rate at or below the kiln process rate determined according to §63.8445(g)(1).

TABLE 3 TO SUBPART JJJJJ OF PART 63—WORK PRACTICE STANDARDS

As stated in §63.8405, you must meet each work practice standard in the following table that applies to you:

For each . . .	You must . . .	According to the following requirements . . .
1. Existing, new or reconstructed periodic kiln.	a. Minimize HAP emissions	i. Develop and use a designed firing time and temperature cycle for each periodic kiln. You must either program the time and temperature cycle into your kiln or track each step on a log sheet; and ii. Label each periodic kiln with the maximum load (in tons) of product that can be fired in the kiln during a single firing cycle; and

For each . . .	You must . . .	According to the following requirements . . .
		iii. For each firing load, document the total tonnage of product placed in the kiln to ensure that it is not greater than the maximum load identified in item 1b; and iv. Develop and follow maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices, controls that regulate air-to-fuel ratios, and controls that regulate firing cycles; and v. Develop and maintain records for each periodic kiln, as specified in §63.8490.
2. Existing, new or reconstructed tunnel kiln.	a. Minimize dioxin/furan emissions	i. Maintain and inspect the burners and associated combustion controls (as applicable); and ii. Tune the specific burner type to optimize combustion.
3. Existing, new or reconstructed tunnel kiln during periods of startup.	a. Minimize HAP emissions	i. Establish the startup push rate for each kiln, the minimum APCD inlet temperature for each APCD, and temperature profile for each kiln without an APCD and include them in your first compliance report, as specified in §63.8485(c)(8); and ii. After initial charging of the kiln with loaded kiln cars, remain at or below the startup push rate for the kiln until the kiln exhaust reaches the minimum APCD inlet temperature for a kiln with an APCD or until the kiln temperature profile is attained for a kiln with no APCD; and iii. If your kiln has an APCD, begin venting the exhaust from the kiln through the APCD by the time the kiln exhaust temperature reaches the minimum APCD inlet temperature.
4. Existing, new or reconstructed tunnel kiln during periods of shutdown.	a. Minimize HAP emissions	i. Do not push loaded kiln cars into the kiln once the kiln exhaust temperature falls below the minimum APCD inlet temperature if the kiln is controlled by an APCD or when the kiln temperature profile is no longer maintained for an uncontrolled kiln; and ii. If your kiln has an APCD, continue to vent the exhaust from the kiln through the APCD until the kiln exhaust temperature falls below the minimum inlet temperature for the APCD.
5. Existing, new or reconstructed tunnel kiln during periods of routine control device maintenance.	a. Minimize HAP emissions.	i. Develop and use a temperature profile for each kiln; and ii. Develop and follow maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices and controls that regulate air-to-fuel ratios; and iii. Develop and maintain records for each kiln, as specified in §63.8490(a)(3).

As stated in §63.8445, you must conduct each performance test in the following table that applies to you:

TABLE 4 TO SUBPART JJJJJ OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS

As stated in §63.8445, you must conduct each performance test in the following table that applies to you:

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
1. Tunnel kiln	a. Select locations of sampling ports and the number of traverse points.	Method 1 or 1A of 40 CFR part 60, appendix A–1.	Sampling sites must be located at the outlet of the APCD and prior to any releases to the atmosphere for all affected sources.
	b. Determine velocities and volumetric flow rate.	Method 2 of 40 CFR part 60, appendix A–1.	You may use Method 2A, 2C, 2D, or 2F of 40 CFR part 60, appendix A–1, or Method 2G of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 2 of 40 CFR part 60, appendix A–1.
	c. Conduct gas molecular weight analysis.	Method 3 of 40 CFR part 60, appendix A–2.	You may use Method 3A or 3B of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 3 of 40 CFR part 60, appendix A–2. ANSI/ASME PTC 19.10–1981 (incorporated by reference, see §63.14) may be used as an alternative to the manual procedures (but not the instrumental procedures) in Methods 3A and 3B.
	d. Measure moisture content of the stack gas.	Method 4 of 40 CFR part 60, appendix A–3.	
	e. Measure HF, HCl and Cl_2 emissions.	i. Method 26A of 40 CFR part 60, appendix A–8; or.	You may use Method 26 of 40 CFR part 60, appendix A–8, as an alternative to using Method 26A of 40 CFR part 60, appendix A–8, when no acid PM (*e.g.,* HF or HCl dissolved in water droplets emitted by sources controlled by a WS) is present. ASTM D6735–01 (Reapproved 2009) (incorporated by reference, see §63.14) may be used as an alternative to Methods 26 and 26A.
		ii. Method 320 of appendix A of this part.	When using Method 320 of appendix A of this part, you must follow the analyte spiking procedures of section 13 of Method 320 of appendix A of this part, unless you can demonstrate that the complete spiking procedure has been conducted at a similar source. ASTM D6348–03 (Reapproved 2010) (incorporated by reference, see §63.14) may be used as an alternative to Method 320 if the test plan preparation and implementation in Annexes A1–A8 are mandatory and the %R in Annex A5 is determined for each target analyte.
	f. Measure PM emissions or non-Hg HAP metals.	i. For PM only: Method 5 of 40 CFR part 60, appendix A–3; or.	
		ii. For PM or non-Hg HAP metals: Method 29 of 40 CFR part 60, appendix A–8.	
	g. Measure Hg emissions.	Method 29 of 40 CFR part 60, appendix A–8.	ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14) may be used as an alternative to Method 29 (portion for Hg only).
2. Tunnel kiln with no add-on control.	Establish the operating limit(s) for kiln process rate if the total facility maximum potential HCl-equivalent emissions are greater than the HCl-equivalent limit in Table 1 to this subpart.	HCl-equivalent limit in Table 1 to this subpart and emissions and production data from the HF/HCl/Cl_2 performance test.	Using the procedures in §63.8445(g)(1), you must determine the maximum process rate(s) for your kiln(s) that would ensure total facility maximum potential HCl-equivalent emissions remain at or below the HCl-equivalent limit in Table 1 to this subpart. The maximum process rate(s) would become your site-specific process rate operating limit(s).

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
3. Tunnel kiln that is complying with PM and/or Hg production-based emission limits.	Determine the production rate during each PM/Hg test run in order to determine compliance with PM and/or Hg production-based emission limits.	Production data collected during the PM/Hg performance tests (*e.g.,* no. of pushes per hour, no. of bricks per kiln car, weight of a typical fired brick).	You must measure and record the production rate, on a fired-product basis, of the affected source for each of the three test runs.
4. Tunnel kiln equipped with a DLA.	a. Establish the operating limit for the average pressure drop across the DLA.	Data from the pressure drop measurement device during the HF/HCl/Cl_2 performance test.	You must continuously measure the pressure drop across the DLA, determine and record the block average pressure drop values for the three test runs, and determine and record the 3-hour block average of the recorded pressure drop measurements for the three test runs. The average of the three test runs establishes your minimum site-specific pressure drop operating limit.
	b. Establish the operating limit for the limestone feeder setting.	Data from the limestone feeder during the HF/HCl/Cl_2 performance test.	You must ensure that you maintain an adequate amount of limestone in the limestone hopper, storage bin (located at the top of the DLA), and DLA at all times during the performance test. You must establish your limestone feeder setting, on a per ton of fired product basis, one week prior to the performance test and maintain the feeder setting for the one-week period that precedes the performance test and during the performance test.
	c. Document the source and grade of limestone used.	Records of limestone purchase.	
5. Tunnel kiln equipped with a DIFF or DLS/FF.	Establish the operating limit for the lime feeder setting.	Data from the lime feeder during the HF/HCl/Cl_2 performance test.	For continuous lime injection systems, you must ensure that lime in the feed hopper or silo and to the APCD is free-flowing at all times during the performance test and record the feeder setting, on a per ton of fired product basis, for the three test runs. If the feed rate setting varies during the three test runs, determine and record the average feed rate from the three test runs. The average of the three test runs establishes your minimum site-specific feed rate operating limit.
6. Tunnel kiln equipped with a WS.	a. Establish the operating limit for the average scrubber liquid pH.	Data from the pH measurement device during the performance HF/HCl/Cl_2 performance test.	You must continuously measure the scrubber liquid pH, determine and record the block average pH values for the three test runs, and determine and record the 3-hour block average of the recorded pH measurements for the three test runs. The average of the three test runs establishes your minimum site-specific liquid pH operating limit.
	b. Establish the operating limit for the average scrubber liquid flow rate.	Data from the flow rate measurement device during the HF/HCl/Cl_2 and PM/non-Hg HAP metals performance tests.	You must continuously measure the scrubber liquid flow rate, determine and record the block average flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded flow rate measurements for the three test runs. The average of the three test runs establishes your minimum site-specific liquid flow rate operating level. If different average wet scrubber liquid flow rate values are measured during the HF/HCl/Cl_2 and PM/non-Hg HAP metals tests, the highest of the average values become your site-specific operating limit.
7. Tunnel kiln equipped with an ACI system.	Establish the operating limit for the average carbon flow rate.	Data from the carbon flow rate measurement conducted during the Hg performance test.	You must measure the carbon flow rate during each test run, determine and record the block average carbon flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded carbon flow rate measurements for the three test runs. The average of the three test runs establishes your minimum site-specific activated carbon flow rate operating limit.

TABLE 5 TO SUBPART JJJJJ OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

As stated in §63.8455, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
1. Collection of all tunnel kilns at the facility, including all process streams.	a. HF, HCl, and Cl_2 emissions must not exceed 26 kg/hr (57 lb/hr) HCl equivalent.	i. You measure HF, HCl, and Cl_2 emissions for each kiln using Method 26 or 26A of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6735–01 (Reapproved 2009) (incorporated by reference, see §63.14); or Method 320 of appendix A of this part or its alternative, ASTM D6348–03 (Reapproved 2010) (incorporated by reference, see §63.14); and ii. You calculate the HCl-equivalent emissions for each kiln using Equation 2 to this subpart; and iii. You sum the HCl-equivalent values for all kilns at the facility using Equation 3 to this subpart; and iv. The facility total HCl-equivalent does not exceed 26 kg/hr (57 lb/hr).
2. Existing large tunnel kiln (design capacity ≥10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.018 kg/Mg (0.036 lb/ton) of fired product or 6.6 mg/dscm (0.0029 gr/dscf) at 17% O_2; or.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8445(f)(1), do not exceed 0.018 kg/Mg (0.036 lb/ton) of fired product or 6.6 mg/dscm (0.0029 gr/dscf) at 17% O_2; and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which PM emissions did not exceed 0.018 kg/Mg (0.036 lb/ton) of fired product or 6.6 mg/dscm (0.0029 gr/dscf) at 17% O_2.
	b. Non-Hg HAP metals emissions must not exceed 0.0026 kg/hr (0.0057 lb/hr).	i. The non-Hg HAP metals emissions measured using Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, do not exceed 0.0026 kg/hr (0.0057 lb/hr); and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which non-Hg HAP metals emissions did not exceed 0.0026 kg/hr (0.0057 lb/hr).
	c. Hg emissions must not exceed 2.1 E–05 kg/Mg (4.1 E–05 lb/ton) of fired product or 7.7 μg/dscm at 17% O_2 or 2.5 E–04 kg/hr (5.5 E–04 lb/hr).	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 2.1 E–05 kg/Mg (4.1 E–05 lb/ton) of fired product or 7.7 μg/dscm at 17% O_2 or 2.5 E–04 kg/hr (5.5 E–04 lb/hr); and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which Hg emissions did not exceed 2.1 E–05 kg/Mg (4.1 E–05 lb/ton) of fired product or 7.7 μg/dscm at 17% O_2 or 2.5 E–04 kg/hr (5.5 E–04 lb/hr).

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
3. Existing small tunnel kiln (design capacity <10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product or 4.8 mg/dscm (0.0021 gr/dscf) at 17% O_2; or.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8445(f)(1), do not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product or 4.8 mg/dscm (0.0021 gr/dscf) at 17% O_2; and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which PM emissions did not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product or 4.8 mg/dscm (0.0021 gr/dscf) at 17% O_2.
	b. Non-Hg HAP metals emissions must not exceed 0.047 kg/hr (0.11 lb/hr).	i. The non-Hg HAP metals emissions measured using Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, do not exceed 0.047 kg/hr (0.11 lb/hr); and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which non-Hg HAP metals emissions did not exceed 0.047 kg/hr (0.11 lb/hr).
	c. Hg emissions must not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product or 91 μg/dscm at 17% O_2 or 8.5 E–04 kg/hr (0.0019 lb/hr).	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product or 91 μg/dscm at 17% O_2 or 8.5 E–04 kg/hr (0.0019 lb/hr); and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which Hg emissions did not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product or 91 μg/dscm at 17% O_2 or 8.5 E–04 kg/hr (0.0019 lb/hr).
4. New or reconstructed large tunnel kiln (design capacity ≥10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.0089 kg/Mg (0.018 lb/ton) of fired product or 3.2 mg/dscm (0.0014 gr/dscf) at 17% O_2; or.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8445(f)(1), do not exceed 0.0089 kg/Mg (0.018 lb/ton) of fired product or 3.2 mg/dscm (0.0014 gr/dscf) at 17% O_2; and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which PM emissions did not exceed 0.0089 kg/Mg (0.018 lb/ton) of fired product or 3.2 mg/dscm (0.0014 gr/dscf) at 17% O_2.
	b. Non-Hg HAP metals emissions must not exceed 0.0026 kg/hr (0.0057 lb/hr).	i. The non-Hg HAP metals emissions measured using Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, do not exceed 0.0026 kg/hr (0.0057 lb/hr); and

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
		ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which non-Hg HAP metals emissions did not exceed 0.0026 kg/hr (0.0057 lb/hr).
	c. Hg emissions must not exceed 1.4 E–05 kg/Mg (2.8 E–05 lb/ton) of fired product or 6.2 μg/dscm at 17% O_2 or 1.6 E–04 kg/hr (3.4 E–04 lb/hr).	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 1.4 E–05 kg/Mg (2.8 E–05 lb/ton) of fired product or 6.2 μg/dscm at 17% O_2 or 1.6 E–04 kg/hr (3.4 E–04 lb/hr); and
		ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which Hg emissions did not exceed 1.4 E–05 kg/Mg (2.8 E–05 lb/ton) of fired product or 6.2 μg/dscm at 17% O_2 or 1.6 E–04 kg/hr (3.4 E–04 lb/hr).
5. New or reconstructed small tunnel kiln (design capacity <10 tph of fired product), including all process streams.	a. PM emissions must not exceed 0.015 kg/Mg (0.030 lb/ton) of fired product or 4.7 mg/dscm (0.0021 gr/dscf) at 17% O_2; or.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8445(f)(1), do not exceed 0.015 kg/Mg (0.030 lb/ton) of fired product or 4.7 mg/dscm (0.0021 gr/dscf) at 17% O_2; and
		ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which PM emissions did not exceed 0.015 kg/Mg (0.030 lb/ton) of fired product or 4.7 mg/dscm (0.0021 gr/dscf) at 17% O_2.
	b. Non-Hg HAP metals emissions must not exceed 0.047 kg/hr (0.11 lb/hr).	i. The non-Hg HAP metals emissions measured using Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, do not exceed 0.047 kg/hr (0.11 lb/hr); and
		ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which non-Hg HAP metals emissions did not exceed 0.047 kg/hr (0.11 lb/hr).
	c. Hg emissions must not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product or 91 μg/dscm at 17% O_2 or 8.5 E–04 kg/hr (0.0019 lb/hr).	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product or 91 μg/dscm at 17% O_2 or 8.5 E–04 kg/hr (0.0019 lb/hr); and
		ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the 3-hour performance test during which Hg emissions did not exceed 1.7 E–04 kg/Mg (3.3 E–04 lb/ton) of fired product or 91 μg/dscm at 17% O_2 or 8.5 E–04 kg/hr (0.0019 lb/hr).

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
6. Existing, new or reconstructed periodic kiln.	a. Minimize HAP emissions	i. Develop a designed firing time and temperature cycle for each periodic kiln. You must either program the time and temperature cycle into your kiln or track each step on a log sheet; and ii. Label each periodic kiln with the maximum load (in tons) of product that can be fired in the kiln during a single firing cycle; and iii. Develop maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices, controls that regulate air-to-fuel ratios, and controls that regulate firing cycles.
7. Existing, new or reconstructed tunnel kiln.	a. Minimize dioxin/furan emissions	i. Conduct initial inspection of the burners and associated combustion controls (as applicable); and ii. Tune the specific burner type to optimize combustion.

TABLE 6 TO SUBPART JJJJJ OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

As stated in §63.8470, you must demonstrate continuous compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .
1. Tunnel kiln equipped with a DLA.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 1 of Table 2 to this subpart for tunnel kilns equipped with a DLA.	i. Collecting the DLA pressure drop data according to §63.8450(a); reducing the DLA pressure drop data to 3-hour block averages according to §63.8450(a); maintaining the average pressure drop across the DLA for each 3-hour block period at or above the average pressure drop established during the HF/HCl/Cl_2 performance test in which compliance was demonstrated; or continuously monitoring the bypass stack damper position at least once every 15 minutes during normal kiln operation, and initiating corrective action within 1 hour after the bypass damper is opened allowing the kiln exhaust gas to bypass the DLA and completing corrective action in accordance with your OM&M plan; and ii. Verifying that the limestone hopper and storage bin (located at the top of the DLA) contain adequate limestone by performing a daily visual check, which could include one of the following: (1) Conducting a physical check of the hopper; (2) creating a visual access point, such as a window, on the side of the hopper; (3) installing a camera in the hopper that provides continuous feed to a video monitor in the control room; or (4) confirming that load level indicators in the hopper are not indicating the need for additional limestone; and iii. Recording the limestone feeder setting daily (on a per ton of fired product basis) to verify that the feeder setting is being maintained at or above the level established during the HF/HCl/Cl_2 performance test in which compliance was demonstrated; and iv. Using the same grade of limestone from the same source as was used during the HF/HCl/Cl_2 performance test; maintaining records of the source and type of limestone; and v. Performing VE observations of the DLA stack at the frequency specified in §63.8470(e) using Method 22 of 40 CFR part 60, appendix A–7; maintaining no VE from the DLA stack.

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .
2. Tunnel kiln equipped with a DIFF or DLS/FF.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 2 of Table 2 to this subpart for tunnel kilns equipped with DIFF or DLS/FF.	i. If you use a bag leak detection system, as prescribed in 63.8450(e), initiating corrective action within 1 hour of a bag leak detection system alarm and completing corrective actions in accordance with your OM&M plan; operating and maintaining the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period; in calculating this operating time fraction, if inspection of the fabric filter demonstrates that no corrective action is required, no alarm time is counted; if corrective action is required, each alarm is counted as a minimum of 1 hour; if you take longer than 1 hour to initiate corrective action, the alarm time is counted as the actual amount of time taken by you to initiate corrective action; or performing VE observations of the DIFF or DLS/FF stack at the frequency specified in §63.8470(e) using Method 22 of 40 CFR part 60, appendix A–7; and maintaining no VE from the DIFF or DLS/FF stack; and ii. Verifying that lime is free-flowing via a load cell, carrier gas/lime flow indicator, carrier gas pressure drop measurement system, or other system; recording all monitor or sensor output, and if lime is found not to be free flowing, promptly initiating and completing corrective actions in accordance with your OM&M plan; recording the feeder setting once during each shift of operation to verify that the feeder setting is being maintained at or above the level established during the HF/HCl/Cl_2 performance test in which compliance was demonstrated.
3. Tunnel kiln equipped with a WS.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 3 of Table 2 to this subpart for tunnel kilns equipped with WS.	i. Collecting the scrubber liquid pH data according to §63.8450(a); reducing the scrubber liquid pH data to 3-hour block averages according to §63.8450(a); maintaining the average scrubber liquid pH for each 3-hour block period at or above the average scrubber liquid pH established during the HF/HCl/Cl_2 performance test in which compliance was demonstrated; and ii. Collecting the scrubber liquid flow rate data according to §63.8450(a); reducing the scrubber liquid flow rate data to 3-hour block averages according to §63.8450(a); maintaining the average scrubber liquid flow rate for each 3-hour block period at or above the highest average scrubber liquid flow rate established during the HF/HCl/Cl_2 and PM/non-Hg HAP metals performance tests in which compliance was demonstrated.
4. Tunnel kiln equipped with an ACI system.	Each emission limit in Table 1 to this subpart and each operating limit in Item 4 of Table 2 to this subpart for tunnel kilns equipped with ACI system.	Collecting the carbon flow rate data according to §63.8450(a); reducing the carbon flow rate data to 3-hour block averages according to §63.8450(a); maintaining the average carbon flow rate for each 3-hour block period at or above the average carbon flow rate established during the Hg performance test in which compliance was demonstrated.
5. Tunnel kiln with no add-on control.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 5 of Table 2 to this subpart for tunnel kilns with no add-on control.	i. Performing VE observations of the stack at the frequency specified in §63.8470(e) using Method 22 of 40 CFR part 60, appendix A–7; and maintaining no VE from the stack. ii. If your last calculated total facility maximum potential HCl-equivalent was not at or below the health-based standard in Table 1 to this subpart, collecting the kiln process rate data according to §63.8450(a); reducing the kiln process rate data to 3-hour block averages according to §63.8450(a); maintaining the average kiln process rate for each 3-hour block period at or below the kiln process rate determined according to §63.8445(g)(1).
6. Periodic kiln	a. Minimize HAP emissions	i. Using a designed firing time and temperature cycle for each periodic kiln; and ii. For each firing load, documenting the total tonnage of product placed in the kiln to ensure that it is not greater than the maximum load identified in Item 1.a.ii of Table 3 to this subpart; and

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .
7. Tunnel kiln	a. Minimize dioxin/furan emissions.	iii. Following maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices, controls that regulate air-to-fuel ratios, and controls that regulate firing cycles; and iv. Developing and maintaining records for each periodic kiln, as specified in § 63.8490. i. Maintaining and inspecting the burners and associated combustion controls (as applicable) and tuning the specific burner type to optimize combustion no later than 36 calendar months after the previous tune-up; and ii. Maintaining records of burner tune-ups used to demonstrate compliance with the dioxin/furan work practice standard; and iii. Submitting a report of most recent tune-up conducted with compliance report.

TABLE 7 TO SUBPART JJJJJ OF PART 63—COMPLIANCE DATES

As stated in § 63.8395, you must meet each compliance date in the following table that applies to you:

If you have a(n) . . .	Then you must . . .	No later than . . .
1. New or reconstructed affected source and the initial startup of your affected source is after December 18, 2014, but before December 28, 2015.	Comply with the applicable emission limitations and work practice standards in Tables 1, 2, and 3 to this subpart.	December 28, 2015.
2. New or reconstructed affected source and the initial startup of your affected source is after December 28, 2015.	Comply with the applicable emission limitations and work practice standards in Tables 1, 2, and 3 to this subpart.	Initial startup of your affected source.
3. Existing affected source	Comply with the applicable emission limitations and work practice standards in Tables 1, 2, and 3 to this subpart.	December 26, 2018.
4. Existing area source that increases its emissions or its potential to emit such that it becomes a major source of HAP by adding a new affected source or by reconstructing.	Be in compliance with this subpart	Initial startup of your affected source as a major source.
5. New area source (*i.e.,* an area source for which construction or reconstruction commenced after December 18, 2014) that increases its emissions or its potential to emit such that it becomes a major source of HAP.	Be in compliance with this subpart	Initial startup of your affected source as a major source.

TABLE 8 TO SUBPART JJJJJ OF PART 63—DEADLINES FOR SUBMITTING NOTIFICATIONS

As stated in § 63.8480, you must submit each notification that applies to you according to the following table:

If you . . .	You must . . .	No later than . . .	As specified in . . .
1. Start up your affected source before December 28, 2015.	Submit an Initial Notification.	June 22, 2016, or no later than 120 days after the source becomes subject to this subpart, whichever is later.	§ 63.9(b)(2).
2. Start up your new or reconstructed affected source on or after December 28, 2015.	Submit an Initial Notification.	120 calendar days after you become subject to this subpart.	§ 63.9(b)(2).
3. Are required to conduct a performance test.	Submit a notification of intent to conduct a performance test.	60 calendar days before the performance test is scheduled to begin.	§ 63.7(b)(1).

If you . . .	You must . . .	No later than . . .	As specified in . . .
4. Are required to conduct a compliance demonstration that includes a performance test according to the requirements in Table 4 to this subpart.	Submit a Notification of Compliance Status, including the performance test results.	60 calendar days following the completion of the performance test, by the close of business.	§ 63.9(h) and § 63.10(d)(2).
5. Are required to conduct a compliance demonstration required in Table 5 to this subpart that does not include a performance test (*i.e.,* compliance demonstrations for the work practice standards).	Submit a Notification of Compliance Status.	30 calendar days following the completion of the compliance demonstrations, by the close of business.	§ 63.9(h).
6. Request to use the routine control device maintenance alternative standard according to § 63.8420(d).	Submit your request	120 calendar days before the compliance date specified in § 63.8395.	

[80 FR 65520, Oct. 26, 2015, as amended at 85 FR 73914, Nov. 19, 2020]

Table 9 to Subpart JJJJJ of Part 63—Requirements for Reports

As stated in § 63.8485, you must submit each report that applies to you according to the following table:

You must submit . . .	The report must contain . . .	You must submit the report . . .
1. A compliance report.	a. If there are no deviations from any emission limitations (emission limits, operating limits) that apply to you, a statement that there were no deviations from the emission limitations during the reporting period. If there were no periods during which the CMS was out-of-control as specified in your OM&M plan, a statement that there were no periods during which the CMS was out-of-control during the reporting period.	Semiannually according to the requirements in § 63.8485(b).
	b. If you have a deviation from any emission limitation (emission limit, operating limit) during the reporting period, the report must contain the information in § 63.8485(c)(9). If there were periods during which the CMS was out-of-control, as specified in your OM&M plan, the report must contain the information in § 63.8485(d).	Semiannually according to the requirements in § 63.8485(b).

Table 10 to Subpart JJJJJ of Part 63—Applicability of General Provisions to Subpart JJJJJ

As stated in § 63.8505, you must comply with the General Provisions in §§ 63.1 through 63.16 that apply to you according to the following table:

Citation	Subject	Brief description	Applies to subpart JJJJJ?
§ 63.1	Applicability	Initial applicability determination; applicability after standard established; permit requirements; extensions, notifications.	Yes.
§ 63.2	Definitions	Definitions for part 63 standards	Yes.
§ 63.3	Units and Abbreviations.	Units and abbreviations for part 63 standards.	Yes.
§ 63.4	Prohibited Activities	Compliance date; circumvention; severability.	Yes.
§ 63.5	Construction/Reconstruction.	Applicability; applications; approvals	Yes.
§ 63.6(a)	Applicability	General Provisions (GP) apply unless compliance extension; GP apply to area sources that become major.	Yes.

Citation	Subject	Brief description	Applies to subpart JJJJJ?
§63.6(b)(1)–(4)	Compliance Dates for New and Reconstructed sources.	Standards apply at effective date; 3 years after effective date; upon startup; 10 years after construction or reconstruction commences for section 112(f).	Yes.
§63.6(b)(5)	Notification	Must notify if commenced construction or reconstruction after proposal.	Yes.
§63.6(b)(6)	[Reserved]		No.
§63.6(b)(7)	Compliance Dates for New and Reconstructed Area Sources That Become Major.	Area sources that become major must comply with major source standards immediately upon becoming major, regardless of whether required to comply when they were area sources.	Yes.
§63.6(c)(1)–(2)	Compliance Dates for Existing Sources.	Comply according to date in subpart, which must be no later than 3 years after effective date; for section 112(f) standards, comply within 90 calendar days of effective date unless compliance extension.	Yes.
§63.6(c)(3)–(4)	[Reserved]		No.
§63.6(c)(5)	Compliance Dates for Existing Area Sources That Become Major.	Area sources that become major must comply with major source standards by date indicated in subpart or by equivalent time period (for example, 3 years).	Yes.
§63.6(d)	[Reserved]		No.
§63.6(e)(1)(i)	Operation & Maintenance.	General Duty to minimize emissions	No. See §63.8420(b) for general duty requirement.
§63.6(e)(1)(ii)	Operation & Maintenance.	Requirement to correct malfunctions ASAP.	No.
§63.6(e)(1)(iii)	Operation & Maintenance.	Operation and maintenance requirements enforceable independent of emissions limitations.	Yes.
§63.6(e)(2)	[Reserved]		No.
§63.6(e)(3)	Startup, Shutdown, and Malfunction Plan (SSMP).	Requirement for startup, shutdown, and malfunction (SSM) and SSMP; content of SSMP.	No.
§63.6(f)(1)	Compliance Except During SSM.	You must comply with emission standards at all times except during SSM.	No.
§63.6(f)(2)–(3)	Methods for Determining Compliance.	Compliance based on performance test, operation and maintenance plans, records, inspection.	Yes.
§63.6(g)	Alternative Standard	Procedures for getting an alternative standard.	Yes.
§63.6(h)	Opacity/VE Standards.	Requirements for opacity and VE standards.	No, not applicable.
§63.6(i)	Compliance Extension.	Procedures and criteria for Administrator to grant compliance extension.	Yes.
§63.6(j)	Presidential Compliance Exemption.	President may exempt source category	Yes.
§63.7(a)(1)–(2)	Performance Test Dates.	Dates for conducting initial performance testing and other compliance demonstrations for emission limits and work practice standards; must conduct 180 calendar days after first subject to rule.	Yes.
§63.7(a)(3)	Section 114 Authority.	Administrator may require a performance test under CAA section 114 at any time.	Yes.
§63.7(a)(4)	Notification of Delay in Performance Testing Due To Force Majeure.	Must notify Administrator of delay in performance testing due to force majeure.	Yes.
§63.7(b)(1)	Notification of Performance Test.	Must notify Administrator 60 calendar days before the test.	Yes.
§63.7(b)(2)	Notification of Rescheduling.	Must notify Administrator 5 calendar days before scheduled date of rescheduled date.	Yes.
§63.7(c)	Quality Assurance(QA)/Test Plan.	Requirements; test plan approval procedures; performance audit requirements; internal and external QA procedures for testing.	Yes.
§63.7(d)	Testing Facilities	Requirements for testing facilities	Yes.
§63.7(e)(1)	Conditions for Conducting Performance Tests.	Cannot conduct performance tests during SSM; not a violation to exceed standard during SSM.	No, §63.8445 specifies requirements.

Citation	Subject	Brief description	Applies to subpart JJJJJ?
§63.7(e)(2)–(3)	Conditions for Conducting Performance Tests.	Must conduct according to subpart and EPA test methods unless Administrator approves alternative; must have at least three test runs of at least 1 hour each; compliance is based on arithmetic mean of three runs; conditions when data from an additional test run can be used.	Yes.
§63.7(e)(4)	Testing under Section 114.	Administrator's authority to require testing under section 114 of the Act.	Yes.
§63.7(f)	Alternative Test Method.	Procedures by which Administrator can grant approval to use an alternative test method.	Yes.
§63.7(g)	Performance Test Data Analysis.	Must include raw data in performance test report; must submit performance test data 60 calendar days after end of test with the notification of compliance status.	Yes.
§63.7(h)	Waiver of Tests	Procedures for Administrator to waive performance test.	Yes.
§63.8(a)(1)	Applicability of Monitoring Requirements.	Subject to all monitoring requirements in subpart.	Yes.
§63.8(a)(2)	Performance Specifications.	Performance Specifications in appendix B of 40 CFR part 60 apply.	Yes.
§63.8(a)(3)	[Reserved]		No.
§63.8(a)(4)	Monitoring with Flares.	Requirements for flares in §63.11 apply	No, not applicable.
§63.8(b)(1)	Monitoring	Must conduct monitoring according to standard unless Administrator approves alternative.	Yes.
§63.8(b)(2)–(3)	Multiple Effluents and Multiple Monitoring Systems.	Specific requirements for installing and reporting on monitoring systems.	Yes.
§63.8(c)(1)	Monitoring System Operation and Maintenance.	Maintenance consistent with good air pollution control practices.	Yes.
§63.8(c)(1)(i)	Routine and Predictable SSM.	Reporting requirements for SSM when action is described in SSMP.	No.
§63.8(c)(1)(ii)	SSM not in SSMP	Reporting requirements for SSM when action is not described in SSMP.	Yes.
§63.8(c)(1)(iii)	Compliance with Operation and Maintenance Requirements.	How Administrator determines if source complying with operation and maintenance requirements.	No.
§63.8(c)(2)–(3)	Monitoring System Installation.	Must install to get representative emission and parameter measurements.	Yes.
§63.8(c)(4)	CMS Requirements	Requirements for CMS	No, §63.8450 specifies requirements.
§63.8(c)(5)	Continuous Opacity Monitoring System (COMS) Minimum Procedures.	COMS minimum procedures	No, not applicable.
§63.8(c)(6)	CMS Requirements	Zero and high level calibration check requirements.	Yes.
§63.8(c)(7)–(8)	CMS Requirements	Out-of-control periods	Yes.
§63.8(d)(1) and (2)	CMS Quality Control	Requirements for CMS quality control	Yes.
§63.8(d)(3)	CMS Quality Control	Written procedures for CMS	No, §63.8425(b)(9) specifies requirements
§63.8(e)	CMS Performance Evaluation.	Requirements for CMS performance evaluation.	Yes.
§63.8(f)(1)–(5)	Alternative Monitoring Method.	Procedures for Administrator to approve alternative monitoring.	Yes.
§63.8(f)(6)	Alternative to Relative Accuracy Test.	Procedures for Administrator to approve alternative relative accuracy test for continuous emissions monitoring systems (CEMS).	No, not applicable.
§63.8(g)	Data Reduction	COMS and CEMS data reduction requirements.	No, not applicable.
§63.9(a)	Notification Requirements.	Applicability; State delegation	Yes.
§63.9(b)	Initial Notifications	Requirements for initial notifications.	
§63.9(c)	Request for Compliance Extension.	Can request if cannot comply by date or if installed BACT/LAER.	Yes.

Citation	Subject	Brief description	Applies to subpart JJJJJ?
§63.9(d)	Notification of Special Compliance Requirements for New Source.	For sources that commence construction between proposal and promulgation and want to comply 3 years after effective date.	Yes.
§63.9(e)	Notification of Performance Test.	Notify Administrator 60 calendar days prior.	Yes.
§63.9(f)	Notification of VE/Opacity Test.	Notify Administrator 30 calendar days prior.	No, not applicable.
§63.9(g)(1)	Additional Notifications When Using CMS.	Notification of performance evaluation	Yes.
§63.9(g)(2)–(3)	Additional Notifications When Using CMS.	Notification of COMS data use; notification that relative accuracy alternative criterion were exceeded.	No, not applicable.
§63.9(h)	Notification of Compliance Status.	Contents; submittal requirements	Yes.
§63.9(i)	Adjustment of Submittal Deadlines.	Procedures for Administrator to approve change in when notifications must be submitted.	Yes.
§63.9(j)	Change in Previous Information.	Must submit within 15 calendar days after the change.	Yes.
§63.9(k)	Electronic reporting procedures.	Electronic reporting procedures for notifications per §63.9(j).	Yes.
§63.10(a)	Recordkeeping/Reporting.	Applicability; general information	Yes.
§63.10(b)(1)	General Recordkeeping Requirements.	General requirements	Yes.
§63.10(b)(2)(i)	Records Related to SSM.	Recordkeeping of occurrence and duration of startups and shutdowns.	No.
§63.10(b)(2)(ii)	Records Related to SSM.	Recordkeeping of failures to meet a standard.	No. See §63.8490(c)(2) for recordkeeping of (1) date, time and duration; (2) listing of affected source or equipment, and an estimate of the volume of each regulated pollutant emitted over the standard; and (3) actions to minimize emissions and correct the failure.
§63.10(b)(2)(iii)	Records Related to SSM.	Maintenance records.	
§63.10(b)(2)(iv)–(v)	Records Related to SSM.	Actions taken to minimize emissions during SSM.	No.
§63.10(b)(2)(vi)–(xii) and (xiv).	CMS Records	Records when CMS is malfunctioning, inoperative or out-of-control.	Yes.
§63.10(b)(2)(xiii)	Records	Records when using alternative to relative accuracy test.	
§63.10(b)(3)	Records	Applicability Determinations	Yes.
§63.10(c)(1)–(15)	Records	Additional records for CMS	No, §§63.8425 and 63.8490 specify requirements
§63.10(d)(1) and (2)	General Reporting Requirements.	Requirements for reporting; performance test results reporting.	Yes.
§63.10(d)(3)	Reporting Opacity or VE Observations.	Requirements for reporting opacity and VE.	No, not applicable.
§63.10(d)(4)	Progress Reports	Must submit progress reports on schedule if under compliance extension.	Yes.
§63.10(d)(5)	SSM Reports	Contents and submission.	No. See §63.8485(c)(9) for malfunction reporting requirements.
§63.10(e)(1)–(3)	Additional CMS Reports.	Requirements for CMS reporting	No, §§63.8425 and 63.8485 specify requirements.
§63.10(e)(4)	Reporting COMS data.	Requirements for reporting COMS data with performance test data.	No, not applicable.
§63.10(f)	Waiver for Recordkeeping/Reporting.	Procedures for Administrator to waive	Yes.
§63.11	Flares	Requirement for flares	No, not applicable.
§63.12	Delegation	State authority to enforce standards.	
§63.13	Addresses	Addresses for reports, notifications, requests.	Yes.
§63.14	Incorporation by Reference.	Materials incorporated by reference	Yes.
§63.15	Availability of Information.	Information availability; confidential information.	Yes.
§63.16	Performance Track Provisions.	Requirements for Performance Track member facilities.	Yes.

[80 FR 65520, Oct. 26, 2015, as amended at 85 FR 73915, Nov. 19, 2020]

Subpart KKKKK—National Emission Standards for Hazardous Air Pollutants for Clay Ceramics Manufacturing

SOURCE: 80 FR 65543, Oct. 26, 2015, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.8530 What is the purpose of this subpart?

This subpart establishes national emission limitations and work practice standards for hazardous air pollutants (HAP) emitted from clay ceramics manufacturing facilities. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations and work practice standards.

§ 63.8535 Am I subject to this subpart?

You are subject to this subpart if you own or operate a clay ceramics manufacturing facility that is, is located at, or is part of a major source of HAP emissions according to the criteria in paragraphs (a) and (b) of this section.

(a) A clay ceramics manufacturing facility is a plant site that manufactures pressed floor tile, pressed wall tile, other pressed tile, or sanitaryware (*e.g.,* sinks and toilets). Clay ceramics manufacturing facilities typically process clay, shale, and various additives; form the processed materials into tile or sanitaryware shapes; and dry and fire the ceramic products. Glazes are applied to many tile and sanitaryware products. A plant site that manufactures refractory products, as defined in § 63.9824, or brick and structural clay products (BSCP), as defined in § 63.8515, is not a clay ceramics manufacturing facility.

(b) A major source of HAP emissions is any stationary source or group of stationary sources within a contiguous area under common control that emits or has the potential to emit any single HAP at a rate of 9.07 megagrams (10 tons) or more per year or any combination of HAP at a rate of 22.68 megagrams (25 tons) or more per year.

§ 63.8540 What parts of my plant does this subpart cover?

(a) This subpart applies to each existing, new, or reconstructed affected source at a clay ceramics manufacturing facility.

(b) Each existing, new, or reconstructed ceramic tile roller kiln, sanitaryware tunnel kiln, sanitaryware shuttle kiln, ceramic tile glaze line using glaze spraying, sanitaryware glaze spray booth, ceramic tile spray dryer, and floor tile press dryer is an affected source.

(c) Process units not subject to the requirements of this subpart are listed in paragraphs (c)(1) through (9) of this section.

(1) Tunnel, roller or shuttle kilns that are used exclusively for refiring.

(2) Tunnel, roller or shuttle kilns that are used exclusively for setting glazes on previously fired products.

(3) Glaze spray operations that are used exclusively with those kilns listed in paragraphs (c)(1) and (2) of this section.

(4) Process units listed in paragraphs (c)(1) through (3) of this section that are permitted to, but do not, process first-fire ware, until such time as they begin to process first-fire ware.

(5) Glaze spray operations that on average use wet glazes containing less than 0.1 (weight) percent metal HAP (dry weight basis) per spray booth over an entire calendar year.

(6) Raw material processing and handling.

(7) Wall tile press dryers.

(8) Sanitaryware ware dryers.

(9) Sources covered by subparts JJJJJ and SSSSS of this part.

(d) A source is a new affected source if construction of the affected source began after December 18, 2014, and you met the applicability criteria at the time you began construction.

(e) An affected source is reconstructed if you meet the criteria as defined in § 63.2.

(f) An affected source is existing if it is not new or reconstructed.

§ 63.8545 When do I have to comply with this subpart?

(a) You must comply with this subpart no later than the compliance dates in Table 8 to this subpart.

(b) You must meet the notification requirements in § 63.8630 according to the schedule in § 63.8630 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

§ 63.8555 What emission limitations and work practice standards must I meet?

(a) You must meet each emission limit in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit in Table 2 to this subpart that applies to you.

(c) You must meet each work practice standard in Table 3 to this subpart that applies to you.

§ 63.8560 What are my options for meeting the emission limitations and work practice standards?

(a) To meet the emission limitations in Tables 1 and 2 to this subpart, you must use one or more of the options listed in paragraphs (a)(1) and (2) of this section.

(1) *Emissions control system.* Use an emissions capture and collection system and an air pollution control device (APCD) and demonstrate that the resulting emissions meet the emission limits in Table 1 to this subpart, and that the capture and collection system and APCD meet the applicable operating limits in Table 2 to this subpart.

(2) *Process changes.* Use low-HAP raw materials or implement manufacturing process changes and demonstrate that the resulting emissions or emissions reductions meet the emission limits in Table 1 to this subpart.

(b) To meet the work practice standards for affected sanitaryware shuttle kilns, you must comply with the requirements listed in Table 3 to this subpart.

(c) To meet the work practice standards for affected sources during periods of startup and shutdown, you must comply with the requirements listed in Table 3 to this subpart.

GENERAL COMPLIANCE REQUIREMENTS

§ 63.8570 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods that you are approved for and in compliance with the alternative standard for routine control device maintenance as specified in paragraph (d) of this section, and except during periods of start-up and shutdown, at which time you must comply with the applicable work practice standard specified in Table 3 to this subpart.

(b) At all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source. During the period between the compliance date specified for your affected source in § 63.8545 and the date upon which continuous monitoring systems (CMS) (*e.g.*, continuous parameter monitoring systems) have been installed and verified and any applicable operating limits have been set, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.

(c) For each affected source that is subject to the emission limits specified in Table 1 to this subpart, you must prepare and implement a written operation, maintenance, and monitoring (OM&M) plan according to the requirements in § 63.8575.

(d) If you own or operate an affected source that is subject to the emission

limits specified in Table 1 to this subpart and must perform routine maintenance on the control device for that affected source, you may bypass the source control device and continue operating the affected source subject to the alternative standard established in this paragraph upon approval by the Administrator and provided you satisfy the conditions listed in paragraphs (d)(1) through (5) of this section.

(1) You must request to use the routine control device maintenance alternative standard from the Administrator no later than 120 calendar days before the compliance date specified in § 63.8545. Your request must justify the need for the routine maintenance on the control device and the time required to accomplish the maintenance activities, describe the maintenance activities and the frequency of the maintenance activities, explain why the maintenance cannot be accomplished during source shutdowns, provide information stating whether the continued operation of the affected source will result in fewer emissions than shutting the source down while the maintenance is performed, describe how you plan to comply with paragraph (b) of this section during the maintenance, and provide any other documentation required by the Administrator.

(2) The routine control device maintenance must not exceed 4 percent of the annual operating uptime for each affected source.

(3) The request for the routine control device maintenance alternative standard, if approved by the Administrator, must be incorporated by reference in and attached to the affected source's title V permit.

(4) You must minimize HAP emissions during the period when the affected source is operating and the control device is offline by complying with the applicable standard in Table 3 to this subpart.

(5) You must minimize the time period during which the affected source is operating and the control device is offline.

(e) If you own or operate an affected kiln that is subject to the work practice standard specified in Table 3 to this subpart, you must be in compliance with that work practice standard at all times, except during periods of natural gas curtailment or other periods when natural gas is not available.

(f) You must be in compliance with the provisions of subpart A of this part, except as noted in Table 9 to this subpart.

§ 63.8575 What do I need to know about operation, maintenance, and monitoring plans?

(a) For each affected source that is subject to the emission limits specified in Table 1 to this subpart, you must prepare, implement, and revise as necessary an OM&M plan that includes the information in paragraph (b) of this section. Your OM&M plan must be available for inspection by the delegated authority upon request.

(b) Your OM&M plan must include, as a minimum, the information in paragraphs (b)(1) through (13) of this section.

(1) Each process and APCD to be monitored, the type of monitoring device that will be used, and the operating parameters that will be monitored.

(2) A monitoring schedule that specifies the frequency that the parameter values will be determined and recorded.

(3) The limits for each parameter that represent continuous compliance with the emission limitations in § 63.8555. The limits must be based on values of the monitored parameters recorded during performance tests.

(4) Procedures for the proper operation and routine and long-term maintenance of each APCD, including a maintenance and inspection schedule that is consistent with the manufacturer's recommendations.

(5) Procedures for installing the CMS sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last APCD).

(6) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system.

(7) Continuous monitoring system performance evaluation procedures and acceptance criteria (*e.g.*, calibrations).

(8) Procedures for the proper operation and maintenance of monitoring equipment consistent with the requirements in §§ 63.8600 and 63.8(c)(1), (3), (7), and (8).

(9) Continuous monitoring system data quality assurance procedures consistent with the requirements in § 63.8(d)(1) and (2). The owner or operator shall keep these written procedures on record for the life of the affected source or until the affected source is no longer subject to the provisions of this part, to be made available for inspection, upon request, by the Administrator. If the performance evaluation plan in § 63.8(d)(2) is revised, the owner or operator shall keep previous (*i.e.*, superseded) versions of the performance evaluation plan on record to be made available for inspection, upon request, by the Administrator, for a period of 5 years after each revision to the plan. The program of corrective action should be included in the plan required under § 63.8(d)(2).

(10) Continuous monitoring system recordkeeping and reporting procedures consistent with the requirements in §§ 63.8635 and 63.8640.

(11) Procedures for responding to operating parameter deviations, including the procedures in paragraphs (b)(11)(i) through (iii) of this section.

(i) Procedures for determining the cause of the operating parameter deviation.

(ii) Actions necessary for correcting the deviation and returning the operating parameters to the allowable limits.

(iii) Procedures for recording the times that the deviation began and ended, and corrective actions were initiated and completed.

(12) Procedures for keeping records to document compliance.

(13) If you operate an affected source and you plan to take the source control device out of service for routine maintenance, as specified in § 63.8570(d), the procedures specified in paragraphs (b)(13)(i) and (ii) of this section.

(i) Procedures for minimizing HAP emissions from the affected source during periods of routine maintenance of the source control device when the affected source is operating and the control device is offline.

(ii) Procedures for minimizing the duration of any period of routine maintenance on the source control device when the affected source is operating and the control device is offline.

(c) Changes to the operating limits in your OM&M plan require a new performance test. If you are revising an operating limit parameter value, you must meet the requirements in paragraphs (c)(1) and (2) of this section.

(1) Submit a notification of performance test to the Administrator as specified in § 63.7(b).

(2) After completing the performance test to demonstrate that compliance with the emission limits can be achieved at the revised operating limit parameter value, you must submit the performance test results and the revised operating limits as part of the Notification of Compliance Status required under § 63.9(h).

(d) If you are revising the inspection and maintenance procedures in your OM&M plan, you do not need to conduct a new performance test.

Testing and Initial Compliance Requirements

§ 63.8585 By what date must I conduct performance tests?

For each affected source that is subject to the emission limits specified in Table 1 to this subpart, you must conduct performance tests within 180 calendar days after the compliance date that is specified for your source in § 63.8545 and according to the provisions in § 63.7(a)(2).

§ 63.8590 When must I conduct subsequent performance tests?

(a) For each affected source that is subject to the emission limits specified in Table 1 to this subpart, you must conduct a performance test before renewing your 40 CFR part 70 operating permit or at least every 5 years following the initial performance test.

(b) You must conduct a performance test when you want to change the parameter value for any operating limit specified in your OM&M plan.

§ 63.8595 How do I conduct performance tests and establish operating limits?

(a) You must conduct each performance test in Table 4 to this subpart that applies to you.

(b) Before conducting the performance test, you must install and calibrate all monitoring equipment.

(c) Each performance test must be conducted according to the requirements in § 63.7 and under the specific conditions in Table 4 to this subpart. Stacks to be tested at sanitaryware manufacturing facilities shall be limited to products of combustion (POC) stacks and not include cooling stacks.

(d) Performance tests shall be conducted under such conditions as the Administrator specifies to you based on representative performance of the affected source for the period being tested. Representative conditions exclude periods of startup and shutdown. You may not conduct performance tests during periods of malfunction. You must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, you shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(e) You must conduct at least three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.

(f) You must use the data gathered during the performance test and the equations in paragraphs (f)(1) through (4) of this section to determine compliance with the emission limitations.

(1) To determine compliance with the production-based particulate matter (PM) and mercury (Hg) emission limits for ceramic tile roller kilns and sanitaryware tunnel kilns in Table 1 to this subpart, you must calculate your mass emissions per unit of production for each test run using Equation 1:

$$MP = \frac{ER}{P} \qquad \text{(Eq. 1)}$$

Where:

MP = mass per unit of production, kilograms (pounds) of pollutant per megagram (ton) of throughput

ER = mass emission rate of pollutant (PM or Hg) during each performance test run, kilograms (pounds) per hour

P = production rate during each performance test run, megagrams (tons) of throughput per hour.

(2) To determine compliance with the PM emission limits for ceramic tile glaze lines with glaze spraying and sanitaryware glaze spray booths in Table 1 to this subpart, you must calculate your mass emissions per unit of first-fire glaze sprayed (dry weight basis) for each test run using Equation 2:

$$MG = \frac{ER}{G} \qquad \text{(Eq. 2)}$$

Where:

MG = mass per unit of glaze application, kilograms (pounds) of PM per megagram (ton) of first-fire glaze sprayed (dry weight basis)

ER = mass emission rate of PM during each performance test run, kilograms (pounds) per hour

G = glaze application rate during each performance test run, megagrams (tons) of first-fire glaze sprayed per hour (dry weight basis).

(3) To determine compliance with the dioxin/furan emission limits for tunnel and roller kilns, ceramic tile spray dryers, and floor tile press dryers in

Table 1 to this subpart, you must calculate the sum of the 2,3,7,8-tetrachlorodibenzo-p-dioxin (2,3,7,8–TCDD) toxic equivalents (TEQs) for each test run using Equation 3:

$$TEQ = \frac{\sum_{i=1}^{n}\left(M_i \times TEF_i\right)}{T_r \times P} \qquad \text{(Eq. 3)}$$

Where:

TEQ = sum of the 2,3,7,8–TCDD TEQs, nanograms per kilogram of throughput processed.

M_i = mass of dioxin or furan congener i during performance test run, nanograms

TEF_i = 2,3,7,8–TCDD toxic equivalency factor (TEF) for congener i, as provided in Table 5 to this subpart

n = number of congeners included in TEQ

T_r = time of performance test run, hours

P = production rate during performance test run, kilograms of throughput processed per hour.

(4) To determine compliance with the health-based standard for acid gas HAP for clay ceramics manufacturing facilities in Table 1 to this subpart, you must:

(i) Calculate the HCl-equivalent emissions for HF and HCl for each tunnel or roller kiln at your facility using Equation 4:

$$E_i = E_{HCl} + \left[E_{HF}\left(\frac{RfC_{HCl}}{RfC_{HF}}\right)\right] \qquad \text{(Eq. 4)}$$

Where:

E_i = HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

E_{HCl} = emissions of HCl, kilograms (pounds) per hour

E_{HF} = emissions of HF, kilograms (pounds) per hour

RfC_{HCl} = reference concentration for HCl, 20 micrograms per cubic meter

RfC_{HF} = reference concentration for HF, 14 micrograms per cubic meter

(ii) If you have multiple tunnel or roller kilns at your facility, sum the HCl-equivalent values for all tunnel or roller kilns at the facility using Equation 5:

$$E_{total} = \sum_{i=1}^{n} E_i \qquad \text{(Eq. 5)}$$

Where:

E_{total} = HCl-equivalent emissions for total of all kilns at facility, kilograms (pounds) per hour

E_i = HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

n = number of tunnel kilns at facility

(iii) Compare this value to the health-based standard in Table 1 to this subpart.

(g) You must establish each site-specific operating limit in Table 2 to this subpart that applies to you as specified in paragraph (g)(1) of this section and in Table 4 to this subpart.

(1)(i) If you do not have an APCD installed on your tunnel or roller kiln, you must calculate the maximum potential HCl-equivalent emissions for HF and HCl for each tunnel or roller kiln at your facility using Equation 6:

$$E_{\max i} = \left(Cap_i\right)\left[\left(MP_{iHCl}\right) + \left(MP_{iHF}\right)\left(\frac{RfC_{HCl}}{RfC_{HF}}\right)\right] \qquad \text{(Eq. 6)}$$

Where:

$E_{max\ i}$ = maximum potential HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

Cap_i = design capacity for kiln i, megagrams (tons) of throughput per hour

MP_{iHCl} = mass of HCl per unit of production for kiln i, kilograms (pounds) of HCl per megagram (ton) of throughput

MP_{iHF} = mass of HF per unit of production for kiln i, kilograms (pounds) of HF per megagram (ton) of throughput

RfC_{HCl} = reference concentration for HCl, 20 micrograms per cubic meter

RfC_{HF} = reference concentration for HF, 14 micrograms per cubic meter

(ii) If you have multiple tunnel or roller kilns at your facility, sum the maximum potential HCl-equivalent values for all tunnel or roller kilns at the facility using Equation 7:

$$E_{\max total} = \sum_{i=1}^{n} E_{\max i} \qquad \text{(Eq. 7)}$$

Where:

$E_{max\ total}$ = maximum potential HCl-equivalent emissions for total of all kilns at facility, kilograms (pounds) per hour

$E_{max\ i}$ = maximum potential HCl-equivalent emissions for kiln i, kilograms (pounds) per hour

n = number of kilns at facility

(iii) If you have a single tunnel or roller kiln at your facility and the total facility maximum potential HCl-equivalent emissions ($E_{max\ total}$) are greater than the HCl-equivalent limit in Table 1 to this subpart, you must determine the maximum process rate for the kiln using Equation 8 that would ensure the total facility maximum potential HCl-equivalent emissions remain at or below the HCl-equivalent limit. The maximum process rate would become your operating limit for process rate and must be included in your OM&M plan.

$$P_{\max i} = \frac{HCl\text{-}eq}{\left[\left(MP_{iHCl}\right) + \left(MP_{iHF}\right)\left(\frac{RfC_{HCl}}{RfC_{HF}}\right)\right]} \qquad \text{(Eq. 8)}$$

Where:

$P_{max\ i}$ = maximum process rate for kiln i, megagrams (tons) per hour

HCl-eq = HCl-equivalent limit in Table 1 to this subpart, 62 kilograms (140 pounds) per hour

MP_{iHCl} = mass of HCl per unit of production for kiln i, kilograms (pounds) of HCl per megagram (ton) of throughput

MP_{iHF} = mass of HF per unit of production for kiln i, kilograms (pounds) of HF per megagram (ton) of throughput

RfC_{HCl} = reference concentration for HCl, 20 micrograms per cubic meter

RfC_{HF} = reference concentration for HF, 14 micrograms per cubic meter

(iv) If you have multiple tunnel or roller kilns at your facility and the total facility maximum potential HCl-equivalent emissions ($E_{max\ total}$) are greater than the HCl-equivalent limit in Table 1 to this subpart, you must determine the combination of maximum process rates that would ensure that total facility maximum potential HCl-equivalent remains at or below the HCl-equivalent limit. The maximum process rates would become your operating limits for process rate and must be included in your OM&M plan.

(2) [Reserved]

(h)(1) As an alternative to meeting the requirements of § 63.8555 for PM or mercury, if you have more than one existing source in any subcategories located at your facility, you may demonstrate compliance by emissions averaging, if your averaged emissions are no higher than the applicable emission limit, according to the procedures in this section. You may not include new or reconstructed sources in an emissions average.

(2) For a group of two or more existing sources in the same subcategory that each vent to a separate stack, you may average PM or mercury emissions among existing units to demonstrate compliance with the limits in Table 1 to this subpart as specified in paragraph (h)(2)(i) through (iv) of this section, if you satisfy the requirements in paragraphs (h)(3) and (4) of this section.

(i) You may average across existing sources in the same kiln type and size category (*e.g.*, roller or tunnel kilns, large or small kilns) and the same subcategory (*e.g.*, sanitaryware manual or spray machine or robot glaze application) where applicable;

(ii) You may not include a unit in the emissions average if the unit shares a common stack with units in other subcategories;

(iii) You may not include spray dryers or press dryers in the emissions average; and

(iv) You may not average between different types of pollutants.

(3) The averaged emissions rate from the existing sources participating in the emissions averaging option must not exceed the limits in Table 1 to this subpart at all times the affected units are subject to numeric emission limits following the compliance date specified in § 63.8545.

(4)(i) You must demonstrate initial compliance using the maximum process rate and the results of the initial performance tests.

(ii) You must use Equation 9 of this section to demonstrate that the PM or mercury emissions from all existing units participating in the emissions averaging option for that pollutant do not exceed the emission limits in Table 1 to this subpart.

$$ER_i = \sum_{i=1}^{n}\left(E_i \times P_{max\,i}\right) \div \sum_{i=1}^{n} P_{max\,i} \quad \text{(Eq. 9)}$$

Where:

ER_i = Average weighted emissions for PM or mercury, in units of kilograms (pounds) per megagram (ton) of fired product for existing floor tile roller kilns and wall tile roller kilns, greenware fired for existing first-fired sanitaryware tunnel kilns, and first-fire glaze sprayed (dry weight basis) for existing tile glaze lines with glaze spraying and average weighted emissions for PM, in units of kilograms (pounds) per megagram (ton) of first-fire glaze sprayed (dry weight basis) for existing sanitaryware manual, spray machine, or robot glaze applications.

E_i = Emission rate (as determined during the initial compliance demonstration) of PM or mercury from unit i, in units of kilograms (pounds) per megagram (ton). Determine the emission rate for PM or mercury by performance testing according to Table 4 to this subpart using the applicable equation in paragraph (f) of this section.

$P_{max\ i}$ = Maximum process rate for unit i, in units of megagrams per hour (tons per hour).

n = Number of units participating in the emissions averaging option.

(5) You must develop and submit upon request to the applicable Administrator for review and approval, an implementation plan for emissions averaging according to the following procedures and requirements in paragraphs (h)(5)(i) through (iv) of this section.

(i) If requested, you must submit the implementation plan no later than 180 days before the date that the facility intends to demonstrate compliance using the emissions averaging option.

(ii) You must include the information contained in paragraphs (h)(5)(ii)(A) through (D) of this section in your implementation plan for all emission sources included in an emissions average:

(A) The identification of all existing sources in the averaging group, including for each either the applicable HAP emissions level or the control technology installed and the date on which you are requesting emissions averaging to commence;

(B) The specific control technology or pollution prevention measure to be used for each source in the averaging group and the date of its installation or application. If the pollution prevention measure reduces or eliminates emissions from multiple sources, the owner or operator must identify each source;

(C) The test plan for the measurement of emissions in accordance with the requirements in this section; and

(D) The operating parameters to be monitored for each control system or device consistent with § 63.8555 and Table 2 to this subpart, and a description of how the operating limits will be determined.

(iii) If submitted upon request, the Administrator shall review and approve or disapprove the plan according to the following criteria:

(A) Whether the content of the plan includes all of the information specified in paragraph (h)(5)(ii) of this section; and

(B) Whether the plan presents sufficient information to determine that compliance will be achieved and maintained.

(iv) The applicable Administrator shall not approve an emissions averaging implementation plan containing any of the following provisions:

(A) Any averaging between emissions of differing pollutants or between differing sources; or

(B) The inclusion of any emission source other than an existing unit in the same subcategories.

(i) For each affected source that is subject to the emission limits specified in Table 1 to this subpart and is equipped with an APCD that is not addressed in Table 2 to this subpart or that is using process changes as a means of meeting the emission limits in Table 1 to this subpart, you must meet the requirements in § 63.8(f) and paragraphs (i)(1) and (2) of this section.

(1) Submit a request for approval of alternative monitoring procedures to the Administrator no later than the notification of intent to conduct a performance test. The request must contain the information specified in paragraphs (i)(1)(i) through (iv) of this section.

(i) A description of the alternative APCD or process changes.

(ii) The type of monitoring device or procedure that will be used.

(iii) The operating parameters that will be monitored.

(iv) The frequency that the operating parameter values will be determined and recorded to establish continuous compliance with the operating limits.

(2) Establish site-specific operating limits during the performance test based on the information included in the approved alternative monitoring procedures request and, as applicable, as specified in Table 4 to this subpart.

[80 FR 65543, Oct. 26, 2015, as amended at 84 FR 58606, Nov. 1, 2019]

§ 63.8600 What are my monitoring installation, operation, and maintenance requirements?

(a) You must install, operate, and maintain each CMS according to your OM&M plan and the requirements in paragraphs (a)(1) through (5) of this section.

(1) Conduct a performance evaluation of each CMS according to your OM&M plan.

(2) The CMS must complete a minimum of one cycle of operation for each successive 15-minute period. To

have a valid hour of data, you must have at least three of four equally spaced data values (or at least 75 percent if you collect more than four data values per hour) for that hour (not including startup, shutdown, malfunction, out-of-control periods, or periods of routine control device maintenance covered by the routine control device maintenance alternative standard as specified in § 63.8570(d)).

(3) Determine and record the 3-hour block averages of all recorded readings, calculated after every 3 hours of operation as the average of the previous 3 operating hours. To calculate the average for each 3-hour average period, you must have at least 75 percent of the recorded readings for that period (not including startup, shutdown, malfunction, out-of-control periods, or periods of routine control device maintenance covered by the routine control device maintenance alternative standard as specified in § 63.8570(d)).

(4) Record the results of each inspection, calibration, and validation check.

(5) At all times, maintain the monitoring equipment including, but not limited to, maintaining necessary parts for routine repairs of the monitoring equipment.

(b) For each liquid flow measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (b)(1) through (3) of this section.

(1) Locate the flow sensor in a position that provides a representative flowrate.

(2) Use a flow sensor with a minimum measurement sensitivity of 2 percent of the liquid flowrate.

(3) At least semiannually, conduct a flow sensor calibration check.

(c) For each pressure measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (c)(1) through (7) of this section.

(1) Locate the pressure sensor(s) in or as close to a position that provides a representative measurement of the pressure.

(2) Minimize or eliminate pulsating pressure, vibration, and internal and external corrosion.

(3) Use a gauge with a minimum measurement sensitivity of 0.5 inch of water or a transducer with a minimum measurement sensitivity of 1 percent of the pressure range.

(4) Check the pressure tap daily to ensure that it is not plugged.

(5) Using a manometer, check gauge calibration quarterly and transducer calibration monthly.

(6) Any time the sensor exceeds the manufacturer's specified maximum operating pressure range, conduct calibration checks or install a new pressure sensor.

(7) At least monthly, inspect all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(d) For each pH measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (d)(1) through (4) of this section.

(1) Locate the pH sensor in a position that provides a representative measurement of pH.

(2) Ensure the sample is properly mixed and representative of the fluid to be measured.

(3) Check the pH meter's calibration at one point daily.

(4) At least monthly, inspect all components for integrity and all electrical connections for continuity.

(e) For each bag leak detection system, you must meet the requirements in paragraphs (e)(1) through (11) of this section.

(1) Each triboelectric bag leak detection system must be installed, calibrated, operated, and maintained according to the EPA–454/R–98–015, ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference, see § 63.14). Other types of bag leak detection systems must be installed, operated, calibrated, and maintained in a manner consistent with the manufacturer's written specifications and recommendations.

(2) The bag leak detection system must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(3) The bag leak detection system sensor must provide an output of relative PM loadings.

(4) The bag leak detection system must be equipped with a device to continuously record the output signal from the sensor.

(5) The bag leak detection system must be equipped with an audible alarm system that will sound automatically when an increase in relative PM emissions over a preset level is detected. The alarm must be located where it is easily heard by plant operating personnel.

(6) For positive pressure fabric filter systems, a bag leak detector must be installed in each baghouse compartment or cell.

(7) For negative pressure or induced air fabric filters, the bag leak detector must be installed downstream of the fabric filter.

(8) Where multiple detectors are required, the system's instrumentation and alarm may be shared among detectors.

(9) The baseline output must be established by adjusting the range and the averaging period of the device and establishing the alarm set points and the alarm delay time according to section 5.0 of the ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference, see § 63.14).

(10) Following initial adjustment of the system, the sensitivity or range, averaging period, alarm set points, or alarm delay time may not be adjusted except as detailed in your OM&M plan. In no case may the sensitivity be increased by more than 100 percent or decreased more than 50 percent over a 365-day period unless such adjustment follows a complete fabric filter inspection which demonstrates that the fabric filter is in good operating condition, as defined in section 5.2 of the ''Fabric Filter Bag Leak Detection Guidance,'' (incorporated by reference, see § 63.14). Record each adjustment.

(11) Record the results of each inspection, calibration, and validation check.

(f) For each lime, chemical, or carbon feed rate measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (f)(1) and (2) of this section.

(1) Locate the measurement device in a position that provides a representative feed rate measurement.

(2) At least semiannually, conduct a calibration check.

(g) For each temperature measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (g)(1) through (3) of this section.

(1) Locate the measurement device in a position that provides a representative temperature.

(2) Use a measurement device with a minimum sensitivity of 1 percent of the temperature being measured.

(3) At least semiannually, conduct a calibration check.

(h) Requests for approval of alternate monitoring procedures must meet the requirements in §§ 63.8595(h) and 63.8(f).

§ 63.8605 How do I demonstrate initial compliance with the emission limitations and work practice standards?

(a) You must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to Table 6 to this subpart.

(b) You must establish each site-specific operating limit in Table 2 to this subpart that applies to you according to the requirements in § 63.8595 and Table 4 to this subpart.

(c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8630(c).

[80 FR 65543, Oct. 26, 2015, as amended at 80 FR 75817, Dec. 4, 2015]

Continuous Compliance Requirements

§ 63.8615 How do I monitor and collect data to demonstrate continuous compliance?

(a) You must monitor and collect data according to this section.

(b) Except for periods of monitor malfunctions, associated repairs, and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times that the affected source is operating. This includes periods of startup, shutdown, malfunction, and routine control device maintenance as specified in

§ 63.8570(d) when the affected source is operating.

(c) You may not use data recorded during monitoring malfunctions, associated repairs, out-of-control periods, or required quality assurance or control activities for purposes of calculating data averages. You must use all the valid data collected during all other periods in assessing compliance. Any averaging period for which you do not have valid monitoring data and such data are required constitutes a deviation from the monitoring requirements.

§ 63.8620 How do I demonstrate continuous compliance with the emission limitations and work practice standards?

(a) You must demonstrate continuous compliance with each emission limit, operating limit, and work practice standard in Tables 1, 2, and 3 to this subpart that applies to you according to the methods specified in Table 7 to this subpart.

(b) For each affected source that is subject to the emission limits specified in Table 1 to this subpart and is equipped with an APCD that is not addressed in Table 2 to this subpart, or that is using process changes as a means of meeting the emission limits in Table 1 to this subpart, you must demonstrate continuous compliance with each emission limit in Table 1 to this subpart, and each operating limit established as required in § 63.8595(h)(2) according to the methods specified in your approved alternative monitoring procedures request, as described in §§ 63.8595(h)(1) and 63.8(f).

(c) You must report each instance in which you did not meet each emission limit and operating limit in this subpart that applies to you. These instances are deviations from the emission limitations in this subpart. These deviations must be reported according to the requirements in § 63.8635(c)(8).

(d) [Reserved]

(e)(1) *Visible emissions testing.* You must demonstrate continuous compliance with the operating limits in Table 2 to this subpart for visible emissions (VE) from tunnel or roller kilns that are uncontrolled or equipped with DIFF, DLS/FF, or other dry control device by monitoring VE at each kiln stack according to the requirements in paragraphs (e)(1)(i) through (iii) of this section.

(i) Perform daily VE observations of each kiln stack according to the procedures of Method 22 of 40 CFR part 60, appendix A–7. You must conduct the Method 22 test while the affected source is operating under normal conditions. The duration of each Method 22 test must be at least 15 minutes.

(ii) If VE are observed during any daily test conducted using Method 22 of 40 CFR part 60, appendix A–7, you must promptly initiate and complete corrective actions according to your OM&M plan. If no VE are observed in 30 consecutive daily Method 22 tests for any kiln stack, you may decrease the frequency of Method 22 testing from daily to weekly for that kiln stack. If VE are observed during any weekly test, you must promptly initiate and complete corrective actions according to your OM&M plan, resume Method 22 testing of that kiln stack on a daily basis, and maintain that schedule until no VE are observed in 30 consecutive daily tests, at which time you may again decrease the frequency of Method 22 testing to a weekly basis.

(iii) If VE are observed during any test conducted using Method 22 of 40 CFR part 60, appendix A–7, you must report these deviations by following the requirements in § 63.8635.

(2) *Alternative to VE testing.* You must demonstrate continuous compliance with the operating limits in Table 2 to this subpart for kiln temperature profile for tunnel or roller kilns that are uncontrolled or equipped with DIFF, DLS/FF, or other dry control device by maintaining the kiln operating temperature within the range of acceptable temperatures (*i.e.*, temperature profile) established for each kiln and product. For any incidence where the kiln is operating outside of its acceptable temperature range (*i.e.*, exceeds its temperature profile) for the product being fired, you must record the incident as a deviation, and perform the necessary corrective action in accordance with your OM&M plan to return the kiln to the acceptable operating temperature for the product being fired. To confirm the kiln has returned to the acceptable

temperature range, you will monitor VE at the kiln stack according to the requirements in paragraphs (e)(2)(i) through (iii) of this section.

(i) Perform VE observations at the stack of each kiln operating outside of its temperature profile according to the procedures of Method 22 of 40 CFR part 60, appendix A–7. The duration of each Method 22 test must be at least 15 minutes.

(ii) If VE are observed during any test conducted using Method 22 of 40 CFR part 60, appendix A–7, you must continue to perform corrective action until VE are no longer observed.

(iii) If VE are observed during any test conducted using Method 22 of 40 CFR part 60, appendix A–7, you must report these deviations by following the requirements in § 63.8635.

(f) Following the compliance date, you must demonstrate compliance with the emissions averaging provision under this subpart on a continuous basis by meeting the requirements of paragraphs (f)(1) through (3) of this section.

(1)(i) After the initial compliance demonstration described in § 63.8595(h)(4), you must demonstrate compliance on a monthly basis determined at the end of every month (12 times per year) according to paragraph (f)(1)(ii) of this section. The first monthly period begins on the compliance date specified in § 63.8545.

(ii) For each calendar month, you must use Equation 10 of this section to calculate the average weighted emission rate for that month.

$$ER_i = \sum_{i=1}^{n}\left(E_i \times P_{month\ i}\right) \div \sum_{i=1}^{n} P_{month\ i} \quad \text{(Eq. 10)}$$

Where:

ER_i = Average weighted emissions for PM or mercury, in units of kilograms (pounds) per megagram (ton) of fired product for existing floor tile roller kilns and wall tile roller kilns, greenware fired for existing first-fired sanitaryware tunnel kilns, and first-fire glaze sprayed (dry weight basis) for existing tile glaze lines with glaze spraying and average weighted emissions for PM, in units of kilograms (pounds) per megagram (ton) of first-fire glaze sprayed (dry weight basis) for existing sanitaryware manual, spray machine, or robot glaze applications, for that calendar month.

E_i = Emission rate (as determined during the most recent compliance demonstration) of PM or mercury from unit i, in units of kilograms (pounds) per megagram (ton). Determine the emission rate for PM or mercury by performance testing according to Table 4 to this subpart using the applicable equation in § 63.8595(f).

$P_{month\ i}$ = The process rate for that calendar month for unit i, in units of megagrams (tons).

n = Number of units participating in the emissions averaging option.

(2) Until 12 monthly weighted average emission rates have been accumulated, calculate and report only the average weighted emission rate determined under paragraph (f)(1)(ii) of this section for each calendar month. After 12 monthly weighted average emission rates have been accumulated, for each subsequent calendar month, use Equation 11 of this section to calculate the 12-month rolling average of the monthly weighted average emission rates for the current calendar month and the previous 11 calendar months.

$$E_{avg} = \sum_{i=1}^{n} ER_i \div 12 \quad \text{(Eq. 11)}$$

Where:

E_{avg} = 12-month rolling average emission rate for PM or mercury, in units of kilograms

(pounds) per megagram (ton) of fired product for existing floor tile roller kilns and wall tile roller kilns, greenware fired for existing first-fired sanitaryware tunnel kilns, and first-fire glaze sprayed (dry weight basis) for existing tile glaze lines with glaze spraying and average weighted emissions for PM, in units of kilograms (pounds) per megagram (ton) of first-fire glaze sprayed (dry weight basis) for existing sanitaryware manual, spray machine, or robot glaze applications.

ER_i = Monthly weighted average, for calendar month ''i,'' in units of kilograms (pounds) per megagram (ton), as calculated by paragraph (f)(1)(ii) of this section.

(3) For each existing unit participating in the emissions averaging option, you must comply with the continuous compliance requirements in Table 7 to this subpart.

(g) Any instance where you fail to comply with the continuous monitoring requirements in paragraphs (f)(1) through (3) of this section is a deviation.

[80 FR 65543, Oct. 26, 2015, as amended at 84 FR 58607, Nov. 1, 2019]

NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.8630 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(f)(4), and 63.9 (b) through (e), (g)(1), and (h) that apply to you, by the dates specified.

(b) You must submit all of the notifications specified in Table 9 to this subpart that apply to you, by the dates specified.

(c) If you are required to conduct a performance test or other initial compliance demonstration as specified in Tables 4 and 6 to this subpart, your Notification of Compliance Status as specified in Table 9 to this subpart must include the information in paragraphs (c)(1) through (4) of this section.

(1) The requirements in § 63.9(h)(2)(i).

(2) The operating limit parameter values established for each affected source with supporting documentation and a description of the procedure used to establish the values.

(3) For each APCD that includes a fabric filter, if a bag leak detection system is used, analysis and supporting documentation demonstrating conformance with EPA guidance and specifications for bag leak detection systems in § 63.8600(e).

(4) Identification of whether you plan to demonstrate compliance by emissions averaging. If you plan to demonstrate compliance by emissions averaging, report the emissions level that was being achieved or the control technology employed on December 28, 2015.

(d) If you own or operate an affected kiln that is subject to the work practice standard specified in Item 1 of Table 3 to this subpart, and you intend to use a fuel other than natural gas or equivalent to fire the affected kiln, your notification of alternative fuel use must include the information specified in paragraphs (d)(1) through (5) of this section.

(1) Company name and address.

(2) Identification of the affected kiln.

(3) Reason you are unable to use natural gas or equivalent fuel, including the date when the natural gas curtailment was declared or the natural gas supply interruption began.

(4) Type of alternative fuel that you intend to use.

(5) Dates when the alternative fuel use is expected to begin and end.

[80 FR 65543, Oct. 26, 2015, as amended at 84 FR 58608, Nov. 1, 2019]

§ 63.8635 What reports must I submit and when?

(a) You must submit each report in Table 10 to this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report by the date in Table 10 to this subpart and as specified in paragraphs (b)(1) through (5) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.8545 and ending on either June 30 or December 31. This reporting period must be at least 6 months, but less than 12 months. For example, if your compliance date is March 1, then the first semiannual reporting period would begin on March 1 and end on December 31.

(2) The first compliance report must be postmarked or delivered no later

than July 31 or January 31 for compliance periods ending on June 30 and December 31, respectively.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31 for compliance periods ending on June 30 and December 31, respectively.

(5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of the dates in paragraphs (b)(1) through (4) of this section.

(c) The compliance report must contain the information in paragraphs (c)(1) through (9) of this section.

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying that, based on information and belief formed after reasonable inquiry, the statements and information in the report are true, accurate, and complete.

(3) Date of report and beginning and ending dates of the reporting period.

(4) A description of control device maintenance performed while the control device was offline and the affected source controlled by the control device was operating, including the information specified in paragraphs (c)(4)(i) through (iii) of this section.

(i) The date and time when the control device was shut down and restarted.

(ii) Identification of the affected source that was operating and the number of hours that the affected source operated while the control device was offline.

(iii) A statement of whether or not the control device maintenance was included in your approved routine control device maintenance request developed as specified in § 63.8570(d). If the control device maintenance was included in your approved routine control device maintenance request, then you must report the information in paragraphs (c)(4)(iii)(A) through (C) of this section.

(A) The total amount of time that the affected source controlled by the control device operated during the current semiannual compliance period and during the previous semiannual compliance period.

(B) The amount of time that each affected source controlled by the control device operated while the control device was offline for maintenance covered under the routine control device maintenance alternative standard during the current semiannual compliance period and during the previous semiannual compliance period.

(C) Based on the information recorded under paragraphs (c)(4)(iii)(A) and (B) of this section, compute the annual percent of affected source operating uptime during which the control device was offline for routine maintenance using Equation 12 of this section.

$$RM = \frac{DT_p + DT_c}{SU_p + SU_c}(100) \quad \text{(Eq. 12)}$$

Where:

RM = Annual percentage of affected source uptime during which control device was offline for routine control device maintenance.

DT_p = Control device downtime claimed under the routine control device maintenance alternative standard for the previous semiannual compliance period.

DT_c = Control device downtime claimed under the routine control device maintenance alternative standard for the current semiannual compliance period.

SU_p = Affected source uptime for the previous semiannual compliance period.
SU_c = Affected source uptime for the current semiannual compliance period.

(5) If there are no deviations from any emission limitations (emission limits or operating limits) or work practice standards that apply to you, the compliance report must contain a statement that there were no deviations from the emission limitations or work practice standards during the reporting period.

(6) If there were no periods during which the CMS was out-of-control as specified in your OM&M plan, the compliance report must contain a statement that there were no periods during which the CMS was out-of-control during the reporting period.

(7) The first compliance report must contain the startup production rate for each ceramic tile roller kiln, floor tile press dryer, ceramic tile spray dryer, and sanitaryware tunnel kiln; the minimum APCD inlet temperature for each APCD; and the temperature profile for each ceramic tile roller kiln, floor tile press dryer, ceramic tile spray dryer, and sanitaryware tunnel kiln without an APCD.

(8) For each deviation that occurs at an affected source, report such events in the compliance report by including the information in paragraphs (c)(8)(i) through (iii) of this section.

(i) The date, time, and duration of the deviation.

(ii) A list of the affected sources or equipment for which the deviation occurred.

(iii) An estimate of the quantity of each regulated pollutant emitted over any emission limit, and a description of the method used to estimate the emissions.

(9) If you plan to demonstrate compliance by emissions averaging, certify the emissions level achieved or the control technology employed is no less stringent than the level or control technology contained in the notification of compliance status in § 63.8630(c)(4), including all necessary documentation to support this certification, such as inputs to Equations 9 through 11 of this subpart.

(d) For each deviation from an emission limitation (emission limit or operating limit) occurring at an affected source where you are using a CMS to comply with the emission limitations in this subpart, you must include the information in paragraphs (c)(1) through (4) and (c)(8), and paragraphs (d)(1) through (11) of this section. This includes periods of startup, shutdown, and routine control device maintenance.

(1) The total operating time of each affected source during the reporting period.

(2) The date and time that each CMS was inoperative, except for zero (low-level) and high-level checks.

(3) The date, time, and duration that each CMS was out-of-control, including the pertinent information in your OM&M plan.

(4) Whether each deviation occurred during routine control device maintenance covered in your approved routine control device maintenance alternative standard or during another period, and the cause of each deviation (including unknown cause, if applicable).

(5) A description of any corrective action taken to return the affected unit to its normal or usual manner of operation.

(6) A breakdown of the total duration of the deviations during the reporting period into those that are due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes.

(7) A summary of the total duration of CMS downtime during the reporting period and the total duration of CMS downtime as a percent of the total source operating time during that reporting period.

(8) A brief description of the process units.

(9) A brief description of the CMS.

(10) The date of the latest CMS certification or audit.

(11) A description of any changes in CMS, processes, or control equipment since the last reporting period.

(e) If you have obtained a title V operating permit according to 40 CFR part 70 or 40 CFR part 71, you must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR

71.6(a)(3)(iii)(A). If you submit a compliance report according to Table 8 to this subpart along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all required information concerning deviations from any emission limitation (including any operating limit), then submitting the compliance report will satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submitting a compliance report will not otherwise affect any obligation you may have to report deviations from permit requirements to the permitting authority.

(f) If you own or operate an affected kiln that is subject to the work practice standard specified in Item 1 of Table 3 to this subpart, and you use a fuel other than natural gas or equivalent to fire the affected kiln, you must submit a report of alternative fuel use within 10 working days after terminating the use of the alternative fuel. The report must include the information in paragraphs (f)(1) through (6) of this section.

(1) Company name and address.

(2) Identification of the affected kiln.

(3) Reason for using the alternative fuel.

(4) Type of alternative fuel used to fire the affected kiln.

(5) Dates that the use of the alternative fuel started and ended.

(6) Amount of alternative fuel used.

(g) Within 60 calendar days after the date of completing each performance test (as defined in § 63.2) required by this subpart, you must submit the results of the performance test following the procedure specified in either paragraph (g)(1) or (g)(2) of this section.

(1) For data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (*https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert*) at the time of the test, you must submit the results of the performance test to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI). (CEDRI can be accessed through the EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*).) Performance test data must be submitted in a file format generated through the use of the EPA's ERT or an alternate electronic file format consistent with the extensible markup language (XML) schema listed on the EPA's ERT website. If you claim that some of the performance test information being submitted is confidential business information (CBI), you must submit a complete file generated through the use of the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website, including information claimed to be CBI, on a compact disc, flash drive, or other commonly used electronic storage media to the EPA. The electronic media must be clearly marked as CBI and mailed to U.S. EPA/OAPQS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same ERT or alternate file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph (g)(1).

(2) For data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT Web site at the time of the test, you must submit the results of the performance test to the Administrator at the appropriate address listed in § 63.13.

[80 FR 65543, Oct. 26, 2015, as amended at 84 FR 58608, Nov. 1, 2019; 86 FR 66043, Nov. 19, 2021]

§ 63.8640 What records must I keep?

(a) You must keep the records listed in paragraphs (a)(1) through (3) of this section.

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) Records of performance tests as required in § 63.10(b)(2)(viii).

(3) Records relating to control device maintenance and documentation of your approved routine control device maintenance request, if you request to use the alternative standard under § 63.8570(d).

(b) You must keep the records required in Table 7 to this subpart to show continuous compliance with each emission limitation and work practice standard that applies to you.

(c) You must also maintain the records listed in paragraphs (c)(1) through (11) of this section.

(1) For each bag leak detection system, records of each alarm, the time of the alarm, the time corrective action was initiated and completed, and a brief description of the cause of the alarm and the corrective action taken.

(2) For each deviation, record the information in paragraphs (c)(2)(i) through (iv) of this section.

(i) The date, time, and duration of the deviation.

(ii) A list of the affected sources or equipment.

(iii) An estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(iv) Actions taken to minimize emissions in accordance with § 63.8570(b) and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(3) For each affected source, records of production rates on a ton throughput processed basis.

(4) Records for any approved alternative monitoring or test procedures.

(5) Records of maintenance and inspections performed on the APCD.

(6) Current copies of your OM&M plan, including any revisions, with records documenting conformance.

(7) Logs of the information required in paragraphs (c)(7)(i) through (iii) of this section to document proper operation of your sanitaryware shuttle kiln.

(i) Records of the firing time and temperature cycle for each sanitaryware shuttle kiln. If all shuttle kilns use the same time and temperature cycles, one copy may be maintained for each kiln. Reference numbers must be assigned to use in log sheets.

(ii) For each sanitaryware shuttle kiln, a log that details the time and temperature protocol reference number, and an indication of whether the appropriate time and temperature cycle was fired.

(iii) For each sanitaryware shuttle kiln, a log of the actual tonnage of greenware fired in the shuttle kiln and an indication of whether the tonnage was below the maximum tonnage for that specific kiln.

(8) Logs of the maintenance procedures used to demonstrate compliance with the maintenance requirements of the sanitaryware shuttle kiln work practice standards specified in Table 3 to this subpart.

(9) For periods of startup and shutdown, records of the following information:

(i) The date, time, and duration of each startup and/or shutdown period, recording the periods when the affected source was subject to the standard applicable to startup and shutdown.

(ii) For periods of startup, the production rate and exhaust temperature prior to the time the exhaust reaches the minimum APCD inlet temperature (for ceramic tile roller kilns, floor tile press dryers, ceramic tile spray dryers, and sanitaryware tunnel kilns with an APCD) or the temperature profile is attained (for ceramic tile roller kilns, floor tile press dryers, ceramic tile spray dryers, and sanitaryware tunnel kilns with no APCD).

(iii) For periods of shutdown, the production rate and exhaust temperature after the time the exhaust falls below the minimum APCD inlet temperature (for ceramic tile roller kilns, floor tile press dryers, ceramic tile spray dryers, and sanitaryware tunnel kilns with an APCD) or the temperature profile is no longer maintained (for ceramic tile roller kilns, floor tile press dryers, ceramic tile spray dryers, and sanitaryware tunnel kilns with no APCD).

(10) All site-specific parameters, temperature profiles, and procedures required to be established or developed according to the applicable work practice standards in Table 3 to this subpart.

(11) If you elect to average emissions consistent with § 63.8595(h), you must additionally keep a copy of the emissions averaging implementation plan

required in § 63.8595(h)(5), all calculations required under § 63.8595(h), including monthly records of process rate, as applicable, and monitoring records consistent with § 63.8620(f).

[80 FR 65543, Oct. 26, 2015, as amended at 84 FR 58609, Nov. 1, 2019]

§ 63.8645 In what form and for how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record onsite for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You may keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.8655 What parts of the General Provisions apply to me?

Table 11 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.16 apply to you.

§ 63.8660 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. EPA, or a delegated authority such as your state, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your state, local, or tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if implementation and enforcement of this subpart is delegated to your state, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a state, local, or tribal agency under subpart E of this part, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the state, local, or tribal agency.

(c) The authorities that cannot be delegated to state, local, or tribal agencies are as specified in paragraphs (c)(1) through (6) of this section.

(1) Approval of alternatives to the applicability requirements in §§ 63.8535 and 63.8540, the compliance date requirements in § 63.8545, and the nonopacity emission limitations in § 63.8555.

(2) Approval of major changes to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major changes to monitoring under § 63.8(f) and as defined in in § 63.90.

(4) Approval of major changes to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

(5) Approval of an alternative to any electronic reporting to the EPA required by this subpart.

(6) Approval of a routine control device maintenance request under § 63.8570(d).

§ 63.8665 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in § 63.2, and in this section as follows:

Air pollution control device (APCD) means any equipment that reduces the quantity of a pollutant that is emitted to the air.

Bag leak detection system means an instrument that is capable of monitoring PM loadings in the exhaust of a fabric filter in order to detect bag failures. A bag leak detection system includes, but is not limited to, an instrument that operates on triboelectric, light-scattering, light-transmittance, or other effects to monitor relative PM loadings.

Clay ceramics manufacturing facility means a plant site that manufactures pressed floor tile, pressed wall tile, other pressed tile, or sanitaryware (*e.g.*, sinks and toilets). Clay ceramics manufacturing facilities typically process clay, shale, and various additives, form the processed materials into tile or sanitaryware shapes, and dry and fire the ceramic products. Glazes are applied to many tile and sanitaryware products. A plant site that manufactures refractory products, as defined in § 63.9824, or brick and

structural clay products (BSCP), as defined in § 63.8515, is not a clay ceramics manufacturing facility.

Cooling stack means a stack (release point) installed on the cooling zone of a tunnel kiln to release air used to cool down the fired product from its maximum temperature to room temperature. A cooling stack does not release any air from the firing zone of the tunnel kiln.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limitation (including any operating limit) or work practice standard; or

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart for any affected source required to obtain such a permit.

Dioxin/furan means, for purposes of this subpart, the sum of the 2,3,7,8–TCDD toxic equivalents calculated using Equation 3 of this subpart.

Dry lime injection fabric filter (DIFF) means an APCD that includes continuous injection of hydrated lime or other sorbent into a duct or reaction chamber followed by a fabric filter.

Dry lime scrubber/fabric filter (DLS/FF) means an APCD that includes continuous injection of humidified hydrated lime or other sorbent into a reaction chamber followed by a fabric filter. These systems typically include recirculation of some of the sorbent.

Emission limitation means any emission limit or operating limit.

Emissions averaging sources means, for purposes of the emissions averaging provisions of § 63.8595(h), the collection of all existing ceramic tile roller kilns, sanitaryware tunnel kilns, ceramic tile glaze lines using glaze spraying, and sanitaryware glaze spray booths, within a kiln type and size category and within a subcategory.

Fabric filter means an APCD used to capture PM by filtering a gas stream through filter media; also known as a baghouse.

Fired product means clay ceramic or sanitaryware products that have gone through the firing process via kilns.

Glaze means a coating of colored, opaque, or transparent material applied to ceramic products before firing.

Glaze line means a production line for glazing ceramic products, which includes glaze spraying (typically comprised of one or more glaze spray booths) and other types of glazing operations (*e.g.*, dipping, flooding, centrifugal disc glazing, curtain coating).

Glaze spray booth means a type of equipment used for spraying glaze on ceramic products.

Glaze spray operation means any type of glaze application that uses glaze spraying, including glaze lines and glaze spray booths.

Greenware means clay ceramic or sanitaryware products that have not gone through the firing process via kilns.

Initial startup means the time at which the kiln first reaches a level of production that is equal to 75 percent of the kiln design capacity or 12 months after the affected source begins firing clay ceramics, whichever is earlier.

Kiln design capacity means the maximum amount of clay ceramics, in Mg (tons), that a kiln is designed to produce in one year divided by the number of hours in a year (8,760 hours), taking into account the void space in the product, the push rate for the kiln, and the stacking pattern, if applicable. If a kiln is modified to increase the capacity, the design capacity is considered to be the capacity following modifications.

Minimum APCD inlet temperature means the minimum temperature that kiln exhaust can be vented to the APCD that ensures the long-term integrity of the APCD.

Particulate matter (PM) means, for purposes of this subpart, emissions of filterable PM that serve as a measure of total particulate emissions, as measured by Method 5 (40 CFR part 60, appendix A–3) or Method 29 (40 CFR part 60, appendix A–8), and as a surrogate for non-mercury metal HAP contained in the particulates including, but not

limited to, antimony, arsenic, beryllium, cadmium, chromium, cobalt, lead, manganese, nickel, and selenium.

Period of natural gas curtailment or supply interruption means a period of time during which the supply of natural gas to an affected facility is halted for reasons beyond the control of the facility. An increase in the cost or unit price of natural gas does not constitute a period of natural gas curtailment or supply interruption.

Plant site means all contiguous or adjoining property that is under common control, including properties that are separated only by a road or other public right-of-way. Common control includes properties that are owned, leased, or operated by the same entity, parent entity, subsidiary, or any combination thereof.

Products of combustion (POC) stack means a stack (release point) installed on the front end of the firing zone of a tunnel kiln to release air used to heat the greenware from room temperature to its maximum temperature.

Responsible official means responsible official as defined in 40 CFR 70.2.

Roller kiln means a continuous kiln similar to a tunnel kiln except that the unfired ceramic product travels through the kiln in a single layer on rollers. In the clay ceramics source category, roller kilns are used at ceramic tile manufacturing plants.

Shuttle kiln means a batch firing kiln that is designed with a removable superstructure that is tilted or raised using hydraulic struts to allow entrance and egress. In the clay ceramics source category, shuttle kilns are used at sanitaryware manufacturing plants.

Spray dryer means a drying chamber used to form a free-flowing powder from a slurry of ceramic mix and water, to improve handling and compaction. In the clay ceramics source category, spray dryers are used at ceramic tile manufacturing plants.

Startup means the setting in operation of an affected source and starting the production process.

Startup production rate means the kiln, press dryer or spray dryer production rate required to bring the process unit to the proper operating temperature during startup.

Tunnel kiln means any continuous kiln that is not a roller kiln that is used to fire clay ceramics. In the clay ceramics source category, tunnel kilns are used at sanitaryware manufacturing plants.

Wet scrubber (WS) means an APCD that uses water, which may include caustic additives or other chemicals, as the sorbent. Wet scrubbers may use any of various design mechanisms to increase the contact between exhaust gases and the sorbent.

Work practice standard means any design, equipment, work practice, operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the Clean Air Act.

[80 FR 65543, Oct. 26, 2015, as amended at 84 FR 58609, Nov. 1, 2019]

Tables to Subpart KKKKK of Part 63

TABLE 1 TO SUBPART KKKKK OF PART 63—EMISSION LIMITS

TABLE 1 TO SUBPART KKKKK OF PART 63—EMISSION LIMITS

As stated in §63.8555, you must meet each emission limit in the following table that applies to you:

For each . . .	You must meet the following emission limits . . .
1. Collection of all tunnel or roller kilns at facility.	HF and HCl emissions must not exceed 62 kilograms per hour (kg/hr) (140 pounds per hour (lb/hr)) HCl equivalent, under the health-based standard, as determined using Equations 4 and 5 of this subpart.
2. Existing floor tile roller kiln ...	a. PM emissions must not exceed 0.063 kilogram per megagram (kg/Mg) (0.13 pound per ton (lb/ton)) of fired product. b. Hg emissions must not exceed 6.3 E–05 kg/Mg (1.3 E–04 lb/ton) of fired product. c. Dioxin/furan emissions must not exceed 2.8 nanograms per kilogram (ng/kg) of fired product.
3. Existing wall tile roller kiln	a. PM emissions must not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product. b. Hg emissions must not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product. c. Dioxin/furan emissions must not exceed 0.22 ng/kg of fired product.
4. Existing first-fire sanitaryware tunnel kiln.	a. PM emissions must not exceed 0.17 kg/Mg (0.34 lb/ton) of greenware fired. b. Hg emissions must not exceed 1.3 E–04 kg/Mg (2.6 E–04 lb/ton) of greenware fired.

TABLE 1 TO SUBPART KKKKK OF PART 63—EMISSION LIMITS—Continued

As stated in § 63.8555, you must meet each emission limit in the following table that applies to you:

For each . . .	You must meet the following emission limits . . .
	c. Dioxin/furan emissions must not exceed 3.3 ng/kg of greenware fired.
5. Existing tile glaze line with glaze spraying.	a. PM emissions must not exceed 0.93 kg/Mg (1.9 lb/ton) of first-fire glaze sprayed (dry weight basis).
	b. Hg emissions must not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis).
6. Existing sanitaryware manual glaze application.	PM emissions must not exceed 18 kg/Mg (35 lb/ton) of first-fire glaze sprayed (dry weight basis).
7. Existing sanitaryware spray machine glaze application.	PM emissions must not exceed 6.2 kg/Mg (13 lb/ton) of first-fire glaze sprayed (dry weight basis).
8. Existing sanitaryware robot glaze application.	PM emissions must not exceed 4.5 kg/Mg (8.9 lb/ton) of first-fire glaze sprayed (dry weight basis).
9. Existing floor tile spray dryer	Dioxin/furan emissions must not exceed 19 ng/kg of throughput processed.
10. Existing wall tile spray dryer	Dioxin/furan emissions must not exceed 0.058 ng/kg of throughput processed.
11. Existing floor tile press dryer.	Dioxin/furan emissions must not exceed 0.024 ng/kg of throughput processed.
12. New or reconstructed floor tile roller kiln.	a. PM emissions must not exceed 0.019 kg/Mg (0.037 lb/ton) of fired product.
	b. Hg emissions must not exceed 2.0 E–05 kg/Mg (3.9 E–05 lb/ton) of fired product.
	c. Dioxin/furan emissions must not exceed 1.3 ng/kg of fired product.
13. New or reconstructed wall tile roller kiln.	a. PM emissions must not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product.
	b. Hg emissions must not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product.
	c. Dioxin/furan emissions must not exceed 0.22 ng/kg of fired product.
14. New or reconstructed first-fire sanitaryware tunnel kiln.	a. PM emissions must not exceed 0.048 kg/Mg (0.095 lb/ton) of greenware fired.
	b. Hg emissions must not exceed 6.1 E–05 kg/Mg (1.3 E–04 lb/ton) of greenware fired.
	c. Dioxin/furan emissions must not exceed 0.99 ng/kg of greenware fired.
15. New or reconstructed tile glaze line with glaze spraying.	a. PM emissions must not exceed 0.31 kg/Mg (0.61 lb/ton) of first-fire glaze sprayed (dry weight basis).
	b. Hg emissions must not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis).
16. New or reconstructed sanitaryware manual glaze application.	PM emissions must not exceed 2.0 kg/Mg (3.9 lb/ton) of first-fire glaze sprayed (dry weight basis).
17. New or reconstructed sanitaryware spray machine glaze application.	PM emissions must not exceed 1.6 kg/Mg (3.2 lb/ton) of first-fire glaze sprayed (dry weight basis).
18. New or reconstructed sanitaryware robot glaze application.	PM emissions must not exceed 1.2 kg/Mg (2.3 lb/ton) of first-fire glaze sprayed (dry weight basis).
19. New or reconstructed floor tile spray dryer.	Dioxin/furan emissions must not exceed 0.071 ng/kg of throughput processed.
20. New or reconstructed wall tile spray dryer.	Dioxin/furan emissions must not exceed 0.058 ng/kg of throughput processed.
21. New or reconstructed floor tile press dryer.	Dioxin/furan emissions must not exceed 0.024 ng/kg of throughput processed.
22. Collection of emissions averaging sources.	PM emissions must not exceed the applicable emission limit, under the emissions averaging option, as determined using Equations 9 through 11 of this subpart.
23. Collection of emissions averaging sources.	Hg emissions must not exceed the applicable emission limit, under the emissions averaging option, as determined using Equations 9 through 11 of this subpart.

[84 FR 58609, Nov. 1, 2019]

TABLE 2 TO SUBPART KKKKK OF PART 63—OPERATING LIMITS

TABLE 2 TO SUBPART KKKKK OF PART 63—OPERATING LIMITS

As stated in §63.8555, you must meet each operating limit in the following table that applies to you:

For each . . .	You must . . .	Or you must . . .
1. Tunnel or roller kiln equipped with a DIFF or DLS/FF..	a. If you use a bag leak detection system, initiate corrective action within 1 hour of a bag leak detection system alarm and complete corrective actions in accordance with your OM&M plan; operate and maintain the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period; and b. Maintain free-flowing lime in the feed hopper or silo and to the APCD at all times for continuous injection systems; maintain the feeder setting (on a per ton of throughput basis) at or above the level established during the performance test for continuous injection systems in which compliance was demonstrated.	i. Maintain no VE from the DIFF or DLS/FF stack; or ii. Maintain your kiln operating temperature within the range of acceptable temperatures (*i.e.,* temperature profile) established for each kiln and product.
2. Tunnel or roller kiln equipped with a WS..	a. Maintain the average scrubber liquid pH for each 3-hour block period at or above the average scrubber liquid pH established during the HF/HCl performance test in which compliance was demonstrated; and b. Maintain the average scrubber liquid flow rate for each 3-hour block period at or above the highest average scrubber liquid flow rate established during the HF/HCl and PM performance tests in which compliance was demonstrated.	
3. Tunnel or roller kiln equipped with an ACI system..	Maintain the 3-hour block average carbon flow rate at or above the highest average carbon flow rate established during the Hg and dioxin/furan performance tests in which compliance was demonstrated.	
4. Tunnel or roller kiln intending to comply with dioxin/furan emission limit without an ACI system.	Maintain the average operating temperature for each 12-hour block period at or below the highest operating temperature established during the dioxin/furan performance test in which compliance was demonstrated	
5. Tunnel or roller kiln with no add-on control.	a. Maintain no VE from the stack; and b. Maintain the kiln process rate at or below the kiln process rate determined according to §63.8595(g)(1) if your total facility maximum potential HCl-equivalent emissions are greater than the HCl-equivalent limit in Table 1 to this subpart; and c. Maintain the average operating temperature for each 12-hour block period at or below the highest operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.	i. Maintain your kiln operating temperature within the range of acceptable temperatures (*i.e.,* temperature profile) established for each kiln and product.
6. Glaze spray operation equipped with a FF.	a. If you use a bag leak detection system, initiate corrective action within 1 hour of a bag leak detection system alarm and complete corrective actions in accordance with your OM&M plan; operate and maintain the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period.	i. Maintain no VE from the FF stack.
7. Glaze spray operation equipped with a WS..	a. Maintain the average scrubber pressure drop for each 3-hour block period at or above the average pressure drop established during the PM performance test in which compliance was demonstrated; and b. Maintain the average scrubber liquid flow rate for each 3-hour block period at or above the average scrubber liquid flow rate established during the PM performance test in which compliance was demonstrated.	

TABLE 2 TO SUBPART KKKKK OF PART 63—OPERATING LIMITS—Continued

As stated in §63.8555, you must meet each operating limit in the following table that applies to you:

For each . . .	You must . . .	Or you must . . .
8. Glaze spray operation equipped with a water curtain..	a. Conduct daily inspections to verify the presence of water flow to the wet control system; and b. Conduct annual inspections of the interior of the control equipment (if applicable) to determine the structural integrity and condition of the control equipment.	
9. Glaze spray operation equipped with baffles.	Conduct an annual visual inspection of the baffles to confirm the baffles are in place.	
10. Spray dryer	Maintain the average operating temperature for each 4-hour block period at or above the average temperature established during the dioxin/furan performance test in which compliance was demonstrated.	
11. Floor tile press dryer	Maintain the average operating temperature for each 4-hour block period at or below the average temperature established during the dioxin/furan performance test in which compliance was demonstrated.	

[86 FR 66043, Nov. 19, 2021]

TABLE 3 TO SUBPART KKKKK OF PART 63—WORK PRACTICE STANDARDS

As stated in §63.8555, you must comply with each work practice standard in the following table that applies to you:

For each . . .	You must . . .	According to one of the following requirements . . .
1. Existing, new, or reconstructed sanitaryware shuttle kiln.	a. Minimize HAP emissions	i. Use natural gas, or equivalent, as the kiln fuel, except during periods of natural gas curtailment or supply interruption, as defined in §63.8665; and ii. Develop and use a designed firing time and temperature cycle for each sanitaryware shuttle kiln. You must either program the time and temperature cycle into your kiln or track each step on a log sheet; and iii. Label each sanitaryware shuttle kiln with the maximum load (in tons) of greenware that can be fired in the kiln during a single firing cycle; and iv. For each firing load, document the total tonnage of greenware placed in the kiln to ensure that it is not greater than the maximum load identified in item 1.a.iii; and v. Develop and follow maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices, controls that regulate air-to-fuel ratios, and controls that regulate firing cycles; and vi. Develop and maintain records for each sanitaryware shuttle kiln, as specified in §63.8640.
2. Existing, new or reconstructed ceramic tile roller kiln, sanitaryware tunnel kiln, floor tile press dryer or ceramic tile spray dryer during periods of startup.	a. Minimize HAP emissions	i. Establish the startup production rate for each kiln or dryer; the minimum APCD inlet temperature for each APCD; and temperature profile for each kiln or dryer with no APCD and include them in your first compliance report, as specified in §63.8635(c)(7); and ii. After initial loading of the kiln or dryer, remain at or below the startup production rate for the kiln or dryer until the kiln or dryer exhaust reaches the minimum APCD inlet temperature for a kiln or dryer with an APCD or until the kiln or dryer temperature profile is attained for a kiln or dryer with no APCD; and iii. If your kiln or dryer has an APCD, begin venting the exhaust from the kiln or dryer through the APCD by the time the kiln or dryer exhaust temperature reaches the minimum APCD inlet temperature.

For each . . .	You must . . .	According to one of the following requirements . . .
3. Existing, new or reconstructed ceramic tile roller kiln, sanitaryware tunnel kiln, floor tile press dryer or ceramic tile spray dryer during periods of shutdown.	a. Minimize HAP emissions	i. Do not load the kiln or dryer once the kiln or dryer exhaust temperature falls below the minimum APCD inlet temperature if the kiln or dryer is controlled by an APCD or when the kiln or dryer temperature profile is no longer maintained for an uncontrolled kiln or dryer; and ii. If your kiln or dryer has an APCD, continue to vent the exhaust from the kiln or dryer through the APCD until the kiln or dryer exhaust temperature falls below the minimum inlet temperature for the APCD.
4. Existing, new or reconstructed ceramic tile roller kiln, sanitaryware tunnel kiln, floor tile press dryer or ceramic tile spray dryer during periods of routine control device maintenance.	a. Minimize HAP emissions	i. Develop and use a temperature profile for each kiln or dryer; and ii. Develop and follow maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices and controls that regulate air-to-fuel ratios; and iii. Develop and maintain records for each kiln or dryer, as specified in § 63.8640(a)(3).

TABLE 4 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS

TABLE 4 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS

As stated in § 63.8595, you must conduct each performance test in the following table that applies to you:

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
1. Tunnel or roller kiln ...	a. Select locations of sampling ports and the number of traverse points.	Method 1 or 1A of 40 CFR part 60, appendix A–1.	Sampling sites must be located at the outlet of the APCD and prior to any releases to the atmosphere for all affected sources.
	b. Determine velocities and volumetric flow rate.	Method 2 of 40 CFR part 60, appendix A–1.	You may use Method 2A, 2C, 2D, or 2F of 40 CFR part 60, appendix A–1, or Method 2G of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 2 of 40 CFR part 60, appendix A–1.
	c. Conduct gas molecular weight analysis.	Method 3 of 40 CFR part 60, appendix A–2.	You may use Method 3A or 3B of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 3 of 40 CFR part 60, appendix A–2. ANSI/ASME PTC 19.10–1981 (incorporated by reference, see § 63.14) may be used as an alternative to the manual procedures (but not the instrumental procedures) in Methods 3A and 3B.
	d. Measure moisture content of the stack gas.	Method 4 of 40 CFR part 60, appendix A–3.	
	e. Measure HF and HCl emissions.	i. Method 26A of 40 CFR part 60, appendix A–8; or	You may use Method 26 of 40 CFR part 60, appendix A–8, as an alternative to using Method 26A of 40 CFR part 60, appendix A–8, when no acid PM (*e.g.,* HF or HCl dissolved in water droplets emitted by sources controlled by a WS) is present. ASTM D6735–01 (Reapproved 2009) (incorporated by reference, see § 63.14) may be used as an alternative to Methods 26 and 26A.
		ii. Method 320 of appendix A of this part.	When using Method 320 of appendix A of this part, you must follow the analyte spiking procedures of section 13 of Method 320 of appendix A of this part, unless you can demonstrate that the complete spiking procedure has been conducted at a similar source. ASTM D6348–03 (Reapproved 2010) (incorporated by reference, see § 63.14) may be used as an alternative to Method 320 if the test plan preparation and implementation in Annexes A1–A8 are mandatory and the %R in Annex A5 is determined for each target analyte.
	f. Measure PM emissions.	i. Method 5 of 40 CFR part 60, appendix A–3; or	

TABLE 4 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS—Continued

As stated in §63.8595, you must conduct each performance test in the following table that applies to you:

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
		ii. Method 29 of 40 CFR part 60, appendix A–8.	
	g. Measure Hg emissions.	Method 29 of 40 CFR part 60, appendix A–8.	ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14) may be used as an alternative to Method 29 (portion for Hg only).
	h. Measure dioxin/furan emissions.	Method 23 of 40 CFR part 60, appendix A–7.	
2. Glaze spray operation	a. Select locations of sampling ports and the number of traverse points.	Method 1 or 1A of 40 CFR part 60, appendix A–1.	Sampling sites must be located at the outlet of the APCD and prior to any releases to the atmosphere for all affected sources.
	b. Determine velocities and volumetric flow rate.	Method 2 of 40 CFR part 60, appendix A–1.	You may use Method 2A, 2C, 2D, or 2F of 40 CFR part 60, appendix A–1, or Method 2G of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 2 of 40 CFR part 60, appendix A–1.
	c. Conduct gas molecular weight analysis.	Method 3 of 40 CFR part 60, appendix A–2.	You may use Method 3A or 3B of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 3 of 40 CFR part 60, appendix A–2. ANSI/ASME PTC 19.10–1981 (incorporated by reference, see §63.14) may be used as an alternative to the manual procedures (but not the instrumental procedures) in Methods 3A and 3B.
	d. Measure moisture content of the stack gas.	Method 4 of 40 CFR part 60, appendix A–3.	
	e. Measure PM emissions.	Method 5 of 40 CFR part 60, appendix A–3.	
	f. Measure Hg emissions (tile glaze spray operations only).	Method 29 of 40 CFR part 60, appendix A–8.	ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14) may be used as an alternative to Method 29 (portion for Hg only).
3. Spray dryer or floor tile press dryer.	a. Select locations of sampling ports and the number of traverse points.	Method 1 or 1A of 40 CFR part 60, appendix A–1.	Sampling sites must be located at the outlet of the APCD and prior to any releases to the atmosphere for all affected sources.
	b. Determine velocities and volumetric flow rate.	Method 2 of 40 CFR part 60, appendix A–1.	You may use Method 2A, 2C, 2D, or 2F of 40 CFR part 60, appendix A–1, or Method 2G of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 2 of 40 CFR part 60, appendix A–1.
	c. Conduct gas molecular weight analysis.	Method 3 of 40 CFR part 60, appendix A–2.	You may use Method 3A or 3B of 40 CFR part 60, appendix A–2, as appropriate, as an alternative to using Method 3 of 40 CFR part 60, appendix A–2. ANSI/ASME PTC 19.10–1981 (incorporated by reference, see §63.14) may be used as an alternative to the manual procedures (but not the instrumental procedures) in Methods 3A and 3B.
	d. Measure moisture content of the stack gas.	Method 4 of 40 CFR part 60, appendix A–3.	
	e. Measure dioxin/furan emissions.	Method 23 of 40 CFR part 60, appendix A–7.	
4. Tunnel or roller kiln with no add-on control.	a. Establish the operating limit(s) for kiln process rate if the total facility maximum potential HCl-equivalent emissions are greater than the HCl-equivalent limit in Table 1 to this subpart.	HCl-equivalent limit in Table 1 to this subpart and emissions and production data from the HF/HCl/Cl_2 performance test.	Using the procedures in §63.8595(g)(1), you must determine the maximum process rate(s) for your kiln(s) that would ensure total facility maximum potential HCl-equivalent emissions remain at or below the HCl-equivalent limit in Table 1 to this subpart. The maximum process rate(s) would become your site-specific process rate operating limit(s).

TABLE 4 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS—Continued

As stated in § 63.8595, you must conduct each performance test in the following table that applies to you:

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
	b. Establish the operating limit for kiln operating temperature.	i. Data from the kiln operating temperature measurement device during the dioxin/furan performance test.	(1) You must continuously measure the kiln operating temperature during three 4-hour test runs and, from a 12-hour block of time consisting of 1-hour increments, calculate the following two values: (a) The standard deviation of the 12 1-hour temperature measurements (refer to Note 1). (b) 1 percent of the 12-hour block average. (2) You must decide which of the two values would provide the greatest variability (*i.e.,* the highest value), and then add this value to the 12-hour block average measured during the compliance testing. The result is the maximum temperature at which your kiln may operate during normal operations.
5. Tunnel or roller kiln that is complying with PM and/or Hg production-based emission limits.	Determine the production rate during each PM/Hg test run in order to determine compliance with PM and/or Hg production-based emission limits.	Production data collected during the PM/Hg performance tests (*e.g.,* the number of ceramic pieces and weight per piece in the kiln during a test run divided by the amount of time to fire a piece).	You must measure and record the production rate, on a ton of throughput processed basis, of the affected kiln for each of the three test runs.
6. Tunnel or roller kiln equipped with a DIFF or DLS/FF.	Establish the operating limit for the lime feeder setting.	Data from the lime feeder during the HF/HCl performance test.	For continuous lime injection systems, you must ensure that lime in the feed hopper or silo and to the APCD is free-flowing at all times during the performance test and record the feeder setting, on a per ton of throughput basis, for the three test runs. If the feed rate setting varies during the three test runs, determine and record the average feed rate from the three test runs. The average of the three test runs establishes your minimum site-specific feed rate operating limit.
7. Tunnel or roller kiln equipped with a WS.	a. Establish the operating limit for the average scrubber liquid pH.	Data from the pH measurement device during the HF/HCl performance test.	You must continuously measure the scrubber liquid pH, determine and record the block average pH values for the three test runs, and determine and record the 3-hour block average of the recorded pH measurements for the three test runs. The average of the three test runs establishes your minimum site-specific liquid pH operating limit.
	b. Establish the operating limit for the average scrubber liquid flow rate.	Data from the flow rate measurement device during the HF/HCl and PM performance tests.	You must continuously measure the scrubber liquid flow rate, determine and record the block average flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded flow rate measurements for the three test runs. The average of the three test runs establishes your minimum site-specific liquid flow rate operating level. If different average wet scrubber liquid flow rate values are measured during the HF/HCl and PM tests, the highest of the average values become your site-specific operating limit.
8. Tunnel or roller kiln equipped with an ACI system.	Establish the operating limit for the average carbon flow rate.	Data from the carbon flow rate measurement conducted during the Hg and dioxin/furan performance tests.	You must measure the carbon flow rate during each test run, determine and record the block average carbon flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded carbon flow rate measurements for the three test runs. The average of the three test runs establishes your minimum site-specific activated carbon flow rate operating limit.

TABLE 4 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS—Continued

As stated in § 63.8595, you must conduct each performance test in the following table that applies to you:

For each . . .	You must . . .	Using . . .	According to the following requirements . . .
9. Tunnel or roller kiln intending to comply with dioxin/furan emission limit without an ACI system.	a. Establish the operating limit for kiln operating temperature.	i. Data from the kiln operating temperature measurement device during the dioxin/furan performance test.	(1) You must continuously measure the kiln operating temperature during three 4-hour test runs and, from a 12-hour block of time consisting of 1-hour increments, calculate the following two values: (a) The standard deviation of the 12 1-hour temperature measurements (refer to Note 1). (b) 1 percent of the 12-hour block average (2) You must decide which of the two values would provide the greatest variability (*i.e.,* the highest value), and then add this value to the 12-hour block average measured during the compliance testing. The result is the maximum temperature at which your kiln may operate during normal operations.
10. Glaze spray operation equipped with a WS.	a. Establish the operating limit for the average scrubber pressure drop.	Data from the pressure drop measurement device during the PM performance test.	You must continuously measure the scrubber pressure drop, determine and record the block average pressure drop values for the three test runs, and determine and record the 3-hour block average of the recorded pressure drop measurements for the three test runs. The average of the three test runs establishes your minimum site-specific pressure drop operating limit.
	b. Establish the operating limit for the average scrubber liquid flow rate.	Data from the flow rate measurement device during the PM performance test.	You must continuously measure the scrubber liquid flow rate, determine and record the block average flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded flow rate measurements for the three test runs. The average of the three test runs establishes your minimum site-specific liquid flow rate operating limit.
11. Spray dryer	Establish the operating limit for operating temperature.	Data from the temperature measurement device during the dioxin/furan performance test.	You must continuously measure the operating temperature, determine and record the block average temperature values for the three test runs, and determine and record the 4-hour block average of the recorded temperature measurements for the three test runs. The average of the three test runs establishes your minimum site-specific operating limit.
12. Floor tile press dryer	Establish the operating limit for operating temperature.	Data from the temperature measurement device during the dioxin/furan performance test.	You must continuously measure the operating temperature, determine and record the block average temperature values for the three test runs, and determine and record the 4-hour block average of the recorded temperature measurements for the three test runs. The average of the three test runs establishes your maximum site-specific operating limit.

Note 1: The standard deviation of the 12 1-hour temperature measurements is calculated as follows:

$$\sigma = \sqrt{\frac{1}{N} \times \sum_{i=1}^{N} \left(x_i - \mu\right)^2} \quad \text{(Eq. 13)}$$

Where:

σ = standard deviation

x_i = each 1-hour temperature measurement

μ = mean of all 12 1-hour measurements

N = 12 measurements

[84 FR 58611, Nov. 1, 2019]

TABLE 5 TO SUBPART KKKKK OF PART 63—TOXIC EQUIVALENCY FACTORS

As stated in §63.8595(f)(3), you must demonstrate initial compliance with each dioxin/furan emission limit that applies to you by calculating the sum of the 2,3,7,8-TCDD TEQs using the TEFs in the following table:

For each dioxin/furan congener . . .	You must calculate its 2,3,7,8-TCDD TEQ using the following TEF . . .
2,3,7,8-tetrachlorodibenzo-p-dioxin	1
1,2,3,7,8-pentachlorodibenzo-p-dioxin	1
1,2,3,4,7,8-hexachlorodibenzo-p-dioxin	0.1
1,2,3,7,8,9-hexachlorodibenzo-p-dioxin	0.1
1,2,3,6,7,8-hexachlorodibenzo-p-dioxin	0.1
1,2,3,4,6,7,8-heptachlorodibenzo-p-dioxin	0.01
Octachlorodibenzo-p-dioxin	0.0003
2,3,7,8-tetrachlorodibenzofuran	0.1
1,2,3,7,8-pentachlorodibenzofuran	0.03
2,3,4,7,8-pentachlorodibenzofuran	0.3
1,2,3,4,7,8-hexachlorodibenzofuran	0.1
1,2,3,6,7,8-hexachlorodibenzofuran	0.1
1,2,3,7,8,9-hexachlorodibenzofuran	0.1
2,3,4,6,7,8-hexachlorodibenzofuran	0.1
1,2,3,4,6,7,8-heptachlorodibenzofuran	0.01
1,2,3,4,7,8,9-heptachlorodibenzofuran	0.01
Octachlorodibenzofuran	0.0003

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

As stated in §63.8605, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
1. Collection of all tunnel or roller kilns at the facility.	a. HF, HCl, and Cl_2 emissions must not exceed 62 kg/hr (140 lb/hr) HCl equivalent.	i. You measure HF and HCl emissions for each kiln using Method 26 or 26A of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6735–01 (Reapproved 2009) (incorporated by reference, see §63.14); or Method 320 of appendix A of this part or its alternative, ASTM D6348–03 (Reapproved 2010) (incorporated by reference, see §63.14); and ii. You calculate the HCl-equivalent emissions for HF for each kiln using Equation 4 to this subpart; and iii. You sum the HCl-equivalent values for all kilns at the facility using Equation 5 to this subpart; and iv. The facility total HCl-equivalent does not exceed 62 kg/hr (140 lb/hr).
2. Existing floor tile roller kiln ...	a. PM emissions must not exceed 0.063 kg/Mg (0.13 lb/ton) of fired product.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8595(f)(1), do not exceed 0.063 kg/Mg (0.13 lb/ton) of fired product; and ii. You establish and have a record of the applicable operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.063 kg/Mg (0.13 lb/ton) of fired product.
	b. Hg emissions must not exceed 6.3 E–05 kg/Mg (1.3 E–04 lb/ton) of fired product.	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 6.3 E–05 kg/Mg (1.3 E–04 lb/ton) of fired product; and

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8605, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 6.3 E–05 kg/Mg (1.3 E–04 lb/ton) of fired product.
	c. Dioxin/furan emissions must not exceed 2.8 ng/kg of fired product.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 2.8 ng/kg of fired product; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 2.8 ng/kg of fired product.
3. Existing wall tile roller kiln	a. PM emissions must not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8595(f)(1), do not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product.
	b. Hg emissions must not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product.	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product.
	c. Dioxin/furan emissions must not exceed 0.22 ng/kg of fired product.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.22 ng/kg of fired product; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.22 ng/kg of fired product.
4. Existing first-fire sanitaryware tunnel kiln.	a. PM emissions must not exceed 0.17 kg/Mg (0.34 lb/ton) of greenware fired.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8595(f)(1), do not exceed 0.17 kg/Mg (0.34 lb/ton) of greenware fired; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.17 kg/Mg (0.34 lb/ton) of greenware fired.
	b. Hg emissions must not exceed 1.3 E–04 kg/Mg (2.6 E–04 lb/ton) of greenware fired.	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 1.3 E–04 kg/Mg (2.6 E–04 lb/ton) of greenware fired; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 1.3 E–04 kg/Mg (2.6 E–04 lb/ton) of greenware fired.
	c. Dioxin/furan emissions must not exceed 3.3 ng/kg of greenware fired.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 3.3 ng/kg of greenware fired; and
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 3.3 ng/kg of greenware fired.

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8605, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
5. Existing tile glaze line with glaze spraying.	a. PM emissions must not exceed 0.93 kg/Mg (1.9 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 0.93 kg/Mg (1.9 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.93 kg/Mg (1.9 lb/ton) of first-fire glaze sprayed (dry weight basis).
	b. Hg emissions must not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis).
6. Existing sanitaryware manual glaze application.	a. PM emissions must not exceed 18 kg/Mg (35 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 18 kg/Mg (35 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 18 kg/Mg (35 lb/ton) of first-fire glaze sprayed (dry weight basis).
7. Existing sanitaryware spray machine glaze application.	a. PM emissions must not exceed 6.2 kg/Mg (13 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 6.2 kg/Mg (13 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 6.2 kg/Mg (13 lb/ton) of first-fire glaze sprayed (dry weight basis).
8. Existing sanitaryware robot glaze application.	a. PM emissions must not exceed 4.5 kg/Mg (8.9 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 4.5 kg/Mg (8.9 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 4.5 kg/Mg (8.9 lb/ton) of first-fire glaze sprayed (dry weight basis).
9. Existing floor tile spray dryer	a. Dioxin/furan emissions must not exceed 19 ng/kg of throughput processed.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 19 ng/kg of throughput processed; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 19 ng/kg of throughput processed.
10. Existing wall tile spray dryer.	a. Dioxin/furan emissions must not exceed 0.058 ng/kg of throughput processed.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.058 ng/kg of throughput processed; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.058 ng/kg of throughput processed.

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8605, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
11. Existing floor tile press dryer.	a. Dioxin/furan emissions must not exceed 0.024 ng/kg of throughput processed.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.024 ng/kg of throughput processed; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.024 ng/kg of throughput processed.
12. New or reconstructed floor tile roller kiln.	a. PM emissions must not exceed 0.019 kg/Mg (0.037 lb/ton) of fired product.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8595(f)(1), do not exceed 0.019 kg/Mg (0.037 lb/ton) of fired product; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.019 kg/Mg (0.037 lb/ton) of fired product.
	b. Hg emissions must not exceed 2.0 E–05 kg/Mg (3.9 E–05 lb/ton) of fired product.	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 2.0 E–05 kg/Mg (3.9 E–05 lb/ton) of fired product; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 2.0 E–05 kg/Mg (3.9 E–05 lb/ton) of fired product.
	c. Dioxin/furan emissions must not exceed 1.3 ng/kg of fired product.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 1.3 ng/kg of fired product; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 1.3 ng/kg of fired product.
13. New or reconstructed wall tile roller kiln.	a. PM emissions must not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8595(f)(1), do not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.19 kg/Mg (0.37 lb/ton) of fired product.
	b. Hg emissions must not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product.	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 1.1 E–04 kg/Mg (2.1 E–04 lb/ton) of fired product.
	c. Dioxin/furan emissions must not exceed 0.22 ng/kg of fired product.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.22 ng/kg of fired product; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.22 ng/kg of fired product.
14. New or reconstructed first-fire sanitaryware tunnel kiln.	a. PM emissions must not exceed 0.048 kg/Mg (0.095 lb/ton) of greenware fired.	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3 or Method 29 of 40 CFR part 60, appendix A–8, over the period of the initial performance test, according to the calculations in §63.8595(f)(1), do not exceed 0.048 kg/Mg (0.095 lb/ton) of greenware fired; and

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8605, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.048 kg/Mg (0.095 lb/ton) of greenware fired.
	b. Hg emissions must not exceed 6.1 E–05 kg/Mg (1.3 E–04 lb/ton) of greenware fired.	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 6.1 E–05 kg/Mg (1.3 E–04 lb/ton) of greenware fired; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 6.1 E–05 kg/Mg (1.3 E–04 lb/ton) of greenware fired.
	c. Dioxin/furan emissions must not exceed 0.99 ng/kg of greenware fired.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.99 ng/kg of greenware fired; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.99 ng/kg of greenware fired.
15. New or reconstructed tile glaze line with glaze spraying.	a. PM emissions must not exceed 0.31 kg/Mg (0.61 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 0.31 kg/Mg (0.61 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 0.31 kg/Mg (0.61 lb/ton) of first-fire glaze sprayed (dry weight basis).
	b. Hg emissions must not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The Hg emissions measured using Method 29 of 40 CFR part 60, appendix A–8 or its alternative, ASTM D6784–02 (Reapproved 2008) (incorporated by reference, see §63.14), over the period of the initial performance test, do not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which Hg emissions did not exceed 8.0 E–05 kg/Mg (1.6 E–04 lb/ton) of first-fire glaze sprayed (dry weight basis).
16. New or reconstructed sanitaryware manual glaze application.	a. PM emissions must not exceed 2.0 kg/Mg (3.9 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 2.0 kg/Mg (3.9 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 2.0 kg/Mg (3.9 lb/ton) of first-fire glaze sprayed (dry weight basis).
17. New or reconstructed sanitaryware spray machine glaze application.	a. PM emissions must not exceed 1.6 kg/Mg (3.2 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 1.6 kg/Mg (3.2 lb/ton) of first-fire glaze sprayed (dry weight basis); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 1.6 kg/Mg (3.2 lb/ton) of first-fire glaze sprayed (dry weight basis).
18. New or reconstructed sanitaryware robot glaze application.	a. PM emissions must not exceed 1.2 kg/Mg (2.3 lb/ton) of first-fire glaze sprayed (dry weight basis).	i. The PM emissions measured using Method 5 of 40 CFR part 60, appendix A–3, over the period of the initial performance test, according to the calculations in §63.8595(f)(2), do not exceed 1.2 kg/Mg (2.3 lb/ton) of first-fire glaze sprayed (dry weight basis); and

TABLE 6 TO SUBPART KKKKK OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8605, you must demonstrate initial compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You have demonstrated initial compliance if . . .
		ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which PM emissions did not exceed 1.2 kg/Mg (2.3 lb/ton) of first-fire glaze sprayed (dry weight basis).
19. New or reconstructed floor tile spray dryer.	a. Dioxin/furan emissions must not exceed 0.071 ng/kg of throughput processed.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.071 ng/kg of throughput processed; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.071 ng/kg of throughput processed.
20. New or reconstructed wall tile spray dryer.	a. Dioxin/furan emissions must not exceed 0.058 ng/kg of throughput processed.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.058 ng/kg of throughput processed; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.058 ng/kg of throughput processed.
21. New or reconstructed floor tile press dryer.	a. Dioxin/furan emissions must not exceed 0.024 ng/kg of throughput processed.	i. The dioxin/furan emissions measured using Method 23 of 40 CFR part 60, appendix A–7, over the period of the initial performance test, do not exceed 0.024 ng/kg of throughput processed; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the period of the initial performance test during which dioxin/furan emissions did not exceed 0.024 ng/kg of throughput processed.
22. Existing, new, or reconstructed sanitaryware shuttle kiln.	a. Minimize HAP emissions	i. Use natural gas, or equivalent, as the kiln fuel; and ii. Develop a designed firing time and temperature cycle for the sanitaryware shuttle kiln. You must either program the time and temperature cycle into your kiln or track each step on a log sheet; and iii. Label each sanitaryware shuttle kiln with the maximum load (in tons) of greenware that can be fired in the kiln during a single firing cycle; and iv. Develop maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices, controls that regulate air-to-fuel ratios, and controls that regulate firing cycles.

[84 FR 58614, Nov. 1, 2019]

TABLE 7 TO SUBPART KKKKK OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

TABLE 7 TO SUBPART KKKKK OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS

As stated in §63.8620, you must demonstrate continuous compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .	Or by . . .
1. Tunnel or roller kiln equipped with a DIFF or DLS/FF.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 1 of Table 2 to this subpart for kilns equipped with DIFF or DLS/FF.	i. If you use a bag leak detection system, as prescribed in §63.8450(e), initiating corrective action within 1 hour of a bag leak detection system alarm and completing corrective actions in accordance with your OM&M plan; operating and maintaining the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period; in calculating this operating time fraction, if inspection of the fabric filter demonstrates that no corrective action is required, no alarm time is counted; if corrective action is required, each alarm is counted as a minimum of 1 hour; if you take longer than 1 hour to initiate corrective action, the alarm time is counted as the actual amount of time taken by you to initiate corrective action; and ii. Verifying that lime is free-flowing via a load cell, carrier gas/lime flow indicator, carrier gas pressure drop measurement system, or other system; recording all monitor or sensor output, and if lime is found not to be free flowing, promptly initiating and completing corrective actions in accordance with your OM&M plan; recording the feeder setting once each shift of operation to verify that the feeder setting is being maintained at or above the level established during the HF/HCl performance test in which compliance was demonstrated.	(1) Performing VE observations of the DIFF or DLS/FF stack at the frequency specified in §63.8620(e) using Method 22 of 40 CFR part 60, appendix A–7; and maintaining no VE from the DIFF or DLS/FF stack; or (2) Maintaining your kiln operating temperature within the range of acceptable temperatures (*i.e.,* temperature profile for each kiln and product; for any incidence where the kiln is operating outside of its acceptable temperature range (*i.e.,* exceeds its temperature profile) for the product being fired, performing VE observations of the DIFF or DLS/FF stack as specified in §63.8620(e) using Method 22 of 40 CFR part 60, appendix A–7; and observing no VE from the DIFF or DLS/FF stack.
2. Tunnel or roller kiln equipped with a WS.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 2 of Table 2 to this subpart for kilns equipped with WS.	i. Collecting the scrubber liquid pH data according to §63.8600(a); reducing the scrubber liquid pH data to 3-hour block averages according to §63.8600(a); maintaining the average scrubber liquid pH for each 3-hour block period at or above the average scrubber liquid pH established during the HF/HCl performance test in which compliance was demonstrated; and ii. Collecting the scrubber liquid flow rate data according to §63.8600(a); reducing the scrubber liquid flow rate data to 3-hour block averages according to §63.8600(a); maintaining the average scrubber liquid flow rate for each 3-hour block period at or above the highest average scrubber liquid flow rate established during the HF/HCl and PM performance tests in which compliance was demonstrated.	

TABLE 7 TO SUBPART KKKKK OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8620, you must demonstrate continuous compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .	Or by . . .
3. Tunnel or roller kiln equipped with an ACI system.	Each emission limit in Table 1 to this subpart and each operating limit in Item 3 of Table 2 to this subpart for kilns equipped with ACI system.	Collecting the carbon flow rate data according to §63.8600(a); reducing the carbon flow rate data to 3-hour block averages according to §63.8600(a); maintaining the average carbon flow rate for each 3-hour block period at or above the highest average carbon flow rate established during the Hg and dioxin/furan performance tests in which compliance was demonstrated.	
4. Tunnel or roller kiln intending to comply with dioxin/furan emission limit without an ACI system.	Each emission limit in Table 1 to this subpart and each operating limit in Item 4 of Table 2 to this subpart for kilns intending to comply with dioxin/furan emission limit without an ACI system.	Collecting the operating temperature data according to §63.8600(a); and maintaining the operating temperature at or below the highest operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.	Collecting the operating temperature data according to §63.8600(a); reducing the operating temperature data to a 12-hour block average; and maintaining the average operating temperature for each 12-hour block period at or below the highest operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.
5. Tunnel or roller kiln with no add-on control.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 5 of Table 2 to this subpart for tunnel or roller kilns with no add-on control.	i. Performing VE observations of the stack at the frequency specified in §63.8620(e) using Method 22 of 40 CFR part 60, appendix A–7; and maintaining no VE from the stack; and	(1) Maintaining your kiln operating temperature within the range of acceptable temperatures (*i.e.,* temperature profile established for each kiln and product for any incidence where the kiln is operating outside of its acceptable temperature range (*i.e.,* exceeds its temperature profile) for the product being fired, performing VE observations of the DIFF or DLS/FF stack as specified in §63.8620(e) using Method 22 of 40 CFR part 60, appendix A–7; and observing no VE from the DIFF or DLS/FF stack.
		ii. If your last calculated total facility maximum potential HCl-equivalent was not at or below the health-based standard in Table 1 to this subpart, collecting the kiln process rate data according to §63.8600(a); reducing the kiln process rate data to 3-hour block averages according to §63.8600(a); maintaining the average kiln process rate for each 3-hour block period at or below the kiln process rate determined according to §63.8595(g)(1); and	
		iii. Collecting the operating temperature data according to §63.8600(a); and maintaining the operating temperature at or below the highest operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.	(1) Collecting the operating temperature data according to §63.8600(a); reducing the operating temperature data to a 12-hour block average; and maintaining the average operating temperature for each 12-hour block period at or below the highest operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.

TABLE 7 TO SUBPART KKKKK OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8620, you must demonstrate continuous compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .	Or by . . .
6. Glaze spray operation equipped with a FF.	Each emission limit in Table 1 to this subpart and each operating limit in Item 6 of Table 2 to this subpart for glaze spray operations equipped with a FF.	If you use a bag leak detection system, initiating corrective action within 1 hour of a bag leak detection system alarm and completing corrective actions in accordance with your OM&M plan; operating and maintaining the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period; in calculating this operating time fraction, if inspection of the fabric filter demonstrates that no corrective action is required, no alarm time is counted; if corrective action is required, each alarm is counted as a minimum of 1 hour; if you take longer than 1 hour to initiate corrective action, the alarm time is counted as the actual amount of time taken by you to initiate corrective action.	Performing VE observations of the FF stack at the frequency specified in §63.8620(e) using Method 22 of 40 CFR part 60, appendix A–7; and maintaining no VE from the FF stack.
7. Glaze spray operation equipped with a WS.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 7 of Table 2 to this subpart for kilns equipped with WS.	i. Collecting the scrubber pressure drop data according to §63.8600(a); reducing the scrubber pressure drop data to 3-hour block averages according to §63.8600(a); maintaining the average scrubber pressure drop for each 3-hour block period at or above the average pressure drop established during the PM performance test in which compliance was demonstrated; and ii. Collecting the scrubber liquid flow rate data according to §63.8600(a); reducing the scrubber liquid flow rate data to 3-hour block averages according to §63.8600(a); maintaining the average scrubber liquid flow rate for each 3-hour block period at or above the average scrubber liquid flow rate established during the PM performance test in which compliance was demonstrated.	
8. Glaze spray operation equipped with a water curtain.	a. Each emission limit in Table 1 to this subpart and each operating limit in Item 8 of Table 2 to this subpart for kilns equipped with a water curtain.	i. Conducting daily inspections to verify the presence of water flow to the wet control system; and ii. Conducting annual inspections of the interior of the control equipment (if applicable) to determine the structural integrity and condition of the control equipment; and iii. Recording as deviations any observations of particulates or other impurities getting into the glaze that has been sprayed onto a piece of ware and completing corrective actions in accordance with your OM&M plan.	

TABLE 7 TO SUBPART KKKKK OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS AND WORK PRACTICE STANDARDS—Continued

As stated in §63.8620, you must demonstrate continuous compliance with each emission limitation and work practice standard that applies to you according to the following table:

For each . . .	For the following . . .	You must demonstrate continuous compliance by . . .	Or by . . .
9. Glaze spray operation equipped with baffles.	Each emission limit in Table 1 to this subpart and each operating limit in Item 9 of Table 2 to this subpart for kilns equipped with baffles.	Conducting an annual visual inspection of the baffles to confirm the baffles are in place.	
10. Spray dryer	Each emission limit in Table 1 to this subpart and each operating limit in Item 10 of Table 2 to this subpart for spray dryers.	Collecting the operating temperature data according to §63.8600(a); reducing the operating temperature data to 4-hour block averages according to §63.8600(a); maintaining the average operating temperature for each 4-hour block period at or above the average operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.	
11. Floor tile press dryer.	Each emission limit in Table 1 to this subpart and each operating limit in Item 11 of Table 2 to this subpart for floor tile press dryers.	Collecting the operating temperature data according to §63.8600(a); reducing the operating temperature data to 4-hour block averages according to §63.8600(a); maintaining the average operating temperature for each 4-hour block period at or below the average operating temperature established during the dioxin/furan performance test in which compliance was demonstrated.	
12. Sanitaryware shuttle kiln.	a. Minimize HAP emissions.	i. Maintaining records documenting your use of natural gas, or an equivalent fuel, as the kiln fuel at all times except during periods of natural gas curtailment or supply interruption; and ii. If you intend to use an alternative fuel, submitting a notification of alternative fuel use within 48 hours of the declaration of a period of natural gas curtailment or supply interruption, as defined in §63.8665; and. iii. Submitting a report of alternative fuel use within 10 working days after terminating the use of the alternative fuel, as specified in §63.8635(g); and iv. Using a designed firing time and temperature cycle for each sanitaryware shuttle kiln; and v. For each firing load, documenting the total tonnage of greenware placed in the kiln to ensure that it is not greater than the maximum load identified in Item 1.a.iii of Table 3 to this subpart; and vi. Following maintenance procedures for each kiln that, at a minimum, specify the frequency of inspection and maintenance of temperature monitoring devices, controls that regulate air-to-fuel ratios, and controls that regulate firing cycles; and vii. Developing and maintaining records for each sanitaryware shuttle kiln, as specified in §63.8640.	

[84 FR 58619, Nov. 1, 2019]

TABLE 8 TO SUBPART KKKKK OF PART 63—COMPLIANCE DATES

As stated in §63.8545, you must meet each compliance date in the following table that applies to you:

If you have a(n) . . .	Then you must . . .	No later than . . .
1. New or reconstructed affected source and the initial startup of your affected source is after December 18, 2014, but before December 28, 2015.	Comply with the applicable emission limitations and work practice standards in Tables 1, 2, and 3 to this subpart.	December 28, 2015.
2. New or reconstructed affected source and the initial startup of your affected source is after December 28, 2015.	Comply with the applicable emission limitations and work practice standards in Tables 1, 2, and 3 to this subpart.	Initial startup of your affected source.
3. Existing affected source	Comply with the applicable emission limitations and work practice standards in Tables 1, 2, and 3 to this subpart.	December 26, 2018.
4. Existing area source that increases its emissions or its potential to emit such that it becomes a major source of HAP by adding a new affected source or by reconstructing.	Be in compliance with this subpart	Initial startup of your affected source as a major source.
5. New area source (*i.e.,* an area source for which construction or reconstruction commenced after December 18, 2014) that increases its emissions or its potential to emit such that it becomes a major source of HAP.	Be in compliance with this subpart	Initial startup of your affected source as a major source.

TABLE 9 TO SUBPART KKKKK OF PART 63—DEADLINES FOR SUBMITTING NOTIFICATIONS

As stated in §63.8630, you must submit each notification that applies to you according to the following table:

If you . . .	You must . . .	No later than . . .	As specified in . . .
1. Start up your affected source before December 28, 2015.	Submit an Initial Notification ..	June 22, 2016, or no later than 120 days after the source becomes subject to this subpart, whichever is later.	§63.9(b)(2).
2. Start up your new or reconstructed affected source on or after December 28, 2015.	Submit an Initial Notification ..	120 calendar days after you become subject to this subpart.	§63.9(b)(2).
3. Are required to conduct a performance test.	Submit a notification of intent to conduct a performance test.	60 calendar days before the performance test is scheduled to begin.	§63.7(b)(1).
4. Are required to conduct a compliance demonstration that includes a performance test according to the requirements in Table 4 to this subpart.	Submit a Notification of Compliance Status, including the performance test results.	60 calendar days following the completion of the performance test, by the close of business.	§63.9(h) and §63.10(d)(2).
5. Are required to conduct a compliance demonstration required in Table 6 to this subpart that does not include a performance test (*i.e.,* compliance demonstrations for the work practice standards).	Submit a Notification of Compliance Status.	30 calendar days following the completion of the compliance demonstrations, by the close of business.	§63.9(h).
6. Request to use the routine control device maintenance alternative standard according to §63.8570(d).	Submit your request	120 calendar days before the compliance date specified in §63.8545.	
7. Own or operate an affected kiln that is subject to the work practice standard specified in Item 1 of Table 3 to this subpart, and you intend to use a fuel other than natural gas or equivalent to fire the affected kiln.	Submit a notification of alternative fuel use.	48 hours following the declaration of a period of natural gas curtailment or supply interruption, as defined in §63.8665.	

[80 FR 65543, Oct. 26, 2015, as amended at 85 FR 73915, Nov. 19, 2020]

TABLE 10 TO SUBPART KKKKK OF PART 63—REQUIREMENTS FOR REPORTS

As stated in §63.8635, you must submit each report that applies to you according to the following table:

You must submit . . .	The report must contain . . .	You must submit the report . . .
1. A compliance report	a. If there are no deviations from any emission limitations or work practice standards that apply to you, a statement that there were no deviations from the emission limitations or work practice standards during the reporting period. If there were no periods during which the CMS was out-of-control as specified in your OM&M plan, a statement that there were no periods during which the CMS was out-of-control during the reporting period.	Semiannually according to the requirements in §63.8635(b).
	b. If you have a deviation from any emission limitation (emission limit, operating limit) during the reporting period, the report must contain the information in §63.8635(c)(8). If there were periods during which the CMS was out-of-control, as specified in your OM&M plan, the report must contain the information in §63.8635(d).	Semiannually according to the requirements in §63.8635(b).
2. A report of alternative fuel use	The information in §63.8635(g)	If you are subject to the work practice standards specified in Table 3 to this subpart, and you use an alternative fuel to fire an affected kiln, by letter within 10 working days after terminating the use of the alternative fuel.

TABLE 11 TO SUBPART KKKKK OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART KKKKK

As stated in §63.8655, you must comply with the General Provisions in §§63.1 through 63.16 that apply to you according to the following table:

Citation	Subject	Brief description	Applies to subpart KKKKK?
§63.1	Applicability	Initial applicability determination; applicability after standard established; permit requirements; extensions, notifications.	Yes.
§63.2	Definitions	Definitions for part 63 standards	Yes.
§63.3	Units and Abbreviations.	Units and abbreviations for part 63 standards.	Yes.
§63.4	Prohibited Activities	Compliance date; circumvention; severability.	Yes.
§63.5	Construction/Reconstruction.	Applicability; applications; approvals	Yes.
§63.6(a)	Applicability	General Provisions (GP) apply unless compliance extension; GP apply to area sources that become major.	Yes.
§63.6(b)(1)–(4)	Compliance Dates for New and Reconstructed sources.	Standards apply at effective date; 3 years after effective date; upon startup; 10 years after construction or reconstruction commences for section 112(f).	Yes.
§63.6(b)(5)	Notification	Must notify if commenced construction or reconstruction after proposal.	Yes.
§63.6(b)(6)	[Reserved].		
§63.6(b)(7)	Compliance Dates for New and Reconstructed Area Sources That Become Major.	Area sources that become major must comply with major source standards immediately upon becoming major, regardless of whether required to comply when they were area sources.	Yes.

Citation	Subject	Brief description	Applies to subpart KKKKK?
§63.6(c)(1)–(2)	Compliance Dates for Existing Sources.	Comply according to date in subpart, which must be no later than 3 years after effective date; for section 112(f) standards, comply within 90 days of effective date unless compliance extension.	Yes.
§63.6(c)(3)–(4)	[Reserved]		No.
§63.6(c)(5)	Compliance Dates for Existing Area Sources That Become Major.	Area sources that become major must comply with major source standards by date indicated in subpart or by equivalent time period (for example, 3 years).	Yes.
§63.6(d)	[Reserved]		No.
§63.6(e)(1)(i)	Operation & Maintenance.	General Duty to minimize emissions	No. See §63.8570(b) for general duty requirement.
§63.6(e)(1)(ii)	Operation & Maintenance.	Requirement to correct malfunctions ASAP.	No.
§63.6(e)(1)(iii)	Operation & Maintenance.	Operation and maintenance requirements enforceable independent of emissions limitations.	Yes.
§63.6(e)(2)	[Reserved]		No.
§63.6(e)(3)	Startup, Shutdown, and Malfunction Plan (SSMP).	Requirement for startup, shutdown, and malfunction (SSM) and SSMP; content of SSMP.	No.
§63.6(f)(1)	Compliance Except During SSM.	You must comply with emission standards at all times except during SSM.	No.
§63.6(f)(2)–(3)	Methods for Determining Compliance.	Compliance based on performance test, operation and maintenance plans, records, inspection.	Yes.
§63.6(g)	Alternative Standard	Procedures for getting an alternative standard.	Yes.
§63.6(h)	Opacity/VE Standards.	Requirements for opacity and VE standards.	No, not applicable.
§63.6(i)	Compliance Extension.	Procedures and criteria for Administrator to grant compliance extension.	Yes.
§63.6(j)	Presidential Compliance Exemption.	President may exempt source category	Yes.
§63.7(a)(1)–(2)	Performance Test Dates.	Dates for conducting initial performance testing and other compliance demonstrations for emission limits and work practice standards; must conduct 180 days after first subject to rule.	Yes.
§63.7(a)(3)	Section 114 Authority.	Administrator may require a performance test under CAA section 114 at any time.	Yes.
§63.7(a)(4)	Notification of Delay in Performance Testing Due To Force Majeure.	Must notify Administrator of delay in performance testing due to force majeure.	Yes.
§63.7(b)(1)	Notification of Performance Test.	Must notify Administrator 60 days before the test.	Yes.
§63.7(b)(2)	Notification of Rescheduling.	Must notify Administrator 5 days before scheduled date of rescheduled date.	Yes.
§63.7(c)	Quality Assurance (QA)/Test Plan.	Requirements; test plan approval procedures; performance audit requirements; internal and external QA procedures for testing.	Yes.
§63.7(d)	Testing Facilities	Requirements for testing facilities	Yes.
§63.7(e)(1)	Conditions for Conducting Performance Tests.	Performance tests must be conducted under representative conditions.	No, §63.8595 specifies requirements.
		Cannot conduct performance tests during SSM; not a violation to exceed standard during SSM.	Yes.
§63.7(e)(2)–(3)	Conditions for Conducting Performance Tests.	Must conduct according to subpart and EPA test methods unless Administrator approves alternative; must have at least three test runs of at least 1 hour each; compliance is based on arithmetic mean of three runs; conditions when data from an additional test run can be used.	Yes.
§63.7(e)(4)	Testing under Section 114.	Administrator's authority to require testing under section 114 of the Act.	Yes.

Citation	Subject	Brief description	Applies to subpart KKKKK?
§63.7(f)	Alternative Test Method.	Procedures by which Administrator can grant approval to use an alternative test method.	Yes.
§63.7(g)	Performance Test Data Analysis.	Must include raw data in performance test report; must submit performance test data 60 days after end of test with the notification of compliance status.	Yes.
§63.7(h)	Waiver of Tests	Procedures for Administrator to waive performance test.	Yes.
§63.8(a)(1)	Applicability of Monitoring Requirements.	Subject to all monitoring requirements in subpart.	Yes.
§63.8(a)(2)	Performance Specifications.	Performance Specifications in appendix B of 40 CFR part 60 apply.	Yes.
§63.8(a)(3)	[Reserved]		No.
§63.8(a)(4)	Monitoring with Flares.	Requirements for flares in §63.11 apply	No, not applicable.
§63.8(b)(1)	Monitoring	Must conduct monitoring according to standard unless Administrator approves alternative.	Yes.
§63.8(b)(2)–(3)	Multiple Effluents and Multiple Monitoring Systems.	Specific requirements for installing and reporting on monitoring systems.	Yes.
§63.8(c)(1)	Monitoring System Operation and Maintenance.	Maintenance consistent with good air pollution control practices.	Yes.
§63.8(c)(1)(i)	Routine and Predictable SSM.	Reporting requirements for SSM when action is described in SSMP.	No.
§63.8(c)(1)(ii)	SSM not in SSMP	Reporting requirements for SSM when action is not described in SSMP.	Yes.
§63.8(c)(1)(iii)	Compliance with Operation and Maintenance Requirements.	How Administrator determines if source complying with operation and maintenance requirements.	No.
§63.8(c)(2)–(3)	Monitoring System Installation.	Must install to get representative emission and parameter measurements.	Yes.
§63.8(c)(4)	CMS Requirements	Requirements for CMS	No, §63.8600 specifies requirements.
§63.8(c)(5)	Continuous Opacity Monitoring System (COMS) Minimum Procedures.	COMS minimum procedures	No, not applicable.
§63.8(c)(6)	CMS Requirements	Zero and high level calibration check requirements.	Yes.
§63.8(c)(7)–(8)	CMS Requirements	Out-of-control periods	Yes.
§63.8(d)(1) and (2)	CMS Quality Control	Requirements for CMS quality control	Yes.
§63.8(d)(3)	CMS Quality Control	Written procedures for CMS	No, §63.8575(b)(9) specifies requirements.
§63.8(e)	CMS Performance Evaluation.	Requirements for CMS performance evaluation.	Yes.
§63.8(f)(1)–(5)	Alternative Monitoring Method.	Procedures for Administrator to approve alternative monitoring.	Yes.
§63.8(f)(6)	Alternative to Relative Accuracy Test.	Procedures for Administrator to approve alternative relative accuracy test for continuous emission monitoring systems (CEMS).	No, not applicable.
§63.8(g)	Data Reduction	COMS and CEMS data reduction requirements.	No, not applicable.
§63.9(a)	Notification Requirements.	Applicability; State delegation	Yes.
§63.9(b)	Initial Notifications	Requirements for initial notifications	Yes.
§63.9(c)	Request for Compliance Extension.	Can request if cannot comply by date or if installed BACT/LAER.	Yes.
§63.9(d)	Notification of Special Compliance Requirements for New Source.	For sources that commence construction between proposal and promulgation and want to comply 3 years after effective date.	Yes.
§63.9(e)	Notification of Performance Test.	Notify Administrator 60 days prior	Yes.
§63.9(f)	Notification of VE/Opacity Test.	Notify Administrator 30 days prior	No, not applicable.
§63.9(g)(1)	Additional Notifications When Using CMS.	Notification of performance evaluation	Yes.

Citation	Subject	Brief description	Applies to subpart KKKKK?
§63.9(g)(2)–(3)	Additional Notifications When Using CMS.	Notification of COMS data use; notification that relative accuracy alternative criterion were exceeded.	No, not applicable.
§63.9(h)	Notification of Compliance Status.	Contents; submittal requirements	Yes.
§63.9(i)	Adjustment of Submittal Deadlines.	Procedures for Administrator to approve change in when notifications must be submitted.	Yes.
§63.9(j)	Change in Previous Information.	Must submit within 15 days after the change.	Yes.
§63.9(k)	Electronic reporting procedures.	Electronic reporting procedures for notifications per §63.9(j).	Yes.
§63.10(a)	Recordkeeping/Reporting.	Applicability; general information	Yes.
§63.10(b)(1)	General Recordkeeping Requirements.	General requirements	Yes.
§63.10(b)(2)(i)	Records Related to SSM.	Recordkeeping of occurrence and duration of startups and shutdowns.	No.
§63.10(b)(2)(ii)	Records Related to SSM.	Recordkeeping of failures to meet a standard.	No. See §63.8640(c)(2) for recordkeeping of (1) date, time and duration; (2) listing of affected source or equipment, and an estimate of the volume of each regulated pollutant emitted over the standard; and (3) actions to minimize emissions and correct the failure.
§63.10(b)(2)(iii)	Records Related to SSM.	Maintenance records	Yes.
§63.10(b)(2)(iv)–(v)	Records Related to SSM.	Actions taken to minimize emissions during SSM.	No.
§63.10(b)(2)(vi)–(xii) and (xiv).	CMS Records	Records when CMS is malfunctioning, inoperative or out-of-control.	Yes.
§63.10(b)(2)(xiii)	Records	Records when using alternative to relative accuracy test.	No, not applicable.
§63.10(b)(3)	Records	Applicability Determinations	Yes.
§63.10(c)(1)–(15)	Records	Additional records for CMS	No, §§63.8575 and 63.8640 specify requirements.
§63.10(d)(1) and (2)	General Reporting Requirements.	Requirements for reporting; performance test results reporting.	Yes.
§63.10(d)(3)	Reporting Opacity or VE Observations.	Requirements for reporting opacity and VE.	No, not applicable.
§63.10(d)(4)	Progress Reports	Must submit progress reports on schedule if under compliance extension.	Yes.
§63.10(d)(5)	SSM Reports	Contents and submission	No. See §63.8635(c)(8) for malfunction reporting requirements.
§63.10(e)(1)–(3)	Additional CMS Reports.	Requirements for CMS reporting	No, §§63.8575 and 63.8635 specify requirements.
§63.10(e)(4)	Reporting COMS data.	Requirements for reporting COMS data with performance test data.	No, not applicable.
§63.10(f)	Waiver for Recordkeeping/Reporting.	Procedures for Administrator to waive	Yes.
§63.11	Flares	Requirement for flares	No, not applicable.
§63.12	Delegation	State authority to enforce standards	Yes.
§63.13	Addresses	Addresses for reports, notifications, requests.	Yes.
§63.14	Incorporation by Reference.	Materials incorporated by reference	Yes.
§63.15	Availability of Information.	Information availability; confidential information.	Yes.
§63.16	Performance Track Provisions.	Requirements for Performance Track member facilities.	Yes.

[80 FR 65543, Oct. 26, 2015, as amended at 85 FR 73915, Nov. 19, 2020]

Subpart LLLLL—National Emission Standards for Hazardous Air Pollutants: Asphalt Processing and Asphalt Roofing Manufacturing

SOURCE: 68 FR 24577, May 7, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.8680 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) for existing and new asphalt processing and asphalt roofing manufacturing facilities. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations.

§ 63.8681 Am I subject to this subpart?

(a) You are subject to this subpart if you own or operate an asphalt processing facility or an asphalt roofing manufacturing facility, as defined in § 63.8698, that is a major source as defined in § 63.2, or is located at, or is part of a major source as defined in § 63.2.

(b) After the applicable compliance date specified in § 63.8683, blowing stills, asphalt storage tanks, saturators, wet loopers, and coaters subject to the provisions of this subpart that are also subject to 40 CFR part 60, subpart UU, are required to comply only with provisions of this subpart.

(c) This subpart does not apply to any equipment that is subject to subpart CC of this part or to subpart K, Ka, or Kb of 40 CFR part 60.

(d) This subpart does not apply to asphalt processing and asphalt roofing manufacturing equipment used for research and development, as defined in § 63.8698.

(e) The provisions of subpart J of 40 CFR part 60 do not apply to emissions from asphalt processing facilities subject to this subpart.

(f) [Reserved]

[68 FR 24577, May 7, 2003, as amended at 70 FR 28364, May 17, 2005; 85 FR 14548, Mar. 12, 2020]

§ 63.8682 What parts of my plant does this subpart cover?

(a) This subpart applies to each new, reconstructed, or existing affected source at asphalt processing and asphalt roofing manufacturing facilities.

(b) The affected source is:

(1) Each asphalt processing facility as defined in § 63.8698; or

(2) Each asphalt roofing manufacturing line as defined in § 63.8698.

(i) If the asphalt roofing manufacturing line is collocated with an asphalt processing facility, the storage tanks that store asphalt flux intended for oxidation in the blowing stills and those tanks that receive asphalt directly from the on-site blowing stills are part of the asphalt processing facility. The remaining asphalt storage tanks are considered to be part of the asphalt roofing facility.

(ii) If an asphalt storage tank is shared by two or more lines at an asphalt roofing manufacturing facility, the shared storage tank is considered part of the line to which the tank supplies the greatest amount of asphalt, on an annual basis.

(iii) If a sealant or adhesive applicator is shared by two or more asphalt roofing manufacturing lines, the shared applicator is considered part of the line that provides the greatest throughput to the applicator, on an annual basis.

(c) An affected source is a new affected source if you commenced construction of the affected source after November 21, 2001, and you met the applicability criteria at the time you commenced construction.

(d) An affected source is reconstructed if you meet the criteria in the reconstruction definition in § 63.2.

(e) An affected source is existing if it is not new or reconstructed.

§ 63.8683 When must I comply with this subpart?

(a) If you have a new or reconstructed affected source and start up:

(1) On or before April 29, 2003, then you must comply with the requirements for new and reconstructed

sources in this subpart no later than April 29, 2003.

(2) After April 29, 2003, then you must comply with the requirements for new and reconstructed sources in this subpart upon startup.

(b) If you have an existing affected source, you must comply with the requirements for existing sources no later than May 1, 2006.

(c) If you have an area source that increases its emissions or its potential to emit such that it becomes a (or part of a) major source as defined in § 63.2, then the following requirements apply:

(1) Any portion of the existing facility that becomes a new or reconstructed affected source must be in compliance with this subpart upon startup or by April 29, 2003, whichever is later.

(2) All other parts of the source to which this subpart applies must be in compliance with this subpart by 3 years after the date the source becomes a major source.

(d) You must meet the notification requirements in § 63.8692 according to the schedules in §§ 63.8692 and 63.9(a) through (f) and (h). Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14548, Mar. 12, 2020]

EMISSION LIMITATIONS

§ 63.8684 What emission limitations and operating limits must I meet?

(a) You must meet each emission limitation in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit in Table 2 to this subpart that applies to you.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14548, Mar. 12, 2020]

GENERAL COMPLIANCE REQUIREMENTS

§ 63.8685 What are my general requirements for complying with this subpart?

(a) Before September 9, 2020, you must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods of startup, shutdown, and malfunction. On and after September 9, 2020, you must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods of nonoperation of the affected source (or specific portion thereof) resulting in cessation of the emissions to which this subpart applies.

(b) Before September 9, 2020, you must always operate and maintain your affected source, including air pollution control and monitoring equipment, according to the provisions in § 63.6(e)(1)(i). On and after September 9, 2020, at all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator that may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the affected source.

(c) Before September 9, 2020, you must develop a written startup, shutdown, and malfunction plan (SSMP) according to the provisions in § 63.6(e)(3). On and after September 9, 2020, a startup, shutdown, and malfunction plan is not required.

(d) You must develop and implement a written site-specific monitoring plan according to the provisions in § 63.8688(g) and (h).

[68 FR 24577, May 7, 2003, as amended at 71 FR 20469, Apr. 20, 2006; 85 FR 14549, Mar. 12, 2020]

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.8686 By what date must I conduct initial performance tests or other initial compliance demonstrations?

(a) For existing affected sources, you must conduct initial performance tests

no later than 180 days after the compliance date that is specified for your source in § 63.8683 and according to the provisions in § 63.7(a)(2).

(b) As an alternative to the requirement specified in paragraph (a) of this section, you may use the results of a previously-conducted emission test to demonstrate compliance with the emission limitations in this subpart if you demonstrate to the Administrator's satisfaction that:

(1) No changes have been made to the process since the time of the emission test; and

(2) The operating conditions and test methods used during testing conform to the requirements of this subpart; and

(3) The control device and process parameter values established during the previously-conducted emission test are used to demonstrate continuous compliance with this subpart; and

(4) The previously-conducted emission test was completed within the last 60 months.

(c) For new sources, you must demonstrate initial compliance no later than 180 calendar days after April 29, 2003 or within 180 calendar days after startup of the source, whichever is later.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14549, Mar. 12, 2020]

§ 63.8687 What performance tests, design evaluations, and other procedures must I use?

(a) You must conduct each performance test in Table 3 to this subpart that applies to you.

(b) Each performance test must be conducted under normal operating conditions and under the conditions specified in Table 3 to this subpart. Operations during periods of startup, shutdown, or nonoperation do not constitute representative conditions for purposes of conducting a performance test. You may not conduct performance tests during periods of malfunction. You must record the process information that is necessary to document operating conditions during the test and explain why the conditions represent normal operation. Upon request, you must make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(c) [Reserved]

(d) Except for opacity and visible emission observations, you must conduct three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.

(e) You must use the following equations to determine compliance with the emission limitations.

(1) To determine compliance with the particulate matter mass emission rate, you must use Equations 1 and 2 of this section as follows:

$$E = M_{PM}/P \qquad \text{(Eq. 1)}$$

Where:

E = Particulate matter emission rate, kilograms of particulate matter per megagram of roofing product manufactured.

M_{PM} = Particulate matter mass emission rate, kilograms per hour, determined using Equation 2.

P = The asphalt roofing product manufacturing rate during the emissions sampling period, including any material trimmed from the final product, megagram per hour.

$$M_{PM} = C * Q * K \qquad \text{(Eq. 2)}$$

Where:

M_{PM} = Particulate matter mass emission rate, kilograms per hour.

C = Concentration of particulate matter on a dry basis, grams per dry standard cubic meter (g/dscm), as measured by the test method specified in Table 3 to this subpart.

Q = Vent gas stream flow rate (dry standard cubic meters per minute) at a temperature of 20 °C as measured by the test method specified in Table 3 to this subpart.

K = Unit conversion constant (0.06 minute-kilogram/hour-gram).

(2) To determine compliance with the total hydrocarbon percent reduction standard, you must use Equations 3 and 4 of this section as follows:

$$RE = \left[\left(M_{THCi} - M_{THCo}\right)/\left(M_{THCi}\right)\right] * (100) \qquad \text{(Eq. 3)}$$

Where:

RE = Emission reduction efficiency, percent.

M_{THCi} = Mass flow rate of total hydrocarbons entering the control device, kilograms per hour, determined using Equation 4.

M_{THCo} = Mass flow rate of total hydrocarbons exiting the control device, kilograms per hour, determined using Equation 4.

$$M_{THC} = C * Q * K \qquad \text{(Eq. 4)}$$

Where:

M_{THC} = Total hydrocarbon mass flow rate, kilograms per hour.

C = Concentration of total hydrocarbons on a dry basis, parts per million by volume (ppmv), as measured by the test method specified in Table 3 to this subpart.

Q = Vent gas stream flow rate (dscm/minute) at a temperature of 20 °C as measured by the test method specified in Table 3 to this subpart.

K = Unit conversion constant (1.10E–04 $(ppmv)^{-1}$ (kilogram/dscm)(minute/hour)).

(3) To determine compliance with the combustion efficiency standard, you must use Equation 5 of this section as follows:

$$CE = \left[1 - \left(CO/CO_2\right) - \left(THC/CO_2\right)\right] \qquad \text{(Eq. 5)}$$

Where:

CE = Combustion efficiency, percent.

CO = Carbon monoxide concentration at the combustion device outlet, parts per million by volume (dry), as measured by the test method specified in Table 3 to this subpart.

CO_2 = Carbon dioxide concentration at the combustion device outlet, parts per million by volume (dry), as measured by the test method specified in Table 3 to this subpart.

THC = Total hydrocarbon concentration at the combustion device outlet, parts per million by volume (dry), as measured by the test method specified in Table 3 to this subpart.

(4) To determine compliance with the total hydrocarbon destruction efficiency standard for a combustion device that does not use auxiliary fuel, you must use Equation 6 of this section as follows:

$$THC\ DE = \left[\left(CO + CO_2\right)/\left(CO + CO_2 + THC\right)\right] \qquad \text{(Eq. 6)}$$

Where:

THC DE = THC destruction efficiency, percent.

CO = Carbon monoxide concentration at the combustion device outlet, parts per million by volume (dry), as measured by the test method specified in Table 3 to this subpart.

CO_2 = Carbon dioxide concentration at the combustion device outlet, parts per million by volume (dry), as measured by the test method specified in Table 3 to this subpart.

THC = Total hydrocarbon concentration at the combustion device outlet, parts per million by volume (dry), as measured by the test method specified in Table 3 to this subpart.

[68 FR 24577, May 7, 2003, as amended at 70 FR 28364, May 17, 2005; 85 FR 14549, Mar. 12, 2020]

§63.8688 What are my monitoring installation, operation, and maintenance requirements?

(a) You must install, operate, and maintain each continuous parameter monitoring system (CPMS) according to the following:

(1) The CPMS must complete a minimum of one cycle of operation for each successive 15-minute period.

(2) To determine the 3-hour average, you must:

(i) Have a minimum of four successive cycles of operation to have a valid hour of data.

(ii) Have valid data from at least three of four equally spaced data values for that hour from a CPMS that is not out-of-control according to your site-specific monitoring plan.

(iii) Determine the 3-hour average of all recorded readings for each operating day, except as stated in §63.8690(c). You must have at least two of the three hourly averages for that period using only hourly average values that are based on valid data (*i.e.,* not from out-of-control periods).

(3) You must record the results of each inspection, calibration, and validation check.

(b) For each temperature monitoring device, you must meet the requirements in paragraph (a) of this section and the following:

(1) Locate the temperature sensor in a position that provides a representative temperature.

(2) For a noncryogenic temperature range, use a temperature sensor with a minimum measurement sensitivity of 2.8 °C or 1.0 percent of the temperature value, whichever is larger.

(3) If a chart recorder is used, it must have a sensitivity in the minor division of at least 20 °F.

(4) Perform an accuracy check at least semiannually or following an operating parameter deviation:

(i) According to the procedures in the manufacturer's documentation; or

(ii) By comparing the sensor output to redundant sensor output; or

(iii) By comparing the sensor output to the output from a calibrated temperature measurement device; or

(iv) By comparing the sensor output to the output from a temperature simulator.

(5) Conduct accuracy checks any time the sensor exceeds the manufacturer's specified maximum operating temperature range or install a new temperature sensor.

(6) At least quarterly or following an operating parameter deviation, perform visual inspections of components if redundant sensors are not used.

(c) For each pressure measurement device, you must meet the requirements of paragraph (a) of this section and the following:

(1) Locate the pressure sensor(s) in, or as close as possible, to a position that provides a representative measurement of the pressure.

(2) Use a gauge with a minimum measurement sensitivity of 0.12 kiloPascals or a transducer with a minimum measurement sensitivity of 5 percent of the pressure range.

(3) Check pressure tap pluggage daily. Perform an accuracy check at least quarterly or following an operating parameter deviation:

(i) According to the procedures in the manufacturer's documentation; or

(ii) By comparing the sensor output to redundant sensor output.

(4) Conduct calibration checks any time the sensor exceeds the manufacturer's specified maximum operating pressure range or install a new pressure sensor.

(5) At least monthly or following an operating parameter deviation, perform a leak check of all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(6) At least quarterly or following an operating parameter deviation, perform visible inspections on all components if redundant sensors are not used.

(d) For monitoring parameters other than temperature and pressure drop, you must install and operate a CPMS to provide representative measurements of the monitored parameters.

(e) For each flare, you must install a device (including but not limited to a thermocouple, an ultraviolet beam sensor, or an infrared sensor) capable of continuously detecting the presence of a pilot flame.

(f) As an option to installing the CPMS specified in paragraph (a) of this section, you may install a continuous emissions monitoring system (CEMS) or a continuous opacity monitoring system (COMS) that meets the applicable requirements in §63.8 according to Table 7 to this subpart and the applicable performance specifications of 40 CFR part 60, appendix B.

(g) For each monitoring system required in this section, you must develop and make available for inspection by the permitting authority, upon request, a site-specific monitoring plan that addresses the following:

(1) Installation of the CPMS, CEMS, or COMS sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last control device);

(2) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system; and

(3) Performance evaluation procedures and acceptance criteria (*e.g.*, calibrations).

(h) In your site-specific monitoring plan, you must also address the following:

(1) Ongoing operation and maintenance procedures in accordance with the general requirements of § 63.8(c)(1)(ii), (c)(3), (c)(4)(ii), and (c)(7) and (8);

(2) Ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d); and

(3) Ongoing recordkeeping and reporting procedures in accordance with §§ 63.8693 and 63.8694 and the general requirements of § 63.10(e)(1) and (e)(2)(i).

(i) You must conduct a performance evaluation of each CPMS, CEMS, or COMS in accordance with your site-specific monitoring plan.

(j) You must operate and maintain the CPMS, CEMS, or COMS in continuous operation according to the site-specific monitoring plan.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14549, Mar. 12, 2020]

§ 63.8689 How do I demonstrate initial compliance with the emission limitations?

(a) You must demonstrate initial compliance with each emission limitation that applies to you according to Table 4 to this subpart.

(b) Except as specified in paragraph (d) of this section, you must establish each site-specific operating limit in Table 2 to this subpart that applies to you according to the requirements in § 63.8687 and Table 3 to this subpart.

(c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8692(e).

(d) For control devices used to comply with the particulate matter standards in Table 1 to this subpart, you may establish any of the operating limits for pressure drop range (*i.e.*, a minimum and a maximum pressure drop) across the control device using manufacturers' specifications in lieu of complying with paragraph (b) of this section.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14549, Mar. 12, 2020]

Continuous Compliance Requirements

§ 63.8690 How do I monitor and collect data to demonstrate continuous compliance?

(a) You must monitor and collect data according to this section.

(b) Before September 9, 2020, except for monitor malfunctions, associated repairs, and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times that the affected source is operating including periods of startup, shutdown, and malfunction when the affected source is operating. On and after September 9, 2020, you must monitor and collect data at all times in accordance with § 63.8685(b), except during periods of nonoperation of the affected source (or specific portion thereof) resulting in cessation of the emissions to which this subpart applies.

(c) You may not use data recorded during monitoring malfunctions, associated repairs, and required quality assurance or control activities in data averages and calculations used to report emission or operating levels, nor may such data be used in fulfilling a minimum data availability requirement, if applicable. You must use all the data collected during all other periods in assessing the operation of the

control device and associated control system.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14549, Mar. 12, 2020]

§ 63.8691 How do I conduct periodic performance tests and demonstrate continuous compliance with the emission limitations and operating limits?

(a) You must demonstrate continuous compliance with each operating limit in Table 2 to this subpart that applies to you according to the procedures specified in Table 5 to this subpart, and you must conduct performance tests as specified in paragraph (e) of this section.

(b) Before September 9, 2020, you must report each instance in which you did not meet each operating limit in Table 5 to this subpart that applies to you. This includes periods of startup, shutdown, and malfunction. These instances are deviations from the emission limitations in this subpart. These deviations must be reported according to the requirements in § 63.8693. On and after September 9, 2020, you must report each instance in which you did not meet each operating limit in Table 5 to this subpart that applies to you, except during periods of nonoperation of the affected source (or specific portion thereof) resulting in cessation of the emissions to which this subpart applies.

(c) [Reserved]

(d) Before September 9, 2020, consistent with §§ 63.6(e) and 63.7(e)(1), deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with § 63.6(e)(1). The Administrator will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in § 63.6(e). On and after September 9, 2020, this paragraph (d) no longer applies.

(e) For each control device used to comply with the PM, THC, opacity, or visible emission standards of this subpart, you must conduct periodic performance tests using the applicable procedures specified in § 63.8687 and Table 4 to this subpart to demonstrate compliance with § 63.8684(a), and to confirm or reestablish the operating limits required by § 63.8684(b). You must conduct periodic performance tests according to the schedule specified in paragraphs (e)(1) through (3) of this section.

(1) Except as specified in paragraph (e)(3) of this section, for each existing affected source, and for each new and reconstructed affected source that commences construction or reconstruction after November 21, 2001 and on or before March 12, 2020, you must conduct the first periodic performance test on or before March 13, 2023. As an alternative to the first periodic performance test, you may use the results of a previously-conducted emission test to demonstrate compliance with the emission limitations in this subpart, such as tests for renewing your facility's operating permit under 40 CFR part 70 or 40 CFR part 71, if you demonstrate to the Administrator's satisfaction that it meets the requirements of § 63.8686(b)(1) through (4). The subsequent periodic performance tests must be conducted no later than 60 months thereafter following the previous performance test.

(2) Except as specified in paragraph (e)(3) of this section, for each new and reconstructed affected source that commences construction or reconstruction after March 12, 2020, you must conduct the first periodic performance test no later than 60 months following the initial performance test required by § 63.8689. If you used the alternative compliance option specified in § 63.8686(b) to comply with the initial performance test, then you must conduct the first periodic performance test no later than 60 months following the date you demonstrated to the Administrator that the requirements of § 63.8686(b) had been met.

(3) If an affected source is not operating on the dates the periodic performance test is required to be conducted as specified in paragraph (e)(1) or (2) of this section, then you are not required to restart the affected source for the sole purpose of complying with paragraph (e)(1) or (2) of this section. Instead, upon restart of the affected source, you must conduct the first periodic performance test within 60 days of achieving normal operating conditions but no later than 180 days

from startup. You must conduct subsequent periodic performance tests no later than 60 months thereafter following the previous performance test.

[68 FR 24577, May 7, 2003, as amended at 71 FR 20469, Apr. 20, 2006; 85 FR 14549, Mar. 12, 2020]

NOTIFICATIONS, REPORTS, AND RECORDS

§ 63.8692 What notifications must I submit and when?

(a) You must submit all the notifications in §§ 63.6(h)(4) and (5), 63.7(b) and (c), 63.8(f), and 63.9(b) through (f) and (h) that apply to you by the dates specified in these sections, except as provided in paragraphs (b) through (f) of this section.

(b) As specified in § 63.9(b)(2), if you start up your affected source before April 29, 2003, you must submit an Initial Notification not later than 120 calendar days after April 29, 2003, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) As specified in § 63.9(b)(3), if you start up your new or reconstructed affected source on or after April 29, 2003, you must submit an Initial Notification not later than 120 calendar days after you become subject to this subpart.

(d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin, as required in § 63.7(b)(1).

(e) If you are required to conduct a performance test, design evaluation, opacity observation, visible emission observation, or other compliance demonstration as specified in Table 3 or 4 to this subpart, you must submit a Notification of Compliance Status according to § 63.9(h)(2)(ii). You must submit the Notification of Compliance Status, including the performance test results, before the close of business on the 60th calendar day following the completion of the performance test according to § 63.10(d)(2). On and after September 9, 2020, you must submit all subsequent Notification of Compliance Status reports to EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through EPA's Central Data Exchange (CDX) (*https://cdx.epa.gov/*). If you claim some of the information required to be submitted via CEDRI is confidential business information (CBI), then submit a complete report, including information claimed to be CBI, to EPA. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to EPA via EPA's CDX as described earlier in this paragraph (e). You may assert a claim of EPA system outage or force majeure for failure to timely comply with the reporting requirement in this paragraph (e) provided you meet the requirements outlined in § 63.8693(h) or (i), as applicable.

(f) If you are using data from a previously-conducted emission test to serve as documentation of conformance with the emission standards and operating limits of this subpart as specified in § 63.8686(b), you must submit the test data in lieu of the initial performance test results with the Notification of Compliance Status required under paragraph (e) of this section.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14550, Mar. 12, 2020; 85 FR 73916, Nov. 19, 2020]

§ 63.8693 What reports must I submit and when?

(a) You must submit each report in Table 6 to this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report by the date in Table 6 to this subpart and according to the following dates:

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.8683 and ending on June 30 or December 31, whichever date is the first date following the end of the first calendar half after the compliance date that is specified for your source in § 63.8683.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date follows the end of the first calendar half after the compliance date that is specified for your affected source in § 63.8683.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date is the first date following the end of the semiannual reporting period.

(5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of the dates in paragraphs (b)(1) through (4) of this section.

(6) On and after September 9, 2020, you must submit all compliance reports to EPA via the CEDRI, which can be accessed through EPA's CDX (*https://cdx.epa.gov/*). You must use the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/compliance-and-emissions-data-reporting-interface-cedri*) for this subpart. The date report templates become available will be listed on the CEDRI website. The report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. If you claim some of the information required to be submitted via CEDRI is CBI, submit a complete report, including information claimed to be CBI, to EPA. The report must be generated using the appropriate form on the CEDRI website or an alternate electronic file consistent with the extensible markup language (XML) schema listed on the CEDRI website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to EPA via EPA's CDX as described earlier in this paragraph (b)(6). You may assert a claim of EPA system outage or force majeure for failure to timely comply with the reporting requirement in this paragraph (b)(6) provided you meet the requirements outlined in § 63.8693(h) or (i), as applicable.

(c) The compliance report must contain the following information:

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying the truth, accuracy, and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) Before September 9, 2020, if you had a startup, shutdown, or malfunction during the reporting period and you took actions consistent with your SSMP, the compliance report must include the information in § 63.10(d)(5)(i). On and after September 9, 2020, this paragraph (c)(4) no longer applies.

(5) For each reporting period, you must include in the compliance report the total number of deviations that occurred during the reporting period. If there are no deviations from any emission limitations (emission limit, operating limit, opacity limit, and visible emission limit) in § 63.8684 that apply to you, then you must include a statement that there were no deviations from the emission limitations during the reporting period.

(6) If there were no periods during which the CPMS, CEMS, or COMS was out-of-control as specified in § 63.8(c)(7), a statement that there were no periods during which the CPMS, CEMS, or COMS was out-of-control during the reporting period.

(d) For each deviation from an emission limitation (emission limit, operating limit, opacity limit, and visible emission limit) in § 63.8684, you must include in the compliance report the information in paragraphs (c)(1)

through (6) of this section, and the information in paragraphs (d)(1) through (13) of this section.

(1) The start date, start time, and duration of each malfunction.

(2) For each instance that the CPMS, CEMS, or COMS was inoperative, except for zero (low-level) and high-level checks, the start date, start time, and duration that the CPMS, CEMS, or COMS was inoperative; the cause (including unknown cause) for the CPMS, CEMS, or COMS being inoperative; and descriptions of corrective actions taken.

(3) For each instance that the CPMS, CEMS, or COMS was out-of-control as specified in §63.8(c)(7), the start date, start time, and duration that the CPMS, CEMS, or COMS was out-of-control, including the information in §63.8(c)(8).

(4) Before September 9, 2020, the start date, start time, and duration of the deviation, and whether each deviation occurred during a period of startup, shutdown, or malfunction or during another period. On and after September 9, 2020, the start date, start time, and duration of the deviation including a description of the deviation and the actions you took to minimize emissions in accordance with §63.8685(b). You must also include:

(i) A list of the affected sources or equipment for which the deviation occurred;

(ii) The cause of the deviation (including unknown cause, if applicable); and

(iii) Any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(5) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.

(6) Before September 9, 2020, a breakdown of the total duration of the deviations during the reporting period into those that are due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes. On and after September 9, 2020, a breakdown of the total duration of the deviations during the reporting period into those that are due to control equipment problems, process problems, other known causes, and other unknown causes.

(7) A summary of the total duration of CPMS, CEMS, or COMS downtime during the reporting period and the total duration of CPMS, CEMS, or COMS downtime as a percent of the total source operating time during that reporting period.

(8) An identification of each air pollutant that was monitored at the affected source.

(9) A brief description of the process units.

(10) A brief description of the CPMS, CEMS, or COMS.

(11) The date of the latest CPMS, CEMS, or COMS certification or audit.

(12) A description of any changes in CPMS, CEMS, or COMS, processes, or controls since the last reporting period.

(13) On and after September 9, 2020, for each deviation from an emission limitation in §63.8684, you must include an estimate of the quantity of each regulated pollutant emitted over any emission limitation in §63.8684, and a description of the method used to estimate the emissions.

(e) Each affected source that has obtained a title V operating permit pursuant to 40 CFR part 70 or 40 CFR part 71 must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If an affected source submits a compliance report pursuant to Table 6 to this subpart along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all required information concerning deviations from any emission limitation (including any operating limit), submission of the compliance report shall be deemed to satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report shall not otherwise affect any obligation the affected source may have to report deviations from permit requirements to the permit authority.

(f) On and after September 9, 2020, within 60 days after the date of completing each performance test required by this subpart, you must submit the results of the performance test following the procedures specified in paragraphs (f)(1) through (3) of this section.

(1) *Data collected using test methods supported by EPA's Electronic Reporting Tool (ERT) as listed on EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test to EPA via the CEDRI, which can be accessed through EPA's CDX (*https://cdx.epa.gov/*). The data must be submitted in a file format generated through the use of EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on EPA's ERT website.

(2) *Data collected using test methods that are not supported by EPA's ERT as listed on EPA's ERT website at the time of the test.* The results of the performance test must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on EPA's ERT website. Submit the ERT generated package or alternative file to EPA via CEDRI.

(3) *CBI.* If you claim some of the information submitted under paragraph (f)(1) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to EPA. The file must be generated through the use of EPA's ERT or an alternate electronic file consistent with the XML schema listed on EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to EPA via EPA's CDX as described in paragraph (f)(1) of this section.

(g) On and after September 9, 2020, within 60 days after the date of completing each continuous monitoring system (CMS) performance evaluation (as defined in §63.2) as specified in your site-specific monitoring plan, you must submit the results of the performance evaluation following the procedures specified in paragraphs (g)(1) through (3) of this section.

(1) *Performance evaluations of CMS measuring relative accuracy test audit (RATA) pollutants that are supported by EPA's ERT as listed on EPA's ERT website at the time of the evaluation.* Submit the results of the performance evaluation to EPA via CEDRI, which can be accessed through EPA's CDX. The data must be submitted in a file format generated through the use of EPA's ERT. Alternatively, you may submit an electronic file consistent with the XML schema listed on EPA's ERT website.

(2) *Performance evaluations of CMS measuring RATA pollutants that are not supported by EPA's ERT as listed on EPA's ERT website at the time of the evaluation.* The results of the performance evaluation must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on EPA's ERT website. Submit the ERT generated package or alternative file to EPA via CEDRI.

(3) *CBI.* If you claim some of the information submitted under paragraph (g)(1) of this section is CBI, you must submit a complete file, including information claimed to be CBI, to EPA. The file must be generated through the use of EPA's ERT or an alternate electronic file consistent with the XML schema listed on EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to EPA via EPA's CDX as described in paragraph (g)(1) of this section.

(h) If you are required to electronically submit a report through CEDRI in EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement in this section. To assert a claim of EPA system outage, you must meet the requirements outlined in

paragraphs (h)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning five business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(i) If you are required to electronically submit a report through CEDRI in EPA's CDX, you may assert a claim of force majeure for failure to timely comply with the reporting requirement in this section. To assert a claim of force majeure, you must meet the requirements outlined in paragraphs (i)(1) through (5) of this section.

(1) You may submit a claim if a force majeure event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For the purposes of this section, a force majeure event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (e.g., hurricanes, earthquakes, or floods), acts of war or terrorism, or equipment failure or safety hazard beyond the control of the affected facility (e.g., large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the force majeure event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the force majeure event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of force majeure and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the force majeure event occurs.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14550, Mar. 12, 2020]

§ 63.8694 What records must I keep?

(a) You must keep the following records:

(1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(2) Before September 9, 2020, the records in § 63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunction. On and after September 9, 2020, this paragraph (a)(2) no longer applies.

(3) Records of performance tests, performance evaluations, and opacity and visible emission observations as required in § 63.10(b)(2)(viii).

(b) You must keep the records in § 63.6(h)(6) for visible emission observations.

(c) You must keep the records required in Table 5 to this subpart to show continuous compliance with each operating limit that applies to you.

(d) Records of any shared equipment determinations as specified in § 63.8682(b).

(e) Any records required to be maintained by this part that are submitted electronically via EPA's CEDRI may be maintained in electronic format. This ability to maintain electronic copies does not affect the requirement for facilities to make records, data, and reports available upon request to a delegated air agency or EPA as part of an on-site compliance evaluation.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14552, Mar. 12, 2020]

§ 63.8695 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You can keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.8696 What parts of the General Provisions apply to me?

Table 7 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.15 apply to you.

§ 63.8697 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. Environmental Protection Agency (U.S. EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if implementation and enforcement of this subpart is delegated.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under 40 CFR part 63, subpart E, the following authorities are retained by the Administrator of U.S. EPA:

(1) Approval of alternatives to the requirements in §§ 63.8681, 63.8682, 63.8683, 63.8684, 63.8685, 63.8686, 63.8687, 63.8688, 63.8689, 63.8690, and 63.8691.

(2) Approval of major changes to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major changes to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major changes to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14552, Mar. 12, 2020]

§ 63.8698 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in 40 CFR 63.2, the General Provisions of this part, and in this section as follows:

Adhesive applicator means the equipment that uses open pan-type application (e.g., a roller partially submerged in an open pan of adhesive) to apply adhesive to roofing shingles for producing laminated or dimensional roofing shingles.

Asphalt flux means the organic residual material from distillation of crude oil that is generally used in asphalt roofing manufacturing and paving and non-paving asphalt products.

Asphalt loading rack means the equipment at an asphalt processing facility used to transfer oxidized asphalt from

a storage tank into a tank truck, rail car, or barge.

Asphalt processing facility means any facility engaged in the preparation of asphalt flux at stand-alone asphalt processing facilities, petroleum refineries, and asphalt roofing facilities. Asphalt preparation, called ''blowing,'' is the oxidation of asphalt flux, achieved by bubbling air through the heated asphalt, to raise the softening point and to reduce penetration of the oxidized asphalt. An asphalt processing facility includes one or more asphalt flux blowing stills, asphalt flux storage tanks storing asphalt flux intended for processing in the blowing stills, oxidized asphalt storage tanks, and oxidized asphalt loading racks.

Asphalt roofing manufacturing facility means a facility consisting of one or more asphalt roofing manufacturing lines.

Asphalt roofing manufacturing line means the collection of equipment used to manufacture asphalt roofing products through a series of sequential process steps. The equipment that comprises an asphalt roofing manufacturing line varies depending on the type of substrate used (*i.e.*, organic or inorganic) and the final product manufactured (*e.g.*, roll roofing, laminated shingles). For example, an asphalt roofing manufacturing line that uses fiberglass mat as a substrate typically would not include a saturator/wet looper (or the saturator/wet looper could be bypassed if the line manufacturers multiple types of products). An asphalt roofing manufacturing line can include a saturator (including wet looper), coater, coating mixers, sealant applicators, adhesive applicators, and asphalt storage and process tanks. The number of asphalt roofing manufacturing lines at a particular facility is determined by the number of saturators (or coaters) operated in parallel. For example, an asphalt roofing manufacturing facility with two saturators (or coaters) operating in parallel would be considered to have two separate roofing manufacturing lines.

Asphalt storage tank means any tank used to store asphalt flux, oxidized asphalt, and modified asphalt, at asphalt roofing manufacturing facilities, petroleum refineries, and asphalt processing facilities. Storage tanks containing cutback asphalts (asphalts diluted with solvents to reduce viscosity for low temperature applications) and emulsified asphalts (asphalts dispersed in water with an emulsifying agent) are not subject to this subpart.

Blowing still means the equipment in which air is blown through asphalt flux to change the softening point and penetration rate of the asphalt flux, creating oxidized asphalt.

Boiler means any enclosed combustion device that extracts useful energy in the form of steam and is not an incinerator.

Coater means the equipment used to apply amended (filled or modified) asphalt to the top and bottom of the substrate (typically fiberglass mat) used to manufacture shingles and rolled roofing products.

Coating mixer means the equipment used to mix coating asphalt and a mineral stabilizer, prior to applying the stabilized coating asphalt to the substrate.

Combustion device means an individual unit of equipment such as a flare, incinerator, process heater, or boiler used for the combustion of organic hazardous air pollutant vapors.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limitation (including any operating limit), or work practice standard;

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart, and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Before September 9, 2020, fails to meet any emission limitation (including any operating limit) or work practice standard in this subpart during startup, shutdown, or malfunction, regardless of whether or not such failure is permitted by this subpart. On and after September 9, 2020, this paragraph (3) no longer applies.

Emission limitation means any emission limit, opacity limit, operating limit, or visible emission limit.

Group 1 asphalt loading rack means an asphalt loading rack that loads asphalt with a maximum temperature of 260 °C (500 °F) or greater and has a maximum true vapor pressure of 10.4 kiloPascals (kPa) (1.5 pounds per square inch absolute (psia)) or greater.

Group 2 asphalt loading rack means an asphalt loading rack that is not a Group 1 asphalt loading rack.

Group 1 asphalt storage tank means an asphalt storage tank that meets both of the following criteria:

(1) Has a capacity of 177 cubic meters (47,000 gallons) of asphalt or greater; and

(2) Stores asphalt at a maximum temperature of 260 °C (500 °F) or greater and has a maximum true vapor pressure of 10.4 kPa (1.5 psia) or greater.

Group 2 asphalt storage tank means any asphalt storage tank with a capacity of 1.93 megagrams (Mg) of asphalt or greater that is not a Group 1 asphalt storage tank.

Incinerator means an enclosed combustion device that is used for destroying organic compounds. Auxiliary fuel may be used to heat waste gas to combustion temperatures. Any energy recovery section present is not physically formed into one manufactured or assembled unit with the combustion section; rather, the energy recovery section is a separate section following the combustion section and the two are joined by ducts or connections carrying flue gas.

Maximum true vapor pressure means the equilibrium partial pressure exerted by the stored asphalt at its maximum storage temperature.

Modified asphalt means asphalt that has been mixed with polymer modifiers.

Oxidized asphalt means asphalt that has been prepared by passing air through liquid asphalt flux in a blowing still.

Process heater means an enclosed combustion device that primarily transfers heat liberated by burning fuel directly to process streams or to heat transfer liquids other than water.

Research and development equipment means any equipment whose primary purpose is to conduct research and development to develop new processes and products, where such equipment is operated under the close supervision of technically trained personnel and is not engaged in the manufacture of products for commercial sale in commerce, except in a *de minimis* manner.

Responsible official means responsible official as defined in 40 CFR 70.2.

Saturator means the equipment in which substrate (predominantly organic felt) is filled with asphalt. Saturators are predominantly used for the manufacture of saturated felt products. The term saturator includes the saturator and wet looper.

Sealant applicator means the equipment that uses open pan-type application (e.g., a roller partially submerged in an open pan of sealant) to apply a sealant strip to a roofing product. The sealant strip is used to seal overlapping pieces of roofing product after they have been applied.

Work practice standard means any design, equipment, work practice, or operational standard, or combination thereof, that is promulgated pursuant to section 112(h) of the Clean Air Act.

[68 FR 24577, May 7, 2003, as amended at 70 FR 28364, May 17, 2005; 85 FR 14552, Mar. 12, 2020]

TABLE 1 TO SUBPART LLLLL OF PART 63—EMISSION LIMITATIONS

For—	You must meet the following emission limitation—
1. Each blowing still, Group 1 asphalt loading rack, and Group 1 asphalt storage tank at existing, new, and reconstructed asphalt processing facilities; and each Group 1 asphalt storage tank at existing, new, and reconstructed asphalt roofing manufacturing lines; and each coating mixer, saturator (including wet looper), coater, sealant applicator, and adhesive applicator at new and reconstructed asphalt roofing manufacturing lines.	a. Reduce total hydrocarbon mass emissions by 95 percent, or to a concentration of 20 ppmv, on a dry basis corrected to 3 percent oxygen; b. Route the emissions to a combustion device achieving a combustion efficiency of 99.5 percent; c. Route the emissions to a combustion device that does not use auxiliary fuel achieving a total hydrocarbon (THC) destruction efficiency of 95.8 percent; d. Route the emissions to a boiler or process heater with a design heat input capacity of 44 megawatts (MW) or greater;

For—	You must meet the following emission limitation—
	e. Introduce the emissions into the flame zone of a boiler or process heater; or f. Route emissions to a flare meeting the requirements of § 63.11(b).
2. The total emissions from the coating mixer, saturator (including wet looper), coater, sealant applicator, and adhesive applicator at each existing asphalt roofing manufacturing line. [a]	a. Limit particulate matter emissions to 0.04 kilograms emissions per megagram (kg/Mg) (0.08 pounds per ton, lb/ton) of asphalt shingle or mineral-surfaced roll roofing produced; or b. Limit particulate matter emissions to 0.4 kg/Mg (0.8 lb/ton) of saturated felt or smooth-surfaced roll roofing produced.
3. Each saturator (including wet looper) and coater at existing, new, and reconstructed asphalt roofing manufacturing lines. [a]	a. Limit exhaust gases to 20 percent opacity; and b. Limit visible emissions from the emission capture system to 20 percent of any period of consecutive valid observations totaling 60 minutes.
4. Each Group 2 asphalt storage tank at existing, new, and reconstructed asphalt processing facility and asphalt roofing manufacturing lines. [a]	Limit exhaust gases to 0 percent opacity. [b]

[a] As an alternative to meeting the particulate matter and opacity limits, these emission sources may comply with the THC percent reduction or combustion efficiency standards.

[b] The opacity limit can be exceeded for one consecutive 15-minute period in any 24-hour period when the storage tank transfer lines are being cleared. During this 15-minute period, the control device must not be bypassed. If the emissions from the asphalt storage tank are ducted to the saturator control device, the combined emissions from the saturator and storage tank must meet the 20 percent opacity limit (specified in 3.a of Table 1 to this subpart) during this 15-minute period. At any other time, the opacity limit applies to Group 2 asphalt storage tanks.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14553, Mar. 12, 2020]

TABLE 2 TO SUBPART LLLLL OF PART 63—OPERATING LIMITS

For—	You must [a]
1. Non-flare combustion devices with a design heat input capacity less than 44 MW or where the emissions are not introduced into the flame zone.	Maintain the 3-hour average [b] combustion zone temperature at or above the operating limit established during the performance test.
2. Flares	Meet the operating requirements specified in § 63.11(b).
3. Control devices used to comply with the particulate matter standards.	a. Maintain the 3-hour average [b] inlet gas temperature at or below the operating limit established during the performance test; and b. Maintain the 3-hour average [b] pressure drop across the device [c] within the operating range limits (*i.e.,* at or above a minimum pressure drop and at or below a maximum pressure drop) established during the performance test, or as an alternative, established according to the manufacturer's specifications as specified in § 63.8689(d).
4. Other control devices that are neither a combustion device nor a control device used to comply with the particulate matter emission standards.	Maintain the approved monitoring parameters within the operating limits established during the performance test.

[a] The operating limits specified in Table 2 to this subpart are applicable if you are monitoring control device operating parameters to demonstrate continuous compliance. If you are using a CEMS or COMS, you must maintain emissions below the value established during the initial performance test.

[b] A 15-minute averaging period can be used as an alternative to the 3-hour averaging period for this parameter.

[c] As an alternative to monitoring the pressure drop across the control device, owners or operators using an ESP to achieve compliance with the emission limits specified in Table 1 to this subpart can monitor the voltage to the ESP. If this option is selected, the ESP voltage must be maintained at or above the operating limit established during the performance test.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14553, Mar. 12, 2020]

TABLE 3 TO SUBPART LLLLL OF PART 63—REQUIREMENTS FOR PERFORMANCE TESTS [A] [B]

For—	You must—	Using—	According to the following requirements—
1. All particulate matter, total hydrocarbon, carbon monoxide, and carbon dioxide emission tests.	a. Select sampling port's location and the number of traverse points.	i. EPA test method 1 or 1A in appendix A to part 60 of this chapter.	A. For demonstrating compliance with the total hydrocarbon percent reduction standard, the sampling sites must be located at the inlet and outlet of the control device prior to any releases to the atmosphere.

For—	You must—	Using—	According to the following requirements—
			B. For demonstrating compliance with the particulate matter mass emission rate, THC destruction efficiency, THC outlet concentration, or combustion efficiency standards, the sampling sites must be located at the outlet of the control device prior to any releases to the atmosphere.
2. All particulate matter and total hydrocarbon tests.	Determine velocity and volumetric flow rate.	EPA test method 2, 2A, 2C, 2D, 2F, or 2G, as appropriate, in appendix A to part 60 of this chapter.	
3. All particulate matter and total hydrocarbon tests.	Determine the gas molecular weight used for flow rate determination.	EPA test method 3, 3A, 3B, as appropriate, in appendix A to part 60 of this chapter.	
4. All particulate matter, total hydrocarbon, carbon monoxide, and carbon dioxide emission tests.	Measure moisture content of the stack gas.	EPA test method 4 in appendix A to part 60 of this chapter.	
5. All particulate matter emission tests.	Measure the asphalt processing rate or the asphalt roofing manufacturing rate and the asphalt content of the product manufactured, as appropriate.		
6. Each control device used to comply with the particulate matter emission standards.	Measure the concentration of particulate matter.	EPA test method 5A in appendix A to part 60 of this chapter.	For demonstrating compliance with the particulate matter standard, the performance tests must be conducted under normal operating conditions and while manufacturing the roofing product that is expected to result in the greatest amount of hazardous air pollutant emissions.
7. All opacity tests	Conduct opacity observations.	EPA test method 9 in appendix A to part 60 of this chapter, or ASTM D7520–16[d f].	Conduct opacity observations for at least 3 hours and obtain 30, 6-minute averages.
8. All visible emission tests.	Conduct visible emission observations.	EPA test method 22 in appendix A to part 60 of this chapter.	Modify EPA test method 22 such that readings are recorded every 15 seconds for a period of consecutive observations totaling 60 minutes.
9. Each combustion device used to comply with the combustion efficiency or THC standards.	a. Measure the concentration of carbon dioxide. b. Measure the concentration of carbon monoxide. c. Measure the concentration of total hydrocarbons.	EPA test method 3A in appendix A to part 60 of this chapter. EPA test method 10 in appendix A to part 60 of this chapter. EPA test method 25A in appendix A to part 60 of this chapter.	
10. Each control device used to comply with the THC reduction efficiency or outlet concentration standards.	Measure the concentration of total hydrocarbons.	EPA test method 25A in appendix A to part 60 of this chapter.	
11. Each combustion device.	Establish a site-specific combustion zone temperature operating limit.	Data from the CPMS and the applicable performance test method(s).	You must collect combustion zone temperature data every 15 minutes during the entire period of the 3-hour performance test, and determine the average combustion zone temperature over the 3-hour performance test by computing the average of all of the 15-minute readings.

For—	You must—	Using—	According to the following requirements—
12. Each control device used to comply with the particulate matter emission standards.	Establish a site-specific inlet gas temperature operating limit; and if not complying with §63.8689(d), also establish site-specific limits for the pressure drop range (*i.e.,* a minimum and a maximum pressure drop) across the device[e].	Data from the CPMS and the applicable performance test method(s).	You must collect the inlet gas temperature and pressure drop[b] data every 15 minutes during the entire period of the 3-hour performance test, and determine the average inlet gas temperature and pressure drop[c] over the 3-hour performance test by computing the average of all of the 15-minute readings. The inlet gas temperature operating limit is set at +20 percent of the test run average inlet gas temperature measured in units of degrees Celsius or degrees Fahrenheit. The maximum (or minimum) pressure drop is set as the maximum (or minimum) average pressure drop of the performance test runs which demonstrated compliance with the applicable emission limit.
13. Each control device that is neither a combustion device nor a control device used to comply with the particulate matter emission standards.	Establish site-specific monitoring parameters.	Process data and data from the CPMS and the applicable performance test method(s).	You must collect monitoring parameter data every 15 minutes during the entire period of the 3-hour performance test, and determine the average monitoring parameter values over the 3-hour performance test by computing the average of all of the 15-minute readings.
14. Each flare used to comply with the THC percent reduction or PM emission limits.	Assure that the flare is operated and maintained in conformance with its design.	The requirements of §63.11(b).	

[a] For initial performance tests, as specified in §63.8686(b), you may request that data from a previously-conducted emission test serve as documentation of conformance with the emission standards and operating limits of this subpart.

[b] Performance tests are not required if: (1) The emissions are routed to a boiler or process heater with a design heat input capacity of 44 MW or greater; or (2) the emissions are introduced into the flame zone of a boiler or process heater.

[c] As an alternative to monitoring the pressure drop across the control device, owners or operators using an ESP to achieve compliance with the emission limits specified in Table 1 to this subpart can monitor the voltage to the ESP.

[d] If you use ASTM D7520–16 in lieu of EPA test method 9, then you must comply with the conditions specified in this footnote. During the digital camera opacity technique (DCOT) certification procedure outlined in Section 9.2 of ASTM D7520–16, you or the DCOT vendor must present the plumes in front of various backgrounds of color and contrast representing conditions anticipated during field use such as blue sky, trees, and mixed backgrounds (clouds and/or a sparse tree stand). You must also have standard operating procedures in place including daily or other frequency quality checks to ensure the equipment is within manufacturing specifications as outlined in Section 8.1 of ASTM D7520–16. You must follow the record keeping procedures outlined in §63.10(b)(1) for the DCOT certification, compliance report, data sheets, and all raw unaltered JPEGs used for opacity and certification determination. You or the DCOT vendor must have a minimum of four (4) independent technology users apply the software to determine the visible opacity of the 300 certification plumes. For each set of 25 plumes, the user may not exceed 15 percent opacity of any one reading and the average error must not exceed 7.5 percent opacity. This approval does not provide or imply a certification or validation of any vendor's hardware or software. The onus to maintain and verify the certification and/or training of the DCOT camera, software and operator in accordance with ASTM D7520–16 and this letter is on the facility, DCOT operator, and DCOT vendor.

[e] You may conduct two separate performance tests to establish the operating limits for pressure drop range (*i.e.,* one performance test to establish a minimum pressure drop operating limit and one performance test to establish a maximum pressure drop operating limit); however, you may choose to establish either, or both, the minimum and maximum pressure drop operating limits using the requirements of §63.8689(d) in lieu of the requirements specified in this Table.

[f] Incorporated by reference, see §63.14.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14553, Mar. 12, 2020]

TABLE 4 TO SUBPART LLLLL OF PART 63—INITIAL AND CONTINUOUS COMPLIANCE WITH EMISSION LIMITATIONS

For—	For the following emission limitation—	You have demonstrated initial compliance if—
1. Each blowing still, Group 1 asphalt loading rack, and Group 1 asphalt storage tank, at existing, new, and reconstructed asphalt processing facilities.	a. Reduce total hydrocarbon mass emissions by 95 percent or to a concentration of 20 ppmv, on a dry basis corrected to 3 percent oxygen.	i. The total hydrocarbon emissions, determined using the equations in §63.8687 and the test methods and procedures in Table 3 to this subpart, over the period of the performance test are reduced by at least 95 percent by weight or to a concentration of 20 ppmv, on a dry basis corrected to 3 percent oxygen; and ii. You have a record of the average control device operating parameters[a] over the performance test during which emissions were reduced according to 1.a.i. of this table.

For—	For the following emission limitation—	You have demonstrated initial compliance if—
	b. Route the emissions to a combustion device achieving a combustion efficiency of 99.5 percent.	i. The combustion efficiency of the combustion device, determined using the equations in §63.8687 and the test methods and procedures in Table 3 to this subpart, over the period of the performance test is at least 99.5 percent; and ii. You have a record of the average combustion zone temperature[a] and carbon monoxide, carbon dioxide, and total hydrocarbon outlet concentrations over the performance test during which the combustion efficiency was at least 99.5 percent.
	c. Route the emissions to a combustion device that does not use auxiliary fuel achieving a THC destruction efficiency of 95.8 percent.	i. The THC destruction efficiency of the combustion device, determined using the equations in §63.8687 and the test methods and procedures in Table 3 to this subpart, over the period of the performance test is at least 95.8 percent; and ii. You have a record of the average combustion zone temperature[a] and carbon monoxide, carbon dioxide, and total hydrocarbon outlet concentrations over the performance test during which the THC destruction efficiency was at least 95.8 percent.
	d. Route emissions to a boiler or process heater with a design heat input capacity of 44 MW or greater.	You have a record of the boiler or process heater design heat capacity.
	e. Introduce the emissions into the flame zone of a boiler or process heater.	You have a record that shows the emissions are being introduced into the boiler or process heater flame zone.
	f. Route emissions to a flare meeting the requirements of §63.11(b).	You have a record of the flare design and operating requirements.
2. Each coating mixer, saturator (including wet looper), coater, sealant applicator, adhesive applicator, and Group 1 asphalt storage tank at new and reconstructed asphalt roofing manufacturing lines.	a. Reduce total hydrocarbon mass emissions by 95 percent or to a concentration of 20 ppmv, on a dry basis corrected to 3 percent oxygen.	See 1.a.i. and ii. of this table.
	b. Route the emissions to a combustion device achieving a combustion efficiency of 99.5 percent.	See 1.b.i. and ii. of this table.
	c. Route the emissions to a combustion device that does not use auxiliary fuel achieving a THC destruction efficiency of 95.8 percent.	See 1.c.i. and ii. of this table.
	d. Route emissions to a boiler or process heater with a design heat input capacity of 44 MW or greater.	See 1.d. of this table.
	e. Introduce the emissions into the flame zone of a boiler or process heater.	See 1.e. of this table.
	f. Route emissions to a flare meeting the requirements of §63.11(b).	See 1.f. of this table.
3. The total emissions from the coating mixer, saturator (including wet looper), coater, sealant applicator, and adhesive applicator at each existing asphalt roofing manufacturing line.	a. Limit PM emissions to 0.04 kg/Mg (0.08 lb/ton) of asphalt shingle or mineral-surfaced roll roofing produced.	i. The PM emissions, determined using the equations in §63.8687 and the test methods and procedures in Table 3 to this subpart, over the period of the performance test are no greater than the applicable emission limitation; and ii. You have a record of the average control device[a] or process parameters over the performance test during which the particulate matter emissions were no greater than the applicable emission limitation.
	b. Limit PM emissions to 0.4 kg/Mg (0.8 lb/ton) of saturated felt or smooth-surfaced roll roofing produced.	See 3.a.i. and ii. of this table.

For—	For the following emission limitation—	You have demonstrated initial compliance if—
4. Each saturator (including wet looper) and coater at an existing, new, or reconstructed asphalt roofing manufacturing line.	a. Limit visible emissions from the emissions capture system to 20 percent of any period of consecutive valid observations totaling 60 minutes.	The visible emissions, measured using EPA test method 22 in appendix A to part 60 of this chapter, for any period of consecutive valid observations totaling 60 minutes do not exceed 20 percent.
	b. Limit opacity emissions to 20 percent.	The opacity, measured using EPA test method 9 in appendix A to part 60 of this chapter, for each of the first 30 6-minute averages does not exceed 20 percent.
5. Each Group 2 asphalt storage tank at existing, new, and reconstructed asphalt processing facilities and asphalt roofing manufacturing lines.	Limit exhaust gases to 0 percent opacity.	The opacity, measured using EPA test method 9 in appendix A to part 60 of this chapter, for each of the first 30 6-minute averages does not exceed 0 percent.

[a] If you use a CEMS or COMS to demonstrate compliance with the emission limits, you are not required to record control device operating parameters.

[68 FR 24577, May 7, 2003, as amended at 85 FR 14554, Mar. 12, 2020]

TABLE 5 TO SUBPART LLLLL OF PART 63—CONTINUOUS COMPLIANCE WITH OPERATING LIMITS [A]

For—	For the following operating limit—	You must demonstrate continuous compliance by—
1. Each non-flare combustion device. [b]	a. Maintain the 3-hour [c] average combustion zone temperature at or above the operating limit establishing during the performance test.	i. Passing the emissions through the control device; and ii. Collecting the combustion zone temperature data according to § 63.8688(b); and iii. Reducing combustion zone temperature data to 3-hour [c] averages according to calculations in Table 3 to this subpart; and iv. Maintaining the 3-hour [c] average combustion zone temperature within the level established during the performance test.
2. Each flare	Meet the operating requirements specified in § 63.11(b).	The flare pilot light must be present at all times and the flare must be operating at all times that emissions may be vented to it.
3. Control devices used to comply with the particulate matter emission standards.	a. Maintain the 3-hour [c] average inlet gas temperature at or below the operating limit established during the performance test; and.	i. Passing the emissions through the control device; and ii. Collecting the inlet gas temperature and pressure drop [d] data according to § 63.8688(b) and (c); and
	b. Maintain the 3-hour [c] average pressure drop across device [d] within the operating range limits that were established pursuant to § 63.8689(b) and/or (d).	iii. Reducing inlet gas temperature and pressure drop [d] data to 3-hour [c] averages according to calculations in Table 3 to this subpart; and iv. Maintaining the 3-hour [c] average inlet gas temperature within the level established during the performance test; and v. Maintaining the 3-hour [c] average pressure drop across device [d] within the level established pursuant to § 63.8689(b) and/or (d).
4. Other control devices that are neither a combustion device nor a control device used to comply with the particulate matter emission standards.	a. Maintain the monitoring parameters within the operating limits established during the performance test.	i. Passing the emissions through the devices; ii. Collecting the monitoring parameter data according to § 63.8688(d); and iii. Reducing the monitoring parameter data to 3-hour [c] averages according to calculations in Table 3 to this subpart; and iv. Maintaining the monitoring parameters within the level established during the performance test.

[a] The operating limits specified in Table 2 to this subpart and the requirements specified in Table 5 to this subpart are applicable if you are monitoring control device operating parameters to demonstrate continuous compliance. If you use a CEMS or COMS to demonstrate compliance with the emission limits, you are not required to record control device operating parameters. However, you must maintain emissions below the value established during the initial performance test. Data from the CEMS and COMS must be reduced as specified in §§ 63.8690 and 63.8(g)(1) through (4).

[b] Continuous parameter monitoring is not required if (1) the emissions are routed to a boiler or process heater with a with a design heat input capacity of 44 MW or greater; or (2) the emissions are introduced into the flame zone of a boiler or process heater.

[c] A 15-minute averaging period can be used as an alternative to the 3-hour averaging period for this parameter.

[d] As an alternative to monitoring the pressure drop across the control device, owners or operators using an ESP to achieve compliance with the emission limits specified in Table 1 to this subpart can monitor the voltage to the ESP. If this option is selected, the ESP voltage must be maintained at or above the operating limit established during the performance test.

[68 FR 24577, May 7, 2003, as amended at 70 FR 28365, May 17, 2005; 85 FR 14555, Mar. 12, 2020]

TABLE 6 TO SUBPART LLLLL OF PART 63—REQUIREMENTS FOR REPORTS

You must submit—	The report must contain—	You must submit the report—
1. An initial notification	The information in §63.9(b)	According to the requirements in §63.9(b).
2. A notification of performance test	A written notification of the intent to conduct a performance test.	At least 60 calendar days before the performance test is scheduled to begin, as required in §63.9(e).
3. A notification of opacity and visible emission observations.	A written notification of the intent to conduct opacity and visible emission observations.	According to the requirements in §63.9(f).
4. Notification of compliance status	The information in §63.9(h)(2) through (5), as applicable.	According to the requirements in §§63.8692(e) and 63.9(h)(2) through (5), as applicable.
5. A compliance report	a. A statement that there were no deviations from the emission limitations during the reporting period, if there are no deviations from any emission limitations (emission limit, operating limit, opacity limit, and visible emission limit) that apply to you.	Semiannually according to the requirements in §63.8693(b).
	b. If there were no periods during which the CPMS, CEMS, or COMS was out-of-control as specified in §63.8(c)(7), a statement that there were no periods during which the CPMS, CEMS, or COMS was out-of-control during the reporting period.	Semiannually according to the requirements in §63.8693(b).
	c. If you have a deviation from any emission limitation (emission limit, operating limit, opacity limit, and visible emission limit), the report must contain the information in §63.8693(c) and (d).	Semiannually according to the requirements in §63.8693(b).
	d. Before September 9, 2020, if you had a startup, shutdown or malfunction during the reporting period and you took actions consistent with your startup, shutdown, and malfunction plan, the compliance report must include the information in §63.10(d)(5)(i). On and after September 9, 2020, this paragraph no longer applies.	Semiannually according to the requirements in §63.8693(b).
6. An immediate startup, shutdown, and malfunction report if you have a startup, shutdown, or malfunction during the reporting period before September 9, 2020, and actions taken were not consistent with your startup, shutdown, and malfunction plan. On and after September 9, 2020, this paragraph no longer applies.	The information in §63.10(d)(5)(ii)	By fax or telephone within 2 working days after starting actions inconsistent with the plan followed by a letter within 7 working days after the end of the event unless you have made alternative arrangements with the permitting authority.
7. Performance test report	The information in §63.7	Within 60 days after completion of the performance test according to the requirements in §63.8693(f).

[68 FR 24577, May 7, 2003, as amended at 85 FR 14555, Mar. 12, 2020]

TABLE 7 TO SUBPART LLLLL OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART LLLLL

Citation	Subject	Brief description	Applies to subpart LLLLL
§63.1	Applicability	Initial Applicability Determination; Applicability After Standard Established; Permit Requirements; Extensions, Notifications.	Yes.
§63.2	Definitions	Definitions for part 63 standards	Yes.
§63.3	Units and Abbreviations	Units and abbreviations for part 63 standards.	Yes.
§63.4	Prohibited Activities	Prohibited Activities; Compliance date; Circumvention, Severability.	Yes.
§63.5	Construction/Reconstruction	Applicability; applications; approvals	Yes.

Citation	Subject	Brief description	Applies to subpart LLLLL
§63.6(a)	Applicability	GP apply unless compliance extension GP apply to area sources that become major.	Yes.
§63.6(b)(1)–(4)	Compliance Dates for New and Reconstructed sources.	Standards apply at effective date; 3 years after effective date; upon startup; 10 years after construction or reconstruction commences for section 112(f).	Yes.
§63.6(b)(5)	Notification	Must notify if commenced construction or reconstruction after proposal.	Yes.
§63.6(b)(6)	[Reserved].		
§63.6(b)(7)	Compliance Dates for New and Reconstructed Area Sources That Become Major.	Area sources that become major must comply with major source standards immediately upon becoming major, regardless of whether required to comply when they were an area source.	Yes.
§63.6(c)(1)–(2)	Compliance Dates for Existing Sources.	1. Comply according to date in subpart, which must be no later than 3 years after effective date. 2. For section 112(f) standards, comply within 90 days of effective date unless compliance extension has been granted.	Yes.
§63.6(c)(3)–(4)	[Reserved].		
§63.6(c)(5)	Compliance Dates for Existing Area Sources That Become Major.	Area sources that become major must comply with major source standards by date indicated in subpart or by equivalent time period (for example, 3 years).	Yes.
§63.6(d)	[Reserved].		
§63.6(e)(1)(i)	Operation & Maintenance	Operate to minimize emissions at all times.	Yes before September 9, 2020. No on and after September 9, 2020. See §63.8685(b) for general duty requirement.
§63.6(e)(1)(ii)	Operation & Maintenance	Correct malfunctions as soon as practicable.	Yes before September 9, 2020. No on and after September 9, 2020.
§63.6(e)(1)(iii)	Operation & Maintenance	Operation and maintenance requirements independently enforceable; information Administrator will use to determine if operation and maintenance requirements were met.	Yes.
§63.6(e)(2)	[Reserved].		
§63.6(e)(3)	Startup, Shutdown, and Malfunction (SSM) Plan (SSMP).	1. Requirement for SSM and startup, shutdown, malfunction plan. 2. Content of SSMP.	Yes before September 9, 2020. No on and after September 9, 2020.
§63.6(f)(1)	Compliance Except During SSM	You must comply with emission standards at all times except during SSM.	Yes before September 9, 2020. No on and after September 9, 2020.
§63.6(f)(2)–(3)	Methods for Determining Compliance	Compliance based on performance test, operation and maintenance plans, records, inspection.	Yes.
§63.6(g)(1)–(3)	Alternative Nonopacity Standard	Procedures for getting an alternative nonopacity standard.	Yes.
§63.6(h)	Opacity/Visible Emission (VE) Standards.	Requirements for opacity and VE limits.	Yes.
§63.6(h)(1)	Compliance with Opacity/VE Standards.	You must comply with opacity/VE emission limitations at all times except during SSM.	Yes before September 9, 2020. No on and after September 9, 2020.
§63.6(h)(2)(i)	Determining Compliance with Opacity/VE Standards.	If standard does not state test method, use EPA test method 9, 40 CFR 60, appendix A for opacity and EPA test method 22, 40 CFR 60, appendix A for VE.	No. The test methods for opacity and visible emissions are specified in §63.8687.
§63.6(h)(2)(ii)	[Reserved].		

Citation	Subject	Brief description	Applies to subpart LLLLL
§63.6(h)(2)(iii)	Using Previous Tests to Demonstrate Compliance with Opacity/VE Standards.	Criteria for when previous opacity/VE testing can be used to show compliance with this rule.	Yes.
§63.6(h)(3)	[Reserved].		
§63.6(h)(4)	Notification of Opacity/VE Observation Date.	Must notify Administrator of anticipated date of observation.	Yes.
§63.6(h)(5)(i), (iii)–(v)	Conducting Opacity/VE Observations	Dates and Schedule for conducting opacity/VE observations.	Yes.
§63.6(h)(5)(ii)	Opacity Test Duration and Averaging Times.	Must have at least 3 hours of observation with thirty 6-minute averages.	Yes.
§63.6(h)(6)	Records of Conditions During Opacity/VE Observations.	Must keep records available and allow Administrator to inspect.	Yes.
§63.6(h)(7)(i)	Report COMS Monitoring Data from Performance Test.	Must submit COMS data with other performance test data.	Yes, if COMS used.
§63.6(h)(7)(ii)	Using COMS instead of EPA test method 9, 40 CFR 60, appendix A.	Can submit COMS data instead of EPA test method 9, 40 CFR 60, appendix A results even if rule requires EPA test method 9, 40 CFR 60, appendix A, but must notify Administrator before performance test.	Yes, if COMS used.
§63.6(h)(7)(iii)	Averaging time for COMS during performance test.	To determine compliance, must reduce COMS data to 6-minute averages.	Yes, if COMS used.
§63.6(h)(7)(iv)	COMS requirements	Owner/operator must demonstrate that COMS performance evaluations are conducted according to §63.8(e), COMS are properly maintained and operated according to §63.8(c) and data quality as §63.8(d).	Yes, if COMS used.
§63.6(h)(7)(v)	Determining Compliance with Opacity/VE Standards.	COMS is probative but not conclusive evidence of compliance with opacity standard, even if EPA test method 9, 40 CFR 60, appendix A observation shows otherwise. Requirements for COMS to be probative evidence, proper maintenance, meeting PS 1, and data have not been altered.	Yes, if COMS used.
§63.6(h)(8)	Determining Compliance with Opacity/VE Standards.	Administrator will use all COMS, EPA test method 9, 40 CFR 60, appendix A, and EPA test method 22, 40 CFR 60, appendix A results, as well as information about operation and maintenance to determine compliance.	Yes.
§63.6(h)(9)	Adjusted Opacity Standard	Procedures for Administrator to adjust an opacity standard.	Yes.
§63.6(i)	Compliance Extension	Procedures and criteria for Administrator to grant compliance extension.	Yes.
§63.6(j)	Presidential Compliance Exemption	President may exempt source category from requirement to comply with rule.	Yes.
§63.7(a)(1)–(2)	Performance Test Dates	Dates for conducting initial performance testing and other compliance demonstrations. Must conduct 180 days after first subject to rule.	Yes.
§63.7(a)(3)	Section 114 Authority	Administrator may require a performance test under CAA section 114 at any time.	Yes.
§63.7(b)(1)	Notification of Performance Test	Must notify Administrator 60 days before the test.	Yes.
§63.7(b)(2)	Notification of Rescheduling	If rescheduling a performance test is necessary, must notify Administrator 5 days before scheduled date of rescheduled date.	Yes.
§63.7(c)	Quality Assurance/Test Plan	1. Requirement to submit site-specific test plan 60 days before the test or on date Administrator agrees with: 2. Test plan approval procedures 3. Performance audit requirements 4. Internal and external QA procedures for testing.	Yes.
§63.7(d)	Testing Facilities	Requirements for testing facilities	Yes.

Citation	Subject	Brief description	Applies to subpart LLLLL
§63.7(e)(1)	Conditions for Conducting Performance Tests.	1. Performance tests must be conducted under representative conditions. Cannot conduct performance tests during SSM. 2. Not a violation to exceed standard during SSM.	Yes before September 9, 2020. No on and after September 9, 2020. See §63.8687.
§63.7(e)(2)	Conditions for Conducting Performance Tests.	Must conduct according to rule and EPA test methods unless Administrator approves alternative.	Yes.
§63.7(e)(3)	Test Run Duration	1. Must have three test runs of at least 1 hour each. 2. Compliance is based on arithmetic mean of three runs. 3. Conditions when data from an additional test run can be used.	Yes.
§63.7(e)(4)	Conduct of performance tests	Administrator's authority to require testing under section 114 of the Act.	Yes.
§63.7(f)	Alternative Test Method	Procedures by which Administrator can grant approval to use an alternative test method.	Yes.
§63.7(g)	Performance Test Data Analysis	1. Must include raw data in performance test report. 2. Must submit performance test data 60 days after end of test with the Notification of Compliance Status. 3. Keep data for 5 years	Yes.
§63.7(h)	Waiver of Tests	Procedures for Administrator to waive performance test.	Yes.
§63.8(a)(1)	Applicability of Monitoring Requirements.	Subject to all monitoring requirements in standard.	Yes.
§63.8(a)(2)	Performance Specifications	Performance Specifications in appendix B of part 60 apply.	Yes, if CEMS used.
§63.8(a)(3)	[Reserved]		
§63.8(a)(4)	Monitoring with Flares	Unless your rule says otherwise, the requirements for flares in §63.11 apply.	Yes.
§63.8(b)(1)	Monitoring	Must conduct monitoring according to standard unless Administrator approves alternative.	Yes.
§63.8(b)(2)–(3)	Multiple Effluents and Multiple Monitoring Systems.	1. Specific requirements for installing monitoring systems. 2. Must install on each effluent before it is combined and before it is released to the atmosphere unless Administrator approves otherwise. 3. If more than one monitoring system on an emission point, must report all monitoring system results, unless one monitoring system is a backup.	Yes.
§63.8(c)(1)(i)	Routine and predictable CMS malfunction.	1. Keep parts for routine repairs readily available. 2. Reporting requirements for CMS malfunction when action is described in SSM plan.	Yes before September 9, 2020. No on and after September 9, 2020.
§63.8(c)(1)(ii)	CMS malfunction not in SSP plan	Keep the necessary parts for routine repairs if CMS.	Yes.
§63.8(c)(1)(iii)	Compliance with Operation and Maintenance Requirements.	Develop a written startup, shutdown, and malfunction plan for CMS.	Yes before September 9, 2020. No on and after September 9, 2020.
§63.8(c)(2)–(3)	Monitoring System Installation	1. Must install to get representative emission and parameter measurements. 2. Must verify operational status before or at performance test.	Yes.
§63.8(c)(4)	CMS Requirements	CMS must be operating except during breakdown, out-of-control, repair, maintenance, and high-level calibration drifts.	No; §63.8690 specifies the CMS requirements.

Citation	Subject	Brief description	Applies to subpart LLLLL
§63.8(c)(4)(i)–(ii)	CMS Requirements	1. COMS must have a minimum of one cycle of sampling and analysis for each successive 10-second period and one cycle of data recording for each successive 6-minute period. 2. CEMS must have a minimum of one cycle of operation for each successive 15-minute period.	Yes, if COMS used.
§63.8(c)(5)	COMS Minimum Procedures	COMS minimum procedures	Yes.
§63.8(c)(6)	CMS Requirements	Zero and High level calibration check requirements.	No; §63.8688 specifies the CMS requirements.
§63.8(c)(7)–(8)	CMS Requirements	Out-of-control periods, including reporting.	Yes.
§63.8(d)	CMS Quality Control	1. Requirements for CMS quality control, including calibration, etc. 2. Must keep quality control plan on record for the life of the affected source. 3. Keep old versions for 5 years after revisions.	Yes.
§63.8(e)	CMS Performance Evaluation	Notification, performance evaluation test plan, reports.	No; §63.8688 specifies the CMS requirements.
§63.8(f)(1)–(5)	Alternative Monitoring Method	Procedures for Administrator to approve alternative monitoring.	Yes.
§63.8(f)(6)	Alternative to Relative Accuracy Test	Procedures for Administrator to approve alternative relative accuracy tests for CEMS.	Yes, if CEMS used.
§63.8(g)(1)–(4)	Data Reduction	1. COMS 6-minute averages calculated over at least 36 evenly spaced data points. 2. CEMS 1-hour averages computed over at least 4 equally spaced data points.	Yes, if CEMS or COMS used.
§63.8(g)(5)	Data Reduction	Data that cannot be used in computing averages for CMS.	No; §63.8690 specifies the CMS requirements.
§63.9(a)	Notification Requirements	Applicability and State Delegation	Yes.
§63.9(b)(1)–(5)	Initial Notifications	1. Submit notification 120 days after effective date. 2. Notification of intent to construct/reconstruct; notification of commencement of construct/reconstruct; notification of startup. 3. Contents of each	Yes.
§63.9(c)	Request for Compliance Extension	Can request if cannot comply by date or if installed Best Achievable Control Technology (BACT)/Lowest Achievable Emission Rate (LAER).	Yes.
§63.9(d)	Notification of Special Compliance Requirements for New Source.	For sources that commence construction between proposal and promulgation and want to comply 3 years after effective date.	Yes.
§63.9(e)	Notification of Performance Test	Notify Administrator 60 days prior	Yes.
§63.9(f)	Notification of VE/Opacity Test	Notify Administrator 30 days prior	Yes.
§63.9(g)	Additional Notifications When Using CMS.	1. Notification of performance evaluation. 2. Notification using COMS data 3. Notification that the criterion for use of alternative to relative accuracy testing was exceeded.	No; §63.8692 specifies the CMS notification requirements.
§63.9(h)(1)–(6)	Notification of Compliance Status	1. Contents. 2. Due 60 days after end of performance test or other compliance demonstration, except for opacity/VE, which are due 30 days after. 3. When to submit to Federal vs. State authority.	Yes.
§63.9(i)	Adjustment of Submittal Deadlines	Procedures for Administrator to approve change in dates when notifications must be submitted.	Yes.

Citation	Subject	Brief description	Applies to subpart LLLLL
§ 63.9(j)	Change in Previous Information	Must submit within 15 days after the change.	Yes.
§ 63.9(k)	Electronic reporting procedures	Electronic reporting procedures for notifications per § 63.9(j).	Yes.
§ 63.10(a)	Recordkeeping/Reporting	1. Applies to all, unless compliance extension. 2. When to submit to Federal vs. State authority. 3. Procedures for owners of more than 1 source.	Yes.
§ 63.10(b)(1)	Recordkeeping/Reporting	1. General Requirements 2. Keep all records readily available. 3. Keep for 5 years	Yes.
§ 63.10(b)(2)(i)	Records related to Startup and Shutdown.	Occurrence of each of operation (process equipment).	Yes before September 9, 2020. No on and after September 9, 2020.
§ 63.10(b)(2)(ii)	Recordkeeping Relevant to Malfunction Periods and CMS.	Occurrence of each malfunction of air pollution equipment.	Yes before September 9, 2020. No on and after September 9, 2020.
§ 63.10(b)(2)(iii)	Recordkeeping Relevant to Maintenance of Air Pollution Control and Monitoring Equipment.	Maintenance on air pollution control equipment.	Yes.
§ 63.10(b)(2)(iv)	Recordkeeping Relevant to Startup, Shutdown, and Malfunction Periods and CMS.	Actions during startup, shutdown, and malfunction.	Yes before September 9, 2020. No on and after September 9, 2020.
§ 63.10(b)(2)(v)	Recordkeeping Relevant to Startup, Shutdown, and Malfunction Periods and CMS.	Actions during startup, shutdown, and malfunction.	Yes before September 9, 2020. No on and after September 9, 2020.
§ 63.10(b)(2)(vi) and (x-xi).	CMS Records	1. Malfunctions, inoperative, out-of-control. 2. Calibration checks 3. Adjustments, maintenance	Yes.
§ 63.10(b)(2)(vii)–(ix)	Records	1. Measurements to demonstrate compliance with emission limitations. 2. Performance test, performance evaluation, and visible emission observation results. 3. Measurements to determine conditions of performance tests and performance evaluations.	Yes.
§ 63.10(b)(2)(xii)	Records	Records when under waiver	Yes
§ 63.10(b)(2)(xiii)	Records	Records when using alternative to relative accuracy test.	Yes.
§ 63.10(b)(2)(xiv)	Records	All documentation supporting Initial Notification and Notification of Compliance Status.	Yes.
§ 63.10(b)(3)	Records	Applicability determinations	Yes.
§ 63.10(c)(1)–(6), (9)–(15).	Records	Additional records for CMS	No; § 63.8694 specifies the CMS recordkeeping requirements.
§ 63.10(c)(7)–(8)	Records	Records of excess emissions and parameter monitoring exceedances for CMS.	No; § 63.8694 specifies the CMS recordkeeping requirements.
§ 63.10(d)(1)	General Reporting Requirements	Requirement to report	Yes.
§ 63.10(d)(2)	Report of Performance Test Results	When to submit to Federal or State authority.	Yes.
§ 63.10(d)(3)	Reporting Opacity or VE Observations	What to report and when	Yes.
§ 63.10(d)(4)	Progress Reports	Must submit progress reports on schedule if under compliance extension.	Yes.
§ 63.10(d)(5)	Startup, Shutdown, and Malfunction Reports.	Contents and submission	Yes before September 9, 2020. No on and after September 9, 2020.

Citation	Subject	Brief description	Applies to subpart LLLLL
§ 63.10(e)(1), (2)	Additional CMS Reports	1. Must report results for each CEM on a unit. 2. Written copy of performance evaluation. 3. Three copies of COMS performance evaluation.	Yes.
§ 63.10(e)(3)	Reports	Excess emission reports	No; § 63.8693 specifies the reporting requirements.
§ 63.10(e)(3)(i)–(iii)	Reports	Schedule for reporting excess emissions and parameter monitor exceedances (now defined as deviations).	No; § 63.8693 specifies the reporting requirements.
§ 63.10(e)(3)(iv)–(v)	Excess Emissions Reports	1. Requirement to revert to the frequency specified in the relevant standard if there is an excess emissions and parameter monitor exceedances (now defined as deviations). 2. Provision to request semiannual reporting after compliance for one year. 3. Submit report by 30th day following end of quarter or calendar half. 4. If there has not been an exceedance or excess emission (now defined as deviations), report content is a statement that there have been no deviations.	No; § 63.8693 specifies the reporting requirements.
§ 63.10(e)(3)(iv)–(v)	Excess Emissions Reports	Must submit report containing all of the information in § 63.10(c)(5)(13), § 63.8(c)(7)–(8).	No; § 63.8693 specifies the reporting requirements.
§ 63.10(e)(3)(vi)–(viii)	Excess Emissions Report and Summary Report.	1. Requirements for reporting excess emissions for CMS (now called deviations). 2. Requires all of the information in § 63.10(c)(5)(13), § 63.8(c)(7)–(8).	No; § 63.8693 specifies the reporting requirements.
§ 63.10(e)(4)	Reporting COMS data	Must submit COMS data with performance test data.	Yes, if COMS used.
§ 63.10(f)	Waiver for Recordkeeping/Reporting	Procedures for Administrator to waive	Yes.
§ 63.11	Flares	Requirements for flares	Yes.
§ 63.12	Delegation	State authority to enforce standards	Yes.
§ 63.13	Addresses	Addresses where reports, notifications, and requests are sent.	Yes.
§ 63.14	Incorporation by Reference	Test methods incorporated by reference.	Yes.
§ 63.15	Availability of Information	Public and confidential information	Yes.

[68 FR 24577, May 7, 2003, as amended at 71 FR 20469, Apr. 20, 2006; 85 FR 14556, Mar. 12, 2020; 85 FR 73916, Nov. 19, 2020]

Subpart MMMMM—National Emission Standards for Hazardous Air Pollutants: Flexible Polyurethane Foam Fabrication Operations

SOURCE: 68 FR 18070, Apr. 14, 2003, unless otherwise noted.

WHAT THIS SUBPART COVERS

§ 63.8780 What is the purpose of this subpart?

This subpart establishes national emission standards for hazardous air pollutants (NESHAP) emitted from flexible polyurethane foam fabrication operations. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission standards.

§ 63.8782 Am I subject to this subpart?

(a) You are subject to this subpart if you own or operate a flexible polyurethane foam fabrication plant site that operates a flame lamination affected source, as defined at § 63.8784(b)(2), and that is located at, or

is part of a major emission source of hazardous air pollutants (HAP) or that operates a loop slitter affected source, as defined at §63.8784(b)(1), that meets the criteria in paragraphs (a)(1) and (2) of this section.

(1) The loop slitter affected source uses one or more HAP-based adhesives at any time on or after April 14, 2003.

(2) The loop slitter affected source is located at or is part of a major source of HAP.

(b) A flexible polyurethane foam fabrication plant site is a plant site where pieces of flexible polyurethane foam are bonded together or to other substrates using HAP-based adhesives or flame lamination.

(c) A major source of HAP is a plant site that emits or has the potential to emit any single HAP at a rate of 10 tons or more per year or any combination of HAP at a rate of 25 tons or more per year.

(d) This subpart does not apply to the following processes in paragraphs (d)(1) and (2) of this section:

(1) Processes that produce flexible polyurethane or rebond foam as defined in subpart III of this part.

(2) A research and development facility, as defined in section 112(c)(7) of the Clean Air Act (CAA).

§63.8784 What parts of my plant does this subpart cover?

(a) This subpart applies to each existing, new, or reconstructed affected source at facilities engaged in flexible polyurethane foam fabrication.

(b) The affected sources are defined in this section in paragraphs (b)(1) and (2) of this section.

(1) The loop slitter adhesive use affected source is the collection of all loop slitters and associated adhesive application equipment used to apply HAP-based adhesives to bond foam to foam at a flexible polyurethane foam fabrication plant site.

(2) The flame lamination affected source is the collection of all flame lamination lines associated with the flame lamination of foam to any substrate at a flexible polyurethane foam fabrication plant site.

(c)(1) A new affected source is one that commences construction after August 8, 2001 and meets the applicability criteria of §63.8782 at the time construction commences.

(2) If you add one or more flame lamination lines at a plant site where flame lamination lines already exist, the added line(s) shall be a new affected source and meet new source requirements if the added line(s) are at a flexible polyurethane foam fabrication plant site that has the potential to emit 10 tons per year or more of any HAP or 25 tons or more per year of any combination of HAP.

(d) A reconstructed affected source is one that commences reconstruction after August 8, 2001 and meets the criteria for reconstruction as defined in §63.2.

(e) An affected source is existing if it commenced construction or reconstruction on or before August 8, 2001.

[68 FR 18070, Apr. 14, 2003, as amended at 71 FR 20470, Apr. 20, 2006; 86 FR 64398, Nov. 18, 2021]

§63.8786 When do I have to comply with this subpart?

(a) If you have a new or reconstructed affected source, you must comply with this subpart according to paragraphs (a)(1) and (2) of this section.

(1) If you start up your new or reconstructed affected source before April 14, 2003, then you must comply with the emission standards for new or reconstructed sources in this subpart no later than April 14, 2003.

(2) If you start up your new or reconstructed affected source on or after April 14, 2003, then you must comply with the emission standards for new or reconstructed sources in this subpart upon startup of your affected source.

(b) If you have an existing affected source, you must comply with this subpart according to paragraphs (b)(1) and (b)(2) of this section, as applicable.

(1) If you have an existing loop slitter affected source, you must comply with the emission standards for existing sources no later than April 14, 2004.

(2) If you have an existing flame lamination affected source, you must comply with the emission standards for existing sources no later than May 17, 2022.

(c) If you have an area source that increases its emissions or its potential to emit such that it becomes a major

source of HAP and an affected source subject to this subpart, the provisions in paragraphs (c)(1) and (2) of this section apply.

(1) A new affected source as specified at §63.8784(c) or a reconstructed affected source as specified at §63.8784(d) must be in compliance with this subpart upon startup.

(2) An existing affected source as specified at §63.8784(e) must be in compliance with this subpart no later than 1 year after the date on which the area source became a major source.

(d) You must meet the notification requirements in §63.8816 according to the schedule in §63.8816 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission standards in this subpart.

(e) If you have a loop slitter affected source, you must have data on hand beginning on the compliance date specified in paragraph (b) of this section as necessary to demonstrate that your adhesives are not HAP-based. The types of data necessary are described in §§63.8802 and 63.8810.

(f) You must comply with the electronic reporting requirements according to paragraphs (f)(1) and (f)(2) of this section.

(1) You must comply with the performance test and CMS performance evaluation requirements of §63.8818(j) on or before May 17, 2022.

(2) You must comply with the compliance report requirements of §63.8818(k) on or before May 17, 2022 or once the report template for this subpart has been available on the CEDRI website for 1 year, whichever date is later.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64398, Nov. 18, 2021]

EMISSION LIMITATIONS

§ 63.8790 What emission limitations must I meet?

(a) You must meet each emission limit in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit in Table 2 to this subpart that applies to you.

GENERAL COMPLIANCE REQUIREMENTS

§ 63.8794 What are my general requirements for complying with this subpart?

(a) For each loop slitter adhesive use affected source, you must be in compliance with the requirements in this subpart at all times.

(b) For each flame lamination affected source, you must be in compliance with the requirements in this subpart at all times.

(c) At all times, you must operate and maintain any affected source, including associated air pollution control equipment and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions. The general duty to minimize emissions does not require you to make any further efforts to reduce emissions if levels required by the applicable standard have been achieved. Determination of whether a source is operating in compliance with operation and maintenance requirements will be based on information available to the Administrator which may include, but is not limited to, monitoring results, review of operation and maintenance procedures, review of operation and maintenance records, and inspection of the source.

(d) For flame lamination affected sources in §63.8786 using a control device to comply with the emission limitations in Table 1 to this subpart, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment during the period between the compliance date specified for your flame lamination affected source in §63.8786 and the date upon which continuous compliance monitoring systems required by §63.8810(c) have been installed and verified and any applicable operating limits have been set.

(e) [Reserved]

(f) For each monitoring system required by §63.8810(c) for flame lamination sources, you must develop and submit for approval a site-specific monitoring plan that addresses the requirements in paragraphs (f)(1) through (3) of this section.

(1) Installation of the continuous monitoring system (CMS) sampling

probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (*e.g.*, on or downstream of the last control device);

(2) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system; and

(3) Performance evaluation procedures and acceptance criteria (*e.g.*, calibrations).

(g) In your site-specific monitoring plan, you must also address the ongoing procedures specified in paragraphs (g)(1) through (3) of this section.

(1) Ongoing operation and maintenance procedures in accordance with the general requirements of §§ 63.8(c)(1), (3), (4)(ii), (7), and (8), and 63.8804;

(2) Ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d); and

(3) Ongoing recordkeeping and reporting procedures in accordance with the general requirements of § 63.10(c), (e)(1), and (e)(2)(i).

[68 FR 18070, Apr. 14, 2003, as amended at 71 FR 20470, Apr. 20, 2006; 86 FR 64399, Nov. 18, 2021]

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.8798 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) For each loop slitter affected source, you must conduct the initial compliance demonstration by the compliance date that is specified for your source in § 63.8786.

(b) For each flame lamination affected source, you must conduct performance tests by the compliance date that is specified for your source in § 63.8786 and according to the provisions in § 63.7(a)(2).

(c) You must conduct subsequent performance tests to demonstrate compliance with the flame lamination emissions limitations in Table 1 to this subpart no less frequently than every 5 years from the date of the last performance test.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64399, Nov. 18, 2021]

§ 63.8800 What performance tests and other procedures must I use to demonstrate compliance with the emission limit for flame lamination?

(a) You must conduct each performance test in Table 3 to this subpart that applies to you.

(b) Each performance test must be conducted according to the requirements in paragraph (c) of this section and under the specific conditions in Table 3 to this subpart.

(c) You must conduct each performance test under conditions representative of normal operations. You may not conduct performance tests during periods of SSM. The owner or operator must record the process information that is necessary to document operating conditions during the test and include in such record an explanation to support that such conditions represent normal operation. Upon request, the owner or operator shall make available to the Administrator such records as may be necessary to determine the conditions of performance tests.

(d) You must conduct at least three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.

(e) For new and reconstructed affected sources, you must determine the percent reduction of HAP emissions during the performance test according to paragraphs (e)(1) through (3) of this section.

(1) If you use chlorinated fire retardant foams, determine the percent reduction of HCl to represent HAP emissions from the source. If you do not use chlorinated fire retardant foams, determine the percent reduction of HCN to represent HAP emissions from the source.

(2) Calculate the concentration of HAP at the control device inlet and at the control device outlet using the procedures in the specified test method.

(3) Compare the calculated HAP concentration at the control device inlet to the calculated HAP concentration at the control device outlet to determine the percent reduction over the period of the performance test, using Equation 1 of this section:

$$R = \frac{\sum_{i=1}^{n} E_{inlet,\,i} - \sum_{i=1}^{n} E_{outlet,\,i}}{\sum_{i=1}^{n} E_{inlet,\,i}} (100) \quad [Eq.\ 1]$$

Where:

R = Efficiency of control device, percent.

$E_{inlet,i}$ = HAP concentration of control device inlet stream for test run i, mg/dscm.

$E_{outlet,i}$ = HAP concentration of control device outlet stream for test run i, mg/dscm.

n = Number of runs conducted for the performance test.

(f) For existing affected sources, you must determine the HCl emissions rate according to paragraphs (f)(1) through (3) of this section.

(1) Calculate the concentration of HCl in the vent outlet to the atmosphere or at the control device outlet, if a control device is used, using the procedures in the specified test method.

(2) Determine the vent outlet gas stream volumetric flow rate or if a control device is used, the control device outlet gas stream volumetric flow rate, using the procedures in the specified test method.

(3) Calculate the HCl emission rate for the period of the performance test using Equation 2 of this section:

$$E_{HCl} = C \; x \; AOF \text{ Eq.2}$$

Where:

E_{HCl} = Emission rate of HCl, lbs/hr.

C= average HCl concentration of vent or control device outlet stream for all test runs, lb/dscft.

AOF = average outlet volumetric flow rate of gas stream, dry basis, dscft/hr.

(g) You must also meet the requirements in paragraphs (g)(1) and (2) of this section.

(1) Conduct the performance tests using foams that are representative of foams typically used at your flame lamination affected source. If you use foams containing chlorinated fire retardants, you must conduct the performance tests using these foams.

(2) Establish all applicable operating limits that correspond to the control system efficiency as described in Table 3 to this subpart.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64399, Nov. 18, 2021]

§ 63.8802 What methods must I use to demonstrate compliance with the emission limitation for loop slitter adhesive use?

(a) *Determine the HAP content for each material used.* To determine the HAP content for each material used in your foam fabrication operations, you must use one of the options in paragraphs (a)(1) through (3) of this section. If you use the option in paragraph (a)(3) of this section, you are subject to the provisions of paragraph (a)(4) of this section.

(1) *Method 311 (appendix A to 40 CFR part 63).* You may use Method 311 for determining the mass fraction of HAP. Use the procedures specified in paragraphs (a)(1)(i) and (ii) of this section when determining HAP content by Method 311.

(i) Include in the HAP total each HAP in Table 8 of this subpart that is measured at 0.1 percent by weight or more and any other HAP that is measured at 1.0 percent by weight or more. Express the weight fraction of each HAP you measure as a value truncated to four places after the decimal point (for example, 0.1234).

(ii) Calculate the total HAP content in the test material by adding up the individual HAP contents and truncating the result to three places after the decimal point (for example, 0.123).

(2) *Alternative method.* You may use an alternative test method for determining mass fraction of HAP if you obtain prior approval by the Administrator. You must follow the procedure in § 63.7(f) to submit an alternative test method for approval.

(3) *Information from the supplier or manufacturer of the material.* You may rely on information other than that generated by the test methods specified in paragraphs (a)(1) and (2) of this section to determine the mass fraction of

HAP according to paragraphs (a)(3)(i) and (ii) of this section. This information may include, but is not limited to, a material safety data sheet (MSDS), a certified product data sheet (CPDS), or a manufacturer's hazardous air pollutant data sheet.

(i) Include in the HAP total each HAP in Table 8 of this subpart that is present at 0.1 percent by weight or more and any other HAP that is present at 1.0 percent by weight or more.

(ii) If the HAP content is provided by the material supplier or manufacturer as a range, then you must use the upper limit of the range for determining compliance.

(4) *Verification of supplier or manufacturer information.* Although you are not required to perform testing to verify the information obtained according to paragraph (a)(3) of this section, the Administrator may require a separate measurement of the total HAP content using the methods specified in paragraph (a)(1) or (2) of this section. If this measurement exceeds the total HAP content provided by the material supplier or manufacturer, then you must use the measured HAP content to determine compliance.

(b) [Reserved]

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64399, Nov. 18, 2021]

§ 63.8806 How do I demonstrate initial compliance with the emission limitations?

(a) You must demonstrate initial compliance with each emission limit that applies to you according to Table 4 to this subpart.

(b) You must establish each site-specific operating limit in Table 2 to this subpart that applies to you according to the requirements in § 63.8800 and Table 3 to this subpart.

(c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8816(e) through (h).

CONTINUOUS COMPLIANCE REQUIREMENTS

§ 63.8810 How do I monitor and collect data to demonstrate continuous compliance?

(a) If you own or operate a loop slitter adhesive use affected source, you must meet the requirements in paragraphs (a)(1) and (2) of this section.

(1) Maintain a list of each adhesive and the manufacturer or supplier of each.

(2) Maintain a record of EPA Method 311 (appendix A to 40 CFR part 63), approved alternative method, or other reasonable means of HAP content determinations indicating the mass percent of each HAP for each adhesive.

(b) If you own or operate a flame lamination affected source, you must meet the requirements in paragraphs (b)(1) through (3) of this section if you use a scrubber, or paragraph (b)(4) of this section if you use any other control device.

(1) Keep records of the daily average scrubber inlet liquid flow rate.

(2) Keep records of the daily average scrubber effluent pH.

(3) If you use a venturi scrubber, keep records of daily average pressure drop across the venturi.

(4) Keep records of operating parameter values for each operating parameter that applies to you.

(c) If you own or operate a control device to meet the emissions limitations for a flame lamination affected source, you must meet the requirements in paragraphs (c)(1) through (4) of this section.

(1) Except for periods of monitoring-associated repairs and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times that the affected source is operating.

(2) In data average calculations and calculations used to report emission or operating levels, you may not use data recorded during monitoring malfunctions, associated repairs, or recorded during required quality assurance or control activities. Nor may such data be used in fulfilling any applicable

minimum data availability requirement. You must use all the data collected during all other periods in assessing the operation of the control device and associated control system.

(3) You must conduct a performance evaluation of each CMS in accordance with your site-specific monitoring plan.

(4) You must operate and maintain the CMS in continuous operation according to the site-specific monitoring plan.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64399, Nov. 18, 2021]

§ 63.8812 How do I demonstrate continuous compliance with the emission limitations?

(a) You must demonstrate continuous compliance with each emission limit and operating limit in Tables 1 and 2 to this subpart that applies to you according to the methods specified in Table 5 to this subpart.

(b) You must report each instance in which you did not meet each emission limit and each operating limit in Tables 1 and 2 to this subpart that applies to you. These instances are deviations from the operating limits in this subpart. These deviations must be reported according to the requirements in § 63.8818.

(c)–(d) [Reserved]

(e) You must meet the following requirements if you are complying with the adhesive use ban for loop slitter adhesive use described in § 63.8790(a).

(1) If, after you submit the Notification of Compliance Status, you use an adhesive for which you have not previously verified percent HAP mass using the methods in § 63.8802, you must verify that each adhesive used in the affected source meets the emission limit, using any of the methods in § 63.8802.

(2) You must update the list of all the adhesives used at the affected source.

(3) With the compliance report for the reporting period during which you used the new adhesive, you must submit the updated list of all adhesives and a statement certifying that, as purchased, each adhesive used at the affected source during the reporting period met the emission limit in Table 1 to this subpart.

[68 FR 18070, Apr. 14, 2003, as amended at 71 FR 20470, Apr. 20, 2006; 86 FR 64400, Nov. 18, 2021]

NOTIFICATION, REPORTS, AND RECORDS

§ 63.8816 What notifications must I submit and when?

(a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(f), and 63.9(b) through (h) that apply to you.

(b) If you own or operate an existing loop slitter or flame lamination affected source, submit an initial notification no later than 120 days after April 14, 2003, or no later than 120 days after the source becomes subject to this subpart, whichever is later.

(c) If you own or operate a new or reconstructed loop slitter or flame lamination affected source, submit the application for construction or reconstruction required by § 63.9(b)(1)(iii) in lieu of the initial notification.

(d) If you own or operate a flame lamination affected source, submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin, as required in § 63.7(b)(1).

(e) If you own or operate a loop slitter affected source, submit a Notification of Compliance Status according to § 63.9(h)(2)(ii) within 60 days of the compliance date specified in § 63.8786.

(f) If you own or operate a flame lamination affected source, submit a Notification of Compliance Status according to § 63.9(h)(2)(ii) that includes the results of the performance test conducted according to the requirements in Table 3 to this subpart. You must submit the notification before the close of business on the 60th calendar day following the completion of the performance test according to § 63.10(d)(2).

(g) For each flame lamination affected source, the Notification of Compliance Status must also include the information in paragraphs (g)(1) and (2) that applies to you.

(1) The operating parameter value averaged over the full period of the performance test (for example, average pH).

(2) The operating parameter range within which HAP emissions are reduced to the level corresponding to meeting the applicable emission limits in Table 1 to this subpart.

(h) For each loop slitter adhesive use affected source, the Notification of Compliance Status must also include the information listed in paragraphs (h)(1) and (2) of this section.

(1) A list of each adhesive used at the affected source, its HAP content (percent by weight), and the manufacturer or supplier of each.

(2) A statement certifying that each adhesive that was used at the affected source during the reporting period met the emission limit in Table 1 to this subpart.

[68 FR 18070, Apr. 14, 2003, as amended at 85 FR 73916, Nov. 19, 2020; 86 FR 64400, Nov. 18, 2021]

§ 63.8818 What reports must I submit and when?

(a) You must submit each report in Table 6 to this subpart that applies to you.

(b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each compliance report for flame lamination affected sources semiannually according to paragraphs (b)(1) through (4) of this section.

(1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.8786 and ending on June 30 or December 31, whichever date is the first date following the end of the first calendar half after the compliance date that is specified for your source in § 63.8786.

(2) The first compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date follows the end of the first calendar half after the compliance date that is specified for your affected source in § 63.8786.

(3) Each subsequent compliance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.

(4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31, whichever date is the first date following the end of the semiannual reporting period.

(c) For each loop slitter adhesive use affected source, you may submit annual compliance reports in place of semiannual reports.

(d) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, and if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of according to the dates in paragraphs (b)(1) through (4) of this section.

(e) The compliance report must contain the information in paragraphs (e)(1) through (5) of this section.

(1) Company name and address.

(2) Statement by a responsible official with that official's name, title, and signature, certifying the truth, accuracy and completeness of the content of the report.

(3) Date of report and beginning and ending dates of the reporting period.

(4) If there are no deviations from any emission limitations (emission limit or operating limit) that applies to you, a statement that there were no deviations from the emission limitations during the reporting period.

(5) For each deviation from an emission limitation that occurs, the compliance report must contain the information specified in paragraphs (e)(5)(i) through (iii) of this section.

(i) The total operating time of each affected source during the reporting period.

(ii) Information on the number, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.

(iii) Information on the number, duration, and cause for continuous parameter monitoring system (CPMS) downtime incidents, if applicable, other than downtime associated with zero and span and other daily calibration checks.

(f) The compliance report for flame lamination affected sources required

by §63.8810(c) to conduct continuous monitoring must also contain the following information in paragraphs (f)(1) and (2) of this section.

(1) If there were no periods during which the CPMS was out-of-control in accordance with the monitoring plan, a statement that there were no periods during which the CPMS was out-of-control during the reporting period.

(2) If there were periods during which the CPMS was out-of-control in accordance with the monitoring plan, the date, time, and duration of each out-of-control period.

(g) The compliance report for a loop slitter adhesive use affected source must also contain the following information in paragraphs (g)(1) and (2) of this section.

(1) For each annual reporting period during which you use an adhesive that was not included in the list submitted with the Notification of Compliance Status in §63.8816(h) (1), an updated list of all adhesives used at the affected source.

(2) A statement certifying that each adhesive that was used at the affected source during the reporting period met the emission limit in Table 1 to this subpart.

(h) Each affected source that has obtained a title V operating permit pursuant to 40 CFR part 70 or 40 CFR part 71 must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If an affected source submits a compliance report pursuant to Table 6 to this subpart along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all required information concerning deviations from any emission limitation (including any operating limit) in this subpart, submission of the compliance report shall be deemed to satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submission of a compliance report shall not otherwise affect any obligation the affected source may have to report deviations from permit requirements to the permit authority.

(i) [Reserved]

(j) For Performance Test and CMS Performance Evaluation Reports, beginning on May 17, 2022, within 60 days after the date of completing each performance test or CMS performance evaluation (as defined in §63.2) required by this subpart, the owner or operator must submit the results of the performance test or CMS performance evaluation following the procedures specified in paragraphs (j)(1) through (3) of this section.

(1) *Data collected using test methods supported by the EPA's Electronic Reporting Tool (ERT) as listed on the EPA's ERT website (https://www.epa.gov/electronic-reporting-air-emissions/electronic-reporting-tool-ert) at the time of the test.* Submit the results of the performance test or the performance evaluation of CMS measuring relative accuracy test audit (RATA) pollutants to the EPA via the Compliance and Emissions Data Reporting Interface (CEDRI), which can be accessed through the EPA's Central Data Exchange (CDX) *(https://cdx.epa.gov/)*. The data must be submitted in a file format generated using the EPA's ERT. Alternatively, you may submit an electronic file consistent with the extensible markup language (XML) schema listed on the EPA's ERT website.

(2) *Data collected using test methods that are not supported by the EPA's ERT as listed on the EPA's ERT website at the time of the test.* The results of the performance test or the performance evaluation of CMS measuring RATA pollutants by methods that are not supported by the ERT, must be included as an attachment in the ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the ERT generated package or alternative file to the EPA via CEDRI.

(3) *Confidential business information (CBI).* Do not use CEDRI to submit information you claim as CBI. Anything submitted using CEDRI cannot later be claimed CBI. Although we do not expect persons to assert a claim of CBI, if you wish to assert a CBI claim for some of the information submitted under paragraph (a)(1) or (2) of this section, you must submit a complete file, including information claimed to be

CBI, to the EPA. The file must be generated using the EPA's ERT or an alternate electronic file consistent with the XML schema listed on the EPA's ERT website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described in paragraphs (a)(1) and (2) of this section. All CBI claims must be asserted at the time of submission. Furthermore, under CAA section 114(c), emissions data is not entitled to confidential treatment, and the EPA is required to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

(k) When submitting reports electronically, on and after the date specified in §63.8786(f)(2), you must submit reports to the EPA via CEDRI, which can be accessed through the EPA's CDX (*https://cdx.epa.gov/*). The EPA will make all the information submitted through CEDRI available to the public without further notice to you. Do not use CEDRI to submit information you claim as confidential business information (CBI). Anything submitted using CEDRI cannot later be claimed CBI. You must use the appropriate electronic report template on the CEDRI website (*https://www.epa.gov/electronic-reporting-air-emissions/cedri*) for this subpart. The date report templates become available will be listed on the CEDRI website. Unless the Administrator or delegated state agency or other authority has approved a different schedule for submission of reports, the report must be submitted by the deadline specified in this subpart, regardless of the method in which the report is submitted. Although we do not expect persons to assert a claim of CBI, if you wish to assert a CBI claim, submit a complete report, including information claimed to be CBI, to the EPA. The report must be generated using the appropriate form on the CEDRI website. Submit the file on a compact disc, flash drive, or other commonly used electronic storage medium and clearly mark the medium as CBI. Mail the electronic medium to U.S. EPA/OAQPS/CORE CBI Office, Attention: Group Leader, Measurement Policy Group, MD C404–02, 4930 Old Page Rd., Durham, NC 27703. The same file with the CBI omitted must be submitted to the EPA via the EPA's CDX as described earlier in this paragraph (k). All CBI claims must be asserted at the time of submission. Furthermore, under CAA section 114(c), emissions data is not entitled to confidential treatment, and the EPA is required to make emissions data available to the public. Thus, emissions data will not be protected as CBI and will be made publicly available.

(l) For claims of EPA system outage, when you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of EPA system outage for failure to timely comply with the reporting requirement. To assert a claim of EPA system outage, you must meet the requirements outlined in paragraphs (l)(1) through (7) of this section.

(1) You must have been or will be precluded from accessing CEDRI and submitting a required report within the time prescribed due to an outage of either the EPA's CEDRI or CDX systems.

(2) The outage must have occurred within the period of time beginning five business days prior to the date that the submission is due.

(3) The outage may be planned or unplanned.

(4) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(5) You must provide to the Administrator a written description identifying:

(i) The date(s) and time(s) when CDX or CEDRI was accessed and the system was unavailable;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to EPA system outage;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(6) The decision to accept the claim of EPA system outage and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(7) In any circumstance, the report must be submitted electronically as soon as possible after the outage is resolved.

(m) For claims of force majeure, when you are required to electronically submit a report through CEDRI in the EPA's CDX, you may assert a claim of force majeure for failure to timely comply with the reporting requirement. To assert a claim of force majeure, you must meet the requirements outlined in paragraphs (m)(1) through (5) of this section.

(1) You may submit a claim if a force majeure event is about to occur, occurs, or has occurred or there are lingering effects from such an event within the period of time beginning five business days prior to the date the submission is due. For the purposes of this section, a force majeure event is defined as an event that will be or has been caused by circumstances beyond the control of the affected facility, its contractors, or any entity controlled by the affected facility that prevents you from complying with the requirement to submit a report electronically within the time period prescribed. Examples of such events are acts of nature (*e.g.*, hurricanes, earthquakes, or floods), acts of war or terrorism, or equipment failure or safety hazard beyond the control of the affected facility (*e.g.*, large scale power outage).

(2) You must submit notification to the Administrator in writing as soon as possible following the date you first knew, or through due diligence should have known, that the event may cause or has caused a delay in reporting.

(3) You must provide to the Administrator:

(i) A written description of the force majeure event;

(ii) A rationale for attributing the delay in reporting beyond the regulatory deadline to the force majeure event;

(iii) Measures taken or to be taken to minimize the delay in reporting; and

(iv) The date by which you propose to report, or if you have already met the reporting requirement at the time of the notification, the date you reported.

(4) The decision to accept the claim of force majeure and allow an extension to the reporting deadline is solely within the discretion of the Administrator.

(5) In any circumstance, the reporting must occur as soon as possible after the force majeure event occurs.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64400, Nov. 18, 2021]

§ 63.8820 What records must I keep?

(a) You must keep a copy of each notification and report that you submit to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63.10(b)(2)(xiv).

(b) For each flame lamination affected source, you must also keep the following records specified in paragraphs (b)(1) through (3) of this section.

(1) Records of performance tests, as required in § 63.10(b)(2)(viii).

(2) Records of the operating parameter values required in § 63.8810(b).

(3) The records specified in paragraphs (b)(3)(i) through (iii) of this section.

(i) The number of deviations. For each deviation, record the date, time, cause, and duration of the deviation.

(ii) For each deviation, record and retain a list of the affected sources or equipment, an estimate of the quantity of each regulated pollutant emitted over any emission limit and a description of the method used to estimate the emissions.

(iii) Record actions taken to minimize emissions in accordance with § 63.8794(c), and any corrective actions taken to return the affected unit to its normal or usual manner of operation.

(c) For each loop slitter adhesive use affected source, you must keep the following records specified in paragraphs (c)(1) and (2) of this section.

(1) A list of each adhesive and the manufacturer or supplier of each.

(2) A record of EPA Method 311 (appendix A to 40 CFR part 63), approved alternative method, or other reasonable means of determining the mass percent of total HAP for each adhesive used at the affected source.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64401, Nov. 18, 2021]

§ 63.8822 In what form and how long must I keep my records?

(a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).

(b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.

(c) You must keep each record on site for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You can keep the records offsite for the remaining 3 years.

OTHER REQUIREMENTS AND INFORMATION

§ 63.8826 What parts of the General Provisions apply to me?

Table 7 to this subpart shows which sections of the General Provisions in §§ 63.1 through 63.15 apply to you.

§ 63.8828 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. Environmental Protection Agency (U.S. EPA), or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if implementation and enforcement of this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under 40 CFR part 63, subpart E, the authorities contained in paragraph (c) of this section are retained by the Administrator of U.S. EPA and are not transferred to the State, local, or tribal agency.

(c) The authorities in paragraphs (c)(1) through (4) that cannot be delegated to State, local, or tribal agencies are as follows:

(1) Approval of alternatives to requirements in §§ 63.8780, 63.8782, 63.8784, 63.8786, and 63.8790.

(2) Approval of major alternatives to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.

(3) Approval of major alternatives to monitoring under § 63.8(f) and as defined in § 63.90.

(4) Approval of major alternatives to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

§ 63.8830 What definitions apply to this subpart?

Terms used in this subpart are defined in the CAA, in 40 CFR 63.2, and in this section as follows:

Adhesive means any chemical substance that is applied for the purpose of bonding foam to foam, foam to fabric, or foam to any other substrate, other than by mechanical means. Products used on humans and animals, adhesive tape, contact paper, or any other product with an adhesive incorporated onto it in an inert substrate shall not be considered adhesives under this subpart.

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart, including but not limited to any emission limitation (including any operating limit); or

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart and that is included in the operating permit for any affected source required to obtain such a permit; or

(3) Fails to meet any emission limitation (including any operating limit) in this subpart, regardless of whether such failure is permitted by this subpart.

Emission limitation means any emission limit or operating limit.

Flame lamination means the process of bonding flexible foam to one or more layers of material by heating the foam surface with an open flame.

Flame lamination line means the flame laminator and associated rollers.

HAP-based adhesive means an adhesive containing 1.0 percent by weight or more of any individual or combination HAP listed in Table 8 to this subpart or 1.0 percent by weight or more of any other individual HAP, according to information from the supplier or manufacturer of the material, EPA Method 311 (appendix A to 40 CFR part 63) or another approved alternative.

Loop slitter means a machine used to create thin sheets of foam from the large blocks of foam or ''buns'' created at a slabstock flexible polyurethane foam production plant.

Research and development process means a laboratory or pilot plant operation whose primary purpose is to conduct research and development into new processes and products where the operations are under the close supervision of technically trained personnel, and which is not engaged in the manufacture of products for commercial sale, except in a *de minimis* manner.

Responsible official means responsible official as defined in 40 CFR 70.2.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64401, Nov. 18, 2021]

TABLE 1 TO SUBPART MMMMM OF PART 63—EMISSION LIMITS

As stated in §63.8790(a), you must comply with the emission limits in the following table:

For . . .	You must . . .
1. Each existing, new, or reconstructed loop slitter adhesive use affected source.	Not use any HAP-based adhesives.
2. Each new or reconstructed flame lamination affected source	Reduce HAP emissions by 90 percent.
3. Each existing flame lamination affected source	Emit no more than 1.45 pounds per hour of HCl per flame lamination line.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64402, Nov. 18, 2021]

TABLE 2 TO SUBPART MMMMM OF PART 63—OPERATING LIMITS FOR EXISTING, NEW, OR RECONSTRUCTED FLAME LAMINATION AFFECTED SOURCES

As stated in §63.8790(b), you must comply with the applicable operating limits in the following table:

For each . . .	You must . . .
1. Scrubber	a. Maintain the daily average scrubber inlet liquid flow rate above the minimum value established during the performance test. b. Maintain the daily average scrubber effluent pH within the operating range value established during the performance test. c. If you use a venturi scrubber, maintain the daily average pressure drop across the venturi within the operating range value established during the performance test.
2. Other type of control device to which flame lamination emissions are ducted.	Maintain your operating parameter(s) within the ranges established during the performance test and according to your monitoring plan.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64402, Nov. 18, 2021]

TABLE 3 TO SUBPART MMMMM OF PART 63—PERFORMANCE TEST REQUIREMENTS FOR EXISTING, NEW, OR RECONSTRUCTED FLAME LAMINATION AFFECTED SOURCES

As stated in §63.8800, you must comply with the requirements for performance tests for flame lamination affected sources in the following table using the requirements in rows 1 through 5 of the table if you are measuring HCl and using a scrubber, row 6 for new or reconstructed sources measuring HCN and using a scrubber, and row 7 if you are using any other

control device. For existing sources not using a control device, you must comply with row 8 and rows 1 through 4 of the table.

For each new or reconstructed flame lamination affected source, you must . . .	Using . . .	According to the following requirements . . .
1. Select sampling port's location and the number of traverse ports.	Method 1 or 1A in appendix A to part 60 of this chapter.	Sampling sites must be located at the inlet and outlet of the scrubber and prior to any releases to the atmosphere.
2. Determine velocity	Method 2, 2A, 2C, 2D, 2F, or 2G in appendix A to part 60 of this chapter..	
3. Determine gas molecular weight.	Not applicable	Assume a molecular weight of 29 (after moisture correction) for calculation purposes.
4. Measure moisture content of the stack gas.	Method 4 in appendix A to part 60 of this chapter..	
5. Measure HCl concentration	Method 26A in appendix A to part 60 of this chapter.	i. For new or reconstructed sources, determine the HCl reduction efficiency of the control device using Method 26A and the procedures specified in § 63.8800(e). ii. For existing sources, determine the HCl emission rate using Method 26A and the procedures specified in § 63.8800(f). iii. Collect scrubber liquid flow rate, scrubber effluent pH, and pressure drop (pressure drop data only required for venturi scrubbers) every 15 minutes during the entire duration of each 1-hour test run, and determine the average scrubber liquid flow rate, scrubber effluent pH, and pressure drop (pressure drop data only required for venturi scrubbers) over the period of the performance test by computing the average of all 15-minute readings.
6. Measure HCN concentration	A method approved by the Administrator.	i. Conduct the performance test according to the site-specific test plan submitted according to § 63.7(c)(2)(i). Measure total HCN emissions and determine the reduction efficiency of the control device. Any performance test which measures HCN concentrations must be submitted for the administrator's approval prior to testing. You must use EPA Method 301 (40 CFR part 63, Appendix A) to validate your method. ii. Collect scrubber liquid flow rate, scrubber effluent pH, and pressure drop (pressure drop data only required for venturi scrubbers) every 15 minutes during the entire duration of each 1-hour test run, and determine the average scrubber liquid flow rate, scrubber effluent pH, and pressure drop (pressure drop data only required for venturi scrubbers) over the period of the performance test by computing the average of all 15-minute readings.
7. If you use any control device other than a scrubber, establish operating parameter limits with which you will demonstrate continuous compliance with the emission limit that applies to the source.	EPA-approved methods and data from the continuous parameter monitoring system.	i. Conduct the performance test according to the site-specific test plan submitted according to § 63.7(c)(2)(i). ii. For new or reconstructed sources, determine the HCl or HCN reduction efficiency of the control device using the EPA-approved method and the procedures specified in § 63.8800(e). iii. For existing sources, determine the HCl emission rate using the EPA-approved method and the procedures specified in § 63.8800(f). iv. Collect operating parameter data as specified in the site-specific test plan.
8. Measure HCl concentration	Method 26A in appendix A to part 60 of this chapter.	Determine the HCl emission rate using the appropriate test methods and the procedures specified in § 63.8800(f).

[86 FR 64402, Nov. 18, 2021]

TABLE 4 TO SUBPART MMMMM OF PART 63—INITIAL COMPLIANCE WITH EMISSION LIMITS

As stated in § 63.8806, you must comply with the requirements to demonstrate initial compliance with the applicable emission limits in the following table:

For . . .	For the following emission limit . . .	You have demonstrated initial compliance if . . .
1. Each new, reconstructed, or existing loop slitter adhesive use affected source.	Eliminate use of HAP-based adhesives ..	You do not use HAP-based adhesives.
2. Each new or reconstructed flame lamination affected source using a scrubber.	Reduce HAP emissions by 90 percent ...	The average HAP emissions, measured over the period of the performance test(s), are reduced by 90 percent.
3. Each new or reconstructed flame lamination affected source using any other control device emissions by.	Reduce HAP emissions by 90 percent ...	The average HAP emissions, measured over the period of the performance test(s), are reduced by 90 percent.
4. Each existing flame lamination affected source.	Emit no more than 1.45 pounds per hour of HCl per flame lamination line.	The average HCl emissions, measured over the period of the performance test(s) do not exceed 1.45 pounds per hour per flame lamination line.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64403, Nov. 18, 2021]

TABLE 5 TO SUBPART MMMMM OF PART 63—CONTINUOUS COMPLIANCE WITH EMISSION LIMITS AND OPERATING LIMITS

As stated in §63.8812(a), you must comply with the requirements to demonstrate continuous compliance with the applicable emission limits or operating limits in the following table:

For . . .	For the following emission limits or operating limits . . .	You must demonstrate continuous compliance by . . .
1. Each new, reconstructed, or existing loop slitter affected source.	Eliminate use of HAP-based adhesives ..	Not using HAP-based adhesives.
2. Each existing, new, or reconstructed flame lamination affected source using a scrubber.	a. Maintain the daily average scrubber inlet liquid flow rate above the minimum value established during the performance. b. Maintain the daily average scrubber effluent pH within the operating range established during the performance test. c. Maintain the daily average pressure drop across the venturi within the operating range established during the performance test. If you use another type of scrubber (*e.g.,* packed bed or spray tower scrubber), monitoring pressure drop is not required.	i. Collecting the scrubber inlet liquid flow rate and effluent pH monitoring data according to §63.8804(a) through (c). ii. Reducing the data to 1-hour and daily block averages according to the requirements in §63.8804(a). iii. Maintaining each daily average scrubber inlet liquid flow rate above the minimum value established during the performance test. iv. Maintaining the daily average scrubber effluent pH within the operating range established during the performance test. v. If you use a venturi scrubber, maintaining the daily average pressure drop across the venturi within the operating range established during the performance test.
3. Each existing, new, or reconstructed flame lamination affected source using any other control device.	a. Maintain the daily average operating parameters above the minimum value established during the performance test, or within the range established during the performance test, as applicable.	i. Collected the operating parameter data according to the site-specific test plan. ii. Reducing the data to one-hour averages according to the requirements in §63.8804(a). iii. Maintaining the daily average during the rate above the minimum value established during the performance test, or within the range established during the performance test, as applicable.

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64403, Nov. 18, 2021]

TABLE 6 TO SUBPART MMMMM OF PART 63—REQUIREMENTS FOR REPORTS

You must submit a compliance report that includes the information in §63.8818(e) through (g) as well as the information in the following table, as applicable. Rows 1 and 3 of the following table apply to loop slitter affected sources. Rows 1 through 4 apply to flame lamination affected sources.

If . . .	Then you must submit a report or statement that . . .
1. There are no deviations from any emission limitations that apply to you.	There were no deviations from the emission limitations during the reporting period.

If . . .	Then you must submit a report or statement that . . .
2. There were no periods during which the operating parameter monitoring systems were out-of-control in accordance with the monitoring plan.	There were no periods during which the CPMS were out-of-control during the reporting period.
3. There was a deviation from any emission limitation during the reporting period.	Contains the information in §63.8818(e)(5).
4. There were periods during which the operating parameter monitoring systems were out-of-control in information in accordance with the monitoring plan.	Contains the information in §63.8818(f)(2).

[68 FR 18070, Apr. 14, 2003, as amended at 86 FR 64403, Nov. 18, 2021]

TABLE 7 TO SUBPART MMMMM OF PART 63—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART MMMMM

As stated in §63.8826, you must comply with the applicable General Provisions requirements according to the following table:

Citation	Requirement	Applies to subpart MMMMM	Explanation
§63.1	Initial applicability determination; applicability after standard established; permit requirements; extensions; notifications.	Yes.	
§63.2	Definitions	Yes	Additional definitions are found in §63.8830.
§63.3	Units and abbreviations	Yes.	
§63.4	Prohibited activities; compliance date; circumvention, severability.	Yes.	
§63.5	Construction/reconstruction applicability; applications; approvals.	Yes.	
§63.6(a)	Compliance with standards and maintenance requirements-applicability.	Yes.	
§63.6(b)(1)–(4)	Compliance dates for new or reconstructed sources.	Yes	§63.8786 specifies compliance dates.
§63.6(b)(5)	Notification if commenced construction or reconstruction after proposal.	Yes.	
§63.6(b)(6)	[Reserved]	Yes.	
§63.6(b)(7)	Compliance dates for new or reconstructed area sources that become major.	Yes	§63.8786 specifies compliance dates.
§63.6(c)(1)–(2)	Compliance dates for existing sources.	Yes	§63.8786 specifies compliance dates.
§63.6(c)(3)–(4)	[Reserved]	Yes.	
§63.6(c)(5)	Compliance dates for existing area sources that become major.	Yes	§63.8786 specifies compliance dates.
§63.6(d)	[Reserved]	Yes.	
§63.6(e)(1)(i)	General duty to minimize emissions.	No	§63.8794(c) specifies general duty requirements.
§63.6(e)(1)(ii)	Requirement to correct malfunctions as soon as possible.	No.	
§63.6(e)(1)(iii)	Enforceability of requirements independent of other regulations.	Yes.	
§63.6(e)(2)	[Reserved]	Yes.	
§63.6(e)(3)	SSM plans	No.	
§63.6(f)(1)	Compliance except during SSM	No.	
§63.6(f)(2)–(3)	Methods for determining compliance.	Yes.	
§63.6(g)	Use of an alternative nonopacity emission standard.	Yes.	
§63.6(h)	Compliance with opacity/visible emission standards.	No	Subpart MMMMM does not specify opacity or visible emission standards.
§63.6(i)	Extension of compliance with emission standards.	Yes.	

Citation	Requirement	Applies to subpart MMMMM	Explanation
§ 63.6(j)	Presidential compliance exemption.	Yes.	
§ 63.7(a)(1)–(2)	Performance test dates	Yes	Except for loop slitter affected sources as specified in § 63.8798(a).
§ 63.7(a)(3)	Administrator's section 114 authority to require a performance test.	Yes.	
§ 63.7(b)	Notification of performance test and rescheduling.	Yes.	
§ 63.7(c)	Quality assurance program and site-specific test plans.	Yes.	
§ 63.7(d)	Performance testing facilities	Yes.	
§ 63.7(e)(1)	Conditions for conducting performance tests.	No	Requirements for performance test conditions are found in § 63.8800(b) and (c).
§ 63.7(e)(2)–(3)	Performance test data reduction and number of test runs.	Yes.	
§ 63.7(f)	Use of an alternative test method.	Yes.	
§ 63.7(g)	Performance test data analysis, recordkeeping, and reporting.	Yes.	
§ 63.7(h)	Waiver of performance tests	Yes.	
§ 63.8(a)(1)–(2)	Applicability of monitoring requirements.	Yes	Unless otherwise specified, all of § 63.8 applies only to new or reconstructed flame lamination sources. Additional monitoring requirements for these sources are found in §§ 63.8794(f) and (g) and 63.8804.
§ 63.8(a)(3)	[Reserved]	Yes.	
§ 63.8(a)(4)	Monitoring with flares	No	Subpart MMMMM does not refer directly or indirectly to § 63.11.
§ 63.8(b)	Conduct of monitoring and procedures when there are multiple effluents and multiple monitoring systems.	Yes.	
§ 63.8(c)(1)–(3)	Continuous monitoring system (CMS) operation and maintenance.	No	CMS requirements are found in § 63.8794(f) and (g).
§ 63.8(c)(4)	Continuous monitoring system requirements during breakdown, out-of-control, repair, maintenance, and high-level calibration drifts.	Yes	Applies as modified by § 63.8794(g).
§ 63.8(c)(5)	Continuous opacity monitoring system (COMS) minimum procedures.	No	Subpart MMMMM does not have opacity or visible emission standards.
§ 63.8(c)(6)	Zero and high-level calibration checks.	Yes	Applies as modified by § 63.8794(f).
§ 63.8(c)(7)–(8)	Out-of-control periods, including reporting.	Yes.	
§ 63.8(d)–(e)	Quality control program and CMS performance evaluation.	No	CMS requirements are found in § 63.8794(f) and (g).
§ 63.8(f)(1)–(5)	Use of an alternative monitoring method.	Yes.	
§ 63.8(f)(6)	Alternative to relative accuracy test.	No	Only applies to sources that use continuous emissions monitoring systems (CEMS).
§ 63.8(g)	Data reduction	Yes	Applies as modified by § 63.8794(g).
§ 63.9(a)	Notification requirements—applicability.	Yes.	
§ 63.9(b)	Initial notifications	Yes	Except § 63.8816(c) requires new or reconstructed affected sources to submit the application for construction or reconstruction required by § 63.9(b)(1)(iii) in lieu of the initial notification.

Citation	Requirement	Applies to subpart MMMMM	Explanation
§63.9(c)	Request for compliance extension.	Yes.	
§63.9(d)	Notification that a new source is subject to special compliance requirements.	Yes.	
§63.9(e)	Notification of performance test	Yes.	
§63.9(f)	Notification of visible emissions/opacity test.	No	Subpart MMMMM does not have opacity or visible emission standards.
§63.9(g)(1)	Additional CMS notifications—date of CMS performance evaluation.	Yes.	
§63.9(g)(2)	Use of COMS data	No	Subpart MMMMM does not require the use of COMS.
§63.9(g)(3)	Alternative to relative accuracy testing.	No	Applies only to sources with CEMS.
§63.9(h)	Notification of compliance status	Yes.	
§63.9(i)	Adjustment of submittal deadlines.	Yes.	
§63.9(j)	Change in previous information	Yes.	
§63.9(k)	Electronic reporting procedures	Yes	Only as specified in §63.9(j).
§63.10(a)	Recordkeeping/reporting applicability.	Yes.	
§63.10(b)(1)	General recordkeeping requirements.	Yes	§§63.8820 and 63.8822 specify additional recordkeeping requirements.
§63.10(b)(2)(i) and (ii)	Records related to SSM periods and CMS.	No	See §63.8820 for recordkeeping of (1) date, time, and duration; (2) listing of affected source or equipment, and an estimate of the quantity of each regulated pollutant emitted over the standard; and (3) actions to minimize emissions and correct the failure.
§63.10(b)(2)(iii)	Records of maintenance on air pollution control equipment..	Yes.	
§63.10(b)(2)(iv) and (v)	Records related to SSM	No.	
§63.10(b)(2)(vi)–(xi)	Records of CMS and other compliance records.	Yes.	
§63.10(b)(2)(xii)	Records when under waiver	Yes.	
§63.10(b)(2)(xiii)	Records when using alternative to relative accuracy test.	No	Applies only to sources with CEMS.
§63.10(b)(2)(xiv)	All documentation supporting initial notification and notification of compliance status.	Yes.	
§63.10(b)(3)	Recordkeeping requirements for applicability determinations.	Yes.	
§63.10(c)	Additional recordkeeping requirements for sources with CMS.	Yes	Applies as modified by §63.8794(g).
§63.10(d)(1)	General reporting requirements	Yes	§63.8818 specifies additional reporting requirements.
§63.10(d)(2)	Performance test results	Yes.	
§63.10(d)(3)	Opacity or visible emissions observations.	No	Subpart MMMMM does not specify opacity or visible emission standards.
§63.10(d)(4)	Progress reports for sources with compliance extensions.	Yes.	
§63.10(d)(5)	SSM reports	No.	
§63.10(e)(1)	Additional CMS reports—general.	Yes	Applies as modified by §63.8794(g).
§63.10(e)(2)(i)	Results of CMS performance evaluations.	Yes	Applies as modified by §63.8794(g).
§63.10(e)(2)	Results of continuous opacity monitoring systems performance evaluations.	No	Subpart MMMMM does require the use of COMS.
§63.10(e)(3)	Excess emissions/CMS performance reports.	Yes	Only applies to new or reconstructed flame lamination affected sources.
§63.10(e)(4)	Continuous opacity monitoring system data reports.	No	Subpart MMMMM does not require the use of COMS.
§63.10(f)	Recordkeeping/reporting waiver	Yes.	

Citation	Requirement	Applies to subpart MMMMM	Explanation
§63.11	Control device requirements—applicability.	No	Facilities subject to subpart MMMMM do not use flares as control devices.
§63.12	State authority and delegations	Yes	§63.8828 lists those sections of subparts MMMMM and A that are not delegated.
§63.13	Addresses	Yes.	
§63.14	Incorporation by reference	Yes	Subpart MMMMM does not incorporate any material by reference.
§63.15	Availability of information/confidentiality..	Yes.	

[86 FR 64404, Nov. 18, 2021]

TABLE 8 TO SUBPART MMMMM OF PART 63—LIST OF HAZARDOUS AIR POLLUTANTS THAT MUST BE COUNTED TOWARD TOTAL HAP CONTENT IF PRESENT AT 0.1 PERCENT OR MORE BY WEIGHT

Chemical name	CAS No.
1,1,2,2-Tetrachloroethane	79–34–5
1,1,2-Trichloroethane	79–00–5
1,1-Dimethylhydrazine	57–14–7
1,2-Dibromo-3-chloropropane	96–12–8
1,2-Diphenylhydrazine	122–66–7
1,3-Butadiene	106–99–0
1,3-Dichloropropene	542–75–6
1,4-Dioxane	123–91–1
2,4,6-Trichlorophenol	88–06–2
2,4/2,6-Dinitrotoluene (mixture)	25321–14–6
2,4-Dinitrotoluene	121–14–2
2,4-Toluene diamine	95–80–7
2-Nitropropane	79–46–9
3,3′-Dichlorobenzidine	91–94–1
3,3′-Dimethoxybenzidine	119–90–4
3,3′-Dimethylbenzidine	119–93–7
4,4′-Methylene bis(2-chloroaniline)	101–14–4
Acetaldehyde	75–07–0
Acrylamide	79–06–1
Acrylonitrile	107–13–1
Allyl chloride	107–05–1
alpha-Hexachlorocyclohexane (a-HCH)	319–84–6
Aniline	62–53–3
Benzene	71–43–2
Benzidine	92–87–5
Benzotrichloride	98–07–7
Benzyl chloride	100–44–7
beta-Hexachlorocyclohexane (b-HCH)	319–85–7
Bis(2-ethylhexyl)phthalate	117–81–7
Bis(chloromethyl)ether	542–88–1
Bromoform	75–25–2
Captan	133–06–2
Carbon tetrachloride	56–23–5
Chlordane	57–74–9
Chlorobenzilate	510–15–6
Chloroform	67–66–3
Chloroprene	126–99–8
Cresols (mixed)	1319–77–3
DDE	3547–04–4
Dichloroethyl ether	111–44–4
Dichlorvos	62–73–7
Epichlorohydrin	106–89–8
Ethyl acrylate	140–88–5
Ethylene dibromide	106–93–4
Ethylene dichloride	107–06–2
Ethylene oxide	75–21–8
Ethylene thiourea	96–45–7
Ethylidene dichloride (1,1-Dichloroethane)	75–34–3
Formaldehyde	50–00–0
Heptachlor	76–44–8
Hexachlorobenzene	118–74–1

Chemical name	CAS No.
Hexachlorobutadiene	87–68–3
Hexachloroethane	67–72–1
Hydrazine	302–01–2
Isophorone	78–59–1
Lindane (hexachlorocyclohexane, all isomers)	58–89–9
m-Cresol	108–39–4
Methylene chloride	75–09–2
Naphthalene	91–20–3
Nitrobenzene	98–95–3
Nitrosodimethylamine	62–75–9
o-Cresol	95–48–7
o-Toluidine	95–53–4
Parathion	56–38–2
p-Cresol	106–44–5
p-Dichlorobenzene	106–46–7
Pentachloronitrobenzene	82–68–8
Pentachlorophenol	87–86–5
Propoxur	114–26–1
Propylene dichloride	78–87–5
Propylene oxide	75–56–9
Quinoline	91–22–5
Tetrachloroethene	127–18–4
Toxaphene	8001–35–2
Trichloroethylene	79–01–6
Trifluralin	1582–09–8
Vinyl bromide	593–60–2
Vinyl chloride	75–01–4
Vinylidene chloride	75–35–4

[86 FR 64406, Nov. 18, 2021]

FINDING AIDS

A list of CFR titles, subtitles, chapters, subchapters and parts and an alphabetical list of agencies publishing in the CFR are included in the CFR Index and Finding Aids volume to the Code of Federal Regulations which is published separately and revised annually.

Table of CFR Titles and Chapters
Alphabetical List of Agencies Appearing in the CFR
List of CFR Sections Affected

Table of CFR Titles and Chapters

(Revised as of July 1, 2024)

Title 1—General Provisions

I Administrative Committee of the Federal Register (Parts 1—49)
II Office of the Federal Register (Parts 50—299)
III Administrative Conference of the United States (Parts 300—399)
IV Miscellaneous Agencies (Parts 400—599)
VI National Capital Planning Commission (Parts 600—699)

Title 2—Grants and Agreements

SUBTITLE A—OFFICE OF MANAGEMENT AND BUDGET GUIDANCE FOR GRANTS AND AGREEMENTS
I Office of Management and Budget Governmentwide Guidance for Grants and Agreements (Parts 2—199)
II Office of Management and Budget Guidance (Parts 200—299)
SUBTITLE B—FEDERAL AGENCY REGULATIONS FOR GRANTS AND AGREEMENTS
III Department of Health and Human Services (Parts 300—399)
IV Department of Agriculture (Parts 400—499)
VI Department of State (Parts 600—699)
VII Agency for International Development (Parts 700—799)
VIII Department of Veterans Affairs (Parts 800—899)
IX Department of Energy (Parts 900—999)
X Department of the Treasury (Parts 1000—1099)
XI Department of Defense (Parts 1100—1199)
XII Department of Transportation (Parts 1200—1299)
XIII Department of Commerce (Parts 1300—1399)
XIV Department of the Interior (Parts 1400—1499)
XV Environmental Protection Agency (Parts 1500—1599)
XVI U.S. International Development Finance Corporation (Parts 1600—1699)
XVIII National Aeronautics and Space Administration (Parts 1800—1899)
XX United States Nuclear Regulatory Commission (Parts 2000—2099)
XXII Corporation for National and Community Service (Parts 2200—2299)
XXIII Social Security Administration (Parts 2300—2399)
XXIV Department of Housing and Urban Development (Parts 2400—2499)

Title 2—Grants and Agreements—Continued

Chap.

XXV National Science Foundation (Parts 2500—2599)
XXVI National Archives and Records Administration (Parts 2600—2699)
XXVII Small Business Administration (Parts 2700—2799)
XXVIII Department of Justice (Parts 2800—2899)
XXIX Department of Labor (Parts 2900—2999)
XXX Department of Homeland Security (Parts 3000—3099)
XXXI Institute of Museum and Library Services (Parts 3100—3199)
XXXII National Endowment for the Arts (Parts 3200—3299)
XXXIII National Endowment for the Humanities (Parts 3300—3399)
XXXIV Department of Education (Parts 3400—3499)
XXXV Export-Import Bank of the United States (Parts 3500—3599)
XXXVI Office of National Drug Control Policy, Executive Office of the President (Parts 3600—3699)
XXXVII Peace Corps (Parts 3700—3799)
LVIII Election Assistance Commission (Parts 5800—5899)
LIX Gulf Coast Ecosystem Restoration Council (Parts 5900—5999)
LX Federal Communications Commission (Parts 6000—6099)

Title 3—The President

I Executive Office of the President (Parts 100—199)

Title 4—Accounts

I Government Accountability Office (Parts 1—199)

Title 5—Administrative Personnel

I Office of Personnel Management (Parts 1—1199)
II Merit Systems Protection Board (Parts 1200—1299)
III Office of Management and Budget (Parts 1300—1399)
IV Office of Personnel Management and Office of the Director of National Intelligence (Parts 1400—1499)
V The International Organizations Employees Loyalty Board (Parts 1500—1599)
VI Federal Retirement Thrift Investment Board (Parts 1600—1699)
VIII Office of Special Counsel (Parts 1800—1899)
IX Appalachian Regional Commission (Parts 1900—1999)
XI Armed Forces Retirement Home (Parts 2100—2199)
XIV Federal Labor Relations Authority, General Counsel of the Federal Labor Relations Authority and Federal Service Impasses Panel (Parts 2400—2499)
XVI Office of Government Ethics (Parts 2600—2699)
XXI Department of the Treasury (Parts 3100—3199)
XXII Federal Deposit Insurance Corporation (Parts 3200—3299)
XXIII Department of Energy (Parts 3300—3399)

Title 5—Administrative Personnel—Continued

Chap.	
XXIV	Federal Energy Regulatory Commission (Parts 3400—3499)
XXV	Department of the Interior (Parts 3500—3599)
XXVI	Department of Defense (Parts 3600—3699)
XXVIII	Department of Justice (Parts 3800—3899)
XXIX	Federal Communications Commission (Parts 3900—3999)
XXX	Farm Credit System Insurance Corporation (Parts 4000—4099)
XXXI	Farm Credit Administration (Parts 4100—4199)
XXXIII	U.S. International Development Finance Corporation (Parts 4300—4399)
XXXIV	Securities and Exchange Commission (Parts 4400—4499)
XXXV	Office of Personnel Management (Parts 4500—4599)
XXXVI	Department of Homeland Security (Parts 4600—4699)
XXXVII	Federal Election Commission (Parts 4700—4799)
XL	Interstate Commerce Commission (Parts 5000—5099)
XLI	Commodity Futures Trading Commission (Parts 5100—5199)
XLII	Department of Labor (Parts 5200—5299)
XLIII	National Science Foundation (Parts 5300—5399)
XLV	Department of Health and Human Services (Parts 5500—5599)
XLVI	Postal Rate Commission (Parts 5600—5699)
XLVII	Federal Trade Commission (Parts 5700—5799)
XLVIII	Nuclear Regulatory Commission (Parts 5800—5899)
XLIX	Federal Labor Relations Authority (Parts 5900—5999)
L	Department of Transportation (Parts 6000—6099)
LII	Export-Import Bank of the United States (Parts 6200—6299)
LIII	Department of Education (Parts 6300—6399)
LIV	Environmental Protection Agency (Parts 6400—6499)
LV	National Endowment for the Arts (Parts 6500—6599)
LVI	National Endowment for the Humanities (Parts 6600—6699)
LVII	General Services Administration (Parts 6700—6799)
LVIII	Board of Governors of the Federal Reserve System (Parts 6800—6899)
LIX	National Aeronautics and Space Administration (Parts 6900—6999)
LX	United States Postal Service (Parts 7000—7099)
LXI	National Labor Relations Board (Parts 7100—7199)
LXII	Equal Employment Opportunity Commission (Parts 7200—7299)
LXIII	Inter-American Foundation (Parts 7300—7399)
LXIV	Merit Systems Protection Board (Parts 7400—7499)
LXV	Department of Housing and Urban Development (Parts 7500—7599)
LXVI	National Archives and Records Administration (Parts 7600—7699)
LXVII	Institute of Museum and Library Services (Parts 7700—7799)
LXVIII	Commission on Civil Rights (Parts 7800—7899)
LXIX	Tennessee Valley Authority (Parts 7900—7999)

Title 5—Administrative Personnel—Continued

Chap.

LXX Court Services and Offender Supervision Agency for the District of Columbia (Parts 8000—8099)

LXXI Consumer Product Safety Commission (Parts 8100—8199)

LXXIII Department of Agriculture (Parts 8300—8399)

LXXIV Federal Mine Safety and Health Review Commission (Parts 8400—8499)

LXXVI Federal Retirement Thrift Investment Board (Parts 8600—8699)

LXXVII Office of Management and Budget (Parts 8700—8799)

LXXX Federal Housing Finance Agency (Parts 9000—9099)

LXXXIII Special Inspector General for Afghanistan Reconstruction (Parts 9300—9399)

LXXXIV Bureau of Consumer Financial Protection (Parts 9400—9499)

LXXXVI National Credit Union Administration (Parts 9600—9699)

XCVII Department of Homeland Security Human Resources Management System (Department of Homeland Security—Office of Personnel Management) (Parts 9700—9799)

XCVIII Council of the Inspectors General on Integrity and Efficiency (Parts 9800—9899)

XCIX Military Compensation and Retirement Modernization Commission (Parts 9900—9999)

C National Council on Disability (Parts 10000—10049)

CI National Mediation Board (Parts 10100—10199)

CII U.S. Office of Special Counsel (Parts 10200—10299)

CIII U.S. Office of Federal Mediation and Conciliation Service (Parts 10300—10399)

CIV Office of the Intellectual Property Enforcement Coordinator (Part 10400—10499)

Title 6—Domestic Security

I Department of Homeland Security, Office of the Secretary (Parts 1—199)

X Privacy and Civil Liberties Oversight Board (Parts 1000—1099)

Title 7—Agriculture

SUBTITLE A—OFFICE OF THE SECRETARY OF AGRICULTURE (PARTS 0—26)

SUBTITLE B—REGULATIONS OF THE DEPARTMENT OF AGRICULTURE

I Agricultural Marketing Service (Standards, Inspections, Marketing Practices), Department of Agriculture (Parts 27—209)

II Food and Nutrition Service, Department of Agriculture (Parts 210—299)

III Animal and Plant Health Inspection Service, Department of Agriculture (Parts 300—399)

IV Federal Crop Insurance Corporation, Department of Agriculture (Parts 400—499)

V Agricultural Research Service, Department of Agriculture (Parts 500—599)

Title 7—Agriculture—Continued

Chap.

VI Natural Resources Conservation Service, Department of Agriculture (Parts 600—699)

VII Farm Service Agency, Department of Agriculture (Parts 700—799)

VIII Agricultural Marketing Service (Federal Grain Inspection Service, Fair Trade Practices Program), Department of Agriculture (Parts 800—899)

IX Agricultural Marketing Service (Marketing Agreements and Orders; Fruits, Vegetables, Nuts), Department of Agriculture (Parts 900—999)

X Agricultural Marketing Service (Marketing Agreements and Orders; Milk), Department of Agriculture (Parts 1000—1199)

XI Agricultural Marketing Service (Marketing Agreements and Orders; Miscellaneous Commodities), Department of Agriculture (Parts 1200—1299)

XIV Commodity Credit Corporation, Department of Agriculture (Parts 1400—1499)

XV Foreign Agricultural Service, Department of Agriculture (Parts 1500—1599)

XVI [Reserved]

XVII Rural Utilities Service, Department of Agriculture (Parts 1700—1799)

XVIII Rural Housing Service, Rural Business-Cooperative Service, Rural Utilities Service, and Farm Service Agency, Department of Agriculture (Parts 1800—2099)

XX [Reserved]

XXV Office of Advocacy and Outreach, Department of Agriculture (Parts 2500—2599)

XXVI Office of Inspector General, Department of Agriculture (Parts 2600—2699)

XXVII Office of Information Resources Management, Department of Agriculture (Parts 2700—2799)

XXVIII Office of Operations, Department of Agriculture (Parts 2800—2899)

XXIX Office of Energy Policy and New Uses, Department of Agriculture (Parts 2900—2999)

XXX Office of the Chief Financial Officer, Department of Agriculture (Parts 3000—3099)

XXXI Office of Environmental Quality, Department of Agriculture (Parts 3100—3199)

XXXII Office of Procurement and Property Management, Department of Agriculture (Parts 3200—3299)

XXXIII Office of Transportation, Department of Agriculture (Parts 3300—3399)

XXXIV National Institute of Food and Agriculture (Parts 3400—3499)

XXXV Rural Housing Service, Department of Agriculture (Parts 3500—3599)

XXXVI National Agricultural Statistics Service, Department of Agriculture (Parts 3600—3699)

Title 7—Agriculture—Continued

Chap.

XXXVII Economic Research Service, Department of Agriculture (Parts 3700—3799)

XXXVIII World Agricultural Outlook Board, Department of Agriculture (Parts 3800—3899)

XLI [Reserved]

XLII Rural Business-Cooperative Service, Department of Agriculture (Parts 4200—4299)

L Rural Business-Cooperative Service, Rural Housing Service, and Rural Utilities Service, Department of Agriculture (Parts 5000—5099)

Title 8—Aliens and Nationality

I Department of Homeland Security (Parts 1—499)

V Executive Office for Immigration Review, Department of Justice (Parts 1000—1399)

Title 9—Animals and Animal Products

I Animal and Plant Health Inspection Service, Department of Agriculture (Parts 1—199)

II Agricultural Marketing Service (Fair Trade Practices Program), Department of Agriculture (Parts 200—299)

III Food Safety and Inspection Service, Department of Agriculture (Parts 300—599)

Title 10—Energy

I Nuclear Regulatory Commission (Parts 0—199)

II Department of Energy (Parts 200—699)

III Department of Energy (Parts 700—999)

X Department of Energy (General Provisions) (Parts 1000—1099)

XIII Nuclear Waste Technical Review Board (Parts 1300—1399)

XVII Defense Nuclear Facilities Safety Board (Parts 1700—1799)

XVIII Northeast Interstate Low-Level Radioactive Waste Commission (Parts 1800—1899)

Title 11—Federal Elections

I Federal Election Commission (Parts 1—9099)

II Election Assistance Commission (Parts 9400—9499)

Title 12—Banks and Banking

I Comptroller of the Currency, Department of the Treasury (Parts 1—199)

II Federal Reserve System (Parts 200—299)

III Federal Deposit Insurance Corporation (Parts 300—399)

Title 12—Banks and Banking—Continued

Chap.

IV Export-Import Bank of the United States (Parts 400—499)

V (Parts 500—599) [Reserved]

VI Farm Credit Administration (Parts 600—699)

VII National Credit Union Administration (Parts 700—799)

VIII Federal Financing Bank (Parts 800—899)

IX (Parts 900—999)[Reserved]

X Consumer Financial Protection Bureau (Parts 1000—1099)

XI Federal Financial Institutions Examination Council (Parts 1100—1199)

XII Federal Housing Finance Agency (Parts 1200—1299)

XIII Financial Stability Oversight Council (Parts 1300—1399)

XIV Farm Credit System Insurance Corporation (Parts 1400—1499)

XV Department of the Treasury (Parts 1500—1599)

XVI Office of Financial Research, Department of the Treasury (Parts 1600—1699)

XVII Office of Federal Housing Enterprise Oversight, Department of Housing and Urban Development (Parts 1700—1799)

XVIII Community Development Financial Institutions Fund, Department of the Treasury (Parts 1800—1899)

Title 13—Business Credit and Assistance

I Small Business Administration (Parts 1—199)

III Economic Development Administration, Department of Commerce (Parts 300—399)

IV Emergency Steel Guarantee Loan Board (Parts 400—499)

V Emergency Oil and Gas Guaranteed Loan Board (Parts 500—599)

Title 14—Aeronautics and Space

I Federal Aviation Administration, Department of Transportation (Parts 1—199)

II Office of the Secretary, Department of Transportation (Aviation Proceedings) (Parts 200—399)

III Commercial Space Transportation, Federal Aviation Administration, Department of Transportation (Parts 400—1199)

V National Aeronautics and Space Administration (Parts 1200—1299)

VI Air Transportation System Stabilization (Parts 1300—1399)

Title 15—Commerce and Foreign Trade

SUBTITLE A—OFFICE OF THE SECRETARY OF COMMERCE (PARTS 0—29)

SUBTITLE B—REGULATIONS RELATING TO COMMERCE AND FOREIGN TRADE

I Bureau of the Census, Department of Commerce (Parts 30—199)

Title 15—Commerce and Foreign Trade—Continued

Chap.

II National Institute of Standards and Technology, Department of Commerce (Parts 200—299)

III International Trade Administration, Department of Commerce (Parts 300—399)

IV Foreign-Trade Zones Board, Department of Commerce (Parts 400—499)

VII Bureau of Industry and Security, Department of Commerce (Parts 700—799)

VIII Bureau of Economic Analysis, Department of Commerce (Parts 800—899)

IX National Oceanic and Atmospheric Administration, Department of Commerce (Parts 900—999)

XI National Technical Information Service, Department of Commerce (Parts 1100—1199)

XIII East-West Foreign Trade Board (Parts 1300—1399)

XIV Minority Business Development Agency (Parts 1400—1499)

XV Office of the Under-Secretary for Economic Affairs, Department of Commerce (Parts 1500—1599)

SUBTITLE C—REGULATIONS RELATING TO FOREIGN TRADE AGREEMENTS

XX Office of the United States Trade Representative (Parts 2000—2099)

SUBTITLE D—REGULATIONS RELATING TO TELECOMMUNICATIONS AND INFORMATION

XXIII National Telecommunications and Information Administration, Department of Commerce (Parts 2300—2399) [Reserved]

Title 16—Commercial Practices

I Federal Trade Commission (Parts 0—999)

II Consumer Product Safety Commission (Parts 1000—1799)

Title 17—Commodity and Securities Exchanges

I Commodity Futures Trading Commission (Parts 1—199)

II Securities and Exchange Commission (Parts 200—399)

IV Department of the Treasury (Parts 400—499)

Title 18—Conservation of Power and Water Resources

I Federal Energy Regulatory Commission, Department of Energy (Parts 1—399)

III Delaware River Basin Commission (Parts 400—499)

VI Water Resources Council (Parts 700—799)

VIII Susquehanna River Basin Commission (Parts 800—899)

XIII Tennessee Valley Authority (Parts 1300—1399)

Title 19—Customs Duties

Chap.

I U.S. Customs and Border Protection, Department of Homeland Security; Department of the Treasury (Parts 0—199)

II United States International Trade Commission (Parts 200—299)

III International Trade Administration, Department of Commerce (Parts 300—399)

IV U.S. Immigration and Customs Enforcement, Department of Homeland Security (Parts 400—599) [Reserved]

Title 20—Employees' Benefits

I Office of Workers' Compensation Programs, Department of Labor (Parts 1—199)

II Railroad Retirement Board (Parts 200—399)

III Social Security Administration (Parts 400—499)

IV Employees' Compensation Appeals Board, Department of Labor (Parts 500—599)

V Employment and Training Administration, Department of Labor (Parts 600—699)

VI Office of Workers' Compensation Programs, Department of Labor (Parts 700—799)

VII Benefits Review Board, Department of Labor (Parts 800—899)

VIII Joint Board for the Enrollment of Actuaries (Parts 900—999)

IX Office of the Assistant Secretary for Veterans' Employment and Training Service, Department of Labor (Parts 1000—1099)

Title 21—Food and Drugs

I Food and Drug Administration, Department of Health and Human Services (Parts 1—1299)

II Drug Enforcement Administration, Department of Justice (Parts 1300—1399)

III Office of National Drug Control Policy (Parts 1400—1499)

Title 22—Foreign Relations

I Department of State (Parts 1—199)

II Agency for International Development (Parts 200—299)

III Peace Corps (Parts 300—399)

IV International Joint Commission, United States and Canada (Parts 400—499)

V United States Agency for Global Media (Parts 500—599)

VII U.S. International Development Finance Corporation (Parts 700—799)

IX Foreign Service Grievance Board (Parts 900—999)

X Inter-American Foundation (Parts 1000—1099)

XI International Boundary and Water Commission, United States and Mexico, United States Section (Parts 1100—1199)

Title 22—Foreign Relations—Continued

Chap.

XII United States International Development Cooperation Agency (Parts 1200—1299)

XIII Millennium Challenge Corporation (Parts 1300—1399)

XIV Foreign Service Labor Relations Board; Federal Labor Relations Authority; General Counsel of the Federal Labor Relations Authority; and the Foreign Service Impasse Disputes Panel (Parts 1400—1499)

XV African Development Foundation (Parts 1500—1599)

XVI Japan-United States Friendship Commission (Parts 1600—1699)

XVII United States Institute of Peace (Parts 1700—1799)

Title 23—Highways

I Federal Highway Administration, Department of Transportation (Parts 1—999)

II National Highway Traffic Safety Administration and Federal Highway Administration, Department of Transportation (Parts 1200—1299)

III National Highway Traffic Safety Administration, Department of Transportation (Parts 1300—1399)

Title 24—Housing and Urban Development

SUBTITLE A—OFFICE OF THE SECRETARY, DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (PARTS 0—99)

SUBTITLE B—REGULATIONS RELATING TO HOUSING AND URBAN DEVELOPMENT

I Office of Assistant Secretary for Equal Opportunity, Department of Housing and Urban Development (Parts 100—199)

II Office of Assistant Secretary for Housing-Federal Housing Commissioner, Department of Housing and Urban Development (Parts 200—299)

III Government National Mortgage Association, Department of Housing and Urban Development (Parts 300—399)

IV Office of Housing and Office of Multifamily Housing Assistance Restructuring, Department of Housing and Urban Development (Parts 400—499)

V Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 500—599)

VI Office of Assistant Secretary for Community Planning and Development, Department of Housing and Urban Development (Parts 600—699) [Reserved]

VII Office of the Secretary, Department of Housing and Urban Development (Housing Assistance Programs and Public and Indian Housing Programs) (Parts 700—799)

Title 24—Housing and Urban Development—Continued

Chap.

VIII Office of the Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Section 8 Housing Assistance Programs, Section 202 Direct Loan Program, Section 202 Supportive Housing for the Elderly Program and Section 811 Supportive Housing for Persons With Disabilities Program) (Parts 800—899)

IX Office of Assistant Secretary for Public and Indian Housing, Department of Housing and Urban Development (Parts 900—1699)

X Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Interstate Land Sales Registration Program) (Parts 1700—1799) [Reserved]

XII Office of Inspector General, Department of Housing and Urban Development (Parts 2000—2099)

XV Emergency Mortgage Insurance and Loan Programs, Department of Housing and Urban Development (Parts 2700—2799) [Reserved]

XX Office of Assistant Secretary for Housing—Federal Housing Commissioner, Department of Housing and Urban Development (Parts 3200—3899)

XXIV Board of Directors of the HOPE for Homeowners Program (Parts 4000—4099) [Reserved]

XXV Neighborhood Reinvestment Corporation (Parts 4100—4199)

Title 25—Indians

I Bureau of Indian Affairs, Department of the Interior (Parts 1—299)

II Indian Arts and Crafts Board, Department of the Interior (Parts 300—399)

III National Indian Gaming Commission, Department of the Interior (Parts 500—599)

IV Office of Navajo and Hopi Indian Relocation (Parts 700—899)

V Bureau of Indian Affairs, Department of the Interior, and Indian Health Service, Department of Health and Human Services (Part 900—999)

VI Office of the Assistant Secretary, Indian Affairs, Department of the Interior (Parts 1000—1199)

VII Office of the Special Trustee for American Indians, Department of the Interior (Parts 1200—1299)

Title 26—Internal Revenue

I Internal Revenue Service, Department of the Treasury (Parts 1—End)

Title 27—Alcohol, Tobacco Products and Firearms

I Alcohol and Tobacco Tax and Trade Bureau, Department of the Treasury (Parts 1—399)

Title 27—Alcohol, Tobacco Products and Firearms—Continued

Chap.

II Bureau of Alcohol, Tobacco, Firearms, and Explosives, Department of Justice (Parts 400—799)

Title 28—Judicial Administration

I Department of Justice (Parts 0—299)

III Federal Prison Industries, Inc., Department of Justice (Parts 300—399)

V Bureau of Prisons, Department of Justice (Parts 500—599)

VI Offices of Independent Counsel, Department of Justice (Parts 600—699)

VII Office of Independent Counsel (Parts 700—799)

VIII Court Services and Offender Supervision Agency for the District of Columbia (Parts 800—899)

IX National Crime Prevention and Privacy Compact Council (Parts 900—999)

XI Department of Justice and Department of State (Parts 1100—1199)

Title 29—Labor

SUBTITLE A—OFFICE OF THE SECRETARY OF LABOR (PARTS 0—99)

SUBTITLE B—REGULATIONS RELATING TO LABOR

I National Labor Relations Board (Parts 100—199)

II Office of Labor-Management Standards, Department of Labor (Parts 200—299)

III National Railroad Adjustment Board (Parts 300—399)

IV Office of Labor-Management Standards, Department of Labor (Parts 400—499)

V Wage and Hour Division, Department of Labor (Parts 500—899)

IX Construction Industry Collective Bargaining Commission (Parts 900—999)

X National Mediation Board (Parts 1200—1299)

XII Federal Mediation and Conciliation Service (Parts 1400—1499)

XIV Equal Employment Opportunity Commission (Parts 1600—1699)

XVII Occupational Safety and Health Administration, Department of Labor (Parts 1900—1999)

XX Occupational Safety and Health Review Commission (Parts 2200—2499)

XXV Employee Benefits Security Administration, Department of Labor (Parts 2500—2599)

XXVII Federal Mine Safety and Health Review Commission (Parts 2700—2799)

XL Pension Benefit Guaranty Corporation (Parts 4000—4999)

Title 30—Mineral Resources

Chap.

I Mine Safety and Health Administration, Department of Labor (Parts 1—199)

II Bureau of Safety and Environmental Enforcement, Department of the Interior (Parts 200—299)

IV Geological Survey, Department of the Interior (Parts 400—499)

V Bureau of Ocean Energy Management, Department of the Interior (Parts 500—599)

VII Office of Surface Mining Reclamation and Enforcement, Department of the Interior (Parts 700—999)

XII Office of Natural Resources Revenue, Department of the Interior (Parts 1200—1299)

Title 31—Money and Finance: Treasury

SUBTITLE A—OFFICE OF THE SECRETARY OF THE TREASURY (PARTS 0—50)

SUBTITLE B—REGULATIONS RELATING TO MONEY AND FINANCE

I Monetary Offices, Department of the Treasury (Parts 51—199)

II Fiscal Service, Department of the Treasury (Parts 200—399)

IV Secret Service, Department of the Treasury (Parts 400—499)

V Office of Foreign Assets Control, Department of the Treasury (Parts 500—599)

VI Bureau of Engraving and Printing, Department of the Treasury (Parts 600—699)

VII Federal Law Enforcement Training Center, Department of the Treasury (Parts 700—799)

VIII Office of Investment Security, Department of the Treasury (Parts 800—899)

IX Federal Claims Collection Standards (Department of the Treasury—Department of Justice) (Parts 900—999)

X Financial Crimes Enforcement Network, Department of the Treasury (Parts 1000—1099)

Title 32—National Defense

SUBTITLE A—DEPARTMENT OF DEFENSE

I Office of the Secretary of Defense (Parts 1—399)

V Department of the Army (Parts 400—699)

VI Department of the Navy (Parts 700—799)

VII Department of the Air Force (Parts 800—1099)

SUBTITLE B—OTHER REGULATIONS RELATING TO NATIONAL DEFENSE

XII Department of Defense, Defense Logistics Agency (Parts 1200—1299)

XVI Selective Service System (Parts 1600—1699)

XVII Office of the Director of National Intelligence (Parts 1700—1799)

XVIII National Counterintelligence Center (Parts 1800—1899)

XIX Central Intelligence Agency (Parts 1900—1999)

Title 32—National Defense—Continued

Chap.

XX Information Security Oversight Office, National Archives and Records Administration (Parts 2000—2099)

XXI National Security Council (Parts 2100—2199)

XXIV Office of Science and Technology Policy (Parts 2400—2499)

XXVII Office for Micronesian Status Negotiations (Parts 2700—2799)

XXVIII Office of the Vice President of the United States (Parts 2800—2899)

Title 33—Navigation and Navigable Waters

I Coast Guard, Department of Homeland Security (Parts 1—199)

II Corps of Engineers, Department of the Army, Department of Defense (Parts 200—399)

IV Great Lakes St. Lawrence Seaway Development Corporation, Department of Transportation (Parts 400—499)

Title 34—Education

SUBTITLE A—OFFICE OF THE SECRETARY, DEPARTMENT OF EDUCATION (PARTS 1—99)

SUBTITLE B—REGULATIONS OF THE OFFICES OF THE DEPARTMENT OF EDUCATION

I Office for Civil Rights, Department of Education (Parts 100—199)

II Office of Elementary and Secondary Education, Department of Education (Parts 200—299)

III Office of Special Education and Rehabilitative Services, Department of Education (Parts 300—399)

IV Office of Career, Technical, and Adult Education, Department of Education (Parts 400—499)

V Office of Bilingual Education and Minority [Reserved]

VI Office of Postsecondary Education, Department of Education (Parts 600—699)

VII Office of Educational Research and Improvement, Department of Education (Parts 700—799) [Reserved]

SUBTITLE C—REGULATIONS RELATING TO EDUCATION

XI [Reserved]

XII National Council on Disability (Parts 1200—1299)

Title 35 [Reserved]

Title 36—Parks, Forests, and Public Property

I National Park Service, Department of the Interior (Parts 1—199)

II Forest Service, Department of Agriculture (Parts 200—299)

III Corps of Engineers, Department of the Army (Parts 300—399)

IV American Battle Monuments Commission (Parts 400—499)

V Smithsonian Institution (Parts 500—599)

VI [Reserved]

Title 36—Parks, Forests, and Public Property—Continued

Chap.

VII Library of Congress (Parts 700—799)

VIII Advisory Council on Historic Preservation (Parts 800—899)

IX Pennsylvania Avenue Development Corporation (Parts 900—999)

X Presidio Trust (Parts 1000—1099)

XI Architectural and Transportation Barriers Compliance Board (Parts 1100—1199)

XII National Archives and Records Administration (Parts 1200—1299)

XV Oklahoma City National Memorial Trust (Parts 1500—1599)

XVI Morris K. Udall Scholarship and Excellence in National Environmental Policy Foundation (Parts 1600—1699)

Title 37—Patents, Trademarks, and Copyrights

I United States Patent and Trademark Office, Department of Commerce (Parts 1—199)

II U.S. Copyright Office, Library of Congress (Parts 200—299)

III Copyright Royalty Board, Library of Congress (Parts 300—399)

IV National Institute of Standards and Technology, Department of Commerce (Parts 400—599)

Title 38—Pensions, Bonuses, and Veterans' Relief

I Department of Veterans Affairs (Parts 0—199)

II Armed Forces Retirement Home (Parts 200—299)

Title 39—Postal Service

I United States Postal Service (Parts 1—999)

III Postal Regulatory Commission (Parts 3000—3099)

Title 40—Protection of Environment

I Environmental Protection Agency (Parts 1—1099)

IV Environmental Protection Agency and Department of Justice (Parts 1400—1499)

V Council on Environmental Quality (Parts 1500—1599)

VI Chemical Safety and Hazard Investigation Board (Parts 1600—1699)

VII Environmental Protection Agency and Department of Defense; Uniform National Discharge Standards for Vessels of the Armed Forces (Parts 1700—1799)

VIII Gulf Coast Ecosystem Restoration Council (Parts 1800—1899)

IX Federal Permitting Improvement Steering Council (Part 1900)

Title 41—Public Contracts and Property Management

SUBTITLE A—FEDERAL PROCUREMENT REGULATIONS SYSTEM [NOTE]

Title 41—Public Contracts and Property Management—Continued

Chap.

SUBTITLE B—OTHER PROVISIONS RELATING TO PUBLIC CONTRACTS

50 Public Contracts, Department of Labor (Parts 50–1—50–999)

51 Committee for Purchase From People Who Are Blind or Severely Disabled (Parts 51–1—51–99)

60 Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor (Parts 60–1—60–999)

61 Office of the Assistant Secretary for Veterans' Employment and Training Service, Department of Labor (Parts 61–1—61–999)

62—100 [Reserved]

SUBTITLE C—FEDERAL PROPERTY MANAGEMENT REGULATIONS SYSTEM

101 Federal Property Management Regulations (Parts 101–1—101–99)

102 Federal Management Regulation (Parts 102–1—102–299)

103—104 [Reserved]

105 General Services Administration (Parts 105–1—105–999)

109 Department of Energy Property Management Regulations (Parts 109–1—109–99)

114 Department of the Interior (Parts 114–1—114–99)

115 Environmental Protection Agency (Parts 115–1—115–99)

128 Department of Justice (Parts 128–1—128–99)

129—200 [Reserved]

SUBTITLE D—FEDERAL ACQUISITION SUPPLY CHAIN SECURITY

201 Federal Acquisition Security Council (Parts 201–1—201–99)

SUBTITLE E [RESERVED]

SUBTITLE F—FEDERAL TRAVEL REGULATION SYSTEM

300 General (Parts 300–1—300–99)

301 Temporary Duty (TDY) Travel Allowances (Parts 301–1—301–99)

302 Relocation Allowances (Parts 302–1—302–99)

303 Payment of Expenses Connected with the Death of Certain Employees (Part 303–1—303–99)

304 Payment of Travel Expenses from a Non-Federal Source (Parts 304–1—304–99)

Title 42—Public Health

I Public Health Service, Department of Health and Human Services (Parts 1—199)

II—III [Reserved]

IV Centers for Medicare & Medicaid Services, Department of Health and Human Services (Parts 400—699)

V Office of Inspector General-Health Care, Department of Health and Human Services (Parts 1000—1099)

Title 43—Public Lands: Interior

SUBTITLE A—OFFICE OF THE SECRETARY OF THE INTERIOR (PARTS 1—199)

Title 43—Public Lands: Interior—Continued

Chap.

SUBTITLE B—REGULATIONS RELATING TO PUBLIC LANDS

I Bureau of Reclamation, Department of the Interior (Parts 400—999)

II Bureau of Land Management, Department of the Interior (Parts 1000—9999)

III Utah Reclamation Mitigation and Conservation Commission (Parts 10000—10099)

Title 44—Emergency Management and Assistance

I Federal Emergency Management Agency, Department of Homeland Security (Parts 0—399)

IV Department of Commerce and Department of Transportation (Parts 400—499)

Title 45—Public Welfare

SUBTITLE A—DEPARTMENT OF HEALTH AND HUMAN SERVICES (PARTS 1—199)

SUBTITLE B—REGULATIONS RELATING TO PUBLIC WELFARE

II Office of Family Assistance (Assistance Programs), Administration for Children and Families, Department of Health and Human Services (Parts 200—299)

III Office of Child Support Services, Administration of Families and Services, Department of Health and Human Services (Parts 300—399)

IV Office of Refugee Resettlement, Administration for Children and Families, Department of Health and Human Services (Parts 400—499)

V Foreign Claims Settlement Commission of the United States, Department of Justice (Parts 500—599)

VI National Science Foundation (Parts 600—699)

VII Commission on Civil Rights (Parts 700—799)

VIII Office of Personnel Management (Parts 800—899)

IX Denali Commission (Parts 900—999)

X Office of Community Services, Administration for Children and Families, Department of Health and Human Services (Parts 1000—1099)

XI National Foundation on the Arts and the Humanities (Parts 1100—1199)

XII Corporation for National and Community Service (Parts 1200—1299)

XIII Administration for Children and Families, Department of Health and Human Services (Parts 1300—1399)

XVI Legal Services Corporation (Parts 1600—1699)

XVII National Commission on Libraries and Information Science (Parts 1700—1799)

XVIII Harry S. Truman Scholarship Foundation (Parts 1800—1899)

XXI Commission of Fine Arts (Parts 2100—2199)

Title 45—Public Welfare—Continued

Chap.

XXIII Arctic Research Commission (Parts 2300—2399)

XXIV James Madison Memorial Fellowship Foundation (Parts 2400—2499)

XXV Corporation for National and Community Service (Parts 2500—2599)

Title 46—Shipping

I Coast Guard, Department of Homeland Security (Parts 1—199)

II Maritime Administration, Department of Transportation (Parts 200—399)

III Coast Guard (Great Lakes Pilotage), Department of Homeland Security (Parts 400—499)

IV Federal Maritime Commission (Parts 500—599)

Title 47—Telecommunication

I Federal Communications Commission (Parts 0—199)

II Office of Science and Technology Policy and National Security Council (Parts 200—299)

III National Telecommunications and Information Administration, Department of Commerce (Parts 300—399)

IV National Telecommunications and Information Administration, Department of Commerce, and National Highway Traffic Safety Administration, Department of Transportation (Parts 400—499)

V The First Responder Network Authority (Parts 500—599)

Title 48—Federal Acquisition Regulations System

1 Federal Acquisition Regulation (Parts 1—99)

2 Defense Acquisition Regulations System, Department of Defense (Parts 200—299)

3 Health and Human Services (Parts 300—399)

4 Department of Agriculture (Parts 400—499)

5 General Services Administration (Parts 500—599)

6 Department of State (Parts 600—699)

7 Agency for International Development (Parts 700—799)

8 Department of Veterans Affairs (Parts 800—899)

9 Department of Energy (Parts 900—999)

10 Department of the Treasury (Parts 1000—1099)

12 Department of Transportation (Parts 1200—1299)

13 Department of Commerce (Parts 1300—1399)

14 Department of the Interior (Parts 1400—1499)

15 Environmental Protection Agency (Parts 1500—1599)

16 Office of Personnel Management, Federal Employees Health Benefits Acquisition Regulation (Parts 1600—1699)

17 Office of Personnel Management (Parts 1700—1799)

Title 48—Federal Acquisition Regulations System—Continued

Chap.

18 National Aeronautics and Space Administration (Parts 1800—1899)

19 Broadcasting Board of Governors (Parts 1900—1999)

20 Nuclear Regulatory Commission (Parts 2000—2099)

21 Office of Personnel Management, Federal Employees Group Life Insurance Federal Acquisition Regulation (Parts 2100—2199)

23 Social Security Administration (Parts 2300—2399)

24 Department of Housing and Urban Development (Parts 2400—2499)

25 National Science Foundation (Parts 2500—2599)

28 Department of Justice (Parts 2800—2899)

29 Department of Labor (Parts 2900—2999)

30 Department of Homeland Security, Homeland Security Acquisition Regulation (HSAR) (Parts 3000—3099)

34 Department of Education Acquisition Regulation (Parts 3400—3499)

51 Department of the Army Acquisition Regulations (Parts 5100—5199) [Reserved]

52 Department of the Navy Acquisition Regulations (Parts 5200—5299)

53 Department of the Air Force Federal Acquisition Regulation Supplement (Parts 5300—5399) [Reserved]

54 Defense Logistics Agency, Department of Defense (Parts 5400—5499)

57 African Development Foundation (Parts 5700—5799)

61 Civilian Board of Contract Appeals, General Services Administration (Parts 6100—6199)

99 Cost Accounting Standards Board, Office of Federal Procurement Policy, Office of Management and Budget (Parts 9900—9999)

Title 49—Transportation

SUBTITLE A—OFFICE OF THE SECRETARY OF TRANSPORTATION (PARTS 1—99)

SUBTITLE B—OTHER REGULATIONS RELATING TO TRANSPORTATION

I Pipeline and Hazardous Materials Safety Administration, Department of Transportation (Parts 100—199)

II Federal Railroad Administration, Department of Transportation (Parts 200—299)

III Federal Motor Carrier Safety Administration, Department of Transportation (Parts 300—399)

IV Coast Guard, Department of Homeland Security (Parts 400—499)

V National Highway Traffic Safety Administration, Department of Transportation (Parts 500—599)

VI Federal Transit Administration, Department of Transportation (Parts 600—699)

VII National Railroad Passenger Corporation (AMTRAK) (Parts 700—799)

Title 49—Transportation—Continued

Chap.

VIII National Transportation Safety Board (Parts 800—999)

X Surface Transportation Board (Parts 1000—1399)

XI Research and Innovative Technology Administration, Department of Transportation (Parts 1400—1499) [Reserved]

XII Transportation Security Administration, Department of Homeland Security (Parts 1500—1699)

Title 50—Wildlife and Fisheries

I United States Fish and Wildlife Service, Department of the Interior (Parts 1—199)

II National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 200—299)

III International Fishing and Related Activities (Parts 300—399)

IV Joint Regulations (United States Fish and Wildlife Service, Department of the Interior and National Marine Fisheries Service, National Oceanic and Atmospheric Administration, Department of Commerce); Endangered Species Committee Regulations (Parts 400—499)

V Marine Mammal Commission (Parts 500—599)

VI Fishery Conservation and Management, National Oceanic and Atmospheric Administration, Department of Commerce (Parts 600—699)

Alphabetical List of Agencies Appearing in the CFR

(Revised as of July 1, 2024)

Agency	CFR Title, Subtitle or Chapter
Administrative Conference of the United States	1, III
Advisory Council on Historic Preservation	36, VIII
Advocacy and Outreach, Office of	7, XXV
Afghanistan Reconstruction, Special Inspector General for	5, LXXXIII
African Development Foundation	22, XV
Federal Acquisition Regulation	48, 57
Agency for International Development	2, VII; 22, II
Federal Acquisition Regulation	48, 7
Agricultural Marketing Service	7, I, VIII, IX, X, XI; 9, II
Agricultural Research Service	7, V
Agriculture, Department of	2, IV; 5, LXXIII
Advocacy and Outreach, Office of	7, XXV
Agricultural Marketing Service	7, I, VIII, IX, X, XI; 9, II
Agricultural Research Service	7, V
Animal and Plant Health Inspection Service	7, III; 9, I
Chief Financial Officer, Office of	7, XXX
Commodity Credit Corporation	7, XIV
Economic Research Service	7, XXXVII
Energy Policy and New Uses, Office of	2, IX; 7, XXIX
Environmental Quality, Office of	7, XXXI
Farm Service Agency	7, VII, XVIII
Federal Acquisition Regulation	48, 4
Federal Crop Insurance Corporation	7, IV
Food and Nutrition Service	7, II
Food Safety and Inspection Service	9, III
Foreign Agricultural Service	7, XV
Forest Service	36, II
Information Resources Management, Office of	7, XXVII
Inspector General, Office of	7, XXVI
National Agricultural Library	7, XLI
National Agricultural Statistics Service	7, XXXVI
National Institute of Food and Agriculture	7, XXXIV
Natural Resources Conservation Service	7, VI
Operations, Office of	7, XXVIII
Procurement and Property Management, Office of	7, XXXII
Rural Business-Cooperative Service	7, XVIII, XLII
Rural Development Administration	7, XLII
Rural Housing Service	7, XVIII, XXXV
Rural Utilities Service	7, XVII, XVIII, XLII
Secretary of Agriculture, Office of	7, Subtitle A
Transportation, Office of	7, XXXIII
World Agricultural Outlook Board	7, XXXVIII
Air Force, Department of	32, VII
Federal Acquisition Regulation Supplement	48, 53
Air Transportation Stabilization Board	14, VI
Alcohol and Tobacco Tax and Trade Bureau	27, I
Alcohol, Tobacco, Firearms, and Explosives, Bureau of	27, II
AMTRAK	49, VII
American Battle Monuments Commission	36, IV
American Indians, Office of the Special Trustee	25, VII
Animal and Plant Health Inspection Service	7, III; 9, I
Appalachian Regional Commission	5, IX
Architectural and Transportation Barriers Compliance Board	36, XI

Agency	CFR Title, Subtitle or Chapter
Arctic Research Commission	45, XXIII
Armed Forces Retirement Home	5, XI; 38, II
Army, Department of	32, V
Engineers, Corps of	33, II; 36, III
Federal Acquisition Regulation	48, 51
Benefits Review Board	20, VII
Bilingual Education and Minority Languages Affairs, Office of	34, V
Blind or Severely Disabled, Committee for Purchase from People Who Are	41, 51
Federal Acquisition Regulation	48, 19
Career, Technical, and Adult Education, Office of	34, IV
Census Bureau	15, I
Centers for Medicare & Medicaid Services	42, IV
Central Intelligence Agency	32, XIX
Chemical Safety and Hazard Investigation Board	40, VI
Chief Financial Officer, Office of	7, XXX
Child Support Services, Office of	45, III
Children and Families, Administration for	45, II, IV, X, XIII
Civil Rights, Commission on	5, LXVIII; 45, VII
Civil Rights, Office for	34, I
Coast Guard	33, I; 46, I; 49, IV
Coast Guard (Great Lakes Pilotage)	46, III
Commerce, Department of	2, XIII; 44, IV; 50, VI
Census Bureau	15, I
Economic Affairs, Office of the Under-Secretary for	15, XV
Economic Analysis, Bureau of	15, VIII
Economic Development Administration	13, III
Emergency Management and Assistance	44, IV
Federal Acquisition Regulation	48, 13
Foreign-Trade Zones Board	15, IV
Industry and Security, Bureau of	15, VII
International Trade Administration	15, III; 19, III
National Institute of Standards and Technology	15, II; 37, IV
National Marine Fisheries Service	50, II, IV
National Oceanic and Atmospheric Administration	15, IX; 50, II, III, IV, VI
National Technical Information Service	15, XI
National Telecommunications and Information Administration	15, XXIII; 47, III, IV
National Weather Service	15, IX
Patent and Trademark Office, United States	37, I
Secretary of Commerce, Office of	15, Subtitle A
Commercial Space Transportation	14, III
Commodity Credit Corporation	7, XIV
Commodity Futures Trading Commission	5, XLI; 17, I
Community Planning and Development, Office of Assistant Secretary for	24, V, VI
Community Services, Office of	45, X
Comptroller of the Currency	12, I
Construction Industry Collective Bargaining Commission	29, IX
Consumer Financial Protection Bureau	5, LXXXIV; 12, X
Consumer Product Safety Commission	5, LXXI; 16, II
Copyright Royalty Board	37, III
Corporation for National and Community Service	2, XXII; 45, XII, XXV
Cost Accounting Standards Board	48, 99
Council on Environmental Quality	40, V
Council of the Inspectors General on Integrity and Efficiency	5, XCVIII
Court Services and Offender Supervision Agency for the District of Columbia	5, LXX; 28, VIII
Customs and Border Protection	19, I
Defense, Department of	2, XI; 5, XXVI; 32, Subtitle A; 40, VII
Advanced Research Projects Agency	32, I
Air Force Department	32, VII
Army Department	32, V; 33, II; 36, III; 48, 51
Defense Acquisition Regulations System	48, 2
Defense Intelligence Agency	32, I

Agency	CFR Title, Subtitle or Chapter
Defense Logistics Agency	32, I, XII; 48, 54
Engineers, Corps of	33, II; 36, III
National Imagery and Mapping Agency	32, I
Navy, Department of	32, VI; 48, 52
Secretary of Defense, Office of	2, XI; 32, I
Defense Contract Audit Agency	32, I
Defense Intelligence Agency	32, I
Defense Logistics Agency	32, XII; 48, 54
Defense Nuclear Facilities Safety Board	10, XVII
Delaware River Basin Commission	18, III
Denali Commission	45, IX
Disability, National Council on	5, C; 34, XII
District of Columbia, Court Services and Offender Supervision Agency for the	5, LXX; 28, VIII
Drug Enforcement Administration	21, II
East-West Foreign Trade Board	15, XIII
Economic Affairs, Office of the Under-Secretary for	15, XV
Economic Analysis, Bureau of	15, VIII
Economic Development Administration	13, III
Economic Research Service	7, XXXVII
Education, Department of	2, XXXIV; 5, LIII
Bilingual Education and Minority Languages Affairs, Office of	34, V
Career, Technical, and Adult Education, Office of	34, IV
Civil Rights, Office for	34, I
Educational Research and Improvement, Office of	34, VII
Elementary and Secondary Education, Office of	34, II
Federal Acquisition Regulation	48, 34
Postsecondary Education, Office of	34, VI
Secretary of Education, Office of	34, Subtitle A
Special Education and Rehabilitative Services, Office of	34, III
Educational Research and Improvement, Office of	34, VII
Election Assistance Commission	2, LVIII; 11, II
Elementary and Secondary Education, Office of	34, II
Emergency Oil and Gas Guaranteed Loan Board	13, V
Emergency Steel Guarantee Loan Board	13, IV
Employee Benefits Security Administration	29, XXV
Employees' Compensation Appeals Board	20, IV
Employees Loyalty Board	5, V
Employment and Training Administration	20, V
Employment Policy, National Commission for	1, IV
Employment Standards Administration	20, VI
Endangered Species Committee	50, IV
Energy, Department of	2, IX; 5, XXIII; 10, II, III, X
Federal Acquisition Regulation	48, 9
Federal Energy Regulatory Commission	5, XXIV; 18, I
Property Management Regulations	41, 109
Energy, Office of	7, XXIX
Engineers, Corps of	33, II; 36, III
Engraving and Printing, Bureau of	31, VI
Environmental Protection Agency	2, XV; 5, LIV; 40, I, IV, VII
Federal Acquisition Regulation	48, 15
Property Management Regulations	41, 115
Environmental Quality, Office of	7, XXXI
Equal Employment Opportunity Commission	5, LXII; 29, XIV
Equal Opportunity, Office of Assistant Secretary for	24, I
Executive Office of the President	3, I
Environmental Quality, Council on	40, V
Management and Budget, Office of	2, Subtitle A; 5, III, LXXVII; 14, VI; 48, 99
National Drug Control Policy, Office of	2, XXXVI; 21, III
National Security Council	32, XXI; 47, II
Presidential Documents	3
Science and Technology Policy, Office of	32, XXIV; 47, II
Trade Representative, Office of the United States	15, XX

Agency	CFR Title, Subtitle or Chapter
Export-Import Bank of the United States	2, XXXV; 5, LII; 12, IV
Families and Services, Administration of	45, III
Family Assistance, Office of	45, II
Farm Credit Administration	5, XXXI; 12, VI
Farm Credit System Insurance Corporation	5, XXX; 12, XIV
Farm Service Agency	7, VII, XVIII
Federal Acquisition Regulation	48, 1
Federal Acquisition Security Council	41, 201
Federal Aviation Administration	14, I
Commercial Space Transportation	14, III
Federal Claims Collection Standards	31, IX
Federal Communications Commission	2, LX; 5, XXIX; 47, I
Federal Contract Compliance Programs, Office of	41, 60
Federal Crop Insurance Corporation	7, IV
Federal Deposit Insurance Corporation	5, XXII; 12, III
Federal Election Commission	5, XXXVII; 11, I
Federal Emergency Management Agency	44, I
Federal Employees Group Life Insurance Federal Acquisition Regulation	48, 21
Federal Employees Health Benefits Acquisition Regulation	48, 16
Federal Energy Regulatory Commission	5, XXIV; 18, I
Federal Financial Institutions Examination Council	12, XI
Federal Financing Bank	12, VIII
Federal Highway Administration	23, I, II
Federal Home Loan Mortgage Corporation	1, IV
Federal Housing Enterprise Oversight Office	12, XVII
Federal Housing Finance Agency	5, LXXX; 12, XII
Federal Labor Relations Authority	5, XIV, XLIX; 22, XIV
Federal Law Enforcement Training Center	31, VII
Federal Management Regulation	41, 102
Federal Maritime Commission	46, IV
Federal Mediation and Conciliation Service	5, CIII; 29, XII
Federal Mine Safety and Health Review Commission	5, LXXIV; 29, XXVII
Federal Motor Carrier Safety Administration	49, III
Federal Permitting Improvement Steering Council	40, IX
Federal Prison Industries, Inc.	28, III
Federal Procurement Policy Office	48, 99
Federal Property Management Regulations	41, 101
Federal Railroad Administration	49, II
Federal Register, Administrative Committee of	1, I
Federal Register, Office of	1, II
Federal Reserve System	12, II
Board of Governors	5, LVIII
Federal Retirement Thrift Investment Board	5, VI, LXXVI
Federal Service Impasses Panel	5, XIV
Federal Trade Commission	5, XLVII; 16, I
Federal Transit Administration	49, VI
Federal Travel Regulation System	41, Subtitle F
Financial Crimes Enforcement Network	31, X
Financial Research Office	12, XVI
Financial Stability Oversight Council	12, XIII
Fine Arts, Commission of	45, XXI
Fiscal Service	31, II
Fish and Wildlife Service, United States	50, I, IV
Food and Drug Administration	21, I
Food and Nutrition Service	7, II
Food Safety and Inspection Service	9, III
Foreign Agricultural Service	7, XV
Foreign Assets Control, Office of	31, V
Foreign Claims Settlement Commission of the United States	45, V
Foreign Service Grievance Board	22, IX
Foreign Service Impasse Disputes Panel	22, XIV
Foreign Service Labor Relations Board	22, XIV
Foreign-Trade Zones Board	15, IV
Forest Service	36, II
General Services Administration	5, LVII; 41, 105
Contract Appeals, Board of	48, 61

Agency	CFR Title, Subtitle or Chapter
Federal Acquisition Regulation	48, 5
Federal Management Regulation	41, 102
Federal Property Management Regulations	41, 101
Federal Travel Regulation System	41, Subtitle F
General	41, 300
Payment From a Non-Federal Source for Travel Expenses	41, 304
Payment of Expenses Connected With the Death of Certain Employees	41, 303
Relocation Allowances	41, 302
Temporary Duty (TDY) Travel Allowances	41, 301
Geological Survey	30, IV
Government Accountability Office	4, I
Government Ethics, Office of	5, XVI
Government National Mortgage Association	24, III
Grain Inspection, Packers and Stockyards Administration	7, VIII; 9, II
Great Lakes St. Lawrence Seaway Development Corporation	33, IV
Gulf Coast Ecosystem Restoration Council	2, LIX; 40, VIII
Harry S. Truman Scholarship Foundation	45, XVIII
Health and Human Services, Department of	2, III; 5, XLV; 45, Subtitle A
Centers for Medicare & Medicaid Services	42, IV
Child Support Services, Office of	45, III
Children and Families, Administration for	45, II, IV, X, XIII
Community Services, Office of	45, X
Families and Services, Administration of	45, III
Family Assistance, Office of	45, II
Federal Acquisition Regulation	48, 3
Food and Drug Administration	21, I
Indian Health Service	25, V
Inspector General (Health Care), Office of	42, V
Public Health Service	42, I
Refugee Resettlement, Office of	45, IV
Homeland Security, Department of	2, XXX; 5, XXXVI; 6, I; 8, I
Coast Guard	33, I; 46, I; 49, IV
Coast Guard (Great Lakes Pilotage)	46, III
Customs and Border Protection	19, I
Federal Emergency Management Agency	44, I
Human Resources Management and Labor Relations Systems	5, XCVII
Immigration and Customs Enforcement Bureau	19, IV
Transportation Security Administration	49, XII
HOPE for Homeowners Program, Board of Directors of	24, XXIV
Housing and Urban Development, Department of	2, XXIV; 5, LXV; 24, Subtitle B
Community Planning and Development, Office of Assistant Secretary for	24, V, VI
Equal Opportunity, Office of Assistant Secretary for	24, I
Federal Acquisition Regulation	48, 24
Federal Housing Enterprise Oversight, Office of	12, XVII
Government National Mortgage Association	24, III
Housing—Federal Housing Commissioner, Office of Assistant Secretary for	24, II, VIII, X, XX
Housing, Office of, and Multifamily Housing Assistance Restructuring, Office of	24, IV
Inspector General, Office of	24, XII
Public and Indian Housing, Office of Assistant Secretary for	24, IX
Secretary, Office of	24, Subtitle A, VII
Housing—Federal Housing Commissioner, Office of Assistant Secretary for	24, II, VIII, X, XX
Housing, Office of, and Multifamily Housing Assistance Restructuring, Office of	24, IV
Immigration and Customs Enforcement Bureau	19, IV
Immigration Review, Executive Office for	8, V
Independent Counsel, Office of	28, VII
Independent Counsel, Offices of	28, VI
Indian Affairs, Bureau of	25, I, V

Agency	CFR Title, Subtitle or Chapter
Indian Affairs, Office of the Assistant Secretary	25, VI
Indian Arts and Crafts Board	25, II
Indian Health Service	25, V
Industry and Security, Bureau of	15, VII
Information Resources Management, Office of	7, XXVII
Information Security Oversight Office, National Archives and Records Administration	32, XX
Inspector General	
Agriculture Department	7, XXVI
Health and Human Services Department	42, V
Housing and Urban Development Department	24, XII, XV
Institute of Peace, United States	22, XVII
Intellectual Property Enforcement Coordinator, Office of	5, CIV
Inter-American Foundation	5, LXIII; 22, X
Interior, Department of	2, XIV
American Indians, Office of the Special Trustee	25, VII
Endangered Species Committee	50, IV
Federal Acquisition Regulation	48, 14
Federal Property Management Regulations System	41, 114
Fish and Wildlife Service, United States	50, I, IV
Geological Survey	30, IV
Indian Affairs, Bureau of	25, I, V
Indian Affairs, Office of the Assistant Secretary	25, VI
Indian Arts and Crafts Board	25, II
Land Management, Bureau of	43, II
National Indian Gaming Commission	25, III
National Park Service	36, I
Natural Resource Revenue, Office of	30, XII
Ocean Energy Management, Bureau of	30, V
Reclamation, Bureau of	43, I
Safety and Environmental Enforcement, Bureau of	30, II
Secretary of the Interior, Office of	2, XIV; 43, Subtitle A
Surface Mining Reclamation and Enforcement, Office of	30, VII
Internal Revenue Service	26, I
International Boundary and Water Commission, United States and Mexico, United States Section	22, XI
International Development, United States Agency for	22, II
Federal Acquisition Regulation	48, 7
International Development Cooperation Agency, United States	22, XII
International Development Finance Corporation, U.S.	2, XVI; 5, XXXIII; 22, VII
International Joint Commission, United States and Canada	22, IV
International Organizations Employees Loyalty Board	5, V
International Trade Administration	15, III; 19, III
International Trade Commission, United States	19, II
Interstate Commerce Commission	5, XL
Investment Security, Office of	31, VIII
James Madison Memorial Fellowship Foundation	45, XXIV
Japan–United States Friendship Commission	22, XVI
Joint Board for the Enrollment of Actuaries	20, VIII
Justice, Department of	2, XXVIII; 5, XXVIII; 28, I, XI; 40, IV
Alcohol, Tobacco, Firearms, and Explosives, Bureau of	27, II
Drug Enforcement Administration	21, II
Federal Acquisition Regulation	48, 28
Federal Claims Collection Standards	31, IX
Federal Prison Industries, Inc.	28, III
Foreign Claims Settlement Commission of the United States	45, V
Immigration Review, Executive Office for	8, V
Independent Counsel, Offices of	28, VI
Prisons, Bureau of	28, V
Property Management Regulations	41, 128
Labor, Department of	2, XXIX; 5, XLII
Benefits Review Board	20, VII
Employee Benefits Security Administration	29, XXV

Agency	CFR Title, Subtitle or Chapter
Employees' Compensation Appeals Board	20, IV
Employment and Training Administration	20, V
Federal Acquisition Regulation	48, 29
Federal Contract Compliance Programs, Office of	41, 60
Federal Procurement Regulations System	41, 50
Labor-Management Standards, Office of	29, II, IV
Mine Safety and Health Administration	30, I
Occupational Safety and Health Administration	29, XVII
Public Contracts	41, 50
Secretary of Labor, Office of	29, Subtitle A
Veterans' Employment and Training Service, Office of the Assistant Secretary for	41, 61; 20, IX
Wage and Hour Division	29, V
Workers' Compensation Programs, Office of	20, I, VI
Labor-Management Standards, Office of	29, II, IV
Land Management, Bureau of	43, II
Legal Services Corporation	45, XVI
Libraries and Information Science, National Commission on	45, XVII
Library of Congress	36, VII
Copyright Royalty Board	37, III
U.S. Copyright Office	37, II
Management and Budget, Office of	5, III, LXXVII; 14, VI; 48, 99
Marine Mammal Commission	50, V
Maritime Administration	46, II
Merit Systems Protection Board	5, II, LXIV
Micronesian Status Negotiations, Office for	32, XXVII
Military Compensation and Retirement Modernization Commission	5, XCIX
Millennium Challenge Corporation	22, XIII
Mine Safety and Health Administration	30, I
Minority Business Development Agency	15, XIV
Miscellaneous Agencies	1, IV
Monetary Offices	31, I
Morris K. Udall Scholarship and Excellence in National Environmental Policy Foundation	36, XVI
Museum and Library Services, Institute of	2, XXXI
National Aeronautics and Space Administration	2, XVIII; 5, LIX; 14, V
Federal Acquisition Regulation	48, 18
National Agricultural Library	7, XLI
National Agricultural Statistics Service	7, XXXVI
National and Community Service, Corporation for	2, XXII; 45, XII, XXV
National Archives and Records Administration	2, XXVI; 5, LXVI; 36, XII
Information Security Oversight Office	32, XX
National Capital Planning Commission	1, IV, VI
National Counterintelligence Center	32, XVIII
National Credit Union Administration	5, LXXXVI; 12, VII
National Crime Prevention and Privacy Compact Council	28, IX
National Drug Control Policy, Office of	2, XXXVI; 21, III
National Endowment for the Arts	2, XXXII
National Endowment for the Humanities	2, XXXIII
National Foundation on the Arts and the Humanities	45, XI
National Geospatial-Intelligence Agency	32, I
National Highway Traffic Safety Administration	23, II, III; 47, VI; 49, V
National Imagery and Mapping Agency	32, I
National Indian Gaming Commission	25, III
National Institute of Food and Agriculture	7, XXXIV
National Institute of Standards and Technology	15, II; 37, IV
National Intelligence, Office of Director of	5, IV; 32, XVII
National Labor Relations Board	5, LXI; 29, I
National Marine Fisheries Service	50, II, IV
National Mediation Board	5, CI; 29, X
National Oceanic and Atmospheric Administration	15, IX; 50, II, III, IV, VI
National Park Service	36, I
National Railroad Adjustment Board	29, III
National Railroad Passenger Corporation (AMTRAK)	49, VII

Agency	CFR Title, Subtitle or Chapter
National Science Foundation	2, XXV; 5, XLIII; 45, VI
Federal Acquisition Regulation	48, 25
National Security Council	32, XXI; 47, II
National Technical Information Service	15, XI
National Telecommunications and Information Administration	15, XXIII; 47, III, IV, V
National Transportation Safety Board	49, VIII
Natural Resource Revenue, Office of	30, XII
Natural Resources Conservation Service	7, VI
Navajo and Hopi Indian Relocation, Office of	25, IV
Navy, Department of	32, VI
Federal Acquisition Regulation	48, 52
Neighborhood Reinvestment Corporation	24, XXV
Northeast Interstate Low-Level Radioactive Waste Commission	10, XVIII
Nuclear Regulatory Commission	2, XX; 5, XLVIII; 10, I
Federal Acquisition Regulation	48, 20
Occupational Safety and Health Administration	29, XVII
Occupational Safety and Health Review Commission	29, XX
Ocean Energy Management, Bureau of	30, V
Oklahoma City National Memorial Trust	36, XV
Operations Office	7, XXVIII
Patent and Trademark Office, United States	37, I
Payment From a Non-Federal Source for Travel Expenses	41, 304
Payment of Expenses Connected With the Death of Certain Employees	41, 303
Peace Corps	2, XXXVII; 22, III
Pennsylvania Avenue Development Corporation	36, IX
Pension Benefit Guaranty Corporation	29, XL
Personnel Management, Office of	5, I, IV, XXXV; 45, VIII
Federal Acquisition Regulation	48, 17
Federal Employees Group Life Insurance Federal Acquisition Regulation	48, 21
Federal Employees Health Benefits Acquisition Regulation	48, 16
Human Resources Management and Labor Relations Systems, Department of Homeland Security	5, XCVII
Pipeline and Hazardous Materials Safety Administration	49, I
Postal Regulatory Commission	5, XLVI; 39, III
Postal Service, United States	5, LX; 39, I
Postsecondary Education, Office of	34, VI
President's Commission on White House Fellowships	1, IV
Presidential Documents	3
Presidio Trust	36, X
Prisons, Bureau of	28, V
Privacy and Civil Liberties Oversight Board	6, X
Procurement and Property Management, Office of	7, XXXII
Public and Indian Housing, Office of Assistant Secretary for	24, IX
Public Contracts, Department of Labor	41, 50
Public Health Service	42, I
Railroad Retirement Board	20, II
Reclamation, Bureau of	43, I
Refugee Resettlement, Office of	45, IV
Relocation Allowances	41, 302
Research and Innovative Technology Administration	49, XI
Rural Business-Cooperative Service	7, XVIII, XLII, L
Rural Housing Service	7, XVIII, XXXV, L
Rural Utilities Service	7, XVII, XVIII, XLII, L
Safety and Environmental Enforcement, Bureau of	30, II
Science and Technology Policy, Office of	32, XXIV; 47, II
Secret Service	31, IV
Securities and Exchange Commission	5, XXXIV; 17, II
Selective Service System	32, XVI
Small Business Administration	2, XXVII; 13, I
Smithsonian Institution	36, V
Social Security Administration	2, XXIII; 20, III; 48, 23
Soldiers' and Airmen's Home, United States	5, XI
Special Counsel, Office of	5, VIII

Agency	CFR Title, Subtitle or Chapter
Special Education and Rehabilitative Services, Office of	34, III
State, Department of	2, VI; 22, I; 28, XI
Federal Acquisition Regulation	48, 6
Surface Mining Reclamation and Enforcement, Office of	30, VII
Surface Transportation Board	49, X
Susquehanna River Basin Commission	18, VIII
Tennessee Valley Authority	5, LXIX; 18, XIII
Trade Representative, United States, Office of	15, XX
Transportation, Department of	2, XII; 5, L
Commercial Space Transportation	14, III
Emergency Management and Assistance	44, IV
Federal Acquisition Regulation	48, 12
Federal Aviation Administration	14, I
Federal Highway Administration	23, I, II
Federal Motor Carrier Safety Administration	49, III
Federal Railroad Administration	49, II
Federal Transit Administration	49, VI
Great Lakes St. Lawrence Seaway Development Corporation	33, IV
Maritime Administration	46, II
National Highway Traffic Safety Administration	23, II, III; 47, IV; 49, V
Pipeline and Hazardous Materials Safety Administration	49, I
Secretary of Transportation, Office of	14, II; 49, Subtitle A
Transportation Statistics Bureau	49, XI
Transportation, Office of	7, XXXIII
Transportation Security Administration	49, XII
Transportation Statistics Bureau	49, XI
Travel Allowances, Temporary Duty (TDY)	41, 301
Treasury, Department of the	2, X; 5, XXI; 12, XV; 17, IV; 31, IX
Alcohol and Tobacco Tax and Trade Bureau	27, I
Community Development Financial Institutions Fund	12, XVIII
Comptroller of the Currency	12, I
Customs and Border Protection	19, I
Engraving and Printing, Bureau of	31, VI
Federal Acquisition Regulation	48, 10
Federal Claims Collection Standards	31, IX
Federal Law Enforcement Training Center	31, VII
Financial Crimes Enforcement Network	31, X
Fiscal Service	31, II
Foreign Assets Control, Office of	31, V
Internal Revenue Service	26, I
Investment Security, Office of	31, VIII
Monetary Offices	31, I
Secret Service	31, IV
Secretary of the Treasury, Office of	31, Subtitle A
Truman, Harry S. Scholarship Foundation	45, XVIII
United States Agency for Global Media	22, V
United States and Canada, International Joint Commission	22, IV
United States and Mexico, International Boundary and Water Commission, United States Section	22, XI
U.S. Copyright Office	37, II
U.S. Office of Special Counsel	5, CII
Utah Reclamation Mitigation and Conservation Commission	43, III
Veterans Affairs, Department of	2, VIII; 38, I
Federal Acquisition Regulation	48, 8
Veterans' Employment and Training Service, Office of the Assistant Secretary for	41, 61; 20, IX
Vice President of the United States, Office of	32, XXVIII
Wage and Hour Division	29, V
Water Resources Council	18, VI
Workers' Compensation Programs, Office of	20, I, VI
World Agricultural Outlook Board	7, XXXVIII

List of CFR Sections Affected

All changes in this volume of the Code of Federal Regulations (CFR) that were made by documents published in the FEDERAL REGISTER since January 1, 2019 are enumerated in the following list. Entries indicate the nature of the changes effected. Page numbers refer to FEDERAL REGISTER pages. The user should consult the entries for chapters, parts and subparts as well as sections for revisions.

For changes to this volume of the CFR prior to this listing, consult the annual edition of the monthly List of CFR Sections Affected (LSA). The LSA is available at *www.govinfo.gov*. For changes to this volume of the CFR prior to 2001, see the ''List of CFR Sections Affected, 1949–1963, 1964–1972, 1973–1985, and 1986–2000'' published in 11 separate volumes. The ''List of CFR Sections Affected 1986–2000'' is available at *www.govinfo.gov*.

2019

40 CFR

84 FR Page

Chapter I

63.8530—65.8665 (Subpart KKKKK) Table 1 revised 58609
63.8530—65.8665 (Subpart KKKKK) Table 2 revised 58610
63.8530—65.8665 (Subpart KKKKK) Table 4 revised 58611
63.8530—65.8665 (Subpart KKKKK) Table 6 revised 58614
63.8530—65.8665 (Subpart KKKKK) Table 7 revised 58619
63.8595 (h) redesignated as (i); new (h) added; (c), new (i) introductory text, and new (1) introductory text revised 58606
63.8620 (e) introductory text, (1), (2), and (3) redesignated as (e)(1) introductory text, (i), (ii), and (iii); new (e)(1) introductory text revised; new (e)(2), (f), and (g) added 58607
63.8630 (c) introductory text revised; (c)(4) added 58608
63.8635 (c) introductory text, (4)(iii)(C), and (g)(1) revised; (c)(9) added 58608
63.8640 (c) introductory text revised; (c)(11) added 58609
63.8665 Amended 58609

2020

40 CFR

85 FR Page

Chapter I

63.6580—63.6675 (Subpart ZZZZ) Table 8 amended 73912
63.6604 (a) through (c) amended 78463
63.6645 (b) and (d) revised 73912
63.7080—63.7143 (Subpart AAAAA) Table 1 amended; Tables 2 through 8 redesignated as Tables 3 through 9; new Table 2 added 44982
63.7080—63.7143 (Subpart AAAAA) New Table 3 and Table 4 revised 44983
63.7080—63.7143 (Subpart AAAAA) New Table 5 revised 44984
63.7080—63.7143 (Subpart AAAAA) New Table 6 and New Table 7 revised 44986
63.7080—63.7143 (Subpart AAAAA) New Table 8 revised 44987
Table 8 amended 73912
63.7080—63.7143 (Subpart AAAAA) New Table 9 revised 44988
Amendatory instruction corrected 84262
63.7083 (a)(1), (2), and (b) revised; (e) added 44977
63.7090 (b) revised; (c) added 44977

40 CFR—Continued

85 FR Page

Chapter I—Continued

63.7100 (a), (b), (c), (d)(3), (4)(iii), (6) introductory text, and (e) revised 44977
63.7110 (d) and (e) revised 44978
63.7112 (a), (b), (c), (j) introductory text, (k) introductory text, (3), and (l) introductory text revised; (m) added 44978
63.7113 (d) and (f) revised 44978
63.7114 (a) introductory text and (b) revised 44979
63.7120 (c) introductory text revised; (c)(3) removed 44979
63.7121 (a), (b), (d), (e) introductory text, and (3) revised 44979
63.7130 (e) revised 44979
(b) and (c) revised 73912
63.7131 (a), (b) introductory text, (c)(4), (d), (e) introductory text, (2), and (f) revised; (b)(6), (e)(12), and (g) through (j) added 44979
63.7132 (a)(2) and (c) revised 44981
63.7133 (d) added 44981
63.7140 Amended 44981
63.7141 (c) revised 44981
63.7142 (a)(2), (3), (b)(2), and (3) redesignated as (a)(3), (4), (b)(3), and (4); (a)(1), new (a)(4) introductory text, new (i), new (v), new (b)(3), and new (4) revised; new (a)(2) and new (b)(2) added 44981
63.7143 Amended 44982
63.7189 (b) revised 73913
63.7340 (b) revised 73913
63.7545 (b) and (c) revised 73913
63.7690 (a)(8) revised 56095
63.7700 (g) added 56095
63.7710 (a) and (b) introductory text revised 56096
63.7720 (a) and (c) revised 56096
63.7732 (a) and (e)(1) introductory text revised 56096
63.7740 (e) revised 56096
63.7741 (d) introductory text revised 56096
63.7744 (e) added 56096
63.7746 (b) removed 56097
63.7750 (b) revised 73913
63.7751 (a) introductory text, (b) introductory text, and (d) amended; (b)(4) and (c) removed; (b)(6), (7), and (8) revised; (e) through (i) added 56097

40 CFR—Continued

85 FR Page

Chapter I—Continued

63.7752 (a)(2), (b)(2), and (4) revised; (d) and (e) added 56099
63.7761 (c) introductory text revised; (c)(5) added 56099
63.7765 Amended 56099
63.7680—63.7765 (Subpart EEEEE) Table 1 revised 56100
63.7780—63.7852 (Subpart FFFFF) Table 1 revised 42125
63.7780—63.7852 (Subpart FFFFF) Table 2 and Table 3 revised 42126
63.7780—63.7852 (Subpart FFFFF) Table 4 revised 42128
63.7783 (a) introductory text, (b), and (c) revised; (f) added 42114
63.7790—7791 Undesignated center heading revised 42115
63.7791 Added 42115
63.7800 (a) revised 42116
63.7810 (a) and (c) revised; (d) added 42116
63.7820 (e) added 42116
63.7821 (a) revised; (e) added 42116
63.7822 (a) and (b)(1) revised 42116
63.7823 (a), (c)(1), (d)(1)(i), (2)(i), (e)(1), and (3) revised 42117
63.7824 (e) introductory text, (1), and (2) revised; (e)(3) amended 42118
63.7825 Redesignated as 63.7826; new section added 42119
63.7826 Redesignated as 63.7827; new section redesignated from 63.7825 42119
63.7827 Redesignated from 63.7826 42119
63.7831 (a)(4), (5), (6), and (f)(4) revised 42120
(f)(4) amended 44992
63.7833 (g)(3) revised; (h) and (i) added 42120
63.7835 Revised 42121
63.7840 (d), (e) introductory text, and (2) revised; (f), (g), and (h) added 42121
(b) revised 73913
63.7841 (d) redesignated as (g); (b)(9) through (13), new (d), (e), and (f) added; (b) introductory text, (4), (7) introductory text, (ii), (8) introductory text, (ii), (iv), (vi), (c), and new (g) revised 42122

40 CFR—Continued

85 FR Page

Chapter I—Continued

63.7842 (a)(3) redesignated as (a)(5); new (a)(3), (4), and (e) added; (a)(2) and (b)(3) revised 42123
63.7851 (c) introductory text revised; (c)(5) added 42124
63.7852 Amended 42124
63.7880—63.7957 (Subpart GGGGG) Table 3 revised 41712
Table 3 amended 73913
63.7882 (a) introductory text revised; (a)(4) added 41702
63.7883 (a), (b) introductory text, (c) introductory text, and (d) introductory text revised; (f) added 41703
63.7895 (c) revised 41703
63.7896 (c)(1), (3), and (f)(1) revised 41703
63.7898 (c)(1) revised 41703
63.7900 (b)(1), (2), (3), (c), and (d) revised 41703
63.7901 (a), (b)(1), (c)(2), and (d)(3) revised 41704
63.7903 (a), (b) introductory text, (c)(1), and (d)(2) revised 41704
63.7905 (b)(1) and (2) revised 41704
63.7906 (b)(2) and (c)(2) revised 41704
63.7908 (b)(1) and (c)(1) revised 41704
63.7910 (b)(1), (2), and (3) revised 41705
63.7911 (b)(2), (c)(2), and (d)(2) revised 41705
63.7912 (c) revised 41705
63.7913 (c)(1) and (d)(1) revised 41705
63.7920—63.7922 Undesignated center heading revised 41705
63.7920 (b)(1) revised; (d) redesignated as (f); (b)(3), new (d), and (e) added 41705
63.7923 Added 41705
63.7925 (b) revised 41706
63.7935 (a), (b), (c), (e), (f), (h)(1), (2), and (3) revised; (g)(4) and (5) added 41707
63.7941 (b)(2) and (4) introductory text revised 41708
63.7942 Revised 41708
63.7943 (d) revised 41708
63.7944 (b)(2)(ii) and (iv) amended; (d) revised 41708
63.7945 (d) added 41708
63.7950 (b) and (c) revised 73913

40 CFR—Continued

85 FR Page

Chapter I—Continued

63.7951 (a)(6), (7), (b)(10), (11), and (e) through (h) added; (b)(4), (7) introductory text, (ii), (8) introductory text, (i), (iv), (vi), and (c) revised 41708
63.7952 (a)(2) revised; (a)(3) and (4) redesignated as (a)(9) and (10); new (a)(3), (4) through (8), and (e) added 41710
63.7957 Amended 41711
63.7880—63.7957 (Subpart GGGGG) Table 3 amended 73913
63.7880—63.7957 (Subpart GGGGG) Table 3 amended 41712
63.7985 (a)(1), (2), (3), (b) introductory text, (1), (2), (3), and (d)(1) through (4) revised 49740
63.7980—63.8105 (Subpart HHHHH) Table 10 amended 73914
63.7990 (a) revised 49741
63.7995 (a) introductory text and (b) revised; (e) added 49741
63.8000 (a), (b)(2), (c)(3), (d)(1) introductory text, (i), (iii), (3), (4)(i)(A), (ii)(C), and (iv) revised; (d)(1)(vi), (8), (e), and (f) added; (d)(2) removed 49741
(d)(1)(vi) correctly amended 75235
63.8005 (a)(2), (d)(1), (e) introductory text, (2), and (g) revised; (d)(5) and (h) added 49743
63.8010 (a) revised 49743
63.8025 (a) revised 49744
63.8050 (c)(3)(i), (ii), and (iii) added 49744
63.8055 (b)(1), (2), and (4) revised 49744
63.8070 (c) revised 49744
(b)(1) revised 73914
63.8075 (c)(1), (d) introductory text, (1), (2)(ii), (e)(5) introductory text, (6)(ii) introductory text, (B), (iii) introductory text, (C), and (E) revised; (e)(6)(ii)(D), (iii)(L), and (f) through (k) added; (e)(8)(ii)(B) removed 49744
63.8080 Introductory text, (c), (e), and (f) revised; (h), (i), and (j) added 49746
63.8090 (b) revised 49747
63.8105 (g) amended 49747
63.7980—63.8105 (Subpart HHHHH) Table 1 amended 49747
63.7980—63.8105 (Subpart HHHHH) Table 3 revised 49747

40 CFR—Continued

85 FR Page

Chapter I—Continued
63.7980—63.8105 (Subpart HHHHH) Table 7 revised 49748
63.7980—63.8105 (Subpart HHHHH) Table 8 amended 49749
63.7980—63.8105 (Subpart HHHHH) Table 9 amended 49749
63.7980—63.8105 (Subpart HHHHH) Table 10 revised 49749
63.7980—63.8105 (Subpart HHHHH) Table 11 added 49751
63.8252 (b) revised 73914
Heading and (b) correctly amended 84262
63.8180—63.8266 (Subpart IIIII) Table 10 amended 73914
63.8380—63.8515 (Subpart JJJJJ) Table 8 amended 73914
63.8380—63.8515 (Subpart JJJJJ) Table 10 amended 73915
63.8530—63.8665 (Subpart KKKKK) Table 9 and Table 11 amended 73915
63.8692 (b) revised 73916
63.8680—86.8698 (Subpart LLLLL) Table 1, Table 2, and Table 3 amended 14553
63.8680—86.8698 (Subpart LLLLL) Table 4 amended 14554
63.8680—86.8698 (Subpart LLLLL) Table 5 and Table 6 amended 14555
63.8680—86.8698 (Subpart LLLLL) Table 7 amended 14556, 73916
63.8681 (a) revised; (f) removed 14548
63.8683 (c) introductory text and (d) revised 14548
63.8684 Heading revised 14548
63.8685 (a), (b), and (c) revised 14549
63.8686 Heading, (a), and (b)(3) revised; (b)(4) added 14549
63.8687 (b) revised; (c) removed 14549
63.8688 (f) and (h) revised 14549
63.8689 (b) revised; (d) added 14549
63.8690 (b) revised 14549
63.8691 Heading, (a), (b), and (d) revised; (e) added 14549
63.8692 (a), (e), and (f) revised 14550
63.8693 (b)(6), (d)(13), (g), (h), and (i) added; (c)(4), (5), (d) introductory text, (1) through (4), (6), and (f) revised 14550
63.8694 (a)(2) revised; (e) added 14552
63.8697 (b)(1) revised 14552
63.8698 Amended 14552

40 CFR—Continued

85 FR Page

Chapter I—Continued
63.8780—63.8830 (Subpart MMMMM) Table 7 amended 73916
63.8816 (b) revised 73916

2021

40 CFR

86 FR Page

Chapter I
63.8635 (g)(1) revised 66043
63.8530—63.8665 (Subpart KKKKK) Table 2 revised 66043
63.8784 (c)(2) and (e) revised 64398
63.8786 (b) revised; (f) added 64398
63.8794 (b) through (d) and (f) introductory text revised; (e) removed 64399
63.8798 (b) revised; (c) added 64399
63.8800 (f) redesignated as (g); new (f) added; (b), (c), (e) introductory text, and new (g) introductory text revised 64399
63.8802 (a)(1)(i) and (3)(i) revised 64399
63.8810 (b) introductory text, (c) introductory text, and (1) revised 64399
63.8812 (b) and (e) introductory text revised; (d) removed 64400
63.8816 (d), (f), (g) introductory text, and (h)(1) revised 64400
63.8818 (b) introductory text and (f) revised; (i) removed; (j) through (m) added 64400
63.8820 (b) revised 64401
63.8830 Amended 64401
63.8780—63.8830 (Subpart MMMMM) Table 1, Table 2 amended; Table 3 revised 64402
63.8780—63.8830 (Subpart MMMMM) Table 4, Table 5, and Table 6 amended 64403
63.8780—63.8830 (Subpart MMMMM) Table 7 revised 64404
63.8780—63.8830 (Subpart MMMMM) Table 8 added 64406

2022

40 CFR

87 FR Page

Chapter I
63.6585 (f)(1) through (3) revised 48607
63.6590 (b)(1)(i) and (3)(iii) revised 48607

40 CFR—Continued

87 FR Page

Chapter I—Continued
63.6604 (b) revised; (c) removed 48607
63.6640 (f) introductory text, (2) introductory text, (3), and (4) introductory text revised; (f)(2)(ii) and (iii) removed 48607
63.6650 (h) introductory text revised; (h)(1)(v) and (vi) removed 48607
63.6655 (f) introductory text revised 48607
63.6675 Amended 48608
63.6580—63.6675 (Subpart ZZZZ) Table 7 revised 48608
63.7500 (a) introductory text, (1), (c), and (e) revised 60840
63.7505 (c) revised 60841
63.7510 (a) introductory text, (b), (c), (f), and (j) revised 60841
63.7515 (b), (c), (e), (g), and (i) revised 60842
63.7520 (d) revised 60842
63.7521 (a) and (c)(1)(ii) revised 60842
63.7522 (b) introductory text, (d), (e)(1), (2), (h), and (j)(1) revised 60843
63.7525 (a) introductory text, (1), (2) introductory text, (ii), (iv), (vi), (l) introductory text, and (m) introductory text revised 60844
63.7530 (b)(4)(ii)(E), (iii), and (h) revised 60845
63.7533 (a), (e), and (f) revised 60845
63.7540 (a) introductory text, (8) introductory text, (ii), (9), (15) introductory text, (19) introductory text, and (b) revised 60846
63.7545 (e)(3) revised 60846
63.7555 (d) introductory text and (5) revised 60846
63.7575 Amended 60846
63.7480—63.7575 (Subpart DDDDD) Table 1 revised 60847
63.7480—63.7575 (Subpart DDDDD) Table 2 revised 60849
63.7480—63.7575 (Subpart DDDDD) Table 3 amended 60852
63.7480—63.7575 (Subpart DDDDD) Table 4 amended 60853
63.7480—63.7575 (Subpart DDDDD) Table 7 revised 60853
63.7480—63.7575 (Subpart DDDDD) Table 8 amended 60855
63.7480—63.7575 (Subpart DDDDD) Table 11 revised 60855

40 CFR—Continued

87 FR Page

Chapter I—Continued
63.7480—63.7575 (Subpart DDDDD) Table 12 revised 60857
63.7480—63.7575 (Subpart DDDDD) Table 13 revised 60859
63.7480—63.7575 (Subpart DDDDD) Table 14 added 60860
63.7480—63.7575 (Subpart DDDDD) Table 15 added 60863
63.7881 (b)(2) and (3) removed 78558
63.7882 (d) added 78558
63.7883 (g) added 78558
63.8180—63.8266 (Subpart IIIII) Heading revised 27018
Table 5 amended; Table 10 revised 27024
63.8180 Revised 27018
63.8182 (c) introductory text revised 27018
63.8184 (a)(1) and (2) revised 27018
63.8186 (a) revised 27019
63.8190 (a)(2) revised 27019
63.8192 Introductory text, (a), and (g) introductory text revised; (h) added 27019
63.8222 Revised 27020
63.8226 Revised 27020
63.8232 Introductory text and (a) revised; (g) added 27020
63.8236 (c) introductory text revised; (e) and (f) added 27020
63.8242 Heading, (a)(2), and (3)(v) revised 27021
63.8246 (b)(1) introductory text and (c) revised; (d) added 27021
63.8248 (a) introductory text, (1), (2), and (2) revised; (b) introductory text added 27021
63.8252 (d) and (e)(1)(i) revised; (f) through (h) added 27021
63.8254 (b) introductory text and (7) through (9) revised; (b)(4) and (c) removed; (b)(13), (14), and (e) added 27022
63.8256 (a)(2) and (c) introductory text revised; (e) and (f) added 27023
63.8262 Revised 27023
63.8264 (c) introductory text revised; (c)(5) added 27023
63.8266 Amended 27023

2023

40 CFR

88 FR Page

Chapter I

63.6580—63.6675 (Subpart ZZZZ) Table 4 revised 18413
63.7995 (a) introductory text and (b) revised; (f) added 10849
63.8000 (d)(1) introductory text revised; (d)(1)(vii) added 10849
63.8005 (a)(1) introductory text, (i), and (d)(1) revised; (a)(1)(iii) and (i) added 10849
63.8075 (d)(1) revised 10849
63.8080 (g) and (i) introductory text revised 10850
63.8105 (g) amended 10850
63.7980—63.8105 (Subpart HHHHH) Table 1 revised 10850

2024

(Regulations published from January 1, 2024, through July 1, 2024)

40 CFR

89 FR Page

Chapter I

63.7782 (c) through (e) revised 23319

40 CFR—Continued

89 FR Page

Chapter I—Continued

63.7783 (a) introductory text revised; (g) added 23319
63.7791 Heading revised 23320
63.7792 Added 23320
63.7793 Added 23322
63.7800 (b) introductory text revised; (b)(8) and (9) added 23323
63.7820 (e) revised 23323
63.7821 Revised 23323
63.7823 (a) revised; (c)(3), (d)(6), and (f) through (h) added 23324
63.7825 Heading, (a) introductory text, (b)(1)(v), (2), and (c) revised; (g) through (k) added 23325
63.7830 (e)(2) revised 23327
63.7833 (j) added 23327
63.7840 (g)(3) and (h)(3) removed; (i) added 23327
63.7841 (b)(14) and (h) added; (d) revised 23328
63.7842 (d) revised; (f) and (g) added 23328
63.7852 Amended 23329
63.7780—63.7852 (Subpart FFFFF) Tables 1 through 4 revised 23329
63.7780—63.7852 (Subpart FFFFF) Tables 5 and 6 added 23335